SEE SHEET 2 FOR
INDEX OF SHEETS

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT

STATE AID PROJECT NO. C 2 -19 -10
CSJ: 0002-19-010, ETC.

BI10C, ETC.
HUDSPETH COUNTY, ETC.

DESIGN SPEED = N/A
A.D.T. (2021)= VARIES
A.D.T. (2041)= VARIES

FEDERAL AID PROJECT NO.			
C 2 -19 -10			
CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		1

PROJECT LOCATION TABLE

REF #	CONTROL	HWY	LIMITS FROM	LIMITS TO	LENGTH (Mi)	AADT (2019)	AADT (2039)	FUNC. CLASS
1	0002-19-010	BI 10C	1.64 MI W OF RM 1111	1.32 MI E OF RM 1111	2.702	1477	2340	5
2	0003-03-049	IH 10	BORACHO RD	0.873 MI E OF BORACHO RD	0.866	9093	11821	1
3	0233-01-052	US 62	9 MI N OF SH 54	NEW MEXICO STATE LINE	18.653	2585	5067	3
4	0233-02-036	US 62	SH 54	9 MI N OF SH 54	9.027	2487	3795	3
5	0233-03-017	SH 54	US 62/180	31.142 MI N OF BI-10D	23.770	434	608	5
6	0233-04-015	SH 54	31.142 MI N OF BI-10D	15.632 MI N OF BI-10D	15.539	434	608	5
7	0233-05-036	SH 54	15.632 MI N OF BI-10D	BI-10D	15.543	3550	4970	5
8	0374-05-030	US 62	14.1 MI E OF EL PASO COUNTY LINE	2.9 MI W OF RM 2317	14.790	1574	2576	3
9	0374-08-026	US 62	HUDSPETH/CULBERSON COUNTY LINE	SH 54	4.808	2107	3203	3
10	1282-02-028	RM 1111	US 62/180	IH 10	42.208	1739	2435	5
11	2122-01-017	FM 1576	STATE LINE	JCT OF FM 2249	6.593	221	385	5
12	2122-01-018	FM 2249	JCT OF FM 1576	JCT OF FM 1437	3.089	446	535	5
13	2203-01-011	FM 1576	JCT OF FM 2249	JCT OF US 62/180	17.301	135	189	5
				NET LENGTH OF PROJECT:	174.889			

FINAL PLANS

CONTRACTOR: ____
LETTING DATE: ____
TIME CHARGES BEGAN: ____
DATE CONTRACTOR BEGAN WORK: ____
DATE WORK WAS COMPLETED: ____
DATE WORK WAS ACCEPTED: ____
TOTAL DAYS CHARGED: ____
ORIGINAL CONTRACT AMOUNT: $ ____
AMOUNT OF CONTRACT AMENDMENTS: $ ____
FINAL CONTRACT COST: $ ____

____ 20 ____

____
AREA ENGINEER

FOR THE CONSTRUCTION OF ONE COURSE SURFACE TREATMENT
CONSISTING OF SEAL COAT AND PAVEMENT MARKINGS



N.T.S.



Texas Department of Transportation

RECOMMENDED FOR LETTING: 10/20/2023
DocuSigned by:
Eduardo Perales, P.E.
2778C5...
SAFETY REVIEW COMMITTEE CHAIRMAN

RECOMMENDED FOR LETTING: 10/20/2023
DocuSigned by:
L. Raul Ortega Jr., P.E.
0F1750B87604474...
DISTRICT DIRECTOR OF TRANSPORTATION PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 10/20/2023
DocuSigned by:
7A68C5EA0D94496...
DISTRICT ENGINEER

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS FOR ALL STATE CONSTRUCTION PROJECTS. (SP000---008)

EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: UNION PACIFIC, RM 736.39, 736.92 & 735.2
TDLR INSPECTION NOT REQUIRED

DATE: 10/12/2023 9:38:56 AM
FILE: pw:\\txdot.projectwiseonline.com:TxDOT5/Documents/24 - ELP/Design Projects/000219010/4 - Design/Plan Set/1. General/TITLE SHEET.dgn

INDEX OF SHEETS

STATE OF TEXAS
KARLA Y. RIOS
140855
LICENSED
PROFESSIONAL ENGINEER

Karla Rios, P.E.

10/19/2023

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET BY A # HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

Karla Rios — NAME

10/19/23 — DATE

Texas Department of Transportation

BI10C, ETC.

INDEX OF SHEETS

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		2

CK: DW: CK: DW:

DATE: 10/19/2023 4:59:52 PM
FILE: pw://txdot.projectwiseonline.com:TxDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/1. General/INDEX OF SHEETS.dgn



PROJECT LOCATION TABLE									
LOCATION	CONTROL	HWY	COUNTY	FROM RM	TO RM	BEGINNING LAT	BEGINNING LONG	ENDING LAT	ENDING LONG
1	0002-19-010	BI 10C	HUDSPETH	82-0.282	82 +2.42	31.1809648	-105.3838342	31.1706844	-105.3406588
2	0003-03-049	IH 10	CULBERSON	166 +0.475	167 +0.345	31.0715171	-104.3894432	31.070185	-104.3748913
3	0233-01-052	US 62	CULBERSON	128 +1.822	148 +0.577	31.8928527	-104.8185087	31.9997273	-104.5339624
4	0233-02-036	US 62	CULBERSON	120 +0.814	128 +1.822	31.7991375	-104.8482937	31.8928527	-104.8185087
5	0233-03-017	SH 54	CULBERSON	328-0.123	350 +1.801	31.79913759	-104.8482937	31.45792543	-104.84159
6	0233-04-015	SH 54	CULBERSON	350 +1.801	366 +1.352	31.4579178	-104.8415904	31.2430747	-104.8539472
7	0233-05-036	SH 54	CULBERSON	366 +1.352	384 +0.042	31.2430747	-104.8539472	31.039886	-104.8305956
8	0374-05-030	US 62	HUDSPETH	64 +0.182	78 +0.927	31.8440204	-105.7741525	31.7899543	-105.5314854
9	0374-08-026	US 62	CULBERSON	114+1.355	120 +0.814	31.7638858	-104.9173393	31.7991375	-104.8482937
10	1282-02-028	RM 1111	HUDSPETH	96+0.44	98+1.132	31.9388496	-105.2014285	31.9388651	-105.1487589
11	2122-01-017	FM 1576	HUDSPETH	314 +0	98 +1.132	32.0002707	-105.1078185	31.9388375	-105.1487589
12	2122-01-018	FM 2249	HUDSPETH	320 +0.622	96 +0.044	31.9388651	-105.1487589	31.9388496	-105.2014285
13	2203-01-011	FM 1576	HUDSPETH	320 +0.624	336 +1.982	31.9388375	-105.1487589	31.7453759	-105.0753966

STATE OF TEXAS
KARLA Y. RIOS
140855
LICENSED
PROFESSIONAL ENGINEER

Karla Rios, P.E.
10/03/2023

Texas Department of Transportation

BI10C, ETC.

PROJECT LOCATION MAP

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		3

DATE: 10/3/2023 5:27:17 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/1. General/PROJECT MAP.dgn

Specification Data

Table 1

Basis of Estimate

Item	Description	Rate
310	ASPH (A-R TYPE II)	0.55 GAL/SY
310	AGGR (TY-PB GR-4 SAC-A	(1CY/110 SY)

1. **Deviation from the rates shown will require approval.**

General Requirements

Maintain the entire project area in a neat and orderly manner throughout the duration of the work. Remove all construction litter and undesirable vegetation within the right of way inside the project limits. This work will be subsidiary to the various bid items.

General Project Description – This project consists of a seal coat treatment in Hudspeth and Culberson Counties, Texas.

Contractor questions on this project are to be addressed to the following individual(s):

Alpine Area Office:

Armando Ramirez, P.E.
Alpine Area Engineer
Armando.Ramirez2@txdot.gov

Aldo Madrid, P.E.
Director of Construction
Aldo.Madrid@txdot.gov

Monica Ruiz, P.E
District Construction Engineer
Monica.Ruiz@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors.

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 4 – Scope of Work

Schedule and perform all work to ensure proper drainage during the course of construction or maintenance operations. All labor, tools, equipment and supervision required, to ensure drainage, removal, and handling of water shall be considered incidental work.

Item 7 – Legal Relations and Responsibilities

Comply with all requirements of the Environmental Permits Issues and Commitments (EPIC) Sheet.

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

Occupational Safety & Health Administration (OSHA) regulations prohibit operations that bring people or equipment within 10 ft. of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all necessary adjustments to ensure the safety of workers near the energized line.

No significant traffic generator events identified.

Law Enforcement Personnel

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site.

Item 8 – Prosecution and Progress

Work is to begin no earlier than April 1st, 2024. Do not begin work before this period unless authorized in writing by the Engineer.

Working days will be calculated in accordance with Section 8.3.1., "**Standard** Workweek."

Create and maintain a Bar schedule.

Submit baseline schedule and obtain approval prior to beginning construction. The monthly progress payment will be held if the monthly update is not submitted.

Item 9 – Measurement and Payment

Monthly progress payments will be made for items of work completed by the 27th day of each month. Any work completed after the 27th will be included for payment in the subsequent monthly progress payment.

Submit Material on Hand (MOH) payment requests at least **two (2)** working days before the end of the month for payment consideration on that month's estimate.

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" WEB-BASED (Course #133119) which can be found online at the following site: **https://www.nhi.fhwa.dot.gov/**

Certificates of completion should be available to all who finish the course. These should be kept by the officers in order to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case by case basis.

Item 316 – Seal Coat

Before applying the seal coat, protect all bridge armor and expansion joints, manhole and valve covers with paper or other suitable materials as directed by the Engineer.

Protect all existing bridges, curbs, and other exposed concrete surfaces within the limits of the project from asphalt materials by any method that is approved. Remove any excessive asphalt materials deposited on these surfaces at the Contractor's expense. During the application of the surface treatment, if existing conditions warrant, the lane widths, transitions, and intersection areas may be varied as directed.

The Engineer will approve asphalt and aggregate rates prior to application.

Prepare the roadway surface prior to placing asphalt to the satisfaction of the Engineer. Some areas may require more extensive cleaning than other areas. This work will not be paid for directly, but will be subsidiary to pertinent items.

Seal coat season is April 1 to September 15. These days may be extended as directed by the Engineer.

Surface treat existing intersections, curb widenings, and widened dipped sections plus any additional areas encountered during construction to conform to the existing surface. The limits are the right-of-way line or as directed.

Use AC-10 or PG 64-22 asphalt for pre-coating aggregate. The stripping characteristics of pre-coated aggregate must not exceed 10% when tested in accordance with Tex-530-C. Add asphalt antistripping agent (Liquid) only to the asphalt pre-coating the aggregate.

Item 502 – Barricades, Signs, and Traffic Handling

Prior to beginning construction, the Engineer will approve the routing of traffic and sequence of work.

Additional signs and barricades, placed as directed, will be considered subsidiary to this Item.

In accordance with Section 7.2.6.1, designate, in writing, a Contractor Responsible Person (CRP) and a CRP alternate to take full responsibility for the set-up, maintenance, and necessary corrective measures of the traffic control plan. The CRP or CRP alternate must be present at site and implement the initial set up of every traffic control phase/stage, at each location, and/or each call out, for the entire duration of the project.

At the written request of the Engineer, immediately remove the CRP or CRP alternate from the project if, in the opinion of the Engineer, is not competent, not present at initial TCP set-ups, or does not perform in a proper, skillful, or safe manner. These individuals shall not be reinstated without written consent of the Engineer.

CRP and CRP alternate must be trained using Department approved training. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 2 for Department approved Training.

Table 2

Contractor Responsible Person and Alternate

Provider	Course Number	Course Title	Duration	Notes
American Traffic Safety Services Association	TCS	Traffic Control Supervisor	2 days	
National Highway Institute	133112 133113	Design and Operation of Work Zone Traffic Control Work Zone Traffic Control for Maintenance Operations	1 day 1 day	Both courses are required to meet minimum required training.
Texas Engineering Extension Services	133112A	Design and Operation of Work Zone Traffic Control	3 days	
University of Texas Arlington Division for Enterprise Development	WKZ421	Traffic Control Supervisor	16 hours	Contact UTA for training needs.

All contractor workers involved with the traffic control implementation and maintenance must participate and complete a Department approved training course. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 3 for Department approved training.

Table 3

Other Work Zone Personnel

Provider	Course Number	Course Title	Duration	Notes
American Traffic Safety Services Association	TCT	Traffic Control Technician	1 day	
Texas Engineering Extension Services	HWS002	Work Zone Traffic Control	16 hours	Identical to HWS-410. Counts for 3 year CRP requirement.
National Highway Institute	133116	Maintenance of Traffic for Technicians	5 hours	Web based
National Highway Institute	134109-I	Maintenance Training Series: Basics of Work Zone Traffic Control	1 hour	Free, Web based
University of Texas at Arlington, Division for Enterprise Development	WKZ100	Work Zone Safety: Temporary Traffic Control	4 hours	Note name change. Free, Web based
TxDOT/AGC Joint Development	N/A	Safe Workers Awareness Highway Construction Work Zone Hazards	16 minutes 18 minutes	Videos available through AGC of Texas offices. English & Spanish
AGC America	N/A	Highway Work Zone Safety Training	1 day	
Texas Engineering Extension Service	HWS400	Temporary Traffic Control Worker	4 hours	Contact TEEX, if interested in course
TxDOT/AGC Joint Development	N/A	Work Zone Fundamentals	10 minutes	Videos available through ACT of Texas offices. English & Spanish

Contractor may choose to train workers involved with the traffic control implementation and maintenance with a contractor developed training in lieu of Department approved training. Contractor developed training must be equivalent to the Department approved training shown in Table 2. Provide the Engineer a copy of the course curriculum for pre-approval, prior to conducting the contractor developed training. Provide the Engineer a copy of the log of attendees after training completion for project records.

Existing regulatory signs, route marker auxiliaries, guide signs, and warning signs that must be removed due to widening shall be relocated temporarily and erected on approved supports at locations shown in the plans, or as directed. This work will not be paid for directly but considered subsidiary to this Item.

Notify the Department officials when major traffic changes are to be made, such as detours. Coordinate with the Department on all traffic changes. Advance notification for the following week's work must be made by 5 P.M. on Wednesdays.

If Law Enforcement Personnel is required by the Engineer, coordinate with local law enforcement as directed or agreed. Complete the weekly tracking form provided by the Department and submit invoices with 5% allowance for Law Enforcement payments by Contractor that agree with the tracking form for payment at the end of each month where approved services were provided.

Provide access to intersecting side roads and driveways at all times, unless otherwise directed.

Any approved change to the sequence of work or TCP, must be signed and sealed by a Contractor's Licensed Professional Engineer assuming full responsibility for any additional barricade signs and devices needed.

Use striping operations to channelize traffic into the newly completed roadway, as directed. Maintain shoulders and median areas in a condition capable of serving as emergency paths, as approved. This work will be subsidiary to this Item.

Use portable changeable message signs (PCMS) to alert public of construction two weeks prior to construction.

Use flaggers when directed. Provide two-way radio communication for all flaggers.

Place and maintain sufficient additional warning signs, beacons, delineators, and barricades to warn and guide the public of all hazards through the construction zone at all times, and as directed.

Use flashing arrow boards on all tapers for each lane closure.

Some signs, barricades, and channelization devices may not be shown at the precise or measured position. Place the barricades, devices, or signs, with approval, in positions to meet field conditions.

Fill any holes left by barricade or sign supports and restore the area to its original condition.

Use Type A flashing warning lights or delineators to mark open excavation, footings, foundations, or other obstructions near lanes that may be open to traffic, as directed.

For additional information pertaining to channelization, signing, spacing details, and flagging procedures required to regulate, warn, and guide traffic through project, refer to the "Barricade and Construction Standards," BC(1)-21 and to the current *Texas Manual on Uniform Traffic Control Devices(TMUTCD).*

Remove or cover signs that do not apply to current conditions at the end of each day's work.

Repair and/or replace all signs damaged by the public or due to weather events.

Safety Contingency

The contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancement, to improve the effectiveness of the TCP that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506 – Temporary Erosion, Sedimentation, and Environmental Controls

It is not anticipated that any erosion, sedimentation, or environmental control devices will be needed on this project. However, if such controls are necessary, the Storm Water Pollution Prevention Plan (SWP3) for this project shall consist of the use of any temporary erosion control measures deemed necessary by the Engineer and as provided under this Item. Payment for the work will be determined in accordance with Article 9.7, "Payment for Extra Work and Force Account Method."

Item 662 – Work Zone Pavement Markings

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engineer as directed. Place final striping on these locations.

Remove and properly dispose of tabs upon completion of the final striping. This work is considered subsidiary to various bid items.

Place tabs as per the Department's Standard sheet TCP (SC-7)-22. Place raised pavement markers in accordance with applicable standards and as directed.

Item 666 –Retroreflectorized Pavement Markings

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required as pavement surface preparation.

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engineer as directed. Place final striping on these locations.

Item 672 – Raised Pavement Markers

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required for pavement surface preparation.

Furnish adhesives that conform to DMS-6100, "Epoxies and Adhesives," and DMS-6130, "Bituminous Adhesive for Pavement Markers," for this Item.

Do not place raised pavement markers when the pavement surface temperature is below 60°F.

Removal of all existing raised pavement markers will be considered subsidiary to the various bid items.

Item 6001 – Portable Changeable Message Sign

Provide messages as directed.

Provide two Portable Changeable Message Signs (PCMS) as advanced notification for two weeks prior to beginning project and throughout duration of project as directed.

Item 6185 – Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

All TMA Operators must participate in a TMA workshop to be conducted by the El Paso District Safety Office, on the proper use of TMAs, prior to working on Department Right of Way (ROW). A certificate of completion will be issued to TMA Operators that successfully complete the TMA workshop. The certificate of completion must be carried by TMA Operators at all times while working on Department right of way.

Acquire the TCP and TMA Operator's certificates of completion prior to the authorization to begin work. No time suspension will be granted, and no traffic control work will be allowed without certificates of completion.

Therefore, the total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

The supporting vehicle for the TMA shall have a minimum gross (i.e., ballasted) vehicular weight of 19,000 pounds.

Basis of Estimate for Stationary TMAs				
		TMA(Stationary)		
Phase	Standard	Required	Additional	TOTAL
1	TCP(SC-1-8)-22	1	0	1

Basis of Estimate for Mobile TMAs			
	TMA(Mobile)		
Standard	Required	Additional	TOTAL
TCP(SC-1-8)-22	1	0	1

Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0002-19-010 **DISTRICT** El Paso **COUNTY** Culberson, Hudspeth
HIGHWAY BI 10C, FM 1576, FM 2249, IH 10, RM 1111, SH 54, US 62

			CONTROL SECTION JOB	**0002-19-010**		**0003-03-049**		**0233-01-052**		**0233-02-036**		**0233-03-017**		**0233-04-015**	
			PROJECT ID	**A00064680**		**A00134544**		**A00176625**		**A00176624**		**A00134545**		**A00134546**	
			COUNTY	**Hudspeth**		**Culberson**		**Culberson**		**Culberson**		**Culberson**		**Culberson**	
			HIGHWAY	**BI 10C**		**IH 10**		**US 62**		**US 62**		**SH 54**		**SH 54**	
ALT	**BID CODE**	**DESCRIPTION**	**UNIT**	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL
	316-6007	ASPH (A-R TYPE II)	GAL	25,833.000		11,852.000		262,613.000		129,798.000		234,469.000		135,725.000	
	316-6126	AGGR(TY-PB GR-4 SAC-A)	CY	428.000		197.000		4,343.000		2,361.000		3,876.000		2,245.000	
	500-6001	MOBILIZATION	LS	1.000											
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000											
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	500.000											
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	500.000											
	510-6002	ONE-WAY TRAF CONT (PILOT CAR)	HR	200.000											
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	1,895.000		817.000		6,684.000		9,004.000		6,908.000		4,624.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,895.000		817.000		6,684.000		9,004.000		6,908.000		4,624.000	
	666-6171	REFL PAV MRK TY II (W) 6" (BRK)	LF					5,873.000		16,897.000					
	666-6174	REFL PAV MRK TY II (W) 6" (SLD)	LF	23,774.000		11,086.000		64,212.000		98,420.000		248,709.000		164,038.000	
	666-6178	REFL PAV MRK TY II (W) 8" (SLD)	LF					1,556.000		988.000					
	666-6180	REFL PAV MRK TY II (W) 12" (SLD)	LF												
	666-6182	REFL PAV MRK TY II (W) 24" (SLD)	LF	59.000		25.000						20.000			
	666-6184	REFL PAV MRK TY II (W) (ARROW)	EA					8.000							
	666-6192	REFL PAV MRK TY II (W) (WORD)	EA	4.000				4.000							
	666-6196	REFL PAV MRK TY II (W) (RR XING)	EA												
	666-6199	REFL PAV MRK TY II (W) 36" (YLD TRI)	EA	10.000								4.000			
	666-6208	REFL PAV MRK TY II (Y) 6" (BRK)	LF	690.000		3,825.000		4,295.000		3,130.000		29,815.000		19,476.000	
	666-6210	REFL PAV MRK TY II (Y) 6" (SLD)	LF	18,732.000		5,090.000		64,221.000		89,165.000		40,992.000		27,919.000	
	672-6007	REFL PAV MRKR TY I-C	EA					147.000		422.000					
	672-6009	REFL PAV MRKR TY II-A-A	EA	388.000		168.000		1,488.000		2,184.000		1,416.000		948.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	59.000		25.000						20.000			
	677-6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA					8.000							
	677-6012	ELIM EXT PAV MRK & MRKS (WORD)	EA	4.000											
	677-6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA												
	677-6019	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	EA	10.000								4.000			
	677-6028	ELIM EXT PV MRK & MRKS (RUMBLE STRIP)	LF			4,683.000									
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000											
	6185-6002	TMA (STATIONARY)	DAY	100.000											
	6185-6005	TMA (MOBILE OPERATION)	DAY	100.000											
	08	CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS	1.000											
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS	1.000											
		CONTRACTOR FORCE ACCOUNT RAILROAD FLAGGING (NON-PARTICIPATING)	LS	1.000											
		CONTRACTOR FORCE ACCOUNT LAW ENFORCEMENT (NON-PARTICIPATING)	LS	1.000											

Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0002-19-010 **DISTRICT** El Paso **COUNTY** Culberson, Hudspeth
HIGHWAY BI 10C, FM 1576, FM 2249, IH 10, RM 1111, SH 54, US 62

				0233-05-036		0374-05-030		0374-08-026		1282-02-028		2122-01-017		2122-01-018	
		CONTROL SECTION JOB													
		PROJECT ID		A00134547		A00176623		A00176620		A00134538		A00134539		A00134542	
		COUNTY		Culberson		Hudspeth		Culberson		Hudspeth		Hudspeth		Hudspeth	
		HIGHWAY		SH 54		US 62		US 62		RM 1111		FM 1576		FM 2249	
ALT	**BID CODE**	**DESCRIPTION**	**UNIT**	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL
	316-6007	ASPH (A-R TYPE II)	GAL	152,382.000		200,857.000		78,354.000		416,639.000		63,590.000		44,690.000	
	316-6126	AGGR(TY-PB GR-4 SAC-A)	CY	2,521.000		3,322.000		1,297.000		6,888.000		1,053.000		740.000	
	500-6001	MOBILIZATION	LS												
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO												
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF												
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF												
	510-6002	ONE-WAY TRAF CONT (PILOT CAR)	HR												
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	4,629.000		6,784.000		2,620.000		19,217.000		2,972.000		493.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	4,629.000		6,784.000		2,620.000		19,217.000		2,972.000		493.000	
	666-6171	REFL PAV MRK TY II (W) 6" (BRK)	LF			5,254.000		2,489.000							
	666-6174	REFL PAV MRK TY II (W) 6" (SLD)	LF	122,102.000		156,448.000		50,242.000		436,868.000		57,289.000		32,058.000	
	666-6178	REFL PAV MRK TY II (W) 8" (SLD)	LF	396.000											
	666-6180	REFL PAV MRK TY II (W) 12" (SLD)	LF	810.000											
	666-6182	REFL PAV MRK TY II (W) 24" (SLD)	LF	523.000						283.000				120.000	
	666-6184	REFL PAV MRK TY II (W) (ARROW)	EA												
	666-6192	REFL PAV MRK TY II (W) (WORD)	EA							2.000					
	666-6196	REFL PAV MRK TY II (W) (RR XING)	EA	2.000											
	666-6199	REFL PAV MRK TY II (W) 36" (YLD TRI)	EA												
	666-6208	REFL PAV MRK TY II (Y) 6" (BRK)	LF	15,871.000		13,940.000		4,880.000		44,370.000		22,338.000		4,008.000	
	666-6210	REFL PAV MRK TY II (Y) 6" (SLD)	LF	31,577.000		55,600.000		21,973.000		152,600.000		8,130.000		1,041.000	
	672-6007	REFL PAV MRKR TY I-C	EA			131.000		62.000							
	672-6009	REFL PAV MRKR TY II-A-A	EA	949.000		1,496.000		587.000		3,939.000		609.000		101.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	523.000						283.000				120.000	
	677-6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA												
	677-6012	ELIM EXT PAV MRK & MRKS (WORD)	EA							2.000					
	677-6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA	2.000											
	677-6019	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	EA												
	677-6028	ELIM EXT PV MRK & MRKS (RUMBLE STRIP)	LF	95,472.000		156,478.000									
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA												
	6185-6002	TMA (STATIONARY)	DAY												
	6185-6005	TMA (MOBILE OPERATION)	DAY												
	08	CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS												
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS												
		CONTRACTOR FORCE ACCOUNT RAILROAD FLAGGING (NON-PARTICIPATING)	LS												
		CONTRACTOR FORCE ACCOUNT LAW ENFORCEMENT (NON-PARTICIPATING)	LS												

Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0002-19-010 **DISTRICT** El Paso **COUNTY** Culberson, Hudspeth
HIGHWAY BI 10C, FM 1576, FM 2249, IH 10, RM 1111, SH 54, US 62

						TOTAL EST.	TOTAL FINAL
		CONTROL SECTION JOB		**2203-01-011**			
		PROJECT ID		**A00134541**			
		COUNTY		**Hudspeth**			
		HIGHWAY		**FM 1576**			
ALT	**BID CODE**	**DESCRIPTION**	**UNIT**	EST.	FINAL		
	316-6007	ASPH (A-R TYPE II)	GAL	140,458.000		1,897,260.000	
	316-6126	AGGR(TY-PB GR-4 SAC-A)	CY	2,323.000		31,594.000	
	500-6001	MOBILIZATION	LS			1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO			5.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF			500.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF			500.000	
	510-6002	ONE-WAY TRAF CONT (PILOT CAR)	HR			200.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	3,488.000		70,135.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	3,488.000		70,135.000	
	666-6171	REFL PAV MRK TY II (W) 6" (BRK)	LF			30,513.000	
	666-6174	REFL PAV MRK TY II (W) 6" (SLD)	LF	182,724.000		1,647,970.000	
	666-6178	REFL PAV MRK TY II (W) 8" (SLD)	LF			2,940.000	
	666-6180	REFL PAV MRK TY II (W) 12" (SLD)	LF			810.000	
	666-6182	REFL PAV MRK TY II (W) 24" (SLD)	LF	10.000		1,040.000	
	666-6184	REFL PAV MRK TY II (W) (ARROW)	EA			8.000	
	666-6192	REFL PAV MRK TY II (W) (WORD)	EA			10.000	
	666-6196	REFL PAV MRK TY II (W) (RR XING)	EA			2.000	
	666-6199	REFL PAV MRK TY II (W) 36" (YLD TRI)	EA			14.000	
	666-6208	REFL PAV MRK TY II (Y) 6" (BRK)	LF	22,148.000		188,786.000	
	666-6210	REFL PAV MRK TY II (Y) 6" (SLD)	LF	13,608.000		530,648.000	
	672-6007	REFL PAV MRKR TY I-C	EA			762.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	715.000		14,988.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	10.000		1,040.000	
	677-6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA			8.000	
	677-6012	ELIM EXT PAV MRK & MRKS (WORD)	EA			6.000	
	677-6016	ELIM EXT PAV MRK & MRKS (RR XING)	EA			2.000	
	677-6019	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	EA			14.000	
	677-6028	ELIM EXT PV MRK & MRKS (RUMBLE STRIP)	LF			256,633.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA			2.000	
	6185-6002	TMA (STATIONARY)	DAY			100.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY			100.000	
	08	CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS			1.000	
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS			1.000	
		CONTRACTOR FORCE ACCOUNT RAILROAD FLAGGING (NON-PARTICIPATING)	LS			1.000	
		CONTRACTOR FORCE ACCOUNT LAW ENFORCEMENT (NON-PARTICIPATING)	LS			1.000	

CK
DW
CK
DW

DATE: 10/19/2023 5:38:52 PM
FILE: pw://txdot.projectwiseonline.com:TXDOTS/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/1. General/QUANTITY SUMMARY

SUMMARY OF EROSION CONTROL ITEMS

LOCATION	506 6038	506 6039
	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	LF	LF
0002-19-010, ETC	500	500
PROJECT TOTALS	500	500

SUMMARY OF TRAFFIC CONTROL ITEMS

LOCATION	500 6001	502 6001	510 6002	6001 6002	6185 6002	6185 6005
	MOBILIZATION	BARRICADES, SIGNS AND TRAFFIC HANDLING	ONE-WAY TRAF CONT (PILOT CAR)	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	LS	MO	HR	EA	DAY	DAY
0002-19-010, ETC	1	5	200	2	100	100
PROJECT TOTALS	1	5	200	2	100	100

SUMMARY OF PAVEMENT MARKING ITEMS

REF #	HWY	CSJ	662 6109	662 6111	666 6171	666 6174	666 6178	666 6180	666 6182	666 6184	666 6192	666 6196	666 6199	666 6208	666 6210
			WK ZN PAV MRK SHT TERM (TAB)TY W	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	REFL PAV MRK TY II (W) 6" (BRK)	REFL PAV MRK TY II (W) 6" (SLD)	REFL PAV MRK TY II (W) 8" (SLD)	REFL PAV MRK TY II (W) 12" (SLD)	REFL PAV MRK TY II (W) 24" (SLD)	REFL PAV MRK TY II (W) (ARROW)	REFL PAV MRK TY II (W) (WORD)	REFL PAV MRK TY II (W) (RR XING)	REFL PAV MRK TY II (W) 36" (YLD TRI)	REFL PAV MRK TY II (Y) 6" (BRK)	REFL PAV MRK TY II (Y) 6" (SLD)
			EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	LF	LF
1	BI 10C	0002-19-010	1,895	1,895		23,774			59		4		10	690	18,732
2	IH 10	0003-03-049	817	870		11,086			25					3,825	5,090
3	US 62	0233-01-052	6,684	6,684	5,873	64,212	1,556			8	4			4,295	64,221
4	US 62	0233-02-036	9,004	9,004	16,897	98,420	988							3,130	89,165
5	SH 54	0233-03-017	6,908	6,908		248,709			20				4	29,815	40,992
6	SH 54	0233-04-015	4,624	4,624		164,038								19,476	27,919
7	SH 54	0233-05-036	4,629	4,629		122,102	396	810	523			2		15,871	31,577
8	US 62	0374-05-030	6,784	6,784	5,254	156,448								13,940	55,600
9	US 62	0374-08-026	2,620	2,620	2,489	50,242								4,880	21,973
10	RM 1111	1282-02-028	19,217	19,217		436,868			283		2			44,370	152,600
11	FM 1576	2122-01-017	2,972	2,972		57,289								22,338	8,130
12	FM 2249	2122-01-018	493	493		32,058			120					4,008	1,041
13	FM 1576	2203-01-011	3,488	3,488		182,724			10					22,148	13,608
PROJECT TOTALS			70,136	70,189	30,513	1,647,970	2,940	810	1,040	8	10	2	14	188,786	530,648

SUMMARY OF PAVEMENT MARKING ITEMS

LOCATION	HWY	CSJ	672 6007	672 6009	677 6007	677 6008	677 6012	677 6016	677 6019	677 6028
			REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	ELIM EXT PAV MRK & MRKS (24")	ELIM EXT PAV MRK & MRKS (ARROW)	ELIM EXT PAV MRK & MRKS (WORD)	ELIM EXT PAV MRK & MRKS (RR XING)	ELIM EXT PAV MRK & MRKS (36")(YLD TRI)	ELIM EXT PV MRK & MRKS (RUMBLE STRIP)
			EA	EA	LF	EA	EA	EA	EA	LF
1	BI 10C	0002-19-010		388	59		4		10	
2	IH 10	0003-03-049		168	25					4,683
3	US 62	0233-01-052	147	1,488		8				
4	US 62	0233-02-036	422	2,184						
5	SH 54	0233-03-017		1,416	20				4	
6	SH 54	0233-04-015		948						
7	SH 54	0233-05-036		949	523			2		95,472
8	US 62	0374-05-030	131	1,496						156,478
9	US 62	0374-08-026	62	587						
10	RM 1111	1282-02-028		3,939	283		2			
11	FM 1576	2122-01-017		609						
12	FM 2249	2122-01-018		101	120					
13	FM 1576	2203-01-011		715	10					
PROJECT TOTALS			762	14,988	1,040	8	6	2	14	256,633

SUMMARY OF ROADWAY ITEMS

LOCATION	HWY	CSJ	316 6007	316 6126
			ASPH (A-R TYPE II)	AGGR(TY-PB GR-4 SAC-A)
			GAL	CY
1	BI 10C	0002-19-010	25,833	428
2	IH 10	0003-03-049	11,852	197
3	US 62	0233-01-052	262,613	4,343
4	US 62	0233-02-036	129,798	2,361
5	SH 54	0233-03-017	234,469	3,876
6	SH 54	0233-04-015	135,725	2,245
7	SH 54	0233-05-036	152,382	2,521
8	US 62	0374-05-030	200,857	3,322
9	US 62	0374-08-026	78,354	1,297
10	RM 1111	1282-02-028	416,639	6,888
11	FM 1576	2122-01-017	63,590	1,053
12	FM 2249	2122-01-018	44,690	740
13	FM 1576	2203-01-011	140,458	2,323
PROJECT TOTALS			1,897,260	31,594

Texas Department of Transportation

BI10C, ETC.

SEAL COAT 2024
GENERAL

QUANTITY SUMMARY

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		6

REF #	CSJ	COUNTY	HIGHWAY	LIMITS	ADT	DESCRIPTION OF WORK	SURFACE AREA	LENGTH OF ROAD	WIDTH	ASPHALT	AGGREGATE
										316	316
										6007	6126
										ASPH (A-R TYPE II)	AGGR(TY-PB GR-4 SAC-A)
										0.55	1
							SY	MI	FT	GAL/SY	CY/110 SY
1	0002-19-010	HUDSPETH	BI 10C	1.64 MI W OF RM 1111	1477	LANES	38,420	2.702	26-44	21131	350
						SHOULDERS	8,549			4702	78
				1.32 MI E OF RM 1111		MISCELLANEOUS	0			0	0
						SUBTOTAL	46,969	2.702		25833	428
2	0003-03-049	CULBERSON	IH 10	BORRACHO STA	9093	LANES	12,207	0.867	20-40	6,715.00	111.00
						SHOULDERS	6,496			3,573.00	60.00
				0.873 MI E OF BORRACHO STA		MISCELLANEOUS	2,842			1,564.00	26.00
						SUBTOTAL	21,545	0.867		11,852.00	197.00
3	0374-05-030	HUDSPETH	US 62	FR: 14.1 MI E OF EL PASO COUNTY LINE	1574	LANES	224,846	14.790	42-44	123666	2045
						SHOULDERS	140,073			77040	1274
				To: 2.9 MI W OF RM 2317		INTERSECTIONS	274			151	3
						SUBTOTAL	365,193	14.790		200857	3322
4	0374-08-026	CULBERSON	US 62	HUDSPETH/CULBERSON COUNTY LINE	2107	LANES	83,839	4.808	44-56	46,112.00	763.00
						SHOULDERS	56,414			31,028.00	513.00
				SH 54		MISCELLANEOUS	2,207			1,214.00	21.00
						SUBTOTAL	142,460	4.808		78,354.00	1,297.00
5	0233-01-052	CULBERSON	US 62	9 MI N OF SH 54	2585	LANES	275,778	18.654	36-74	151,678.00	2,508.00
						SHOULDERS	188,895			103,893.00	1,718.00
				NEW MEXICO STATE LINE		MISCELLANEOUS	12,803			7,042.00	117.00
							s				
						SUBTOTAL	477,476	18.654		262,613.00	4,343.00
6	0233-02-036	CULBERSON	US 62	SH 54	2487	LANES	175,669	9.027	36-74	87,835.00	1,597.00
						SHOULDERS	83,455			41,728.00	759.00
				9 MI N OF SH 54		MISCELLANEOUS	470			235.00	5.00
						SUBTOTAL	259,594	9.027		129,798.00	2,361.00
7	0233-03-017	CULBERSON	SH 54	US 62/180	434	LANES	309,537	23.770	26-32	170,246.00	2,814.00
						SHOULDERS	111,173			61,146.00	1,011.00
				31.142 MI N OF BI-10D		MISCELLANEOUS	5,594			3,077.00	51.00
						SUBTOTAL	426,304	23.770		234,469.00	3,876.00

Texas Department of Transportation

BI10C, ETC.

MATERIALS SUMMARY

SHEET 1 OF 2

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		7

DATE: 10/3/2023 5:31:41 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/1. General/MATERIALS SUMMARY 1.dgn

CK | DW | CK | DW

REF #	CSJ	COUNTY	HIGHWAY	LIMITS	ADT	DESCRIPTION OF WORK	SURFACE AREA	LENGTH OF ROAD	WIDTH	ASPHALT	AGGREGATE
										316	316
										6007	6126
										ASPH (A-R TYPE II)	AGGR(TY-PB GR-4 SAC-A)
										0.55 GAL/SY	1 CY/110 SY
							SY	MI	FT		
8	0233-04-015	CULBERSON	SH 54	31.142 MI N OF BI-10D	434	LANES	176,458	14.539	22-28	97,052.00	1,605.00
						SHOULDERS	69,931			38,462.00	636.00
				15.632 MI N OF BI-10D		MISCELLANEOUS	382			211.00	4.00
						SUBTOTAL	246,771	14.539		135,725.00	2,245.00
9	0233-05-036	Culberson	SH 54	15.632 MI N OF BI-10D	3550	LANES	202,452	14.740	22-54	111,349.00	1,841.00
						SHOULDERS	71,071			39,090.00	647.00
				BI-10D		MISCELLANEOUS	3,531			1,943.00	33.00
						SUBTOTAL	277,054	14.740		152,382.00	2,521.00
10	1282-02-028	HUDSPETH	RM 1111	US 62/180	1739	LANES	571,148	42.208	24-54	314,132.00	5,193.00
						SHOULDERS	179,282			98,605.00	1,630.00
				IH 10		INTERSECTIONS	7,095			3,902.00	65.00
						SUBTOTAL	757,525	42.208		416,639.00	6,888.00
11	2121-01-017	HUDSPETH	FM 1576	STATE LINE	221	LANES	78,558	6.593	28-30	43,208.00	715.00
						SHOULDERS	34,619			19,041.00	315.00
				JCT OF FM 2249		MISCELLANEOUS	2,437			1,341.00	23.00
						SUBTOTAL	115,614	6.593		63,590.00	1,053.00
12	2122-01-018	HUDSPETH	FM 2249	JCT OF FM 1576	446	LANES	53,551	4.564	30.00	29,454.00	487.00
						SHOULDERS	26,775			14,727.00	244.00
				JCT OF FM 1437		INTERSECTIONS	924			509.00	9.00
						SUBTOTAL	81,250	4.564		44,690.00	740.00
13	2203-01-011	HUDSPETH	FM 1576	US 62/180	135	LANES	202,998	17.301	24-30	111,650.00	1,846.00
						SHOULDERS	51,888			28,539.00	472.00
				IH 10		INTERSECTIONS	488			269.00	5.00
						SUBTOTAL	255,374	17.301		140,458.00	2,323.00

Texas Department of Transportation

BI10C, ETC.

MATERIALS SUMMARY

SHEET 2 OF 2

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		8

DATE: 10/3/2023 5:31:42 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/000219010/4 - Design/Plan Set/1. General/MATERIALS SUMMARY 1.dgn

DW | CK | DW | CK

REF. # 1	0002-19-010	10C	INTERSECTIONS, WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
NONE	ASPH	0	0	0	0	0
					TOTAL	0

REF. # 2	0003-03-049	10	INTERSECTIONS, WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
GORE 1	ASPH					758
GORE 2	ASPH					295
MISCELLANEOUS DRIVEWAYS	ASPH					1789
					TOTAL	2842

REF. # 3	0233-01-052	62	INTERSECTIONS, WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
GORE 1	ASPH					1194
GORE 2	ASPH					437
MISCELLANEOUS RAMP	ASPH					7445
MISCELLANEOUS DRIVEWAYS	ASPH					3727
					TOTAL	12803

REF. # 4	0233-02-036	62	INTERSECTIONS ,WIDING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
MISCELLANEOUS DRIVEWAYS	ASPH					470
					TOTAL	470

REF. # 5	0233-03-017	54	INTERSECTIONS, WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
GORE 1	ASPH					358
MISCELLANEOUS DRIVEWAYS	ASPH					4666
MISCELLANEOUS REST AREA	ASPH					570
					TOTAL	5594

REF. # 6	0233-04-015	54	INTERSECTIONS, WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
MISCELLANEOUS DRIVEWAYS	ASPH					382
					TOTAL	382

REF. # 7	0233-05-036	54	INTERSECTIONS, WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
E. ASTER ST.	ASPH	25	38	28	24	188
W 1ST ST.	ASPH	24	45	22	19	190
W 2ND ST.	ASPH	17	32	14	14	117
W 3RD ST.	ASPH	18	53	17	13	154
E 4TH ST.	ASPH	19	43	17	14	139
E 5TH ST.	ASPH	24	28	17	20	131
E 6TH ST.	ASPH	25	33	20	18	156
E 7TH ST.	ASPH	30	30	25	20	165
E 8TH ST.	ASPH	27	28	21	16	148
E 9TH ST.	ASPH	20	41	19	16	178
E 10TH ST.	ASPH	27	28	22	22	150
E 11TH ST.	ASPH	39	31	18	34	194
MISCELLANEOUS DRIVEWAYS	ASPH					1201
MISCELLANEOUS REST AREA	ASPH					420
					TOTAL	3531

REF. # 8 - 0374-05-030 US		62	INTERSECTIONS,WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
MISCELLANEOUS DRIVEWAYS	ASPH					274
					TOTAL	274

REF. # 9 -0374-08-026 US		62	INTERSECTIONS,WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
GORE 1	ASPH					351
MISCELLANEOUS DRIVEWAYS	ASPH					1856
					TOTAL	2207

REF. # 10 -1282-02-028 RM		1111	INTERSECTIONS,WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
THE BLVD	ASPH	40	29	12	12	286
MOUNTAIN RD / SUNRISE	ASPH	64	25	12	12	366
PAT AVE	ASPH	20	26	6	10	89
N MARTIN AVE	ASPH	16	25	10	10	90
N CAMMACK AVE	ASPH	18	26	12	14	92
WAILING	ASPH	23	26	11	14	276
W CAVENDER ST	ASPH	19	22	12	9	111
BROWN ST	ASPH	18	26	11	7	115
W EVERMAN	ASPH	18	28	10	10	124
MISCELLANEOUS DRIIVEWAYS	ASPH					5546
					TOTAL	7095

REF. # 11 - 2122-01-017 FM		1576	INTERSECTIONS,WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
MISCELLANEOUS DRIVEWAYS	ASPH					2437
					TOTAL	2437

REF. # 12 - 2122-01-018 FM		2249	INTERSECTIONS,WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
MAIN ST	ASPH	87	24			606
MISCELLANEOUS DRIVEWAYS	ASPH					318
					TOTAL	924

REF. # 13 - 2203-01-011 FM		1576	INTERSECTIONS,WIDENING, RAMPS,CROSSOV & GORES QUANTITY				
INTERSECTION, WIDENING, RAMPS, CROSSOV., GORES	TYP	LENGTH FT	WIDTH FT	R1 FT	R2 FT	AREA SY
MISCELLANEOUS DRIVEWAYS	ASPH					488
					TOTAL	488

Texas Department of Transportation

BI10C, ETC.

INTERSECTIONS, GORES, AND MISCELLANEOUS QUANTITIES

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		9

DATE: 10/3/2023 5:31:59 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/3. Roadway/INTERSECTIONS, GORES, AND MISCELLANEOUS QUANTITIES 1.dgn

CK DW CK DW

DATE:
FILE:

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.

2.

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

4.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

☒ No Permit Required

☐ Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)

☐ Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)

☐ Individual 404 Permit Required

☐ Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.

2.

3.

4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
☐ Temporary Vegetation	☒ Silt Fence	☐ Vegetative Filter Strips
☐ Blankets/Matting	☐ Rock Berm	☐ Retention/Irrigation Systems
☐ Mulch	☐ Triangular Filter Dike	☐ Extended Detention Basin
☐ Sodding	☐ Sand Bag Berm	☐ Constructed Wetlands
☐ Interceptor Swale	☐ Straw Bale Dike	☐ Wet Basin
☐ Diversion Dike	☐ Brush Berms	☐ Erosion Control Compost
☐ Erosion Control Compost	☐ Erosion Control Compost	☐ Mulch Filter Berm and Socks
☐ Mulch Filter Berm and Socks	☐ Mulch Filter Berm and Socks	☐ Compost Filter Berm and Socks
☐ Compost Filter Berm and Socks	☐ Compost Filter Berm and Socks	☐ Vegetation Lined Ditches
	☐ Stone Outlet Sediment Traps	☐ Sand Filter Systems
	☐ Sediment Basins	☐ Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical.
Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP:	Best Management Practice	SPCC:	Spill Prevention Control and Countermeasure
CGP:	Construction General Permit	SW3P:	Storm Water Pollution Prevention Plan
DSHS:	Texas Department of State Health Services	PCN:	Pre-Construction Notification
FHWA:	Federal Highway Administration	PSL:	Project Specific Location
MOA:	Memorandum of Agreement	TCEQ:	Texas Commission on Environmental Quality
MOU:	Memorandum of Understanding	TPDES:	Texas Pollutant Discharge Elimination System
MS4:	Municipal Separate Stormwater Sewer System	TPWD:	Texas Parks and Wildlife Department
MBTA:	Migratory Bird Treaty Act	TxDOT:	Texas Department of Transportation
NOT:	Notice of Termination	T&E:	Threatened and Endangered Species
NWP:	Nationwide Permit	USACE:	U.S. Army Corps of Engineers
NOI:	Notice of Intent	USFWS:	U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

* Dead or distressed vegetation (not identified as normal)
* Trash piles, drums, canister, barrels, etc.
* Undesirable smells or odors
* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

☐ Yes ☒ No

If "No", then no further action is required.
If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

☐ Yes ☒ No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

☒ No Action Required ☐ Required Action

Action No.

1.

2.

3.

Texas Department of Transportation — Design Division Standard

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

EPIC

FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR	
©TxDOT: February 2015	CONT	SECT	JOB	HIGHWAY	
REVISIONS 12-12-2011 (DS)	0002	19	010, ETC.	BI 10C, ETC.	
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY		SHEET NO.	
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	ELP	HUDSPETH, ETC.		10	

TCP SELECTION TABLE

CSJ	ROADWAY	LIMITS FROM	LIMITS TO	TYPE OF WORK	SHEET
0374-05-030	US 62	14.1 MI E OF EL PASO COUNTY LINE	2.9 MI W OF RM 2317	SEAL COAT	TCP(SC-1)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-13
				RPM INSTALLATION	TCP(3-3)-14
1282-02-028	RM 111	US 62/180	IH 10	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-12 TCP(3-2)-13
				RPM INSTALLATION	TCP(3-3)-14
0002-19-010	BI 10C	1.64 MI W OF RM 1111	1.32 MI E OF RM 1111	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22, TCP(SC-6)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-13 TCP(3-2)-13 TCP(3-3)-14 TCP(3-4)-13
				SYMBOL, STOP BARS AND CROSSWALKS	TCP(1-2)-18
				RPM INSTALLATION	TCP(3-3)-14
2203-01-011	FM 1576	JCT OF FM 2249	JCT OF US 62/180	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-12 TCP(3-2)-13
				SYMBOL, STOP BARS AND CROSSWALKS	TCP(1-2)-18
				RPM INSTALLATION	TCP(3-3)-14
2122-01-018	FM 2249	JCT OF FM 1576	JCT OF FM 1437	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-12 TCP(3-2)-13
				SYMBOL, STOP BARS AND CROSSWALKS	TCP(1-2)-18
				RPM INSTALLATION	TCP(3-3)-14
2122-01-017	FM 1576	STATE LINE	JCT OF FM 2249	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-12 TCP(3-2)-13
				RPM INSTALLATION	TCP(3-3)-14
0374-08-026	US 62	HUDSPETH/CULBERSON COUNTY LINE	SH 54	SEAL COAT	TCP(SC-1)-22,TCP(SC-2)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-2)-13 TCP(3-3)-14
				SYMBOL, STOP BARS AND CROSSWALKS	TCP(1-2)-18
				RPM INSTALLATION	TCP(3-3)-14
0233-02-036	US 62	SH 54	9 MI N OF SH 54	SEAL COAT	TCP(SC-2)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-2)-13 TCP(3-3)-14
				RPM INSTALLATION	TCP(3-3)-14
0233-01-052	US 62	9 MI N OF SH 54	NEW MEXICO STATE LINE	SEAL COAT	TCP(SC-1)-22,TCP(SC-2)-22, TCP(SC-5)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-2)-13 TCP(3-3)-14
				RPM INSTALLATION	TCP(3-3)-14
0233-03-017	SH 54	US 62/180	31.142 MI N OF BI-10D	SEAL COAT	TCP(SC-1)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-13 TCP(3-2)-13 TCP(3-3)-14
				RPM INSTALLATION	TCP(3-3)-14
0233-04-015	SH 54	31.142 MI N OF BI-10D	15.632 MI N OF BI-10D	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-13 TCP(3-2)-13 TCP(3-3)-14
				RPM INSTALLATION	TCP(3-3)-14
0233-05-036	SH 54	15.632 MI N OF BI-10D	BI-10D	SEAL COAT	TCP(SC-1)-22,TCP(SC-4)-22
				WORK ZONE SHORT TERM PAVEMENT MARKINGS	TCP(SC-7)-22 TCP(SC-8)-22
				EDGELINE, BROKEN AND CENTERLINE STRIPING	TCP(3-1)-13 TCP(3-2)-13 TCP(3-3)-14
				RPM INSTALLATION	TCP(3-3)-14

STATE OF TEXAS
KARLA Y. RIOS
140855
LICENSED
PROFESSIONAL ENGINEER

Karla Rios, P.E.

10/03/2023

Texas Department of Transportation

BI10C, ETC.

TCP SELECTION TABLE

SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0002	19	010, ETC.	BI 10C, ETC.
DIST	COUNTY		SHEET NO.
ELP	HUDSPETH, ETC.		11

DATE: 10/3/2023 5:32:36 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/000219010/4 - Design/Plan Set/2. TCP/TCP Selection Table.dgn

CK | DW | CK | DW

DATE: 10/3/2023 5:32:55 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/2. TCP/bc-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).

2. The development and design of the Traffic Control Plan (TCP)is the responsibility of the Engineer.

3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.

4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.

5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.

6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.

7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.

8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.

9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.

10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.

11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.

12. The Engineer has the final decision on the location of all traffic control devices.

13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.

2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.

2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC(1)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
4-03 7-13	DIST	COUNTY		SHEET NO.
9-07 8-14	ELP	HUDSPETH, ETC.		12
5-10 5-21				

DATE: 10/3/2023 5:32:55 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/000219010/4 - Design/Plan Set/2. TCP/bc-21.dgn

TYPICAL LOCATION OF CROSSROAD SIGNS



May be mounted on back of "ROAD WORK AHEAD"(CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK"(G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES"(G20-1aT)sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING[1,5,6]

SIZE

Sign Number or Series	Conventional Road	Expressway/ Freeway
CW20[4] CW21 CW22 CW23 CW25	48" x 48"	48" x 48"
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"

SPACING

Posted Speed	Sign △ Spacing "X"
MPH	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500[2]
60	600[2]
65	700[2]
70	800[2]
75	900[2]
80	1000[2]
*	*[3]

* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

△ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD"(CW20-1D)signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES"(G20-5T)sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

□ The "BEGIN WORK ZONE"(G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.

** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.

◊ Area for placement of "ROAD WORK AHEAD" (CW20-1D)sign and other signs or devices as called for on the Traffic Control Plan.

◊◊ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
⟼	Type 3 Barricade
○ ○ ○	Channelizing Devices
▬	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		13

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project.

Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

a) rough road or damaged pavement surface
b) substantial alteration of roadway geometrics (diversions)
c) construction detours
d) grade
e) width
f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
4. Frequency of work zone speed limit signs should be:
   40 mph and greater 0.2 to 2 miles
   35 mph and less 0.2 to 1 mile
5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
8. Techniques that may help reduce traffic speeds include but are not limited to:
   A. Law enforcement.
   B. Flagger stationed next to sign.
   C. Portable changeable message sign (PCMS).
   D. Low-power (drone) radar transmitter.
   E. Speed monitor trailers or signs.
9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

Texas Department of Transportation — Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS 9-07 8-14 7-13 5-21	0002	19	010, ETC.	BI 10C, ETC.
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH, ETC.	14

DATE: 10/3/2023 5:32:55 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002196010/4 - Design/Plan Set/2. TCP/bc-21.dgn

DATE: 10/3/2023 5:32:55 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/000219010/4 - Design/Plan Set/2. TCP/bc-21.dgn

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS





Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectorized when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B_{FL} OR C_{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
   a. Long-term stationary - work that occupies a location more than 3 days.
   b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
   c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
   d. Short, duration - work that occupies a location up to 1 hour.
   e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

Texas Department of Transportation | Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		15

DATE: 10/3/2023 5:32:56 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/000219010/4 - Design/Plan Set/2. TCP/bc-21.dgn





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support.
The maximum sign square footage shall adhere to the manufacturer's recommendation.
Two post installations can be used for larger signs.







SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

* See BC(4) for definition of "Work Duration."

** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.

☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

Texas Department of Transportation | Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		16

DATE: 10/3/2023 5:32:56 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002901074 - Design/Plan Set/2. TCP/bc-21.dgn

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
11. Do not use the word "Danger" in message.
12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
13. Do not display messages that scroll horizontally or vertically across the face of the sign.
14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
16. Each line of text should be centered on the message board rather than left or right justified.
17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD
Alternate	ALT
Avenue	AVE
Best Route	BEST RTE
Boulevard	BLVD
Bridge	BRDG
Cannot	CANT
Center	CTR
Construction Ahead	CONST AHD
CROSSING	XING
Detour Route	DETOUR RTE
Do Not	DONT
East	E
Eastbound	(route) E
Emergency	EMER
Emergency Vehicle	EMER VEH
Entrance, Enter	ENT
Express Lane	EXP LN
Expressway	EXPWY
XXXX Feet	XXXX FT
Fog Ahead	FOG AHD
Freeway	FRWY, FWY
Freeway Blocked	FWY BLKD
Friday	FRI
Hazardous Driving	HAZ DRIVING
Hazardous Material	HAZMAT
High-Occupancy	HOV
Vehicle Highway	HWY
Hour(s)	HR, HRS
Information	INFO
It Is	ITS
Junction	JCT
Left	LFT
Left Lane	LFT LN
Lane Closed	LN CLOSED
Lower Level	LWR LEVEL
Maintenance	MAINT
Major	MAJ
Miles	MI
Miles Per Hour	MPH
Minor	MNR
Monday	MON
Normal	NORM
North	N
Northbound	(route) N
Parking	PKING
Road	RD
Right Lane	RT LN
Saturday	SAT
Service Road	SERV RD
Shoulder	SHLDR
Slippery	SLIP
South	S
Southbound	(route) S
Speed	SPD
Street	ST
Sunday	SUN
Telephone	PHONE
Temporary	TEMP
Thursday	THURS
To Downtown	TO DWNTN
Traffic	TRAF
Travelers	TRVLRS
Tuesday	TUES
Time Minutes	TIME MIN
Upper Level	UPR LEVEL
Vehicles (s)	VEH, VEHS
Warning	WARN
Wednesday	WED
Weight Limit	WT LIMIT
West	W
Westbound	(route) W
Wet Pavement	WET PVMT
Will Not	WONT

Roadway designation * IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM- X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM- XX AM

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

1. Only 1 or 2 phases are to be used on a PCMS.
2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
2. Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
4. Highway names and numbers replaced as appropriate.
5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
6. AHEAD may be used instead of distances if necessary.
7. FT and MI, MILE and MILES interchanged as appropriate.
8. AT, BEFORE and PAST interchanged as needed.
9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		17

DATE: 10/3/2023 5:32:56 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/2. TCP/bc-21.dgn

1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional)while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
7. Maximum spacing of Barrier Reflectors is forty (40) feet.
8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
10. Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
11. Single slope barriers shall be delineated as shown on the above detail.



Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square.Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

1. Warning lights shall meet the requirements of the TMUTCD.
2. Warning lights shall NOT be installed on barricades.
3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
3. The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
4. The Flashing Arrow Board should be able to display the following symbols:



5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
6. The straight line caution display is NOT ALLOWED.
7. The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
8. Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
9. The sequential arrow display is NOT ALLOWED.
10. The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION

Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

TRUCK-MOUNTED ATTENUATORS

1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
2. Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
3. Refer to the CWZTCD for a list of approved TMAs.
4. TMAs are required on freeways unless otherwise noted in the plans.
5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC(7)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		18

101

DATE: 10/3/2023 5:32:56 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/00021901O/4 - Design/Plan Set/2. TCP/bc-21.dgn

GENERAL NOTES

1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:

1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
9. Drum body shall have a maximum unballasted weight of 11 lbs.
10. Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials," Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
6. Ballast shall not be placed on top of drums.
7. Adhesives may be used to secure base of drums to pavement.







DETECTABLE PEDESTRIAN BARRICADES

1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
5. Warning lights shall not be attached to detectable pedestrian barricades.
6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24"
Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

Texas Department of Transportation | Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
4-03 8-14	DIST	COUNTY		SHEET NO.
9-07 5-21	ELP	HUDSPETH, ETC.		19
7-13				

102

DATE: 10/3/2023 5:32:57 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/2. TCP/bc-21.dgn



FIXED
(Rigid or self-righting)

DRIVEABLE



(Rigid or self-righting)

PORTABLE

1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)



1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
2. The OTLD may be used in combination with 42" cones or VPs.
3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
4. To be effective, the chevron should be visible for at least 500 feet.
5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
2. LCDs may be used instead of a line of cones or drums.
3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

1. Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	Minimum Desirable Taper Lengths ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices On a Taper	On a Tangent
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

** Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12

Texas Department of Transportation | Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		20

DATE: 10/3/2023 5:32:57 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190104 - Design/Plan Set/2. TCP/bc-21.dgn

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.



TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW

The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic.
Barricade striping should slant downward in the direction of detour.



PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW

1. Where positive redirectional capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.



LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
SB	Steady burn warning light or yellow warning reflector

PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS



28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	ELP	HUDSPETH, ETC.		21

104

WORK ZONE PAVEMENT MARKINGS

GENERAL

1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
2. Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
3. Additional supplemental pavement marking details may be found in the plans or specifications.
4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
7. All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

1. Raised pavement markers are to be placed according to the patterns on BC(12).
2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
2. Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.

MAINTAINING WORK ZONE PAVEMENT MARKINGS

1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
3. Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
7. Over-painting of the markings SHALL NOT BE permitted.
8. Removal of raised pavement markers shall be as directed by the Engineer.
9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
10. Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
   A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
   B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
3. Small design variances may be noted between tab manufacturers.
4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

1. Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
2. All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
3. Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body).
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
2-98 9-07 5-21	DIST	COUNTY		SHEET NO.
1-02 7-13	ELP	HUDSPETH, ETC.		22
11-02 8-14				

105

DATE: 10/3/2023 5:32:57 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/00021901/4 - Design/Plan Set/2. TCP/bc-21.dgn

PAVEMENT MARKING PATTERNS

REFLECTORIZED PAVEMENT MARKINGS - PATTERN A



RAISED PAVEMENT MARKERS - PATTERN A



REFLECTORIZED PAVEMENT MARKINGS - PATTERN B



RAISED PAVEMENT MARKERS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer.
Prefabricated markings may be substituted for reflectorized pavement markings.

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

EDGE & LANE LINES FOR DIVIDED HIGHWAY



REFLECTORIZED PAVEMENT MARKINGS



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

TWO-WAY LEFT TURN LANE

STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS

SOLID LINES

DOUBLE NO-PASSING LINE



EDGE LINE OR SINGLE NO-PASSING LINE



WIDE LINE

(FOR LEFT TURN CHANNELIZING LINE OR CHANNELIZING LINE USED TO DISCOURAGE LANE CHANGING.)



BROKEN LINES

CENTER LINE OR LANE LINE



AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



Centerline only - not to be used on edge lines

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

Texas Department of Transportation

Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
1-97 9-07 5-21	DIST	COUNTY		SHEET NO.
2-98 7-13	ELP	HUDSPETH, ETC.		23
11-02 8-14				

106

DATE: 10/3/2023 5:33:15 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/...



TCP(SC-1a)

ONE LANE TWO-WAY (TWO LANES)
CONTROL WITH PILOT VEHICLE



TCP(SC-1b)

ONE LANE TWO-WAY (THREE LANES)
CONTROL WITH PILOT VEHICLE
AND CHANNELIZING DEVICES

LEGEND

Symbol	Description	Symbol	Description
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing Distance "X"	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
** Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT) S = Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except: if project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
3. Sign spacing may be increased or an additional ROAD WORK AHEAD (CW20-1D) sign may be used if advance warning ahead of the flagger sign is less than 1500 feet.
4. Flaggers should use two-way radios or other methods of communication at all times for traffic control coordination.
5. Flaggers should use 24" STOP (CW20-8) / SLOW (CW20-8aT) paddles to control traffic. Flags should be limited to emergency situations.
6. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
7. If the seal coat operation crosses intersections, traffic in these areas must be controlled. Care must be taken to prevent vehicles from crossing the asphalt before the aggregate is placed. This may require positioning additional traffic control personnel (flaggers) at the intersection.
8. Temporary rumble strips are not required on seal coat operations.
9. The pilot car is used to guide vehicles through traffic control zone. The pilot car shall have an identification name displayed and PILOT CAR, FOLLOW ME (G20-4) sign or message board mounted in a conspicuous position on rear.

TCP (SC-1a)

1. Channelizing devices on the centerline are not required when a pilot car is leading traffic, unless directed by the Engineer.

Texas Department of Transportation

Traffic Safety Division Standard

TRAFFIC CONTROL PLAN
SEAL COAT OPERATIONS
ONE-LANE TWO-WAY

TCP(SC-1)-22

FILE: tcpsc-1-22.dgn	DN:	CK:	DW:	CK:
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
4-21	DIST		COUNTY	SHEET NO.
10-22	ELP		HUDSPETH, ETC.	24

217



TCP (SC-2a)

ONE LANE CLOSED EACH DIRECTION CONTROL W/ CHANNELIZING DEVICES



TCP (SC-2b)

ONE LANE CLOSED EACH DIRECTION CONTROL W/ CHANNELIZING DEVICES



TCP (SC-2c)

CENTER LANES CLOSED CONTROL W/ CHANNELIZING DEVICES

LEGEND

(symbol)	Type 3 Barricade	(symbol)	Channelizing Devices
(symbol)	Heavy Work Vehicle	(symbol)	Truck Mounted Attenuator (TMA)
(symbol)	Trailer Mounted Flashing Arrow Board	(symbol)	Portable Changeable Message Sign (PCMS)
(symbol)	Sign	(symbol)	Traffic Flow
(symbol)	Flag	(symbol)	Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices On a Taper	On a Tangent	Minimum Sign Spacing Distance "X"	Suggested Longitudinal Buffer Space "B"
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT)
S = Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except: if project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
3. The ROAD WORK AHEAD (CW20-1D) sign may be repeated if the visibility of the work zone is less than 1500 feet.
4. If the seal coat operation crosses intersections, traffic in these areas must be controlled. Care must be taken to prevent vehicles from crossing the asphalt before the aggregate is placed. This may require positioning additional traffic control personnel (flaggers) at the intersection.
5. Temporary rumble strips are not required on seal coat operations.

TCP (SC-2a) and (SC-2b)

6. Channelizing devices which separate two-way traffic shall be spaced on tapers at:
   a.) 20 feet;
   b.) 15 feet when posted speeds are 35 mph or slower; or
   c.) at 1/2(S) for tangent sections.
   This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

Texas Department of Transportation | Traffic Safety Division Standard

TRAFFIC CONTROL PLAN SEALCOAT OPERATIONS MULTILANE ROADS (UNDIVIDED)

TCP(SC-2)-22

FILE:	tcpsc-2-22.dgn	DN:	CK:	DW:	CK:
©TxDOT	October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS		0002	19	010, ETC.	BI 10C, ETC.
4-21		DIST		COUNTY	SHEET NO.
10-22		ELP		HUDSPETH, ETC.	25

218

DATE: 10/3/2023 5:33:51 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/...



TCP(SC-3a)

ONE LANE CLOSED

CONTROL W/ CHANNELIZING DEVICES



TCP(SC-3b)

TWO LANES CLOSED

CONTROL W/ CHANNELIZING DEVICES



TCP(SC-3c)

CENTER LANES CLOSED

CONTROL W/ CHANNELIZING DEVICES

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing Distance "X"	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT)
S = Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except: if project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
3. If the seal coat operation crosses intersections, traffic in these areas must be controlled. Care must be taken to prevent vehicles from crossing the asphalt before the aggregate is placed. This may require positioning additional traffic control personal (flaggers) at the intersection.
4. Temporary rumble strips are not required on seal coat operations.

TCP (SC-3a) and (SC-3b)

5. Channelizing devices which separate two-way traffic shall be spaced on tapers at:
   a.) 20 feet;
   b.) 15 feet when posted speeds are 35 mph or slower; or
   c.) at 1/2(S) for tangent sections.
   This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

Texas Department of Transportation — Traffic Safety Division Standard

TRAFFIC CONTROL PLAN SEAL COAT OPERATIONS MULTILANE ROADS (W/ CENTER LEFT TURN LANE)

TCP(SC-3)-22

FILE: tcpsc-3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
4-21	DIST		COUNTY	SHEET NO.
10-22	ELP		HUDSPETH, ETC.	26

219

DATE: 10/3/2023 5:34:09 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/000290/04/tcpsc4-22.dgn



ONE LANE TWO-WAY (T-INTERSECTION) CONTROL WITH PILOT VEHICLE

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices On a Taper	On a Tangent	Minimum Sign Spacing Distance "X"	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
30	$L=\frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L=WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
** Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT) S = Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except: if project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
3. Flaggers should use two-way radios or other methods of communication at all times for traffic control coordination.
4. Flaggers should use 24" STOP (CW20-8) / SLOW (CW20-8aT) paddles to control traffic. Flags should be limited to emergency situations.
5. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
6. Temporary rumble strips are not required on seal coat operations.
7. The pilot car is used to guide vehicles through traffic control zone. The pilot car shall have an identification name displayed and PILOT CAR, FOLLOW ME (G20-4) sign or message board mounted in a conspicuous position on rear.

Texas Department of Transportation | Traffic Safety Division Standard

TRAFFIC CONTROL PLAN SEAL COAT OPERATIONS NEAR INTERSECTION

TCP(SC-4)-22

FILE: tcpsc-4-22.dgn	DN:	CK:	DW:	CK:
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-21 10-22	0002	19	010, ETC.	BI 10C, ETC.
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		27



TCP (SC-5a)

ONE LANE CLOSURE



TCP (SC-5b)

LANE AND RAMP CLOSURE AT EXIT RAMPS



TCP (SC-5c)

LANE AND RAMP CLOSURE AT ENTRANCE RAMPS

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing Distance "X"	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L=\frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only

** Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT)
S = Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

GENERAL NOTES

1. Flags attached to signs where shown, are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except:
   - If project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
   - USE NEXT RAMP (CW25-1T) sign is optional with approval by the Engineer.
3. Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
4. The PCMS may be omitted if: it is replaced with a RAMP CLOSED AHEAD (CW20RP-3D) sign or when a permanent Dynamic Message Sign (DMS) is available in the appropriate location to display a similar message as called for on the PCMS.
5. Temporary rumble strips are not required on seal coat operations.

Texas Department of Transportation

Traffic Safety Division Standard

TRAFFIC CONTROL PLAN
SEAL COAT OPERATIONS
DIVIDED HIGHWAYS

TCP(SC-5)-22

FILE: tcpsc-5-22.dgn	DN:		CK:	DW:	CK:	
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY		
REVISIONS 4-21 10-22	0002	19	010, ETC.	BI 10C, ETC.		
	DIST	COUNTY		SHEET NO.		
	ELP	HUDSPETH, ETC.		28		

221

DATE: 10/3/2023 5:34:43 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/



TCP (SC-6a)

MULTIPLE LANE EXIT RAMP CLOSURE



TCP (SC-6b)

SINGLE LANE EXIT RAMP CLOSURE



TCP (SC-6c)

TYPICAL EXIT RAMP CLOSURE

LEGEND

Symbol	Description	Symbol	Description
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L=WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'
85		850'	935'	1020'	85'	170'	695'

** Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT)
S = Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Place channelizing devices at 20' spacings. Tighter spacing allowed as necessary to address field conditions or observed driver behavior.
2. See the Standard Highway Sign Design for Texas (SHSD) for sign details.
3. The PCMS may be omitted if replaced with a RAMP CLOSED AHEAD (CW20RP-3D) sign or when a permanent Dynamic Message Sign (DMS) is available in an appropriate location to display a similar message as called for on the PCMS.
4. When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) for traffic control details.
5. A Truck Mounted Attenuator (TMA), where shown, is REQUIRED and shall have a RAMP CLOSED (R11-2bT) sign mounted on the rear of the truck.

SHEET 6 OF 8

Texas Department of Transportation

Traffic Safety Division Standard

TRAFFIC CONTROL PLAN SEAL COAT OPERATIONS DIVIDED HIGHWAYS

TCP(SC-6)-22

FILE: tcpsc-6-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
10-22	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		29

222

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS (TABS)



CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



LANE LINES FOR DIVIDED HIGHWAY



TWO-WAY LEFT TURN LANE

TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS



WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS (TABS)

SOLID LINES	DOUBLE NO-PASSING LINE	
	SINGLE NO-PASSING LINE or CHANNELIZATION LINE	
	8" WIDE SOLID LINE	
BROKEN LINES (FOR CENTER LINE OR LANE LINE)		
WIDE DOTTED LINES (FOR LANE DROP LINES)		
WIDE GORE MARKINGS		

TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS

1. Temporary markings for surfacing projects shall be Temporary Flexible-Reflective Roadway Marker Tabs with protective cover unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two days before the surfacing is applied. After the surfacing is rolled and swept, the protective cover over the reflective strip shall be removed.
2. Temporary Flexible-Reflective Roadway Marker Tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with a yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
3. Temporary Flexible-Reflective Roadway Marker Tabs will require normal maintenance replacement when used on roadways with an Average Daily Traffic (ADT) per lane of up to 7500 vehicles with no more than 10% truck mix. When roadway volumes exceed these values, additional maintenance replacement of these devices should be planned for.
4. When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low- beam head light at night, unless sight distance is restricted by roadway geometrics.
5. No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 4.
6. Tabs shall meet requirements of Departmental Material Specification DMS-8242.
7. Tabs shall NOT be used to simulate edge lines.

NOTES:

1. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
2. For exit gores where a lane is being dropped, place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are NOT acceptable.
3. Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as ¼ inch, unless otherwise noted.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

1. DMSs referenced above may be found along with embedded links to their respective MPLs at the following website: http://www.txdot.gov

SHEET 7 OF 8

TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS



Texas Department of Transportation

Traffic Safety Division Standard

TEMPORARY PAVEMENT MARKINGS FOR SEAL COAT OPERATIONS

TCP(SC-7)-22

FILE: tcpsc-7-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-21 10-22	0002	19	010, ETC.	BI 10C, ETC.
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		30

223

DATE: 10/3/2023
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/...

DATE: 2023.8/29
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/00219010/4 - Design/Plan Set/2. TCP/tcpsc-8-22.dgn



NOTE

Signing shown for one direction of travel only.

NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS

DO NOT PASS (R4-1) SIGN and NO-PASSING ZONES

A. Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel, except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.

B. At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibitd over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is a considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.

C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshields and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one day of operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.

D. DO NOT PASS and PASS WITH CARE signs are to remain in place until permanent pavement markings are installed.

NO CENTER LINE (CW8-12) SIGN

A. Center line markings are yellow pavement markings that delineate the separation between lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.

B. At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing center line), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately two mile intervals within the work area, beyond major intersections, and other locations deemed necessary by the Engineer.

C. The NO CENTER LINE signs are to remain in place until permanent pavement markings are installed.

LOOSE GRAVEL (CW8-7) SIGN

A. When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately two miles in rural areas and closer in urban areas.

B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

COORDINATION OF SIGN LOCATIONS

A. The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.

B. Where possible, the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed:
   a.) In the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) sign and the TRAFFIC FINES DOUBLE (R20-5T) sign; and
   b.) One "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing.

LOOSE GRAVEL and NO CENTER LINE sign placements will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing Distance "X"
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Surfacing operations that cover or obliterate existing pavement markings must first have the passing zones clearly marked with tabs as well as having any of the traffic control devices detailed on this sheet furnished and erected as directed by the Engineer.
2. The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
3. Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Short Duration / Short Term Stationary Work Zone Sign Supports.
4. When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
5. Signs on divided highways, freeways and expressways should be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.

Texas Department of Transportation | Traffic Safety Division Standard

TRAFFIC CONTROL DETAILS FOR SEAL COAT OPERATIONS

TCP(SC-8)-22

FILE: tcpsc-8-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	http://ww	BI 10-C
4-21	DIST	COUNTY		SHEET NO.
10-22	ELP	HUDSPETH		31



TCP (1-2a)

ONE LANE TWO-WAY CONTROL WITH YIELD SIGNS

(Less than 2000 ADT - See note 7)



TCP (1-2b)

ONE LANE TWO-WAY CONTROL WITH FLAGGERS

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L=WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

1. Flags attached to signs where shown are REQUIRED.
2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
4. Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
6. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

7. R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
8. R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

TCP (1-2b)

9. Flaggers should use two-way radios or other methods of communication to control traffic.
10. Length of work space should be based on the ability of flaggers to communicate.
11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
12. Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
13. Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation — Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP(1-2)-18

FILE: tcp1-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-90 4-98 2-94 2-12 1-97 2-18	0002	19	http://ww	BI 10-C
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH		32



TCP (3-1a)

UNDIVIDED MULTILANE ROADWAY



TRAIL/SHADOW VEHICLE A

with RIGHT Directional display Flashing Arrow Board



TCP (3-1b)

TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)

TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



TRAIL/SHADOW VEHICLE B

with Flashing Arrow Board in CAUTION display

LEGEND

Symbol	Description	Symbol	ARROW BOARD DISPLAY
*	Trail Vehicle		
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY"(CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



STRIPING FOR TMA

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS UNDIVIDED HIGHWAYS

TCP(3-1)-13

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-94 4-98 8-95 7-13 1-97	0002	19	010, ETC.	BI 10C, ETC.
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		33

175

DATE: 10/3/2023 5:36:12 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002-19-010



RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP (3-2a)



INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP (3-2b)

LEGEND

Symbol	Description	Symbol	ARROW BOARD DISPLAY
*	Trail Vehicle		
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
2. For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
3. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
4. The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
5. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
9. Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
10. The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
12. The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
13. Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
14. The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.



STRIPING FOR TMA

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS DIVIDED HIGHWAYS

TCP (3-2)-13

FILE: tcp3-2.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT 0002	SECT 19	JOB 010, ETC.	HIGHWAY BI 10C, ETC.
REVISIONS 2-94 4-98 8-95 7-13 1-97	DIST ELP	COUNTY HUDSPETH, ETC.		SHEET NO. 34

176



TCP (3-3a)

TWO LANE HIGHWAY WITH PAVED SHOULDERS
(WORK ON TRAVEL LANE)



TCP (3-3b)

TWO LANE HIGHWAY WITHOUT PAVED SHOULDERS
(WORK ON TRAVEL LANE)



TCP (3-3c)

DIVIDED MULTILANE HIGHWAY



TCP (3-3d)

UNDIVIDED MULTILANE HIGHWAY



TRAIL/SHADOW VEHICLE A

with RIGHT Directional display Flashing Arrow Board



TRAIL/SHADOW VEHICLE B

with Flashing Arrow Board in Caution Mode



ADVANCE WARNING VEHICLE



STRIPING FOR TMA

LEGEND

Symbol	Description	Symbol	ARROW BOARD DISPLAY
*	Trail Vehicle		
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
12. For divided highways with three or four lanes in each direction, use TCP(3-2).
13. Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
14. The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
15. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation | Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL
TCP(3-3)-14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-94 4-98 8-95 7-13 1-97 7-14	0002	19	010, ETC.	BI 10C, ETC.
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH, ETC.	35

DATE: 10/3/2023 5:36:48 PM
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/tcp3-4-13.dgn



TYPICAL TRAFFIC CONTROL FOR
CONTINUOUS LEFT TURN LANE SYMBOL MARKINGS



TYPICAL TRAFFIC CONTROL FOR
OUTSIDE DUAL LEFT TURN LANE SYMBOL MARKINGS



TYPICAL TRAFFIC CONTROL FOR
OUTSIDE LANE MARKINGS

TYPICAL TRAFFIC CONTROL FOR
INSIDE LANE MARKINGS



TYPICAL TRAFFIC CONTROL FOR
LEFT TURN LANE MARKINGS

TYPICAL TRAFFIC CONTROL FOR
CENTER LANE MARKINGS

LEGEND

*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow	■ ■ ■	Channelizing Devices

Posted Speed *	Formula	Minimum Desirable Taper Lengths ** 10' Offset	11' Offset	12' Offset	Suggested Maximum Spacing of Channelizing Devices On a Taper	On a Tangent	Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
30	$L=\frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L=WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only

** Taper lengths have been rounded off.
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. This traffic control plan is for use on conventional roads posted at 45 mph or less and is intended for mobile operations that move continuously or intermittently (stopping up to approximately 15 minutes) such as short-line striping and in-lane rumble strips. When activities are anticipated to take longer amounts of time or traffic conditions warrant, a short duration or short-term stationary traffic control plan should be used.

2. A Truck Mounted Attenuator shall be used on Shadow Vehicle. Striping on the back panel of all truck mounted attenuators shall be 8" red and white reflective sheeting placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental material specification DMS-8300, Type A.

3. All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.

4. The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the drivers side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.

5. Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C as per BC Standards. The arrow board operation shall be controlled from inside the truck.



STRIPING FOR TMA

Texas Department of Transportation

Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS FOR ISOLATED WORK AREAS UNDIVIDED HIGHWAYS

TCP(3-4)-13

FILE: tcp3-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT July, 2013	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		36



EDGE LINE AND LANE LINES ONE-WAY ROADWAY WITH OR WITHOUT SHOULDERS



TYPICAL TWO-LANE, TWO-WAY PAVEMENT MARKINGS THROUGH INTERSECTIONS

GENERAL NOTES

1. Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.

2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.





CENTERLINE AND LANE LINES FOUR LANE TWO-WAY ROADWAY WITH OR WITHOUT SHOULDERS

* 2" minimum for restripe projects when approved by the Engineer.

** 8" minimum for restripe projects when approved by the Engineer.



TYPICAL MULTI-LANE, TWO-WAY PAVEMENT MARKINGS THROUGH INTERSECTIONS



TWO LANE TWO-WAY ROADWAY WITH OR WITHOUT SHOULDERS



DETAIL "B"

* 2" minimum for restripe projects when approved by the Engineer.



For posted speed on road being marked equal to or greater than 45 MPH.

YIELD LINES



For posted speed on road being marked equal to or less than 40 MPH.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

GUIDE FOR PLACEMENT OF STOP LINES, EDGE LINE & CENTERLINE

Based on Traveled Way and Pavement Widths for Undivided Roadways



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES

1. Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections.
Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.

2. Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.

3. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

DATE: 2024/8/29
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002-19-010 ...

Texas Department of Transportation
Traffic Safety Division Standard

TYPICAL STANDARD PAVEMENT MARKINGS

PM(1)-22

FILE: pm1-22.dgn	DN:	CK:	DW:	CK:
©TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 11-78 8-00 6-20; 8-95 3-03 12-22; 5-00 2-12	0002	19	http://ww	BI 10-C
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH	37

22A

DATE: 2024/8/29
FILE: pw://txdot.projectwiseonline.com:TXDOTS/Documents/24 - ELP/Design Projects/...

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE



CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS



CENTERLINE & LANE LINES FOR FOUR LANE TWO-WAY ROADWAYS



DETAIL "A" DETAIL "B" DETAIL "C"



CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.

See Note 3.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS



6" EDGE LINE, 6" CENTERLINE OR 6" LANE LINE

REFLECTORIZED PROFILE PATTERN DETAIL

USING REFLECTIVE PROFILE PAVEMENT MARKINGS

A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

NOTES

1. Edge lines should typically be 6" wide and the materials shall be specified in the plans.
2. Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

GENERAL NOTES

1. All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
3. Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

Texas Department of Transportation

Traffic Safety Division Standard

POSITION GUIDANCE USING RAISED MARKERS RELECTORIZED PROFILE MARKINGS PM(2)-22

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-77 8-00 6-20 4-92 2-10 12-22 5-00 2-12	0002	19	http://ww	BI 10-C
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH	38

22B



LANE REDUCTION

NOTES

1. Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
2. On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
3. Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
4. For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.

ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	
45 MPH	775	L=WS
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

GENERAL NOTES

1. Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
2. When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
3. Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
4. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.



A two-way left-turn (TWLT) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.

TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE



TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A



DETAIL B

* 2" minimum allowed for restripe projects when approved by the Engineer.

Texas Department of Transportation

Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS

PM(3)-22

FILE: pm3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 4-98 3-03 6-20 5-00 2-10 12-22 8-00 2-12	0002	19	http://ww	BI 10-C
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH	39

22C

DATE: 2025/8/29
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/0002190...



NOTES

A1: Center of RR mast to center of rail: 12' minimum, 15' typical.

A2: Tip of gate to center of rail: 12' minimum, 15' typical.

B: Center of mast (cantilever, gate, or mast flasher) of nearest active traffic control device to stop line: 8' (NOTE: Stop line may be moved as needed, but should be at least 8' back from gates, if present).

C: Near edge of detectable warning surface to nearest rail: 12' minimum.

D: Center of gate mast to center of cantilever mast: 6' typical. NOTE: Cantilever may be located in front or behind gates.

E: Edge of median or curb to nearest rail: 10' typical. NOTE: Design median edge to be parallel with rail.

F: Edge of planking panel from edge of pavement or sidewalk: 3' minimum. NOTE: Field panels need not be in line with gauge panels.

G: Length of panels along rail: 8' typical.

H: Width of field panel: 2' typical (check with railroad company).

I: Distance between rails: 4'- 8'1/2".

J1: Tip of gate to tip of gate: 2' maximum.

J2: 90% of traveled roadway to be covered by gate.

K: Nearest edge of RR cabinet from edge of pavement: 30' typical. NOTE: Cabinet not required to be parallel to edge of pavement.

L: Nearest edge of RR cabinet from nearest rail: 25' typical.

M: Center of RR mast to edge of sidewalk: 6' minimum.

N: Center of gate mast to leading edge of non-traversable median: 100' minimum to qualify as a Quiet Zone SSM. NOTE: 60'will suffice if there is a street intersection within the 100' and all street intersections within 60' are closed.

O: Width of median for RR gate assembly: 8'-6" minimum, 10' typical when using median gates. NOTE: Center of gate mast minimum 4'-3" from face of curb.

P: Center of RR mast to face of curb: 5'-3" minimum. Center of RR mast to edge of pavement (with shoulder): 7' minimum. Center of RR mast to edge of pavement (no shoulder): 9'-3" minimum. NOTE: Final location determined by the railroad company.

Q: Gate length: 28' or less typical, but railroad company may allow up to 32' under special circumstances.

R: Stop line to first RR Crossing transverse line (bike lane): 50' typical.

S: Stop line to GRADE CROSSING ADVANCE WARNING (W10-1) sign and adjacent RR Crossing pavement markings. See Table 1. See RCD(2) for other signs.



TABLE 1	
Approach Speed (mph)	Desirable Placement (feet)
20	100
25	100
30	100
35	100
40	125
45	175
50	250
55	325
60	400
65	475
70	550
75	650

LEGEND	
	Sign
	Object Marker
	Traffic Flow
	Cantilever
	Gate Assembly
	Mast Flasher Pair

GENERAL NOTES

1. Medians and curbs must be non-traversable to qualify as a Quiet Zone Supplementary Safety Measure (SSM). Non-traversable curbs in Quiet Zones are 6" tall minimum and used on roadways where speed does not exceed 40 mph.
2. Raised pavement markers may be used to supplement striping. See PM(2) and PM(3) standard sheets.
3. Medians preferred whenever possible to prevent vehicles from driving around gates.
4. Longitudinal edge striping may be continued thru crossing as needed. Illumination may also be considered for nighttime visibility.
5. See SMD standard sheets for sign mounting details.
6. See the Standard Highway Sign Design for Texas (SHSD) manual for sign and pavement marking details.



NOTES

T: Tip of gate to edge of curb: 1' maximum for Quiet Zone SSM, 90% of traveled way covered by gates for all other locations.

U: Non-traversable curb length from gate: 100' minimum for a Quiet Zone SSM, 10' minimum for all other locations.



CROSSING SURFACE CROSS SECTION

Texas Department of Transportation

Traffic Safety Division Standard

RAILROAD CROSSING DETAILS SIGNING, STRIPING, AND DEVICE PLACEMENT RCD(1)-22

FILE: rcd1-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-16 11-22	0002	19	http://ww	BI 10-C
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH	40

DATE: 2024/8/29
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/...

PASSIVE CROSSING



NOTES

1. STOP or YIELD sign may also be installed to the left of the crossbuck sign, rather than below it.
2. A 2" white retroreflective strip shall be installed on front and back of crossbuck sign post.
3. See the Crossbuck Assemblies with YIELD or STOP Signs at Passive Grade Crossings section of the TMUTCD for further details about sign mounting arrangements.

PATHWAY CROSSING



NOTES

1. A shared use path is considered a separate pathway crossing when more than 25' from traveled way of adjacent roadway.
2. Detectable warning used at stop bar.
3. Smaller signs preferred. See the Design of Bicycle Signs section within the TMUTCD for sizing details.

TABLE 1	
Approach Speed (mph)	Desirable Placement (feet)
20	100
25	100
30	100
35	100
40	125
45	175
50	250
55	325
60	400
65	475
70	550
75	650

GENERAL NOTES

1. Railroad company to provide active traffic control devices, CROSSBUCK (R15-1), NUMBER OF TRACKS (R15-2P) plaque (if more than 1 track), and EMERGENCY NOTIFICATION (I-13) signs.
2. LOW GROUND CLEARANCE (W10-5) signs may be relocated further upstream of crossing to provide advance warning of alternate route.
3. GRADE CROSSING AND INTERSECTION ADVANCE WARNING (W10-2) signs may be modified as needed to fit roadway geometry.
4. Table 1 placement distances may vary per the Placement of Warning Signs section of the TMUTCD.
5. See Table 1 to determine placement of STOP AHEAD (W3-1) and YIELD AHEAD (W3-2) signs unless shown otherwise.
6. DO NOT STOP ON TRACKS (R8-8) signs installed when potential for vehicles stopping on tracks is significant as determined by sealing engineer. Install so sign does not block view of RR mast.
7. See the Standard Highway Sign Design for Texas (SHSD) manual for sign and pavement marking details.

GRADE CROSSING NEAR A PARALLEL STREET



NOTE

This design shows a four-way stop scenario only. Other signs may be substituted for traffic signal or other traffic control scenarios. This note also applies to T-Intersection design below.

	"A" <100'	"A" ≥100'
"B"	See Table 1. Place pavement markings and signs on opposite side of intersection from rail if spacing from Table 1 would put markings within intersection.	See Table 1. Place pavement markings and signs between rail and intersection if spacing from Table 1 would put markings within intersection.
"C"	See Table 1.	GRADE CROSSING AND INTERSECTION ADVANCE WARNING (W10-2, W10-3, W10-4) signs should only be installed if W10-1 sign is not between intersection and railroad crossing. If needed, see Table 1.

TWO-WAY



TWO-WAY WITH MEDIAN



ONE-WAY



SIGNS



** Includes a NO TRAIN HORN (W10-9P) plaque if crossing is in a Quiet Zone. If needed, is mounted below W10-2/W10-3/W10-4 signs.

NO TRAIN HORN W10-9P 30" X 24"

T-INTERSECTION



*Use Table 1 if sufficient space exists.

NOTE

Railroad crossing pavement markings and adjacent signs not included when distance between near edge of intersection and near rail is less than 100'. GRADE CROSSING AND INTERSECTION ADVANCE WARNING (W10-3) signs installed on roadway parallel with rail in this case.

TWO ADJACENT CROSSINGS



NOTE

Separate active traffic control devices, railroad crossing pavement markings, and adjacent signs required when tracks are more than 100' apart.

Texas Department of Transportation

Traffic Safety Division Standard

RAILROAD CROSSING DETAILS SIGNING & STRIPING

RCD(2)-22

FILE: rcd2-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS 2-16 11-22	0002	19	http://ww	BI 10-C
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH	41

15

DATE: 2023/8/29
FILE: pw://txdot.projectwiseonline.com:TXDOT5/Documents/24 - ELP/Design Projects/...

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):
CSJ: 0002-19-010, ETC.

1.2 PROJECT LIMITS:
From: 1.64 MI W OF RM 1111

To: 1.32 MI E OF RM 1111

1.3 PROJECT COORDINATES:
BEGIN: (Lat) 31.1809648 ,(Long) -105.3838342

END: (Lat) 31.1706844 ,(Long) -105.3406588

1.4 TOTAL PROJECT AREA (Acres): 1,013 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.00

1.6 NATURE OF CONSTRUCTION ACTIVITY:
SEAL COAT PREVENTIVE MAINTENANCE

1.7 MAJOR SOIL TYPES:

Soil Type	Description
N/A	N/A

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):
PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

☐ PSLs determined during preconstruction meeting
☐ PSLs determined during construction
☒ No PSLs planned for construction

Type	Sheet #s
N/A	N/A

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:
(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

✖ Mobilization
☐ Install sediment and erosion controls
☐ Blade existing topsoil into windrows, prep ROW, clear and grub
☐ Remove existing pavement
☐ Grading operations, excavation, and embankment
☐ Excavate and prepare subgrade for proposed pavement widening
☐ Remove existing culverts, safety end treatments (SETs)
☐ Remove existing metal beam guard fence (MBGF), bridge rail
☐ Install proposed pavement per plans
☐ Install culverts, culvert extensions, SETs
☐ Install mow strip, MBGF, bridge rail
☐ Place flex base
☐ Rework slopes, grade ditches
☐ Blade windrowed material back across slopes
☐ Revegetation of unpaved areas
☐ Achieve site stabilization and remove sediment and erosion control measures
☐ Other: _____
☐ Other: _____
☐ Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

☐ Sediment laden stormwater from stormwater conveyance over disturbed area
✖ Fuels, oils, and lubricants from construction vehicles, equipment, and storage
✖ Solvents, paints, adhesives, etc. from various construction activities
☐ Transported soils from offsite vehicle tracking
✖ Construction debris and waste from various construction activities
☐ Contaminated water from excavation or dewatering pump-out water
✖ Sanitary waste from onsite restroom facilities
✖ Trash from various construction activities/receptacles
☐ Long-term stockpiles of material and waste
☐ Other: _____
☐ Other: _____
☐ Other: _____

1.11 RECEIVING WATERS:
Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
N/A	N/A

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

☒ Development of plans and specifications
☒ Perform SWP3 inspections
☒ Maintain SWP3 records and update to reflect daily operations
☐ Other: _____
☐ Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

☒ Day To Day Operational Control
☒ Maintain schedule of major construction activities
☒ Install, maintain and modify BMPs
☐ Other: _____
☐ Other: _____
☐ Other: _____

STATE OF TEXAS
KARLA Y. RIOS
140855
LICENSED PROFESSIONAL ENGINEER

Karla Rios, P.E.
10/03/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

Sheet 1 of 2

Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
	STP( )		42
STATE	STATE DIST.	COUNTY	
TEXAS	ELP	HUDSPETH, ETC.	
CONT.	SECT.	JOB	HIGHWAY NO.
0002	19	010	BI 10C, ETC.

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- ✖ ☐ Protection of Existing Vegetation
- ☐ ☐ Vegetated Buffer Zones
- ☐ ☐ Soil Retention Blankets
- ☐ ☐ Geotextiles
- ☐ ☐ Mulching/ Hydromulching
- ☐ ☐ Soil Surface Treatments
- ☐ ☐ Temporary Seeding
- ☐ ☐ Permanent Planting, Sodding or Seeding
- ☐ ☐ Biodegradable Erosion Control Logs
- ☐ ☐ Rock Filter Dams/ Rock Check Dams
- ☐ ☐ Vertical Tracking
- ☐ ☐ Interceptor Swale
- ☐ ☐ Riprap
- ☐ ☐ Diversion Dike
- ☐ ☐ Temporary Pipe Slope Drain
- ☐ ☐ Embankment for Erosion Control
- ☐ ☐ Paved Flumes
- ☐ ☐ Other: _____
- ☐ ☐ Other: _____
- ☐ ☐ Other: _____
- ☐ ☐ Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- ☐ ☐ Biodegradable Erosion Control Logs
- ☐ ☐ Dewatering Controls
- ☐ ☐ Inlet Protection
- ☐ ☐ Rock Filter Dams/ Rock Check Dams
- ☐ ☐ Sandbag Berms
- ✖ ☐ Sediment Control Fence
- ☐ ☐ Stabilized Construction Exit
- ☐ ☐ Floating Turbidity Barrier
- ☐ ☐ Vegetated Buffer Zones
- ☐ ☐ Vegetated Filter Strips
- ☐ ☐ Other: _____
- ☐ ☐ Other: _____
- ☐ ☐ Other: _____
- ☐ ☐ Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To
N/A	N/A	N/A

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- ☐ Excess dirt/mud on road removed daily
- ☐ Haul roads dampened for dust control
- ☐ Loaded haul trucks to be covered with tarpaulin
- ☐ Stabilized construction exit
- ☐ Other: _____
- ☐ Other: _____
- ☐ Other: _____
- ☐ Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- ✖ Chemical Management
- ✖ Concrete and Materials Waste Management
- ✖ Debris and Trash Management
- ☐ Dust Control
- ✖ Sanitary Facilities
- ☐ Other: _____
- ☐ Other: _____
- ☐ Other: _____
- ☐ Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To
N/A	N/A	N/A

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- ☒ Fire hydrant flushings
- ☒ Irrigation drainage
- ☒ Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- ☒ Potable water sources
- ☒ Springs
- ☒ Uncontaminated groundwater
- ☒ Water used to wash vehicles or control dust
- ☒ Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

STATE OF TEXAS
KARLA Y. RIOS
140855
LICENSED
PROFESSIONAL ENGINEER

Karla Rios, P.E.

10/03/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
	STP( )		43
STATE	STATE DIST.	COUNTY	
TEXAS	ELP	HUDSPETH, ETC.	
CONT.	SECT.	JOB	HIGHWAY NO.
0002	19	010	BI 10C, ETC.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA.SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.



SECTION A-A

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT^2. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.

LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING

Texas Department of Transportation
Design Division Standard

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

FENCE & VERTICAL TRACKING

EC(1)-16

FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0002	19	010, ETC.	BI 10C, ETC.
	DIST		COUNTY	SHEET NO.
	ELP		HUDSPETH, ETC.	44

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

☑ This project is adjacent or parallel work, not within RR ROW:

DOT No.: 764092A
Crossing Type: RR OVER
RR Company Operating Track at Crossing: UNION PACIFIC
RR Company Owning Track at Crossing: UNION PACIFIC
RR MP: 736.39
RR Subdivision: VALENTINE
City: SIERRA BLANCA
County: HUDSPETH
CSJ at this Crossing: 0002-19-010

Scope of Work, including any TCP, to be performed by State Contractor:

ONE COURSE SURFACE TREATMENT (SEAL COAT) AS PART OF A PREVENTIVE MAINTENANCE.

Scope of Work to be performed by Railroad Company:

N/A

II. FLAGGING & INSPECTION

No. of Days of Railroad Flagging Expected: 1

On this project, night or weekend flagging is:

☑ Expected
☐ Not Expected

Flagging services will be provided by:

☐ Railroad Company: TxDOT will pay flagging invoices. Flagging Agreement with Railroad will be needed
☑ Outside Party: Contractor will pay flagging invoices to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30-day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

☑ **UPRR** UP.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
UP.request@nrssinc.net
Call Center 877-984-677

☐ **BNSF** BNSFinfo@railprosfs.com
Call Center 877-315-0513, Select #1 for flagging

☐ **KCS** KCS.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
Bottom Line On-Track Safety Services
bottomline076@aol.com, 903-767-7630

☐ OTHERS:

Contractor must incorporate Construction Inspection into anticipated construction schedule.

☑ Not Required
☐ Required. Contact Information for Construction Inspection:

III. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

☐ Required. Railroad Point of Contact: _____
☑ Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

IV. RAILROAD INSURANCE REQUIREMENTS

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies and corresponding certificates of insurance must be issued by the contractor on behalf of the Railroad. Separate insurance policies and certificates are required when more than one Railroad Company is operating on the same right of way, or when several Railroad Companies are involved and operate on their own separate right of ways.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Escalated Limits

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	$500,000 / $500,000 / $500,000
Commercial General Liability	$2,000,000 / $4,000,000
Business Automobile	$2,000,000

Railroad Protective Liability Limits

☐ Not Required	
☑ Non - Bridge/Typical Maintenance Projects. Includes repairs to overpass/underpass and culvert structures	$2,000,000 / $6,000,000
☐ Bridge Structure Projects. Includes new construction or replacement of overpass/ underpass structures	$5,000,000 / $10,000,000
☐ Other: _____	

V. CONTRACTOR'S RIGHT OF ENTRY (CROE)

☐ Not Required
☑ Required: UPRR Maintenance Consent Letter. TxDOT to assist
☐ Required: TxDOT to assist in obtaining the UPRR CROE
☐ Required: Contractor to obtain
  ☐ BNSF: _____
  https://bnsf.railpermitting.com
  ☐ KCS
  https://jllrpg.360works.com/fmi/webd/rpo_web_kcs.fmp12
  ☐ Other Railroads: _____

To view previously approved CROE templates agreed upon between the State and Railroad, see: https://www.txdot.gov/business/resources/railroad-highway-crossing/sample-right-of-entry-agreements.html

Approved CROE templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed CROE between the Contractor and the Railroad if required on project.

VI. RAILROAD COORDINATION MEETING

A Railroad Coordination Meeting is required. See item 5, Article 8.1, of the Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges Manual for more details.

VII. RAILROAD SAFETY ORIENTATION

A. Complete the Railroad's course "Orientation for Contractor's Safety," and maintain registration prior to working on the Railroad's property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other Railroads. Refer to each Railroad's specific contractor right of entry for training information.

Know and follow the Contractor's Right of Entry Agreement EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are subject to the same insurance requirements as the Prime Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call: UNION PACIFIC RAILROAD COMPANY
Railroad Emergency Line at: 800-848-8715
Location: DOT 764092A
RR Milepost: 736.39
Subdivision: VALENTINE

RRD Review Only
Initials: JLL
Date: 11/1/2023

Texas Department of Transportation | Rail Division

RAILROAD SCOPE OF WORK
PROJECT SPECIFIC DETAILS

FILE: rr-scope-of-work.pdf	DN: TxDOT	CK:	DW:	CK:	
© TxDOT June 2014	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0002	19	010, ETC	BI 10C, ETC	
3/2023	DIST	COUNTY		SHEET NO.	
	ELP	HUDSPETH, ETC		45	

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

☑ This project is adjacent or parallel work, not within RR ROW:

DOT No.: 764091T
Crossing Type: AT GRADE
RR Company Operating Track at Crossing: UNION PACIFIC
RR Company Owning Track at Crossing: UNION PACIFIC
RR MP: 736.92
RR Subdivision: VALENTINE SUB
City: VAN HORN
County: HUDSPETH
CSJ at this Crossing: 1282-02-028

Scope of Work, including any TCP, to be performed by State Contractor:

ONE COURSE SURFACE TREATMENT (SEAL COAT) AS PART OF A PREVENTIVE MAINTENANCE.

Scope of Work to be performed by Railroad Company:

N/A

II. FLAGGING & INSPECTION

No. of Days of Railroad Flagging Expected: 1

On this project, night or weekend flagging is:

☑ Expected
☐ Not Expected

Flagging services will be provided by:

☐ Railroad Company: TxDOT will pay flagging invoices. Flagging Agreement with Railroad will be needed
☑ Outside Party: Contractor will pay flagging invoices to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30-day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

☑ **UPRR** UP.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
UP.request@nrssinc.net
Call Center 877-984-677

☐ **BNSF** BNSFinfo@railprosfs.com
Call Center 877-315-0513, Select #1 for flagging

☐ **KCS** KCS.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
Bottom Line On-Track Safety Services
bottomline076@aol.com, 903-767-7630

☐ OTHERS:

Contractor must incorporate Construction Inspection into anticipated construction schedule.

☑ Not Required
☐ Required. Contact Information for Construction Inspection:

III. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

☐ Required. Railroad Point of Contact: _____
☑ Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

IV. RAILROAD INSURANCE REQUIREMENTS

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies and corresponding certificates of insurance must be issued by the contractor on behalf of the Railroad. Separate insurance policies and certificates are required when more than one Railroad Company is operating on the same right of way, or when several Railroad Companies are involved and operate on their own separate right of ways.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Escalated Limits

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	$500,000 / $500,000 / $500,000
Commercial General Liability	$2,000,000 / $4,000,000
Business Automobile	$2,000,000

Railroad Protective Liability Limits

☐ Not Required	
☑ Non - Bridge/Typical Maintenance Projects. Includes repairs to overpass/underpass and culvert structures	$2,000,000 / $6,000,000
☐ Bridge Structure Projects. Includes new construction or replacement of overpass/ underpass structures	$5,000,000 / $10,000,000
☐ Other: _____	

V. CONTRACTOR'S RIGHT OF ENTRY (CROE)

☐ Not Required
☑ Required: UPRR Maintenance Consent Letter. TxDOT to assist
☐ Required: TxDOT to assist in obtaining the UPRR CROE
☐ Required: Contractor to obtain
- ☐ BNSF: _____
  https://bnsf.railpermitting.com
- ☐ KCS
  https://jllrpg.360works.com/fmi/webd/rpo_web_kcs.fmp12
- ☐ Other Railroads: _____

To view previously approved CROE templates agreed upon between the State and Railroad, see: https://www.txdot.gov/business/resources/railroad-highway-crossing/sample-right-of-entry-agreements.html

Approved CROE templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed CROE between the Contractor and the Railroad if required on project.

VI. RAILROAD COORDINATION MEETING

A Railroad Coordination Meeting is required. See item 5, Article 8.1, of the Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges Manual for more details.

VII. RAILROAD SAFETY ORIENTATION

A. Complete the Railroad's course "Orientation for Contractor's Safety," and maintain registration prior to working on the Railroad's property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other Railroads. Refer to each Railroad's specific contractor right of entry for training information.

Know and follow the Contractor's Right of Entry Agreement EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are subject to the same insurance requirements as the Prime Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call: UNION PACIFIC RAILROAD COMPANY
Railroad Emergency Line at: 800-848-8715
Location: DOT 764091T
RR Milepost: 736.92
Subdivision: VALENTINE SUB

RRD Review Only
Initials: JLL
Date: 11/7/2023

Texas Department of Transportation | Rail Division

RAILROAD SCOPE OF WORK
PROJECT SPECIFIC DETAILS

FILE: rr-scope-of-work.pdf	DN: TxDOT	CK:	DW:	CK:		
© TxDOT June 2014	CONT	SECT	JOB	HIGHWAY		
REVISIONS	0002	19	010, ETC	BI 10C, ETC		
3/2023	DIST	COUNTY		SHEET NO.		
	ELP	HUDSPETH, ETC		46		

I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)

☑ This project is adjacent or parallel work, not within RR ROW:

DOT No.: 796208M
Crossing Type: AT GRADE
RR Company Operating Track at Crossing: UNION PACIFIC
RR Company Owning Track at Crossing: UNION PACIFIC
RR MP: 735.2
RR Subdivision: TOYAH
City: VAN HORN
County: CULBERSON
CSJ at this Crossing: 0233-05-036

Scope of Work, including any TCP, to be performed by State Contractor:

ONE COURSE SURFACE TREATMENT (SEAL COAT) AS PART OF A PREVENTIVE MAINTENANCE.

Scope of Work to be performed by Railroad Company:

N/A

II. FLAGGING & INSPECTION

No. of Days of Railroad Flagging Expected: 1

On this project, night or weekend flagging is:

☑ Expected
☐ Not Expected

Flagging services will be provided by:

☐ Railroad Company: TxDOT will pay flagging invoices. Flagging Agreement with Railroad will be needed
☑ Outside Party: Contractor will pay flagging invoices to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30-day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

☑ **UPRR** UP.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
UP.request@nrssinc.net
Call Center 877-984-677

☐ **BNSF** BNSFinfo@railprosfs.com
Call Center 877-315-0513, Select #1 for flagging

☐ **KCS** KCS.info@railpros.com
Call Center 877-315-0513, Select #1 for flagging
Bottom Line On-Track Safety Services
bottomline076@aol.com, 903-767-7630

☐ OTHERS:

Contractor must incorporate Construction Inspection into anticipated construction schedule.

☑ Not Required
☐ Required. Contact Information for Construction Inspection:

III. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD

☐ Required. Railroad Point of Contact: _____
☑ Not Required

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

IV. RAILROAD INSURANCE REQUIREMENTS

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies and corresponding certificates of insurance must be issued by the contractor on behalf of the Railroad. Separate insurance policies and certificates are required when more than one Railroad Company is operating on the same right of way, or when several Railroad Companies are involved and operate on their own separate right of ways.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Escalated Limits

Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	$500,000 / $500,000 / $500,000
Commercial General Liability	$2,000,000 / $4,000,000
Business Automobile	$2,000,000

Railroad Protective Liability Limits

☐ Not Required	
☑ Non - Bridge/Typical Maintenance Projects. Includes repairs to overpass/underpass and culvert structures	$2,000,000 / $6,000,000
☐ Bridge Structure Projects. Includes new construction or replacement of overpass/ underpass structures	$5,000,000 / $10,000,000
☐ Other: _____	

V. CONTRACTOR'S RIGHT OF ENTRY (CROE)

☐ Not Required
☑ Required: UPRR Maintenance Consent Letter. TxDOT to assist
☐ Required: TxDOT to assist in obtaining the UPRR CROE
☐ Required: Contractor to obtain
- ☐ BNSF: _____
  https://bnsf.railpermitting.com
- ☐ KCS
  https://jllrpg.360works.com/fmi/webd/rpo_web_kcs.fmp12
- ☐ Other Railroads: _____

To view previously approved CROE templates agreed upon between the State and Railroad, see: https://www.txdot.gov/business/resources/railroad-highway-crossing/sample-right-of-entry-agreements.html

Approved CROE templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed CROE between the Contractor and the Railroad if required on project.

VI. RAILROAD COORDINATION MEETING

A Railroad Coordination Meeting is required. See item 5, Article 8.1, of the Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges Manual for more details.

VII. RAILROAD SAFETY ORIENTATION

A. Complete the Railroad's course "Orientation for Contractor's Safety," and maintain registration prior to working on the Railroad's property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other Railroads. Refer to each Railroad's specific contractor right of entry for training information.

Know and follow the Contractor's Right of Entry Agreement EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

VIII. SUBCONTRACTORS

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are subject to the same insurance requirements as the Prime Contractor.

IX. EMERGENCY NOTIFICATION

In Case of Railroad Emergency
Call: UNION PACIFIC RAILROAD COMPANY
Railroad Emergency Line at: 800-848-8715
Location: DOT 796208M
RR Milepost: 735.2
Subdivision: TOYAH

RRD Review Only
Initials: JLL
Date: 11/7/2023

Texas Department of Transportation — Rail Division

RAILROAD SCOPE OF WORK
PROJECT SPECIFIC DETAILS

FILE: rr-scope-of-work.pdf		DN: TxDOT	CK:	DW:		CK:	
© TxDOT June 2014		CONT	SECT	JOB		HIGHWAY	
REVISIONS		0002	19	010, ETC		BI 10C, ETC	
3/2023		DIST	COUNTY			SHEET NO.	
		ELP	HUDSPETH, ETC			47	

PART 1 - GENERAL

1.01 DESCRIPTION

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

1.02 REQUEST FOR INFORMATION / CLARIFICATION

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

1.03 PLANS / SPECIFICATIONS

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

PART 2 - UTILITIES AND FIBER OPTIC

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

PART 3 - CONSTRUCTION

3.01 GENERAL

A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.

B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.

C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.

D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.

E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.

F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.

G. All permanent clearances shall be verified before project closing.

3.02 RAILROAD OPERATIONS

A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.

B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.

C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:

1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.

2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES

A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.

B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.

C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.

D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
1. Exactly what the work entails.
2. The days and hours that work will be performed.
3. The exact location of work, and proximity to the tracks.
4. The type of window requested and the amount of time requested.
5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.

E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

3.04 INSURANCE

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

3.05 RAILROAD SAFETY ORIENTATION

A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."

B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

3.06 COOPERATION

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES

Abide by the following minimum temporary clearances during the course of construction:
A. 15' - 0" (BNSF)(UPRR)and 14'-0" (KCS) horizontal from centerline of track
B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

3.08 APPROVAL OF REDUCED CLEARANCES

A. Maintain minimum track clearances during construction as specified in Section 3.07.

B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.

C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

Texas Department of Transportation | Rail Division

RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

REVISIONS
March 2020

FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
	CONT	SECT	JOB	HIGHWAY
	0002	19	010, ETC.	BI 10C, ETC.
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		48

3.09 MAINTENANCE OF RAILROAD FACILITIES

A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.

B. Perform all such maintenance and repair of damages due to the Contractors's operations at Contractor's expense.

C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

3.10 SITE INSPECTIONS BY RAILROAD's DESIGNATED REPRESENTATIVE

A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
1. Pre-construction meetings.
2. Pile driving/drilling of caissons or drilled shafts.
3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
4. Erection of precast concrete or steel bridge superstructure.
5. Placement of waterproofing (prior to placing ballast on bridge deck).
6. Completion of the bridge structure.

B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.

C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

3.11 RAILROAD REPRESENTATIVES

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.

B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.

C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.

D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.

E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

3.12 COMMUNICATIONS AND SIGNAL LINES

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

3.13 TRAFFIC CONTROL

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK

A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".

B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193
7:00 AM to 9:00 PM CST Monday-Friday except holidays,
staffed 24 hrs/day for emergencies
48 hrs notice required

BNSF 1-800-533-2891
24 hour number
5 working days notice required

KCS 1-800-344-8377
Texas One Call, a 24 hour number
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

3.15 RAILROAD FLAGGING

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

3.16 CLEANING OF RIGHT-OF-WAY

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

Texas Department of Transportation | Rail Division

RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT October 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS March 2020	0002	19	010, ETC.	BI 10C, ETC.
	DIST	COUNTY		SHEET NO.
	ELP	HUDSPETH, ETC.		49