

STATE PROJECT NO.			
C 710-02-071			
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		1

DESIGN CRITERIA = PM
 A.D.T (2021)= 10,578
 A.D.T (2041)= 14,809

FINAL PLANS

LETTING DATE: _____
 DATE CONTRACTOR BEGAN WORK: _____
 DATE WORK WAS COMPLETED & ACCEPTED: _____
 FINAL CONTRACT COST: \$ _____
 CONTRACTOR : _____

**STATE OF TEXAS
 DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED
 STATE HIGHWAY IMPROVEMENT**

STATE AID PROJECT NO. C 710-02-71

**FM 105
 ORANGE COUNTY
 CSJ: 0710-02-071**

NET LENGTH OF ROADWAY= 16,725 FT.= 3.167 MI.
 NET LENGTH OF BRIDGE = 0 FT.= 0 MI.
 NET LENGTH OF PROJECT = 16,725 FT.= 3.167 MI.

LIMITS: FROM FM 2802 SOUTH TO FM 1131


FOR THE CONSTRUCTION OF AN OVERLAY PROJECT

CONSISTING OF BASE REPAIR AND OVERLAY

BEGIN PROJECT

CSJ: 0710-02-071
 STA: 518+00
 REF MRK: 434+0.643

END PROJECT
 CSJ: 0710-02-071
 STA: 685+25
 REF MRK: 436+1.800



N. T. S

EXCEPTIONS: NONE
 EQUATIONS: NONE
 RAILROAD CROSSINGS: NONE

©2023
 BY TEXAS DEPARTMENT OF TRANSPORTATION
 ALL RIGHTS RESERVED.



SUBMITTED FOR LETTING: 9/21/2023
 DocuSigned by:
 [Signature]
 50238C8D55P5476... DISTRICT DESIGN ENGINEER

RECOMMENDED FOR LETTING: 9/21/2023
 DocuSigned by:
 Lisa Collins
 506370F3P0246... DISTRICT DIRECTOR OF TRANSPORTATION
 PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 9/22/2023
 DocuSigned by:
 Martin W. Gorb, P.E.
 578CD7495060440... DISTRICT ENGINEER

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH
 BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS
 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF
 TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION
 ITEMS LISTED AND DATED AS FOLLOWS. SHALL GOVERN ON
 THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS FOR
 ALL STATE CONSTRUCTION PROJECTS. (SP000--008)

INDEX OF SHEETS

SHEET NO. DESCRIPTION

SEE SHEET 2 FOR INDEX OF SHEETS

DATE: 9/14/2023 10:45:22 PM
 FILE: c:\tdot\pw_online\tdot5\pwwonline_richard.pastorella\0979174\Title_Sheet.dgn

INDEX OF SHEETS

GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3-4 TYPICAL SECTIONS
- 5-8 GENERAL NOTES
- 9-10 ESTIMATE & QUANTITY
- 11-12 QUANTITY SUMMARY

ENVIRONMENTAL ISSUES

- ## 78 SW3P-B
- 79-80 STORMWATER POLLUTION PREVENTION PLAN (SW3P)
- ## 81-83 EC(9)-16
- 84 EPIC

TRAFFIC CONTROL PLAN


- 13 SEQUENCE OF WORK
- ## 14-25 BC(1)-21 THRU BC(12)-21
- ## 26 TCP (2-4) - 18
- ## 27 TCP (3-1) - 13
- ## 28 TCP (3-3) - 14
- ## 29 TCP (3-4) - 13
- ## 30 WZ(RS) - 22
- ## 31 WZ(UL) - 13
- ## 32 WZ(STPM)-23

ROADWAY DETAILS

- 33-40 ROADWAY LAYOUT
- 41 HOT MIX LONGITUDINAL AND PAVEMENT EDGE JOINT DETAILS
- 42 TAPER DETAILS
- 43 TREATMENT FOR VARIOUS EDGE CONDITIONS
- ## 44 TE(HMAC)-11
- 45 DRIVEWAY & PUBLIC ROAD DETAILS
- 46-49 DRIVEWAY & PUBLIC ROAD SUMMARY
- ## 50 RS (2)-23

TRAFFIC DETAILS

- 51-58 PAVEMENT MARKING & SIGN LAYOUT
- 59-60 SUMMARY OF SMALL SIGNS
- 61-62 SIGN DETAILS
- ## 63 PM(1)-22
- ## 64 PM(2)-22
- ## 65 PM(3)-22
- ## 66 SMD(GEN)-08
- ## 67 SMD(SLIP-1)-08
- ## 68 SMD(SLIP-2)-08
- ## 69 SMD(SLIP-3)-08
- ## 70 TSR(3)-13
- ## 71 TSR(4)-13
- ## 72-75 MB(1)-21 THRU MB(4)-21
- ## 76-77 MBP(1)-22 THRU MBP(2)-22



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A "##" HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.


J. Horne 09/21/2023
 _____ DATE
 NAME

INDEX OF SHEETS




FHWA TEXAS DIVISION		SHEET NO. 2	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	ORANGE	
CONTROL	SECTION	JOB	HIGHWAY NO.
0710	02	071	FM 105

Ck:
Dw:
Ck:
Dw:



EXIST TYPICAL SECTION

STA. 518+00 - 535+61




PROP TYPICAL SECTION

STA. 518+27 - 535+61

PROP. 4' WIDE 1" DEEP MILL TO REMOVE RUMBLE STRIPS
PROP. FILL DG-HMA, TYPE D, PG 64-22

PROP. 4' WIDE 1" DEEP MILL TO REMOVE RUMBLE STRIPS
PROP. FILL DG-HMA, TYPE D, PG 64-22




J. Horne

09/18/2023

FM 105 TYPICAL SECTIONS

N. T. S


SHEET 1 OF 2




CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		3

DATE: 9/12/2023 3:21:00 PM
FILE: c:\ttdot\pw_online\ttdot5\koyloa_russ\d0979161\Typical Sections.dgn

DATE: 9/12/2023 3:22:13 PM
 FILE: c:\t\dot\p_w_online\t\dot5\koy\o_russ\d0979161\Typical Sections.dgn




EXIST TYPICAL SECTION
 STA. 535+61 - 685+25



PROP. 4' WIDE 1" DEEP MILL TO REMOVE RUMBLE STRIPS
 PROP. FILL DG-HMA, TYPE D, PG 64-22

PROP TYPICAL SECTION
 STA. 535+61 - 685+25

PROP. 4' WIDE 1" DEEP MILL TO REMOVE RUMBLE STRIPS
 PROP. FILL DG-HMA, TYPE D, PG 64-22




J. Horne
 09/18/2023

FM 105
TYPICAL SECTIONS

N. T. S

SHEET 2 OF 2



CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		4

GENERAL NOTES:

Contractor questions on this project are to be addressed to the following individual(s):

Bryce Broussard, P.E. (Bryce.Broussard@txdot.gov)

Jim Grissom, P.E. (Jim.Grissom@txdot.gov)

Contractor questions will be accepted through email, phone and in person by the above individuals.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

NOTICE

Maintain adequate drainage throughout the limits of the project during all construction phases. Provide a weekly a list of equipment, including idle equipment, used on the project each week.

Item 000 Utilities

Consider the locations of overhead utilities depicted on the plans as approximate and employ responsible care to avoid damaging or accommodate utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of overhead facilities. If utility damage (breaks, leaks, nicks, dents, gouges, etc.) occurs, contact the utility facility owner or operator immediately. In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others.

Item 4 Scope of Work

Remove all vegetation from pavement edges, intersections and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

It is the contractor's responsibility to field verify all drainage structure's shown in the plans.

It is the contractor's responsibility to mark the location of all existing striping and place proposed striping back in the same location or as shown in the plans.

Item 5 Control of the Work

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

Verify all horizontal and vertical control, approach grades to structures and driveways before beginning work. Notify the Engineer immediately if discrepancies are discovered.

Furnish, to the Engineer, a list of the final centerline elevations based on the alignment stationing shown on the plans.

Item 6 Control of Materials

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

Mixing of materials, storing of materials, storing of equipment, or repairing of equipment on top of concrete pavement or bridge decks will not be permitted unless specifically authorized.

Item 7 Legal Relations and Responsibilities

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Always maintain ingress and egress to the adjacent property. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

No significant traffic generator events have been identified in the project limits.

Item 8 Prosecution and Progress

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Maintain one lane in each direction open to traffic during construction, unless otherwise approved.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

Submit monthly progress schedules in accordance with Section 8.5.5.2.3., "Progress Schedule." Failure to supply updated project schedule may result in the Engineer withholding progress (monthly) payments.

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

Working days will be charged during the observed curing times, even if no other work is being performed.

Where road closures or detours around structures are necessary to accomplish proposed work, the removal of existing structures and/or cutting of existing pavement will not be permitted until all pre-cast members for the proposed structure have been cast, tested and approved for use.

HURRICANE

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

Item 134 Backfilling Pavement Edges

Embankment quantity by station includes both sides of the roadway. No deduction in payment will be made when in the opinion of the Engineer only one side of a roadbed section requires backfilling.

Item 168 Vegetative Watering

Equip water trucks with sprinkler systems capable of covering the entire area to be seeded or sodded from the roadway.

Water all newly placed sod or seeded areas the same day of installation. Thereafter, maintain the sod or seeded areas in a well-watered condition and at no time allow the areas to dry to the condition that water stress is evident.

Mechanical watering may not be required during periods of adequate moisture as determined.

Furnish and apply water at a rate of 6.788 Mega gallons per acre per cycle or as directed on the plans.

Comply with stabilization requirements for 70% grass coverage; uniform vegetative coverage is required. During this period, meter and operate water equipment under pumping pressure capable of delivering the required quantities of water necessary. For Permanent seeding each cycle will be executed weekly for 12 weeks, unless directed otherwise. For Temporary seeding each cycle will be executed weekly for 6 weeks, unless directed otherwise.

Provide a log book showing daily water usage and receipts of water applied, in addition to metering the water equipment.

Item 351 Flexible Pavement Structure Repair

The repair areas will require full depth saw-cut when milling is not used. Consider this work to be subsidiary to the various bid items of the contract.

Provide Flexible Pavement Repair with material meeting the requirements of Item 3076, Type B (PG 64-22) unless approved otherwise. Place Hot Mix with a constant longitudinal surface grade and tie in flush with the existing surface at each end and both sides of the repair area.

Unless otherwise directed, place new DG-HMA with maximum 5" lifts. The minimum patch sizes will be 6' in width and 10' in length.

Match the existing cross slope in the repair areas, unless directed otherwise.

All repair locations must be filled the same day they are excavated. No open cut areas will be allowed overnight.

All excavated materials will be removed from the project daily.

Ordinary compaction will be used on this project.

Station limits may be adjusted as directed to meet varying field conditions

For repair locations located in areas to be planed, perform flexible pavement repairs after planing operations.

Seal the perimeter of the repair areas with hot poured rubber in accordance with Item 712. Consider this work to be subsidiary to the various bid items of the contract.

Item 354 Planing and Texturing Pavement

Where the underlying flexible base is exposed during the planing operation, prime this area with an asphalt at a rate as directed and patch with an approved HMA material, at the end of the day’s operation in which it occurs. These items of work will not be paid for directly but will be subsidiary to Item 354.

Schedule the work so that a HMA is placed no more than two weeks after milling has been performed on any pavement surface, unless otherwise approved. The Engineer may require the seal coat to be placed sooner than two weeks in cases when base materials are exposed or when the pavement structure is showing signs of distress.

If the Engineer determines an adjacent driveway needs to be tapered back to prevent a drop-off an additional pass will need to be made to taper the driveway as directed or for a distance of 24” into the driveway. This work will be measured and paid for under Item 354.

Cut and/or remove raised concrete repair areas, concrete curb, exposed rebar, etc. flush with the concrete pavement surface. This work will not be paid for directly but will be subsidiary to Item 354

Item 502 Barricades, Signs, and Traffic Handling

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

<u>Square Feet</u>	<u>Minimum Thickness</u>
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506 Temporary Erosion, Sedimentation, and Environmental Controls

The Contractor Force Account “SW3P Contingency” that has been established for this project is intended to be used in the event that controls, other than what is shown in the plans, become necessary. The SW3P for this project will consist of the use of any temporary erosion control

measures deemed necessary and as specified under this Item. This work will be paid for in accordance with Article 4.4., "Changes in the Work.

Item 530 Intersections, Driveways, and Turnouts

Use material meeting the requirements of Item 3076, Type D, PG 64-22 for Item 530.

Item 585 Ride Quality for Pavement Surfaces

Use Surface Test Type B pay adjustment 2 to evaluate ride quality of the travel lanes in accordance with this item.

Item 666 Retroreflectorized Pavement Markings

Furnish Type II drop-on glass beads.

Item 672 Raised Pavement Markers

Remove all existing traffic buttons before the application of the overlay. Consider this work to be subsidiary to the various bid items of the contract. Location and details of the existing buttons are available at the Area Engineer 's office.

Item 3076 Dense graded Hot Mix Asphalt and Item 3077 Superpave Mixtures

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor’s testing equipment. The contractor will provide the SGC” Superpave Gyrotory Compactor” and TGC “Texas Gyrotory Compactor”. All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., “Electrical Requirements.”

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68°F through 72°F).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

1. A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
2. Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
3. Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
4. An operational telephone system.
5. Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
6. Water (for testing purposes) from an approved source
7. Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.
8. A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment
9. A laboratory sink measuring 24 × 30 in. and 12 in. deep
10. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.
11. Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes. RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements. Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

A material transfer device (MTD) will be required for all surface courses of HMA on this project. An MTD is defined as a self-propelled, wheel-mounted vehicle capable of receiving HMA from the haul trucks separate from the paver. The MTD will have a minimum storage capacity of approximately 25 tons and will be equipped with a pivoting discharge conveyor and a means of completely remixing the HMA before placement. The Engineer may approve an alternative device on a trial basis for the surface course. This device will be capable of receiving HMA separate from the paver and must have remixing capabilities. For all other courses of HMA, other than the surface, an alternative device may be used as long as it is capable of receiving HMA separate from the paver.

Item 6185

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMA's for mobile operations.

Therefore, 3 total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.



CONTROLLING PROJECT ID 0710-02-071

DISTRICT Beaumont
HIGHWAY FM 105

Estimate & Quantity Sheet

COUNTY Orange

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	134-6004	BACKFILL (TY A OR B)	STA	167.000	
	164-6003	BROADCAST SEED (PERM) (RURAL) (CLAY)	SY	18,552.000	
	164-6009	BROADCAST SEED (TEMP) (WARM)	SY	9,276.000	
	164-6011	BROADCAST SEED (TEMP) (COOL)	SY	9,276.000	
	168-6001	VEGETATIVE WATERING	MG	156.000	
	351-6006	FLEXIBLE PAVEMENT STRUCTURE REPAIR(10")	SY	3,043.000	
	354-6021	PLANE ASPH CONC PAV(0" TO 2")	SY	1,822.000	
	354-6043	PLANE ASPH CONC PAV (1")	SY	22,263.000	
	500-6001	MOBILIZATION	LS	1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	6.000	
	506-6041	BIODEG EROSN CONT LOGS (IN STL) (12")	LF	1,000.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,000.000	
	530-6011	INTRSCT, DRVWAYS, & TURNOUT (ACP)	SY	4,657.000	
	533-6001	RUMBLE STRIPS (SHOULDER)	LF	33,394.000	
	560-6011	MAILBOX INSTALL-S (TWW-POST) TY 4	EA	68.000	
	560-6012	MAILBOX INSTALL-D (TWW-POST) TY 4	EA	2.000	
	560-6013	MAILBOX INSTALL-M (TWW-POST) TY 4	EA	13.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	45.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	3.000	
	644-6007	IN SM RD SN SUP&AM TY10BWG(1)SA(U)	EA	1.000	
	644-6017	IN SM RD SN SUP&AM TY10BWG(2)SA(P)	EA	1.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	50.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	2,540.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	4,210.000	
	666-6029	REFL PAV MRK TY I (W)8"(DOT)(090MIL)	LF	143.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	172.000	
	666-6289	REF PROF PAV MRK TY I(Y)6"(SLD)(090MIL)	LF	40,742.000	
	666-6293	REF PROF PAV MRK TY I(Y)6"(BRK)(090MIL)	LF	9,920.000	
	666-6305	RE PM W/RET REQ TY I (W)6"(BRK)(090MIL)	LF	8,090.000	
	666-6308	RE PM W/RET REQ TY I (W)6"(SLD)(090MIL)	LF	35,702.000	
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	294.000	
	668-6077	PREFAB PAV MRK TY C (W) (ARROW)	EA	2.000	
	668-6085	PREFAB PAV MRK TY C (W) (WORD)	EA	5.000	
	672-6007	REFL PAV MRKR TY I-C	EA	406.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	1,355.000	
	3076-6066	TACK COAT	GAL	1,336.000	
	3076-6071	D-GR HMA TY-D PG 64-22 (EXEMPT)	TON	1,260.000	
	3077-6033	SP MIXESSP-CSAC-A PG76-22	TON	17,190.000	
	3077-6075	TACK COAT	GAL	15,213.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000	
	6185-6002	TMA (STATIONARY)	DAY	72.000	

DISTRICT	COUNTY	CCSJ	SHEET
Beaumont	Orange	0710-02-071	9



CONTROLLING PROJECT ID 0710-02-071

DISTRICT Beaumont
HIGHWAY FM 105

COUNTY Orange

Estimate & Quantity Sheet

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	6185-6005	TMA (MOBILE OPERATION)	DAY	18.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000	

BASIS OF ESTIMATE

ITEM	DESCRIPTION	RATE	# OF UNITS	UNIT	QUANTITY	UNIT
168-6001	VEGETATIVE WATER	1.4GAL/SY/CYCLE	18552	SY	156	MG
3076-6071	D-GR HMA TY-D PG64-22 (EXEMPT)	113LBS/SY*IN	22263	SY	1260	TON
3076-6066	TACK COAT	0.06 GAL /SY	22263	SY	1336	GAL
3077-6033	SP MIXES SP-C SAC-A PG76-22	113 LBS/SY*IN	152128	SY	17190	TON
3077-6075	TACK COAT	0.1 GAL /SY	152128	SY	15213	GAL

ROADWAY ITEMS

	134	164			168*	351	354	
	6004	6003	6009	6011	6001	6006	6021	6043
	BACKFILL (TY A OR TY B)	BROADCAST SEED (PERM) (RURAL) (CLAY)	BROADCAST SEED (TEMP) (WARM)	BROADCAST SEED (TEMP) (COOL)	VEGETATIVE WATER	FLEXIBLE PAVEMENT STRUCTURE REPAIR (10")	PLANE ASPH CONC PAV (0" TO 2")	PLANE ASPH CONC PAV (1")
UNIT OF MEASURE	STA	SY	SY	SY	SY	SY	SY	SY
0710-02-071	167	18552	9276	9276	18552	3043	1822	22263
TOTALS	167	18552	9276	9276	18552	3043	1822	22263

*FOR CONTRACTOR INFO ONLY, FOR PAY QUANTITY SEE BASIS OF ESTIMATE

ROADWAY ITEMS

	530	3076*		3077*	
	6011	6071	6066	6033	6075
	INTRSCT, DRVWAYS, & TURNOUTS (ACP)	D-GR HMA TY-D PG64-22 (EXEMPT)	TACK COAT	SP MIXES SP-C SAC-A PG76-22	TACK COAT
UNIT OF MEASURE	SY	SY	SY	SY	SY
0710-02-071	4657	22263	22263	152128	152128
TOTALS	4657	22263	22263	152128	152128

*FOR CONTRACTOR INFO ONLY, FOR PAY QUANTITY SEE BASIS OF ESTIMATE

PAVEMENT MARKING ITEMS


	672	
	6007	6009
	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A
UNIT OF MEASURE	EA	EA
0710-02-071	406	1355
TOTALS	406	1355

RUMBLE STRIP ITEMS

	533
	6001
	RUMBLE STRIP (SHOULDER)
UNIT OF MEASURE	LF
0710-02-071	33394
TOTALS	33394

SH 105
QUANTITY SUMMARY

SHEET 1 OF 2



CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		11

PAVEMENT MARKING ITEMS

	666						668		
	6305	6308	6029	6035	6289	6293	6077	6076	6085
	RE PM W/RET REQ TY I (W)6"(BRK)(090MIL)	RE PM W/RET REQ TY I (W)6"(SLD)(090MIL)	REFL PAV MRK TY I (W)8"(DOT)(090MIL)	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	REF PROF PAV MRK TY I (Y)6"(BRK)(090MIL)	REF PROF PAV MRK TY I (Y)6"(BRK)(090MIL)	PREFAB PAV MRK TY C (W) (ARROW)	PREFAB PAV MRK TY C (W) (24") (SLD)	PREFAB PAV MRK TY C (W) (WORD)
UNIT OF MEASURE	LF	LF	LF	LF	LF	LF	EA	LF	EA
0710-02-071	8090	35702	143	172	40742	9920	2	294	5
TOTALS	8090	35702	143	172	40742	9920	2	294	5

SIGN ITEMS

	560			644				
	6011	6012	6013	6001	6004	6007	6017	6076
	MAILBOX INSTALL-S(TWW-POST) TY4	MAILBOX INSTALL-D(TWW-POST) TY4	MAILBOX INSTALL-M(TWW-POST) TY4	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	IN SM RD SN SUP&AM TY10BWG(1)SA(U)	IN SM RD SN SUP&AM TY10BWG(2)SA(P)	REMOVE SM RD SN SUP&AM
UNIT OF MEASURE	EA	EA	EA	EA	EA	EA	EA	EA
0710-02-071	68	2	13	45	3	1	1	50
TOTALS	68	2	13	45	3	1	1	50

SW3P ITEMS

	506	
	6041	6043
	BIODEG EROSN CONT LOG (INSTL)(12")	BIODEG EROSN CONT LOG (REMOVE)
UNIT OF MEASURE	LF	LF
0710-02-071	1000	1000
TOTALS	1000	1000

MISC ITEMS

	6001
	6002
	PORTABLE CHANGEABLE MESSAGE SIGN
UNIT OF MEASURE	EA
0710-02-071	2
TOTALS	2


WORKZONE MARKING ITEMS

	662	
	6109	6111
	WK ZN PAV MRK SHT TERM (TAB) TY W	WK ZN PAV MRK SHT TERM (TAB) TY Y-2
UNIT OF MEASURE	EA	EA
0710-02-071	2540	4210
TOTALS	2540	4210

SH 105
QUANTITY SUMMARY

DATE: 9/14/2023 9:35:18 PM
FILE: c:\tdot\pw_online\txdot\5\pworkline_richard.pastorella\d0979174\SUMMARIES.dgn

SHEET 2 OF 2




CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		12

SEQUENCE OF WORK:

1. MOBILIZE & INSTALL CONSTRUCTION BARRICADES, SIGNS, AND EROSION CONTROL DEVICES AS DIRECTED, MAINTAIN THESE ITEMS THROUGHOUT THE DURATION OF THIS PROJECT.
2. REPAIR AREAS OF BASE FAILURE AS DIRECTED BY THE ENGINEER. FILL ALL EXCAVATED AREAS THE SAME DAY.
3. MILL AND INLAY EXISTING RUMBLE STRIPS.
4. MILL TRANSITIONS AND CONSTRUCT OVERLAY. PLACE TABS IN ACCORDANCE WITH WZ(STPM). CONSTRUCT INTERSECTION AND PUBLIC DRIVEWAYS AS SHOWN IN THE PLANS. BACKFILL PAVEMENT EDGES.
5. PLACE EDGELINE RUMBLE STRIPS PRIOR THE PAVEMENT MARKINGS.
6. PLACE PERMANENT MARKINGS WITH 14 DAYS OF TABS PER STANDARDS AND MARKING LAYOUT IN PLANS.
7. PREFORM MAILBOX AND ROADSIDE SIGN UPGRADE AS STATED IN PLANS
8. CLEAN SITE AND REMOVE BARRICADES, SIGNS, AND SW3P ITEMS AFTER FINAL ACCEPTANCE

NOTES:

- PREPARE THE BID ACCORDING TO THIS SEQUENCE OF WORK. THE ENGINEER MAY MAY APPROVE ADJUSTMENTS TO THE SCHEDULE OF WORK AFTER LETTING.
- REFER TO THE GENERAL NOTES AND PLAN SHEETS FOR ADDITIONAL DIRECTION.



J. Horne

09/18/2023

FM 105
SEQUENCE OF
WORK

2023			
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		13

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 8:56:12 AM
 FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979178\BC(1)-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS


SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) - 21			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
		DW:	TxDOT
		CR:	TxDOT
REVISIONS	CONT	SECT	JOB
4-03 7-13	0710	02	071
9-07 8-14			FM 105
5-10 5-21	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	14

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 8:57:08 AM
 FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979178\BC(11-12)-21.dgn

TYPICAL LOCATION OF CROSSROAD SIGNS



- # May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
*			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	15	

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 8:58:10 AM
FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979178\BC(11-12)-21.dgn

SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT:	0710
		SECT:	02
		JOB:	071
		HIGHWAY:	FM 105
REVISIONS		DIST:	COUNTY
9-07	8-14		
7-13	5-21	BMT:	ORANGE
		SHEET NO.:	16

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0710	02	071	FM 105				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	ORANGE	17					


DATE: 9/13/2023 8:58:48 AM
FILE: c:\ttdot\p_w_online\ttdot5\kay\c_a_russ\d0979178\BC (1-12)-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- * See BC(4) for definition of "Work Duration."
- ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	18	

DATE: 9/13/2023 8:59:41 AM
FILE: c:\txdot\pw_online\kay\ca_russ\d0979178\BC(11-12)-21.dgn

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:00:12 AM
FILE: c:\t\dot\p\online\txdot5\kay\ca_russ\d0979178\BC (1-12)-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT


Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CR:	TxDOT
REVISIONS	0710	DW:	TxDOT
9-07	8-14	CK:	TxDOT
7-13	5-21	CONT	SECT
		0710	02
		071	FM 105
		DIST	COUNTY
		BMT	ORANGE
			SHEET NO.
			19

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 9:00:49 AM
 FILE: c:\ttdot\p_w_online\ttdot5\kay\ca_russ\d09178\BC(11-12)-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)




DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0710	02	071	FM 105				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	BMT	ORANGE		20				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:01:25 AM
 FILE: c:\t\dot\pw_online\t\dot5\kay\ca_russ\d0979178\BC(11-12)-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign
substrates shall NOT be used on
plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0710	02	071	FM 105				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	BMT	ORANGE	21					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:01:43 AM
 FILE: c:\t\dot\pw_online\t\dot5\kay\la_russ\d0979178\BC(11-12)-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	22	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:02:19 AM
 FILE: c:\t\dot\pw_online\t\dot5\kay\ca_russ\d0979178\BC (11-12)-21.dgn


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) -21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	ORANGE	23	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	ORANGE	24	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:02:47 AM
 FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979178\BC(11-12)-21.dgn

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
1-97 9-07 5-21				
2-98 7-13				
11-02 8-14	BMT	COUNTY	ORANGE	SHEET NO. 25


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 9:03:09 AM
FILE: c:\txdot\pw_online\txdot5\kay\la_russ\d0979178\BC(11-12)-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:10:15 AM
 FILE: c:\txdot\pw_online\txdot5\kay\la_russ\d0979178\tcp(2-4)-18.dgn



TCP (2-4a)
ONE LANE CLOSED



TCP (2-4b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.


TCP (2-4b)

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.


		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN			
LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS			
TCP (2-4) - 18			
FILE: tcp2-4-18.dgn	DN:	CK:	DW:
© TxDOT December 1985	CONT	SECT	JOB
REVISIONS	0710	02	071
8-95 3-03	DIST	COUNTY	SHEET NO.
1-97 2-12	BMT	ORANGE	26
4-98 2-18			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 9:12:31 AM
 FILE: c:\t\dot\pw_online\t\dot5\kay\ca_russ\d0979178\tcp(3-1)-13.dgn




TCP (3-1a)
UNDIVIDED MULTILANE ROADWAY




TCP (3-1b)
TWO-WAY ROADWAY WITH PAVED SHOULDERS



TCP (3-1c)
TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS



TRAIL/SHADOW VEHICLE A
 with RIGHT Directional display Flashing Arrow Board




TRAIL/SHADOW VEHICLE B
 with Flashing Arrow Board in CAUTION display

LEGEND				
*	Trail Vehicle	ARROW BOARD DISPLAY		
**	Shadow Vehicle			
***	Work Vehicle		RIGHT Directional	
	Heavy Work Vehicle		LEFT Directional	
	Truck Mounted Attenuator (TMA)		Double Arrow	
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)	

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



STRIPING FOR TMA









Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 MOBILE OPERATIONS
 UNDIVIDED HIGHWAYS**

TCP (3-1)-13

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	ORANGE	27	
1-97				

DATE: 9/13/2023 9:15:21 AM
 FILE: c:\txdot\pw_online\txdot5\kay\la_russ\d0979178\tcp(3-3)-14.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.

Texas Department of Transportation


Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
RAISED PAVEMENT
MARKER INSTALLATION/REMOVAL
TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
2-94 4-98	DIST	COUNTY		SHEET NO.
8-95 7-13	BMT	ORANGE		28
1-97 7-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 9:17:22 AM
 FILE: c:\txdot\pw_online\txdot5\kay.la_russ\d0979178\TCP(3-4)-13.dgn




TYPICAL TRAFFIC CONTROL FOR CONTINUOUS LEFT TURN LANE SYMBOL MARKINGS

TYPICAL TRAFFIC CONTROL FOR OUTSIDE DUAL LEFT TURN LANE SYMBOL MARKINGS



TYPICAL TRAFFIC CONTROL FOR OUTSIDE LANE MARKINGS

TYPICAL TRAFFIC CONTROL FOR INSIDE LANE MARKINGS



TYPICAL TRAFFIC CONTROL FOR LEFT TURN LANE MARKINGS

TYPICAL TRAFFIC CONTROL FOR CENTER LANE MARKINGS

LEGEND		
*	Trail Vehicle	ARROW BOARD DISPLAY
**	Shadow Vehicle	
** *	Work Vehicle	RIGHT Directional
	Heavy Work Vehicle	LEFT Directional
	Truck Mounted Attenuator (TMA)	Double Arrow
	Traffic Flow	Channelizing Devices


Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

GENERAL NOTES

1. This traffic control plan is for use on conventional roads posted at 45 mph or less and is intended for mobile operations that move continuously or intermittently (stopping up to approximately 15 minutes) such as short-line striping and in-lane rumble strips. When activities are anticipated to take longer amounts of time or traffic conditions warrant, a short duration or short-term stationary traffic control plan should be used.
2. A Truck Mounted Attenuator shall be used on Shadow Vehicle. Striping on the back panel of all truck mounted attenuators shall be 8" red and white reflective sheeting placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental material specification DMS-8300, Type A.
3. All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.
4. The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the drivers side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
5. Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C as per BC Standards. The arrow board operation shall be controlled from inside the truck.




STRIPING FOR TMA

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN MOBILE OPERATIONS FOR ISOLATED WORK AREAS UNDIVIDED HIGHWAYS			
TCP(3-4)-13			
FILE: tcp3-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT July, 2013	CONT: 0710	SECT: 02	JOB: 071
REVISIONS			FM 105
	DIST: BMT	COUNTY: ORANGE	SHEET NO.: 29


DATE: 9/13/2023 9:19:38 AM
 FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979178\WZ(RS)-22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
 * For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation
 Traffic Safety Division Standard





TEMPORARY RUMBLE STRIPS

WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	BMT	ORANGE	30	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 10:43:44 AM
 FILE: c:\txdot\pw_online\txdot5\kay\la_russ\d0979178\WZ(UL)-13.dgn



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

GENERAL NOTES

1. If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
2. UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
4. Signs shall be spaced at the distances recommended as per BC standards.
5. Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
6. Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
7. Short term markings shall not be used to simulate edge lines.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.

MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"



SIGNING FOR UNEVEN LANES


WZ(UL) - 13

FILE: wzu1-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
8-95 2-98 7-13	DIST	COUNTY	SHEET NO.	
1-97 3-03	BMT	ORANGE	31	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/13/2023 10:47:07 AM
 FILE: c:\txdot\pw_onlinetxdot\5\kay\la_russ\00979178\wz(stpm)-23.dgn

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS




WZ(STPM)-23

FILE: wzsstpm-23.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2023	CONTRACT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
4-92 7-13	DIST	COUNTY	SHEET NO.	
1-97 2-23	BMT	ORANGE	32	
3-03				

CK:
DW:
CK:
DN:


LEGEND

- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- ⊞ - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023




FM 105
ROADWAY LAYOUT

© TxDOT 2023		SHEET 1 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	33	



DATE: 9/15/2023 7:49:22 AM
FILE: c:\txdot\pw_online\txdot5\pwork\line_richard.pastore\at09791611\Sheet Container.dgn

DW: CK: DW: CK: DW: CK:



LEGEND

- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- ⊞ - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



**FM 105
RODWAY LAYOUT**





© TxDOT 2023		SHEET 2 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	34	

DATE: 9/15/2023 7:58:29 AM
 FILE: c:\txdot\pw_onlinetxdat5\pwork\line_richard.pastore\la0979161\Sheet Container.dgn

CK: DW: CK: DN:

LEGEND

- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- ⊞ - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



FM 105
ROADWAY LAYOUT



© TxDOT 2023		SHEET 3 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	35	

DATE: 9/15/2023 8:17:45 AM
FILE: c:\txdot\pw_onlinetxdot5\pwork\line_richard.pastore\la0979161\Sheet Container.dgn

DW: _____
 CK: _____
 DW: _____
 CK: _____

LEGEND


- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- ⊞ - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



**FM 105
ROADWAY LAYOUT**




©TxDOT 2023		SHEET 4 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	36	

DATE: 9/15/2023 8:30:44 AM
 FILE: c:\txdot\pw_onlinetxdot5\pwwonline_richard.pastorel\at09791611\Sheet Container.dgn

CK: DW: CK: DN:


LEGEND

- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- # - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023



FM 105
ROADWAY LAYOUT




© TxDOT 2023		SHEET 5 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	37	

DATE: 9/15/2023 8:40:15 AM
FILE: c:\txdot\pw_onlinetxdot5\pworkline_richard.pastorella\0979161\Sheet Container.dgn

DW: _____
 CK: _____
 DW: _____
 CK: _____

LEGEND

- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- ⊞ - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



**FM 105
ROADWAY LAYOUT**



©TxDOT 2023		SHEET 6 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	38	

DATE: 9/15/2023 8:49:09 AM
 FILE: c:\txdot\pw_online\txdot5\pwwonline_richard.pastore\la0979161\Sheet Container.dgn

CK: DW: CK: DN:

LEGEND

- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- # - SIDE ROADS
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



FM 105
ROADWAY LAYOUT

© TxDOT 2023 SHEET 7 OF 8



CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	39	

DATE: 9/15/2023 8:58:39 AM
FILE: c:\txdot\pw_onlinetxdot5\pwwonline_richard.pastore\at0979161\Sheet Container.dgn

DN: CK: DW: CK: CK:

LEGEND


- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- OHE - OVERHEAD ELECTRICAL LINE
- ⊕ - DRIVEWAYS
- # - SIDE ROADS
- △ - DELINIATOR



J. Horne






09/18/2023

N.T.S



FM 105
ROADWAY LAYOUT

© TxDOT 2023		SHEET 8 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	40	




** SEE LAYOUT SHEETS FOR DEPTH AND TYPE OF HMA.

NOTES:

LONGITUDINAL JOINTS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LAND WIDTH. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. TACK COAT SHALL BE APPLIED TO THE IN-PLACE TAPER BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED.

PAVEMENT EDGES SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL BE PLACED WITHIN THE NORMAL LANE WIDTH UNLESS OTHERWISE SHOWN ON THE PLANS. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. COMPACTION OF THE PAVEMENT EDGE TAPER WILL BE REQUIRED TO AS NEAR TO FINAL DENSITY AS POSSIBLE.



J. Horne
09/18/2023


HOT MIX
LONGITUDINAL
AND
PAVEMENT EDGE
JOINT DETAILS




FED. RD. DIV. NO.				SHEET NO.
6				41
STATE	DIST.	COUNTY		
TEXAS	BMT	ORANGE		
CONT.	SECT.	JOB	HIGHWAY NO.	
0710	02	071	FM 105	

DATE: 9/13/2023 3:03:54 PM
 FILE: c:\txdot\pw_online\txdot5\koy\o_russ\d0979179\BEG-END Project Taper .dgn


DN: CK: DM: CK:



BEGIN PROJECT TAPER



END PROJECT TAPER



J. Horne
 09/18/2023


FM 105
 TAPER DETAILS
 N. T. S.

©2023			
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		42



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DEFINITION OF TREATMENT ZONES FOR VARIOUS EDGE CONDITIONS


Edge Height (D) in Inches versus Lateral Clearance (Y) in Feet



Edge Condition I
S = (3:1) (or flatter)



Edge Condition II
S = ((2.99):1) to (1:1)



Edge Condition III
S is steeper than (1:1)






FIGURE-1: CONDITIONS INDICATING USE OF POSITIVE BARRIER FOR ZONE 5 ([Cross-hatched symbol])



- E = ADT x T
Where ADT is that portion of the average daily traffic volume traveling within 20 feet (generally two adjacent lanes) of the edge dropoff condition; and, T is the duration time in years of the dropoff condition.
- Figure-1 provides a practical approach to the use of positive barriers for the protection of vehicles from pavement drop-offs. Other factors, such as the presence of heavy machinery, construction workers, or the mix and volume of traffic may make the use of positive barriers appropriate, even when the edge condition alone may not justify the use of a barrier.
- An approved end treatment should be provided for any positive barrier end located within a lateral offset of 20 feet from the edge of the travel lane.

These guidelines apply to temporary traffic control areas or work zones where continuous pavement edges or drop-offs exist parallel and adjacent to a lane used by traffic. The edge conditions may be present between shoulders and travel lanes, between adjacent or opposing travel lanes, or at intermediate points across the width of the paved surface. Due to the variability in construction operations, tolerances in the variables may be allowed by the engineer. These guidelines do not apply to short term operations. These guidelines do not constitute a rigid standard or policy; rather, they are guidance to be used in conjunction with engineering judgement. These guidelines may be updated on the Design Division's on-line manuals.

Warning Device or Traffic Barrier
4" White Edge Line or Edge of Lanes being used for maintenance of traffic.



Zone	Treatment Types Guidelines:
①	No treatment.
②	CW 8-11 "Uneven Lanes" signs.
③	CW 8-9a "Shoulder Drop-Off" or CW 8-11 signs plus vertical panels.
④	CW 8-9a or CW 8-11, signs plus drums. Where restricted space precludes the use of drums, use vertical panels. An edge fill may be provided to change the edge slope to that of the preferable Edge Condition I.
⑤	Check indications (Figure-1) for positive barrier. Where positive barrier is not indicated, the treatment shown above for Zone- 4 may be used after consideration of other applicable factors.

FACTORS CONSIDERED IN THE GUIDELINES:

- The "Edge Condition" is the slope (S) of the drop-off (H:V). The "Edge Height" is the depth of the drop-off "D".
- Distance "X" is to be the maximum practical under job conditions. Two feet minimum for high speed conditions. Distance "Y" is the lateral clearance from edge of travel lane to edge of dropoff. Distance "Z" does not have a minimum.
- In addition to the factors considered in the guidelines, each construction zone drop-off situation should be analyzed individually, taking into account other variables, such as: traffic mix, posted speed in the construction zone, horizontal curvature, and the practicality of the treatment options.
- The conditions for indicating the use of positive or protective barriers are given by Zone-5 and Figure-1. Traffic barriers are primarily applicable for high speed conditions. Urban areas with speeds of 30 mph or less may have a lesser need for signing, delineation, and barriers. Right-angled edges, however, with "D" greater than 2 inches and located within a lateral offset of 6 feet, may indicate a higher level of treatment.
- If the distance "Y" must be less than 3 feet, the use of a positive barrier may not be feasible. In such a case, consider either: 1) narrowing the lanes to a desired 11 to 12 feet or 10 foot minimum (see CW20-8 sign), or 2) provide an edge slope such as Edge Condition I.

Edge Condition Notes:

- Edge Condition I: Most vehicles are able to traverse an edge condition with a slope rate of (3 to 1) or flatter. The slope must be constructed with a compacted material capable of supporting vehicles.
- Edge Condition II: Most vehicles are able to traverse an edge condition with a slope between (2.99 to 1) and (1 to 1) so long as "D" does not exceed 5 inches. Under-carriage drag on most automobiles will occur when "D" exceeds 6 inches. As "D" exceeds 24 inches, the possibility for rollover is greater in most vehicles.
- Edge Condition III: When slopes are greater than (1 to 1) and where "D" is greater than 2 inches, a more difficult control factor may exist for some vehicles, if not properly treated. For example, where "D" is greater than 2 inches and up to 24 inches different types of vehicles may experience different steering control at different edge heights. Automobiles might experience more steering control differential when "D" is greater than 2 inches and up to 5 inches. Trucks, particularly those with high loads, have more steering control differential when "D" is greater than 5 inches and up to 24 inches. When "D" exceeds 24 inches, the possibility of rollover is greater for most vehicles.
- Milling or overlay operations that result in Edge Condition III should not be in place without appropriate warning treatments, and these conditions should not be left in place for extended periods of time.

Engineer's Seal

 Date 09/18/2023
 [Signature]

Texas Department of Transportation
 Traffic Operations Division
TREATMENT FOR VARIOUS EDGE CONDITIONS

© TxDOT August 2000		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS					
CONT	SECT	JOB		HIGHWAY	
0710	02	071		FM 105	
DIST		COUNTY		SHEET NO.	
BMT		ORANGE		43	


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 3:30:30 PM
 FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979179\TE (HMAC) - 11.dgn

GENERAL NOTES


1. UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
2. FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
3. PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
4. THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
5. THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.




CONDITION - 1
 THIN HMAC SURFACES OR HMAC OVERLAY
 WITH THICKNESS OF 2.5" OR LESS



CONDITION - 2
 OVERLAY OF EXISTING PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



CONDITION - 3
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 2.5" TO 5"



CONDITION - 4
 NEW OR RECONSTRUCTED PAVEMENT
 HMAC THICKNESS 5" OR GREATER

(NOT TO SCALE)




				Design Division Standard	
TAPERED EDGE DETAILS HMAC PAVEMENT					
TE (HMAC) - 11					
FILE: tehmac11.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0710	02	071	FM 105	
	DIST	COUNTY		SHEET NO.	
	BMT	ORANGE		44	

DATE: 9/13/2023 3:41:35 PM
FILE: c:\t\dot\pw_online\txdot5\koy\g_russ\0979179\DRIVEWAY & PUBLIC ROAD DETAILS.dgn

PUBLIC ROAD DATA SHEET

DWY #	STATION	LT	RT	TYPE				PRIVATE DRIVE	PUBLIC ROAD	WIDTH	LENGTH
				ACP	CONC	GRAV	GRASS				
				FT	FT						
2	519+10	X		X				X	69	34	
8	528+12	X		X				X	84	34	
21	537+13		X	X				X	68	34	
42	553+76	X		X				X	73	34	
44	554+75	X		X				X	79	34	
48	557+41		X	X				X	73	34	
62	570+20		X	X				X	72	34	
63	571+54	X		X				X	82	34	
65	574+56		X	X				X	75	34	
77	588+10	X		X				X	69	34	
82	591+42		X	X				X	75	34	
91	596+44	X		X				X	49	34	
108	613+27		X	X				X	76	34	
111	617+51	X		X				X	77	34	
114	620+80		X	X				X	77	34	
120	628+00		X	X				X	62	34	
125	630+26	X		X				X	68	34	
130	633+19		X	X				X	75	34	
133	635+65	X		X				X	75	34	
135	638+92	X		X				X	68	34	
138	642+58		X	X				X	73	34	
141	644+86	X		X				X	75	34	
147	649+10	X		X				X	67	34	
150	653+10		X	X				X	66	34	
165	662+28	X		X				X	78	34	
178	671+50	X		X				X	78	34	
181	674+33	X			X			X	80	34	
184	676+11		X	X				X	78	34	
188	678+10	X			X			X	32	34	

FOR CONTRACTOR INFORMATION ONLY



J. Horne

09/18/2023

PUBLIC ROAD SUMMARY

N. T. S.

© 2023

CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		45

DATE: 9/13/2023 3:42:22 PM
 FILE: c:\txdot\p_w_online\txdot5\koy1a_russ\0919179\DRIVEWAY & PUBLIC ROAD DETAILS.dgn


DRIVEWAY DATA SHEET

DWY #	STATION	LT	RT	TYPE				PRIVATE DRIVE	PUBLIC ROAD	WIDTH	LENGTH
				ACP	CONC	GRAV	GRASS			FT	FT
1	519+07		X		X			X		58	5
3	520+02		X		X			X		28	5
4	520+58		X		X			X		29	5
5	521+87	X			X			X		33	5
6	525+00		X		X			X		32	5
7	528+00		X		X			X		30	5
9	528+96	X			X			X		60	5
10	529+30		X		X			X		25	5
11	530+05	X			X			X		37	5
12	530+07		X		X			X		30	5
13	530+57		X		X			X		27	5
14	530+77		X		X			X		32	5
15	530+85	X			X			X		29	5
16	532+05	X			X			X		35	5
17	532+05		X		X			X		32	5
18	534+14		X		X			X		35	5
19	534+87		X		X			X		27	5
20	536+09	X			X			X		40	5
22	537+26	X			X			X		36	5
23	538+29		X		X			X		44	5
24	540+85		X		X			X		47	5
25	541+11	X			X			X		79	5
26	543+30	X			X			X		37	5
27	543+30		X		X			X		48	5
28	544+53		X		X			X		32	5
29	545+89		X		X			X		33	5
30	545+89	X			X			X		30	5
31	546+28	X			X			X		31	5
32	547+32		X		X			X		35	5
33	547+68	X			X			X		34	5
34	548+74		X		X			X		48	5
35	549+17	X			X			X		28	5
36	549+58	X			X			X		30	5
37	550+48		X		X			X		56	5
38	551+61	X			X			X		32	5
39	552+16	X			X			X		33	5
40	552+17		X		X			X		41	5
41	553+18	X			X			X		32	5
43	553+86		X		X			X		45	5
45	554+90	X			X			X		32	5
46	555+19	X			X			X		29	5
47	556+35		X		X			X		30	5
49	557+88	X			X			X		28	5
50	559+92	X				X		X		32	5


FOR CONTRACTOR INFORMATION ONLY

PRIVATE DRIVE

NOTES:
 1. TO BE PAID FOR UNDER ITEM 530




PLAN



SECTION

DRIVEWAY SUMMARY

N.T.S.



J. Horne
 09/18/2023

SHEET 1 OF 4

		2023	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		46

DATE: 9/13/2023 3:43:02 PM
 FILE: c:\txdot\p_w_online\txdot5\koy\g_russ\d0979179\DRIVEWAY & PUBLIC ROAD DETAILS.dgn



DRIVEWAY DATA SHEET

DWY #	STATION	LT	RT	TYPE				PRIVATE DRIVE	PUBLIC ROAD	WIDTH	LENGTH
				ACP	CONC	GRAV	GRASS			FT	FT
51	560+41		X		X			X		34	5
52	561+65	X			X			X		32	5
53	562+13		X		X			X		30	5
54	562+21	X			X			X		36	5
55	562+59		X		X			X		43	5
56	564+00		X		X			X		30	5
57	564+80		X			X		X		54	5
58	565+64		X		X			X		30	5
59	566+06	X			X			X		29	5
60	568+75		X		X			X		40	5
61	569+55	X			X			X		32	5
64	573+46	X			X			X		34	5
66	577+20		X		X			X		30	5
67	577+39	X			X			X		29	5
68	578+41		X		X			X		34	5
69	579+37	X			X			X		30	5
70	580+57		X		X			X		29	5
71	581+41		X		X			X		32	5
72	583+11		X		X			X		32	5
73	583+31	X			X			X		34	5
74	585+20		X		X			X		48	5
75	585+20	X			X			X		30	5
76	586+57	X			X			X		35	5
78	588+94		X		X			X		48	5
79	589+46	X			X			X		34	5
80	590+76		X		X			X		34	5
81	590+84	X			X			X		34	5
83	592+25	X			X			X		35	5
84	593+32	X			X			X		41	5
85	593+75	X			X			X		34	5
86	594+20		X		X			X		35	5
87	595+43	X			X			X		32	5
88	595+66		X		X			X		31	5
89	596+25	X			X			X		30	5
90	596+51		X		X			X		35	5
92	597+32	X			X			X		44	5
93	598+15	X			X			X		90	5
94	598+25		X		X			X		31	5
95	599+15	X			X			X		66	5
96	599+65		X		X			X		32	5
97	600+21	X			X			X		86	5
98	600+51		X		X			X		31	5
99	601+15	X			X			X		60	5
100	602+17	X			X			X		150	5

FOR CONTRACTOR INFORMATION ONLY


PRIVATE DRIVE

NOTES:
1. TO BE PAID FOR UNDER ITEM 530



DRIVEWAY SUMMARY

N.T.S.



J. Horne
09/18/2023

SHEET 2 OF 4

© 2023			
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		47

DATE: 9/13/2023 3:43:34 PM
 FILE: c:\txdot\p_w_online\txdot5\koy\g_russ\09179\DRIVEWAY & PUBLIC ROAD DETAILS.dgn


DRIVEWAY DATA SHEET

DWY #	STATION	LT	RT	TYPE				PRIVATE DRIVE	PUBLIC ROAD	WIDTH	LENGTH
				ACP	CONC	GRAV	GRASS			FT	FT
101	603+89		X		X			X		32	5
102	604+75		X		X			X		42	5
103	607+44	X			X			X		32	5
104	609+23		X		X			X		32	5
105	610+34		X		X			X		28	5
106	611+61		X		X			X		30	5
107	612+20	X			X			X		31	5
109	615+30	X			X			X		31	5
110	615+78		X		X			X		35	5
112	619+00	X			X			X		32	5
113	619+40		X		X			X		37	5
115	623+42		X		X			X		36	5
116	624+72		X		X			X		27	5
117	624+96	X			X			X		32	5
118	625+92		X		X			X		75	5
119	627+47		X		X			X		28	5
121	628+15	X			X			X		45	5
122	628+65		X		X			X		64	5
123	629+44		X		X			X		64	5
124	629+75	X			X			X		26	5
126	631+31	X			X			X		32	5
127	631+49		X		X			X		36	5
128	632+62	X			X			X		31	5
129	633+00		X		X			X		28	5
131	634+08	X			X			X		34	5
132	635+10		X		X			X		34	5
134	636+26		X		X			X		36	5
136	640+19	X			X			X		30	5
137	642+28	X			X			X		29	5
139	642+98	X			X			X		32	5
140	643+68	X			X			X		34	5
142	645+49		X		X			X		40	5
143	646+35		X		X			X		34	5
144	646+35	X			X			X		35	5
145	647+57	X			X			X		29	5
146	647+87		X		X			X		34	5
148	651+43		X		X			X		20	5
149	651+92	X			X			X		66	5
151	654+00		X		X			X		38	5
152	654+68	X			X			X		69	5
153	655+38	X			X			X		29	5
154	655+92		X		X			X		45	5
155	656+51	X			X			X		33	5
156	657+00		X		X			X		28	5


FOR CONTRACTOR INFORMATION ONLY

PRIVATE DRIVE

NOTES:
1. TO BE PAID FOR UNDER ITEM 530




PLAN



SECTION

DRIVEWAY SUMMARY

N.T.S.



09/18/2023

SHEET 3 OF 4

		© 2023															
		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>0710</td> <td>02</td> <td>071</td> <td>FM 105</td> </tr> <tr> <td>DIST</td> <td colspan="2">COUNTY</td> <td>SHEET NO.</td> </tr> <tr> <td>BMT</td> <td colspan="2">ORANGE</td> <td>48</td> </tr> </table>		CONT	SECT	JOB	HIGHWAY	0710	02	071	FM 105	DIST	COUNTY		SHEET NO.	BMT	ORANGE
CONT	SECT	JOB	HIGHWAY														
0710	02	071	FM 105														
DIST	COUNTY		SHEET NO.														
BMT	ORANGE		48														

DATE: 9/13/2023 3:43:57 PM
 FILE: c:\t\dot\p_w_online\txdot5\koy\g_russ\0919179\DRIVEWAY & PUBLIC ROAD DETAILS.dgn



DRIVEWAY DATA SHEET

Dwy #	STATION	LT	RT	TYPE				PRIVATE DRIVE	PUBLIC ROAD	WIDTH	LENGTH
				ACP	CONC	GRAV	GRASS			FT	FT
157	657+60	X			X			X		34	5
158	658+20	X			X			X		30	5
159	658+93		X		X			X		28	5
160	659+20	X			X			X		34	5
161	660+41	X			X			X		34	5
162	660+48		X		X			X		20	5
163	661+28		X		X			X		24	5
164	661+88		X		X			X		14	5
166	663+85		X		X			X		28	5
167	664+38	X			X			X		26	5
168	665+72	X			X			X		25	5
169	665+91		X		X			X		34	5
170	666+28	X			X			X		25	5
171	666+45		X		X			X		44	5
172	668+10	X			X			X		38	5
173	668+70		X		X			X		35	5
174	669+23	X			X			X		20	5
175	669+69		X		X			X		30	5
176	670+39		X		X			X		26	5
177	671+24		X		X			X		60	5
179	672+70		X		X			X		41	5
180	674+10		X		X			X		38	5
182	675+12		X		X			X		86	5
183	675+30	X			X			X		50	5
185	676+35	X			X			X		30	5
186	676+96	X			X			X		46	5
187	677+23		X		X			X		44	5
189	679+10	X			X			X		162	5
190	680+56	X			X			X		52	5
191	681+06	X			X			X		35	5
192	682+15		X		X			X		40	5
193	682+54	X			X			X		44	5
194	684+00	X			X			X		134	5

FOR CONTRACTOR INFORMATION ONLY


PRIVATE DRIVE

NOTES:
1. TO BE PAID FOR UNDER ITEM 530



DRIVEWAY SUMMARY

N. T. S.




09/18/2023

SHEET 4 OF 4


		2023															
		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>0710</td> <td>02</td> <td>071</td> <td>FM 105</td> </tr> <tr> <td>DIST</td> <td colspan="2">COUNTY</td> <td>SHEET NO.</td> </tr> <tr> <td>BMT</td> <td colspan="2">ORANGE</td> <td>49</td> </tr> </table>		CONT	SECT	JOB	HIGHWAY	0710	02	071	FM 105	DIST	COUNTY		SHEET NO.	BMT	ORANGE
CONT	SECT	JOB	HIGHWAY														
0710	02	071	FM 105														
DIST	COUNTY		SHEET NO.														
BMT	ORANGE		49														

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/13/2023 3:46:55 PM
 FILE: c:\t\dot\pw_online\txdot5\kay\o_russ\d0979179\rs(2)-23.dgn




PROFILE VIEW
OPTION 1




PROFILE VIEW
OPTION 2




PROFILE VIEW
OPTION 3



PROFILE VIEW
OPTION 4




PLAN VIEW




PLAN VIEW

* This distance may vary based on width of shoulder



PLAN VIEW

* This distance may vary based on width of shoulder




PLAN VIEW

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)


CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)

CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)




PLAN VIEW
OPTION 5

RAISED EDGE LINE (Rumble Strips)




PLAN VIEW
OPTION 6

PROFILE EDGE LINE MARKINGS (Rumble Strips)



PLAN VIEW
OPTION 7

PREFORMED THERMOPLASTIC EDGE LINE (Rumble Strips)



PLAN VIEW
OPTION 8

PREFORMED THERMOPLASTIC EDGE LINE (Rumble Strips)

GENERAL NOTES

- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) and FPM(1) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
- See the Shoulder Width Table below for determining what options may be used for edge line rumble strips.
- Breaks in edge line rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections, or driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration or deceleration lanes, crossovers, gore areas, or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
- Consideration shall be given to bicyclists. See RS(6).

WHEN INSTALLING MILLED DEPRESSION EDGE LINE RUMBLE STRIPS:

- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
- Pavement markings can be applied over milled shoulder rumble strips to create an edge line rumble strip.

WHEN INSTALLING RAISED OR PROFILE EDGE LINE RUMBLE STRIPS:

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edge line when used as a rumble strip. The color of the button should match the color of the adjacent edge line marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- The minimum distance between the edge line and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edge lines may substitute for buttons.




SHOULDER WIDTH TABLE		
EQUAL TO OR LESS THAN 2 FEET	GREATER THAN 2 FEET LESS THAN 4 FEET	EQUAL TO OR GREATER THAN 4 FEET
Option 1, 5, 6 or 8	Option 1, 2, 3, 5, 6 or 7	Option 2, 4, 5, 6 or 7

EDGE LINE RUMBLE STRIPS ON UNDIVIDED OR TWO LANE HIGHWAYS RS(2)-23			
FILE: rs(2)-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT	January 2023	CONTRACT SECT	JOB HIGHWAY
		0710 02	071 FM 105
10-13 1-23		DIST COUNTY	SHEET NO.
		BMT ORANGE	50

CK: DW: CK: DW:

LEGEND


- WS - 6" WHITE SOLID
- WB - 6" WHITE BROKEN
- 8WS - 8" WHITE SOLID
- 8WD - 8" WHITE DOTTED
- YS - 6" YELLOW SOLID
- YB - 6" YELLOW BROKEN
- 2YS - 6" DOUBLE YELLOW SOLID
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- ⊕ - DRIVEWAYS
- ⊞ - SIDE ROADS
- ⊠ - SINGLE MAILBOX
- ⊡ - DOUBLE MAILBOX
- ⊣ - MULTIPLE MAILBOX
- ⊞ - SIGN
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S




FM 105
PAVEMENT MARKING
& SIGN LAYOUT

©TxDOT 2023 SHEET 1 OF 8




CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	51	

DATE: 9/15/2023 9:53:05 AM
FILE: c:\txdot\pw_online\txdot51\pavonline_richard.pastore\la09791841\Pavement Marking & Sign Layout.dgn

CK: DW: CK: DN:



- LEGEND**
- WS - 6" WHITE SOLID
 - WB - 6" WHITE BROKEN
 - 8WS - 8" WHITE SOLID
 - 8WD - 8" WHITE DOTTED
 - YS - 6" YELLOW SOLID
 - YB - 6" YELLOW BROKEN
 - 2YS - 6" DOUBLE YELLOW SOLID
 - EOP - EDGE OF PAVEMENT
 - ROW - RIGHT OF WAY
 - # - DRIVEWAYS
 - # - SIDE ROADS
 - 🏠 - SINGLE MAILBOX
 - 🏠 - DOUBLE MAILBOX
 - 🏠 - MULTIPLE MAILBOX
 - ⊕ - SIGN
 - △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



**FM 105
PAVEMENT MARKING
& SIGN LAYOUT**




© TxDOT 2023		SHEET 2 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	52	

DATE: 9/15/2023 9:50:13 AM
FILE: c:\ttdot\pw_onlinetx\dtdot5\pwwonline_richard.pastorel\at09791841\Pavement Marking & Sign Layout.dgn

CK:
DW:
CK:
DN:

LEGEND

- WS - 6" WHITE SOLID
- WB - 6" WHITE BROKEN
- 8WS - 8" WHITE SOLID
- 8WD - 8" WHITE DOTTED
- YS - 6" YELLOW SOLID
- YB - 6" YELLOW BROKEN
- 2YS - 6" DOUBLE YELLOW SOLID
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- Ⓜ - DRIVEWAYS
- Ⓢ - SIDE ROADS
- Ⓜ - SINGLE MAILBOX
- Ⓜ - DOUBLE MAILBOX
- Ⓜ - MULTIPLE MAILBOX
- Ⓢ - SIGN
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



FM 105
PAVEMENT MARKING
& SIGN LAYOUT




© TxDOT 2023		SHEET 3 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	53	

DATE: 9/15/2023 9:58:07 AM
FILE: c:\txdot\pw_online\txdot5\pwwonline_richard.pastorelala\09791841 Pavement Marking & Sign Layout.dgn

CK: DW: CK: DN:

LEGEND

- WS - 6" WHITE SOLID
- WB - 6" WHITE BROKEN
- 8WS - 8" WHITE SOLID
- 8WD - 8" WHITE DOTTED
- YS - 6" YELLOW SOLID
- YB - 6" YELLOW BROKEN
- 2YS - 6" DOUBLE YELLOW SOLID
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- ⊕ - DRIVEWAYS
- # - SIDE ROADS
- 🏠 - SINGLE MAILBOX
- 🏠 - DOUBLE MAILBOX
- 🏠 - MULTIPLE MAILBOX
- ⊕ - SIGN
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S.
Texas Department of Transportation

FM 105
PAVEMENT MARKING
& SIGN LAYOUT

© TxDOT 2023 SHEET 5 OF 8




CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	55	

DATE: 9/15/2023 10:22:51 AM
FILE: c:\txdot\pw_onlinetxdot5\pworkline_richard.pastore\140979184\Pavement Marking & Sign Layout.dgn

DW:
 CK:
 DN:

LEGEND

- WS - 6" WHITE SOLID
- WB - 6" WHITE BROKEN
- 8WS - 8" WHITE SOLID
- 8WD - 8" WHITE DOTTED
- YS - 6" YELLOW SOLID
- YB - 6" YELLOW BROKEN
- 2YS - 6" DOUBLE YELLOW SOLID
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- # - DRIVEWAYS
- # - SIDE ROADS
- Ⓜ - SINGLE MAILBOX
- Ⓜ - DOUBLE MAILBOX
- Ⓜ - MULTIPLE MAILBOX
- # - SIGN
- △ - DELINIATOR



J. Horne

09/18/2023

N.T.S
 Texas Department of Transportation

**FM 105
 PAVEMENT MARKING
 & SIGN LAYOUT**



©TxDOT 2023		SHEET 6 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	56	

DATE: 9/15/2023 10:29:15 AM
 FILE: c:\txdot\pw_online\tdot5\pavonline_richard.pastore\at09791841Pavement Marking & Sign Layout.dgn

CK: DW: CK: DN:


LEGEND

- WS - 6" WHITE SOLID
- WB - 6" WHITE BROKEN
- 8WS - 8" WHITE SOLID
- 8WD - 8" WHITE DOTTED
- YS - 6" YELLOW SOLID
- YB - 6" YELLOW BROKEN
- 2YS - 6" DOUBLE YELLOW SOLID
- EOP - EDGE OF PAVEMENT
- ROW - RIGHT OF WAY
- ⊕ - DRIVEWAYS
- # - SIDE ROADS
- Ⓜ - SINGLE MAILBOX
- Ⓜ - DOUBLE MAILBOX
- Ⓜ - MULTIPLE MAILBOX
- Ⓢ - SIGN
- △ - DELINIATOR



J. Horne

09/18/2023




FM 105
PAVEMENT MARKING
& SIGN LAYOUT

© TxDOT 2023		SHEET 7 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		57



DATE: 9/15/2023 10:33:21 AM
FILE: c:\txdot\pw_onlinetxdot5\pworkline_richard.pastore\1409791841 Pavement Marking & Sign Layout.dgn

CK: DW: CK: DN:

DATE: 9/18/2023 10:43:21 AM
 FILE: c:\pwworkspace\109791841\pavement marking & sign layout.dgn




- LEGEND**
- WS - 6" WHITE SOLID
 - WB - 6" WHITE BROKEN
 - 8WS - 8" WHITE SOLID
 - 8WD - 8" WHITE DOTTED
 - YS - 6" YELLOW SOLID
 - YB - 6" YELLOW BROKEN
 - 2YS - 6" DOUBLE YELLOW SOLID
 - EOP - EDGE OF PAVEMENT
 - ROW - RIGHT OF WAY
 - ⊕ - DRIVEWAYS
 - # - SIDE ROADS
 - Ⓜ - SINGLE MAILBOX
 - Ⓜ - DOUBLE MAILBOX
 - Ⓜ - MULTIPLE MAILBOX
 - ⊕ - SIGN
 - △ - DELINIATOR



J. Horne

09/18/2023

N.T.S



**FM 105
 PAVEMENT MARKING
 & SIGN LAYOUT**

© TxDOT 2023		SHEET 8 OF 8	
CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	58	

SUMMARY OF SMALL SIGNS

DATE: 9/14/2023 8:15:58 AM
 FILE: c:\txdot\pw_online\txdot5\kay\g_russ\d0979184\SUMMARY OF SMALL SIGNS.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

STA.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
518+35	1	M3-1	NORTH	12 x 6	X		10BWG	1	SA	U		
	---	M1-6F	(FARM ROAD) (105)	24 x 24								
	---	M6-3	(ARROW) (VERTICAL)	21 x 15								
	---	M3-2	EAST	12 x 6								
	---	M1-6F	(FARM ROAD) (2802)	24 x 24								
	---	M6-1R	(ARROW) (HORIZONTAL) (RIGHT)	21 x 15								
519+39	2	D3-1G	NORTHWOOD DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
519+68	3	R3-9b	TWO-WAY LEFT TURN ONLY	24 x 36	X		10BWG	1	SA	P		
519+67	4	R3-7R	MANDATORY RIGHT TURN	30 x 30	X		10BWG	1	SA	P		
520+94	5	M4-6	END	24 x 12	X		10BWG	1	SA	P		
	---	R3-9b	TWO-WAY LEFT TURN ONLY	21 x 15								
522+10	6	D1-1R	MAURICEVILLE ---->	VAR x 12	X		10BWG	1	SA	T		
522+83	7	D2-2	VIDOR 7 ORANGEFIELD 20	VAR x 30	X		10BWG	2	SA	P		
525+32	8	R3-7R	MANDATORY RIGHT TURN	30 x 30	X		10BWG	1	SA	P		
528+39	9	D3-1G	BLACK HETZEL LN	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
534+50	10	R2-1	SPEED LIMIT (60)	18 x 24	X		10BWG	1	SA	P		
534+53	11	R2-1	SPEED LIMIT (65)	18 x 24	X		10BWG	1	SA	P		
536+89	12	D3-1G	AUNT SADIE DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
542+70	13	W9-2TL	LANE ENDS MERGE LEFT	30 x 30	X		10BWG	1	SA	P		
554+03	14	D3-1G	BELLARD RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
554+42	15	D3-1G	STEPHENSON RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
557+12	16	D3-1G	MERLIN ST	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
561+21	17	W9-1R	RIGHT LANE ENDS	30 x 30	X		10BWG	1	SA	P		
	---	W16-3P(1)	1/2 MILE	30 x 24								
569+90	18	D3-1G	MARY ANN RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
571+80	19	D3-1G	TIMER RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
574+30	20	D3-1G	JASPER ST	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
574+30	21	D3-1G	WEST CIRCLE DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
589+94	22	M3-1	NORTH	12 x 6	X		10BWG	1	SA	P		
	---	M1-6F	(FARM ROAD) (105)	24 x 24								
	---	D10-7aT	REFERENCE MARKER 436	10 x 3								
591+18	23	D3-1G	NORTHWOOD DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
596+70	24	D3-1G	STANLEY RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
613+03	25	D3-1G	HARDIN ST	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
617+78	26	D3-1G	W CIRCLE DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
620+57	27	D3-1G	FARRAGUT HTS	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
627+52	28	D3-1G	BECKY RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
630+51	29	D3-1G	DECKER RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
632+94	30	D3-1G	OLDBURY RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
630+51	31	D3-1G	N SUNSET DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).

SHEET 1 OF 2



SUMMARY OF SMALL SIGNS

SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	ORANGE	59	

SUMMARY OF SMALL SIGNS

DATE: 9/14/2023 8:16:38 AM
 FILE: c:\txdot\pw_online\txdot5\koy\c_russ\d0979184\SUMMARY OF SMALL SIGNS.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

STA.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
639+17	32	D3-1G	BRIARCLIFF RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
642+35	33	D3-1G	PUG RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
645+12	34	D3-1G	WILLETE RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
649+25	35	D3-1G	POST RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
652+81	36	D3-1G	COREBETT ST	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
662+51	37	D3-1G	TRAVILLO RD	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
665+06	38	W2-2R	SIDE ROAD-90 DEGREE	18 x 18	X		10BWG	1	SA	P		
671+85	39	D3-1G	BROOKHOLLOW ST	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
673+03	40	M2-1	(JCT)	21 x 15	X		10BWG	1	SA	P		
	---	M1-6F	(FARM ROAD) (105)	24 x 24								
674+60	41	D3-1G	PINE FOREST DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
675+06	42	W11-8L	FIRE TRUCK (SYMBOL)	24 x 24	X		10BWG	1	SA	P		
675+80	43	D3-1G	PLEASANT DR	VAR x 8	X		10BWG	1	SA	P		
	---	R1-1	STOP	30 x 30								
680+15	44	R2-1	SPEED LIMIT (55)	18 x 24	X		10BWG	1	SA	P		
680+19	45	R2-1	SPEED LIMIT (60)	18 x 24	X		10BWG	1	SA	P		
683+00	46	D1-1R	LAKEVIEW ---->	VAR x 12	X		10BWG	1	SA	T		
683+07	47	M3-1	NORTH	12 x 6	X		10BWG	1	SA	P		
	---	M1-6F	(FARM ROAD) (105)	24 x 24								
685+11	48	M3-1	NORTH	12 x 6	X		10BWG	1	SA	P		
	---	M1-6F	(FARM ROAD) (1131)	24 x 24								
	---	M6-1	(HORZ. ARROW) --->	21 x 15								
685+11	49	R1-2	YIELD	30 x 30 x 30	X		10BWG	1	SA	P		
685+11	50	I-2oT	PINE FOREST CITY LIMIT POP 487	VAR x 24	X		10BWG	1	SA	T		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
 - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
 - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).




SUMMARY OF SMALL SIGNS


SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	ORANGE	60	


DATE: 9/15/2023 11:01:20 AM
 FILE: c:\t\dot\pw_online\tdot5\pwnonline_richard_pastorello\0979184\Signs_Detail.s.dgn



D2-2 8in;
 1.9" Radius, 0.8" Border, White on Green;
 "VIDOR", ClearviewHwy-3-W; "7", ClearviewHwy-3-W;
 1.9" Radius, 0.8" Border, White on Green;
 "ORANGEFIELD", ClearviewHwy-3-W; "20", ClearviewHwy-3-W;




D1-1 6in RT;
 1.5" Radius, 0.5" Border, White on Green;
 "MAURICEVILLE", ClearviewHwy-3-W; Standard Arrow Custom 9.0" X 6.1" 0";




D1-1 6in RT;
 1.5" Radius, 0.5" Border, White on Green;
 "LAKEVIEW", ClearviewHwy-3-W;
 Standard Arrow Custom 9.0" X 6.1" 0";




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "BLACK", ClearviewHwy-3-W;
 "HETZEL", ClearviewHwy-3-W;
 "LN", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "NORTHWOOD", ClearviewHwy-3-W;
 "DR", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "STEPHENSON", ClearviewHwy-3-W;
 "RD", ClearviewHwy-3-W;




I-2aT 6in;
 1.5" Radius, 0.8" Border, White on Green;
 "PINE FOREST", ClearviewHwy-5-W-R;
 "CITY LIMIT", ClearviewHwy-3-W; "POP 487", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "AUNT", ClearviewHwy-3-W;
 "SADIE", ClearviewHwy-3-W;
 "DR", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "STEPHENSON", ClearviewHwy-3-W;
 "RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "MARY", ClearviewHwy-3-W;
 "ANN", ClearviewHwy-3-W;
 "RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "JASPER", ClearviewHwy-3-W;
 "ST", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "BELLARD", ClearviewHwy-3-W;
 "RD", ClearviewHwy-3-W;



D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "MERLIN", ClearviewHwy-3-W;
 "ST", ClearviewHwy-3-W;



D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "TIMER", ClearviewHwy-3-W;
 "RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
 1.0" Radius, 0.4" Border, White on Green;
 "WEST", ClearviewHwy-3-W;
 "CIRCLE", ClearviewHwy-3-W;
 "DR", ClearviewHwy-3-W;

**FM 105
SIGN DETAILS**

N. T. S

SHEET 1 OF 2




J. Horne


09/18/2023

CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		61


DATE: 9/15/2023 11:02:47 AM
FILE: c:\t\dot\p_w_online\t\dot5\pwnonline_richard_passtore\la\d0979184\Signs_Detail.s.dgn




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"NORTHWOOD", ClearviewHwy-3-W;
"DR", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"STANLEY", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"HARDIN", ClearviewHwy-3-W;
"ST", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"PUG", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"WILLETE", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;



D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"DECKER", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"OLDBURY", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"N", ClearviewHwy-3-W;
"SUNSET", ClearviewHwy-3-W;
"DR", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"PINE", ClearviewHwy-3-W;
"FOREST", ClearviewHwy-3-W;
"DR", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"PLEASANT", ClearviewHwy-3-W;
"DR", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"POST", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"COREBETT", ClearviewHwy-3-W;
"ST", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"TRAVILLO", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"BRIARCLIFF", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"BROOKHOLLOW", ClearviewHwy-3-W;
"ST", ClearviewHwy-3-W;




D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"W", ClearviewHwy-3-W;
"CIRCLE", ClearviewHwy-3-W;
"DR", ClearviewHwy-3-W;



D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"FARRAGUT", ClearviewHwy-3-W;
"HTS", ClearviewHwy-3-W;



D3-1G(1) 4in;
1.0" Radius, 0.4" Border, White on Green;
"BECKY", ClearviewHwy-3-W;
"RD", ClearviewHwy-3-W;



John

09/18/2023


FM 105 SIGN DETAILS

N. T. S


SHEET 2 OF 2

CONT	SECT	JOB	HIGHWAY
0710	02	071	FM 105
DIST	COUNTY		SHEET NO.
BMT	ORANGE		62


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**





**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



YIELD LINES



FOUR LANE DIVIDED ROADWAY CROSSOVERS

NOTES


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

GENERAL NOTES

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**
Based on Traveled Way and Pavement Widths
for Undivided Roadways

Texas Department of Transportation

Traffic Safety Division Standard

**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1) - 22


FILE: pm1-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	071002	071	FM 105	
11-78 8-00 6-20	DIST	COUNTY	SHEET NO.	
8-95 3-03 12-22	BMT	ORANGE	63	
5-00 2-12				

22A


DATE:
FILE:

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS




**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY ROADWAYS**




DETAIL "A"

DETAIL "B"

DETAIL "C"




CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.
See Note 3.



**REFLECTORIZED PROFILE
PATTERN DETAIL**

USING REFLECTIVE PROFILE PAVEMENT MARKINGS

6" EDGE LINE, 6" CENTERLINE
OR 6" LANE LINE

NOTES


1. Edge lines should typically be 6" wide and the materials shall be specified in the plans.
2. Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

GENERAL NOTES


1. All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
2. On concrete pavements the raised pavement markers should be placed to one side of the longitudinal joints.
3. Use raised pavement marker Type I-C with undivided roadways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS




**POSITION GUIDANCE USING
RAISED MARKERS
REFLECTORIZED PROFILE
MARKINGS
PM(2) - 22**

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	071002	071	FM 105	
4-77 8-00 6-20	DIST	COUNTY	SHEET NO.	
4-92 2-10 12-22	BMT	ORANGE	64	
5-00 2-12				

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LANE REDUCTION

NOTES

1. Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
2. On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
3. Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
4. For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.


ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	
45 MPH	775	L=WS
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

GENERAL NOTES


1. Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
2. When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
3. Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
4. Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.

TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY




TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS



DETAIL A

DETAIL B

* 2" minimum allowed for restripe projects when approved by the Engineer.



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP

Texas Department of Transportation
Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 22

FILE: pm3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT REVISIONS 2022	CONT SECT	JOB	HIGHWAY	
4-98 3-03 6-20	071002	071	FM 105	
5-00 2-10 12-22	DIST	COUNTY	SHEET NO.	
8-00 2-12	BMT	ORANGE	65	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


Post Type
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
 TWT = Thin-Walled Tubing (see SMD(TWT))
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)

Anchor Type
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
 WS = Wedge Anchor Steel - (see SMD(TWT))
 WP = Wedge Anchor Plastic (see SMD(TWT))
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Mounting Designation
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))
 IF REQUIRED
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft. in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




BEHIND BARRIER




BEHIND GUARDRAIL

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.



BEHIND CONCRETE BARRIER



* Signs shall be mounted using the following condition that results in the greatest sign elevation:


- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND



RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

Texas Department of Transportation
 Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS


SMD(GEN)-08

© TxDOT July 2002	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONTRACT	SECTION	JOB
		0710	02	071
		DIST	COUNTY	SHEET NO.
		BMT	ORANGE	66

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 8:51:29 AM
 FILE: c:\txdot\pww\online\txdot5\kay\la_russ\d0979184\smds1.dgn

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.
















 Texas Department of Transportation
Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0710	02	071	FM 105
		DIST	COUNTY	SHEET NO.	
		BMT	ORANGE	67	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 8:53:13 AM
 FILE: c:\t\dot\p\online\tdot5\kay\la_russ\d0979184\smds2.dgn



GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.




**SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM
 SMD(SLIP-2)-08**


© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0710	02	071	FM 105
		DIST	COUNTY	SHEET NO.	
		BMT	ORANGE	68	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/14/2023 8:56:00 AM
 FILE: c:\txdot\pww\online\txdot5\kay\la_russ\d0979184\smds3.dgn




SM RD SGN ASSM TY XXXX(1)XX(T-2EXT)
 (* - See Note 12)




Detail B



Detail C
 Splices shall only be allowed behind the sign substrate.




SM RD SGN ASSM TY XXXX(1)XX(U-XX)




Typical Sign Mount
 SM RD SGN ASSM TY S80(2)XX(IP-EXAL)


* Additional stiffener placed at approximate center of signs when sign width is greater than 10'.



Detail E




Detail A




Detail D

EXTRUDED ALUMINUM SIGN WITH T BRACKET



Extruded Aluminum Sign With T Bracket



Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details
 See Detail E for clamp installation

GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)



**SIGN MOUNTING DETAILS
 SMALL ROADSIDE SIGNS
 TRIANGULAR SLIPBASE SYSTEM
 SMD (SLIP-3) -08**




© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0710	02	071	FM 105
		DIST	COUNTY		SHEET NO.
		BMT	ORANGE		69

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 8:58:58 AM
 FILE: c:\txdot\pw_online\txdot5\kay\ca_russ\d0979184\tsr-13.dgn

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>


		Traffic Operations Division Standard	
<h3>TYPICAL SIGN REQUIREMENTS</h3>			
<h3>TSR(3) - 13</h3>			
FILE:	tsr3-13.dgn	DN:	TxDOT
©TxDOT	October 2003	CK:	TxDOT
REVISIONS		DW:	TxDOT
		CK:	TxDOT
12-03	7-13	CONT	SECT
9-08		0710	02
		JOB	HIGHWAY
		071	FM 105
		DIST	COUNTY
		BMT	ORANGE
		SHEET NO.	70

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 9:00:23 AM
 FILE: c:\txdot\pw_online\txdot5\koy\ca_russ\d0979184\tsr-4-13.dgn

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



TYPICAL SIGN REQUIREMENTS



TSR(4) - 13

FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0710	02	071	FM 105				
12-03	7-13	DIST	COUNTY		SHEET NO.				
9-08		BMT	ORANGE		71				



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 9:03:39 AM
 FILE: c:\txdot\p_w_online\txdot5\kay\g_russ\d0979184\mb-21(1).dgn

TYPE 1 - MULTIPLE



TYPE 4 - MULTIPLE



MAILBOX SIZES


MAILBOX SIZE	TYPICAL DIMENSIONS			MAX **
	LENGTH	WIDTH	HEIGHT	
SMALL	19 1/2"	6"	7"	6 LBS
MEDIUM	22 1/2" *	8" *	11 1/2" *	8 LBS
LARGE	23 1/2"	11 1/2"	13 1/2"	11 LBS
EXTRA LARGE	18"	14"	12"	13 LBS
LOCKABLE	18"	11 1/2"	15"	23 LBS

* See Note 1.
 ** Excluding Molded Plastic on 4 X 4 Post

GENERAL NOTES:

- Dimensions shown (length, width, and height) are typical, not maximums. However, anytime a medium size mailbox is mounted on a single/double mount or on the outside position on a multi mount, the dimensions shown are maximums.
- Mailboxes shall be made of light weight sheet metal or light weight plastic. Heavy steel, cast iron or decorative mailboxes shall not be used on the state highway system.



TYPICAL INSTALLATION MEASUREMENTS



NOTE:

Mailbox installations in sidewalk areas shall be in accordance with the latest TxDOT Design Standard sheets PED-Pedestrian Facilities Curb Ramps.



TYPE 2 and 4 - SINGLE/DOUBLE




NOTE:

Double mailbox mounts are not allowed with a type 4 multiple mailbox installation

TYPE 3 - SINGLE/DOUBLE



PLACEMENT OF EMERGENCY LOCATION NUMBER




NOTES:

- Location numbers are provided by homeowner. Minimum size 1" height.
- Location number is typically placed on the mailbox in a contrasting color.
- Black numbers may be placed on the Type 2 object marker if the numbers cannot be placed on the mailbox.
- Alternatively, a green or blue plate with white numbers attached may be mounted below the object marker. Other contrasting color configuration, as approved, may be used.
- See 3 of 4 for Foundation details.
- See 4 of 4 for Hardware details.

SHEET 1 OF 4

TYPE 5



Texas Department of Transportation Maintenance Division Standard

MAILBOX MOUNTING AND ASSEMBLY


MB(1)-21

FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
2/2005	11/2009	4/2015		
6/2005	1/2011			
11/2006	7/2014			
	DIST	COUNTY		SHEET NO.
	BMT	ORANGE		72

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 9:08:27 AM
 FILE: c:\txdot\pw_online\txdot5\kay\g_russ\d0979184_mb-21(1).dgn

TYPE 1 - MULTI LOCKABLE AND XL MAILBOX



Multiple Mailbox Post
 NIGP#: 45057255254
 For 12 gauge steel

TYPE 2/4 - SINGLE LOCKABLE MAILBOX





Plate Washer (X2)
 NIGP: 45057250255

Single Mailbox Bracket
 NIGP: 45057252350

Bolt, 3/8" x 3 1/2" hex (X2)
 NIGP: 32020561117

Bolt, 5/16" x 1 1/4" hex (X4)
 NIGP: 32020681246

TYPE 2/4 - SINGLE XL MAILBOX



L-bracket (X4)
 NIGP#: 45057250263

Bolt, 3/8" x 3 1/2" hex (X2)
 NIGP: 32020561117

Bolt, 5/16" x 1 1/2" hex (X4)
 NIGP: 32020560507

Single Mailbox Bracket
 NIGP: 45057252350


Bolt, 1/4" x 3/4" hex (2 each side)
 NIGP: 45057521002
 Field Drill Holes as Needed

Plate Washer (X2)
 NIGP: 45057250255

Bolt, 3/8" x 3 1/2" hex (X2)
 NIGP: 32020561117

NOTE:
 Follow same configuration when mounting an XL mailbox on a Type 4 multi post.

TYPE 1 MULTI - LOCKABLE ARCHITECTURAL (LA)



Bolt, 3/8" x 3/4" hex (X6)
 NIGP: 45057521028
 Typical at Each Angle Bracket and plate washer


Mailbox Bracket
 NIGP: 45057252251 (Inverted)

Bolt, 3/8" x 4 1/2" hex
 NIGP: 32020561133
 Drill Ø 1/16" hole in Post

Plate Washer (X2)
 NIGP: 45057250255

Angle Bracket Part A (X2)
 NIGP: 45057258001

TYPE 1 MULTI - XL MAILBOX



L-bracket (X4)
 NIGP#: 45057250263

Bolt, 3/8" x 3/4" hex (X6)
 NIGP: 45057521028
 Typical at Each Angle Bracket and plate washer

Angle Bracket Part A (X2)
 NIGP: 45057258001

Bolt, 1/4" x 3/4" hex (2 each side)
 NIGP: 45057521002
 Field Drill Holes as Needed


Mailbox Bracket
 NIGP#: 45057252251 (Inverted)

Bolt, 5/16" x 2 1/2" hex (X4)
 NIGP: 32020220938
 Use existing hole in mailbox

Plate Washer (X2)
 NIGP#: 45057250255

Bolt, 3/8" x 4 1/2" hex
 NIGP: 32020561133
 Drill Ø 1/16" hole in Post

TYPE 3 - XL MAILBOX MOUNTING



Bolt, 5/16" x 1 1/2" hex (X4)
 NIGP: 32020560507

L-bracket (X4)
 NIGP: 45057250263

Plate Washer (X2)
 NIGP: 45057250255

Angle Bracket Part B
 NIGP: 45057258027

Angle Bracket Part A
 NIGP: 45057258001

Bolt, 1/4" x 3/4" hex (2 each side)
 NIGP: 45057521002
 Field Drill Holes as Needed

Mailbox Bracket
 NIGP: 45057252251 (Inverted)

Bolt, 3/8" x 3/4" hex (X2)
 NIGP: 45057521028
 Typical at Each Angle Bracket

Bolt, 5/16" x 3" (X2)
 NIGP: 32020743004


SHEET 2 OF 4

		Maintenance Division Standard	
<h2>XL AND LOCKABLE ARCHITECTURAL MAILBOX ASSEMBLY</h2> <h3>MB (2) - 21</h3>			
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT March 2004	CONT	SECT	JOB
REVISIONS	0710	02	071
2/2005	11/2009	4/2015	FM 105
6/2005	1/2011		
11/2006	7/2014		
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	73	


DATE: 9/15/2023 11:06:18 AM
 FILE: c:\txdot\pw_online\txdot5\pwnonline_richard_pastorella\0979184\mb-21.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any standard to other formats or for incorrect results or damages resulting from its use.

TYPE 1 - SUPPORT/FOUNDATION

Thin Wall Tube w/ V-LOC Anchorage




TYPE 3 - SUPPORT/FOUNDATION




NOTES:

1. Attach Object Marker (OM) facing direction of traffic.
2. OM will also be required on opposite side if installed on a 2-Lane, 2-Way roadway.

TYPE 5 - SUPPORT/FOUNDATION



TYPE 6 - TEMPORARY MAILBOX SUPPORT




Plastic Drum NIGP: 55093383655
 Rubber Collar NIGP: 55093387102

NOTES:

1. Place on approved plastic drum as shown in the Compliant Work Zone Traffic Control Devices (CWZTCD).
2. Existing attachment hardware shall be used unless damaged. Damaged hardware shall be replaced.


TYPE 2 - SUPPORT/FOUNDATION

Thin Wall Steel Tube w/Wedge Anchor System



TYPE 4 - SUPPORT/FOUNDATION

Whitecoated steel post NIGP: 45057561107
 Multiple post NIGP: 45057257409
 Recycled Rubber post (RR) NIGP: 45057561057



GENERAL NOTES:

1. Erect post plumb or vertical.
2. When galvanized part is required galvanize in accordance with Item 445.
3. Use a concrete footing as shown or when directed. Concrete footing will be required when soils do not hold the support/foundations in a stable condition, only on Type 1, Type 2, and Type 4

SHEET 3 OF 4



MAILBOX SUPPORT AND FOUNDATION

















MB (3) - 21

FILE: MB-21.dgn	DN:	CK:	DW:	CK:
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
2/2005	11/2009	4/2015		
6/2005	1/2011			
11/2006	7/2014			
	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	74	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023 9:09:26 AM
 FILE: c:\txdot\pw_online\txdot5\kay\la_russ\d0979184\mb-21(1).dgn

TYPE	TYPE 1	TYPE 2	TYPE 3	TYPE 4	TYPE 5	TYPE 6
Configuration	Multiple	Single or Double	Single or Double	Single	Double	Multiple
Mailbox Size NIGP #	Outside Position: S or M Inside Position: S, M, L, XL, or LA	Single: S, M, L, XL, or LA Double: SS, SM, MM	Single: S, M, L, or XL Double: SS, SM, MM	S, M, L, XL, or LA	SS, SM, or MM	Outside Position: S or M Inside Position: S, M, L, or XL
Mailbox Post NIGP #	45057255254 (Galvanized Multiple)	45057561404 (Thin Walled Govanize)	57044325108 (Wing Channel Post)	45057561107 (Thin walled white powder coated) 45057561057 (Recycled Rubber Post: S or M only)	45057561107 (Thin Walled White Powder Coated)	45057257409 (White Powder Coated Multiple)
Post and Mailbox Hardware NIGP #	45057259009 (Wedge) 45057256500 (V-Wing Socket) 45057253002 (Bracket Extension) 45057252251 (Mailbox Bracket) 45057258001 (Part A Angle Bracket x2) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	80130598701 (Wedge) 80130238407 (Wedge Anchor) 45057253002 (Bracket Extension) 45057252343 (Double MB Bracket) 45057252350 (S. Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	45057541653 (Type 3 Double Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057253002 (Bracket Extension) 45057258001 (Part A Angle Bracket) 45057258027 (Part B Angle Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057252350 (Single Mailbox Bracket) 45057253002 (Bracket Extension) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252343 (Double Mount Bracket) 45057252251 (Mailbox Bracket x2)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252350 (Single Mount Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)
Foundation Used	Class B Concrete (Required for LA Mailboxes)	Class B Concrete (Required for LA Mailboxes)	None	Class B Concrete (not used with recycled rubber post, required for LA Mailboxes)	Class B Concrete (not required)	Class B Concrete

 NIGP: 45057250263 L-Bracket x4 for XL sized mailboxes	 NIGP: 45057252343 Double Mailbox Bracket For Type 2 and Type 4 double mount	 NIGP: 45057252350 Single Mailbox Bracket For Type 2 single and for Type 4 single and multi mount	 NIGP: 45057258001 Part "A" Angle Bracket For Type 1 multi (2 per mailbox) and Type 3 single and double
 NIGP: 45057251055 Type 6 Angle Bracket (2 per mailbox)	 NIGP: 45057252251 Mailbox Bracket For Type 1 multi and any double mount (use 2)	 NIGP: 45057253002 Bracket Extension Use 1 for a medium Mailbox Use 2 for a Large Mailbox	 NIGP: 45057258027 Part "B" Angle Bracket For Type 3 single and double
 NIGP: 80130598701 Wedge for Type 2	 NIGP: 45057250255 Plate Washer for Architecural and XL Mailboxes	 NIGP: 45057541653 Type 3 double mailbox bracket	 NIGP: 55083571053 Type 4 Mailbox Wedge
 NIGP: 55083571004 Type 4 Mailbox Socket	 NIGP: 80130238407 Type 2 Wedge Anchor	 NIGP: 45057259009 Wedge for Type 1 V-wing Socket	 NIGP: 45057256500 V-wing Socket for Type 1 Foundation

NIGP #	OBJECT MARKERS AND CONFORMABLE SHEETING
55008311759	Type 2 OM 4"x4" (3 Needed) for Type 3 Wing Channel Post
55008312906	Type 2 OM 6"x12" (1 needed) for Type 3 Wing Channel Post
80149872006	12" Conformable Reflective Yellow Sheeting for Flexible Posts

NOTES:

- Type 2 object marker in accordance with Traffic Engineering Standard Delineators & Object Markers.
- A light weight receptacle for newspaper delivery can be attached to mailbox posts if the receptacle does not touch the mailbox, present a hazard to traffic or delivery of the mail, extend beyond the front of the mailbox, or display advertising, except the publication title.

BID CODES FOR CONTRACTS

MB-(X) ASSM TY (XXX) (X)

Type of Mailbox _____

S = Single
D = Double
M = Multiple
MP = Molded Plastic


Type of Post _____

WC = Winged Channel Post
RR = Recycled Rubber
TWW = Thin Walled White Tubing
TWG = Thin Walled Galvanized Tubing
TIM = Timber

Type of Foundation _____


Ty 1 = V-Loc
Ty 2 = Wedge Anchor Steel System
Ty 3 = Winged Channel post
Ty 4 = Wedge Anchor Plastic System
Ty 5 = 4 X 4 Post

SHEET 4 OF 4


 Texas Department of Transportation		Maintenance Division Standard
<h2>NIGP PARTS LIST AND COMPATIBILITY</h2> <h3>MB(4)-21</h3>		
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT
©TxDOT March 2004	CONT	SECT
REVISIONS	0710	02
2/2005 11/2009 4/2015	JOB	071
6/2005 1/2011	HIGHWAY	FM 105
11/2006 7/2014	DIST	COUNTY
	BMT	ORANGE
		SHEET NO.
		75

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of work files to other formats or for incorrect results or damages resulting from its use.


DATE: 9/15/2023 11:11:32 AM
 FILE: c:\txdot\pw_online\txdot5\pwnonline_richard.pastorella\0979184\MBP MBP(1)-22.dgn




CASE 1. OFF TRAVEL WAY DELIVERY



CASE 2. BACK SIDE DELIVERY




CASE 3. DELIVERY NEAR RIGHT OF WAY LINE



TYPICAL PLAN

GENERAL NOTES:

- CASE 1 IS THE MOST COMMON METHOD.
- TURN OUT BEHIND MAILBOX FOR CASE 2 WILL NORMALLY BE ALLOWED FOR NATURAL TERRAIN THAT WILL SERVE AS AN ALL WEATHER SURFACE.
- ALL WEATHER DRIVEWAYS FOR CASE 3 MAILBOXES LOCATED AT THE RIGHT OF WAY LINE SHOULD NORMALLY BE PLACED IN CONJUNCTION WITH COUNTY ROADS OR OTHER CONNECTING COMMUNITY ROADS OR STREETS. WHEN 3 OR MORE MULTI-RACKS ARE ANTICIPATED, THE USE OF AN NDCBU IS RECOMMENDED. ONLY RURAL PATRONS LOCATED ON STATE MAINTAINED HIGHWAYS MAY HAVE A MAILBOX OR NDCBU SLOT ON TxDOT RIGHT OF WAY.



TYPICAL SECTION CASE 1

↑ MAIL DELIVERY VEHICLE TRAVEL DIRECTION

SHEET 1 OF 2



Guideline
**MAILBOX SIDE ROAD PLACEMENT
 AND TURNOUTS**

MBP(1)-22

FILE: MBP-22.DGN	DN: VS	CK:	DW: VS	CK:
© TxDOT OCTOBER 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0710	02	071	FM 105
12/2012 5/2014	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	76	

* NDCBU MAY BE INSTALLED ON COUNTY ROAD ROW WITH APPROVAL OF COUNTY.

NOTES:

For projects disturbing 5 or more acres, place laminated copies of the TxDOT and Contractor Construction Site Notices and the TxDOT and Contractor Notices of Intent on the SW3P Notification Board.


For projects disturbing between 1 and 5 acres, place laminated copies of the TxDOT and Contractor Construction Site Notices on the SW3P Notification Board.

For projects with an Individual Permit with the US Army Corp of Engineer, place a laminated copy of the Permit Certificate on the Notification Board.

Center all postings.

Notification Boards are to be constructed from chloroplast and placed at a location within the right-of-way but outside the clear zone as directed by the Engineer. This work will not be paid for directly, but will be considered subsidiary to other items.

CSN - Construction Site Notice, Large for projects greater than 5 acres, Small for projects greater than 1 and less than 5 acres.



2.3" Radius, 0.9" Border, White on Blue;
 [TxDOT PROJECT] E Mod; [SW3P] E Mod; [INFORMATION] E Mod;



BEAUMONT DISTRICT
SW3P
NOTIFICATION BOARD
DETAIL
(SW3P-B)

REVISIONS © 2022	FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.		SHEET NO. 78
	STATE	DISTRICT	COUNTY	
	TEXAS	BMT	ORANGE	
	CONTROL	SECTION	JOB	HIGHWAY NO.
	0710	02	071	FM 105

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):
0710-02-071

1.2 PROJECT LIMITS:

From: FM 2802, SOUTH

To: FM 1131

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 30.2328373, (Long) -94.0216726

END: (Lat) 30.1873078, (Long) -94.0231895

1.4 TOTAL PROJECT AREA (Acres): 57.77

1.5 TOTAL AREA TO BE DISTURBED (Acres): approx. 31.60

1.6 NATURE OF CONSTRUCTION ACTIVITY:

PREFORM BASE REPAIR, PLACE OVERLAY
RE-STRIPE, AND REPLACE ROADSIDE SIGNS

1.7 MAJOR SOIL TYPES:

Soil Type	Description
EVADALE SILT LOAM, 0 TO 1% SLOPES	SILT LOAM, LOAM, SILTY CLAY LOAM, CLAY
EVADALE-ALDINE COMPLEX, 0 TO 1% SLOPES	SILT LOAM, LOAM, CLAY LOAM, SILTY CLAY LOAM, CLAY
EVADALE- GIST COMPLEX, 0 TO 1% SLOPES	SILT LOAM, SILTY CLAY LOAM, VERY FINE SANDY LOAM, CLAY, LOAM, CLAY LOAM, SILTY CLAY
TEXLA SLIT LOAM 0 TO 2% SLOPES	SILT LOAM, SILTY CLAY LOAM, VERY FINE SANDY LOAM, CLAY, LOAM, CLAY LOAM, SILTY CLAY

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- Other: _____
- Other: _____
- Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
TIGER CREEK	TIGER CREEK Segment ID: 0601B
CANEY CREEK	TIGER CREEK Segment ID: 0601B
TENMILE CREEK	NECHES RIVER TIDAL Segment ID: 0601
TIGER CREEK Segment ID: 0601B	NECHES RIVER TIDAL Segment ID: 0601

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT


- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:

MS4 Entity



J. Horne

09/18/2023

STORMWATER POLLUTION PREVENTION PLAN (SWP3)



Sheet 1 of 2

Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				79
STATE	STATE DIST.	COUNTY		
TEXAS	BMT	ORANGE		
CONT.	SECT.	JOB	HIGHWAY NO.	
0710	02	071	FM 105	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

T / P

- Sediment Trap
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
 - Not required (<10 acres disturbed)
 - Required (>10 acres) and implemented.
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
 - Required (>10 acres), but not feasible due to:
 - Available area/Site geometry
 - Site slope/Drainage patterns
 - Site soils/Geotechnical factors
 - Public safety
 - Other: _____

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:


- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.



J. Horne

09/18/2023


STORMWATER POLLUTION PREVENTION PLAN (SWP3)

© 2022 Sheet 2 of 2
Texas Department of Transportation


FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				80
STATE	STATE DIST.	COUNTY		
TEXAS	BMT	ORANGE		
CONT.	SECT.	JOB	HIGHWAY NO.	
0710	02	071	FM 105	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023
 FILE: c:\txdot\p_w_online\txdot5\kay.lg.russ\d0979185\ec916.dgn




PLAN VIEW




SECTION A-A

EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW



SECTION C-C


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
 - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
 - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
 - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
 - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
 - CL-DI EROSION CONTROL LOG AT DROP INLET
 - CL-CI EROSION CONTROL LOG AT CURB INLET
 - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<i>Design Division Standard</i>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0710	02	071
	DIST	COUNTY	SHEET NO.
	BMT	ORANGE	81


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023
 FILE: c:\txdot\pw_online\txdot5\kay.lg.russ\d0979185\ec916.dgn



**EROSION CONTROL LOGS ON SLOPES
 STAKE AND TRENCHING ANCHORING**


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART





**EROSION CONTROL LOGS ON SLOPES
 STAKE AND LASHING ANCHORING**

CL-SSL



STAKE AND TRENCHING ANCHORING DETAIL

CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL

LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

TRENCH DEPTH TABLE




STAKE NOTCH DETAIL

SHEET 2 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0710 02	071	FM 105
DIST	COUNTY	SHEET NO.	
BMT	ORANGE	82	


DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/14/2023
 FILE: c:\txdot\pw_online\txdot5\kay.lg.russ\d0979185\ec916.dgn




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET



CL-CI

NOTE:
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG EC (9) - 16			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT: 0710	SECT: 02	JOB: 071
REVISIONS			FM 105
	DIST: BMT	COUNTY: ORANGE	SHEET NO.: 83

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. TxDOT - Beaumont District

No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or as required by the Engineer.
- Comply with TCEQ Permit 150000 as this project is estimated to disturb more than five acres. TxDOT will file for a NOI first under TCEQ Permit 150000 as the Primary Operator. Contractor will be supplied a copy of the NOI and TCEQ Authorization Certificate. Contractor must use the TxDOT information to complete their own NOI per SP 506-003/SP 007-004. Contractor files a NOI as the Primary Operator for Day-to-Day Operational Control and provides copies of their NOI, TCEQ Authorization Certificate, and Contractor Site Notice to the District. To ensure the Permit reflects a single construction site, the Regulated Entity Number (REN) must be the same for TxDOT and the Contractor. Contact the Beaumont District Construction Office with questions regarding TCEQ Permit 150000
- Take measures to prevent construction materials and debris including, but not limited to wastewater (i.e., cooling liquid, etc.) associated with concrete removal from entering any inlets, ditches, or waterways.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions, including Regional conditions for the State of Texas, associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required: Permit # _____
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- Maintain a neat and clean worksite next to the water and do not allow any debris to fall into the water.
- Comply with "Work In or Near Waters/Wetlands Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Mulching	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	

III. CULTURAL RESOURCES

No Action Required Required Action

Action No.

- Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

IV. VEGETATION RESOURCES

No Action Required Required Action

Action No.

- No vegetation removal or trimming of any kind is allowed. Exceptions are allowed for mowed or maintained grass.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

No Action Required Required Action

Action No.

- If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own. Avoid any unnecessary impacts to dens if found.
- If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEOC for guidance.
- Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
- Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and Texas Parks and Wildlife (TPW) Code Section 64.002. The full MBTA guidance may be found here: <https://ftp.dot.state.tx.us/pub/txdot-info/env/toolkit/350-01-gui.pdf>
- Resource specific BMPs (Section I) and Pavement BMPs (Section II, F) from the "Updated Best Management Practices (BMPs) for TxDOT Maintenance Activities" guidance under the TxDOT Maintenance Program EA shall be reviewed and implemented where appropriate. The maintenance EA BMPs may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/080-01-bmp.pdf>

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MSA: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

No Action Required Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances
- Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
None				

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

Action No.

- Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous materials or contamination is noted during construction.
- Notify TxDOT Inspector or DEOC of any hazardous materials spills including fuel, hydraulic fluid, etc.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required Required Action

Action No.

- Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.



ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC

Jerrold Justice
APPROVED BY DATE 09/19/2023
DISTRICT ENVIRONMENTAL DEPARTMENT

FILE: epic.dgn	DN: TxDOT	CK: AM	DW: VP	CK: AR
© TxDOT February 2019	CONT	SECT	JOB	HIGHWAY
	0710	02	071	FM 105
	DIST	COUNTY	SHEET NO.	
	BMT	ORANGE	84	

DATE: FILE: