

INDEX OF SHEETS

SEE SHEET 2 FOR INDEX OF SHEETS AND SHEET 3 FOR LOCATION MAP

**STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT.
BR 2022 (699)

**CR 1495 @ WOODBURY CREEK
RAINS COUNTY, ETC.**

LIMITS: CR 1495 AT WOODBURY CREEK

NET LENGTH OF ROADWAY = 281.00 FT. = 0.053 MI.
NET LENGTH OF BRIDGE = 75.00 FT. = 0.014 MI.
NET LENGTH OF PROJECT = 356.00 FT. = 0.067 MI.

FOR THE CONSTRUCTION OF: BRIDGE REPLACEMENT
CONSISTING OF: BRIDGE REPLACEMENT AND APPROACHES

FHWA TEXAS DIVISION			SHEET NO. 1
STATE	DISTRICT	COUNTY	
TEXAS	PAR	RAINS	
CONTROL	SECTION	JOB	HIGHWAY NO.
0901	30	018	CR

DESIGN SPEED: 15 MPH
CURRENT AADT (YEAR): 48 (2018)
FUTURE AADT (YEAR): 48 (2042)


FINAL PLANS

LETTING DATE: _____
DATE CONTRACTOR BEGAN WORK: _____
DATE WORK WAS COMPLETED: _____
DATE WORK WAS ACCEPTED: _____
ORIGINAL CONTRACT WORKING DAYS: _____
USED _____ OF _____ WORKING DAYS
NO. OF CHANGE ORDERS: _____
FINAL CONTRACT COST: _____
PERCENT OVER/UNDER RUN: _____
CONTRACTOR: _____

I CERTIFY THAT THIS PROJECT WAS BUILT IN ACCORDANCE WITH PLANS AND SPECIFICATIONS.

AREA ENGINEER _____ DATE _____

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1) - 21 THRU BR (12) - 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".



CR 1495 BRIDGE
@ WOODBURY CREEK
CSJ: 0901-30-018
EXISTING NBI: 01-1900-AA02-58-001
PROPOSED NBI: 01-1900-AA14-95-001

EXCEPTIONS: N/A
EQUATIONS: N/A
RAILROAD CROSSINGS: N/A

CONCURRENCE: 10/4/2023
DocuSigned by:
Linda Wallace
75FBF39C7820409 RAINS COUNTY JUDGE

©2023 Texas Department of Transportation

SUBMITTED FOR LETTING: 10.02.23
Monte R. Peter P.E.
DESIGN ENGINEER

RECOMMENDED FOR LETTING: 10/4/2023
DocuSigned by:
James Atkins II
A2C81980FB8844 AREA ENGINEER

APPROVED FOR LETTING: 10/5/2023
DocuSigned by:
Noel Paramanathan
AF7AF41AFE0495 DISTRICT ENGINEER

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023)


© 2023 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED.

FILE: T:\PARTDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Plan Sheets\A001 TITLE SHEET.dgn
DATE: 10/2/2023 1:31:35 PM

INDEX OF SHEETS

DATE: 10/4/2023 4:31:00 PM
 FILE: I:\PARTDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Plan Sheets\A100 INDEX OF SHEETS.dgn

SHEET NO.	DESCRIPTION
GENERAL	
1	TITLE SHEET
2	INDEX OF SHEETS
3, 3A-3B	GENERAL NOTES
4	ESTIMATE & QUANTITY
TRAFFIC CONTROL PLAN STANDARDS	
* 5-16	BC (1)-21 THRU BC (12)-21
17	WZ(RCD)-13
ROADWAY DETAILS	
18	TREE TRIMMING AND BRUSH REMOVAL
ROADWAY DETAILS STANDARDS	
* 19	GF(31)-19
* 20	SGT(12S)31-18
* 21	SGT(15)31-20
22	OMITTED
CR 1495 AT WOODBURY CREEK	
23	TYPICAL SECTION
24	ROAD CLOSURE PLAN
25	QUANTITY SUMMARY
26	PLAN AND PROFILE
27	BORING LOGS
28	BRIDGE HYDROLOGIC DATA
29	BRIDGE HYDRAULIC DATA
30	BRIDGE LAYOUT
31	BRIDGE QUANTITIES AND BEARING SEAT ELEVATIONS
BRIDGE STANDARDS	
* 32-34	AIG-24
* 35-36	SIG-24
* 37-38	IGSD-24
* 39-40	IGD
* 41-43	IGEB
* 44-45	IGMS
* 46	IGSK
* 47	IGTS
* 48-49	CSAB
* 50-51	FD
* 52-55	PCP
* 56	PCP-FAB
* 57-58	MEBR(C)
* 59-60	TYPE T631LS
* 61-62	SRR
PAVEMENT MARKINGS STANDARDS	
* 63	D&OM(1)-20
* 64	D&OM(2)-20
65	OMITTED
* 66	D&OM(5)-20
* 67	D&OM(VIA)-20
ENVIRONMENTAL PLANSHEETS	
68	SWP3 LAYOUT
69-70	SWP3
71	EPIC
ENVIRONMENTAL ISSUES STANDARDS	
* 72	EC(1)-16
* 73	EC(2)-16
* 74	EC(3)-16



CR 1495 @
WOODBURY CREEK
 INDEX OF
 SHEETS

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED
 BY A * ON THIS SHEET HAVE BEEN ISSUED
 BY ME AND ARE APPLICABLE TO THIS PROJECT.
Monte R. Rater P.E. Oct. 5, 2023
NAME DATE

©2023			
CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST		COUNTY	SHEET NO.
PAR		RAINS	2

County: Rains

Control: 0901-30-018

Highway: CR

Sheet:

GENERAL NOTES

General:

Contractor questions on this project are to be addressed to the following individual(s):

Greenville Area Office

James Atkins II, P.E. - James.Atkins@txdot.gov

Willie Bolden II, P.E. - Willie.Bolden@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address: <https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

On Contractor request, earthwork cross sections and construction timelines will be posted to TxDOT's Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Dispose of waste materials at an approved site. Furnish written approval from the property owner before disposal of waste materials.

Locate equipment a minimum of 30 feet from roadway when possible. Place signs and barricades as approved.

Stockpile sites for construction materials must be approved. Give at least 48 hours notification prior to stockpiling material.

Item 5 Control of the Work:

The responsibility for the construction surveying on this contract will be in accordance with Section 5.9.3, Method A.

Working days will be computed and charged in accordance with Article 8.3.1.4 Standard Work Week.

County: Rains

Control: 0901-30-018

Highway: CR

Sheet: 3

Right and left are determined based upon the forward direction of stationing in the specific control section.

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at:

<https://www.txdot.gov/business/resources/highway/bridge/bridge-publications.html#design>

Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

Item 6 Control of Materials:

The existing bridge has lead-containing paint. Provide a demolition plan to the Engineer three weeks in advance of lead paint disturbance to allow lead paint removal by TxDOT on-call contractor before Contractor bridge demolition.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html>

Item 7 Legal Relations and Responsibilities:

No significant traffic generator events identified.

Item 8 Prosecution and Progress:

Before beginning work on this project submit in writing, for approval, a plan of construction operations outlining in detail a sequence of work to be followed.

Provide a Bar Chart progress schedule for this project.

This project includes SP 000---002 which allows up to a 60-day delay to begin work on the project to allow for Contractor Mobilization.

County: Rains

Control: 0901-30-018

Highway: CR

Sheet:

Item 9 Measurement and Payment:

Items of work for the Monthly Estimate will be cut off on the 25th of each month. Items of work performed after the 25th will be processed and paid on the following month's estimate. Material On Hand (MOH) will cut off on the 20th of each month. Special circumstances will be considered on a case-by-case basis.

Item 100 Preparing Right of Way:

Remove all trees 25 foot from centerline on both sides of roadway. At cross structures, remove trees to ROW line and within 100' of the structure, parallel to the roadway. Remove underbrush and neatly trim trees and overhanging branches to produce a 60' vertical clear area within the limits of Prep ROW. Remove any trees or underbrush that interferes with any construction operation, including relocation of ditches or other drainage elements. Receive approval of equipment used to trim limbs. A boom axe will not be allowed. Remove all trimmed debris from the ROW or mulch all debris and incorporate into the topsoil on State ROW to the satisfaction of the Engineer.

The County Commissioner will be responsible to relocate existing gates and rebuild livestock fences as necessary, including temporary fences when required. The Contractor shall coordinate Prep ROW operations with the County Commissioner for gate and fence relocation. The Contractor shall coordinate with the County Commissioner eight weeks in advance of necessary gate/fence relocation.

Removal/relocation and disposal of existing road and bridge signs shall be subsidiary to this item.

Item 110 Excavation:

Before excavation operations the existing topsoil shall be salvaged in a manner to preserve the vigor of the existing Bermuda grass sod per Item 160.

This item also includes excavation of existing gravel/ rock on the roadway. The existing gravel/ rock shall be used as foundation for the proposed flexible base. The equipment, labor, fuel, incidentals, etc. to stockpile, place, and compact the excavated gravel/ rock shall be subsidiary to this item. The gravel/ rock shall be placed and prepared as specified for Item 247 as used in the plans.

Item 132 Embankment:

Test potential embankment sources using Tex-145-E to determine the presence and concentration of sulfates. Do not bring soil with greater than 3000 ppm sulfates into project.

Excavation pits for project embankment made within 250 feet of State Right of Way must be approved.

County: Rains

Control: 0901-30-018

Highway: CR

Sheet: 3A

Before embankment operations the existing topsoil shall be salvaged in a manner to preserve the vigor of the existing Bermuda grass sod per Item 160.

Item 164 Seeding for Erosion Control, 166 Fertilizer:

Apply fertilizer with a ratio of 3-1-2 (N-P-K) over the areas to be seeded. This work will not be paid for directly, but will be considered subsidiary.

Item 168 Vegetative Watering:

Use water trucks equipped with a sprinkler system adequate to permit coverage of the entire seeded area from the roadbed. This equipment must be available to perform watering throughout the duration of vegetative establishment.

Water all seeded areas the day seed is applied. Thereafter, maintain the seeded areas in a well-watered condition throughout the duration of vegetative establishment.

Item 247 Flexible Base:

Grading requirements
Tests to be in accordance with TxDOT Standard Test Methods

Item Desc.	Soil Constants			
	Linear Shrinkage	LL	Wet Ball	WBMV (incr. passing #40 sieve)
Item 247 Flex Base	6.0 max.	40 max.	40 max.	20% max.
PERCENT RETAINED ON SIEVE:				
1-3/4"	7/8"	3/8"	No. 4	No. 40
0	10-35	30-50	45-65	70-85

Flexible Base will not contain more than 1% by weight of clay balls.

Place blue top hubs for alignment and elevations of new base at centerline and edge of pavement.

Item 400 Excavation and Backfill for Structures:

Excavation and backfill for bridge construction/installation will be subsidiary to Item 420.

Item 416 Drill Shaft Foundations:

One core hole per bent/abutment required.

Item 420 Concrete Structures:

Do not use membrane curing for structural elements.

Type A bridge expansion joints shall be subsidiary to Item 420.

County: Rains

Control: 0901-30-018

Highway: CR

Sheet:

Item 422 Concrete Superstructures:

Saw-cut grooves on bridge deck are not required.

Item 432 Riprap:

The Engineer may adjust placement of riprap in the field.

Filter fabric is required for stone riprap.

Bridge demolition waste concrete may be used for stone rip rap. Cut protruding rebar within 2” of concrete surface. Maximum waste concrete cobble size shall match proposed stone rip rap Dmax size.

Item 496 Removing Structure:

The Contractor shall retain possession of all salvaged bridge materials.

Item 502 Barricades, Signs and Traffic Handling:

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The following items will be required for flagger on this project:

1. Flaggers are required to wear a white hard hat while performing flagging operations.
2. Flaggers will be required at the intersection of all State maintained roadways.
3. Flaggers may be required at other high traffic generating intersections as deemed necessary by the Area Engineer.

The traffic control plan for this contract consists of the installation and maintenance of warning signs and other traffic control devices shown in the plans, specification data which may be included in the general notes, applicable provisions of the Texas Manual on Uniform Traffic Control Devices (TMUTCD), traffic control plan sheets included in the plans, standard BC sheets and Item 502 of the Standard Specifications.

Do not begin Item 502, Barricades, Signs, and Traffic Handling, on the roadway until both of the following conditions are met:

1. The work schedule is approved.
2. No more than 5 workdays will pass between the beginning of Item 502 and the actual commencement of roadway work bid items.

County: Rains

Control: 0901-30-018

Highway: CR

Sheet: 3B

The final estimate will be withheld until all disturbed areas are covered with at least 70% perennial vegetative cover.

Correct all deficiencies within the time frame noted on the Traffic Control Device Inspection Form 599. Failure to make corrections within time frame specified may result in no payment for this Item for the month of the noted deficiency.

Item 506 Temporary Erosion, Sedimentation & Environmental Controls:

The Temporary Erosion Control measures for this project will consist of using the following items, as directed:

1. Temporary Silt Fence
2. Rock Filter Dams: All rock filter dams shall be installed with 6:1 slopes regardless of their location on the project. Failure to do so will result in no payment for the dam.

Silt fences will remain the property of the Contractor upon completion of the project. The final estimate will not be released until all silt fences have been properly removed, or as directed and 70% establishment of vegetative cover is obtained.

Acquire approval for any change to the location of temporary sediment fence, as shown in the plans, prior to installation. Placement of erosion protection devices may be altered, as directed, to satisfy the requirements of the SW3P.

The pay item to remove rock filter dams will require only a partial removal after 70 percent perennial vegetation has been established and approved. When removing the rock filter dams, leave the lower layer of rock adjacent to the ground in place so as not to disturb the soil.

Refer to the SW3P sheet for the total disturbed area for the project.

The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs) within one mile of the project limits will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within one mile of the project limits exceeds five acres, provide a copy of the Contractors NOI for PSLs on the ROW (to the appropriate MS4 operator when on an off-system route).

Item 540 Metal Beam Guard Fence:

MBGF delineation shall be installed within ten (10) working days of the completion of each MBGF section. Concrete mow strip is not considered to be a part of this work.



CONTROLLING PROJECT ID 0901-30-018

DISTRICT Paris
HIGHWAY CR 1495

Estimate & Quantity Sheet

COUNTY Rains

ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL
	100-6002	PREPARING ROW	STA	6.000	
	100-6004	PREPARING ROW(TREE)(12" TO 24" DIA)	EA	1.000	
	100-6011	PREPARING ROW(TREE)(24" TO 36" DIA.)	EA	1.000	
	110-6001	EXCAVATION (ROADWAY)	CY	23.000	
	110-6002	EXCAVATION (CHANNEL)	CY	450.000	
	132-6003	EMBANKMENT (FINAL)(ORD COMP)(TY B)	CY	143.000	
	164-6009	BROADCAST SEED (TEMP) (WARM)	SY	200.000	
	164-6011	BROADCAST SEED (TEMP) (COOL)	SY	200.000	
	164-6023	CELL FBR MLCH SEED(PERM)(RURAL)(CLAY)	SY	400.000	
	168-6001	VEGETATIVE WATERING	MG	2.000	
	247-6064	FL BS (CMP IN PLC)(TY A GR 4) (6")	SY	568.000	
	400-6005	CEM STABIL BKFL	CY	72.000	
	416-6004	DRILL SHAFT (36 IN)	LF	336.000	
	420-6013	CL C CONC (ABUT)	CY	37.600	
	422-6001	REINF CONC SLAB	SF	1,950.000	
	425-6035	PRESTR CONC GIRDER (TX28)	LF	298.000	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	186.000	
	450-6019	RAIL (TY T631LS)	LF	198.000	
	496-6009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000	
	500-6001	MOBILIZATION	LS	1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4.000	
	506-6001	ROCK FILTER DAMS (INSTALL) (TY 1)	LF	80.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	80.000	
	506-6020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	78.000	
	506-6024	CONSTRUCTION EXITS (REMOVE)	SY	78.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	400.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	400.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	100.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	12.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000	

ESTIMATE & QUANTITY



DISTRICT	COUNTY	CCSJ	SHEET
Paris	Rains	0901-30-018	4

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format.

DATE: 10/4/2023 8:34:47 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\Traffic Control Plan\STANDARD\BC (1)-21.dgn

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) -21			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
		DW:	TxDOT
		CK:	TxDOT
CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
REVISIONS		DIST	COUNTY
4-03	7-13		
9-07	8-14		
5-10	5-21	PAR	RAINS
			SHEET NO.
			5


DATE: 10/4/2023 8:34:48 PM
 FILE: T:\PARTDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\CONSTRUCTION\BC(2)-21.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	RATNS	6	

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project.

DATE: 10/4/2023 8:35:02 PM
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT.dgn


SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) -21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CON:	0901
		SECT:	30
		JOB:	018
		HIGHWAY:	CR
REVISIONS		DIST:	COUNTY
9-07	8-14	PAR:	RAINS
7-13	5-21		SHEET NO.
			7

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:03 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (1)-21 THRU BC (1)-21.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed.
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTC list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTC) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary - work that occupies a location more than 3 days.
 - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - d. Short, duration - work that occupies a location up to 1 hour.
 - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTC lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTC list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.


FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12


		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES			
BC (4) -21			
FILE:	bc-21.dgn	DWG:	TxDOT
© TxDOT	November 2002	CONT:	SECT:
REVISIONS		0901	30
9-07	8-14	018	CR
7-13	5-21	DIST:	COUNTY:
		PAR:	RATNS
			SHEET NO. 8

DATE: 10/4/2023 8:35:04 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (5)-21.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for the accuracy of the information resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC (5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0901	30	018	CR					
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	PAR	RATNS	9					

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

Other Condition List

FRONTAGE ROAD CLOSED
SHOULDER CLOSED XXX FT
RIGHT LN CLOSED XXX FT
RIGHT X LANES OPEN
DAYTIME LANE CLOSURES
I-XX SOUTH EXIT CLOSED
EXIT XXX CLOSED X MILE
RIGHT LN TO BE CLOSED
X LANES CLOSED TUE - FRI
ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT
ROAD REPAIRS XXXX FT
LANE NARROWS XXXX FT
TWO-WAY TRAFFIC XX MILE
CONST TRAFFIC XXX FT
UNEVEN LANES XXXX FT
ROUGH ROAD XXXX FT
ROADWORK NEXT FRI-SUN
US XXX EXIT X MILES
LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE *

FORM X LINES RIGHT
USE XXXXX RD EXIT
USE EXIT I-XX NORTH
USE I-XX E TO I-XX N
WATCH FOR TRUCKS
EXPECT DELAYS
PREPARE TO STOP
END SHOULDER USE
WATCH FOR WORKERS

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats for use in CAD systems. For more information, contact TxDOT at (512) 221-1211. FILE: T:\PARTDPD\CR_1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 - TRAFFIC CONTROL PLAN STANDARDS\BC (6)-21.dgn


WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLRs
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	Hwy	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

<h3>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</h3>			
<h2>BC (6) - 21</h2>			
FILE:	bc-21.dgn	DWG:	TxDOT
REVISED:	November 2002	CONT:	SECT:
REVISIONS:	0901	30	018
9-07	8-14	DIST:	COUNTY:
7-13	5-21	PAR:	RATNS
			SHEET NO. 10


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 10/4/2023 8:35:07 PM
 FILE: I:\PARTDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (1)-21 THRU BC (12)-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0901	30	018	CR				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	PAR	RATNS	11					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 10/4/2023 8:35:08 PM
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\BC (1)-21 THRU BC (12)-21.dgn

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS



- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
 - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
 - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.



BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
 (Maximum Sign Dimension)
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
 mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0901	30	018	CR				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	PAR	RATNS	12					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:10 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (1)-21-21.dgn



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
 L=Length of Taper (FT.) W=Width of Offset (FT.)
 S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0901	30	018	CR				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	PAR	RAINS		13				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 10/4/2023 8:35:11 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (1)-21 THRU BC (12)-21.dgn

TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.


Barricades shall NOT be used as a sign support.



TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TRAFFIC CONTROL FOR MATERIAL STOCKPILES


Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




PLAN VIEW

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) -21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	PAR	RAINS	14	

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
	0901	30	018	CR
REVISIONS	DIST	COUNTY	SHEET NO.	
2-98 9-07 5-21	PAR	RAINS	15	
1-02 7-13				
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 DATE: 10/4/2023 8:35:12 PM
 FILE: I:\PARTPDD\CR_1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (11)-21.dgn

PAVEMENT MARKING PATTERNS



REFLECTORIZED PAVEMENT MARKINGS - PATTERN A



REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A



RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.






RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CK:	TxDOT
©TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0901	30	018	CR				
1-97	9-07	5-21							
2-98	7-13								
11-02	8-14	DIST	COUNTY	SHEET NO.					
PAR		RAINS		16					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect use of this standard or for damages resulting from its use.


DATE: 10/4/2023 8:35:13 PM
FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\01 TRAFFIC CONTROL PLAN STANDARDS\BC (12)-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any damages resulting from its use.

DATE: 10/4/2023 8:35:14 PM
 FILE: I:\PARTD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\WorkArea\WZ (RCD) - 13.dgn



ROAD CLOSURE BEYOND THE INTERSECTION
 Signing for a Numbered Route with an Off-Site Detour



ROAD CLOSURE AT THE INTERSECTION
 Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "x" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'


* Conventional Roads Only

GENERAL NOTES



1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.

		Traffic Operations Division Standard	
WORK ZONE ROAD CLOSURE DETAILS			
WZ (RCD) - 13			
FILE: wzrcd-13.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
© TxDOT August 1995	CONT	SECT	JOB
REVISIONS	0901	30	018
1-97 4-98 7-13	DIST	COUNTY	SHEET NO.
2-98 3-03	PAR	RAINS	17


DATE: 10/3/2023 4:55:36 PM
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Plan Sheets\K001 TREE TRIMMING AND BRUSH REMOVAL.dgn



BRUSH REMOVAL UNDER BRIDGE AND IN CHANNEL



TREE TRIMMING



TREE REMOVAL
 SPECIFIC LOCATION SPECIFIED IN PLANS

Monte R. Rater P.E.
 10.05.23
 STATE OF TEXAS
 MONTE L. RATER
 #95859
 LICENSED PROFESSIONAL ENGINEER

CR 1495 @
 WOODBURY CREEK
 0901-30-018
 TREE TRIMMING
 AND
 BRUSH REMOVAL


NOT TO SCALE

© 2023

CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	18	


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 10/4/2023
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Des\gn\CAD Standards\GF (31) -19.dgn




TYPICAL POST PLACEMENT


NOTE: (SEE GENERAL NOTE 14 FOR RAIL HEIGHT MEASUREMENT)



WOOD BLOCK TO ROUND WOOD POST




WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST


GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.



ELEVATION MID-SPAN RAIL SPLICE


SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.




LOW FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.



BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.




MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.







NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.

				Design Division Standard
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF (31) -19				
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
	DIST	COUNTY	SHEET NO.	
	PAR	RATNS	19	

DATE: 10/4/2023
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Des\ign\CAD Standards\02 ROADWAY DETAILS STANDARDS\SGT(12S)31-18.dgn
 DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- * NOTES:**
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.



ALTERNATIVE ITEMS NOT SHOWN. *
 * ITEM (P) 8" WOOD-BLOCKOUT
 ** ITEM (Q) 25' GUARD FENCE PANEL

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSG STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSG.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSG PANELS, ONE 25'-0" MBSG PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" x 6" x 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6x9 OR W6x8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" x 18"	E3151



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard


SINGLE GUARDRAIL TERMINAL

MSKT-MASH-TL-3

SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT SECT	JOB	HIGHWAY	
REVISIONS	0901	30	018	CR
	DIST	COUNTY	SHEET NO.	
	PAR	RAINS	20	






DATE: 10/4/2023
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Des\Ign\CAD Standards\SGT (15)31-20.dgn
 DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6" 12GA	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6" 12GA	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0" 12GA	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CBO8
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WBO8
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/8"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GGR17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81

ITEM	QTY	SMALL HARDWARE	ITEM #
a	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPlice BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563HD HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M




NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15)31-20


FILE: sg+153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT: 0901	SECT: 30	JOB: 018	HIGHWAY: CR
REVISIONS	DIST: PAR	COUNTY: RAINS	SHEET NO. 21	

DW:
 CK:
 DW:
 CK:




EXISTING TYPICAL SECTION
 STA. 3+48 - 4+73
 STA. 5+23 - 6+47

 EXISTING BRIDGE
 STA. 4+73 - 5+23




PROPOSED TYPICAL SECTION
 TRANSITION FROM STA. 3+48 (12') TO STA. 3+98 (24')
 STA. 3+98 - 4+60
 STA. 5+35 - 5+97
 TRANSITION FROM STA. 5+97 (24') TO STA 6+47 (12')

 PROPOSED BRIDGE
 STA. 4+60 - 5+35



Oct. 4, 2023
 Monte R. Rater P.E.




NOTES:
 * 1. 3' OF 10:1 ONLY PRESENT WHERE MBGF IS REQUIRED ON EACH SIDE OF ROADWAY



CR 1495
 TYPICAL SECTION
 @
 WOODBURY CREEK

©TxDOT 2023		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
901	30	18	CR 1495
DIST	COUNTY	SHEET NO.	
PAR	RAINS	23	

DATE: 09/14/2023 04:19 PM
 FILE: DOCUMENT NAME




- ① ROAD CLOSED
X.XX MILES AHEAD
LOCAL TRAFFIC ONLY
R11-3g
60 X 30
- ② ROAD CLOSED
1000 FT
CW20-3B
48 X 48
- ③ ROAD CLOSED
500 FT
CW20-3C
48 X 48
- ④ TY III BARRICADE
- ⑤ ROAD CLOSED
R11-2
48 X 30
- ⑥ NAME
ADDRESS
CITY
STATE
CONTRACTOR
G20-6T
48" X 30"



NOTES:
UTILIZE THE TRAFFIC CONTROL DEVICES ON THIS PAGE WITH THOSE REQUIRED ON WZ(RCD) AND BC(1)-21 THROUGH BC(12)-21 WITH SUPPORT FROM THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD).

SIGN SPACING NOT TO SCALE UTILIZE TXDOT STANDARDS OR THE TMUTCD FOR APPROPRIATE SIGN/DEVICE SIZE AND SPACING.

Monte R. Rater P.E.



CR 1495 @
WOODBURY CREEK
0901-30-018
ROAD CLOSURE
PLAN



- LEGEND
- TYPE III BARRICADES (SKID MOUNT)
 - P TRAFFIC MOUNT AND POST
 - ▨ CONSTRUCTION AREA

© 2023

CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY		SHEET NO.
PAR	RAINS		24

DATE: 10/3/2023 4:55:38 PM
FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Plan Sheets\ROAD CLOSURE PLAN.dgn

CK: DW: CK: DW:

SUMMARY OF ROADWAY ITEMS

LOCATION		WIDTH	100 6002	100 6004	100 6011	110 6001	110 6002	132 6003	247 6064
			PREPARING ROW	PREPARING ROW(TREE) (12" TO 24" DIA)	PREPARING ROW(TREE) (24" TO 36" DIA.)	EXCAVATION (ROADWAY)	EXCAVATION (CHANNEL)	EMBANKMENT (FINAL) (ORD COMP) (TY B)	FL BS (CMP IN PLC)(TY A GR 4) (6")
FROM	TO		STA	EA	EA	CY	CY	CY	SY
2+91	3+48	12	1			7		1	38
3+48	3+98	* 18	1			7		4	100
3+98	4+60	24	1					62	165
4+60	5+35	BRIDGE	1				450		
5+35	5+97	24	1	1	1			63	165
5+97	6+47	* 18	1			9		9	100
TOTALS			6	1	1	23	450	143	568

* AVERAGE WIDTH IN TRANSITION

SUMMARY OF REMOVAL ITEMS

LOCATION	496 6009
REMOV STR (BRIDGE Ø - 99 FT LENGTH)	
EA	
STA. 4+60 TO STA. 5+25	1
TOTALS	1

SUMMARY OF MBGF ITEMS

LOCATION		LT/RT	540 6002	544 6001	658 6062
			MTL W-BEAM GD FEN (STEEL POST)	GUARDRAIL END TREATMENT (INSTALL)	INSTL DEL ASSM (D-SW) SZ 1(BRF) GF2 (BI)
FROM	TO		LF	EA	EA
4+10	4+60	RT	25	1	3
4+10	4+60	LT	25	1	3
5+35	5+85	RT	25	1	3
5+35	5+85	LT	25	1	3
TOTALS			100	4	12


SUMMARY OF LANDSCAPE ITEMS

LOCATION		WIDTH	164 6009	164 6011	164 6023	168 6001	FERTILIZER 3-1-2 *
			BROADCAST SEED (TEMP) (WARM)	BROADCAST SEED (TEMP) (COOL)	CELL FBR MLCH SEED (PERM) (RURAL) (CLAY)	VEGETATIVE WATERING	
FROM	TO	LF	SY	SY	SY	MG	LBS
3+48	4+60	16	100	100	200	1	10
5+35	6+47	16	100	100	200	1	10
TOTALS			200	200	400	2	20

* FOR CONTRACTOR'S INFORMATION ONLY: 2 CYCLES AT 50 LBS NITROGEN PER ACRE
AT 21-7-14 (NPK) ANALYSIS = 0.0492 LBS/SY/CYCLE
WATERING: BASED ON 2 APPLICATIONS, 0.5" RAINFALL EQUIVALENT = 0.003 MG/SY/CYCLE

SUMMARY OF EROSION CONTROL ITEMS

LOCATION		506 6001	506 6011	506 6020	506 6024	506 6038	506 6039
		ROCK FILTER DAMS (INSTALL) (TY 1)	ROCK FILTER DAMS (REMOVE)	CONSTRUCT ION EXITS (INSTALL) (TY 1)	CONSTRUCT ION EXITS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
FROM	TO	LF	LF	SY	SY	LF	LF
2+98	3+48			78	78		
3+48	4+60	40	40			200	200
5+35	6+47	40	40			200	200
TOTALS		80	80	78	78	400	400




CR 1495
QUANTITY SUMMARY

©2023 SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	25	

DATE: 10/4/2023 8:40:53 PM
FILE: p:\w\l\tdot\projectwiseonline.com\TXDOT\Documents\01 - PAR\Design Projects\0901300184 - Design\Plan Set\1 - General\QUANTITY SUMMARY.dgn


DATE: 10/3/2023 8:23:03 PM
 FILE: pw:\txdot\project\iseline.com\TXDOT\Documents\01 - PAR\Design Projects\090130018\4 - Design\Plan_Sets\3 - Roadway\PLAN AND PROFILE



- PROPOSED C
- EXISTING FENCE
- EXISTING R.O.W.
- CHANNEL BOTTOM OF BANK
- CHANNEL TOP OF BANK
- CHANNEL E

CONTROL POINT
 2" CAP SET IN CONCRETE
 STA: 0+61 OFFSET 20.52' LT
 N: 6984064.9182
 E: 2786276.4171
 EL= 377.53

SCALE:
 VERTICAL: 1"= 40'
 HORIZONTAL: 1"= 40'



CR 1495
 PLAN & PROFILE


©TxDOT 2023 SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	26	

GEOTECHNICAL REPORT PROVIDED BY: RABA-KISTNER INC.


380

BORING HOLE: B-7
STARTING EL= 378.27'



- ① CLAY, DARK BROWN AND BROWN, VERY SANDY, WITH FERROUS STAINING (CL)
- ② CLAY, SOFT TO MEDIUM STIFF, BROWN, WITH FERROUS STAINING (CH)
- ③ CLAY, VERY SOFT, GRAY AND BROWN, WITH FERROUS STAINING (CH)
- ④ CLAY, SLIGHTLY COMPACT, GRAY AND BROWN, CLAYEY (SC)
- ⑤ CLAY, HARD TO VERY HARD, DARK GRAY WITH SAND SEAMS (CH)

BORING HOLE: B-8
STARTING EL= 378.71'



- ① CLAY, BROWN, WITH FERROUS STAINING (CL)
- ② CLAY, VERY SOFT TO STIFF, GRAY, SANDY, WITH FERROUS STAINING (CL)
- ③ CLAY, SLIGHTLY COMPACT, GRAY AND BROWN, CLAYEY (SC)
- ④ CLAY, HARD TO VERY HARD, DARK GRAY WITH SAND SEAMS (CH)

380

GWEL = -2'

370

360

350

340

330

320

310




CR 1495
BORING LOGS

DATE: 10/3/2023 5:43:16 PM
FILE: p:\txdot\projectwiseonline.com\TXDOT\Documents\01 - PAR\Design Projects\090130018\4 - Design\Plan Set\7 - Bridge\BORING LOGS

©TxDOT 2023		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	27	

DATE: 10/3/2023 5:49:12 PM
 FILE: p:\t\tdot\projectwiseonline.com\TXDOT2\Documents\01 - PAR\Design Projects\090130018\4 - Design\Plan Set\7 - Bridge\BRIDGE HYDRAULIC DATA




DRAINAGE AREA = 24.32 SQ MI

CR 1495 @ WOODBURY CREEK BRIDGE

HYDROLOGIC METHOD
 DRAINAGE AREA WAS DETERMINED BY SURVEY DATA, USGS TOPOGRAPHIC MAPS,
 DIGITAL ELEVATION MODELS AND FIELD OBSERVATIONS.
 THE PEAK FLOWS WERE DETERMINED USING THE OMEGA EM REGRESSION METHOD.

OMEGA EM REGRESSION EQUATIONS	
A (SQ MI)	25
P (IN)	44
S (FT/FT)	0.002
OMEGA	-0.015
Frequency	Discharge (cfs)
2-year	1470.78
5-year	2862.35
10-year	3880.71
25-year	5499.32
50-year	6881.71
100-year	8478.16
200-year	10239.58
250-year	10857.04
500-year	12897.43



10/06/2023
 Katie J. Vick, P.E.

Texas Department of Transportation

CR 1495
BRIDGE
HYDROLOGIC
DATA

©TXDOT 2023 SHEET 1 OF 2

CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	28	

Data use subject to license.
 ● DeLorme. Topo North America™ 10.
 www.delorme.com


MN (1.9° E)

0 1/2 1 1 1/2 2 2 1/2 mi
 Data Zoom 11-0


CK:
DW:
CK:
DN:

HEC-RAS 2 YEAR FLOOD EVENT						
RIVER STATION	EXISTING WATER SURFACE ELEVATION	PROPOSED WATER SURFACE ELEVATION	DIFFERENCE (FT)	EXISTING CHANNEL VELOCITY (FT/S)	PROPOSED CHANNEL VELOCITY (FT/S)	DIFFERENCE (FT/S)
7112	380.42	380.24	-0.18	2.06	2.31	0.25
6432	380.05	379.85	-0.2	3.1	2.87	-0.23
5617	379.56	379.45	-0.11	2.4	2.16	-0.24
5276	379.38	379.26	-0.12	2.31	2.44	0.13
4964	379.28	379.14	-0.14	1.56	1.69	0.13
4445	379.19	379.03	-0.16	1.44	1.54	0.1
4240	379.13	378.96	-0.17	1.38	1.46	0.08
4016	379.08	378.9	-0.18	1.74	1.93	0.19
3134	378.82	378.52	-0.3	2.22	2.64	0.42
3069	378.77	378.43	-0.34	2.48	3.09	0.61
3042	BRIDGE					
3019	378.31	378.31	0	3.13	3.13	0
2802	378.19	378.19	0	2.24	2.24	0
2512	378.02	378.02	0	2.79	2.79	0
2257	377.73	377.73	0	2.6	2.6	0
1972	377.48	377.48	0	2.94	2.94	0
1673	377.23	377.23	0	2.66	2.66	0
1409	376.74	376.74	0	3.75	3.75	0
1240	376.4	376.4	0	3	3	0
973	375.94	375.94	0	2.49	2.49	0


RIVER STATION	EXISTING WATER SURFACE ELEVATION	PROPOSED WATER SURFACE ELEVATION	DIFFERENCE (FT)	EXISTING CHANNEL VELOCITY (FT/S)	PROPOSED CHANNEL VELOCITY (FT/S)	DIFFERENCE (FT/S)
7112	383.29	383.28	-0.01	3.59	3.59	0
6432	382.99	382.99	0	3.42	3.43	0.01
5617	382.69	382.68	-0.01	3.27	3.28	0.01
5276	382.54	382.53	-0.01	3.1	3.11	0.01
4964	382.38	382.37	-0.01	2.8	2.81	0.01
4445	382.2	382.19	-0.01	2.85	2.86	0.01
4240	382.03	382.02	-0.01	3.13	3.14	0.01
4016	381.91	381.9	-0.01	3.32	3.33	0.01
3134	381.36	381.34	-0.02	4.52	4.55	0.03
3069	381.26	381.24	-0.02	4.83	4.87	0.04
3042	BRIDGE					
3019	381.16	381.16	0	5.48	5.48	0
2802	381.04	381.04	0	3.61	3.61	0
2512	380.84	380.84	0	4.53	4.53	0
2257	380.46	380.46	0	4.06	4.06	0
1972	380.18	380.18	0	4.29	4.29	0
1673	379.9	379.9	0	3.77	3.77	0
1409	379.35	379.35	0	5.31	5.31	0
1240	378.88	378.88	0	4.87	4.87	0
973	378.39	378.39	0	3.8	3.8	0




HEC-RAS WATER SURFACE PROFILES



SECTION AT DOWNSTREAM FACE RIVER STA. 3042



HEC-RAS CROSS-SECTION LAYOUT



10/06/2023

Katie J. Vick, P.E.



CR 1495

BRIDGE
HYDRAULIC
DATA

© TxDOT2023		SHEET 2 OF 2	
CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	29	



DATE: 10/3/2023 8:21:08 PM

FILE: p:\t\dot\project\seonline.com\TXDOT2\Documents\01 - PAR\Design Projects\090130018\4 - Design\Plan Set\7 - Bridge\BRIDGE HYDRAULIC DATA

NOTES:

1. THE EXISTING AND PROPOSED WATER SURFACE ELEVATIONS WERE COMPUTED USING HEC-RAS 6.2
2. THE PROPOSED BRIDGE CONDITIONS WERE MODELED IN HEC-RAS USING THE ENERGY (STANDARD STEP) METHOD FOR LOW FLOW AND THE PRESSURE AND/OR WEIR METHOD FOR HIGH FLOW. THE REACH BOUNDARY CONDITIONS WERE ESTABLISHED BY CALCULATING A NORMAL DEPTH BASED ON THE CHANNEL SLOPE OF 0.0018 UPSTREAM AND DOWNSTREAM.
3. THIS SITE LIES WITHIN A FEMA FLOOD HAZARD AREA (ZONE A) AS SHOWN ON FEMA FLOOD INSURANCE MAP 488379C0115D, EFFECTIVE DATE 4/17/2012
4. COORDINATION WITH THE RAINS COUNTY FLOODPLAIN ADMINISTRATOR WAS COMPLETED ON XX/XX/2023

DATE: 10/04/2023 4:59:12 PM
 FILE: \\txdot-project\seonline.com\TXDOT\Documents\01 - PAR\Design Projects\090130018\4 - Design\Plan_Sets\1 - General\BRIDGE_LAYOUT.dgn



HYDRAULIC DATA

Q(2) = 1470.78 CFS
 V(2) = 3.09 FPS
 Q(100) = 8478.16 CFS
 V(100) = 4.87 FPS

BRIDGE DATA

DESIGN SPEED: 15 MPH (MOIEC)
 AADT(2041): 48
 FUNCTIONAL CLASS: LOCAL LEVEL TERRAIN

EXISTING STRUCTURE:

NBI# 01-190-AA02-58-001
 STA: 4+73 - 5+23
 50' SINGLE SPAN CONCRETE DECK W/ STEEL SUBSTRUCTURE

PROPOSED STRUCTURE:

NBI# 01-190-AA14-95-001
 STA: 4+60 - 5+35
 75' SINGLE SPAN Tx28 PRESTRESSED CONCRETE I-GIRDER 3:1 ABUTMENT SLOPE

BENCHMARK


NAIL IN TREE
 STA: 5+24
 OFFSET 13.66' RT
 EL = 379.685'

NOTES:

DRILLED SHAFTS SHALL BE FOUNDED AT THE ELEVATION SHOWN OR DEEPER AS NECESSARY TO OBTAIN A MINIMUM OF TWO SHAFT DIAMETERS PENETRATION INTO HARD CLAY
 IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL DIMENSIONS PRIOR TO ORDERING MATERIALS
 DESIGNED ACCORDING TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS 9TH EDITION (2020) AND TXDOT BRIDGE DESIGN MANUAL (NOV 2021)
 "D" DENOTES DOWELED END CONNECTION

HL93 LOADING:
 SUPERSTRUCTURE INV/OPR RATINGS: 1.37/1.77

REFER TO PROFILE AND PROFILE SHEETS FOR CONTROL POINTS
 SCALE:
 VERTICAL: 1" = 20'
 HORIZONTAL: 1" = 20'



410
405
400
395
390
385
380
375
370
365
360
355
350
345
340
335
330

STATE OF TEXAS

MONTE L. RATER

95859

PROFESSIONAL ENGINEER

10.05.23

Monte R. Rater P.E.

Texas Department of Transportation

CR 1495

BRIDGE LAYOUT

© TXDOT 2023		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	30	


DATE: 10/4/2023 8:56:18 PM
 FILE: p:\txdot\projectwiseonline.com\TXDOT2\Documents\01 - PAR\Design Projects\090130018\4 - Design\Plan Set\7 - Bridge\BRIDGE QUANTITIES AND BEARING SEAT ELEVATIONS

DW: CK: DW: CK:

SUMMARY OF BRIDGE ITEMS							
LOCATION	400 6005	416 6004	420 6013	422 6001	425 6035	432 6033	450 6019
	CEM STABIL BKFL	DRILL SHAFT (36 IN)	CL C CONC (ABUT)	REINF CONC SLAB	PRESTR CONC GIRDER (TX28)	RIPRAP (STONE PROTECTI ON)(18 IN)	RAIL (TY T631LS)
	CY	LF	CY	SF	LF	CY	LF
STA. 4+60 - 5+25	72	336	37.6	1950	298	186	198
BRIDGE TOTALS-	72	336	37.6	1950	298	186	198

BEARING SEAT ELEVATIONS (FT)

ABUT 1 (FWD)	GIRDER 1 376.068	GIRDER 2 376.201	GIRDER 3 376.201	GIRDER 4 376.068
ABUT 2 (BK)	GIRDER 1 376.068	GIRDER 2 376.201	GIRDER 3 376.201	GIRDER 4 376.068



10.05.23

Monte R. Rater P.E.

Texas Department of Transportation


CR 1495
BRIDGE QUANTITIES
AND
BEARING SEAT
ELEVATIONS

©2023 SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
0901	30	018	CR
DIST	COUNTY	SHEET NO.	
PAR	RAINS	31	


10/4/2023 8:35:20 PM
 DATE: 10/4/2023 8:35:20 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\1 AIG-24.dgn

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



SHOWING DRILLED SHAFTS SHOWING PILES


PLAN 1



SHOWING DRILLED SHAFTS SHOWING PILES


ELEVATION

Header Slope	Girder Type	Wingwall Type	Wingwall Lgth "WL"
2:1	Tx28	Cantilevered	8.000'
	Tx34	Cantilevered	9.000'
	Tx40	Cantilevered	10.000'
	Tx46	Cantilevered	11.000'
3:1	Tx54	Cantilevered	12.000'
	Tx28	Cantilevered	12.000'
	Tx34	Founded	13.000'
	Tx40	Founded	15.000'
	Tx46	Founded	16.000'
	Tx54	Founded	18.000'




BEARING SEAT DETAIL

(Bearing surface must be clean and free of all loose material before placing bearing pad.)



SECTION A-A

(With approach slab) 6



BACKWALL DETAIL

(Without approach slab) 6

TABLE OF FOUNDATION LOADS

Span Length	All Girder Types	
	Tons/Shaft	Tons/Pile
40	64	54
45	69	56
50	73	59
55	77	61
60	81	63
65	85	65
70	88	67
75	92	69
80	96	71
85	100	73
90	104	75
95	108	77
100	111	79
105	115	80
110	119	82
115	123	84
120	126	86
125	130	88

- 1 See Table A for variable dimensions based on header slope and girder type.
- 2 See Table A to determine if wingwall foundations are required.
- 3 For piling larger than 16" adjust Bars S spacing as required to avoid piling.
- 4 Increase as required to maintain 3" from finished grade.
- 5 See Span details for "y" value.
- 6 See Bridge Layout to determine if approach slab is present.
- 7 Omit Dowels D at end of multi-span unit. Adjust reinforcing steel total accordingly.
- 8 With pile foundations, move Bars A shown to clear piles.
- 9 Spacing based on girder type:
 Tx28 ~ 3 spaces at 1'-0" Max
 Tx34 ~ 3 spaces at 1'-0" Max
 Tx40 ~ 4 spaces at 1'-0" Max
 Tx46 ~ 4 spaces at 1'-0" Max
 Tx54 ~ 5 spaces at 1'-0" Max
- 10 Field bend as needed to clear piles.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 See Bridge Layout for header slope and foundation type, size and length.
 See Common Foundation Details (FD) standard sheet for all foundation details and notes.
 See Concrete Riprap (CRR) standard sheet or Stone Riprap (SRR) standard sheet for riprap attachment details, if applicable.
 See applicable rail details for rail anchorage in wingwalls.
 These abutment details may be used with standard SIG-24 only.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

MATERIAL NOTES:
 Provide Class C concrete (f'c = 3,600 psi).
 Provide Class C (HPC) concrete if shown elsewhere in the plans.
 Provide Grade 60 reinforcing steel.
 Galvanize dowel bars D.

HL93 LOADING SHEET 1 OF 3





ABUTMENTS
 TYPE TX28 THRU TX54
 PRESTR CONC I-GIRDERS
 24' ROADWAY

AIG-24

FILE:	DN: TAR	CK: KCM	DW: JTR	CK: TAR
©TxDOT August 2017	CON: 0901	SECT: 30	JOB: 018	HIGHWAY: CR
REVISIONS:	DIST: PAR	COUNTY: RAINS	SHEET NO. 32	

Bridge Division Standard

DATE: 10/4/2023 8:35:22 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\1 AIG-24.dgn
 DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- ⑤ See Span details for "y" value.
- ⑨ Spacing based on girder type:
 Tx28 ~ 3 spaces at 1'-0" Max
 Tx34 ~ 3 spaces at 1'-0" Max
 Tx40 ~ 4 spaces at 1'-0" Max
 Tx46 ~ 4 spaces at 1'-0" Max
 Tx54 ~ 5 spaces at 1'-0" Max
- ⑩ Field bend as needed to clear piles.
- ⑪ Adjust as required to avoid piling.

HL93 LOADING

SHEET 2 OF 3

		Bridge Division Standard		
ABUTMENTS TYPE TX28 THRU TX54 PRESTR CONC I-GIRDERS 24' ROADWAY				
AIG-24				
FILE:	DN: TAR	CK: KCM	DW: JTR	CK: TAR
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
DIST	COUNTY		SHEET NO.	
PAR	RAINS		33	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:23 PM
 FILE: T:\PARTPDD\CR_1495 @ Woodbury Creek Bridge Replacement\Des\gn\CAD_Standards\03 BRIDGE STANDARDS\1_AIG-24.dgn

TABLES OF ESTIMATED QUANTITIES WITH 2:1 HEADER SLOPE ⁽¹²⁾



TYPE Tx28 Girders					TYPE Tx34 Girders					TYPE Tx40 Girders					TYPE Tx46 Girders					TYPE Tx54 Girders									
Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight					
A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328					
D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11					
H	8	#6	25'-8"	308	H	8	#6	25'-8"	308	H	10	#6	25'-8"	386	H	10	#6	25'-8"	386	H	12	#6	25'-8"	463					
L	18	#6	4'-0"	108	L	18	#6	4'-0"	108	L	18	#6	4'-0"	108	L	18	#6	4'-0"	108	L	18	#6	4'-0"	108					
S	22	#5	11'-6"	264	S	22	#5	11'-6"	264	S	22	#5	11'-6"	264	S	22	#5	11'-6"	264	S	22	#5	11'-6"	264					
U	4	#6	8'-1"	49	U	4	#6	8'-1"	49	U	4	#6	8'-1"	49	U	4	#6	8'-1"	49	U	4	#6	8'-1"	49					
V	25	#5	11'-4"	296	V	25	#5	12'-4"	322	V	25	#5	13'-4"	348	V	25	#5	14'-4"	374	V	25	#5	15'-8"	409					
wH1	14	#6	9'-5"	198	wH1	14	#6	10'-5"	219	wH1	14	#6	11'-5"	240	wH1	14	#6	12'-5"	261	wH1	14	#6	13'-5"	282					
wH2	20	#6	7'-8"	230	wH2	20	#6	8'-8"	260	wH2	24	#6	9'-8"	348	wH2	24	#6	10'-8"	385	wH2	28	#6	11'-8"	491					
wS	18	#4	7'-10"	94	wS	20	#4	7'-10"	105	wS	22	#4	7'-10"	115	wS	24	#4	7'-10"	126	wS	26	#4	7'-10"	136					
wV	18	#5	11'-4"	213	wV	20	#5	12'-4"	257	wV	22	#5	13'-4"	306	wV	24	#5	14'-4"	359	wV	26	#5	15'-8"	425					
Reinforcing Steel				Lb	3,099	Reinforcing Steel				Lb	3,231	Reinforcing Steel				Lb	3,503	Reinforcing Steel				Lb	3,651	Reinforcing Steel				Lb	3,966
Class "C" Concrete				CY	15.2	Class "C" Concrete				CY	16.6	Class "C" Concrete				CY	18.1	Class "C" Concrete				CY	19.7	Class "C" Concrete				CY	21.6

TABLES OF ESTIMATED QUANTITIES WITH 3:1 HEADER SLOPE ⁽¹²⁾

TYPE Tx28 Girders					TYPE Tx34 Girders					TYPE Tx40 Girders					TYPE Tx46 Girders					TYPE Tx54 Girders									
Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight	Bar	No.	Size	Length	Weight					
A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328	A	10	#11	25'-0"	1,328					
D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11	D ⁽⁷⁾	2	#9	1'-8"	11					
H	8	#6	25'-8"	308	H	8	#6	25'-8"	308	H	10	#6	25'-8"	386	H	10	#6	25'-8"	386	H	12	#6	25'-8"	463					
L	18	#6	4'-0"	108	L	18	#6	4'-0"	108	L	18	#6	4'-0"	108	L	18	#6	4'-0"	108	L	18	#6	4'-0"	108					
S	22	#5	11'-6"	264	S	22	#5	11'-6"	264	S	22	#5	11'-6"	264	S	22	#5	11'-6"	264	S	22	#5	11'-6"	264					
U	4	#6	8'-1"	49	U	4	#6	8'-1"	49	U	4	#6	8'-1"	49	U	4	#6	8'-1"	49	U	4	#6	8'-1"	49					
V	25	#5	11'-4"	296	V	25	#5	12'-4"	322	V	25	#5	13'-4"	348	V	25	#5	14'-4"	374	V	25	#5	15'-8"	409					
wH1	14	#6	13'-5"	282	wH1	14	#6	14'-5"	303	wH1	14	#6	16'-5"	345	wH1	14	#6	17'-5"	366	wH1	14	#6	19'-5"	408					
wH2	20	#6	11'-8"	350	wH2	20	#6	12'-8"	381	wH2	24	#6	14'-8"	529	wH2	24	#6	15'-8"	565	wH2	28	#6	17'-8"	743					
wS	26	#4	7'-10"	136	wS	28	#4	7'-10"	147	wS	32	#4	7'-10"	167	wS	34	#4	7'-10"	178	wS	38	#4	7'-10"	199					
wV	26	#5	11'-4"	307	wV	28	#5	12'-4"	360	wV	32	#5	13'-4"	445	wV	34	#5	14'-4"	508	wV	38	#5	15'-8"	621					
Reinforcing Steel				Lb	3,439	Reinforcing Steel				Lb	3,581	Reinforcing Steel				Lb	3,980	Reinforcing Steel				Lb	4,137	Reinforcing Steel				Lb	4,603
Class "C" Concrete				CY	17.8	Class "C" Concrete				CY	19.3	Class "C" Concrete				CY	21.7	Class "C" Concrete				CY	23.4	Class "C" Concrete				CY	26.4


⁽⁷⁾ Omit Dowels D at end of multi-span unit. Adjust reinforcing steel total accordingly.

⁽¹²⁾ Quantities shown are for one abutment only (with approach slab). With no approach slab, add 1.0 CY Class "C" concrete and 154 lbs reinforcing steel for 4 additional Bars H.


 Texas Department of Transportation				Bridge Division Standard	
ABUTMENTS TYPE TX28 THRU TX54 PRESTR CONC I-GIRDERS 24' ROADWAY					
AIG-24					
FILE:	DN: TAR	CK: KCM	DW: JTR	CK: TAR	
 August 2017	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0901	30	018	CR	
	DIST	COUNTY	SHEET NO.		
PAR		RAINS			34

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES\$
FILE: \$FILES\$



PLAN 1



TYPICAL TRANSVERSE SECTION
(Showing girder type Tx46)

TABLE OF SECTION DEPTHS	
GIRDER TYPE	"Y" AT \bar{C} BRG (3)
	Ft/In
Tx28	3'-4"
Tx34	3'-10"
Tx40	4'-4"
Tx46	4'-10"
Tx54	5'-6"

BAR TABLE

BAR	SIZE
A	#4
D	#4
G	#4
H	#4
J	#4
M	#4
OA	#5
P	#4
T	#4

- 1 If multi-span units (with slab continuous over interior bents) are indicated on the Bridge Layout, see standard IGCS for adjustment to slab reinforcement and quantities.
- 2 Span lengths for Prestressed Concrete I-Girder type:
Type Tx28 for spans lengths 40,000' thru 75,000'.
Type Tx34 for spans lengths 40,000' thru 85,000'.
Type Tx40 for spans lengths 40,000' thru 100,000'.
Type Tx46 for spans lengths 40,000' thru 115,000'.
Type Tx54 for spans lengths 40,000' thru 125,000'.
- 3 "Y" value shown is based on theoretical girder camber, dead load deflection from an 8 1/2" concrete slab, a constant roadway grade, and using precast panels (PCP). The Contractor will adjust this value as necessary for any roadway vertical curve.

HL93 LOADING SHEET 1 OF 2



PRESTRESSED CONCRETE I-GIRDER SPANS (TYPE Tx28 THRU Tx54) 24' ROADWAY

SIG-24


FILE:	DN: JMH	CK: NRN	DW: JTR	CK: TAR
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-19: Increased "X" and "Y" Values. 01-23: Removed PCP(O) reference.	DIST	COUNTY	SHEET NO.	
PAR	RATNS	35		

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard by the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES\$
FILE: \$FILES\$
\$TIME\$

TABLE OF DEAD LOAD DEFLECTIONS

TYPE Tx28 GIRDERS			TYPE Tx34 GIRDERS			TYPE Tx40 GIRDERS			TYPE Tx46 GIRDERS			TYPE Tx54 GIRDERS		
SPAN LENGTH	"A"	"B"	SPAN LENGTH	"A"	"B"	SPAN LENGTH	"A"	"B"	SPAN LENGTH	"A"	"B"	SPAN LENGTH	"A"	"B"
Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft	Ft
40	0.007	0.010	40	0.004	0.006	40	0.003	0.004	40	0.002	0.003	40	0.001	0.002
45	0.012	0.017	45	0.007	0.010	45	0.005	0.007	45	0.004	0.005	45	0.002	0.003
50	0.019	0.027	50	0.011	0.016	50	0.007	0.010	50	0.005	0.007	50	0.004	0.005
55	0.028	0.040	55	0.017	0.024	55	0.011	0.016	55	0.008	0.011	55	0.005	0.007
60	0.041	0.057	60	0.024	0.034	60	0.016	0.022	60	0.011	0.015	60	0.007	0.010
65	0.056	0.079	65	0.033	0.047	65	0.022	0.031	65	0.015	0.021	65	0.010	0.014
70	0.077	0.108	70	0.046	0.064	70	0.030	0.042	70	0.021	0.029	70	0.014	0.019
75	0.102	0.143	75	0.061	0.085	75	0.040	0.056	75	0.027	0.038	75	0.018	0.025
			80	0.079	0.111	80	0.052	0.073	80	0.036	0.050	80	0.024	0.033
			85	0.102	0.143	85	0.066	0.093	85	0.046	0.064	85	0.030	0.042
						90	0.084	0.118	90	0.057	0.080	90	0.038	0.053
						95	0.105	0.147	95	0.071	0.100	95	0.047	0.066
						100	0.130	0.182	100	0.088	0.124	100	0.058	0.082
									105	0.108	0.151	105	0.071	0.100
									110	0.130	0.182	110	0.086	0.121
									115	0.156	0.219	115	0.103	0.144
									120			120	0.123	0.172
									125			125	0.145	0.203



DEAD LOAD DEFLECTION DIAGRAM

Calculated deflections shown are due to the concrete slab on interior girders only (Ec = 5000 ksi). Adjust values as required for exterior girders and if optional slab forming is used. These values may require field verification.

TABLE OF ESTIMATED QUANTITIES

SPAN LENGTH	REINF CONCRETE SLAB	Prestressed Concrete Girders			TOTAL REINF STEEL ⁵
		ABUT TO INT BT ⁴	INT BT TO INT BT ⁴	ABUT TO ABUT ⁴	
Ft	SF	LF	LF	LF	Lb
40	1,040	158.00	158.00	158.00	2,392
45	1,170	178.00	178.00	178.00	2,691
50	1,300	198.00	198.00	198.00	2,990
55	1,430	218.00	218.00	218.00	3,289
60	1,560	238.00	238.00	238.00	3,588
65	1,690	258.00	258.00	258.00	3,887
70	1,820	278.00	278.00	278.00	4,186
75	1,950	298.00	298.00	298.00	4,485
80	2,080	318.00	318.00	318.00	4,784
85	2,210	338.00	338.00	338.00	5,083
90	2,340	358.00	358.00	358.00	5,382
95	2,470	378.00	378.00	378.00	5,681
100	2,600	398.00	398.00	398.00	5,980
105	2,730	418.00	418.00	418.00	6,279
110	2,860	438.00	438.00	438.00	6,578
115	2,990	458.00	458.00	458.00	6,877
120	3,120	478.00	478.00	478.00	7,176
125	3,250	498.00	498.00	498.00	7,475

- ⁴ Fabricator will adjust lengths for girder slopes as required.
- ⁵ Reinforcing steel weight is calculated using an approximate factor of 2.3 lbs/SF.

MATERIAL NOTES:
 Provide Class 5 concrete (f'c = 4,000 psi).
 Provide Class 5 (HPC) concrete if shown elsewhere in the plans.
 Provide Grade 60 reinforcing steel.
 Provide bar laps, where required, as follows:
 Uncoated ~ #4 = 1'-7"
 Epoxy coated ~ #4 = 2'-5"
 Deformed welded wire reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars A, D, OA, P or T unless noted otherwise.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Multi-span units, with slab continuous over interior bents, may be formed with the details shown on this sheet and the I-Girder Continuous Slab Detail (IGCS) standard.
 See I-Girder Thickened Slab End Details (IGTS) standard for details and quantity adjustments.
 See Prestressed Concrete Panels (PCP) standard and Prestressed Concrete Panel Fabrication Details (PCP-FAB) standard for panel details not shown.
 See I-Girder Miscellaneous Slab Details (IGMS) standard for miscellaneous details.
 See applicable rail details for rail anchorage in slab.
 See Permanent Metal Deck Forms (PMDF) standard for details and quantity adjustments if this option is used.
 This standard does not support the use of transition bents.

Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING SHEET 2 OF 2

Texas Department of Transportation Bridge Division Standard

PRESTRESSED CONCRETE I-GIRDER SPANS (TYPE Tx28 THRU Tx54) 24' ROADWAY

SIG-24

FILE:	DN: JMH	CK: NRN	DW: JTR	CK: TAR
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-19: Increased "X" and "Y" Values. 01-23: Removed PCP(O) reference.	DIST	COUNTY	SHEET NO.	
PAR	RAINS		36	


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard by TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/5/2023 3:06:03 PM
 FILE: T:\PARTIPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\IGSD-24.dgn

STRUCTURE	DESIGNED GIRDERS									DEPRESSED STRAND PATTERN		CONCRETE		OPTIONAL DESIGN					LOAD RATING FACTORS			NON-STANDARD STRAND PATTERNS	
	SPAN NO.	GIRDER NO.	GIRDER TYPE	PRESTRESSING STRANDS					NO.			TO END (in)	RELEASE STRGTH (1) f'ci (ksi)	MINIMUM 28 DAY COMP STRGTH f'c (ksi)	DESIGN LOAD COMP STRESS (TOP ̵) (SERVICE I) fct(ksi)	DESIGN LOAD TENSILE STRESS (BOT ̵) (SERVICE III) fcb(ksi)	REQUIRED MINIMUM ULTIMATE MOMENT CAPACITY (STRENGTH I) (kip-ft)	LIVE LOAD DISTRIBUTION FACTOR (2)		STRENGTH I			
				NON-STD STRAND PATTERN	TOTAL NO.	SIZE (in)	STRGTH fpu (ksi)	"e" ̵ (in)		"e" END (in)	Moment							Shear	Inv	Opr	Inv		
Type Tx54 Girders 24' Roadway 8.5" Slab	40	ALL	Tx54		8	0.6	270	21.01	21.01			4.000	5.000	0.511	-0.578	1798	0.770	0.800	2.05	2.66	3.76		
	45	ALL	Tx54		10	0.6	270	21.01	21.01			4.000	5.000	0.636	-0.703	2126	0.740	0.800	2.24	2.90	3.69		
	50	ALL	Tx54		12	0.6	270	21.01	21.01			4.000	5.000	0.781	-0.850	2533	0.720	0.810	1.81	2.35	2.91		
	55	ALL	Tx54		12	0.6	270	21.01	21.01			4.000	5.000	0.938	-1.007	2951	0.700	0.810	1.90	2.46	2.79		
	60	ALL	Tx54		12	0.6	270	21.01	21.01			4.000	5.000	1.108	-1.173	3271	0.680	0.810	1.60	2.07	2.25		
	65	ALL	Tx54		14	0.6	270	21.01	21.01			4.000	5.000	1.285	-1.348	3547	0.670	0.810	1.66	2.16	2.16		
	70	ALL	Tx54		14	0.6	270	21.01	21.01			4.000	5.000	1.482	-1.540	3502	0.660	0.820	1.41	1.82	1.73		
	75	ALL	Tx54		16	0.6	270	20.76	20.26	4	6.5	4.000	5.000	1.689	-1.733	3745	0.640	0.820	1.47	1.91	1.66		
	80	ALL	Tx54		16	0.6	270	20.76	20.76			4.000	5.000	1.912	-1.944	4001	0.630	0.820	1.26	1.63	1.30		
	85	ALL	Tx54		18	0.6	270	20.56	19.67	4	8.5	4.000	5.000	2.148	-2.166	4406	0.620	0.820	1.07	1.39	1.00		
	90	ALL	Tx54		20	0.6	270	20.41	19.21	4	10.5	4.000	5.000	2.379	-2.384	4806	0.610	0.820	1.33	1.73	1.16		
	95	ALL	Tx54		22	0.6	270	20.28	18.46	4	14.5	4.000	5.000	2.639	-2.624	5234	0.600	0.820	1.35	1.75	1.07		
	100	ALL	Tx54		26	0.6	270	20.08	16.39	4	28.5	4.000	5.000	2.896	-2.871	5699	0.600	0.830	1.52	1.97	1.14		
	105	ALL	Tx54		30	0.6	270	19.81	12.21	6	44.5	4.000	5.000	3.180	-3.130	6153	0.590	0.830	1.51	1.96	1.02		
	110	ALL	Tx54		32	0.6	270	19.63	11.38	6	50.5	4.100	5.000	3.477	-3.400	6619	0.580	0.830	1.63	2.12	1.03		
115	ALL	Tx54		36	0.6	270	19.34	12.01	6	50.5	4.700	5.500	3.786	-3.679	7096	0.570	0.830	1.60	2.07	1.00			
120	ALL	Tx54		38	0.6	270	19.22	13.22	6	44.5	5.200	6.100	4.116	-3.985	7646	0.570	0.830	1.65	2.14	1.01			
125	ALL	Tx54		42	0.6	270	19.01	12.72	6	50.5	5.600	6.600	4.415	-4.257	8113	0.560	0.830	1.71	2.24	1.09			
Type Tx62 Girders 24' Roadway 8.5" Slab	60	ALL	Tx62		12	0.6	270	25.78	25.78			4.000	5.000	0.878	-0.986	3525	0.700	0.800	1.81	2.35	2.73		
	65	ALL	Tx62		12	0.6	270	25.78	25.78			4.000	5.000	1.016	-1.133	3847	0.690	0.800	1.89	2.45	2.64		
	70	ALL	Tx62		14	0.6	270	25.78	25.78			4.000	5.000	1.171	-1.293	4173	0.680	0.810	1.61	2.08	2.16		
	75	ALL	Tx62		14	0.6	270	25.78	25.78			4.000	5.000	1.332	-1.455	4132	0.660	0.810	1.68	2.18	2.10		
	80	ALL	Tx62		16	0.6	270	25.53	25.53			4.000	5.000	1.506	-1.633	4429	0.650	0.810	1.45	1.88	1.72		
	85	ALL	Tx62		16	0.6	270	25.53	25.53			4.000	5.000	1.691	-1.819	4610	0.640	0.810	1.24	1.61	1.37		
	90	ALL	Tx62		16	0.6	270	25.53	25.53			4.000	5.000	1.885	-2.013	5051	0.630	0.810	1.29	1.68	1.31		
	95	ALL	Tx62		20	0.6	270	25.18	24.78	4	6.5	4.000	5.000	2.081	-2.209	5493	0.620	0.820	1.11	1.44	1.02		
	100	ALL	Tx62		22	0.6	270	25.05	23.96	4	10.5	4.000	5.000	2.295	-2.420	5959	0.610	0.820	1.16	1.50	1.01		
	105	ALL	Tx62		24	0.6	270	24.94	23.28	4	14.5	4.000	5.000	2.514	-2.642	6475	0.610	0.820	1.37	1.78	1.10		
	110	ALL	Tx62		26	0.6	270	24.85	22.70	4	18.5	4.000	5.000	2.723	-2.850	6936	0.600	0.820	1.39	1.80	1.03		
	115	ALL	Tx62		30	0.6	270	24.58	17.78	6	40.5	4.000	5.000	2.963	-3.083	7440	0.590	0.820	1.56	2.02	1.09		
	120	ALL	Tx62		34	0.6	270	24.25	15.07	6	58.5	4.200	5.000	3.213	-3.325	7957	0.580	0.820	1.55	2.01	1.00		
	125	ALL	Tx62		36	0.6	270	24.11	17.11	6	48.5	4.700	5.600	3.480	-3.591	8551	0.580	0.820	1.64	2.13	1.04		
	130	ALL	Tx62		40	0.6	270	23.88	16.68	6	54.5	5.100	6.100	3.733	-3.836	9072	0.570	0.820	1.52	2.09	1.02		
135	ALL	Tx62		42	0.6	270	23.78	16.35	6	58.5	5.300	6.300	4.002	-4.104	9676	0.570	0.830	1.61	2.18	1.05			

(1) Based on the following allowable stresses (ksi):
 Compression = 0.65 f'ci
 Tension = 0.24 √ f'ci
 Optional designs must likewise conform.

(2) Portion of full HL93.



HL93 LOADING SHEET 2 OF 2


Texas Department of Transportation
 Bridge Division Standard

PRESTRESSED CONCRETE I-GIRDER STANDARD DESIGNS
 24' ROADWAY

IGSD-24

FILE:	DN: EFC	CK: AJF	DW: EFC	CK: TAR
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-19: Redesigned girders. 1-21: Added load rating.	DIST	COUNTY	SHEET NO.	
	PAR	RATNS	38	

10/4/2023 8:35:29 PM
 DATE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\4 IGD.dgn
 FILE:



- ① Bundle with Bars R.
- ② Measured along ϵ Girder at interior bents; perpendicular to abutment bkwl or inverted-T stem.
- ③ The average of the top and bottom spacing of Bars R cannot exceed the required spacing.
- ④ L/20, but not less than 5'-0" (-0,+2').


GIRDER ELEVATION

- ⑥ Bars P (#6 x 15'-0") required in Tx62 and Tx70 girders. At the fabricator's option bars larger than #6 may be used. When L is less than 50 ft, Bars P are to be the same length as Bars T.
- ⑦ Bars P (#6 x 15'-0") are only required in Tx28, Tx34, Tx40, Tx46, and Tx54 girders when "e" at girder ends exceeds 0.25 x "D". At the fabricator's option bars larger than #6 may be used. When L is less than 50 ft, Bars P are to be the same length as Bars T.
- ⑧ 1 $\frac{3}{8}$ " Clear Cover to Bars S.
- ⑨ Space Bars A at 6" Max for girders requiring overhang bracket hangers. Space at 12" Max for all other girders. Tie to Bars R as necessary. See standard IGMS for "Deck Forming Notes".
- ⑩ Based on 155 pcf total weight of concrete and reinforcing steel.
- ⑪ Smooth trowel finish on the slab overhang side of exterior girder.


GIRDER DIMENSIONS AND SECTION PROPERTIES								
Girder Type	"D" (in.)	"B" (in.)	"Yt" (in.)	"Yb" (in.)	Area (in. ²)	"Ix" (in. ⁴)	"Iy" (in. ⁴)	Weight (10) (plf)
Tx28	28	6	15.02	12.98	585	52,772	40,559	630
Tx34	34	12	18.49	15.51	627	88,355	40,731	675
Tx40	40	18	21.90	18.10	669	134,990	40,902	720
Tx46	46	22	25.90	20.10	761	198,089	46,478	819
Tx54	54	30	30.49	23.51	817	299,740	46,707	880
Tx62	62	37 $\frac{1}{2}$ "	33.72	28.28	910	463,072	57,351	980
Tx70	70	45 $\frac{1}{2}$ "	38.09	31.91	966	628,747	57,579	1,040

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Provide Class H concrete.
 Provide Grade 60 reinforcing steel.
 An equal area of deformed Welded Wire Reinforcement (WWR) (ASTM A1064) may be substituted for Bars A, C, R or T unless otherwise noted.
 It is permissible for bars or strands to come in contact with materials used in forming anchor holes.
 When vertical clearance of the span is less than or equal to 20', provide additional Bars C and CH in every girder of that span.


Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.



TYPE Tx62 & Tx70



TYPE Tx46 & Tx54



TYPE Tx28, Tx34 & Tx40

HL93 LOADING SHEET 1 OF 2

Texas Department of Transportation
 Bridge Division Standard


PRESTRESSED CONCRETE I-GIRDER DETAILS

IGD

FILE: 0901	DN: TxDOT	CK: JMH	DW: JTR	CK: TAR
REVISIONS	CONT	SECT	JOB	HIGHWAY
10-19- Added Bars C and CH full length for VC<= 20'	0901	30	018	CR
3-23- Clarified C and CH requirement	DIST	COUNTY	SHEET NO.	
	PAR	RATNS		39


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:30 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\4 IGD.dgn




PLAN OF GIRDER ENDS (12)


To control top flange cracking that may occur during form removal, additional top flange reinforcing may be placed as shown in girder ends at the Fabricator's option.




OPTIONAL TOP FLANGE REINFORCING DETAIL




BARS CH (#4)




BARS C (#4)




BARS U (#5)




BARS A (#3)




OPTIONAL WELDED WIRE REINFORCEMENT (WWR) DETAIL



BARS R (#4) (16)



BARS S (#6)



BARS T (#4)

- (12) Reinforcing patterns shown are provided as guides to determine reinforcement placement in skewed ends. Place Bars S as close to girder end as cover requirements permit, which may prevent them to be bundled with Bars R.
- (13) Bars may be cut or bent at skewed end as required.
- (14) Increase as necessary for bars at skewed end.
- (15) No portion of bar less than 10 ft.
- (16) For Welded Wire Reinforcement (WWR) option, area of Bars R may be reduced in proportion to the increase in reinforcement yield strength over 60 ksi. Yield strength of WWR is limited to 75 ksi.




PRESTRESSED CONCRETE I-GIRDER DETAILS

IGD


FILE:	DN: TxDOT	CK: JMH	DW: JTR	CK: TAR
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-19: Added Bars C and CH full length for VC<= 20'	DIST	COUNTY	SHEET NO.	
3-23: Clarified C and CH requirement	PAR	RATNS	40	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:35:32 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Desi\gn\CAD_Standards\03 BRIDGE STANDARDS\5 IGEB.dgn



AT INVERTED-T BENT W/SKEW




AT CONVENTIONAL INTERIOR BENT W/SKEW




AT ABUTMENT W/SKEW³


- ① Dowel at doweled girder end [labeled (D) on Bridge Layout]. Required for outside girder only or as shown on substructure details.
- ② For purposes of computing bearing seat elevations, nominal centerline of bearing must be defined as shown. The actual center of bearing pad may vary from this line.
- ③ For transition bents with backwall, girder and elastomeric bearings must receive the same treatment as shown for abutments.
- ④ When angle exceeds 0°, one or both girders ends must be skewed to maintain the clearance between girder ends as shown in view.
- ⑤ See Table of Bearing Pad Dimensions for bearing size. Girder end skew angles in Table not applicable for this situation. Table reflects girder conflicts of this type on radial bents only.



AT INVERTED-T BENT





AT CONVENTIONAL INTERIOR BENT




AT ABUTMENT³

GENERAL NOTES:
 These details accommodate skew angles up to 60°. Shop drawings for approval are required. A bearing layout which identifies location and orientation of all bearings must be developed by the bearing fabricator. Permanently mark each bearing in accordance with the bearing layout. A copy of the bearing layout is to be provided to the Engineer. Cost of furnishing and installing elastomeric bearings, including beveled and embedded steel plates, must be included in unit price bid for "Prestressed Concrete Girders".

GIRDER END DETAILS



GIRDER CONFLICT DETAILS



HL93 LOADING SHEET 1 OF 3


Texas Department of Transportation
 Bridge Division Standard

**ELASTOMERIC BEARING AND GIRDER END DETAILS
 PRESTR CONCRETE I-GIRDERS**

IGEB

FILE:	DN: AEE	CK: JMH	DW: JTR	CK: TxDOT
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
DIST	COUNTY		SHEET NO.	
PAR	RAINS		41	


10/4/2023 8:35:33 PM
 DATE: 10/4/2023 8:35:33 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\5 IGEB.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




LAMINATED ELASTOMERIC BEARING PAD
(50 DUROMETER)

Girder Type	Abutments	Int Bents	Inv-T Bents
	Face of Bkwl to Face of Cap	Overall Cap Width	Corbel Width
Tx28 thru Tx54	1'-9"	3'-6"	1'-10 1/2"
Tx62 & Tx70	2'-0"	4'-0"	2'-1 1/2"

Bent Type	Girder Type	Bearing Type (13)	Girder End Skew Angle Range	Pad Size Lgth x Wdth	Pad Clip Dimensions	
					"A"	"B"
ABUTMENTS, INVERTED-T AND TRANSITION BENTS WITH BACKWALLS	Tx28, Tx34, Tx40, Tx46 & Tx54	G-1-"N"	0° thru 21°	8" x 21"	---	---
		G-2-"N"	21°+ thru 30°	8" x 21"	1 1/2"	2 1/2"
		G-3-"N"	30°+ thru 45°	9" x 21"	4 1/2"	4 1/2"
		G-4-"N"	45°+ thru 60°	15" Dia	---	---
	Tx62 & Tx70	G-5-"N"	0° thru 21°	9" x 21"	---	---
		G-6-"N"	21°+ thru 30°	9" x 21"	1 1/2"	2 1/2"
		G-7-"N"	30°+ thru 45°	10" x 21"	4 1/2"	4 1/2"
		G-8-"N"	45°+ thru 60°	10" x 21"	7 1/4"	4 1/4"
CONVENTIONAL INTERIOR BENTS	Tx28, Tx34, Tx40, Tx46 & Tx54	---	---	---	---	---
	Tx62 & Tx70	G-5-"N"	0° thru 60°	9" x 21"	---	---
CONVENTIONAL INTERIOR BENTS WITH SKEWED GIRDER ENDS (GIRDER CONFLICTS) (16)	Tx28, Tx34, Tx40, Tx46 & Tx54	G-1-"N"	0° thru 18°	8" x 21"	---	---
		G-2-"N"	18°+ thru 30°	8" x 21"	1 1/2"	2 1/2"
		G-9-"N"	30°+ thru 45°	8" x 21"	3"	3"
		G-10-"N"	45°+ thru 60°	9" x 21"	6"	3 1/2"
	Tx62 & Tx70	G-5-"N"	0° thru 18°	9" x 21"	---	---
		G-5-"N"	18°+ thru 30°	9" x 21"	---	---
		G-11-"N"	30°+ thru 45°	9" x 21"	1 1/2"	1 1/2"
G-12-"N"	45°+ thru 60°	9" x 21"	3"	1 3/4"		



ROUND BEARINGS FOR SKEWED GIRDER ENDS AT FACE OF INVERTED-T STEM OR FACE OF BKWL



SKEWED GIRDER ENDS AT INT BENTS, FACE OF INVERTED-T STEM OR FACE OF BKWL

SKEWED GIRDER ENDS AT CONVENTIONAL INTERIOR BENTS (NO GIRDER DOWELS)

BEARING PAD PLACEMENT DIAGRAMS

- (2) For purposes of computing bearing seat elevations, nominal centerline of bearing must be defined as shown. The actual center of bearing pad may vary from this line.
- (6) 3" for inverted-T.
- (7) Place centerline pad as near nominal centerline bearing as possible between limits shown.
- (8) Girder end skew angle is equal to 90° minus the girder angle except at some conflicting girders.
- (9) Provide 2" dia hole only at locations required. See Substructure details for location.
- (10) See Table of Bearing Pad Dimensions for dimensions.
- (11) Maximum and minimum layer thicknesses shown are for elastomer only, on tapered layers.
- (12) Locate Permanent Mark here.
- (13) Indicate BEARING TYPE on all pads. For tapered pads, locate BEARING TYPE on the high side. The Fabricator must include the value of "N" (amount of taper in 1/8" increments) in this mark.
Examples: N=0, (for 0" taper)
N=1, (for 1/8" taper)
N=2, (for 1/4" taper)
(etc.)
Fabricated pad top surface slope must not vary from plan girder slope by more than (0.0625" / IN) IN/IN.
- (14) Substructure dimensions must satisfy the minimums provided to accommodate the elastomeric bearings shown on this standard.
- (15) See sheet 3 of 3 for beveled plate use when slopes exceed 5 percent.
- (16) If girder end is skewed for a girder conflict at an interior bent and a beveled sole plate is required, use bearing type for abutments at this location. Location of bearing centerline is to be set as for abutments in this case.

HL93 LOADING SHEET 2 OF 3

Texas Department of Transportation
 Bridge Division Standard


ELASTOMERIC BEARING AND GIRDER END DETAILS PRESTR CONCRETE I-GIRDERS

IGEB



FILE: TxDOT August 2017	DN: AEE	CK: JMH	DW: JTR	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
	0901	30	018	CR
	DIST	COUNTY	SHEET NO.	
	PAR	RATNS	42	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:35 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\5 IGEB.dgn



PLAN VIEW OF SOLE PLATE DETAILS



BEVELED PLATE DETAILS

- 17 Cut beveled and embedded plates to match girder end skew. Adjust location of screw and stud as shown when necessary.
- 18 Slotted hole is required at doweled girder end locations.

SOLE PLATE NOTES:

Provide constant thickness elastomeric bearings with beveled and embedded steel sole plates in accordance with these details when the girder slope exceeds 5 percent or if otherwise required in the plans. Provide for all girders in the span.

On the shop drawings, dimension sole plates to the nearest 1/16" based on required thickness at centerline of bearing and slope of girder. Thickness tolerance variation from the approved shop drawings is 1/16" +/-, except variation from a plane parallel to the theoretical top surface can not exceed 1/16" total. Bearing surface tolerances listed in Item 424 apply to embedded and beveled plates.



Steel plate must conform to ASTM A36, A572 Gr 50, or A709 Gr 36 or Gr 50. Hot dip galvanize both the embedded plate and beveled sole plate after fabrication. Seal weld caps to embedded plate before galvanizing.

When determining if relocation of screw holes and studs are necessary for skewed girder ends, minimum clearance from screw or stud centerline to plate edge is 1.25".

Tap threads in the embedded plate only. Drill and tap prior to galvanizing.

3/4" Dia screws must be electroplated, socket flat head countersunk cap screws conforming to ASTM F835. Electroplating must conform to ASTM B633, SC 2, Type I. Provide screws long enough to maintain a 3/4" minimum embedment into the embedded plate and galvanized cap. Provide galvanized steel caps (16 ga Min) with a nominal 1" inside diameter and deep enough to accommodate the screws, but not less than 1/2" deep or deeper than 1".

Install beveled sole plates prior to shipping girders. Installed screw heads must not protrude below the bottom of the beveled plate.



GIRDER DETAILS

HL93 LOADING SHEET 3 OF 3




**ELASTOMERIC BEARING AND GIRDER END DETAILS
PRESTR CONCRETE I-GIRDERS**

IGEB


FILE:	DN: AEE	CK: JMH	DW: JTR	CK: TxDOT
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
DIST	COUNTY	SHEET NO.		
PAR	RATNS	43		

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:35:36 PM
 FILE: T:\PARTPDD\CR_1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\6 IGMS.dgn




HAUNCH REINFORCING DETAIL



BARS U (#4)




C-I-P DRAIN DETAIL




TYPICAL PART TRANSVERSE SLAB SECTION WITHOUT PCP


Top reinforcing steel not shown for clarity.



TREATMENT AT GIRDER END FOR SKEWED SPANS



TYPE A JOINT DETAIL



DRAIN DETAIL

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications.
 Payment for Type A joint will be as per Item 454, "Bridge Expansion Joints."
 All other items (reinforcing steel, drains, etc.) shown on this sheet are subsidiary to other bid items.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

DECK FORMWORK NOTES:
 Overhang bracket hangers are limited to a safe working load of 3,600 lbs, applied to and along the axis of a coil rod at 45 degrees from vertical, regardless of higher loads permitted by hanger manufacturers. Do not place a hanger less than 12" from girder end. Space hangers accordingly.


- ① Space Bars U with girder Bars R in all areas where measured haunch exceeds 3 1/2".
- ② Roughen outside of PVC with coarse rasp or equal to ensure bond with cast-in-place concrete.
- ③ Bars B(#4) spaced at 9" Max with 2" end cover. Overhang option, Contractor's may end alternating bars B(#4) at centerline outside girder.
- ④ Provide Grade 60 reinforcing steel. Provide bar laps, where required, as follows:
 Uncoated ~ #4 = 1'-7"
 Epoxy coated ~ #4 = 2'-5"
- ⑤ Class 7 silicone sealant that conforms to DMS-6310. Install when ambient temperature is between 55°F and 85°F and rising. Engineer to determine allowable hours for sealant application.
- ⑥ 1 1/4" backer rod must be compatible with joint sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as shown.
- ⑦ The maximum distance between Type A expansion joints is 100'. See Bridge Layout for location of joints.
- ⑧ Drain entrance formed in rail or sidewalk.
- ⑨ Water may not be discharged onto girders.
- ⑩ All drain pipe and fittings to be 4" diameter (Sch 40) PVC. See Item 481 "Pipe for Drains" for pipe, connections and solvent welding. Bend reinforcing steel to clear PVC 1". Drain length and location is as directed by the Engineer. Drains are not permitted over roadways or railroads, or within 10'-0" of bent caps. Degrease outside of exposed PVC, apply acrylic water base primer, then coat with same surface finishing material as used for outside girder face. Variations of the above designs, as required for the type of rail used and its location on the structure, may be installed with the approval and direction of the Engineer.

SHEET 1 OF 2


				Bridge Division Standard		
MISCELLANEOUS SLAB DETAILS PRESTR CONCRETE I-GIRDERS						
IGMS						
FILE:	DN: TxDOT	CK: TxDOT	DW: JTR	CR: TxDOT		
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY		
REVISIONS	0901	30	018	CR		
10-19: Modified Note 7. Type A now a pay item.	DIST	COUNTY	SHEET NO.			
	PAR	RATNS			44	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:35:37 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\6 IGMS.dgn




SHOWING EXPANSION JOINTS




**SHOWING CONST JTS OR CONTROLLED JTS
 REINFORCEMENT OVER INV-T BENTS**




BARS W (#4)



DRIP BEAD DETAIL



CHAMFER LIMITS DETAIL (15)




**CONTROLLED JOINT DETAIL
 (Saw-cutting is not allowed)**

- (11) See Layout for joint type.
- (12) Dowels DD (#11) spaced at 5 Ft Max. See Inv-T bents for quantity and location.
- (13) Space Bars Y (#4) at 12" Max. Use 2" end cover. Number of Bars Y must satisfy spacing limit. Place parallel to bent.
- (14) Space Bars W at 12" Max (3" from end of cap). Tilt if necessary to maintain cover requirements. Place parallel to longitudinal slab reinforcement.
- (15) See Span details for type of joint and joint locations.

SHEET 2 OF 2

		Bridge Division Standard		
MISCELLANEOUS SLAB DETAILS PRESTR CONCRETE I-GIRDERS				
IGMS				
FILE:	DN: TxDOT	CK: TxDOT	DW: JTR	CK: TxDOT
©TxDOT August 2017	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-19: Modified Note 7, Type A now a pay item.	DIST	COUNTY	SHEET NO.	
	PAR	RAINS	45	

DATE: 10/4/2023 8:35:39 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Desi\gn\CAD Standards\03 BRIDGE STANDARDS\7 IGSK.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



PARTIAL PLANS WITH NO SKEW

Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.

PARTIAL PLANS WITH 15° SKEW

Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.


PARTIAL PLANS WITH 30° SKEW

Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.

PARTIAL PLANS WITH 45° SKEW


Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.

- ① Place shear keys on the upstream side of structure between outside girder and next adjacent girder, unless shown otherwise on plans.
- ② UHMW polyethylene wear pad. (Typ)
- ③ Leave a 1/4" gap plus or minus between girder and face of wear pad. Cast wear pad with shear key, smooth side facing girder. Care must be taken to keep concrete from flowing under girder. Slope top of shear keys in accordance with Item 420.4.9, "Treatment and Finishing of Horizontal Surfaces."
- ④ Measure at higher bearing seat elevation forward or back. Dimension based on typical bearing pad and bearing seat. Increase as necessary to maintain 5" overlap.
- ⑤ With No Skew = 1'-8 1/4", measured along $\bar{\ell}$ cap. With Skew = $1'-8 \frac{1}{4}" \div \cos \text{Skew}$, measured along $\bar{\ell}$ cap.
- ⑥ With No Skew = 1'-4 1/4", measured along $\bar{\ell}$ cap. With Skew = $1'-4 \frac{1}{4}" \div \cos \text{Skew}$, measured along $\bar{\ell}$ cap.
- ⑦ Face of UHMW polyethylene wear pad. Smooth side of pad facing girder.
- ⑧ Abutments = 1/2 Cap width. Interior bents = Cap width.
- ⑨ Abutments = 1/2 Cap width $\div \cos \text{Skew}$. Interior bents = Cap width $\div \cos \text{Skew}$.




PARTIAL ELEVATION OF ABUTMENT OR INTERIOR BENT CAP

Showing shear key with girder Type Tx46. Other I-Girder types similar.




ELEVATION





PART SECTION



ULTRA HIGH MOLECULAR WEIGHT (UHMW) POLYETHYLENE WEAR PAD DETAILS



BARS M (#5)



BARS Na (#5) (For abutments)



BARS Nb (#5) (For interior bents)


CONSTRUCTION NOTES:
 Provide Class "C" concrete ($f'_c = 3,600$ psi). Provide Class "C" (HPC) if shown elsewhere on the plans.
 Provide Grade 60 reinforcing steel.
 Provide epoxy coated reinforcing steel for shear key if abutment or interior bent reinforcing steel is epoxy coated.
 Provide Ultra High Molecular Weight (UHMW) polyethylene wear pads in accordance with ASTM D6712.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications. Details showing skew are drawn showing right forward skew. See Bridge Layout for actual skew direction.
 These details are limited to bridges skewed 45 degrees and less. This standard is only applicable for I-Girders.
 Modify details for bearing conditions, and girder spacing not shown on this standard. Details do not account for sole plate or pedestal bearing seat.
 Include shear key concrete in abutment or bent concrete for payment.
 UHMW polyethylene wear pads are subsidiary to Class "C" concrete.
 Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.


		Bridge Division Standard	
SHEAR KEY DETAILS PRESTR CONCRETE I-GIRDERS			
IGSK			
FILE:	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT August 2017	CON: 0901	SECT: 30	JOB: 018
REVISIONS	DIST: PAR	COUNTY: RAINS	SHEET NO: 46

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:40 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\8 IGTS.dgn




PARTIAL PLAN FOR SLABS WITHOUT BREAKBACK



PARTIAL PLAN FOR SLABS WITH BREAKBACK


- ① End top transverse reinforcing steel at inside Bar G. End bottom transverse reinforcement steel 1'-0" beyond inside Bar G.
- ② "A" = ("OH" + 2.333 "B") x Tan ϕ
- ③ Provide clear cover as indicated unless otherwise shown on Span Details.
- ④ Only required on slabs with breakbacks.
- ⑤ Thickened slab end dimensioned perpendicular to face of bkwl, centerline interior bent or face of inverted-T stem.




GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications. These details are restricted to Prestressed Concrete I-Girder Spans. These details are to be used in conjunction with the Span Details and PCP standard (if prestressed concrete panels are used). When Option 2 from PCP standard is used, provide Bars AA, G, K and OA in the slab.

MATERIAL NOTES:
 Provide Grade 60 reinforcing steel. If slab reinforcing steel is shown on the Slab Details to be epoxy coated, then Bars AA, G, K, H, J, M and OA must be epoxy coated. Provide bar laps, where required, as follows:
 Uncoated ~ #4 = 1'-7"
 Epoxy Coated ~ #4 = 2'-5"

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.



TYPICAL TRANSVERSE SECTION
 (Showing Prestressed Conc I-Girders at ̄ Brg)




SECTION A-A
 (Showing with 2" and more of haunch)


HL93 LOADING		Bridge Division Standard	
THICKENED SLAB END DETAILS			
PRESTRESSED CONCRETE I-GIRDER SPANS			
IGTS			
FILE:	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT	August 2017	CONTRACT NO. 0901	SECTION 30
REVISIONS		JOB NO. 018	HIGHWAY CR
		DIST. PAR	COUNTY RAINS
			SHEET NO. 47

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:42 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\9 CSAB.dgn



OPTION 1 ~ PLAN WITH WINGWALLS
 Cast-in-place retaining walls similar.



OPTION 1 ~ PLAN WITH MSE RETAINING WALLS


- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans, flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a) If flowable backfill is to be placed over MSE backfill, then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b) Place flowable fill in lifts not exceeding 2 feet in height. Place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).

GENERAL NOTES:


See the Bridge Layout for selected Option. Option 1 is intended for construction only requiring plasticity index (PI) controlled embankment fill or excavation in competent soils/rocks in order to construct the abutment. Option 2 is intended for new construction requiring high plasticity embankment fill with a PI greater than 30 or pavement built in poor native soil. Poor soils are defined as high plasticity clays or expansive clays.
 Construct abutment backfill in accordance with Item 400, "Excavation and Backfill for Structures".
 Provide Cement Stabilized Backfill (CSB) meeting the requirements of Item 400, "Excavation and Backfill for Structures", to the limits shown at bridge abutments.
 If required elsewhere in the plans, provide Flowable Backfill meeting the requirements of Item 401, "Flowable Backfill", to the limits shown at bridge abutments.
 Details are drawn showing left forward skew. See Bridge Layout for actual skew direction.
 These details do not apply when Concrete Block retaining walls are used in lieu of wingwalls.

SHEET 1 OF 2

		Bridge Division Standard		
CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT				
CSAB				
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT	April 2019	CONTRACT	SECTION	HIGHWAY
	0901	30	018	CR
02-20: Added Option 2.		DIST	COUNTY	SHEET NO.
03-23: Updated General Notes.		PAR	RAINS	48



WITHOUT APPROACH SLAB




WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)

SECTION A-A


DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever.
 TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:43 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\9 CSAB.dgn




OPTION 2 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.




OPTION 2 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans, flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a). If flowable backfill is to be placed over MSE backfill, then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b). Place flowable fill in lifts not exceeding 2 feet in height. Place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).
- ⑥ 1'-0" for BAS-A
1'-10" for BAS-C



WITHOUT APPROACH SLAB



SECTION B-B


WITH APPROACH SLAB
 (Showing BAS-C, BAS-A similar.)

SHEET 2 OF 2


		Bridge Division Standard	
CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT			
CSAB			
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT	April 2019	CONTRACT	HIGHWAY
REVISIONS	0901	30	018
02-20: Added Option 2.	DIST	COUNTY	SHEET NO.
03-23: Updated General Notes.	PAR	RATNS	49

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:35:44 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\10 FD.dgn




ABUTMENTS, WINGWALLS AND MULTI-DRILLED SHAFT FOOTINGS




INTERIOR BENTS DRILLED SHAFT DIA EQUAL TO COLUMN DIA



INTERIOR BENTS DRILLED SHAFT DIA GREATER THAN COLUMN DIA



OPTIONAL INTERIOR BENT DRILLED SHAFT DETAIL




DRILLED SHAFT SECTIONS


DRILLED SHAFT DETAILS

TABLE OF PILE EMBEDMENT	
Pile Type	Embedment Depth (Ft)
16" Sq Concrete 18" Sq Concrete HP14 Steel HP16 Steel	1'-0"
20" Sq Concrete 24" Sq Concrete HP18 Steel	1'-6"

See Prestressed Concrete Piling (CP) standard for additional details on concrete pile embedment.




ORIENTATION OF STEEL H-PIILING



VERTICAL PILE BATTERED PILE


PIILING DETAILS
(Concrete or steel H)




DETAIL "A"

(Showing plan view of a 30° skewed abutment)


- ① #3 spiral at 6" pitch (one and a half flat turns top and bottom).
- ② Min extension into supported element:
#6 Bars = 1'-11"
#7 Bars = 2'-0"
#9 Bars = 2'-3"
- ③ Min lap with column reinf:
#7 Bars = 2'-11"
#9 Bars = 3'-9"
#11 Bars = 4'-8"
- ④ Min extension into supported element:
#6 Bars = 1'-11"
#7 Bars = 2'-3"
#9 Bars = 2'-9"
- ⑤ Drilled shafts may extend to the bottom of bent caps for "H" heights of 6 ft and less (as shown on the Bridge Layout), if approved. This option can only be used when the drilled shaft diameter equals the column diameter. Obtain approval of the forming method above the ground line prior to construction. No adjustments in payment will be made if this option is used.
- ⑥ 1'-0" Min, unless shown otherwise on plans.
- ⑦ Or as shown on plans.




ELEVATION



SECTION A-A



SECTION B-B



SECTION THRU FLANGE OR WEB

STEEL H-PILE SPLICE DETAIL

Use when required.

STEEL H-PILE TIP REINFORCEMENT



See Item 407 "Steel Piling" to determine when tip reinforcement is required and for options to the details shown.

SHEET 1 OF 2


		Bridge Division Standard	
<h2>COMMON FOUNDATION DETAILS</h2>			
<h3>FD</h3>			
FILE: TxDOT April 2019 REVISIONS 01-20: Added #11 bars to the FD bars.	DN: TxDOT CON: 0901 SECT: 30 DIST: PAR	CK: TxDOT JOB: 018 COUNTY: RAINS	CW: TxDOT HIGHWAY: CR SHEET NO.: 50

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:35:46 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\10_FD.dgn





THREE PILE FOOTING^⑧
 For 36" Dia and smaller columns.



FOUR PILE FOOTING^⑧
 For 42" Dia and smaller columns.



FIVE PILE FOOTING^⑧
 For 42" Dia and smaller columns.



- ③ Min lap with column reinforcing:
 #7 Bars = 2'-11"
 #9 Bars = 3'-9"
 #11 Bars = 4'-8"
- ⑥ 1'-0" Min, unless shown otherwise on plans.
- ⑦ Or as shown on plans.
- ⑧ See Bridge Layout for type, size and length of piling.
- ⑨ Number and size of FD bars must match column reinforcing. Tie FD bars to the top of the bottom reinforcing mat.
- ⑩ Adjust FD quantity, size and weight as needed to match column reinforcing.

TABLE OF FOOTING QUANTITIES FOR 30" COLUMNS

ONE 3 PILE FOOTING				
Bar	No.	Size	Length	Weight
F1	11	#4	3'- 2"	23
F2	6	#4	8'- 2"	33
F3	6	#4	6'- 11"	28
F4	8	#9	3'- 2"	86
F5	4	#9	6'- 11"	94
F6	4	#9	8'- 2"	111
FC	12	#4	3'- 6"	28
FD ^⑩	8	#9	8'- 1"	220

Reinforcing Steel	Lb	623
Class "C" Concrete	CY	4.8

ONE 4 PILE FOOTING				
Bar	No.	Size	Length	Weight
F1	20	#4	7'- 2"	96
F2	16	#8	7'- 2"	306
FC	16	#4	3'- 6"	37
FD ^⑩	8	#9	8'- 1"	220

Reinforcing Steel	Lb	659
Class "C" Concrete	CY	6.3

ONE 5 PILE FOOTING				
Bar	No.	Size	Length	Weight
F1	20	#4	8'- 2"	109
F2	16	#9	8'- 2"	444
FC	24	#4	3'- 6"	56
FD ^⑩	8	#9	8'- 1"	220

Reinforcing Steel	Lb	829
Class "C" Concrete	CY	8.0

CONSTRUCTION NOTES:

- See Bridge Layout for foundation type required. Use these foundation details unless shown otherwise.
- Drive piling under abutment wingwalls to a minimum resistance of 10 Tons/Pile unless shown otherwise.
- Provide Class C Concrete ($f'_c = 3,600$ psi), unless shown otherwise.
- Provide Grade 60 reinforcing steel.
- Galvanize reinforcing if shown elsewhere in the plans.
- Provide bar laps for drilled shaft reinforcing, where required, as follows:
 Uncoated or galvanized (#6) ~ 2'-6"
 Uncoated or galvanized (#7) ~ 2'-11"
 Uncoated or galvanized (#9) ~ 3'-9"

GENERAL NOTES:

Designed according to AASHTO LRFD Bridge Design Specifications.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

DESIGNER NOTES:

- Do not use the drilled shaft details shown on this standard for retaining wall, noise wall, barrier, or sign foundations without structural evaluation.
- Do not use the footings shown on this standard in direct contact with salt water or exposed to salt water spray.
- Maximum allowable pile loads for the footings shown are:
 72 Tons/Pile with 24" Dia Columns
 80 Tons/Pile with 30" Dia Columns
 100 Tons/Pile with 36" Dia Columns
 120 Tons/Pile with 42" Dia Columns

SHEET 2 OF 2




COMMON FOUNDATION DETAILS

FD


FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT	April 2019	CONTRACT	SECTION	HIGHWAY
REVISIONS	0901	30	018	CR
01-20: Added #11 bars to the FD bars.	DIST	COUNTY	SHEET NO.	
PAR	RATNS	51		

10/4/2023 8:35:47 PM
 DATE: 10/4/2023 8:35:47 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\11 PCP.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




NORMAL GRADING DETAIL ③

Showing prestressed concrete I-girders.
(Other beam types similar)




SPECIAL GRADING DETAIL FOR CONCRETE BEAMS

Showing prestressed concrete I-girders.
(Other beam types similar)



HAUNCH REINFORCING DETAIL


Showing prestressed concrete I-girders.
(Other beam types similar)




PRESTR CONC I-GIRDERS

WIDTH	HEIGHT ④	
	Min	Max
1" (Min)	1/2"	2"
1 1/4"	1/2"	2 1/2"
1 1/2"	1/2"	3"
1 3/4"	1/2"	3 1/2"
2"	1/2"	4"
2 1/4"	1/2"	4 1/2" ②
2 1/2"	1/2"	5" ②
2 3/4"	1/2"	5 1/2" ②
3" (Max)	1/2"	6" ②

- ① 2" Min for I-girders, 1 1/2" Min for all other beam types.
- ② Allowed for prestressed concrete I-girders, not allowed on other beam types.
- ③ To reduce the quantity of cast-in-place concrete, bedding strip thickness may be increased in 1/4" increments. Bedding strips must be comprised of one layer. Bond bedding strips to the beams with an adhesive compatible with bedding strips. Bedding strips over 2.5" high may need to be bonded to panels. The same thickness strip must be used under any one panel edge and the maximum change in thickness between adjacent panels is 1/4". Alternatively, bedding strips may be cut to grade. Panels may be supported by an alternate method, using a commercial product, if approved by the Engineer of Bridge Design, Bridge Division. If bedding strips exceed 6" high for I-girders, 4" high for all other beam types, use Special Grading Detail for Concrete Beams or submit an alternate method to the Bridge Division for approval.
- ④ Height must not exceed twice the width.
- ⑤ Provide clear cover as indicated unless otherwise shown on Span Details.
- ⑥ See Span Details and Thickened Slab End Details for top slab reinforcement and clear cover. Transverse top slab reinforcement may rest on top of prestressed concrete panels if necessary to maintain clear cover.
- ⑦ Space Bars UP(#4) with Beam Bars R(#4) in all areas where measured haunch exceeds 3 1/2" with I-girders, and 3" for all other beam types. Epoxy coating for Bars UP is not required.
- ⑧ Do not locate construction joints on top of a panel.
- ⑨ Butt adjacent bedding strips together with adhesive. Cut v-notches, approx 1/4" deep, in the top of the bedding strips at 8" o.c..




BARS UP (#4) ⑦




PANEL JOINTS

(Panel reinforcing not shown for clarity.
The gap cannot be considered as a panel fabrication tolerance. Adjust panel placement to minimize joint openings.)



PRESTR CONC I-BEAMS



BEDDING STRIP DETAIL ⑨

CONSTRUCTION NOTES:

Erected panels must bear uniformly on bedding strips of extruded polystyrene placed along top flange edges. Placing panels to minimize joint openings is recommended. If additional blocking is needed, special grading details for supporting the panels and extra reinforcing between beam and slab will be considered subsidiary to deck construction. Bars U, shown on PCP-FAB, may be bent over or cut off if necessary. Care must be taken to ensure proper cleaning of construction debris and consolidation of concrete material under the edges of the panels. Bedding strips must be placed at beam flange edges so that adequate space is provided for the mortar to flow a minimum of 1 1/2" under the panels as the slab concrete is placed. To allow the proper amount of mortar to flow between beam and panel, the minimum vertical opening must be at least 1/2". Roadway cross-slope reduces the opening available for entry of the mortar. Bedding strips varying in thickness across the beam are therefore required. For clear span between U-beams less than or equal to 18", see Permissible Slab Forming Detail on Miscellaneous Slab Detail sheets, UBMS.

MATERIAL NOTES:

Provide Grade 60 reinforcing steel in the cast-in-place slab. See Table of Reinforcing Steel for size and spacing of reinforcement. If the top and bottom layer of reinforcing steel is shown on the Span Details to be epoxy coated, then the D, E, P, & Z bars must be epoxy coated. Provide bar Laps, where required, as follows:
Uncoated ~ #4 = 1'-7"
Epoxy Coated ~ #4 = 2'-5"

GENERAL NOTES:

Designed according to AASHTO LRFD Bridge Design Specifications. Panel placement may follow either Option 1 or Option 2 except Option 1 must be used if the skew exceeds 45 degrees. Use of Prestressed Concrete Panels is not permitted for horizontally curved steel plate or tub girders. See Span Details for other possible restrictions on their use. These details are to be used in conjunction with the Span Details, PCP-FAB and other applicable standard drawings. When panel support (bedding strips) deviates from what is shown herein, provide details signed and sealed by a professional Engineer. Any additional reinforcement or concrete required on this standard is considered subsidiary to the bid item "Reinforced Concrete Slab".

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bar dimensions shown are out-to-out of bar.


HL93 LOADING

SHEET 1 OF 4


		Bridge Division Standard	
<h2>PRESTRESSED CONCRETE PANELS DECK DETAILS</h2>			
<h3>PCP</h3>			
FILE:	DN: TxDOT	CK: TxDOT	DW: JTR
CONTRACT:	0901	SECTION:	30
REVISIONS:	JOB:		018
3/2023: Removed top flange tension limit.	DIST:	COUNTY:	SHEET NO.
	PAR	RATNS	52

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:35:48 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Des\ign\CAD Standards\03 BRIDGE STANDARDS\11 PCP.dgn




PRESTRESSED CONCRETE I-BEAMS




STEEL BEAMS (13)



PRESTRESSED CONCRETE I-GIRDERS




PRESTRESSED CONCRETE X-BEAMS



NORMAL OVERHANG WITH PRESTR CONC U-BEAMS


TYPICAL PART TRANSVERSE SECTIONS

SLOPED OVERHANG WITH PRESTR CONC U-BEAMS



AT FLARED BEAMS OR GIRDERS


See PCP-FAB standard for Min and Max dimensions based on beam/girder type.



OVER CONC U-BEAMS

PART PLANS OF PANEL PLACEMENT


- 5 Provide clear cover as indicated unless otherwise shown on Span Details.
- 6 See Span Details and Thickened Slab End Details for top slab reinforcement and clear cover. Transverse top slab reinforcement may rest on top of prestressed concrete panels if necessary to maintain clear cover.
- 9 Butt adjacent bedding strips together with adhesive. Cut v-notches, approx 1/4" deep, in the top of the bedding strips at 8' o.c..
- 10 Equally space additional bar if more than 1'-3" Max.
- 11 The actual thickness constructed may exceed the slab thickness shown on the Span Details but the extra thickness may be no more than 2" (1" for prestressed concrete U-beams and steel beams). Bearing seat elevations or finished grade may be adjusted.
- 12 Field adjust Bars Z1(#4) to match actual slope of slab overhangs. Width of slab overhang will vary along span with curved slab edges. Adjust Bar Z1(#4) dimensions to maintain proper cover. Bars Z2(#4) are located at Inverted-Tee stems only.
- 13 Panels are allowed over top tension flanges, as approved by the Engineer. See Span Details for additional top mat reinforcement required in tension zones. Location of concrete placement sequence boundaries and bolted field splices should be considered by the contractor in determining panel limits.



PLAN AT SPLICE


(Showing steel beams with flange width transition)

Cut bedding strip to adjust for difference in flange thickness.




ELEVATION AT SPLICE

(Showing steel beams with different flange thickness)



PRESTRESSED CONCRETE SPREAD SLAB BEAMS

Bars P over exterior beams are still required when no overhang is used. In this case, only one Bar D, 2" from slab edge, is required.



BARS Z (#4) (12)

HL93 LOADING

SHEET 2 OF 4


Texas Department of Transportation
 Bridge Division Standard

PRESTRESSED CONCRETE PANELS DECK DETAILS

PCP


FILE:	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT	April 2019	CONTRACT	SECTION	HIGHWAY
REVISIONS	0901	30	018	CR
3/2023: Removed top flange tension limit.	DIST	COUNTY	SHEET NO.	
PAR	RATNS		53	

10/4/2023 8:35:50 PM
 DATE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Desi\gn\CAD Standards\03 BRIDGE STANDARDS\11 PCP.dgn
 FILE:




AT ALL SPAN ENDS UNLESS NOTED OTHERWISE
 AT INTERIOR BENTS
 AT THICKENED END SLABS

OPTION 1 ~ PLAN OF SLABS WITH NORMAL REINFORCEMENT




AT ALL SPAN ENDS UNLESS NOTED OTHERWISE
 AT INTERIOR BENTS
 AT THICKENED END SLABS


OPTION 1 ~ PLAN OF SLABS WITH SKEWED REINFORCEMENT




AT THICKENED SLAB ENDS FOR PRESTR CONCRETE U-BEAMS




AT THICKENED SLAB ENDS FOR PRESTR CONCRETE I-BEAMS AND STEEL BEAMS




AT SLAB CONTINUOUS OVER CONVENTIONAL INTERIOR BENTS FOR ALL SIMPLE SPAN BEAMS



AT CONVENTIONAL END DIAPHRAGMS FOR STEEL BEAMS



AT SLAB OVER ABUTMENT BACKWALL FOR ALL BEAMS



AT SLAB CONTINUOUS OVER INVERTED-T BENTS FOR ALL BEAMS

OPTION 1 ~ ELEVATIONS AT BEAM ENDS

- 6 See Span Details and Thickened Slab End Details for top slab reinforcement and clear cover. Transverse top slab reinforcement may rest on top of prestressed concrete panels if necessary to maintain clear cover.
- 9 Butt adjacent bedding strips together with adhesive. Cut v-notches, approx 1/4" deep, in the top of the bedding strips at 8' o.c.
- 14 Max Spacing as listed unless otherwise shown.
- 15 At connection with cast-in-place slab, extend longitudinal panel reinforcement. See PCP-FAB for details.
- 16 Maintain one Bar E(#4) parallel to panel ends (Typ).
- 17 Bars E(#4) not continuous over beam flanges must overlap beam flange 6" Min.
- 18 Add flared Bars E(#4) (Min Spa = 6", Max Spa = 12") as required at panel ends.
- 19 Where possible, Bars E(#4) may be extended into overhangs to replace Bars P(#4). Bars Z(#4) are required for sloped overhangs with U-Beams.
- 20 See appropriate thickened slab end details for reinforcing and limits of thickened slab end.

TABLE OF REINFORCING STEEL (14)		
BAR	SIZE	Max Spa (in.)
D	#4	9
E	#4	9
P	#4	18
UP	#4	~
Z	#4	18

HL93 LOADING SHEET 3 OF 4



PRESTRESSED CONCRETE PANELS DECK DETAILS

PCP

FILE:	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT	April 2019	CONTRACT	SECTION	HIGHWAY
REVISIONS	0901	30	018	CR
3/2023: Removed top flange tension limit.	DIST	COUNTY	SHEET NO.	
PAR	RATNS	54		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:35:51 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Des\ign\CAD Standards\03 BRIDGE STANDARDS\11 PCP.dgn






TABLE OF REINFORCING STEEL (14)		
BAR	SIZE	Max Spa (in.)
D	#4	9
E	#4	9
P	#4	18
UP	#4	~
Z	#4	18


OPTION 2 ~ PLAN OF SLAB
 (Showing U-Beams; other beams similar)




JOINTS (BETWEEN BEAMS/GIRDERS OR AT INV-T STEM)
 For SEJ-B, SEJ-M, SEJ-S(0), AJ, and Type A expansion joints only.



CONVENTIONAL INTERIOR BENT
 Panel against panel between beams/girders.



CONVENTIONAL INTERIOR BENT
 Panel against beam/girder end in adjacent span.




INVERTED-T BENT
 Panels against inverted-tee stem

OPTION 2 ~ ELEVATIONS AT BEAM ENDS (6)

ELEVATION EXAMPLE OF END PANEL AND TIMBER BOARD (23)

See "Option 2 ~ Elevation At Beam Ends".

- (6) See Span Details and Thickened Slab End Details for top slab reinforcement and clear cover. Transverse top slab reinforcement may rest on top of prestressed concrete panels if necessary to maintain clear cover.
- (14) Max Spacing as listed unless otherwise shown.
- (21) 1 1/2" Vinyl or plastic joint former at controlled joints (Stress Cap, Zip Strip, Stress Lock, or equal as approved by the Engineer.)
- (22) End panel may be set up to 2" lower to accommodate expansion joint hardware, provided bedding strip is not less than 1/2" thick.
- (23) 3/4" thick redwood timber board, leave in place. Redwood timber board placed flush with top of panel or within 1/4" Max above panel. Place 3/4" pyramid shape chamfer along top of timber board. See "Elevation Example of End Panel and Timber Board". Place straight, within 1/2" of centerline of bent or face of inverted-tee, across bridge width and end board at exterior flange edge of fascia beams/girders. Do not extend into overhang.
- (24) Place panel within 1/2" of 3/4" thick board.
- (25) Permanent galvanized steel sheet form. Removable formwork is acceptable.
- (26) Place end panel within 1/2" of expansion joint opening. End panel cannot encroach on required expansion joint opening.
- (27) Place additional (#4) bar 5'-0" in length between every slab Bars T. Center (#4) bar on Joint.
- (28) Place additional (#4) bar continuous 2'-6" beyond each side of Inverted-T Stem between every slab bars T.



OPTION 2 ~ SHOWING MODIFICATION TO BEAM/GIRDER TOP FLANGE FOR SKEWS OVER 5°

Showing I-Beam/I-Girder, U-Beams and Steel Beams similar.

SPECIAL OPTION 2 CONSTRUCTION NOTES:

- When Option 2 is chosen bottom mat of thickened end slab reinforcing is not required. Use the same top mat as shown on the Thickened Slab End Details sheet.
- Placing panels adjacent to expansion joints and bent centerlines prior to completing interior panel placement is recommended. Saw cutting panels to fit is acceptable when approved by the Engineer. Minimum distance from a saw cut edge to a panel strand is 1 1/2". Do not extend the longitudinal panel reinforcement into the cast-in-place slab.
- Top flanges of beams and girders on skewed bridges must be modified as shown on this drawing. The Contractor is responsible for coordinating this modification with the beam fabricator prior to submitting shop drawings for approval.
- Fabricator may optionally skew the whole end. When electing to skew whole end, girder end details and bearing type at conventional interior bent must be changed to use condition at abutment. Fabricator must coordinate change in bearing type, bearing centerline location, and dowel location with Engineer and Contractor. Show appropriate changes on girder and bearing shop drawings.
- Bending of anchor studs of expansion joints shown on standards AJ, SEJ-B, SEJ-M, and SEJ-S(0) is permissible if necessary to clear top of end panels. The Contractor is responsible for coordinating modifications with the joint fabricator. Submit shop drawings for approval when modifications to expansion joint hardware are made.
- Bedding strips under skewed end panels must conform to the requirements of Item 422 except their minimum compressive strength must be 60 psi.
- Provide Bars AA, G, K and OA from standard IGTS in the slab.

HL93 LOADING SHEET 4 OF 4


Texas Department of Transportation Bridge Division Standard

PRESTRESSED CONCRETE PANELS DECK DETAILS


PCP

FILE:	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT April 2019 REVISIONS	CONT	SECT	JOB	HIGHWAY
0901	30		018	CR
3/2023: Removed top flange tension limit.	DIST	COUNTY	SHEET NO.	
PAR	RATNS		55	

10/4/2023 8:35:53 PM
 DATE: 10/4/2023 8:35:53 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\12 PCP-FAB.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TYPICAL NON-SKEWED PANEL PLAN



TYPICAL SKEWED END PANEL PLAN

(Only to be used with details shown elsewhere in the plans.)

- 1 At connection with cast-in-place slab, extend longitudinal panel reinforcement 1'-0" (+2", -0") past panel end. Alternatively, provide (#3) x 2'-0" dowels at 6" Max Spacing and extend dowels 1'-0" past panel end.
- 2 Four loops required per panel.
- 3 Four loops required per panel. 3/8" or 1/2" strands may be used.
- 4 Normal dimensions must be used on spans with parallel beams. Maximum and Minimum dimensions apply only to spans with flared beams.
- 5 See Normal Grading Detail on PCP standard for lap requirements and bedding strip dimensions. Some laps shown in tables cannot utilize all bedding strip widths.
- 6 One Splice allowed per panel. No more than two sheets of WWR are allowed.
- 7 Provide (#4) bars under transverse reinforcing, 10 Spaces at 4" = 3'-4". Omit for 5 degree (1:12) skew and smaller.
- 8 End Cover 2 1/2" Max, 1" Min.
- 9 Recess strands on indicated panel edge in accordance with Item 424.
- 10 At the fabricator's option, Bars U may be placed parallel to transverse panel reinforcing with horizontal legs in plane of transverse panel reinforcing.
- 11 Use length of indicated panel edge as panel width for purpose of determining type of transverse reinforcing.
- 12 Timber form work permissible this edge.

TABLE A (4) (5)				TABLE B (4) (5)			
Beam Type	Normal (In.)	Min (In.)	Max (In.)	Top Flange Width	Normal (In.)	Min (In.)	Max (In.)
A	3	2 1/2	3 1/2	11" to 12"	2 3/4	2 1/2	2 3/4
B	3	2 1/2	3 1/2	Over 12" to 15"	3 1/4	3	3 1/4
C	4	3	4 1/2	Over 15" to 18"	4	3	4 1/4
IV	6	4	7 1/2	Over 18"	5	3 1/2	6 1/4
VI	6 1/2	4 1/2	8 1/2				
U40 - 54	5 1/2	5 1/2	7				
Tx28-70	6	5	7 1/2				
XB20 - 40	4	3	4 1/2				
XSB12 - 15	4	3	4 1/2				

GENERAL NOTES:


Provide Class H concrete for panels. Release strength $f'_{ci}=3,500$ psi. Minimum 28 day strength $f'_{c}=5,000$ psi.
 Provide 3/4" chamfer along bottom edge of panel on beam side. Do not use epoxy-coated reinforcing steel bar or strand in panels. Remove laitance from top panel surface. Finish top of panel to a roughness between a No. 6 and No. 9 concrete surface profile, inclusive, as specified by the International Concrete Repair Institute (ICRI).
 Shop drawings for the fabrication of panels will not require the Engineer's approval if fabrication is in accordance with the details shown on this standard.
 A panel layout which identifies location of each panel must be developed by the Fabricator. Permanently mark each panel in accordance with the panel layout. A copy of the layout is to be provided to the Engineer.

TRANSVERSE PANEL REINFORCEMENT:




For panel widths over 5', use 3/8" or 1/2" Dia (270k) prestressing strands with a tension of 14.4 kips per strand.
 For panel widths over 3'-6" up to and including 5', use 3/8" or 1/2" Dia (270k) prestressing strands with a tension of 14.4 kip per strand. Optionally, (#4) Grade 60 reinforcing bars may be used in lieu of prestressed strands.
 For panel widths up to 3'-6", use (#4) Grade 60 reinforcing bars (prestressed strands alone are not allowed).
 Place transverse panel reinforcement at panel centroid and space at 6" Max.

LONGITUDINAL PANEL REINFORCEMENT:



Any of the following options may be used for longitudinal panel reinforcement:
 1. (#3) Grade 60 reinforcing steel at 6" Max Spacing. No splices allowed.
 2. 3/8" Dia prestressing strands at 4 1/2" Max Spacing (unstressed). No splices allowed.
 3. 1/2" Dia prestressing strands at 6" Max Spacing (unstressed). No splices allowed.
 4. Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) providing 0.22 sq in per foot of panel width. Wires larger than D11 not permitted. Provide transverse wires to ensure proper handling of reinforcing. One splice per panel is allowed. See WWR Splice Detail.
 No combination of longitudinal reinforcement options in a panel is allowed. Place longitudinal panel reinforcement above or below transverse panel reinforcement. Must be placed above transverse panel reinforcement for skewed end panels with supplemental (#4) reinforcement.



No splice required for wires parallel to strands (transverse panel reinforcement)




TYPICAL SECTIONS FOR DETERMINING PANEL WIDTH




HL93 LOADING

		Bridge Division Standard	
PRESTRESSED CONCRETE PANEL FABRICATION DETAILS			
PCP-FAB			
FILE:	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT	April 2019	REVISED	
CONTRACT NO.	0901	SECTION	30
JOB NO.	018	COUNTY	CR
DISTRICT	PAR	COUNTY	RATNS
CHECKED BY		SHEET NO.	56

10/4/2023 8:35:55 PM
 DATE: 10/4/2023 8:35:55 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\13 MEBR(C).dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



ERECTION BRACING




PLAN


HAULING & ERECTION:
 The Contractor's attention is directed to the possible lateral instability of prestressed concrete girders and beams over 130' long, especially during hauling and erection. The use of the following methods to improve stability is encouraged: Locate lifting devices at the maximum practical distance from girder ends; use external lateral stiffening devices during hauling and erection; lift with vertical lines using two machines; and take care in handling to minimize inertial and impact forces.

ERECTION BRACING:
 Erection bracing details shown are considered the minimum for fulfilling the bracing requirements of Item 425. Required erection bracing must be placed immediately after erection of each girder and remain in place until additional bracing as required for slab placement is in place. This standard is needed in all cases to meet requirements for Slab Placement Bracing.

PHASED CONSTRUCTION:
 Place erection and slab placement bracing for all girders in a phase as shown in these details. For phases after first, also place erection and slab placement bracing between outer girder of completed phase and adjacent girder of current phase. When the phase construction joint is between girders, top bracing can be omitted.




DETAIL "A"



FOR ERECTION BRACING, OPTION 1

(This option is not allowed when slab is formed with PMDF or plywood.)




END VIEW

DIAGONAL BRACING DETAILS


(To be used on both ends of the first girder/beam erected in the span in each phase.)

- ① If angle shown exceeds 120 degrees, move diagonal brace to other side of girder/beam and place square to girder/beam. This may prevent exterior girder from being erected first.
- ② Place and weld #5 bars as shown during erection. If forming deck with prestressed panels, bars can be temporarily removed, one at a time, during panel erection. Re-install bar prior to additional panel erection. Bars can rest on panels and be bent down and welded to girder Bars R (See Sheet 2 of 2).
- ③ Clear distance between spacers must not exceed 3'. Nail together with 16d nails.
- ④ Use wedges as necessary to obtain tight fit. Nail wedges to timbers.
- ⑤ Pressure treated landscape timbers can not be used.
- ⑥ All hardware used with cable must be able to develop a minimum 25 kips breaking strength. Use thimbles at all loops in cable. Install cable clamps with saddles bearing against the live end and U-bolts bearing against the dead end.
- ⑦ It is acceptable to tie anchor bolts to cap reinforcement.
- ⑧ Prior to installing, field bend strap to lay flush on both girders' top flange and slope between flange tips.
- ⑨ Anchor bolt may be drilled and epoxied in place. Provide 25k minimum pullout. Core drill hole.




FOR ERECTION BRACING, OPTION 2

HORIZONTAL BRACING DETAILS




PLAN

DETAIL "B"



ELEVATION




PLAN

ANGLE BRACE DETAILS

SHEET 1 OF 2


		Bridge Division Standard			
MINIMUM ERECTION AND BRACING REQUIREMENTS PRESTRESSED CONCRETE I-GIRDERS AND I-BEAMS MEBR(C)					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
©TxDOT	August 2017	CONTRACT	SECTION	HIGHWAY	
	REVISIONS	0901	30	018	CR
		DIST	COUNTY	SHEET NO.	
		PAR	RATNS	57	

DATE: 10/4/2023 8:35:56 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Desi\gn\CAD Standards\03 BRIDGE STANDARDS\13 MEBR(C).dgn
 DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SLAB PLACEMENT BRACING


TABLE A				
Girder or Beam Type	OPTION 1-RIGID BRACING (STEEL STRAP)		OPTION 2-FLEXIBLE BRACING (NO. 5 OVER PCP)	
	Maximum Bracing Spacing		Maximum Bracing Spacing	
	Slab Overhang less than 4'-0" (11)	Slab Overhang 4'-0" and greater (11)	Slab Overhang less than 4'-0" (11)	Slab Overhang 4'-0" and greater (11)
Tx28	1/4 points	1/4 points	Tx28	1/4 points
Tx34	1/4 points	1/4 points	Tx34	1/4 points
Tx40	1/4 points	1/8 points	Tx40	1/4 points
Tx46	1/4 points	1/8 points	Tx46	1/4 points
Tx54	1/4 points	1/8 points	Tx54	1/4 points
Tx62	1/4 points	1/8 points	Tx62	1/4 points
Tx70	1/4 points	1/8 points	Tx70	1/4 points
A	1/8 points	1/8 points	A	2.0 ft
B	1/8 points	1/8 points	B	3.0 ft
C	1/8 points	1/8 points	C	4.5 ft
IV	1/4 points	1/8 points	IV	1/4 points
VI	1/4 points	1/8 points	VI	1/4 points



FOR SLAB PLACEMENT BRACING, OPTION 1 - RIGID
 (Showing slab formed with PCP. This option is not allowed when slab is formed with PMDF or plywood.)



FOR SLAB PLACEMENT BRACING, OPTION 2 - FLEXIBLE
 (Showing slab formed with PCP.)



PLAN
DETAIL "B"

HORIZONTAL BRACING DETAILS (5)


- (2) Place and weld #5 bars as shown during erection. If forming deck with prestressed panels, bars can be temporarily removed, one at a time, during panel erection. Re-install bar prior to additional panel erection. Bars can rest on panels and be bent down and welded to girder Bars R.
- (3) Clear distance between spacers must not exceed 3'. Nail together with 16d nails.
- (4) Use wedges as necessary to obtain tight fit. Nail wedges to timbers.
- (5) Pressure treated landscape timbers can not be used.
- (8) Prior to installing, field bend strap to lay flush on both girders' top flange and slope between flange tips.
- (10) Bracing spacing (1/4 and 1/8 points) measured between first and last typical brace location.
- (11) Measure slab overhang from centerline of girder or beam. When overhang varies in span, determine bracing spacing based on largest overhang.

SLAB PLACEMENT BRACING:
 The details for slab placement bracing are considered minimum for fulfilling the requirements of Specification Items 422 and 425. Required slab placement bracing must remain in place until slab concrete has attained a compressive strength of 3000 psi.



GENERAL NOTES:
 Bracing details for spans longer than 150' are not provided. The Contractor must submit proposed bracing details for such conditions to the Engineer for approval prior to erection. Systems equal to or better than those shown may be used provided details of such systems are submitted to and approved by the Engineer prior to erection. Use of these systems or details does not relieve the Contractor of the responsibility for the adequacy of the bracing and the safety of the structure. Removal of bracing for short periods of time to align girders and beams is permissible. All turn-buckles, come-alongs, anchors and other connections must be capable of developing the full strength of the cable shown. Furnish anchor bolts and nuts in accordance with Item 449, "Anchor Bolts".

		Bridge Division Standard	
MINIMUM ERECTION AND BRACING REQUIREMENTS PRESTRESSED CONCRETE I-GIRDERS AND I-BEAMS MEBR(C)			
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT August 2017	CON: 0901	SECT: 30	JOB: 018
REVISIONS:	COUNTY: PAR		HIGHWAY: CR
	COUNTY: RAINS		SHEET NO. 58

10/4/2023 8:35:58 PM
 DATE: 10/4/2023 8:35:58 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\14 TYPE T631LS.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- ① 9" Min, 5'-9" Max
- ② Maintain 6'-3" Rail Post spacing wherever possible for use with nominal 25'-0" or 12'-6" W-Beam sections. Symmetry of post spacing on both sides and along the structure is not necessary.
- ③ Increase 2" for structures with overlay.
- ④ Tighten the first hex nut by hand until the top and bottom edges of the W-Beam engage the Backer Plate (Backer Plate should be snug against the post). Then tighten hex nut one revolution with wrench and secure with the second hex nut.
- ⑤ PL $\frac{1}{8}$ " x $1\frac{3}{4}$ " x $1\frac{3}{4}$ " with $\frac{3}{8}$ " Dia Hole centered in PL (ASTM A36). Square Guardrail Washer (FWR01).
- ⑥ The post nearest to a slab joint or end of structure may be shifted up to 9" in order to satisfy the minimum offset dimension. Drill a new $\frac{3}{8}$ " Dia hole on the centerline of W-beam for shifted post. Paint hole with two coats of zinc-rich paint conforming to the Item "Galvanizing". All other posts must remain on the typical spacing.
- ⑦ $\frac{7}{8}$ " Dia formed holes for $\frac{3}{8}$ " Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ASTM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod. See "Cast-In-Place & Formed Hole Anchor Bolt Options".
- ⑧ $\frac{3}{8}$ " Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ASTM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod. See "Cast-In-Place & Formed Hole Anchor Bolt Options".




The use of this railing is restricted to speeds of 45 mph or less.


SHEET 1 OF 2

		Bridge Division Standard		
TRAFFIC RAIL				
TYPE T631LS				
FILE:	DN: TxDOT	CK: AES	DW: JTR	CK: AES
©TxDOT	September 2019	CONTRACT	SECTION	HIGHWAY
	REVISIONS	0901	30	018 CR
07/2020: Allowing 9'-4" or 6'-3" W-Beam sections	DIST	COUNTY	SHEET NO.	
03/2023: MBGF Notes	PAR	RAINS	59	


10/4/2023 8:35:59 PM
 DATE: 10/4/2023 8:35:59 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\14 TYPE T631LS.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




W-BEAM ELEVATION




W-BEAM SPLICE ELEVATION




POST ELEVATION



SECTION A-A




WASHER PLATE DETAIL



BACKER PLATE

$\frac{3}{8}$ " Dia heavy hex head anchor bolt (ASTM F3125 Gr A325 or A449) or threaded rod (ATSM A193 Gr B7 or F1554 Gr 105) with one hardened steel washer (ASTM F436) and one regular lock washer placed under heavy hex nut (ASTM A563). One additional heavy hex nut must be furnished and tack welded for each threaded rod.



CAST-IN-PLACE & FORMED HOLE ANCHOR BOLT OPTIONS (10)

- 9 See "Rail Details On Bridge Slab" and/or "Rail Section On Abutment Wingwall".
- 10 See "Material Notes" for anchor bolt information.
- 11 Backer PL 1/2" x 8 x 1'-3" (ASTM A1011 CS or SS Gr 33, or A1008 CS or SS Gr 33 (11 Gage acceptable)).
- 12 Used for structures with overlay.
- 13 Used for structures without overlay.
- 14 At the nominal end of the bridge rail for payment, one 9'-4 1/2" or 6'-3" W-beam section is permitted in order to achieve the required W-Beam splice location on the MBGF.

MBGF AND END TREATMENT NOTES:
 This traffic railing must be anchored by metal beam guard fence (MBGF) and/or guard fence end treatments. Determine MBGF length of need in accordance with the Roadway Design Manual, unless otherwise specified. The minimum MBGF length of need required for anchoring the railing is: SGT; or DAT plus 12.5' of MBGF, as applicable. Provide CRT posts as shown in "Roadway Elevation of Rail." The SGT and DAT plus 12.5' MBGF must be installed tangent to primary roadway.

CONSTRUCTION NOTES:
 Face of rail post must be plumb unless otherwise approved by the Engineer. Post must be perpendicular to adjacent roadway grade. Use epoxy mortar under post base plates if gaps larger than 1/16" exist.
 Fully anchored guardrail must be attached to each end of rail. A metal beam guard fence transition is not used with this rail.
 At the Contractor's option anchor bolts may be an adhesive anchor system. See "Material Notes".
 Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.
 It is recommended to show a Rail Layout with rail posts and W-beam splices. Fabricator must submit erection drawings to the Engineer for approval.
 Round or chamfer exposed edges of rail post and backer plate to approximately 1/16" by grinding.
 Shop drawings are not required for this rail.

MATERIAL NOTES:
 Galvanize all steel components.
 Anchor bolts for base plate must be 3/8" Dia ASTM F3125 Gr A325 or A449 bolts (or ASTM A193 Gr B7 or F1554 Gr 105 threaded rods with one tack welded heavy hex nut each) with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements.
 Optional adhesive anchorage system must be 3/8" Dia ASTM A193 Gr B7 or F1554 Gr 105 fully threaded rods with one hardened steel washer (ASTM F436) and one regular lock washer placed under each heavy hex nut. Nuts must conform to ASTM A563 requirements. Embed fully threaded rod into slab and/or abutment wingwall using a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 4 3/4". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 8 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing."
 W-beam must meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified in the plans. The Contractor may furnish rail elements of 25'-0" or 12'-6" (Nominal) lengths and a single rail element of 9'-4 1/2" or 6'-3" (Nominal) length. W-Beam must have slotted holes at 3'-1 1/2".
 Some part numbers from the "Task Force 13" Guide to Standardized Highway Barrier Hardware have been furnished for quick reference.


GENERAL NOTES:
 This railing has been successfully evaluated by full-scale crash test to meet MASH TL-2 criteria. This railing can be used for speeds of 45 mph and less.
 This rail is designed to deflect approximately 2' to 2'-6" as it contains and redirects the errant vehicle. This rail may not be installed on top of or behind curbs that project above finished grade, on bridges with expansion joints providing more than 5" movement, on retaining walls, or on grade separations and interchanges.
 Repairs to impact-damaged post and base plate unit are not permitted. Replace all impact-damaged posts with a new post and base plate unit.
 Average weight of railing with no overlay: 13 plf total.

SHEET 2 OF 2


		Bridge Division Standard	
<h1>TRAFFIC RAIL</h1>			
<h2>TYPE T631LS</h2>			
FILE:	DN: TxDOT	CK: AES	DW: JTR
©TxDOT	September 2019	CONTRACT	SECTION
REVISIONS	0901	30	018
07/2020: Allowing 9'-4 1/2" or 6'-3" W-beam sections	DIST	COUNTY	SHEET NO.
03/2023: MBGF Notes	PAR	RATNS	60

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:36:01 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\15_SRR.dgn




PLAN



ELEVATION




SECTION A-A AT CAP



SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".


8"X 18 Gage galvanized flashing full length of cap



CAP OPTION A

Nail flashing to cap or wingwall and seal with joint sealer

8"X 18 Gage galvanized flashing full length of cap



CAP OPTION B

DETAIL C

Plug ends and seal joint along ends of cap and side of wingwalls with joint sealer

GENERAL NOTES:

Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

SHEET 1 OF 2

					Bridge Division Standard
<h2>STONE RIPRAP</h2>					
<h3>SRR</h3>					
FILE:	DN: AES	CK: JGD	DW: BWH	CK: AES	
©TxDOT	April 2019	CONT	SECT	JOB	HIGHWAY
	REVISIONS	0901	30	018	CR
		DIST	COUNTY	SHEET NO.	
		PAR	RATNS	61	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:36:02 PM
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\03 BRIDGE STANDARDS\15_SRR.dgn




FIGURE 1 ~ TYPE R STONE RIPRAP
dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP
dry or mortared




FIGURE 3 ~ TYPE F STONE RIPRAP
grouted




FIGURE 4 ~ COMMON STONE RIPRAP
dry or grouted





FIGURE 5 ~ PROTECTION STONE RIPRAP

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



PROTECTION STONE RIPRAP TOE OPTIONS

SHEET 2 OF 2

		Bridge Division Standard			
<h2>STONE RIPRAP</h2>					
<h3>SRR</h3>					
FILE:	DN: AES	CK: JGD	DW: BWH	CK: AES	
©TxDOT	April 2019	CONTRACT	SECTION	HIGHWAY	
	REVISIONS	0901	30	018	CR
		DIST	COUNTY	SHEET NO.	
		PAR	RATNS	62	

DATE: 10/4/2023 8:36:04 PM
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\REFLECTOR\REFLECTOR.dwg
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into a digital format or for any errors or omissions resulting from its use.

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	DEVICE	SINGLE	DOUBLE	INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back	INSTL OM ASSM (OM-XX) (XXXX)XXX(XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
	SIZE 1	SIZE 2	SIZE 3	SIZE 4		SINGLE	DOUBLE		
SHEETING	Yellow, White or Red Type B or C reflective sheeting				SHEETING	Yellow, White or Red Type B or C Reflective Sheeting			
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF

OBJECT MARKERS								
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4
SHEETING	Yellow-Type B _{FL} or C _{FL} Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			Red -Type B _{FL} or C _{FL} Sheeting
POST TYPE	TWT	WC	WC	WFLX	TWT			TWT
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.		
DEVICE	GF1	GF2	CTB	W1-8				W1-6			
SHEETING	Yellow, White, Red			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only	MOUNTING HEIGHT	7'-0"		
				NOTE	1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).						

Texas Department of Transportation
Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

D & OM(1)-20

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	PAR	RATNS	63	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information contained herein.

DATE: 10/4/2023 8:36:05 PM
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\Standard\Traffic Safety Division\Standard

POST TYPE AND SUPPORT FOUNDATION DETAILS

TYPE OF BARRIER MOUNTS


WING CHANNEL (WC)

FLEXIBLE POSTS (YFLX, WFLX)


WEDGE ANCHOR SYSTEMS

GUARD FENCE ATTACHMENT


GND




GND




SRF




WAS




WAP



GF 1



GF 2



NOTES

1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only.
2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.


NOTES

1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices.
2. Install per manufacturer's recommendations.
3. Post length may vary to meet field conditions.
4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.

NOTE

1. Install per manufacturer's recommendations.

CONCRETE TRAFFIC BARRIER (CTB)




GENERAL NOTES

1. Place delineators on a section of roadway at a consistent distance from the edge of pavement.
2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS


CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN

DELINEATORS AND TYPE 2 OBJECT MARKERS




NOTE

Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)



NOTE

Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.



See general notes 1, 2 and 3.




DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2) -20

FILE: dcm2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	PAR	RATNS	64	


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**

D & OM(5) - 20








FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0901	30	018	CR
7-20	DIST	COUNTY	SHEET NO.	
	PAR	RAINS	66	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from one format to another.

DATE: 10/4/2023 8:36:07 PM
 FILE: T:\PARTPDD\CR_1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\09010301.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard or for any damages resulting from its use.

DATE: 10/4/2023 8:36:08 PM
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\Delin\Delin.dgn



OBJECT MARKERS SMALLER THAN 3 FT²

- NOTES**
- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
 - Mounting should be flush with top of attenuator. Minimum size 96" x 24".




NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.


		Traffic Safety Division Standard	
DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS D & OM(VIA) -20			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT
© TXDOT December 1989	CONT	SECT	HIGHWAY
REVISIONS	0901	30	018 CR
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	PAR	RAINS	67
4-98 7-20			
20G			

CK:
DW:
CK:
DW:



LEGEND

- DIRECTION OF TRAFFIC
- CHANNEL
- SILT FENCE
- ROCK FILTER DAM
- SEEDING & WATERING



Monte R. Rater P.E.
10.04.23
STATE OF TEXAS
MONTE L. RATER
#95859
LICENSED PROFESSIONAL ENGINEER

Texas Department of Transportation

CR 1495
SWP3 LAYOUT

©TxDOT 2023 SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
901	30	18	CR 1495
DIST	COUNTY	SHEET NO.	
PAR	RAINS	68	

NOTE: CONSTRUCTION EXIT LOCATION TO BE DETERMINED IN THE FIELD PRIOR TO CONSTRUCTION

DATE: 09/16/2023 03:53 PM
FILE: DOCUMENT NAME

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):
0901-30-018

1.2 PROJECT LIMITS:

FROM: @ WOODBURY CREEK

TO: _____

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 32.797489°, (Long) -95.838706°

END: (Lat) 32.797999°, (Long) -95.837942°

1.4 TOTAL PROJECT AREA (Acres): 0.343 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.06 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:
ROADWAY, BRIDGE, EROSION, & SEDIMENT CONTROL

1.7 MAJOR SOIL TYPES:

Soil Type	Description
NAHATCHE SOILS	CONSISTS OF CLAY LOAM, LOAM, AND STRATIFIED LOAM TO SILTY CLAY LOAM

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

- Other: _____
- Other: _____
- Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- _____

- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
SABINE RIVER	FRESHWATER STREAM


* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: _____
- Other: _____



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.				SHEET NO.
				69
STATE	STATE DIST.	COUNTY		
TEXAS	PAR	RAINS		
CONT.	SECT.	JOB	HIGHWAY NO.	
0901	30	018	CR	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.


2.8 DEWATERING:

2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.10 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.				SHEET NO.
				70
STATE	STATE DIST.	COUNTY		
TEXAS	PAR	RAINS		
CONT.	SECT.	JOB	HIGHWAY NO.	
0901	30	018	CR	

DATE: 10/4/2023
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Plan Sheets\EPIC.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.
2.
- No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.
2.
3.
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input checked="" type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input checked="" type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

1. LEAD INSPECTION REPORTS FOR THE WOODBURY CR BRIDGE INDICATE THAT PAINT ON THE STEEL STRUCTURES CONTAINS LEAD. ANY COATINGS, PAINT, OR OTHER ITEMS AT THIS LOCATION SHALL BE TREATED AS LEAD CONTAINING PAINT (LCP). FOR TASKS THAT EXPOSE AN EMPLOYEE TO LEAD ABOVE THE PERMISSIBLE EXPOSURE LIMIT (PEL), THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING EXPOSURE ASSESSMENT AND WORKER PROTECTION AS REQUIRED UNDER OSHA 1926.62 (LEAD IN CONSTRUCTION). WHEN STRIPPING BACK OF LEAD PAINT IS PERFORMED AS A PROTECTIVE MEASURE, STRIP BACK SUFFICIENT LCP TO FACILITATE THE PROJECT WORK. LCP INSPECTION REPORTS ARE AVAILABLE FOR REVIEW AT THE PARIS DISTRICT OFFICE. FOR ADDITIONAL INFORMATION CONTACT TxDOT'S DISTRICT ENVIRONMENTAL COORDINATOR AT 903-737-9300.


VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)


- No Action Required Required Action

Action No.

1.
2.
3.


 Texas Department of Transportation		Design Division Standard		
<h2 style="margin: 0;">ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</h2> <h3 style="margin: 0;">EPIC</h3>				
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP	CK: AR
©TxDOT: February 2015		CONT	SECT	HIGHWAY
12-12-2011 (DS) REVISIONS		0901	30	018
05-07-14 ADDED NOTE SECTION IV.		DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.		PAR	RATNS	71

10/04/2023
 T:\12\BRTD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\05 env standards\EC(1)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES


1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING


				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0901	30	018	CR	
	DIST	COUNTY		SHEET NO.	
	PAR	RAINS		72	

DATE: 10/4/2023
 FILE: T:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\05 env standards\EC(2)-16.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




FILTER DAM AT TOE OF SLOPE

(RFD1)




FILTER DAM AT SEDIMENT TRAP

(RFD1) OR (RFD2)




FILTER DAM AT CHANNEL SECTIONS

(RFD1) OR (RFD2) OR (RFD3)




"V" SHAPE PLAN VIEW




TYPE 4 (SACK GABIONS)


(RFD4)




SECTION B-B



SECTION A-A



PROFILE



SECTION C-C

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4"
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC(2)-16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0901	30	018
	DIST	COUNTY	SHEET NO.
	PAR	RAINS	73

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023
 FILE: I:\PARTPDD\CR 1495 @ Woodbury Creek Bridge Replacement\Design\CAD Standards\05 env standards\EC(3)-16.dgn



PLAN VIEW




ELEVATION VIEW


CONSTRUCTION EXIT (TYPE 1)
 ROCK CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 1)

- The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
- The coarse aggregate should be open graded with a size of 4" to 8".
- The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other materials approved by the Engineer.
- The construction exit shall be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW





ELEVATION VIEW

CONSTRUCTION EXIT (TYPE 2)
 TIMBER CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 2)

- The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50'.
- The treated timber planks shall be attached to the railroad ties with 1/2" x 6" min. lag bolts. Other fasteners may be used as approved by the Engineer.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The approach transitions shall be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- The construction exit should be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



SECTION A-A
 CONSTRUCTION EXIT (TYPE 3)
 SHORT TERM

GENERAL NOTES (TYPE 3)

- The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
- The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES CONSTRUCTION EXITS EC(3)-16			
FILE: ec316	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	0901	30	018
	DIST	COUNTY	SHEET NO.
	PAR	RAINS	74