

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED
HIGHWAY ROUTINE MAINTENANCE CONTRACT

| | | | | |
|---------------|-------------------------|-------------|---------|-------------|
| GRAPHICS FILE | MAINTENANCE PROJECT NO. | | | SHEET NO. |
| | RMC-637381001 | | | 1 |
| CHECKED | STATE | STATE DIST. | COUNTY | |
| | TEXAS | DALLAS | KAUFMAN | |
| CHECKED | CONT. | SECT. | JOB | HIGHWAY NO. |
| | 6373 | 81 | 001 | IH0020 |


TYPE OF WORK:

GUARD FENCE & CABLE BARRIER REPAIR

PROJECT NO. : RMC-637381001

HIGHWAY : IH0020

LIMITS : VARIOUS ROADWAYS IN THE KAUFMAN/ROCKWALL MAINTENANCE SECTION



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Lane D. Selman, PE 10/27/20
 DATE

© by Texas Department of Transportation
 (512) 416-2055 : all rights reserved



RECOMMENDED FOR LETTING

Lane D. Selman, PE 10/27 20 20
 AREA ENGINEER

RECOMMENDED FOR LETTING

DocuSigned by:
David Mornu, P.E. 12/10/2020
 72258D0350B94E4... 20
 DISTRICT MAINTENANCE ENGINEER

RECOMMENDED FOR LETTING


DocuSigned by:
JEFFREY BUSH 12/10/2020
 345B765E803F406... 20
 DIRECTOR OF OPERATIONS

| |
|------------------|
| LEVELS DISPLAYED |
| 1 2 3 4 |

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|--|----------------------------------|
| I. GENERAL | |
| 1 | TITLE SHEET |
| 2 | INDEX OF SHEETS |
| 3A-3B | ESTIMATE AND QUANTITY SHEET |
| 4A-4I | GENERAL NOTES |
| | |
| II. MISCELLANEOUS SHEETS | |
| 5 | STANDARD RAILING TYPE 4 RII-1946 |
| 6 | STANDARD RAILING TYPE II-1954 |
| 7 | GIBRALTAR CABLE BARRIER SYSTEM |
| | |
| III. MAINTENANCE STANDARD | |
| 8 | PCF-05 |
| | |
| IV. TRAFFIC ENGINEERING STANDARDS | |
| 9 | D & OM (1) - 20 |
| 10 | D & OM (2) - 20 |
| 11 | D & OM (5) - 20 |
| 12 | D & OM (VIA) - 20 |
| 13-24 | BC(1) - 14 THRU BC(12) - 14 |
| 25 | WZ(RS) - 16 |
| 26 | TCP (1-1) - 18 |
| 27 | TCP (1-2) - 18 |
| 28 | TCP (1-4) - 18 |
| 29 | TCP (1-5) - 18 |
| 30 | TCP (6-4) - 18 |
| | |
| V. TRAFFIC ENGINEERING STANDARDS | |
| 31 | GF(31) - 19 |
| 32 | GF(31)DAT - 19 |
| 33 | GF(31)LS - 19 |
| 34-35 | GF(31)TR TL3 - 19 |
| 36 | GF(31)TR TL2 - 19 |
| 37 | BED - 14 |
| 38 | SGT(10S)31 - 16 |
| 39 | SGT(11S)31 - 18 |
| 40 | SGT(12S)31 - 18 |
| 41 | SGT(15)31 - 20 |
| 42 | REACT(N) -16 |
| 43 | REACT(W) - 16 |
| 44 | SMTC(N) - 16 |
| 45 | SMTC(W) - 16 |
| 46 | QGUARD(M10)(N) - 20 |
| 47 | TRACC(W) - 16 |
| 48 | SSCC - 16 |
| 49A | CASS(TL3) - 14 |
| 49B | CASS(TL4) - 14 |
| 50A | GBRLTR(TL3) - 14 |
| 50B | GBRLTR(TL4) - 14 |
| 51 | MBGF - 19 |
| 52 | MBGF(SR) - 19 |
| 53 | MBGF(TR) - 19 |
| 54 | MBGF(TL2) - 19 |
| 55 | MBGF(T101) - 19 |
| 56 | GF(31)MS - 19 |
| 57 | BED(28) - 19 |

| SHEET NO. | DESCRIPTION |
|-----------------------------|---------------------|
| VI. BRIDGE STANDARDS | |
| 58-59 | TYPE T203 |
| 60-62 | TYPE T221 |
| 63-64 | TYPE T501 |
| 65 | MBGF (B) - 71 (MOD) |



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE
 SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING
 APPLICABLE TO THIS PROJECT.

Jahorroy, P.E. 10/28/20
 Signature of Registrant & Date



INDEX OF SHEETS

| DESIGN | FED. RD. DIV. NO. | MAINTENANCE PROJECT NO. | | HIGHWAY NO. |
|----------|-------------------|-------------------------|--------|-------------|
| GRAPHICS | 6 | RMC-637381001 | | IH0020 |
| CHECK | TEXAS | DISTRICT | COUNTY | SHEET NO. |
| CHECK | CONTROL | SECTION | JOB | 2 |
| | 6373 | 81 | 001 | |

Estimate Sheet

| ESTIMATE SUMMARY | | | | | | | | | | | | | | | |
|------------------|-------|-----|-------|-----|-------|-------------------------------|-------|-------------|--------------|--------------|----------|---|------|-----------|-------|
| | | | | | | CONTROL 6373-81-001 IH0020 | | A L T | ITEM CODE | | | DESCRIPTION | UNIT | TOTAL | |
| EST | FINAL | EST | FINAL | EST | FINAL | EST | FINAL | | ITEM CODE | DESC CODE | SP NO | | | EST | FINAL |
| | | | | | | 300.000 | | | 104 | 6021 | | REMOVING CONC (CURB) | LF | 300.000 | |
| | | | | | | 150.000 | | | 429 | 6007 | | CONC STR REPAIR (VERTICAL & OVERHEAD) | SF | 150.000 | |
| | | | | | | 100.000 | | | 432 | 6045 | | RIPRAP (MOW STRIP)(4 IN) | CY | 100.000 | |
| | | | | | | 100.000 | | | 500 | 6033 | | MOBILIZATION (CALLOUT) | EA | 100.000 | |
| | | | | | | 300.000 | | | 529 | 6002 | | CONC CURB (TY II) | LF | 300.000 | |
| | | | | | | 500.000 | | | 540 | 6001 | 001 | MTL W-BEAM GD FEN (TIM POST) | LF | 500.000 | |
| | | | | | | 200.000 | | | 540 | 6002 | 001 | MTL W-BEAM GD FEN (STEEL POST) | LF | 200.000 | |
| | | | | | | 2.000 | | | 540 | 6006 | 001 | MTL BEAM GD FEN TRANS (THRIE-BEAM) | EA | 2.000 | |
| | | | | | | 1.000 | | | 540 | 6013 | 001 | TRANSITION ADJUSTMENT | EA | 1.000 | |
| | | | | | | 200.000 | | | 540 | 6014 | 001 | SHORT RADIUS | LF | 200.000 | |
| | | | | | | 5.000 | | | 540 | 6016 | 001 | DOWNSTREAM ANCHOR TERMINAL SECTION | EA | 5.000 | |
| | | | | | | 200.000 | | | 542 | 6001 | | REMOVE METAL BEAM GUARD FENCE | LF | 200.000 | |
| | | | | | | 10.000 | | | 544 | 6001 | | GUARDRAIL END TREATMENT (INSTALL) | EA | 10.000 | |
| | | | | | | 5.000 | | | 545 | 6005 | | CRASH CUSH ATTEN (REMOVE) | EA | 5.000 | |
| | | | | | | 2.000 | | | 545 | 6006 | | CRASH CUSH ATTEN (INSTL)(L)(N)(TL2) | EA | 2.000 | |
| | | | | | | 5.000 | | | 545 | 6007 | | CRASH CUSH ATTEN (INSTL)(L)(N)(TL3) | EA | 5.000 | |
| | | | | | | 100.000 | | | 658 | 6013 | | INSTL DEL ASSM (D-SW)SZ (BRF)CTB | EA | 100.000 | |
| | | | | | | 100.000 | | | 658 | 6026 | | INSTL DEL ASSM (D-SY)SZ (BRF)CTB | EA | 100.000 | |
| | | | | | | 100.000 | | | 658 | 6027 | | INSTL DEL ASSM (D-SY)SZ (BRF)CTB (BI) | EA | 100.000 | |
| | | | | | | 100.000 | | | 658 | 6067 | | INSTL DEL ASSM (D-DW)SZ 1(BRF)GF2 | EA | 100.000 | |
| | | | | | | 100.000 | | | 658 | 6068 | | INSTL DEL ASSM (D-DY)SZ 1(BRF)GF2 | EA | 100.000 | |
| | | | | | | 15000.000 | | | 770 | 6001 | | REPAIR RAIL ELEMENT (W - BEAM) | LF | 15000.000 | |
| | | | | | | 150.000 | | | 770 | 6002 | | REPAIR RAIL ELEMENT (THRIE - BEAM) | LF | 150.000 | |
| | | | | | | 25.000 | | | 770 | 6003 | | REP RAIL ELMNT(THRIE-BM TRANS TO W -BM) | LF | 25.000 | |
| | | | | | | 150.000 | | | 770 | 6004 | | REPAIR RAIL ELEMENT (CURVED RAIL) | LF | 150.000 | |
| | | | | | | 115.000 | | | 770 | 6005 | | REM/REPAIR RAIL ELEMENT (CURVED RAIL) | LF | 115.000 | |
| | | | | | | 2000.000 | | | 770 | 6006 | | RAISE RAIL ELEMENT | LF | 2000.000 | |
| | | | | | | 150.000 | | | 770 | 6008 | | REALIGN EXISTING RAIL | LF | 150.000 | |
| | | | | | | 1000.000 | | | 770 | 6012 | | REM / REPL TIMBER POST W / O CONC FND | EA | 1000.000 | |
| | | | | | | 21.000 | | | 770 | 6013 | | REM / REPL STEEL POST W / O CONC FND | EA | 21.000 | |
| | | | | | | 50.000 | | | 770 | 6014 | | REM / REPL TIMBER POST W / CONC FND | EA | 50.000 | |
| | | | | | | 20.000 | | | 770 | 6015 | | REM / REPL STEEL POST W / CONC FND | EA | 20.000 | |
| | | | | | | 585.000 | | | 770 | 6017 | | REALIGN POSTS | EA | 585.000 | |
| | | | | | | 500.000 | | | 770 | 6019 | | REMOVE & REPLACE BLOCKOUT | EA | 500.000 | |
| | | | | | | 5000.000 | | | 770 | 6021 | | REPLACE SINGLE GDRAIL TERMINAL RAIL | LF | 5000.000 | |
| | | | | | | 1000.000 | | | 770 | 6022 | | REPLACE SINGLE GDRAIL TERMINAL POST | EA | 1000.000 | |
| | | | | | | 5.000 | | | 770 | 6024 | | REPLACE TERMINAL ANCHOR POSTS | EA | 5.000 | |
| | | | | | | 20.000 | | | 770 | 6027 | | REMOVE GDRAIL END TRT / REPL WITH SGT | EA | 20.000 | |
| | | | | | | 200.000 | | | 770 | 6028 | | REPL SINGLE GDRAIL TERM IMPACT HEAD | EA | 200.000 | |
| | | | | | | 70.000 | | | 770 | 6029 | | REM & RESET SGT IMPACT HEAD | EA | 70.000 | |
| | | | | | | 150.000 | | | 770 | 6030 | | REPLACE SGT CABLE ASSEMBLY | EA | 150.000 | |
| | | | | | | 150.000 | | | 770 | 6031 | | REPLACE SGT CABLE ANCHOR | EA | 150.000 | |
| | | | | | | 100.000 | | | 770 | 6032 | | REPLACE SGT STRUT | EA | 100.000 | |
| | | | | | | 110.000 | | | 770 | 6033 | | REPLACE SGT OBJECT MARKER | EA | 110.000 | |
| | | | | | | 100.000 | | | 770 | 6052 | | REPAIR STEEL POST WITH BASE PLATE | EA | 100.000 | |
| | | | | | | 200.000 | | | 770 | 6057 | | REMOVE & REPLACE STL BLOCKOUT | EA | 200.000 | |
| | | | | | | 150.000 | | | 771 | 6001 | | REPLACE POSTS (TL-3) | EA | 150.000 | |
| | | | | | | 2500.000 | | | 771 | 6002 | | REPLACE POSTS (TL-4) | EA | 2500.000 | |
| | | | | | | 10.000 | | | 771 | 6003 | | CABLE SPLICE / TURNBUCKLE (TL-3) | EA | 10.000 | |
| | | | | | | 50.000 | | | 771 | 6004 | | CABLE SPLICE / TURNBUCKLE (TL-4) | EA | 50.000 | |

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

GENERAL NOTES:

General:

This project consists of performing "Guard Fence & Cable Barrier Repair" on various roadways in the Kaufman-Rockwall Maintenance Section.

The Department reserves the right to revise schedule as it deems necessary.

Provide and maintain a dedicated email address for receipt of work orders and correspondence throughout the term of this contract. Acknowledgement of emailed work order/callouts is required no less than 12 hr. from notification.

Contractor's attention is called to the fact that all adjoining pavement sections will be protected during all phases of construction and any damages incurred due to Contractor's operation will be repaired and replaced at the Contractor's expense.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through:

Melvin Harris
2570 S. Washington St.
Kaufman, Texas 75142
972-962-3848

Contractor questions on this project are to be emailed to the following individuals:

Melvin Harris Melvin.D.Harris@txdot.gov
LeAnn Kemp LeAnn.Kemp@txdot.gov

Contractor questions will only be accepted through email to the above individuals.

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Attention is directed to the possible presence of underground utilities owned by the Texas Department of Transportation (irrigation, signal, illumination and surveillance, communication, and control) on the right of way. Call the Department for locates at 214-320-6682 and 214-320-6205 48 hr. in advance of excavation. Contact the appropriate department of the local city or town a minimum of 48 hr. in advance of excavation.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Cost associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Item 2 – Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal.

Order plans from any Reproduction Company listed at:

http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

View or download plans at:

<http://www.dot.state.tx.us/business/plansonline/plansonline.htm>

Item 3 – Award and Execution of Contract:

This contract is Non-Site Specific.

After written notification, work request will be on a callout basis.

Each callout work request will be continuously prosecuted to completion.

Work site is defined as the locations presented on the written callout work request.

Minimum quantity is \$1,000 per written callout notification.

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

Schedule and begin physical work on the repair items in the order presented in each written callout work request within 48 hr. or as directed.

Item 7 – Legal Relations and Responsibilities:

Pre-construction safety meeting will be conducted with Contractor’s personnel prior to work beginning on a continuously prosecuted contract or before each callout work request

Attendance of this meeting will not be paid directly but considered subsidiary to the various bid items

There are no significant traffic generators identified for this project.

Holiday restrictions – the Engineer may decide that no lane closures or construction operations will be allowed during the restricted periods listed in the following holiday schedule. TxDOT has the right to lengthen, shorten, or otherwise modify these restricted periods as actual, or expected, traffic conditions may warrant.

- New Year’s Eve and Day (noon on December 31 thru 10 P.M. January 1)
- Easter Holiday weekend (noon on Friday thru 10 P.M. Sunday)
- Memorial Day weekend (noon on Friday thru 10 P.M. Monday)
- Independence Day (noon on July 3 thru 10 P.M. on July 5)
- Labor Day weekend (noon on Friday thru 10 P.M. Monday)
- Thanksgiving Holiday (noon on Wednesday thru 10 P.M. Sunday)
- Christmas Holiday (noon on December 23 thru 10 P.M. December 26)

Holiday restrictions for Independence Day, Thanksgiving Holiday, and the Christmas Holiday may be extended for the “week of” due to the nature of work being performed and the work location at the discretion of the Engineer for safety of the traveling public.

There are no significant traffic generators identified for this project.

Item 8 – Prosecution and Progress:

Working days will be charged in accordance with Section 8.3.1.5., “Calendar Day”.

The response time specified in this contract is an essential element. Liquidated damages will be assessed when the Contractor fails to begin work within the specified response time and/or the Contractor does not have all of the personnel and pieces of equipment necessary to fulfill the requirement of the item(s). The dollar amount specified in this contract will be deducted from

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

any money due or to become due for any Item(s) and will continue to be deducted for each day until work begins. This amount will be assessed not as a penalty, but as liquidated damages.

The continuous prosecution of each callout work request is an essential element of the contract. Failure to respond to a callout work request in the time frame allowed or discontinuance of the prosecution of work on any callout work request without the Engineer’s approval will result in liquidated damages being charged each working day that the callout work request remains incomplete. The dollar amount specified in the contract will be deducted from any money due or to become due the Contractor. This amount will be assessed not as a penalty but as liquidated damages.

The continuous prosecution to completion is an essential element of the contract. Failure to continuously prosecute the work without the Engineer’s approval will result in liquidated damages being charged each working day until work commences. The dollar amount specified in the contract will be deducted from any money due or to become due to the Contractor. This amount will be assessed not as a penalty but as liquidated damages.

When a minimum production rate is shown in the plans, liquidated damages will be charged for each working day the minimum production rate is not met.

Item 9 – Measurement and Payment:

Do not obtain law enforcement personnel without requesting in writing 48 hr. prior to need and the Engineer’s written approval. The Department may compensate the Contractor for providing full time, off-duty, uniformed, law enforcement personnel, and patrol car. The law enforcement personnel may be required for assistance with traffic control for lane or ramp closures or other situations that dictate the need for law enforcement officers as directed. Off-duty law enforcement personnel will have transportation jurisdiction and full police powers. Law enforcement personnel will show proof of certification by the Texas Commission on Law Enforcement (TCOLE). This will be paid under “Force Account – Law Enforcement Personnel”. TxDOT Form 318 will be utilized.

Payment for police officer hours under force account method will not exceed the duration of the lane closure. Time will begin when set up operations commence and end when the closure is removed.

Item 421 – Hydraulic Cement Concrete:

Furnish mix designs to the Engineer in a format compatible to the latest version of the Department’s Construction Management System (Site Manager).

Mix Design templates may be downloaded at:

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

<http://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/forms/site-manager.html>.

All test molds will be furnished by the Contractor and will be maintained in proper condition. Provide personnel to transport the test samples to a curing location as directed, remove from the mold to a curing tank. Concrete will not be placed when impending weather conditions arise, and it is determined rainfall may occur. If rainfall should begin after the placement operations begin, the Contractor will provide coverage to protect the work. If texture of the pavement is destroyed or damaged, Contractor will restore the pavement texture by grooving or as directed.

Item 500 – Mobilization:

Mobilization is call-out.

Item 502 – Barricades, Signs, and Traffic Handling:

Provide traffic control in compliance with the latest edition of the “Texas Manual on Uniform Traffic Control Devices” (TMUTCD), the “Traffic Control Standard Sheets” (TCSS), and as directed.

Perform work Monday through Friday during daylight hours. Do not begin work until 30 minutes after sunrise and cease operations 30 minutes before sunset.

If closing a lane is necessary, closure times will be Monday through Friday, 9 A.M. to 3:30 P.M. Close no more than one lane at a time, unless otherwise approved. Provide proposed lane closure information to the Engineer by 1 P.M. on the day prior to the proposed closures. Furnish information for Monday closures or closures following a national or state holiday on the last office workday prior to the closures. Do not close lanes if the above reporting requirements have not been met.

Nighttime and weekend work will be allowed with prior approval, except for emergency work.

Maximum length of lane closure will be 2 miles.

Traffic Control Plans with a lane closure causing backups of 20 minutes or greater in duration will be modified by the Engineer.

Erect barricades and signs in locations not obstructing the traveling public’s view of the normal roadway signing or necessary sight distance.

Provide sufficient and qualified staff and equipment to revise the traffic control as directed.

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

Trailer all slow moving vehicles (designed to operate 25 mph or less) crossing freeway main lanes.

When moving unlicensed equipment on or across any pavement or public highways, protect the pavement from all damage using an acceptable method.

Equipment and materials will not be left within 30 ft. of the travel lane during non-working hours.

The work performed, materials furnished and all labor, tools, and equipment necessary to complete the work for Non-Site Specific locations under this Item will not be measured or paid for directly but will be considered subsidiary to the various bid items of this contract.

The “Force Account – Safety Contingency” has been established for this project and is intended to be utilized for work zone enhancements to improve the effectiveness of the Traffic Control Plan that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 540 – Metal Beam Guard Fence:

This bid item is to be used at locations where metal beam guard fence did not previously exist (or at locations where the metal beam guard fence is to be upgraded to current standard as directed).

Use GF(31) series standards and BED-14 standard for work performed under this item.

New metal beam guard fence at locations where it is repaired or replaced in like kind will be paid for under Item 770 “Guard Fence Repair”.

Item 542 – Removing Metal Beam Guard Fence:

This bid item is to be used at locations where the metal beam guard fence is removed but not replaced as directed or at locations where the metal beam guard fence is removed and upgraded to current standards as directed.

Removal of metal beam guard fence to be repaired or replaced in like kind will be paid for under Item 770 “Guard Fence Repair”.

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

Item 544 – Guardrail End Treatment:

This bid item is to be used at locations where guardrail end treatments did not previously exist.

Use 31 in. standards for work performed under this item.

Guardrail end treatments at locations where they are repaired, replaced in like kind, or replaced with SGT will be paid for under Item 770 “Guard Fence Repair”.

Item 545 – Crash Cushion Attenuator:

A MASH compliant attenuator is required for new installation.

Payment for “Remove” will only be made when replacement end treatment does not match existing end treatment.

The bidirectional traffic transition is required for each installation on the project. Transitions will not be measured or paid for directly but will be subsidiary to pertinent Items.

Item 658 – Delineator and Object Marker Assemblies:

Provide a flat mount delineator for guard fence attachment meeting the following requirements. 33 in. in length and be flattened and sealed on each end enabling mounting height to be consistent without the use of a tape measure. Post will be a minimum of 2-3/8 in. outside diameter composed of recycled tire rubber and post-consumer materials. Post will be permanently sealed at the top and be a minimum of 3 in. wide and capable of displaying a 3 in. wide by 12 in. long piece of reflective sheeting.

Item 770 – Guard Fence Repair:

Perform work Monday through Friday, unless otherwise approved.

Furnish all materials.

The Engineer will determine whether damaged Guard Fence will be repaired or whether to upgrade the installation to current standards using other items of work.

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

Use MBGF series standards, BED(28)-19 standard and 28 in. SGT standards or use GF(31) series standards, BED-14 standard and 31 in. SGT standards as appropriate for each damaged installation.

Item 771 – Repair Cable Barrier System:

Furnish all materials.

Place or replace a reflective delineator on every 3rd post of the cable system. This will not be paid directly but will be subsidiary to this item.

Replacement parts will be the appropriate test level shown below.

The Gibraltar System (TL-3) is on US 175 from East of Bud Stoeys to FM 1390 (MM 616-618) and from FM 2860 to Henderson County Line (MM 630-MM644).

The Gibraltar System (TL-4) is on the following:

IH 20 from Dallas County Line to Van Zandt County Line (MM 487-MM 513)

US 80 from Dallas County Line to FM 1392 (MM 672-MM 682) and from FM 429 to Van Zandt County Line (MM 688-700)

US 175 from Dallas County Line to SH 34 By Pass (MM 608-MM 622).

The Cass System TL-4 is on IH 30 from SH 205 to Hunt County Line (MM 69-MM 79)

Re-tensioning will be done as directed.

Retro-fit detail “Gibraltar Cable Barrier System” is for Contractor’s Information Only for foundation replacement use.

Disconnection and replacement of the cable at Retro-fit locations will be subsidiary to various bid items.

Re-tensioning will be done in accordance with manufacturer’s recommendations.

Item 772 – Post and Cable Fence:

Furnish all materials and hardware.

Item 774 – Attenuator Repair:

Begin physical work within 48 hr. of each written notification.

Project Number: RMC-637381001

Control: 6373-81-001

County: Kaufman

Highway: IH0020

Remove and replace with a MASH compliant system as directed.

Payment for removal of an existing crash cushion will only be made when replacement attenuator does not match the existing attenuator.

Hardware is subsidiary to this item.

If concrete is needed, furnish Class "A" Concrete in accordance with Item 421.

Item 776 – Metal Rail Repair:

Furnish all materials.

Item 6001 – Portable Changeable Message Sign:

Provide Portable Changeable Message Signs (PCMS) units as approved.

PCMS will be placed as directed.


Item 6185 – Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA):

The total number of truck mounted attenuators (TMA) required when utilizing the traffic control standards are shown in the tables below.

| TCP 1 Series | Scenario | Required TMA |
|--------------|----------|--------------|
| (1-1)-18 | | 1 |
| (1-2)-18 | | 1 |
| (1-4)-18 | | 1 |
| (1-5)-18 | | 1 |
| TCP 6 Series | Scenario | Required TMA |
| (6-4)-12 | A | 1 |
| | B | 2 |

Shadow vehicles equipped for truck mounted attenuators (TMA) for mobile and stationary operations must be available for use at any time as determined by the Engineer.

The Contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA needed for the project for those times per plan requirements. Additional TMAs used that are not specified in the plans in which the Contractor expects compensation will require prior approval from the Engineer.




The approach Posts may be precast or cast in place. If cast in place, the portion below the ground line may be round of 10" min. diameter; the forms being omitted if the material is such that it will not cave.


ELEVATION
OUTSIDE FACE

3/4" Expansion-bolt
balls. Draw nuts tight then
back nuts off 1/4" to 5/8"
burr threads.

Note:
The minimum number of rail splices may be used as required at interior posts, as long as individual sections within lengths of 40 feet. Splices shall not be introduced at points nearer than two post spacings from end of railing or from an expansion joint of the structure.




RAIL SPLICE




SECTION C-C

At end of railing, chain
links may be allowed
to facilitate barbing,
for slabs with weld rebar,
and grade of concrete.




SECTION A-A
INTERMEDIATE POST

VIEW B-B
INSIDE FACE



APPROACH POSTS



DETAIL OF WF BEAM ANCHOR SECTION
AND METHOD OF RAILERECTION

Outlets from anchor section shall be aligned by
transit or right wire with such accuracy as to insure full
bearing and true alignment of railing.
All continuous lengths of railing between expansion
joints of the structure or between expansion joints and
end of railing shall be completely erected in an offset
position & rigidly held to line and grade for a minimum of
48 hours after all posts are placed. The railing shall be
completely supported independent of post forms.
All spacer blocks shall be of identical thickness and
each shall have parallel surfaces of contact.


GENERAL NOTES:-

- All concrete shall be Class A. All corners for concrete posts shall be rubbed to 1/4" radius.
- Dimensions relating to reinforcing steel are to centers of bars.
- Vertical reinforcing for concrete posts shall be set when placing concrete in spans. All anchorage provisions are considered as part of the railing.
- Railing and other exposed metal surfaces shall be painted according to prevailing specifications; embedded metal shall not be painted.
- All posts shall be set vertically.
- If the metal railing is properly cleaned by sandblasting or pickling, the shop coat of paint may be applied by spray.


TEXAS HIGHWAY DEPARTMENT
EXISTING RAILING
TYPE 4
R II (1946)

Texas Department of Transportation


| | | | | |
|------------------------|-----------|-----------|-----------------|--------------|
| FILE: qf31trf1319.dgn | DIST: D01 | CR: KM | DR: KM | CR: CGL/AG |
| © TxDOT: NOVEMBER 2019 | CONT: 81 | JOB: 001 | HIGHWAY: IH0020 | |
| REVISIONS | | DIST: DAL | COUNTY: KAUFMAN | SHEET NO.: 5 |




ELEVATION - OUTSIDE FACE




ELEVATION - OUTSIDE FACE
30'-0" & 30'-4" & 40'-0" CONG. SLAB
AND GIRDER SPANS




SPLICES



SHIM DETAIL




SECTION - 9" CURBS
30'-0" & 30'-4" & 40'-0" CONG. SLAB
AND GIRDER SPANS
2'-0" ROWING ONLY




SECTION - 9" CURBS

OUTSIDE ELEVATION



SECTION - 18" CURBS



SECTION - 18" CURBS
30'-4" & 40'-0" CONG. SLAB
AND GIRDER SPANS
[25'-0" ROWING ONLY]


GENERAL NOTES:
 Rail sections may be of two panel lengths or continuous for a number of panel lengths not to exceed 50'-0" length.
 All anchorage provisions including bolts, nuts, washers, shim plates and 3 hook anchor bolts are considered parts of the railing.
 The lower anchor bolts for posts at the downstream ends of skewed spans shall be bent as required to provide a maximum penetration of bolts into slab and to provide a minimum cover of 1 1/2" for the bolt.
 At posts where railing channel is applied provide 3" opening between ends of channel, tighten 6" bolts and then back off 1/2" turn and bolt threads.
 Rail Post anchor bolts, nuts and washers shall, after shop fabrication, be conditioned by the Lightite Process in accordance with A.S.T.M. Spec. A 153 or Galvanneal in accordance with A.S.T.M. Spec. 158.
 All Posts shall be set vertically.
 If the metal railing is properly cleaned by sand blasting or pickling the shop coat of paint may be applied by spray.

TEXAS HIGHWAY DEPARTMENT
 EXISTING RAILING
 TYPE II (1954)


Texas Department of Transportation

| | | | | |
|------------------------|----------|---------|-----------|-----------|
| FILE: qf31trf1319.dgn | DW:TxDOT | CR:KM | DW:KM | CR:CGL/AG |
| © TXDOT: NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | IH0020 |
| | DIST | COUNTY | SHEET NO. | |
| | DAL | KAUFMAN | 6 | |

Cable Barrier System Direction >>>



Cable Barrier System Direction >>>



Note:
Drill 24" DIA. x 14'-0" deep in front of existing terminal and tie into existing terminal using rebar dowels as shown.




DAVID
2/5/2008

GIBRALTAR CABLE
BARRIER SYSTEM
(Gibraltar Inc.)


| | | | | |
|------------------------|------------|-----------------|--------------|-----------------|
| FILE: g7319r+1319.dgn | DW: TRDOT | ERI: KM | DW: KM | ERI: CGL/AG |
| © TRDOT: NOVEMBER 2019 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: IH0020 |
| REVISIONS | DIST: DAL | COUNTY: KAUFMAN | SHEET NO.: 7 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| LEVELS DISPLAYED | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 |
|------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|




WOOD POST & CABLE UNIT



WOOD POST DETAIL




CONCRETE ANCHOR DETAILS



THIMBLE-EYE BOLT DETAILS


Clamp keepers on both sides of Reflector as shown above.




OBJECT MARKER KEEPER DETAIL

GENERAL NOTES


1. Furnish Class "B" or better concrete in accordance with Item 421, "Hydraulic Cement Concrete". Cure concrete anchors at least five (5) days before attaching the cable.
2. Furnish galvanized cable fittings in accordance with the Item 445, Galvanizing.
3. Furnish posts meeting the requirements of DMS 7200, "Timer Posts and Blocks for Metal Beam Guard Fence." Do not use painted timber posts.
4. Cover the entire surface of object marker (reflector) with a reflectorized sheeting material conforming to Departmental Material Specification DMS 8300, "Sign Face Materials", Type C.
5. Furnish cable conforming to ASTM designation A475.



WIRE CABLE CONNECTION (at turnbuckles & eyebolts) DETAIL



TOP VIEW



SIDE VIEW

SLIP JOINT DETAIL

Texas Department of Transportation
Maintenance Division

POST & CABLE FENCE

PCF-05

| | | | | | |
|------------------------------|---------|---------|---------------------------|--------|---------|
| FILE: pcF05.dgn | DN: | CK: | DW: LJB | CK: JG | NEG: |
| © TxDOT FEB. 2005 | DIST | FED REC | MAINTENANCE PROJECT NO. # | | SHEET |
| REVISIONS | DALLAS | 6 | RMC-637381001 | | 8 |
| 2/02 Rev. Design Div. PCF-99 | COUNTY | CONTROL | SECT | JOB | HIGHWAY |
| | KAUFMAN | 6373 | 81 | 001 | TH0020 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

| REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS | | | | DELINEATORS | | | | D & OM DESCRIPTIVE CODES | |
|---|--------|--------|--------|--|--------|-------------------------|-------------------------|--|--------------------------|
| DEVICE | SIZE 1 | SIZE 2 | SIZE 3 | SIZE 4 | DEVICE | SINGLE | DOUBLE | INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) | |
| | | | | | | 1-Size 2 reflector unit | 1-Size 1 reflector unit | 2-Size 2 reflector units | 2-Size 1 reflector units |
| SHEETING: Yellow, White or Red Type B or C reflective sheeting | | | | SHEETING: Yellow, White or Red Type B or C Reflective Sheeting | | | | | |
| NOTE: 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes. | | | | POST TYPE: WC, YFLX, WFLX, GND | | | | | |
| | | | | MOUNT TYPE: GND, SRF | | | | | |

| OBJECT MARKERS | | | | | | | | D & OM DESCRIPTIVE CODES | |
|---|---------------|---------------|-------|---------------|-------|-------|---------------|--------------------------------------|---|
| DEVICE | Type 1 (OM-1) | Type 2 (OM-2) | | Type 3 (OM-3) | | | Type 4 (OM-4) | INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) | |
| | OM-1 | OM-2X | OM-2Y | OM-2Z | OM-3L | OM-3R | OM-3C | OM-4 | TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional |
| SHEETING: Yellow-Type B or C Sheeting FL, Yellow - Type B or C Sheeting, Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting, Red -Type B _{FL} or C _{FL} Sheeting | | | | | | | | | |
| POST TYPE: TWT, WC, WFLX, TWT | | | | | | | | | |
| MOUNT TYPE: WAS, WAP, GND, GND, GND, SRF, WAS, WAP, WAS, WAP | | | | | | | | | |

| DEPARTMENTAL MATERIAL SPECIFICATIONS | |
|--|----------|
| FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES) | DMS-4400 |
| SIGN FACE MATERIALS | DMS-8300 |
| DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS | DMS-8600 |

| BARRIER REFLECTORS (BRF) | | | CHEVRONS | | | | ONE DIRECTION LARGE ARROW | | NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative. |
|---|-----|-----|--|------|--|--|--|------|--|
| DEVICE | GF1 | GF2 | CTB | W1-8 | | | | W1-6 | |
| 1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov. | | | 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6). | | | | | | |
| SHEETING: Yellow, White, Red | | | SIZE (W x L): 18"x 24" (Conventional), 24"x 30" (Conventional Oversize), 30"x 36" (Expressway), 36" x 48" (Freeway) | | | | SIZE (W x L): 48" x 24" (Conventional), 60" x 30" (Expressway & Freeway) | | |
| NOTE: 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches. | | | MOUNTING HEIGHT: 4'-0" or 7'-0", 7'-0" Only | | | | MOUNTING HEIGHT: 7'-0" | | |



DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

D & OM(1)-20

| | | | | |
|---------------------|--------------|-----------------|-------------|----------------|
| FILE: dom1-20.dgn | DN: TXDOT | CR: TXDOT | OW: TXDOT | CK: TXDOT |
| © TXDOT August 2004 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 10020 |
| 10-09 3-15 | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 9 | |
| 4-10 7-20 | | | | |

DATE: DATE TIME
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

POST TYPE AND SUPPORT FOUNDATION DETAILS

TYPE OF BARRIER MOUNTS

WING CHANNEL (WC)

FLEXIBLE POSTS (FLX)

WEDGE ANCHOR SYSTEMS

GUARD FENCE ATTACHMENT

GND

GND








SRF

WAS

WAP

GF1

GF2



NOTES

1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only.
2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.

EMBEDDED

NOTES

1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices.
2. Install per manufacturer's recommendations.
3. Post length may vary to meet field conditions.

STEEL


PLASTIC

NOTE

1. Install per manufacturer's recommendations.

CONCRETE BARRIER / BRIDGE RAIL




CTB



TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS

CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN

DELINEATORS AND TYPE 2 OBJECT MARKERS



NOTE

Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

NOTE

Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTIONAL LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

See general notes 1, 2 and 3.

GENERAL NOTES

1. Place delineators on a section of roadway at a consistent distance from the edge of pavement.
2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.




DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-15


| | | | | |
|---------------------|-----------|-----------|-----------|-----------|
| FILE: dom2-15.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT August 2004 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 10-09 3-15 | DIST | COUNTY | SHEET NO. | |
| 4-10 | DALLAS | KAUFMAN | 10 | |

DATE: DATE TIME
 FILE: DOCUMENT NAME

**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**




**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:
If terminal ends include an object marker, there is no need to install an OM-2 in front of terminal.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**









DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: DATE TIME
FILE: DOCUMENT NAME

| LEGEND | | Texas Department of Transportation | | Traffic Operations Division Standard | |
|--------|--------------------------|---|--|--------------------------------------|--|
| | Bidirectional Delineator | <p align="center">DELINEATOR & OBJECT MARKER PLACEMENT DETAILS</p> <p align="center">D & OM(5) - 15</p> <p>FILE: dom5-15.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: TxDOT</p> <p>© TxDOT August 2015 CONT: 6373 SECT: 81 JOB: 001 HIGHWAY: 190020</p> <p>REVISIONS</p> <p>DIST: DALLAS COUNTY: KAUFMAN SHEET NO.: 11</p> | | | |
| | Delineator | | | | |
| | OM-3 | | | | |
| | OM-2 | | | | |
| | Terminal End | | | | |
| | TRAFFIC FLOW | | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



OBJECT MARKERS SMALLER THAN 3 FT²




NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

NOTES

- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- Mounting should be flush with top of attenuator. Minimum size 96" x 24".



DATE: DATE TIME
FILE: DOCUMENT NAME

| | | | |
|---|--------------|--------------------------------------|-----------------|
| | | Traffic Operations Division Standard | |
| DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS D & OM(VIA)-15 | | | |
| FILE: domvia15.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT |
| © TxDOT December 1989 | CONT: 6373 | SECT: 81 | JOB: 001 |
| 4-92 8-04 | DIST: DALLAS | COUNTY: KAUFMAN | HIGHWAY: 1H0020 |
| 8-95 3-15 | | | SHEET NO. 12 |
| 4-98 | | | |
| 206 | | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. As shown on BC(2), the OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER (see Sign Detail G20-10T) and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. However, the TRAFFIC FINES DOUBLE sign will not be required on projects consisting solely of mobile operation work, such as striping or milling edgeline rumble strips. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits.
11. Except for devices required by Note 10, traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY APPAREL NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.

DATE: DATE TIME
 FILE: DOCUMENT NAME



Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found on-line at the web address given below or by contacting:

Texas Department of Transportation
 Traffic Operations Division - TE
 Phone (512) 416-3118

| THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov |
|--|
| COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) |
| DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) |
| MATERIAL PRODUCER LIST (MPL) |
| ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" |
| STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) |
| TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) |
| TRAFFIC ENGINEERING STANDARD SHEETS |

SHEET 1 OF 12

Traffic Operations Division Standard


BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC (1) - 14

| | | | | |
|-----------------------|--------------|-----------------|--------------|-----------------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: IH0020 |
| 4-03 5-10 8-14 | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 13 | |
| 9-07 7-13 | | | | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ⚠ May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

| Sign Number or Series | SIZE | | SPACING | |
|---------------------------------------|-------------------|--------------------|------------------|--------------------------------|
| | Conventional Road | Expressway/Freeway | Posted Speed MPH | Sign Spacing "X" Feet (Apprx.) |
| CW20 ⁴ | 48" x 48" | 48" x 48" | 30 | 120 |
| CW21 | | | 35 | 160 |
| CW22 | | | 40 | 240 |
| CW23 | | | 45 | 320 |
| CW25 | | | 50 | 400 |
| CW1, CW2, CW7, CW8, CW9, CW11, CW14 | 36" x 36" | 48" x 48" | 55 | 500 ² |
| CW3, CW4, CW5, CW6, CW8-3, CW10, CW12 | 48" x 48" | 48" x 48" | 60 | 600 ² |
| | | | 65 | 700 ² |
| | | | 70 | 800 ² |
| | | | 75 | 900 ² |
| | | | 80 | 1000 ² |
| | | | * | * ³ |


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- ⊗ The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- ** Required CSJ Limit signing. See Note 10 on BC(1). TRAFFIC FINES DOUBLE signs will not be required on projects consisting solely of mobile operations work.
- ⊗ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- ⊗ Contractor will install a regulatory speed limit sign at the end of the work zone.

| LEGEND | |
|--------|---|
| — | Type 3 Barricade |
| ○ ○ ○ | Channelizing Devices |
| ⊗ | Sign |
| X | See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements. |

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-14


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 | 8-14 | DIST | COUNTY | SHEET NO. |
| 7-13 | | DALLAS | KAUFMAN | 14 |

DATE: DATE TIME
 FILE: DOCUMENT NAME

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the travelled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

| | |
|--------------------|----------------|
| 40 mph and greater | 0.2 to 2 miles |
| 35 mph and less | 0.2 to 1 mile |
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME

SHEET 3 OF 12

| | | | |
|---|-----------|--------------------------------------|-----------|
| | | Traffic Operations Division Standard | |
| <h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2> | | | |
| <h3>BC (3) - 14</h3> | | | |
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB |
| REVISIONS | 6373 | 81 | 001 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. |
| 7-13 | DALLAS | KAUFMAN | 15 |


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS




* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports




Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24" as detailed below.
- When used at night, the STOP/SLOW paddle shall be retroreflectORIZED.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC sheets or the CWZTCD. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD). The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.


SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12



BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES


BC (4) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DW: TxDOT | CR: TxDOT | GW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 | DALLAS | KAUFMAN | 16 | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SKID MOUNTED WOOD SIGN SUPPORTS
LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS □



GROUND MOUNTED SIGN SUPPORTS
Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS



| Nominal Post Size | Number of Posts | Maximum Sq. feet of Sign Face | Minimum Soil Embedment | Drilled Hole(s) Required |
|-------------------|-----------------|-------------------------------|------------------------|--------------------------|
| 4 x 4 | 1 | 12 | 36" | NO |
| 4 x 4 | 2 | 21 | 36" | NO |
| 4 x 6 | 1 | 21 | 36" | YES |
| 4 x 6 | 2 | 36 | 36" | YES |

WOOD POST SYSTEM FOR GROUND MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- See BC(4) for definition of "Work Duration."
- * Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- △ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DW: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 | DALLAS | KAUFMAN | 17 | |

DATE: DATE TIME
FILE: DOCUMENT NAME

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

| |
|-----------------------|
| FREEWAY CLOSED X MILE |
| ROAD CLOSED AT SH XXX |
| ROAD CLSD AT FM XXXX |
| RIGHT X LANES CLOSED |
| CENTER LANE CLOSED |
| NIGHT LANE CLOSURES |
| VARIOUS LANES CLOSED |
| EXIT CLOSED |
| MALL DRIVEWAY CLOSED |
| XXXXXXXX BLVD CLOSED |

Other Condition List

| |
|--------------------------|
| ROADWORK XXX FT |
| FLAGGER XXXX FT |
| RIGHT LN NARROWS XXXX FT |
| MERGING TRAFFIC XXXX FT |
| LOOSE GRAVEL XXXX FT |
| DETOUR X MILE |
| ROADWORK PAST SH XXXX |
| BUMP XXXX FT |
| TRAFFIC SIGNAL XXXX FT |

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

| |
|----------------------|
| MERGE RIGHT |
| DETOUR NEXT X EXITS |
| USE EXIT XXX |
| STAY ON US XXX SOUTH |
| TRUCKS USE US XXX N |
| WATCH FOR TRUCKS |
| EXPECT DELAYS |
| REDUCE SPEED XXX FT |
| USE OTHER ROUTES |
| STAY IN LANE |

Location List

| |
|--------------------------|
| AT FM XXXX |
| BEFORE RAILROAD CROSSING |
| NEXT X MILES |
| PAST US XXX EXIT |
| XXXXXXXX TO XXXXXXX |
| US XXX TO FM XXXX |

Warning List

| |
|-----------------------|
| SPEED LIMIT XX MPH |
| MAXIMUM SPEED XX MPH |
| MINIMUM SPEED XX MPH |
| ADVISORY SPEED XX MPH |
| RIGHT LANE EXIT |
| USE CAUTION |
| DRIVE SAFELY |
| DRIVE WITH CARE |

** Advance Notice List

| |
|-----------------------|
| TUE-FRI XX AM-X PM |
| APR XX-XX X PM-X AM |
| BEGINS MONDAY |
| BEGINS MAY XX |
| MAY X-X XX PM - XX AM |
| NEXT FRI-SUN |
| XX AM TO XX PM |
| NEXT TUE AUG XX |
| TONIGHT XX PM-XX AM |

** See Application Guidelines Note 6.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

| WORD OR PHRASE | ABBREVIATION | WORD OR PHRASE | ABBREVIATION |
|------------------------|--------------|----------------------|--------------|
| Access Road | ACCS RD | Major | MAJ |
| Alternate | ALT | Miles | MI |
| Avenue | AVE | Miles Per Hour | MPH |
| Best Route | BEST RTE | Minor | MNR |
| Boulevard | BLVD | Monday | MON |
| Bridge | BRDG | Normal | NORM |
| Canal | CANT | North | N |
| Center | CTR | Northbound (route) N | |
| Construction Ahead | CONST AHD | Parking | PKING |
| CROSSING | XING | Road | RD |
| Detour Route | DETOUR RTE | Right Lane | RT LN |
| Do Not | DONT | Saturday | SAT |
| East | E | Service Road | SERV RD |
| Eastbound (route) E | | Shoulder | SHLDR |
| Emergency | EMER | Slippery | SLIP |
| Emergency Vehicle | EMER VEH | South | S |
| Entrance, Enter | ENT | Southbound (route) S | |
| Express Lane | EXP LN | Speed | SPD |
| Expressway | EXPWY | Street | ST |
| XXXX Feet | XXXX FT | Sunday | SUN |
| Fog Ahead | FOG AHD | Telephone | PHONE |
| Freeway | FRWY, FWY | Temporary | TEMP |
| Freeway Blocked | FWY BLKD | Thursday | THURS |
| Friday | FRI | To Downtown | TO DWNTN |
| Hazardous Driving | HAZ DRIVING | Traffic | TRAF |
| Hazardous Material | HAZMAT | Travelers | TRVLR |
| High-Occupancy Vehicle | HOV | Tuesday | TUES |
| Highway | HWY | Time Minutes | TIME MIN |
| Hour(s) | HR, HRS | Upper Level | UPR LEVEL |
| Information | INFO | Vehicles (s) | VEH, VEHS |
| It Is | ITS | Warning | WARN |
| Junction | JCT | Wednesday | WED |
| Left | LFT | Weight Limit | WT LIMIT |
| Left Lane | LFT LN | West | W |
| Lane Closed | LN CLOSED | Westbound (route) W | |
| Lower Level | LWR LEVEL | Wet Pavement | WET PVMT |
| Maintenance | MAINT | Will Not | WONT |

Roadway designation = IH-number, US-number, SH-number, FM-number

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES


- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 | DALLAS | KAUFMAN | 18 | |

DATE: DATE TIME FILE: DOCUMENT NAME


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet crashworthy standards as defined in the National Cooperative Highway Research Report 350. Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{PL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential Chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

| REQUIREMENTS | | | |
|--------------|--------------|-------------------------------|-----------------------------|
| TYPE | MINIMUM SIZE | MINIMUM NUMBER OF PANEL LAMPS | MINIMUM VISIBILITY DISTANCE |
| B | 30 x 60 | 13 | 3/4 mile |
| C | 48 x 96 | 15 | 1 mile |

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the National Cooperative Highway Research Report No. 350 (NCHRP 350) or the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 | DALLAS | KAUFMAN | 19 | |

DATE: DATE TIME
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST


- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums


SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.




DIRECTION INDICATOR BARRICADE

- The Direction Indicator Barricade may be used in tapers, transitions, and other areas where specific directional guidance to drivers is necessary.
- If used, the Direction Indicator Barricade should be used in series to direct the driver through the transition and into the intended travel lane.
- The Direction Indicator Barricade shall consist of One-Direction Large Arrow (CWI-6) sign in the size shown with a black arrow on a background of Type B_{FL} or Type C_{FL} Orange retroreflective sheeting above a rail with Type A retroreflective sheeting in alternating 4" white and orange stripes sloping downward at an angle of 45 degrees in the direction road users are to pass. Sheetting types shall be as per DMS 8300.
- Double arrows on the Direction Indicator Barricade will not be allowed.
- Approved manufacturers are shown on the CWZTCD List. Ballast shall be as approved by the manufacturers instructions.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a device that is detectable by a person with a visual disability traveling with the aid of a long cane shall be placed across the full width of the closed sidewalk.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades may use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.





BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 14

| | | | | |
|-----------------------|------------|------------|------------|-----------|
| FILE: bc-14.dgn | DWG: TxDOT | CHK: TxDOT | APP: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 4-03 7-13 | DIST | COUNTY | SHEET NO. | |
| 9-07 8-14 | DALLAS | KAUFMAN | 20 | |


DATE: DATE TIME
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual Appendix B "Treatment of Pavement Drop-offs in Work Zones" for additional guidelines on the use of VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10) placed near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate NCHRP 350 crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' |
| 35 | | 205' | 225' | 245' | 35' | 70' |
| 40 | | 265' | 295' | 320' | 40' | 80' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' |
| 50 | | 500' | 550' | 600' | 50' | 100' |
| 55 | | 550' | 605' | 660' | 55' | 110' |
| 60 | | 600' | 660' | 720' | 60' | 120' |
| 65 | | 650' | 715' | 780' | 65' | 130' |
| 70 | | 700' | 770' | 840' | 70' | 140' |
| 75 | | 750' | 825' | 900' | 75' | 150' |
| 80 | | 800' | 880' | 960' | 80' | 160' |

**Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 | DALLAS | KAUFMAN | 21 | |


DATE: DATE TIME
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.



PLAN VIEW


1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW

These drums are not required on one-way roadway




PLAN VIEW

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)

| LEGEND | |
|--------|---|
| | Plastic drum |
| | Plastic drum with steady burn light or yellow warning reflector |
| | Steady burn warning light or yellow warning reflector |

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

THIS DEVICE SHALL NOT BE USED ON PROJECTS LET AFTER MARCH 2014.



EDGE LINE CHANNELIZER

1. This device is intended only for use in place of a vertical panel to channelize traffic by indicating the edge of the travel lane. It is not intended to be used in transitions or tapers.
2. This device shall not be used to separate lanes of traffic (topposing or otherwise) or warn of objects.
3. This device is based on a 42 inch, two-piece cone with an alternate striping pattern: four 4 inch retroreflective bands, with an approximate 2 inch gap between bands. The color of the band should correspond to the color of the edgeline (yellow for left edgeline, white for right edgeline) for which the device is substituted or for which it supplements. The reflectorized bands shall be retroreflective Type A conforming to Departmental Material Specification DMS-8300, unless otherwise noted.
4. The base must weigh a minimum of 30 lbs.


SHEET 10 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 14


| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DW: TxDOT | CR: TxDOT | OW: TxDOT | CK: TxDOT |
| © TxDOT November 2002 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 9-07 8-14 | DIST | COUNTY | SHEET NO. | |
| 7-13 | DALLAS | KAUFMAN | 22 | |



Two-Piece cones




One-Piece cones



Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers used at night shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

DATE: DATE TIME
FILE: DOCUMENT NAME

WORK ZONE PAVEMENT MARKINGS

GENERAL

1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
2. Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
3. Additional supplemental pavement marking details may be found in the plans or specifications.
4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
7. All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

1. Raised pavement markers are to be placed according to the patterns on BC(12).
2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
2. Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
3. Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
7. Over-painting of the markings SHALL NOT BE permitted.
8. Removal of raised pavement markers shall be as directed by the Engineer.
9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
10. Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
3. Small design variances may be noted between tab manufacturers.
4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS


1. Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
2. All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
3. Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

| DEPARTMENTAL MATERIAL SPECIFICATIONS | |
|--|----------|
| PAVEMENT MARKERS (REFLECTORIZED) | DMS-4200 |
| TRAFFIC BUTTONS | DMS-4300 |
| EPOXY AND ADHESIVES | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS | DMS-6130 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |
| TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS | DMS-8242 |

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11) - 14

| | | | | |
|-----------------------|-----------|-----------|-----------|-----------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT February 1998 | CONT | SECT | JOB | HIGHWAY |
| | 6373 | 81 | 001 | 1H0020 |
| REVISIONS | | | | |
| 2-98 9-07 | | | | |
| 1-02 7-13 | | | | |
| 11-02 8-14 | | | | |
| | DIST | COUNTY | SHEET NO. | |
| | DALLAS | KAUFMAN | 23 | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



(FOR LEFT TURN CHANNELIZING LINE OR CHANNELIZING LINE USED TO DISCOURAGE LANE CHANGING.)




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 14

| | | | | |
|-----------------------|------------|--------------|-----------------|-----------------|
| FILE: bc-14.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| © TxDOT February 1998 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 1H0020 |
| REVISIONS | | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO.: 24 |
| 1-97 9-07 | | | | |
| 2-98 7-13 | | | | |
| 11-02 8-14 | | | | |



Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Warning sign and rumble strip sequence in opposite direction is same as below



GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Removal of the Temporary Rumble Strips should be accomplished before removing the advance warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an AFAD or a portable traffic signal.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment.

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Panel | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | L = WS ² / 60 | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | 700' | 770' | 840' | 70' | 140' | 800' | 475' | |
| 75 | 750' | 825' | 900' | 75' | 150' | 900' | 540' | |

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
| | ✓ | ✓ | | |

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

| Speed | Approximate distance between strips in an Array |
|---------------------|---|
| ≤ 40 MPH | 10' |
| > 40 MPH & ≤ 55 MPH | 15' |
| > 55 MPH | 20' |

Texas Department of Transportation
 Traffic Operations Division Standard

TEMPORARY RUMBLE STRIPS


WZ (RS) - 16

| | | | | |
|-----------------------|--------------|-----------------|--------------|-----------------|
| FILE: wzrs16.dgn | DN: TxDOT | CK: TxDOT | DW: TxDOT | CK: TxDOT |
| © TxDOT November 2012 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 1H0020 |
| REVISIONS | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 25 | |

DATE: DATE TIME
 FILE: DOCUMENT NAME


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME




TCP (1-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND

| | | | |
|--|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|-------------------|-----------------------|---------------------------------------|------------|------------|---|--------------|---|--|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|-------------------------------------|-------------------------------------|------------------------------|----------------------|
| | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | | |

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.



**TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK**

TCP (1-1) - 18

| | | | | |
|-----------------------|------|---------|-----|--------------|
| FILE: tcp1-1-18.dgn | DN: | CKI: | DW: | CKI: |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 2-94 4-98 | | | | |
| 8-95 2-12 | | | | |
| 1-97 2-18 | | | | |
| DALLAS | | KAUFMAN | | SHEET NO. 26 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME



| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" | Stopping Sight Distance |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|-------------------------|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' | 200' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' | 250' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' | 305' |
| 45 | | 450' | 495' | 540' | 45' | 90' | 320' | 195' | 360' |
| 50 | L = WS | 500' | 550' | 600' | 50' | 100' | 400' | 240' | 425' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' | 495' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' | 570' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' | 645' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' | 730' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' | 820' |

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | | |

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.


TCP (1-2b)

- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.


| | | | |
|--|-----------------|--------------------------------------|-----------|
| | | Traffic Operations Division Standard | |
| TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL | | | |
| TCP (1-2) - 18 | | | |
| FILE: tcp1-2-18.dgn | DN: | CKI: | DW: |
| © TxDOT December 1985 | CONT: 6373 | SECT: 81 | JOB: 001 |
| REVISIONS: | 4-90 4-98 | 2-94 2-12 | 1-97 2-18 |
| DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 27 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME



TCP (1-4a)
ONE LANE CLOSED



TCP (1-4b)
TWO LANES CLOSED

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | $L = WS$ | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | | |

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

TCP (1-4b)

- Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

Texas Department of Transportation
Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
LANE CLOSURES ON MULTILANE
CONVENTIONAL ROADS**


TCP (1-4) - 18

| | | | | |
|-----------------------|--------|---------|-----------|---------|
| FILE: tcp1-4-18.dgn | DN: | CK: | DW: | CK: |
| © TxDOT December 1985 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 2-94 4-98 | DIST | COUNTY | SHEET NO. | |
| 8-95 2-12 | DALLAS | KAUFMAN | 28 | |
| 1-97 2-18 | | | | |


153

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: DATE TIME
FILE: DOCUMENT NAME



TCP (1-5a)
ONE LANE CLOSURE



TCP (1-5b)
LANE CLOSURE NEAR EXIT RAMP



TCP (1-5c)
LANE CLOSURE NEAR ENTRANCE RAMP

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed * | Formula | Minimum Desirable Taper Lengths ** | | | Suggested Maximum Spacing of Channelizing Devices | | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|-----------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | | |
| 30 | $L = \frac{WS^2}{60}$ | 150' | 165' | 180' | 30' | 60' | 120' | 90' |
| 35 | | 205' | 225' | 245' | 35' | 70' | 160' | 120' |
| 40 | | 265' | 295' | 320' | 40' | 80' | 240' | 155' |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 320' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 400' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 500' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 600' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 700' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 800' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 900' | 540' |

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | | ✓ | | |

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
LANE CLOSURES FOR
DIVIDED HIGHWAYS**

TCP (1-5) - 18

| | | | | |
|-----------------------|------------|---------|------|------------|
| FILE: tcp1-5-18.dgn | DN: | CKI: | DW: | CKI: |
| © TxDOT February 2012 | CONT: | SECT: | JOB: | HIGHWAY: |
| 2-18 | REVISIONS: | 6373 | 81 | 001 |
| | DIST: | COUNTY: | | SHEET NO.: |
| | DALLAS | KAUFMAN | | 29 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME




TCP (6-4a)
EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP

| | |
|----------------------------|-------------------------|
| STREET A EXIT CLOSED | USE STREET B EXIT |
| EXIT XX CLOSED | USE EXIT XY |

Or, as an option when exits are numbered

Place 1 mile (approx.) in advance of closed ramp.



TCP (6-4b)
EXIT RAMP OPEN

| LEGEND | | | |
|--------|--------------------------------------|--|---|
| | Type 3 Barricade | | Channelizing Devices (CDs) |
| | Heavy Work Vehicle | | Truck Mounted Attenuator (TMA) |
| | Trailer Mounted Flashing Arrow Board | | Portable Changeable Message Sign (PCMS) |
| | Sign | | Traffic Flow |
| | Flag | | Flagger |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" * * | | | Suggested Maximum Spacing of Channelizing Devices | | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|---|------------|------------|---|--------------|---|
| | | 10' Offset | 11' Offset | 12' Offset | On a Taper | On a Tangent | |
| 45 | L = WS | 450' | 495' | 540' | 45' | 90' | 195' |
| 50 | | 500' | 550' | 600' | 50' | 100' | 240' |
| 55 | | 550' | 605' | 660' | 55' | 110' | 295' |
| 60 | | 600' | 660' | 720' | 60' | 120' | 350' |
| 65 | | 650' | 715' | 780' | 65' | 130' | 410' |
| 70 | | 700' | 770' | 840' | 70' | 140' | 475' |
| 75 | | 750' | 825' | 900' | 75' | 150' | 540' |
| 80 | | 800' | 880' | 960' | 80' | 160' | 615' |

* * * Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

| TYPICAL USAGE | | | | |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| | ✓ | ✓ | ✓ | |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP (6-4) - 12

| | | | | |
|----------------------|-----------|-----------|-----------|-----------|
| FILE: tcp6-4.dgn | DN: TxDOT | CR: TxDOT | OW: TxDOT | CR: TxDOT |
| ©TxDOT February 1994 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| 1-97 8-98 | DIST | COUNTY | SHEET NO. | |
| 4-98 8-12 | DALLAS | KAUFMAN | 30 | |


DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:




TYPICAL POST PLACEMENT

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25' - 0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




ELEVATION 25' - 0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.




BUTTON HEAD BOLT

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.




WOOD BLOCK TO RECTANGULAR WOOD POST **ROUTED WOOD BLOCK TO I-BEAM STEEL POST**

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.

NOTE: (SEE GENERAL NOTE 14 FOR RAIL HEIGHT MEASUREMENT)

- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25' - 0", OR 12' - 6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

12" x 12" x 1/4" (ASTM A36) STEEL BOTTOM PLATE WITH 1" DIA. HOLES REQUIRED WITH BOLT-THROUGH INSTALLATION.

NOTE: TWO INSTALLATION OPTIONS.


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 5/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 5/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

| | | | | | |
|---|-----------|---------|--------|--------------------------|--|
| | | | | Design Division Standard | |
| METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19 | | | | | |
| FILE: gf3119.dgn | DN: TxDOT | CK: KM | DW: VP | CK: CGL/AG | |
| © TXDOT: NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 | |
| | DIST | COUNTY | | SHEET NO. | |
| | DALLAS | KAUFMAN | | 31 | |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:










DOWNSTREAM ANCHOR TERMINAL (DAT)
 NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.

- GENERAL NOTES**
1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
 2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
 3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
 4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
 5. REFER TO GF (31) SHEET FOR TERMINAL CONNECTION DETAILS.

MOW STRIP INSTALLATION
 IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.

| # | (DAT) PARTS LIST | QTY |
|----|------------------------------|-----|
| 1 | STEEL FOUNDATION TUBE | 2 |
| 2 | DAT TERMINAL POST | 2 |
| 3 | CHANNEL STRUT | 2 |
| 4 | TERMINAL RAIL ELEMENT | 1 |
| 5 | SHELF ANGLE BRACKET | 1 |
| 6 | BCT BEARING PLATE | 1 |
| 7 | BCT POST SLEEVE | 1 |
| 8 | GUARDRAIL ANCHOR BRACKET | 1 |
| 9 | (ROUNDED) W-BEAM END SECTION | 1 |
| 10 | BCT CABLE ANCHOR | 1 |
| 11 | RECESSED NUT, GUARDRAIL | 20 |
| 12 | 1 1/4" BUTTON HEAD BOLT | 4 |
| 13 | 10" BUTTON HEAD BOLT | 2 |
| 14 | 5/8" X 2" HEX HEAD BOLT | 8 |
| 15 | 5/8" X 8" HEX HEAD BOLT | 4 |
| 16 | 5/8" X 10" HEX HEAD BOLT | 2 |
| 17 | 5/8" FLAT WASHER | 18 |



Design Division Standard


METAL BEAM GUARD FENCE (DOWNSTREAM ANCHOR TERMINAL) TL-3 MASH COMPLIANT GF (31) DAT-19

| | | | | |
|----------------------------------|--------------|-----------------|--------------|-----------------|
| FILE: gf31dat19.dgn | DN: TXDOT | CK: KM | DW: VP | CK: CGL/AG |
| © TXDOT: NOVEMBER 2019 REVISIONS | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 190020 |
| | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 32 | |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE:
FILE:

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.



**RECTANGULAR CRT POST
(6" X 8" X 6' LONG)**

(6) CRT REQUIRED
SEE ELEVATION DETAIL FOR LOCATIONS




**LATERAL OFFSET BETWEEN THE
GUARDRAIL AND THE CULVERT HEADWALL**

GENERAL NOTES

1. THE TYPE OF LINE POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF THE TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENT SHALL MEET ALL REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 12'-6" OR 25'-0" NOMINAL LENGTHS.
3. RAIL POST HOLES ARE OFFSET 3'-1 1/2" FROM STANDARD GUARDRAIL TO ACCOMMODATE THE MIDSPAN SPLICING.
4. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC160) AND NO MORE THAN 1" BEYOND IT.
5. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
6. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
7. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
8. REFER TO GF (31) STANDARD SHEET FOR ADDITIONAL DETAILS.
9. FLAME CUTTING OF HOLES IN GUARDRAIL SHALL NOT BE PERMITTED. IF YOU ENCOUNTER MIS-ALIGNED BOLT HOLES IN GUARDRAIL CONTACT THE DESIGN DIVISION FOR ADDITIONAL INFORMATION & OPTIONS.

NOTE: SEE GF (31) STANDARD FOR STANDARD LINE POSTS.


DIRECTION OF TRAFFIC







**ELEVATION DETAIL
LONG SPAN GUARDRAIL**

| | | | |
|---|-----------|--------------------------|-----------|
| | | Design Division Standard | |
| METAL BEAM GUARD FENCE LONG SPAN TL-3 MASH COMPLIANT | | | |
| GF (31) LS-19 | | | |
| FILE: gf31ls19.dgn | DN: TxDOT | CK: KM | DW: VP |
| © TxDOT: NOVEMBER 2019 | CONTRACT | SECTION | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 |
| | DIST | COUNTY | SHEET NO. |
| | DALLAS | KAUFMAN | 33 |


DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- ### GENERAL NOTES
- CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
 - CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5'-3/4") HEIGHT; SEE CURRENT CCG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE:17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
 - CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
 - UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
 - FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
 - THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF(31) STANDARD SHEET.
 - THE POST LENGTH SHALL BE MARKED ON ALL 7'-0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 3/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
 - POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 - RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
 - BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 - FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
 - WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
 - UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TXDOT'S CONSTRUCTION DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
 - REFER TO GF(31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
 - THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
 - IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION, (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED) (TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED) (STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT.2 FOR ADDITIONAL INFORMATION.



BRIDGE APPROACH - UPSTREAM: THE NESTED RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.
BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.



| THRIE-BEAM TERMINAL - CURB TABLE | |
|--|--------------|
| PRECAST CURB FULL LENGTH EQUALS 12'-2" | |
| THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS. | |
| CURB (1) | LENGTH 5'-8" |
| CURB (2) | LENGTH 6'-6" |
| TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7 | |
| CONNECTING PRECAST CURB SECTIONS (1) & (2): | |
| FORM OR CORE (1" DIA. HOLE 9" LONG) INTO EACH CURB END. | |
| USE (1) #5 GR.60 REBAR 18" LONG TO CONNECT BOTH CURBS. | |
| SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE: | |
| FORM OR CORE FOUR (1" DIA. HOLES), SEE BOTH VIEWS FOR HOLE LOCATIONS. DRIVE (4) #5 GR.60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB. | |
| FILL HOLES WITH APPROVED GROUT MIXTURE. | |



* NOTES: NOT NEEDED FOR CAST-IN-PLACE. SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS. PERCUSSION DRILLING IS NOT PERMITTED WITH TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.

HIGH-SPEED TRANSITION

SHEET 1 OF 2

METAL BEAM GUARD FENCE

THRIE-BEAM TRANSITION

TL-3 MASH COMPLIANT

GF(31)TR TL3-19

| | | | | |
|-----------------------|----------|-------|-----------|-----------|
| FILE: gf31tr+1319.dgn | DN:TxDOT | CK:KM | DW:VP | CK:CGL/AG |
| ©TXDOT: NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| DIST | COUNTY | | SHEET NO. | |
| DALLAS | KAUFMAN | | 34 | |



DATE: FILE:

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.

DISCLAIMER: THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE:
FILE:

REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)



HIGH-SPEED TRANSITION

SHEET 2 OF 2




METAL BEAM GUARD FENCE
THRIE-BEAM TRANSITION
TL-3 MASH COMPLIANT
GF (31) TR TL3-19

| | | | | |
|------------------------|-----------|---------|-----------|------------|
| FILE: gf31trtl319.dgn | DN: TxDOT | CK: KM | DW: KM | CK: CGL/AG |
| © TXDOT: NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| | DIST | COUNTY | SHEET NO. | |
| | DALLAS | KAUFMAN | 35 | |

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:







- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (ASTM A325 OR A449)
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 1/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563)

THRIE-BEAM CONNECTOR TO CONCRETE RAIL

NOTE: HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE: CHAMFER REQUIRED ON CONCRETE RAILS THAT EXTEND BEYOND THE FACE OF GUARDRAIL TRANSITION.




- (2) 5/8" BUTTON HEAD POST BOLTS & NUTS: (FBB04)
- (1) 5/8" FLAT WASHER: (FWC14a) UNDER EACH NUT


- (1) 5/8" BUTTON HEAD POST BOLT & NUT: (FBB04)
- (1) 5/8" FLAT WASHER: (FWC14a) UNDER EACH NUT

PLATE WASHER INSTRUCTIONS


BRIDGE APPROACH - UPSTREAM: THE SHORT RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.
BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.



SECTION A-A




SECTION B-B




WOOD BLOCK TO ROUND WOOD POST

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.



WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST

GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. REFER TO GF(31) STANDARD SHEET.
2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS.
3. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
4. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM BOLT LENGTH TO MEET REQUIRED LENGTH.
5. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
6. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
7. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
8. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT, MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
9. REFER TO GF(31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
10. FOR ROUND WOOD POSTS SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE TRANSITION.




LOW-SPEED TRANSITION

| | | | |
|--|-----------------|--------------------------|--------|
| | | Design Division Standard | |
| METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-2 MASH COMPLIANT GF(31) TR TL2-19 | | | |
| FILE: gf31tr+1219.dgn | DN: TxDOT | CK: KM | DW: VP |
| © TxDOT: NOVEMBER 2019 | CONT: SECT | JOB: HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 |
| DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 36 | |

NOTE: * "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME



GENERAL NOTES




1. For more detail: See GF(31), SGT()31, GF(31)TR, and GF(31)TL2 standard sheets.
2. Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
3. Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
4. MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
5. Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
6. Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal, See Detail A)
7. The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
8. For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge locations shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
9. Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
10. A minimum 25' length of MBGF will be required.



Note:
All rail elements shall be lapped in the direction of adjacent traffic.

| | | | |
|--|--------------|--------------------------|---------------|
| | | Design Division Standard | |
| BRIDGE END DETAILS (METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS) | | | |
| BED-14 | | | |
| FILE: bed14.dgn | DN: TxDOT | CR: AM | OW: BD/VP |
| © TxDOT: December 2011 | CONT: SECT | JOB: HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 |
| REVISED APRIL 2014 SEE I-MEMO 04141 | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO.: 37 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE SoftStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MOW STRIP STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IT IS ACCEPTABLE TO INSTALL THE SoftStop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
 - DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoaching ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTE A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE B PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

NOTE C W-BEAM SPLICE LOCATED BETWEEN LINE POST(4) AND LINE POST(5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

| PART | QTY | MAIN SYSTEM COMPONENTS |
|----------|-----|--|
| 620237B | 1 | PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.) |
| 15208A | 1 | SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH) |
| 15215G | 1 | SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS |
| 61G | 1 | SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25' - 0") |
| 15205A | 1 | POST #0 - ANCHOR POST (6' - 5 1/2") |
| 15203G | 1 | POST #1 - (SYTP) (4' - 9 1/2") |
| 15000G | 1 | POST #2 - (SYTP) (6' - 0") |
| 533G | 6 | POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6' - 0") |
| 4076B | 7 | BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14") |
| 6777B | 7 | BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14") |
| 15204A | 1 | ANCHOR PADDLE |
| 15207G | 1 | ANCHOR KEEPER PLATE (24 GA) |
| 15206G | 1 | ANCHOR PLATE WASHER (1/2" THICK) |
| 15201G | 2 | ANCHOR POST ANGLE (10" LONG) |
| 15202G | 1 | ANGLE STRUT |
| HARDWARE | | |
| 4902G | 1 | 1" ROUND WASHER F436 |
| 3908G | 1 | 1" HEAVY HEX NUT A563 GR.DH |
| 3717G | 2 | 3/4" X 2 1/2" HEX BOLT A325 |
| 3701G | 4 | 3/4" ROUND WASHER F436 |
| 3704G | 2 | 3/4" HEAVY HEX NUT A563 GR.DH |
| 3360G | 16 | 5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR |
| 3340G | 25 | 5/8" W-BEAM RAIL SPLICE NUTS HGR |
| 3500G | 7 | 3/8" X 10" HGR POST BOLT A307 |
| 3391G | 1 | 5/8" X 1 3/4" HEX HD BOLT A325 |
| 4489G | 1 | 3/8" X 9" HEX HD BOLT A325 |
| 4372G | 4 | 3/8" WASHER F436 |
| 105285G | 2 | 3/8" X 2 1/2" HEX HD BOLT GR-5 |
| 105286G | 1 | 3/8" X 1 1/2" HEX HD BOLT GR-5 |
| 3240G | 6 | 3/8" ROUND WASHER (WIDE) |
| 3245G | 3 | 3/8" HEX NUT A563 GR.DH |
| 5852B | 1 | HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE B |

Texas Department of Transportation
Design Division Standard








TRINITY HIGHWAY SOFTSTOP END TERMINAL MASH - TL-3 SGT (10S) 31-16

| | | | | |
|-------------------|-----------------|--------------|--------|-----------|
| FILE: sgt10s3116 | DW: TxDOT | CR: KM | DR: VP | CR: MB/VP |
| ©TxDOT: JULY 2016 | CONT: SECT | JOB: HIGHWAY | | |
| REVISIONS | | | | |
| 6373 | 81 | 001 | 1H0020 | |
| DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 38 | | |

DATE: DATE TIME
FILE: DOCUMENT NAME

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
- FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
- SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
- COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
- IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
- MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
- IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
- THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
- A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

| ITEM# | PART NUMBER | DESCRIPTION | QTY |
|-------|-----------------|---|-----|
| 1 | BSI-1610060-00 | SOIL ANCHOR - GALVANIZED | 1 |
| 2 | BSI-1610061-00 | GROUND STRUT - GALVANIZED | 1 |
| 3 | BSI-1610062-00 | MAX-TENSION IMPACT HEAD | 1 |
| 4 | BSI-1610063-00 | W6x9 I-BEAM POST 6FT. - GALVANIZED | 1 |
| 5 | BSI-1610064-00 | TSS PANEL - TRAFFIC SIDE SLIDER | 1 |
| 6 | BSI-1610065-00 | ISS PANEL - INNER SIDE SLIDER | 1 |
| 7 | BSI-1610066-00 | TOOTH - GEOMET | 1 |
| 8 | BSI-1610067-00 | RSS PLATE - REAR SIDE SLIDER | 1 |
| 9 | B061058 | CABLE FRICTION PLATE - HEAD UNIT | 1 |
| 10 | BSI-1610069-00 | CABLE ASSEMBLY - MASH X-TENSION | 2 |
| 11 | BSI-1012078-00 | X-LITE LINE POST - GALVANIZED | 8 |
| 12 | B090534 | 8" W-BEAM COMPOSITE-BLOCKOUT XT110 | 8 |
| 13 | BSI-4004386 | 12'-6" W-BEAM GUARD FENCE PANELS 12GA. | 4 |
| 14 | BSI-1102027-00 | X-LITE SQUARE WASHER | 1 |
| 15 | BSI-2001886 | $\frac{3}{8}$ " X 7" THREAD BOLT HH (GR.5) GEOMET | 1 |
| 16 | BSI-2001885 | $\frac{3}{4}$ " X 3" ALL-THREAD BOLT HH (GR.5) GEOMET | 4 |
| 17 | 4001115 | $\frac{3}{8}$ " X 1 $\frac{1}{4}$ " GUARD FENCE BOLTS (GR.2) MGAL | 48 |
| 18 | 2001840 | $\frac{3}{8}$ " X 10" GUARD FENCE BOLTS MGAL | 8 |
| 19 | 2001636 | $\frac{3}{8}$ " WASHER F436 STRUCTURAL MGAL | 2 |
| 20 | 4001116 | $\frac{3}{8}$ " RECESSED GUARD FENCE NUT (GR.2) MGAL | 59 |
| 21 | BSI-2001888 | $\frac{3}{8}$ " X 2" ALL THREAD BOLT (GR.5) GEOMET | 1 |
| 22 | BSI-1701063-00 | DELINEATION MOUNTING (BRACKET) | 1 |
| 23 | BSI-2001887 | $\frac{1}{4}$ " X $\frac{3}{4}$ " SCREW SD HH 410SS | 7 |
| 24 | 4002051 | GUARDRAIL WASHER RECT AASHTO FWRO3 | 1 |
| 25 | SEE NOTE BELOW | HIGH INTENSITY REFLECTIVE SHEETING | 1 |
| 26 | 4002337 | 8" W-BEAM TIMBER-BLOCKOUT, PDB01B | 8 |
| 27 | BSI-4004431 | 25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA. | 2 |
| 28 | MANMAX Rev- (D) | MAX-TENSION INSTALLATION INSTRUCTIONS | 1 |

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.

** ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS

Texas Department of Transportation

Design Division Standard

MAX-TENSION END TERMINAL

MASH - TL-3

SGT (11S) 31-18


FILE: sgt11s3118.dgn DN: TxDOT CK: KM DW: TxDOT CK: CL

© TxDOT: FEBRUARY 2018 CONT SECT JOB HIGHWAY

REVISIONS

| | | | |
|--------|---------|-----------|--------|
| 6373 | 81 | 001 | 100020 |
| DIST | COUNTY | SHEET NO. | |
| DALLAS | KAUFMAN | 39 | |


DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- * NOTES:**
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN THEIR PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

| ITEM | QTY | MAIN SYSTEM COMPONENTS | ITEM NUMBERS |
|----------------|-----|---|--------------|
| A | 1 | MSKT IMPACT HEAD | MS3000 |
| B | 1 | W-BEAM GUARDRAIL END SECTION, 12 Go. | SF1303 |
| C | 1 | POST 1 - TOP (6" X 6" X 1/8" TUBE) | MTPHP1A |
| D | 1 | POST 1 - BOTTOM (6" W6X15) | MTPHP1B |
| E | 1 | POST 2 - ASSEMBLY TOP | UHP2A |
| F | 1 | POST 2 - ASSEMBLY BOTTOM (6" W6X9) | HP2B |
| G | 1 | BEARING PLATE | E750 |
| H | 1 | CABLE ANCHOR BOX | S760 |
| J | 1 | BCT CABLE ANCHOR ASSEMBLY | E770 |
| K | 1 | GROUND STRUT | MS785 |
| L | 6 | W6X9 OR W6X8.5 STEEL POST | P621 |
| M | 6 | COMPOSITE BLOCKOUTS | CBSP-14 |
| N | 1 | W-BEAM MGS RAIL SECTION (9'-4 1/2") | G12025 |
| O | 2 | W-BEAM MGS RAIL SECTION (12'-6") | G1203A |
| P | 6 | WOOD BLOCKOUT 6" X 8" X 14" | P675 |
| Q | 1 | W-BEAM MGS RAIL SECTION (25'-0") | G1209 |
| SMALL HARDWARE | | | |
| a | 2 | 3/8" x 1" HEX BOLT (GRD 5) | B5160104A |
| b | 4 | 3/8" WASHER | W0516 |
| c | 2 | 3/8" HEX NUT | N0516 |
| d | 25 | 3/8" Dia. x 1 1/4" SPLICE BOLT (POST 2) | B580122 |
| e | 2 | 3/8" Dia. x 9" HEX BOLT (GRD A449) | B580904A |
| f | 3 | 3/8" WASHER | W050 |
| g | 33 | 3/8" Dia. H.G.R NUT | N050 |
| h | 1 | 3/4" Dia. x 8 1/2" HEX BOLT (GRD A449) | B340854A |
| j | 1 | 3/4" Dia. HEX NUT | N030 |
| k | 2 | 1 ANCHOR CABLE HEX NUT | N100 |
| l | 2 | 1 ANCHOR CABLE WASHER | W100 |
| m | 8 | 1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER | SB12A |
| n | 8 | 1/2" STRUCTURAL NUTS | N012A |
| o | 8 | 1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS | W012A |
| p | 1 | BEARING PLATE RETAINER TIE | CT-100ST |
| q | 6 | 3/8" x 10" H.G.R. BOLT | B581002 |
| r | 1 | OBJECT MARKER 18" X 18" | E3151 |



ALTERNATIVE ITEMS NOT SHOWN. *
 * ITEM (P) 8" WOOD-BLOCKOUT
 ** ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

SINGLE GUARDRAIL TERMINAL
MSKT-MASH-TL-3
SGT (12S) 31-18

| | | | | |
|----------------------|-----------|-----------|----------|--------|
| FILE: sgt12s3118.dgn | DN: TxDOT | CK: KM | DW: VP | CK: CL |
| © TxDOT: APRIL 2018 | CONT SECT | JOB | HIGHWAY | |
| REVISIONS | | | | |
| 6373 | 81 | 001 | 11/02/20 | |
| DIST | COUNTY | SHEET NO. | | |
| DALLAS | KAUFMAN | | | 40 |






DATE: FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

| ITEM | QTY | MAIN SYSTEM COMPONENTS | ITEM # |
|----------------|-----|--|----------|
| A | 1 | SGET IMPACT HEAD | SIH1A |
| B | 1 | MODIFIED GUARDRAIL PANEL 12'-6" 12GA | 126SPZGP |
| B2 | 1 | MODIFIED GUARDRAIL PANEL 9'-4 1/2" 12GA | GP94 |
| C | 2 | STANDARD GUARDRAIL PANEL 12'-6" 12GA | GP126 |
| D | 1 | STANDARD GUARDRAIL PANEL 25'-0" 12GA | GP25 |
| E | 7 | MODIFIED YIELDING I-BEAM POST W6x8.5 | YP6MOD |
| F | 6 | COMPOSITE BLOCKOUT 6" X 8" X 14" | CB08 |
| G | 6 | WOOD BLOCKOUT 6" X 8" X 14" | WB08 |
| H | 1 | STRUT 3" X 3" X 80" X 1/4" A36 ANGLE | STR80 |
| I | 1 | FOUNDATION TUBE 6" X 8" X 72" X 3/8" | FNDT6 |
| J | 1 | WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50" | WBRK50 |
| K | 1 | WOOD STRIKE BLOCK | WSBLK14 |
| L | 1 | STRIKE PLATE 1/4" A36 BENT PLATE | SPLT8 |
| M | 1 | REINFORCEMENT PLATE 12 GA. GR55 | REPLT17 |
| N | 1 | GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2" | GGR17 |
| O | 1 | BEARING PLATE 8" X 8 3/8" X 3/8" A36 | BPLT8 |
| P | 1 | PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.) | PSLV4 |
| Q | 1 | BCT CABLE 3/4" X 81" LENGTH | CBL81 |
| SMALL HARDWARE | | | |
| o | 1 | 3/8" X 12" GUARDRAIL BOLT 307A HDG | 12GRBLT |
| b | 7 | 3/8" X 10" GUARDRAIL BOLT 307A HDG | 10GRBLT |
| c | 33 | 3/8" X 1 1/4" GR SPLICE BOLTS 307A HDG | 1GRBLT |
| d | 3 | 3/8" FLAT WASHER F436 A325 HDG | 58FW436 |
| e | 1 | 3/8" LOCK WASHER HDG | 58LW |
| f | 39 | 3/8" GUARDRAIL HEX NUT HDG | 58HN563 |
| g | 2 | 1/2" X 2" STRUT BOLT A325 HDG | 2BLT |
| h | 6 | 1/2" X 1 1/4" PLATE BOLT A325 HDG | 125BLT |
| i | 16 | 1/2" FLAT WASHER F436 A325 HDG | 12FWF436 |
| j | 8 | 1/2" LOCK WASHER HDG | 12LW |
| k | 8 | 1/2" HEX NUT A563 HDG | 12HN563 |
| l | 4 | 3/8" X 3" HEX LAG SCREW GR5 HDG | 38LS |
| m | 4 | 3/8" FLAT WASHER F436 A325 HDG | 38FW844 |
| n | 2 | 1" FLAT WASHER F436 A325 HDG | 1FWF436 |
| o | 2 | 1" HEX NUT A563HD HDG | 1HN563 |
| p | 1 | 18" TO 24" LONG ZIP TIE RATED 175-200LB | ZPT18 |
| q | 1 | 1 1/2" X 4" SCH-40 PVC PIPE | PSPCR4 |
| r | 1 | RFID CHIP RATED MIL-STD-810F | RFID810F |
| s | 1 | IMPACT HEAD REFLECTIVE SHEETING | RS30M |



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15) 31-20

| | | | | |
|---------------------|------------|---------|-----------|--------|
| FILE: sgt153120.dgn | DN: TxDOT | CK: KM | DW: VP | CK: VP |
| © TxDOT: APRIL 2020 | CONT: SECT | JOB: | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| | DIST: | COUNTY: | SHEET NO. | |
| | DALLAS | KAUFMAN | 41 | |


Design Division Standard

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL PLAN VIEW

MODEL B (Self Contained Steel Backup)




TYPICAL ELEVATION VIEW

MODEL B (Self Contained Steel Backup)




TYPICAL PLAN VIEW

MODEL C (Concrete Backup with Side Mount Anchors)



TYPICAL ELEVATION VIEW

MODEL C (Concrete Backup with Side Mount Anchors)





GENERAL NOTES

1. For specific information regarding installation and technical guidance of the system, contact: Trinity Highway - Energy Absorption at 1(888)323-6374, 70 W. Madison St. Suite 2350, Chicago, IL 60602
2. The nose of the REACT 350 shall be clad with a plastic wrap with standard delineation adhered to the wrap and shall have a series of side marker reflectors on both sides of the unit. See site plan views for marker and plastic wrap color orientation.
3. All steel components to be hot dipped galvanized except stakes, drive spikes, threaded bolts in backup unit, and wedge fittings on cables.
4. The installation area should be free from curbs, elevated objects, or depressions. If the REACT system is to span expansion joints contact the manufacturer.
5. The REACT system should be approximately parallel with the barrier or centerline of merging barriers. The maximum permissible cross-slope is 8%.
6. REACT 350 II has laminated panels in cylinders 1, 5, & 6.


| TYPE | REACT 350 4-B | REACT 350 4-C | REACT 350 II 6-B | REACT 350 II 6-C |
|----------------|---------------|---------------|------------------|------------------|
| Test Level | TL-2 | TL-2 | TL-3 | TL-3 |
| OVERALL LENGTH | 15'-3" | 13'-9" | 21'-3" | 19'-5" |

| FOUNDATION TYPE | MINIMUM THICKNESS | ANCHORAGE |
|----------------------------------|----------------------|--|
| A CONCRETE PAD OR ROADWAY | 6" | MP-3 WITH 7" STUDS [5.5" EMBEDMENT] |
| B ASPHALT OVER CONCRETE PAVEMENT | 6" CONCRETE PAVEMENT | ANCHOR LENGTH REQUIRED IS 7" STUD PLUS ASPHALT THICKNESS |
| C ASPHALT OVER BASE | 6" ACP + 6" BASE | MP-3 WITH 18" STUDS [16.5" EMBEDMENT] |
| D ASPHALT ONLY | 8" | MP-3 WITH 18" STUDS [16.5" EMBEDMENT] |



ASPHALT PAVEMENT DETAIL

CONCRETE PAVEMENT DETAIL



TYPICAL CYLINDER





LOW MAINTENANCE

| | | | |
|--|-----------|--------------------------|-----------|
| | | Design Division Standard | |
| TRINITY HIGHWAY ENERGY ABSORPTION (REACT 350 NARROW) (REACT 350 II NARROW) REACT (N) - 16 | | | |
| FILE: reactn16.dgn | DN: TxDOT | CR: KM | DN: VP |
| © TxDOT February 1998 | CONT | SECT | JOB |
| REVISIONS | 6373 | 81 | 001 |
| REVISOR | DIST | COUNTY | SHEET NO. |
| REVISED 06, 2013 (VP) | DALLAS | KAUFMAN | 42 |
| REVISED 03, 2016 (VP) | | | |

DATE: DATE TIME
 FILE: DOCUMENT NAME

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
FILE: DOCUMENT NAME



MONORAIL ASSEMBLY DETAIL
(See the manufacturer's shop drawings for monorail hardware installation.)

GENERAL NOTES

1. For specific information regarding installation and technical guidance of the system, contact: Trinity Highway - Energy Absorption at 1(888)323-6374. 70 W. Madison St. Suite 2350. Chicago, IL 60602
2. The nose of the REACT 350 shall be clad with a plastic wrap with standard delineation adhered to the wrap and shall have a series of side marker reflectors on both sides of the unit. See site plan views for marker and plastic wrap color orientation.
3. For bi-directional traffic, appropriate transition details will be as shown on the manufacturer's shop drawings.
4. Details of components for the REACT(W) and backups and reinforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
5. If the cross-slope varies more than 2% over the length of the system, the concrete pad will require leveling. Maximum permissible cross-slope is 8%.
6. The installation area should be free from curbs, elevated objects, or depressions.
7. The REACT(W) system should be approximately parallel with the barrier or $\frac{1}{2}$ of merging barriers.
8. All steel components to be hot dipped galvanized except stakes, drive spikes, threaded bolts in backup unit, and wedge fittings on cables.

WIDE REACT SYSTEMS

| SYSTEM TYPE | BACKUP WIDTH | TEST LEVEL | SYSTEM LENGTH | EFFECTIVE LENGTH | PAD LENGTH |
|-------------|--------------|------------|---------------|------------------|------------|
| W60 | 60" | TL-2 | 18'-10" | 16'-3" | 19'-6" |
| | | TL-3 | 30'-10" | 29'-3" | 32'-6" |
| W96 | 96" | TL-2 | 18'-10" | 17'-6" | 19'-7" |
| | | TL-3 | 34'-9" | 32'-10" | 35'-6" |
| W120 | 120" | TL-3 | 33'-10" | 32'-2" | 35'-6" |

(See the manufacturer's shop drawings for additional details.)

ANCHOR SYSTEM TYPE

MP-3[®] polyester anchoring system with 7.5" studs, 5.5" embedment

FOUNDATION TYPES

Minimum 8" Reinforced concrete pad (Required reinforcing steel for concrete pad shall be shown on the manufacturer's shop drawings.)

Minimum 8" Non-reinforced concrete roadway (Measuring at least 12' wide by 50' long)

Minimum 7" Concrete deck structure, or Minimum 6" Reinforced concrete roadway

Texas Department of Transportation
Design Division Standard


**TRINITY HIGHWAY
ENERGY ABSORPTION
CRASH CUSHION
(REACT 350 WIDE)
REACT (W) - 16**

| | | | | |
|-----------------------|-----------|---------|-----------|---------|
| FILE: reactw16.dgn | DN: TxDOT | CK: KM | DN: VP | CK: VP |
| ©TxDOT: October 2001 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| REVISED 03, 2016 (VP) | DIST | COUNTY | SHEET NO. | |
| | DALLAS | KAUFMAN | 43 | |


LOW MAINTENANCE

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



PLAN VIEW



ELEVATION VIEW

6" REINFORCED PAD SHOWN
(SEE FOUNDATION OPTIONS)

GENERAL NOTES

1. FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: WORK AREA PROTECTION, CORP. AT (800) 327-4417, OR (630) 377-9100.
2. FOR BI-DIRECTIONAL TRAFFIC, APPROPRIATE TRANSITION PANELS WILL BE REQUIRED.
3. ADDITIONAL DETAILS FOR THE TRANSITION OPTION AND FOUNDATION OPTION WILL BE SHOWN ON THE MANUFACTURER'S SHOP DRAWINGS FURNISHED TO THE ENGINEER.
4. CONCRETE SHALL BE CLASS "S" WITH A MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI.
5. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
6. THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
7. THE SCI100GM & SCI70GM SYSTEMS SHOULD BE APPROXIMATELY PARALLEL WITH THE BARRIER OR CENTERLINE OF MERGING BARRIERS.

NOTE:
FOR ATTACHMENT AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BI-DIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

NOTE:
SIDE PANELS CAN TRAVEL 30" BEYOND THE LAST TERMINAL BRACE AT THE REAR OF THE CUSHION. ALL OBJECTS THAT MAY INTERFERE WITH THIS MOTION CAN AFFECT PERFORMANCE OF AND MAY CAUSE UNDUE DAMAGE TO THE CRASH CUSHION.

| MODEL | TEST LEVEL | UNIT LENGTH (approx.) | UNIT WIDTH | FOUNDATION LENGTH | OBSTACLE WIDTH |
|----------|------------|-----------------------|------------|-------------------|----------------|
| SCI70GM | TL-2 | 13'-6" | 2'-10 5/8" | 15'-6 1/4" | 24" to 36" |
| SCI100GM | TL-3 | 21'-6" | 3'-1 1/2" | 23'-0" | 24" to 36" |

SYSTEM AND PAD LENGTHS VARY DEPENDING ON BACKUP TYPE.

FOUNDATION OPTIONS

| |
|---|
| 6" REINFORCED CONCRETE (5 1/2" ANCHOR EMBEDMENT) |
| 8" UNREINFORCED CONCRETE (5 1/2" ANCHOR EMBEDMENT) |
| 3" MIN. ASPHALT OVER 3" MIN. CONCRETE (16 1/2" ANCHOR EMBED.) |
| 6" ASPHALT OVER 6" COMPACT SUBBASE (16 1/2" ANCHOR EMBED.) |
| 8" MINIMUM ASPHALT (16 1/2" ANCHOR EMBEDMENT) |

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

TRANSITION OPTIONS

| |
|---------------------------|
| CONCRETE VERTICAL WALL |
| CONCRETE TRAFFIC BARRIERS |
| GUARDRAIL (W-BEAM) |
| GUARDRAIL (THRIE-BEAM) |

TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS (I.E. ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES).


FOR BI-DIRECTIONAL TRANSITION PANEL AND END SHOE DETAILS, SEE MANUFACTURER'S PRODUCT MANUAL.

| | | | | | |
|---|-----------|---------|-----------|--------------------------|--|
| | | | | Design Division Standard | |
| WORK AREA PROTECTION CORP (SMART-NARROW) | | | | | |
| SMTC (N) - 16 | | | | | |
| FILE: smtcn16.dgn | DN: TxDOT | CR: KM | DN: VP | CR: VP | |
| © TxDOT: February 2006 | CONT | SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 | |
| REVISED 06, 2013 (VP) | DIST | COUNTY | SHEET NO. | | |
| REVISED 03, 2016 (VP) | DALLAS | KAUFMAN | 44 | | |



LOW MAINTENANCE

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: DATE TIME
 FILE: DOCUMENT NAME



PLAN VIEW



ELEVATION VIEW

GENERAL NOTES

1. FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: WORK AREA PROTECTION, CORP. AT (800) 327-4417, OR (630) 377-9100.
2. FOR BI-DIRECTIONAL TRAFFIC, APPROPRIATE TRANSITION PANELS WILL BE REQUIRED.
3. ADDITIONAL DETAILS FOR THE TRANSITION OPTIONS AND FOUNDATION OPTIONS WILL BE SHOWN ON THE MANUFACTURER'S SHOP DRAWINGS FURNISHED TO THE ENGINEER.
4. CONCRETE SHALL BE CLASS "S" WITH A MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI.
5. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
6. THE INSTALLATION AREA SHOULD BE FREE FROM CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
7. THE SC1100GM & SC170GM SYSTEMS SHOULD BE APPROXIMATELY PARALLEL WITH THE BARRIER OR ϕ OF MERGING BARRIERS.

NOTE: FOR ATTACHMENT AND TRANSITIONS TO OTHER SHAPES, BARRIERS RAILINGS AND BI-DIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

NOTE: SIDE PANELS CAN TRAVEL 30" BEYOND THE LAST TERMINAL BRACE AT THE REAR OF THE CUSHION. ALL OBJECTS THAT MAY INTERFERE WITH THIS MOTION CAN AFFECT PERFORMANCE OF AND MAY CAUSE UNDUE DAMAGE TO THE CRASH CUSHION.

| WIDE TRANSITION LENGTHS | | |
|-------------------------|----------------------------|----------------------------|
| GORE WIDTH | TL-2 OVERALL SYSTEM LENGTH | TL-3 OVERALL SYSTEM LENGTH |
| 41" | 20'-1" | 28'-1" |
| 48" | 21'-10" | 29'-10" |
| 55" | 23'-5" | 31'-5" |
| 60" | 24'-7" | 32'-7" |
| 68" | 26'-6" | 34'-6" |
| 69" | 26'-8" | 34'-8" |
| 81" | 29'-7" | 37'-7" |
| 88" | 31'-2" | 39'-2" |
| 94" | 32'-7" | 40'-7" |
| 100" | 34'-1" | 42'-1" |
| 107" | 35'-8" | 43'-8" |
| 112" | 36'-11" | 44'-11" |
| 120" | 38'-10" | 46'-10" |
| 126" | 40'-2" | 48'-2" |
| 133" | 41'-11" | 49'-11" |

| FOUNDATION OPTIONS |
|---|
| 6" Reinforced Concrete (5 1/2" Anchor Embedment) |
| 8" Unreinforced Concrete (5 1/2" Anchor Embedment) |
| 3" Min. Asphalt over 3" Min. Concrete (16 1/2" Anchor Embed.) |
| 6" Asphalt over 6" Compact Subbase (16 1/2" Anchor Embed.) |
| 8" Minimum Asphalt (16 1/2" Anchor Embedment) |

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

| TRANSITION OPTIONS |
|---------------------------|
| Concrete Vertical Wall |
| Concrete Traffic Barriers |
| Guardrail (W-Beam) |
| Guardrail (Three-Beam) |

TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS (I.E. ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES).

FOR BI-DIRECTIONAL TRANSITION PANEL AND END SHOE DETAILS, SEE MANUFACTURER'S PRODUCT MANUAL.

| MODEL (WIDE) | TEST LEVEL | FRONT SECTION LENGTH | UNIT WIDTH | FOUNDATION LENGTH | GORE WIDTH |
|--------------|------------|----------------------|------------|---------------------------|-------------|
| SC170GM | TL-2 | 13'-6" | 2'-10 5/8" | OVERALL LENGTH PLUS 1'-6" | 41" TO 133" |
| SC1100GM | TL-3 | 21'-6" | 3'-1 1/2" | OVERALL LENGTH PLUS 1'-6" | 41" TO 133" |

SYSTEM AND PAD LENGTHS VARY DEPENDING ON BACKUP TYPE.


LOW MAINTENANCE

| | | | | | |
|--|------------|----------|--------------|--------------------------|---------------|
| | | | | Design Division Standard | |
| WORK AREA PROTECTION CORP (SMART-WIDE) | | | | | |
| SMTC (W) - 16 | | | | | |
| FILE: smtcw16.dgn | DN: TxDOT | CR: KM | DR: BD/VP | CR: VP | |
| © TxDOT: FEBRUARY 2006 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 1H0020 | |
| REVISIONS REVISED 06, 2013 VP REVISED 03, 2016 VP REVISED 04, 2018 VP | | | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO.: 45 |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


NOTE:
A TRANSITION MAY BE REQUIRED TO INSTALL THE QUADGUARD M10 TO THE OBJECT BEING SHIELDED.

QUADGUARD M10 24" WIDE 6-BAY SYSTEM



| KEY | | KEY | |
|-----|---------------------|-----|-----------------|
| ① | QUADGUARD CARTRIDGE | ④ | MONORAILS |
| ② | DIAPHRAGM | ⑤ | NOSE ASSEMBLY |
| ③ | FENDER PANEL | ⑥ | BACKUP ASSEMBLY |

NOTE:
PROVISION SHALL BE MADE FOR REAR FENDER SIDE PANELS TO SLIDE REARWARD UPON IMPACT, 30" MIN.



NOTES:
CONTACT THE MANUFACTURER WITH SITE SPECIFIC DATA (SSD) FOR CONCRETE PAD AND ANCHOR BLOCK INSTALLATION REQUIREMENTS.

A MANUFACTURER'S DRAWING PACKAGE UNIQUE AND SPECIFIC FOR THE QUADGUARD M10 (N) INSTALLATION AND DETAILED INFORMATION REGARDING THE TYPE OF BACKUP ASSEMBLY FOR THE REQUIRED TRANSITION WILL BE PROVIDED TO THE ENGINEER AND INSTALLER.

6" REINFORCED CONCRETE PAD REQUIRES THE INSTALLATION OF AN ANCHOR BLOCK AS SHOWN ON THE MANUFACTURER'S DRAWING PACKAGE.


8" NON-REINFORCED CONCRETE PAD MAY NOT REQUIRE AN ANCHOR BLOCK, IF THE PAD IS INSTALLED AGAINST AN IMMOVABLE CONCRETE BACKUP.

CONCRETE PAD AND ANCHOR BLOCK COMBINATIONS SHALL BE CONFIRMED WITH THE MANUFACTURER BASED UPON SITE SPECIFIC DATA (SSD).

NOTE:
THE QUADGUARD M10 24" WIDE 6-BAY - NARROW SYSTEM HAS BEEN TESTED TO MASH TEST LEVEL 3.

| TL-3 MODEL # | QM10024 | CYLINDER TYPES IN BAYS | | |
|--------------|---------|------------------------|---------|---------|
| BAYS | 6 | TYPE-MII | TYPE-MI | TYPE-MI |
| DIAPHRAGMS | 6 | 3 | 3 | 1 |
| WIDTH | 24" | REAR | FRONT | NOSE |

BACKUP ASSEMBLY TYPES FOR SYSTEM TRANSITIONS




⑥ TENSION STRUT BACKUP

| SYSTEM TRANSITIONS TYPES | |
|--------------------------|--------------------------------------|
| 1 | QUAD-BEAM TO CONCRETE SAFETY BARRIER |
| 2 | QUAD-BEAM TO CONCRETE BRIDGE RAIL |
| 3 | QUAD-BEAM TO CONCRETE END SHOE |
| 4 | QUAD-BEAM TO THRIE-BEAM RAIL |
| 5 | QUAD-BEAM TO W-BEAM RAIL |

NOTE:
TRANSITION ASSEMBLIES FOR THE QUADGUARD M10 TO THRIE-BEAM OR W-BEAM FENCE REQUIRES I-BEAM POSTS:

10 (W6X9) I-BEAM POSTS,
POST 1 THRU 4 (84" LONG)
POST 5 THRU 10 (72" LONG)



⑥ CONCRETE BACKUP

NOTES:
CONTACT THE MANUFACTURER WITH SITE SPECIFIC DATA (SSD) FOR THE CORRECT BACKUP ASSEMBLY AND TRANSITION PANELS OR SIDE PANELS USED FOR STANDARD AND BI-DIRECTIONAL INSTALLATIONS: AT DIVIDED-HIGHWAY MEDIANS OR UNDIVIDED ROADWAYS WHERE THE SYSTEM IS EXPOSED TO IMPACTS FROM ONE OR TWO DIFFERENT DIRECTIONS OF TRAFFIC FLOW.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY - ENERGY ABSORPTION INC. AT 1(888)323-6374.
- SEE THE RECENT QUADGUARD M10 PRODUCT DESCRIPTION ASSEMBLY MANUAL FOR IMPACT PERFORMANCE CHARACTERISTICS AND DESIGN LIMITATIONS AND THE DRAWING PACKAGE FOR THE NARROW 24" SYSTEM BEFORE INSTALLING THE QUADGUARD M10 SYSTEM AT ANY GIVEN LOCATION.
- FOR BI-DIRECTIONAL TRAFFIC: THE LOCATION AND OR WIDTH OF THE QUADGUARD M10 IS RESTRICTED. AS BI-DIRECTIONAL TRAFFIC APPROACHES THE REAR OF THE QUADGUARD M10, THE QUADGUARD M10 SHOULD NOT EXTEND FURTHER INTO THE TRAFFIC-SIDE OF THE BARRIER THAN THE OBSTACLE. ANY TRANSITION INSTALLED MUST EITHER BE TANGENT TO BOTH QUADGUARD AND OBSTACLE OR MUST ANGLE TOWARD FIELD SIDE OF THE BARRIER.
- SYSTEM TRANSITION: APPROPRIATE TRANSITION PANELS OR SIDE PANELS WILL BE REQUIRED FOR PROPER IMPACT PERFORMANCE. THE CORRECT PANEL(S) TO USE WILL DEPEND ON THE DIRECTION OF TRAFFIC FLOW AND WHAT TYPE OF BARRIER OR ROAD FEATURE THE QUADGUARD M10 SYSTEM IS SHIELDING. SEE THE QUADGUARD M10 PRODUCT DESCRIPTION & ASSEMBLY MANUAL FOR FURTHER DETAILS.
- COMPONENTS FOR THE QUADGUARD M10 BACKUP AND REINFORCING DETAILS ARE SHOWN ON THE QUADGUARD M10 PRODUCT DESCRIPTION & ASSEMBLY MANUAL.
- CONCRETE PAD SHALL BE 6" MIN. REINFORCED 28MPa [4,000 PSI] (P.C.) OR 8" MIN. NON-REINFORCED 28MPa [4,000 PSI] CONCRETE ROADWAY MEASURING AT LEAST 12'-0" WIDE BY 50'-0" LONG. ANCHOR BLOCK IS NOT REQUIRED WHEN USING 8" CONCRETE PAD INSTALLED AGAINST AN IMMOVABLE STRUCTURE, E.G. CONCRETE WALL.
- IF THE CROSS-SLOPE VARIES MORE THAN 2% OVER THE LENGTH OF THE SYSTEM, THE CONCRETE PAD WILL REQUIRE LEVELING. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
- THE INSTALLATION AREA SHOULD BE FREE OF CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
- THE QUADGUARD M10 SYSTEM SHOULD BE INSTALLED APPROXIMATELY PARALLEL WITH THE BARRIER.
- FOR THE TENSION STRUT BACKUP THE DISTANCE BETWEEN THE BACK OF BACKUP AND THE BARRIER WALL SHOULD NOT EXCEED 7" IN ANY CASE.
- TXDOT HAS ONLY APPROVED THE 24" WIDE QUADGUARD M10 SYSTEM. THE QUADGUARD M10 PRODUCT DESCRIPTION AND ASSEMBLY MANUAL INCLUDES SYSTEM WIDTH OF 24". ONLY THE 24" SYSTEM IS ALLOWED TO BE INSTALLED ON TEXAS ROADWAYS.

FOUNDATION & ANCHORING REQUIREMENTS
FOUNDATION TYPES: A, B, C, & D

| | |
|--------------------|---|
| FOUNDATION TYPE: A | REINFORCED CONCRETE PAD OR ROADWAY |
| FOUNDATION: | 6" MINIMUM DEPTH (P.C.C.) |
| ANCHORAGE: | 7" STUDS EMBEDDED 5 1/2" - APPROVED ADHESIVE |
| FOUNDATION TYPE: B | ASPHALT OVER P.C.C. |
| FOUNDATION: | 3" MIN. (A.C.) OVER 3" MIN. (P.C.C.) |
| ANCHORAGE: | 18" THREADED ROD EMBEDDED 16 1/2" |
| FOUNDATION TYPE: C | ASPHALT OVER SUBBASE |
| FOUNDATION: | 6" MIN. (A.C.) OVER 6" MIN. (C.S.) |
| ANCHORAGE: | 18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE |
| FOUNDATION TYPE: D | ASPHALT ONLY |
| FOUNDATION: | 8" MIN. (A.C.) |
| ANCHORAGE: | 18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE |

KEYS:
ASPHALT CONCRETE (A.C.)
COMPACTED SUBBASE (C.S.)
PORTLAND CEMENT CONCRETE (P.C.C.)

NOTE: SEE TRINITY'S PRODUCT DESCRIPTION ASSEMBLY MANUAL FOR THE APPROVED ADHESIVE.

IF THE UNIT IS ANCHORED TO ASPHALTIC CONCRETE, IT SHOULD BE RELOCATED TO FRESH, UNDISTURBED ASPHALT AND RE-ANCHORED AFTER EACH IMPACT TO ENSURE ADEQUATE FUTURE PERFORMANCE.

TENSION STRUT BACKUP MAY BE USED IN CONSTRUCTION ZONES ON ASPHALT CONCRETE (A.C.) FOR TEMPORARY USE ONLY.

DATE:
FILE:

NOTE:
THIS STANDARD IS A BASIC REPRESENTATION OF THE QUADGUARD M10 SYSTEM AND IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.




REUSABLE

Design Division Standard

TRINITY HIGHWAY
 ENERGY ABSORPTION
 QUADGUARD M10
 (MASH TL-3 NARROW-24" ONLY)
 QUADGUARD (M10) (N) - 20

| | | | | |
|------------------------|-----------|---------|-----------|--------|
| FILE: qguardm10n20.dgn | DN: TXDOT | CK: KM | DW: VP | CK: AG |
| © TXDOT: APRIL 2020 | CONT SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 81 | 001 | 1H0020 | |
| | DIST | COUNTY | SHEET NO. | |
| | DALLAS | KAUFMAN | 46 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



| TYPE (WIDE) | TEST LEVEL |
|-----------------------------|------------|
| FASTRACC (4 Stage System) | 70 |
| TRACC (3 Stage System) | TL-3 |
| SHORTTRACC (2 Stage System) | TL-2 |

NOTE: The Stage System refers to number of replaceable "sled sections" that could be replaced independently.

| Wide-FASTRACC WING EXTENSIONS | | | | |
|-------------------------------|-------|---------------|------------------|--|
| NUMBER OF WING EXTENSIONS | WIDTH | SYSTEM LENGTH | EFFECTIVE LENGTH | Wide-FASTRACC EXTENSION PART NUMBER (LEFT# / RIGHT#) |
| 0 (BASE UNIT) | 71" | 25'-11" | 27'-11" | |
| 1 | 78" | 28'-3" | 30'-3" | 33940 |
| 2 | 85" | 30'-7" | 32'-7" | 33941 / 33942 |
| 3 | 92" | 32'-11" | 34'-11" | 33943 / 33944 |
| 4 | 99" | 35'-2" | 37'-2" | 33945 / 33946 |
| 5 | 106" | 37'-6" | 39'-6" | 33947 / 33948 |
| 6 | 113" | 39'-10" | 41'-10" | 33949 / 33950 |
| 7 | 120" | 42'-2" | 44'-2" | 33951 / 33952 |
| 8 | 127" | 44'-5" | 46'-5" | 33953 / 33954 |
| 9 | 134" | 46'-9" | 48'-9" | 33955 / 33956 |
| 10 | 141" | 49'-1" | 51'-1" | 33957 / 33958 |
| 10+ | | | | CONSULT TRINITY SALES PERSON |

| Wide-TRACC WING EXTENSIONS | | | | |
|----------------------------|-------|---------------|------------------|---|
| NUMBER OF WING EXTENSIONS | WIDTH | SYSTEM LENGTH | EFFECTIVE LENGTH | Wide-TRACC EXTENSION PART NUMBER (LEFT# / RIGHT#) |
| 0 (BASE UNIT) | 58" | 21' | 23' | |
| 1 | 65" | 23'-4" | 25'-4" | 33940 |
| 2 | 72" | 25'-8" | 27'-8" | 33941 / 33942 |
| 3 | 79" | 28' | 30' | 33943 / 33944 |
| 4 | 86" | 30'-4" | 32'-4" | 33945 / 33946 |
| 5 | 92" | 32'-8" | 34'-8" | 33947 / 33948 |
| 6 | 99" | 35' | 37' | 33949 / 33950 |
| 7 | 106" | 37'-4" | 39'-4" | 33951 / 33952 |
| 8 | 113" | 39'-8" | 41'-8" | 33953 / 33954 |
| 9 | 120" | 42' | 44' | 33955 / 33956 |
| 10 | 127" | 44'-4" | 46'-4" | 33957 / 33958 |
| 10+ | | | | CONSULT TRINITY SALES PERSON |

| Wide-SHORTTRACC WING EXTENSIONS | | | | |
|---------------------------------|-------|---------------|------------------|--|
| NUMBER OF WING EXTENSIONS | WIDTH | SYSTEM LENGTH | EFFECTIVE LENGTH | Wide-SHORTTRACC EXTENSION PART NUMBER (LEFT# / RIGHT#) |
| 0 (BASE UNIT) | 39" | 15' | 17' | |
| 1 | 46" | 17'-4" | 19'-4" | 33940 |
| 2 | 53" | 18'-9" | 20'-9" | 33941 / 33942 |
| 3 | 60" | 21'-1" | 23'-1" | 33943 / 33944 |
| 4 | 66" | 23'-5" | 25'-5" | 33945 / 33946 |
| 5 | 73" | 25'-8" | 27'-8" | 33947 / 33948 |
| 6 | 80" | 28'-1" | 30'-1" | 33949 / 33950 |
| 7 | 87" | 30'-4" | 32'-4" | 33951 / 33952 |
| 8 | 94" | 32'-7" | 34'-7" | 33953 / 33954 |
| 9 | 101" | 34'-11" | 36'-11" | 33955 / 33956 |
| 10 | 108" | 37'-3" | 39'-3" | 33957 / 33958 |
| 10+ | | | | CONSULT TRINITY SALES PERSON |

Attachment and transitions to other shapes, barriers railings and bi-directional traffic flows are available. (See manufacturer's product manual).

| BACKUP SUPPORT OPTIONS | |
|--------------------------------------|--|
| SQUARE CONCRETE BACKUP | |
| CONCRETE BARRIER (CTB) BACKUP | |
| SINGLE SLOPE CONCRETE BARRIER (SSCB) | |
| GUARDRAIL BACKUP (BASE-PLATED POST) | |
| GUARDRAIL BACKUP (DRIVEN POST) | |
| TRANSITION OPTIONS | |
| VERTICAL WALL | |
| MODIFIED (CTB) TO VERTICAL WALL | |
| CONCRETE BARRIER (CTB) | |
| GUARDRAIL (W-BEAM) | |
| GUARDRAIL (THRIE-BEAM) | |

FOR BI-DIRECTIONAL TRANSITION PANEL DETAILS (SEE MANUFACTURER'S PRODUCT MANUAL).

BACKUP AND TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS, (I.E. ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES).

| FOUNDATION OPTIONS | |
|---------------------------------------|--|
| 6" REINFORCED CONCRETE | |
| 8" UNREINFORCED CONCRETE | |
| 3" MIN. ASPHALT OVER 3" MIN. CONCRETE | |
| 6" ASPHALT OVER 6" COMPACT SUBBASE | |
| 8" MINIMUM ASPHALT | |

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, (SEE MANUFACTURER'S PRODUCT MANUAL).

GENERAL NOTES

- For specific information regarding installation and technical guidance of the system, contact: Trinity Highway at 1(888)323-6374, 2525 N. Stemmons Freeway - Dallas, TX 75207
- Contact the company for: Custom widths from 31" up to 57" wide, and transition panels for bi-directional traffic applications.
- Details of components for the WideTRACC, Backups and re-inforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
- Concrete shall be class "S" with a min. compressive strength 4,000 p.s.i.
- If the cross-slope varies more than 2% over the length of the system, the concrete pad will require leveling. Maximum permissible cross-slope 8%.
- The installation area should be free from curbs, elevated objects, or depressions.
- The WideTRACC system should be approximately parallel with the barrier or ϕ of merging barriers.
- The Unit shown is flared on both sides, but can be flared on a single side either left or right. The flares will effect the length and width of the system. (See Wing Extension Tables)

| Wide-TRACC - BILL OF MATERIAL | | | | |
|-------------------------------|----------------|-----------|-----------------|---------------------------------|
| PART # | FAST TRACC QTY | TRACC QTY | SHORT TRACC QTY | DESCRIPTION |
| 25937A | 1 | | | WIDEFASTRACC UNIT ASSEMBLY |
| 25939A | | 1 | | WIDETRACC UNIT ASSEMBLY |
| 25997A | | | 1 | WIDESHORTTRACC UNIT ASSEMBLY |
| 3310G | 4 | 4 | 4 | 5/8" LOCKWASHER |
| 4372G | 4 | 4 | 4 | 5/8" FLATWASHER |
| 4451G | 4 | 4 | 4 | 5/8" DIA X 6" EXP. WEDGE ANCHOR |
| 6531B | 1 | 1 | 1 | PLASTIC NOSEPIECE |
| 6668B | 4 | 4 | 4 | REFLECTIVE SHEETING |

| ANCHOR HARDWARE (CONCRETE BASE) | | | | |
|---------------------------------|----|----|----|-----------------------------------|
| 5204B | 72 | 50 | 18 | 5/8" DIA X 7-1/8" THD ANCHOR STUD |
| 4372G | 72 | 50 | 18 | 5/8" FLATWASHER |
| 3310G | 72 | 50 | 18 | 5/8" LOCKWASHER |
| 3361G | 72 | 50 | 18 | 5/8" HEX NUT |
| 5206B | 6 | 4 | 2 | Adhesive, Hilti Hit HY-150 |

| ANCHOR HARDWARE (ASPHALT BASE) | | | | |
|--------------------------------|----|----|----|--------------------------------|
| 6380G | 72 | 50 | 18 | 5/8" Dia x 18" Thd Anchor Stud |
| 4372G | 72 | 50 | 18 | 5/8" Flatwasher |
| 3310G | 72 | 50 | 18 | 5/8" Lockwasher |
| 3361G | 72 | 50 | 18 | 5/8" HEX NUT |
| 5206B | 15 | 11 | 4 | ADHESIVE, HILTI HIT HY-150 |

| ANCHOR HARDWARE (OPTIONAL ITEMS, AS NEEDED) | | | | |
|---|-----|-----|-----|------------------------------------|
| 5207B | A/R | A/R | A/R | NOZZLE, MIXER, HILTI HIT HY-150 |
| 5208B | A/R | A/R | A/R | EXT. TUBE, MIXER, HILTI HIT HY-150 |
| 5205B | A/R | A/R | A/R | DISPENSER GUN, HILTI HIT HY-150 |
| 5209B | A/R | A/R | A/R | DRILL BIT, 1/2", HILTI SDS |



**TRINITY HIGHWAY
CRASH CUSHION
(WIDE UNIT)
TRACC (W) - 16**





| | | | | |
|-----------------------|-----------|---------|--------|-----------|
| FILE: traccw16.dgn | DN: TxDOT | CR: KM | DN: VP | CR: VP |
| ©TxDOT February 2006 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| REVISED 06, 2013 (VP) | DIST | COUNTY | | SHEET NO. |
| REVISED 03, 2016 (VP) | DALLAS | KAUFMAN | | 47 |

REUSABLE





DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



Note:
Tie 3/8" cable using cable ties on opposite side of the post breaker.



NOTE:
Concrete bridge rails may require a modified end at the terminal connection. (Contact the Bridge Division for details.)

GENERAL NOTES

- For specific information regarding installation and technical guidance of the system, contact Road Systems, Inc., at (330)346-0721, 3616 Old Howard County Airport, Big Springs, TX 79720
- Due to the Single-Sided design, the BEAT-SSCC is not appropriate for use at locations where backside hits towards the rigid concrete barrier are possible, e.g. In gore areas, or in narrow median locations where backside opposite direction hits are likely.
- All bolts, nuts, cable assemblies, cable anchors, bearing plate, tubing, post, impact heads, and other steel components shall be galvanized, unless otherwise noted.
- The breakaway cable assembly must be taut. A locking device, (vice grips or channel lock pliers) should be used to prevent the cable from twisting when tightening the nuts.
- When site conditions permit, posts may be driven. The lower section of post #1 should not be driven with the upper post section attached. If posts are placed in a drilled hole, the backfill material must be satisfactorily compacted to prevent settlement.
- If rock excavation is encountered, see manufacturer's installation booklet for installation recommendations.
- Post shall not be set full depth in concrete.
- The appropriate connection of the SSCC to the stationary rigid structure is a critical component to insure proper performance of the system. The length of the 1" bolts used to attach the system to the rigid structure will vary with the wall thickness and will need to be determined in the field.
- The approach area in front of the SSCC and the area within the system itself shall be free of fixed obstacles greater than 4 inches in height and have a fill slope or a cut slope of 1V:10H or flatter.
- Unless otherwise shown in the plans, SSCC rail placed in the vicinity of curbs shall be blocked out so that the face of curb is located directly below the face of rail. The steel posts shall be installed at the proper ground elevation above the gutter pan or roadway surface. Curbs located along or in front of the SSCC system shall not be greater than 4 inches in height.
- An object marker shall be installed on the front of the impact head as detailed on D & OM(VIA).

| ITEM | QTY | DESCRIPTION |
|-----------------|-----|--|
| A | 1 | Box-Beam Impact Head |
| B | 1 | Upper End Post (A1) W6 x 9 x 1'-9 1/2" LG. |
| C | 1 | Lower End Post (A4) W6 x 15 x 8'-0" LG. |
| D | 1 | Support Bracket (B1) L4 x 2 x 4" LG. |
| E | 1 | Post Breaker (A2) Welded TS2 x 2 x 1/4" |
| F | 1 | Cable Anchor Assembly |
| G | 1 | Cable Anchor Bearing Plate |
| H | 1 | End Tube Rail (A5) x 8'-0" LG. |
| J | 7 | Steel Breakaway Post W6 x 9 x 6'-0" LG. |
| K | 5 | Support Bracket w/ Blockout (A9) TS6 x 6 w/ Bent PL. |
| L | 1 | Second Rail (A11) x 16'-2 1/2" LG. |
| M | 1 | Transition Blockout (A6) x 5'-6" LG. |
| N | 2 | Trans. Support Bracket (A10) 3/8" Bent PL. w/ Gusset |
| P | 2 | End Section Splice Plate (A3) - Detail Below |
| Q | 2 | 1" Square Washer (B10) PL 4 x 4 x 1/4" |
| R | 1 | Anchor Rail (A13) x 8'-6 1/8" LG. |
| S | 2 | Splice Plate (A12) PL 10 x 10 x 3/8" Detail Below |
| T | 1 | 3/8" GALV. Cable x 20'-0" (A14) |
| U | 6 | Tie Plate (C10) PL 11 1/2" x 3 1/2" x 3/8" |
| V | 1 | Spacer (D10) (OMIT ON VERTICAL WALL) |
| HARDWARE | | |
| a | 14 | 3/8" x 7 1/2" Hex Bolt (A449) |
| b | 14 | 3/8" Hex Nut |
| c | 28 | 3/8" Washer |
| d | 1 | 1/4" x 3" Hex Bolt (A449) |
| e | 1 | 1/4" Hex Nut |
| f | 1 | 1/4" Washer |
| g | 7 | 3/8" x 1 1/2" Bolt (A307) |
| h | 7 | 3/8" Recess Nut |
| i | 8 | 3/8" x 2" Hex Bolt (A325 or A449) |
| j | 1 | 3/8" x 8" Hex Bolt (A325 or A449) |
| k | 18 | 3/8" Hex Nut |
| m | 25 | 3/8" Washer |
| n | 1 | 3/8" x 3" Hex Bolt (A325 or A449) |
| p | 4 | 3/8" x 9" Hex Bolt (A325 or A449) |
| q | 1 | 1/2" x 5" Hex Bolt (A325 or A449) |
| r | 2 | 1/2" Hex Nut |
| s | 1 | 1/2" x 2" Hex Bolt (A307, A325 or A449) |
| t | 2 | 1" x 10" Hex Bolt (A325 or A449) (Length Varies w/Wall Sect) |
| u | 4 | 1" Hex Nut (2H Heavy Hex Nut) |
| v | 4 | 1" Washer Structural Washer |
| w | 2 | 1/2" Washer |
| x | 2 | Cable Tie |
| y | 1 | Object Marker |

Design
Division
Standard


ROAD SYSTEMS INC
CRASH CUSHION
(BEAT)
SSCC-16

| | | | | |
|-----------------------|-----------|---------|-----------|---------|
| FILE: SSCC16.dgn | DN: TxDOT | CR: KM | DR: BD | CR: VP |
| ©TxDOT April 2003 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| REVISED 03, 2016 (VP) | DIST | COUNTY | SHEET NO. | |
| | DALLAS | KAUFMAN | 48 | |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Preferred Installation: Locate post #2 away from nearest traffic. System has been successfully tested with opposite installation.


Length-of-Need Cass Cable Terminal (CCT):
Departure Installation: Length-of-Need: 44'-9" (At Post #8)
Approach Installation: Length-of-Need: 19'-9" (12" Past Post #4)




PLAN VIEW




ELEVATION VIEW (TYPICAL LAY-OUT)




CABLE SPLICE WITH TURNBUCKLE (OPEN BODY STYLE)
CABLE STUD ASSEMBLY
TORPEDO CABLE SPLICE




SECTION E-E




SECTION F-F




SECTION G-G




VIEW A-A (CABLE RELEASE POST 1-3)




VIEW B-B (TERMINAL LINE POST 4-7)



SECTION C-C (SOCKETED POST)



SECTION D-D (BASE PLATED POST)



STANDARD POST & CONCRETE FOOTING (SOCKETED POST)

GENERAL NOTES

- This drawing is a general overview of CASS TL-3 Barrier System. See SS-730 (latest version) for specific details of CASS cable terminal (CCT) and cable safety system (CASS) requirements, proper installation, options and specification.
- CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity (800-527-6050) or consult the design, installation, or repair manual(s) for additional information.
- All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
- All posts shall be socketed unless otherwise specified. All cables shall be pre-stretched unless otherwise specified.
- For payment see Special Specification "Cable Barrier System".
- CASS TL-3 shall be installed on shoulders or medians with slopes of 6:1 or flatter without obstructions, depressions, etc. That may significantly affect the stability of an errant vehicle. Grading of site and/or appropriate fill materials may be required. The designer/installer shall "Flatten" or "Round" various topographical inconsistencies that could interfere with the ability of the installer to consistently maintain the design height (in relation to the terrain) of the cables. Please consult manual(s) and/or TxDOT Memo(s) for installations in "Ditch Sections".
- CASS TL-3 post spacing may be modified to avoid obstacles that conflict with the installation of CASS TL-3 line posts or to reduce deflection on radiuses. No post space can exceed the maximum post TxDOT space limit of 20'. Reducing or increasing post spacing affects deflection. CASS TL-3 may be laterally transferred at a rate not to exceed 30:1.
- Post foundations may be drilled through existing pavement. Please see line post foundation chart for minimum footing requirements in various applications.
- For aesthetic purposes Trinity recommends all sleeves, driven posts, and lower cable release posts to be installed reasonably plumb (approximately 1/8" per foot).
- CASS TL-3 shall be installed in well-drained, compacted, NCHRP Report 350 Standard soil. If soil does not meet this classification, if solid rock/concrete is encountered below grade or if soil is susceptible to severe freeze/thaw cycles, please contact Trinity about alternate footing design(s). Trinity suggests the use of "Mow strips" for erosion prevention and ease of maintenance / installation.
- See the Texas MUTCD for proper "Barrier" Delineation.

| MOW STRIP DETAIL* | | CONCRETE FOOTING CHART | | | |
|-------------------|---------|------------------------|--------------|-------------------|-----|
| MOW STRIP | DEPTH | WIDTH | FOOTING TUBE | SLEEVE REBAR RING | |
| NONE | | | 30" Min. | 27" Min. | YES |
| HMA | 6" Min. | 3' Min. | 27" Min. | 15" Min. | NO |
| HMA | 8" Min. | 3' Min. | 24" Min. | 15" Min. | NO |
| RC | 3" Min. | 3' Min. | 24" Min. | 15" Min. | NO |

Chart does not apply to Terminal Posts 1 thru 9.
 * Mow strip or pavement.
 HMA = Hot Mix Asphalt (Not Recycled Asphalt Pavement).
 RC = Reinforced Concrete (TxDOT Class A Minimum).

Trinity Highway Products, LLC.
 2525 Stemmons Freeway
 Dallas, TX 75207
 Phone: (800) 644-7976
 Product: INFO@TRIN.NET

| CABLE TENSION CHART | |
|---------------------|--------------------------|
| FAHRENHEIT DEGREES | PRE-STRETCHED LB / FORCE |
| -10 | 7300 |
| 0 | 7000 |
| 10 | 6600 |
| 20 | 6300 |
| 30 | 6000 |
| 40 | 5600 |
| 50 | 5300 |
| 60 | 5000 |
| 70 | 4600 |
| 80 | 4300 |
| 90 | 4000 |
| 100 | 3600 |
| 110 | 3300 |
| 120 | 3000 |
| 130 | 2700 |
| 140 | 2500 |
| 150 | 2300 |

Allowable deviation from chart in tangent sections: +800, -200 pounds/force. Cable tension readings are typically higher in curved cable sections.

Texas Department of Transportation
TRINITY CABLE SAFETY SYSTEM (TL-3)
CASS (TL3) - 14












| | | | | |
|---------------------|-----------------|---------------|--------|-----|
| FILE: CASSt1314.dgn | DN: TxDOT | CR: RM | DN: VP | CK: |
| ©TxDOT: MARCH 2014 | CONT: SECT | JOB: HIGHWAY | | |
| REVISIONS | 6373 81 | 001 | 1H0020 | |
| DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 49A | | |

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Preferred Installation: Locate post #2 away from nearest traffic. System has been successfully tested with opposite installation.

Length-of-Need Cass Cable Terminal (CCT):
Departure Installation: Length-of-Need: 44'-9" (At Post #8)
Approach Installation: Length-of-Need: 19'-9" (12" Post Post #4)



GENERAL NOTES

- This drawing is a general overview of CASS TL-4 Barrier System. See SS-740 (latest version) for specific details of CASS cable terminal (CCT) and cable safety system (CASS) requirements, proper installation, options and specification.
- CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity (800-527-6050) or consult the design, installation, or repair manual(s) for additional information.
- All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
- All posts shall be socketed unless otherwise specified. All cables shall be pre-stretched unless otherwise specified.
- For payment see Special Specification "Cable Barrier System".
- CASS-TL4 shall be installed on shoulders or medians with slopes of 6:1 or flatter without obstructions, depressions, etc. That may significantly affect the stability of an errant vehicle. Grading of site and/or appropriate fill materials may be required. The designer/installer shall "Flatten" or "Round" various topographical inconsistencies that could interfere with the ability of the installer to consistently maintain the design height (in relation to the terrain) of the cables. Please consult manual(s) and / or TxDOT Memo(s) for installations in "Ditch Sections".
- CASS TL-4 post spacing may be modified to avoid obstacles that conflict with the installation of cass-tl4 line posts or to reduce deflection on radiuses. No post space can exceed the maximum post TxDOT space limit of 20'. Reducing or increasing post spacing affects deflection. CASS TL-4 may be laterally transferred at a rate not to exceed 30:1.
- Post foundations may be drilled through existing pavement. Please see line post foundation chart for minimum footing requirements in various applications.
- For aesthetic purposes Trinity recommends all sleeves, driven posts, and lower cable release posts to be installed reasonably plumb (approximately 1/8" per foot).
- CASS TL-4 shall be installed in well-drained, compacted, NCHRP Report 350 Standard soil. If soil does not meet this classification, if solid rock/concrete is encountered below grade or if soil is susceptible to severe freeze/thaw cycles, please contact Trinity about alternate footing design(s). Trinity suggests the use of "Mow strips" for erosion prevention and ease of maintenance / installation.
- See the Texas MUTCD for proper "Barrier" Delineation.

| MOW STRIP DETAIL | | CONCRETE FOOTING CHART | | | |
|------------------|---------|------------------------|----------|-------------|------------|
| MOW STRIP | DEPTH | WIDTH | FOOTING | TUBE SLEEVE | REBAR RING |
| NONE | | | 30" Min. | 27" Min. | YES |
| HMA | 6" Min. | 3' Min. | 27" Min. | 15" Min. | NO |
| HMA | 8" Min. | 3' Min. | 24" Min. | 15" Min. | NO |
| RC | 3" Min. | 3' Min. | 24" Min. | 15" Min. | NO |

Chart does not apply to Terminal Posts 1 thru 9.
 * Mow strip or pavement.
 HMA = Hot Mix Asphalt (Not Recycled Asphalt Pavement).
 RC = Reinforced Concrete (TxDOT Class A Minimum).

Trinity Highway Products, LLC.
 2525 Stemmons Freeway
 Dallas, TX 75207
 Phone: (800) 644-7976
 Product: INFO@TRIN.NET

| CABLE TENSION CHART | |
|---------------------|--------------------------|
| FAHRENHEIT DEGREES | PRE-STRETCHED LB / FORCE |
| -10 | 7300 |
| 0 | 7000 |
| 10 | 6600 |
| 20 | 6300 |
| 30 | 6000 |
| 40 | 5600 |
| 50 | 5300 |
| 60 | 5000 |
| 70 | 4600 |
| 80 | 4300 |
| 90 | 4000 |
| 100 | 3600 |
| 110 | 3300 |
| 120 | 3000 |
| 130 | 2700 |
| 140 | 2500 |
| 150 | 2300 |

Allowable deviation from chart in tangent sections: +800, -200 pounds/force. Cable tension readings are typically higher in curved cable sections.

Texas Department of Transportation









TRINITY CABLE SAFETY SYSTEM (TL-4)

CASS (TL4) - 14

| | | | | |
|--------------------|------------|------------|----------|--------|
| FILE: CASS1414.dgn | DN: TxDOT | CR: RM | DR: VP | CK: |
| ©TxDOT: March 2014 | CONT: SECT | JOB: | HIGHWAY: | |
| REVISIONS: | 6373 | 81 | 001 | 1H0020 |
| DIST: | COUNTY: | SHEET NO.: | | |
| DALLAS | KAUFMAN | 49B | | |

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



CABLE RELEASE AND ANCHOR POST
(Shown with Tube Plate Option)
(See Note 9)

TERMINAL POST
(Shown with Concrete Mowstrip)
(See Note 9)

LINE POST SOCKETED
(Shown with Rebar Ring/Bars Socket Option)
(See Note 9)

LINE POST SOCKETED
(Shown with Welded Rebar Socket Option)
(See Note 9)

LINE POST (DRIVEN OPTION)
(Shown with Driven Socket Option)
(See Note 9)

- ### GENERAL NOTES
- For additional information contact Gibraltar, Inc. at 1-800-495-8957, 830-798-5444, or see the manufacturer's product manual.
 - All concrete shall be CLASS A.
 - The Cable Barrier System shall be installed on shoulders or on medians with slopes of 6:1 or flatter.
 - The Cable Barrier System is accepted by the FHWA Test Level - 3.
 - See the Texas MUTCD for proper "Barrier" delineation.
 - Rock Clause: Where solid rock is encountered:
 - For socketed post, continue digging 12" diameter, 15" deep into rock or the required plan depth, whichever comes first.
 - For driven post, core drill a 4" diameter hole 18" deep into rock or the required plan depth, whichever comes first.
 - For Anchor post, continue digging 24" diameter, 30" deep into rock or the required plan depth, whichever comes first.
 - Tolerances:
 - * LP = 3" out of plumb, at top
 - * Cable height = 1"
 - * Anchor Post = 5" off of Cable Reference Line
 - The Gibraltar cable barrier system shall be installed in NCHRP Report 350 standard compacted soil. Soil must be well drained.
 - All non-welded rebar by others.
 - Minimum recommended line post foundation.
 - Without mowstrip, 36" Deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long
 - With 4" minimum depth hot mix asphalt, 30" deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long.
 - With 3" minimum depth concrete mowstrip, 24" deep x 12" diameter foundations. (No rebar required)
 - Direct drive post 42" deep.

| CABLE TENSION CHART # | |
|-----------------------|------|
| -10 °F | 8000 |
| 0 °F | 7600 |
| 10 °F | 7200 |
| 20 °F | 6800 |
| 30 °F | 6400 |
| 40 °F | 6000 |
| 50 °F | 5600 |
| 60 °F | 5200 |
| 70 °F | 4800 |
| 80 °F | 4400 |
| 90 °F | 4000 |
| 100 °F | 3600 |
| 110 °F | 3200 |

| DEFLECTION | |
|------------|--------------|
| Deflection | Post Spacing |
| 8'-0" | 20 FT |
| 7'-0" | 12 FT |
| 6'-8" | 10 FT |


* Allowable Deviation from Chart +/- 10%

Design Division Standard
GIBRALTAR CABLE BARRIER SYSTEM (TL-3)
GBRLTR(TL3)-14

| | | | | |
|----------------------|------------|---------|----------|-----------|
| FILE: gbrltr1314.dgn | DN: TxDOT | CR: RM | DW: VP | CK: |
| ©TxDOT: March 2014 | CONT: SECT | JOB: | HIGHWAY: | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| | DIST: | COUNTY: | | SHEET NO. |
| | DALLAS | KAUFMAN | | 50A |

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GENERAL NOTES

- For additional information contact Gibraltar, Inc. at 1-800-495-8957, 830-798-5444, or see the manufacturer's product manual.
- All concrete shall be CLASS A.
- The Cable Barrier System shall be installed on shoulders or on medians with slopes of 6:1 or flatter. If installed on slopes steeper than 6:1 up to 4:1 the TL-4 system performs as a TL-3 and Gibraltar must be contacted for various guidelines related to placement.
- The Cable Barrier System is accepted by the FHWA Test Level - 4.
- See the Texas MUTCD for proper "Barrier" delineation.
- Rock Clause: Where solid rock is encountered:
 - For socketed post, continue digging 12" diameter, 15" deep into rock or the required plan depth, whichever comes first.
 - For driven post, core drill a 4" diameter hole 18" deep into rock or the required plan depth, whichever comes first.
 - For Anchor post, continue digging 24" diameter, 30" deep into rock or the required plan depth, whichever comes first.
- Tolerances:
 - * LP = 3" out of plumb, at top
 - * Cable height = 1"
 - * Anchor Post = 5" off of Cable Reference Line
- The Gibraltar cable barrier system shall be installed in NCHRP Report 350 standard compacted soil. Soil must be well drained.
- All non-welded rebar by others.
- Minimum recommended line post foundation.
 - Without mowstrip, 36" Deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long
 - With 4" minimum depth hot mix asphalt, 30" deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long.
 - With 3" minimum depth concrete mowstrip, 24" deep x 12" diameter foundations. (No rebar required)
 - Direct drive post 42" deep.

CABLE TENSION CHART*

| | |
|--------|------|
| -10 °F | 8000 |
| 0 °F | 7600 |
| 10 °F | 7200 |
| 20 °F | 6800 |
| 30 °F | 6400 |
| 40 °F | 6000 |
| 50 °F | 5600 |
| 60 °F | 5200 |
| 70 °F | 4800 |
| 80 °F | 4400 |
| 90 °F | 4000 |
| 100 °F | 3600 |
| 110 °F | 3200 |

DEFLECTION

| Deflection | Post Spacing |
|------------|--------------|
| 8'-0" | 20 FT |
| 7'-0" | 12 FT |
| 6'-8" | 10 FT |

* Allowable Deviation from Chart +/- 10%

Texas Department of Transportation
Design Division Standard


GIBRALTAR CABLE BARRIER SYSTEM (TL-4)

GBRL TR (TL4) - 14


| | | | | |
|-----------------------|--------------|-----------------|---------------|-----------------|
| FILE: gbrrtrtl414.dgn | DN:TxDOT | CK:RM | DW:VP | CK: |
| ©TxDOT: March 2014 | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 1H0020 |
| REVISIONS | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO. 50B | |

DATE: FILE: CABLE RELEASE AND ANCHOR POST


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TYPICAL POST




WOOD BLOCK TO ROUND WOOD POST




WOOD BLOCK TO RECTANGULAR WOOD POST




WOOD BLOCK TO STEEL POST



*** LOW FILL CULVERT POST FOR USE ON NON-BRIDGE CLASS CULVERTS ONLY**




* Post(s) may require field modifications to ensure proper guardrail height.




RAIL SPLICE DETAIL

GENERAL NOTES

- The type of post (round wood post, rectangular wood post, or steel post) will be shown elsewhere in the plans. The exact position of MGBF shall be shown elsewhere in the plans or as directed by the Engineer. Steel posts to be galvanized in accordance with Item 445, "Galvanizing."
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans. The Contractor may furnish rail elements of 12 1/2 or 25 foot nominal lengths.
- Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the nut (ASTM A563) and Type A (1 1/4" O.D.) washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 3/8" x 1 1/4" (or 2" long at triple rail splices) with a 3/8" double recessed nut (ASTM A563).
- Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item.
- Crown shall be widened to accommodate the Metal Beam Guard Fence.
- The lateral approach to the guard fence, shall have a slope rate of not more than 1V:10H.
- Unless otherwise shown in the plans, guard fence placed in the vicinity of curbs shall be positioned so that the face of curb is located directly below or behind the face of the block. Rail placed over curbs shall be installed so that the post bolt is located approximately 21 inches above the gutter pan or roadway surface.
- If solid rock is encountered within 0 to 18" of the finished grade, drill a 22" dia. hole, 24" into the rock, or drill two 12" dia. front to back overlapping holes, 24" into the rock. If solid rock is encountered below 18", drill a 12" dia. hole, 12" into the rock or to the standard embedment depth, whichever is less. Any excess post length, after meeting these depths, may be field cut to ensure proper guardrail mounting height. Backfill with a cohesionless material.
- Posts shall not be set in concrete, of any depth.
- Special fabrication will be required at installations having a curvature of less than 150 ft. radius.
- The terminal anchor section (TAS) post shall be set in Class A concrete (unless otherwise shown in the plans) in accordance with Item 421, "Hydraulic Cement Concrete." Concrete shall be subsidiary to the bid item requiring construction of the terminal anchor section (TAS). Terminal anchor post to be galvanized in accordance with Item 445, "Galvanizing."
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.




ELEVATION 12 1/2" (NOM.) W-BEAM SECTION
25 foot sections may also be supplied (See General Note 2)




**** TERMINAL ANCHOR SECTION (TAS)**

Terminal anchor sections are only for downstream use, when located outside the horizontal clearance area of opposing traffic.



OPTION (1)

Note: This anchor post requires four additional 3/4" holes (snap or field) in the rail member with eight 3/8" hex bolts with nut and plate washer.




OPTION (2)


Note: This anchor post requires the use of the 10 ga. terminal connector with four 3/8" hex bolts with nut and washer.

TERMINAL ANCHOR POST OPTIONS
(See General Note 11)

Notes:
 Either concrete anchor may be used with either post option above. No construction joint is allowed in the concrete anchor.
 Terminal rail may be bolted to post and in twist position prior to placing concrete anchor.
 If concrete anchor is precast, the area should be compacted as directed by the Engineer, when placed in the field.



TERMINAL CONCRETE ANCHOR OPTIONS
(See General Note 11)



TERMINAL CONNECTOR

For connection hardware to concrete rails, see the MGBF transition standards.

ONLY FOR USE IN MAINTENANCE REPAIRS OR HIGHLY CONSTRAINED SITE CONDITIONS.

Texas Department of Transportation
Design Division Standard

METAL BEAM GUARD FENCE




MBGF - 19

| | | | | |
|-----------------------|------------|--------|-----------|--------|
| FILE: mbgf19.dgn | DN: TxDOT | CK: KM | DN: BD | CK: VP |
| © TxDOT NOVEMBER 2019 | CONT: SECT | JOB: | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| DIST: | COUNTY: | | SHEET NO. | |
| DALLAS | KAUFMAN | | 51 | |

DATE:
FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:



GENERAL NOTES


- The type of (CRT) post (round wood post, or rectangular wood post) will be shown elsewhere in the plans. The exact position of MBGF shall be shown elsewhere in the plans or as directed by the Engineer.
- Steel posts are not permitted at CRT post positions.
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans. The Contractor may furnish rail elements of 12 1/2 or 25 foot nominal lengths.
- Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the nut (ASTM A563) and Type A (1 1/4" O.D.) washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 5/8" x 1 1/4" (or 2" long at triple rail splices) with a 3/8" double recessed nut (ASTM A563).
- Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item.
- Crown shall be widened to accommodate the Metal Beam Guard Fence.
- The lateral approach to the guard fence, shall have a slope rate of not more than 1V:10H.
- Unless otherwise shown in the plans, guard fence placed in the vicinity of curbs shall be positioned so that the face of curb is located directly below or behind the face of the block. Rail placed over curbs shall be installed so that the post bolt is located approximately 21 inches above the gutter pan or roadway surface.
- If solid rock is encountered within 0 to 18" of the finished grade, drill a 22" dia. hole, 24" into the rock, or drill two 12" dia. front to back overlapping holes, 24" into the rock. If solid rock is encountered below 18", drill a 12" dia. hole, 12" into the rock or to the standard embedment depth, whichever is less. Any excess post length, after meeting these depths, may be field cut to ensure proper guardrail mounting height. Backfill with a cohesionless material.
- Guardrail posts shall not be set in concrete, of any depth.
- Special rail fabrication will be required at installations having a curvature of less than 150 ft. radius. The required radius shall be shown on the plans.
- The terminal anchor section (TAS) post shall be set in Class A concrete (unless otherwise shown in the plans) in accordance with Item 421, "Hydraulic Cement Concrete." Concrete shall be subsidiary to the bid item requiring construction of the terminal anchor section (TAS). Terminal anchor post to be galvanized in accordance with Item 445, "Galvanizing."
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.

(CRT) POST DETAIL CONTROLLED RELEASE TERMINAL POST

Two or more wood CRT post(s) are required at any radius installation located at intersecting roadways or driveways.

"DRIVEWAY" TERMINAL ANCHOR SECTION




Only for use within driveway locations, where a standard (TAS) Terminal Anchor Section can not be installed.



GENERAL NOTES

- The "Driveway" Terminal Anchor Section is ONLY to be used within driveway locations, where the ROW is limited and a standard 25 ft. (TAS) Terminal Anchor Section, is too long.
- Terminal anchor post shall be set in Class A concrete.
- All steel shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."




PLATE WASHER FOR METAL BEAM
(Galvanized after fabrication)



ONLY FOR USE IN MAINTENANCE REPAIRS OR HIGHLY CONSTRAINED SITE CONDITIONS.






| | | | | | |
|---|-----------|---------|-----------|--------------------------|--|
| | | | | Design Division Standard | |
| METAL BEAM GUARD FENCE (SHORT RADIUS) MBGF (SR) - 19 | | | | | |
| FILE: mbgfsr19.dgn | DN: TxDOT | CR: KM | DN: BD | CR: VP | |
| © TxDOT NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 | |
| | DIST | COUNTY | SHEET NO. | | |
| | DALLAS | KAUFMAN | 52 | | |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



GENERAL NOTES

- Concrete curb may be cast-in-place or precast as shown on this sheet. When used in conjunction with thrie-beam guard fence transitions, curb shall be Type II (Typically 5 3/4" height above surface; See CCCC standard sheet) unless otherwise shown in the plans. If other curb heights are shown in the plans in conjunction with the transition, the curb height may be from 4" to 8" with a relatively vertical face. Concrete curb shall be continuous to the seventh post.
- Contact the Design Division for drainage cut options needed within the curb section of the transition.
- The type of post (round wood, rectangular wood or steel) will be shown elsewhere in the plans.
- The post length shall be marked on all 7'-0" long posts by the Manufacturer. The mark shall be located within the top 1 ft. region of the post, at least 3/8" in height, and visible after installation. Wooden posts shall be marked with a brand, and steel posts with a stencil before galvanizing.
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans. The thrie-beam terminal connector and the thrie-beam transition to w-beam shall be of the same material, but shall not be less than 10 gauge.
- Contractor shall verify that the locations of bolt holes match those in the thrie-beam terminal connector prior to ordering materials.
- Unless otherwise shown in the plans, transitions shall be placed with the block face in front of or directly above the curb face.
- Install terminal connector with (12) rectangular guardrail plate washers (FWR03) and (12) 3/8" x 2" button head splice bolts with recessed nuts.
- Button head "post bolts & nuts" shall meet the requirements of (ASTM A307), and shall be of sufficient length to extend through the full thickness of the nut and 3/8" washer (FWC16a) and not more than 1" beyond it. Trim remaining bolt length to meet required length.
- Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing". Fittings shall be subsidiary to the bid item.
- Crown shall be widened to accommodate transitions.
- If solid rock is encountered. See the MBGF standard sheet for the proper installation guidance.
- Posts shall not be set in concrete.
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT, maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.



TYPE II CURB
Cast-in-Place or Precast

PRECAST CURB: Type II Precast Curb secured with 4-#5 Gr.60 Galv. Rebar stakes 18" long. The 12'-2" section of curb may be cast in two sections.
Section ① 5'-8" long
Section ② 6'-6" long with the last 3'-6" of curb tapered to a 4" height.
The Joint Connection is two 9" long 1" dia female ends connected with 1-#5 Gr.60 Galv. Rebar 18" long.

NOTES:
(5) 3/8" dia. heavy hex bolts, length will vary depending on width of concrete rail, leave 1" of bolt length past the 3/8" hex nut. Trim as required.
See General Notes: 6 & 7 for additional connection details.

BRIDGE APPROACH - UPSTREAM: THE NESTED RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.
BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.

ONLY FOR USE IN MAINTENANCE REPAIRS.

Texas Department of Transportation
Design Division Standard


METAL BEAM GUARD FENCE TRANSITION (THRIE-BEAM TRANSITION) MBGF (TR) - 19

| | | | | |
|-----------------------|------------|--------|-----------|--------|
| FILE: mbgfr19.dgn | DN: TxDOT | CR: KM | DR: BD | CR: VP |
| © TxDOT NOVEMBER 2019 | CONT: SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| DIST | COUNTY | | SHEET NO. | |
| DALLAS | KAUFMAN | | 53 | |


DATE: FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE:
FILE:




TYPICAL PLAN VIEW




TYPICAL ELEVATION VIEW

- GENERAL NOTES**
1. The type of post (round wood post, rectangular wood post, or steel post) will be shown elsewhere in the plans. The exact position of transitions shall be shown elsewhere in the plans or as directed by the Engineer.
 2. Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans.
 3. Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the nut and Type A 1 3/4" O.D. washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 3/8" x 2" (at triple rail splices) with 3/8" double recessed nuts (ASTM A563).
 4. Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item requiring construction of the transition.
 5. Crown will be widened to accommodate transitions.
 6. If solid rock is encountered. See the MBSF standard sheet for the proper installation guidance.
 7. Posts shall not be set in concrete.
 8. Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT, maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.
 9. Refer to MBSF standard sheet for additional details.




TERMINAL CONNECTOR

FOR USE WITH MBSF CONNECTIONS TO CONCRETE BRIDGE RAILS AND TRAFFIC BARRIERS



SECTION A-A



WOOD BLOCK TO RECTANGULAR WOOD POST

WOOD BLOCK TO STEEL POST

WOOD BLOCK TO ROUND WOOD POST

ONLY FOR USE IN MAINTENANCE REPAIRS.




METAL BEAM GUARD FENCE TRANSITION (TL2)
(Low Speed Transition)
MBSF (TL2) - 19


| | | | | |
|-----------------------|-----------|--------|-----------|---------|
| FILE: mbsft1219.dgn | DN: TxDOT | CR: KM | DN: BD | CR: VP |
| © TxDOT NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| DIST | COUNTY | | SHEET NO. | |
| DALLAS | KAUFMAN | | 54 | |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE:
FILE:




TYPICAL PLAN VIEW




TYPICAL ELEVATION VIEW

GENERAL NOTES


1. The type of post (round wood post, rectangular wood post, or steel post) will be shown elsewhere in the plans. The exact position of transitions shall be shown elsewhere in the plans or as directed by the Engineer.
2. Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans.
3. Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the nut (ASTM A563) and the Type A 1 3/4" O.D. washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 5/8" x 2" (at triple rail splices) with a 5/8" double recessed nuts (ASTM A563).
4. Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item requiring construction of the transition.
5. Crown will be widened to accommodate transitions.
6. If solid rock is encountered. See the MBGF standard sheet for proper installation guidance.
7. Posts shall not be set in concrete.
8. Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT, maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.
8. Refer to MBGF Standard Sheet for additional details.




SECTION A-A



WOOD BLOCK TO ROUND WOOD POST



WOOD BLOCK TO RECTANGULAR WOOD POST




WOOD BLOCK TO STEEL POST

ONLY FOR USE IN MAINTENANCE REPAIRS.

| | | | |
|---|-----------|--------------------------|---------|
| | | Design Division Standard | |
| METAL BEAM GUARD FENCE TRANSITION (T101) (T101 BRIDGE RAIL) MBGF (T101) - 19 | | | |
| FILE: mbgft10119.dgn | DN: TxDOT | CR: KM | DR: BD |
| © TxDOT NOVEMBER 2019 | CONT SECT | JOB | HIGHWAY |
| REVISIONS | 6373 81 | 001 | 1H0020 |
| DIST | COUNTY | SHEET NO. | |
| DALLAS | KAUFMAN | 55 | |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: FILE:



Note: See SGT standard sheets for proper installation and length of need requirements.

GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip (See GF(31) standard sheet for proper installation)


GENERAL NOTES

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leave-out behind the post shall be a minimum of 7".
4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Thickness of the mow strip will be 4".
7. The limits of payment for reinforced concrete will include leave-outs for the posts.
8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type I or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




SECTION A-A

Typical




MOW STRIP DETAIL

Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)

Curb shown on top of mow strip



CURB OPTION (3)




Texas Department of Transportation
 Design Division Standard

METAL BEAM GUARD FENCE (MOW STRIP)
TL-3 MASH COMPLIANT
GF(31)MS-19

| | | | | |
|------------------------|-----------|---------|-----------|------------|
| FILE: gf31ms19.dgn | DN: TxDOT | CK: KM | DW: VP | CK: CGL/AG |
| © TxDOT: NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | 1H0020 |
| | DIST | COUNTY | SHEET NO. | |
| | DALLAS | KAUFMAN | 56 | |



DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE:
FILE:



GENERAL NOTES

1. For more detail: See MBGF, SGT, and MBGF Transition standard sheets.
2. Quantities of metal beam guard fence (MBGF) at individual bridge ends are shown elsewhere in plans.
3. Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
4. MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
5. Terminal anchor sections (TAS) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
6. Direct connection of MBGF (at 6'-3" post spacing without transition) to concrete rail are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (See Detail A)
7. The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
8. For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge locations shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge.
9. Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.




All rail elements shall be lapped in the direction of adjacent traffic.

ONLY FOR USE IN MAINTENANCE REPAIRS.


| | | | |
|--|------------|--------------------------|-----------------|
| | | Design Division Standard | |
| BRIDGE END DETAILS (28" METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS) BED (28) - 19 | | | |
| FILE: bed2819.dgn | DN: TxDOT | CR: KM | OW: BD |
| © TxDOT NOVEMBER 2019 | CONT: SECT | JOB: 001 | HIGHWAY: 190020 |
| REVISIONS | | DIST: DALLAS | COUNTY: KAUFMAN |
| | | SHEET NO. 57 | |

DISCLAIMER: The use of this standard is covered by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




- ① Showing TL-3 Splice location, TL-2 Splice location is 1'-0".
- ② Metal Beam Guard Fence Transitions must be attached to the bridge rail and extended along the embankment unless otherwise shown in the plans.
- ③ Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence".
- ④ Wingwall Length minus 5'-0" (Varies)
- ⑤ Bolts shall be sufficient length to extend 1/2" to 3/4" beyond nut.
- ⑥ Increase 2" for structures with overlay.
- ⑦ 4 additional Bars R1#4 3'-8" in length shall be placed inside Bars S1#31 and centered 2'-0" from end of rail when Terminal Connections are required. Field bend as needed.
- ⑧ Bolt recesses are only required when pedestrians sidewalks are adjacent to back of rail.


ROADWAY ELEVATION OF RAIL



④ 4 - 1" Dia holes and 2 1/2" Dia x 2" deep recesses. Holes and recesses must be formed or cored. Percussion drilling is not permitted. Adjust placement of reinforcing steel as necessary to avoid bolt holes and recesses. ⑧



ISOMETRIC VIEW AT END OF BRIDGE RAIL



④ 5 - 1" Dia holes and 2 1/2" Dia x 2" deep recesses. Holes and recesses must be formed or cored. Percussion drilling is not permitted. Adjust placement of reinforcing steel as necessary to avoid bolt holes and recesses. ⑧

SHEET 1 OF 2



Texas Department of Transportation
Bridge Division

TRAFFIC RAIL

TYPE T203

| | | | | |
|------------------------|------------|-----------|---------|------------|
| FILE: g731tr1319.dgn | DN: TxDOT | CR: KM | DM: KM | CR: CGL/AG |
| © TxDOT: NOVEMBER 2019 | CONT: SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | IH0020 |
| DIST | COUNTY | SHEET NO. | | |
| DAL | KAUFMAN | 58 | | |

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




ELEVATION AT ABUTMENT WINGWALL




If two or more SP bars are used in a continuous panel length, they shall be butted within the center 3 ft of a rail post. At Contractor's option, Bars S spaced at 6\"/>

BARS SP (0.207\"/>

SECTIONS THRU RAIL




- ④ Wingwall Length minus 5'-0\"/>
- ⑥ Increase 2\"/>
- ⑦ 4 additional Bars R1(=4) 3'-8\"/>
- ⑧ 3 1/2\"/>
- ⑨ 3 1/2\"/>
- ⑩ Top longitudinal slab bar may be adjusted laterally 3\"/>
- ⑪ 1 1/2\" x 3/4\" or 3/4\" x 3/4\" Chamfer (1 typ at all openings)
- ⑫ Length shown for 6 1/2\"/>
- ⑬ Wing-wall Length minus 4'-10 1/2\"/>
- ⑭ Bars U can be rotated slightly to maintain cover requirements shown.



GENERAL NOTES:

This rail has been successfully evaluated by full-scale crash test to meet NCHRP Report 350 TL-3 criteria. This rail can be used for design speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for design speeds of 45 mph and less.
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
 All steel components, except reinforcing, shall be galvanized unless otherwise shown on plans.
 All concrete shall be Class "C". Chamfer all exposed corners. Epoxy coat Bars V and U if slab bars are epoxy coated. All reinforcing shall be Grade 60 except spirals.
 Face of rail and parapet shall be vertical transversely unless otherwise shown in the plans or approved by the Engineer. Openings shall have end faces perpendicular to adjacent roadway grade. Water barriers shall be provided at openings draining onto undercrossing roadways and sidewalks. They may be cast-in-place or precast in convenient lengths and bonded to the bridge deck with an approved epoxy cement.
 Shop drawings will not be required for this rail. Average weight of railing with no overlay is 250 pcf.



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT

Texas Department of Transportation
 Bridge Division



TRAFFIC RAIL

TYPE T203




| | | | | |
|-----------------------|----------|-------|-----------|-----------|
| FILE: qf31rft1319.dgn | DW:TXDOT | CR:KM | DW:KM | CR:GCL/AG |
| © 2001 NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | IH0020 |
| DIST | COUNTY | | SHEET NO. | |
| DAL | KAUFMAN | | 59 | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



DATE:
 TIME:
 FILE:
 DOCUMENT NAME:



- 1 Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- 2 Back of rail offset may, with Engineer's approval, be continued to the end of the railing.
- 3 Exp Joint or Splice Joint as required.
- 4 One shop splice per HSS rail section is permitted with minimum 85 percent penetration. The weld may be square groove, or single vee groove. Grind smooth.
- 5 Increase 2" for structures with overlay.
- 6 Place 4 additional Bars R(#4) 3'-8" in length inside Bars S(#4) and centered 2'-0" from end of rail when Terminal Connections are required. Field bend as needed.
- 7 HSS 2.875 x 0.203
- 8 HSS 2.375 x 0.154
- 9 3/8" Dia Hole in bottom of HSS rail (Minimum 1 hole between posts ~ Typ)



Note that at least two anchor points (as shown) are required for the Bridge Rail on the Abutment Wingwall. Longer Wingwalls may require more than two Rail anchorages.



POST BASE PLATE PLAN RAIL TURNDOWN BASE PLATE PLAN

HSS RAIL DETAILS

SHEET 1 OF 3

Texas Department of Transportation **Bridge Division Standard**


COMBINATION RAIL

TYPE C221


| | | | | |
|----------------------|-----------------|---------------|----------|-----------------|
| FILE: r1st018-19.dgn | DN: TxDOT | CK: TxDOT | DW: JTR | CK: JMH |
| REVISIONS | CONT: 6373 | SECT: 81 | JOB: 001 | HIGHWAY: 1H0020 |
| DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO.: 60 | | |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS




ON BRIDGE SLAB


SECTIONS THRU RAIL WITHOUT RAISED SIDEWALK



SECTION THRU OPTIONAL SIDE SLOT DRAIN




ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS



ON BRIDGE SLAB

SECTIONS THRU RAIL WITH RAISED SIDEWALK



OPTIONAL SIDE SLOT DRAIN DETAIL


Note: Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. Drains should not be placed over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.

- ⑤ Increase 2" for structures with overlay.
- ⑩ 5 #4" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑪ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars must be furnished at the Contractors expense.
- ⑫ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑬ Raised Sidewalk
- ⑭ Space U(#4) bars at 4" Max when end region of panel length is less than 6'-0" to side slot drain. Space U(#4) bars at 6" Max when end region of panel length is 6'-0" and greater to side slot drain.


| | | | |
|---------------------------|--------------|---------------------------------|---------------|
| | | Bridge Division Standard | |
| <h2>COMBINATION RAIL</h2> | | | |
| <h3>TYPE C221</h3> | | | |
| FILE: r1std018-19.dgn | DN: TxDOT | CK: TxDOT | DW: JTR |
| ©TxDOT September 2019 | CONT: 6373 | SECT: 81 | JOB: 001 |
| REVISIONS | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO.: 61 |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

| RAIL DATA FOR HORIZONTAL CURVES | | | |
|---------------------------------|------------------------|------------------|---------------------------------------|
| | RADIUS TO FACE OF RAIL | MAX CHORD LENGTH | CONSTRUCT OR FABRICATE |
| HSS Rail | Over 2800' | 29'-0" | Straight rail panels |
| | Over 1400' thru 2800' | 14'-6" | To required radius or to chords shown |
| | Over 700' thru 1400' | 7'-3" | To required radius |
| | Thru 700' | Zero | To required radius |





PIPE SPLICE DETAILS



| DESCRIPTION | LONGITUDINAL WIRES | VERTICAL WIRES |
|--------------------------------------|--------------------------------|---|
| Minimum (Cumulative Total) Wire Area | 1.067 Sq In. | 0.267 Sq In. per Ft |
| Minimum Maximum | No. of Wires 8 10 | Spacing 4" 8" |
| | Maximum Wire Size Differential | The smaller wire must have an area of 40% or more of the larger wire. |


CONSTRUCTION NOTES:

MATERIAL NOTES:



GENERAL NOTES:

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.



PLAN OF RAIL AT EXPANSION JOINTS


Example showing Slab Expansion Joints without breakbacks.

- ⑤ Increase 2" for structures with overlay.
- ⑦ HSS 2.875 x 0.203
- ⑧ HSS 2.375 x 0.154
- ⑮ No longitudinal wires may be in top center of cage.
- ⑯ Bend or cut as required to clear drain slots.
- ⑰ For raised sidewalks, add sidewalk height to total bar height. Use sidewalk height at rail's location.
- ⑱ See "Material Notes" for anchor bolt information.

SHEET 3 OF 3

| | | | |
|---------------------------|--------------|--------------------------|---------------|
| | | Bridge Division Standard | |
| <h1>COMBINATION RAIL</h1> | | | |
| <h2>TYPE C221</h2> | | | |
| FILE: r1std018-19.dgn | DN: TxDOT | CK: TxDOT | DW: JTR |
| ©TxDOT September 2019 | CONT: 6373 | SECT: 81 | JOB: 001 |
| REVISIONS | DIST: DALLAS | COUNTY: KAUFMAN | SHEET NO.: 62 |

DATE: FILE:




AT ABUTMENT BENTS
Showing TL-3 Transition

AT SLAB EXP JOINTS

AT INTERMEDIATE WALL JOINTS


ROADWAY ELEVATION OF RAIL



INTERMEDIATE WALL JOINT DETAIL


Note: Provide intermediate wall joints over all slab construction joints, over interior supports on continuous units, and at equal intervals in between as necessary to maintain a 33' maximum length of unbroken wall.

4 - 3/4" Dia A325 Hex Head Bolts with two 1 3/4" O.D. washers. Place washer under each head and nut. The 4 Terminal Connection Bolts shall be tightened in a well distributed pattern so to prevent damage or distortion of the W-Beam Connection and the MBSF Transition. Bolts shall be cut off after installation so as to extend no more than 3/4" beyond nut. End of cut-off bolt shall be painted with Zinc-rich paint.




SECTION
ELEVATION
TL-2 TERMINAL CONNECTION DETAILS

5 - 1" Dia A325 Hex Head Bolts with two 1 3/4" O.D. washers. Place washer under each head and nut. The 5 Terminal Connection Bolts shall be tightened in a well distributed pattern so to prevent damage or distortion of the Inrie-Beam Connection and the MBSF Transition. Bolts shall be cut off after installation so as to extend no more than 3/4" beyond nut. End of cut-off bolt shall be painted with Zinc-rich paint.



SECTION
ELEVATION
TL-3 TERMINAL CONNECTION DETAILS



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT

- 1 Metal Beam Guard Fence Transitions must be attached to the bridge rail and extended along the embankment unless otherwise shown in the plans.
- 2 Sawing TL-3 Splice location, TL-2 Splice location is 1'-0".
- 3 Terminal Connectors and associated hardware are to be paid for under the item "Metal Beam Guard Fence".
- 4 Increase 2" for structures with Overlay.
- 5 4 additional Bars R (#4) 3'-8" in length shall be placed inside Bars S (#5) and centered 2'-0" from end of rail when Terminal Connections are required.
- 6 Back of rail offset may, with Engineer's approval be continued to the end of the railing.
- 7 Bolt recesses are only required when pedestrian sidewalks are adjacent to back of rail.

TRAFFIC RAIL


TYPE T501

| | | | | |
|----------------------|----------|---------|-----------|-----------|
| FILE: g31trt1319.dgn | DM:TXDOT | CR:KM | DR:KM | CR:CGL/AG |
| © 2001 NOVEMBER 2019 | CONT | SECT | JOB | HIGHWAY |
| REVISIONS | 6373 | 81 | 001 | IH0020 |
| | DIST | COUNTY | SHEET NO. | |
| | DAL | KAUFMAN | 63 | |

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any particular use, however, TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




LEVELS: BIPALOID
ACCT

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. The accuracy of any kind is made by TxDOT for any purpose other than for the conversion of this standard. TxDOT assumes no responsibility for the conversion of this standard, other formats or for incorrect results or damages resulting from its use.




- ④ Increase 2" for structures with Overlay.
- ⑤ 1/2" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑥ As an aid in supporting reinforcement, additional longitudinal bars may be used in the slab with the approval of the Engineer. Such bars shall be furnished at the Contractor's expense.
- ⑦ Top longitudinal slab bar may be adjusted laterally 3" to tie reinforcing.
- ⑧ Bend or cut as required to clear drain slots.
- ⑨ No longitudinal wires may be within upper band.

GENERAL NOTES:
 This rail has been evaluated and approved to be of equal strength to railings with like geometry, which have been crash tested to meet NCHRP Report 350 TL-4 criteria. This rail can be used for design speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for design speeds of 45 mph and less.
 Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
 All steel components except reinforcing shall be galvanized unless otherwise shown on plans.
 All concrete shall be Class "C".
 All reinforcing steel shall be Grade 60.
 Shop drawings will not be required for this rail.
 This railing may be constructed with slip-forms when approved by the Engineer, with equipment approved by the Engineer. Sensor control for both line and grade must be provided. Tack welding to provide bracing for slip-form operations is acceptable. Welding can be performed at a minimum spacing of 3 ft between the cage and the anchorage. It is permissible to weld to U, WU and S bars at any location on the cage. If increased bracing is needed, additional anchorage devices must be added and welding must be performed in the upper two thirds of the cage.
 The back of railing shall be vertical unless otherwise shown on the plans or approved by the Engineer.
 Deformed welded wire reinforcement (WWR) may be used as an option to conventional reinforcing and shall be made in accordance with ASTM A497 (Deformed Wire). Configurations of Reinforcing Steel and WWR or configurations of WWR other than shown will be permitted when the conditions in the table are satisfied and the dimension from end of section to first welded vertical wire does not exceed 3'.
 Epoxy coat bars U and WU if slab bars are epoxy coated. Average weight of railing with no overlay is 325 pcf.



OPTIONAL SIDE SLOT DRAIN DETAIL
 Note: Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. If continuous slots at 8 ft c-c are required, then details as on standard Type T502 should apply. Drains should not be placed over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.



SECTION THRU OPTIONAL SIDE SLOT DRAIN


| DESCRIPTION | LONGITUDINAL WIRES | VERTICAL WIRES |
|--------------------------------------|--|---------------------|
| Minimum (Cumulative Total) Wire Area | 0.933 Sq In. | 0.248 Sq In. per Ft |
| Minimum | No. of Wires | Spacing |
| Maximum | 6 | 4" |
| Maximum Wire Size Differential | 11 | 12" |
| | The smaller wire shall have an area of 40% or more of the larger wire. | |

Texas Department of Transportation
 Bridge Division


TRAFFIC RAIL

TYPE T501



| | | | | |
|-----------------------|-----------|-----------|---------|-----------|
| FILE: of31trt1319.dgn | DW:TDOT | CR:KM | DW:KM | CR:CGL/AG |
| ©TDOT NOVEMBER 2019 | CONF SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 81 | 001 | IH0020 | |
| DIST | COUNTY | SHEET NO. | | |
| DAL | KAUFMAN | 64 | | |



METAL BEAM GUARD FENCE (BARRIER) & CONTROL-OF-ACCESS HEADLIGHT-BARRIER FENCE







TREATMENT AT MEDIAN OBSTRUCTIONS



NOTE: ON NEW STRUCTURES OR STRUCTURES TO BE WIDENED LOCATE OPEN JOINTS OFF 1/4 OF ROADWAY. ON EXISTING STRUCTURES WHERE OPEN JOINT IS ON 1/4 OF STRUCTURE LOCATE BARRIER'S OFF CENTER WITH 2" REVERSE CURVE TRANSITION OFF END OF STRUCTURE.

NOTE: Provide 4 additional shop or field drilled holes in end of guard fence for attachment to terminal anchor post. Rail members may be bolted to angle of terminal anchor and the two assemblies positioned to greater alignment prior to placing concrete around 8" x 17" posts.



Permissible square punching guide hole 5/8" max.

GENERAL NOTES

- BOLTS USED IN ATTACHING THE LINE AND PULL POSTS OF THE CONTROL-OF-ACCESS HEADLIGHT BARRIER FENCE TO THE METAL BEAM GUARD FENCE SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT BUT NOT MORE THAN THE DIAMETER OF THE BOLT BEYOND IT.
- SECTIONS OF RAIL MEMBERS OF COMPARABLE STRENGTH MAY BE SUBSTITUTED IF APPROVED BY THE ENGINEER.
- AT THE OPTION OF THE CONTRACTOR, THE RAIL ELEMENT FOR THE GUARD FENCE MAY BE FURNISHED IN 25 FOOT LENGTHS, WITH POST BOLT SLOTS FOR 5/8" DIAMETER BOLT ANCHORAGE TO INTERMEDIATE POSTS.
- ALL STEEL FITTINGS SHALL BE GALVANIZED.
- A 5/8" PEDESTRIAN CONTROL CABLE SHALL BE PLACED THROUGH THE POSTS AS INDICATED UNLESS OTHERWISE SPECIFIED.
- THE TYPE OF END TREATMENT SHOWN SHALL BE USED UNLESS OTHERWISE SHOWN ON THE PLANS.
- FOR CONTROL-OF-ACCESS HEADLIGHT BARRIER FENCE DETAILS, SEE STANDARD.
- ALL ANCHORAGE PROVISIONS INCLUDING BOLTS, NUTS AND WASHERS ARE CONSIDERED AS PARTS OF THE RAIL FOR PAYMENT.
- METAL BEAM GUARD FENCE SHOULD MAINTAIN CONTINUITY OF STRENGTH AT ALL TIMES. NO SPECIAL PROVISIONS FOR EXPANSION AT OR NEAR STRUCTURES OR AT ANY OTHER LOCATION ARE NEEDED DUE TO THE ABILITY OF THE RAIL TO DISTRIBUTE SUCH MOVEMENT OVER CONSIDERABLE LENGTH OF RAIL.
- APPROACH POSTS SHALL BE SET VERTICAL. BRIDGE POSTS SHALL BE SET PERPENDICULAR TO PROFILE GRADE AND CROSS SLOPE OF DECK.
- BRIDGE POSTS SHALL BE SEATED ON ELASTOMETRIC PADS 7" x 11" x 1/16". ADDITIONAL PADS OR HALF PADS MAY BE USED IN SHIMMING FOR ALIGNMENT. POST HEIGHT SHOWN WILL INCREASE BY THE THICKNESS OF THE PAD.
- FOR RAILS ON HORIZONTAL CURVES, FABRICATE OR FURNISH AS FOLLOWS: THRU 150' RADIUS - FABRICATE TO THE REQUIRED RADIUS. OVER 150' RADIUS - FURNISH IN STRAIGHT SECTIONS.

TEXAS HIGHWAY DEPARTMENT
GALV. STL. BEAM GD. FENCE (BAR.) (BLOCKOUT)

MBGF (B-71) (MOD)

| | | | | |
|------------------------|------------|---------|-----------|------------|
| FILE: qf31frt1319.dgn | DW: TXDOT | CR: KM | DW: KM | CR: CGL/AG |
| © TXDOT: NOVEMBER 2019 | CONT: SECT | JOB | HIGHWAY | |
| REVISIONS | 6373 | 81 | 001 | IH0020 |
| | DIST | COUNTY | SHEET NO. | |
| | DAL | KAUFMAN | 65 | |