

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED

STATE HIGHWAY IMPROVEMENT

PROJECT: TMC 6359-011-001

COUNTY: GARZA

HIGHWAY: US-84

CALLOUT CONTRACT

FOR THE PURCHASE OF MATERIALS ONLY, DELINEATOR AND OBJECT MARKER ASSEMBLIES

Index of Sheets:

- 2A General Notes
- 2B Plan Notes
- 3 Estimate & Quantity Sheet

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

RECOMMENDED FOR LETTING:


APPROVED FOR LETTING:

DocuSigned by:
Joseph Hunt
F13D8742DB21426...

Traffic Management Section Director

DocuSigned by:
Michael A. Chacon, P.E.
06D7FD8C5CEC46B

Director, Traffic Safety Division



TEXAS DEPARTMENT OF TRANSPORTATION
Traffic Safety Division

© 2021 TxDOT
All rights reserved.

STATE DISTRICT	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Garza	6359	11	001	1

GENERAL NOTES:

General:

Following work authorization Notice-to-Proceed (NTP) date; contract is valid for no longer than 365 calendar days.

Contractor questions on this project are to be emailed to the following individual:

Daryl Starkes – Materials Management Section Director

Daryl.Starkes@txdot.gov

Contractor questions will only be accepted through email to the above individuals. All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT’s Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Questions regarding the plans and/or the project after the contract has been awarded should be referred to the Managing Engineer:

Mr. Joseph Hunt
 Traffic Management Section Director
 9500 N. Lake Creek Parkway
 Austin, TX 78717
 (512) 506-5115

This project consists of supplying materials at locations as specified in the plans.

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any or all contracts.

Prior to beginning operations, the Department will arrange a preconstruction conference between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the contract, proposed procedures and the plans for performing the work while always providing for safe passage of traffic. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 9.2 “Plans Quantity Measurement,” plans quantity measurement requirements are not applicable for this contract.

Department-approved safety hats and safety vests will be worn by all workers and visitors when:

Workers are outside of vehicles at all outdoor worksites. This includes those who occasionally visit worksites either on the highway surface or right-of-way.

Working in areas where there is a danger of head injury from impact, from falling or flying objects, or from electrical shock or burns.

Non-compliance with this requirement will be grounds for suspension of work.

All work on this contract will be scheduled and directed by the Regional Distribution Managers as listed below:

Regional Distribution Center	Regional Distribution Manager	Telephone Number	Address
Post	Lane Jones	806-495-3531	TXDOT - Post RDC 709 South Broadway Post, Texas 79356

Item 2: Instructions to Bidders

This project includes plan sheets that are not part of the bid proposal. Views plans on-line or download from the web at: <https://www.txdot.gov/business/letting-bids/plans-online.html>.

Order plans from any of the plan reproduction companies shown on the web at: http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm.

Item 3: Award and Execution of Contract

Time requirements will be stated within each work order. Contractor will be given no less than 14 calendar days to successfully complete each work order.

Materials will be delivered to the specified locations upon request. Contractors will be given no more than 45 calendar days for delivery.

Written notification of delivery shall be given by contractor at least 14 business days prior to delivery.

Deliveries will only be accepted between the hours of 8AM – 4PM at the specified locations.

TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division						
© 2021 TxDOT						
State District	STATE	STATE PROJECT NO.			HIGHWAY	
Lubbock	TX	TMC 6359-11-001			US-84	
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET	
1	Henderson	6359	11	001	2A	

Item 8: Prosecution and Progress

Time charges will be in accordance with Article 8.3.1.5 "Calendar Day".

In accordance with Article 8.6 "Failure to Complete Work on Time," liquidated damages will be charged for failure to complete each Work Order in the specified number of days. The amount assessed per day for liquidated damages will be 5% of the estimated cost of the Work Order, but not to be less than \$250 per day and not to exceed \$1000 per day.

Unless otherwise directed, prosecute the work continuously to completion of the contract.

Item 9: Measurement & Payment

In accordance with Article 9.1, "Measurement of Quantities," Provide all measurements required for pay a minimum of 2 days before the equipment is used.

Contractor is responsible for obtaining annual overweight tolerance permit if hauling material which exceeds the legal road weight.

Item 8022: Delineator and Object Marker Assemblies

Materials will be delivered upon request to the Regional Distribution Center listed below. Contact Supervisors listed to arrange for delivery.


Regional Distribution Center	Regional Distribution Manager	Telephone Number	Address
Post	Lane Jones	806-495-3531	TXDOT - Post RDC 709 South Broadway Post, Texas 79356

Delivery is subsidiary to the Item, "Delineator and Object Marker Assemblies."

On date of delivery, before unloading materials, obtain approval from the Regional Distribution Manager, or designee, where to place materials.

Replace materials that become damaged during delivery at no expense to the Department.

Packaging requirements and minimum order quantities shown in the following tables must be followed. Where there are no minimum quantity requirements, only minimum order amounts will be followed.

 TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	2A

Item No.	Bid No.	Description	UOM	Shipping QTY	Min Order
8022	6005	DELIN, REFL,TYPE C,BOLT ON, 2 WAY, (W)	EA	200/box	\$ 1,500.00
8022	6006	DELIN, REFL,TYPE C,BOLT ON, 1 WAY, (W)	EA	200/box	\$ 1,000.00
8022	6007	DELIN,REFL,TYPE C,BOLT ON,1 WAY,(Y FL)	EA	200/box	\$ 2,500.00
8022	6008	DELIN, REFL,TYPE C,GLUE ON, 1 WAY, (W)	EA	200/box	\$ -
8022	6009	DELIN, REFL,TYPE C,GLUE ON, 1 WAY, (Y)	EA	200/box	\$ -
8022	6010	DELIN, REFL,TYPE C,GLUE ON, 2 WAY, (W)	EA	200/box	\$ 1,500.00
8022	6011	DELIN, REFL, F/ METAL POST,1 WAY, (W)	EA	200/box	\$ -
8022	6012	BRKT TYPE C,F/MTL GDRAIL,1 WAY (Y FL)	EA	200/box	\$ -
8022	6013	DELIN, REFL, F/ CONC BAR,1 WAY, (W)	EA	100/box	\$ 1,500.00
8022	6014	DELIN, REFL, F/ CONC BAR,2 WAY, (W)	EA	100/box	\$ 2,000.00
8022	6015	DELIN, REFL, F/ CONC BAR,1 WAY, (Y)	EA	100/box	\$ 1,500.00
8022	6016	DELIN, REFL, F/ CONC BAR,2 WAY, (Y)	EA	100/box	\$ 1,200.00
8022	6017	DELIN, PLAS, 3",AMBER,ACRYLIC, CEN MTS	EA	200/box	\$ 400.00
8022	6018	DELIN, PLAS, 3",CLEAR,ACRYLIC, CEN MTS	EA	200/box	\$ 300.00
8022	6019	POST, DELIN,WFLX, 3.8"X27",NAIL ON	EA	25/box	\$ -
8022	6024	PST, DELIN, WFLX ,RECY,33"L,1 FLT END	EA	25/box	\$ -
8022	6025	POST, DELIN, WFLX, SURF, 36", OMNI DIR	EA	25/box	\$ -
8022	6026	POST, DELIN, WFLX, SURF, 48", OMNI DIR	EA	25/box	\$ -
8022	6027	POST,DELIN, WFLX, SURF, 48", REPL POST	EA	25/box	\$ -
8022	6031	POST,DELIN,WING CHAN,GALV, 6'6", 3/8"H	EA	25/box	\$ 10,000.00
8022	6039	PST, DELIN,YFLX ,RECY,33"L,1 FLT END	EA	25/box	\$ -
8022	6040	POST, DELIN, YFLX, SURF, 36", OMNI DIR	EA	25/box	\$ -
8022	6041	POST, DELIN, YFLX, SURF, 48", OMNI DIR	EA	25/box	\$ -
8022	6042	POST,DELIN, YFLX, SURF, 48", REPL POST	EA	25/box	\$ -
8022	6043	POST, DELIN,YFLX, 3.8"X27",NAIL ON	EA	25/box	\$ -

TEXAS DEPARTMENT OF TRANSPORTATION					
Traffic Safety Division					
© 2021 TxDOT					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	2A

PLAN NOTES FOR DELINEATORS AND OBJECT MARKERS 8022:

6005. DELINEATOR, REFLECTORIZED, TYPE C BRACKET, BOLT ON, 2 WAY, WHITE

DELIN, REFL, TYPE C, BOLT ON, 2 WAY, (W), Guardrail, Type D Prismatic, Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008317202 (For Internal Use Only)

6006. DELINEATOR, REFLECTORIZED, TYPE C BRACKET, BOLT ON, 1 WAY WHITE

DELIN, REFL, TYPE C, BOLT ON, 1 WAY, (W) Guardrail, Type D Prismatic, Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.

- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008317608 (For Internal Use Only)

6007. DELINEATOR, REFLECTORIZED, TYPE C, BOLT ON, 1 WAY, YELLOW

DELIN, REFL, TYPE C, BOLT ON, 1 WAY, (Y FL) Type E Florescent, Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____


Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008317616 (For Internal Use Only)

6008. DELINEATOR, REFLECTORIZED, TYPE C, GLUE ON, 1 WAY, WHITE

DELIN, REFL, TYPE C, GLUE ON, 1 WAY, (W) Guardrail, Type D Prismatic, Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material

 <p>TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT</p>					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	28

Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.

- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____
Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)
NIGP: 55008317806 (For Internal Use Only)

6009. DELINEATOR, REFLECTORIZED, TYPE C, GLUE ON, 1 WAY, YELLOW DELIN, REFL, TYPE C, GLUE ON, 1 WAY, (Y FL) Guardrail, Type E Florescent, Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____
Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)
NIGP: 55008317814 (For Internal Use Only)

6010. DELINEATOR, REFLECTORIZED, TYPE C, GLUE ON, 2 WAY, WHITE DELIN, REFL, TYPE C, GLUE ON, 2 WAY, (W) Guardrail, Type D Prismatic, Must comply with:


- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____
Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)
NIGP: 55008317822 (For Internal Use Only)

6011. DELINEATOR, REFLECTORIZED, F/ METAL POST, 1 WAY, WHITE DELIN, REFL, F/ METAL POST, 1 WAY, (W) Type D Prismatic, Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.

 <p>TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT</p>					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	28

- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008318200 (For Internal Use Only)

6012. TYPE C BRACKET, F/METAL GUARDRAIL POST, 1 WAY YELLOW, TYPE E
 TYPE C BRKT,F/MTL GDRAIL PST,1 WAY (Y FL) Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM, latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008318226 (For Internal Use Only)

6013. DELINEATOR, REFLECTORIZED, F/ CONCRETE BARRIER, 1 WAY, WHITE
 DELIN, REFL, F/ CONC BAR,1 WAY, (W) Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The

agency must give written authorization for this waiver.

- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008318507 (For Internal Use Only)

6014. DELINEATOR, REFLECTORIZED, F/CONCRETE BARRIER, 2 WAY, WHITE
 DELIN, REFL, F/ CONC BAR,2 WAY, (W) Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____


Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008318523 (For Internal Use Only)

6015. DELINEATOR, REFLECTORIZED, F/CONCRETE BARRIER, 1 WAY, YELLOW
 DELIN, REFL, F/ CONC BAR,1 WAY, (Y) Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material

 TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	28

- Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
 - 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
 - 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008318606 (For Internal Use Only)

6016. DELINEATOR, REFLECTORIZED, F/CONCRETE BARRIER, 2 WAY, YELLOW DELIN, REFL, F/ CONC BAR,2 WAY, (Y) Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____

Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55008318622 (For Internal Use Only)

6017. DELINEATOR, PLASTIC, 3", AMBER, ACRYLIC, CENTER MOUNTING DELIN, PLAS, 3".AMBER.ACRYLIC. CEN MTS Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

Make/Manufacturer: _____


Part/Product No.: _____

Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)

NIGP: 55034353106 (For Internal Use Only)

6018. DELINEATOR, PLASTIC, 3", CLEAR, ACRYLIC, CENTER MOUNTING DELIN, PLAS, 3",CLEAR.ACRYLIC. CEN MTS Must comply with:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-8600, latest revision and shall be listed on Material Producer List (MPL) for Type C Delineator Units, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(1), latest revision.
- 3) Preshipment sample: A preshipment sample of each item on this order will be required. If the sample meets specifications, it will be considered part of the order. Items that fail to meet specifications will be returned to the vendor at vendor's cost. Upon completion of inspection, written authorization will be made for shipment of balance of items. This preshipment sample may be waived at the discretion of the ordering agency. The agency must give written authorization for this waiver.
- 4) Testing: The goods and materials ordered will be tested upon receipt. Testing will take not more than 22 working days. Payment will be made within 30 days after tests have been completed and goods or materials are found to meet specifications or the day on which the correct invoice for goods or materials was received, whichever is later.

 TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	28

which the correct invoice for goods or materials was received, whichever is later.
 Make/Manufacturer: _____
 Part/Product No.: _____
 Please refer to the "Instructions" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov)
 NIGP: 55034353452 (For Internal Use Only)


- 6019. POST, DELINEATOR, FLEXIBLE, 3.8" X 27", NAIL ON, WHITE**
 POST, DELIN,FLEX, 3.8"X27",NAIL ON,(W) The above shall be manufactured in accordance with the following:
- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
 - 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.
- Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.
 NIGP: 55041570502 (For Internal Use Only)
- 6024. POST, DELINEATOR, WHITE, FLEXIBLE, 33" L W/1 FLAT END**
 PST, DELIN, WFLX, 33"L,W/1 FLAT END The above shall be manufactured in accordance with the following:
- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
 - 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.
- Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.
 NIGP: 55041661509 (For Internal Use Only)

- 6025. POST, DELINEATOR, WHITE, FLEXIBLE, SURFACE, 36", OMNI DIRECTIONAL**
 POST, DELIN, WFLX, SURF, 36", OMNI DIR The above shall be manufactured in accordance with the following:
- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
 - 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.
- Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.

NIGP: 55041671003 (For Internal Use Only)

- 6026. POST, DELINEATOR, WHITE, FLEXIBLE, SURFACE, 48", OMNI DIRECTIONAL**
 POST, DELIN, WFLX, SURF, 48", OMNI DIR The above shall be manufactured in accordance with the following:
- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
 - 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.
- Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.
 NIGP: 55041671607 (For Internal Use Only)
- 6027. POST, DELINEATOR, WHITE, FLEXIBLE, SURFACE, 48", REPLACEMENT POST**
 POST,DELIN, WFLX, SURF, 48", REPL POST The above shall be manufactured in accordance with the following:
- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
 - 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.
- Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.
 NIGP: 55041671623 (For Internal Use Only)

- 6031. 6'6" GALV WING CHANNEL DELINEATOR POST 3/8" HOLES**
 POST,DELIN,WING CHAN,GALV, 6'6", 3/8"H The above shall be manufactured in accordance with the following:
- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
 - 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.

 TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	28

Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.
NIGP: 57044325504 (For Internal Use Only)

6039. POST, DELINEATOR, YELLOW FLEXIBLE, 33" L W/1 FLAT END
PST, DELIN, YFLX , 33"L,W/1 FLAT END The above shall be manufactured in accordance with the following:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.

Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.

6040. POST, DELINEATOR, YELLOW, FLEXIBLE, SURFACE, 36", OMNI DIRECTIONAL
POST, DELIN, YFLX, SURF, 36", OMNI DIR The above shall be manufactured in accordance with the following:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.

Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.

6041. POST, DELINEATOR, YELLOW, FLEXIBLE, SURFACE, 48", OMNI DIRECTIONAL
POST, DELIN, YFLX, SURF, 48", OMNI DIR The above shall be manufactured in accordance with the following:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.

Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.

6042. POST, DELINEATOR, YELLOW, FLEXIBLE, SURFACE, 48", REPLACEMENT POST
POST,DELIN, YFLX, SURF, 48", REPL POST The above shall be manufactured in accordance with the following:


- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.

Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.

6043. POST, DELINEATOR, FLEXIBLE, 3.8" X 27", NAIL ON, YELLOW
POST, DELIN,FLEX, 3.8"X27",NAIL ON,(Y) The above shall be manufactured in accordance with the following:

- 1) The only delineators that may be bid shall meet TxDOT Departmental Material Specification DMS-4400 latest revision and shall be listed on Material Producer List (MPL) for Flexible Delineator and Object Marker Posts, latest revision.
- 2) Delineators shall also meet TxDOT Standard Plans Delineator & Object Marker Installation and Material Description D & OM(2), latest revision.

Please refer to the "Instructions TxDOT" tab included in this RFP on how to access specification documents through TxDOT website (www.txdot.gov) and product testing and payment requirements.

 TEXAS DEPARTMENT OF TRANSPORTATION Traffic Safety Division © 2021 TxDOT					
State District	STATE	STATE PROJECT NO.			HIGHWAY
Lubbock	TX	TMC 6359-11-001			US-84
REVISIONS	COUNTY	CONTROL	SECTION	JOB	SHEET
1	Henderson	6359	11	001	2B

Roadsign Assembly Estimate Sheet

ROADWAY	EST	FINAL	AL T	ITEM NO * ITEM CODE	DESC CODE	DESCRIPTION	UNIT	TOTAL	
								EST	FINAL
				8022	6005	DELIN, REFL, TYPE C, BOLT ON, 2 WAY, (W)	EA	3000	
				8022	6006	DELIN, REFL, TYPE C, BOLT ON, 1 WAY, (W)	EA	2400	
				8022	6007	DELIN, REFL, TYPE C, BOLT ON, 1 WAY, (Y FL)	EA	2400	
				8022	6008	DELIN, REFL, TYPE C, GLUE ON, 1 WAY, (W)	EA	2400	
				8022	6009	DELIN, REFL, TYPE C, GLUE ON, 1 WAY, (Y)	EA	2000	
				8022	6010	DELIN, REFL, TYPE C, GLUE ON, 2 WAY, (W)	EA	2000	
				8022	6011	DELIN, REFL, F/METAL POST, 1 WAY, (W)	EA	25	
				8022	6012	BRKT, TYPE C, F/MTL GDRAL, 1 WAY, (Y FL)	EA	25	
				8022	6013	DELIN, REFL, F/CONG BAR, 1 WAY, (W)	EA	4000	
				8022	6014	DELIN, REFL, F/CONG BAR, 2 WAY, (Y)	EA	3000	
				8022	6015	DELIN, REFL, F/CONG BAR, 1 WAY, (Y)	EA	1000	
				8022	6016	DELIN, REFL, F/CONG BAR, 2 WAY, (Y)	EA	4000	
				8022	6017	DELIN, PLAS, 3" AMBER, ACRYLIC, CEN MTS	EA	10000	
				8022	6018	DELIN, PLAS, 3" CLEAR, ACRYLIC, CEN MTS	EA	7500	
				8022	6019	POST, DELIN, FLEX, 3.8" X 27" NAIL ON, (W)	EA	1000	
				8022	6024	PST, DELIN, FL, RECY, 33" L, W/1 FLAT END	EA	100	
				8022	6025	POST, DELIN, FLEX, SURF, 36", OMNI DIR	EA	100	
				8022	6026	POST, DELIN, FLEX, SURF, 48", OMNI DIR	EA	100	
				8022	6027	POST, DELIN, FLEX, SURF, 48", REPL POST	EA	100	
				8022	6031	POST, DELIN, WING, CHAN, GALV, 66", 3/8"H	EA	5000	
				8022	6039	POST, DELIN, YFLX, 33" L, 1 FLT END	EA	100	
				8022	6040	POST, DELIN, YFLX, SURF, 36", OMNI DIR	EA	100	
				8022	6041	POST, DELIN, YFLX, SURF, 48", OMNI DIR	EA	100	
				8022	6042	POST, DELIN, YFLX, SURF, 48", REPL POST	EA	100	
				8022	6043	POST, DELIN, YFLX, 3.8" X 27" NAIL ON	EA	100	

ESTIMATE SHEET				STATE PROJECT NO.		HIGHWAY	
State District		Federal District		STATE			
Lubbock		NA		TX		TMC 6359-11-001	
REVISIONS		STATE		COUNTY		CONTROL	
1		TX		Garza		6359	
				SECTION		JOB	
				11		001	
				SHEET		3	