## STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

# PLANS OF PROPOSED MATERIALS MAINTENANCE CONTRACT


## MATERIALS ONLY

PROJECT NUMBER MMC 638370001

# BASTROP, ETC FM535, ETC

LIMITS: VARIOUS COUNTIES INCLUDING BASTROP, BLANCO, BURNET, CALDWELL, GILLESPIE, HAYS, LEE, LLANO, MASON, TRAVIS AND WILLIAMSON FOR THE DELIVERY OF SEAL COAT AGGREGATE

CONSISTING OF AGGREGATE



SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION ON NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT.




Jacob Wells

-03D704AB5F08458

\$FILE\$ \$DATE\$ FILE: DATE:

CO	CONT	SECT	ECT JOB		HIGHWAY	
63	383	70	001	FN	535,	ETC.
D	DIST	COUNTY		SHEE	T NO.	
Α	AUS	ΒA	STROP, E	TC.		1



	GENERAL
1	TITLE SHEET
2	INDEX OF SHEETS
3, 3A	GENERAL NOTES
4	ESTIMATE AND QUANTITY
5	LOCATION SUMMARY

POL

			in District nance Off	
Texa	.® Is Dep	parti	ment of Tra	nsportation
I N [	DEX	C	)F She	EETS
© 2019	CONT	SECT	JOB	HIGHWAY

 © 2019
 CONT
 SECT
 JOB
 HIGHWAY

 DS:
 CK:
 6383
 70
 001
 FM 535, E†c.

 DW:
 CK:
 DIST
 COUNTY
 SHEET NO.

 DW:
 CK:
 AUS
 BASTROP, E†c.
 2

### **GENERAL NOTES:**

#### **GENERAL**

Contractor questions on this project are to be addressed to the following individual(s):

Pre-Bid Contact List	
District Maintenance	Brenda.Guerra@tx

dot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address: https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Written notice will be given to begin work on this project.

Work must begin within seven (7) calendar days after such notification. Time charges will begin when work begins regardless if it falls within seven (7) calendar days of the notification to begin work.

The contractor will have "One hundred twenty" (120) calendar days to complete all work under this contract.

Work under this contract consists of "Seal Coat Aggregate Material Delivery" at various locations in "Bastrop, Blanco, Burnet, Caldwell, Gillespie, Hays, Lee, Llano, Mason, Travis, and Williamson Counties".

Prior to beginning operations, the Department will arrange a preconstruction conference between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the contract, proposed procedures and the plans for performing the work while providing for safe passage of traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

Each contract is considered separate and individual from others. Requirements to complete work on any or all contracts may occur at the same time. If requests are issued at the same time, it is expected that the work will be completed in the time frame allowed.

Sheet: 3 Control: 6383-70-001

Project Number: MMC 638370001 County: BASTROP, Etc. Highway: FM 535, Etc.

Material orders and delivery are expected to be fulfilled no later than 21 calendar days after request for material is made. Delivery of materials will be coordinated by the responsible Maintenance Supervisor:

Bastrop Blanco Burnet Caldwell Gillespie Hays Llano Mason Travis East & Central Travis North Travis South Williamson East Williamson West

Lee

Robert Wilson Scott D. Scott Mark Hoefelmer Michael Self Logan Ketron Jesse Serna Marcus Snowde James Low Cole Farmer **Greg Stephens** Anthony Reitan Ronald Switzer Jackie Volek John Taylor

### **ITEM 3 – AWARD AND EXECUTION OF CONTRACT**

A work order will be issued to the contractor for specific items and quantities to be delivered as well as days to complete the work order and expected delivery date.

This Contract includes non-site-specific work. Multiple work orders will be used to procure work of the type identified in the Contract at locations that have not yet been determined.

### **ITEM 6 - CONTROL OF MATERIALS**

Use materials from pre-qualified producers. A list of material producers pre-qualified by the Construction Division (CST) of the Texas Department of Transportation (TxDOT) can be found at the following website: https://www.txdot.gov/business/resources/producer-list.html

The Contractor is responsible for furnishing all materials included in this contract. Materials provided by Contractor will be new unless otherwise shown on the plans or approved. The Contractor must receive approval from the Engineer prior to ordering materials for this contract.

The Contractor is required to have sufficient supply of material to deliver within the allotted time.

Give a minimum of 1 business day notice for materials, which require inspection at the Plant.

Furnish uncontaminated materials of uniform quality that meet the requirements of the plans and specifications. Materials may be rejected if evidence of contamination is present. Additional sampling for acceptance may be required.

Delivery of material will not be accepted without scale certifications and tested/approved material received 48 hours prior to scheduled delivery.

#### Sheet: 3 Control: 6383-70-001

	512-359-6914	Robert.Wilson@txdot.gov
	830-868-7166	Scott.Scott@txdot.gov
eyer	512-756-2316	Mark.Hoefelmeyer@txdot.gov
	512-398-2412	Michael.Lynn.Self@txdot.gov
	830-997-4362	Logan.Ketron@txdot.gov
	512-353-1061	Jesse.Serna@txdot.gov
en	512-253-6070	Marcus.Snowden@txdot.gov
	325-247-5146	James.Low@txdot.gov
	325-347-6447	Cole.Farmer@txdot.gov
	512-997-2267	Gregory.Stephens@txdot.gov
l	512-331-5361	Anthony.Reitan@txdot.gov
	512-627-9874	Ronald.Switzer@txdot.gov
	512-365-5254	Jackie.Volek@txdot.gov
	512-930-4700	John.Taylor@txdot.gov

**Project Number:** MMC 638370001 **County:** BASTROP, Etc. **Highway:** FM 535, Etc.

#### **ITEM 8 – PROSECUTION AND PROGRESS**

Time charges will be in accordance with Article 8.3.1.5 "Calendar Day".

In accordance with Article 8.6 "Failure to Complete Work on Time," liquidated damages shall be charged each day for failure to meet each work order. This will include:

1. Failure to deliver at the starting date or continually progress on the work order.

2. Failure to deliver the required materials per day.

3. Failure to complete work order within 3 weeks (21 calendar days) from the issue date on work order.

The amount assessed per day for liquidated damages shall be 1 % of the estimated cost of the work order, not to be less than \$200 per day and not to exceed \$500 per day.

### **ITEM 9 – MEASUREMENT AND PAYMENT**

In accordance with Article 9.1," Measurement of Quantities," furnish the tare and maximum gross weights as well as the volume capacity of all vehicles, trucks, truck-tractors, trailers, semitrailers, or combination of such vehicles used to deliver materials for the contract. Also, furnish calculations supporting these weights and capacities. Provide all measurements required for pay a minimum of 2 days before the equipment is used.

In accordance with Article 9.2 "Plans Quantity Measurement," plans quantity measurement requirements are not applicable for this contract. Quantities shown in the plans are for bidding purposes only. TxDOT does not guarantee that all quantities shown in plans will be requested for delivery.

Contractor is responsible for obtaining annual overweight tolerance permit if hauling material which exceeds the legal road weight.

### SS 8039 – AGGREGATES FOR SURFACE TREATMENTS (MATERIALS ONLY)

Previously tested aggregates delivered to the locations, which are found to contain excessive quantities of dust (more than 0.5 percent passing the no. 40 sieve) during pre-coating, stockpiling or hauling operations, will be rejected. Use test method Tex-200-F, Part II, for testing.

Report to the State's representative at the time of arrival at the locations and obtain a signature documenting the date and time.

Table 3 Los Angeles Abrasion, % Max, is lowered from 35 to 30 and is applicable to all aggregates.

Table 3 Magnesium Sulfate Soundness, % Max, is lowered from 25 to 20 and is applicable to all aggregates.

All aggregate will be SAC B or better.

Sheet: 3A Control: 6383-70-001



#### CONTROLLING PROJECT ID 6383-70-001

DISTRICT Austin HIGHWAY FM0535 **COUNTY** Bastrop

**Estimate & Quantity Sheet** 

		CONTROL SEC	TION JOB	6383-70	-001		
		PROJECT ID COUNTY		A00178	370		
				Bastro	ор	TOTAL EST.	TOTAL FINAL
			HIGHWAY	FM05	35		
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	8039-6253	AGGR (TY D GR 4) (DEL) (INVEH) (ST1)	CY	1,100.000		1,100.000	
	8039-6254	AGGR (TY D GR 4) (DEL) (INVEH) (ST2)	CY	2,000.000		2,000.000	
	8039-6255	AGGR (TY D GR 4) (DEL) (INVEH) (ST3)	CY	2,500.000		2,500.000	
	8039-6256	AGGR (TY D GR 4) (DEL) (INVEH) (ST4)	CY	2,000.000		2,000.000	
	8039-6257	AGGR (TY D GR 4) (DEL) (INVEH) (ST5)	CY	2,000.000		2,000.000	
	8039-6258	AGGR (TY D GR 4) (DEL) (INVEH) (ST6)	CY	1,000.000		1,000.000	
	8039-6259	AGGR (TY D GR 4) (DEL) (INVEH) (ST7)	CY	1,600.000		1,600.000	
	8039-6260	AGGR (TY D GR 4) (DEL) (INVEH) (ST8)	CY	1,700.000		1,700.000	
	8039-6261	AGGR (TY D GR 4) (DEL) (INVEH) (ST9)	CY	3,000.000		3,000.000	
	8039-6262	AGGR (TY D GR 4) (DEL) (INVEH) (ST10)	CY	3,000.000		3,000.000	
	8039-6263	AGGR (TY D GR 4) (DEL) (INVEH) (ST11)	CY	3,320.000		3,320.000	



DISTRICT	COUNTY	CCSJ	SHEET	
Austin	Bastrop	6383-70-001	4	

SITE #1: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF BASTROP COUNTY SITE #2: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF BLANCO COUNTY SITE #3: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF BURNET COUNTY SITE #4: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF CALDWELL COUNTY SITE #5: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF GILLESPIE COUNTY SITE #6: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF HAYS COUNTY SITE #7: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF LEE COUNTY SITE #8: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF LANO COUNTY SITE #9: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF MASON COUNTY SITE #9: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF TRAVIS COUNTY SITE #10: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF TRAVIS COUNTY SITE #10: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF TRAVIS COUNTY SITE #10: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF TRAVIS COUNTY SITE #10: ANY DELIVERY ADDRESS OR LAT/LONG WITHIN THE LIMITS OF WILLIAMSON COUNTY

FOR THE PURPOSE OF THIS CONTRACT THE DELIVERY SITES ARE AS FOLLOWS:

\*ALL AGGREGATE WILL BE SAC B OR BETTER.

				SUMMARY	OF MATERIALS	QUANTITIES						
		8039 6253	8039 6254	8039 6255	8039 6256	8039 6257	8039 6258	8039 6259	8039 6260	8039 6261	8039 6262	8039 6263
		AGGR	AGGR	AGGR	AGGR	AGGR	AGGR	AGGR	AGGR	AGGR	AGGR	AGGR
DELIVERY		(TY D GR 4)	(TY D GR 4)	(TY D GR 4)	(TYDGR4)	(TY D GR 4)						
LOCATION	MAINTENANCE SECTION			(DEL) (INVEH)								
LOCATION	SECTION	(DEL) (INVEH)	(DEL)(INVEH)									
		(SITE 1)	(SITE 2)	(SITE 3)	(SITE 4)	(SITE 5)	(SITE 6)	(SITE 7)	(SITE 8)	(SITE 9)	(SITE 10)	(SITE 11)
		CY	CY	CY	CY	CY	CY	CY	CY	CY	СҮ	CY
174 SH 29 E. BASTROP TX 78602	BASTROP	1100										
608 US 281 S. JOHNSON CITY TX 78636	BLANCO		2000									
3029 SH 29 E. BURNET TX 78611	BURNET			2500								
1315 N BLANCO ST LOCKHART TX 78644	CALDWELL				2000							
3029 SH 29 E. BURNET TX 78611	GILLESPIE					2000						
1710 SH 21 SAN MARCUS TX 78633	HAYS						1000					
3391 SH 21 W LINCOLN TX 78948	LEE							1600				
3029 SH 29 E. BURNET TX 78611	LLANO								1700			
2424 HWY 29 MASON TX 76856	MASON									3000		
1001 PARMER LANE AUSTIN TX 78753	TRAVIS CENTRAL										1000	
2001 WHITESTONE CEDAR PARK TX 78613	TRAVIS NORTH											1000
1001 E. PARMER LANE AUSTIN 78753	TRAVIS EAST										1000	
12315 US 290 W AUSTIN 78737	TRAVIS SOUTH										1000	
2727 S AUSTIN AVE GEORGETOWN 78627	Williamson West											1200
3101 W 2ND ST TAYLOR 76574	Williamson East											1120
PROJECT TOTALS		1100	2000	2500	2000	2000	1000	1600	1700	3000	3000	3320

Austin District	
Maintenance Office	

Texas Department of Transportation

### location Summary

© 20		CONT	SECT	JOB		HIGHWAY
DS:	ск:	6383	70	001	FM	535, ETC.
DW:	ск:	DIST		COUNTY		SHEET NO.
		AUS	ΒA	STROP, ETC		5