

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION
PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT
PROJECT: MMC-6403-14-001
COUNTY: GRAYSON, ETC.
HIGHWAY: US0075, ETC
CALLOUT CONTRACT
FOR THE PURCHASE OF MATERIALS ONLY, DE-ICING SALT


Note: See Project Summary Sheets for complete listing of limits, lengths, equations and exceptions.


Index of Sheets:

- 2 General Notes
- 3 Estimate & Quantity Sheet
- 4 Plan Sheet

RECOMMENDED FOR LETTING:

APPROVED FOR LETTING:

DocuSigned by:

7D58DA3054CC40D...
4/22/2022
District Maintenance Administrator

DocuSigned by:

182793D7AE194E0...
4/26/2022
Director of Operations

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

DISTRICT	COUNTY	HIGHWAY	CONTROL
PARIS	GRAYSON, ETC.	US0075, ETC	6403-14-001

© 2021 BY Texas Department of Transportation
All Rights Reserved.

Project Number: MMC – 640314001

Sheet 2

County: GRAYSON, ETC.

Control: 6403-14-001

Highway: US 0075, Etc.

GENERAL NOTES:

PROJECT DESCRIPTION – The primary intent of this on-call contract is to purchase roadway materials only.

This project consists of supplying “De-Icing Salt” in the Paris District as specified in the plans.

Contractor questions on this project are to be addressed to the following individual(s):

District Maintenance Office:

Tad Eudy – Tad.Eudy@txdot.gov

Tommy Henderson, P.E. – Tommy.Henderson@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT’s Public FTP at the following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

TXDOT PROJECT SUPERVISOR – All work on this contract will be scheduled and directed by the following person(s). Payments will be made on a monthly basis for work completed and accepted according to specifications. All payment requests will be directed to the same:

Site 1 – Fannin County, Jerry Hale, Maintenance Supervisor.
2405 N. Center, Bonham, Texas 75418, Phone: 903-583-7566

Site 2 – Red River County, Mark Miller, Maintenance Supervisor
2002 W. Main St., Clarksville, Texas 75426, Phone: 903-427-3561

Site 3 – Delta County, John Vanderschaaf, Asst. Maintenance Supervisor
131 Hwy 64, Cooper, Texas 75432, Phone: 903-395-2139

Site 4 – Rains County, Kevin Wilson, Asst. Maintenance Supervisor
1520 W US 69, Emory, Texas 75440, Phone: 903-473-2682

Project Number: MMC – 640314001

Sheet 2

County: GRAYSON, ETC.

Control: 6403-14-001

Highway: US 0075, Etc.

Site 5 – Hunt County, Duane Andrus, Maintenance Supervisor
3001 IH30 East, Greenville, Texas 75402, Phone: 903-455-2303

Site 6 – Franklin County, Shane Bolton, Assist. Maintenance Supervisor
104 East IH30, Mount Vernon, Texas 75457, Phone: 903-537-4976

Site 7 – Lamar County, David Escobedo, Maintenance Supervisor
3600 S. W. Loop 286, Paris, Texas 75460, Phone: 903-785-4468

Site 8 – Grayson County, Matt Poirot, Maintenance Supervisor
3904 Hwy 75 South, Sherman, Texas 75090, Phone: 903-892-6529

Site 9 – Hopkins County, Clint Traylor, Maintenance Supervisor
1100 Hillcrest Drive on SH 19, Sulphur Springs, Texas 75482, Phone: 903-885-4031

Site 10 – Paris District Headquarters, Tad Eudy, District Maintenance Administrator
1365 N. Main, Paris, Texas 75460, Phone: 903-737-9222

Contract Prosecution: Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

The work performed, equipment used, and materials furnished for a complete project will be paid for directly as indicated elsewhere in the plans and specifications. Payment for complete work will be made upon accepted of the work by the department.

ITEM 2 – INSTRUCTIONS TO BIDDERS:

Views plans on-line or download from the web at:

<https://www.txdot.gov/business/letting-bids/plans-online.html>

Order plans from any of the plan reproduction companies shown on the web at:

http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

ITEM 4 – SCOPE OF WORK:

This contract may be extended per Special Provision 004-004.

Project Number: MMC – 640314001

Sheet 2

County: GRAYSON, ETC.

Control: 6403-14-001

Highway: US 0075, Etc.

ITEM 5 – CONTROL OF THE WORK:

Upon completion of the work and before final acceptance and final payment is made, clear and remove from the site all surplus and discarded material and will leave the entire project in a neat and slightly condition.

- Make all deliveries between the hours of 8 A.M. and 4 P.M. CST unless prior arrangements have been made with the Maintenance Supervisor.
- TxDOT will not place orders for less than 24 TONS.
- Material shall be delivered a method capable of placing material in the opening of the salt storage building, i.e. End Dump or Live Bottom trailers.

ITEM 6 – CONTROL OF MATERIALS:

Furnish all material for this project in accordance with applicable specifications.

ITEM 8 – PROSECUTION AND PROGRESS:

Time will be computed according to Item 8.3.1.5 “Calendar Day”.

In accordance with Article 8.6 “Failure to Complete Work on Time,” liquidated damages will be charged for failure to complete each Work Order within 7 days from the issue date of the work order. All work orders stand on their own.

The amount assessed per day for liquidated damages will be 5% of the estimated cost of the Work Order, not to be less than \$250 per day and not to exceed \$1,000 per day.

ITEM 9 – MEASUREMENT & PAYMENT:

In accordance with Article 9.1,” Measurement of Quantities,” furnish the tare and maximum gross weights as well as the volume capacity of all vehicles, trucks, truck-tractors, trailers, semi-trailers, or combination of such vehicles used to deliver materials for the contract. Also furnish calculations supporting these weights and capacities. Provide all measurements required for pay a minimum of 2 days before the equipment is used.

Project Number: MMC – 640314001

Sheet 2

County: GRAYSON, ETC.

Control: 6403-14-001

Highway: US 0075, Etc.

Contractor is responsible for obtaining annual overweight tolerance permit if hauling material which exceeds the legal road weight.

F.O.B. Destination, freight prepaid and allowed. This means the vendor will prepay and include the freight charges in the unit price.

ITEM 8008 – De-Icing Salt (Materials Only):

TY-I

Supply Sodium Chloride (De-Icing Salt) Type I salt for broadcasting on roadway.

Material will be roadway grade salt (Sodium Chloride), in bulk salt form, for the quantity identified on the call-out work order. Bulk salt will be clean and free of debris.

TY-II

Supply Sodium Chloride (De-Icing Salt) Type II salt for making brine.

Material will be brine quality salt (Sodium Chloride), in bulk salt form, for the quantity identified on the call-out work order. Bulk salt will be clean and free of debris.

ITEM	DESCRIPTION	QTY	UOM
8008	6002 DE-ICING/ANTI-ICING (DEL)(TY I)(ST 2)	100	TON
8008	6003 DE-ICING/ANTI-ICING (DEL)(TY I)(ST 3)	100	TON
8008	6004 DE-ICING/ANTI-ICING (DEL)(TY I)(ST 4)	100	TON
8008	6006 DE-ICING/ANTI-ICING (DEL)(TY I)(ST 6)	100	TON
8008	6007 DE-ICING/ANTI-ICING (DEL)(TY I)(ST 7)	300	TON
8008	6009 DE-ICING/ANTI-ICING (DEL)(TY II)(ST 1)	400	TON
8008	6014 DE-ICING/ANTI-ICING (DEL)(TY II)(ST 5)	400	TON
8008	6017 DE-ICING/ANTI-ICING (DEL)(TY II)(ST 8)	500	TON
8008	6018 DE-ICING/ANTI-ICING (DEL)(TY II)(ST 9)	400	TON
8008	6019 DE-ICING/ANTI-ICING (DEL)(TY II)(ST 10)	300	TON

PLAN SHEET

CONT	SECT	JOB	HIGHWAY
6403	14	001	US0075, ETC
DIST	COUNTY		SHEET NO.
01	GRAYSON, Etc.		4