

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6408-34-001
 CSJ: 6408-34-001
 HIGHWAY: IH 35W, ETC
 LIMITS OF WORK: TARRANT COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
 DESCRIPTION: DENSE GRADED HOT MIX ASPHALT (MATERIAL ONLY)

RECOMMENDED
 FOR LETTING: 6/3/2022
 Date

RECOMMENDED
 FOR LETTING: 6/3/2022
 Date

DocuSigned by:

 7B89CC87CF28477...
 AREA ENGINEER

DocuSigned by:
Matthew L. Evans
 E9AEAF95D42641B...
 DIRECTOR OF MAINTENANCE


RECOMMENDED
 FOR LETTING: 6/3/2022
 Date

DocuSigned by:
Carl L. Johnson, PE
 2FE36139F0614C3...
 DISTRICT ENGINEER

INDEX OF SHEETS

| | |
|------|---------------------------|
| 1 | TITLE SHEET |
| 2A-E | GENERAL NOTES |
| 3 | ESTIMATE & QUANTITY SHEET |
| 4 | DELIVERY SITES SHEET |

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

| | | | |
|--------------------|--|-----------|-------------|
| © 2022 |  Texas Department of Transportation | | |
| FED.RD. DIV. NO | PROJECT NO. | SHEET NO. | |
| 6 | 6408-34-001 | 1 | |
| STATE | DISTRICT | COUNTY | |
| TEXAS | FTW | TARRANT | |
| CONTROL | SECTION | JOB | HWY NO. |
| 6408 | 34 | 001 | IH 35W, ETC |
| FILENAME | | | DATE |
| MMC 6408-34-001 | | | 5/5/2022 |

Project Number: MMC 6408-34-001**Control:** 6408-34-001**County:** Tarrant**Highway:** IH 35W, Etc.**GENERAL NOTES:****General:**

The purpose of this contract is to supply "**Dense Graded Hot Mix Asphalt and Asphaltic Con Patching Material**" to locations provided to the Contractor by Work Order

Provide and maintain a dedicated email address for receipt of work orders and correspondence throughout the term of this contract. Acknowledgement of emailed work order/callouts is required no more than 12 hr. from notification.

Contractor's attention is called to the fact that all Department property will be protected during all phases of the execution of the contract and any damages incurred due to Contractor's operation will be repaired and replaced at the Contractor's expense.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Prior to beginning operations, the Department will arrange a preconstruction meeting between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

Coordinate work through the Maintenance Section Supervisor or Representative:

| North Tarrant | |
|--|--|
| 508 Blue Mound Rd Saginaw, TX 76179 (817) 399-4350 | 2501 W. Euless Blvd, Euless, TX 76040 (817) 370-6901 |

Bids will be received at 6230 East Stassney Lane, Austin, TX 78744.

Project Number: MMC 6408-34-001

Control: 6408-34-001

County: Tarrant

Highway: IH 35W, Etc.

Contractor questions on this project are to be emailed to the following individual:

Area Engineer: Minh Tran

Minh.Tran@txdot.gov

Asst. Area Engineer: James Bell

James.Bell1@txdot.gov

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

[https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/](https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/)

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Attention is directed to the possible presence of underground utilities owned by the Texas Department of Transportation (irrigation, signal, illumination and surveillance, communication, and control) on the right of way. Call TxDOT for locates at 817-370-6500, or the appropriate department of the local city or town a minimum of 48 hr. in advance of excavation.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Cost associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Item 2 – Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal.

Order plans from any Reproduction Company listed at:

http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

View or download plans at:

<http://www.dot.state.tx.us/business/plansonline/plansonline.htm>

Project Number: MMC 6408-34-001

Control: 6408-34-001

County: Tarrant

Highway: IH 35W, Etc.

Item 3 – Award and Execution of Contract:

This contract is non-site specific, only materials received delivered to the Delivery Sites within state right of way or state property specified in the plans will be paid.

Material will be made available for pickup or delivery, as indicated in the plans.

When material is specified to be picked up by TxDOT, material shall be made available within 48 hrs. or as directed in the Work Order.

When material is specified to be delivered, successfully deliver each Work Order within 3 calendar days upon notification, or as directed in the Work Order. Delivery hours will be stated in the Work Order. This contract may require work to be done at night between the hours of 9PM and 5AM.

Notify the Maintenance Section Supervisor 24 hours in advance prior to delivery.

Item 4 – Scope of Work:

This contract allows for two (2) 120-day extensions as allowed by Special Provision 004-004, provided both the Contractor and TxDOT agree.

Item 6 – Control of Materials:

Use materials from pre-qualified producers. A list of material producers pre-qualified by the Construction Division (CST) of the Texas Department of Transportation (TxDOT) can be found at the following website:

<https://www.txdot.gov/business/resources/producer-list.html>

Item 7 – Legal Relations and Responsibilities:

Appropriate Personal Protective Equipment (PPE), including Department-approved safety hats and safety shirts, will be worn by all workers and visitors when:

Workers are outside of vehicles at all outdoor worksites. This includes those who occasionally visit worksites either on the highway surface or right of way.

Working in areas where there is danger of head injury from impact, from falling or flying objects, or from electrical shock or burns.

Project Number: MMC 6408-34-001

Control: 6408-34-001

County: Tarrant

Highway: IH 35W, Etc.

Non-compliance with this requirement will be grounds of suspension of work.

All work on this contract will be scheduled and directed by the Maintenance Section Supervisor.

Any hazardous spills or releases of this material on TxDOT property will be promptly cleaned and remediated at Contractor's expense, including cost of spilled material.

Item 8 – Prosecution and Progress:

Working days will be charged in accordance with Section 8.3.1.5., "Calendar Day".

Unless otherwise directed, prosecute the work continuously to completion of the Callout Work Request.

This contract may require work to be done at night between the hours of 9PM and 5AM.

Item 9 – Measurement and Payment:

Units delivered in volume and weight measurements will be in accordance with Article 9.1, "Measurement of Quantities". Furnish the tare and maximum gross weights as well as the volume capacity of all vehicles, trucks, truck-tractors, trailers, semi-trailers or combination of such vehicles to deliver materials for the contract. Also furnish calculations supporting these weights and capacities. Provide all measurements required for pay a minimum of two days before the equipment is used.

When material is measured by the ton, provide a conversion rate to cubic yards on each haul ticket.

Contractor is responsible for obtaining annual overweight tolerance permit if hauling materials exceed the legal road weight.

Items with units measured individually, not measured by volume or weight, will be counted and confirmed at point of delivery.

In accordance with Article 9.2, "Plans Quantity Measurement", plans quantity measurement requirements are not applicable to this contract.

TxDOT does not guarantee that all quantities shown in plans will be requested for delivery.

Project Number: MMC 6408-34-001

Control: 6408-34-001

County: Tarrant

Highway: IH 35W, Etc.

Item 500 – Mobilization:

Mobilization does not apply to this Maintenance Materials Contract.

Item 8011 – Dense-Graded Hot Mix Asphalt (Materials Only):

No Blending, of the material to meet SAC A will be allowed.

Substitute binders are not allowed on this project.

RAP and RAS are not permitted in any surface and level-up mixes on this project

Furnish a mix design to the State's representative to be sent to the District Laboratory for verification testing.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Use only Department MPL approved asphalt release agents. Diesel and/or solvents in the production, transportation, and/or construction of the mix is prohibited.

No material shall be left in the haul vehicle overnight.

Canvas covers and insulating of the truck bodies will be required.

Contractor must have equipment and personnel to supply a minimum of 500 ton per day.


Include the approved mix design number on each delivery ticket.

Item 8019 – Asphaltic Conc Patch Material (Materials Only):

This item will be measured by the ton as defined in the plans and specifications. Delivery location will be listed in each Work Order.

ESTIMATE SUMMARY

| ITEM-CODE | | DESCRIPTION | UNIT | TOTAL | |
|-----------|----------------------|---|------|--------|-------|
| ITEM NO. | DESC. CODE SP NO. | | | EST. | FINAL |
| 8011 | 6039 | D-GR HMA(SQ) TY B SAC B PG64-22(PICKUP) | TON | 1,000 | |
| 8011 | 6040 | D-GR HMA(SQ) TY C SAC A PG70-28(DEL) | TON | 10,000 | |
| 8019 | 6010 | ASPHALTIC CONC PATCH MATERIAL (DEL) | TON | 200 | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |




ESTIMATE AND QUANTITIES

| | | | | | | | |
|--------|------------------|-------|-------------------------|-------------|-------------|-------------|---|
| DESIGN | FED RD. DIV. NO. | 6 | MAINTENANCE PROJECT NO. | 6408-34-001 | HIGHWAY NO. | IH 35W, ETC | |
| | GRAPHICS | | | | | | |
| CHECK | STATE | TEXAS | DISTRICT | FTW | COUNTY | TARRANT | |
| | CONTROL | 6408 | SECTION | 34 | JOB | 001 | |
| | | | | | | SHEET NO. | 3 |

| SITE NO. | MAINTENANCE OFFICE | DELIVERY SITE | ITEM NO. | DES. NO. | UNIT | QUANTITY |
|----------|--------------------|---|----------|----------|------|----------|
| 1 | NORTH TARRANT | VARIOUS LOCATIONS WITHIN NORTH TARRANT COUNTY | 8011 | 6039 | TON | 1,000 |
| 1 | NORTH TARRANT | VARIOUS LOCATIONS WITHIN NORTH TARRANT COUNTY | 8011 | 6040 | TON | 10,000 |
| 1 | NORTH TARRANT | VARIOUS LOCATIONS WITHIN NORTH TARRANT COUNTY | 8019 | 6010 | TON | 200 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

* APPROXIMATE LOCATIONS FOR DELIVERY

**Texas Department of Transportation**

DELIVERY SITE SHEET

| | | | |
|--------|-------------------|-------------------------|---------|
| DESIGN | FED. RD. DIV. NO. | MAINTENANCE PROJECT NO. | |
| | 6 | 6408-34-001 | |
| CHECK | STATE | DISTRICT | COUNTY |
| | TEXAS | FTW | TARRANT |