DATE CONTRACT LETTING: \_\_\_ DATE CONTRACTOR BEGAN WORK: \_\_

CONTRACTOR: \_\_\_\_

# STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

		I NOSECT N	٠.
	S	TP 2024(62	29) HES
CONT	SECT	JOB	HIGHWAY
0910	00	137	VAR
DIST		COUNTY	SHEET NO.
TYL		SMITH, ETC	. 1

# PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

PROJECT NO. STP 2024(629) HES

# SMITH COUNTY, ETC. VARIOUS HIGHWAYS

INSTALL BACKPLATES WITH REFLECTIVE BORDERS IN VARIOUS LOCATIONS IN THE TYLER DISTRICT

NOT TO SCALE Texas Department of Transportation NO EXCEPTIONS

SIGN IN ACCORDANCE WITH THE STANDARD BC SHEETS AND PART 6 OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND THE CONTRACT PROVISIONS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, October 23, 2023)

FINAL PLANS

DATE WORK COMPLETED & ACCEPTED: \_\_\_\_\_

USED \_\_\_\_\_OF \_\_\_\_ ALLOTTED DAYS \_\_\_\_\_

FINAL CONTRACT COST : \$ \_\_\_\_\_

NO EQUATIONS NO RAILROAD CROSSINGS ELIMINATED RECOMMENDED FOR LETTING:

Rolando Mendez

10/30/2023

10/31/2023

10/30/2023

APPROVED FOR LETTING:

SUBMITTED FOR LETTING:

DISTRICT ENGINEER

Juanita Daniels-West, P.E. DIRECTOR OF TRANSPORTATION OPERATIONS

© 2023 by Texas Department of Transportation all rights reserved

-8F5FF128DB7C484... DISTRICT DESIGN ENGINEER

# GENERAL

SHEET NO. DESCRIPTION

1 TITLE SHEET
2 SUPPLEMENTAL INDEX OF SHEETS
3, 3A - 3B GENERAL NOTES
4 ESTIMATE & QUANTITY SHEET
QUANTITY SUMMARY

# TRAFFIC CONTROL PLAN

# TRAFFIC ITEMS

# ENVIRONMENTAL ISSUES

SHEET NO. DESCRIPTION

27 - 28 STORMWATER POLLUTION PREVENTION PLAN EPIC

<u>SHEET NO.</u> <u>STANDARDS</u> 30 - 32 \* EC(9)-16



SUPPLEMENTAL INDEX OF SHEETS

\* THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Texas Departmen	nt of	Transporta	tic
_			

CONT	SECT	JOB	,	HIGHWAY
0910	00	137		VAR
DIST		COUNTY		SHEET NO.
TYL	9	SMITH, ETC		2

Project Number: Sheet 3

County: Smith, etc. Control: 0910-00-137

Highway: Various

**GENERAL NOTES:** 

GENERAL.

Contractor questions on this project are to be addressed to the following individuals:

Juanita Daniels-West, P.E. Juanita.DanielsWest@txdot.gov

Steven Swindell, P.E. Steven.Swindell@txdot.gov

For Q&A on Proposals navigate to:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

Use the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project and click on the link in the window that pops up to view the Q&A.

All relevant project documentation including Contract Time Determinations and cross-sections will still be posted to the districts FTP website.

https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/Tyler%20District/Construction%20Projects

# **ITEM 4. SCOPE OF WORK**

Preserve the integrity of all right of way monuments within project limits. Right of way monuments damaged or destroyed during construction must be replaced by a registered professional land surveyor (RPLS), at the Contractor's expense.

# ITEM 5. CONTROL OF THE WORK

If utility lines need adjustments during construction operations, modify operations and continue the work in a manner that will allow others to make the utility adjustments. Additional working time may be allowed for delays caused by these utility adjustments.

Unless otherwise approved, complete all work at an intersection before beginning work at another intersection. Start work in one county and complete all work in that county before proceeding to the next county.

# ITEM 6. CONTROL OF MATERIALS

Project Number: Sheet 3

County: Smith, etc. Control: 0910-00-137

Highway: Various

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the link below:

https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html

# ITEM 7. LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

# ITEM 502. BARRICADES, SIGNS, AND TRAFFIC HANDLING

The traffic control plan for this Contract consists of: the installation and maintenance of warning signs and other traffic control devices shown on the plans; specification data, which may be included in the general notes; applicable provisions of the Texas Manual on Uniform Traffic Control Devices (TMUTCD); traffic control plan sheets included on the plans; standard BC sheets; Compliant Work Zone Traffic Control Device List, and Item 502 of the standard specifications.

Use ground-mounted sign mounts with two posts for all temporary work zone signs unless otherwise directed.

Inspect and correct deficiencies each day throughout the duration of the Contract. In accordance with Article 502.4., "Payment," no payment will be made for the month if the Contractor fails to provide or properly maintain signs and devices in compliance with Contract requirements. Temporary warning signs that are visible when conditions do not apply will be considered improper maintenance of signs.

Provide at least one employee on call nights and weekends (or any other time that work is not in progress) for maintenance of signs and traffic control devices. This employee must have an address and telephone number near the project, as approved. Notify the Engineer in writing of the name, address, and telephone number of this employee. The Engineer will furnish this information to local law enforcement officials.

General Notes Sheet A General Notes Sheet B

Project Number: Sheet 3A

County: Smith, etc. Control: 0910-00-137

Highway: Various

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 30 minutes.

Refer to the traffic control plan sheets for traffic handling through the work area. Contractor may vary the signing arrangement and spacing as necessary to fit field conditions; however, any proposed changes in the traffic control plan must be approved before implementation.

High-visibility safety apparel is required for workers in accordance with the General Notes on current BC standards.

Place and maintain signs, channelizing devices, and flaggers to direct and route traffic at any location and for any period of time as may be required or directed.

When operations require a lane closure, provide cones, vertical panels, drums, signs, flaggers, and flashing arrow panels as necessary to route traffic around the closed lane as shown on the plans and as directed. Lane closures will be limited to one specific lane as directed.

Lane closures will not be allowed before 8 A.M. unless otherwise directed.

Unless otherwise approved, construction operations will not be allowed on Good Friday, Easter weekend, the Friday before Memorial Day thru Memorial Day, July 4th, the Friday before Labor Day thru Labor Day, the Wednesday before Thanksgiving Day thru Sunday, Christmas Eve, Christmas Day, New Year's Eve, New Year's Day, or on any other high traffic days or holidays as determined by the Engineer.

Provide truck-mounted attenuators (TMA) as shown on the appropriate traffic control plan sheets. Provide a letter certifying that all TMA used on this project meet NCHRP 350 or AASHTO Manual for Assessing Safety Hardware (MASH) requirements.

Regulate all construction activities and equipment to minimize inconvenience to the traveling public. At points where it is necessary for trucks to stop, load, or unload, provide warning signs and flaggers to protect the traveling public.

The Contractor Force Account "Safety Contingency" is intended to be used for work zone enhancements that could not be foreseen in the project planning and design stage for the purpose of improving the effectiveness of the Traffic Control Plan. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Provide flaggers at county roads, commercial driveways, and other intersecting roadways deemed necessary by the Engineer to maintain control of the work zone during one-lane two-way

Project Number: Sheet 3A

County: Smith, etc. Control: 0910-00-137

Highway: Various

operations. Provide communication radios to each flagger in the work zone and the pilot vehicle operator.

Lane closures will not be allowed on IH 20 on Saturday, Sunday, or after 12 P.M. on Friday.

With prior approval, provide uniformed law enforcement officers for traffic control during construction operations at high-volume intersections. The law enforcement officer's intersection control force account is under control 0910-00-137.

When operations require a sidewalk closure, use traffic control devices that control pedestrian flow as necessary to route pedestrians around the closed sidewalk as shown on sidewalk closures and bypass walkway sheet as directed.

The use of Law Enforcement Officers (LEOs) will be required for this project. Before the preconstruction meeting, coordinate with local agencies to be prepared for staffing needs.

Provide uniformed LEOs with marked vehicles during work zone activities. The officer in marked vehicle will be located as approved to monitor or direct traffic during the closure. The Engineer will approve the method used to direct traffic at signalized intersections. Additional officers and vehicles may be provided when directed.

Complete the daily tracking form provided by the Department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case-by-case basis.

All law enforcement personnel used in work zone traffic control must be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" (Course #133119) which can be found online at the following site: <a href="https://www.nhi.fhwa.dot.gov">www.nhi.fhwa.dot.gov</a>.

Certificates of completion should be available to all who finish the course. These should be kept by the officers to verify completion when reporting to the work site.

Provide the Engineer 72-hour notice of lane or ramp closures to provide advance notice to the traveling public by way of media and for any dynamic message sign programing. Place Portable Changeable Message Signs (PCMS) at locations as directed a minimum of 3 days in advance of entrance ramp closures on the affected crossroad. These signs are to remain in place during the ramp closures.

All work required by these general notes, except as provided for by Item 502, will not be paid for directly, but will be subsidiary to Item 502 unless otherwise shown on the plans.

Sheet D

General Notes Sheet C General Notes

Project Number: Sheet 3B

County: Smith, etc. Control: 0910-00-137

Highway: Various

# ITEM 506. TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

Temporary erosion control work will be paid for under the Contractor's force account under control 0910-00-137.

# ITEM 680. INSTALLATION OF HIGHWAY TRAFFIC SIGNALS

When directed, provide a uniformed law enforcement officer to maintain traffic control when the signal lights are placed in operation and at any time the normal signal operation is interrupted due to failure of Contractor supplied materials or workmanship.

The Contractor's maintenance responsibility begins on the day work is authorized, and continues until final acceptance. Designate in writing an IMSA certified signal technician who is available to perform repair work within a 2-hour response time at all times. This work will not be paid for directly, but will be subsidiary to Item 680.

# ITEM 682. VEHICLE AND PEDESTRIAN SIGNAL HEADS

Fabricate the traffic signal heads using polycarbonate. Cover the traffic signal heads with factory-made signal head covers until placed in operation.

# ITEM 6001. PORTABLE CHANGEABLE MESSAGE SIGN

Provide a non-erodible, stable surface to place the Portable Changeable Message Sign (PCMS) units adjacent to the roadway as directed. Payment for this surface is incidental to Item 6001.

# ITEM 6185. TRUCK MOUNTED ATTENUATOR (TMA)

Shadow vehicles with truck mounted attenuator (TMA) are required on the traffic control plan and TCP standards for this project. The Contractor will be responsible for determining if one or more of these traffic control operations will be ongoing at the same time to determine the total number of TMAs needed for the project. Additional truck mounted attenuators (TMAs) may be required as deemed necessary by the Engineer.

The TMA/TA used for installation/removal of traffic control for a work area will be subsidiary to the TMA/TA used to perform the work.

General Notes Sheet E



# **Estimate & Quantity Sheet**

CONTROLLING PROJECT ID 0910-00-137

DISTRICT Tyler
HIGHWAY Various

**COUNTY** Smith

Report Created On: Nov 17, 2023 11:05:24

		CONTROL SECTION	N JOB	0910-0	0-137		
		PROJ	ECT ID	A0018	4674		
		C	YTNUC	Smi	th	TOTAL EST.	TOTAL FINAL
		HIG	HWAY	Vario	ous		TINAL
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	5.000		5.000	
	682-6001	VEH SIG SEC (12")LED(GRN)	EA	1,068.000		1,068.000	
	682-6002	VEH SIG SEC (12")LED(GRN ARW)	EA	419.000		419.000	
	682-6003	VEH SIG SEC (12")LED(YEL)	EA	1,072.000		1,072.000	
	682-6004	VEH SIG SEC (12")LED(YEL ARW)	EA	293.000		293.000	
	682-6005	VEH SIG SEC (12")LED(RED)	EA	1,104.000		1,104.000	
	682-6006	VEH SIG SEC (12")LED(RED ARW)	EA	111.000		111.000	
	682-6054	BACKPLATE W/REF BRDR(3 SEC)(VENT)ALUM	EA	828.000		828.000	
	682-6055	BACKPLATE W/REF BRDR(4 SEC)(VENT)ALUM	EA	192.000		192.000	
	682-6056	BACKPLATE W/REF BRDR(5 SEC)(VENT)ALUM	EA	163.000		163.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	60.000		60.000	
	6185-6002	TMA (STATIONARY)	DAY	150.000		150.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	10.000		10.000	
	18	LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		ENVIRONMENTAL: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Tyler	Smith	0910-00-137	4

					SIGNAL SUM	MARY PART	1 OF 5										
		Existing o	nd Proposed Signal	Head Arrangem	ents		ITEM 680					ITEM	682				NOTES:
	R Y YA GA G	RA YA YA GA	R Y GA G	RA YA GA	R R Y G	R Y G	INSTALL		VEH SI	G SEC	(12")	(LED)		В	BACK PLA	ΤE	
							HWY	(GRN)	(GRN	(YEL)		(RED)	(RED	1	REFL BR		
LOCATION							TRF SIG (UPGRADE)		ARW)		ARW)		ARW)		VENT) AL (4 SEC)	(5 SEC)	1
	EA	EΑ	EΑ	EA		EA	[1] EA	EΑ	EΑ	EΑ	EA	EΑ	EΑ	EΑ	EΑ	EA	
Smith County:																	
US 69 @ Toll 49 (North)				4	4		1	4	4	4	4	8	4	4	4	0	One 3 section arrow head is for right turn
US 69 @ FM 16	4					8	1	12	4	12	4	12	0	8	0	4	
US 69 @ South St./Jim Hogg Rd.	2		2			6	1	10	4	10	2	10	0	6	2	2	
US 69 @ Eagle Spirit Dr.	2		2			6	1	10	4	10	2	10	0	6	2	2	
US 69 @ CR 474	4					6	1	10	4	10	4	10	0	6	0	4	
US 69 @ Centennial Blvd	5			2		9	1	14	7	14	7	14	2	11	0	5	
US 69 @ IH 20				2		14	1	14	2	14	2	14	2	16	0	0	
US 69 @ Ann Campbell Rd.			2	2		6	1	8	4	8	2	8	2	8	2	0	
US 69 @ Toll 49 (South)		1	4			3	1	7	5	7	2	7	1	3	5	0	
US 271 @ IH 20				2		12	1	12	2	12	2	12	2	14	0	0	
SH 31 @ FM 2661			6	2		2	1	8	8	8	2	8	2	4	6	0	Span Wire Signal
SH 31 @ Toll 49			2	2	8	2	1	12	4	12	2	20	2	4	10	0	
SH 31 @ SS 164 (Greenbriar Rd.)	2		2			7	1	11	4	11	2	1.1	0	7	2	2	
SH 64 @ Toll 49	2					8	1	10	2	10	2	10	0	8	0	2	
SH 64 @ SS 124				1		6	1	6	1	6	1	6	1	7	0	0	
SH 64 @ Wise Elementry School	1		1			5	1	7	2	7	1	7	0	5	1	1	
SH 64 @ SS 248 (University Blvd.	2		2			6	1	10	4	10	2	10	0	6	2	2	
SH 64 @ Kissam Elem. School	2		2			8	1	12	4	12	2	12	0	8	2	2	
SH 64 @ Chapel Hill High School	1					6	1	7	1	7	1	7	0	6	0	1	
SH 110 @ Toll 49 (North)																	Recently installed; does not need new heads.
SH 110 @ Trane Plant	1			2		6	1	7	3	7	3	7	2	8	0	1	
SH 110 @ Grande Blvd.	1		2			4	1	7	3	7	1	7	0	4	2	1	
SH 110 @ Toll 49 (South)	1		1		8	1	1	11	2	1.1	1	19	0	1	9	1	
SH 110 @ Acker Tap St.	2		2			5	1	9	4	9	2	9	0	5	2	2	
SH 110 @ Wildcat Dr.	1			1		5	1	6	2	6	2	6	1	6	0	1	
SH 110 @ FM 346				7		8	1	8	7	8	7	8	7	15	0	0	
SH 155 @ Lake Placid Rd.	2		2			6	1	10	4	10	2	10	0	6	2	2	
SH 155 @ SH 57 (Grande Blvd.)		2	2			6	1	8	4	8	4	8	2	6	4	0	
SH 155 @ Toll 49	2		2		8	2	1	14	4	14	2	22	0	2	10	2	
SH 155 @ Big Eddy Rd.			6	2		2	1	8	8	8	2	8	2	4	6	0	
SH 155 @ FM 344/FM 2661			2	2		6	1	8	4	8	2	8	2	8	2	0	
SS 248 @ FM 848	2		2			6	1	10	4	10	2	10	0	6	2	2	
SL 323 @ FM 14	2			2		8	1	10	4	10	4	10	2	10	0	2	
SL 323 @ American Legion Rd.	1		2			7	1	10	3	10	1	10	0	7	2	1	
SS 364 @ Greenbriar Rd.	2		2			4	1	8	4	8	2	8	0	4	2	2	
FM 346 @ FM 2964/Quail Ln.							1	0	0	0	0	0	0	0	0	0	
FM 346 @ FM 848	2		2			6	1	10	4	10	2	10	0	6	2	2	
FM 346 @ Whitehouse High School	1		1			5	1	7	2	7	1	7	0	5	1	1	
FM 848 @ Acker Tap St.	2		2			4	1	8	4	8	2	8	0	4	2	2	
FM 2493 @ FM 2813	4					6	1	10	4	10	4	10	0	6	0	4	
FM 2964 @ Toll 49	1		1			8	1	10	2	10	1	10	0	8	1	1	
Smith Totals:	54	3	56	33	28	225	40	363	146	363	93	391	36	258	87	54	
			_	_													
CSJ 0910-00-137 PART 1 SUBTOTAL	54	3	56	33	28	225	40	363	146	363	93	391	36	258	87	54	

[1] Note: For Contractor's information only. Item 680 will not be paid for directly, but will be subsidiary to the various bid items.

				SIGN	AL SUMMARY	PART 2	OF 5	ı								
	E	xisting and Propos	ed Signal Head Arm	rangements		ITEM 680					ITEM	682				NOTES:
LOCATION	R Y YA GA G	RA YA YA GA	R Y GA G	RA YA GA	R Y G	INSTALL HWY TRF SIG	(GRN)		G SEC		(LED) (RED)	(RED	W.	ACK PLA <sup>-</sup> /REFL BR /ENT) AL	DR	
EGGATION						(UPGRADE)					<b>.</b> .		(3 SEC)	(4 SEC)	(5 SEC	
ood County:	EA	EA	EA	EA	EA	EA	EΑ	EΑ	EA	EΑ	EA	EA	EA	EA	EA	
S 69 @ SL 564		1	4	3		1	4	8	4	5	4	4	3	5	0	Need to confrim head types
S 69 @ SH 37	4	·		Ť	8	1	12	4	12	4	12	0	- 8	0	4	need to contributed types
5 69 @ US 80	2		2		6	1	10	4	10	2	10	0	6	2	2	
S 80 @ Johnson St.	2		2		6	1	10	4	10	2	10	0	6	2	2	
S 80 @ FM 14	4				6	1	10	4	10	4	10	0	6	0	4	
+ 37 @ Elm S+.	5			2	9	1	14	7	14	7	14	2	1.1	0	5	
H 37 @ SH 11				2	1 4	1	14	2	14	2	14	2	16	0	0	
H 37 @ FM 515			2	2	6	1	8	4	8	2	8	2	8	2	0	
H 37 @ SL 564		1	4		3	1	7	5	7	2	7	1	3	5	0	
M 515 @ FM 312				2	12	1	12	2	12	2	12	2	14	0	0	
M 515 @ FM 852			6	2	2	1	8	8	8	2	8	2	4	6	0	
Wood Totals:	17	2	20	13	72	11	109	52	109	34	109	15	85	22	17	Need to confrim head types
SJ 0910-00-137 PART 2 SUBTOTAL	17	2	20	13	72	11	109	52	109	34	109	15	85	22	17	

[1] Note: For Contractor's information only. Item 680 will not be paid for directly, but will be subsidiary to the various bid items.

# QUANTITY SUMMARY



				50	MMART 1 / 3
FED. RD. DIV. NO.	FEDERAL	AID PROJECT	NO.		SHEET NO.
6					5
STATE	DIST.		COUNTY		
TEXAS	TYLER	SM	IITH, E	TC.	
CONT.	SECT.	JOB	HI	GHWAY	r NO.
0910	00	137	VA	ARIO	OUS

					SIGNAL SU	MMARY PART	3 OF 5									
		Existing and	Proposed Signal	Head Arrangemen	ts		ITEM 680					ITEM	682			NOTES:
LOCATION	R Y YA GA G	RA YA YA GA	R Y GA G	RA YA GA	R R	R Y G	INSTALL HWY TRF SIG (UPGRADE)	(GRN)		S SEC	(12") (YEL ARW)	(LED) (RED)	(RED ARW)	W.	ACK PLATARET BR VENT) AL	DR UM
	EΔ	EA	EΑ	EA	FΔ	EA	[1] EA	EA	EΑ	EΑ	EA	EΑ	EA	EΑ	EA	EA
Gregg County:	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	LA	
US 80 @ Dean St.						8	1	8	0	8	0	8	0	8	0	0
US 80 @ US 271	2		2			6	1 1	10	4	10		10	0	6	2	2
US 80 @ SL 485	4					8	1 1	12	4	12	4	12	0	8	0	4
US 80 @ Shell Camp Rd.	2					8	1	10	2	10	2	10	0	8	0	2
US 80 @ FM 3272	2		2			6	i	10	4	10	2	10	0	6	2	2
US 80 @ SH 42	2		2			6	1 1	10	4	10	2	10	0	6	2	2
US 259 @ FM 2751	2		2			6	1	10	4	10	2	10	0	6	2	2
US 259 @ FM 2275	<u>-</u>	2	2			6	i	8	4	8	4	8	2	6	4	0
US 259 @ IH 20/SH 149 (North)	1		1	2		7	1	9	4	9	3	9	2	9	1	1
US 259 @ IH 20/SH 149 (South)	1		2	2		6	1 1	9	3	9	1	9	0	6	2	1
BU 259 @ SH 31/FM 349	'	4				10	1 1	10	4	10	8	10	4	10	4	0
BU 259 @ Pentecost Rd.	2	7				8	1	10	2	10	2	10	0	8	0	2
BU 259 @ FM 2204 (Stone Rd.)	2		4	2		6	i	10	6	10	2	10	2	8	4	0
BU 259 @ Kilgore St.			<u> </u>			6	1 1	6	0	6	0	6	0	6	0	0
BU 259 @ SH 42 (Lantrip St.)			2	2		8	1 1	10	4	10	2	10	2	10	2	0
BU 259 @ North St.			2	2		6	1 1	8	4	8	2	8	2	8	2	0
BU 259 @ Hourston St.			2	2		5	1 1	7	4	7	2	7	2	7	2	0
BU 259 @ FM 1249 (Dudley Rd.)	4			2		8	1 1	12	4	12	4	12	0	8	0	4
US 271 @ FM 2275	1					7	1	8	1	8	1	- 8	0	7	0	1
US 271 @ SL 485 (North)	1					6	2	7	1	7	1	7	0	6	0	1
US 271 @ Gay Ave.	2					6	1	8	2	8	2	- 8	0	6	0	2
US 271 @ Gdy AVE.	4					8	1	12	4	12	4	12	0	8	0	4
SH 31 @ Fritz Swanson Rd.	2		2			6	1	10	4	10	2	10	0	6	2	2
SH 42 @ FM 2206	2		2			6	'	10	4	10		10	-	0		Under Construction; no work
SH 42 @ FM 1252		4				8	1	8	4	8	8	8	4	8	4	0
SH 42 @ SH 31	4	4				8	1	12	4	12	4	12	0	8	0	4 Span Wire Signal
SH 42 @ Longview St.	4		2	2		6	1	8	4	8	2	8	2	8	2	0 spain wire signal
SH 42 @ Kilgore St.	4		۷	۷		8	1	12	4	12	4	12	0	8	0	4
SH 135 @ FM 1252	4					8	1	12	4	12	4	12	0	8	0	4 4
SH 135 @ FM 1252 SH 135 @ Gladewater St.	2					8	1	10	2	10	2	10	0	8	0	2
SH 322 @ IH 20/SL 281 (North)	2		2			6	1	10	4	10	2	10	0	6	2	2
SH 322 @ IH 20/SL 281 (Nor fil)	2		3	2		13	1	18	7	18	4	18	2	15	3	2 2
SH 322 @ SH 149	1		J			6	1	7	1	7	1	7	0	6	0	1
SH 322 @ SH 149 SH 322 @ FM 349	2		2			7	1	11	4	11	2	11	0	7	2	
SS 502 @ FM 1844	2		۷	2		6	1	8	4	8	4	8	2	8	0	2   Span Wire Signal   2
SS 502 @ FM 1644 SS 502 @ FM 2275		4				10	1	10	4	10	8	10	4	10	4	0
FM 2204 @ Pentecost Rd.		4	1	2		5	1	6	3	6	2	6	2	7	1	0
FM 2208 @ Smelly Rd.			2	2		6	1	8	4	8	2	- 8	2	8	2	0
FM 3272 @ Center St.	2		2			6	1	10	4	10	2	10	0	6	2	2
	4		۷		4	0	1	0	0	4	0	8	0	4	0	
FM 3272 @ School Crosswalk	57	1.4	39	20	4	268	40	364		368				· ·		0 Pedestrain Hybrid Beacon 57
Gregg Totals:	31	14	29	20	4	208	40	204	130	308	105	372	34	292	53	31
CSJ 0910-00-137 PART 3 SUBTOTAL	57	1 4	39	20	4	268	40	364	130	368	105	372	34	292	53	57

[1] Note: For Contractor's information only. Item 680 will not be paid for directly, but will be subsidiary to the various bid items.

				SIGN	IAL SUMMARY	PART 3	OF 5	5										
	Existing and Proposed Signal Head Arrangements ITEM 680 ITEM 682															NOTES:		
	R Y YA GA G	RA YA YA GA	R Y GA G	RA YA GA	R Y G	INSTALL HWY	(GRN)	VEH SI	G SEC		(LED)	(RED	4	BACK PLA				
LOCATION						TRF SIG		ARW)		ARW)		ARW)	(	VENT) AL	.UM			
						(UPGRADE)							(3 SEC)	(4 SEC)	(5 SEC			
	EA	EA	EA	EA	EA	EA	EΑ	EA	EA	EΑ	EA	EΑ	EA	EA	EA			
Cherokee County:																		
JS 69 @ US 175																Recently updated; does not need new heads		
IS 69 @ SH 135/Pine St.																Recently updated; does not need new heads		
S 69 @ Cherokee St.																Recently updated; does not need new heads		
S 69 @ US 79																Recently updated; does not need new heads		
S 69 @ El Paso St.																Recently updated; does not need new heads		
S 69 @ Canada St.																Recently updated; does not need new heads		
S 69 @ Tena St.																Construction Pending; no work		
S 69 @ SL 456				4	8	1	8	4	8	4	8	4	12	0	0			
S 69 @ US 84			2	2	6	1	8	4	8	2	8	2	8	2	0			
S 79 @ FM 347	2		1		6	1	9	3	9	2	9	0	6	1	2			
IS 79 @ Austin St.	2				8	1	10	2	10	2	10	0	8	0	2			
M 347 @ US 175																Construction Pending; no work		
M 347 @ Commerce St.					8	1	8	0	8	0	8	0	8	0	0			
M 347 @ Larisa St.					8	1	8	0	8	0	8	0	8	0	0			
M 347 @ Tena St			2		6	1	8	2	8	0	8	0	6	2	0			
Cherokee Totals:	4	0	5	6	50	7	59	15	59	10	59	6	56	5	4			
CSJ 0910-00-137 PART 3 SUBTOTAL	4	0	5	6	50	7	59	15	59	10	59	6	56	5	4			

[1] Note: For Contractor's information only. Item 680 will not be paid for directly, but will be subsidiary to the various bid items.

# QUANTITY SUMMARY



FED.RD. DIV.NO.	FEDERAL	. AID PROJECT	NO.	SHEET NO.
6				6
STATE	DIST.		COUNTY	
TEXAS	TYLER	SM	IITH, ETC.	
CONT.	SECT.	JOB	HIGHWA	Y NO.
0910	00	137	VARI	OUS

SIGNAL SUMMARY PART 5 OF 5																	
		Existing a	ınd Proposed Signal	Head Arrangeme	ents		ITEM 680					ITEM 68	32				NOTES:
_	R Y YA GA G	RA YA YA GA	R Y GA G	RA YA GA	R R Y G	R Y G	INSTALL HWY		VEH SI (GRN		(YEL	(RED)		W/	ACK PLAT	DR	
LOCATION	111111111111111111111111111111111111111						TRF SIG (UPGRADE) [1]		ARW)		ARW)	1	ARW)		(4 SEC)		
	EA	EA	EA	EA	EA	EA	EA	EA	EΑ	EΑ	EΑ	EA	EΑ	EΑ	EA	EA	
Rusk County:																	
US 79 @ FM 225	4					8	1	12	4	12	4	12	0	8	0	4	
US 79 @ Jacksonville Dr.						6	1	6	0	6	0	6	0	6	0	0	
US 79 @ Walmart	2		2			6	1	10	4	10	2	10	0	6	2	2	
US 79 @ FM 3310/South Main St.	2		2				1	4	4	4	2	4	0	0	2	2	
US 79 @ US 259 (South)			2	3		6	1	8	5	8	3	8	3	9	2	0	
US 79 @ FM 840/East Main St.	4					8	1	12	4	12	4	12	0	8	0	4	
US 79 @ Webster Dr.	2					10	1	12	2	12	2	12	0	10	0	2	
US 79 @ US 259/SH 43/SH 64				5		11	1	11	5	11	5	11	5	16	0	0	
BU 79 @ Richardson Dr.	2					6	1	8	2	8	2	8	0	6	0	2	
BU 79 @ FM 13/BS 64 (Main St.)	4			5			1	4	9	4	9	4	5	5	0	4	
BU 79 @ BS 64/Marshall St.				2		6	1	6	2	6	2	6	2	8	0	0	
BU 259 @ SH 42 (Woodlawn St.)	1			1		8	1	9	2	9	2	9	1	9	0	1	
BU 259 @ Beckley St.			2	2		6	1	8	4	8	2	8	2	8	2	0	
US 259 @ SH 322	2		2			6	1	10	4	10	2	10	0	6	2	2	
US 259 @ Wylie Schools			6			2	1	8	6	8	0	8	0	2	6	0	
US 259 @ SH 315			5			2	1	7	5	7	0	7	0	2	5	0	
SH 64 @ Evenside St.	2		2			6	1	10	4	10	2	10	0	6	2	2	
SH 64 @ SH 323/BS 64	4					8	1	12	4	12	4	12	0	8	0	4	İ
SH 64 @ Longview Dr./Mill St.				2		8	1	8	2	8	2	8	2	10	0	0	
FM 13 @ Evenside St.	2		2			4	1	8	4	8	2	8	0	4	2	2	
Rusk Totals:	31	0	25	20	0	117	20	173	76	173	51	173	20	137	25	31	
										ĺ	İ	İ	İ	ĺ		İ	
CSJ 0910-00-137 PART 5 SUBTOTAL	31	0	25	20	0	117	20	173	76	173	51	173	20	137	25	31	
CSJ 0910-00-137 PART 1 SUBTOTAL	54	3	56	33	28	225	40	363	146	363	93	391	36	258	87	54	
CSJ 0910-00-137 PART 2 SUBTOTAL	17	2	20	13	0	72	11	109	52	109	34	109	15	85	22	17	
CSJ 0910-00-137 PART 3 SUBTOTAL	4	0	5	6	0	50	7	59	15	59	10	59	6	56	5	4	
CSJ 0910-00-137 PART 4 SUBTOTAL	57	14	39	20	0	268	39	364	130	364	105	364	34	288	53	57	
PROJECT TOTAL	163	19	1 45	92	28	732	117	1068	419	1068	293	1096	111	824	192	163	

[1] Note: For Contractor's information only. Item 680 will not be paid for directly, but will be subsidiary to the various bid items.

	BASIS OF ESTIMATE								
I LIEM I DESCRIPTION I RATE I LINIT I						PROJECT TOTAL	PAY UNIT		
500	MOBILIZATION		1.00	LS	1.00	1	LS		
502	BARRICADES, SIGNS AND TRAFFIC HANDLING		5.0	MO	5.0	5	MO		

PORTABLE CHANGEABLE MESSAGE SIGN							
		ITEM 6001					
SIGN	LOCATION	PORTABLE CHANGEABLE MESSAGE SIGN DAY					
#1	AS DIRECTED	30					
#2	AS DIRECTED	30					
CSJ 0910-0	0-137 SUBTOTAL	60					
PROJECT TO	TAL	60					

NOTE: UP TO TWO SIGNS ARE SHOWN. ADDITIONAL SIGNS MAY BE NEEDED IF WORKING ON MULTIPLE LOCATIONS AT A TIME.

TRUCK MOUNTED	TRUCK MOUNTED ATTENUATORS								
	ITEM 6185 ITEM 61								
STAGE OF PROJECT	NUMBER OF TRUCKS	TMA (STATIONARY) [3]	TMA (MOBILE)						
		DAY	DAY						
[1] LANE CLOSURE TCP AND TRAFFIC SIGNAL WORK	2	150							
[2]MOBILE OPERATIONS, AS NEEDED	2		10						
CSJ 0910-00-137 SUBTOTAL		150	10						
PROJECT TOTAL		150	10						

- [1] ESTIMATED NUMBER OF TRUCKS IS FOR TWO CREWS WORKING AT A TIME.
- [1][2] ADDITIONAL TRUCKS MAY BE REQUIRED IF WORKING AT MULTIPLE LOCATIONS.
- [2] MOBILE OPERATIONS ARE NOT EXPECTED
- [3] TMA FOR STATIONARY OPERATIONS MUST BE RELOCATED TO MULTIPLE LOCATIONS EACH DAY

# QUANTITY SUMMARY



				SL	JMMARY	3 /	3
FED. RD. DIV. NO.	FEDERAL	FEDERAL AID PROJECT NO.					
6						7	
STATE	DIST.		COUNTY				
TEXAS	TYLER	SN	TC.				
CONT.	SECT.	JOB	HI	GHWAY	/ NO.		
0910	00	137	V	AR I	OUS		

## BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

#### WORKER SAFETY NOTES:


- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

# COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

# THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




Safety Division Standard

# BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS

BC(1)-21

		• -	•	_				
FILE:	bc-21.dgn	DN: T	×D0T	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
C TxDOT	November 2002	CONT	SECT	SECT JOB HIGHWA		GHWAY		
4-03	REVISIONS 7-13	0910	00	137	137		VAR	
9-07 8-14 5-10 5-21		DIST		COUNTY			SHEET NO.	
		TYL	SMITH, ETC.			8		



- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- 5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

#### BEGIN T-INTERSECTION WORK ZONE ★ ★ G20-9TP ★ ★ R20-5T FINES DOUBLE X R20-50TP BORNERS ARE PRESENT ROAD WORK ⟨⇒ NEXT X WILES X X G20-2bT WORK ZONE G20-1bTI $\Diamond$ INTERSECTED 1000'-1500' - Hwy 1 Block - City 1000'-1500' - Hwy 1 Block - City ROADWAY $\Rightarrow$ ROAD WORK G20-1bTR NEXT X MILES => WORK ZONE G20-2bT \* \* Limit BEGIN G20-5T \* \* G20-9TP ZONE TRAFFI G20-6T \* \* R20-5T FINES DOUBLE ¥ × R20-5aTP #MEN #ORKERS ARE PRESENT ROAD WORK G20-2

# CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

# TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING 1,5,6

#### SIZE

	Posted Speed	Sign∆ Spacing "X"	
	MPH	Feet (Apprx.)	
	30	120	
	35	160	
	40	240	
1	45	320	
	50	400	
	55	500 <sup>2</sup>	
	60	600 <sup>2</sup>	
1	65	700 <sup>2</sup>	
	70	800 <sup>2</sup>	
	75	900 <sup>2</sup>	
	80	1000 <sup>2</sup>	
_	*	* 3	

SPACING

- Sign onventional Expressway/ Number Freeway or Series CW20' CW21 CW22 48" x 48" 48" x 48' CW23 CW25 CW1, CW2, CW7. CW8. 48" x 48' 36" x 36" CW9, CW11 CW14 CW3, CW4, CW5, CW6, 48" x 48" 48" x 48' CW8-3, CW10, CW12
- \* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- $\triangle$  Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

#### GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design

#### SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS X X G20-9TP SPEED STAY ALERT ROAD LIMIT R4-1 DO NOT PASS appropriate OBEY TRAFFIC ★ ★ R20-5T WORK FINES WARNING \* \* G20-5T ROAD WORK CW1-4L AHEAD DOUBL F SIGNS CW20-1D \* \* R20-5aTP ROAD STATE LAW TALK OR TEXT LATER CW13-1P R2-1 X > ROAD ★ ★ G20-6T WORK WORK G20-10T \* \* R20-3T X X AHEAD CONTRACTOR AHEAD Type 3 Barricade or WPH CW13-1P CW20-1D channelizing devices $\Diamond$ $\Diamond$ $\Leftrightarrow$ $\Diamond$ $\Rightarrow$ $\Rightarrow$ Beginning of NO-PASSING $\Rightarrow$ $\Rightarrow$ SPEED END G20-2bT X X R2-1 LIMIT line should $\otimes | \times \times$ FND coordinate ROAD WORK When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional with sign "ROAD WORK AHEAD"(CW20-1D)signs are placed in advance of these work areas to remind drivers they are still G20-2 X X location **NOTES** within the project limits. See the applicable TCP sheets for exact location and spacing of signs and SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS

DECTA

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- \*\* CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at the end of the work zone.

	LEGEND					
⊢⊣ Type 3 Barricade						
0	Channelizing Devices					
<b>þ</b>	Sign					
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.					

# SHEET 2 OF 12

Texas Department of Transportation

Traffic Safety

# BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC(2)-21

		. —	•	_			
LE:	bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>T×DOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	T×DOT	ck: TxDOT
TxD0T	November 2002	CONT	SECT	JOB		нІ	GHWAY
	REVISIONS	0910	00	137		٧	'AR
9-07	8-14 5-21	DIST	COUNTY			SHEET NO.	
7-13		TYL	SMITH, ETC.			9	

SAMEL LATOO! OF STORTING FOR WORK DEC	INITIO DOWNSTILLAM OF THE COULTINITIS	'   BEGIN	
ROAD CLOSED R11-2 CW1-4L CW13-1P XX MPH Contained or channelizing devices X	ROAD WORK AHEAD X X X X A 4 4 4 4	X XG20-9TP WORK ZONE STAY ALER	WARNING SIGNS
WORK SPACE &	END ROAD WORK	CSJ Limit  X  SPEED R2-1  LIMIT  WORK ZON	
	G20-2 × ×	X X	

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



# GUIDANCE FOR USE:

# LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

# SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

# GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:

40 mph and greater 0.2 to 2 miles

35 mph and less 0.2 to 1 mile

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to:
  A. Law enforcement.
  - B. Flagger stationed next to sign.
  - C. Portable changeable message sign (PCMS).
  - D. Low-power (drone) radar transmitter.
- E. Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only.
   Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12

Traffic Safety Division Standard



BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

		_		_			
ILE:	bc-21.dgn	DN: Tx[	)OT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		HIGHWAY	
	REVISIONS 8-14 5-21	0910	00	137		VAR	
9-07 7-13		DIST	COUNTY			SHEET NO.	
		TYL		SMITH, ETC.			10


DATE:

97

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS 12' min. ROAD ROAD ROAD ROAD WORK minimum WORK WORK WORK from AHEAD AHEAD AHEAD curb AHEAD min. \* \* XX 7.0' min. 7.0' min. 9.0' max. 6' or 7.0' min. 9.0' max. 6.0' min. greater 9.0' max. Paved Paved shou I der shoul de

> \* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\* \* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and


Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

> Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

# STOP/SLOW PADDLES

of at least the same gauge material.

- 1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectorized when used at night. 3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING RE	QUIREMENT	S (WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

# CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

SIDE ELEVATION

Wood

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports. the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZICD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

#### GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question reaardina installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

#### <u>DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)</u>

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
- Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
- Short, duration work that occupies a location up to 1 hour.
- Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

#### SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plagues mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

#### SIZE OF SIGNS

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

#### SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

# REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background. 3. Orange sheeting, meeting the requirements of DMS-8300 Type  $B_{FL}$  or Type  $C_{FL}$ , shall be used for rigid signs with orange backgrounds.

# SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

# REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.

# Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

# SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular
- impact. Rubber (such as tire inner tubes) shall NOT be used. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured
- with rubber bases may be used when shown on the CWZTCD list. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or
- hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

# FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12


Traffic Safety Division Standard




# BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21


LE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
TxD0T	November 2002	CONT SECT		JOB		HIGHWAY		
	REVISIONS 8-14 5-21	0910	00	137		V	VAR	
9-07		DIST	COUNTY		SHEET NO.			
7-13		TYI	SMITH ETC			11		





# GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



32′

# WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

# OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

## GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
  - ★ See BC(4) for definition of "Work Duration."
  - Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

# SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

Traffic Safety Division Standard

BC(5)-21

		_		_			
FILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB		H10	SHWAY
	REVISIONS	0910	00	137		V	AR
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	TYL		SMITH. E	TC		12

<u>SKID</u>	MOUNTED	PERFORATED	SQUARE	STEEL	<u>TUBING</u>	<u>SIGN</u>	<u>SUPPORTS</u>	
'								

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

weld starts here

SINGLE LEG BASE

Side View

#### PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit romp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Nor thbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	F	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
	EMER	Slippery	SL IP
Emergency		South	S
Emergency Vehicle	ENT	Southbound	(route) S
Entrance, Enter	EXP LN	Speed	SPD
Express Lane	EXP LN EXPWY	Street	ST
Expressway	XXXX FT	Sunday	SUN
XXXX Feet		Telephone	PHONE
Fog Ahead	FOG AHD FRWY. FWY	Temporary	TEMP
Freeway		Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving		Travelers	TRVLRS
Hazardous Material		Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway	HR. HRS	Vehicles (s)	VEH, VEHS
Hour (s)		Warning	WARN
Information	INFO	Wednesday	WED
It Is	ITS	Weight Limit	WT LIMIT
Junction	JCT	West	W
Left	LFT	Westbound	(route) W
Left Lane	LFT LN	Wet Pavement	WET PVMT
Lane Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL		
Maintenance	MAINT		

## Roadway

designation # IH-number, US-number, SH-number, FM-number

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

# Phase 1: Condition Lists

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT

# Phase 2: Possible Component Lists

Action to Take/E <sup>.</sup> Lis		Location List	Warning List	* * Advance Notice List
MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- XX X PM-X AM
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE	NEXT TUE AUG XX
USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM- XX AM
STAY IN LANE *		* * See	Application Guidelin	es Note 6.

#### APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase

- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

# WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- 7. FT and MI, MILE and MILES interchanged as appropriate.
  8. AT. BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4)

PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


#### FULL MATRIX PCMS SIGNS

BLVD

CLOSED

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

# SHEET 6 OF 12




Traffic Safety Division Standard

# PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) -21


FILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C TxDOT	November 2002	CONT	SECT	JOB		Н	IGHWAY
	REVISIONS	0910	00	137		,	/AR
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	TYL		SMITH, E	TC.		13

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of pregualified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1). 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



# CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- 4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10. Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer
- 11. Single slope barriers shall be delineated as shown on the above detail.



LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.


LOW PROFILE CONCRETE

BARRIER (LPCB) USED

IN WORK ZONES

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

# LOW PROFILE CONCRETE BARRIER (LPCB)




# DELINEATION OF END TREATMENTS

# END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH), Refer to the CWZTCD List for approved end treatments and manufacturers.

# BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

# Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

# WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type  $B_{FL}$  or  $C_{FL}$  Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

# WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- 5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.


# WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.

  2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions
- or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- 4. The Flashing Arrow Board should be able to display the following symbols:



- 5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- 8. Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.

  9. The sequential arrow display is NOT ALLOWED.

  10. The flashing arrow display is the TxDOT standard; however, the sequential chevron
- display may be used during daylight operations.
- 11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
  12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
  13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility,
- flash rate and dimming requirements on this sheet for the same size arrow. 14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway
- to bottom of panel.

	REQUIREMENTS									
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE							
В	30 × 60	13	3/4 mile							
С	48 × 96	15	1 mile							

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE
TRAFFIC BARRIER OR GUARDRAIL.

# FLASHING ARROW BOARDS

SHEET 7 OF 12

#### TRUCK-MOUNTED ATTENUATORS

- 1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted in the plans.
- 5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION ARROW PANEL. REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC(7)-21

FILE:	bc-21.dgn	DN: T	×D0T	ck: TxDOT	DW:	TxDOT	ck: TxDO
① TxD0T	November 2002	CONT	SECT	JOB		HIO	CHWAY
REVISIONS		0910	00	137		V	AR
9-07	8-14	DIST	COUNTY				SHEET NO.
7-13	5-21	TYI	SMITH ETC				14

# GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Monual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

#### GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:

- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- to be held down while separating the drum body from the base.


  8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Drum and base shall be marked with manufacturer's name and model number.


# RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

#### BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.





## DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or shorp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub>Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12


Texas Department of Transportation

Traffic Safety Division Standard

# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES


BC(8)-21

LE: bc-21.dgn	DN: T>	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
TxDOT November 2002	CONT	SECT	JOB		HIC	SHWAY	
REVISIONS  -03	0910	00	137		V	VAR	
-03	DIST	COUNTY SH				SHEET NO.	
'-13	TYI	SMITH ETC 15					




- 1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
   Self-righting supports are available with portable base.
- Self-righting supports are available with portable base See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

# VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42"
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type  $B_{FL}$  or Type  $C_{FL}$  conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

# CHEVRONS

#### **GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



#### LONGITUDINAL CHANNELIZING DEVICES (LCD)

36"

Fixed Base w/ Approved Adhesive

(Driveable Base, or Flexible

Support can be used)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

#### WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	D	Minimur esirab er Len **	le	Suggested Maximum Spacing of Channelizing Devices		
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	2	150′	1651	1801	30'	60′	
35	$L = \frac{WS^2}{60}$	2051	2251	2451	35′	70′	
40	80	265′	295′	320′	40′	80′	
45		450′	495′	540′	45′	90′	
50		500′	550′	6001	50`	100′	
55	L=WS	550′	6051	660′	55 <i>°</i>	110′	
60	- 113	600'	660′	720′	60′	120′	
65		650′	715′	7801	65′	130′	
70		700′	770′	840′	70′	140′	
75		750′	8251	900′	75′	150′	
80		8001	880′	960′	80′	160′	

\*\*X\*Toper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

# SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Traffic Safety Division Standard


# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) -21


		_		_			
ILE:	bc-21.dgn	DN: T	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		HIC	HWAY
REVISIONS		0910	00	137		V	AR
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	TYL		SMITH. E	TC.		16

#### TYPE 3 BARRICADES

- 1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- 2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- 5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- 6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- Warning lights shall NOT be installed on barricades.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The  $\,$ sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




# TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

# TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION


1. Where positive redirectional capability is provided, drums may be omitted. 2. Plastic construction fencing may be used with drums for safety as required in the plans. 3. Vertical Panels on flexible support may be substituted for drums when the Typical shoulder width is less than 4 feet. Plastic Drum 4. When the shoulder width is greater than 12 feet. steady-burn lights PERSPECTIVE VIEW may be omitted if drums are used. 5. Drums must extend the length These drums are not required of the culvert widening. on one-way roadway LEGEND Plastic drum Plastic drum with steady burn light um of two drums s locross the work or yellow warning reflector Steady burn warning light or yellow warning reflector Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums) PLAN VIEW

**CONES** 4" min. orange ₹2" min. 1 4" min. white 2" min. 4" min. orange [6" min. \_2" min. 2" min. \**1**4 min. 4" min. white 42" min. 28' min.

Two-Piece cones




One-Piece cones



CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- 1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- 2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base. or ballast, that is added to keep the device upright and in place.
- 3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- 7. Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12



Texas Department of Transportation

# BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

Traffic Safety Division Standard

BC(10)-21

			-	_			
ILE:	bc-21.dgn	DN: T	×D0T	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT	November 2002	CONT	SECT	JOB		HIG	YAWH
REVISIONS		0910	00	137		V	AR
9-07	8-14 5-21	DIST		COUNTY		9	SHEET NO.
7-13	3-21	TYL		SMITH. E	TC.		17

# WORK ZONE PAVEMENT MARKINGS

# **GENERAL**

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard povement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

# RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

#### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


#### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per

#### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10. Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

# Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

## RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
YELLOW - (two amber reflective surfaces with yellow body).
WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIO	NS
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


	• •	- 7				
E: bc-21.dgn	DN: T>	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT February 1998	CONT	SECT	JOB		Н	IGHWAY
REVISIONS -98 9-07 5-21	0910	00	137			VAR
·98 9-07 5-21 ·02 7-13	DIST	COUNTY SHEET		SHEET NO.		
02 8-14	TYL		SMITH, E	TC		18

DATE:


105


#### PAVEMENT MARKING PATTERNS 10 to 12" Type II-A-An 1 Q O O O O O O O O O ₹> `Yellow -Type Y buttons RAISED PAVEMENT MARKERS - PATTERN A REFLECTORIZED PAVEMENT MARKINGS - PATTERN A Type II-A-A <>> □وہ/ہ □ ہ ہ ہ اُ ہ ہ 4 to 8" Type Y Type II-A-Abuttons-REFLECTORIZED PAVEMENT MARKINGS - PATTERN B RAISED PAVEMENT MARKERS - PATTERN B Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings. CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE. TWO-WAY HIGHWAYS Type I-C Type W buttons-Type I-C or II-C-R 0000 00000 0000 Yellow Type I-A Type Y buttons ₹> Yellow White 0000 Type W buttons-└Type I-C or II-C-R REFLECTORIZED PAVEMENT MARKINGS RAISED PAVEMENT MARKERS Prefabricated markings may be substituted for reflectorized pavement markings. EDGE & LANE LINES FOR DIVIDED HIGHWAY Type I-C Type W buttons-0000**0** 0000 0000 White ↗ Type II-A-A Type Y buttons ➪ ₹> 0000 Type W buttons-RAISED PAVEMENT MARKERS REFLECTORIZED PAVEMENT MARKINGS Prefabricated markings may be substituted for reflectorized pavement markings. LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS Type W buttons Type I-C-Type 0 0 0 ➪ ₹> 0000 0000 Type W buttons~ └Type I-C REFLECTORIZED PAVEMENT MARKINGS RAISED PAVEMENT MARKERS Prefabricated markings may be substituted for reflectorized pavement markings.

TWO-WAY LEFT TURN LANE









	LEGEND						
	Type 3 Barricade	••	Channelizing Devices				
	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)				
Ê	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)				
-	Sign	♡	Traffic Flow				
$\Diamond$	Flag	9	Flagger				

Posted Speed	Formula	Minimum Desirable Taper Lengths ***		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	-B-	
30	2	150′	1651	180'	30′	60′	120'	90,	2001
35	L = \frac{\WS^2}{60}	2051	225'	2451	35′	70′	160'	120′	250'
40	6	265'	2951	3201	40′	80'	240'	155′	3051
45		450'	4951	5401	45′	90'	320'	195′	360'
50		500′	550′	6001	50'	100′	4001	240'	4251
55	L=WS	5501	6051	660,	55′	110'	500′	295′	495'
60	L-#3	600,	660'	720'	60′	1201	600'	350′	570′
65		6501	7151	780′	65′	1301	700′	410'	6451
70		7001	770'	8401	701	140′	800,	475′	730′
75		750′	8251	9001	75′	150′	900'	540′	820′

\* Conventional Roads Only

\*\* Taper lengths have been rounded off.

L=Length of Taper (FT) W:Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
	1	1				

#### GENERAL NOTES

- 1. Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be amitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- 4. Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

# TCP (1-2a)

- 7. R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-20P "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

#### TCP (1-2b

- 9. Flaggers should use two-way radios or other methods of communication to control traffic.
- 10. Length of work space should be based on the ability of flaggers to communicate.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- 12. Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
   13. Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be
- Flaggers should use 24 S10P/SLOW paddles to control traffic. Flags should be limited to emergency situations.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP(1-2)-18

FILE: tcp1-2-18.dgn	CN:		CK:	DW:	CK:
CTxDOT December 1985	CONT	SECT	108		HIGHWAY
REVISIONS 4-90 4-98	0910	00	137		VAR
2-94 2-12	DIST		COUNTY		SHEET NO.
1-97 2-18	TYL		SMITH, E	TC.	21



SIGNAL WORK AHEAD

CW20SG-1

SIGNAL WORK AHEAD

CW20SG-1

 $\triangle$ 

 $\Box$ 

 $\Diamond$ 

NEAR SIDE LANE CLOSURE

SHORT DURATION OR SHORT TERM STATIONARY

⇧

| 4

R4-7 24" × 30"

 $\Diamond$ 

 $\triangle$ 

CW20SG-1

10' min.

Typical

SIGNAL WORK AHEAD

CW20SG-1 48" x 48"

1/2 L

|♡|�

SIGNAL WORK AHEAD

CW20SG-1

-See Note 8

LANE CLOSE

CW20-5TR

SIGNAL WORK AHEAD

CW20SG-1 48" × 48

SIGNAL WORK AHEAD

CW20SG-1

OPERATIONS IN THE INTERSECTION

CW20SG-1 48" x 48"

10' min.

1/2L

 $\Diamond$ 

R4-7

24" x 30'


Х

Typical

WORK

CW20SG-1 48" x 48"

See Note



	LEGEND							
		Type 3 Barricade	00	Channelizing Devices				
		Heavy Work Vehicle		Truck Mounted Attenuator (TMA)				
ĺ		Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)				
	<b>ŀ</b>	Sign	♡	Traffic Flow				
<	$\nabla$	Flag	4	Flagger				

Posted Speed	Formula	Desirable		Spacin Channe		Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"В"
30	, <u>ws²</u>	150′	1651	180′	30'	60′	120'	90′
35	L = WS	2051	2251	245'	35′	70′	160′	120′
40	80	265′	295′	3201	40'	80′	240'	155′
45		450′	4951	540′	45'	90′	320′	195′
50		5001	550′	600,	50′	100′	400′	240′
55	L=WS	550′	6051	660′	55′	110'	500′	295′
60	L-113	600′	660′	720′	60′	120'	600′	350′
65		650′	715′	780′	65′	130′	700′	410'
70		7001	770′	840'	70′	140′	8001	475′
75		750′	825′	9001	75′	150'	900'	540′


\*\* Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.

# GENERAL NOTES

- 1. The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.
- 2. Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- 4. Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- 5. High level warning devices (flag trees) may be used at corners of the vehicle.
- 6. When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P)
- 7. For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- 8. The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.



SIGNAL WORK AHEAD

CW20SG-1

24" × 30"

signs may be implemented when approved by the engineer.

Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.

SHEET 1 OF 2




Traffic Operations Division Standard

# TRAFFIC SIGNAL WORK TYPICAL DETAILS

WZ(BTS-1)-13

.E: wzbts-13.dgn	DN: TxDOT		ck: TxDOT	DW:	TxDOT	ck: TxDOT
TxDOT April 1992	CONT SECT JOB HIG		SHWAY			
REVISIONS	0910	00	137		V	AR
98 10-99 7-13	DIST	DIST COUNTY				SHEET NO.
98 3-03	TYL	TYL SMITH, ETC.				22



# GENERAL NOTES FOR WORK ZONE SIGNS

- Signs shall be installed and maintained in a straight and plumb condition.  $% \left( 1\right) =\left( 1\right) +\left( 1\right)$
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- Nails shall NOT be used to attach signs to any support.
- All signs shall be installed in accordance with the plans or as directed by the Engineer.
- The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).
- The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.
- Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as directed by the Engineer.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".
- Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

## DURATION OF WORK

Work zone durations are defined in Part 6, Section 6G.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

# SIGN MOUNTING HEIGHT

- Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.
- Sign height of Short-term/Short Duration warning signs shall be as shown on Figure 6F-2 of the TMUTCD.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

# REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.  $\,$
- Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

# REFLECTIVE SHEETING

All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

## SIGN SUPPORT WEIGHTS

- Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber, such as tire inner tubes, shall not be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fastners. Sandbags shall be placed along the length of the skids to weigh down the
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.


LEGEND					
-	Sign				
	Channelizing Devices				
	Type 3 Barricade				

DEPARTMENTAL MATERIAL	SPECIFICATIONS
SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
WHITE	BACKGROUND	TYPE A SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:

http://www.txdot.gov/txdot\_library/publications/construction.htm



Temporary Traffic Barrier

See Note 4 below

- Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.
- "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic
- substrates, they may be mounted on top of a plastic drum at or near the location shown. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9)
- and manufacturer's recommendations. Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.
- Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.
- The width of existing sidewalk should be maintained if practical.
- Pavement markings for mid-block crosswalks shall be paid for under the appropriate bid items.
- When crosswalks or other pedestrian facilities are closed or relocated. temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian





TRAFFIC SIGNAL WORK BARRICADES AND SIGNS

WZ(BTS-2)-13

Operation Division Standard

CW2OSG-

SIGNA

			_	_		_	
FILE:	wzbts-13.dgn	DN: T>	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT	April 1992	CONT	SECT	JOB		H10	GHWAY
	REVISIONS	0910	00	137		V	AR
2-98 10-		DIST		COUNTY			SHEET NO.
4-98 3-	03	TYL		SMITH. E	TC		23

 $\Diamond$ 

WZ (RS-1a)

RUMBLE STRIPS ON ONE-LANE

TWO-WAY APPLICATION

Warning sign

TABLE 1

< 4,500

> 4,500

3,500

> 3,500

< 2,600

<u>></u> 2,600

< 1,600

<u>></u> 1,600

N/A

RUMBLE

AHEAD,

ROAD

WORK AHEAD CW17-2T

48" X 48"

CW20-1D 48" X 48"

(See note 2)

# of Rumble

Strip

Arrays


2

2

1

2

2



# **GENERAL NOTES**

- 1. Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- 2. The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- 3. Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control
- 4. Remove Temporary Rumble Strips before removing the advanced warning signs.
- 5. Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- 6. Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- 7. This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- 9. Replace defective Temporary Rumble Strips as directed by the Engineer.
- 10. Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

	LEGEND					
	Type 3 Barricade	■ ■ Channelizing Device				
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)			
<b>E</b>	Trailer Mounted Flashing Arrow Panel	M	Portable Changeable Message Sign (PCMS)			
-	Sign	₽	Traffic Flow			
$\Diamond$	Flag	ПO	Flagger			

Posted Speed	Formula	Minimum Desirable Taper Lengths **		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	ws <sup>2</sup>	150′	1651	1801	30′	60′	1201	90′
35	L = WS	2051	225′	2451	35′	70′	160′	120′
40	8	2651	2951	3201	40'	80′	240'	155′
45		450′	495′	540'	45′	90′	320'	195′
50		500′	550′	6001	50°	100′	4001	240′
55	L=WS	550′	6051	660'	55′	110′	500′	295′
60	L - # 3	600'	660′	720′	60′	120′	600'	350′
65		650′	715′	780′	65′	130′	700′	410'
70		700′	770′	840′	70′	140′	800'	475′
75		750′	825′	900′	75′	150′	900′	540′

- \* Conventional Roads Only
- \*\* Taper lengths have been rounded off. L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed (MPH)

TYPICAL USAGE					
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY	
	✓	✓			

- Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.
- For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

TABLE 2					
Speed	Approximate distance between strips in an array				
<u>&lt;</u> 40 MPH	10′				
> 40 MPH & <u>&lt;</u> 55 MPH	15′				
= 60 MPH	20′				
<u>&gt;</u> 65 MPH	<del>*</del> 35′+				

*
Texas Department of Transportation

TEMPORARY RUMBLE STRIPS

Traffic Safety Division Standard

WZ (RS) -22

FILE: WZ	zrs22.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
€ TxDOT No	ovember 2012	CONT	SECT	JOB		HIC	GHWAY
		0910	00	137		V	٩R
2-14 1-2 4-16	22	DIST		COUNTY			SHEET NO.
4-10		TYL	5	SMITH, E	TC.		24

## GENERAL NOTES FOR ALL ELECTRICAL WORK

- The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
- 2. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
- 3. Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is  $\frac{1}{2}$  in. or less in diameter.
- 4. Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
- 5. Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
- 6. When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

# CONDUIT

# A. MATERIALS

- 1. Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies. Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
- 2. Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
- 3. Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.

AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" × 8" × 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" × 8" × 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" × 8" × 4"	8" × 8" × 4"	10" x 10" x 4"
#8	8" × 8" × 4"	8" × 8" × 4"	8" × 8" × 4"

- 4. Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
- 5. Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
- 6. Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
- 7. Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

- 8. Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
- 9. When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
- 10. Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.
- B. CONSTRUCTION METHODS
- 1. Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
- 2. Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
- 3. Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
- 4. Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
- 5. When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
- 6. Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
- 7. During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
- 8. Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
- 9. Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
- 10. Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
- 11. At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
- 12. Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
- 13. Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
- 14. File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing," Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.





# ELECTRICAL DETAILS CONDUITS & NOTES

Operation: Division Standard


ED(1)-14

:	ed1-14.dgn	DN:		CK:	DW:		CK:
TxDOT	October 2014	CONT	SECT	JOB		н	SHWAY
	REVISIONS	0910	00	137		٧	AR
		DIST	COUNTY			SHEET NO.	
		TYL		SMITH. E	TC.		25






# FOUR-SECTION HEAD HORIZONTAL OR VERTICAL




# **GENERAL NOTES:**

- 1. Backplates are optional for traffic signals and pedestrian hybrid beacons. When backplates are used, a 2-inch wide fluorescent yellow AASHTO Type BFL or CFL retroreflective border conforming to TxDOT DMS-8300 is required. Place on all approaches when used.
- 2. Signal head and backplate compatability must be verified by the contractor prior to installation.
- 3. When using backplates on signal heads, venting is preferred to reduce cyclic vibration stress.
- 4. When a vented backplate is used, the retroreflective border must not be placed over the louvers.
- 5. This standard sheet applies to all signal heads with backplates, including but not limited to:
  - Pole mounted
  - Overhead mounted
  - Span wire mounted
  - Mast arm mounted
  - Vertical signal heads
  - Horizontal signal heads
  - Clustered signal heads
  - Pedestrian hybrid beacons




HORIZONTAL OR VERTICAL

HORIZONTAL OR VERTICAL



**CLUSTER** 



PEDESTRIAN HYBRID **BEACON** 

border

TRAFFIC SIGNAL HEAD WITH BACKPLATE

Texas Department of Transportation

TS-BP-20

Traffic Safety Division Standard

	υ.		_			
FILE: ts-bp-20.dgn	DN: Tx	DOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxDOT June 2020	CONT	SECT	JOB		н	I] GHWAY
REVISIONS	0910	00	137		'	/AR
	DIST		COUNTY			SHEET NO.
	TYL		SMITH, E	TC.		26

# STORMWATER POLLUTION PRVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For projects with less than one acre of soil disturbing activity and that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

# 1.0 SITE/PROJECT DESCRIPTION

# 1.1 PROJECT CONTROL SECTION JOB (CSJ):

0910-00-137

# 1.2 PROJECT LIMITS:

From: Signalized intersections in Smith, Wood, Gregg, Cherokee,

To: and Rusk counties

# 1.3 PROJECT COORDINATES:

BEGIN: (Lat)31.506612 ,(Long)-95.735127

END: (Lat)32.837968 \_,(Long)<u>-96.0762</u>18

1.4 TOTAL PROJECT AREA (Acres): 6.2 for 117 sites

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.0

# 1.6 NATURE OF CONSTRUCTION ACTIVITY:

Replacing signal heads

# 1.7 MAJOR SOIL TYPES:

Soil Type	Description
N/A	Project spans five counties

# 1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below: ☐ PSLs determined during preconstruction meeting

PSLs determined during construction

X No PSLs planned for construction

Туре	Sheet #s			
N/A	N/A			

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

# 1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

X Mobilization

- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment Excavate and prepare subgrade for proposed pavement
- widenina
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- ☐ Place flex base
- ☐ Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- X Other: Update if project scope changes to require soil disturbing activities. None planned at this time.

Other:		

Other:		

# 1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- X Fuels, oils, and lubricants from construction vehicles, equipment,
- Solvents, paints, adhesives, etc. from various construction
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Discharges from concrete washout activities, runoff from concrete cutting activities, and other concrete related activities
- X Other: Update if project scope changes to require soil

disturbing a	ctivities.	None planned at	this time.
□ Other			

□ Other:			

# 1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

I ributaries	Classified waterbody
Wood County Locations:	
Smith County Locations:	TBD if earthwork is added.
Cherokee County Locations:	
Gregg County Locations:	
Rusk County Locations:	

\* Add (\*) for impaired waterbodies with pollutant in ().

#### 1.12 ROLES AND RESPONSIBILITIES: TxDOT

- X Development of plans and specifications
- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations

Otner:			

# 1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

X Day To Day Operational Control

X Maintain schedule of major construction activities

X Install, maintain and modify BMPs

☐ Other:	,	
☐ Other:		



# STORMWATER POLLUTION **PREVENTION PLAN (SWP3)** (Less Than 1 Acre)



July 2023 Sheet 1 of 2

Texas Department of Transportation

FED. RD. DIV. NO.			PROJECT NO.		SHEET NO.
					27
STATE		STATE DIST.	C	COUNTY	
TEXAS	S	TYL	SMI	TH, ETC.	
CONT		SECT	IOB	HICHWAY N	NO.

DIV. NO.			PROJECT NO.		NO.
					27
STATE		STATE DIST.	C	OUNTY	
TEXAS	5	TYL	SMI	TH, ETC.	
CONT.		SECT.	JOB	HIGHWAY N	10.
0910	)	00	137	VAR	

# STORMWATER POLLUTION PRVENTION PLAN (SWP3):

# 2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

	OSION CONTROL AND SOIL ABILIZATION BMPs:
T/P	
□ X Pr	otection of Existing Vegetation
□ □ Ve	egetated Buffer Zones
	il Retention Blankets
	eotextiles
	ulching/ Hydromulching
	il Surface Treatments
	emporary Seeding
	ermanent Planting, Sodding or Seeding
	odegradable Erosion Control Logs
	ock Filter Dams/ Rock Check Dams
	ertical Tracking
	erceptor Swale
│ □ □ Ri <sub>l</sub>	prap version Dike
	emporary Pipe Slope Drain
	nbankment for Erosion Control
	aved Flumes
□ X Ot	her: Update if project scope changes.
□ □ Ot	her:
□ □ Ot	her:
□ □ Otl	her:
2.2 SED	IMENT CONTROL BMPs:
T/P	
□ □ Bio	odegradable Erosion Control Logs
□ □ De	watering Controls
	et Protection
	ck Filter Dams/ Rock Check Dams
	ndbag Berms
	diment Control Fence
	abilized Construction Exit
	pating Turbidity Barrier
	getated Buffer Zones
	getated Filter Strips
	her: Update if project scope changes.
□ □ Otl	her:
□ □ Otl	her:
□ □ Otl	her:
	the Environmental Layout Sheets/ SWP3 Layout She
∣ located i	n Attachment 1.2 of this SWP3

# 2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

Type	Stationing			
Туре	From	То		
I/A				
Refer to the Environmental Layocated in Attachment 1.2 of this		3 Layout She		

# 2.4 OFFSITE VEHICLE TRACKING CONTROLS:

Excess dirt/mud on road removed daily

☐ Haul roads dampened for dust control				
☐ Loaded haul trucks to be covered with tarpaulin				
☐ Stabilized construction exit☐ Daily street sweeping				
X Other: N/A				
□ Other:				
□ Other:				
Othor				

# 2.5 POLLUTION PREVENTION MEASURES:

- □ Chemical Management
- ☐ Concrete and Materials Waste Management
- X Debris and Trash Management
- □ Dust Control
- Sanitary Facilities
- X Other: Update if project scope changes.

Other:			
□ Other:			

# **2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Turno	Stationing		
Туре	From	То	
Preserve all existing vegetation.			

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

# 2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

# 2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

# 2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

# 2.10 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

## Note:

For the current scope of work, this project does not require an SWP3. These SWP3 sheets will be updated accordingly if the project scope changes in a way that requires an SWP3 to be developed.



# STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)



July 2023 Sheet 2 of 2

Texas Department of Transportation


ED. RD. IV. NO.	PROJECT NO.				SHEET NO.
				28	
STATE		STATE DIST.	COUNTY		
TEXAS	ò	TYL	SMITH, ETC.		
CONT.		SECT.	JOB	HIGHWAY N	١0.
0910		00	137	VAR	

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

	TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit		General (applies to all projects):
	required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.	Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease	Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are
	List MS4 Operator(s) that may receive discharges from this project.	work in the immediate area and contact the Engineer immediately.	provided with personal protective equipment appropriate for any hazardous materials used.
use.	They may need to be notified prior to construction activities.	No Action Required	Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing
÷		Action No.	compounds or additives. Provide protected storage, off bare ground and covered, for
ē	2.	1. See above guidance for accidental discovery of cultural resources	products which may be hazardous. Maintain product labelling as required by the Act.  Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS.
ing fi	☐ No Action Required ☐ ☐ Required Action  Action No.	2.	In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator
result	Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000 if applicable	3.	immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.
sabou	accordance with trues rethirt tak isoood it appircable	4.	Contact the Engineer if any of the following are detected:  * Dead or distressed vegetation (not identified as normal)
or dan		IV. <u>VEGETATION RESOURCES</u>	<ul> <li>* Trash piles, drums, canister, barrels, etc.</li> <li>* Undesirable smells or odors</li> <li>* Evidence of leaching or seepage of substances</li> </ul>
st Ins		Preserve native vegetation to the extent practical.  Contractor must adhere to Construction Specification Requirements Specs 162,	Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?
ot res		164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.	Yes X No
corre	II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER	No Action Required	If "No", then no further action is required. If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.
for in	USACE Permit required for filling, dredging, excavating or other work in any	Action No.	Are the results of the asbestos inspection positive (is asbestos present)?  Yes No
ە ك	water bodies, rivers, creeks, streams, wetlands or wet areas.	1. NO ACTION REQUIRED BEYOND ABOVE-MENTIONED SPECS	If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with
ormats	The Contractor must adhere to all of the terms and conditions associated with the following permit(s):	2.	the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.
ther f	No Permi⁺ Required	3.	If "No", then TxDOT is still required to notify DSHS 15 working days prior to any
0 0t p.	Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)	4.	scheduled demolition.  In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and
nda	☐ Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)		asbestos consultant in order to minimize construction delays and subsequent claims.
is sto	☐ Individual 404 Permit Required ☐ Other Nationwide Permit Required: NWP#	V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES	Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:
÷		AND MIGRATORY BIRDS.	⋈ No Action Required
٥	Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation		Action No.
	and post-project TSS.	☐ No Action Required ☐ ☐ Required Action	1.
	1.	Action No.	
		. ADJEDE TO DIDECTION CONCEDNING MICDATORY DIDEC	2.
	2.	1. ADHERE TO DIRECTION CONCERNING MIGRATORY BIRDS	3.
	3.	2. LISTED BELOW	VII. OTHER ENVIRONMENTAL ISSUES
	4.	3.	(includes regional issues such as Edwards Aquifer District, etc.)
	The elevation of the ordinary high water marks of any areas requiring work		
	to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.	4.	Action No.
	Best Management Practices:	If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The	1.
	Erosion Sedimentation Post-Construction TSS	work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes	2.
	☐ Temporary Vegetation ☐ Silt Fence ☐ Vegetative Filter Strips	are discovered, cease work in the immediate area, and contact the	Design Division
	☐ Blankets/Matting ☐ Rock Berm ☐ Retention/Irrigation Systems	Engineer immediately.	Texas Department of Transportation Standard
	☐ Mulch ☐ Triangular Filter Dike ☐ Extended Detention Basin		ENVIRONMENTAL PERMITS,
	☐ Sodding ☐ Sand Bag Berm ☐ Constructed Wetlands	LIST OF ABBREVIATIONS	
	☐ Interceptor Swale ☐ Straw Bale Dike ☐ Wet Basin	BMP: Best Management Practice SPCC: Spill Prevention Control and Countermeasure	ISSUES AND COMMITMENTS
	☐ Diversion Dike ☐ Brush Berms ☐ Erosion Control Compost	CCP: Construction General Permit SW3P: Storm Water Pollution Prevention Plan DSHS: Texas Department of State Health Services PCN: Pre-Construction Notification	- EDIC
	☐ Erosion Control Compost ☐ Erosion Control Compost ☐ Mulch Filter Berm and Socks	FHWA: Federal Highway Administration PSL: Project Specific Location	EPIC
	Mulch Filter Berm and Socks	MOU: Memorandum of Understanding TPDES: Texas Pollutant Discharge Elimination System MS4: Municipal Separate Stormwater Sewer System TPWD: Texas Parks and Wildlife Department	FILE: epic.dgn   DN: TXDOT   CK: RG   DW: VP   CK: AR
	Stone Outlet Sediment Traps Sand Filter Systems	MBTA: Migratory Bird Treaty Act  TXD0T: Texas Department of Transportation  NOT: Notice of Termination  TXE: Threatened and Endangered Species	© TXDOT: February 2015 CONT SECT JOB HIGHWAY  12-12-2011 (DS) REVISIONS 0910 00 137 VA
ILE:	Sediment Basins Grassy Swales	NWP: Notice of Intent  WSACE: U.S. Army Corps of Engineers  NOI: Notice of Intent  USFWS: U.S. Fish and Wildlife Service	05-07-14 ADDED NOTE SECTION IV. DIST COUNTY SHEET NO.
ш		The second of th	01-63-2015 SECTION I CHANGED TIEM 1122 TYL SMITH, ETC 29

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

III. CULTURAL RESOURCES




TEMP. EROSION

R. O. W.

ADDITIONAL UPSTREAM

STAKES FOR HEAVY RUNOFF EVENTS

CONTROL LOG



TEMP. EROSION

COMPOST CRADLE


UNDER EROSION

CONTROL LOG

CONTROL LOG

#### STAKE ON DOWNHILL SIDE OF LOG AT 8' (ON CENTER) MAX. AS NEEDED TO SECURE LOG, (TYP.) OR AS DIRECTED BY THE ENGINEER. R. O. W. TEMPORARY EROSION CONTROL LOG FLOW DISTURBED AREA SECURE END BACK OF CURB OF LOG TO STAKE AS DIRECTED LIP OF GUTTER ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS

# PLAN VIEW



EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

# (CL-ROW

# **GENERAL NOTES:**

- 1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S RECOMMENDATIONS. OR AS DIRECTED BY THE ENGINEER.
- 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
- UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS. USE RECYCLABLE CONTAINMENT MESH.
- FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
- STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
- 6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
- COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
- SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
- TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE
- 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

# SECTION A-A EROSION CONTROL LOG DAM




# LEGEND

CL-D — EROSION CONTROL LOG DAM

CONTROL LOG

- -(cl-boc)- EROSION CONTROL LOG AT BACK OF CURB
- (CL-ROW) EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING -(CL-SST
- EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING (CL-SSL)
- —(CL-DI - EROSION CONTROL LOG AT DROP INLET
- $\cdot($  <code>CL-CI</code>  $)\!-$  <code>EROSION CONTROL LOG AT CURB INLET</code>
- ackslashCL-GIackslashEROSION CONTROL LOG AT CURB & GRATE INLET



SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB

(CL-BOC)

REBAR STAKE DETAIL

# SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.


The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets
- 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS


SHEET 1 OF 3



TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES **EROSION CONTROL LOG** 

EC(9) - 16

DN:TxDOT CK: KM DW: LS/PT CK: LS ILE: ec916 C) TxDOT: JULY 2016 CONT SECT JOB 0910 00 137 VAR SMITH, ETC 30



STAKE NOTCH DETAIL

**EROSION CONTROL LOG** 

EC(9) - 16

CONT SECT

0910 00

FILE: ec116 C TxDOT: JULY 2016 DN:TxDOT CK: KM DW: LS/PT CK: LS

VAR 31

JOB

137

SMITH, ETC.

2"

3"

4"

5"


8"


12"

18"

# (CL - G I)-

# EROSION CONTROL LOG AT CURB & GRADE INLET





SANDBAG DETAIL

# NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.

6" CURB-

SHEET 3 OF 3

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

**EROSION CONTROL LOG** 

EC(9) - 16

CONT SECT

0910 00

DN:TxDOT CK: KM DW: LS/PT CK: LS

VAR

SHEET NO.

JOB 137

SMITH, ETC.

Texas Department of Transportation

FILE: ec916 C TxDOT: JULY 2016







