SEE SHEET 2 FOR INDEX OF SHEETS AND LOCATION MAP

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED HIGHWAY ROUTINE MAINTENANCE CONTRACT

PROJECT NUMBER: RMC 6460-83-001

US 190, ETC.

MADISON

TYPE OF WORK: ROADSIDE MOWING

LIMITS: FROM VARIOUS TO VARIOUS

TOTAL LENGTH OF PROJECT = 220.400 MILES



NO EXCEPTIONS NO RAILROAD CROSSINGS

RECOMMENDED FOR LETTING

DocuSigned by JACE LEE, P 程56 PR 包括 化 F MAINTENANCE

NO EQUATIONS

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 SHALL GOVERN ON THIS PROJECT.

> (c) 2023 By Texas Department of Transportation: all rights reserved.


FED. RD. PROJECT NUMBER		NUMBER	HIGHWAY NUMBER			
6	RMC 6460-	-83-001	US 190, ETC.			
STATE	DISTRICT		COUNTY			
TEXAS	BRY					
CONTROL	SECTION	JC)B	SHEET NO.		
				1		

TEXAS DEPARTMENT OF TRANSPORTATION

11/13/2023

DATE:

INDEX OF SHEETS



GENERAL NOTES:

DEBT TO THE STATE:

If the Comptroller is currently prohibited from issuing a warrant to the Contractor because of a debt owed to the State, then the Contractor agrees that any payment owing under the contract will be applied toward the debt or delinquent taxes until the debt or delinquent taxes are paid in full.

GENERAL:

Pre-Bid Contractor questions on this project are to be addressed to the following individual(s):

Paul M. Ray, P.E. – District Maintenance – <u>Paul.Ray@txdot.gov</u> Michael Estillette – District Maintenance – <u>Michael.Estillette@txdot.gov</u>

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address: <u>https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors</u>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

ITEM 2 – INSTRUCTIONS TO BIDDERS

View plan sheets on-line or download from the web at: <u>http://www.txdot.gov/business/letting-bids/plans-online.html</u>

Order plans from any of the plan reproduction companies shown on the web at: <u>http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm</u>

By signing this proposal, the Contract bidder acknowledges they have a copy of the "Standard Specifications for Construction of Highways, Streets and Bridges", adopted by the Texas Department of Transportation, November 1, 2014.

ITEM 3 – AWARD AND EXECUTION OF CONTRACT:

This is a non-site specific (callout) Contract. Multiple Work Orders will be used to procure work of the type identified in the Contract on an as need basis.

This is a multiple work order contract. Contract will commence upon the issuance of the first Work Order by the Engineer or his representative and will continue for one (1) calendar year. Work is not continuous during the term of the contract.

A work order will be given the Contractor specifying the number of acres for the mowing cycle, the number of working days allowed to complete the mowing cycle and the date when time charges for that mowing cycle will be started.

The number of working days allowed for each work order will be based on a production rate of 140 acres/day

Fraction of a day will be rounded up to the next whole number.

Work orders may be issued until one (1) calendar year after authorization for work is given. No work orders will be issued after this date unless there is mutual agreement between the Contractor and the Department. The contract will be in effect until the work on the last work order is completed.

ITEM 4 – SCOPE OF WORK:


The Contract allows for a one (1)-year extension with mutual agreement between the Contractor and Engineer as allowed by SP 004-001.

ITEM 7 – LEGAL RELATIONS AND RESPONSIBILITIES:

This project is on a hurricane evacuation route. Furnish at the pre-construction meeting a written plan outlining procedure to suspend work, secure the job site and safely handle traffic through and across the project in the event of a hurricane evacuation.

During the hurricane season (June 1 through November 30), do not close any travel lanes except when the Contractor can demonstrate that they can provide labor, equipment, material, work plan, and quality of work to satisfactorily return all lanes to an open, all-weather travel surface within three days of receiving written or verbal notice but no later than 3 days prior to hurricane landfall. Construction of temporary lanes to an all-weather surface will be paid in accordance with Article 9.7, "Payment for Extra Work and Force Account Method".

In addition to lane closures, cease work 3 days prior to hurricane landfall on or near the roadway that adversely impacts the flow of traffic and reduces the capacity of the highway during an evacuation. Prohibit the Contractor's, sub-contractors' or material suppliers'



vehicles from entering or exiting the stream of traffic including material hauling and delivery, and mobilization or demobilization of equipment. When directed, this prohibition will include a reasonable time period for the evacuees to return to their point of origin.

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractor's or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, mobilization or demobilization of equipment.

The following roadways are recognized evacuation routes in the Bryan District:

Primary Evacuation Routes: IH 45, US 290, SH 6, SH 36

Secondary Evacuation Routes: US 79, US 84, SH 7, SH 30, SH 21, SH 105

Other routes may be designated.

ITEM 8 – PROSECUTION AND PROGRESS:

Contract length will be computed and charged in accordance with Article 8.3.1.5. "Calendar Dav"

Work orders will be issued in accordance with Section 8.3.1.4, "Standard Workweek"

Notify the Engineer by 7:45 a.m., if work will not be performed that day.

Report each day, or as directed, prior to the beginning of work to the Maintenance Supervisor as to the time(s), location(s), and work expected for inspection and acceptance as it develops and/or is completed.

By noon of each Wednesday, provide the Engineer a written outline of the daily work schedule for the following week. Include in the outline the times and places for proposed traffic control changes, lane and shoulder closures, and moving operations or other operations that affect traffic on the roadway.

Milestone 1:

Milestone 1 sets a date of October 3, 2024 for the Contractor to complete cycle 2 locations given in the summary table found in the plans.

If the second mowing cycle is not accepted by the Engineer prior to expiration of the Work Order (WO), the schedule of liquidated damages in SP 000-1243 will be applied.

Work Order time charges for all cycles begin on the date stated in the Work Order.

Equipment and material may be pre-staged at approved locations.

Do not commence work before sunrise. Coordinate work on the project so that no machinery is on the travel way or in picnic areas after sunset. Complete work during daylight hours when weather conditions are appropriate.

Remove mud immediately from the roadway that is a result of mowing operations.

Remove and properly dispose of all debris and litter generated by Contractor personnel at mower parking areas on State right-of-way.

This Contract is independent of other active Contracts held by the Contractor. If the Contractor is awarded multiple Contracts, they should expect overlapping work to be completed so as not to incur liquidated damages. Multiple crews may be required to meet production rate requirements. Use of multiple crews to complete work will not be paid for directly but is subsidiary to pertinent Items.

ITEM 502 – BARRICADES, SIGNS, AND TRAFFIC HANDLING:

In accordance with Article 502.4.1.6 traffic control will not be paid for directly but shall be subsidiary to pertinent items of the contract.

The traffic control plan will be governed by PART VI of the TMUTCD, the BC standards sheets, and the traffic control standard sheets or as directed by the Engineer. Additional signing and/or barricades shown in the TMUTCD, BC, and TCP standards may be required by the Engineer to ensure the safety of the traveling public.

ITEM 506 – TEMPORARY EROSION, SEDIMENTATION AND ENVIRONMENTAL CONTROLS:

It is not anticipated that any erosion control devices will be needed on this project. However, in the event that any devices are needed, payment for the work will be determined in accordance with Article 9.7, "Payment for Extra Work and Force Account Method".

			PRINT DATE	REVISION DATE			
Texas Department of Transportation Bryan District Maintenance Office							
		ERAL N 2 OF 3 SH					
FED. RD. DIV. NO.	PROJECT	NUMBER	HIGHWAY	NUMBER			
6	RMC 6460-	-83-001	US 190,	ETC.			
STATE	DISTRICT		COUNTY				
TEXAS	BRY	MADISON					
CONTROL	SECTION	J	ЭВ	SHEET NO.			
				4			

ITEM 730 – ROADSIDE MOWING:

Hand trim around fixed objects, which includes, but are not limited to: sign posts, delineators, culvert headwalls, pipe ends, guard fence, bridge approach railing, mailbox supports, trees, shrubs, utility poles, curbs, historical markings and the edges of riprap or other appurtenances which are located in the highway right of way. Fixed objects damaged or destroyed by mowers will be paid for by the Contractor. Hand trim grass to a height of approximately two (2) inches for approximately a two (2)-foot radius around the object.

If excessive vegetation growth occurs between scheduled mowing cycles, the Contractor may be required to perform an additional full width mowing cycle within urban acres of this contract as directed by the Engineer. The Contractor will be paid for the additional cycle at the unit bid price set forth in the contract except as provided in Article 4.4 "Changes in the Work."

Construction / Maintenance projects may be in progress on some sections of highway covered by this contract. Mowing will be performed on these sections of highways as directed by the Engineer. Areas where mowing is impractical because of material stockpiles, grading operations, work sites, etc. will be excluded from the mowing requirement.

The Engineer may identify locations of various highways that require site investigation for endangered plant species. Mowing widths through these locations will be as specified by the Engineer.

Adjust mowers for a cutting height of approximately seven (7) inches. Mow all vegetation less than or approximately one and one-half (1.5) inches in diameter.

If, during the mowing cycle, weeds are knocked down, but not cut, the Contractor will be required to return within 72 hours to cut these weeds.

Tract must be completed to the satisfaction of the Engineer before payment will be made.

Pressure wash mowing equipment before entering and leaving the county.

Ensure all State-designated "no mow" area(s) are properly identified prior to conducting mowing operations. Do not perform mowing operations within the boundaries of these areas between August 31 and January 1. Damages to "no-mow" areas may result in reimbursement to the State to re-establish wildflower growth.

			PRINT DATE	REVISION DATE				
Texas Department of Transportation Bryan District Maintenance Office								
	GENERAL NOTES SHEET 3 OF 3 SHEETS							
FED. RD. DIV. NO.	PROJECT	NUMBER	HIGHWAY	NUMBER				
6	RMC 6460-	-83-001	US 190,	ETC.				
STATE	DISTRICT		COUNTY					
TEXAS	BRY	MADISON						
CONTROL	SECTION	J	рв	SHEET NO.				
				4A				

	ESTIMATE SUMMARY										
	ITEM CODE				HIGHWAY: US 190, ETC. PROJECT: 6460-83-001						
ITEM NO.	DESC CODE	SP NO.	DESCRIPTION	UNIT	ALL BID EST.	ITEMS REVISED					
500	6033		MOBILIZATION (CALLOUT)	EA	3.000						
730	6002		FULL - WIDTH MOWING	AC	4,399.000						

			PRINT DATE	REVISION DATE				
Texas Department of Transportation Bryan District Maintenance Office ESTIMATE AND QUANTITY								
		SHEET						
		SHEET						
FED. RD. DIV. NO.	PROJECT	NUMBER	HIGHWAY	NUMBER				
6	RMC 6460-	-83-001	US 190,	ETC.				
STATE	DISTRICT		COUNTY					
TEXAS	BRY	MADISON						
CONTROL	SECTION	JC	рв	SHEET NO.				
				5				

TRACT	HIGHWAY	LIMITS	LENGTH (MI)	ITEM 730-6	002 FULL-WIDT	H MOWING
TRACT				Cycles	Acres/Cycle	Total Acres
1	US 190	FROM BRAZOS COUNTY LINE TO MADISONVILLE	18.600	3	155.00	465.00
2	SH 21	FROM MADISONVILLE TO HOUSTON COUNTY LINE	15.900	3	129.00	387.00
3	OSR	FROM NAVASOTA RIVER TO SH 75	21.400	3	210.00	630.00
4	FM 39	FROM LEON COUNTY LINE TO US 190	7.700	3	63.00	189.00
5	OSR	FROM SH 75 TO SH 21	11.700	2	97.00	194.00
6	SH 75	FROM LEON COUNTY LINE TO MADISONVILLE	9.900	2	75.00	150.00
7	SH 75	FROM MADISONVILLE TO WALKER COUNTY LINE	9.700	2	91.00	182.00
8	SH 90	FROM MADISONVILLE TO GRIMES COUNTY LINE	7.500	2	64.00	128.00
9	SP 67	FROM SH 75 TO IH 45	0.300	2	2.00	4.00
10	SP 104	FROM SH 75 TO IH 45	0.900	2	8.00	16.00
11	LP 160	FROM US 190 IN NORTH ZULCH TO US 190	0.600	2	3.00	6.00
12	FM 39	FROM NORTH ZULCH TO GRIMES COUNTY LINE	6.100	2	53.00	106.00
13	FM 247	FROM SH 21 TO WALKER COUNTY LINE	9.600	2	67.00	134.00
14	FM 579	FROM OSR TO LEON COUNTY LINE	1.300	2	13.00	26.00
15	FM 978	FROM FM 39 TO MADISONVILLE	12.500	2	90.00	180.00
16	FM 1119	FROM LEON COUNTY LINE TO OSR	3.100	2	29.00	58.00
17	FM 1372	FROM COUNTY ROAD 438 TO FM 39	4.700	2	47.00	94.00
18	FM 1372	FROM FM 39 TO US 190	11.000	2	96.00	192.00
19	FM 1428	FROM SH 21 TO FM 247	9.200	2	85.00	170.00
20	FM 1452	FROM FM 39 TO US 190	10.400	2	74.00	148.00
21	FM 1452	FROM FM 39 TO OSR	7.100	2	67.00	134.00
22	FM 1452	FROM US 190 TO SH 90	3.600	2	35.00	70.00
23	FM 2158	FROM SH 21 TO FM 1428	5.100	2	53.00	106.00
24	FM 2289	FROM OSR TO FM 1452	10.500	2	103.00	206.00
25	FM 2346	FROM OSR TO SH 21	6.500	2	62.00	124.00
26	FM 2548	FROM SH 21AT MIDWAY TO SH 21	6.700	2	66.00	132.00
27	FM 2865	FROM US 190 TO COUNTY ROAD 431	2.500	2	24.00	48.00
28	FM 3060	FROM SH 21 TO COUNTY ROAD 245	2.100	2	20.00	40.00
29	FM 3091	FROM IH 45	4.200	2	40.00	80.00
		TO COUNTY ROAD 216 PROJECT TOTALS			1,921.00	

\$FILE\$
FILENAME
460-83-001

			PRINT DATE	REVISION DATE				
Texas Department of Transportation Bryan District Maintenance Office								
	SUMMARY SHEET							
FED. RD. DIV. NO.	PROJECT	NUMBER	HIGHWAY	NUMBER				
6	RMC 6460-	-83-001	US 190,	ETC.				
STATE	DISTRICT		COUNTY					
TEXAS	BRY	MADISON						
CONTROL	SECTION	JC	ЭВ	SHEET NO.				
				6				

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessory worning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travellanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES


- 1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

INE AT ST (CWZTCD) NUALS)"

(TMUTCD)

7	Texas Department of Transportation								
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS BC(1)-21									
FILE:	bc-21.dgn	dn: Tx	DOT	ск: ТхDOT	DW:	TxDOT	ск: TxDOT		
© TxDOT	November 2002			RMC •		ни	GHWAY		
4-03	REVISIONS			6460-83-001		US 1	90, ETC.		
9-07	8-14	DIST		COUNTY			SHEET NO.		
5-10	5-21	BRY		MADISO	N		7		
95									

SHEET 1 OF 12




any Practice Act". No warranty of no responsibility for the conve resulting from its use. Igineering F ossumes domoges exos En TxDOT sults or d by the whotsoeve incorrect e s s si po A this standar TxDOT for a to other for DISCLAIMER: The use of 11 kind is mode by T of this standard to

DATE

	TYPICAL CONS	STRUCTIO	N WARI	NING SIGN	SIZE	AND SPAC	CING 1,5,6		
		SIZE	:			SP	ACING		
< s	Sign Number or Series	Conventio Roo	-	Expresswa Freeway		Posted Speed	Sign * Spacing "X"		
ſĽ	CW20 ⁴ CW21 CW22	48" x	48"	48" × 48"		МРН 30	Feet (Apprx.) 120		
	CW23 CW25					35 40 45	160 240 320		
×	CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" × 36"	48 [.]	x 48"		45 50 55 60	400 500 ² 600 ²		
	CW3, CW4,	48" x 48"	48	x 48"		65 70 75	700 ² 800 ² 900 ²		
	CW10, CW12					80 *	1000 ²		
	 For typical sign sp see Port 6 of the (TMUTCD) typical a Minimum distance work orea and/or 	"Texas Manu pplication diag from work a	alon Unife grams or grea to fil	orm Traffic TCP Standard rst Advance 1	ControlDe I Sheets. Vorning si	vices"			
	GENERAL NOTES								
	 Special or larger size signs may be used as necessary. Distance between signs should be increased as required to have 1500 feet advance warning. 								
	 Distance between signs should be increased as required to have 1/2 mile or more advance warning. 								
EY #NG IS LAW	4. 36" x 36" "ROAD t crossroads at the Note 2 under "Ty 5. Only diamond shape	discretion of pical Location	the Engin of Crossr	neer as per 1 road Signs".					
**	6. See sign size listing Sign Designs for 1 sizes.								
4		1		LE	GEND				
_			Ι	Type 3	Barrico	de			
			000	Channel	izing De	vices			
			-	Sign					
istonce			x	Warning Spacing TMUTCI	pical Coi Sign S chart (for sid require	or the gn			
GIN RO. cific pr ounded	oject.			SHEET	2 OF	12			
ie Engir	Engineer.			partment of	f Transp	oortation	Traffic Safety Division Standard		
en adva inform k zone	ndvance rm lhe								
tion an operation 20-1D):	ons.		-		_				
Traffic		FILE: b	c-21.dgn		2)-2	21 ск: ТхDOT D W :	TxDOT CK: TxDO		
ot		Ŭ	REVISIONS			RMC • 6460-83-001	HIGHWAY US 190, ETC.		
			-21		DIST BRY	COUNTY MADISON	SHEET NO. 8		

96



DIST

BRY

7-13 5-21

97


COUNT

MADISON

SHEET NO.

9

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TaDOT for any purpose whotspever. TaDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer. Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- 5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texos" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been amilted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the inspector's TxDOT diary and having both the inspector and Contractor initial and date the agreed upon changes. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside
- signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) signs, supports for temporary large robusive signs shall meet the requirements between on the reinporary large robusive signs (rhos) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or morred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.

9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

- <u>QURATION OF WORK (as defined by the "Texas Manualon Uniform Traffic Control Devices" Part 6</u>
- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days. b. Intermediate term stationary - work that occupies a location more than one daylight period up to 3 days, or night lime work losting
- more than one hour. c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
- d. Short, duration work that occupies a location up to 1 hour. e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)
- SIGN MOUNTING HEIGHT 1. The bottom of Long-term/intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except
- as shown for supplemental plaques mounted below other signs. 2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground. 3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing. 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to
- appropriate Long-term/Intermediate sign height.

SIZE OF SIGNS

l. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- 1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the spice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- While sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first closs workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
 Long-term stationary or intermediate stationary signs installed on square metal lubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any
- intersections where the sign may be seen from approaching traffic. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely
- covered when not required. When signs are covered, the material used shall be opaque, such as heavy mitblack plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- . Burlap shall NOT be used to cover signs.
- 6. Duct tope or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use
- of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights. Sondbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sondbags should be made of a durable material that tears upon vehicular
- impact. Rubber (such as lire inner lubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used fo ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sondbags shallonly be placed along or loid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbaas shall be placed
- along the length of the skids to weigh down the sign support. Sondbags shall NOT be placed under the skid and shall not be used to level sion supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or lorger and shall be arange or fluorescent red-arange in color. Flags shall not be allowed to cover any partian of the sign face.


Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

3. Orange sheeting, meeting the requirements of DMS-8300 Type B $\,$ or Type G $_{
m L}$, shall be used for rigid signs with orange bockgrounds.

98

	SHEE	T 4	OF	12				
	★* Texas Department	of Tra	nsp	ortation		Ĺ	Divis	ety sion
Texas Department of Transportation Division Standard BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES BC(4)-21								N
FILE:	bc-21.dgn	· ·	DOT	ск: ТхDOT	DW:	TxDO	T	ск: ТхDOT
© TxDOT	November 2002			RMC •			HIGH	WAY
	REVISIONS		6	460-83-001		U	S 190	, ETC.
9-07	8-14	DIST		COUNTY			SH	HEET NO.
7-13	5-21	BRV		MADISO	N			10

MADISON



DISCLAMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDDT for any purpose whotsoever. TxDDT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- 2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- 6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnigh Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flosh" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message. 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches
- and must be legible from at least 400 feet. 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bors is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Rood A	CCS RD	Najor MAJ	
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PK ING RD
CROSSING	XING	Rood	
Detour Route	DETOUR RTE	Right Lone	RT LN SAT
Do Not	DONT	Soturday	SERV RD
East	E	Service Rood	
Eastbound	(route) E	Shoulder	SHLDR SLIP
Emergency	EMER	Slippery	I SLIP
Emergency Vehicle		South	
Entrance. Enter	ENT	Southbound	(route) S
Express Lone	EXP LN	Speed	SPD ST
Expresswoy	EXPWY	Street	SUN
XXXX Feet	XXXX FT	Sunday	
Fog Ahegd	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN TRAF
Hazardous Driving		Troffic	
Hazardous Material		Irovelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour (s)	HR, HRS	Vehicles (s)	VEH, VEHS
Information	INFO	Warning	WARN
It is	ITS	Wednesday	WED
Junction	JCT	Weight Limit	WT LIMIT
Left		West	Ŵ
Left Lone		Westbound	(route) 🕷
Lone Closed		Wet Povement	WET PVMT
Lower Level	LWR LEVEL	Will Not	WONT
Maintenance	MAINT	-	

designation . IH-number, US-number, SH-number, FM-number

RECOMMENDED	PHASES	and	FORMATS	FOR	PCMS	MESSAGES	DUR

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

		Uther Col
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT
XXXXXXXX BLVD CLOSED	× LANES SHIFT in Phose 1 m	ust be used with S

Other Conc	lition List
ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	L ANE S SHIF T

MERGE FORM X LINES RIGHT RIGHT DETOUR USE XXXXX NEXT X EXITS RD EXIT USE USE EXIT EXIT XXX I-XX NORTH STAY ON USE US XXX I-XX F SOUTH TO I-XX N TRUCKS WATCH USE FOR US XXX N TRUCKS WATCH EXPECT FOR DELAYS TRUCKS PREPARE EXPECT DELAYS TO STOP REDUCE END SPEED SHOULDER XXX FT USE WATCH USE OTHER FOR ROUTES WORKERS STAY IN

Action to Take/Effect on Travel

List

STAY IN LANE in Phose 2.

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phose can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phose Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

LANE

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate. 2. Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- 3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate. 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed. 6. AHEAD may be used instead of distances if necessary. 7. FT and MI, MILE and MILES interchanged as appropriate
- 8. AT, BEFORE and PAST interchanged as needed. 9. Distances or AHEAD can be eliminated from the message if a
 - location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the some size arrow.


Roodway

RING ROADWORK ACTIVITIES

Phase 2: Possible Component Lists



File: bc:21.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: TxDOT File: bc:21.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: TxDOT GTXDOT November 2002 RMC · HIGHWAY REVISIONS 6460-83-001 UIS 190, ETC. 9-07 8-14 DIST COUNTY SHET NO.		SHEE	т 6	OF	12			
PORTABLE CHANGEABLE MESSAGE SIGN (PCMS) BC(6)-21 FILE: bc-21.dgn [©]TXDOT November 2002 RMC • REVISIONS 6460-83-001 9-07 8-14 DIST COUNTY	7	★° Texas Department	of Tra	nsp	ortation		Sa Div	nfety vision
BC(6) - 21 FILE: bc-21.dgn DN: TXDOT CK: TXDOT DW: TXDOT DE: TXDOT DW: TXDOT DE: TXDOT DW: TXDOT DW: TXDOT DW: TXDOT DW: TXDOT DW: TXDOT DE: TXDOT	BAR	PORTABLE	Cł		NGEA	Bl	.Е	N
FILE: bc-21.dgn DN: TXDOT CK: TXDOT CM: TXDOT CM: TXDOT CM: TXDOT CM: TXDOT CM: TXDOT CK: TXDOT		ME 33AGE	210	N		13		
C TxDOT November 2002 RMC - HIGHWAY RE VISIONS 6460-83-001 US 190, ETC. 9-07 8-14 DIST COUNTY SHEET NO.		BC	(6)	-2	21			
REVISIONS 6460-83-001 US 190, ETC. 9-07 8-14 DIST COUNTY SHEET NO. 7 17 5-01 DIST COUNTY SHEET NO.	FILE:	bc-21.dgn	DN: TX	DOT	ск: TxDOT	DW:	TxDOT	ск: TxDOT
9-07 8-14 DIST COUNTY SHEET NO.	© TxD01	November 2002			RMC •		ню	HWAY
				6	460-83-001		US 1	90, ETC
7-13 5-21 BRY MADISON 12	•••	• · · ·	DIST		COUNTY			SHEET NO.
	7-13	5-21	BRY		MADISO	N		12



GENERAL NOTES

- 1. For long term stationary work zones on freeways, drums shall be used as the primory channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD)
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS


- Pre-qualified plastic drums shall meet the following requirements:
- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air lurbulence created by passing vehicles.
- 3. Plostic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The lop of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material. 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10.Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING


- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retrorellectivity requirements of Deportune tal Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballost material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavemen surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- 3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to povement.









DETECTABLE PEDESTRIAN BARRICADES


- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- 2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5. Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.





- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or lurn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spocing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B or Aype C conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stalionary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact. 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travellanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballosted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve doytime/nighttime visibility. They may also be supplemented with povement markings. 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements
- specific to the device, and used only when shown on the CWZTCD list. 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH)
- urban areas. When used on a laper in a low speed urban area, the laper shall be delineated and the laper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top I the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS


Practice Act". No warranty of any no responsibility for the conversion resulting from its use. DISCLAMER: The use of this standard is governed by the "Texas Engineering f tind is mode by TxDDT for any purpose whatsoever. TxDDT ossumes of this standard to other formats or for incorrect results or damages

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manualon Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone oreos where channelizing devices are frequently impacted by erront vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, foded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spocing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the odhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final povement surfaces, including povement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	0	Minimum esirable er Lengl x x		Suggested Spocing Channeli Devi	g of zing
		10° Offset	11 [.] Offset	12° Offsel	On a Taper	On a Tangent
30		150'	165'	180'	30'	60'
35	L. <u>WS²</u>	205'	225'	245	35'	70'
40	00	265'	295'	320'	40'	80'
45		450'	495'	540'	45'	90.
50		500 [.]	550'	600'	50'	100'
55	L-WS	550'	605'	660	55'	110 [.]
60] - "3	600 [.]	660'	720'	60 [.]	120'
65]	650'	715'	780'	65'	130'
70]	700'	770'	840'	70'	140'
75]	750'	825'	900.	75'	150 [.]
80		800 [.]	880.	960'	80'	160'

x x Toper lengths have been rounded off. L-Length of Taper (FT.) W-Width of Offset (FT.) S-Posted Speed (MPH)




SHEET 9 OF 12	
Texas Department of Transportation	Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21

FILE:	bc-21.dgn	dn: Tx	DOT	ск: TxDOT	DW:	TxD0	T ск: TxDOT
© ⊺xD0T	November 2002			RMC •			HIGHWAY
	REVISIONS		6	460-83-001		US	6 190, ETC.
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	BRY		MADISO	N		15

103



		BC	(10))-	21			
FILE:	bc-21.dgn		dn: T	xDOT	ск: ТхDOT	DW:	TxDOT	ск: TxDOT
© TxDOT	November 2002				RMC •		н	IGHWAY
	REVISIONS			(6460-83-001		US	190, ETC.
9-07	8-14 5-21		DIST		COUNTY			SHEET NO.
7-13	5-21		BRY		MADISO	N		16
104								

WORK ZONE PAVEMENT MARKINGS

GENERAL

- 1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- 2. Color, patterns and dimensions shall be in conformance with the "Texos Monual on Uniform Traffic Control Devices" (TMUTCD).
- 3. Additional supplemental pavement marking details may be found in the plans or specifications.
- 4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- 5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPW).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- 7. All work zone povement markings shall be installed in accordance with Item 662, "Work Zone Povement Markings."

RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns on BC(12).
- 2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS


- 1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- 2. Non-removable prefabricated pavement markings (fail back) shall meet the requirements of DMS-8240.

MAINTAINING WORK ZONE PAVEMENT MARKINGS

- 1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- 2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- 1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- 2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- 3. Povement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Povement Markings and Markers".
- 4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- 5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised pavement markers shall be as directed by the
- 9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

1/4" and less than 1".

- 1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- 2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - A Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic povement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.

3. Small design variances may be noted between tab manufacturers.

4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- 1. Raised povement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- 2. All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- 3. Adhesive for guidemarks shall be bituminous material hot applied or butylrubber pod for all surfaces, or thermoplastic for concrete surfaces

Guidemarks shall be designated as:


YELLOW - (Iwo amber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242


A list of pregualified reflective raised pavement markers. non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEE	т 11	OF	12				
Texas Department	of Tra	nsp	ortation		Ĺ	Traffic Safety Division tandar	1
BARRICADE AN PAVEMEI BC		MA	rkin			ION	
FILE: bc-21.dgn	DN: T:	DOT	ск: ТхDOT	DW:	TxDO	Т Ск: Т	xDOT
© TxDOT February 1998			RMC •			HIGHWAY	
REVISIONS		6	460-83-001		U	5 190, ET(c.
2-98 9-07 5-21 1-02 7-13	DIST		COUNTY			SHEET	NO.
11-02 8-14	BRY		MADISO	N		17	

105



DATE



GENERAL NOTES FOR WORK ZONE SIGNS

- 1. Contractor shallinstall and maintain signs in a straight and plumb condition and/or as directed by the Engineer. 2. Wooden sign posts shall be painted while.
- 3. Barricades shall NOT be used as sign supports.
- 4. Nails shall NOT be used to attach signs to any support.
- 5. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and
- quide the traveling public safely through the work zone.
- 6. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texos" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initiation date the agreed upon changes. The additional signs requested by the Engineer/Inspector shall not be subsidiary.
- 7. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD). The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so that the Engineer con verify the correct procedures are being followed. 8. The Contractor is responsible for sign installations and replacing signs with damaged or crocked substrates and/or damaged or marred
- reflective sheeting as directed by the Engineer/Inspector.
- 9. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".

10. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

- Duration of Work (as defined by the "Texas Manualan Uniform Traffic Control Devices" Part VI) 1. The Contractor is responsible for ensuring the sign support and substrate meets crashworthiness. For moving operation all signs and supportS are Short-term Duration for daytime work.
- 2. The Contractor shall furnish the sign sizes shown on this sheet or as directed by the Engineer.

SIGN SUBSTRATES

- 1. The Contractor shall ensure that the sign substrate is allowed for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- 2. "Mesh" type materials are NOT an approved sign substrate. 3. All wooden individual sign panels labricated from 2 or more pieces shall have one or more plywood cleal, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood
- screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign faces. REFLECTIVE SHEETING
- 1. Reflectorized signs shall be constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 or DMS-8310. The DMS specifications can be accessed from the following web address: http://manuals.dot.state.tx.us:80/dvnaweb/colmates/@Generic CollectionView:cs+default;ts+default
- 2. White sheeting, meeting the requirements of DMS-8300 Type C (High Specific Intensity), shall be used for signs with white background and channelizing devices.
- 3. Orange sheeting, meeting the requirements of DMS-8300 Type E (Fluorescent Prismatic), shall be used for signs with arange backgrounds. SIGN LETTERS
- 1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- 1. Signs should be removed or completely covered when not mowing.
- 2. Duct tape or other adhesive material shall NOT be affixed to a sign face.
- 3. Signs and supports shall be removed by the end of the day.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry cohesionless sand is recommended.
- 2. The sandbags will be lied shut to keep the sand from spilling and to maintain a constant weight.
- 3. Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
- 4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- 5. Sandbags shall be made of a durable material that lears upon vehicular impact. 6. Rubber (such as lire inner lubes) shall NOT be used for sandbags.
- 7. Rubber ballosts (such as those used with cones or edgeline channelizers) shall NOT be used as sign support weights.
- 8. Sondbags shall only be placed along or loid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign supports.
- 9. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS Any sign, sign support or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced or repaired as soon as possible by the Contractor at the Contractor's expense.

Only pre-qualified products shall be used. A copy of the "Comptiont Work Zone Traffic Control Devices List" (CWZTCD) describes pre-audified products and their sources and may be oblained by conlocting:

Slandards Engineer

Traffic Operations Division • TE Texas Department of Transportation 125 East 11th Street Austin, Texos 78701-2483 Phone (512) 416-3120 For (512) 415-3299

Instructions to locate the "CWZTCD" on TxDOT website are:

Start at website . www.dot.state.t=.us Click on "About TxDOT", Click on "Organizational Chart". Click on Traffic Operations Box Click on "Comptiont Work Zone Traffic Control Devices". Click on "View PDF". This sile is prinloble.

Engineering Practice purpose whatsoever. s standard to j from its use. governed by the "Texas | mode by TxDOT for any | for the conversion of this sults or damages resulting "Texas for any , or the DISCLAIMER The use of this standard is gove Act" . No warranty of any kind is mad TxDOT assumes no responsibility for t other formats or for incorrect results 1 12 13 14 15 16 7 282930 3132 1 34 44 54 64 7 48 960 61 62 63

Tex		Main	tenanc	n i of ce Divi cd Pla	sio		ort	ation
		RO	ADSI	DE				
TRAF	FIC	СС	ONTF	ROL	ΡL	AN		
TRAF			ONTF		ΡL	AN	NO	T TO SCALE
	R					. AN		T TO SCALE ieg no:
SHEET 1 OF 1	R	S-T	CP-(05 DW:-		X:-		
SHEET 1 OF 1 File: RSTCP05.DGN	R	S-T	СР-(ск: JG	05 	PROJECT	X:-	N	IEG NO.:
SHEET 1 OF 1 FLE: RSTCPO5.DGN ©TxDOT FEBRUARN	R	S-T	CP-(CK: JG FEDERAL REGION	05 DW:- RMC	PR0JEC1 6460	CK:- NO.	N	IEG NO.: SHEET