

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

PROJECT NUMBER: C 508-1-394
CSJ: 0508-01-394, ETC



COUNTY: HARRIS

LIMITS: VARIOUS LOCATIONS, ALONG IH 10, IH 69, IH 610, SS 548, US 90, SAN JACINTO MONUMENT

NET LENGTH OF PROJECT = 93.983 MILES
TYPE OF WORK: FOR THE CONSTRUCTION OF LANDSCAPE ENHANCEMENTS.
CONSISTING OF: LANDSCAPE DEVELOPMENT AND MAINTENANCE

FED. RD. DIV. NO.	FEDERAL AID or STATE PROJECT NO.		HIGHWAY NO.
6	C508-1-394		IH10, ETC
STATE	DISTRICT	COUNTY	SHEET NO.
TEXAS	HOU	HARRIS	001
CONTROL	SECTION	JOB	
0508	01	0508-01-394, ETC	

ROADWAY CLASSIFICATION: N/A
DESIGN SPEED: N/A
ADT: REF TABLE



CSJ	PROJECT NUMBER	HWY	LIMITS	LENGTH		ADT	FUTURE ADT
				FT.	MI.		
0508-01-394	508-1-394	IH 10	IH 45 TO HARRIS / CHAMBERS CL	150047.04	28.418	148,128	189,604
0271-14-247	271-14-247	IH 610	US 290 TO IH 10 E	69025.44	13.073	165,104	231,146
0271-15-103	271-15-103	IH 610	IH 10 TO BUFFALO BAYOU	17893.92	3.369	109,503	153,904
2483-01-016	2483-1-16	SS 548	EAST CROSS TIMBERS TO IH 610	7529.28	1.426	55,397	77,556
0028-02-110	28-2-110	US 90	IH 10 TO KRENEK ROAD	80910.72	15.324	50,234	70,328
0177-11-163	177-11-163	US 69	IH 10 TO LANGLEY ROAD	9926.4	1.880	158,372	221,721
0177-07-125	177-7-125	US 69	LANGLEY ROAD TO FM 1960	53845.44	10.198	194,898	272,857
0177-06-095	177-6-95	US 69	FM 1960 TO MONTGOMERY / HARRIS CL	13902.24	2.633	122,392	171,349
0177-05-127	177-5-127	US 69	MONTGOMERY / HARRIS CL TO FOSTORIA RD	93149.76	17.642	86,822	121,551
0376-01-015	376-1-15	P 1836	SAN JACINTO MONUMENT	0			

Westwood 20329 STATE HIGHWAY 240, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-469
TX REG. SURVEYING FIRM LS-10193805

TEXAS DEPARTMENT OF TRANSPORTATION

NOTE:

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014, AND SPECIFICATION ITEMS AND DATED AS FOLLOWS SHALL GOVERN THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS FOR ALL STATE CONSTRUCTION CONTRACTS (SP000---008).

EQUATIONS: NONE
EXCEPTIONS: NONE
RAILROAD CROSSINGS: 21

SUBMITTED: 11/29/2023
DocuSigned by: 20
Vipinkumar Sumari, P.E.
199D0DCE0D5E40E...

APPROVED: 11/30/2023
FOR LEAD ENGINEER: 20
James Koch, P.E.
For DISTRICT ENGINEER

11/28/2023 1:42 PM
T:\BBS\WAGS\EA\HARRIS\PLAN PRODUCTION\SHEETS\COVER INDEX\COVER_INDEX.DWG
COUNTY: HARRIS PROJECT NO. C1508-1-394
HWY NO: IH 10, ETC LETTING DATE FEB 02-2024
DATE ACCEPTED: _____

HARRIS COUNTY
AREA BOUNDARY MAP
HOUSTON DISTRICT
TEXAS DEPARTMENT OF TRANSPORTATION
NTS

INDEX OF SHEETS

I. GENERAL

- 001 TITLE SHEET
- 002 SHEET INDEX
- 003,A-C GENERAL NOTES
- 004,A ESTIMATE & QUANTITY SHEET
- 005 SUMMARY OF QUANTITIES

II. TRAFFIC CONTROL PLAN STANDARDS

- 006 TRAFFIC CONTROL PLAN AND PHASING NARRATIVE
- 007 * BC (1)-21
- 008 * BC (2)-21
- 009 * BC (3)-21
- 010 * BC (4)-21
- 011 * BC (5)-21
- 012 * BC (6)-21
- 013 * BC (7)-21
- 014 * BC (8)-21
- 015 * BC (9)-21
- 016 * BC (10)-21
- 017 * BC (11)-21
- 018 * BC (12)-21
- 019 * WZ (BRK)-13
- 020 * TCP (1-1)-18
- 021 * TCP (1-2)-18
- 022 * TCP (1-4)-18
- 023 * TCP (5-1)-18
- 024 * TCP (6-1)-12
- 025 * TCP (6-2)-12
- 026 * TCP (6-3)-12
- 027 * TCP (6-4)-12
- 028 * TCP (6-5)-12
- 029 * TCP (6-8)-14

III. MISC

- 030 PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE
- 031 - 036 PLANT MAINTENANCE
- 037 LANDSCAPE TREATMENT (TY 3)
- 038 LANDSCAPE TREATMENT (TY 4)
- 039 LANDSCAPE TREATMENT (TY 5)
- 040 LANDSCAPE TREATMENT (TY 6)
- 041 LANDSCAPE TREATMENT (TY 7)
- 042 LANDSCAPE TREATMENT (TY 8)
- 043 LANDSCAPE TREATMENT (TY 10)
- 044 - 048 PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT
- 049 - 055 US 90 PLANTING PLANS
- 056 - 057 IH 69 PLANTING PLANS
- 058 - 063 IH 69 PLANTING PLANS
- 064 - 065 IH 69 PLANTING PLANS
- 066 - 073 IH 69 PLANTING PLANS
- 074 - 080 IH 610 PLANTING PLANS
- 081 - 082 IH 610 PLANTING PLAN
- 083 - 097 IH 10 PLANTING PLAN
- 098 SS 548 PLANTING PLAN
- 099 - 106 SAN JACINTO
- 107 * FERTILIZER, SEED, SOD, STRAW, COMPOST AND WATER
- 108 - 115 * PLANTING AND ESTABLISHMENT

IV. ENVIRONMENTAL ISSUES STANDARDS

- 116 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS
- 117 - 118 TXDOT STORM WATER POLLUTION PREVENTION PLAN
- 119 * ECL-12

The Standard sheets specifically identified above with a (*) have been selected by me, Mark C. Schluter, P.E.



Mark C. Schluter

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MARK C. SCHLUTER, P.E. 53830 ON 08/30/2023. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-469
TX REG. SURVEYING FIRM LS-10193805



SHEET INDEX

FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.
6		002
STATE	DISTRICT	COUNTY
TEXAS	HOU	HARRIS
CONTROL	SECTION	JOB
0508	01	394,ETC
		HIGHWAY NO
		IH 10, ETC

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

General Notes:

General:

Area Engineer contact information for this project follows:

Jamal Elahi, P.E., Area Engineer
281-464-5501
Jamal.elahi@txdot.gov

Vanessa Bosques, P.E., Assistant Area Engineer
409-978-2516
Vanessa.bosques@txdot.gov

Submit any questions about this project via the Letting Pre-Bid Q&A web page, located at:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

The Letting Pre-Bid Q&A web page for each project can be accessed by scrolling or filtering the dashboard using the controls on the left side to navigate to the project. Hover over the blue hyperlink of the project to view the Q&A and click on the link in the window that pops up.

Large files with relevant project documentation, such as Geotech reports, As-Built plans, and cross-sections will continue to be provided on the following FTP site:

[Index of /pub/txdot-info/Pre-Letting Responses/Houston District \(state.tx.us\)](https://pub.txdot-info/Pre-Letting%20Responses/Houston%20District) or

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/Houston%20District/>

The following standard detail sheets are modified:

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved, except for roadway illumination, electrical, and traffic signal items.

The cost for materials, labor, and incidentals to provide for traffic across the roadway and for ingress and egress to private property in accordance with Section 7.2.4 of the standard specifications is subsidiary to the various bid items. Restore access roadways to their original condition upon completing construction.

Unless otherwise shown on the plans or otherwise directed, commence work after sunrise and ensure construction equipment is off the road by sunset.

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

Procure permits and licenses, which are to be issued by the City, County, or Municipal Utility District.

General: Site Management

Mow the grass and weeds within the project limits a maximum of 3 times a year as directed. This work is subsidiary to the various bid items.

Do not mix or store materials, or store or repair equipment, on top of concrete pavement or bridge decks unless authorized by the Engineer. Permission will be granted to store materials on surfaces if no damage or discoloration will result.

Personal vehicles of employees are not permitted to park within the right of way, including sections closed to public traffic. Employees may park on the right of way at the Contractor's office, equipment, and materials storage yard sites.

Assume ownership of debris and dispose of at an approved location. Do not dispose of debris on private property unless approved in writing by the District Engineer.

General: Traffic Control and Construction

When design details are not shown on the plans, provide signs and arrows conforming to the latest "Standard Highway Sign Designs for Texas" manual.

General: Utilities

Consider the locations of underground utilities depicted in the plans as approximate and employ responsible care to avoid damaging utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities.

If the Contractor damages or causes damage (breaks, leaks, nicks, dents, gouges, etc.) to the utility, contact the utility facility owner or operator immediately.

Be aware that an operational Computerized Transportation Management System (CTMS) exists within the limits of this project and that the system must remain operational throughout construction. If the Contractor damages or causes damage to this system, repair such damage within 8 hours of occurrence at no cost to the Department. In the event of system damage, notify the Director of Traffic Management Systems at 713-881-3283 within one hour of occurrence. Failure of the Contractor to repair damage to the main fiber optic cable and CCTV cable trunk lines, which convey all corridor information to TranStar, will result in the Contractor being billed for the full cost of emergency repairs.

At least 72 hours before starting work, make arrangements for locating existing Department-owned above ground and underground fiber optic, communications, power, illumination, and traffic signal cabling and conduit. Do this by calling the Department's Houston District Traffic Signal Operations

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

Office at 713-802-5662, or by e-mailing the Department's Houston District Traffic Signal Operations Office at: HOU-LocateRequest@txdot.gov, to schedule marking of underground lines on the ground. Use caution if working in these areas to avoid damaging or interfering with existing facilities.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Costs associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Perform electrical work in conformance with the National Electrical Code (NEC) and Department's standard sheets.

Before beginning any underground work, notify the City of Houston's Chief Inspector, Public Works and Engineering, to establish the locations of any existing electrical systems for lighting facilities within the limits of this project.

Item 7: Legal Relations and Responsibilities

Do not initiate activities in a Project Specific Location (PSL), associated with a U.S. Army Corps of Engineers (USACE) permit area, that have not been previously evaluated by the USACE as part of the permit review of this project. Such activities include those pertaining to, but are not limited to, haul roads, equipment staging areas, borrow and disposal sites. Associated defined here means materials are delivered to or from the PSL. The permit area includes the waters of the U.S. or associated wetlands affected by activities associated with this project. Special restrictions may be required for such work. Assume responsibility for consultations with the USACE regarding activities, including PSLs that have not been previously evaluated by the USACE. Provide the Department with a copy of consultations or approvals from the USACE before initiating activities.

The Contractor may proceed with activities in PSLs that do not affect a USACE permit area if a self-determination has been made that the PSL is non-jurisdictional or if proper USACE clearances have been obtained in jurisdictional areas or have been previously evaluated by the USACE as part of the permit review of this project. The Contractor is solely responsible for documenting any determinations that their activities do not affect a USACE permit area. Maintain copies of their determinations for review by the Department or any regulatory agency.

Document and coordinate with the USACE, if required, before hauling any excavation from or hauling any embankment to a USACE permit area by either 1 or 2 below:

1. **Restricted Use of Materials for the Previously Evaluated Permit Areas.** Document both the Project Specific Locations (PSL) and their authorization. Maintain copies for review by the Department or any regulatory agency. When an area within the project limits has been evaluated by the USACE as part of the permit process for this project:

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

- a. Suitable excavation of required material in the areas shown on the plans and cross sections as specified in the Item, "Excavation" is used for permanent or temporary fill (under the Item, "Embankment") within a USACE permit area.
- b. Suitable embankment (under the Item, "Embankment") from within the USACE permit area is used as fill within a USACE evaluated area.
- c. Unsuitable excavation or excess excavation, "Waste" (under the Item, "Excavation"), that is disposed of at a location approved within a USACE evaluated area.

2. **Contractor Materials from Areas Other than Previously Evaluated Areas.** Provide the Department with a copy of USACE coordination or approvals before initiating any activities for an area within the project limits that has not been evaluated by the USACE or for any off right of way locations used for the following, but not limited to, haul roads, equipment staging areas, borrow and disposal sites:
 - a. The Item, "Embankment" used for temporary or permanent fill within a USACE permit area.
 - b. Unsuitable excavation or excess excavation, "Waste" (under the Item, "Excavation"), that is disposed of outside a USACE evaluated area.

The total area disturbed for this project is 10.76 acres. The disturbed area in this project, the project locations in the Contract, and Contractor project specific locations (PSLs) within 1 mile of the project limits for the Contract, will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the ROW. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer (to the appropriate MS4 operator when on an off-state system route) and to the local government that operates a separate storm drain system.

This project does not require a U.S. Army Corps of Engineers (USACE) Section 404 Permit before letting, but if a permit is needed during construction, assume responsibility for preparing the permit application. Submit the permit application to the Department's District Environmental Section for approval. Once the permit application is approved, the Department will submit it to the USACE. Assume responsibility for the requested revisions, in coordination with the Department's District Environmental Section.

Maintain the roadway slope stability. Maintaining slope stability is subsidiary to the various bid items.

The nesting / breeding season for migratory birds is February 15 through September 30.

Conduct any tree removal outside of the migratory bird nesting season. If this is not possible due to scheduling, then exercise caution to remove only those trees with no active nests. Do not destroy nests on structures or in trees within the project limits during the nesting / breeding season.

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

Take measures to prevent the building of nests on any structures or trees within the project limits throughout the duration of the construction if work / removal will be performed during the nesting / breeding season. This can be accomplished by application of bird repellent gel, netting by hand every 3 to 4 days, or any other non-threatening method approved by the Houston District Environmental Section. Obtain this approval well in advance of the planned use. Contact the Houston District Environmental Section at 713-802-5244. The cost of this work is subsidiary to the various bid items.

This project is on a hurricane evacuation route. Provide at the pre-construction meeting a written plan outlining procedures to suspend work, secure the job site, and safely handle traffic through and across the project in the event of a hurricane evacuation.

During the hurricane season (June 1 through November 30), do not close any travel lanes except when the Contractor can demonstrate that he/she can provide labor, equipment, material, a work plan, and quality of work to satisfactorily return all lanes to an open, all-weather travel surface within 3 days of receiving written or verbal notice but no later than 3 days before the predicted hurricane landfall. Construction of temporary lanes to an all-weather surface will be paid for in accordance with Article 9.7, "Payment for Extra Work and Force Account Method."

In addition to lane closures, cease work 3 days before the predicted hurricane landfall on or near the roadway that adversely impacts the flow of traffic and reduces the capacity of the highway during an evacuation. Vehicles of the Contractor, subcontractors, or material suppliers will not be allowed to enter or exit the traffic stream, including those for the purpose of material hauling and delivery, and mobilization or demobilization of equipment. When directed, this prohibition will include a reasonable time period for the evacuees to return to their point of origin.

No significant traffic generator events have been identified.

Item 8: Prosecution and Progress

Working days will be computed and charged based on a standard workweek in accordance with Section 8.3.1.4.

Item 156: Bulldozer Work

Perform bulldozer work to grade or make repairs to slopes to control erosion if such work is not within the scope of other contract requirements.

Item 161: Compost

Item 162: Sodding for Erosion Control

Item 164: Seeding for Erosion Control

Item 166: Fertilizer

Item 168: Vegetative Watering

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

Refer to the "Fertilizer, Seed, Sod, Straw, Compost, and Water" plan sheet for material specifications, application rates, and for watering requirements.

Item 502: Barricades, Signs, and Traffic Handling

Use a traffic control plan for handling traffic through the various phases of construction. Follow the phasing sequence unless otherwise agreed upon by the Area Engineer and the Project Manager. Ensure this plan conforms to the latest "Texas Manual on Uniform Traffic Control Devices" and the latest Barricade and Construction (BC) Standard Sheets. The latest versions of Work Zone Standard Sheets WZ (BTS-1) and WZ (BTS-2) are the traffic control plan for the signal installations.

Submit changes to the traffic control plan to the Area Engineer. Provide a layout showing the construction phasing, signs, striping, and signalizations for changes to the original traffic control plan.

Furnish and maintain the barricades and warning signs, including the necessary temporary and portable traffic control devices, during the various phases of construction. Place and construct these barricades and warning signs in accordance with the latest "Texas Manual on Uniform Traffic Control Devices" for typical construction layouts.

Cover work zone signs when work related to the signs is not in progress, or when any hazard related to the signs no longer exists.

Keep the delineation devices, signs, and pavement markings clean. This work is subsidiary to the Item, "Barricades, Signs, and Traffic Handling."

Do not mount signs on drums or barricades, except those listed in the latest Barricades and Construction standard sheets.

Use traffic cones for daytime work only. Replace the cones with plastic drums during nighttime hours.

Do not reduce the existing number of lanes open to traffic except as shown on the following time schedule:

One Lane Closure			
Day	Daytime Closure Hours	Nighttime Closure Hours	Restricted Hours Subject to Lane Assessment Fee
Monday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Tuesday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Wednesday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Thursday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Friday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

Day	Daytime Closure Hours	Nighttime Closure Hours	Restricted Hours Subject to Lane Assessment Fee
Wednesday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Thursday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Friday	9:00 AM – 4:00 PM	NOT PERMITTED	6:00 AM – 9:00 AM 4:00 PM – 7:00 PM
Saturday	*	NOT PERMITTED	N/A
Sunday	*	NOT PERMITTED	N/A

* As approved by Engineer

The above times are approved for the traffic control conditions listed. The Area Engineer may approve other closure times if traffic counts warrant. The Area Engineer may reduce the above times for special events.

Law enforcement assistance will be required for this project and is expected to be required for major traffic control changes and lane closures. Coordinate with local law enforcement and arrange for law enforcement as directed or agreed by the Engineer. Before payment will be made, complete the “Daily Report on Law Enforcement Force Account Work” (Form 318), provided by the Department and submit daily invoices that agree with this form for any day during the month in which approved services were provided.

Provide full-time, off-duty, uniformed, certified peace officers, as part of traffic control operations. The peace officers must be able to show proof of certification by the Texas Commission on Law Enforcement Officers Standards. The cost of the officers is paid for on a force account basis.

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Item 506: Temporary Erosion, Sedimentation and Environmental Controls

A Storm Water Pollution Prevention Plan (SWP3) is required. Since the disturbed area is more than 5 acres, a “Notice of Intent” (NOI) is also required.

Use appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. Remove and dispose of materials in compliance with State and Federal laws.

County: Houston District

Control: 0508-01-394, ETC

Highway: IH 10, ETC

Before starting construction, review with the Engineer the SWP3 used for temporary erosion control as outlined on the plans. Before construction, place the temporary erosion and sedimentation control features as shown on the SWP3.

Schedule the seeding or sodding work as soon as possible. The project schedule provides for a vegetation management plan.

After completing earthwork operations, restore and reseed the disturbed areas in accordance with the Department’s specifications for permanent or temporary erosion control.

Implement temporary and permanent erosion control measures to comply with the National Pollution Discharge Elimination System (NPDES) general permit under the Clean Water Act.

Before starting grading operations and during the project duration, place the temporary or permanent erosion control measures to prevent sediment from leaving the right of way.

Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

A shadow vehicle with Truck Mounted Attenuators (TMAs) or Trailer Attenuators (TAs) is required as shown on the appropriate Traffic Control Plan (TCP) sheets. TMAs/TAs must meet the requirements of the Compliant Work Zone Traffic Control Device List.

Level 3 Compliant TMAs/TAs are required for this project.

A total of one (1) shadow vehicle with a TMA/TA is required for the work with the exception of Pavement Marking Operations. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.

A total of three (3) shadow vehicles with a TMA/TA are required for Pavement Marking Operations. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.

In addition to the shadow vehicles with TMAs/TAs that are specified as being required on the TCP layout sheets for this project, provide additional shadow vehicles with TMAs/TAs as shown on the TCP Standard sheets. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0508-01-394

DISTRICT Houston
HIGHWAY IH 10, IH 610, IH 69, PR 1836C, SS 548, US 90

COUNTY Harris, Montgomery

CONTROL SECTION JOB				0028-02-110		0177-05-127		0177-06-095		0177-07-125		0177-11-163		0271-14-247	
PROJECT ID				A00198787		A00198784		A00198786		A00200442		A00200455		A00198666	
COUNTY				Harris		Montgomery		Harris		Harris		Harris		Harris	
HIGHWAY				US 90		IH 69		IH 69		IH 69		IH 69		IH 610	
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL
	100-6013	PREP ROW (TREE) (2" TO 12" DIA)	EA	4.000		14.000		9.000		25.000		2.000		34.000	
	160-6005	FURNISHING AND PLACING TOPSOIL	CY												
	161-6009	EROSION CONTROL COMPOST	CY											2,097.000	
	161-6012	GENERAL USE COMPOST	CY											1,019.000	
	162-6002	BLOCK SODDING	SY												
	166-6001	FERTILIZER	AC												
	168-6001	VEGETATIVE WATERING	MG												
	192-6003	PLANT MATERIAL (3-GAL)	EA											2,261.000	
	192-6023	PLANT MATERIAL (15 GAL) (TREE)	EA											238.000	
	192-6028	PLANT MATERIAL (1 GAL) (SHRUB)	EA												
	192-6065	PLANT BED PREP (TYPE III)	SY											19,124.000	
	193-6001	PLANT MAINTENANCE	MO												
	193-6002	PLANT MAINTENANCE	CYC												
	500-6001	MOBILIZATION	LS												
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO												
	506-6040	BIODEG EROSN CONT LOGS (IN STL) (8")	LF											1,000.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF											1,000.000	
	730-6107	FULL - WIDTH MOWING	CYC												
	1006-6001	LANDSCAPE SOIL AMENDMENT (TYPE I)	SY											19,124.000	
	1006-6002	LANDSCAPE SOIL AMENDMENT (TYPE II)	SY											19,124.000	
	1006-6003	LANDSCAPE SOIL AMENDMENT (TYPE III)	SY											2,499.000	
	1006-6004	LANDSCAPE SOIL AMENDMENT (TYPE IV)	SY											12,495.000	
	1006-6005	LANDSCAPE SOIL AMENDMENT (TYPE V)	SY											2,499.000	
	1022-6003	LANDSCAPE TREATMENT(TY 3)	EA	0.188		0.214		0.032		0.125		0.023		0.013	
	1022-6004	LANDSCAPE TREATMENT(TY 4)	EA	0.376		0.428		0.064		0.250		0.046		0.026	
	1022-6005	LANDSCAPE TREATMENT (TY 5)	EA	0.188		0.214		0.032		0.125		0.023		0.013	
	1022-6006	LANDSCAPE TREATMENT (TY 6)	EA	0.188		0.214		0.032		0.125		0.023		0.013	
	1022-6007	LANDSCAPE TREATMENT (TY 7)	EA												
	1022-6008	LANDSCAPE TREATMENT (TY 8)	EA	0.300		0.250				0.150				0.150	
	1022-6010	LANDSCAPE TREATMENT (TY 10)	EA	0.188		0.214		0.032		0.125		0.023		0.013	
	6185-6002	TMA (STATIONARY)	DAY												
	6185-6005	TMA (MOBILE OPERATION)	DAY												
08		CONTRACTOR FORCE ACCOUNT LAW ENFORCEMENT (NON-PARTICIPATING)	LS												
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS												
		CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS												



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0508-01-394

DISTRICT Houston
HIGHWAY IH 10, IH 610, IH 69, PR 1836C, SS 548, US 90

COUNTY Harris, Montgomery

CONTROL SECTION JOB				0271-15-103		0376-01-015		0508-01-394		2483-01-016		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00200438		A00200456		A00198664		A00198788			
COUNTY				Harris		Harris		Harris		Harris			
HIGHWAY				IH 610		PR 1836C		IH 10		SS 548			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	100-6013	PREP ROW (TREE) (2" TO 12" DIA)	EA					26.000				114.000	
	160-6005	FURNISHING AND PLACING TOPSOIL	CY					12.000				12.000	
	161-6009	EROSION CONTROL COMPOST	CY	72.000								2,169.000	
	161-6012	GENERAL USE COMPOST	CY	36.000								1,055.000	
	162-6002	BLOCK SODDING	SY					45.000				45.000	
	166-6001	FERTILIZER	AC					0.010				0.010	
	168-6001	VEGETATIVE WATERING	MG					1.000				1.000	
	192-6003	PLANT MATERIAL (3-GAL)	EA									2,261.000	
	192-6023	PLANT MATERIAL (15 GAL) (TREE)	EA									238.000	
	192-6028	PLANT MATERIAL (1 GAL) (SHRUB)	EA	492.000								492.000	
	192-6065	PLANT BED PREP (TYPE III)	SY	656.000								19,780.000	
	193-6001	PLANT MAINTENANCE	MO					19.000				19.000	
	193-6002	PLANT MAINTENANCE	CYC					6.000				6.000	
	500-6001	MOBILIZATION	LS					1.000				1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO					8.000				8.000	
	506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF					48.000				1,048.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF					48.000				1,048.000	
	730-6107	FULL - WIDTH MOWING	CYC			6.000						6.000	
	1006-6001	LANDSCAPE SOIL AMENDMENT (TYPE I)	SY	656.000								19,780.000	
	1006-6002	LANDSCAPE SOIL AMENDMENT (TYPE II)	SY	656.000								19,780.000	
	1006-6003	LANDSCAPE SOIL AMENDMENT (TYPE III)	SY									2,499.000	
	1006-6004	LANDSCAPE SOIL AMENDMENT (TYPE IV)	SY									12,495.000	
	1006-6005	LANDSCAPE SOIL AMENDMENT (TYPE V)	SY	492.000								2,991.000	
	1022-6003	LANDSCAPE TREATMENT(TY 3)	EA	0.041				0.347		0.017		1.000	
	1022-6004	LANDSCAPE TREATMENT(TY 4)	EA	0.082				0.694		0.034		2.000	
	1022-6005	LANDSCAPE TREATMENT (TY 5)	EA	0.041				0.347		0.017		1.000	
	1022-6006	LANDSCAPE TREATMENT (TY 6)	EA	0.041				0.347		0.017		1.000	
	1022-6007	LANDSCAPE TREATMENT (TY 7)	EA			1.000						1.000	
	1022-6008	LANDSCAPE TREATMENT (TY 8)	EA					0.150				1.000	
	1022-6010	LANDSCAPE TREATMENT (TY 10)	EA	0.041				0.347		0.017		1.000	
	6185-6002	TMA (STATIONARY)	DAY					45.000				45.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY					60.000				60.000	
08		CONTRACTOR FORCE ACCOUNT LAW ENFORCEMENT (NON-PARTICIPATING)	LS					1.000				1.000	
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS					1.000				1.000	
		CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS					1.000				1.000	

SUMMARY OF ITEMS											
LOCATION	ITEM 100	ITEM 160	ITEM 161		ITEM 162	ITEM 165	ITEM 168	ITEM 192			
	6013	6005	6009	6012	6002	6001	6001	6008	6023	6028	6065
	PREP ROW (TREE) (2" TO 12" DIA)	FURNISHING AND PLACING TOPSOIL	EROSION CONTROL COMPOST	GENERAL USE COMPOST	BLOCK SODDING	FERTILIZER	VEGETATIVE WATERING	PLANT MATERIAL (3 GAL)	PLANT MATERIAL (15 GAL) (TREE)	PLANT MATERIAL (1 GAL) (TSHRUB)	PLANT BED PREP (TYPE III)
	EA	CY	CY	CY	SY	AC	CY	EA	EA	EA	SY
0028-02-110 (US 90)	4	0	0	0	0	0	0	0	0	0	0
0177-05-127 (IH 69)	14	0	0	0	0	0	0	0	0	0	0
0177-06-095 (IH 69)	9	0	0	0	0	0	0	0	0	0	0
0177-07-125 (IH 69)	25	0	0	0	0	0	0	0	0	0	0
0177-11-168 (IH 69)	2	0	0	0	0	0	0	0	0	0	0
0271-14-247 (IH 610)	34	0	2097	1019	0	0	0	2261	238	0	19124
0271-15-108 (IH 610)	0	0	72	36	0	0	0	0	0	492	656
0376-01-015 (PR 1836)	0	0	0	0	0	0	0	0	0	0	0
0508-01-394 (IH 10)	26	12	0	0	45	0.01	1	0	0	0	0
2483-01-016 (SS 548)	0	0	0	0	0	0	0	0	0	0	0
TOTAL	114	12	2169	1055	45	0.01	1	2261	238	492	19780

SUMMARY OF ITEMS												
LOCATION	ITEM 193		ITEM 500	ITEM 502	ITEM 506		ITEM 730	ITEM 1006				
	6001	6002	6001	6001	6041	6043	6107	6001	6002	6003	6004	6005
	PLANT MAINTENANCE	PLANT MAINTENANCE	MOBILIZATION	BARRICADES, SIGNS AND TRAFFIC HANDLING	BIODEG EROSN CONT LOGS (INSTL) (12")	BIODEG EROSN CONT LOGS (REMOVE)	FULL-WIDTH MOWING	LANDSCAPE SOIL AMENDMENT (TYPE I)	LANDSCAPE SOIL AMENDMENT (TYPE II)	LANDSCAPE SOIL AMENDMENT (TYPE III)	LANDSCAPE SOIL AMENDMENT (TYPE IV)	LANDSCAPE SOIL AMENDMENT (TYPE V)
	MO	CYC	LS	MO	LF	LF	CYC	SY	SY	SY	SY	SY
0028-02-110 (US 90)					0	0	0	0	0	0	0	0
0177-05-127 (IH 69)					0	0	0	0	0	0	0	0
0177-06-095 (IH 69)					0	0	0	0	0	0	0	0
0177-07-125 (IH 69)					0	0	0	0	0	0	0	0
0177-11-168 (IH 69)					0	0	0	0	0	0	0	0
0271-14-247 (IH 610)	21	7	1	8	1000	1000	0	19124	19124	2499	12495	2499
0271-15-108 (IH 610)					0	0	0	656	656	0	0	492
0376-01-015 (PR 1836)					0	0	6	0	0	0	0	0
0508-01-394 (IH 10)					48	48	0	0	0	0	0	0
2483-01-016 (SS 548)					0	0	0	0	0	0	0	0
TOTAL	19	6	1	8	1048	1048	6	19780	19780	2499	12495	2991

SUMMARY OF ITEMS									
LOCATION	ITEM 1022							ITEM 6185	
	6003	6004	6005	6006	6007	6008	6010	6002	6005
	LANDSCAPE TREATMENT (TY 3)	LANDSCAPE TREATMENT (TY 4)	LANDSCAPE TREATMENT (TY 5)	LANDSCAPE TREATMENT (TY 6)	LANDSCAPE TREATMENT (TY 7)	LANDSCAPE TREATMENT (TY 8)	LANDSCAPE TREATMENT (TY 10)	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	EA	EA	EA	EA	EA	EA	EA	DAY	DAY
0028-02-110 (US 90)	0.188	0.376	0.188	0.188	0	0.30	0.188		
0177-05-127 (IH 69)	0.214	0.428	0.214	0.214	0	0.25	0.214		
0177-06-095 (IH 69)	0.032	0.064	0.032	0.032	0	0	0.032		
0177-07-125 (IH 69)	0.125	0.25	0.125	0.125	0	0.00	0.125		
0177-11-168 (IH 69)	0.023	0.046	0.023	0.023	0	0	0.023		
0271-14-247 (IH 610)	0.013	0.026	0.013	0.013	0	0.15	0.013	75	75
0271-15-108 (IH 610)	0.041	0.082	0.041	0.041	0	0	0.041		
0376-01-015 (PR 1836)	0	0	0	0	1	0	0		
0508-01-394 (IH 10)	0.347	0.694	0.347	0.347	0	0.15	0.347		
2483-01-016 (SS 548)	0.017	0.034	0.017	0.017	0	0	0.017		
TOTAL	1	2	1	1	1	1	1	45	60

* SEE PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE
 ** QUANTITY INCLUDES MULTIPLE APPLICATIONS (SEE PLANTING AND ESTABLISHMENT SHEETS)
 *** THIS ITEM IS USED ONLY FOR TREES NOT REQUIRED FOR REMOVAL PER ITEM 193-6002, 1022-6003 OR 1022-6005. CONTRACTOR WILL MARK TREES FOR APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO WORK



Westwood 20329 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805

2023 Texas Department of Transportation

SUMMARY OF QUANTITIES

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO.	SHEET NO. 005
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEP 1 2023

BEGINNING OF PROJECT:

- INSTALL CONSTRUCTION BARRICADES AND PROJECT SIGNS AS PER BARRICADE AND CONSTRUCTION STANDARDS IN PLANS
- INSTALL SWP3 DEVICES AS NEEDED

ALL PHASES:

- INSTALL AND PLACE TRAFFIC CONTROL DEVICES AS PER TRAFFIC CONTROL PLAN STANDARDS IN PLANS AS NEEDED
- CONDUCT LANDSCAPE WORK
- PERFORM CLEAN-UP ON WORK AREAS

END OF PROJECT:

- REMOVE ALL TRAFFIC CONTROL DEVICES, ADVANCE WARNING SIGNS, AND SWP3 DEVICES



Mark C. Schluter

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MARK C. SCHLUTER, P.E. 53830 ON 08/30/2023. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



**TRAFFIC CONTROL PLAN
PHASING NARRATIVE**

SHEET 1 OF 1



FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	C508-1-394		006
STATE	DIST.	COUNTY	
TEXAS	HOU	HARRIS	
CONT.	SECT.	JOB	HIGHWAY NO.
0508	01	394,ETC	IH 10,ETC

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS			
BC (1) -21			
FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT	SECT	JOB
REVISIONS	0508 01	394, ETC IH 10, ETC	
4-03 7-13	DIST	COUNTY	SHEET NO.
9-07 8-14	HOU	HARRIS	007
5-10 5-21			


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "X" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25	36" x 36"	48" x 48"	50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14			55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12			60	600 ²
			65	700 ²
			70	800 ²
	75	900 ²		
	80	1000 ²		
	*	*	*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
—	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	008	

DATE: FILE:

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present.

Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 - 40 mph and greater 0.2 to 2 miles
 - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	050801	394, ETC	IH 10, ETC	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	009	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21

FILE#	bc-21.dgn	DW	TxDOT	CR	TxDOT	DW	TxDOT	CR	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0508 01	394, ETC		IH 10, ETC				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	HOU	HARRIS		010				


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- ### GENERAL NOTES
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		0508 01	394, ETC IH 10, ETC						
9-07	8-14	DIST:	COUNTY:	SHEET NO.:					
7-13	5-21	HOU:	HARRIS	011					

DATE: FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM - X PM
APR XX - XX X PM - X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM - XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

DATE: FILE:




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	012	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE:
FILE:

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY				
REVISIONS		0508 01	394, ETC IH 10, ETC						
9-07	8-14	DIST:	COUNTY		SHEET NO.				
7-13	5-21	HOU:	HARRIS		013				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane
Divider, Driveway sign D70a, Keep Right
R4 series or other signs as approved
by Engineer



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign
substrates shall NOT be used on
plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY				
REVISIONS		0508 01	394, ETC IH 10, ETC						
4-03	8-14	DIST:	COUNTY:		SHEET NO.				
9-07	5-21	HOU:	HARRIS		014				
7-13									


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long cones and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

**Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21


FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	015	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.



PLAN VIEW


1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW

These drums are not required on one-way roadway




PLAN VIEW

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508	01	394, ETC	IH 10, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	HARRIS	016	

DATE: FILE:

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11)-21

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS				
2-98	9-07	5-21	0508 01	394, ETC IH 10, ETC
1-02	7-13		DIST	COUNTY
11-02	8-14		HOU	HARRIS
				SHEET NO. 017

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A



REFLECTORIZED PAVEMENT MARKINGS - PATTERN B


Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.






RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 21



FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508	01	394, ETC	IH 10, ETC
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	HOU	HARRIS	018	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

BACKGROUND COLOR	SIGN DESIGNATION	SIGN	SIGN DIMENSIONS	REFLECTIVE SHEETING	SQ FT	GALVANIZED STRUCTURAL STEEL		DRILLED SHAFT
						Size	(LF)	
							① ②	24" DIA. (LF)
Orange	G20-7T		96" X 48"	Type B _{FL} or C _{FL}	32	▲	▲ ▲	▲
Orange	G20-7T		192" X 96"	Type B _{FL} or C _{FL}	128	W8x18	16 17	12

▲ See Note 6 Below

LEGEND

	Sign
	Large Sign
	Traffic Flow

DEPARTMENTAL MATERIAL SPECIFICATIONS

PLYWOOD SIGN BLANKS	DMS-7100
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL}
BLACK	LEGEND & BORDERS	NON-REFLECTIVE ACRYLIC FILM

GENERAL NOTES

1. See BC and SMD sheets for additional sign support details.
2. Sign locations shall be approved by the Engineer.
3. For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
4. Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
5. Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
6. The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
7. The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:
Item 636 - Aluminum Signs
Item 647 - Large Roadside Sign Supports and Assemblies.
Item 416 - Drilled Shaft Foundations
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.




WORK ZONE
"GIVE US A BRAKE"
SIGNS

WZ(BRK)-13


FILE: wzbrk-13.dgn	DWG: TxDOT	CHK: TxDOT	DATE: TxDOT	CR: TxDOT
©TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
6-96 5-98 7-13	DIST	COUNTY	SHEET NO.	
8-96 3-03	HOU	HARRIS, ETC	019	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TCP (1-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.



TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK



TCP (1-1) - 18

FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS	0508 01	394, ETC	IH 10, ETC	
2-94 4-98	DIST:	COUNTY:	SHEET NO.:	
8-95 2-12	HOU	HARRIS	020	
1-97 2-18				

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

TCP (1-2b)

- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP (1-2) - 18


FILE: tcp1-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
4-90 4-98	DIST	COUNTY	SHEET NO.	
2-94 2-12	HOU	HARRIS	021	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (1-4a)
ONE LANE CLOSED



TCP (1-4b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	$L = WS$	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

TCP (1-4b)

- Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

Texas Department of Transportation
Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
LANE CLOSURES ON MULTILANE
CONVENTIONAL ROADS**


TCP (1-4) - 18

FILE:	tcp1-4-18.dgn	DN:	CK:	DW:	CK:
© TxDOT	December 1985	CON:	SECT:	JOB:	HIGHWAY:
REVISIONS		0508 01	394, ETC	IH 10,	ETC
2-94	4-98	DIST:	COUNTY:	SHEET NO.	
8-95	2-12	HOU	HARRIS	022	
1-97	2-18				


154

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (5-1a)
WORK AREA ON SHOULDER



TCP (5-1b)
WORK AREA ON SHOULDER

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	$L = WS$	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset(FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

- GENERAL NOTES**
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
 - 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.





**TRAFFIC CONTROL PLAN
 SHOULDER WORK FOR
 FREEWAYS / EXPRESSWAYS**

TCP (5-1) - 18

FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0508 01	394, ETC IH 10, ETC	
	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	023	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Texas Department of Transportation
Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
FREEWAY LANE CLOSURES**

TCP (6-1) - 12


FILE:	tcp6-1.dgn	DN:	TxDOT	CK:	TxDOT	DN:	TxDOT	CK:	TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
8-12	REVISIONS	0508 01	394, ETC IH 10, ETC						
	DIST	COUNTY		SHEET NO.					
	HOU	HARRIS		024					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



TCP (6-2a)
ENTRANCE RAMP OPEN
WORK WITHIN 500' OF RAMP



TCP (6-2b)
ENTRANCE RAMP CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainline can be seen from both roadways.
- See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA NEAR RAMP

TCP (6-2) - 12


FILE:	tcp6-2.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	February 1994	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0508 01	394, ETC IH 10, ETC						
1-97	8-98	DIST	COUNTY		SHEET NO.				
4-98	8-12	HOU	HARRIS		025				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (6-3a)
ENTRANCE RAMP OPEN



TCP (6-3b)
EXIT RAMP CLOSED
TRAFFIC EXITS PRIOR TO CLOSED RAMP

STREET B
EXIT
CLOSED

USE
STREET A
EXIT

Or, as an option when
exits are numbered

EXIT XY
CLOSED

USE
EXIT XX

Place 1 mile (approx.)
in advance of Street A
exit.

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES:
1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard



TRAFFIC CONTROL PLAN
WORK AREA BEYOND RAMP

TCP (6-3) - 12

FILE: tcp6-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	HOU	HARRIS	026	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
 - See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard


TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP (6-4) - 12


FILE: tcp6-4.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	HOU	HARRIS	027	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (6-5a)
EXIT RAMP OPEN



TCP (6-5b)
**EXIT RAMP OPEN
TWO LANE CLOSURE WITHIN
1500' PAST EXIT RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" * * *			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

* * * Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
 - See BC standards for sign details.
 - If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN
WORK AREA BEYOND EXIT RAMP**

TCP (6-5) - 12


FILE:	tcp6-5.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CK:	TxDOT
©TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0508 01	394, ETC IH 10, ETC						
1-97	8-98	DIST	COUNTY		SHEET NO.				
4-98	8-12	HOU	HARRIS		028				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



TCP (6-8a)



TCP (6-8b)



TCP (6-8c)

LEGEND

	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT)
 S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Place channelizing devices in the gore at 20' spacing.
 - See the Standard Highway Sign Design for Texas (SHSD) for sign details.
 - The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
 - When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) for traffic control details.
 - Truck mounted attenuator is required.
 - The PCMS may be omitted if replaced with a "RAMP CLOSED" AHEAD (CW20RP-3D) Sign.
 - Roadway ADT should be greater than 10,000.

Texas Department of Transportation
 Traffic Operations Division Standard

WORK IN EXIT GORE FOR ADT GREATER THAN 10,000

TCP (6-8) - 14

FILE: tcp6-8.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0508 01	394, ETC	IH 10, ETC	
	DIST	COUNTY	SHEET NO.	
	HOU	HARRIS	029	

ITEM 193-6002 PLANT MAINTENANCE - CYC

BEGIN	** END	BEGIN	** END	BEGIN
193-6002	193-6002	193-6002	193-6002	193-6002
PLANT MAINTENANCE - CYC 1	PLANT MAINTENANCE - CYC 2	PLANT MAINTENANCE - CYC 2	PLANT MAINTENANCE - CYC 2	PLANT MAINTENANCE - CYC 2
ALL LOCATIONS ONCE	ALL LOCATIONS ONCE	ALL LOCATIONS ONCE	ALL LOCATIONS ONCE	ALL LOCATIONS ONCE

AS SHOWN ON PLANTING AND MAINTENANCE TIMELINE SHEET

REQUIREMENTS FOR EXISTING LANDSCAPE WITHIN TXDOT ROW

GENERAL

- Perform all requirements described on this sheet unless otherwise shown.
- Work area(s) include existing plant beds, areas adjacent to each existing plant bed, area adjacent to detention pond inlets/outlets, barrier slots and adjacent vegetation and landscape encroaching on and/or over TxDOT ROW from adjacent properties.
- Work includes removing trees, shrubs, grass and/or ground cover. Removals may actually reduce the original plant bed size and eliminate further maintenance of an area.
- Work includes pruning and removal of plant material growing on and/or hanging over TxDOT ROW:
 - Pruning in accordance with ANSI A300.
 - Removal of plant material, including stumps, to existing grade.
 - Chipping and evenly distributing plant debris on site.
 - Removing any plant debris too large to chip from site.
 - Filling any holes from the removal of plant material with topsoil, topsoil is incidental and not paid for separately.
 - Use of herbicide is permitted under the supervision of a licensed professional.
- Do not prune or remove more plant material than what can be chipped or removed the same day unless otherwise approved by Engineer.

SCOPE OF WORK

- Each cycle includes completing the specified work for all locations identified within the project limits once. The project limits include all area(s) within the entire full width, length and height (overhanging vegetation) of the right of way. Confine all maintenance operations and associated work to these areas and other such areas of the right-of-way that may be required to gain access to the area(s).
 - Each cycle includes completing the specified work for locations identified within the project limits one time.
 - One cycle is a one time treatment of the entire project limits unless noted differently in plans.

PLANT BED MAINTENANCE

- Redefine and/or reshape all existing planting areas in accordance with PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT sheets.
- Maintain planting areas so that planting areas do not hinder roadway drainage, especially behind slotted barrier.
 - Clean each barrier drain slot adjacent to planting area (see detail this sheet). Sediment may spread within bed area. Debris and trash must be properly disposed. Ensure positive drainage away from roadway and slotted openings. Removal of vegetation, soil, mulch, and debris is incidental.
- Chemically control weeds and undesirable grasses in planting areas with ROUNDUP PROMAX.

DETENTION POND INLET/OUTLET MAINTENANCE

- Maintenance is limited to approx. 20' around each pond inlet/outlet structure.
 - Contractor is responsible for locating and staking work area adjacent to each inlet/outlet structure.
 - Number of inlet/outlet structures vary for each pond within limits of project.
 - All locations will be approved prior to any additional work in these areas.
- Manually remove trees and shrubs to even with grade.
 - Chemically spot treat stumps with an approved herbicide.
- Mow approved work area(s) to height of 4"-7" after removal of trees and shrubs.

UNDESIRABLES

- Chemically treat and remove all JOHNSON GRASS within redefined planting areas, adjacent 5'- 7' perimeter areas and along fences/walls/structures adjacent to perimeter area with an approved herbicide.
 - Do not remove undesirable plant until herbicide manufacturer's recommended time period for herbicide absorption.
 - Repeat as required for complete kill.
- Remove invasive and/or undesirable trees, shrubs and vines within redefined planting areas, adjacent 5'- 7' perimeter areas and along fences/walls/structures adjacent to perimeter area.
 - Chemically treat stumps of cut invasive and/or undesirable plants with PATHFINDER II BASAL BARK HERBICIDE, or approved equal.
 - Invasive and/or undesirable plants include but are not limited to: willow, tallow, baccharis, mulberry, trumpet vine, bind weed, Japanese honeysuckle, morning glory, vetch, sunflower, etc.
 - Repeat stump treatment as necessary for complete kill.

HERBICIDE

- Chemically treat all areas as described herein with an approved herbicide as needed to control and/or kill weeds and/or stumps.
 - Perform herbicide applications under supervision of STATE LICENSED APPLICATOR.
 - Do not mow and/or trim until after herbicide manufacturer's recommended absorption time.
 - Do not allow herbicide to come in contact with desirable vines, shrubs, or trees, including seedlings.
 - Herbicide is subsidiary to ITEM 193-6002.

MOWING AND TRIMMING

- Mow a minimum of 5' to 20' maximum perimeter of all redefined planting areas, determined by original layouts and site conditions/constraints, to standard height (4"-7").
- Scalp mow/trim within all redefined planting areas, including between trees after herbicide manufacturer's recommended time period for herbicide absorption.
 - Trimming with cord trimmer is allowed within planting areas in between trees.
 - Many existing and new desirable seedling plants exist in planting areas, extra caution IS NECESSARY TO PROTECT SEEDLINGS.
 - Do not touch, scratch, or scar existing and new desirable plants.
 - Do not trim within 12" inches of any existing and new desirable plant. Tall grass may remain around desirable plant. Hand pull undesirable plants within 12" inches of desirable plant.
 - Damaged plants will be replaced, maintained, and warranted through duration of contract at Contractor's expense.
 - Damaged plants will be replaced immediately, unless otherwise directed.

PRUNING AND REMOVALS

- Prune all plants of any size, height, and diameter in the following conditions:
 - Within sight clearance areas for traffic and signage, see PLANT MAINTENANCE, Sheet 3, 4 AND 5 OF 6 (pruning related to signage applies to both existing and any new signs installed for the duration of contract).
 - With vertical clearance issues over any roadways and access routes (19' Min.), 8'- 10' width planting area perimeter (9' Min.) and sidewalks (9' Min.), see PLANT MAINTENANCE, Sheet 3 and 4 OF 6.
 - Prune all sucker growth and/or new limbs to maintain clear trunk in accordance with PLANT MAINTENANCE, Sheet 2 of 6.
 - Prune dead, dying or damaged branches/limbs (includes freeze and/or drought damage to any existing plant material).
- Remove all plants of any size, height, and diameter not conforming to PLANT MAINTENANCE, Sheet 4 and 5 of 6, and:
 - Remove dead, dying and non-viable plants with permanent structural damage.
 - Remove invasive or undesirable plants as described on this sheet.
 - Remove leaning trees more than Approx. 8" off center measured at a height of Approx. 5' (see leaning tree removal image this sheet).
 - Remove any existing stumps to grade.
 - Remove all pampas grass within planting areas unless otherwise noted on plans.
 - Remove oleanders, crape myrtle, wax myrtle, etc. (large shrubs) 75' in front of and 25' behind any ground mounted sign (small and large) unless otherwise noted on plans, treat stumps as described in note #14.
 - Remove crape myrtle, wax myrtle, etc. (multi-stemmed tree) located < 10' from travel lane and along entire edge of sign site triangle.
 - Remove all vines from trees and shrubs and vines that have fallen from installed support structure(s).
 - Remove all vines from barriers, fences, retaining walls, sign structures, sound walls, etc. adjacent to planting areas unless otherwise noted on plans.

STAKES AND STRAPS


- Remove all existing stakes, straps, guy wires, cables, and tags from site.

IRRIGATION SYSTEMS

- Remove any existing irrigation system not in use to grade within redefined planting areas.
 - Receive TxDOT approval prior to any removals.
 - Cap and seal all cut irrigation lines and pipes.
 - Removed irrigation system becomes the property of the Contractor and will be disposed of appropriately - removal is incidental.

OTHER

- Remove all litter and debris (rocks, tires, concrete, lumber, trash, bandit signs, etc.) located within planting areas.
- Treat all fire ant colonies within planting areas.
- Treat existing plants displaying evidence of insect, fungal, bacterial, or other negative indications - use appropriate methods and products for treatments.
- Remove silt fence, erosion control logs, and staking associated with any planting area unless directed otherwise.
- Access to some areas is constrained. No additional compensation is allowed for limited access.
- Reference ITEM 5.10 INSPECTION OF THE TEXAS STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES 2014.
- At any time during all phases of the contract, any materials or work performed not in accordance with plans and specifications will be replaced.
- Report missing or broken grates and/or manhole covers to project inspector and/or area office immediately.
- and/or reworked until in compliance with no additional compensation.
- Any adjustments due to the failure to comply with plans and specifications shown will be at Contractor's expense.
- District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment.
- Clean all concrete rails drainage slots and behind concrete rails at bridges.



CLEAN DRAIN SLOT AND BEHIND GUARD RAIL



LEANING TREE REMOVAL

CLEAR ZONE (Tree Setbacks)	
Dimensions are minimum requirements and are not limited to the items listed, adjustments will be made to accommodate site conditions.	
DO NOT PLANT WITHIN SIGHT TRIANGLE	
46'	Travel Lane (shoulder section) with slopes greater than or equal to 5:1
32'	Travel Lane (shoulder section) with slope less than 5:1, Direct Connector, Highmast Lighting, Overhead Transmission Line, CTMS, AVI, Camera, Sensor, Antenna, and/or Other Warning Devices
18'	Ramp, Overhead Distribution Line
10'	Bridge Overhang, Concrete Barrier, Curb, Ground Boxes, Guard Rail, Culvert/Inlet, Manhole, Retaining Wall, Ditch, Right-of-way Line, Riprap, Fence, Large and Small Sign (See PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT, Sheets 2 and 3 of 5 for sight triangles)



Westwood 20329 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805

©2023 Texas Department of Transportation

PLANT MAINTENANCE

SHEET 1 OF 6


FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.
6	27-12-169	D31
STATE	DISTRICT	COUNTY
TEXAS	HOU	FORT BEND, ETC
CONTROL	SECTION	JOB
0027	12	169, ETC
		HIGHWAY NO
		IH 69, ETC

NOV 2023


EXISTING




PRUNING REQUIREMENTS



FOUNDATION



PLANT MAINTENANCE - UNDERSTORY AND SUCKER GROWTH PRUNING, TRIMMING AND REMOVAL



Dana Dean Cote
08/30/2023

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

PLANT MAINTENANCE


SHEET 2 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 032
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC


NOV 2023

EXISTING


RETAINING WALL




DIRECT CONNECTOR




BARRIER








HIGHWAY SHOULDER








CURB



PROPOSED



FOUNDATION




PLANT MAINTENANCE - EDGE PRUNING, TRIMMING AND REMOVAL



08/30/2023

Westwood 20329 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805



PLANT MAINTENANCE


SHEET 3 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 033
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC


NOV 2023

FOUNDATION


SIGNS




PRUNING/REMOVALS




FOUNDATION




ELEVATION



CTMS
CTMS requires sight triangle one direction



Large Sign (double or triple post)
Applies to ground mounted and structure mounted (rails, wall, columns, etc.) signs



Small Sign
Applies to ground mounted and structure mounted (rails, wall, columns, etc.) signs

PLAN

PLANT MAINTENANCE - SIGHT CLEARANCE FOR SIGNAGE



Westwood 20329 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805


Texas Department of Transportation

PLANT MAINTENANCE


SHEET 4 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 034
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC


NOV 2023



Camera
Camera requires sight triangle both directions



High Mast Lighting, etc.
High mast lighting, sensors, antennas, etc. require full or partial circle depending on location and access required - access will be determined in the field



Ground Box, Inlet, Manhole, etc.
Include any riprap as part of structure

PLANT MAINTENANCE - CAMERA, HIGHMAST LIGHTING AND DRAIN INLET CLEARANCE



Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805


Texas Department of Transportation

PLANT MAINTENANCE


SHEET 5 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 035
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC


NOV 2023



EXISTING CONDITION



BRANCHES / LIMBS TO BE REMOVED




IMPROPERLY PRUNED TREES

Cut limbs at a major fork in the branch or, if the entire branch is encroaching into the area to be cleared, remove the branch at the trunk.

Do not leave a stub beyond the branch collar or cut through the branch collar when making pruning cuts.

The branch collar is generally visible, but if it is not, make the final cut approximately 1/2" from the parent branch or trunk, perpendicular to the branch or limb being removed.




PROPERLY PRUNED TREES


PLANT MAINTENANCE - BRANCH / LIMB REMOVAL

FLAILING EQUIPMENT IS NOT ALLOWED FOR THIS WORK

- A - STEP 1
Cut 1/3 way through bottom of limb 8-12" above main stem or trunk
- B - STEP 2
Remove limb 4-6" beyond the first cut
- C - STEP 3
Remove stub with a smooth cut just beyond the branch collar of the removed limb




PRUNING CUTS - LIMBS 2" IN DIAMETER AND GREATER



Dana Dean Cote
08/30/2023

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



PLANT MAINTENANCE

SHEET 6 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 036
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC

NOV 2023

ITEM 1022-6003 LANDSCAPE TREATMENT (TY 3) – EA

REQUIREMENTS FOR EXISTING LANDSCAPE WITHIN TXDOT ROW

1022-6003
LANDSCAPE TREATMENT (TY 3)
ALL LOCATIONS

AS SHOWN ON PLANTING AND MAINTENANCE TIMELINE SHEET

GENERAL

1. Perform all requirements described on this sheet unless otherwise shown.
2. Work area(s) include existing plant beds, areas adjacent to each existing plant bed, area adjacent to detention pond inlets/outlets, barrier slots and adjacent vegetation and landscape encroaching on and/or over TxDOT ROW from adjacent properties.
3. Work includes removing trees, shrubs, grass and/or ground cover. Removals may actually reduce the original plant bed size and eliminate further maintenance of an area.
4. Work includes pruning and removal of plant material growing on and/or hanging over TxDOT ROW:
 - Pruning in accordance with ANSI A300.
 - Removal of plant material, including stumps, to existing grade.
 - Chipping and evenly distributing plant debris on site.
 - Removing any plant debris too large to chip from site.
 - Filling any holes from the removal of plant material with topsoil, topsoil is incidental and not paid for separately.
 - Use of herbicide is permitted under the supervision of a licensed professional.
5. Do not prune or remove more plant material than what can be chipped or removed the same day unless otherwise approved by Engineer.

SCOPE OF WORK

6. Each cycle includes completing the specified work for all locations identified within the project limits once. The project limits include all area(s) within the entire full width, length and height (overhanging vegetation) of the right of way. Confine all maintenance operations and associated work to these areas and other such areas of the right-of-way that may be required to gain access to the area(s).
 - Each cycle includes completing the specified work for locations identified within the project limits one time.
 - One cycle is a one time treatment of the entire project limits unless noted differently in plans.

PLANT BED MAINTENANCE

7. Redefine and/or reshape all existing planting areas in accordance with PLANTING, ESTABLISHMENT and MAINTENANCE LAYOUT sheets.
8. Maintain planting areas so that planting areas do not hinder roadway drainage, especially behind slotted barrier.
 - Clean each barrier drain slot adjacent to planting area (see detail this sheet). Sediment may spread within bed area. Debris and trash must be properly disposed.
 - Ensure positive drainage away from roadway and slotted openings. Removal of vegetation, soil, mulch, and debris is incidental.
9. Chemically control weeds and undesirable grasses in planting areas with ROUNDUP PROMAX.

DETENTION POND INLET/OUTLET MAINTENANCE

10. Maintenance is limited to approx. 20' around each pond inlet/outlet structure.
 - Contractor is responsible for locating and staking work area adjacent to each inlet/outlet structure.
 - Number of inlet/outlet structures vary for each pond within limits of project.
 - All locations will be approved prior to any additional work in these areas.
11. Manually remove trees and shrubs to even with grade.
 - Chemically spot treat stumps with an approved herbicide.
12. Mow approved work area(s) to height of 4'-7" after removal of trees and shrubs.

UNDESIRABLES

13. Chemically treat and remove all JOHNSON GRASS within redefined planting areas, adjacent 5'- 7' perimeter areas and along fences/walls/structures adjacent to perimeter area with an approved herbicide.
 - Do not remove undesirable plant until herbicide manufacturer's recommended time period for herbicide absorption.
 - Repeat as required for complete kill.
14. Remove invasive and/or undesirable trees, shrubs and vines within redefined planting areas, adjacent 5'- 7' perimeter areas and along fences/walls/structures adjacent to perimeter area.
 - Chemically treat stumps of cut invasive and/or undesirable plants with PATHFINDER II BASAL BARK HERBICIDE, or approved equal.
 - Invasive and/or undesirable plants include but are not limited to: willow, tallow, baccharis, mulberry, trumpet vine, bind weed, Japanese honeysuckle, morning glory, vetch, sunflower, etc.
 - Repeat stump treatment as necessary for complete kill.

HERBICIDE

15. Chemically treat all areas as described herein with an approved herbicide as needed to control and/or kill weeds and/or stumps.
 - Perform herbicide applications under supervision of STATE LICENSED APPLICATOR.
 - Do not mow and/or trim until after herbicide manufacturer's recommended absorption time.
 - Do not allow herbicide to come in contact with desirable vines, shrubs, or trees, including seedlings.
 - Herbicide is subsidiary to ITEM 193-6002.

MOWING AND TRIMMING

16. Mow a minimum of 5' to 20' maximum perimeter of all redefined planting areas, determined by original layouts and site conditions/constraints, to standard height (4"-7").
17. Scalp mow/trim within all redefined planting areas, including between trees after herbicide manufacturer's recommended time period for herbicide absorption.
 - Trimming with cord trimmer is allowed within planting areas in between trees.
 - Many existing and new desirable seedling plants exist in planting areas, extra caution IS NECESSARY TO PROTECT SEEDLINGS.
 - Do not touch, scratch, or scar existing and new desirable plants.
 - Do not trim within 12" inches of any existing and new desirable plant. Tall grass may remain around desirable plant. Hand pull undesirable plants within 12" inches of desirable plant.
 - Damaged plants will be replaced, maintained, and warranted through duration of contract at Contractor's expense.
 - Damaged plants will be replaced immediately, unless otherwise directed.

PRUNING AND REMOVALS

18. Prune all plants of any size, height, and diameter in the following conditions:
 - Within sight clearance areas for traffic and signage, see PLANT MAINTENANCE, Sheet 3, 4 AND 5 OF 6 (pruning related to signage applies to both existing and any new signs installed for the duration of contract).
 - With vertical clearance issues over any roadways and access routes (19' Min.), 8'- 10' width planting area perimeter (9' Min.) and sidewalks (9' Min.), see PLANT MAINTENANCE, Sheet 3 and 4 OF 6.
 - Prune all sucker growth and/or new limbs to maintain clear trunk in accordance with PLANT MAINTENANCE, Sheet 2 of 6.
 - Prune dead, dying or damaged branches/limbs (Includes freeze and/or drought damage to any existing plant material).
19. Remove all plants of any size, height, and diameter not conforming to PLANT MAINTENANCE, Sheet 4 and 5 of 6, and:
 - Remove dead, dying and non-viable plants with permanent structural damage.
 - Remove invasive or undesirable plants as described on this sheet.
 - Remove leaning trees more than Approx. 8" off center measured at a height of Approx. 5' (see leaning tree removal image this sheet).
 - Remove any existing stumps to grade.
 - Remove all pampas grass within planting areas unless otherwise noted on plans.
 - Remove oleanders, crape myrtle, wax myrtle, etc. (large shrubs) 75' in front of and 25' behind any ground mounted sign (small and large) unless otherwise noted on plans, treat stumps as described in note #14.
 - Remove crape myrtle, wax myrtle, etc. (multi-stemmed tree) located < 10' from travel lane and along entire edge of sign site triangle.
 - Remove all vines from trees and shrubs and vines that have fallen from installed support structure(s).
 - Remove all vines from barriers, fences, retaining walls, sign structures, sound walls, etc. adjacent to planting areas unless otherwise noted on plans.

STAKES AND STRAPS

20. Remove all existing stakes, straps, guy wires, cables, and tags from site.



IRRIGATION SYSTEMS

21. Remove any existing irrigation system not in use to grade within redefined planting areas.
 - Receive TxDOT approval prior to any removals.
 - Cap and seal all cut irrigation lines and pipes.
 - Removed irrigation system becomes the property of the Contractor and will be disposed of appropriately – removal is incidental.


OTHER

22. Remove all litter and debris (rocks, tires, concrete, lumber, trash, bandit signs, etc.) located within planting areas.
23. Treat all fire ant colonies within planting areas.
24. Treat existing plants displaying evidence of insect, fungal, bacterial, or other negative indications – use appropriate methods and products for treatments.
25. Remove silt fence, erosion control logs, and staking associated with any planting area unless directed otherwise.
26. Access to some areas is constrained. No additional compensation is allowed for limited access.
27. Reference ITEM 5.10 INSPECTION OF THE TEXAS STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES 2014. At any time during all phases of the contract, any materials or work performed not in accordance with plans and specifications will be replaced.
28. Report missing or broken grates and/or manhole covers to project inspector and/or area office immediately and/or reworked until in compliance with no additional compensation.
29. Any adjustments due to the failure to comply with plans and specifications shown will be at Contractor's expense.
30. District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment.
31. Clean all concrete rails drainage slots and behind concrete rails at bridges.

CLEAR ZONE (Tree Setbacks)	
Dimensions are minimum requirements and are not limited to the items listed, adjustments will be made to accommodate site conditions.	
DO NOT PLANT WITHIN SIGHT TRIANGLE	
46'	Travel Lane (shoulder section) with slopes greater than or equal to 5:1
32'	Travel Lane (shoulder section) with slope less than 5:1, Direct Connector, Highmast Lighting, Overhead Transmission Line, CTMS, AVI, Camera, Sensor, Antenna, and/or Other Warning Devices
18'	Ramp, Overhead Distribution Line
10'	Bridge Overhang, Concrete Barrier, Curb, Ground Boxes, Guard Rail, Culvert/Inlet, Manhole, Retaining Wall, Ditch, Right-of-way Line, Riprap, Fence, Large and Small Sign (See PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT, Sheets 2 and 3 of 5 for sight triangles)



LEANING TREE REMOVAL



08/30/2023

20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-469
TX REG. SURVEYING FIRM LS-10193805

Westwood

Texas Department of Transportation

LANDSCAPE TREATMENT (TY 3)

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO.
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC

NOV 2023

ITEM 1022-6004 LANDSCAPE TREATMENT (TY 4) – EA

1022-6004
LANDSCAPE TREATMENT (TY4)
ALL LOCATIONS ONCE

AS SHOWN ON PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE, SHEET 1 OF 1


REQUIREMENTS FOR TRIMMING EXISTING LARGE SHRUBS (OLEANDERS)

GENERAL

- All requirements described under ITEM 1022-6004 for existing landscape areas apply.
- Work areas shown in plans must be identified by Contractor in the field and approved by Engineer Prior to beginning any work.
 - For each treatment, perform all requirements described on this sheet unless otherwise shown.
- Work includes pruning/trimming of oleanders and/or large shrubs and subsequent removal of plant material debris:
 - Prune/trim in accordance with ANSI 300.
 - Pruned/trimmed plant material debris may be chipped and spread evenly of site or removed from site.
 - Do not create more plant material debris than what can be removed from the site the same day unless otherwise directed.
- Each treatment includes completing the specified work for all locations identified within the project limits once.

TRIMMING

- Trim all oleanders and/or large shrubs in designated areas shown in plans.
- Trim all oleanders and/or large shrubs in accordance with details shown.
- District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment.



LARGE SHRUB PRUNING (OLEANDER AND/OR OTHER LARGE SHRUB SHOWN IN PLANS)

GENERAL

LARGE SHRUB PRUNING OCCURS ONLY ONCE DURING THE CONTRACT PERIOD AS DIRECTED. Make an examination of the project site and become familiar with the nature and extent of the work to be accomplished. No extra compensation will be allowed for work made necessary by unusual conditions or obstacles encountered during the progress of the work. Damage to any utilities, structures or right-of-way by the Contractor will be repaired at Contractor's expense.

SCHEDULE

Schedule and sequence all work activities in order to complete the work within the specified timeframe.

CERTIFICATION


Certification and/or reference that, through training and/or on the job experience, Contractor is familiar with the techniques and equipment required for the proposed work.

EQUIPMENT

Furnish all equipment, tools and machinery, in good repair and operating condition, necessary for the proper prosecution of the proposed work. If at anytime the Engineer determines any equipment is defective to the point that it may affect the quality of work, that equipment will be immediately repaired or replaced.

SCOPE OF WORK

The project limits include all area(s) shown on the plans. Confine all maintenance operations and associated work to these areas and other such areas of the right-of-way that may be required to gain access to the area(s). Prune OLEANDERS in the manner described in these details. Pruning and trimming will conform to approved and/or acceptable horticultural practices included in ANSI 300 and appropriate to the type of shrub and special conditions. PRUNE AND TRIM A 30' SECTION OF BOTH SINGLE AND MULTIPLE ROW PLANTINGS IN THE PRESENCE OF THE ENGINEER BEFORE FULL SCALE PRUNING OPERATIONS BEGIN.



Dana Dean Cote
08/30/2023

Westwood		20329 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805	
		Texas Department of Transportation	
LANDSCAPE TREATMENT (TY 4)			
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 038	
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC	
CONTROL 0027	SECTION 12	JOB 169, ETC	HIGHWAY NO IH 69, ETC

ITEM 1022-6005 LANDSCAPE TREATMENT (TY5) - EA

BEGIN ** END

1022-6005
LANDSCAPE TREATMENT (TY5)
ALL LOCATIONS ONCE

AS SHOWN ON PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE, SHEET 1 OF 1

REQUIREMENTS FOR TRIMMING AND REMOVING HAZARDOUS TREES AND/OR PALMS

GENERAL

1. Work areas shown in plans must be identified by Contractor in the field and approved by Landscape Architect Prior to beginning any work.
 - Limits of work include entire TXDOT ROW and any nearby tree overhanging or which can impact anything within TXDOT ROW.
2. Trees to be pruned/removed must be tagged for Landscape Architect review and approval.
 - For each treatment, perform all requirements described on this sheet unless otherwise shown.
3. Work includes pruning and trimming of all trees and tree limbs and/or removal of dead or dying trees of any size, including palms, that could become hazard to roadway.
 - Prune/trim in accordance with ANSI 300.
 - Pruned/trimmed plant material debris may be chipped and spread evenly on site within existing landscape areas or removed from site. Chipped debris location must be approved prior to work.
 - Do not create more plant material debris than what can be removed from the site the same day unless otherwise directed.
 - Remove to smooth grade
4. Each treatment includes completing the specified work for all locations identified within the project limits.
5. Remove any hazardous tree, including palms, as directed by landscape architect.

TRIMMING

6. Trim any tree limbs as directed by Landscape Architect. Trim trees as shown in details.
7. Remove all large dead trees, including palms, that could create a hazardous condition in roadway in accordance with details shown.
8. District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment.

STUMP TO GRADE

9. All removals must be smooth with existing grade. Stumps above existing grade are not allowed.

CRITICAL TREE PRUNING AND REMOVAL OCCURS ONLY ONCE DURING THE CONTRACT PERIOD.

10. Make an examination of the project site and become familiar with the nature and extent of the work to be accomplished.
 - No extra compensation will be allowed for work made necessary by unusual conditions or obstacles encountered during the progress of the work.
 - Damage to any utilities, structures or right-of-way by the Contractor will be repaired at Contractor's expense.

SCHEDULE

11. Schedule and sequence all work activities in order to complete the work within the specified timeframe.

CERTIFICATION

12. Certification and/or reference that, through training and/or on the job experience, Contractor is familiar with the techniques and equipment required for the proposed work.

EQUIPMENT

13. Furnish all equipment, tools and machinery, in good repair and operating condition, necessary for the proper prosecution of the proposed work. If at anytime the Engineer determines any equipment is defective to the point that it may affect the quality of work, that equipment will be immediately repaired or replaced.

SCOPE OF WORK

14. The project limits include all area(s) within the entire full width and length of the right of way. Confine all maintenance operations and associated work to these areas and other such areas of the right-of-way that may be required to gain access to the area(s).
15. Access is limited. No additional compensation is allowed for limited access or constrained areas.
16. One cycle is a one time treatment of the entire project limits unless noted different in plans.

TRAFFIC CONTROL

17. Traffic control must be approved by the Engineer prior to work.
18. Follow traffic control plans and details.
19. Traffic controls necessary for work on freeway mainlanes ingress/egress, ramps, connectors, bridges, HOV/HOT lanes, and mainlane shoulders will be provided by TXDOT.
 - Traffic control in all other locations and condition is the responsibility of the Contractor.
20. Contractor is responsible for coordination and planning.
21. Traffic control, barricades, and costs in all other locations and condition is the responsibility of the Contractor.

PRUNE TREES PROPERLY

Cut limbs at a major fork in the branch or, if the entire branch is encroaching into the area to be cleared, remove the branch at the trunk.

Do not leave a stub beyond the branch collar or cut through the branch collar when making pruning cuts.


The branch collar is generally visible, but if it is not, make the final cut approximately 1/2" from the parent branch or trunk, perpendicular to the branch or limb being removed.

FLAILING EQUIPMENT IS NOT ALLOWED FOR THIS WORK


A - STEP 1
Cut 1/3 way through bottom of limb 8-12" above main stem or trunk

B - STEP 2
Remove limb 4-6" beyond the first cut

C - STEP 3
Remove stub with a smooth cut just beyond the branch collar of the removed limb



PRUNING CUTS - LIMBS 2" IN DIAMETER AND GREATER



CRITICAL TREE PRUNING AND REMOVAL (ROADSIDE LANDSCAPE AREA)



08-30-2023

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

LANDSCAPE TREATMENT (TY 5)

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 039	
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC	
CONTROL 0027	SECTION 12	JOB 169, ETC	HIGHWAY NO IH 69, ETC

NOV 2023


ITEM 1022-6006 LANDSCAPE TREATMENT (TY 6) - EA

1022-6006
LANDSCAPE TREATMENT (TY6)
ALL LOCATIONS ONCE

AS SHOWN ON PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE, SHEET 1 OF 1

TRAFFIC CONTROL

- Traffic control must be approved by the engineer prior to work.
- Follow traffic control plans and details.
- Traffic control is necessary for work on freeway mainlanes ingress/egress ramps, connectors, bridges, HOV/HOT lanes, and mainlane shoulders will be provided by TXDOT. Contractor is responsible for coordination and planning.
- Traffic control in all other locations and condition is the responsibility of the contractor



** See note below for dripline of direct connector.

* Mow edge varies at signs and structures
** 29' mow edge adjacent to direct connectors

REQUIREMENTS FOR REMOVING AND TREATING VEGETATION ON STRUCTURES, IN PAVEMENT, AROUND COLUMNS/POLES AND CLEARING BULLPEN AREAS.


GENERAL

1. All requirements described under ITEM 1022-6006 for roadway structures with in right of work corridor including guardrails, columns, bull pens, fencing, coping, MSE walls, sound walls, poles.
2. Work areas shown in plans must be identified by Contractor in the field and approved by Engineer Prior to beginning any work.
- For each treatment, perform all requirements described on this sheet unless otherwise shown.
3. Work includes the manual and/or mechanical removal of vegetative material growing in cracks and spaces of concrete and metal structures.
4. Herbicide all stumps, cracks, and for areas where vegetation is removed.
5. Clean bull pen areas, remove all debris, silt, vegetation, trash, and deliterious materials.
identified within the project limits once. Bullpens are extremely constrained areas between traffic rails, walls, mainlanes and frontage roads, HOV/HOT lanes, connector ramps, under HOV/HOT lanes, under connectors, etc.
6. In all bullpen areas, contractor is required to clear and remove all silt and debris in concrete rail drainage slots.
7. Site conditions are constrained. Contractor is responsible for accessing all location regardless of constraints, height, elevation, scope, and grade.
8. Clear all inlet grates and drainage to inlets.
9. Access to work is limited. No additional compensation will be allowed for work areas mad necessary by conditions or obstacles encountered during progress of the work.



Dana Dean Cote
08/30/2023

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



LANDSCAPE TREATMENT (TY 6)

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 040
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC

NOV 2023

ITEM 1022-6007 LANDSCAPE TREATMENT (TY 7) – EA

1022-6007 LANDSCAPE TREATMENT (TY 7) AS SHOWN ON PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE, SHEET 1 OF 1
ALL LOCATIONS ONCE

GENERAL

1. Work areas shown in plans must be identified by Contractor in the field and approved by Landscape Architect Prior to beginning any work.
2. Contractor to make an examination of the project site and become familiar with the nature and extent of the work to be completed. no extra compensation will be allowed for work made damage to existing utilities, structures, or right of way by the contractor will repaired at contractors expense.
3. For each treatment, perform all requirements described on this sheet unless otherwise shown.
4. Each treatment includes completing the specified work for all locations identified within the project limits.
5. District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment. All items pertaining to this Treatment are incidental to this item and will paid for by the Treatment, unless otherwise noted.
6. No disturbance (includes rutting), excavation, or cutting of existing soils is allowed. All work to be performed in accordance with this treatment is to be performed without disturbance of soils.
7. Any structure, cut stone, or existing elements found while clearing are to remain in place and not be disturbed. Handwork may be required around existing elements. No additional compensation is allowed for handwork.
 - 7A. Notify on site Texas Historical Committee staff of located elements.
 - 7B. Notify TXDOT site inspector and District Landscape Architect for clarification of work within these areas.
8. Contractor to coordinate with onsite Texas Historical Committee (THC) staff for bird survey and nesting site coordination.
9. Contractor to coordinate with onsite THC for special events that may impact progress of work.
 - 9A. THC should provide minimum two week notice for each event.
10. Aquatic appropriate herbicide to be used for all applications defined in clearing notes below. Contractor is to submit product data to be used to TXDOT for approval prior to utilization.
11. Contractor is to access treatment area as described on plans.
 - 10A. Coordinate with THC for vehicle and equipment parking and/or storage.
12. Contractor is responsible for accessing entire site location. No additional compensation is allowed for unique requirements necessary for accessing all vegetation and removal locations.
13. Any adjustments due to the failure to comply with plans and specifications shown will be at Contractor's expense.

EQUIPMENT:

1. Mechanical equipment is allowed to be used within this treatment area.
 - 1A. Furnish all equipment, tools, and machinery.
 - 1B. All equipment is to be in good repair and operating condition, necessary for the proper prosecution of the proposed work.
 - 1C. If at any time the engineer determines any equipment unsafe or is indirectly causing a negative impact to the sites environment, that equipment will be immediately repaired or replaced.
2. Pressure wash equipment, tools, and machinery before equipment, tools, and machinery enters or leaves designated areas shown on plans. Notify the inspector before washing, the inspector will approve the washing locations so seed and plant material is contained.
 - 3A. Any equipment taken off site and brought back will need to repeat this process each time.
 - 3B. This process will remain in tact / force for the entire duration of the project.
3. Metal track equipment/machinery is not allowed within San Jacinto Monument areas.
4. Contractor will make every effort to avoid any type of rutting. If any rutting does occurs, Contractor is to notify THC of impact for monitoring.
5. Coordinate with San Jacinto Monument for parking and laydown, equipment storage areas.

CLEARING:

1. Work includes removal of plant material as described below.
2. Removal of dead, diseased or dying trees of any size and species, including palms, that could become hazard to roadway or project site. Reference Landscape Treatment TY 5 sheet for additional information.
3. Removal of invasive tree species as listed by the Texas A & M Forest Service and Texas Parks and Wildlife Department.
4. Removal of all plant material that is 11" caliper or less, measured at DBH. Exclusions to this removal are listed below.
 - 4A. Any tree between 8"-11" caliper is to be flagged and approved by Landscape Architect prior to removal.
 - 4B. Treat stumps with herbicide.
5. Tree Clearing Exclusions:
 - 5A. Bald Cypress of any size located within the treatment limits shall remain in place.
 - 5B. Any tree found to be in conjunction with nesting birds is to remain in place.
 - 5C. Any tree flagged or taped off by the THC staff is to remain in place.
6. Removal of all vines and vegetation found on trees.
 - 6A. Remove all vegetation within 5' from the ground.
 - 6B. Treat vines with herbicide.
7. Removal of all underbrush, woody / herbaceous material, etc. to grade.

TRIMMING

1. Prune/trim in accordance with ANSI 300.
2. Prune all trees, limbs, etc to height of 5' from grade.

STUMP TO GRADE:

1. Stumps are to be trimmed and removed flush with existing grade.
2. All tree, vine and brush stumps are to be treated with herbicide following trimming.

CHIPPING:

1. Pruned / trimmed / removed plant material debris may be chipped and spread evenly on site the same day unless otherwise directed.
2. Do not create more plant material debris than what can be chipped or removed from the site within 48 hrs unless otherwise directed.
3. Any trunks or large sections of limbs that can not be shredded are to be hauled off site.

TRASH AND DEBRIS REMOVAL


1. Remove all non-vegetative trash and debris within treatment area off site.
2. Any debris located within designated debris pile locations on plans in accordance with Treatment must be removed and hauled off site.

SCHEDULE:

1. Schedule and sequence all work activities in order to complete within the specific timeframe.
2. Any work done within the months of March – July will need to be coordinated with THC to avoid tree and ground nesting bird sites within treatment area(s).

TREE AND GROUND NESTING BIRD SCHEDULE

NO WORK TO BE DONE WITHIN THESE MONTHS UNLESS OTHERWISE APPROVED BY THC AND TXDOT REPRESENTATIVE. SUBMIT ALL REQUESTS TO TXDOT FOR APPROVAL PRIOR TO ANY WORK.												
MONTH	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
TREE REMOVAL			X	X	X	X	X					
TREE TRIMMING			X	X	X	X	X					
UNDER-STORY REMOVAL								X	X	X	X	
MOWING Ref. ITEM 730-6107								X	X	X	X	



Dana Dean Cote
08/30/2023

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

LANDSCAPE TREATMENT (TY 7)

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 041
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC

NOV 2023

ITEM 1022-6008 LANDSCAPE TREATMENT (TY 8) - EA

1022-6008
LANDSCAPE TREATMENT (TY 8)
ALL LOCATIONS ONCE

AS SHOWN ON PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE, SHEET 1 OF 1

Requirements for existing detention pond, channels, inlets/outlets, basins and other drainage structures located in TxDOT right of way for entire limits of contract.

General:

1. Perform all requirements described on this sheet unless otherwise shown. Projects limits is the entire TxDOT right of way.
2. Each cycle includes completing the all of the work for all locations within the project limits once.
3. Each cycle will be paid separately.
4. Access to some areas is constrained, accessible only by water or muddy areas. No additional compensation is allowed for limited access.
5. Contractor is responsible for accessing entire water bodies and muddy areas. No additional compensation is allowed for unique requirements necessary for accessing all vegetation.
6. Reference Item 5.10 Inspection of the Texas Standard Specifications for construction and maintenance of highways, streets, and bridges 2014. At any time during all phases of the contract, any materials or work performed not in accordance with plans and specifications will be replaced and/or reworded until in compliance with no additional compensation.
7. Any adjustments due to the failure to comply with plans and specifications shown will be at Contractor's expense.
8. District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment.

Herbicide:

9. Herbicide is incidental to Item 1022 and will not be paid separately. Herbicide must be provided by Contractor.
10. Submit herbicide to District Landscape Architect or Vegetation Specialist for approval prior to work.
11. Perform herbicide applications under supervision of a State Licensed Applicator.
12. Follow herbicide label for application methods, rates, safety requirements, and additional requirements.
13. Chemically treat all grasses, shrubs, cat tails, weeds, trees, vines, and brush with an approved herbicide meeting Texas Department of Agriculture, Texas Commission on Environmental Quality, and EPA requirements for herbicide use in aquatic areas.
14. Treatment includes all areas of detention ponds, outfall channels, inlets, and drainage structures located in TxDOT right of way.
15. Application must result in complete kill of grasses, shrubs, cat tails, trees, vines, and brush. Contractor is required to achieve complete kill of vegetation. Follow herbicide label for allowances to reapply herbicide.
 - Achieving complete kill may require multiple applications.
 - No additional compensation allowed for additional applications

Pruning and Removals:

16. Pruning and removal may begin following visual confirmation of complete kill and time period allowing for complete kill and as specified on herbicide label.
17. Prune and remove vegetation accessible by hand without wading into water. Removal is limited to areas easily accessed by worker standing on moderately solid ground.
18. Pruned and removed vegetation must be removed from site and properly disposed.
19. Prune or remove vegetation to match level of water surface if in water body, or to match level of existing grade in other areas.
20. Do not dig into soil or impact grading.

Debris Removal:

21. At time of vegetation pruning and removal, contractor is responsible for removing all trash and debris located in areas where pruned and removed vegetation are located. Trash and debris removal is incidental to Item 1022 and will not be paid separately.



20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Westwood

©2023
Texas Department of Transportation

LANDSCAPE TREATMENT (TY 8)

SHEET 1 OF 1

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 042
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC
CONTROL 0027	SECTION 12	JOB 169, ETC
		HIGHWAY NO IH 69, ETC

NOV 2023

ITEM 1022-6010 LANDSCAPE TREATMENT (TY10) - EA

BEGIN ** END

**1022-6010
LANDSCAPE TREATMENT(TY10)
ALL LOCATIONS ONCE**

AS SHOWN ON PLANTING, MAINTENANCE AND ESTABLISHMENT TIMELINE, SHEET 1 OF 1

REQUIREMENTS FOR EXISTING SIDEWALK AND PEDESTRIAN ACCESS LOCATION IN TXDOT RIGHT OF WAY FOR ENTIRE LIMITS OF CONTRACT.

GENERAL

1. Perform all requirements described on this sheet unless otherwise shown. Project limits is the entire TXDOT Right of Way.
2. EACH CYCLE INCLUDES COMPLETING THE SPECIFIED WORK FOR ALL LOCATIONS IDENTIFIED WITHIN THE PROJECT LIMITS ONCE.
3. Access to some areas is constrained. No additional compensation is allowed for limited access.
4. Reference ITEM 5.10 INSPECTION OF THE TEXAS STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES 2014.
At any time during all phases of the contract, any materials or work performed not in accordance with plans and specifications will be replaced and/or reworked until in compliance with no additional compensation.
5. Any adjustments due to the failure to comply with plans and specifications shown will be at Contractor's expense.
6. District Landscape Architect or Vegetation Specialist must approve completed work prior to acceptance and payment.

SIDEWALKS AND RAMPS

7. Remove all silt, vegetation, trash, and debris located on ramps, sidewalks, ramp aprons, and gutters immediately at ramps.
8. Mow 5' along all perimeters and trim all vegetation edges at ramps and sidewalks.
9. Some locations may be covered by silt and vegetation. Contractor is responsible for uncovering and cleaning regardless of existing condition.
10. Debris must be removed daily, temporary piles are not allowed.


SCOPE OF WORK

11. The project limits include all area(s) within the entire full width and length of the right of way. Confine all maintenance operations and associated work to these areas and other such areas of the right-of-way that may be required to gain access to the area(s).
12. Access is limited. No additional compensation is allowed for limited access or constrained areas.
13. One cycle is a one time treatment of the entire limit project limits unless noted different in plans.
14. Each cycle includes completing the specified work for locations identified within the project limits one time.



Dana Dean Cote
08-30-2023

Westwood 20329 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-459
TX REG. SURVEYING FIRM LS-10193605



LANDSCAPE TREATMENT (TY 10)

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. 27-12-169	SHEET NO. 043	
STATE TEXAS	DISTRICT HOU	COUNTY FORT BEND, ETC	
CONTROL 0027	SECTION 12	JOB 169, ETC	HIGHWAY NO IH 69, ETC


NOV 2023

CLEAR ZONE (Tree Setbacks)	
Dimensions are minimum requirements and are not limited to the items listed, adjustments will be made to accommodate site conditions.	
DO NOT PLANT WITHIN SIGHT TRIANGLE	
46'	Travel Lane (shoulder section) with slopes greater than or equal to 5:1
32'	Travel Lane (shoulder section) with slope less than 5:1, Highmast Lighting, Overhead Transmission Line, CTMS, AVI, Camera, Sensor, Antenna, and/or Other Warning Devices
18'	Ramp, Overhead Distribution Line
10'	Bridge Overhang, Concrete Barrier, Curb, Ground Boxes, Guard Rail, Culvert/Inlet, Manhole, Retaining Wall, Ditch, Right-of-way Line, Riprap, Fence, Large and Small Sign (See PLANTING LAYOUT DETAILS, Sheet 3 of 4 for sight triangles)

NOTES:


- All planting and maintenance areas will be located within the limits of the project.
- PLANTING AND MAINTENANCE (TYPICAL) LAYOUT, Sheets 1 Thru 4 are diagrammatic representations of proposed work areas, clear zones and plant layout. Actual layout may be modified in the field by Landscape Architect to accommodate site conditions.
- Layout all planting and maintenance areas before starting any plant installation. Locate and stake all items and/or limits of work to be performed in the field. All locations will be approved prior to any work. Any work performed prior to approval will not be paid for, and any adjustments will be at Contractors expense.

LEGEND	
	GRP TREE/SHRUB PLANTING, ESTABLISHMENT AND MAINTENANCE AREA (TYP)
	GRP SHRUB ONLY PLANTING, ESTABLISHMENT AND MAINTENANCE AREA (TYP)
	MOW EDGE OF PLANTING, ESTABLISHMENT AND MAINTENANCE AREA (TYP)




Roadway Planting and Maintenance Areas (Typ)


See CLEAR ZONE table this sheet for dimensions not shown.



Typical Elevation



Typical Elevation



Typical Elevation



08/30/2023


NTS

PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT


SHEET 1 OF 5

Texas Department of Transportation		
FED. RD. DIV. NO. 6	PROJECT NO. C508-1-394	SHEET NO. 044
STATE TEXAS	DIST. HOU	COUNTY HARRIS
CONT. 0508	SECT. 01	JOB 394, ETC
		HIGHWAY NO. IH 10, ETC


HIGHWAY TRAVEL LANES



Landscape areas vary in size, shape, location, number and access. All available areas will be determined in the field with Landscape Architect.



Dana Dean Cote
 08/30/2023



Interchange Planting and Maintenance Areas (Typ)
 Interchange w/ Direct Connectors


NTS
 08/30/2023
 PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT
 SHEET 2 OF 5

Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	C508-1-394	045	
STATE	DIST.	COUNTY	
TEXAS	HOU	HARRIS	
CONT.	SECT.	JOB	HIGHWAY NO.
0508	01	394,ETC	IH 10, ETC


CLEAR ZONE / SIGHT DISTANCE REQUIREMENTS

Dimensions are minimum requirements and are not limited to the items shown, adjustments will be made to accommodate site conditions




Camera

Camera requires sight triangle both directions




Ditch





High Mast Lighting, etc.

High mast lighting, sensors, antennas, etc. require full or partial circle depending on location and access required - access will be determined in the field




CTMS

CTMS requires sight triangle one direction



Transmission lines
Overhead Lines




Large Sign (double or triple post)

Applies to ground mounted and structure mounted (rails, wall, columns, etc.) signs

Small Sign

Applies to ground mounted and structure mounted (rails, wall, columns, etc.) signs



Ground Box, Inlet, Manhole, etc.

Include any riprap as part of structure



08/30/2023


NTS

PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT

SHEET 3 OF 5




FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	C508-1-394	046	
STATE	DIST.	COUNTY	
TEXAS	HOU	HARRIS	
CONT.	SECT.	JOB	HIGHWAY NO.
0508	01	394,ETC	IH 10, ETC




PLANT LEGEND			
SYMBOL	DESC	SIZE (GAL)	% QTY
	Bald Cypress	3g	10%
	Bald Cypress	15g	10%
	Sycamore	3g	10%

- 1) Locate bed area(s) and determine square footage, unless otherwise shown in plans. The square footage determines tree quantities of each species. Use 8' O.C. spacing to determine quantities.
- 2) Evenly distribute Bald Cypress and Sycamore 8' O.C. in groups of 1, 3 and 5. These plants should be located first within and/or adjacent to poor drainage (moist and/or wet) areas of the site. If moist/wet areas dominate the site bald cypress should be planted one-for-one in lieu of loblolly pine.



PLANT LEGEND			
SYMBOL	DESC	SIZE (GAL)	% QTY
	Loblolly Pine	3g	10%
	Magnolia	3g	10%
	Crape Myrtle	3g	10%

- 1) Evenly distribute Loblolly Pine 8' O.C. in groups of 1, 3 and 5.
- 2) Evenly distribute Crape Myrtles 4' O.C. in groups of 3, or 5 (red, white and pink) within the interior of planting area(s) and freeway edge without barrier. Locate a minimum of 18' from any curb, barrier or retaining wall and to avoid conflict with signage.
- 3) Evenly distribute Magnolia 8' O.C. in groups or individually within the interior of the planting area(s).




PLANT LEGEND			
SYMBOL	DESC	SIZE (GAL)	% QTY
	Bur Oak	3g	5%
	Cedar Elm	3g	10%
	Shumard Oak	3g	10%
	Redbud	3g	5%
	White Oak	3g	10%

- 1) Evenly distribute Oaks, Elms and Redbud 8' O.C. in groups and individually within remaining area(s) as shown.

Tree Layout Sequence Within New Planting Area (Typ)
Trees Within New Planting Areas



PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT			
SHEET 4 OF 5			
FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	C508-1-394	047	
STATE	DIST.	COUNTY	
TEXAS	HOU	HARRIS	
CONT.	SECT.	JOB	HIGHWAY NO.
0508	01	394,ETC	IH 10, ETC




PLANT LEGEND			
SYMBOL	DESC	SIZE (GAL)	% QTY
	Bald Cypress	3g	1/3
	Loblolly Pine	3g	1/3
	Sycamore	3g	1/3


1) Evenly distribute Bald Cypress, Loblolly Pine, Sycamore, Magnolia and Cedar Elm 8'O.C. in groups and individually to fill voids in existing areas.

Tree Layout Within Existing Planting Area (Typ)


Trees Within Existing Planting Areas



Shrub Planting Typical Elevation
Shoulder / Curb



Shrub Planting Typical Elevation
Barrier / Sound Wall / Curb



Shrub Planting Typical Elevation
Retaining Wall / Curb




Dana Dean Cote
08/30/2023

NTS

PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT			
SHEET 5 OF 5			
FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	C508-1-394	048	
STATE	DIST.	COUNTY	
TEXAS	HOU	HARRIS	
CONT.	SECT.	JOB	HIGHWAY NO.
0508	01	394,ETC	IH 10, ETC

BEGGING OF ROADWAY



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 050

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- * 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805




US 90
PLANTING PLAN

CSJ: 0028-02-110 SHEET 1 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 049
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 049



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 051

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

US 90
PLANTING PLAN

CSJ: 0028-02-110 SHEET 2 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 050
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC


SEP 2023

MATCHLINE - SEE SHEET 050



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 052

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

PLANS NTS



08/30/2023

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



**US 90
PLANTING PLAN**

CSJ: 0028-02-110 SHEET 3 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 051	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394, ETC	HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 051



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 053

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- * 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

US 90
PLANTING PLAN

CSJ: 0028-02-110 SHEET 4 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 052	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394, ETC	HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 052



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 054

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA


NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation


US 90
PLANTING PLAN

CSJ: 0028-02-110 SHEET 5 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 053	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394, ETC	HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 053



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 055

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- * 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



US 90
 PLANTING PLAN

CSJ: 0028-02-110 SHEET 6 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 054
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 054



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



END OF ROADWAY

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA.
- * 1022-6008 LANDSCAPE TREATMENT (TY 8) EA.


ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



US 90 PLANTING PLAN

CSJ: 0028-02-110 SHEET 7 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 055
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 056



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 058

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

DETENTION AREA/POND


- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - * 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - * 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



IH 69 PLANTING PLAN

CSJ: 0177-11-163 SHEET 2 OF 2

FED. NO. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 057
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

E:\PROJECTS\2023\10-14-AM\1886\W445\EA\HARRIS\PLAN PRODUCTION\0177-11-163\I-69\I-69 PLANTING PLANDWG
 T: 281.883.0103

SEPT 2023

MATCHLINE - SEE SHEET 057



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 059

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation

IH 69 PLANTING PLAN


CSJ: 0177-07-125

SHEET 1 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 058
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 058



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 060

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - * 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - * 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



IH 69 PLANTING PLAN

CSJ: 0177-07-125 SHEET 2 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 059	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 059



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 061

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

IH 69 PLANTING PLAN

CSJ:0177-07-125 SHEET 3 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 060
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 060



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 062

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

IH 69 PLANTING PLAN

CSJ:0177-07-125 SHEET 4 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 061
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 061



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 063

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

IH 69 PLANTING PLAN

CSJ: 0177-07-125 SHEET 5 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 062
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 062



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 064

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation


IH 69 PLANTING PLAN

CSJ: 0177-07-125 SHEET 6 OF 6

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 063
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 063



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 066

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation


IH 69 PLANTING PLAN

CSJ: 0177-06-095 SHEET 1 OF 2

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 064	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394, ETC	HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 064



MATCHLINE - SEE SHEET 066

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



PLANS NTS

08/30/2023

Westwood		20320 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103	
		TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805	
IH 69 PLANTING PLAN			
CSJ: 0177-06-095		SHEET 2 OF 2	
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 065	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394, ETC	HIGHWAY NO IH 10, ETC

SEP 2023

BEGINNING OF ROADWAY



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 067

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a **Westwood** company SUITE 350 HOUSTON, TX 77070 281.883.0103



IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 1 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 066
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 066



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 068

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a Westwood company SUITE 350
 HOUSTON, TX 77070
 281.883.0103



IH 69 PLANTING PLAN

CSJ: 0177-05-127

SHEET 2 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 067	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 067



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 069

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a **Worwood** company SUITE 350 HOUSTON, TX 77070 281.883.0103



IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 3 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 068
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 068



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 070

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a **Westwood** company SUITE 350
 HOUSTON, TX 77070
 281.883.0103




IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 4 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 069
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 069



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 071

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a **Woodward Clyde** company SUITE 350
 HOUSTON, TX 77070
 281.883.0103




IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 5 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 070
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 069



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 072

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a **Westwood** company SUITE 350
 HOUSTON, TX 77070
 281.883.0103



IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 6 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 071
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 071



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 073

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA


NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS




IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 7 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 072	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 072



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



END OF ROADWAY

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA


NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
 08/30/2023

PLANS NTS

Pacheco Koch 20329 STATE HIGHWAY 249
 a **Worwood** company SUITE 350
 HOUSTON, TX 77070
 281.883.0103



IH 69 PLANTING PLAN

CSJ: 0177-05-127 SHEET 8 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 073
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

BEGINNING OF ROADWAY



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 075

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805




IH 610
PLANTING PLAN

CSJ: 0271-14-247 SHEET 1 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 074
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 074



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 076

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



IH 610
 PLANTING PLAN

CSJ: 0271-14-247 SHEET 2 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 075
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 075



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 077

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA


CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA


NOTES
 PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805




IH 610
PLANTING PLAN

CSJ: 0271-14-247 SHEET 3 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 076
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 076



MATCHLINE - SEE SHEET 078

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



IH 610
 PLANTING PLAN

CSJ: 0271-14-247 SHEET 4 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 077
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 077



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 079

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



IH 610
PLANTING PLAN


CSJ: 0271-14-247

SHEET 5 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 078	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC


SEP 2023

MATCHLINE - SEE SHEET 078



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 080

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805




IH 610 PLANTING PLAN

CSJ: 0271-14-247 SHEET 6 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 079
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE THIS SHEET



MATCHLINE THIS SHEET

MATCHLINE - SEE SHEET 079



EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES
 PLANTING PLANS SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND


- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



PLANS NTS



IH 610 PLANTING PLAN

CSJ: 0271-14-247 SHEET 7 OF 7

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 080
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET ###



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 082

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/23/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation

IH 610
PLANTING PLAN


CSJ: 0271-15-103

SHEET 1 OF 2

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 081	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394, ETC	HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 081



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



END OF ROADWAY

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
- 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
- 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805




IH 610 PLANTING PLAN

CSJ: 0271-15-103 SHEET 2 OF 2

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 082
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC


SEP 2023

BEGINNING OF ROADWAY



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 084

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - * 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - * 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation


IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 1 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 083
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 083



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 085

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation

IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 2 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 084
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 084



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 086

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



Texas Department of Transportation

IH 10 PLANTING PLAN


CSJ: 0508-01-394

SHEET 3 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 085
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 085



MATCHLINE - SEE SHEET 087

EXISTING TREE PLANTING AREA

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- * 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- * 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- * 193-6002 PLANT MAINTENANCE CYC
- * 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



Texas Department of Transportation

IH 10 PLANTING PLAN


CSJ: 0508-01-394

SHEET 4 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 086	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 086



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 088

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA


ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS




IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 5 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 087
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 087



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 089

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND


-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)
 SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation


IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 6 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 088
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 088



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 090

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA




Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood		20320 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805	
		Texas Department of Transportation	
IH 10 PLANTING PLAN			
CSJ: 0508-01-394		SHEET 7 OF 15	
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 089	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 089



MATCHLINE - SEE SHEET 091

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL


-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND


-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)
 SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood		20320 STATE HIGHWAY 249, STE. 350 HOUSTON, TX 77070 281.883.0103 TX REG. ENGINEERING FIRM F-489 TX REG. SURVEYING FIRM LS-10193805	
		Texas Department of Transportation	
IH 10 PLANTING PLAN			
CSJ: 0508-01-394		SHEET 8 OF 15	
FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 090	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 090



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 092

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES
 PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation

IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 9 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 091
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 091



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 093

EXISTING TREE PLANTING AREA

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

- 193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 10 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 092
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 092



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 094

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805

Texas Department of Transportation

IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 11 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 093
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 093



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 095

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS. CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS. ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS. ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 12 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 094
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 094



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 096

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA


NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation

IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 13 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 095	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEPT 2023

MATCHLINE - SEE SHEET 095



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



MATCHLINE - SEE SHEET 097

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES


PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805




IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 14 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 096	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC


SEPT 2023

MATCHLINE - SEE SHEET 096



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



END OF ROADWAY

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

CRITICAL TREE PRUNING AND REMOVAL

-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)


SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 1022-6010 LANDSCAPE TREATMENT (TY 10) EA



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805

 Texas Department of Transportation

IH 10 PLANTING PLAN

CSJ: 0508-01-394 SHEET 15 OF 15

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 097	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC


SEPT 2023

BEGINNING OF ROADWAY



MATCHLINE THIS SHEET

MATCHLINE THIS SHEET



END OF ROADWAY

EXISTING TREE PLANTING AREA

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA
- 1022-6004 LANDSCAPE TREATMENT (TY 4) EA

DETENTION AREA/POND

-  193-6002 PLANT MAINTENANCE CYC
- 1022-6003 LANDSCAPE TREATMENT (TY 3) EA

CRITICAL TREE PRUNING AND REMOVAL


-  1022-6005 LANDSCAPE TREATMENT (TY 5) EA

ENTIRE CORRIDOR RIGHT-OF-WAY AREAS (WITHIN PROJECT LIMITS SHOWN)

- SEE DETAILS FOR TYPICAL SECTION AND ADDITIONAL INFORMATION:
- 1022-6005 LANDSCAPE TREATMENT (TY 5) EA
 - 1022-6006 LANDSCAPE TREATMENT (TY 6) EA
 - 1022-6010 LANDSCAPE TREATMENT (TY 10) EA

NOTES

PLANTING PLAN SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
 CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
 CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
 ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
 ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
 08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
 HOUSTON, TX 77070 281.883.0103
 TX REG. ENGINEERING FIRM F-489
 TX REG. SURVEYING FIRM LS-10193805



SS 548
PLANTING PLAN

CSJ: 2483-01-016 SHEET 1 OF 1

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 098
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEPT 2023



MATCHLINE - SEE SHEET 100

MATCHLINE - SEE SHEET 101


TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

PLANS NTS



Dana Dean Cote
08/30/2023

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



Texas Department of Transportation

SAN JACINTO
PLANTING PLAN


CSJ: 0376-01-015 SHEET 1 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 099
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEP 2023



MATCHLINE - SEE SHEET 099



UPPER SAN JACINTO BAY


MATCHLINE - SEE SHEET 102

TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY


NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805




SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015

SHEET 2 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 100	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEP 2023



MATCHLINE - SEE SHEET 099

MATCHLINE - SEE SHEET 102

MATCHLINE - SEE SHEET 103

TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

PLANS NTS



Dana Dean Cote
08/30/2023

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015 SHEET 3 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 101	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 100



CRYSTAL BAY

MARSH

UPPER SAN JACINTO BAY

MATCHLINE - SEE SHEET 101


MATCHLINE - SEE SHEET 104

TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



Texas Department of Transportation

SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015

SHEET 4 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 102	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

SEP 2023



MATCHLINE - SEE SHEET 105

TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.

PLANS NTS



Dana Dean Cote
08/30/2023

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015

SHEET 5 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 103	
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS	
CONTROL 0508	SECTION 01	JOB 394,ETC	HIGHWAY NO IH 10, ETC

MATCHLINE - SEE SHEET 104

SEP 2023

MATCHLINE - SEE SHEET 102



UPPER SAN JACINTO BAY

MARSH

PROPOSED
NON-VEGETATIVE
TRASH AND DEBRIS
COLLECTION SITE
THC MUST APPROVE

EDGE OF MARSH, LIMITS
OF TREATMENT

LANDSCAPE TREATMENT (TY 7)
WITH
FULL-WIDTH MOW
16 AC

UTILITY EASMENT, EDGE OF
TREATMENT

PARK RD 1836 N

MATCHLINE - SEE SHEET 103

MATCHLINE - SEE SHEET 106

TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



Texas Department of Transportation


SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015

SHEET 6 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 104
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEP 2023



MATCHLINE - SEE SHEET 103

MATCHLINE - SEE SHEET 106

TREATMENTS:




1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015 SHEET 7 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 105
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394, ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

MATCHLINE - SEE SHEET 104

LANDSCAPE TREATMENT (TY 7)
AND
FULL-WIDTH MOW
1 AC



UPPER SAN JACINTO BAY

MATCHLINE - SEE SHEET 105




TREATMENTS:



1022-6007 LANDSCAPE TREATMENT (TY 7) EA
MOWING ACREAGE SHOWN FOR INFORMATIONAL PURPOSES ONLY

NOTES
SHEETS ARE DIAGRAMMATIC REPRESENTATIONS OF PROPOSED WORK AREAS ONLY.
CONTRACTOR IS RESPONSIBLE FOR LOCATING AND STAKING LIMITS OF EACH WORK AREA AS MAY BE REQUIRED IN ACCORDANCE WITH PLANS.
CONTRACTOR TO REVIEW PLANTING, ESTABLISHMENT AND MAINTENANCE LAYOUT AND ASSORTED DETAIL SHEETS.
ADJUSTMENTS WILL BE MADE TO ACCOMMODATE SITE CONDITIONS.
ALL LOCATIONS WILL BE APPROVED PRIOR TO ANY ADDITIONAL WORK.



Dana Dean Cote
08/30/2023

PLANS NTS

Westwood 20320 STATE HIGHWAY 249, STE. 350
HOUSTON, TX 77070 281.883.0103
TX REG. ENGINEERING FIRM F-489
TX REG. SURVEYING FIRM LS-10193805



SAN JACINTO
PLANTING PLAN

CSJ: 0376-01-015 SHEET 8 OF 8

FED. RD. DIV. NO. 6	FEDERAL AID PROJECT NO. C508-1-394	SHEET NO. 106
STATE TEXAS	DISTRICT HOU	COUNTY HARRIS
CONTROL 0508	SECTION 01	JOB 394,ETC
		HIGHWAY NO IH 10, ETC

SEP 2023

TYPE OF WORK

ITEMS AND REQUIREMENTS FOR EACH TYPE OF WORK

SODDING	PERMANENT SEEDING	TEMPORARY SEEDING	Reference Item 161, 162, 164, 166, 168 of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges 2014 for specifications, dimensions, volumes and measurements that are not shown. Use latest Houston District, Special Provisions for those items indicated.		
	✓		161-6017 COMPOST MANUF TOPSOIL (BIP)(4") SY	APPLICATION RATE Item 161.2.1. Compost Manufactured Topsoil (CMT)	Item 161.2. Materials. Submit quality control (QC) documentation to the Engineer. Compost producer's STA certification must be dated to meet STA requirements (certification must be within 30 or 90 days per STA requirements). Lab analysis performed by an STA-certified lab must be dated within 30 days before delivery of the compost.
✓			162-6002 BLOCK SODDING SY	GRASS SPECIES Item 162.2. Materials. Common Bermuda (Cynodon Dactylon)	Item 162.2.1. Block Sod. Use block palletized or roll type sod. REMOVE PLASTIC BACKING FROM ROLL TYPE SOD. Place sod within 48 hours of delivery to site. No exceptions. Place sod with joints alternating on each row to prevent continuous joint lines. Peg sod as needed with wood pegs to hold sod in place. Pegging sod is subsidiary to Item 162.
	✓		164-6066 DRILL SEEDING(PERM)(WARM OR COOL) SY Item 164.1. Description Provide and install seeding as shown on District Standard	PLANTING MONTH SEED MIX March, April, May, June, July, August, September, October Hulled - Bermudagrass (Cynodon dactylon) - 40.0 lbs PLS/acre Foxtail Millet (Setaria italica) - 34.0 lbs PLS/acre Green Sprangletop (Leptochloa dubia) - 4.0 lbs PLS/acre Sideoats Grama (Bouteloua curtipendula) - 3.2 lbs PLS/acre Little Bluestem (Schizachyrium scoparium) - 1.4 lbs PLS/acre November, December, January, February Unhulled - Bermudagrass (Cynodon dactylon)- 40.0 lbs PLS/acre Oats (Avena sativa) - 72.0 lbs PLS/acre Green Sprangletop (Leptochloa dubia) - 4.0 lbs PLS/acre Sideoats Grama (Bouteloua curtipendula) - 3.2 lbs PLS/acre Little Bluestem (Schizachyrium scoparium) - 1.4 lbs PLS/acre	PLS (Pure Live Seed) Provide documentation of PLS requirements per Item 164.2.1. CONSTRUCTION. Cultivate the area to a depth of 4 inches before placing the seed unless otherwise directed. When performing permanent seeding after an established temporary seeding, cultivate the seedbed to a depth of 4 inches or mow the area before placement of the permanent seed. Plant the seed and place the straw or hay mulch after the area has been completed to lines and grades as shown on the plans. Drill Seeding. Plant seed or seed mixture uniformly over the area shown on the plans at a depth of 1/4 to 1/3 inch using a cultipacker(turfgrass) type seeder. Plant seed along the contour of the slopes.
	✓		164-6052 BROADCAST SEED(PERM)(SPECIAL MIX) SY Item 164.1. Description Provide and install seeding as shown on District Standard		
		✓	164-6051 DRILL SEED(TEMP)(WARM OR COOL) SY Item 164.1. Description Provide and install seeding as shown on District Standard	PLANTING MONTH SEED MIX March, April, May, June, July, August, September, October Foxtail Millet (Setaria italica) - 34.0 lbs PLS/acre November, December, January, February Oats (Avena sativa) - 72.0 lbs PLS/acre	Use broadcast seeding method where site conditions prevent drill seeding method. Broadcast Seeding. Distribute the dry seed or dry seed mixture uniformly over the areas shown on the plans using hand or mechanical distribution on top of soil.
		✓	164-6009 BROADCAST SEED(TEMP)(WARM) SY Item 164.1. Description Provide and install seeding as shown on District Standard		
	✓	✓	162-6003 STRAW OR HAY MULCH SY	APPLICATION RATE Immediately after planting the seed or seed mixture, apply straw or hay mulch uniformly over the seeded area. Apply straw or hay mulch at 2 tons per acre. Use tacking agent with straw or hay mulch as described on this sheet.	Use straw or hay mulch in conformance with Article 162.2.5, "Mulch." Use biodegradable, tacking agents only applied at a rate in accordance with manufacturer's recommendations. Use the following products or an approved equal(see note this sheet): Conweb/Contac Guar Gum, Profile Products Corporation, (307) 655-9565, Ramtec/Procol/Viscol Guar Gum, Ramtec Corporation, (800) 366-1180
✓	✓	✓	166-6001 FERTILIZER AC Item 166.2. Materials Use fertilizer as shown on District Standard	APPLICATION RATE Deliver and evenly distribute fertilizer at a rate of 4000 lbs/acre.	Use a NON-CHEMICAL fertilizer which meets all the following criteria: (1) BRAND NAME must be registered with the Texas State Chemist as a commercial fertilizer. (2) Meets USEPA guidelines for unrestricted use. (3) Derived from biological sources such as, but not limited to: sewage sludge, manures, vegetation, etc. (4) In granular form and essentially dust free. Submit proof of registration and nutrient source to Engineer. Use the following products or an approved equal(see note this sheet): Sigma, SIGMA AgriScience, 281-851-6749 Sustainite-standard grade, Automation Nation, Inc., 713-675-4999 Milorganite, MMSD, 800-287-9645 Agricultural Organic P/L, Ag Org, INC., 713-523-4396
✓	✓	✓	168-6001 VEGETATIVE WATERING MG	APPLICATION RATE Item 168.3 Construction. 6000 gallons/acre per working day x 20 consecutive working days = 120,000 gallons total/acre	Begin watering immediately after installation of seed or sod. Replace, fertilize, and water any seed or sod in poor condition due to the failure to apply the specified amount of water within the time allowed at no expense to the Department.

SEQUENCE OF WORK


BLOCK SOD	PERMANENT SEEDING	TEMPORARY SEEDING
1.FERTILIZER 2.CULTIVATE SOIL (ITEM 162.3) 3.SOD 4.VEGETATIVE WATERING	1.FERTILIZER 2.COMPOST MANUFACTURED TOPSOIL 3.CULTIVATE SOIL (ITEMS 164.3 AND 161.3.1) 4.PERMANENT SEEDING 5.STRAW OR HAY MULCH 6.VEGETATIVE WATERING	1.FERTILIZER 2.CULTIVATE SOIL (PER ITEM 164.3) 3.TEMPORARY SEEDING 4.STRAW OR HAY MULCH 5.VEGETATIVE WATERING



FERTILIZER, SEED, SOD, STRAW, COMPOST, AND WATER

SHEET 1 OF 1

REVISIONS		FILE:	FED. BY:	STATE:	PROJECT NUMBER			SHEET	
10/2014	UPDATED TO 2014 SPECS	OCT 2014	6	TEXAS				107	
3/2015	MINOR CORRECTIONS	ORIGINAL:		DIST:	COUNTY:	CONTROL:	SECT:	JOB:	HIGHWAY:
				HOU:	HARRIS	0508	01	394,ETC	IH 10,ETC



TREE PLANTING DETAIL

FOR PALM TREE PLANTING DETAIL SEE PLANTING AND ESTABLISHMENT SHEET 2 of 8

SHRUB AND VINE PLANTING DETAIL

VEGETATIVE WATERING SCHEDULE FOR TREES, SHRUBS, VINES			
FOR VEGETATIVE WATERING FOR PALMS ONLY SEE PLANTING AND ESTABLISHMENT SHEET 2 of 8			
PHASE	ITEM DESCRIPTION	FREQUENCY	RATE / PLANT
Item 192.3 Construction	Item 192.3.7. Watering is incidental to Item 192 and is not paid for separately. See Initial Watering note	Begin same day as planting then: 3 times per week with 1 day minimum between waterings. See Initial Watering note	CNTR SIZE WATER QTY 30 GAL = 16 gallons 15 GAL = 10 gallons 5 GAL = 4 gallons 3 GAL = 2 gallons 1 GAL = 2 gallons
Item 192.3.15 Maintenance	Item 192.3.15.1. Watering is incidental to Item 192 and is not paid for separately	See Initial Watering note	(1/2 X plant CNTR gallon size per plant for sizes not shown, one (1) gallon minimum) See Initial Watering Note
Item 193 Landscape Establishment (When Shown in Plans)	Item 193.3.3. Watering is incidental to Item 193 and is not paid for separately	2 times per week with 2 days minimum between waterings	

NOTES:
Apply water over the rootball within the tree well only, unless otherwise shown on plans. Adjust rate and frequency to meet site conditions and weather as approved or directed by engineer.


Plant material in poor condition due to the failure to apply the specified amount of water within the time allowed or overwatering will be replaced at contractor's expense.

PROVIDE MONTHLY METER READINGS OF WATER APPLIED.


Prior to arrival at project or storage area, provide watering plan(s) of plants to be installed or stored. Watering plan(s) must be approved by engineer prior to delivery to project or storage area.

INITIAL WATERING AND ROOT STIMULATOR REQUIREMENTS	
PHASE	Item 192.3 Construction. Initial watering.
ITEM DESCRIPTION	Item 192.3.5. Plant Installation. Root stimulator material is incidental to Item 192 and is not paid for separately.
MATERIALS and SOLUTION	Two (2) ounces of root stimulator concentrate per one (1) gallon water. Root stimulator must be commercially available and labeled as an all organic/non-chemical liquid concentrate Bio-Stimulant and Root Stimulator. Use the following product or an approved equal: Super Seaweed, San Jacinto Environmental Supplies, 713-957-0909.
FREQUENCY and RATE	At the time of planting, provide initial watering at rate shown in Vegetative Watering Schedule this sheet. Use root stimulator solution for initial watering.

- GENERAL NOTES:
- Reference Item 192 of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges 2014 for specifications, dimensions, volumes, and measurements not shown.
 - Reference Item 192.3, mark plant locations and bed outlines.
 - Verify that all planting meets the following clear zone minimum distance requirements from the edge of the travel lane: Trees: 32' unless protected by a barrier, Shrubs: 16' unless protected by a barrier, Groundcovers and vines: no minimum distance. Engineer has final authority over all clear zone related issues.
 - Locate and stake all underground conduits and utilities associated with but not limited to: CTMS, CTMS power supply, lighting, signal wires and detectors, gas, electric, telephone, fiber optics, etc.
 - Locate and stake existing ground boxes, inlets, culverts, manholes, etc. within the project area with a 4' wooden stake painted orange. Maintain the stakes in place for duration of the contract. Remove stakes when directed by engineer.
 - Reference Item 5.10 Inspection of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges 2014. At any time during all phases of the contract, any materials or work performed not in accordance with the plans and specifications will be replaced and/or reworked until in compliance.
 - Any adjustments due to the failure to comply with plans and specifications shown will be at contractors expense.



TREE PLACEMENT WITHIN PLANTING BED PREP AREA, LAYOUT AND SPACING SHOWN ON PLANS



SHRUB AND VINE PLACEMENT WITHIN PLANTING BED PREP AREA LAYOUT AND SPACING SHOWN ON PLANS


Texas Department of Transportation
©2023 HOUSTON DISTRICT

PLANTING AND ESTABLISHMENT
SHEET 1 of 8

Details not to scale TREE & SHRUB


FILE:	FED DIV 6	STATE TEXAS	PROJECT NUMBER	SHEET 108
REVISIONS:	DIST HOU	COUNTY HARRIS	CONTROL 0508	SECT 01
FEB 2015 for 2014 specs			JOB 394,ETC	HIGHWAY IH 10,ETC

STD K-4



PLAN VIEW
PALM TREE AND PERFORATED TUBE

IF PALM MATERIAL FALLS TO THE GROUND DURING DELIVERY, CONSTRUCTION, ESTABLISHMENT, OR MAINTENANCE, IT IMMEDIATELY BECOMES THE PROPERTY OF THE CONTRACTOR AND MUST BE REPLACED AT CONTRACTOR'S EXPENSE.



Watering Monitor Tube:
(For all palms unless otherwise directed by landscape architect). Install 4" diameter perforated tube with removable cap. Use tube with perforations completely around and within 1' of the finished grade. Install cap 4" above surface. Construct pit for tube to be 8" diameter and line with 1" to 2" diameter rock. Paint dark brown. See plan view for tube location. Monitor tube and rock are incidental. Cut tube off at grade at end of contract or as directed by engineer or landscape architect.

PALM TREE PLANTING

VEGETATIVE WATERING SCHEDULE FOR PALMS ONLY

PHASE	ITEM DESCRIPTION	FREQUENCY AND RATE
Item 192.3 Construction	Item 192.3.7. Watering is incidental to Item 192 and is not paid for separately	Maintain the root ball and surrounding backfill evenly moist, but never saturated. See notes this schedule. Submit watering schedule to engineer for approval prior to installation.
Item 192.3.15 Maintenance	Item 192.3.15.1. Watering is incidental to Item 192 and is not paid for separately	
Item 193 Landscape Establishment (When Shown in Plans)	Item 193.3.3. Watering is incidental to Item 193 and is not paid for separately.	

NOTES:
Apply water over the rootball within the tree well only. Adjust rate and frequency to meet site conditions and/or weather as approved or directed by engineer.
Monitor watering to maintain rootball and surrounding backfill evenly moist, but not saturated. Inspect monitor tubes and pump out standing water. Daily inspection and pumping is required when rootball is over-saturated by rain, run-off, watering or other events.
Plant material in poor condition due to the failure to apply the specified amount of water within the time allowed or overwatering will be replaced at contractor's expense.
PROVIDE MONTHLY METER READINGS OF WATER APPLIED.
Prior to arrival at project or storage area, provide watering plan(s) of plants to be installed or stored. Watering plan(s) must be approved by engineer prior to delivery to project or storage area.


- GENERAL NOTES:
- Reference Item 192 of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges 2014 for specifications, dimensions, volumes, and measurements not shown.
 - Reference Item 19.3, mark plant locations and bed outlines.
 - Verify that all planting meets the following clear zone minimum distance requirements from the edge of the travel lane:
Trees: 32' unless protected by a barrier,
Shrubs: 16' unless protected by a barrier,
Groundcovers and vines: no minimum distance.
Engineer has final authority over all clear zone related issues.
 - Roadway edges shown on the plans are to be considered the edge of travel lane unless labeled otherwise.
 - Locate and stake all underground conduits and utilities associated with but not limited to: CTMS, CTMS power supply, lighting, signal wires and detectors, gas, electric, telephone, fiber optics, etc.
 - Repair and/or replace any damaged underground conduits and utilities at contractor's expense.
 - Locate and stake existing ground boxes, inlets, culverts, manholes, etc. within the project area with a 4" wooden stake painted orange. Maintain the stakes in place for duration of the contract. Remove stakes when directed by engineer.
 - Repair and/or replace any damaged structures, pavement, riprap, equipment, materials, slopes, vegetation, and surfaces at contractor's expense.
- PALM TREATMENTS, APPLICATIONS, AND SPECIALIST NOTES:
- Treatments to plant material to ensure health and quality of plant from disease, stress, insects, or other detrimental impacts are incidental.
 - Applications of fertilizers, vitamins and hormones are incidental.
 - Multiple treatments and applications are incidental.
 - Required soil tests are incidental.
 - Palm specialists are incidental. Submit qualifications of palm specialist at preconstruction meeting for approval by engineer.

- REQUIREMENTS AT TIME OF PLANTING:
- Apply an approved aluminum based foliar fungicide to tops and bottoms of fronds and bud.
 - After fungicide has dried, apply an approved insecticide to the fronds and trunk.
 - After insecticide has dried, apply an approved anti-desiccant to the fronds and trunk.
 - Test soil for pH level and treat as specified in previous notes on this sheet.
 - Incorporate "Palm Saver" or an approved equal palm fertilizer into the backfill around the rootball.
 - When backfilling around rootball, work backfill equally around rootball in 6" lifts to eliminate air pockets.
 - Soak each lift up to finish grade using an approved liquid form of vitamins and hormones specifically for palms diluted with water at a ratio recommended by manufacturer. Use a liquid which contains but is not limited to Mg and Mn.
 - Use backfill consisting of the following: 70% existing soil removed from the plant pit and 15% Erosion Control Compost as described in Item 161.2.2 Compost and 15% rock limited to 1 inch to 1-1/2 inch. Work backfill equally around the rootball as described in previous notes on this sheet. Rock and compost are incidental.
 - Use Erosion Control Compost for surface application for palm planting as described in Item 161.2.2 Compost. Compost for surface application for palm planting is incidental.
 - Maintain soil moisture conditions as specified in watering schedule on this sheet.

- REQUIREMENTS AFTER PLANTING:
- Every 4 months, test soil for pH level and treat as specified in previous notes on this sheet. Provide the pH soil test report shall be provided to Landscape Architect and Palm Specialist in order to determine type and amount of fertilizer.
 - Fertilize palms every 4 months with a combination of "Palm Saver", K and Mg in liquid form with granular form of K and Mg sulfates.
 - Apply all granular palm fertilizers by drilling 10" into soil around rootball.
 - Application of fertilizers and micronutrients may be adjusted according to soil and palm conditions.
 - Maintain watering and soil moisture conditions as specified on this sheet.
 - For further recommendations for treatment of insects, diseases, and nutritional problems, contact palm specialist.
 - At anytime remove any/all dead fronds as directed.

* Complete this work in the presence of the engineer.

- REQUIREMENTS PRIOR TO PLANTING:
- Test pH of soil after bed preparation work is completed. Collect soil sample 18" below final surface. Provide results to landscape architect and palm specialist. Provide comments and recommendations from palm specialist to landscape architect. Desired soil pH is between 6.5 and 6.8. When soil pH is high, incorporate an approved aluminum sulphate into soil as recommended by manufacturer and pH test. Additional applications and pH testing may be required to adjust pH before and after planting.
 - Provide documentation from palm specialist verifying palm species, condition and health of all palm materials to engineer.
 - Spray foliage with an approved anti-desiccant.
 - Maintain rootball, trunk, and frond moisture conditions during transportation and storage activities.
 - Apply an approved soil fungicide to entire rootball.
 - For further information on identifying insects, diseases, and nutritional problems, the palm specialist will be contacted.



PLANTING AND ESTABLISHMENT
SHEET 2 of 8

Details not to scale PALM TREE


FILE:	FED DIV 6	STATE TEXAS	PROJECT NUMBER	SHEET 109
REVISIONS:	DIST HOU	COUNTY HARRIS	CONTROL 0508	SECT 01
FEB 2015 for 2014 specs			JOB 394.ETC	HIGHWAY IH 10,ETC

PLANT SPECIFICATIONS *				MINIMUM SPECIFICATIONS					
Abbr	Botanical Name	Common Name	Qty	Color	Root Cond	Caliper	Height	Spread	Remarks
TD	TAXODIUM DISTICHUM	BALD CYPRESS	238	N/A	15 GAL	1.25"	7'	3'	STRAIGHT LEADER/TRUNK, FULL BRANCHING, SPECIMEN QUALITY (MUST "NOT" REQUIRE BAMBOO SPLINT TO STAND UPRIGHT)
TOTAL			238						
CC	CERCIS CANADENSIS 'TEXENSIS'	TEXAS REDBUD	119	PINK	3 GAL	3/4"	4'	1.5'	FULL BRANCHING, STRAIGHT LEADER/TRUNK, SPECIMEN QUALITY (MUST "NOT" REQUIRE BAMBOO SPLINT TO STAND UPRIGHT)
MGL	MAGNOLIA GRANDIFLORA 'LITTLE GEM'	LITTLE GEM MAGNOLIA	238	N/A					
PO	PLATANUS OCCIDENTALIS	SYCAMORE AMERICAN	238	N/A					
PT	PINUS TAEDA	LOBLOLLY PINE	238	N/A					
QA	QUERCUS ALBA	WHITE OAK	238	N/A					
QM	QUERCUS MACROCARPA	BUR OAK	119	N/A					
QS	QUERCUS SHUMARDII	SHUMARDII OAK	238	N/A					
UC	ULMUS CRASSIFOLIA	CEDAR ELM	238	N/A					
TD2	TAXODIUM DISTICHUM	BALD CYPRESS	238	N/A					
LI1	LAGERSTROEMIA INDICA X 'MUSKOGEE'	MUSKOGEE CRAPE MYRTLE	80	LAVENDER					
LI2	LAGERSTROEMIA INDICA X 'NATCHEZ'	NATCHEZ CRAPE MYRTLE	79	WHITE					
LI3	LAGERSTROEMIA INDICA X 'ARAPAHO'	ARAPAHO CRAPE MYRTLE	80	RED					
PA	PARKINSONIA ACULEATA	RETAMA	118	YELLOW					
TOTAL			2261	2261					
TD	FICUS PUMILA	FIG IVY	492	N/A	1 GAL		12'	12'	FULL BRANCHING, SPECIMEN QUALITY

- PLANT SPECIFICATION NOTES:
- Reference Item 5.10 INSPECTION of the Texas Standard Specifications for Construction of Highways, Streets and Bridges 2014. Inspection or lack of inspection will not relieve the contractor from obligation to provide materials or perform the work in accordance with the contract.
 - Reference Item 192 of the Texas Standard Specifications for Construction of Highways, Streets and Bridges 2014 for specifications, dimensions, volumes and measurements that are not shown.
 - All plants must be nursery grown in containers unless otherwise shown on plans.
 - Provide photographs of plant material when requested by engineer and landscape architect.
 - REJECTION OF PLANTS.** Reference Item 192.2 for rejection of plants and unacceptable characteristics.
 - MEASURING CALIPER.** Reference Item 192.2 and ANSI Z60.1, Section 1.2.1, American Standard For Nursery Stock, for caliper measuring procedures. Caliper measurement shall be taken 6 inches above the soil line for container grown stock less than 4.5 inches in caliper. If caliper measured at 6 inches is 4.5 inches or more, caliper shall be measured at 12 inches above ground level, soil line, or root flare as appropriate.
 - ROOT BALL DEPTH.** Reference ANSI Z60.1, Section 1.5.3 for rootball depth measurement procedures. Depth of root ball is measured from the top of the ball, which in all cases shall begin in the root flare.
 - HANDLING AND CARE.** Properly handle and maintain plants during delivery, handling, storage, and planting. The engineer and landscape architect may inspect any phase of work and may reject any plant material improperly handled and/or maintained.
 - DELIVERY NOTICE.** Reference Item 192.3.2 plant delivery. Provide 48 hour notice of proposed plant material delivery prior to arrival at project or storage area.
 - DELIVERY TICKETS.** For each plant material shipment, provide invoice showing the number, size, and name (common and botanical) of each of the species of plant material.
 - WATERING PLAN(S).** Prior to arrival at project or storage area, provide watering plan(s) of plants to be installed or stored. Watering plan(s) must be approved by engineer and landscape architect prior to delivery to project or storage area.
 - Refer to the plans, details and specifications for information and requirements associated with plant material not shown.

- *
1. All plant material must meet all specifications.
2. All plant material must be specimen quality, GRADE A material.
3. Trunks must be self-supporting (able to hold itself upright and straight without bamboo or other supports). Trunks must be straight, strong and appropriate caliper for plant height (root to shoot ratio).
4. Trees with extra height not appropriate for root mass, as determined by Landscape Architect, will be rejected.
5. Branching must be appropriately dense with leaves/needles. Branching with "lion tail" attributes (leaves and needles only on the ends of limbs) will be rejected.
6. Root flares must be exposed. Trees grown too deep in containers will be rejected.



 Texas Department of Transportation
©2023 HOUSTON DISTRICT

PLANTING AND ESTABLISHMENT
SHEET 3 of 8

PLANT SPECIFICATIONS

FILE:	FED DIV 6	STATE TEXAS	PROJECT NUMBER	SHEET 110
REVISIONS: FEB 2015 for 2014 specs	DIST HOU	COUNTY HARRIS	CONTROL 050B	SECT 01
			JOB 394,ETC	HIGHWAY IH 10,ETC


TYPE OF WORK

ITEMS AND REQUIREMENTS FOR EACH TYPE OF WORK


192-6063 PLANT BED PREP (TYPE I) SY	192-6064 PLANT BED PREP (TYPE II) SY	192-6065 PLANT BED PREP (TYPE III) SY	192-6066 PLANT BED PREP (TYPE IV) SY	Reference Item 161, 192 of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges 2014 for specifications, dimensions, volumes and measurements that are not shown. Reference Special Specification Item 1006.		
✓	✓	✓		161-6012 GENERAL USE COMPOST CY	APPLICATION RATE Item 161.2.3. General Use Compost. Apply 2 in. uniform layer over bed preparation area.	Item 161.2. Materials. Compost producer's STA certification must be dated to meet STA requirements (certification must be within 30 or 90 days). Lab analysis performed by an STA-certified lab must be dated within 30 days before delivery of the compost.
✓	✓	✓	✓	1006-6001 LANDSCAPE SOIL AMENDMENT (TYPE I) SY	APPLICATION RATE Apply 0.30 lbs/SY. Each application is paid for separately. See timeline for multiple applications.	Use a non-chemical fertilizer with the following requirements: (1) Is OMRI Listed or certified by Washington State Department of Agriculture meeting USDA National Organic Program Rules, provide current certification. (2) Is registered with Texas State Chemist as a commercial fertilizer. (3) Meets USEPA guidelines for unrestricted use. (4) Derived from the following biological source: processed poultry manure. (5) Contains 3.0% nitrogen and 2.2% of nitrogen is water insoluble, 4% phosphate, 3% soluble potash, 10% calcium. (6) Use the following product or an approved equal: Plant Vigor 3-4-3 Plus 10% Calcium manufactured by Natural Resources Group, Inc., Tomball, Texas 800-279-9567.
✓	✓	✓	✓	1006-6002 LANDSCAPE SOIL AMENDMENT (TYPE II) SY	APPLICATION RATE Apply 0.25 lbs/SY.	Humate containing 2.25% iron in the raw material and greater than 45% humic acid, dextrose 2.5% to 5% on weight basis. Pelletized humate without added binders and pass #16 mesh. Use the following product or an approved equal: San Jacinto Humate, San Jacinto Environmental Supplies, 713-957-0909.
	✓	✓	✓	1006-6003 LANDSCAPE SOIL AMENDMENT (TYPE III) SY	See PLANTING AND ESTABLISHMENT SHEET 5 of 8 For Requirements	
				1006-6004 LANDSCAPE SOIL AMENDMENT (TYPE IV) SY	See PLANTING AND ESTABLISHMENT SHEET 5 of 8 For Requirements	
✓	✓	✓	✓	1006-6005 LANDSCAPE SOIL AMENDMENT (TYPE V) SY	APPLICATION RATE Apply 0.30 lbs/SY. Each application is paid for separately. See timeline for multiple applications.	Use a non-chemical fertilizer with the following requirements: (1) Is OMRI Listed or certified by Washington State Department of Agriculture meeting USDA National Organic Program Rules, provide current certification. (2) Is registered with Texas State Chemist as a commercial fertilizer. (3) Meets USEPA guidelines for unrestricted use. (4) Derived from the following biological source: worm castings. (5) Contains 0.02% humic acid derived from humate, 1.0% nitrogen and 0.9% of nitrogen is water insoluble, 0.5% phosphate, 0.2% soluble potash, 1.0% calcium, 0.02% iron. (6) Use the following product or an approved equal: Black Castings manufactured by Vermi-Technology Unlimited available from Earth's Outlet 866-504-1139.
✓				RIPPING/TRENCHING Incidental to Item 192 Plant Bed Preparation.	RIP/TRENCH DEPTH Rip/Trench to a depth of 18 inches (+/- 2"). Distance between each rip/trench is 24 inches.	
✓	✓	✓		ROTOR TILLING Incidental to Item 192 Plant Bed Preparation.	ROTOR TILL DEPTH After application of compost and amendments and rip/trench (when required), rotor till to a depth of 8 inches (+/- 2").	
		✓	✓	HERBICIDE and MOWING Incidental to Item 192 Plant Bed Preparation. Scalp mow 15 days after final herbicide treatment.	APPLICATION RATE Prior to all other work, apply two applications of an approved herbicide with 15 days between the applications. Apply herbicide during weather conditions and at a rate per manufacturer's recommendations.	

GENERAL BED PREPARATION NOTES:

- Reference Item 192 of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges 2014 for specifications, dimensions, volumes and measurements not shown.
- Reference Item 192.3 mark plant locations and bed outlines.
- Locate and stake all underground conduits and utilities associated with but not limited to: CTMS, CTMS power supply, lighting, signal wires and detectors, gas, electric, telephone, fiber optics, etc.
- Locate and stake existing ground boxes, inlets, culverts, manholes, etc. within the project area with a 4' wooden stake painted orange. Maintain the stakes in place for duration of the project. Remove stakes when directed by engineer.
- Repair any damage within right of way caused by contractor at no additional expense to the Department.
- Provide a 1000 SF "mock up" of soil amendment, general use compost, and bed preparation complete and in place within an approved area for approval by engineer.
- Pick-up litter prior to scalp mow and bed preparation.
- All concrete, steel, trash, and other debris uncovered during bed preparation work which the engineer determines as detrimental to the project will become the responsibility of the contractor and disposed of in an approved manner. Debris removal will occur daily and will be incidental to bed preparation and will not be paid for separately.
- Reference Item 5.10 Inspection of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges 2014. At any time during all phases of the contract, any materials or work performed not in accordance with the plans and specifications will be replaced and/or reworked until in compliance.
- Any adjustments due to the failure to comply with plans and specifications shown will be at contractor's expense.
- Clean and clear bed prep areas and nearby inlets of existing tall vegetation and any piles or layers of dead grass and weeds caused by drought or mowing operations by others.



PLANTING BED PREPARATION SECTION
SEE ITEMS AND REQUIREMENTS THIS SHEET FOR DIMENSIONS, RATES, AND SPECIFICATIONS
(See Top-of-Slope detail this sheet when applicable)



TOP-OF-SLOPE and/or
EDGE OF PAVEMENT TREATMENT
OF BED PREPARATION AREA
Install at all areas with the following conditions:
Within the bed preparation areas at top-of-slope (adjacent to shoulder sections and areas with slotted barrier/curb) and/or at edge of roadway, remove tilled or untilled (TYPE IV) soil as shown. Evenly distribute removed soil in a thin layer over adjacent existing tilled or untilled (TYPE IV) soil being careful not to create a mound. This work is incidental to Item 192 Plant Bed Prep Preparation.

Texas Department of Transportation
HOUSTON DISTRICT
PLANTING AND ESTABLISHMENT
SHEET 4 of 8

Details not to scale		BED PREPARATION				
FILE:	REV BY	STATE	PROJECT NUMBER		SHEET	
	6	TEXAS			111	
REVISIONS:	DIST	COUNTY	CONTROL	SECT	JOB	HIGHWAY
FEB 2015 for 2014 specs	HOU	HARRIS	0508	01	394,ETC	IH 10,ETC

USE COMPOST TEA OR EXTRACT AS SHOWN ON THIS SHEET

COMPOST EXTRACT

ITEM 1006-6003 LANDSCAPE SOIL AMENDMENT (TYPE III) and
ITEM 1006-6004 LANDSCAPE SOIL AMENDMENT (TYPE IV) requirements.

MATERIALS REQUIREMENTS

Compost for use in liquid compost/extract must contain the following (per gram dry weight of compost):

1. Test within range of Soil Food Web standards using a full bio-assay to include the following:
 - a) 15-25 micrograms of active bacteria,
 - b) 100- 3000 micrograms total bacterial biomass,
 - c) 15-25 micrograms active fungal biomass,
 - d) 100-300 micrograms total fungal biomass,
 - e) 10,000 each of flagellates and amoebae,
 - f) 20-100 ciliates, and
 - g) 20 to 30 beneficial nematodes.

2. Meet the Solvita Compost Maturity test of 6.0 or higher.

Liquid compost/extract must contain the following (per gram dry weight):

1. 150-3000 micrograms total bacterial biomass,
2. 2-20 micrograms total fungal biomass,
3. 1000 each of flagellates and amoebae,
4. 20-50 ciliates, and
5. 2-10 beneficial nematodes.

Liquid compost must be verified, with time and date, for content to have minimum activity and meet minimum standards as specified above using a 100x and 400x microscope with camera attachment by a Soil Foodweb Certified Advisor or their representative. This verification must be within 30 minutes of material leaving premises on the day of manufacture. Picture will be kept on file for each 500 gallons manufactured.

Liquid compost/extract additives include the following:

1. Mycorrhizal fungi endo/ecto blend sourced with a minimum potency of 100,000 propagules per pound with NO Tricoderma included in the inoculum.
2. Humate, low sodium, naturally processed 70% humate that has been liquefied to 12% humic-fulvic as available from Mesa Verde Resources at 877-418-8776 or approved equal.
3. Fulvic acid derived from natural shale ore as available from Sustainable Growth Texas at 936-232-5738 or approved equal.
4. Soluble kelp seaweed, dehydrated liquid extract made from the seaplant Ascophyllum nodosum as available from Sustainable Growth Texas at 936-232-5738, or approved equal.
5. Naturally derived blackstrap non-sulfured molasses (for foliar application only).

Liquid compost/extract with additives solution must sit on air for 3-4 hours and monitored every 1/2 hour with a Dissolved Oxygen Meter to assure the material does not drop below 6ppm oxygen content during full activation period.

EQUIPMENT REQUIREMENTS

For each batch use a delivery tank verified for overall cleanliness, to be free of residue, soil, compost or stains. Tank shall then be rinsed with clean non-chlorinated or non-chloramines treated well water before filling with Liquid Compost. All equipment used for application of liquid compost must have never been used or will not be used with any non organic conventional inorganic fertilizers or chemical herbicides or pesticides, owner must submit written verification to this.

Tank shall be equipped with two, 2 inch quick coupler type fittings capable of coupling, without leaks. All lines and fittings should have quick couplers at every junction. Ninety (90) degree bend fittings should be avoided for quick clean out and verification of cleanliness.

Delivery tank must be equipped with an operating circulation pump of a low velocity, high volume pump of diaphragm or centrifugal design.

Injectors capable of penetrating four (4) inches into soil and/or root balls as manufactured by LESCO Deeproot Feeder at 713-466-6730 or approved equal.

Delivery tank must be equipped with an operating aeration system.

Dissolved oxygen meter.

TRANSPORT, STORAGE AND APPLICATION REQUIREMENTS

Liquid compost/extract with additives solution must be circulated for five (5) minutes per five hundred (500) gallons of material every three (3) hours. Liquid compost/extract with additives solution must be continuously aerated from time of manufacture through complete application. All solution must be applied within 24 hours, or new material must be sourced. Materials not applied within 24 hours is not allowed.

CONSTRUCTION METHODS AND APPLICATION RATES

1006-6003 LANDSCAPE SOIL AMENDMENT (TYPE III) SY

Installation date: Install root injection 14 calendar days minimum to 30 calendar days maximum after plant installation.

Limits: Each injected tree and woody shrub equals one square yard of Landscape Soil Amendment (Type III).

Inject 1/2 gallon liquid compost/extract with additives solution four (4) inches into the root zone and/or rootball of each tree and woody shrub only. Mix additives with liquid compost/extract using the following rates:

1. Mycorrhizal fungi endo/ecto blend: 30 lbs per 500 gallons of liquid compost/extract,
2. Humate: 30 lbs per 500 gallons of liquid compost/extract,
3. Fulvic acid: 32 oz per 500 gallons of liquid compost/extract,
4. Soluble kelp seaweed: 2 lbs per 500 gallons of liquid compost/extract.

1006-6004 LANDSCAPE SOIL AMENDMENT (TYPE IV) SY

Installation date: Install first foliar application 30 calendar days minimum to 60 calendar days maximum after root injection described on this sheet. Additional foliar applications as described on following sheets.

Limits/measurement: Each SY of foliar spray equals each tree or woody shrub. Spray foliar application over all trees and woody shrubs.

Solution must be sprayed targeting the full surface of the plant including leaves (top and bottom), limbs and trunk.

Spray foliar application at the following rates:

1. Liquid compost/extract: 500 gallons per acre,
2. Humate: 2 lbs per acre,
3. Fulvic acid: 32 oz per acre,
4. Soluble kelp seaweed: 2 lbs per acre,
5. Blackstrap molasses: 16 oz per acre.

Soil Foodweb Certified Advisor:

Sustainable Growth Texas
103 Sherbrook Circle
Conroe, TX 77385
936-232-5738
sustainablegrowthtexas.com

Soil Foodweb Oregon, LLC
728 SW Wake Robin Ave.
Corvallis, Oregon 97333-1612
541-752-5066
soilfoodweb.com

Soil Foodweb New York, Inc.
555-7 Hallock Ave.
Port Jefferson Station, NY 11776
631-474-8848
soilfoodwebny.com

COMPOST TEA

ITEM 1006-6003 LANDSCAPE SOIL AMENDMENT (TYPE III) and
ITEM 1006-6004 LANDSCAPE SOIL AMENDMENT (TYPE IV) requirements.

MATERIALS REQUIREMENTS

Compost for use in liquid compost tea must contain the following (per gram dry weight of compost):

Test within range of Soil Food Web standards using a full bio-assay to include the following:

- a) 15-25 micrograms of active bacteria,
- b) 100- 300 micrograms total bacterial biomass,
- c) 15-25 micrograms active fungal biomass,
- d) 100-300 micrograms total fungal biomass,
- e) 10,000 each of flagellates and amoebae,
- f) Less than 50 ciliates, and
- g) No root feeding nematodes present.

Actively aerated compost tea must contain the following per milliliter as applied (measured after having passed through the actual application apparatus):

1. Meet the minimum desired ranges by Soil Food Web for:

- a. Active bacteria 10-150
- b. Total bacteria 150-3000
- c. Active Fungi 2-10
- d. Total Fungi 2-20
- e. Flagellates and amoebae 2000 combined
- f. Ciliates 50 or less
- g. No root feeding nematodes present

Tea is to be tested from application device a minimum once per month during each application cycle. Each batch of actively aerated compost tea must be qualitatively assessed using light microscope methods as established by Soil Food Web. Photographs of microscopy must be kept on file with a qualitative assay report.

If the following additives are used in tea brewing to meet the minimum biological standards, the additives must meet these standards.

- a) Fish Hydrolysate - certified organic manufacturers documentation verifying no oil extraction has occurred.
- b) Kelp - must be certified organic soluble extract.
- c) Humic Acid - certified organic water extracted.
- d) Molasses - certified organic blackstrap molasses.

Actively aerated compost tea must maintain dissolved oxygen level above 6 mg/l until application. Use a dissolved oxygen meter to monitor.

EQUIPMENT REQUIREMENTS

For each batch use a delivery tank verified for overall cleanliness, to be free of residue, soil, compost or stains. Tank shall then be rinsed with clean non-chlorinated or non-chloramines treated well water before filling with Liquid Compost Tea. All equipment used for application of liquid compost must have never been used or will not be used with any non organic conventional inorganic fertilizers or chemical herbicides or pesticides, owner must submit written verification to this nature.

Application pump must be high volume (greater than 3.0 gpm) and low pressure (less than 60 psi). Application pump must be a diaphragm type pump. Foliar application device must be capable of adequately covering front and backs of leaves. Foliar application device shall be Gunjet AA18-AL or approved equal.

Delivery tank must be equipped with an operating aeration system capable of maintaining 6 mg/l oxygen content.

Injectors capable of penetrating four (4) inches into soil and/or root balls as manufactured by LESCO Deeproot Feeder at 713-466-6730 or approved equal.

Dissolved oxygen meter.

TRANSPORT, STORAGE AND APPLICATION REQUIREMENTS

Actively aerated compost tea must be continuously aerated from time of manufacture through complete application.

Materials not applied within 24 hours are not allowed.

CONSTRUCTION METHODS AND APPLICATION RATES

1006-6003 LANDSCAPE SOIL AMENDMENT (TYPE III) SY

Installation date: Install root injection 14 calendar days minimum to 30 calendar days maximum after plant installation.

Limits: Each injected tree and woody shrub equals one square yard of Landscape Soil Amendment (Type III).

Inject 1/2 gallon liquid compost tea with additives solution four (4) inches into the root zone and/or rootball of each tree and woody shrub only. Mix additives with compost tea using the following rates:

1. 8 oz/ Fish Hydrolysate per gallon.

1006-6004 LANDSCAPE SOIL AMENDMENT (TYPE IV) SY

Installation date: Install first foliar application 30 calendar days minimum to 60 calendar maximum after root injection described on this sheet. Additional foliar applications as described on following sheets.

Limits/measurement: Each SY of foliar spray equals each tree or woody shrub. Spray foliar application over all trees and woody shrubs.

Solution must be sprayed targeting the full surface of the plant including

leaves (top and bottom), limbs and trunk.

Spray foliar application at the following rate:

1. Liquid compost tea: 500 gallons per acre.

Soil Foodweb Certified Advisor:

Sustainable Growth Texas
103 Sherbrook Circle
Conroe, TX 77385
936-232-5738
sustainablegrowthtexas.com

Soil Foodweb New York, Inc.
555-7 Hallock Ave.
Port Jefferson Station, NY 11776
631-474-8848
soilfoodwebny.com

Soil Foodweb Oregon, LLC
728 SW Wake Robin Ave.
Corvallis, Oregon 97333-1612
541-752-5066
oregonfoodweb.com



Texas Department of Transportation

HOUSTON DISTRICT

PLANTING AND ESTABLISHMENT

SHEET 5 of 8

COMPOST TEA/EXTRACT

Details not to scale

FILE:	FED STATE	PROJECT NUMBER			SHEET	
6	TEXAS				112	
REVISIONS:	DIST	COUNTY	CONTROL	SECT	JOB	HIGHWAY
FEB 2015 for 2014 specs	HOU	HARRIS	0508	01	394,ETC	IH 10,ETC

PROJECT CONDITIONS DURING INSTALLATION AND SUSPENSION

During project installation and suspension periods, project site conditions are contractor's responsibility. Contractor will maintain project site conditions as shown on plans. All project site maintenance work is incidental and is not paid for separately unless otherwise shown on plans. Reference pertinent items of the Texas Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges 2014 for specifications, dimensions, volumes and measurements that are not shown. Notify engineer prior to each site visit, determination of the completeness of work will be done in the presence of the engineer same day as work activity.

DESCRIPTION OF WORK	TIMELINE	
	BEGINNING OF PROJECT CONSTRUCTION OR SUSPENSION	END OF CONSTRUCTION/INSTALLATION
WATERING (See PLANTING AND ESTABLISHMENT SHEET 1 of 8, VEGETATIVE WATERING SCHEDULE FOR TREES, SHRUBS, VINES) and/or (See PLANTING AND ESTABLISHMENT SHEET 2 of 8 VEGETATIVE WATERING SCHEDULE FOR PALMS ONLY)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
MOWING, TRIMMING, AND EDGING (From back of curb, retaining wall, barrier, and riprap to bed preparation areas, otherwise 6' width around outside edge of bed preparation areas, around and between planting bed preparation areas, including areas around any structures within the outer limits adjacent to the roadway). DO NOT MOW, TRIM, OR EDGE WITHIN 3' of ANY TREE	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
WEED CONTROL REQUIREMENT <input checked="" type="checkbox"/> See PLANTING AND ESTABLISHMENT SHEET 7 of 8 For Requirements	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
PLANT SUPPORTS See PLANTING AND ESTABLISHMENT SHEET 5 of 8 For Requirements	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
PRUNING (Includes palm plant material and dead, diseased, or damaged palm fronds.)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
INSECT, DISEASE, AND ANIMAL INSPECTION AND TREATMENT (Exterminate all active ant colonies in bed preparation areas)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
LITTER AND DEBRIS COLLECTION AND DISPOSAL (Includes planting bed preparation areas and designated mowing limits. In addition, keep all inlets within or near planting bed preparation areas free of debris and litter)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
TREE TRUNK WRAP AND PROTECTION GUARD REMOVAL AND DISPOSAL (Not applicable)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
PLANT REPLACEMENT *	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
1006-6004 SOIL AMENDMENT (TYPE IV) (PLANTING AND ESTABLISHMENT SHEETS 4 AND 5 of 8, each application will be paid for separately)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
1006-6005 SOIL AMENDMENT (TYPE V) (PLANTING AND ESTABLISHMENT SHEETS 4 AND 5 of 8, each application will be paid for separately)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
FERTILIZER (Only when Item 192 Palm Material is part of the contract, see PLANTING AND ESTABLISHMENT SHEET 2 of 8, REQUIREMENTS AFTER PLANTING)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	
IRRIGATION SYSTEM (Only when Item 170 Irrigation System or a temporary irrigation system is part of the contract, see IRRIGATION DETAILS AND MATERIALS SHEET 1 OF 3, GUARANTEE AND ACCEPTANCE)	FOLLOW SAME REQUIREMENTS AND FREQUENCY SHOWN ON PLANTING AND ESTABLISHMENT SHEET 7 OF 8.	

* Remove any materials damaged by actions described in Item 7.18.1. Removal and disposal of damaged materials is incidental to Item 192. Contractor may be reimbursed for plant replacement in accordance with Item 7.18.1. Theft is not a reimbursable repair.




PLANTING AND ESTABLISHMENT
SHEET 6 of 8

PROJECT CONDITIONS

FILE:	FED DIV:	STATE:	PROJECT NUMBER			SHEET
	6	TEXAS				113
REVISIONS:	DIST:	COUNTY:	CONTROL:	SECT:	JOB:	HIGHWAY:
FEB 2015 for 2014 specs	HOU	HARRIS	0508	01	394,ETC	IH 10,ETC

<p>I. STORMWATER POLLUTION PREVENTION</p> <p>Texas Pollutant Discharge Elimination System (TPDES) TXR 150000: Stormwater Discharge Permit or Construction General Permit is required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506. Refer to the TxDOT SWP3 Summary Sheets, SWP3 Binder Template, and Form 2118.</p> <p>No Additional Comments</p>	<p>III. CULTURAL RESOURCES</p> <p>Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the area and contact the Engineer immediately.</p> <p>No Additional Comments</p>	<p>VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES</p> <p>Refer to TxDOT Standard Specifications in the event potentially contaminated materials are observed, such as dead or distressed vegetation, trash disposal areas, drums, canisters, barrels, leaching or seepage of substances, unusual smells or odors, or stained soil, cease work in the area and contact the Engineer immediately.</p> <p>No Additional Comments</p>
<p>II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS</p> <p>United States Army Corps of Engineers (USACE) Permit is required for filling, dredging, excavating or other work in water bodies, rivers, creeks, streams, wetlands or wet areas. The Contractor must adhere to all of the terms and general conditions associated with the following permit(s). If additional work not represented in the plans is required, contact the Engineer immediately.</p> <p><input checked="" type="checkbox"/> No United States Army Corps (USACE) Permit Required</p> <p><input type="checkbox"/> Work is authorized by the United States Army Corps of Engineers (USACE) under a Nationwide Permit (NWP) without a Pre-Construction Notification (PCN). Project specific permit was not issued by USACE, therefore is not in the plan set. The USACE general conditions are in the "General Notes."</p> <p><input type="checkbox"/> Work is authorized by the United States Army Corps of Engineers (USACE) under a Nationwide Permit (NWP) with a Pre-Construction Notification (PCN). The project specific permit issued by the United States Army Corps of Engineers (USACE) is included in the plan set. The USACE general conditions are in the "General Notes."</p> <p><input type="checkbox"/> Work is authorized by the United States Army Corps of Engineers (USACE) under a Individual Permit (IP). The project specific permit issued by the United States Army Corps of Engineers (USACE) is included in the plan set.</p> <p><input type="checkbox"/> Work would be authorized by the United States Army Corps of Engineers (USACE) permit. The project specific permit issued by the USACE will be provided to the contractor.</p> <p>United States Coast Guard (USCG) Permit is required for projects that involve the construction or modification (including changes to lighting) of a bridge or causeway across a water body determined to be navigable by the United States Coast Guard (USCG) under Section 9 of the Rivers and Harbors Act. If additional work not represented in the plans is required, contact the Engineer immediately.</p> <p><input checked="" type="checkbox"/> No United States Coast Guard (USCG) Coordination Required</p> <p><input type="checkbox"/> United States Coast Guard (USCG) Permit</p> <p><input type="checkbox"/> United States Coast Guard (USCG) Exemption</p> <p>No Additional Comments</p>	<p>IV. VEGETATION RESOURCES</p> <p>Preserve native vegetation to the extent practical. Refer to TxDOT Standard Specifications in order to comply with requirements for invasive species, beneficial landscaping and tree/brush removal.</p> <p>No Additional Comments</p> <p>V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS</p> <p>If any of the listed species below are observed, cease work in the area, do not disturb species or habitat and contact the Engineer immediately.</p> <p>The work may not remove active nests (from bridges, structures, or vegetation adjacent to the roadway, etc.) during nesting season (February 15 to October 1). If removal of structures or vegetation is necessary during the nesting season, the Contractor shall conduct a bird survey no more than 3 days in advance of the clearing/demolish start date. All bird surveys shall be conducted by a Field Biologist and adhere to the guidance document "Avoiding Migratory Birds and Handling Potential Violations" found in the TxDOT Environmental Compliance Toolkits at the time of the survey. (See below for Field Biologist and Ornithologist qualifications)</p> <p>No Additional Comments</p> <p><small>Field Biologist, Ornithologist – a field biologist is defined as an individual qualified to perform field investigations, presence/absence surveys and habitat surveys for protected avian species or species of concern. A mandatory bachelor's degree in biology or a related science is required. At a minimum, the Field Biologist, Ornithologist, shall have completed and reported a minimum of three presence/absence and habitat surveys for protected avian species in the past five years. A minimum of three projects must have been conducted in Texas. Surveys shall have been performed for documentation of species in accordance with a protocol approved by USFWS or TPWD, or following generally accepted methodologies.</small></p>	<p>VII. OTHER ENVIRONMENTAL ISSUES</p> <p>Comments:</p>

			TxDOT Houston District		
<p>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</p> <p>EPIC</p>					
FILE:	EPIC Sheet.dgn	DN:	CK:	DW:	CK:
© TxDOT:	March 2017	CONT	SECT	JOB	HIGHWAY
		0508	01	394, etc.	VA
<small>UPDATED section V, text and added definition (10/17) ADDED USCG and USACE notes in Section VII (04/18)</small>		DIST	COUNTY	SHEET NO.	
		HOU	Harris	116	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept in the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):
0508-01-394,ETC

1.2 PROJECT LIMITS:

From: VARIOUS LOCATIONS

To: VARIOUS LOCATIONS

1.3 PROJECT COORDINATES:

BEGIN: (Lat) _____, (Long) _____

END: (Lat) _____, (Long) _____

1.4 TOTAL PROJECT AREA (Acres): 10.76

1.5 TOTAL AREA TO BE DISTURBED (Acres): 10.76

1.6 NATURE OF CONSTRUCTION ACTIVITY:

CONSTRUCTION OF LANDSCAPE AND SCENIC ENHANCEMENTS, CONSISTING OF LANDSCAPE DEVELOPMENT.

1.7 MAJOR SOIL TYPES:

Soil Type	Description
CLODINE URBAN LAND COMPLEX	DEEP POORLY DRAINED, MODERATELY PERMEABLE SOILS
TEXLA URBAN LAND	DEEP SOMEWHAT DRAINED SOILS
URBAN LAND	MAJORITY IMPROVED NON-NATIVE COMPACTED SOILS

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
 - Blade existing topsoil into windrows, prep ROW, clear and grub
 - Remove existing pavement
 - Grading operations, excavation, and embankment
 - Excavate and prepare subgrade for proposed pavement widening
 - Remove existing culverts, safety end treatments (SETs)
 - Remove existing metal beam guard fence (MBGF), bridge rail
 - Install proposed pavement per plans
 - Install culverts, culvert extensions, SETs
 - Install mow strip, MBGF, bridge rail
 - Place flex base
 - Rework slopes, grade ditches
 - Blade windrowed material back across slopes
 - Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- Other: PLANT BED PREPARATION, IRRIGATION SYSTEM, PLACEMENT OF PLANT MATERIAL.
- Other: _____
- Other: _____
- Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
GREENS BAYOU WHITE OAK BAYOU	FRESHWATER STREAM FRESHWATER STREAM
HUNTING BAYOU LITTLE WHITE OAK BAYOU	FRESHWATER STREAM FRESHWATER STREAM
CARPENTERS BAYOU HALLS BAYOU	FRESHWATER STREAM FRESHWATER STREAM
GARNERS BAYOU GOOSE CREEK	FRESHWATER STREAM FRESHWATER STREAM
SAN JACINTO RIVER CEDER BAYOU	TIDAL STREAM TIDAL STREAM
HOUSTON SHIP CHANNEL	TIDAL STREAM

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: _____
- Other: _____
- Other: _____

1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:

MS4 Entity
N / A

STORMWATER POLLUTION PREVENTION PLAN (SWP3)



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
6				117
STATE	STATE DIST.	COUNTY		
TEXAS	HOU	HARRIS		
CONT.	SECT.	JOB	HIGHWAY NO.	
0508	01	394,ETC	IH 10,ETC	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: EROSION CONTROL COMPOST
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

T / P

- Sediment Trap
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained

Sedimentation Basin

- Not required (<10 acres disturbed) Required (>10 acres) and implemented.
 - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
 - 3,600 cubic feet of storage per acre drained
- Required (>10 acres), but not feasible due to:
 - Available area/Site geometry
 - Site slope/Drainage patterns
 - Site soils/Geotechnical factors
 - Public safety
 - Other: _____

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To
N / A		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To
N / A		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3 .

2.9 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.


STORMWATER POLLUTION PREVENTION PLAN (SWP3)



FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6			118
STATE	STATE DIST.	COUNTY	
TEXAS	HOU	HARRIS	
CONT.	SECT.	JOB	HIGHWAY NO.
0508	01	394,ETC	IH 10,ETC




CURB INLETS 8" DIAMETER LOGS

ITEM 506-6040 BIODEG EROSN CONT LOGS (INSTL) (8")



DROP INLETS AND OTHER LOCATIONS 12" DIAMETER LOGS

ITEM 506-6041 BIODEG EROSN CONT LOGS (INSTL) (12")



MATERIAL REQUIREMENTS

FILL:

Use 100% shredded mulch or other non-compost biodegradable material as fill for logs. No compost or fines.

DO NOT USE MATERIAL WHICH PROHIBITS WATER INFILTRATION.

LOG MESH:

Use mesh with 1/4" openings or larger. Mesh must allow water infiltration but also hold fill material in place.

SEDIMENT BASIN & TRAP USAGE GUIDELINES

A sediment trap (erosion control log) may be used to filter sediment out of runoff draining from an unstabilized area.

Traps: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).







Sediment traps should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way

The trap should be cleaned when the capacity has been reduced by 1/2 or the sediment has accumulated to a depth of 1', whichever is less.

REQUIRED ITEMS:

- ITEM 506-6040 BIODEG EROSN CONT LOGS (INSTL) (8") LF
- ITEM 506-6041 BIODEG EROSN CONT LOGS (INSTL) (12") LF
- ITEM 506-6043 BIODEG EROSN CONT LOGS (REMOVE) LF



Texas Department of Transportation
Houston District

EROSION CONTROL LOG

ECL-12

FILE: STDG4a.DGN	DW: TxDot	CK: TxDot	DW: TxDot	CK: TxDot
©TxDOT 2014	DISTRICT: HOU	FED REG: 6	PROJECT NUMBER:	SHEET: 119
REVISIONS				
3/15 MINOR CORRECTIONS				
COUNTY:		CONTROL:	SECT:	JOB:
HARRIS, ETC		0508	01	398 H10, ETC