

FHWA TEXAS DIVISION	PROJECT NO.		SHEET NO.
	F2024(810)		1
STATE	DISTRICT	COUNTY	
TEXAS	BMT	LIBERTY	
CONTROL	SECTION	JOB	HIGHWAY NO.
0952	01	062	FM 1008

DESIGN CRITERIA: PM  
 DES. SPEED: N/A  
 ADT (2025): 7,600  
 ADT (2045): 10,400  
 URBAN UNDIVIDED

**INDEX OF SHEETS**

SHEET NO.    DESCRIPTION

SEE SHEET #2

STATE OF TEXAS  
 DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED  
 STATE HIGHWAY IMPROVEMENT

FEDERAL PROJECT NO.: F2024(810)

CSJ: 0952-01-062

FM 1008


LIBERTY COUNTY

(CSJ: 0952-01-062) PROJECT LENGTH = 14541.12 FT = 2.754 MI  
 LIMITS: FROM ARNOLD DR, SOUTH TO SH 321

FOR THE CONSTRUCTION OF AN OVERLAY PROJECT  
 CONSISTING OF BASE REPAIRS, MILL & INLAY

0952-01-062  
 END PROJECT  
 STATION 156+32  
 REF. MRK. 452+1.259

0952-01-062  
 BEGIN PROJECT  
 STATION 10+61  
 REF. MRK. 450+0.489



NTS

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)-21 THRU BC (12)-21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".



SUBMITTED FOR LETTING: 1/4/2024  
 DocuSigned by:

*[Signature]*  
 DISTRICT DESIGN ENGINEER

RECOMMENDED FOR LETTING: 1/8/2024  
 DocuSigned by:

*Lisa Collins*  
 DISTRICT DIRECTOR OF TRANSPORTATION  
 PLANNING AND DEVELOPMENT

APPROVED FOR LETTING: 1/8/2024  
 DocuSigned by:

*Maxim N. Gorb, P.E.*  
 DISTRICT ENGINEER

578CD749508D410...

EQUATIONS: NONE  
 EXCEPTIONS: NONE  
 RAILROAD CROSSINGS: NONE

©2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023).

12/28/2023 10:11:46 AM D:\txdot\projectwiseonline.com\TXDOTS\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3 - Roadway\TitleSheet.dgn

# INDEX OF SHEETS

## GENERAL

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- 3-6 TYPICAL SECTIONS
- 7-14 GENERAL NOTES
- 15-16 ESTIMATE & QUANTITY
- 17-20 QUANTITY SUMMARY

## TRAFFIC CONTROL PLAN

- 21 SEQUENCE OF WORK
- ## 22-33 BC(1)-21 THRU BC(12)-21
- ## 34 TCP (2-2)-18
- ## 35 TCP (2-4)-18
- ## 36 TCP (3-1)-13
- ## 37 TCP (3-3)-14
- ## 38 TCP (SC-1)-22
- ## 39 TCP (SC-7)-22
- ## 40 TCP (SC-8)-22
- ## 41 WZ (BTS-1)-13
- ## 42 WZ (BTS-2)-13
- ## 43 WZ (RS)-22
- ## 44 WZ (STPM)-23
- ## 45 WZ (UL)-13

## ROADWAY DETAILS


- 46 PVMT EDGE JOINT DETAIL
- 47-52 ROADWAY LAYOUT
- 53 CLEARING DETAIL
- 54 DRIVEWAY SUMMARY & DETAILS
- 55 MAILBOX TURNOUT

## TRAFFIC STANDARDS

- 56-58 STRIPING LAYOUTS
- 59 SUMMARY OF SMALL SIGNS
- 60 SMALL SIGN DETAIL
- ## 61 SMD (GEN)-08
- ## 62 SMD (SLIP-1)-08
- ## 63 SMD (SLIP-2)-08
- ## 64 SMD (SLIP-3)-08
- ## 65 TSR (3)-13
- ## 66 TSR (4)-13
- ## 67 TSR (5)-13
- ## 68 D & OM(4)-20
- ## 69 D & OM(5)-20
- ## 70 D & OM(VIA)-20
- ## 71 PM (1)-22
- ## 72 PM (2)-22
- ## 73 PM (3)-22

## ENVIRONMENTAL ISSUES

- 74-75 SWP3
- ## 76 INLET PROTECTION
- 77 EPIC



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE BY A ## HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

*Jason D. Waldrep, P.E.*

P. E.

12/27/2023

DATE


FM 1008

INDEX OF SHEETS



FHWA TEXAS DIVISION		FEDERAL AID PROJECT NO.		SHEET NO.
TEXAS		BMT		2
CONTROL		SECTION		JOB
0952		01		062
		HIGHWAY NO.		FM 1008


DATE: 12/22/2023 7:11:29 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\TypicalSections.dgn



**EXISTING TYPICAL SECTION**

STA 10+61 TO STA 16+99



NOTE: MILL (1" AT CL & 2" AT GUTTER) INLAY (3" AT CL & 2" AT GUTTER) IN CURB AND GUTTER SECTION ONLY.  
 \*THE PURPOSE IS TO REESTABLISH A 2.5% NORMAL CROWN.



**PROPOSED TYPICAL SECTION**

STA 10+00 TO STA 10+91 (STRIPING ONLY)  
 STA 10+91 (BEG MILL AND INLAY) TO STA 16+99

EDGE TAPER DETAIL STA 10+91 TO STA 24+71



*Jason D. Waldrep, P.E.*

**FM 1008  
 TYPICAL SECTIONS**


SHEET 1 OF 4




CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		3

N. T. S.


DATE: 12/22/2023 7:11:29 PM  
 FILE: P:\7\tdot.projects\095201062\4 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\TypicalSections.dgn




NOTE: MILL (1" AT CL & 2" AT GUTTER) INLAY (3" AT CL & 2" AT GUTTER) IN CURB AND GUTTER SECTION ONLY.  
 \*THE PURPOSE IS TO REESTABLISH A 2.5% NORMAL CROWN.




EDGE TAPER DETAIL STA 10+91 TO STA 24+71





  
 12/27/2023  
*Jason D. Waldrep, P.E.*  
**FM 1008**  
**TYPICAL SECTIONS**


SHEET 2 OF 4

		CONT	SECT	JOB	HIGHWAY
		0952	01	062	FM 1008
		DIST	COUNTY		SHEET NO.
		BMT	LIBERTY		4

N. T. S.


DATE: 12/22/2023 7:11:29 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\TypicalSections.dgn



  
 12/27/2023  
*Jason D. Waldrep, P.E.*




**FM 1008**  
**TYPICAL SECTIONS**

SHEET 3 OF 4

			
CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		5

N. T. S.

12/22/2023 7:11:30 PM  
 Pw://ttdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/3. Roadway/TypicalSections.dgn



12/27/2023  
 Jason D. Waldrep, P.E.

**FM 1008**  
**TYPICAL SECTIONS**

SHEET 4 OF 4

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		6

N. T. S.

Highway: FM 1008

Control: 0952-01-62

**GENERAL NOTES:**

Contractor questions on this project are to be addressed to the following individual(s):

Name Roberto Rodriguez, P.E.  
Email Roberto.M.Rodriguez@txdot.gov

Name Nyemb Nyemb, P.E.  
Email Nyemb,Neymb@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Assume full responsibility for the preservation of all sod, shrubbery, and trees at the site during construction. Carefully preserve and replace, in their original position, all sod and shrubbery removed. Replace all Contractor damaged sod and/or shrubbery at the Contractor's own expense.

Maintain adequate drainage throughout the limits of the project during all construction phases. Provide a list of equipment, including idle equipment, used on the project weekly.

**Item 000 Utilities**

Consider the locations of underground utilities depicted on the plans as approximate and employ responsible care to avoid damaging, or accommodate utility facilities. Depending upon scope and magnitude of

Highway: FM 1008

Control: 0952-01-62

planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities. If utility damage (breaks, leaks, nicks, dents, gouges, etc.) occurs, contact the utility facility owner or operator immediately. In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others.

**Item 4 Scope of Work**

Remove all vegetation from pavement edges, intersections and driveways before planing or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

It is the contractor's responsibility to mark the location of all existing striping and place proposed striping back in the same location or as shown in the plans.

**Item 5 Control of the Work**

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

**Item 6 Control of Materials**

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Highway: FM 1008

Control: 0952-01-62

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the link below:

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html>

for clarification on material categorization.

Mixing of materials, storing of materials, storing of equipment, or repairing of equipment on top of concrete pavement or bridge decks will not be permitted unless specifically authorized.

#### Item 7 Legal Relations and Responsibilities

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Maintain ingress and egress to the adjacent property at all times. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

Personal vehicles of the contractor's employees will not be parked within the right of way at any time including any section closed to public traffic, unless the vehicle is being used for construction procedures. However, the Contractor's employees may park on the right of way at sites where the contractor has their office, equipment and materials storage yard.

The Contractor will be familiar with the right of way map and the location of all the right of way monumentation. Care will be taken by the Contractor and its subcontractors to protect and avoid disturbance to the right of way

Highway: FM 1008

Control: 0952-01-62

monumentation. Any monument disturbed by the Contractor will be repaired and/or replaced to the satisfaction of the Engineer. This work will be corrected at the contractor's expense.

No significant traffic generator events have been identified in the project limits.

#### Item 8 Prosecution and Progress

Working days will be charged during all observed curing times, even if no other work is being performed.

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Notify the Engineer 72 hours in advance of any temporary or permanent lane, ramp or connector affected by closures, detours, or restrictions to lane widths, alterations to vertical clearances or modifications to alignment/radii. Any other modification to the roadway that may adversely affect the mobility of oversized/overweight trucks will require 5 business day advance written notice to the Engineer.

For all travel lanes, ramps, or connector closures, provide information regarding dates, times, typical work hours, type of closure, reason for closure, and expected project duration to the Liberty Area Office. This information will be provided 72 hours in advance of the closure to the Liberty Area Office. If approved, the Liberty Area Office will forward the information to the Public Information Officer for the Beaumont District.

No simultaneous daytime and nighttime work will be allowed unless otherwise approved.

Night work will be allowed.

Provide full-time, off-duty uniformed officer(s), with transportation jurisdiction and full police powers in the county or city in which the project



Highway: FM 1008

Control: 0952-01-62

is located, during construction as directed . The officer(s) must be able to show proof of certification by the Texas Commission on Law Enforcement Officers Standards.

Officer(s) will be paid by force account, and must be approved. The vehicle used must be a marked law enforcement vehicle in the city or county where the project is located. Complete the daily tracking form provided by the Department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Maintain one lane open to traffic during construction, unless otherwise approved.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

Limit lane closures to 1 mile unless otherwise approved.

Supplemental lighting in addition to lighting on equipment and work vehicles will be required to insure adequate lighting for workers safety and inspection. All operations including plaining and ACP placement must be adequately lighted using supplemental lighting. All supplemental lights are subject to the approval of the Engineer. Supplemental lighting will be added to the milling machine, asphalt distributor, aggregate spreader, rollers and laydown machine unless otherwise approved. This is considered subsidiary to the various bid Items of the contract.

All edges must be backfilled by the end of the day with a 3:1 or flatter slope. No drop offs will be left overnight.

The Engineer will suspend time charges after completion of all work and removal of the barricades. The Department will grant final acceptance when all performance periods are complete.

Accrue Contract time charges through the Contractor's completion of the final punch list. Time will not be suspended until all work is completed.

Submit a work schedule to the Engineer at the preconstruction meeting indicating completion dates for each location, and the number of crews required for the completion of the contract within the contract time period.

Highway: FM 1008

Control: 0952-01-62

If at any time during the contract the work progress is behind the initial schedule, submit documentation indicating how the project will be accelerated to ensure project completion in the remaining contract time.

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

Working days will be charged during the observed curing times, even if no other work is being performed.

### **HURRICANE**

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

### **Item 134 Backfilling Pavement Edges**

Backfilling Pavement Edges by station includes both sides of the roadway. No deduction in payment will be made when in the opinion of the Engineer only one side of a roadbed section requires backfilling.

Use RAP salvaged from within the project limits to the maximum extent possible. Size RAP so that all material passes the two-inch sieve. Use RAP that does not contain deleterious material such as clay or organic material.

As SP-C is placed, backfill the pavement edges daily so that no drop-off conditions exist. Type A or B material will meet one of the following requirements:

1. Item 132, Type C - Embankment Type C will conform to the following specification requirements:
  - Liquid Limit – 40 maximum,
  - Plasticity Index – 25 maximum, 8 minimum,
  - Cohesionless sand will not be permitted.

Highway: FM 1008

Control: 0952-01-62

2. Reclaimed asphalt pavement (RAP) generated from this project.

**Item 164 Seeding for Erosion Control**

Final grading and stabilization (seeding) will be achieved as soon as possible and not scheduled only for the end of the project. Final grading and stabilization should be initiated as the overall work progresses.

Eliminate seeding in areas of natural growth determined to have enough cover.

**Item 166 Fertilizer**

This item is not paid for directly, but is subsidiary to item 164

Fertilize all the seeded or sodded areas of project.

Furnish and apply fertilizer with analysis of 13-13-13 at a rate of 600 bulk pounds per acre.

**Item 168 Vegetative Watering**

Equip water trucks with sprinkler systems capable of covering the entire area to be seeded or sodded from the roadway.

Water all newly placed sod or seeded areas the same day of installation. Thereafter, maintain the sod or seeded areas in a well-watered condition and at no time allow the areas to dry to the condition that water stress is evident.

Mechanical watering may not be required during periods of adequate moisture as determined.

Furnish and apply water at a rate of 6.788 Mega gallons per acre per cycle or as directed on the plans.

Comply with stabilization requirements for 70% grass coverage; uniform vegetative coverage is required. During this period, meter and operate water equipment under pumping pressure capable of delivering the required quantities of water necessary. For Permanent seeding each cycle will be executed weekly for 12 weeks, unless directed otherwise. For Temporary

Highway: FM 1008

Control: 0952-01-62

seeding each cycle will be executed weekly for 6 weeks, unless directed otherwise.

Provide a log book showing daily water usage and receipts of water applied, in addition to metering the water equipment.

**Item 316 Seal Coat**

Furnish medium pneumatic-tire rollers in accordance with Item 210, "Rolling."

All trucks hauling materials to be paid for by truck measurement will be "struck off" before delivery to the project.

The open season for the application of asphalt is **May 1<sup>st</sup> through September 15<sup>th</sup>** unless otherwise directed in writing.

Seal intersections and driveways before sealing the main lanes. Seal all existing roadway surfaces, including extra widths, crossovers, roadside parks, picnic areas, mailbox turnouts, public road intersections, and public drives, within the limits of each project. Do not seal intersections or driveways surfaced with ACP or constructed of concrete.

Sweep all roadways with a powered rotary broom before placement of the surface treatment to remove all loose or excess material or debris. After rolling, sweep as soon as aggregate has sufficiently bonded to remove excess. Use a vacuum broom on all roadway sections with curb and gutter and all roadway sections within the city limits of any city.

Vehicles used to haul aggregate from the stockpile to the chip spreader will not be overloaded. Any damage to the roadway caused by the vehicles will be repaired by the Contractor at his expense and subsequent loads will be reduced so as not to cause further damage.

Cure the surface treatment as directed before placement of the overlay.

**Item 351 Flexible Pavement Structure Repair**

The repair areas will require full depth saw-cut when milling is not used. Consider this work to be subsidiary to the various bid items of the contract.

Highway: FM 1008

Control: 0952-01-62

Highway: FM 1008

Control: 0952-01-62

Provide Flexible Pavement Repair with Material meeting the requirements of Item 3076, Type B (PG 64-22) unless approved otherwise. Place Hot Mix with a constant longitudinal surface grade and tie in flush with the existing surface at each end and both sides of the repair area.

Unless otherwise directed, place new D-G HMA with maximum 5" lifts. The minimum patch sizes will be 6' in width and 10' in length.

Match the existing cross slope in the repair areas, unless directed otherwise.

All repair locations must be filled the same day they are excavated. No open cut areas will be allowed overnight.

All excavated materials will be removed from the project daily.

Ordinary compaction will be used on this project.

Seal the perimeter of the repair areas with hot poured rubber in accordance with Item 712. Consider this work to be subsidiary to the various bid items of the contract.

**Item 354 Plaining and Texturing Pavement**

Where the underlying flexible base is exposed during the plaining operation, prime this area with an asphalt at a rate as directed and patch with an approved HMA material, at the end of the day's operation in which it occurs. These items of work will not be paid for directly but will be subsidiary to Item 354.

Stockpile salvaged materials at the Material Stockpile found 3.07 Miles North of FM 1008 on SH 321. Forty-eight hours prior to beginning any and all plaining, the Contractor is directed to contact Rodney Shivers (Liberty Maintenance Supervisor) at (936) 336-5669.

**Item 502 Barricades, Signs, and Traffic Handling**

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

<u>Square Feet</u>	<u>Minimum Thickness</u>
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Arrange asphalt laydown schedule to meet plan striping requirements.

Restrict work to one side of the roadway at a time.

Use 42" Cones as channelizing devices.

Remove all traffic control devices from the right of way when they are not in use. Devices scheduled to be used within 3 days may be placed along the shoulder of the roadway or along the right of way when not in use, or stored in other approved areas on the project. Cover any construction signs that are not in effect and are installed in a fashion that will not allow them to be removed from the right of way easily.

Arrange construction operations to prevent the hauling of materials through the completed pavement sections unless otherwise approved.

Provide all flaggers and pilot vehicle drivers with two-way radio communication capability. Provide flaggers at each side road intersection.

**Item 506 Temporary Erosion, Sedimentation, and Environmental Controls**

It is not anticipated that any erosion, sedimentation, or environmental control devices will be needed on this project. The Contractor Force Account "SW3P Contingency" that has been established for this project is

Highway: FM 1008

Control: 0952-01-62

intended to be used in the event that such controls become necessary. The SW3P for this project will consist of the use of any temporary erosion control measures deemed necessary and as specified under this Item. This work will be paid for in accordance with Article 4.4., "Changes in the Work.

The Contractor will designate a clean out area for concrete trucks. No other area will be allowed without approval of the Engineer.

#### **Item 585 Ride Quality for Pavement Surfaces**

Use Surface Test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

#### **Item 644 Small Roadside Sign Assemblies**

Erect Reference Marker signs at the same station as they were located before removal.

#### **Item 658 Delineator and Object Marker Assemblies**

Mount reflectors on a steel or concrete bridge rail, where the bridge is greater than 200' in length, at a height of 6" from the top of the rail to the bottom of the reflector.

Mount reflectors on a steel or concrete bridge rail, where the bridge is 200' or less in length, at the same height as the reflectors in the MBGF rail element.

Use bolt-on attachment for delineator assemblies attached to guard fence.

Install delineators when directed. This may require installation of delineators on portions of guardrail and bridge rail that is not being repaired in order to maintain consistency with adjacent sections.

MBGF will receive GF2 delineators installed on 100' maximum spacing.

Type C delineators will be installed using Adhesive 795A manufactured by Davidson Traffic Control Products or an equivalent approved in writing.

Highway: FM 1008

Control: 0952-01-62

#### **Item 666 Retroreflectorized Pavement Markings**

Furnish Type II drop-on glass beads.

#### **Item 672 Raised Pavement Markers**

Remove all existing traffic buttons before the application of the seal coat. Consider this work to be subsidiary to the various bid items of the contract.

#### **Item 677 Eliminating Existing Pavement Markings and Markers**

Remove all contaminates and loose material. Consider this work to be subsidiary to the various bid items of the contract.

Remove existing raised pavement markers before the addition of the asphaltic pavement or seal coat. Dispose of the removed markers from the project at the end of each workday. Consider this work to be subsidiary to the various bid items of the contract.

#### **Item 3077 Superpave Mixtures**

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC "Superpave Gyrotory Compactor" and TGC "Texas Gyrotory Compactor". All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Allow the One Course Surface Treatment to cure a minimum of 14 days before placement of the Superpave Mixture.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down,

Highway: FM 1008

Control: 0952-01-62

weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68°F through 72°F).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

1. A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
2. Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
3. Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
4. An operational telephone system.
5. Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
6. Water (for testing purposes) from an approved source.
7. Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and fireproof surface for the ignition oven with a minimum of

Highway: FM 1008

Control: 0952-01-62

6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.

8. A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment.
9. A laboratory sink measuring 24 × 30 in. and 12 in. deep.
10. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.
11. Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17.

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes. RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements.

Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

A material transfer device (MTD) will be required for all surface courses of HMA on this project. An MTD is defined as a self-propelled, wheel-mounted vehicle capable

Highway: FM 1008

Control: 0952-01-62

of receiving HMA from the haul trucks separate from the paver. The MTD will have a minimum storage capacity of approximately 25 tons and will be equipped with a pivoting discharge conveyor and a means of completely remixing the HMA before placement. The Engineer may approve an alternative device on a trial basis for the surface course. This device will be capable of receiving HMA separate from the paver and must have remixing capabilities. For all other courses of HMA, other than the surface, an alternative device may be used as long as it is capable of receiving HMA separate from the paver.

Overlay across the ends of any curb ramps must not create a barrier to their use. Changes in level up to 1/4" may be vertical; between 1/4" and 1/2" must be beveled with a slope no greater than 1:2; greater than 1/2" will require a "ramp".

Arrange laydown operations to leave existing centerline markings in place for the maximum time feasible.

Furnish non-tracking tack coat meeting the requirements of SP 3096. The work for this and materials furnished are subsidiary to this item.

**Item 6185**

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMA's for mobile operations.

In addition to the shadow vehicles with truck mounted attenuator (TMA) that are specified as being required for this project, provide one additional shadow vehicle with TMA for TCP as detailed in the general notes of the standards elsewhere in the plans.

Therefore, two total shadow vehicles with TMA will be required for this type of work.

The contractor will be responsible for determining the total number of TMA's required based on the number of operations going on at the same time.



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0952-01-062

DISTRICT Beaumont

COUNTY Liberty

HIGHWAY FM 1008

CONTROL SECTION JOB				0952-01-062		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00177795			
COUNTY				Liberty			
HIGHWAY				FM 1008			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6002	PREPARING ROW	STA	100.000		100.000	
	134-6004	BACKFILL (TY A OR B)	STA	130.000		130.000	
	164-6003	BROADCAST SEED (PERM) (RURAL) (CLAY)	SY	4,387.000		4,387.000	
	168-6001	VEGETATIVE WATERING	MG	72.500		72.500	
	316-6017	ASPH (AC-20-5TR)	GAL	16,425.000		16,425.000	
	316-6404	AGGR (TY-PB GR-4 OR TY-PL GR-4 SAC-A)	CY	351.000		351.000	
	351-6006	FLEXIBLE PAVEMENT STRUCTURE REPAIR(10")	SY	5,491.000		5,491.000	
	354-6003	PLAN & TEXT ASPH CONC PAV(0" TO 3")	SY	2,535.000		2,535.000	
	354-6043	PLANE ASPH CONC PAV (1")	SY	5,850.000		5,850.000	
	354-6089	PLANE ASPH CONC PAV(1" TO 2")	SY	7,355.000		7,355.000	
	429-6003	CONC STR REPAIR(DECK REP(PART DEPTH))	SF	320.000		320.000	
	465-6274	MANH (COMPL)(RISER ONLY)	EA	8.000		8.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		5.000	
	506-6047	TEMP SDMT CONT FENCE (INLET PROTECTION)	LF	70.000		70.000	
	530-6004	DRIVEWAYS (CONC)	SY	214.000		214.000	
	530-6005	DRIVEWAYS (ACP)	SY	66.000		66.000	
	530-6008	TURNOUTS (ACP)	SY	39.000		39.000	
	530-6016	DRIVEWAYS (BASE)	SY	198.000		198.000	
	533-6004	RUMBLE STRIPS (CENTERLINE) ASPHALT	LF	12,500.000		12,500.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	34.000		34.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	2.000		2.000	
	644-6007	IN SM RD SN SUP&AM TY10BWG(1)SA(U)	EA	2.000		2.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	38.000		38.000	
	658-6069	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BR)	EA	42.000		42.000	
	662-6005	WK ZN PAV MRK NON-REMOV (W)6"(BRK)	LF	2,956.000		2,956.000	
	662-6008	WK ZN PAV MRK NON-REMOV (W)6"(SLD)	LF	27,672.000		27,672.000	
	662-6012	WK ZN PAV MRK NON-REMOV (W)8"(SLD)	LF	211.000		211.000	
	662-6016	WK ZN PAV MRK NON-REMOV (W)24"(SLD)	LF	144.000		144.000	
	662-6037	WK ZN PAV MRK NON-REMOV (Y)6"(SLD)	LF	29,541.000		29,541.000	
	662-6041	WK ZN PAV MRK NON-REMOV (Y)24"(SLD)	LF	110.000		110.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	21.000		21.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,477.000		1,477.000	
	666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	211.000		211.000	
	666-6305	RE PM W/RET REQ TY I (W)6"(BRK)(090MIL)	LF	3,000.000		3,000.000	
	666-6308	RE PM W/RET REQ TY I (W)6"(SLD)(090MIL)	LF	27,672.000		27,672.000	
	666-6320	RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL)	LF	29,541.000		29,541.000	



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0952-01-062

DISTRICT Beaumont

COUNTY Liberty

HIGHWAY FM 1008

CONTROL SECTION JOB				0952-01-062		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00177795			
COUNTY				Liberty			
HIGHWAY				FM 1008			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	668-6076	PREFAB PAV MRK TY C (W) (24") (SLD)	LF	144.000		144.000	
	668-6077	PREFAB PAV MRK TY C (W) (ARROW)	EA	4.000		4.000	
	668-6078	PREFAB PAV MRK TY C (W) (DBL ARROW)	EA	4.000		4.000	
	668-6085	PREFAB PAV MRK TY C (W) (WORD)	EA	8.000		8.000	
	668-6108	PREFAB PAV MRK TY C (Y) (24") (SLD)	LF	110.000		110.000	
	672-6007	REFL PAV MRKR TY I-C	EA	15.000		15.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	1,463.000		1,463.000	
	3076-6071	D-GR HMA TY-D PG 64-22 (EXEMPT)	TON	322.000		322.000	
	3077-6033	SP MIXES SP-C SAC-A PG76-22	TON	7,325.000		7,325.000	
	3077-6075	TACK COAT	GAL	2,737.000		2,737.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY	54.000		54.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	20.000		20.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	



DATE: 12/22/2023 7:12:35 PM  
 FILE: p:\t\dot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\Quantity\_Summar ies.dgn

### BASIS OF ESTIMATE

ITEM	CODE	DESCRIPTION	QUANTITY	RATE	DEPTH	QUANTITY
168	6001	VEGETATIVE WATERING	1.78 AC	6.788 MG/AC/CYCLE, 6 CYCLES	-	72.5 MG
316	6017	ASPH (AC-20-5TR)	45624 SY	0.36 GAL/SY	-	16425 GAL
316	6404	AGGR (TY-PB GR-4 OR TY-PL GR-4 SAC-A)	45624 SY	130 CY/SY	-	351 CY
3077	6033	SP MIXES SP-C SAC-A PG76-22	7,355 SY	110 LB/SY/IN	2.5 IN	1,011 TON
3077	6033	SP MIXES SP-C SAC-A PG76-22	38,269 SY	110 LB/SY/IN	3 IN	6,314 TON
3077	6075	TACK COAT	45,624 SY	0.06 GAL/SY	-	2,737 GAL

### SIGNING

STA	TO	STA	644	644	644	644
			6001	6004	6007	6076
			IN SM RD SN SUP&AM TY10BWG(1)SA(P)	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	IN SM RD SN SUP&AM TY10BWG(1)SA(U)	REMOVE SM RD SN SUP&AM
			EA	EA	EA	EA
10+00	TO	156+32	34	2	2	38
<b>TOTAL:</b>						<b>38</b>

### ROADWAY ITEMS

STA	TO	STA	LENGTH (FT)	WIDTH (FT)	SURFACE AREA (SY)	100	134	164	354		429	465	506	533	658	3076	3077		
						6002	6004	6003	6003	6043	6089	6003	6274	6047	6004	6069	6071**	6033*	6075*
						PREPARING ROW	BACKFILL (TY A OR B)	BROADCAST SEED (PERM) (RURAL) (CLAY)	PLANE & TEXT ASPH CONC PAV (0" TO 3")	PLANE ASPH CONC PAV (1")	PLANE ASPH CONC PAV (1" TO 2")	CONC STR REPAIR (DECK REP(PART DEPTH))	MANH (COMPL) (RISER ONLY)	TEMP SDMT CONT FENCE (INLET PROTECTION)	RUMBLE STRIPS (CENTERLINE) ASPHALT	INST DEL ASSM (D-SW) SZ (BRF) CTB(BR)	D-GR HMA TY-D PG64-22	SP MIXES SP-C SAC-A PG 76-22	TACK COAT
						STA	STA	SY	SY	SY	SY	SF	EA	LF	LF	EA	TON	SY	SY
10+00	TO	24+70	1,470	48	7,355	20	-	-	534	-	7,355	-	8	70	-	-	-	7355	-
24+70	TO	156+32	13,162	26	38,269	80	130	4387	2001	5850	-	320	-	-	12,500	42	322	38269	38269
<b>PROJECT TOTAL:</b>						<b>100</b>	<b>130</b>	<b>4387</b>	<b>2535</b>	<b>5,850</b>	<b>7,355</b>	<b>320</b>	<b>8</b>	<b>70</b>	<b>12,500</b>	<b>42</b>	<b>322</b>	<b>45,624</b>	<b>38,269</b>

\* FOR THE CONTRACTORS INFORMATION ONLY  
 \*\*RUMBLE STRIP REMOVAL/REPLACE MATERIAL

### SUMMARY OF PAVEMENT MARKINGS

STA	TO	STA	662						666					
			6005	6008	6012	6016	6037	6041	6109	6111	6035	6305	6308	6320
			WK ZN PAV MRK NON-REMOV (W) 6" (BRK)	WK ZN PAV MRK NON-REMOV (W) 6" (SLD)	WK ZN PAV MRK NON-REMOV (W) 8" (SLD)	WK ZN PAV MRK NON-REMOV (W) 24" (SLD)	WK ZN PAV MRK NON-REMOV (Y) 6" (SLD)	WK ZN PAV MRK NON-REMOV (Y) 24" (SLD)	WK ZN PAV MRK SHT TERM (TAB)TY W	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	REFL PAV MRK TY I (W) 8" (SLD) (090MIL)	RE PM W/RET REQ TY I (W) 6" (BRK) (090MIL)	RE PM W/RET REQ TY I (W) 6" (SLD) (090MIL)	RE PM W/RET REQ TY I (W) 6" (SLD) (090MIL)
			LF	LF	LF	LF	LF	EA	EA	LF	LF	LF	LF	
10+00	TO	24+71	2,752	1,962	122	120	3,521	12	176	122	2,800	1,962	3,521	
24+71	TO	156+32	204	25,710	89	24	26,020	110	9	1,301	89	200	25,710	26,020
<b>PROJECT TOTAL:</b>			<b>2,956</b>	<b>27,672</b>	<b>211</b>	<b>144</b>	<b>29,541</b>	<b>110</b>	<b>21</b>	<b>1,477</b>	<b>211</b>	<b>3,000</b>	<b>27,672</b>	<b>29,541</b>

### SUMMARY OF PAVEMENT MARKINGS (Continued)


STA	TO	STA	668				672		
			6076	6077	6078	6085	6108	6007	6009
			PREFAB PAV MRK TY C (W) (24")(SLD)	PREFAB PAV MRK TY C (W) (ARROW)	PREFAB PAV MRK TY C (W) (DBL ARROW)	PREFAB PAV MRK TY C (W) (WORD)	PREFAB PAV MRK TY C (Y) (24")(SLD)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A
			LF	EA	EA	EA	LF	EA	EA
10+00	TO	24+71	120	4	2	8	55	7	147
24+71	TO	156+32	24	-	2	-	55	8	1,316
<b>PROJECT TOTAL:</b>			<b>144</b>	<b>4</b>	<b>4</b>	<b>8</b>	<b>110</b>	<b>15</b>	<b>1,463</b>

### WORK ZONE ITEMS

STA	TO	STA	6001	6185	
			6002	6002	6005
			PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	TMA (MOBILE OPS)
			EA	DAY	DAY
10+91	TO	156+32	2	54	20
<b>TOTAL:</b>			<b>2</b>	<b>54</b>	<b>20</b>

## FM 1008 QUANTITY SUMMARY

SHEET 1 OF 4



CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		17

DATE: 12/22/2023 7:12:35 PM  
 FILE: p:\t\dot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\Quantity\_Summaries.dgn

**SUMMARY OF FLEXIBLE PAVEMENT REPAIRS**

NO.	STA	DIRECTION NORTH BOUND (NB) / SOUTH BOUND (SB)	LOCATION OFFSET	WIDTH	LENGTH	AREA	351	3076
							6006	6010*
							FLEXIBLE PAVEMENT STRUCTURE REPAIR (10")	D-GR HMA TY-B PG76-22
			LT/RT	FT	FT	SY	SY	TON
1	13+11	NB	LT	6	10	7	7	4
2	14+31	NB	LT	6	10	7	7	4
3	16+16	NB	LT	6	32	21	21	12
4	16+99	NB	LT	12	58	77	77	42
5	20+10	NB	LT	12	61	81	81	45
6	22+38	NB	LT	6	10	7	7	4
7	24+38	NB	LT	6	86	57	57	31
8	24+71	NB	LT	12	15	20	20	11
9	32+37	NB		6	93	62	62	34
10	61+69	NB		6	1566	1044	1044	574
11	72+82	NB		12	467	623	623	343
12	77+69	NB		6	372	248	248	136
13	81+95	NB		6	50	33	33	18
14	86+68	NB		6	173	115	115	63
15	89+03	NB		6	65	43	43	24
16	93+90	NB		6	305	203	203	112
17	103+04	NB		6	185	123	123	68
18	106+21	NB		6	224	149	149	82
19	111+31	NB		6	120	80	80	44
20	115+90	NB		6	10	7	7	4
21	123+21	NB		6	125	83	83	46
22	123+45	NB		6	174	116	116	64
23	131+21	NB		6	55	37	37	20
24	149+39	NB		6	27	18	18	10
25	147+28	NB		6	307	205	205	113
26	152+50	NB		6	43	29	29	16
27	153+76	NB		12	21	28	28	15
28	26+12	SB		6	51	34	34	19
29	27+13	SB		6	20	13	13	7
30	27+67	SB		12	57	76	76	42
31	31+24	SB		6	40	27	27	15
32	33+04	SB		12	35	47	47	26
33	34+12	SB		6	100	67	67	37
34	36+46	SB		12	125	167	167	92
35	37+06	SB		12	10	13	13	7
36	38+72	SB		6	100	67	67	37
37	41+33	SB		12	30	40	40	22
38	42+62	SB		6	150	100	100	55
39	48+90	SB		6	103	69	69	38
40	51+94	SB		6	28	19	19	10
41	65+62	SB		12	105	140	140	77
42	66+75	SB		6	31	21	21	12
43	74+74	SB		6	61	41	41	23
44	76+79	SB		6	20	13	13	7
45	81+02	SB		6	82	55	55	30
46	81+28	SB		6	55	37	37	20
47	83+56	SB		6	71	47	47	26
48	84+29	SB		6	115	77	77	42
49	85+18	SB		6	41	27	27	15
50	87+46	SB		6	24	16	16	9
<b>SUB TOTAL:</b>							<b>4532</b>	<b>2495</b>

\* FOR THE CONTRACTORS INFORMATION ONLY.


**SUMMARY OF FLEXIBLE PAVEMENT REPAIRS (continued)**

NO.	STA	DIRECTION NORTH BOUND (NB) / SOUTH BOUND (SB)	LOCATION OFFSET	WIDTH	LENGTH	AREA	351	3076
							6006	6010*
							FLEXIBLE PAVEMENT STRUCTURE REPAIR (10")	D-GR HMA TY-B PG76-22
			LT/RT	FT	FT	SY	SY	TON
51	88+56	SB		6	168	112	112	62
52	89+31	SB		6	105	70	70	39
53	93+55	SB		6	244	163	163	90
54	93+55	SB		6	85	57	57	31
55	96+41	SB	LT	12	84	112	112	62
56	99+38	SB	LT	6	45	30	30	17
57	99+99	SB	RT	6	45	30	30	17
58	100+77	SB	RT	6	38	25	25	14
59	105+25	SB	RT	12	72	96	96	53
60	110+54	SB	LT	6	64	43	43	24
<b>TOTAL:</b>							<b>5491</b>	<b>2992</b>

\* FOR THE CONTRACTORS INFORMATION ONLY.

**FM 1008**  
**QUANTITY SUMMARY**

SHEET 2 OF 4



**Texas  
Department  
of Transportation**

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		18


DATE: 12/22/2023 7:12:36 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\Quantity\_Summaries.dgn

### DRIVEWAY & MB TURNOUT ITEMS

STA	DESCRIPTION	LOCATION	MATERIAL	WIDTH	LENGTH	AREA (SY)	530			
							6004	6005	6008	6016
							DRIVEWAYS (CONC)	DRIVEWAYS (ACP)	TURNOUTS (ACP)	DRIVEWAYS (BASE)
		LT/RT		FT	FT		SY	SY	SY	SY
	N MAIN ST (LEFT)	LT	CONC	-	-	-	-	-	-	-
	N MAIN ST (RIGHT)	RT	CONC	-	-	-	-	-	-	-
	N CHURCH ST	LT	CONC	-	-	-	-	-	-	-
	N WINFREE ST (LEFT)	LT	CONC	-	-	-	-	-	-	-
	N WINFREE ST (RIGHT)	RT	CONC	-	-	-	-	-	-	-
	N PRAIRIE ST	RT	CONC	45	3	15	15	-	-	-
	LOWE ST	LT	CONC	45	3	15	15	-	-	-
	E WARING ST	LT	CONC	70	3	23	23	-	-	-
	SHERWOOD ST	LT	CONC	70	3	23	23	-	-	-
	HILCREST ST	LT	CONC	60	3	20	20	-	-	-
	SLOVER DR	LT	CONC	80	3	27	27	-	-	-
	NE CLAYTON ST	RT	GRAVEL	45	3	15	-	-	-	1
10+91	1	LT	CONC	-	-	-	-	-	-	-
11+37	2	RT	CONC	-	-	-	-	-	-	-
12+12	3	RT	CONC	-	-	-	-	-	-	-
12+48	4	LT	CONC	-	-	-	-	-	-	-
13+11	5	LT	CONC	-	-	-	-	-	-	-
13+14	6	RT	CONC	-	-	-	-	-	-	-
13+61	7	RT	CONC	-	-	-	-	-	-	-
14+17	8	RT	CONC	-	-	-	-	-	-	-
14+71	9	LT	CONC	-	-	-	-	-	-	-
15+05	10	LT	CONC	-	-	-	-	-	-	-
15+58	11	RT	CONC	-	-	-	-	-	-	-
16+12	12	RT	CONC	-	-	-	-	-	-	-
16+21	13	LT	CONC	-	-	-	-	-	-	-
17+68	14	LT	GRAVEL	-	-	-	-	-	-	-
17+89	15	RT	GRAVEL	-	-	-	-	-	-	-
18+11	16	RT	GRAVEL	-	-	-	-	-	-	-
18+31	17	LT	CONC	-	-	-	-	-	-	-
18+69	18	RT	GRAVEL	-	-	-	-	-	-	-
19+24	19	LT	CONC	-	-	-	-	-	-	-
20+02	20	RT	GRAVEL	-	-	-	-	-	-	-
20+86	21	RT	GRAVEL	-	-	-	-	-	-	-
21+78	22	RT	CONC	-	-	-	-	-	-	-
22+37	23	LT	CONC	-	-	-	-	-	-	-
22+64	24	RT	CONC	-	-	-	-	-	-	-
23+38	25	LT	CONC	-	-	-	-	-	-	-
23+74	26	RT	ASPH	-	-	-	-	-	-	-
26+12	27	LT	GRAVEL	12	3	4	-	-	-	1
27+13	28	LT	GRAVEL	26	3	9	-	-	-	1
27+67	29	LT	GRAVEL	25	3	8	-	-	-	1
31+24	30	LT	CONC	18	3	6	6	-	-	-
33+04	31	LT	GRAVEL	22	3	7	-	-	-	1
34+12	32	LT	GRAVEL	14	3	5	-	-	-	1
36+46	33	LT	GRAVEL	17	3	6	-	-	-	1
37+06	34	LT	GRAVEL	15	3	5	-	-	-	1
38+72	35	LT	GRAVEL	14	3	5	-	-	-	1
41+33	36	RT	GRAVEL	45	3	15	-	-	-	1
<b>SUB TOTAL:</b>							<b>129</b>	<b>0</b>	<b>0</b>	<b>10</b>

### FM 1008 QUANTITY SUMMARY

SHEET 3 OF 4



CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		19

DATE: 12/22/2023 7:12:36 PM  
 FILE: p:\t\dot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\Quantity\_Summaries.dgn


DWG: CKS: DW: CKS:

**DRIVEWAY & MB TURNOUT ITEMS (CONT.)**

STA	DESCRIPTION	LOCATION	MATERIAL	WIDTH	LENGTH	AREA (SY)	530			
							6004	6005	6008	6016
							DRIVEWAYS (CONC)	DRIVEWAYS (ACP)	TURNOUTS (ACP)	DRIVEWAYS (BASE)
	LT/RT		FT	FT		SY	SY	SY	CY	
42+62	37	LT	ASPH	46	3	15	-	15	-	-
48+90	38	LT	ASPH	28	3	9	-	9	-	-
51+94	39	LT	ASPH	30	3	10	-	10	-	-
65+62	40	LT	CONC	20	3	7	7	-	-	-
66+75	41	RT	GRAVEL	30	3	10	-	-	-	10
74+74	42	LT	CONC	26	3	9	9	-	-	-
76+79	43	LT	CONC	24	3	8	8	-	-	-
81+02	44	RT	GRAVEL	20	3	7	-	-	-	7
81+28	45	LT	GRAVEL	16	3	5	-	-	-	5
83+56	46	RT	GRAVEL	26	3	9	-	-	-	9
84+29	47	RT	GRAVEL	18	3	6	-	-	-	6
85+18	48	LT	GRAVEL	18	3	6	-	-	-	6
87+46	49	LT	CONC	32	3	11	11	11	-	-
88+56	50	LT	GRAVEL	34	3	11	-	-	-	11
89+31	51	LT	GRAVEL	20	3	7	-	-	-	7
93+55	52	LT	GRAVEL	16	3	5	-	-	-	5
93+55	53	RT	GRAVEL	22	3	7	-	-	-	7
96+41	54	LT	CONC	45	3	15	15	-	-	-
99+38	55	RT	GRAVEL	20	3	7	-	-	-	7
99+76	56 (MB TURNOUT)	RT	ASPH	10	35	39	-	-	39	-
99+99	57	RT	GRAVEL	16	3	5	-	-	-	5
100+77	58	LT	GRAVEL	22	3	7	-	-	-	7
105+25	59	RT	GRAVEL	12	3	4	-	-	-	4
110+54	60	LT	GRAVEL	35	3	12	-	-	-	12
119+88	61	RT	GRAVEL	36	3	12	-	-	-	12
120+87	62	RT	GRAVEL	18	3	6	-	-	-	6
122+06	63	LT	ASPH	18	3	6	-	6	-	-
126+15	64	LT	GRAVEL	15	3	5	-	-	-	5
127+43	65	RT	CONC	52	3	17	17	-	-	-
128+38	66	LT	GRAVEL	56	3	19	-	-	-	19
131+44	67	LT	GRAVEL	18	3	6	-	-	-	6
132+95	68	RT	CONC	28	3	9	9	-	-	-
134+74	69	RT	CONC	28	3	9	9	-	-	-
136+56	70	RT	GRAVEL	12	3	4	-	-	-	4
138+38	71	RT	ASPH	24	3	8	-	8	-	-
145+23	72	RT	GRAVEL	18	3	6	-	-	-	6
147+27	73	RT	ASPH	20	3	7	-	7	-	-
152+81	74	LT	GRAVEL	40	3	13	-	-	-	13
153+83	75	RT	GRAVEL	28	3	9	-	-	-	9
<b>SUB TOTAL SHEET 3 OF 4:</b>							<b>129</b>	<b>0</b>	<b>0</b>	<b>10</b>
<b>SUB TOTAL:</b>							<b>85</b>	<b>66</b>	<b>39</b>	<b>188</b>
<b>TOTAL:</b>							<b>214</b>	<b>66</b>	<b>39</b>	<b>198</b>

**FM 1008**  
**QUANTITY SUMMARY**

SHEET 4 OF 4




CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		20

SEQUENCE OF WORK

1. MOBILIZE & INSTALL CONSTRUCTION BARRICADES AND SIGNS.
2. PERFORM FULL DEPTH BASE REPAIRS AT LOCATIONS SHOWN ELSEWHERE IN THE PLANS AND/OR DETERMINED BY THE ENGINEER.
3. MILL AND FILL EXISTING RUMBLE STRIPS (MUST BE DONE ON SAME DAY) NORTH OF CURB AND GUTTER SECTION.
4. MILL (1" AT CL & 2" AT GUTTER) AND FILL (3" AT CL & 2" AT GUTTER) WITH SP-C, IN CURB AND GUTTER SECTION ONLY. NOTE: MILL AND FILL SAME DAY OPERATION.
  - a. INSTALL CONSTRUCTION BARRICADES AND SIGNS FOR RIGHT LANE CLOSURE. PLACE EROSION CONTROL DEVICES AS DIRECTED. MAINTAIN THESE ITEMS THROUGHOUT THE PROJECT DURATION.
  - b. START MILLING OPERATIONS ALONG THE CENTERLINE OF THE ROADWAY, EFFECTIVELY REMOVING MATERIAL ONE LANE AT A TIME THEN FILLING IT BACK WITHIN THE SAME DAY.
    - i. CARE MUST BE TAKEN TO FOLLOW THE DESIRED MILLING DEPTHS, SHOWN ELSWHERE IN THE PLANS AS THE MILLING MACHINE MOVES ACROSS THE EXISTING CROSS SLOPE APPROACHING THE CURB AND GUTTER.
    - ii. THE MILL DEPTH VARIES FROM 1" OF DEPTH AT THE CENTERLINE TO 2" OF DEPTH AT THE GUTTER.
  - c. PERFORM A VARIABLE 3" TO 2" SP-C INLAY IMMEDIATELY FOLLOWING EACH LANE BEING MILLED OUT.
    - i. CARE MUST BE TAKEN TO FOLLOW THE DESIRED PAVING DEPTHS, SHOWN ELSWHERE IN THE PLANS AS THE PAVING MACHINE MOVES ACROSS THE EXISTING CROSS SLOPE APPROACHING THE CURB AND GUTTER.
    - ii. THE INTENT IS CREATE A SMOOTH TIE IN WITH THE SURFACE OF THE GUTTER.
    - iii. THE PAVING DEPTH VARIES FROM 3" DEEP AT THE CENTERLINE TO 2" DEEP AT THE GUTTER.
  - d. FOLLOWING THE REMOVAL OF THE EXISTING STRIPING INSTALL WORK ZONE TABS AS DIRECTED IN THE STANDARD. THE USE OF TEMPORARY STRIPING MAY BE NECESSARY TO PROVIDE ADEQUATE DELINEATION IF TIME EXTENDS BEYOND 14 DAYS.
5. INSTALL ONE COURSE SURFACE TREATMENT FULL WIDTH NORTH OF THE CURB AND GUTTER SECTION. TAPER SECTIONS FOR SMOOTH CONNECTIONS ARE INCLUDED HERE.
  - a. INSTALL WORK ZONE TABS AS DIRECTED IN THE STANDARD.
6. PERFORM UNIFORM 3" SP-C OVERLAY NORTH OF THE CURB AND GUTTER SECTION.
  - a. EFFECTIVELY CONVER ROADWAY TO ELIMINATE ANY DROPOFFS ALONG THE CENTERLINE OF FM 1008.
  - b. FOLLOWING THE REMOVAL OF THE EXISTING STRIPING INSTALL TEMPORARY STRIPING TO PROVIDE ADEQUATE DELINEATION AS DETAILED ELSEWHERE IN THE PLANS.
7. PERFORM INTERSECTION AND DRIVEWAYS IMPROVEMENTS IN ACCORDANCE WITH THE DRIVEWAY DETAILS GIVEN ELSEWHERE IN THE PLANS.
8. INSTALL PERMANENT PAVEMENT MARKINGS WITHIN 14 DAYS OF REMOVING THE CENTERSTIPE.
9. INSTALL SIGNS.
10. CLEAN SITE & REMOVE BARRICADES, SIGNS, AND SW3P ITEMS AFTER FINAL ACCEPTANCE

NOTES

1. NIGHT TIME WORK IS REQUIRED FOR PAVING PROCEDURES.
2. REFER TO THE GENERAL NOTES & PLAN SHEETS FOR ADDITIONAL DIRECTION.
3. THE SEQUENCE OF WORK MAY BE MODIFIED WITH THE ENGINEERS APPROVAL.



12/27/2023

*Jason D. Waldrep, P.E.*

SEQUENCE OF WORK

FM 1008



FHWA TEXAS DIVISION		SHEET NO. 21	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	LIBERTY	
CONTROL	SECTION	JOB	HIGHWAY NO.
0952	01	062	FM 1008

DATE: 12/22/2023 7:12:44 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/0922010624 - Design/Plan Set/1 - General/BC-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for any damages resulting from its use.

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b> <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS) "
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
<b>BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS</b>			
<b>BC (1) - 21</b>			
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT: 0952	SECT: 01	JOB: 062
REVISIONS	DIST: COUNTY		HIGHWAY: FM 1008
4-03 7-13			
9-07 8-14			
5-10 5-21	BMT	LIBERTY	SHEET NO. 22


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard or for any damages resulting from its use.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - Contractor will install a regulatory speed limit sign at the end of the work zone.

**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	LIBERTY	23	






DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/22/2023 7:12:45 PM  
 FILE: pw://tcdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/bc-21.dgn


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

**Nails shall NOT be allowed.**  
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTC list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTC) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short, duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTC lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTC list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12


Texas Department of Transportation  
 Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**



FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	LIBERTY	25	

DATE: 12/22/2023 7:12:46 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/0952010624 - Design/Plan Set/...  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




### SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS





### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



### SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



### WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

### GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."  
 \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.  
 See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



## BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS	0952	01	062	FM	1008				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	LIBERTY	26					

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

### Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number




## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		0952	01	062	FM 1008				
9-07	8-14	DIST:	COUNTY:	SHEET NO.:					
7-13	5-21	BMT	LIBERTY	27					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/22/2023 7:12:47 PM  
 FILE: pw://txdot.projectwiseonline.com: BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**  
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**  
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0952	01	062	FM 1008				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	BMT	LIBERTY		28				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/22/2023 7:12:47 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/bc-21.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**




- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
  - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
  - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
  - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
  - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
  - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
  - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
  - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
  - Drum body shall have a maximum unballasted weight of 11 lbs.
  - Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0952	01	062	FM 1008				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	BMT	LIBERTY	29					
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/22/2023 7:12:47 PM  
 FILE: pw://txdot.projectwiseonline.com: BMT/Design Projects/095201062/4 - Design/Plan Set/L. General/bc-21.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**

Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\* \* \* Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	LIBERTY	30	

DATE: 12/22/2023 7:12:48 PM  
 FILE: \\txdot.projectwiseonline.com\BMT\Design Projects\095201062\4 - Design\Plan Set\1 - General\bc-21.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	LIBERTY	31	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	LIBERTY	32	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/22/2023 7:12:48 PM  
 FILE: pw://twdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1 - General/bc-21.dgn



## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.






RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



### SOLID LINES




### BROKEN LINES



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	BMT	LIBERTY	33	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 12/22/2023 7:12:48 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/Plan Set/1.dgn



DATE: 12/22/2023 7:12:59 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\09222008\20a\09222008.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in the drawings or for any damages or injuries resulting from its use.



TCP (2-4a)  
**ONE LANE CLOSED**



TCP (2-4b)  
**TWO LANES CLOSED**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

**TCP (2-4a)**

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.


**TCP (2-4b)**

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.


		Traffic Operations Division Standard	
<b>TRAFFIC CONTROL PLAN          LANE CLOSURES ON MULTILANE          CONVENTIONAL ROADS</b>			
<b>TCP (2-4) - 18</b>			
FILE: tcp2-4-18.dgn	DWG:	CHK:	DWG:
© TxDOT December 1985	CONT	SECT	JOB
REVISIONS	0952 01	062	FM 1008
8-95 3-03	DIST	COUNTY	SHEET NO.
1-97 2-12	BMT	LIBERTY	35
4-98 2-18			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions resulting from its use.


DATE: 12/22/2023 7:13:05 PM  
 FILE: p:\t\tdot\project\wiseon\line.com\TXDOT15\Documents\20 - BMT\Design Projects\2023\122223\122223.dgn




**TCP (3-1a)**  
**UNDIVIDED MULTILANE ROADWAY**




**TCP (3-1b)**  
**TWO-WAY ROADWAY WITH PAVED SHOULDERS**



**TCP (3-1c)**  
**TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS**



**TRAIL/SHADOW VEHICLE A**  
with RIGHT Directional display Flashing Arrow Board




**TRAIL/SHADOW VEHICLE B**  
with Flashing Arrow Board in CAUTION display

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



**STRIPING FOR TMA**









Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS**  
**UNDIVIDED HIGHWAYS**

**TCP (3-1) - 13**

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	LIBERTY	36	
1-97				

DATE: 12/22/2023 7:13:09 PM  
 FILE: \\txdot.projectwiseonline.com:TXDOT15\Documents\20 - BMT\Design Projects\09230027\09230027.dgn  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information provided.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
Heavy Work Vehicle		LEFT Directional
Truck Mounted Attenuator (TMA)		Double Arrow
Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

**GENERAL NOTES**

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.


Texas Department of Transportation

Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS**  
**RAISED PAVEMENT**  
**MARKER INSTALLATION/REMOVAL**  
**TCP (3-3) - 14**

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 7-13	BMT	LIBERTY	37	
1-97 7-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project.



TCP (SC-1a)  
ONE LANE TWO-WAY (TWO LANES)  
CONTROL WITH PILOT VEHICLE



TCP (SC-1b)  
ONE LANE TWO-WAY (THREE LANES)  
CONTROL WITH PILOT VEHICLE  
AND CHANNELIZING DEVICES

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths * * *			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing Distance "x"	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L = Length of Taper (FT) W = Width of Offset (FT) S = Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except: if project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
- Sign spacing may be increased or an additional ROAD WORK AHEAD (CW20-1D) sign may be used if advance warning ahead of the flagger sign is less than 1500 feet.
- Flaggers should use two-way radios or other methods of communication at all times for traffic control coordination.
- Flaggers should use 24" STOP (CW20-8) / SLOW (CW20-8aT) paddles to control traffic. Flags should be limited to emergency situations.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- If the seal coat operation crosses intersections, traffic in these areas must be controlled. Care must be taken to prevent vehicles from crossing the asphalt before the aggregate is placed. This may require positioning additional traffic control personnel (flaggers) at the intersection.
- Temporary rumble strips are not required on seal coat operations.
- The pilot car is used to guide vehicles through traffic control zone. The pilot car shall have an identification name displayed and PILOT CAR, FOLLOW ME (G20-4) sign or message board mounted in a conspicuous position on rear.

TCP (SC-1a)

- Channelizing devices on the centerline are not required when a pilot car is leading traffic, unless directed by the Engineer.

SHEET 1 OF 8

		Traffic Safety Division Standard	
<b>TRAFFIC CONTROL PLAN SEAL COAT OPERATIONS ONE-LANE TWO-WAY</b>			
<b>TCP (SC-1) - 22</b>			
FILE: tcpsc-1-22.dgn	DW: CK:	CK:	CK:
© TxDOT October 2022	CONT SECT	JOB	HIGHWAY
REVISIONS	0952 01	062	FM 1008
4-21 10-22	DIST	COUNTY	SHEET NO.
	BMT	LIBERTY	38


END ROAD WORK  
G20-2  
48" X 24" min.  
(See note 2)

END ROAD WORK  
G20-2  
48" X 24" min.  
(See note 2)


END ROAD WORK  
G20-2  
48" X 24" min.  
(See note 2)

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions resulting from its use.


**WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS (TABS)**




**CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS**



**LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS**




**LANE LINES FOR DIVIDED HIGHWAY**



**TWO-WAY LEFT TURN LANE**

**TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS**



**TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS**

1. Temporary markings for surfacing projects shall be Temporary Flexible-Reflective Roadway Marker Tabs with protective cover unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two days before the surfacing is applied. After the surfacing is rolled and swept, the protective cover over the reflective strip shall be removed.
2. Temporary Flexible-Reflective Roadway Marker Tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with a yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
3. Temporary Flexible-Reflective Roadway Marker Tabs will require normal maintenance replacement when used on roadways with an Average Daily Traffic (ADT) per lane of up to 7500 vehicles with no more than 10% truck mix. When roadway volumes exceed these values, additional maintenance replacement of these devices should be planned for.
4. When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
5. No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 4.
6. Tabs shall meet requirements of Departmental Material Specification DMS-8242.
7. Tabs shall NOT be used to simulate edge lines.

**NOTES:**

1. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
2. For exit gores where a lane is being dropped, place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are NOT acceptable.
3. Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.

**DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)**


1. DMSs referenced above may be found along with embedded links to their respective MPLs at the following website: <http://www.txdot.gov>

SHEET 7 OF 8

**WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS (TABS)**

SOLID LINES	DOUBLE NO-PASSING LINE	
	SINGLE NO-PASSING LINE or CHANNELIZATION LINE	
	8" WIDE SOLID LINE	
BROKEN LINES (FOR CENTER LINE OR LANE LINE)		
WIDE DOTTED LINES (FOR LANE DROP LINES)		
WIDE GORE MARKINGS		

**TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS**



Height of sheeting is usually more than 1/4" and less than 1".

Texas Department of Transportation

Traffic Safety Division Standard

**TEMPORARY PAVEMENT MARKINGS FOR SEAL COAT OPERATIONS**  
**TCP (SC-7) -22**




FILE: tcpsc-7-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
4-21	DIST	COUNTY	SHEET NO.	
10-22	BMT	LIBERTY	39	





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions resulting from its use.

DATE: 12/22/2023 7:13:27 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\092200082\092200082.dwg





**LEGEND**

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.**



**GENERAL NOTES**


- The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.
- Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- High level warning devices (flag trees) may be used at corners of the vehicle.
- When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P) signs may be implemented when approved by the engineer.
- For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.
- Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.

**TRAFFIC SIGNAL WORK TYPICAL DETAILS**

**WZ (BTS-1) - 13**

FILE: wzbts-13.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT: 0952	SECT: 01	JOB: 062	HIGHWAY: FM 1008
REVISIONS	DIST: BMT	COUNTY: LIBERTY	SHEET NO.: 41	
2-98 10-99 7-13				
4-98 3-03				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions resulting from its use.



**TYPICAL ADVANCE SIGNAL PROJECT SIGNING**  
FOR LONG TERM and INTERMEDIATE-TERM STATIONARY WORK OPERATIONS

- NOTES**
1. Project signing as shown shall be in place whenever signal contract work is in progress.
  2. For closely adjoining projects, advance signing may not be required in advance of each intersection, but only in advance of the intersections at the project limits. Actual locations will be as directed by the Engineer.
  3. Advance signs shall be removed when signal construction operations are no longer under way, as directed by the Engineer.
  4. Warning sign spacing shown is typical for both directions.
  5. See the Table on sheet 1 of 2 for Typical warning sign spacing.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Signs shall be installed and maintained in a straight and plumb condition.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. Nails shall NOT be used to attach signs to any support.
5. All signs shall be installed in accordance with the plans or as directed by the Engineer.
6. The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).
7. The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.
8. Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as directed by the Engineer.
9. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".
10. Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

**DURATION OF WORK**

1. Work zone durations are defined in Part 6, Section 66.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

**SIGN MOUNTING HEIGHT**

1. Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.
2. Sign height of Short-term/Short Duration warning signs shall be as shown on Figure 6F-2 of the TMUTCD.
3. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.
2. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs.
3. Duct tape or other adhesive material shall NOT be affixed to a sign face.
4. Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

**SIGN SUPPORT WEIGHTS**

1. Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber, such as tire inner tubes, shall not be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**LEGEND**


	Sign
	Channelizing Devices
	Type 3 Barricade

**DEPARTMENTAL MATERIAL SPECIFICATIONS**


SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
WHITE	BACKGROUND	TYPE A SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING


Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:  
[http://www.txdot.gov/txdot\\_library/publications/construction.htm](http://www.txdot.gov/txdot_library/publications/construction.htm)



**SIDEWALK DIVERSION**



**SIDEWALK DETOUR**



**CROSSWALK CLOSURES**

**PEDESTRIAN CONTROL**

1. Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.
2. "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation.
3. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic substrates, they may be mounted on top of a plastic drum at or near the location shown.
4. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9) and manufacturer's recommendations.
5. Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.
6. Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.
7. The width of existing sidewalk should be maintained if practical.
8. Pavement markings for mid-block crosswalks shall be paid for under the appropriate bid items.
9. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.

SHEET 2 OF 2

Texas Department of Transportation Traffic Operations Division Standard

**TRAFFIC SIGNAL WORK BARRICADES AND SIGNS**


**WZ (BTS-2) - 13**

FILE: wzbts-13.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CRK: TxDOT
© TxDOT April 1992	CONT: 0952	SECT: 01	JOB: 062	HIGHWAY: FM 1008
2-98 10-99 7-13	DIST: BMT	COUNTY: LIBERTY	SHEET NO.: 42	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. The user of this standard is advised to verify the accuracy of the information contained herein. DATE: 2023/12/28 7:13:41 PM FILE: C:\DOCUMENTS\PROJECTS\wzrs22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



**RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION**



**RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY**

**GENERAL NOTES**

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS/60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT)  
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.  
 \* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation Traffic Safety Division Standard


## TEMPORARY RUMBLE STRIPS

### WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	BMT	LIBERTY	43	

DATE: 12/22/2023 7:13:37 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOTS/Projects/095201062/4 - Design/Plan Set1 - General Notes.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS




### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)




## WORK ZONE SHORT TERM PAVEMENT MARKINGS

### WZ(STPM)-23

FILE: wzsstpm-23.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2023	CONTRACT	SECTION	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
4-92 7-13	DIST	COUNTY	SHEET NO.	
1-97 2-23	BMT	LIBERTY	44	
3-03				



FILE: p:\p\dot\project\wiseonline.com\TXDOT\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\PMVT Edge Joint Detail.dgn  
 DATE: 12/22/2023 13:50:11 PM TXDOT\project\wiseonline.com\TXDOT\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\PMVT Edge Joint Detail.dgn




\*\* SEE LAYOUT SHEETS FOR DEPTH AND TYPE OF HMA.

NOTES:

LONGITUDINAL JOINTS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LAND WIDTH. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. TACK COAT SHALL BE APPLIED TO THE IN-PLACE TAPER BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED.

PAVEMENT EDGES SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL BE PLACED WITHIN THE NORMAL LANE WIDTH UNLESS OTHERWISE SHOWN ON THE PLANS. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. COMPACTION OF THE PAVEMENT EDGE TAPER WILL BE REQUIRED TO AS NEAR TO FINAL DENSITY AS POSSIBLE.



Jason D. Waldrep, P.E.

12/27/2023


PAVEMENT EDGE JOINT DETAILS

FM 1008



FHWA TEXAS DIVISION		SHEET NO. 46	
STATE	DISTRICT	COUNTY	
TEXAS	BMT	LIBERTY	
CONTROL	SECTION	JOB	HIGHWAY NO.
0952	01	062	FM 1008



DATE: 12/22/2023 7:13:56 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/3. Roadway/Roadway\_LAYOUT.dgn



NOTE: A hot-mix cold laid "wedge" must be placed at all locations where the surface is milled and not in laid the same day between the night time hours of 7pm to 5am, prior to being open to traffic. Wedge must be a minimum of five (5) feet in length. This work is to be considered subsidiary to various bid items.

**LEGEND**

	SIGN
	DRIVEWAY
	BASE REPAIR
	6" WSLD
	6" YSLD
	6" WBRK
	8" WSLD
	24" WSLD
	OVERHEAD ELECTRIC
	6" WHITE SOLID
	6" YELLOW SOLID
	6" WHITE BROKEN
	8" WHITE SOLID
	24" WHITE SOLID



NOTE: 100' TAPER MILLING FOR TRANSITION, STA 24+71 - 25+71



**ROADWAY LAYOUT**  
SHEET 1 OF 6

Jason D. Waldrep, P.E.  
 12/27/2023

N. T. S.

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		47

DATE: 12/22/2023 7:13:56 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - BMT\Design\Plan Set\3. Roadway\ROADWAY\_LAYOUT.dgn



**LEGEND**

	SIGN
	DRIVEWAY
	BASE REPAIR
6" WSLD	6" WHITE SOLID
6" YSLD	6" YELLOW SOLID
6" WBRK	6" WHITE BROKEN
8" WSLD	8" WHITE SOLID
24" WSLD	24" WHITE SOLID
-OE- OE-	OVERHEAD ELECTRIC

**ROADWAY LAYOUT**  
 SHEET 2 OF 6


Jason D. Waldrep, P.E.  
 12/27/2023

N. T. S.  
 Texas Department of Transportation

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		48




DATE: 12/22/2023 7:13:57 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3 - Roadway\ROADWAY\_LAYOUT.dgn




**LEGEND**

	SIGN
	DRIVEWAY
	BASE REPAIR
6" WSLD	6" WHITE SOLID
6" YSLD	6" YELLOW SOLID
6" WBRK	6" WHITE BROKEN
8" WSLD	8" WHITE SOLID
24" WSLD	24" WHITE SOLID
-OE- OE-	OVERHEAD ELECTRIC



ROADWAY LAYOUT  
 SHEET 3 OF 6




Jason D. Waldrep, P.E.

12/27/2023



CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		49


DATE: 12/22/2023 7:13:57 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - BMT\Design\Plan Set\3. Roadway\ROADWAY\_LAYOUT.dgn



NOTE: 100' TAPER MILLING FOR TRANSITION, STA 96+36 - STA 97+36 & STA 98+56 - STA 99+56 (120' BRIDGE: STRIPING ONLY)


**LEGEND**

	SIGN
	DRIVEWAY
	BASE REPAIR
6" WSLD	6" WHITE SOLID
6" YSLD	6" YELLOW SOLID
6" WBRK	6" WHITE BROKEN
8" WSLD	8" WHITE SOLID
24" WSLD	24" WHITE SOLID
-OE- -OE-	OVERHEAD ELECTRIC



ROADWAY LAYOUT

SHEET 4 OF 6



Jason D. Waldrep, P.E.


12/27/2023



N. T. S.

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY	SHEET NO.	
BMT	LIBERTY	50	


DATE: 12/22/2023 7:13:57 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT5\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\ROADWAY\_LAYOUT.dgn



NOTE: 100' TAPER MILLING FOR TRANSITION, STA 117+31 - STA 118+31 & STA 119+21 - STA 120+21 - 100' (90' BRIDGE: STRIPING ONLY)


**LEGEND**

	SIGN
	DRIVEWAY
	BASE REPAIR
6" WSLD	6" WHITE SOLID
6" YSLD	6" YELLOW SOLID
6" WBRK	6" WHITE BROKEN
8" WSLD	8" WHITE SOLID
24" WSLD	24" WHITE SOLID
-OE-OE-	OVERHEAD ELECTRIC



ROADWAY LAYOUT

SHEET 5 OF 6




Jason D. Waldrep, P.E.

12/27/2023




CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		51

DATE: 12/22/2023 7:13:58 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\ROADWAY\_LAYOUT.dgn



**LEGEND**


	SIGN
	DRIVEWAY
	BASE REPAIR
6" WSLD	6" WHITE SOLID
6" YSLD	6" YELLOW SOLID
6" WBRK	6" WHITE BROKEN
8" WSLD	8" WHITE SOLID
24" WSLD	24" WHITE SOLID
-OE- -OE-	OVERHEAD ELECTRIC



**ROADWAY LAYOUT**

SHEET 6 OF 6

NOTE: 100' TAPER MILLING FOR TRANSITION, STA 155+32 - STA 156+32



Jason D. Waldrep, P.E.


12/27/2023




N. T. S.

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		52

DNE:   
 CK:   
 DW:   
 CK:



**INTERSECTING ROADWAY CLEARING**



**CURVED ROADWAY CLEARING**



**NOTES:**

1. ALL TREE LIMBS EXTENDING INTO THE CLEARING LIMITS WILL BE REMOVED TO A MINIMUM HEIGHT OF SIXTEEN FEET (16') ABOVE THE ADJACENT PAVEMENT EDGE ELEVATION.
2. CLEARING OPERATIONS SHALL BE PERFORMED IN ACCORDANCE WITH ITEM 100, "PREPARING THE RIGHT OF WAY", EXCEPT THOSE SHOWN BY THESE DETAILS.



*Jason D. Waldrep, P.E.*

01/02/2024



**CLEARING  
DETAIL**




FMBA TEXAS DIVISION			SHEET NO. 53
STATE	DISTRICT	COUNTY	
TEXAS	20	BMT	
CONTROL	SECTION	JOB	HIGHWAY NO.
0952	01	062	FM 1008

NTS


DATE: 12/22/2023 7:14:02 PM  
 FILE: p:\t\tdot\project\wiseonline.com\TXDOT15\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\DRIVEWAY Summary Detail.dgn



**NOTE:**  
 FOR MORE DETAILS SEE \*\*DRIVEWAY & INTERSECTION ITEMS SUMMARY.

12/27/2023  
  
*Jason D. Waldrep, P.E.*  
**FM 1008  
 DRIVEWAY &  
 PUBLIC ROAD  
 SUMMARY AND  
 DETAILS**


**NTS**



CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		54


DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/27/2023  
 FILE: pwt://txdot.projectwiseonline.com: TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/3. Roadway/mbtrnout.dgn



**PLAN**

12/27/2023





*Jason D. Waldrep, P.E.*

**DESIGN DETAILS FOR  
 TYPICAL MAILBOX TURNOUTS  
 MBTRNOUT**


FILE: mbtrnout.dgn	DNR TxDOT	CHK:	DWG:	CK:
© TxDOT 1989	CONT SECT	JOB	HIGHWAY	
REVISIONS	0952 01	062	FM 1008	
	DIST	COUNTY	SHEET NO.	
	BMT	LIBERTY	55	

DATE: 12/22/2023 7:14:16 PM  
 FILE: pw://twdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/3. Roadway/STRIPING SIGNS.dgn



**LEGEND**

	SIGN
	MANHOLE
6WS	6" WHITE SOLID
6WB	6" WHITE BROKEN
6DYS	6" DOUBLE YELLOW SOLID
8WSLD	8" WHITE SOLID
8WBKN	8" WHITE BROKEN
24WS	24" WHITE STOP BAR



12/27/2023  
 Jason D. Waldrep, P.E.

**FM 1008  
 PAVEMENT MARKINGS  
 & SIGNING**



SHEET 1 OF 3

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		56

N. T. S.




DATE: 12/22/2023 7:14:17 PM  
 FILE: pw://ttdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/3. Roadway/STRIPING SIGNS.dgn



**LEGEND**


	DELINEATOR
	SIGN
6WS	6" WHITE SOLID
6WB	6" WHITE BROKEN
6DYS	6" DOUBLE YELLOW SOLID
8WSLD	8" WHITE SOLID
8WBKN	8" WHITE BROKEN
24WS	24" WHITE STOP BAR



12/27/2023  
 Jason D. Waldrep, P.E.

**FM 1008  
 PAVEMENT MARKINGS  
 & SIGNING**


SHEET 2 OF 3



CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY		SHEET NO.
BMT	LIBERTY		57


NOTE: ALL SIGNS SHALL BE REPLACED AT EXISTING LOCATIONS WITH MATCHING SIGNAGE.

N. T. S.



LEGEND

	SIGN
6WS	6" WHITE SOLID
6WB	6" WHITE BROKEN
6DYS	6" DOUBLE YELLOW SOLID
8WSLD	8" WHITE SOLID
8WBKN	8" WHITE BROKEN
24WS	24" WHITE STOP BAR




*Jason D. Waldrep, P.E.*

12/27/2023

**FM 1008  
 PAVEMENT MARKINGS  
 & SIGNING**

SHEET 3 OF 3




CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY	SHEET NO.	
BMT	LIBERTY	58	


N. T. S.




FILE: pw:\txdot\projectwiseonline.com\TXDOT5\Documents\20 - BMT\Design Projects\095201062\4 - Design\Plan Set\3. Roadway\SmallSignDetails.dgn  
 DATE: 12/28/2023 04:51 AM




D1-1 8in UP;  
 1.5" Radius, 0.5" Border, White on Green;  
 Standard Arrow Custom 10.0" X 7.1" 90°; "Kenefick", ClearviewHwy-3-W;



I-3 5in;  
 1.5" Radius, 0.5" Border, White on Green;  
 "Linney", ClearviewHwy-3-W;  
 "Creek", ClearviewHwy-3-W;



I-3 5in;  
 1.5" Radius, 0.5" Border, White on Green;  
 "French", ClearviewHwy-3-W;  
 "Creek", ClearviewHwy-3-W;



*Jason D. Waldrep, P.E.*

01/02/2024

**FM 1008  
 SMALL SIGN  
 DETAIL**

NTS



FHWA TEXAS DIVISION		FEDERAL AID PROJECT NO.		SHEET NO.
				60
STATE	DISTRICT	COUNTY		
TEXAS	BMT	LIBERTY		
CONTROL	SECTION	JOB	HIGHWAY NO.	
0952	01	062	062	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/22/2023 7:14:21 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/sgnngen.dgn

## SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

**Post Type**

FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))  
 TWT = Thin-Walled Tubing (see SMD(TWT))  
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))  
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

**Number of Posts (1 or 2)**


**Anchor Type**

UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))  
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))  
 WS = Wedge Anchor Steel - (see SMD(TWT))  
 WP = Wedge Anchor Plastic (see SMD(TWT))  
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))  
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

**Sign Mounting Designation**

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))  
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))  
 IF REQUIRED  
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))  
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))  
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


## REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


## SIGN LOCATION

### PAVED SHOULDERS



#### LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



#### GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft. in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

### T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




### BEHIND BARRIER




#### BEHIND GUARDRAIL

\*\*Sign clearance based on distance required for proper guard rail or concrete barrier performance.



#### BEHIND CONCRETE BARRIER

## TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

### SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

### CURB & GUTTER OR RAISED ISLAND



### RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

\*\*\* Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.


Texas Department of Transportation  
Traffic Operations Division

## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD (GEN) - 08

© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0952	01	062	FM 1008
		DIST	COUNTY		SHEET NO.
		BMT	LIBERTY		61

# TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



## NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. [http://www.txdot.gov/business/producer\\_list.htm](http://www.txdot.gov/business/producer_list.htm) The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

## GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
  - 10 BWG Tubing (2.875" outside diameter)
    - 0.134" nominal wall thickness
    - Seamless or electric-resistance welded steel tubing or pipe
    - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
    - Other steels may be used if they meet the following:
      - 55,000 PSI minimum yield strength
      - 70,000 PSI minimum tensile strength
      - 20% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
    - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
    - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
  - Schedule 80 Pipe (2.875" outside diameter)
    - 0.276" nominal wall thickness
    - Steel tubing per ASTM A500 Gr C
    - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
      - 46,000 PSI minimum yield strength
      - 62,000 PSI minimum tensile strength
      - 21% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
    - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
    - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

## ASSEMBLY PROCEDURE


### Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

### Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

## CONCRETE ANCHOR



5/8" diameter Concrete Anchor - 8 places (embed a minimum of 5 1/2" and torque to min. of 50 ft-lbs). Anchor may be expansion or adhesive type.

SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/22/2023 7:14:25 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/smsd1.dgn

















## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS		CONT	SECT	JOB
			0952	01	062
			DIST	COUNTY	HIGHWAY
		BMT	LIBERTY		FM 1008
					SHEET NO.
					62

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/22/2023 7:14:29 PM  
 FILE: pw://tcdot.projectwiseonline.com:TXDOT5/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/smds2.dgn



All dimensions are in english unless detailed otherwise.

SM RD SGN ASSM TY XXXXX(1)XX(T) (\* - See Note 12)

GENERAL NOTES:

1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA
 

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
12. Post open ends shall be fitted with Friction Caps.
13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT	
SIGN DESCRIPTION	SUPPORT
48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T)
	TY 10BWG(1)XX(P-BM)
60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T)
	TY 10BWG(1)XX(P-BM)
48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T)
48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(P-BM)
36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
48x60-inch signs	TY S80(1)XX(T)
48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
48x60-inch signs	TY S80(1)XX(T)
48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.













SIGN MOUNTING DETAILS  
 SMALL ROADSIDE SIGNS  
 TRIANGULAR SLIPBASE SYSTEM  
 SMD(SLIP-2)-08

© TxDOT July 2002	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CON: 0952	SECT: 01	JOB: 062
		DIST: BMT	COUNTY: LIBERTY	HIGHWAY: FM 1008
				SHEET NO.: 63

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/22/2023 7:14:33 PM  
 FILE: pw://ttdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/1. General/sms3.dgn



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG       | 1          | 16 SF          |
| 10 BWG       | 2          | 32 SF          |
| Sch 80       | 1          | 32 SF          |
| Sch 80       | 2          | 64 SF          |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)



**SIGN MOUNTING DETAILS  
 SMALL ROADSIDE SIGNS  
 TRIANGULAR SLIPBASE SYSTEM  
 SMD(SLIP-3) - 08**

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0952	01	062	FM 1008
		DIST	COUNTY		SHEET NO.
		BMT	LIBERTY		64






DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for the accuracy of the information contained herein.

### REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

### REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR WARNING SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR SCHOOL SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

### GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

#### ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

#### DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS

### TSR(4) - 13


FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0952	01	062	FM 1008				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		BMT	LIBERTY	66					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions that may appear in this standard.

DATE: 12/22/2023 7:14:46 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/0922000223/0922000223.dgn

### ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	

CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT


**NOTE**

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.


<http://www.txdot.gov/>

### SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5



EXIT ONLY PANEL


### MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

**NOTE:**

- Sheeting for legend, symbols, and borders must be cut at panel joints.
- Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".



SCREW ATTACHMENT




NUT/BOLT ATTACHMENT


**NOTE:**

Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

### ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.



## TYPICAL SIGN REQUIREMENTS


### TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	BMT	LIBERTY	67	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information presented herein. TxDOT reserves the right to change the information presented herein without notice.


DATE: 12/22/2023 7:14:50 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/09220004/20a changes for 09220004.dgn

**CROSSOVERS**




**DETAIL 1**

**FOR CULVERTS WITHOUT MBGF**




**DETAIL 2**

**FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES**




**DETAIL 3**

**TYPICAL APPLICATION OF DEAD END BARRICADE**



**DETAIL 4**

**TYPICAL DEAD END BARRICADE INSTALLATION**



**NOTES**

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

**DETAIL 5**

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator




**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(4) -20**

FILE: dom4-20.dgn	DN: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
3-15	DIST	COUNTY	SHEET NO.	
7-20	BMT	LIBERTY	68	


**TWO-WAY, TWO LANE ROADWAY  
WITH REDUCED WIDTH APPROACH RAIL**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY  
WITH METAL BEAM GUARD FENCE (MBGF)**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY  
BRIDGE WITH NO APPROACH RAIL**



**LEGEND**

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &  
OBJECT MARKER  
PLACEMENT DETAILS**

**D & OM(5)-20**


FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0952	01	062	FM 1008
7-20	DIST	COUNTY	SHEET NO.	
	BMT	LIBERTY	69	

DATE: 12/22/2023 7:14:54 PM  
 FILE: //txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/0952/01/062/FM 1008/0952-01-062-FM 1008.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard. TxDOT reserves the right to change this standard without notice.




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions in this standard.

DATE: 12/22/2023 7:15:02 PM  
 FILE: p:\t\dot\project\wiseon\line.com\TXDOT15\Documents\20 - BMT\Design Projects\09220002\20a\09220002.dgn



**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**


- GENERAL NOTES**
- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
  - The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




\* 2" minimum for restripe projects when approved by the Engineer.  
 \*\* 8" minimum for restripe projects when approved by the Engineer.




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




\* 2" minimum for restripe projects when approved by the Engineer.



**YIELD LINES**



For posted speed on road being marked equal to or less than 40 MPH.




NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**  
 Based on Traveled Way and Pavement Widths for Undivided Roadways

**NOTES**

- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.



**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

Texas Department of Transportation  
 Traffic Safety Division Standard

**TYPICAL STANDARD  
PAVEMENT MARKINGS**

**PM(1) - 22**

FILE:	pml-22.dgn	DN:	CK:	DW:	CK:
© TxDOT	December 2022	CONT	SECT	JOB	HIGHWAY
11-78	8-00 6-20	0952	01	062	FM 1008
8-95	3-03 12-22	DIST	COUNTY	SHEET NO.	
5-00	2-12	BMT	LIBERTY	71	


22A





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or for any errors or omissions that may appear hereon.

DATE: 12/22/2023 7:15:10 PM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/0925000222/0925000222.dgn



**LANE REDUCTION**

**NOTES**

- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.


ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	$L = \frac{WS^2}{60}$
35 MPH	565	
40 MPH	670	
45 MPH	775	L=WS
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

**GENERAL NOTES**


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




**TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE**




A two-way left-turn (TWLTL) lane-use arrow pavement marking should be used at or just downstream from the beginning of a two-way left-turn lane within a corridor. Repeating the marking after each intersection or dedicated turn bay is not required unless stated elsewhere in the plans.


**TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY**



**TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP**



**TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS**



**DETAIL A**

**DETAIL B**

Texas Department of Transportation  
 Traffic Safety Division Standard

**TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 22**

FILE: pm3-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
4-98	0952	01	062	FM 1008
5-00			COUNTY	SHEET NO.
8-00	BMT		LIBERTY	73

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**

0952-01-062

**1.2 PROJECT LIMITS:**

From: ARNOLD DRIVE, SOUTH

To: SH 321

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 30.0785549, (Long) -94.8679353

END: (Lat) 30.0464515, (Long) -94.8916703

**1.4 TOTAL PROJECT AREA (Acres):** \_\_\_\_\_

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** <1 ACRE

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

BASE REPAIR AND OVERLAY

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
COMPACT SAND/DIRT MAKEUP	A COMBINATION OF CLAY AND SAND

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: \_\_\_\_\_

Other: \_\_\_\_\_

Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Other: \_\_\_\_\_

Other: \_\_\_\_\_

Other: \_\_\_\_\_

Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody

\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations

Other: \_\_\_\_\_

Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs

Other: \_\_\_\_\_

Other: \_\_\_\_\_

**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (More Than 1 Acre)**



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
	F 2024(810)			74
STATE	STATE DIST.	COUNTY		
TEXAS	BMT	LIBERTY		
CONT.	SECT.	JOB	HIGHWAY NO.	
0952	01	062	FM 1008	

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

**2.9 MAINTENANCE:**


Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (More Than 1 Acre)**




FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
	F 2024(810)		75
STATE	STATE DIST.	COUNTY	
TEXAS	BMT	LIBERTY	
CONT.	SECT.	JOB	HIGHWAY NO.
0952	01	062	FM 1008

DATE: 12/22/2023 7:15:22 PM  
 FILE: cwt://txdot.projectwiseonline.com:TXDOT15/Documents/20 - BMT/Design Projects/095201062/4 - Design/Plan Set/3 - Roadway/Inlet Protection.dgn




**SILT FENCE DETAIL**


GALVANIZED WELDED WIRE MESH (W.W.M.)  
 (12.5 GA. SWG MIN.) WITH A MAXIMUM  
 OPENING SIZE OF 2" X 4" OR WOVEN MESH  
 (W.M.)



**SILT FENCE PLAN**



**ANCHORAGE DETAIL**




**ANCHORAGE PLAN**


12/27/2023

**NOTES:**


- REMOVE SECTION OF FILTER FABRIC AS SHOWN OR AS DIRECTED, FASTEN FABRIC TO EXPOSED WIRE WITH HOG RINGS OR CORD AT A MAXIMUM SPACING OF 15".
- PLACE SANDBAGS AS SHOWN AT A MAXIMUM OF 3' ON CENTER BOTH IN THE GUTTER AND ON THE INLET. SUBMIT ALTERNATIVE ANCHORING METHODS FOR APPROVAL PRIOR TO INSTALLATION.
- INSPECT INLETS DAILY. REMOVE ACCUMULATED SEDIMENT 2" OR MORE DEEP. REPAIR OR REPLACE DAMAGED INLET PROTECTION AS NECESSARY.



**SANDBAG DETAIL**



**SECTION B-B**



*Jason D. Waldrep, P.E.*

**INLET PROTECTION  
SILT FENCE**

CONT	SECT	JOB	HIGHWAY
0952	01	062	FM 1008
DIST	COUNTY	SHEET NO.	
BMT	LIBERTY	76	