

# STATE OF TEXAS

## DEPARTMENT OF TRANSPORTATION


### MATERIALS MAINTENANCE CONTRACT


PROJECT NO. MMC 6464-45-001  
 CSJ: 6464-45-001  
 HIGHWAY: IH0030, ETC.  
 LIMITS OF WORK: Various Locations within South Tarrant County

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY  
 DESCRIPTION: Dense Grade Hot Mix

RECOMMENDED FOR LETTING: 2/20/2024  
 Date

RECOMMENDED FOR LETTING: 2/22/2024  
 Date

DocuSigned by:  
  
 E0D25AC6252D429...  
 AREA ENGINEER

DocuSigned by:  
  
 4848DA2AA1AB440...  
 MAINTENANCE ENGINEER


RECOMMENDED FOR LETTING: 2/22/2024  
 Date

DocuSigned by:  
  
 1FD8BDF41B5F486...  
 DIRECTOR OF MAINTENANCE

#### INDEX OF SHEETS

- 1 TITLE SHEET
- 2A-C GENERAL NOTES
- 3 ESTIMATE & QUANTITY SHEET
- 4 DELIVERY SITES SHEET

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2023		 Texas Department of Transportation	
FED.RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	6464-45-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HWY NO.
6464	45	001	IH0030, ETC.
FILENAME			DATE
MMC 6464-45-001			4/19/2022

**Project Number:** MMC-6464-45-001

**Control:** 6464-45-001

**County:** Tarrant County

**Highway:** IH0030, Etc.

**GENERAL NOTES:**

**General:**

This purpose of this contract is to supply **Dense Graded Hot Mix Asphalt and Asphaltic Concrete Patching Material** at the following locations:

Site 1	Various Locations within South Tarrant County
--------	---

This contract includes an item for pickup. Materials shall be available for pickup within 75 miles of the TxDOT office located at 2540 Edgecliff Road, Fort Worth, TX 76133. Load material into TxDOT equipment at time of pickup.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through the Maintenance Section Supervisor or Representative:

<b>South Tarrant County</b>
2540 Edgecliff Road Fort Worth, TX 76133 (940) 327-9458

Bids will be received at 2501 Southwest Loop 820, Fort Worth, TX 76133.

Contractor questions on this project are to be emailed to the following individuals:

**Area Engineer:** Maribel Rangel  
**Project Manager:** Bobby Sullivan

Maribel.Rangel@txdot.gov  
Bobby.Sullivan@txdot.gov

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

**Project Number:** MMC-6464-45-001

**Control:** 6464-45-001

**County:** Tarrant County

**Highway:** IH0030, Etc.

**Section 10.2 - Instructions to Bidders:**

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

**Section 10.4 – Scope of Work:**

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended twice, not to exceed 540 calendar days for the entire contract term if mutually agreed.

**Section 10.8 - Prosecution and Progress:**

There are 180 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Types of accepted haul vehicles include End Dumps.

Each Work Order will have **no less than 7 calendar days to begin material delivery** or to make material available for pick-up, as described in the Work Order in accordance with Article 10.8.3., "Work Orders".

Each Work Order will specify a delivery site by the bid item in the contract and quantity to be supplied.

Unless otherwise directed, prosecute the work continuously to completion of the Work Order.

**Item 8011 – Dense-Graded Hot Mix Asphalt (Materials Only):**

No Blending, of the material to meet SAC A will be allowed.

Substitute binders are not allowed on this project.

RAP and RAS are not permitted in any surface and level-up mixes on this project

**Project Number:** MMC-6464-45-001

**Control:** 6464-45-001

**County:** Tarrant County

**Highway:** IH0030, Etc.

Furnish a mix design to the State's representative to be sent to the District Laboratory for verification testing.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Use only Department MPL approved asphalt release agents. Diesel and/or solvents in the production, transportation, and/or construction of the mix is prohibited.

No material shall be left in the haul vehicle overnight.

Canvas covers and insulating of the truck bodies will be required.

Contractor must have equipment and personnel to supply a minimum of 500 ton per day.

Include the approved mix design number on each delivery ticket.

**Item 8019 – Asphaltic Conc Patch Material (Materials Only):**

This item will be measured by the ton as defined in the plans and specifications. Delivery location will be listed in each Work Order.



