

# STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

## PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT


STATE PROJECT NUMBER  
C 152 -2 -71  
0152-02-071

NET LENGTH OF PROJECT = 290.4 FEET = 0.055 MILES  
ROADWAY = 290.4 FEET = 0.055 MILES  
BRIDGE = 0.00 FEET = 0.00 MILES

### CALDWELL COUNTY US 183

FROM: CEMETERY ST  
TO: CITY PARK RD

FOR THE CONSTRUCTION OF LANDSCAPE & SCENIC ENHANCEMENT  
CONSISTING OF LANDSCAPING & IRRIGATION



EXCEPTIONS: NONE  
EQUATIONS: NONE  
RAILROAD CROSSINGS: NONE



CONT	SECT	JOB	HIGHWAY
0152	02	071	US 183
DIST	COUNTY		SHEET NO.
AUS	CALDWELL		1

### DESIGN SPEED

MAIN LANES: N/A

A. D. T.

2023: N/A VPD  
2024: N/A VPD

### FINAL PLANS

DATE OF LETTING: \_\_\_\_\_

DATE WORK BEGAN: \_\_\_\_\_

DATE WORK COMPLETED AND ACCEPTED: \_\_\_\_\_

FINAL CONTRACT COST: \$ \_\_\_\_\_

CONTRACTOR: \_\_\_\_\_

LIST OF APPROVED CHANGE ORDERS:

I CERTIFY THAT THIS PROJECT  
WAS CONSTRUCTED IN SUBSTANTIAL  
COMPLIANCE WITH THE FINAL AS-BUILT  
PLANS AND SPECIFICATIONS.

\_\_\_\_\_  
P. E. DATE

RECOMMENDED FOR LETTING: 1/24/2024

DocuSigned by:  
*Susana Ceballos P.E.*  
E1816167B5C7414...  
DISTRICT DESIGN ENGINEER

APPROVED FOR LETTING: 1/25/2024

DocuSigned by:  
*Heather Kelly-Nguyen*  
DIRECTOR OF TRANSPORTATION  
PLANNING & DEVELOPMENT

SUBMITTED FOR LETTING: 1/24/2024

DocuSigned by:  
*Diana K. Schulzes P.E.*  
6775445255A3482...  
AREA ENGINEER

Registered Accessibility  
Specialist  
(RAS) Inspection Required



TDLR No. EABPRJ \_\_\_\_\_

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF  
TRANSPORTATION ON NOVEMBER 1, 2014 AND SPECIFICATION ITEMS  
LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT:  
SPECIAL LABOR PROVISIONS FOR STATE PROJECTS (000---008).


FILE: pw://twdot.projectwiseonline.com/TXD014/Documents/14 - AUS/Design Projects/015202071/4 - Design/Plan Set/1. General/US183\*GEN\*TITLE.dgn  
DATE: 1/24/2024 10:13:38 AM

DATE: 1/8/2024 3:03:30 PM  
FILE: D:\txdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\1. General\US183\_GEN\_INDEX.dgn


<b>GENERAL</b>		<b>TXDOT STANDARDS</b>	
1	TITLE SHEET	## 25	BC (1)-21 # 52 ED (1)-14
2	INDEX OF SHEETS	## 26	BC (2)-21 # 53 ED (3)-14
3, 3A-3J	GENERAL NOTES	## 27	BC (3)-21 # 54 ED (4)-14
4	ESTIMATE & QUANTITY	## 28	BC (4)-21 # 55 ED (5)-14
5	QUANTITY SUMMARY	## 29	BC (5)-21 # 56 ED (6)-14
6	ASSET MAINTENANCE	## 30	BC (6)-21 # 57 ED (7)-14
		## 31	BC (7)-21
		## 32	BC (8)-21
		## 33	BC (9)-21
		## 34	BC (10)-21
		## 35	BC (11)-21
		## 36	BC (12)-21
		## 37	TCP (1-1)-18
		## 38	TCP (1-5)-18
		## 39	TCP (3-5)-18
		## 40	TCP (5-1)-18
		## 41	TPD-19 (AUS)
		## 42	WZ (RS)-22
		## 43	CCCG-22
		## 44	PED-18 1 OF 4
		## 45	PED-18 2 OF 4
		## 46	PED-18 3 OF 4
		## 47	PED-18 4 OF 4
		## 48	EC (1)-16
		## 49	EC (9)-16 1 OF 3
		## 50	EC (9)-16 2 OF 3
		## 51	EC (9)-16 3 OF 3
<b>LANDSCAPE PLANS</b>			
7	DEMOLITION PLAN		
8	LAYOUT PLAN		
9	PAVEMENT LAYOUT PLAN		
10	PLANTING PLAN		
11	IRRIGATION PLAN		
12	LIGHTING PLAN		
<b>LANDSCAPE DETAILS</b>			
13-15	HARDSCAPE DETAILS		
16	PLANTING DETAILS		
17	PLANTING SPECIFICATIONS & QUANTITIES		
18-19	IRRIGATION DETAILS		
20	LANDSCAPE ESTABLISHMENT		
21	LIGHTING DETAILS		
<b>ENVIRONMENTAL ISSUES</b>			
22-23	STORMWATER POLLUTION PREVENTION PLAN (SWP3)		
24	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS		



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED SHOWN WITH A (##) HAVE BEEN SELECTED BY ME OR UNDER MY SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.


DocuSigned by:  
  
 640GCE004A5D45G...  
 MARK F. HERBER, P.E.      1/9/2024      DATE

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED SHOWN WITH A (#) HAVE BEEN SELECTED BY ME OR UNDER MY SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

DocuSigned by:  
  
 CE208F8BC5604A4...  
 GREG JONES, P.E.      1/9/2024      DATE

**Austin District  
Central Design**

---

 **Texas Department of Transportation**

---

INDEX OF SHEETS

© 2024	CONT	SECT	JOB	HIGHWAY
0152	02	071	US 183	
DIST	COUNTY		SHEET NO.	
AUS	CALDWELL		2	

The "POL" signifies to the Plans Online Office that this index sheet was created with the Excel workbook. Please do not delete.

**GENERAL NOTES: Version: January 4, 2024**

**GENERAL**

Contractor questions and requests for documents on this project are to be addressed to the following individual(s):

Bastrop Area [Diana.Schulze@txdot.gov](mailto:Diana.Schulze@txdot.gov)  
Bastrop Area [Tanli.Sun@txdot.gov](mailto:Tanli.Sun@txdot.gov)

Questions and requests for documents will be accepted via the Letting Pre-Bid Q&A web page. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved.

If work is performed at Contractor's option, when inclement weather is impending, and the work is damaged by subsequent precipitation, the Contractor is responsible for all costs associated with replacing the work, if required.

The roadbed will be free of organic material prior to placing any section of the pavement structure.

Contact the supervisor for the passenger facility at Capital Metro and request the relocation of Capital Metro signs. Contact the supervisor at (512) 385-0190.

Equip all construction equipment used in roadway work with highly visible omnidirectional flashing warning lights.

Intelligent Transportation Systems (ITS) Infrastructure may exist within the limits of this project and that the system must remain operational throughout construction. The exact location of ITS Infrastructure is not known. Contact the TxDOT Area Engineer's or Inspection Team's Office for the location(s) at least 72 hours before commencing any work that might affect present ITS Infrastructure. In the event of system damage, notify TxDOT/CTECC at (512) 974-0883 within one hour of occurrence. Refer to Item 6000 for additional details.

Provide a smooth, clean sawcut along the existing asphalt or concrete pavement structure, as directed. Consider subsidiary to the pertinent Items.

Construct all manholes/valves to final pavement elevations prior to the placement of final surface. If the manholes/valves are going to be exposed to traffic, place temporary asphalt around the manhole/valve to provide a 50:1 taper. The asphalt taper is subsidiary to the ACP work.

Keep the roadway free of debris and sediment caused by construction activities. Dispose of all material in accordance with federal, state, and local regulations. This work is subsidiary.

Damage to existing pipes and SET's due to Contractor operations will be repaired at Contractor's expense.

All locations used for storing construction equipment, materials, and stockpiles of any type, within the right of way, will be as directed. Use of right of way for these purposes will be restricted to those locations where driver sight distance to businesses and side street intersections is not obstructed and at other locations where an unsightly appearance will not exist. The Contractor will not have exclusive use of right of way but will cooperate in the use of the right of way with the city/county and various public utility companies as required.

Coordinate and obtain approval for all bridgework over existing roadways.

**Bridge Vertical Clearance and Traffic Handling.**

Notify TxDOT project staff and the local bridge engineer 10 business days prior to the following: change in vertical clearance, placing beams/girders over traffic, opening or removing traffic from a bridge or portion of a bridge, and completion of bridge work. This requirement includes bridge class culverts. Provide vertical clearance for all structures (including signal mast arms, span wires, and overhead sign bridge structures) within the project limit. Submit information and notices to local bridge engineer at [AUS\\_BRG\\_Notify@txdot.gov](mailto:AUS_BRG_Notify@txdot.gov).

During evacuation periods for Hurricane events the Contractor will cooperate with Department for the restricting of Lane Closures and arranging for Traffic Control to facilitate Coastal Evacuation Efforts.

**ITEM 2 – INSTRUCTIONS TO BIDDERS**

This Contract includes non-site specific work. Multiple work orders will be used to procure work of the type identified in the Contract at locations that have not yet been determined.

**ITEM 5 – CONTROL OF THE WORK**

Place construction or silt fence 2 ft. inside TxDOT ROW along the Railroad ROW. If work is to be performed inside the Railroad ROW, then the Contractor will coordinate with the Railroad for a Railroad Flagger. This work is subsidiary.

Place construction stakes at intervals of no more than 100 ft. This work is subsidiary.

Provide a 72 hour advance email notice to [AUS\\_Locate@TxDOT.gov](mailto:AUS_Locate@TxDOT.gov) to request illumination, traffic signal, ITS, or toll equipment utility locates. Provide [AUS\\_Locate@TxDOT.gov](mailto:AUS_Locate@TxDOT.gov) an

electronic pdf of as-builts within 21 calendar days of illumination, traffic signal, ITS, or toll equipment being placed into operation. As-built shall include GPS coordinates of manholes and junction boxes. Include final version of RFI's and revised plan sheets.

#### **Precast Alternate Proposals.**

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at [Alternate Precast Proposal Submission \(txdot.gov\)](http://www.txdot.gov). Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

#### **Thermoplastic Pipe Alternate Proposals**

When a reinforced concrete or corrugated metal pipe is included in the plans, a thermoplastic polypropylene pipe alternate may be submitted in a 2-phase process. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

Phase 1 submit an official request to TxDOT PM with a summary of proposed locations, max depth of placement for each location, cover depth, and pipe diameters. TxDOT goal is to review and respond within 10 days. Phase 1 approval does not guarantee Phase 2 approval.

Phase 2 submit the following documents with all documents signed and sealed by a licensed Engineer in the state of Texas. 1-Provide a redline or revised set of drainage plans reflecting the revised locations. 2-Provide certification that the use of the alternate pipe and proposed bedding are adequate for the proposed application, depth, etc. 3-Provide a completed thermoplastic pipe installation drawing using the following,

<https://ftp.txdot.gov/pub/txdot/brg/thermoplastic-pipe-installation-drawing.pdf>  
<https://ftp.txdot.gov/pub/txdot/brg/thermoplastic-pipe-installation-drawing.dgn>

For all uses of thermoplastic pipe as an alternate, furnish, install, and inspect the thermoplastic pipe in accordance with SS4216 or latest thermoplastic pipe special specification at time of letting. Minimum values, such as cover depth, required by the specification, installation drawing, etc. will not be waived. Use granular backfill unless flowable fill or CSB is required by the alternate design. Backfill locations shown in the bid plans using flowable fill or CSB must use the backfill per the bid plans.

#### **Electronic Shop Drawing Submittals.**

Submit electronic shop drawing submittals according to the current [Guide to Electronic Shop Drawing Submittal](http://www.txdot.gov) which can be found online at, <https://www.txdot.gov/business/resources/highway/bridge/shop-drawing-submittal-cycle.html>.

Pre-approved producers can be found online at, <https://www.txdot.gov/business/resources/materials/material-producer-list.html>.

Use the following contact list for all submittals that are not required to be sent to Bridge Division and to copy the Engineer for all submittals to the Bridge Division.

#### Submittal Contact List

Bastrop Area	<a href="mailto:Diana.Schulze@txdot.gov">Diana.Schulze@txdot.gov</a>	<a href="mailto:AUS_BA-ShopReview@txdot.gov">AUS_BA-ShopReview@txdot.gov</a>
Signal Shop	<a href="mailto:Kevin.Plumlee@txdot.gov">Kevin.Plumlee@txdot.gov</a>	
Signal Shop	<a href="mailto:Dave.Henry@txdot.gov">Dave.Henry@txdot.gov</a>	

#### **ITEM 6 - CONTROL OF MATERIALS**

Give a minimum of 1 business day notice for materials, which require inspection at the Plant.

For structures with paint containing hazardous materials, provide locations of material removal 60 days prior to begin removal. For metal elements to be removed, mechanical shear or unbolting for removal and disposal does not require paint abatement but requires 60-day advance notice.

For removal, tie, or tap of asbestos concrete (AC) pipe, contact TxDOT and the local utility company 60 days prior to performing the work. Expose the AC pipe to provide a minimum of 1 ft. of clearance around the top and sides. A minimal amount of soil may remain around the AC pipe to avoid disturbance. The local utility company will be responsible for the demo notice to DSHS and removal of the AC pipe. Tie or tap into existing AC pipe may require removing an entire section of pipe from collar to collar and replacement of pipe with new pipe using existing bid items.

#### **Storage of Material Near Structures**

Do not store equipment or flammable material within 100 ft. of bridges, culverts, or near their openings (portals). Flammable materials include all material that is not metal or aluminum.

#### **ITEM 7 – LEGAL RELATIONS AND RESPONSIBILITIES**

TxDOT will coordinate with TDLR regarding pedestrian elements and sidewalks. The contractor will procure and provide all permits, licenses, and inspections; pay all charges, fees, and taxes regarding TDLR rules governing industrialized housing and buildings.

No significant traffic generator events identified.

Refer to the Environmental Permits, Issues and Commitments (EPIC) plan sheets for additional requirements and permits.

When any abandoned well is encountered, cease construction operations in this area and notify the Engineer who will coordinate the proper plugging procedures. A water well driller licensed in the State of Texas must be used to plug a well.

Perform maintenance of vehicles or equipment at designated maintenance sites. Keep a spill kit on-site during fueling and maintenance. This work is subsidiary.



Maintain positive drainage for permanent and temporary work for the duration of the project. Be responsible for any items associated with the temporary or interim drainage and all related maintenance. This work is subsidiary.

Suspend all activities near any significant recharge features, such as sinkholes, caves, or any other subterranean openings that are discovered during construction or core sampling. Do not proceed until the designated Geologist or TCEQ representative is present to evaluate and approve remedial action.

Locate aboveground storage tanks kept on-site for construction purposes in a contained area as to not allow any exposure to soils. The containment will be sized to capture 150% of the total capacity of the storage tanks.

**PSL in Edwards Aquifer Recharge and Contributing Zone.**

Obtain written approval from the Engineer for all on or off right of way PSLs not specifically addressed in the plans. Provide a signed sketch of the location 30 business days prior to use of the PSL. Include a list of materials, equipment and portable facilities that will be stored at the PSL. TxDOT will coordinate with the necessary agencies. Approval of the PSL is not guaranteed. Un approved PSL is not a compensable impact.

**Work within a USACE Jurisdictional Area.**

Do not initiate activities within a U.S. Army Corps of Engineers (USACE) jurisdictional area that have not been previously evaluated by the USACE as part of the permit review of this project. Such activities include, but are not limited to, haul roads, equipment staging areas, borrow and disposal sites. Obtain written approval from the Engineer for activities not specifically addressed in the plans. Provide a signed sketch and description of the location 60 business days prior to begin work at the location. Complete and return any forms provided by TxDOT. Approval of the work is not guaranteed. Un approved work is not a compensable impact.

**Work over or near Bodies of Water (lakes, rivers, ponds, creeks, dry waterways, etc.).**

Keep on site a universal spill kit adequate for the body of water and the work being performed. Debris is not allowed to fall into the ordinary high-water level (OHWL). Debris that falls into the OHWL must be removed at the end of each work day. Debris that falls into the floodway must be removed at the end of each work week or prior to a rain event. Install and maintain traffic control devices to maintain a navigable corridor for water traffic, except during bridge demo and beam placement. This work is subsidiary.

Obtain written approval from the Engineer for temporary fill or crossings not specifically addressed in the plans. Provide a signed sketch of the location 60 business days prior to begin work at the location. Complete and return any forms provided by TxDOT. Approval of the work is not guaranteed. Unapproved work is not a compensable impact.

**DSHS Asbestos and Demolition Notification.**

Complete and provide the Texas Department of State Health Services (DSHS) notification form to the Engineer and email to [AUS\\_BRG\\_Notify@txdot.gov](mailto:AUS_BRG_Notify@txdot.gov) at least 30 calendar days prior to

bridge removal or renovation for each phase or step of work. Notify the Engineer via email of any changes to the work start and end dates.

**Migratory Birds and Bats.**

Migratory birds and bats may be nesting within the project limits and concentrated on roadway structures such as bridges and culverts. Remove all old and unoccupied migratory bird nests from any structures, trees, etc. between September 16 and February 28. Prevent migratory birds from re-nesting between March 1 and September 15. Prevention shall include all areas within 25 ft. of proposed work. All methods used for the removal of old nesting areas and the prevention of re-nesting must be submitted to TxDOT 30 business days prior to begin work. This work is subsidiary.

If active nests are encountered on-site during construction, all construction activity within 25 ft. of the nest must stop. Contact the Engineer to determine how to proceed.

**Tree and Brush Trimming and Removal.**

Work will be conducted September 16 thru February 28. Work conducted outside this timeframe will require a bird survey. Submit a survey request to TxDOT 30 business days prior to begin work.

If within the removal time period, removal work may be conducted during delayed start period using proper traffic control per TCP standards.

Upon begin removal operations, all removal work for the project must be completed within 21 calendar days. Completion of removal includes removing from ROW or mulching of all debris.

No extension of time or compensation will be granted for a delay or suspension due to the above bird, bat, and tree/brush requirements.

**Law Enforcement Personnel.**

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site. A minimum number of hours is not guaranteed. Payment is for work performed. If the Contractor has a field office, provide an office location for a supervisory officer when event requires a supervising officer. This work is subsidiary.

A maximum combined rate of \$85 per hour for the law enforcement personnel and the patrol vehicle will be allowed. Any scheduling fee is subsidiary per Standard Specification 502.4.2. Cancel law enforcement personnel when the event is canceled. Cancellation, minimums or "show up" fees will not be paid when cancellation is made 12 hours prior to beginning of the

event. Failure to cancel within 12 hours will not be cause for payment for cancellation, minimums, or "show up" time. Payment of actual "show up" time to the event site due to cancellation will be on a case-by-case basis at a maximum of 2 hours per officer.

Alterations to the cancellation and maximum rate must be approved by the Engineer or pre-determined by official policy of the officer's governing authority.

**Back Up Alarm.**

For hours 9 P to 5 A, utilize a non-intrusive, self-adjusting noise level reverse signal alarm. This is not applicable to hotmix or seal coat operations. This is subsidiary.

**ITEM 8 – PROSECUTION AND PROGRESS**

A Special Provision to Item 8 to revise the begin work date has been included for the following reason(s): Planting must be installed between the months of September and November.

**Lane Closure Assessment Fee.**

The monthly estimate will be deducted a fee per 15-minute interval according to the following schedule for each closure or obstruction that extends beyond the allowable closure time. Fee will be based on Annual Average Daily Traffic (AADT) of the roadway. Use AADT information as shown on the plans. If AADT is not found on the plans please use TxDOT – Statewide Planning Map [https://www.txdot.gov/apps/statewide\\_mapping/StatewidePlanningMap.html](https://www.txdot.gov/apps/statewide_mapping/StatewidePlanningMap.html). If the roadway has a peak direction of traffic, the Engineer may reduce the fee by 25 percent for off-peak direction of traffic for up to 30 minutes.

AADT		Lane Closure Assessment Fee (per lane per 15 minutes)
More than	To and Including	
0	10000	\$150.00
10000	20000	\$300.00
20000	40000	\$600.00
40000	60000	\$900.00
60000	80000	\$1,200.00
80000	100000	\$1,500.00
100000		\$1,800.00
All of IH 35 Mainlanes		\$2,000.00

**ITEM 110 – EXCAVATION**

The Engineer will define unsuitable material.

**ITEM 160 - TOPSOIL**

Off-site topsoil will have a minimum PI of 25.

No Sandy Loam allowed.

Obtain approval of the actual depth of the topsoil sources for both on-site and off-site sources.

Construct topsoil stockpiles of no more than five (5) feet in height.

It is permissible to use topsoil dikes for erosion control berms within the right of way, as directed.

Seed or track slopes within 14 days of placement.

Salvage topsoil from sites of excavation and embankment. Maximum salvage depth is 6 inches. Windrowing of topsoil obtained from the Right of Way (ROW) is not allowed.

**ITEM 170 - IRRIGATION SYSTEM**

All work, equipment, and materials for the irrigation system are considered subsidiary to Item 170. Submit copy of Texas Irrigation license at preconstruction meeting.

Submit for approval, an irrigation plan for a drip irrigation system, designed by a licensed irrigator, according to the information shown in the plans and following TCEQ requirements. Design the system to sufficiently distribute water to all plant material in accordance with the rules and regulations of TCEQ and the local water authority. Install the irrigation design, as approved.

Provide a seasonal (spring, summer, fall, winter) watering schedule based on either current/real time evapotranspiration data or monthly historical evapotranspiration data, monthly effective rainfall estimates, plant landscape coefficient factors, and site factors.

Locate all underground utilities and conduit locations prior to digging or trenching.

Place irrigation pipe to avoid conflicts with utilities and other appurtenances. Place all valves in accessible locations, as directed. Contact Engineer for location of TxDOT utility lines.

Do not install substitutions or alternate equipment without prior approval. Install equipment according to manufacturer's directions, unless otherwise directed.

All costs and fees for water will be considered subsidiary to Item 170.

Establish the water service account under the Contractor's name and pay for all fees, deposits, and costs related to equipment, installation, inspections, and water service throughout the project, until final completion and acceptance. Contact Georgetown Utility Systems Customer Service/Austin Water to obtain information regarding fees and costs. The State will not be responsible for any changes or increases in water fees or price structure.

Provide 1 inch, temporary hydrant water meters from the City Georgetown Utility Systems Customer Service/Austin Water Services for irrigation purposes and provide water throughout the duration of the entire contract. Be aware of all hydrant meter renewal requirements, fines, and/or penalties. Contact Georgetown Utility Systems Customer Service/Austin Water Water Services at (512) 930-3640/(512) 972-0101 to obtain information regarding the costs and all current requirements for temporary fire hydrant meters.

Provide RPZ backflow prevention assemblies that are approved by the city water authority. Ensure that temporary hydrant meters are secured to hydrants. The State is not responsible for theft of hydrant meters.

Schedule, coordinate, and pay all fees for installation of hydrant meters and BPA testing, as required by the local water authority.

All sleeves and bores for irrigation are considered subsidiary. No additional compensation will be given for bores that are needed to replace lost, damaged, or non-existing sleeves. Provide a minimum of eighteen (18) inches clearance below the bottom of roadway pavement structures for bores, with a minimum depth of no less than 30 inches to pavement surface.

Use SCHD 80 PVC pipe for bore casings, all exposed, above ground irrigation pipe. Use SCHD 40 PVC for all below ground irrigation pipe unless otherwise directed. Bury main lines and lateral pipe a minimum of 12 inches below grade.

Provide one-half (½) inch drip tubing with punch-in emitters, as shown in the plans. Staple and bury drip tubing two (2) inches below soil line.

Prior to backfilling, test the system according to Item 170, with TxDOT inspector present.

AS-BUILT DRAWINGS. Provide "As-Built" drawings on 11" x 17" sheets that show the exact location of bores, valves, backflow preventer, quick couplers, and location changes of irrigation mainlines, if different from original layout. Show the dimensional distances of valve and device locations from 2 permanent objects such as curbs, walls, light poles, etc. Additional irrigation sheets for this purpose can be obtained from the Engineer. Show valve and mainline location changes in RED ink, if different than originally shown in the plans. As-Built Drawings must be sealed by a Licensed Irrigation Contractor and must include all information required by TCEQ.

Submit As-Built Irrigation Drawings for approval before final payments for Item 170 are made and before the Landscape Establishment period (Item 193) begins.

Monitor water distribution and check for leaks or over-saturation. Repair and adjust irrigation to prevent wasted water.

Conform to watering schedule, times, and usage restrictions set by the city or local water authority. Repair and replace parts as required to keep irrigation systems operating and functioning properly, without additional compensation, throughout the entire contract.

Ensure proper distribution of water for proper plant growth. Immediately repair irrigation malfunctions and replace materials or equipment, as needed, to keep irrigation system fully operational. The irrigation system shall be run a minimum of monthly to ensure the life of the plant material. Plants that are damaged or die as a result of irrigation system failures or not operating, will be immediately replaced at no additional expense to the State.

At completion of contract and as directed, contact the local water authority to disconnect temporary hydrant meters. Remove hydrant meters and cap irrigation lines. Close the water account, as directed. Do not transfer account to the State.

#### ITEM 192 – LANDSCAPE PLANTING

Locate all underground utilities and conduits prior to digging.

The Engineer may make adjustments to the plant and planting bed locations to meet field conditions. These changes are considered incidental and there will be no additional compensation.

Do not work subsoil for planting operations when moisture content is so great that excessive compaction will occur, or when subsoil is so dry that the clods will not break readily. Apply water if necessary. These conditions will be determined by the Engineer as planting operations begin.

It may be necessary to suspend planting operations if the Engineer determines that unusually hot, dry weather or water restrictions will affect thriving growth of plant material. If planting operations are suspended, time charges will also be suspended until the Engineer determines that planting operations can begin again. Continue to maintain previously planted plants during time suspension. No extra compensation will be allowed due to such suspensions.

Remove undesirable vegetation from work zone, as directed. This work is incidental and will be considered subsidiary to Item 192.

If requested, provide tree or plant photos that show that the materials provided will meet minimum measurements and size specifications. Submit one photo per size and item. Photo will be used as the standard for all sizes.

Provide Compost that meets specifications under Item 161. Ensure that mulch and compost is free of visible debris and unsuitable materials.

Prior to backfilling bed areas, conduct water percolation tests, as shown in the plans. Contact Landscape Architect if excavated bed areas do not drain efficiently.

Water all plants within the same day of installation. Thoroughly soak root balls of large plants and trees. Set base of plant pit so that top of root ball is set slightly above grade and will not settle below grade. If top of root ball settles below grade, plant must be replanted at proper depth or replaced, without additional compensation.

Stake trees for support during the same day as planted. Trees that cannot stand erect without plant supports will be rejected. Ensure trees and tall shrubs remain plumb and straight for all given conditions throughout the contract period. Staking method must allow trunk to sway with the wind while remaining plumb.

#### Maintenance and 90-Day Warranty.

Maintain all plants in a healthy, growing condition. Replace dead or severely damaged plants as directed.

Keep project area clean and remove all litter. Remove all trimmings and debris from project site.

Keep planting beds free of weeds and undesirable species. Do not use string trimmers or spray herbicide in planting beds or tree watering basins. Spraying herbicide is not allowed. Apply herbicide by a wicking method, only. A wicking method consists of a wick or rope soaked in herbicide attached to a handle. The wetted wick is used to wipe or brush herbicide over the weed. Do not allow herbicide to contact planted vegetation, contaminate the soil, or contact bodies of water.

Use Glyphosate, (Round-Up or approved equal), in a wicking method for weed control after plants have been installed. Follow manufacturer's directions and use properly licensed personnel.

Mow a five (5) foot border around each planting bed. Mow turf to a height of four (4) inches. Remove litter from area before mowing. Mow according to the following schedule:

Mow every two weeks from March 1 to October 31.  
Mow once a month from November 1 to February 28.

At the end of the 90-day maintenance period of Item 192, and prior to beginning Item 193, "Plant Establishment," replace all dead or damaged plants that are considered unacceptable, as directed. Item 193 will begin after all work is complete and in-place, and all punch list items have been corrected, as directed and approved.

#### **ITEM 193 -LANDSCAPE ESTABLISHMENT**

Item 193 will begin, as directed, after the 90-day maintenance and warranty period (Item 192) has been completed and approved.

Continue to provide all maintenance activities described in Item 192 and as shown in the plans.

Assume responsibility for health and growth of all plant material in landscaped areas. Keep plants, trees, plant beds, watering basins, and areas immediately around plantings neat and presentable. Remove all dead or broken limbs, sucker growth, litter, and debris from beds and tree basins.

Correct erosion damage. Maintain depth of mulch or erosion control compost, as shown in the plans. Additional mulch or erosion control compost material needed to maintain proper depth and coverage will be considered subsidiary to Item 193.

Keep irrigation system fully operational. Cost of water will be considered subsidiary to this Item. If irrigation system fails, provide an alternative means of watering plants until system is made fully operational. Trucks, tanks, or any additional equipment needed to provide water to plants will be considered subsidiary. Plants that are damaged or die as a result of irrigation failures, will be immediately replaced at no additional expense to the State.

Keep irrigation system operating and fully functional.

Replace dead or unacceptable plant material, only as directed. Replacements for deciduous trees and deciduous woody shrubs that are planted during winter dormancy, without green foliage, will only be considered acceptable after healthy, visible foliage appears after dormancy period.

Do not replace any perennial-type plants during the period from November 1, to March 1.

Notify Engineer two (2) days prior to each maintenance visit. Record dates, times, and completed tasks of all maintenance visits, for approval. Notify Engineer immediately if emergencies or significant problems arise.

Complete all punch list items before final approval and project close-out.

#### **ITEM 360 – CONCRETE PAVEMENT**

Provide Class K concrete as necessary to follow work sequence, comply with closure restrictions, and meet requirements for opening to traffic. This work is subsidiary.

Tining will be longitudinal.

After preparation of subgrade and base courses for CRCP, saw cut and remove 2 in. of existing CRCP prior to widening CRCP to create a clean vertical joint for widening. Unless otherwise specified on the plans, the work performed, materials furnished, equipment, labor, tools, and incidentals will not be paid for directly but will be subsidiary.

#### **ITEM 400 - EXCAVATION AND BACKFILL FOR STRUCTURES**

Unless shown on the plans, the following backfill will apply to cutting and restoring flexible pavement. Backfill with cement-stabilized backfill. The cement-stabilized backfill is subsidiary.

Cap the backfill with Type B hot-mix to a depth equal to the adjacent hot-mix. At locations where the backfill surface is final, place 1-1/2 in. Type D for the surface. The minimum hot-mix depth will be 4 in.

Unless shown on the plans, flowable fill option 1 item will be used for pavement widening. Saw-cut the pavement at the edge of the excavation. This work is subsidiary.

Backfill the bridge ends in accordance with the limits shown on TxDOT "CSAB" Standard. Use material in accordance with "CSAB" or Item 423, Type BS. The "CSAB" optional bond breaker materials are allowed. This work is subsidiary.

#### **ITEM 432 - RIPRAP**

Mow strip riprap will be 4 in. and all other riprap will be 5 in. unless otherwise shown on the plans. Mow strip for cable barrier may be placed monolithically with the barrier foundations if using concrete in accordance with Item 543. Fiber reinforcement is not allowed except in mow strip for cable barrier if foundation and mow strip are placed monolithically. GFRP is allowed reinforcement for all applications.



Saw-cut existing riprap then epoxy 12 in. long No. 3 or No. 4 bars 6 in. deep at a maximum spacing of 18 in. in each direction to tie new riprap to existing riprap. This work is subsidiary.

Provide Type A Grade 3 or 5 flexible base for cement stabilized riprap. Compressive strengths for flexible base are waived.

SGT approach taper, paid for using mow strip item, will be installed using concrete, flexible base coated with SS-1 at a rate of 0.12 GAL/SY, or HMA Type B/C/D. Placement will be ordinary compaction and does not require placement using an asphalt paver.

**ITEM 502 - BARRICADES, SIGNS, AND TRAFFIC HANDLING**

Table 1

Roadway	Limits	Allowable Closure Time
IH 35	All (1 lane closed)	9 P to 5 A
IH 35	All (2 lanes closed, see allowable work below)	9 P to 5 A
IH 35	All (2 lanes closed, all work)	11 P to 5 A
SH 45	US 183 to SH130	8 P to 5 A
LP 1	William Cannon to Parmer Lane	8 P to 5 A
US 183	SH 29 to FM 1327	8 P to 5 A
SH 71	SH 130 to IH 35	8 P to 5 A
SH 71	SH 304 to Tahitian Drive	8 P to 5 A
SH 71	US 290 W to RM 3238	8 P to 5 A
US 290 W	IH 35 to Nutty Brown Rd	8 P to 5 A
US 290 E	IH 35 to SH 95	8 P to 5 A
FM 734	FM 1431 to US 290 E	8 P to 5 A
US 79	IH 35 to Bus 79 in Taylor	8 P to 5 A
RM 1431	Lohmans Ford Rd to IH 35	8 P to 5 A
SH 29	LP 332 western terminus to SH 130	8 P to 5 A
SH 80	Charles Austin to River Road	8 P to 5 A
RM 2222	All	8 P to 5 A
RM 620	All	8 P to 5 A
RM 2244	All	8 P to 5 A
SPUR 69	All	8 P to 5 A
LP 360	All	8 P to 5 A
LP 343	All	8 P to 5 A
LP 275	All	8 P to 5 A
FM 1325	All	8 P to 5 A
All	Within 200' of a signalized intersection	9 P to 5 A
All	All (Full Closure, see allowable work below)	11 P to 4 A

Table 3 (Mobile Operations)

Roadway	Allowable Sun Night thru Fri Noon	Allowable Sat thru Sun Morn
Within Austin City Limits	10 A to 2 P and 7 P to 6 A	7 P to 10 A
Outside Austin City Limits	9 A to 3 P and 7 P to 7 A	6 P to 11 A
IH 35 main lanes	10 P to 5 A	9 P to 9 A

AADT over 50,000                      8 P to 6 A    8 P to 10 A  
For roadways without defined allowable closure times, nighttime lane closures will be allowed from 8 P to 6 A.

Daytime or Friday night lane closures will not be allowed unless otherwise shown on the plans. One lane in each direction will remain open at all times for all roadways unless otherwise shown on the plans.

Two lanes closed on IH 35 allowed to begin at 9 P.M. for main lane (shoulder work not included) hotmix overlay or pavement repair operations (does not include bridge joint work).

Full closures only allowed Friday night thru Monday morning for bridge beam installation, bridge demolition, or OSB truss removal/installation. Full closures only allowed for roadways with frontage roads or if a designated detour route is provided in the plans.

No closures will be allowed on the weekends, working day prior, and working day after the National Holidays defined in the Standard Specifications, Good Friday, and Easter weekend.

No closures will be allowed 1 P.M. to 11 P.M. the Sunday of the Super Bowl.

Time charges will not be suspended during the large and special events listed below. These events are provided in the contract to allow scheduling of work around these lane closure restrictions.

All lanes will be open by noon of the day before the large events listed in below table. No closures will be allowed on Friday and the weekends for projects within 20 miles of these large events:

Table 4 (Large Events)

Event	City	Dates
Formula 1 @ COTA	Austin	Annually (See Event Website)
Moto GP @ COTA	Austin	Annually (See Event Website)
ACL Fest	Austin	Annually (See Event Website)
SXSW	Austin	Annually (See Event Website)
ROT Rally	Bastrop	Annually (See Event Website)
UT Football Games	Austin	Annually (See Event Website)
Sales Tax Holiday	All	Annually (See Event Website)
Rodeo Austin	Austin	Annually (See Event Website)

All lanes will be open by noon of the day before the special events listed in below table. No closures will be allowed on Friday and the weekends for projects within 10 miles of these special events:

Table 5 (Special Events)

Event	City	Dates
Eaker BBQ Competition	Fredericksburg	March 10, 2024
Sherwood Forest Faire	McDade / Paige	Weekends in March and April
Smithville Jamboree	Smithville	April 4-6, 2024
Wiener Dog Races	Buda	April 29-30, 2023
Founders Day Festival	Dripping Springs	April 28-30, 2023
Red Poppy Festival	Georgetown	April 26-28, 2024
Crawfish Open	Llano	3 <sup>rd</sup> Friday and Saturday in April
Fair and Rodeo	Liberty Hill	May 18, 2023
Founders Day Ceremony	Fredericksburg	2 <sup>nd</sup> Weekend in May
Crawfish Festival	Fredericksburg	Saturday before Memorial Day
Lakefest Boat Races	Marble Falls	June 10-11, 2023
Watermelon Thump	Luling	Last Full Weekend in June
Pie in the Sky	Kyle	Sept 1-2, 2023
Wine and Music Festival	Georgetown	Last Saturday of September
Deer Season Opening Weekend	All Counties in Burnet Area Office	1 <sup>st</sup> Friday and Saturday of Season
Christmas Nights of FBG Lights	Fredericksburg	Nov 21, 2023
Christmas on Mercer	Dripping Springs	Dec 2, 2023
Lady of Guadalupe Procession	Fredericksburg	Dec 12, 2023
Texas State Graduation Fall	San Marcos	TBD
Texas State Graduation Spring	San Marcos	TBD

All the large and special events listed in the above tables occur annually. Coordinate with the Department and review the city/event website to plan around the future events.

To account for directional traffic volumes, begin and end times of closures may be shifted equally by the Engineer. The closure duration will remain. Added compensation is not allowed.

One-way traffic control, including work performed under Item 510, must be set up to provide a maximum of 20 minutes of delay to the traveling public.

Submit an emailed request for a lane closure (LCN) to TxDOT. The email will be submitted in the format provided. Receive concurrence prior to implementation. Submit a cancellation of lane closures a minimum of 18 hours prior to implementation. Blanket requests for extended periods are not allowed. Max duration of a request is 2 weeks prior to requiring resubmittal.

Provide 2-hour notice prior to implementation and immediately upon removal of the closure.

For roadways listed in Table 1: Submit the request 96 hours prior to implementation.

For roadways not listed in Table 1: Submit the request a minimum of 48 hours prior to the closure and by the following deadline immediately prior to the closure: 11A on Tuesday or 11A on Friday.

For all roadways: Submit request for traffic detours and full roadway closures 168 hours prior to implementation. Submit request for nighttime work 96 hours to implementation date.

Cancellations of accepted closures (not applicable to full closures or detours) due to weather will not require resubmission in accordance with the above restrictions if the work is completed during the next allowable closure time.

Closures that conflict with adjacent contractor will be prioritized according to critical path work per latest schedule. Conflicting critical path or non-critical work will be approved for first LCN submitted. Denial of a closure due to prioritization or other reasons will not be reason for time suspension, delay, overhead, etc.

Meet with the Engineer prior to lane closures to ensure that sufficient equipment, materials, devices, and workers will be used. Take immediate action to modify current and future traffic control, if at any time the queue becomes greater than 20 minutes.

Consider inclement weather prior to implementing the lane closures. Do not set up traffic control when the pavement is wet.

Cover, relocate, or remove existing small, large, and overhead signs that conflict with traffic control. Cover large and overhead signs to remain using latest standard TS-CD. This work is subsidiary.

Install all permanent signs, delineation, and object markers required for the operation of the roadway before opening to traffic. Use of temporary mounts is allowed or may be required until the permanent mounts are installed or not impacted by construction. Maintain the temporary mounts. This work is subsidiary.

Place a 28-inch cone, meeting requirements of BC (10) and Ty III barricades, on top of foundations that have protruding studs. This work is subsidiary.

Vertical panels used on roadways with speed limit 55mph or greater must be round in shape or have a self-righting mechanism. The “flat” or “oblong” shaped vertical panels are not allowed.

A series of sequential flashing warning lights, per BC(7), must be installed in a merging taper for long term stationary TCP. This includes all TCP setups, such as those shown on the plans or TCP setups per the standards.

Edge condition treatment types must be in accordance with the TxDOT standard. Installation and removal of a safety slope is subsidiary.

To determine a speed limit or an advisory speed limit, submit a request to TxDOT 60 business days prior to manufacture of the sign.

For non-site-specific signal projects, 2 months of barricades will be paid per work order location.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

**ITEM 506 - TEMPORARY EROSION, SEDIMENTATION, AND ENV CONTROLS**

If SW3P plan sheets are not provided, place the control measures as directed.

Install, maintain, remove control measures in areas of the right of way utilized by the Contractor that are outside the limits of disturbance required for construction. Permanently stabilize the area. This work is subsidiary.

Erosion control measures must be initiated immediately in areas where construction activities have ceased and will not resume for a period exceeding 14 calendar days. Vertical track all exposed soil, stockpiles, and slopes. Re-track after each rain event or every 14 days, whichever occurs first. Sheep foot roller is allowed for vertical tracking. This work is subsidiary.

For routine or anticipated dewatering, notify the engineer 72 hours before beginning dewatering. Notify the Engineer within 1 hour of beginning emergency or recent rainfall dewatering. Water located within the ROW that will leave the ROW must appear free of pollutants such as suspended sediment, oil sheen, floating solids, etc. Dirty water must pass thru adequate BMPs prior to leaving the ROW to prevent discharge of dirty water. Bypass pumping of water found in a navigable waterway that enters from outside the ROW and is discharged downstream of the ROW will not require the use of BMPs. Dewatering BMPs will be paid for in conformance with the applicable bid items. However, if the necessary BMP item is not included in the Contract, payment for the BMP will be in accordance with Article 9.7., "Payment for Extra Work and Force Account Method." The act of dewatering and the equipment used to dewater will not be paid for directly but will be subsidiary to pertinent bid items.

Unless a specific pay item is provided in the plans, the installation of the 6:1 or flatter for RFD side slopes in the safety zone will be subsidiary to pertinent bid items.

Cover small waste containers (100 gallons or less) at all times. This work is subsidiary. Large waste containers (more than 100 gallons) must have a secondary discharge containment system around the container using erosion control logs. Installation of the log for each container location will be paid using existing bid items. Repair, remove, or replace of the log will not be paid. Revisions, repairs, remove or replace of the log during exchange of empty/full containers at the same location will not be paid.

Portable restrooms must be located more than 50 ft. from a waterway. Tie or stake down portable restrooms to prevent tipping due to vandalism or weather. This work is subsidiary.

Provide a designated location for disposal when excess and waste, including waste generated from cleaning of all equipment used for mixing, hauling, and transfer concrete is disposed in the ROW or PSL. Manufactured disposal containers must be metal or a plastic material with minimum 10 mil thickness. Paper, earthen berms, or pits must be lined with minimum 10 mill thickness polyethylene sheeting. Disposal locations must be located a minimum of 50 ft. from a waterway, tree, or sensitive feature. The disposal location must have a minimum height of 6 in. Maintain a minimum 4 in. of freeboard at all times. Disposal locations are not required for cleaning of small hand tools. Hardened concrete waste may be used as embankment if placed in accordance with Item 132.

**ITEMS 528, 529, 530, 531, & 536 – MISCELLANEOUS CONSTRUCTION**

Reinforcement will be in accordance with Section 432.3.1 unless shown on the plans. Fiber reinforcement is not allowed. GFRP is allowed reinforcement for all applications. Class A and B Concrete are allowed to use Coarse Aggregate Grades 1-8.

Unless shown on the plans, all concrete will be 5 in. thick and have 2 in. sand, base, or RAP bedding. Furnish base meeting the requirement for any type or grade in accordance with Item 247. Compressive strengths for flexible base are waived. RAP must be 100% passing a 1 in. sieve. Bedding and flexible base must be placed using ordinary compaction.

Expansion joints will be placed every 40 ft. Expansion joints must be 1 in. wide asphalt board and flush with the surface. The bottom of the asphalt board will be at half the depth of the concrete. The reinforcement will be continuous thru the expansion joint. Sidewalk cross slope must not exceed 1.5%.

If roots are encountered verify with the Engineer before accommodating or removing 2 in. diameter or larger roots. Root removal must be in accordance with Section 752.4.2. Roots may remain in the bedding or base. For improvements within 6 in. of a root, the concrete thickness may be reduced by 1 in. and the bedding increased by 1 in. to minimize impacts to the roots. Adjust bedding and surface profile to provide a 1 in. bedding cushion around the roots. The surface profile may be adjusted to the extent allowed by ADA. This work is subsidiary.

**ITEM 528 - COLORED TEXTURED CONCRETE AND LANDSCAPE PAVERS**

Use concrete patterns and colors as shown on the plans and details. Seal concrete with a clear sealer provided by the color manufacturer.

**ITEMS 600s & 6000s – ITS, TOLLING, LIGHTING, SIGNING, MARKINGS, AND SIGNALS**

Meet the requirements of the NEC, Texas MUTCD, TxDOT standards, and TxDOT Standard Specifications. Notify the Engineer if existing elements to remain do not meet code or specification.

Provide all service, equipment and material required to provide a functional item and interface with existing equipment and software.

For signal shop contact Robert Bolin ([Robert.Bolin@txdot.gov](mailto:Robert.Bolin@txdot.gov)) and Kevin Plumlee ([Kevin.Plumlee@txdot.gov](mailto:Kevin.Plumlee@txdot.gov)).

Use the TxDOT provided form to submit an electrical, illumination, and signal checklist prior to request for signal activation or a punch list.

Provide a 7-day advance email notice to the Engineer to request illumination or traffic signal punch list inspection.

Provide a 14-day advance email notice to the Engineer with signal technician contact information and signal locations prior to working or assuming operations of illumination or traffic signal.

Provide a 60-day advance email notice to the Engineer to request signal timing if timing is not provided in the plans.

Provide a 180-day advance email notice to the Engineer for equipment to be provided by TxDOT.

Provide equipment that requires TxDOT programming, etc. to TxDOT 180 day in advance.

Prior to relief of maintenance, a 30-day Test Period is required for signals and ITS equipment in accordance with Item 680.3.1.8. Response time to reported trouble calls shall be less than 2 hours. Complete repairs within 24 hours. Notify the Engineer and maintain a logbook in the controller cabinet of each trouble call. Do not clear the error log in the conflict monitor without approval.

Maintain the existing ITS equipment and HUB buildings operational during construction. ITS downtime is allowed from 12A to 4A. Downtime is restricted to one time per HUB or equipment.

Definitions of abbreviations used to designate ITS equipment, material, etc. can be provided by the Engineer.

Provide email notice to TxDOT and toll road owner 60 business days prior to begin work that impacts tolling equipment. Attend a pre-construction meeting with TxDOT and toll road owner prior to begin work.

Coordinate with toll road owner during construction that impacts or installs tolling equipment. Toll owner will assist with inspection to ensure tolling equipment will operate correctly. Provide email notice to TxDOT and toll road owner 30 business days in advance of completion of toll equipment work. Once toll equipment work is complete, allow 60 calendar days for toll road owner to complete their portion of the work and testing.

Stakes or other physical method shall be installed to hold down conduit prior to placement of concrete/flow fill encasement.

Minimum distance between HDPE joints will be 200 ft.

For conduit mounted to bridges in hangers, fiberglass can be substituted for RMC. Furnish and install per Special Specification 6390.

#### ITEM 610 - ROADWAY ILLUMINATION ASSEMBLIES

Upon removal, contact signal shop to stockpile a maximum of 10 assemblies that meet the current TxDOT standards at the Austin District Headquarters located at 7901 North IH 35, 78753. If signal shop declines receipt of these assemblies, Contractor will be responsible for disposal.

For each assembly, paint the service, circuit, run and assembly number/letter using 3 in. tall characters and black paint. The marking shall be stacked vertically with the service on top and the assembly number/letter on the bottom. Paint 6 ft. above the roadway surface on the hand access door side of the pole or adjacent to the assembly if mounted to a structure. This work is subsidiary.

For both transformer and shoe-base type illumination poles, provide double-pole breakaway fuse holder.

Provide 10-amp time delay fuses.

Maintain all new and existing illumination for the duration of the contract. All existing illumination will remain operational until replaced by new illumination or required to be removed due to construction.

#### ITEM 618 - CONDUIT

Shift the locations of conduit and ground boxes to accommodate field conditions. Install conduit not exceeding 2 feet in any direction from a straight line. Install conduit at a minimum depth of 2 ft. below finished grade. Installation of the conduit by jacking or boring method will be at a depth of at least 1 ft. below subgrade.

Install a high tension, non-metallic pull rope in all empty conduit runs. This work is subsidiary. Use a coring device, not a hammer drill, when drilling holes through concrete structures.

Structurally mounted junction boxes will be as shown on the plans. When used for traffic signal installations, these boxes will be 12" x 12" x 8". This work is subsidiary.

For underground conduit, smooth wall schedule 40 equivalent HDPE can be substituted for schedule 40 PVC. Schedule 80 bore can be replaced with a schedule 40 equivalent HDPE carrier pipe of adequate size to carry the proposed conduits. HDPE must transition to RMC/PVC per ED (11)-14.

When using existing conduit, ensure that all conduits have bushings and cleaned of dirt, mud, grease, and other debris. Re-strap existing or relocated conduit per the specification. This work is subsidiary.



Abandoned underground conduit must have all conductors removed.

**ITEM 620 - ELECTRICAL CONDUCTORS**

Provide 10-amp time delay fuses.

For Flashing Beacons (Item 685) and Pedestal Poles (Item 687), provide single-pole breakaway disconnects.

Install a minimum size 8 AWG equipment grounding conductor (EGC) in all conduits including loop detectors and traffic signal cables. Payment and the size of the EGC will be in accordance with standard ED (3)-14 note 12.

Permanently mark “Illumination” on the luminaire conductors installed inside a traffic signal pole. Make the marks easily visible from the hand hole.

**ITEM 624 – GROUND BOXES**

Aggregate for fill under the box will be crushed, have a maximum size of 2 in., minimum size of ½ in., and requirements per Item 302 are waived.

**ITEM 628 – ELECTRICAL SERVICES**

Contact the utility company upon execution of contract and prior to the pre-construction meeting to make arrangements for all work and materials provided by the utility company. Contact [AUS\\_Auditors@txdot.gov](mailto:AUS_Auditors@txdot.gov) for account approval and information. Accounts shall be placed in the name of TxDOT.

**ITEM 6000s – ITS**

Coordinate with the Department at least 120 hours (5 days) in advance of interrupting existing Department ITS communication devices that will result in the elements being non-operational or offline. Network downtime may be no more than 4 hours and may only be scheduled for the weekend between the hours of 10:00 PM and 5:00 AM on Saturday and Sunday. The schedule must be coordinated and approved by the Department. If more than 4 hours of downtime is needed, use alternative communication routes via wireless communication or temporary duct bank. Refer to table below for contact information.

Name	Organization	Email
Douglas Turner	TxDOT	<a href="mailto:Douglas.L.Turner@txdot.gov">Douglas.L.Turner@txdot.gov</a>
Kevin Plumlee	TxDOT	<a href="mailto:Kevin.Plumlee@txdot.gov">Kevin.Plumlee@txdot.gov</a>

Every effort must be made to protect the duct bank during construction. Repair or replace any damages to the duct bank/cable/conduit caused by the Contractor to its original condition at no additional cost to the Department. Failure of the Contractor to repair damage to any infrastructure that conveys any corridor information to TxDOT/CTECC will result in the Contractor being billed for the full cost of emergency repairs.

Acceptable response time for repair of communication trunklines:

- Major or backbone fiber optic cables, radios, and/or power supply.

- Four hours.
- Minor fiber optic cables (CCTV, DMS, & RVSD).
  - Twelve hours.

Protect and preserve the existing Department infrastructure not affected by the construction.

**ITEM 6185 – TRUCK MOUNTED ATTENUATOR AND TRAILER ATTENUATOR**

The TMA/TA used for installation/removal of traffic control for a work area will be subsidiary to the TMA/TA used to perform the work.

The contractor will be responsible for determining if one or more operations will be ongoing at the same time to determine the total number of TMA/TA required for the work. TMA/TAs paid by the day is full compensation for all worksite locations during an entire day.

TMA/TAs used to protect damaged attenuators will be paid by the day using the force account item for the repair.



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0152-02-071

DISTRICT Austin  
HIGHWAY US 183

COUNTY Caldwell

CONTROL SECTION JOB				0152-02-071		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00191382			
COUNTY				Caldwell			
HIGHWAY				US 183			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	104-6022	REMOVING CONC (CURB AND GUTTER)	LF	30.000		30.000	
	110-6003	EXCAVATION (SPECIAL)	CY	119.000		119.000	
	170-6001	IRRIGATION SYSTEM	LS	1.000		1.000	
	192-6002	PLANT MATERIAL (1-GAL)	EA	103.000		103.000	
	192-6004	PLANT MATERIAL (5-GAL)	EA	50.000		50.000	
	192-6012	MULCH	CY	6.500		6.500	
	192-6014	PLANT SOIL MIX	CY	52.000		52.000	
	192-6025	PLANT MATERIAL (45 GAL) (TREE)	EA	9.000		9.000	
	193-6001	PLANT MAINTENANCE	MO	24.000		24.000	
	193-6007	IRRIGATION SYSTEM OPER AND MAINT	MO	24.000		24.000	
	432-6006	RIPRAP (CONC)(CL B)	CY	6.000		6.000	
	459-6001	GABIONS (GALV)	CY	14.000		14.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		5.000	
	506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	100.000		100.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	100.000		100.000	
	528-6001	COLORED TEXTURED CONC (4")	SY	200.000		200.000	
	529-6008	CONC CURB & GUTTER (TY II)	LF	30.000		30.000	
	531-6001	CONC SIDEWALKS (4")	SY	139.000		139.000	
	531-6010	CURB RAMPS (TY 7)	EA	2.000		2.000	
	618-6014	CONDT (PVC) (SCH 40) (3/4")	LF	225.000		225.000	
	618-6023	CONDT (PVC) (SCH 40) (2")	LF	50.000		50.000	
	618-6024	CONDT (PVC) (SCH 40) (2") (BORE)	LF	110.000		110.000	
	620-6005	ELEC CONDR (NO.10) BARE	LF	455.000		455.000	
	620-6006	ELEC CONDR (NO.10) INSULATED	LF	2,320.000		2,320.000	
	624-6001	GROUND BOX TY A (122311)	EA	1.000		1.000	
	628-6116	ELC SRV TY D 120/240 060(NS)AL(E)SP(O)	EA	1.000		1.000	
	1002-6002	LANDSCAPE AMENITY (TY 1)	EA	1.000		1.000	
	1002-6003	LANDSCAPE AMENITY (TY 2)	EA	4.000		4.000	
	4099-6001	ORNAMENTAL STEEL FENCE	LF	54.000		54.000	
	6185-6002	TMA (STATIONARY)	DAY	20.000		20.000	
08		CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS	1.000		1.000	
		CONTRACTOR FORCE ACCOUNT WORK (NON-PARTICIPATING)	LS	1.000		1.000	
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS	1.000		1.000	

DISTRICT	COUNTY	CCSJ	SHEET
Austin	Caldwell	0152-02-071	4

DATE: 12/11/2023 4:29:59 PM  
FILE: P:\txdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\1. General\US183\_GEN\_SUM.dgn

LOCATION	104 6022	110 6003	170 6001	192 6002	192 6004	192 6012	192 6014	192 6025	193 6001	193 6007	432 6006	459 6001	506 6040	506 6043	528 6001	529 6002
	REMOVING CONC ( CURB AND GUTTER)	EXCAVATION ( SPECIAL)	IRRIGATION SYSTEM	PLANT MATERIAL ( 1-GAL)	PLANT MATERIAL ( 5-GAL)	MULCH	PLANT SOIL MIX	PLANT MATERIAL ( 45 GAL) ( TREE)	PLANT MAINTENAN CE	IRRIGATION SYSTEM OPER AND MAINT	RIPRAP ( CONC) ( CL B)	GABIONS ( GALV)	BIODEG EROSN CONT LOGS ( INSTL) ( 8")	BIODEG EROSN CONT LOGS ( REMOVE)	COLOR TEXTURED CONC ( 4")	CONC CURB & GUTTER ( TY II)
	LF	CY	LS	EA	EA	CY	CY	EA	MO	MO	CY	CY	LF	LF	SY	LF
US 183 @ CEMETERY ST	30	119	1	103	50	6.5	52	9	24	24	6	14	100	100	200	30
PROJECT TOTALS	30	119	1	103	50	6.5	52	9	24	24	6	14	100	100	200	30

LOCATION	531 6001	531 6010	618 6014	618 6023	618 6024	620 6005	620 6006	624 6001	628 6116	1002 6002	1002 6003	4099 6001	6185 6002
	CONC SIDEWALKS ( 4")	CURB RAMPS ( TY 7)	CONDT ( PVC) ( SCH 40) ( 3/4")	CONDT ( PVC) ( SCH 40) ( 2")	CONDT ( PVC) ( SCH 40) ( 2") ( BORE)	ELEC CONDR ( NO. 10) BARE	ELEC CONDR ( NO. 10) INSULATED	GROUND BOX TY A ( 122311)	ELC SRV TY D 120/240 060(NS) A L (E) SP (O)	LANDSCAPE AMENITY ( TY 1)	LANDSCAPE AMENITY ( TY 2)	ORNAMENTA L STEEL FENCE	TMA ( STATION ARY)
	SY	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	LF	DAY
US 183 @ CEMETERY ST	139	2	225	50	110	455	2320	1	1	1	4	54	20
PROJECT TOTALS	139	2	225	50	110	455	2320	1	1	1	4	54	20

**Austin District  
Central Design**

QUANTITY SUMMARY

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY		SHEET NO.
	AUS	CALDWELL		5


DATE: 12/11/2023 10:54:56 AM  
 FILE: P:\txdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\1. General\HW1234\_GEN\_ASSET\_MAINTENANCE.dgn

ASSET DESCRIPTION	ROADWAY	LIMITS	
		FROM	TO
Traffic Signals			
Illumination			
Landscaping Features	US 183	29.8896	29.8887999
		-97.67095	-97.6709094
Aesthetic/Noise Walls/ Special Features			
Other			


Note: The asset locations specified in the tables are provided in GPS grid coordinates.

The City of Lockhart accepts the fixed responsibility to maintain, control, supervise, and regulate the above on State highway ROW through its corporate limits. This document is per Chapter 311 of the Texas Transportation Code supplemental to the existing Municipal Maintenance Agreement (MMA) with the City of Lockhart. This document does not relieve the City of Lockhart from their responsibility to maintain all roads within their city limits as stated in the MMA.

Executed on behalf of the City by: \_\_\_\_\_ Date: \_\_\_\_\_


<b>Austin District Maintenance Office</b>			
 Texas Department of Transportation			
<b>US 183 ASSET MAINTENANCE</b>			
<small>SHEET 1 OF 1</small>			
© 2024	CONT	SECT	JOB
DS: CR:	0152	02	071
			US 183
DW: CR:	DIST		COUNTY
	AUS		CALDWELL
			SHEET NO.
			6






**LEGEND**

ROW	---
SIGN	⊥
POWER POLE	○
OVERHEAD ELECTRIC	—E—
EXISTING TREE	⊙
EXCAVATION (SPECIAL) 6\"/>	



- NOTES:**
1. ALL MEASUREMENTS ARE APPROXIMATE. EXCAVATION LAYOUT MUST BE APPROVED BY TXDOT PRIOR TO CONSTRUCTION.
  2. CONTRACTOR IS RESPONSIBLE FOR ENSURING NO DAMAGE IS DONE TO EXISTING US 183 BRIDGE FOUNDATIONS AND STRUCTURES DURING CONSTRUCTION.

ITEM	DESCRIPTION	QUANTITY	UNITS
110-6003	EXCAVATION (SPECIAL)	119	CY
104-6022	REMOVING CONC (CURB AND GUTTER)	30	LF




**Austin District  
Central Design**

**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
DEMOLITION PLAN**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	7	



**LEGEND**

- ROW — . . . —
- SIGN — — — —
- POWER POLE ○
- OVERHEAD ELECTRIC — — — —
- EXISTING TREE ○
- ORNAMENTAL STEEL FENCE — — — —
- GABIIONS 1'-5' height with cast stone cap 2'-8' height
- DETAIL NUMBER (ON DETAIL SHEET) SHEET NUMBER — 1 — 15
- SECTION DETAIL — 4 — 13



Designed by:  
*Hilary Garnish*  
 F08EE0CACE74A7...  
 1/8/2024

**NOTES:**

1. SEE PAVEMENT LAYOUT PLAN FOR PAVEMENT SCORING & EXPANSION JOINT LAYOUT.
2. ALL MEASUREMENTS ARE APPROXIMATE. LAYOUT MUST BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION.
3. MEET EXISTING GRADES AT EDGES OF PROPOSED PAVEMENT.
4. GRADE TO ENSURE POSITIVE DRAINAGE OFF PROPOSED PAVEMENT AT SLOPES BETWEEN 1% TO 2%. PROVIDE SMOOTH EVEN WALKING SURFACE ON ALL PROPOSED PAVEMENT.

**SHEET QUANTITY**

ITEM	DESCRIPTION	QUANTITY	UNITS
459-6001	GABIIONS (GALV)	14	CY
529-6008	CONC CURB & GUTTER (TY II)	30	LF
531-6010	CURB RAMPS (TY 7)	2	EA
4099-6001	ORNAMENTAL STEEL FENCE	54	LF



SCALE: 1" = 10'



*Austin District  
 Central Design*



**US 183  
 LOCKHART GCAA  
 LAYOUT PLAN**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	8	





- LEGEND**
- ROW — — — —
  - SIGN — b
  - POWER POLE o
  - OVERHEAD ELECTRIC — E —
  - EXISTING TREE (•)
  - ORNAMENTAL STEEL FENCE [Symbol]
  - GABIIONS 1'-5' height with cast stone cap 2'-8' height [Symbol]
  - PROPOSED CONC SIDEWALKS (4') [Symbol]
  - PROPOSED COLORED TEXTURED CONC (4') - TYPE I [Symbol]
  - PROPOSED COLORED TEXTURED CONC (4') - TYPE II [Symbol]
  - PROPOSED COLORED TEXTURED CONC (4') - TYPE III [Symbol]
  - PROPOSED COLORED TEXTURED CONC (4') - TYPE IV [Symbol]



Hilary Garnish  
 F9BEE0CATED74A7...  
 1/8/2024

*Austin District  
 Central Design*




**US 183  
 LOCKHART GCAA  
 PAVEMENT  
 LAYOUT PLAN**


- NOTES:**
- ALL MEASUREMENTS ARE APPROXIMATE. LAYOUT MUST BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION.
  - PLACE EXPANSION JOINTS AROUND GABIIONS, ORNAMENTAL STEEL FENCE FOOTINGS, AND BETWEEN COLORED TEXTURED CONC (4") TYPES & CONC SIDEWALKS (4").
  - MEET EXISTING GRADES AT EDGES OF PROPOSED PAVEMENT.
  - GRADE TO ENSURE POSITIVE DRAINAGE OFF PROPOSED PAVEMENT AT SLOPES BETWEEN 1% TO 2%. PROVIDE SMOOTH, STABLE, AND SLIP RESISTANT WALKING SURFACE ON ALL PROPOSED PAVEMENT.

**SHEET QUANTITY**

ITEM	DESCRIPTION	QUANTITY	UNITS
528-6001	COLORED TEXTURED CONC (4")	200	SY
531-6001	CONC SIDEWALKS (4")	139	SY



© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY		SHEET NO.
	AUS	CALDWELL		9



**LEGEND**



- ROW — — — —
- SIGN —
- POWER POLE ○
- OVERHEAD ELECTRIC — E —
- EXISTING TREE ○
- ORNAMENTAL STEEL FENCE —
- GABIONS 1'-5' height with cast stone cap 2'-8' height

**SHEET QUANTITY SUMMARY**

ITEM	DESCRIPTION	QUANTITY	UNITS
192-6002	PLANT MATERIAL (1-GAL)	103	EA
192-6004	PLANT MATERIAL (5-GAL)	50	EA
192-6012	MULCH	6.5	CY
192-6014	PLANT SOIL MIX	52	CY
192-6025	PLANT MATERIAL (45 GAL TREE)	9	EA

**PLANT SPECIFICATIONS**

ITEM	COMMON NAME	BOTANICAL NAME	QUANTITY	SIZE	SPACING	MIN. HEIGHT	MIN. SPREAD	NOTES
192-6002	Golden Groundsel	<i>Pachera obovata</i>	24	1 GAL.	12" O.C.	6"	6"	Container grown
	Frogfruit	<i>Phyla nodiflora</i>	59	1 GAL.	12" O.C.	6"	6"	Container grown
	Zexmenia	<i>Wedelia texana</i>	20	1 GAL.	30" O.C.	6"	6"	Container grown
	<b>TOTAL:</b>		<b>103</b>	1 GAL.				
192-6004	Crossvine	<i>Bignonia capreolata</i>	4	5 GAL.	30" O.C.	12"	4'	Container grown
	Purple Trailing Lantana	<i>Lantana montevidensis</i>	10	5 GAL.	30" O.C.	12"	12"	Container grown, Purple flower
	Texas Sedge	<i>Carex texensis</i>	27	5 GAL.	18" O.C.	12"	12"	Container grown
	Dwarf Yaupon	<i>Ilex vomitoria 'Compacta'</i>	9	5 GAL.	4.5' O.C.	12"	12"	Container grown
		<b>TOTAL:</b>		<b>50</b>	5 GAL.			
192-6025	Texas Redbud	<i>Cercis canadensis var. texensis</i>	6	45 GAL.	12' O.C.	8'	4'	Container grown, multi-trunk
	Texas Mountain Laurel	<i>Sophora secundiflora</i>	3	45 GAL.	10' O.C.	5'	3'	Container grown, multi-trunk
	<b>TOTAL:</b>		<b>9</b>	45 GAL.				




**Austin District  
Central Design**


**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
PLANTING PLAN**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	10	








**LEGEND**

- ROW — . . . —
- SIGN — — — —
- POWER POLE ○
- OVERHEAD ELECTRIC — E —
- EXISTING TREE ○
- ORNAMENTAL STEEL FENCE — — — —
- GABIONS 1'-5' height with cast stone cap 2'-8' height

- NOTES:**
- IRRIGATION LINES SHOWN ON THE PLANS ARE DIAGRAMMATIC ONLY. ROUTE LINES TO AVOID CONFLICTS, AS DIRECTED.
  - PROVIDE AN IRRIGATION DESIGN FROM A LICENSED IRRIGATOR, IN ACCORDANCE WITH REQUIREMENTS SHOWN ON THE IRRIGATION DETAILS, TCEQ REQUIREMENTS AND ITEM 170 OF THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS, AND BRIDGES 2014," PLANS, DETAILS, AND NOTES. SUBMIT THE IRRIGATION DESIGN FOR APPROVAL, PRIOR TO INSTALLATION.
  - COORDINATE WITH LOCAL WATER AUTHORITY FOR ACCESS AND USE OF ADJACENT TAPS FOR TEMPORARY METERS, ALL FEES AND COSTS FOR TEMPORARY METERS, INSPECTIONS, WATER USED, IRRIGATION DESIGN, INSTALLATION, MATERIAL, EQUIPMENT, AND BORES ARE SUBSIDIARY TO ITEM 170. BE AWARE OF WATER AUTHORITY RULES AND TIME LIMITATIONS THAT APPLY TO USE OF TEMPORARY METERS. (SEE IRRIGATION DETAILS AND GENERAL NOTES).
  - EXTEND BORE CASINGS A MINIMUM OF 8' BEHIND THE FACE OF CURB, THE SIDEWALK OR EDGE OF PAVEMENT. SEE GENERAL NOTES FOR BORE DEPTH. ALL BORES SHALL BE AT REQUIRED DEPTH PRIOR FACE OF CURB, THE SIDEWALK OR EDGE OF PAVEMENT.

**IRRIGATION LEGEND:**

- ⊕ FIRE HYDRANT
- MAINLINE
- ≡≡≡ CASED BORE/SLEEVE
- Ⓡ RAIN/FREEZE SENSOR
- Ⓢ CONTROLLER



**Austin District  
Central Design**

**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
IRRIGATION PLAN**


© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	11	

DATE: 12/11/2023 10:55:16 AM  
FILE: p:\txdot\project\wisconsin\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\10. Miscellaneous\Plans\US 183 LIGHTING PLAN.dgn

ELECTRICAL SERVICE DATA												
ELEC. SERVICE ID	PLAN SHEET NUMBER	ELECTRICAL SERVICE DESCRIPTION	SERVICE CONDUIT SIZE	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN CKT. BKR. POLE/AMPS	LIGHTING CONTACTOR AMPS	PANELBD/LOADCENTER AMPS RATING	BRANCH CIRCUIT ID.	BRANCH CKT. BKR. POLE/AMPS	BRANCH CIRCUIT AMPS	KVA LOAD
ES1		ELC SRV TY D 120/240 060 (NS)AL(E)SP(O)	2"	3/#6	N/A	2P/60	2P/30	100	A-GABION LIGHTING NORTH	1P/15	10	3
									B-GABION LIGHTING SOUTH	1P/15	9	
									C-RECEPTACLE NORTH	1P/15	3	
									D-RECEPTACLE SOUTH	1P/15	3	

LEGEND



- ELECTRICAL SERVICE
- CONDUIT AND CONDUCTOR
- CONDUIT AND CONDUCTOR (BORED)
- GROUND BOX
- CONDUIT RUN NUMBER
- JUNCTION BOX
- RECEPTACLE



RUN NO.	SUMMARY OF CONDUITS AND CABLES						LENGTH (FT)	STATUS
	0618 6014 CONDT (PVC) (SCH 40) (3/4")	0618 6023 CONDT (PVC) (SCH 40) (2")	0618 6024 CONDT (PVC) (SCH 40) (2") (BORE)	0620 6005 ELEC CONDR (NO.10) BARE	0620 6006 ELEC CONDR (NO.10) INSULATED			
1		50		1	60	8 (A, B, C, D)	480	I
2			110	1	115	8 (A, B, C, D)	920	I
3	7			1	10	4 (A, C)	40	I
4	15			1	20	2 (A)	40	I
5	11			1	15	4 (A, C)	60	I
6	23			1	25	4 (A, C)	100	I
7	11			1	15	4 (A, C)	60	I
8	15			1	20	4 (A, C)	80	I
9	15			1	20	4 (A, C)	80	I
10	16			1	20	4 (A, C)	80	I
11	7			1	10	4 (A, C)	40	I
12	27			1	30	2 (A)	60	I
13	23			1	25	2 (A)	50	I
14	9			1	10	4 (B, D)	40	I
15	16			1	20	4 (B, D)	80	I
16	12			1	15	4 (B, D)	60	I
17	10			1	15	2 (B)	30	I
18	8			1	10	2 (B)	20	I
TOTAL	225	50	110		455		2320	385

QUANTITY SUMMARY				
TXDOT BID ITEM		ITEM DESCRIPTION	UNIT	QUANTITY
*1002	6002	LANDSCAPE AMENITY (TY 1)	EA	1
1002	6003	LANDSCAPE AMENITY (TY 2)	EA	4
618	6014	CONDT (PVC) SCH (40) (3/4")	LF	225
618	6023	CONDT (PVC) SCH (40) (2")	LF	50
618	6024	CONDT (PVC) SCH (40) (2") (BORE)	LF	110
620	6005	ELEC CONDR (NO.10) BARE	LF	455
620	6006	ELEC CONDR (NO.10) INSULATED	LF	2320
624	6001	GROUND BOX TY A (122311)	EA	2
628	6116	ELC SRV TY D 120/240 060(NS)AL(E)SP(O)	EA	1

\* LANDSCAPE AMENITY (TY 1) ESTIMATED TO BE 580 FT.



**Austin District  
Traffic Operations**


**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
LIGHTING PLAN**

SHEET OF


© 2024	CONT	SECT	JOB	HIGHWAY
DS:	CR:	0152 02	071	US 183
DW:	CR:	DIST	COUNTY	SHEET NO.
		AUS	CALDWELL	12






1  
14  
TYPICAL DEMOLITION SECTION A  
SEE DEMOLITION PLAN FOR SECTION LOCATION

SCALE: 3/16" = 1'




2  
13  
TYPICAL PROPOSED CONSTRUCTION SECTION A  
SEE LAYOUT PLAN FOR SECTION LOCATION

SCALE: 3/16" = 1'



3  
13  
TYPICAL DEMOLITION SECTION B  
SEE DEMOLITION PLAN FOR SECTION LOCATION

SCALE: 3/16" = 1'



4  
13  
TYPICAL PROPOSED CONSTRUCTION SECTION B  
SEE LAYOUT PLAN FOR SECTION LOCATION

SCALE: 3/16" = 1'




DocuSigned by  
Hilary Garnish  
F0BEE0ACF874A73  
12/11/2023

Austin District  
Central Design  
Texas Department of Transportation

US 183  
LOCKHART GCAA  
HARDSCAPE  
DETAILS

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY		SHEET NO.
	AUS	CALDWELL		13





**ORNAMENTAL STEEL FENCE NOTES:**


1. ALUMINUM PANELS, STEEL TUBING & PICKETS, ATTACHMENTS, AND ORNAMENTAL STEEL FENCE CONCRETE FOOTINGS SUBSIDIARY TO ITEM 4099-6001, ORNAMENTAL STEEL FENCE. SEE SCHEDULE OF MATERIALS AND FINISHES.
2. DIMENSIONS ARE APPROXIMATE. PROVIDE SHOP DRAWINGS TO BE APPROVED BY THE LANDSCAPE ARCHITECT. FABRICATE ORNAMENTAL STEEL FENCE PRIOR TO INSTALLATION - ALUMINUM PANELS MAY BE ATTACHED ON-SITE. ALL STEEL TO BE GALVANIZED AFTER FABRICATION.
3. SMOOTH AND ROUND ANY SHARP CORNERS AND EDGES.

**GABION (GALV) NOTES:**

1. CAST STONE CAP SUBSIDIARY TO ITEM 459-6001 GABIONS (GALV).
2. GABION CONCRETE FOOTING SUBSIDIARY TO ITEM 432-6006, RIPRAP (CONC)(CL B).
3. CONTRACTOR RESPONSIBLE FOR SECURING & FASTENING GABION BASKETS ACCORDING TO MANUFACTURER'S INSTRUCTIONS.
4. FILL GABIONS WITH DECORATIVE CRUSHED GLASS, TO BE PROVIDED BY TXDOT. CONTRACTOR RESPONSIBLE FOR TRANSPORTING DECORATIVE CRUSHED GLASS TO SITE FROM THIS LOCATION IN CCORDINATION WITH TXDOT:  
EAST OF 4508 BELLMEAD DR,  
WACO, TX 76705  
COORDINATES: 31°36'18.8"N 97°04'48.0"W


1  
14 GABION & ORNAMENTAL STEEL FENCE SECTION  
SEE LAYOUT PLAN FOR SECTION LOCATIONS

SCALE: 1/2" = 1'



2  
14 1'-5" HEIGHT GABION @ PLANTING BED & COLORED TEXTURED CONC (4") SECTION  
SEE DETAIL 1 (THIS SHEET) FOR SECTION LOCATIONS

SCALE: 3/8" = 1'




3  
14 2'-8" HEIGHT GABION @ PLANTING BED & COLORED TEXTURED CONC (4") SECTION  
SEE DETAIL 1 (THIS SHEET) FOR SECTION LOCATIONS

SCALE: 3/8" = 1'



Documented by  
Hilary Garnish  
F9BEE0CACE74A7...  
1/8/2024



**US 183  
LOCKHART GCAA  
HARDSCAPE  
DETAILS**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY		SHEET NO.
	AUS	CALDWELL		14




**SCHEDULE OF MATERIALS & FINISHES**

ITEM	DESCRIPTION	SPEC. OR FINISH	NOTES
GABIONS			
459-6001	GABIONS (GALV)	<u>Cast Stone Cap</u>	See plans and details for cast stone cap dimensions. Mortar between adjacent pieces with matching color to give appearance of uniform surface as needed.
		<u>Gabion Baskets</u>	Welded wire mesh gabion baskets, 3"x3" mesh, 9 guage stainless steel wire. DuraWeld or approved equal.
		<u>Crushed Glass</u>	Provided by TxDOT
432-6006	RIPRAP (CONC)(CL B)	Class B concrete, rebar, and subgrade compaction	
PROPOSED PAVING			
528-6001	COLORED TEXTURED CONC (4")	<u>Type I</u>	Colorado Flag SikaStamp or approved equal, Smoke integral color with Slate Gray release color, SikaColor Integral Color or approved equal.
		<u>Type II</u>	Chiseled Slate Texture SikaStamp or approved equal, Shadow Slate integral color with Slate Gray release color, SikaColor Integral Color or approved equal.
		<u>Type III</u>	Chiseled Slate Texture SikaStamp or approved equal, Smoke integral color with Slate Gray release color, SikaColor Integral Color or approved equal.
		<u>Type IV</u>	New Brick Running Bond SikaStamp or approved equal, Brick Red integral color with Walnut release color, SikaColor Integral Color, or approved equal.
531-6001	CONC SIDEWALKS (4")	White color, medium broom finish.	
ORNAMENTAL STEEL FENCE			
4099-6001	ORNAMENTAL STEEL FENCE	3'-9"x3'x1/8" aluminum panels, with smoothed and rounded corners and edges.	Provide shop drawings to be approved by the Landscape Architect prior to construction.
		3.5"x3.5"x2" square hot-dipped galvanized steel cap, with smoothed and rounded corners and edges.	
		3"x3" square hot-dipped galvanized steel tubing	
		2"x2" square hot-dipped galvanized steel tubing	
		1"x1" hot-dipped galvanized steel pickets, 1/8" thick	


**NOTES:**

- 2"Wx1"H CAST STONE CAP OVERHANG TYP. ON ALL SIDES, EXCEPT WHERE 1'-5" GABION IS FLUSH WITH 2'-8" GABION.



1  
15 COLORED TEXTURED CONC (4") & CONC SIDEWALKS (4")  
ITEM 528-6001 & 531-6001

SCALE: 1" = 1'



2  
15 GABIONS (GALV) CAST STONE CAP  
ITEM 528-6001 & 531-6001

SCALE: 1" = 1'



**Austin District  
Central Design**

**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
HARDSCAPE  
DETAILS**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY		SHEET NO.
	AUS	CALDWELL		15

**PLANTING NOTES**


1. REFERENCE ITEM 192 OF THE TEXAS STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS AND BRIDGES 2014 FOR SPECIFICATIONS, DIMENSIONS, VOLUMES AND MEASUREMENTS THAT HAVE BEEN MODIFIED OR ARE NOT SHOWN.
2. REJECTION OF PLANTS WILL BE IN ACCORDANCE WITH ITEM 192.2.2.
3. PLANTING AREA PREPARATION:
  - 3.1. MULCH: FURNISH DOUBLE GROUND HARDWOOD MULCH
  - 3.2. GENERAL USE COMPOST: FURNISH GENERAL USE COMPOST ACCORDING TO ITEM 161.2.3.
  - 3.3. FURNISH COMPOST AND MULCH MATERIALS THAT ARE FREE OF VISIBLE GLASS, METAL, ROCK, PLASTIC, PAPER, LARGE PIECES OF WOOD, DIRT CLODS, DEBRIS, OR ANY UNSUITABLE MATERIAL THAT WOULD DETRACT THE QUALITY AND APPEARANCE OF THE PLANTING AREA.
4. DO NOT INSTALL PLANTS UNTIL IRRIGATION SECTIONS ARE OPERABLE.
5. AFTER PLANT AND BED LOCATIONS HAVE BEEN VERIFIED NOT TO BE IN CONFLICT WITH UTILITIES OR POSE A SAFETY HAZARD, PREPARE BED AREAS ACCORDING TO THE PLANS, AND DIG PLANT PITS ACCORDING TO 192.3.4.
6. INSTALL PLANTS ACCORDING TO THE PLANS AND SPECIFICATIONS. WATER ALL PLANTS WITHIN THE SAME DAY OF PLANTING. THOROUGHLY SOAK ROOT BALLS. SET TOP OF ROOTBALL HIGH ENOUGH TO ALLOW FOR SETTLING SO THAT THE TOP OF ROOT BALL DOES NOT SINK OR SETTLE BELOW GRADE. REPLANT AND RAISE THE ELEVATION OF ANY PLANTS THAT SETTLES WHERE THE TOP OF THE ROOT BALL IS BELOW THE SURROUNDING GRADE. DO NOT PLACE ANY ADDITIONAL SOIL ON TOP OF THE ROOT BALL.
7. INSTALL IRRIGATION EMITTERS DURING OR IMMEDIATELY AFTER PLANT INSTALLATION. WATER USED FOR IRRIGATION WILL BE CONSIDERED SUBSIDIARY TO ITEM 170 AND ITEM 193.
8. APPLY WATER IMMEDIATELY AFTER PLANTING AT TWO (2) TIMES THE GALLON SIZE OF THE PLANT CONTAINER. THEREAFTER, SCHEDULE IRRIGATION TO KEEP THE PLANTS IN A HEALTHY, GROWING CONDITION.
9. STRESSED PLANT MATERIAL WILL BE REJECTED ACCORDING TO ITEM 192.2.2. AND REPLACED AT THE CONTRACTOR'S EXPENSE.
10. MAINTAIN ALL LANDSCAPING, IRRIGATION, AND ASSOCIATED WORK IMMEDIATELY AFTER PLANTING AND DURING THE 90-DAY MAINTENANCE PERIOD. AT THE COMPLETION OF THE 90-DAY MAINTENANCE PERIOD, AND AS DIRECTED, CONDUCT A WALK-THRU WITH TXDOT PERSONNEL AND CORRECT PUNCHLIST ITEMS, PRIOR TO ENTERING THE LANDSCAPE ESTABLISHMENT PERIOD (ITEM 193). MAINTENANCE DURING THE LANDSCAPE ESTABLISHMENT PERIOD (ITEM 193) WILL BE PAID FOR MONTHLY.
11. MAINTAIN MULCH AT THE SPECIFIED DEPTH OF THREE (3) INCHES OVER THE FULL EXTENT OF THE BED. KEEP TREE WATERING BASINS INTACT AND MAINTAINED. KEEP BED AREAS AND TREE WATERING BASINS FREE OF WEEDS. NYLON STRING TRIMMERS (WEED-EATERS) ARE NOT ALLOWED IN TREE BASINS.
  - 11.1. A WICKING METHOD OF HERBICIDE APPLICATION, (ROUND-UP OR APPROVED EQUAL), MAY BE USED BY PROPERLY LICENSED PERSONNEL. IMMEDIATELY REPLACE ANY PLANT THAT IS DAMAGED OR KILLED BY HERBICIDE OR WEED CONTROL OPERATIONS, AS DIRECTED, AND WITHOUT ADDITIONAL COMPENSATION. REPLACE DEAD OR DAMAGED PLANTS AS DIRECTED.
12. UNDER ITEM 193, OBTAIN APPROVAL PRIOR TO REPLACING PLANTS. REPLACE PLANTS ONLY AS APPROVED AND AS DIRECTED.
13. STAKING MATERIAL SHALL BE REMOVED AFTER APPROVAL BY LANDSCAPE ARCHITECT.

**SOIL PERCOLATION TEST**

1. CONDUCT SOIL PERCOLATION TESTS PRIOR TO PLANT INSTALLATION IN FLAT AREAS OF THE PLANTING BEDS BY EXCAVATING A TEST PIT EIGHTEEN (18) INCHES DEEP AND EIGHTEEN (18) INCHES WIDE.
2. PROVIDE SEVERAL TEST PITS AT THE PROJECT SITE AND PERFORM PERCOLATION TESTS AT EACH ONE, AS DIRECTED.
3. FILL PIT WITH WATER TO ONE HALF DEPTH. ALLOW TO DRAIN.
4. FILL HOLE AGAIN WITH WATER TO ONE HALF DEPTH. MEASURE WATER LEVEL FROM TOP EDGE OF PIT. TIME THE RATE OF DRAINAGE.
5. IF WATER DRAINS SLOWER THAN ONE HALF INCH PER HOUR, REPORT FINDINGS AND CONTACT TXDOT LANDSCAPE ARCHITECT FOR DIRECTION.


**MINIMUM PLANT PIT SIZES**

1. PIT DEPTH: EXCAVATE PIT TWO (2) INCHES DEEPER THAN ROOT BALL AND BACKFILL BOTTOM WITH TWO (2) INCHES OF SOIL/COMPOST MIX AND LIGHTLY COMPACT. WHEN SETTING PLANTS INTO THE PIT, ENSURE THAT THE TOP OF THE ROOT BALL IS SLIGHTLY HIGHER THAN THE SURROUNDING GRADE.
2. PIT DIAMETER:
  - 2.1. PLANTS 15 GALLON OR LARGER:
    - 2.1.1. PROVIDE A MINIMUM HORIZONTAL DIMENSION OF TWELVE (12) INCHES BETWEEN THE ROOT BALL AND THE SIDES OF THE PIT.
  - 2.2. PLANTS SMALLER THAN 15 GALLON:
    - 2.2.1. PROVIDE A MINIMUM HORIZONTAL DIMENSION OF TWO (2) TIMES THE ROOT BALL DIAMETER ACROSS THE PIT.




**INDIVIDUAL TREE PLANTING DETAILS**

NTS



**SHRUB PLANTING IN MASS BEDS**

NTS



DocuSigned by:  
Hilary Garnish  
F0B5E0CACE97A73  
12/11/2023

**Austin District  
Central Design**

**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
PLANTING DETAILS**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST			SHEET NO.
	AUS			CALDWELL 16

### PLANT SPECIFICATIONS

ITEM	COMMON NAME	BOTANICAL NAME	QUANTITY	SIZE	SPACING	MIN. HEIGHT	MIN. SPREAD	NOTES
192-6002	Golden Groundsel	<i>Packera obovata</i>	24	1 GAL.	12" O.C.	6"	6"	Container grown
	Frogfruit	<i>Phyla nodiflora</i>	59	1 GAL.	12" O.C.	6"	6"	Container grown
	Zexmenia	<i>Wedelia texana</i>	20	1 GAL.	30" O.C.	6"	6"	Container grown
		<b>TOTAL:</b>	<b>103</b>	1 GAL.				
192-6004	Crossvine	<i>Bignonia capreolata</i>	4	5 GAL.	30" O.C.	12"	4'	Container grown
	Purple Trailing Lantana	<i>Lantana montevidensis</i>	10	5 GAL.	30" O.C.	12"	12"	Container grown, Purple flower
	Texas Sedge	<i>Carex texensis</i>	27	5 GAL.	18" O.C.	12"	12"	Container grown
	Dwarf Yaupon	<i>Ilex vomitoria 'Compacta'</i>	9	5 GAL.	4.5' O.C.	12"	12"	Container grown
		<b>TOTAL:</b>	<b>50</b>	5 GAL.				
192-6025	Texas Redbud	<i>Cercis canadensis var. texensis</i>	6	45 GAL.	12' O.C.	8'	4'	Container grown, multi-trunk
	Texas Mountain Laurel	<i>Sophora secundiflora</i>	3	45 GAL.	10' O.C.	5'	3'	Container grown, multi-trunk
		<b>TOTAL:</b>	<b>9</b>	45 GAL.				

#### PLANT REQUIREMENTS

1. PROVIDE PLANTS THAT ARE NURSERY GROWN IN CONTAINERS.
2. PROVIDE 48 HOUR NOTICE OF DELIVERY OF PLANT MATERIAL PRIOR TO ARRIVAL AT PROJECT SITE OR STORAGE AREA. PROVIDE DOCUMENTATION FROM DELIVERY SOURCE SHOWING QUANTITIES, SIZE, AND NAME OF PLANTS (COMMON AND BOTANICAL) THAT MATCHES NAMES SHOWN IN THE PLANS. TXDOT LANDSCAPE ARCHITECT TO INSPECT PLANTS PRIOR TO INSTALLATION.
3. PROVIDE PLANS FOR WATER AND CARE OF PLANTS THAT WILL BE STORED AT THE SITE, FOR APPROVAL.
4. PROPERLY HANDLE AND MAINTAIN PLANTS DURING DELIVERY, STORAGE, AND INSTALLATION. PLANTS THAT SHOW SIGNS OF DAMAGE OR STRESS, MAY BE REJECTED AT ANY TIME. COVER AND PROTECT THE PLANTS DURING TRANSPORT TO PREVENT DAMAGE TO FOLIAGE, LIMBS, AND TRUNKS FROM WIND, HEAT, BREAKAGE, SCARRING, ABRASIONS, AND DRYING.
5. IF REQUESTED, SUBMIT FOR APPROVAL, A DIGITAL PHOTO OF EACH PLANT SPECIES PROCURED FOR THE PROJECT, TO BE USED AS AN EXAMPLE OF THE PLANT. TAKE PHOTOS WITH A MEASURING STICK OR POLE, CLEARLY VISIBLE IN THE PHOTO, TO VERIFY SIZE REQUIREMENTS.

#### REPAIR OF DISTURBED AREAS

1. REPAIR AND RESEED ALL BARE OR DISTURBED AREAS THAT OCCUR AS A RESULT OF WORK ACTIVITIES, INCLUDING VEHICLES, EQUIPMENT, STOCKPILING, STORAGE, ETC., DURING THIS CONTRACT.
2. CORRECT GRADES AND ESTABLISH TURF WITH SEEDING AND WATERING, AS DIRECTED, UNTIL AN ACCEPTABLE COVERAGE HAS BEEN ATTAINED AND APPROVED. RYE GRASS IS NOT ALLOWED.
3. THIS WORK IS CONSIDERED SUBSIDIARY, AND WILL NOT BE PAID FOR SEPARATELY.

#### WARRANTY

1. ASSUME RESPONSIBILITY FOR KEEPING PLANTS AND TREES IN A HEALTHY, GROWING CONDITION AND THE IRRIGATION SYSTEM FUNCTIONING, THROUGHOUT THE PROJECT DURATION.
2. REPLACE DEAD OR UNACCEPTABLE PLANT MATERIAL, ACCORDING TO ITEM 192, AS DIRECTED.
3. REPLACE DEAD OR UNACCEPTABLE PLANT MATERIAL UNDER ITEM 193, ONLY AS DIRECTED BY THE ENGINEER. PLANT REPLACEMENTS UNDER ITEM 193 WILL BE PAID FOR SEPARATELY.
4. CORRECT IRRIGATION PROBLEMS, REPLACE DAMAGED, FAILED, OR DEFICIENT EQUIPMENT AND/OR MATERIALS, AND CORRECT UNACCEPTABLE WORKMANSHIP, AS DIRECTED. FAILURE TO COMPLY WILL RESULT IN FORFEITED PAYMENTS.
5. PLANT MATERIAL THAT IS IN DORMANCY WILL NOT BE EVALUATED UNTIL OTHER PLANTS OF SAME SPECIES ARE LEAFED-OUT. REMOVAL AND DISPOSAL OF DAMAGED OR REJECTED MATERIAL IS INCIDENTAL TO ITEM 192.
6. PLANTS OR WORK THAT IS DAMAGED BY ACTIONS DESCRIBED IN ITEM 7.17.1. WILL BE REIMBURSED IN ACCORDANCE WITH THAT ITEM, AS DIRECTED. THEFT IS NOT A REIMBURSABLE REPAIR.
7. REMOVAL AND DISPOSAL OF DAMAGED OR REJECTED MATERIAL IS INCIDENTAL TO THE VARIOUS BID ITEMS.



DocuSigned by:  
**Hilary Garnish**  
 F9BEE0CACE074A7  
 12/11/2023


**Austin District  
 Central Design**



**US 183  
 LOCKHART GCAA  
 PLANTING SPECIFICATIONS  
 & QUANTITIES**

© 2024	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY		SHEET NO.
	AUS	CALDWELL		17






**QUICK-COUPLER VALVE**

SECTION

NOTE: AT END OF PROJECT, SUBMIT 1 QUICK-COUPLER KEY WITH ATTACHED SWIVEL HOSE BIB

NTS




**BACKFLOW PREVENTER**

IN-GROUND INSTALLATION

SECTION

NTS




**RAIN SENSOR**

SECTION - PLACE WITHIN BED AREA

PLACE RAIN SENSOR POST AS DIRECTED. DO NOT EXCEED MAXIMUM WIRE DISTANCE LIMITS FROM CONTROLLER TO SENSOR.


NTS



**DRIP VALVE ASSEMBLY**

SECTION - PLACE WITHIN BED AREA


NTS



**TYPICAL HYDRANT METER ASSEMBLY**

NOTE: CONTRACTOR IS RESPONSIBLE FOR SECURITY OF TEMPORARY HYDRANT METERS. SECURE TEMPORARY HYDRANT METERS AGAINST THEFT OR VANDALISM.


NTS



**DRIP VALVE ASSEMBLY**

PLAN - PLACE WITHIN BED AREA

NTS




**DRIP VALVE ASSEMBLY**

PLAN - PLACE WITHIN BED AREA

NTS

**NOTES:**

1. SUBMIT AN IRRIGATION DESIGN FOR AN UNDERGROUND, AUTOMATIC, IRRIGATION SYSTEM OPERATED BY CONTROLLERS, DESIGNED BY A LICENSED IRRIGATOR, AS LICENSED BY TCEQ. INCLUDE CALCULATIONS OF FLOW, PIPE SIZES, VALVES, ZONES, BACKFLOW PREVENTION DEVICE, AND OTHER DEVICES AND INFORMATION AS REQUIRED BY TCEQ. SUBMIT PLAN TO ENGINEER FOR APPROVAL.
2. PROVIDE TEMPORARY HYDRANT METERS FROM THE LOCAL WATER AUTHORITY. ESTABLISH ACCOUNT(S) FOR WATER SERVICE AND PAY FOR ALL FEES AND INSPECTIONS. PROVIDE AND PAY FOR WATER USAGE THROUGHOUT THE CONTRACT. REQUIREMENTS AND RESTRICTIONS REGARDING TEMPORARY HYDRANT PERMITS VARY FROM ONE WATER AUTHORITY TO ANOTHER. BE AWARE OF TIME LIMITATIONS, PENALTIES, FINES, AND/OR FEES INCLUDED IN PERMITS FOR TEMPORARY HYDRANT METERS.
3. PROVIDE AND PAY FOR BACKFLOW PREVENTION DEVICES THAT ARE APPROVED BY THE LOCAL WATER AUTHORITY. PAY FOR INSPECTIONS, AND MAINTENANCE OF BACKFLOW PREVENTION DEVICES.
4. BURY ALL IRRIGATION LINES THAT ARE DOWNSTREAM FROM TEMPORARY HYDRANT METER. USE SCHEDULE 40 PVC FOR ALL UNDERGROUND LINES AND SCHEDULE 80 PVC FOR ALL ABOVE GROUND LINES.
5. PROVIDE CASED BORES, ACCORDING TO ITEM 170, FOR CROSSING DRIVES, SIDEWALKS, AND ROADWAYS. CASED BORES FOR IRRIGATION PURPOSES ARE CONSIDERED SUBSIDIARY TO ITEM 170.
6. PROVIDE A MANUAL SHUT-OFF VALVE FOR IRRIGATION MAIN LINE NEAR THE WATER SOURCE (HYDRANT METER). PLACE VALVE IN SEPARATE, IN-GROUND, VALVE BOX. MARK AS "SHUT-OFF."
7. PROVIDE QUICK COUPLERS THAT CAN CONNECT TO HOSES TO REACH ALL PLANTED AREAS.
8. PROVIDE AIR RELIEF VALVES AT THE HIGHEST POINT AND FLUSH VALVES AT THE LOWEST POINT IN EACH SECTION (ZONE) AS REQUIRED. PLACE AIR RELIEF VALVES IN VALVE BOXES.
7. ALL FEES, COSTS, DEVICES, MATERIALS, AND LABOR ASSOCIATED WITH THE IRRIGATION SYSTEMS ARE CONSIDERED SUBSIDIARY TO ITEM 170.




NOTE: SURROUND ALL IRRIGATION VALVE BOXES WITH CONCRETE APRONS AS SHOWN. ONE APRON MAY SURROUND TWO OR MORE BOXES WHEN CLUSTERED TOGETHER. CONCRETE APRONS ARE CONSIDERED SUBSIDIARY TO ITEM 170.

**CONCRETE APRON FOR VALVE BOXES**

PLAN


NTS



**CONTROLLER ON POST**

MOUNT

NTS



**Austin District Central Design**

Texas Department of Transportation


**IRRIGATION DETAILS**

SHEET 1 OF 2


© 2023	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	18	

DATE: \$DATE\$  
FILE: \$FILES\$







INDIVIDUAL EMITTER PLACEMENT - 1 GAL. CONTAINER NTS




INDIVIDUAL EMITTER PLACEMENT - 5 GAL. CONTAINER NTS



INDIVIDUAL EMITTER PLACEMENT - 45 GAL. CONTAINER NTS




DRIP TUBING LAYOUT NTS



RISER DETAIL FOR SUPPLY HEADER TO DRIP TUBING NTS

DRIP IRRIGATION NOTES:

- TOTAL NUMBER OF EMITTERS AND LATERALS SHALL NOT ALLOW FOR GPM (GALLONS PER MINUTE) FLOWING THROUGH ONE SECTION AND ONE FILTER TO EXCEED 20 GPM. STAKE REMOTE CONTROL VALVE ASSEMBLY AND QUICK COUPLER LOCATIONS FOR ENGINEER'S APPROVAL.
- PLACE VALVE ASSEMBLIES AND QUICK COUPLER VALVES IN ACCESSIBLE LOCATIONS, AS DIRECTED. SURROUND VALVES WITH CONCRETE APRON. (SEE DETAIL)



• ALTERNATE MATERIALS AND DEVICES MUST BE EQUIVALENT SUBSTITUTIONS AND MUST BE APPROVED BY ENGINEER, PRIOR TO INSTALLATION.

THIS IS ONLY A PARTIAL LIST OF COMPONENTS AND MATERIALS. PROVIDE ALL COMPONENTS AND MATERIALS NEEDED TO COMPLETE A FULLY FUNCTIONING IRRIGATION SYSTEM. ENSURE THAT ALL COMPONENTS ARE COMPATIBLE.

EMITTER PLACEMENT SCHEDULE		
PLANT CONTAINER SIZE	EMITTER	
	QTY	NOMINAL FLOW
45 GAL. CONTAINER	8	2 GPH
5 GAL. CONTAINER	2	2 GPH
1 GAL. CONTAINER	1	2 GPH


NOTE: LAYOUTS SHOWN ARE FOR EXAMPLE ONLY. ACTUAL DRIP LAYOUTS MAY DIFFER DEPENDING ON BED FORMS AND SITE CONSTRAINTS.

KEEP TUBING LENGTH AND FLOW WITHIN MAXIMUM LIMITS AND KEEP DRIP SECTIONS SIMILAR IN SIZE.

DRIP TUBING SECTION (TYP) SHALL BE APPROX. EQUAL TO OTHER SECTION SIZES.

IRRIGATION SCHEDULE *		
WEEK AFTER PLANTING	IRRIGATION INTERVAL	RUN TIME
1 THRU 6	2 DAYS	45 MINUTES
7 THRU 12	3 DAYS	45 MINUTES
13 THRU 104	7 DAYS	45 MINUTES
105 AND BEYOND	AS NEEDED	2 GPH

12/11/2023



Designed by:  
*Hilary Garnish*  
F9BEE0ACED74A7...

• THE IRRIGATION SCHEDULE SHOWN, IS A SUGGESTED BASELINE STARTING SCHEDULE AFTER ALL PLANTS HAVE BEEN THOROUGHLY WATERED AND TREES HAVE BEEN WATERED TO THE BOTTOM OF ROOT ZONES ON THE SAME DAY AS THEY ARE PLANTED.

ADJUST THIS SCHEDULE TO ACCOMMODATE SEASONAL WEATHER CONDITIONS AND LOCAL WATERING RESTRICTIONS.

BE RESPONSIBLE FOR MONITORING PLANT MATERIAL TO ENSURE IT RECEIVES PROPER DISTRIBUTION OF WATER FOR THRIVING GROWTH AND ADJUST SCHEDULE ACCORDINGLY.

CHECK SOIL MOISTURE FREQUENTLY TO ENSURE THAT BED AREA IS DRAINING PROPERLY AND PLANTS ARE NOT BEING OVER-WATERED, OR UNDER-WATERED.

IRRIGATION MATERIALS SPECIFICATIONS

DESCRIPTION	EXAMPLE OR EQUAL	SIZE	REMARKS
RPZ BACKFLOW PREVENTER	AS APPROVED BY LOCAL CODE	as required	
VALVE ASSEMBLY:	RAINBIRD XCZ-PRB-100-COM or XCZ-PRB-150-COM w/ PRESSURE REGULATING QUICK-CHECK BASKET FILTER and BALL VALVE	as required	Ensure that all parts and devices are compatible and provide rates, flows, and other factors that are within acceptable limits according to the guidelines of the manufacturer.
AC POWERED CONTROLLER W/ RAIN/FREEZE SENSOR	HUNTER PRO HC OR APPROVED EQUAL (wifi enabled)	compatible solenoids	
RAIN/FREEZE SENSOR	HUNTER RFC or EQUAL		Attach to post as shown in plans.
DRIP TUBING	XT-700 OR EQUAL		Ensure all flow rates, pressures, filtration mesh and other items comply with the guidelines of the manufacturer.
DRIP EMITTERS	XERI-BUG or EQUAL	2.0 GPH	Pressure compensating
QUICK COUPLERS	RAINBIRD OR EQUAL	as required	slotted key w/ swivel hose attachment
PVC PIPE	USE SCH. 40 FOR ALL UNDERGROUND MAIN LINES, AND LATERAL LINES USE SCH. 80 FOR ALL CASED BORE AND ABOVE GROUND PURPOSES.		

**Austin District  
Central Design**

Texas Department of Transportation

## IRRIGATION DETAILS

SHEET 2 OF 2

© 2023	CONT	SECT	JOB	HIGHWAY
	0152	02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	19	

DATE: \$DATE\$  
FILE: \$FILE\$

DATE: 12/11/2023 10:55:32 AM FILE: D:\t\tdot\project\wisconsin\14 - AUS\Design Projects\015202071\4 - AUS\Design Projects\015202071\4 - Design\Plan Set\10 - Miscellaneous\Plans\LANDSCAPE\_ESTAB.dgn

ITEM 193 LANDSCAPE ESTABLISHMENT				TIMELINE (Days) Repeat as Necessary																																																				
DESCRIPTION OF WORK				1	8	16	23	31	38	46	53	61	68	76	83	91	98	106	113	121	128	136	143	151	158	166	173	181	188	196	203	211	218	226	233	241	248	256	263	271	278	286	293	301	308	316	323	331	339	347	355					
				7	15	22	30	37	45	52	60	67	75	82	90	97	105	112	120	127	135	142	150	157	165	172	180	187	195	202	210	217	225	232	240	247	255	262	270	277	285	292	300	307	315	322	330	338	346	354	362					
PLANT MAINTENANCE	EVERY TWO WEEKS	INSPECT & TREAT	NOTIFY THE ENGINEER AT FIRST SIGN OF INSECT, DISEASE, ANIMAL DAMAGE, THEFT, VANDALISM, OR GRAFFITI.	EVERY 2 WEEKS	*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*	
		WEEDING	KEEP PLANTING BEDS FREE OF WEEDS AND INVASIVES. DO NOT USE STRING TRIMMERS NEAR PLANTS/TREES. ONLY USE WICKING METHOD TO APPLY HERBICIDE IN BED AREAS. REMOVE DEAD PLANTS FROM PROJECT SITE.	EVERY 2 WEEKS		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		
		REMOVE LITTER	REMOVE LITTER FROM PLANTING BEDS, INCLUDING ANY MATERIAL CLINGING TO BRANCHES.	EVERY 2 WEEKS		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		
	EVERY TWO TO FOUR WEEKS - SEASONAL	MOWING	PRIOR TO MOWING, REMOVE LITTER FROM MOWING AREA. MOW TO A 5 FOOT BORDER AROUND PLANT BEDS. MOW TO A HEIGHT OF 4 INCHES. - MOW EVERY TWO WEEKS FROM MAR. 1 TO OCT. 31. - MOW ONCE A MONTH FROM NOV. 1 TO FEB. 28.	EVERY 2 WEEKS MARCH 1 TO OCTOBER 31		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		
				EVERY 4 WEEKS NOVEMBER 1 TO FEBRUARY 28				*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		
	EVERY FOUR WEEKS	PLANT SUPPORTS	INSPECT AND REPAIR, ADJUST, OR ADD PLANT SUPPORTS TO KEEP TREES IN UPRIGHT POSITION. REPLACE TREES DAMAGED BY STAKING NEGLIGENCE, AT CONTRACTOR'S EXPENSE.	EVERY 4 WEEKS			*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*	
REMOVE ALL TREE SUPPORTS AT THE END OF THE CONTRACT. (AT THE END OF ITEM 193).			REMOVE PLANT SUPPORTS AND SUPPORT MATERIALS AT END OF CONTRACT.																																																					
PRUNING		MAINTAIN A NATURAL SHAPE. REMOVE SUCKER GROWTH FROM TRUNKS. TRIM TO REMOVE LIMBS THAT MAY IMPAIR VEHICLE, BICYCLE, OR PEDESTRIAN SAFETY.	EVERY 4 WEEKS			*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		
EVERY 12 WEEKS	MULCH	APPLY MULCH AS REQUIRED TO MAINTAIN THE SPECIFIED DEPTH. KEEP MULCH 3" AWAY FROM TRUNKS.	EVERY 12 WEEKS							*				*					*				*				*				*				*				*				*				*			*		*				
PLANT REPLACEMENT	AS DIRECTED	INSPECT & REPLACE	REPLACE DEAD, DAMAGED, OR MISSING PLANTS WITH THE SAME SIZE AND TYPE SPECIFIED IN THE PLANS, AS DIRECTED. PLANTS THAT ARE DEAD, DAMAGED, OR MISSING AS A RESULT OF THEFT, CONTRACTOR'S NEGLIGENCE, OR CONSTRUCTION ACTIVITIES WILL BE REPLACED AT THE CONTRACTOR'S EXPENSE.	SCHEDULE PLANT REPLACEMENT AS DETERMINED BY THE ENGINEER.																																																				
IRRIGATION OPER. & MAINT.	EVERY TWO WEEKS	INSPECT	MONITOR IRRIGATION FOR LEAKS AND PROPER OPERATION. CHECK WATER DISTRIBUTION, SOIL MOISTURE, AND DRAINAGE.	EVERY 2 WEEKS	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*
		MAINT.	MAINTAIN IRRIGATION SYSTEM ACCORDING TO ITEM 193. RE-BURY EXPOSED DRIP TUBING. REPLACE STRESSED, DAMAGED, OR DEAD PLANTS RESULTING FROM NEGLIGENCE AT CONTRACTOR'S EXPENSE. IMMEDIATELY SHUT-DOWN THE SYSTEM IF DAMAGE OR LEAKS OCCUR. MAKE REPAIRS WITHIN TWO WEEKS OF SHUT DOWN. NOTIFY ENGINEER WHEN REPAIRS ARE MADE. REPLACE BATTERIES AS NEEDED.	EVERY 2 WEEKS		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		*		

\* = WORK REQUIRED DURING DEFINED PERIOD OF TIMELINE. ALL WORK MUST BE COMPLETED OVER ENTIRE PROJECT TO BE CONSIDERED COMPLETE.


**IRRIGATION NOTES:**

- SUBMIT "AS-BUILT" IRRIGATION DRAWINGS BY MARKING IN RED, ALL LOCATIONS OF VALVES AND IRRIGATION DEVICES. SHOW ANY CHANGES IN PIPE ROUTING. PROVIDE "AS-BUILT" DRAWINGS ON 11"x17" PLAN SHEETS, PRODUCED AND SEALED BY A LICENSED IRRIGATOR, AND SUBMIT TO THE ENGINEER PRIOR TO CLOSING OUT PROJECT AND RECEIVING FINAL RETAINAGE.
- BE AWARE OF TIME LIMITATIONS AND OTHER INFORMATION ON THE TEMPORARY HYDRANT WATER METER PERMITS ACQUIRED THROUGH LOCAL WATER AUTHORITIES. RE-APPLY FOR NEW PERMIT PRIOR TO THE EXPIRATION DATE, AS STATED ON THE PERMIT.

**PLANTING NOTES:**

- ASSUME RESPONSIBILITY FOR KEEPING PLANTS AND TREES IN A HEALTHY, GROWING CONDITION AND THE IRRIGATION SYSTEM FUNCTIONING.
- REPLACE DEAD OR UNACCEPTABLE PLANT MATERIAL, CORRECT IRRIGATION PROBLEMS, REPLACE DAMAGED, FAILED, OR DEFICIENT EQUIPMENT AND/OR MATERIALS, AND CORRECT UNACCEPTABLE WORKMANSHIP, AS DIRECTED. FAILURE TO COMPLY WILL RESULT IN FORFEITED PAYMENTS.
- PLANT MATERIAL THAT IS IN DORMANCY WILL NOT BE EVALUATED UNTIL OTHER PLANTS OF SAME SPECIES ARE LEAFED-OUT. REMOVAL AND DISPOSAL OF DAMAGED OR REJECTED MATERIAL IS INCIDENTAL TO ITEM 192.
- PLANTS OR WORK THAT IS DAMAGED BY ACTIONS DESCRIBED IN ITEM 7.1.B.1. WILL BE REIMBURSED IN ACCORDANCE WITH THAT ITEM, AS DIRECTED. THEFT IS NOT A REIMBURSABLE REPAIR.
- CHEMICAL FERTILIZATION IS NOT INCLUDED AS PART OF THIS CONTRACT.
- REMOVAL AND DISPOSAL OF DAMAGED OR REJECTED MATERIAL IS INCIDENTAL TO THE VARIOUS BID ITEMS.

12/11/2023



**Austin District Central Design**











Texas Department of Transportation

**US 183 LANDSCAPE ESTABLISHMENT**

SHEET 1 OF 1

© 2024	CONT	SECT	JOB	HIGHWAY
0152	02		071	US 183
		DIST	COUNTY	SHEET NO.
AUS		CALDWELL		20

DATE: 12/11/2023 10:55:49 AM  
FILE: pwt://txdot.projectwiseonline.com:TXDOT4/Documents/14 - AUS/Design Projects/015202071/4 - Design/Plan Set/10. Miscellaneous/Plans/US 183 LIGHTING DETAILS



COND'T (PVC)  
SCH (40) (3/4")

**NOTES:**

**Landscape Amenity (TY 1) - LED White Linear Lighting**


1. Provide electronic submittals of the complete fixture to the Engineer at the project address. Obtain the Engineer's approval on the submittals before beginning work.
2. Lighting design is based on American Lighting Hybrid 3 linear tape lighting. Provide this or an equivalent system according to the following specifications:

- A. Flexible LED strip light with cross section 11/16"W x 5/16"H.
- B. White 5000K LEDs spaced every 5/8", 20 LEDs per foot, 4W per foot.
- C. Capable of run length up to 150'.
- D. Lighting system operates at 120V AC
- E. Ensure fixture is UL listed for wet locations and rated IP65.
- F. Install tape light approximately 6 in. from gabion walls. Orient strips so LEDs are aimed outward to shine through glass rocks.
- G. Power tape lights with a 120V circuit directly wired to the tape light in a junction box instead of with an external plug. Include fusing as recommended by manufacturer.

3. Landscape Amenity (TY 1) includes furnishing, installing, testing, and aiming luminaires; drivers, LEDs, internal conductors, power cables, connections, and brackets; system performance testing; and equipment, labor, tools, and incidentals.

**Landscape Amenity (TY 2) - GFCI Receptacle**

1. Provide 120 VAC receptacles surface mounted to the gabions in metal outlet boxes and with gasketed weather protective outdoor "While in Use" lockable covers. Install NEMA Type 5-20R, 120 VAC GFCI duplex receptacles. Locate the receptacles as shown in the plans.



**Austin District  
Traffic Operations**

**Texas Department of Transportation**

**US 183  
LOCKHART GCAA  
LIGHTING DETAILS**

SHEET 1 OF 1

© 2024	CONT	SECT	JOB	HIGHWAY
DS: CR:	0152	02	071	US 183
DW: CR:	DIST		COUNTY	SHEET NO.
AUS		CALDWELL		21



**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For all projects with any soil disturbing activities, TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office. If no field office is available, then this SWP3 shall be kept at the appropriate TxDOT Area Office.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**

0152-02-071

**1.2 PROJECT LIMITS:**

From: CEMETERY STREET

To: CITY PARK ROAD

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 29.8896, (Long) -97.670950

END: (Lat) 29.8887999, (Long) -97.6709094

**1.4 TOTAL PROJECT AREA (Acres): 0.66 AC**

**1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.14 AC**

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

LANDSCAPING & IRRIGATION

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
BrB	Branyon clay, 1 to 3 percent slopes, frequently flooded

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
  - Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
  - Excavate and prepare subgrade for proposed pavement widening
  - Remove existing culverts, safety end treatments (SETs)
  - Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
  - Install culverts, culvert extensions, SETs
  - Install mow strip, MBGF, bridge rail
  - Place flex base
  - Rework slopes, grade ditches
  - Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- Other: Excavation, Removing Concrete

Other: Plant Bed Preparation

Other: Install gabions, install Decorative Fence  
Install Irrigation system, Planting, install lighting

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
  - Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
  - Long-term stockpiles of material and waste
  - Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
	Town Branch (1810A)


\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_



**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)**

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
	SEE TITLE SHEET			22
STATE	STATE DIST.	COUNTY		
TEXAS		CALDWELL		
CONT.	SECT.	JOB	HIGHWAY NO.	
0152	02	071	US 183	



**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

\_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**


- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

**2.9 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



DocuSign  
Hilary Garnish  
F9BEE09A5E974A7  
12/11/2023

**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)**

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
	SEE TITLE SHEET			23
STATE	STATE DIST.	COUNTY		
TEXAS		CALDWELL		
CONT.	SECT.	JOB	HIGHWAY NO.	
0152	02	071	US 183	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.  
2.  
 No Action Required     Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required  
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)  
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)  
 Individual 404 Permit Required  
 Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.  
2.  
3.  
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

**Best Management Practices:**

<b>Erosion</b>	<b>Sedimentation</b>	<b>Post-Construction TSS</b>
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input checked="" type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input checked="" type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input checked="" type="checkbox"/> Grassy Swales

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

- No Action Required     Required Action

Action No.

1. Since this project involves vegetation which could contain nesting birds, the following general note for migratory birds should also be added to the plans:

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MFTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes     No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes     No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required     Required Action

Action No.

1.  
2.  
3.


**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required     Required Action

Action No.

1.  
2.  
3.

 Texas Department of Transportation		Design Division Standard
<b>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC</b>		
FILE: epic.dgn	DNR TxDOT	CR: RG    DNR: VP    CR: AR
© TxDOT: February 2015	CONT SECT	JOB HIGHWAY
12-12-2011 (DS) REVISIONS	0152 02	071 US 183
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	AUS	CALDWELL 24

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT or any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this information into any other format or for the use of this information on any project.

DATE: 12/11/2023 10:56:51 AM  
 FILE: D:\t\tdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\0152001174 - Design\14 - AUS\14-001-001.dgn

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12



**BARRICADE AND CONSTRUCTION  
GENERAL NOTES  
AND REQUIREMENTS**


**BC (1) - 21**

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0152 02	071	US 183
4-03 7-13				
9-07 8-14				
5-10 5-21	AUS	CALDWELL		25




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "X" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25	36" x 36"	48" x 48"	50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14			55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12			60	600 <sup>2</sup>
			65	700 <sup>2</sup>
	48" x 48"	48" x 48"	70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
	Type 3 Barricade
	Channelizing Devices
	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

BARRICADE AND CONSTRUCTION PROJECT LIMIT


BC (2) - 21

FILE: bc-21.dgn	DWG: TxDOT	CR: TxDOT	DWG: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152 02		071	US 183
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	AUS	CALDWELL		26

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard for any purpose other than that for which it was intended.

DATE: 12/11/2023 10:57:01 AM  
FILE: \\txdot.projectwiseonline.com:TXDOT14\Documents\14 - AUS\Design Projects\14-15000172-01\14-15000172-01.dgn

**SHEET 3 OF 12**

Traffic Safety Division Standard

## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


### BC (3) -21

FILE: bc-21.dgn	DNR TxDOT	CR: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
9-07 8-14	0152	02	071	US 183
7-13 5-21	DIST	COUNTY	SHEET NO.	
AUS	CALDWELL	<b>27</b>		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect or damages resulting from its use.

DATE: 12/11/2023 10:57:07 AM  
 FILE: Pw://ttdot.projectwiseonline.com:TXDOT4/Documents/14 - AUS/Design Projects/015202071/4 - Design/Plan Set/2 - TCP/015202071 TXDOT STANDARDS.dgn


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.


ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectorized when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS


- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12

		<b>Traffic Safety Division Standard</b>	
<h2>BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES</h2>			
<h3>BC (4) -21</h3>			
FILE:	bc-21.dgn	DWG: TxDOT	CR: TxDOT
© TxDOT	November 2002	CONT: 0152 02	SECT: 071
REVISIONS			
9-07	8-14		
7-13	5-21	DIST: AUS	COUNTY: CALDWELL
			SHEET NO.: 28




DATE: 12/11/2023 10:57:17 AM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT4/Documents/14 - AUS/Design Projects/01520201/14 - Design/Plan Set/2-CP/01520201 TXDOT STANDARDS.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results resulting from its use.




**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS




**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**WEDGE ANCHORS**  
 Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**  
 MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- \* See BC(4) for definition of "Work Duration."
- \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC (5) - 21**

FILE: bc-21.dgn	DWF: TxDOT	CR: TxDOT	DWG: TxDOT	CR: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	<b>0152 02</b>		<b>071</b>	<b>US 183</b>
9-07 <b>8-14</b>	DIST	COUNTY	SHEET NO.	
7-13 5-21	<b>AUS</b>	<b>CALDWELL</b>	<b>29</b>	

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLRS
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

Other Condition List

ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT

ROAD REPAIRS XXXX FT
LANE NARROWS XXXX FT
TWO-WAY TRAFFIC XX MILE
CONST TRAFFIC XXX FT
UNEVEN LANES XXXX FT
ROUGH ROAD XXXX FT
ROADWORK NEXT FRI-SUN
US XXX EXIT X MILES
LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE *

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

\*\* Advance Notice List

TUE-FRI XX AM-XX PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS


- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

<p><b>BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)</b></p> <p><b>BC (6) -21</b></p>			
FILE: bc-21.dgn	DWG: TxDOT	CR: TxDOT	CHK: TxDOT
© TxDOT November 2002	CONT: 0152	SECT: 02	JOB: 071
9-07	8-14	US 183	
7-13	5-21	DIST: AUS	COUNTY: CALDWELL
			SHEET NO. 30


DATE: 12/11/2023 10:57:26 AM  
 FILE: p:\t\dot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\0152020174 - Design\Plan Set\2 - TPCP\0152020174 - TXDOT - STANDARDS.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for increasing the number of characters per word.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/11/2023 10:57:33 AM  
 FILE: Pw://txdot.projectwiseonline.com:TXDOT4/Documents/14 - AUS/Design Projects/015202071 - Design/Plan Set/2 - TCP/015202071 TXDOT STANDARDS.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)



LOW PROFILE CONCRETE BARRIER (LPCB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




DELINEATION OF END TREATMENTS

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**

- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**


- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Traffic Safety Division Standard

## BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 21

FILE: bc-21.dgn	DWG: TxDOT	CR: TxDOT	DWG: TxDOT	CR: TxDOT
© TxDOT November 2002		CONT: 0152	SECT: 02	JOB: 071
REVISIONS		0152	02	071
9-07	8-14	DIST: AUS	COUNTY: CALDWELL	SHEET NO.: 31
7-13	5-21			



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 12/11/2023 10:57:39 AM  
 FILE: P:\t\dot\project\wiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\015202071 - Design\Plan Set\2 - TCP\015202071 TXDOT STANDARDS.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**



- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
  - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
  - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
  - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
  - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
  - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
  - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
  - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
  - Drum body shall have a maximum unballasted weight of 11 lbs.
  - Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



This detail is not intended for fabrication. See note 3 and the CWZTCD list for providers of approved Detectable Pedestrian Barricades



18" x 24" Sign (Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, or merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE:	bc-21.dgn	DWG:	TxDOT	CHK:	TxDOT	APP:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY				
REVISIONS		0152	02	071	US 183				
4-03	8-14	DIST:	COUNTY:		SHEET NO.				
9-07	5-21	AUS	CALDWELL		32				
7-13									


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/11/2023 10:57:44 AM  
 FILE: \\txdot.projectwiseonline.com:TXDOT14\Documents\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\2 - TCP\015202071 TXDOT STANDARDS.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths × ×			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

××Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

**SHEET 9 OF 12**



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**


FILE: bc-21.dgn	DWG: TXDOT	CHK: TXDOT	APP: TXDOT	CR: TXDOT
© TXDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		<b>0152 02</b>	<b>071</b>	<b>US 183</b>
<b>9-07</b>	<b>8-14</b>	DIST	COUNTY	SHEET NO.
7-13	5-21	<b>AUS</b>	<b>CALDWELL</b>	<b>33</b>

DATE: 12/11/2023 10:57:50 AM  
 FILE: P:\t\dot\project\wiseonline.com\TXDOT4\Documents\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\2 - TCP\015202071 TXDOT STANDARDS.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) -21**

FILE: bc-21.dgn	DWG: TxDOT	CR: TxDOT	REV: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152	02	071	US 183
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	AUS	CALDWELL	34	



WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 12/11/2023 10:57:56 AM  
 FILE: pw://txdot.projectwiseonline.com:TXDOT14/Documents/14 - AUS/Design Projects/0152020714 - Design/Plan Set/2 - TCP/015202071 TxDOT STANDARDS.dgn

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11)-21

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		0152 02	071	US 183
2-98 9-07	5-21			
1-02 7-13		DIST	COUNTY	SHEET NO.
11-02 8-14		AUS	CALDWELL	35

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS


BC (12) - 21

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	BY: TxDOT	CR: TxDOT
©TxDOT February 1998		CONT: 0152 02	SECT: 071	JOB: US 183
REVISIONS		SHEET NO.		
1-97	9-07	5-21		
2-98	7-13			
11-02	8-14			
DIST: AUS	COUNTY: CALDWELL			

DATE: 12/11/2023 10:58:01 AM  
 FILE: D:\txdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\0152020714 - Design\Plan Set\2 - TCP\015202071 TXDOT STANDARDS.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the use of this standard in any project or for any damages or expenses resulting from its use.

DATE: 12/11/2023 10:58:08 AM  
 FILE: D:\txdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\14-000001\14-000001.dgn




TCP (1-1a)

WORK SPACE NEAR SHOULDER  
 Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER  
 Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER  
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.




TRAFFIC CONTROL PLAN  
 CONVENTIONAL ROAD  
 SHOULDER WORK

TCP (1-1) - 18


FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152	02	071	US 183
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	AUS	CALDWELL	37	
1-97 2-18				




DATE: 12/11/2023 10:58:16 AM  
 FILE: D:\projects\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\14-0114\14-0114.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for its use.



TCP (1-5a)  
ONE LANE CLOSURE



TCP (1-5b)  
LANE CLOSURE NEAR EXIT RAMP



TCP (1-5c)  
LANE CLOSURE NEAR ENTRANCE RAMP

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	700'	770'	840'	70'	140'	800'	475'	
75	750'	825'	900'	75'	150'	900'	540'	

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

- GENERAL NOTES
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
  - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.


Texas Department of Transportation  
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN  
 LANE CLOSURES FOR  
 DIVIDED HIGHWAYS


**TCP (1-5) - 18**

FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
©TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0152 02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	38	


DATE: 12/11/2023 10:58:23 AM  
 FILE: \\txdot.projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\01220114\01220114.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for its use.




TWO LANE HIGHWAY WITH PAVED SHOULDERS MINIMUM 8'




TWO LANE HIGHWAY WITH NO SHOULDER OR NARROW SHOULDER




MULTILANE HIGHWAY




MULTILANE HIGHWAY




SHADOW VEHICLE A  
with Flashing Arrow Board in Caution Mode



TYPICAL SHADOW VEHICLE B  
with RIGHT Directional display Flashing Arrow Board



TYPICAL SHADOW VEHICLE C  
with LEFT Directional display Flashing Arrow Board



STRIPING FOR TMA

LEGEND

**	Shadow Vehicle	ARROW BOARD DISPLAY	
***	Work Vehicle		RIGHT Directional
	Sign		LEFT Directional
	Heavy Work Vehicle		Double Arrow
	Truck Mounted Attenuator (TMA) or Trailer Attenuator (TA)		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>


GENERAL NOTES

- All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the Shadow Vehicle is required.
- Striping on the back panel of all TMAs shall be 8" red reflective sheeting with white background, placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS-8300, TYPE A.
- Flashing Arrow Panels shall be Type B or Type C as per BC Standards. The panel operation shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When the work convoy must change lanes, the Shadow Vehicle should change lanes first to protect the Work Vehicle.
- Spacing between Shadow and Work Vehicle will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the Shadow Vehicle in time to slow down and/or change lanes as they approach the Work Convoy.
- Use of an arrow panel on the Work Vehicle is optional except as provided in note 13, but may be required by the Engineer. If an arrow panel is not used, dual flashing beacons, mounted as high and as widely separated as practicable at the rear of the Work Vehicle shall be required.
- On two-lane two-way roadways, the Work and Shadow Vehicles should pull over periodically to allow motor vehicle traffic to pass.
- Work and Shadow Vehicles should stay on the shoulder of highways having 8' or wider shoulders when possible.
- A Trail Vehicle may be added to the operation when approved by the Engineer. See TCP (3) series standards.
- The shadow vehicle may be omitted on conventional roadways when a TMA or TA and arrow panel is mounted to the herbicide vehicle. A separate shadow vehicle will be required on expressways and Freeways.

		<b>Traffic Operations Division Standard</b>	
<b>TRAFFIC CONTROL PLAN</b> <b>MOBILE OPERATIONS</b> <b>HERBICIDE TRUCK OPERATIONS</b> <b>TCP (3-5) - 18</b>			
FILE: tcp3-5.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT July 2015	CONT	SECT	JOB
4-18	0152	02	071
	DIST	COUNTY	SHEET NO.
	AUS	CALDWELL	39


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to metric units or for its use.

DATE: 12/11/2023 10:58:30 AM  
 FILE: p:\t\dot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\01220014\01220014.dgn



TCP (5-1a)

WORK AREA ON SHOULDER



TCP (5-1b)

WORK AREA ON SHOULDER

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

GENERAL NOTES

- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
- 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.




TRAFFIC CONTROL PLAN  
 SHOULDER WORK FOR  
 FREEWAYS / EXPRESSWAYS


TCP (5-1) - 18

FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0152 02	071	US 183
	DIST	COUNTY	SHEET NO.	
	AUS	CALDWELL	40	


DATE: 12/11/2023 10:58:38 AM  
 FILE: D:\txdot\projectwise\one\line.com\TXDOT4\Documents\14 - AUS\Design Projects\015202071\4 - Design\Plan Set\2. TCP\015202071 TXDOT STANDARDS.dgn




**LINEAR CONSTRUCTION THROUGH STAND OF TREES**



**PLAN VIEW PAVING UNDER TREES**



**TYPICAL TREE GROUPING PROTECTION**



**TYPICAL TREE PROTECTION**

**NOTES:**

- CRITICAL ROOT ZONE IS 1 FT. AWAY FROM TREE TRUNK FOR EVERY 1 IN. OF TREE DIAMETER MEASURED AT 4 FT. HEIGHT.
- WATER TREES EVERY 2 WEEKS WITH A MINIMUM OF 100 GALLONS PER TREE.
- SPRAY TREE WITH WATER TO REMOVE CONSTRUCTION DUST WHEN DIRECTED.
- CONSTRUCTION FENCE SHALL BE 4 FT. TALL.
- DO NOT PERFORM WORK OR STORE EQUIPMENT WITHIN PROTECTED AREA.
- COVER THE CRITICAL ROOT ZONE BETWEEN THE PROTECTED AREA AND THE CONSTRUCTION ZONE WITH 4 IN. OF MULCH
- PERFORM TREE TRIMMING AND WOUND REPAIR PER STANDARD SPECIFICATIONS.
- DAMAGED AND EXPOSED ROOTS SHALL BE TRIMMED AND TREATED PER STANDARD SPECIFICATIONS. BACKFILL EXPOSED ROOTS WITH TOPSOIL WITHIN 24 HOURS OF EXPOSURE.
- PLACE PLASTIC UNDER CONCRETE PLACED IN THE CRITICAL ROOT ZONE.
- PLACE A ROOT BARRIER IN THE CRITICAL ROOT ZONE AT THE EDGE OF TREATED SUBGRADE TO THE DEPTH OF THE SUBGRADE.
- ALL WORK IS SUBSIDIARY TO BID ITEM.


				Austin District Standard	
<h2>TREE PROTECTION DETAILS</h2>					
<h3>TPD-19 (AUS)</h3>					
©TXDOT 2024 <small>REVISIONS</small> 06/164 SHEET CREATED 04/194 APPROVED	CONT <b>0152</b>	SECT <b>02</b>	JOB <b>071</b>	HIGHWAY <b>US 183</b>	
	DIST <b>AUS</b>	COUNTY <b>CALDWELL</b>		SHEET NO. <b>41</b>	




DATE: 12/11/2023 10:58:43 AM  
 FILE: P:\txdot\projectwiseonline.com\TXDOT14\Documents\14 - AUS\Design Projects\2023\14-000001\14-000001.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to any other format or for its use.

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35'+

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT)  
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.  
 \* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation  
 Traffic Safety Division Standard


TEMPORARY RUMBLE STRIPS

WZ (RS) -22


FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152 02	071	US 183	
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	AUS	CALDWELL	42	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:  
FILE:




**TYPE I CURB (MONOLITHIC)  
2" - 4" HEIGHT**




**TYPE I CURB  
2" - 4" HEIGHT**




**TYPE I CURB AND GUTTER  
2" - 4" HEIGHT**




**TYPE II CURB (MONOLITHIC)  
5" - 5 3/4" HEIGHT**




**TYPE II CURB  
5" - 5 3/4" HEIGHT**




**TYPE II CURB AND GUTTER  
5" - 5 3/4" HEIGHT**




**TYPE III CURB (KEYED)  
2" - 4" HEIGHT**




**TYPE IIa CURB  
5" - 5 3/4" HEIGHT**




**TYPE IIa CURB AND GUTTER  
5" - 5 3/4" HEIGHT**



**TYPE IV CURB (KEYED)  
5" - 5 3/4" HEIGHT**



**EXPANSION JOINT DETAIL**




**CURB TRANSITION**

Note: To be paid for as Highest Curb

**GENERAL NOTES**

- All materials and construction shall be in accordance with Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- Concrete shall be Class A.
- When reinforcing bars are used, they shall be No.4 unless otherwise shown. The use of fiber reinforced concrete in lieu of reinforcing steel is acceptable. Use fibers meeting the requirements of DMS 4550, "Fibers for Concrete," and dose fibers in accordance with Material Producers List (MPL) "Fibers for Class A and B Concrete Applications."
- Round exposed sharp edges with a rounding tool, to a minimum radius of 1/4 inch.
- All existing curbs and driveways to be removed shall be sawed or removed at existing joints.
- Where concrete curb is to be placed on existing concrete pavement, Bar B may be drilled and grouted in place, or may be inserted into fresh concrete.
- Expansion and contraction joints shall be constructed to match pavement joints in all curbs and curb and gutter adjacent to jointed concrete pavement. Where placement of curb or curb and gutter is not adjacent to concrete pavement, expansion joints shall be provided at structures, curb returns at streets, and at locations directed by The Engineer.
- Vertical and horizontal dowel bars and transverse reinforcing bars shall be placed at four feet C-C.
- Dimension 'T' shown is the thickness of concrete pavement. When curb is installed adjacent to flexible pavement dimension 'T' is 8" maximum.
- Usual profile grade line. Refer to typical sections and plan-profile sheets for exact locations.
- One-half inch expansion joint material shall be provided where curb or curb and gutter is adjacent to sidewalk or riprap.
- When horizontal permissible construction joints are used, the longitudinal pavement steel shall be placed in accordance with pavement details shown elsewhere in the plans. Reinforcing steel for curb section shall then conform to that required for concrete curb.
- Bar B placement as needed (typically at four ft. C-C) to support curb reinforcing steel during concrete placement.




**CURB TRANSITION NOTE:**  
Field conditions may require a longer or shorter transition, and shall be shown elsewhere in the plans, or as directed by the Engineer.

		Design Division Standard	
<h2>CONCRETE CURB AND GUTTER</h2>			
<h3>CCCG-22</h3>			
FILE: cccg21.dgn	DNR TxDOT	CR: AN	DWR: CS
© TxDOT: JUNE 2022	CONT: 0152	SECT: 02	JOB: 071
REVISIONS	DIST: AUS	COUNTY: CALDWELL	SHEET NO.: 43

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

**TYPE 1**




**PERPENDICULAR CURB RAMP**

**TYPE 2**




**PARALLEL CURB RAMP**

**TYPE 3**




**COMBINATION CURB RAMPS**

**TYPE 20**




**CURB RAMPS AT MEDIAN ISLANDS**



**TYPE 7**




**DIRECTIONAL RAMPS WITHIN RADIUS**



**TYPE 10**




**TYPE 6**



**BLENDED TRANSITION (FLUSH LANDING)**


INSTALL DETECTABLE WARNING SURFACE AT EACH END OF THE CUT-THROUGH RAMP WITH A MINIMUM 2' USUAL SIDEWALK SURFACE BETWEEN. IF MEDIAN IS LESS THAN 6' WIDE, ELIMINATE DETECTABLE WARNING SURFACES.

**TYPE 21**




NOTE: CURB DETAILS ARE SHOWN ELSEWHERE IN THE PLANS.

**TYPE 22**



**COMBINATION ISLAND RAMPS**

BOTTOM GRADE BREAK OF CURB RAMP WILL NORMALLY BE AT GUTTER LINE. SURFACE SLOPES AT GRADE BREAKS SHALL BE FLUSH.



**TYPICAL SECTION OF PERPENDICULAR CURB RAMP AT CONNECTION TO ROADWAY**

**NOTES / LEGEND:**

SEE GENERAL NOTES ON SHEET 2 OF 4 FOR MORE INFORMATION.

DENOTES PLANTING OR NON-WALKING SURFACE NOT PART OF PEDESTRIAN CIRCULATION PATH.



DENOTES PREFERRED LOCATION OF PEDESTRIAN PUSH BUTTON IF APPLICABLE.



GUTTER LINE

GRADE BREAK

RAMP LIMITS OF PAYMENT



**PEDESTRIAN FACILITIES CURB RAMPS**

**PED-18**

FILE: ped18	DW: TxDOT	DW: VP	CK: KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152	02	071	US 183
REVISED 08, 2005	DIST	COUNTY		SHEET NO.
REVISED 06, 2012	AUS	CALDWELL		44
REVISED 01, 2018				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

## GENERAL NOTES

### CURB RAMP

1. Install a curb ramp or blended transition at each pedestrian street crossing.
2. All slopes shown are maximum allowable. Cross slopes of 1.5% and lesser running should be used. Adjust curb ramp length or grade of approach sidewalks as directed.
3. Maximum allowable cross slope on sidewalk and curb ramp surfaces is 2%.
4. The minimum sidewalk width is 5'. Where the sidewalk is adjacent to the back of curb, a 6' sidewalk width is desirable. Where a 5' sidewalk cannot be provided due to site constraints, sidewalk width may be reduced to 4' for short distances. 5' x 5' passing areas at intervals not to exceed 200' are required.
5. Turning Spaces shall be 5' x 5' minimum. Cross slope shall be maximum 2%.
6. Clear space at the bottom of curb ramps shall be a minimum of 4' x 4' wholly contained within the crosswalk and wholly outside the parallel vehicular travel path.
7. Provide flared sides where the pedestrian circulation path crosses the curb ramp. Flared sides shall be sloped at 10% maximum, measured parallel to the curb. Returned curbs may be used only where pedestrians would not normally walk across the ramp, either because the adjacent surface is planted, substantially obstructed, or otherwise protected.
8. Additional information on curb ramp location, design, light reflective value and texture may be found in the latest draft of the Proposed Guidelines for Pedestrian Facilities in the Public Right of Way (PROWAG) as published by the U.S. Architectural and Transportation Barriers Compliance Board (Access Board).
9. To serve as a pedestrian refuge area, the median should be a minimum of 6' wide, measured from back of curbs. Medians should be designed to provide accessible passage over or through them.
10. Small channelization islands, which do not provide a minimum 5' x 5' landing at the top of curb ramps, shall be cut through level with the surface of the street.
11. Crosswalk dimensions, crosswalk markings and stop bar locations shall be as shown elsewhere in the plans. At intersections where crosswalk markings are not required, curb ramps shall align with theoretical crosswalks unless otherwise directed.
12. Provide curb ramps to connect the pedestrian access route at each pedestrian street crossing. Handrails are not required on curb ramps.
13. Curb ramps and landings shall be constructed and paid for in accordance with Item 531 "Sidewalks".
14. Place concrete at a minimum depth of 5" for ramps, flares and landings, unless otherwise directed.
15. Furnish and install No. 3 reinforcing steel bars at 18" o.c. both ways, unless otherwise directed.
16. Provide a smooth transition where the curb ramps connect to the street.
17. Curbs shown on sheet 1 within the limits of payment are considered part of the curb ramp for payment, whether it is concrete curb, gutter, or combined curb and gutter.
18. Existing features that comply with applicable standards may remain in place unless otherwise shown on the plans.

### DETECTABLE WARNING MATERIAL


19. Curb ramps must contain a detectable warning surface that consists of raised truncated domes complying with PROWAG. The surface must contrast visually with adjoining surfaces, including side flares. Furnish and install an approved cast-in-place dark brown or dark red detectable warning surface material adjacent to uncolored concrete, unless specified elsewhere in the plans.
20. Detectable Warning Materials must meet TxDOT Departmental Materials Specification DMS 4350 and be listed on the Material Producer List. Install products in accordance with manufacturer's specifications.
21. Detectable warning surfaces must be firm, stable and slip resistant.
22. Detectable warning surfaces shall be a minimum of 24 inches in depth in the direction of pedestrian travel, and extend the full width of the curb ramp or landing where the pedestrian access route enters the street.
23. Detectable warning surfaces shall be located so that the edge nearest the curb line is at the back of curb and neither end of that edge is greater than 5 feet from the back of curb. Detectable warning surfaces may be curved along the corner radius.
24. Shaded areas on Sheet 1 of 4 indicate the approximate location for the detectable warning surface for each curb ramp type.

### DETECTABLE WARNING PAVERS (IF USED)

25. Furnish detectable warning paver units meeting all requirements of ASTM C-936, C-33. Lay in a two by two unit basket weave pattern or as directed.
26. Lay full-size units first followed by closure units consisting of at least 25 percent (25%) of a full unit. Cut detectable warning paver units using a power saw.



### SIDEWALKS

27. Provide clear ground space at operable parts, including pedestrian push buttons. Operable parts shall be placed within unobstructed reach range specified in PROWAG section R406.
28. Place traffic signal or illumination poles, ground boxes, controller boxes, signs, drainage facilities and other items so as not to obstruct the pedestrian access route or clear ground space.
29. Street grades and cross slopes shall be as shown elsewhere in the plans.
30. Changes in level greater than 1/4 inch are not permitted.
31. The least possible grade should be used to maximize accessibility. The running slope of sidewalks and crosswalks within the public right of way may follow the grade of the parallel roadway. Where a continuous grade greater than five percent (5%) must be provided, handrails may be desirable to improve accessibility. Handrails may also be needed to protect pedestrians from potentially hazardous conditions. If provided, handrails shall comply with PROWAG R409.
32. Handrail extensions shall not protrude into the usable landing area or into intersecting pedestrian routes.
33. Driveways and turnouts shall be constructed and paid for in accordance with Item "Intersections, Driveways and Turnouts". Sidewalks shall be constructed and paid for in accordance with Item, "Sidewalks".
34. Sidewalk details are shown elsewhere in the plans.




**SECTION VIEW DETAIL**  
**CURB RAMP AT DETECTIBLE WARNINGS**

### DETECTABLE WARNING SURFACE DETAILS



\* NOTE:  
 BOTH ENDS OF THE  
 DETECTABLE WARNING SURFACE  
 SHALL BE 5' OR LESS  
 FROM BACK OF CURB.



SHEET 2 OF 4



# PEDESTRIAN FACILITIES CURB RAMP

## PED-18





FILE: ped18	DN: TxDOT	DW: VP	CK: KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152	02	071	US 183
REVISED 08, 2005	DIST	COUNTY	SHEET NO.	
REVISED 06, 2012	AUS	CALDWELL	45	
REVISED 01, 2018				

DATE:  
 FILE:




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**SIDEWALK TREATMENT AT DRIVEWAYS**




**NOTES:**  
 \* WHERE DRIVEWAYS CROSS THE PEDESTRIAN ROUTE, SIDES SHALL BE FLARED AT 10% MAX SLOPE.  
 \* \* IF CURB HEIGHT IS GREATER THAN 6 INCHES, USE GRADE LESS THAN OR EQUAL TO 5%. HANDRAIL AND DETECTABLE WARNING ARE NOT REQUIRED.




**PROTECTED ZONE**

NOTE: IN PEDESTRIAN CIRCULATION AREA, MAXIMUM 4" PROJECTION FOR POST OR WALL MOUNTED OBJECTS BETWEEN 27" AND 80" ABOVE THE SURFACE.




**CLEAR SPACE ADJACENT TO PEDESTRIAN PUSH BUTTON**



**PLACEMENT OF STREET FIXTURES**

NOTE: ITEMS NOT INTENDED FOR PUBLIC USE. MINIMUM 4' X 4' CLEAR GROUND SPACE REQUIRED AT PUBLIC USE FIXTURES.



**DETECTION BARRIER FOR VERTICAL CLEARANCE < 80"**

SHEET 3 OF 4

Texas Department of Transportation Design Division Standard

**PEDESTRIAN FACILITIES CURB RAMPS**






**PED-18**

FILE: ped18	DW: TxDOT	DW: VP	CK: KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152	02	071	US 183
REVISED 08, 2005	DIST	COUNTY	SHEET NO.	
REVISED 06, 2012	AUS	CALDWELL	46	
REVISED 01, 2018				


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL CROSSING LAYOUTS  
SEE SHEET 1 OF 4 FOR DETAILS AND DIMENSIONS



MID-BLOCK PLACEMENT PERPENDICULAR RAMPS



LEGEND:

SHOWS DOWNWARD SLOPE. →

DENOTES PREFERRED LOCATION OF PEDESTRIAN PUSH BUTTON (IF APPLICABLE). ☒

DENOTES PLANTING OR NON-WALKING SURFACE NOT PART OF PEDESTRIAN CIRCULATION PATH. ↙ ↘ ↙ ↘ ↙ ↘ ↙ ↘

SHEET 4 OF 4



Design Division Standard

PEDESTRIAN FACILITIES  
CURB RAMPS


PED-18

FILE: ped18	DW: TxDOT	DW: VP	CK: KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0152	02	071	US 183
REVISED 08, 2005	DIST	COUNTY	SHEET NO.	
REVISED 06, 2012	AUS	CALDWELL	47	
REVISED 01, 2018				


DATE:  
FILE:

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information from a digital or electronic format to a printed format. For more information, please contact the Texas Department of Transportation, Engineering Services, at (512) 469-2121.

12/11/2023 10:59:58 AM  
 pw://twdot\_projectwiseonline.com/TXD014/Documents/14 - AUS/Design Projects/015202/071/EC(1)-16/48



TEMPORARY SEDIMENT CONTROL FENCE



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

**SEDIMENT CONTROL FENCE USAGE GUIDELINES**

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT<sup>2</sup>. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


**LEGEND**

Sediment Control Fence



**GENERAL NOTES**

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING




TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING

**EC(1)-16**


FILE: ec116	DNR TxDOT	CK: KM	DN: VP	DN/CK: LS
© 2024	JULY 2016	CONT	SECT	HIGHWAY
REVISIONS		<b>0152 02</b>	<b>071</b>	<b>US 183</b>
DIST	COUNTY	SHEET NO.		
<b>AUS</b>	<b>CALDWELL</b>	<b>48</b>		

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into any other format or for any errors or omissions resulting from its use.

1/8/2024 2:23:25 PM  
 pw://ttdot.projectwiseonline.com/TXD014/Documents/14 - AUS/Design Projects/015202071/015202071.dwg




PLAN VIEW




SECTION A-A

EROSION CONTROL LOG DAM

CL-D




PLAN VIEW




SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB

CL-BOC




PLAN VIEW




SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS



REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

**Log Traps:** The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:

1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.


SHEET 1 OF 3

		<b>Design Division Standard</b>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG <b>EC (9) - 16</b>			
FILE: ec916	DNR TxDOT	CK: KM	DWR: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0152 02	071	US 183
DIST	COUNTY	SHEET NO.	
AUS	CALDWELL	49	

- CL-D EROSION CONTROL LOG DAM
- CL-BOC EROSION CONTROL LOG AT BACK OF CURB
- CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
- CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
- CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
- CL-DI EROSION CONTROL LOG AT DROP INLET
- CL-CI EROSION CONTROL LOG AT CURB INLET
- CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET




1/8/2024 2:23:33 PM  
 pw://txdot.projectwiseonline.com/TXD014/Documents/14 - AUS/Design Projects/015202071/015202071.dwg  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of units or the accuracy of the information provided. © 2016 TxDOT



EROSION CONTROL LOGS ON SLOPES  
 STAKE AND TRENCHING ANCHORING


CL-SST



END SECTION RAP DETAIL


SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

\* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:  
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;  
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




EROSION CONTROL LOGS ON SLOPES  
 STAKE AND LASHING ANCHORING

CL-SSL



STAKE AND TRENCHING ANCHORING DETAIL

CL-SST




STAKE AND LASHING ANCHORING DETAIL

CL-SSL

SHEET 2 OF 3


LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"



STAKE NOTCH DETAIL


		<b>Design Division Standard</b>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG <b>EC (9) - 16</b>			
FILE: ec116	DNR TxDOT	CK: KM	DWR: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0152 02	071	US 183
DIST	COUNTY	SHEET NO.	
AUS	CALDWELL	50	

1/8/2024 2:24:16 PM  
 pw://txdot.projectwiseonline.com/TXD014/Documents/14 - AUS/Design Projects/015202071/015202071.dwg  
 DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of any information into a digital format.




EROSION CONTROL LOG AT DROP INLET

CL-DI



EROSION CONTROL LOG AT CURB INLET


CL-CI



EROSION CONTROL LOG AT CURB INLET



CL-CI

NOTE:  
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



EROSION CONTROL LOG AT CURB & GRADE INLET

CL-GI



SHEET 3 OF 3

		<b>Design Division Standard</b>	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG <b>EC (9) - 16</b>			
FILE: ec916	DNR TxDOT	CR: KM	DNR LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	0152 02	071	US 183
DIST	COUNTY	SHEET NO.	
AUS	CALDWELL	51	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

**GENERAL NOTES FOR ALL ELECTRICAL WORK**

1. The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
2. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
3. Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is 1/2 in. or less in diameter.
4. Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
5. Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
6. When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

**CONDUIT**

**A. MATERIALS**

1. Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
2. Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
3. Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.

AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" x 8" x 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" x 8" x 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" x 8" x 4"	8" x 8" x 4"	10" x 10" x 4"
#8	8" x 8" x 4"	8" x 8" x 4"	8" x 8" x 4"

4. Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
5. Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
6. Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
7. Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

8. Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
9. When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
10. Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.

**B. CONSTRUCTION METHODS**

1. Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
2. Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
3. Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
4. Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
5. When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
6. Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
7. During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
8. Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
9. Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
10. Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
11. At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
12. Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
13. Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
14. File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.

**Texas Department of Transportation**  
 Traffic Operations Division Standard

## ELECTRICAL DETAILS CONDUITS & NOTES

### ED(1) - 14

FILE: ed1-14.dgn	DWG: 0152	CK: 02	DWG: 071	CK: US 183
© TxDOT October 2014	CONT: 0152	SECT: 02	JOB: 071	HIGHWAY: US 183
REVISIONS		DIST: AUS	COUNTY: CALDWELL	SHEET NO.: 52

# ELECTRICAL CONDUCTORS

## A. MATERIAL INFORMATION

1. Provide Type XHHW insulated conductors in accordance with Departmental Material Specification (DMS) 11040 "Conductors" and Item 620 "Electrical Conductors." Provide conductors as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 620. Color code insulated conductors in conformance with the NEC. Identify grounded (neutral) conductors with white insulation. Identify grounding conductors (ground wires) with green insulation or bare conductors. Identify ungrounded (hot) conductors with any color insulation except green, white, or gray. Keep color scheme consistent throughout the wiring system. Identify conductors 6 American Wire Gauge (AWG) and smaller by continuous color jacket. Identify electrical conductors 4 AWG and larger by continuous color jacket or by colored tape. When identifying conductors with colored tape, mark at least 6 in. of the conductor's insulation with half laps of tape.
2. Provide a solid copper 6 AWG grounding electrode conductor to bond the electrical service equipment to the concrete encased grounding electrode or the ground rod at the service location. Connect the grounding electrode conductor to the ground rod with a UL listed connector in accordance with DMS 11040. Connect the grounding electrode conductor to the concrete encased grounding electrode as shown in the plans.
3. Where two or more circuits are present in one conduit or enclosure, permanently identify the conductors of each branch circuit by attaching a non-metallic tag around both circuit conductors at each accessible location. Provide tags with two straps, large enough to indicate circuit number, letter, or other identification as shown in the plans. Print circuit identification on the tag with a permanent marker.
4. Use listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors for splicing as specified in DMS 11040. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Provide UL listed gel-filled insulating splice covers. Splicing materials, insulating materials, breakaway disconnects, splice covers, and fuse holders are subsidiary to various bid items.


## B. CONSTRUCTION METHODS

1. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the conduit system. After installing conductors in conduit, perform conductor pull test. If a conductor cannot be freely pulled, make any needed alterations or repairs at no additional cost to the department. Perform insulation resistance tests in accordance with Item 620. Coordinate with the Engineer to witness the tests.
2. Leave 2 ft. minimum, 3 ft. maximum length for each conductor up to the splice in ground boxes. Leave 3 ft. minimum, 4 ft. maximum length of conductor in ground boxes when pulled through with no splice. Leave 1 ft. minimum, 1.5 ft. maximum length of conductor at enclosures, weatherheads and pole bases.
3. Make splices only in junction boxes, ground boxes, pole bases, or electrical enclosures and use only listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors. Insulate splices with heavy wall heat shrink tubing or gel-filled insulating splice covers to provide a watertight splice. Overlap conductor insulation with heat shrink tubing a minimum of 2 in. past both sides of the splice. Where heat shrink tubing may not shrink sufficiently to provide a watertight seal around the individual conductors, prior to heating the tubing, increase the diameter of the conductor insulation using hot melt adhesive tape to provide a watertight seal between the individual conductors and the heat shrink tubing. Ensure the tape extends past the heat shrink tubing. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Heat shrink tubing that appears to have been burned, or overheated, is considered defective and must be replaced.
4. Size and install gel-filled insulating splice covers according to manufacturer's specifications when used in place of heat shrink tubing.
5. Wire nuts with factory applied waterproof sealant may be used for 8 AWG or smaller conductors in above ground junction boxes, but not in pole bases or ground boxes. Install wire nuts in an upright position to prevent the accumulation of water.
6. Support conductors in illumination poles with a J-hook at the top of the pole.
7. When terminating conductors, remove the insulation and jacketing material without nicking the individual strands of the conductor. Conductors with nicked individual conductor strands or removed strands will be considered damaged.
8. Replace conductors and cables that are damaged beyond repair or that fail an insulation resistance test at no additional cost to the department.
9. Do not repair damaged conductors with duct tape, electrical tape, or wire nuts. Use only approved splicing methods.
10. Do not terminate more than one conductor under a single connector, unless the connector is rated for multiple conductors. Do not exceed the pressure connector's listing for maximum number and size of conductors allowed.
11. Install breakaway connectors on conductors bid under Item 620 whenever those conductors pass through a breakaway support device. Follow manufacturer's instructions when terminating conductors to breakaway connectors. Properly torque threaded connections. Proper terminations are critical to the safe operation of breakaway devices. Trim waterproofing boots on breakaway connectors to fit snugly around the conductor to ensure waterproof connection. Only one conductor may enter a single opening in a boot. Provide waterproof boots with the correct number of openings. Leave unused openings factory sealed. Use prequalified breakaway connectors as shown on the MPL.

12. Provide and install a separate stranded equipment grounding conductor (EGC) in all conduits that contain circuit wiring of 50 volts or more. Unless shown elsewhere, size the EGC to be the same size as the largest current carrying conductor contained in the conduit. Ensure all EGCs are bonded together at every accessible location. For traffic signal installations, provide a minimum size 8 AWG EGC. The EGC is paid for under Item 620.

## C. TEMPORARY WIRING

1. Install temporary conductors and electrical equipment in accordance with the NEC article "Temporary Installations" and Department standard sheets.
2. Provide a ground fault circuit interrupter (GFCI) for power outlets for portable electrical equipment, power tools, ice machines, ice storage bins and refrigerators located outdoors at grade. GFCI may be any one of the following: molded cord and plug set, receptacle, or circuit breaker type.
3. Use listed wire nuts with factory applied sealant for temporary wiring where approved.
4. Enclose conductor splices within a listed enclosure or ground box, or ensure the splices are more than 10 ft. above grade vertically and more than 5 ft. horizontally from any metal structure. Where installing temporary conductors in areas subject to vehicle traffic or mobile construction equipment, ensure the vertical clearance to ground is at least 18 ft. when measured at the lowest point. Ground messenger wires that support power conductors in conformance with the NEC.
5. Protect and when necessary repair any existing electrical conduits uncovered during the construction process in a timely manner and in conformance with the NEC.



**SPLICE OPTION 1  
Compression Type**


## GROUND RODS & GROUNDING ELECTRODES

### A. MATERIAL INFORMATION


1. Provide and install a grounding electrode at electrical services. Provide ground rods according to DMS 11040 and the plans. Larger diameter or longer length rods may be called for in some specific locations, see the individual plans sheets. Concrete encased grounding electrodes may be called for in specific locations including electrical service, see individual plan sheets.

### B. CONSTRUCTION METHODS

1. Furnish auxiliary ground rods for lightning protection and install in soil, concrete, or both, as called for in the plans. For ground rods installed in concrete, ensure the connection of the conductor to the ground rod is readily accessible for inspection or repairs. For ground rods installed in soil, ensure that the upper end is between 2 to 4 in. below finished grade.
2. Do not place ground rods in the same drilled hole as a timber pole.
3. Install ground rods so the imprinted part number is at the upper end of the rod.
4. Remove all non-conductive coatings such as concrete splatter from the rod at the clamp location.
5. Route all conductors as short and straight as possible for connection to lightning protection ground rods. When a bend is required, ensure a minimum radius bend of four inches for these conductors.
6. Unless otherwise called for in the plans, protect grounding electrode conductors with non-metallic conduit. When protecting grounding electrode conductors with metal conduit, provide and install a grounding type bushing and properly sized bonding jumper on each end of the metal conduit.
7. Written authorization is required before installing a ground rod in a horizontal trench for rocky soil or a solid rock bottom.



**SPLICE OPTION 2  
Split Bolt Type**



**SPLICE OPTION 3  
Listed Screw Type**

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:


		Traffic Operations Division Standard	
<h1>ELECTRICAL DETAILS CONDUCTORS</h1>			
<h2>ED(3) - 14</h2>			
FILE: ed3-14.dgn	DWG: TxDOT	CHK: TxDOT	DWG: TxDOT
© TxDOT October 2014	CONT: 0152	SECT: 02	JOB: 071
REVISIONS	DIST: AUS	COUNTY: CALDWELL	SHEET NO.: 53







DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**SCHEMATIC TYPE A  
THREE WIRE**

Red insulation or color code 6" length of Line 1 or Line 2 conductors' insulation with red tape where conductor exits the weatherhead.


White insulation or color code 6" length of neutral conductors' insulation with white tape where conductor exits the weatherhead.

⑧ Two Photocell viewing windows not shown but required when photocell is listed as enclosure mounted. Windows not required when photocell is listed as pole top mounted.



**SCHEMATIC TYPE C  
THREE WIRE**


WIRING LEGEND	
————	Power Wiring
- - - -	Control Wiring
—N—	Neutral Conductor
—G—	Equipment grounding conductor—always required



**SCHEMATIC TYPE D - CUSTOM  
120/240 VOLTS - THREE WIRE**

Red insulation or color code 6" length of Line 1 or Line 2 conductors' insulation with red tape where conductor exits the weatherhead.

White insulation or color code 6" length of neutral conductors' insulation with white tape where conductor exits the weatherhead.



**SCHEMATIC TYPE T  
120/240 VOLTS - THREE WIRE**  
Galvanized steel—"Buy Off The Shelf" only. When required install photocell top of the pole or on luminaire only, no lighting contractor will be installed.

SCHEMATIC LEGEND	
1	Safety Switch (when required)
2	Meter (when required—verify with electric utility provider)
3	Service Assembly Enclosure
4	Main Disconnect Breaker (See Electrical Service Data)
5	Circuit Breaker, 15 Amp (Control Circuit)
6	Auxiliary Enclosure
7	Control Station ("H-O-A" Switch)
8	Photo Electric Control (enclosure-mounted shown)
9	Lighting Contactor
10	Power Distribution Terminal Blocks
11	Neutral Bus
12	Branch Circuit Breaker (See Electrical Service Data)
13	Separate Circuit Breaker Panelboard
14	Load Center
15	Ground Bus


				Traffic Operations Division Standard	
<b>ELECTRICAL DETAILS SERVICE ENCLOSURE AND NOTES</b> <b>ED(6) - 14</b>					
FILE:	ed6-14.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2014	CONT:	0152	SECT:	02
REVISIONS		JOB:	US 183	HIGHWAY	
		DIST:	AUS	COUNTY:	CALDWELL
		SHEET NO.		56	

DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**SUPPORT TYPE STEEL POLE (SP) AND STEEL FRAME (SF)**

1. Provide steel pole and steel frame supports as per TxDOT Departmental Material Specification (DMS) 11080 "Electrical Services." Mount all equipment and conduit on 12 gauge galvanized steel or stainless steel channel strut, 1 1/2 in. or 1 3/8 in. wide by 1 in. up to 3 3/4 in. deep Unistrut, Kindorf, B-line or equal. Bolt or weld all channel and hardware to vertical members as approved. Do not stack channel. File smooth and paint field cut ends of all channel with zinc-rich paint before installing.
2. Provide poles for overhead service with an eyebolt or similar fitting for attachment of the service drop to the pole in conformance with the electric utility provider's specifications.
3. Provide and install galvanized 3/4 in. x 18 in. x 4 in. (dia. x length x hook length) anchor bolts for underground service supports. Provide and install galvanized 3/4 in. x 56 in. x 4 in. anchor bolts for overhead service supports. Ensure anchor bolts have 3 in of thread, with 3 1/4 in. to 3 1/2 in. of the exposed anchor bolt projecting above finished foundation. Provide and install leveling nuts for all anchor bolts.
4. Bond one of the anchor bolts to the rebar cage with 6 AWG bare stranded copper conductor. Use listed mechanical connectors rated for embedment in concrete. See Inset B.
5. Furnish and install rigid metallic ells in all steel pole and steel frame foundations for all conduits entering the service from underground.
6. Use class C concrete for foundations. Ensure reinforcing steel is Grade 60 with 3" of unobstructed concrete cover.
7. Drill and top steel poles and frames for 1/2 in. X 13 UNC tank ground fitting. For steel pole service supports, provide and install tank ground fitting 4 in. to 6 in. below electrical service enclosure. Provide properly sized hole through the bottom of the enclosure for the service grounding electrode conductor. Ensure electrical service grounding electrode conductor is as short and straight as possible from the enclosure to the tank ground fitting. For steel frame service supports, provide and install tank ground fitting on steel frame post. Install service grounding electrode conductor in a non-metallic conduit or tubing from the enclosure to the steel frame post. Connect electrical service grounding electrode conductor to the tank ground fitting. See steel frame and steel pole details and Inset A for more information. Size service entrance conduit and branch circuit conduit as shown in the plans. For underground conduit runs from the electrical service, extend RMC from the service enclosure to an RMC elbow, and then connect the schedule type and size of conduit shown in the plans. Provide and install grounding bushings where RMC terminates in the enclosure. Grounding bushings are not required when RMC is fitted into a sealing hub or threaded boss.
8. If Steel pole or frame is painted, bond each separate painted piece with a bonding jumper attached to a tapped hole.
9. Provide 1/4" - 20 machine screws for bonding. Do not use sheet metal screws. Remove all non-conductive material at contact points. Terminate bonding jumpers with listed devices. Install minimum size 6 AWG stranded copper bonding jumpers. Make up all threaded bonding connections wrench tight.
10. Avoid contact of the service drop and service entrance conductors with the metal pole to prevent abrasion of the insulated conductors.
11. Shop drawings are not required for service support structure unless specifically stated elsewhere or directed by the Engineer.



DATE:  
FILE:

<p>Texas Department of Transportation</p>		<p>Traffic Operations Division Standard</p>	
<p><b>ELECTRICAL DETAILS</b> <b>SERVICE SUPPORT</b> <b>TYPES SF &amp; SP</b></p> <p><b>ED(7)-14</b></p>			
FILE: ed7-14.dgn	DWG: TxDOT	CHK: TxDOT	DRW: TxDOT
REV: 0152	SECT: 02	JOB: 071	HIGHWAY: US 183
DIST: AUS	COUNTY: CALDWELL	SHEET NO.: 57	