

# STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

DESIGN SPEED = 70 MPH MAINLANES

CSJ	ADT (YR 2024)	ADT (YR 2044)
0114-11-094	33,063 VPD	47,445 VPD
0114-12-016	49,441 VPD	69,717 VPD

FED. RD. DIV. NO.	PROJECT NO.	SHEET NO.
6	STP 2024 (635) HES	1
STATE	DIST.	COUNTY
TEXAS	HOU	WALLER, ETC.
CONT.	SECT.	JOB
0114	11	094, ETC.
		HIGHWAY NO.
		US 290

## INDEX OF SHEETS


SEE SHEET 2 FOR INDEX OF SHEETS

## PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

COUNTY: WALLER, ETC.  
US 290  
LIMITS: US 290: WASHINGTON C/L TO FIELDS STORE RD.  
PROJECT: STP 2024(635)HES  
CONTROL 0114-11-094, ETC.

FOR TRAFFIC SAFETY IMPROVEMENTS CONSISTING  
OF INSTALLING A MEDIAN BARRIER

CSJ	ROADWAY LENGTH	BRIDGE LENGTH	TOTAL LENGTH
0114-11-094	64,387.59 FT / 12.194 MI	3,051.00 FT / 0.577 MI	67,438.59 FT / 12.772 MI
0114-12-016	1,000.00 FT / 0.189 MI	000.00 FT / 0.000 MI	1,000.00 FT / 0.189 MI
<b>TOTAL</b>	<b>65,387.59 FT / 12.383 MI</b>	<b>3,051.00 FT / 0.577 MI</b>	<b>68,438.59 FT / 12.961 MI</b>




BEGIN PROJECT  
STA 128+18.30  
CSJ 0114-11-094  
REF MRK = 687 +0.241  
MP = 0.088

STA 999+97.59  
CSJ 0114-11-094  
REF MRK = 704 +1.698  
MP = 16.584

STA 0+00.00  
CSJ 0114-12-016  
REF MRK = 704 +1.698  
MP = 0.000

END PROJECT  
STA 10+00.00  
CSJ 0114-12-016  
REF MRK = 704 +1.903  
MP = 0.205

**PROJECT LAYOUT MAP**  
N. T. S.



FUNCTIONAL CLASSIFICATION: RURAL PRINCIPAL ARTERIAL

© 2024 By TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SUBMITTED FOR LETTING: 1/9/2024

DocuSigned by:  
*Carlos M. Zepeda Jr., P.E.*  
999FB2AF5ACE472...  
AREA ENGINEER

APPROVED FOR LETTING: 1/26/2024

DocuSigned by:  
*Brett McLeod*, P.E.  
F06C2D7624E543D...  
FOR DISTRICT ENGINEER

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014, AND THE SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, October 23, 2023).

EQUATIONS: STA 999+97.59 (BK) = STA 0+00.00 (AH)  
EXCEPTIONS: NO. 1 STA 128+18.30 TO STA 250+73.00  
NO. 2 STA 267+63.00 TO STA 342+49.00  
RR CROSSINGS: UNION PACIFIC RR UNDERPASS AT STA 467+76.00

COUNTY WALLER, ETC. PROJ. NO. STP 2024(635)HES  
HWY. NO. US 290 LETTING DATE  
DATE ACCEPTED

SHEET NO.    DESCRIPTION

**I. GENERAL**

- 1    TITLE SHEET
- 2    INDEX OF SHEETS
- 3-6    TYPICAL SECTIONS
- 7,7A-7D    GENERAL NOTES
- 8    ESTIMATE & QUANTITY SHEET
- 9-10    SUMMARY OF QUANTITIES

**II. TRAFFIC CONTROL PLAN**

STANDARDS - TRAFFIC CONTROL

- \* 11-22    BARRICADE AND CONSTRUCTION BC(1)-21 THRU BC(12)-21
- \* 23    WORK ZONE "GIVE US A BRAKE" SIGNS WZ(BRK)-13
- \* 24    TEMPORARY RUMBLE STRIPS WZ(RS)-22
- \* 25    TRAFFIC CONTROL PLAN LANE CLOSURES FOR DIVIDED HIGHWAYS TCP(1-5)-18
- \* 26    TRAFFIC CONTROL PLAN LANE CLOSURES ON DIVIDED HIGHWAYS TCP(2-6)-18

**III. ROADWAY DETAILS**

- 27-63    CABLE BARRIER LAYOUT

STANDARDS - ROADWAY

- \* 64-66    BRIFEN WIRE ROPE SAFETY FENCE (TL-4) BRIFEN(TL4)-14
- \* 67    TRINITY CABLE SAFETY SYSTEM (TL-4) CASS(TL4)-14
- \* 68    GIBRALTAR CABLE BARRIER SYSTEM (TL-4) GBRLTR(TL4)-14
- \* 69-70    NU-CABLE BARRIER SYSTEM (TL-4)(4 CABLE) NU-CABLE(TL4)-14


**IV. RAILROAD**

- 71    RAILROAD SCOPE OF WORK PROJECT SPECIFIC DETAILS
- 72-73    RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

**V. ENVIRONMENTAL ISSUES**

SWP3

- 74-75    TXDOT STORM WATER POLLUTION PREVENTION PLAN SWP3
- \* 76    TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES - FENCE & VERTICAL TRACKING EC(1)-16
- \* 77    EROSION CONTROL LOG ECL-12 (HOU DIST)
- \* 78    ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC) (HOU DIST)



\* THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.


*Robert S. Bissett, Jr.*, P.E.    12/04/23  
DATE

INDEX OF SHEETS

SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		2





TYPICAL SECTION

STA 130+44.00 TO STA 481+28.00



*Robert S. Bissett, Jr.*  
12/04/23

NOTES:

1. CROSSOVER AND DECELERATION LANES OMITTED FOR CLARITY.
2. SEE "CABLE BARRIER LAYOUT" SHEETS FOR LOCATIONS OF CABLE BARRIER.


TYPICAL SECTIONS



SCALE: 1"=10'H


SHEET 1 OF 4

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER ETC.		3



**TYPICAL SECTION**

STA 130+44.00 TO STA 481+28.00



*Robert S. Bissett, Jr.*

12/04/23

**NOTES:**

1. CROSSOVER AND DECELERATION LANES OMITTED FOR CLARITY.
2. SEE "CABLE BARRIER LAYOUT" SHEETS FOR LOCATIONS OF CABLE BARRIER.


**TYPICAL SECTIONS**




SCALE: 1"=10'H

SHEET 2 OF 4


CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		4



**TYPICAL SECTION**  
**STA. 487+00 TO STA. 996+00**



**TYPICAL SECTION**  
**STA. 996+00 TO STA. 11+00**



*Robert S. Bissett, Jr.*  
 12/04/23

**TYPICAL SECTIONS**


- NOTES:**  
 1. CROSSOVER AND DECELERATION LANES OMITTED FOR CLARITY.  
 2. SEE "CABLE BARRIER LAYOUT" SHEETS FOR LOCATIONS OF CABLE BARRIER.

©2023 Texas Department of Transportation


NOT TO SCALE

SHEET 3 OF 4


CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST COUNTY			SHEET NO.
HOU WALLER ETC.			5



**TYPICAL SECTION**  
STA. 487+00 TO STA. 996+00



**TYPICAL SECTION**  
STA. 996+00 TO STA. 11+00



*Robert S. Bissett, Jr.*  
12/04/23

**TYPICAL SECTIONS**

- NOTES:**  
 1. CROSSOVER AND DECELERATION LANES OMITTED FOR CLARITY.  
 2. SEE "CABLE BARRIER LAYOUT" SHEETS FOR LOCATIONS OF CABLE BARRIER.

©2023 Texas Department of Transportation

NOT TO SCALE

SHEET 4 OF 4

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	6

County: Waller, etc.

Highway: US 290

Control: 0114-11-094, etc.

**General Notes:**

**General:**

Area Engineer contact information for this project follows:

Carlos M. Zepeda, Jr., P.E.,  
Phone: (281)238-7920  
Email: [Carlos.Zepeda@txdot.gov](mailto:Carlos.Zepeda@txdot.gov)

Daniel J. Dvorak, P.E.  
Phone: (281)238-7915  
Email: [Daniel.Dvorak@txdot.gov](mailto:Daniel.Dvorak@txdot.gov)

Submit any questions about this project via the Letting Pre-Bid Q&A web page, located at:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

The Letting Pre-Bid Q&A web page for each project can be accessed by scrolling or filtering the dashboard using the controls on the left side to navigate to the project. Hover over the blue hyperlink of the project to view the Q&A and click on the link in the window that pops up.

All relevant project documentation, including Contract Time Determinations and cross-sections will continue to be provided on the following FTP site:

[Index of /pub/txdot-info/Pre-Letting Responses/Houston District \(state.tx.us\)](https://pub.txdot-info/Pre-Letting Responses/Houston District (state.tx.us)) or

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/Houston%20District/>

If fixed features require, the governing slopes shown may vary between the limits shown and to the extent determined by the Engineer.

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved, except for roadway illumination, electrical, and traffic signal items.

The cost for materials, labor, and incidentals to provide for traffic across the roadway and for ingress and egress to private property in accordance with Section 7.2.4 of the standard specifications is subsidiary to the various bid items. Restore access roadways to their original condition upon completing construction.

Clearly mark or highlight on the shop drawings, the items being furnished for this project. Submit required shop drawings in accordance with the shop drawing distribution list shown in the note for Item 5 for review and distribution.

County: Waller, etc.

Highway: US 290

Control: 0114-11-094, etc.

Unless otherwise shown on the plans or otherwise directed, commence work after sunrise and ensure construction equipment is off the road by sunset.

Procure permits and licenses, which are to be issued by the City, County, or Municipal Utility District.

**General: Site Management**

Mow the grass and weeds within the project limits a maximum of 3 times a year as directed. This work is subsidiary to the various bid items.

Do not mix or store materials, or store or repair equipment, on top of concrete pavement or bridge decks unless authorized by the Engineer. Permission will be granted to store materials on surfaces if no damage or discoloration will result.

Personal vehicles of employees are not permitted to park within the right of way, including sections closed to public traffic. Employees may park on the right of way at the Contractor's office, equipment, and materials storage yard sites.

Assume ownership of debris and dispose of at an approved location. Do not dispose of debris on private property unless approved in writing by the District Engineer.

Control the dust caused by construction operations. For sweeping the base material in preparation for laying asphalt and for sweeping the finished concrete pavement, use one of the following types of sweepers or approved equal:

Tricycle Type	Truck Type - 4 Wheel
Wayne Series 900	M-B Cruiser II
Elgin White Wing	Wayne Model 945
Elgin Pelican	Mobile TE-3
	Mobile TE-4
	Murphy 4042

**General: Utilities**

Consider the locations of underground utilities depicted in the plans as approximate and employ responsible care to avoid damaging utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities.

If the Contractor damages or causes damage (breaks, leaks, nicks, dents, gouges, etc.) to the utility, contact the utility facility owner or operator immediately.

At least 72 hours before starting work, make arrangements for locating existing Department-owned above ground and underground fiber optic, communications, power, illumination, and

traffic signal cabling and conduit. Do this by calling the Department’s Houston District Traffic Signal Operations Office at 713-802-5662, or by e-mailing the Department’s Houston District Traffic Signal Operations Office at [HOU-LocateRequest@txdot.gov](mailto:HOU-LocateRequest@txdot.gov), to schedule marking of underground lines on the ground. Use caution if working in these areas to avoid damaging or interfering with existing facilities.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Costs associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Perform electrical work in conformance with the National Electrical Code (NEC) and Department’s standard sheets.

**Item 5: Control of Work**

Submit shop drawings electronically for the fabrication of items as documented in Table 1 below. Information and requirements for electronic submittals can be viewed in the “Guide to Electronic Shop Drawing Submittal” which can be accessed through the following web link, [https://ftp.txdot.gov/pub/txdot-info/library/pubs/bus/bridge/e\\_submit\\_guide.pdf](https://ftp.txdot.gov/pub/txdot-info/library/pubs/bus/bridge/e_submit_guide.pdf) References to 11 in. x 17 in. sheets in individual specifications for structural items imply electronic CAD sheets.

**Table 1**  
2014 Construction Specification Required Shop/Working Drawing Submittals - TxDOT Generated Plans

Spec Item No.'s	Product	Submittal Required	Approval Required (Y/N)	Contractor/Fabricator P.E. Seal Required	Reviewing Party	Shop or Working Drawing (Note 1)
7.16.1&.2	Construction Load Analyses	Y	Y	Y	B	WD
400	Excavation and Backfill for Structures (cofferdams)	Y	N	Y	A	WD
403	Temporary Special Shoring	Y	N	Y	C	WD
420	Formwork/Falsework	Y	N	Y	A	WD
423	Retaining Walls, (calcs req'd.)	Y	Y	Y	C	SD
425	Optional Design Calculations (Prstrs Bms)	Y	Y	Y	B	SD
425	Prestr Concr Sheet Piling	Y	Y	N	B	SD
425	Prestr Concr Beams	Y	Y	N	B	SD
425	Prestr Concr Bent	Y	Y	N	B	SD
426	Post Tension Details	Y	Y	N	B	SD
434	Elastomeric Bearing Pads (All)	Y	Y	N	B	SD
441	Bridge Protective Assembly	Y	Y	N	B	SD
441	Misc Steel (various steel assemblies)	Y	Y	N	B	SD
441	Steel Pedestals (bridge raising)	Y	Y	N	B	SD
441	Steel Bearings	Y	Y	N	B	SD
441	Steel Bent	Y	Y	N	B	SD
441	Steel Diaphragms	Y	Y	N	B	SD
441	Steel Finger Joint	Y	Y	N	B	SD
441	Steel Plate Girder	Y	Y	N	B	SD

441	Steel Tub-Girders	Y	Y	N	B	SD
441	Erection Plans, including Falsework	Y	N	Y	A	WD
449	Sign Structure Anchor Bolts	Y	Y	N	T	SD
450	Railing	Y	Y	N	A	SD
462	Concrete Box Culvert	Y	Y	N	C	SD
462	Concrete Box Culvert (Alternate Designs Only, calcs req'd.)	Y	Y	Y	B	SD
464	Reinforced Concrete Pipe (Jack and Bore only; ONLY when requested)	Y	Y	Y	A	SD
465	Pre-cast Junction Boxes, Grates, and Inlets	Y	Y	N	A	SD
465	Pre-cast Junction Boxes, Grates, and Inlets (Alternate Designs Only, calcs req'd.)	Y	Y	Y	B	SD
466	Pre-cast Headwalls and Wingwalls	Y	Y	N	A	SD
467	Pre-cast Safety End Treatments	Y	Y	N	A	SD
495	Raising Existing Structure (calcs req'd.)	Y	Y	Y	B	SD
610	Roadway Illumination Supports (Non-Standard only, calcs req'd.)	Y	Y	Y	BRG	SD
613	High Mast Illumination Poles (Non-standard only, calcs req'd.)	Y	Y	Y	BRG	SD
627	Treated Timber Poles	Y	Y	N	T	SD
644	Special Non-Standard Supports (Bridge Mounts, Barrier Mounts, Etc.)	Y	Y	Y	T	SD
647	Large Roadside Sign Supports	Y	Y	Y	T	SD
650	Cantilever Sign Structure Supports - Alternate Design Calcs.	Y	Y	Y	T	SD
650	Sign Structures	Y	Y	N	T	SD
680	Installation of Highway Traffic Signals	Y	Y	N	T	SD
682	Vehicle and Pedestrian Signal Heads	Y	Y	N	T	SD
684	Traffic Signal Cables	Y	Y	N	T	SD
685	Roadside Flashing Beacon Assemblies	Y	Y	N	T	SD
686	Traffic Signal Pole Assemblies (Steel) (Non-Standard only)	Y	Y	Y	T	SD
687	Pedestal Pole Assemblies	Y	Y	N	T	SD
688	Detectors	Y	Y	N	A	SD
784	Repairing Steel Bridge Members	Y	Y	Y	B	WD
SS	Prestr Concr Crown Span	Y	Y	N	B	SD
SS	Sound Barrier Walls	Y	Y	Y	A	SD
SS	Camera Poles	Y	Y	Y	TMS	SD
SS	Pedestrian Bridge (Calcs req'd.)	Y	Y	Y	B	SD
SS	Screw-In Type Anchor Foundations	Y	Y	N	T	SD
SS	Fiber Optic/Communication Cable	Y	Y	N	TMS	SD
SS	Spread Spectrum Radios for Signals	Y	Y	N	T	SD
SS	VIVDS System for Signals	Y	Y	N	T	SD
SS	CTMS Equipment	Y	Y	N	TMS	SD

Notes:

1. Document flow for Working Drawings differs from Shop Drawings in that Working Drawings must be submitted to the Engineer rather than the Engineer of Record and they are for the information of the Engineer only; an approval stamp and distribution to all project offices is not required.



**Key to Reviewing Party**

A - Area Office	
Area Office	Email Address
Fort Bend Area Office	<a href="mailto:HOU-FBAShpDrwgs@txdot.gov">HOU-FBAShpDrwgs@txdot.gov</a>
C - Construction Office	
Construction	<a href="mailto:HOU-ConstrShpDrwgs@txdot.gov">HOU-ConstrShpDrwgs@txdot.gov</a>
Laboratory	<a href="mailto:HOU-LabShpDrwgs@txdot.gov">HOU-LabShpDrwgs@txdot.gov</a>
T - Traffic Engineer	
Traffic Operations	<a href="mailto:HOU-TrfShpDrwgs@txdot.gov">HOU-TrfShpDrwgs@txdot.gov</a>

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with “Standard Operating Procedure for Alternate Precast Proposal Submission” found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

**Item 6: Control of Materials**

To comply with the latest provisions of the Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the Contractor must submit an original of the TxDOT Construction Material Buy America Certification Form for items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

**Item 7: Legal Relations and Responsibilities**

Do not initiate activities in a Project Specific Location (PSL), associated with a U.S. Army Corps of Engineers (USACE) permit area, that have not been previously evaluated by the USACE as part of the permit review of this project. Such activities include those pertaining to, but are not limited to, haul roads, equipment staging areas, borrow and disposal sites. Associated defined here means materials are delivered to or from the PSL. The permit area includes the waters of the U.S. or associated wetlands affected by activities associated with this project. Special restrictions may be required for such work. Assume responsibility for consultations with the USACE regarding activities, including PSLs that have not been previously evaluated by the USACE. Provide the Department with a copy of consultations or approvals from the USACE before initiating activities.

The Contractor may proceed with activities in PSLs that do not affect a USACE permit area if a self-determination has been made that the PSL is non-jurisdictional or if proper USACE clearances have been obtained in jurisdictional areas or have been previously evaluated by the USACE as part of the permit review of this project. The Contractor is solely responsible for documenting any determinations that their activities do not affect a USACE permit area. Maintain copies of their determinations for review by the Department or any regulatory agency.

Document and coordinate with the USACE, if required, before hauling any excavation from or hauling any embankment to a USACE permit area by either 1 or 2 below:

1. **Restricted Use of Materials for the Previously Evaluated Permit Areas.**  
 Document both the Project Specific Locations (PSL) and their authorization. Maintain copies for review by the Department or any regulatory agency. When an area within the project limits has been evaluated by the USACE as part of the permit process for this project:
  - a. Suitable excavation of required material in the areas shown on the plans and cross sections as specified in the Item, “Excavation” is used for permanent or temporary fill (under the Item, “Embankment”) within a USACE permit area.
  - b. Suitable embankment (under the Item, “Embankment”) from within the USACE permit area is used as fill within a USACE evaluated area.
  - c. Unsuitable excavation or excess excavation, “Waste” (under the Item, “Excavation”), that is disposed of at a location approved within a USACE evaluated area.
  
2. **Contractor Materials from Areas Other than Previously Evaluated Areas.**  
 Provide the Department with a copy of USACE coordination or approvals before initiating any activities for an area within the project limits that has not been evaluated by the USACE or for any off right of way locations used for the following, but not limited to, haul roads, equipment staging areas, borrow and disposal sites:
  - a. The Item, “Embankment” used for temporary or permanent fill within a USACE permit area.
  - b. Unsuitable excavation or excess excavation, “Waste” (under the Item, “Excavation”), that is disposed of outside a USACE evaluated area.

This project does not require a U.S. Army Corps of Engineers (USACE) Section 404 Permit before letting, but if a permit is needed during construction, assume responsibility for preparing the permit application. Submit the permit application to the Department’s District Environmental Section for approval. Once the permit application is approved, the Department will submit it to the USACE. Assume responsibility for the requested revisions, in coordination with the Department’s District Environmental Section.

Maintain the roadway slope stability. Maintaining slope stability is subsidiary to the various bid items.

No significant traffic generator events have been identified.

**Item 8: Prosecution and Progress**

The Department will not adjust the number of days for the project and milestones, if any, due to differences in opinion regarding any assumptions made in the preparation of the schedule or for errors, omissions, or discrepancies found in the time determination schedule.

Working days will be computed and charged based on a *standard* workweek in accordance with Section 8.3.1.4.

**Item 110: Excavation**

If manipulating the excavated material requires moving the same material more than once to accomplish the desired results, the excavation is measured and paid for only once regardless of the manipulation required.

**Items 360, 420, and 421: All Concrete Items**

For the Department’s concrete cylinder split samples, transport the test cylinders to the Houston District Laboratory located at 7600 Washington Avenue in Houston, or to the appropriate Area Laboratory, when applicable. Transporting the test cylinders is subsidiary to the various bid items.

**Item 502: Barricades, Signs, and Traffic Handling**

Use a traffic control plan for handling traffic through the various phases of construction. Follow the phasing sequence unless otherwise agreed upon by the Area Engineer and the Project Manager. Ensure this plan conforms to the latest “Texas Manual on Uniform Traffic Control Devices” and the latest Barricade and Construction (BC) Standard Sheets.

Submit changes to the traffic control plan to the Area Engineer. Provide a layout showing the construction phasing, signs, striping, and signalizations for changes to the original traffic control plan.

Furnish and maintain the barricades and warning signs, including the necessary temporary and portable traffic control devices, during the various phases of construction. Place and construct these barricades and warning signs in accordance with the latest “Texas Manual on Uniform Traffic Control Devices” for typical construction layouts.

Cover work zone signs when work related to the signs is not in progress, or when any hazard related to the signs no longer exists.

Keep the delineation devices, signs, and pavement markings clean. This work is subsidiary to the Item, “Barricades, Signs, and Traffic Handling.”

Before detouring traffic onto the mainlane shoulders, remove dirt, debris, vegetation, and other deleterious material from the surface of the shoulders. Appropriately sign the detour in an approved manner. This work is subsidiary to the various bid items.

Do not mount signs on drums or barricades, except those listed in the latest Barricades and Construction standard sheets.

Use traffic cones for daytime work only. Replace the cones with plastic drums during nighttime hours.

Place positive barriers to protect drop-off conditions greater than 2 ft. within the clear zone that remain overnight.

Do not reduce the existing number of lanes open to traffic except as shown on the following time schedule:

**One Lane Closure**

Day	Daytime Closure Hours	Nighttime Closure Hours	Restricted Hours
Monday	9:00 AM - 4:00 PM	7:00 PM - 12:00 AM	6:00 AM - 9:00 AM 4:00 PM - 7:00 PM
Tuesday	9:00 AM - 4:00 PM	12:00 AM - 5:00 AM 7:00 PM - 12:00 AM	6:00 AM - 9:00 AM 4:00 PM - 7:00 PM
Wednesday	9:00 AM - 4:00 PM	12:00 AM - 5:00 AM 7:00 PM - 12:00 AM	6:00 AM - 9:00 AM 4:00 PM - 7:00 PM
Thursday	9:00 AM - 4:00 PM	12:00 AM - 5:00 AM 7:00 PM - 12:00 AM	6:00 AM - 9:00 AM 4:00 PM - 7:00 PM
Friday	9:00 AM - 4:00 PM	12:00 AM - 5:00 AM	6:00 AM - 9:00 AM 4:00 PM - 7:00 PM
Saturday	Not Allowed	Not Allowed	N/A
Sunday	Not Allowed	Not Allowed	N/A

The above times are approved for the traffic control conditions listed. The Area Engineer may approve other closure times if traffic counts warrant. The Area Engineer may reduce the above times for special events.

Law enforcement assistance will be required for this project and is expected to be required for major traffic control changes and lane closures. Coordinate with local law enforcement and arrange for law enforcement as directed or agreed by the Engineer. Before payment will be made, complete the “Daily Report on Law Enforcement Force Account Work” (Form 318), provided by the Department and submit daily invoices that agree with this form for any day during the month in which approved services were provided.

Provide full-time, off-duty, uniformed, certified peace officers, as part of traffic control operations. The peace officers must be able to show proof of certification by the Texas Commission on Law Enforcement Officers Standards. The cost of the officers is paid for on a force account basis.

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible

County: Waller, etc.

County: Waller, etc.

Sheet 7D

Highway: US 290

Control: 0114-11-094, etc.

Highway: US 290

Control: 0114-11-094, etc.

Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

**Item 506: Temporary Erosion, Sedimentation and Environmental Controls**

The use of hay bales is not permitted as Storm Water Pollution Prevention Plan (SWP3) measures.

Use appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. Remove and dispose of materials in compliance with State and Federal laws.

Before starting construction, review with the Engineer the SWP3 used for temporary erosion control as outlined on the plans. Before construction, place the temporary erosion and sedimentation control features as shown on the SWP3.

Implement temporary and permanent erosion control measures to comply with the National Pollution Discharge Elimination System (NPDES) general permit under the Clean Water Act.

**Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)**

A shadow vehicle with Truck Mounted Attenuators (TMAs) or Trailer Attenuators (TAs) is required as shown on the appropriate Traffic Control Plan (TCP) sheets. TMAs/TAs must meet the requirements of the Compliant Work Zone Traffic Control Device List.

Level 3 Compliant TMAs/TAs are required for this project.

A total of one (1) shadow vehicle with a TMA/TA is required for the work with the exception of Pavement Marking Operations. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0114-11-094

DISTRICT Houston  
HIGHWAY US 290

COUNTY Harris, Waller

CONTROL SECTION JOB				0114-11-094		0114-12-016		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00180623		A00180624			
COUNTY				Waller		Harris			
HIGHWAY				US 290		US 290			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	110-6001	EXCAVATION (ROADWAY)	CY	2,368.000		36.000		2,404.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	2,368.000		36.000		2,404.000	
	500-6001	MOBILIZATION	LS	0.983		0.017		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	12.000		1.000		13.000	
	543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	63,404.000		964.000		64,368.000	
	543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EA	41.000		1.000		42.000	
	6185-6002	TMA (STATIONARY)	DAY	366.000		6.000		372.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000	
		LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000	

SUMMARY OF QUANTITIES

	ROADWAY, SIGNING & PAVEMENT MARKING LAYOUT SHEET	0110-6001	0432-6045	0502-6001	0543-6002	0543-6020	6185-6002
		EXCAVATION (ROADWAY)	RIPRAP (MOW STRIP) (4 IN)	BARRICADES, SIGNS AND TRAFFIC HANDLING	CABLE BARRIER SYSTEM (TL-4)	CABLE BARRIER TERMINAL SECTION (TL-4)	TMA (STATIONARY)
		CY	CY	MO	LF	EA	DAY
	1						
	2						
	3						
	4						
	5						
	6	59	59		1,581	2	
	7						
	8						
0114-11-094	9	5	5		116	1	
	10	89	89		2,400		
	11	82	82		2,163	4	
	12	86	86		2,301	2	
	13	83	83		2,193	4	
	14	86	86		2,306	2	
	15	66	66		1,739	4	
	16	91	91		2,425	2	
	17	89	89		2,403		
	18	68	68		1,823	2	
	19	77	77		2050	2	
	20	89	89		2,400		
	21	81	81		2,158	2	

SUMMARY OF QUANTITIES

SHEET 1 OF 2



CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER ETC.		9

**SUMMARY OF QUANTITIES**

	ROADWAY, SIGNING & PAVEMENT MARKING LAYOUT SHEET	0110-6001	0432-6045	0502-6001	0543-6002	0543-6020	6185-6002
		EXCAVATION (ROADWAY)	RIPRAP (MOW STRIP) (4 IN)	BARRICADES, SIGNS AND TRAFFIC HANDLING	CABLE BARRIER SYSTEM (TL-4)	CABLE BARRIER TERMINAL SECTION (TL-4)	TMA (STATIONARY)
		CY	CY	MO	LF	EA	DAY
0114-11-094	22	89	89		2,403		
	23	72	72		1,928	2	
	24	94	94		2,508	2	
	25	75	75		2,016	2	
	26	89	89		2,400		
	27	90	90		2,408		
	28	93	93		2,504	2	
	29	90	90		2,407		
	30	89	89		2,401		
	31	77	77		2,040	2	
	32	89	89		2,400		
	33	90	90		2,415	2	
	34	89	89		2,402		
	35	89	89		2,400		
	36	73	73		1,934	2	
	37	29	29		780		
		<b>SUB-TOTAL</b>	<b>2,368</b>	<b>2,368</b>	<b>12</b>	<b>63,404</b>	<b>41</b>
0114-12-016	37	36	36		964	1	
	<b>SUB-TOTAL</b>	<b>36</b>	<b>36</b>	<b>1</b>	<b>964</b>	<b>1</b>	<b>6</b>
	<b>TOTAL</b>	<b>2,404</b>	<b>2,404</b>	<b>13</b>	<b>64,368</b>	<b>42</b>	<b>372</b>

**SUMMARY OF QUANTITIES**

SHEET 2 OF 2



CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		10

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

DATE: \$DATES \$TIMES  
 FILE: \$FILES

**WORKER SAFETY NOTES:**


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<p><b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b>  <a href="http://www.txdot.gov">http://www.txdot.gov</a></p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard
<p><b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b></p> <p><b>BC (1) -21</b></p>		
FILE: bc-21.dgn	DNR: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT: 0114	SECT: 11
4-03 7-13	9-07 8-14	5-10 5-21
REVISIONS	JOB: 094 ETC.	HIGHWAY: US 290
DIST: HOU	COUNTY: WALLER, ETC.	SHEET NO.: 11

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL LOCATION OF CROSSROAD SIGNS**



## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.


**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - \*\* CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12

Texas Department of Transportation  
Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-21**

FILE: bc-21.dgn	DWG: TxDOT	CR: TxDOT	DWG: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	HOU	WALLER, ETC.		12


DATE: \$DATES  
FILE: \$FILES



# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present.

Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
  - 40 mph and greater 0.2 to 2 miles
  - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES  
FILE: \$FILES

SHEET 3 OF 12




## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

### BC (3) - 21

FILE:	bc-21.dgn	DNR TxDOT	CR: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0114	11	094, ETC.	US 290
9-07	8-14	DIST	COUNTY	SHEET NO.	
7-13	5-21	HOU	WALLER, ETC.	13	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.





**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**

FILE: bc-21.dgn	DWG: TxDOT	CR: TxDOT	REV: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT: 0114	SECT: 11	JOB: 094, ETC.	HIGHWAY: US 290
9-07 8-14	DIST: 7-13	COUNTY: 5-21	CITY: WALLER, ETC.	SHEET NO.: 14


DATE: \$DATES  
 FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





### SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



### SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

### WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

### GENERAL NOTES

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- \* See BC(4) for definition of "Work Duration."
- \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



## BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE: bc-21.dgn	DNR TxDOT	CR: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	WALLER, ETC.	15	

DATE: \$DATES  
FILE: \$FILES

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

### Other Condition List

ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM - X PM
APR XX - XX X PM - X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X - X XX PM - XX AM
NEXT FRI - SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM - XX AM

\*\* See Application Guidelines Note 6.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound (route) N	
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound (route) E		Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound (route) S	
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound (route) W	
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation = IH-number, US-number, SH-number, FM-number

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	DRW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT: 0114	SECT: 11	JOB: 094, ETC.	HIGHWAY: US 290
REVISIONS:	0114	11	094, ETC.	US 290
9-07 8-14	DIST:	COUNTY:	SHEET NO.:	
7-13 5-21	HOU:	WALLER, ETC.	16	

DATE: \$DATES \$TIMES  
FILE: \$FILES


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**


- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>PL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE: \$DATES \$TIMES  
 FILE: \$FILES

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) - 21**

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT	
© TxDOT November 2002		CONT: 0114	SECT: 11	JOB: 094, ETC.	HIGHWAY: US 290
REVISIONS		DIST: COUNTY		SHEET NO.	
9-07	8-14	HOU		WALLER, ETC.	17
7-13	5-21				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CWI-8, Opposing Traffic Lane  
Divider, Driveway sign D70a, Keep Right  
R4 series or other signs as approved  
by Engineer



12" x 24"  
Vertical Panel  
mount with diagonals  
sloping down towards  
travel way

Plywood, Aluminum or Metal sign  
substrates shall NOT be used on  
plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT	
© TxDOT November 2002		CONT: 0114	SECT: 11	JOB: 094, ETC.	HIGHWAY: US 290
REVISIONS		DATE	BY	APP	SHEET NO.
4-03	8-14				
9-07	5-21				
7-13					
DIST: HOU		COUNTY: WALLER, ETC.	SHEET NO. 18		


DATE: \$DATES  
FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\*\*Taper lengths have been rounded off.  
L=Length of Taper (FT.) W=Width of Offset (FT.)  
S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
9-07 8-14			COUNTY	SHEET NO.
7-13 5-21			HOU	WALLER, ETC. 19


DATE: \$DATES  
FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	HOU	WALLER, ETC.	20	

DATE: \$DATES  
FILE: \$FILES



## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES  
FILE: \$FILES

SHEET 11 OF 12




## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


**BC(11)-21**

FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	DRW: TxDOT	CR: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		0114	11	094, ETC.
2-98	9-07	5-21		US 290
1-02	7-13			
11-02	8-14			
	DIST	COUNTY		SHEET NO.
	HOU	WALLER, ETC.		<b>21</b>

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.






RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



### SOLID LINES




### BROKEN LINES



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DWG: TxDOT	CHK: TxDOT	DRW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
1-97 9-07 5-21	DIST	COUNTY		SHEET NO.
2-98 7-13	HOU	WALLER, ETC.		22
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES \$TIMES  
FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES  
FILE: \$FILES



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

\* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

BACKGROUND COLOR	SIGN DESIGNATION	SIGN	SIGN DIMENSIONS	REFLECTIVE SHEETING	SQ FT	GALVANIZED STRUCTURAL STEEL		DRILLED SHAFT
						Size	(LF)	
Orange	G20-7T		96" X 48"	Type B <sub>FL</sub> or C <sub>FL</sub>	32	▲	▲	▲
Orange	G20-7T		192" X 96"	Type B <sub>FL</sub> or C <sub>FL</sub>	128	W8x18	16 17	12

▲ See Note 6 Below

LEGEND

	Sign
	Large Sign
	Traffic Flow

DEPARTMENTAL MATERIAL SPECIFICATIONS

PLYWOOD SIGN BLANKS	DMS-7100
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub>
BLACK	LEGEND & BORDERS	NON-REFLECTIVE ACRYLIC FILM

GENERAL NOTES

- See BC and SMD sheets for additional sign support details.
- Sign locations shall be approved by the Engineer.
- For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
- Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
- Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
- The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
- The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:  
 Item 636 - Aluminum Signs  
 Item 647 - Large Roadside Sign Supports and Assemblies.  
 Item 416 - Drilled Shaft Foundations
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.

Texas Department of Transportation  
Traffic Operations Division Standard

**WORK ZONE  
"GIVE US A BRAKE"  
SIGNS**

**WZ (BRK) - 13**

FILE: wzbrk-13.dgn	DWG: TxDOT	CHK: TxDOT	APP: TxDOT	CR: TxDOT
©TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
6-96 5-98 7-13	DIST	COUNTY	SHEET NO.	
8-96 3-03	HOU	WALLER, ETC.	23	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2

Rumble Strip Array (See note 1)


Rumble Strip Array (See note 1)

The second Rumble Strip Array is required when the ADT thresholds in Table 1 indicate the need for 2 Arrays.



WZ (RS-1a)

**RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION**



WZ (RS-1b)

**RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY**

**GENERAL NOTES**

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only

\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT)  
S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

\* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

Texas Department of Transportation Traffic Safety Division Standard

## TEMPORARY RUMBLE STRIPS


### WZ (RS) - 22

FILE: wzrs22.dgn DWN: TxDOT CK: TxDOT DW: TxDOT CK: TxDOT  
 © TxDOT November 2012 CONT: SECT: JOB: HIGHWAY:  
 REVISIONS: 0114 11 094, ETC. US 290  
 2-14 1-22 DIST: COUNTY: SHEET NO.:  
 4-16 HOU WALLER, ETC. 24


DATE: \$DATES \$TIMES  
FILE: \$FILES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: \$DATES  
FILE: \$FILES  
\$TIMES



**ONE LANE CLOSURE**



**LANE CLOSURE NEAR EXIT RAMP**



**LANE CLOSURE NEAR ENTRANCE RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Traffic Operations Division Standard

**TEXAS DEPARTMENT OF TRANSPORTATION**


**TRAFFIC CONTROL PLAN  
LANE CLOSURES FOR  
DIVIDED HIGHWAYS**

**TCP (1-5) - 18**


FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	0114	11	094. ETC.	US 290
	DIST	COUNTY	SHEET NO.	
	HOU	WALLER, ETC.	25	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: \$DATES  
FILE: \$FILES  
\$TIMES



TCP (2-6a)  
**ONE LANE CLOSURE**



TCP (2-6b)  
**LANE CLOSURE NEAR EXIT RAMP**



TCP (2-6c)  
**LANE CLOSURE NEAR ENTRANCE RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula L = WS <sup>2</sup> / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing * "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
  - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
  - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
  - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation  
Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
LANE CLOSURES ON  
DIVIDED HIGHWAYS**

**TCP (2-6) - 18**


FILE: tcp2-6-18.dgn	DWG:	CK:	DW:	CK:
© TxDOT	December 1985	CONT	SECT	JOB
REVISIONS	0114	11	094, ETC.	US 290
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	HOU	WALLER, ETC.	26	
1-97 2-18				

CK: DW: CK: DN:




- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER


- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



MATCHLINE STA. 140+18.30



MATCHLINE STA. 152+18.30



*Robert S. Bissett, Jr.*  
12/04/23

PI 142+34.88  
 Δ 04°46'55.1" (RT)  
 D 01°00'00.0"  
 T 239.24'  
 L 478.20'  
 R 5729.58'  
 PC 139+95.64  
 PT 144+73.84

DATE: \$DATE\$  
 FILE: \$FILES\$



**CABLE BARRIER LAYOUT**

SHEET 1 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	27	


SCALE: 1"=100'

DATE: \$DATE\$  
 FILE: \$FILES\$  
 \$TIMES\$  
 DW: \$DW\$  
 CK: \$CK\$  
 DN: \$DN\$



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
 12/04/23

© 2023  
 Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 2 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	28	

SCALE: 1"=100'



DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DN: \_\_\_\_\_

DATE: \$DATE\$  
 FILE: \$FILES\$

MATCHLINE STA. 176+18.30

MATCHLINE STA. 188+18.30


MATCHLINE STA. 188+18.30

MATCHLINE STA. 200+18.30



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23



**CABLE BARRIER LAYOUT**

SHEET 3 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	29	

SCALE: 1"=100'

CK: DW: CK: DN:

MATCHLINE STA. 200+18.30

MATCHLINE STA. 212+18.30

MATCHLINE STA. 212+18.30

MATCHLINE STA. 224+18.30

EXISTING ROW

☉ US 290

205+00

210+00

EXISTING ROW

EXISTING ROW

☉ US 290

P/ 218+35.45

215+00


220+00

EXISTING ROW



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

DATE: \$DATE\$  
FILE: \$FILES\$

\$TIMES

SCALE: 1"=100'

© 2023  
Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 4 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	30	

DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DN: \_\_\_\_\_


DATE: \$DATE\$  
 FILE: \$FILES\$

MATCHLINE STA. 224+18.30

MATCHLINE STA. 236+18.30


MATCHLINE STA. 236+18.30

MATCHLINE STA. 248+18.30



- LEGEND**
- TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.





*Robert S. Bissett, Jr.*  
 12/04/23

<b>Texas Department of Transportation</b>			
<b>CABLE BARRIER LAYOUT</b>			
SHEET 5 OF 37			
CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		31

SCALE: 1"=100'

CK: DW: CK: DN:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.

DATE: \$DATE\$  
FILE: \$FILE\$


*Robert S. Bissett, Jr.*  
12/04/23

<b>CABLE BARRIER LAYOUT</b>			
SHEET 6 OF 37			
CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		32

SCALE: 1"=100'

CK: DW: CK: DN:



PI 272+26.22  
 Δ 14°40'28.2" (RT)  
 D 01°00'00.0"  
 T 737.76'  
 L 1467.45'  
 R 5729.58'  
 PC 264+88.46  
 PT 279+55.91



- LEGEND
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.

DATE: \$DATE\$  
 FILE: \$FILES\$



*Robert S. Bissett, Jr.*  
 12/04/23

Texas Department of Transportation



CABLE BARRIER LAYOUT

SHEET 7 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	33	


SCALE: 1"=100'

CK: DW: CK: DN:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

DATE: \$DATE\$  
FILE: \$FILES\$

\$TIMES

SCALE: 1"=100'

© 2023  
Texas Department of Transportation



**CABLE BARRIER LAYOUT**

SHEET 8 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	34	


CK: DW: CK: DN:

DATE: \$DATE\$  
FILE: \$FILES



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT



SHEET 9 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	35

SCALE: 1"=100'


CK: DW: CK: DN:

DATE: \$DATE\$  
FILE: \$FILES\$



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*

12/04/23

Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 10 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	36	

SCALE: 1"=100'

EXISTING GAS LINE  
ENERGY TRANSFER  
STEEL PIPE SIZE: 12.75"

EXISTING RCP

CABLE BARRIER SYSTEM  
1,200 LF (OF 2,581 LF)

CABLE BARRIER SYSTEM  
1,200 LF (OF 2,581 LF)

☉ US 290

☉ US 290

EXISTING ROW

US 290 WB MAINLANES

US 290 EB MAINLANES

EXISTING ROW

EXISTING ROW

US 290 WB MAINLANES

US 290 EB MAINLANES

EXISTING ROW

MATCHLINE STA. 344+18.30

MATCHLINE STA. 356+18.30

MATCHLINE STA. 356+18.30

MATCHLINE STA. 368+18.30

345+00

350+00

355+00

360+00

365+00



22'

22'




CK: DW: CK: DN:

DATE: \$DATE\$  
FILE: \$FILES



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT



SHEET 11 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	37

SCALE: 1"=100'

CK: DW: CK: DN:

DATE: \$DATE\$  
FILE: \$FILES\$



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT

SHEET 12 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	38	



SCALE: 1"=100'

CK: DW: CK: DN:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

© 2023  
Texas Department of Transportation

### CABLE BARRIER LAYOUT



SHEET 13 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	39	

DATE: \$DATE\$  
FILE: \$FILES\$


SCALE: 1"=100'

CK: DW: CK: DN:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT



SHEET 14 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	40

DATE: \$DATE\$  
FILE: \$FILES\$

SCALE: 1"=100'

CK: DW: CK: DN:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

© 2023  
Texas Department of Transportation


### CABLE BARRIER LAYOUT

SHEET 15 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	41	

DATE: \$DATES\$  
FILE: \$FILES\$

SCALE: 1"=100'



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

© 2023  
Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 16 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	42	

DATE: \$DATE\$  
FILE: \$FILES\$

SCALE: 1"=100'

CK: DW: CK: DN:



DATE: \$DATE\$  
FILE: \$FILES

MATCHLINE STA. 512+18.30

MATCHLINE STA. 524+18.30


MATCHLINE STA. 524+18.30

MATCHLINE STA. 536+18.30



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 17 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	43	



SCALE: 1"=100'


CK: DW: CK: DN:




- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



  
*Robert S. Bissett, Jr.*  
 12/04/23

  
**CABLE BARRIER LAYOUT**  
 SHEET 18 OF 37


CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	44

DATE: \$DATE\$  
FILE: \$FILES\$

SCALE: 1"=100'





CK: DW: CK: DN:




- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.




  
 Robert S. Bissett, Jr.  
 12/04/23

DATE: \$DATE\$ \$TIMES\$  
FILE: \$FILES\$

  
**CABLE BARRIER LAYOUT**  
 SHEET 19 OF 37


CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	45

SCALE: 1"=100'



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

© 2023  
Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 20 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	46

DATE: \$DATE\$  
FILE: \$FILES\$

SCALE: 1"=100'



CK: DW: CK: DW:

LEGEND

- ← TRAFFIC DIRECTION
- EXISTING SIGN TO BE RELOCATED
- ◇ RELOCATED SIGN NUMBER

NOTES:


1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



PI	623+30.29
Δ	16°18'12.9" (LT)
D	01°00'00.0"
T	820.73'
L	1630.36'
R	5729.58'
PC	615+09.56
PT	631+39.92

END CABLE BARRIER SYSTEM  
APPROX. 63' BEYOND GUARDRAIL  
(MINIMUM 60')

BEGIN CABLE BARRIER SYSTEM  
AT RIPRAP EMBANKMENT



*Robert S. Bissett, Jr.*

12/04/23



CABLE BARRIER LAYOUT



SHEET 21 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	47	

DATE: \$DATES\$  
FILE: \$FILES\$

SCALE: 1"=100'


CK: DW: CK: DW:




- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.

DATE: \$DATES\$  
FILE: \$FILES\$

  
 Robert S. Bissett, Jr.  
 12/04/23

  
**CABLE BARRIER LAYOUT**

SHEET 22 OF 37




CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	48

SCALE: 1"=100'

CK: DW: CK: DW: CK: DW:

- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
 12/04/23

© 2023  
 Texas Department of Transportation

**CABLE BARRIER LAYOUT**



SHEET 23 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		49

DATE: \$DATES\$  
 FILE: \$FILES\$

SCALE: 1"=100'

CK: DW: CK: DN:



PI 697+31.83  
 Δ 29°11'25.4" (RT)  
 D 01°00'00.0"  
 T 1491.93'  
 L 2919.04'  
 R 5729.58'  
 PC 682+39.90  
 PT 711+58.94

- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

**CABLE BARRIER LAYOUT**



SHEET 24 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	50

DATE: \$DATE\$  
FILE: \$FILES\$


SCALE: 1"=100'

CK:  
DW:  
CK:  
DW:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

DATE: \$DATE\$  
FILE: \$FILES\$




<b>CABLE BARRIER LAYOUT</b>			
SHEET 25 OF 37			
CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY		SHEET NO.
HOU	WALLER, ETC.		51

SCALE: 1"=100'

CK: DW: CK: DW:

- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT

SHEET 26 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	52

DATE: \$DATES\$  
FILE: \$FILES\$



SCALE: 1"=100'




CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DN: \_\_\_\_\_

- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



PI 769+42.99  
 Δ 27°31'48.0" (LT)  
 D 01°00'00.0"  
 T 1403.61'  
 L 2753.00'  
 R 5729.58'  
 PC 755+39.38  
 PT 782+92.38



*Robert S. Bissett, Jr.*  
 12/04/23



**CABLE BARRIER LAYOUT**



SHEET 27 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	53	

DATE: \$DATE\$ \$TIMES  
 FILE: \$FILES\$


SCALE: 1"=100'

CK: DW: CK: DW:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

DATE: \$DATES\$  
FILE: \$FILES\$

© 2023  
Texas Department of Transportation

### CABLE BARRIER LAYOUT

SHEET 28 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	54



SCALE: 1"=100'

CK: DW: CK: DW:




- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



PI 815+66.57  
 Δ 14°18'31.5" (RT)  
 D 01°15'00.0"  
 T 575.34'  
 L 1144.70'  
 R 4583.66'  
 PC 809+91.23  
 PT 821+35.93



*Robert S. Bissett, Jr.*  
12/04/23



**CABLE BARRIER LAYOUT**

SHEET 29 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	55

DATE: \$DATE\$  
FILE: \$FILES\$

SCALE: 1"=100'


CK: DW: CK: DW:

- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.


MATCHLINE STA. 824+18.30

MATCHLINE STA. 836+18.30




MATCHLINE STA. 836+18.30

MATCHLINE STA. 848+18.30



DATE: \$DATES\$  
FILE: \$FILES\$



*Robert S. Bissett, Jr.*  
12/04/23





**CABLE BARRIER LAYOUT**

SHEET 30 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	56


SCALE: 1"=100'

CK: DW: CK: DW:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

© 2023  
Texas Department of Transportation

### CABLE BARRIER LAYOUT



SHEET 31 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	57

DATE: \$DATES\$  
FILE: \$FILES\$


SCALE: 1"=100'

CK: DW: CK: DW:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

DATE: \$DATE\$  
FILE: \$FILES\$

© 2023  
Texas Department of Transportation

**CABLE BARRIER LAYOUT**

SHEET 32 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	58	



SCALE: 1"=100'

CK: DW: CK: DW: CK: DW:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



Robert S. Bissett, Jr.  
 12/04/23

**CABLE BARRIER LAYOUT**

SHEET 33 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	59

DATE: \$DATE\$  
FILE: \$FILES\$




SCALE: 1"=100'

CK: DW: CK: DW:



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT

SHEET 34 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	60

DATE: \$DATE\$  
FILE: \$FILES\$


SCALE: 1"=100'



CK: DW: CK: DW:


- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



DATE: \$DATES\$  
FILE: \$FILES\$

SCALE: 1"=100'




*Robert S. Bissett, Jr.*  
12/04/23



**CABLE BARRIER LAYOUT**

SHEET 35 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	61



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
 12/04/23

© 2023  
 Texas Department of Transportation


**CABLE BARRIER LAYOUT**

SHEET 36 OF 37

CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST	COUNTY	SHEET NO.	
HOU	WALLER, ETC.	62	


DATE: \$DATE\$  
 FILE: \$FILES\$

SCALE: 1"=100'



- LEGEND**
- ← TRAFFIC DIRECTION
  - EXISTING SIGN TO BE RELOCATED
  - ◇ RELOCATED SIGN NUMBER

- NOTES:**
1. APPROXIMATE LOCATIONS OF EXISTING CROSS DRAINAGE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT LOCATION IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.
  2. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY UTILITIES OR PIPELINES CROSSING US 290 IN ORDER TO AVOID CONFLICT WITH THE CABLE BARRIER SYSTEM POSTS.



*Robert S. Bissett, Jr.*  
 12/04/23

Texas Department of Transportation

### CABLE BARRIER LAYOUT

SHEET 37 OF 37



CONT	SECT	JOB	HIGHWAY
0114	11	094, ETC.	US 290
DIST		COUNTY	SHEET NO.
HOU		WALLER, ETC.	63

DATE: \$DATES\$  
 FILE: \$FILES\$

SCALE: 1"=100'

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES  
FILE: \$FILES



ROPE TENSION TABLE		
ROPE TEMP (°F)	TENSION (LBS)	TENSION (kN)
0	5700	25.4
5	5550	24.7
10	5400	24.0
15	5250	23.4
20	5100	22.7
25	4950	22.0
30	4800	21.4
35	4650	20.74
40	4500	20.0
45	4350	19.3
50	4200	18.7
55	4050	18.0
60	3900	17.3
65	3750	16.7
70	3600	16.0
75	3450	15.3
80	3300	14.7
85	3150	14.0
90	3000	13.3
95	2850	12.7
100	2700	12.0
105	2550	11.3
110	2400	10.7
115	2250	10.0
120	2100	9.3
125	1950	8.7
130	1800	8.0
135	1650	7.3
140	1500	6.7

\* ROPE TENSION: ± 20% AFTER 2-WEEK INTERVAL

GENERAL NOTES:

- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. AT 1-866-427-4336.
- THE BRIFEN WRSF HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-4 CONDITIONS ON SLOPES 6:1 OR FLATTER AND NCHRP 350 TL-3 CONDITIONS ON SLOPES 4:1 TO 6:1.
- THE POST SPACING SHALL BE DETERMINED BY THE SPECIFYING AGENCY. POST SPACING MAY BE DECREASED TO AVOID OBSTRUCTIONS OR UTILITIES. IN NO EVENT SHALL THE POST SPACING EXCEED 21'-0".
- BRIFEN WRSF SHALL BE PLACED ON A SMOOTH SURFACE, WITHOUT HUMPS, DROP-OFFS, HOLES, ETC THAT WOULD INTERFERE WITH THE STABILITY OF THE ERRANT VEHICLE. GRADING, FILL AND COMPACT MAY BE REQUIRED TO ASSURE THAT ROPES ARE INSTALLED AT THE DESIGN HEIGHT.
- THE WRGT-FL END ANCHOR HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-3 CONDITIONS. THE LENGTH OF NEED BEGINS 31'-0" FROM THE END ANCHOR. POSTS A THROUGH POST B3, SPACED 6'-6" APART, HAVE WEAKENED CUTS AT THE GROUND THAT SHALL FACE THE ANCHOR.
- ANCHOR AND LINE POST DIMENSIONS AND STEEL REINFORCEMENT WILL BE DETERMINED ON PROJECT SPECIFIC SOIL CLASSIFICATION, PROPERTIES AND TEMPERATURE EXTREMES. CONTACT BRIFEN USA, INC. FOR ADDITIONAL INFORMATION.
- ALL REINFORCEMENT AND CONCRETE FOR THE ANCHORS AND LINE POSTS PROVIDED BY OTHERS.
- REINFORCEMENT AND CONCRETE PROPERTIES SHALL MEET AGENCY SPECIFICATIONS.
- FOR PLACEMENT NEAR GUARDRAIL OR OTHER OBSTACLES CONTACT BRIFEN USA, INC. FOR ADDITIONAL DRAWINGS AND SUPPORT.
- TAPER RATES FOR THE BRIFEN WRSF ARE AS FOLLOWS:  
HORIZONTAL: 25:1 MAXIMUM, 50:1 PREFERABLE  
VERTICAL: 25:1 MAXIMUM, 50:1 PREFERABLE

\*SEE SHEET 3 OF 3 FOR FURTHER INFORMATION

SHEET 1 OF 3



**BRIFEN  
WIRE ROPE SAFETY FENCE  
(TL-4)**


**BRIFEN(TL4) - 14**

FILE: brifent1414.dgn	DN: TxDOT	CK: RM	DW: VP	CK:
© TxDOT: MARCH 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
	DIST	COUNTY	SHEET NO.	
	HOU	WALLER, ETC.	64	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES  
FILE: \$FILES


**LINE POST ASSEMBLY [Z11]**



**NOTES SPECIFIC TO LINE POST ASSEMBLY**

1. ROPE HEIGHTS SHALL BE  $\pm 1"$  TO GROUND LINE.
2. POST SHALL BE  $\pm 4"$  FROM VERTICAL PLUMB.
3. POST CAPS SHALL BE USED IF SPECIFIED.
4. REFLECTORS SHALL BE SPACED ACCORDING TO AGENCY SPECIFICATIONS.
5. REFLECTORS CAN BE PLACED ON THE POST CAP OR POST.


**ROPE CONNECTION DETAIL**



**NOTES SPECIFIC TO ROPE CONNECTION DETAIL**

1. THE WIRE ROPE TERMINALS SHALL BE THREADED A MINIMUM OF 1-1/2" INTO RIGGING SCREW.
2. AFTER FINAL TENSIONING, THE TERMINALS SHALL BE VISIBLE IN THE INSPECTION HOLES.

**SOCKET ASSEMBLY**



**NOTES SPECIFIC TO CONCRETE FOOTING**

1. SIZE OF FOOTING WILL BE DETERMINED BY SOIL CONDITIONS, FOUNDATION TYPE AND PROJECT CONDITIONS.
2. CONCRETE BASED ON AGENCY SPECIFICATIONS.
3. CONCRETE BY OTHERS.
4. REINFORCING RING (BY OTHERS) WILL BE USED ACCORDING TO FOUNDATION SIZE AND TYPE. THE REINFORCING RING MAY BE OMITTED IF THE FOOTING IS PLACED IN A CONTINUOUS CONCRETE MOW STRIP.
5. FOOTING SHALL BE FLUSH WITH THE GROUND LINE, TO A MAXIMUM OF 1 INCH BELOW OR ABOVE GROUND LINE.
6. SOCKET SHALL BE  $\pm 2^\circ$  OF VERTICAL PLUMB.

**NOTES SPECIFIC TO DRIVE SOCKETS**

1. SIZE OF SOIL PLATE WILL BE DETERMINED BY SOIL CONDITIONS AND PROJECT CONDITIONS.
2. THE SOIL PLATE SHALL BE PARALLEL TO ROADWAY AND CAN FACE TOWARD OR AWAY FROM THE TRAVEL LANE.
3. FOOTING SHALL BE FLUSH WITH THE GROUND LINE, TO A MAXIMUM OF 1 INCH BELOW OR ABOVE GROUND LINE.
4. SOCKET SHALL BE  $\pm 2^\circ$  OF VERTICAL PLUMB.
5. SOCKETS SHALL BE DRIVEN IN A MANNER TO NOT DISTORT OR DESTROY THE TOP OF SOCKET TO A DEGREE THAT PLACES THE SOCKET OR LINE POST OUT OF CONSTRUCTION TOLERANCES.

**GENERAL NOTES:**

1. BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. 1-866-427-4336.
2. THE BRIFEN WRSF HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-4 CONDITIONS ON SLOPES 6:1 OR FLATTER AND NCHRP 350 TL-3 CONDITIONS ON SLOPES 4:1 TO 6:1.
3. THE POST SPACING SHALL BE DETERMINED BY THE SPECIFYING AGENCY. POST SPACING MAY BE DECREASED TO AVOID OBSTRUCTIONS OR UTILITIES. IN NO EVENT SHALL THE POST SPACING EXCEED 21'-0".
4. BRIFEN WRSF SHALL BE PLACED ON A SMOOTH SURFACE, WITHOUT HUMPS, DROP-OFFS, HOLES, ETC THAT WOULD INTERFERE WITH THE STABILITY OF THE ERRANT VEHICLE. GRADING, FILL AND COMPACTION MAY BE REQUIRED TO ASSURE THAT ROPES ARE INSTALLED AT THE DESIGN HEIGHT.

SHEET 2 OF 3



**BRIFEN  
WIRE ROPE SAFETY FENCE  
(TL-4)**


**BRIFEN(TL4) - 14**

FILE: brifent1414.dgn	DN: TxDOT	CK: RM	DW: VP	CK:
© TxDOT: MARCH 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
	DIST	COUNTY	SHEET NO.	
	HOU	WALLER, ETC.	65	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: \$DATES\$  
FILE: \$FILES\$


### WRGT-FL END ANCHOR LAYOUT



#### GENERAL NOTES:

- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. AT 1-866-427-4336.
- THE WRGT-FL END ANCHOR HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-3 CONDITIONS. THE LENGTH OF NEED BEGINS 31'-0" FROM THE END ANCHOR. POSTS A THROUGH POST B3, SPACED 6'-6" APART, HAVE WEAKENED CUTS AT THE GROUND THAT SHALL FACE THE ANCHOR.
- ANCHOR AND LINE POST DIMENSIONS AND STEEL REINFORCEMENT WILL BE DETERMINED ON PROJECT SPECIFIC SOIL CLASSIFICATION, PROPERTIES AND TEMPERATURE EXTREMES. CONTACT BRIFEN USA, INC. FOR ADDITIONAL INFORMATION.
- ALL REINFORCEMENT AND CONCRETE FOR THE ANCHORS AND LINE POSTS PROVIDED BY OTHERS.
- REINFORCEMENT AND CONCRETE PROPERTIES SHALL MEET AGENCY SPECIFICATIONS.
- FOR PLACEMENT NEAR GUARDRAIL OR OTHER OBSTACLES CONTACT BRIFEN USA, INC. FOR ADDITIONAL DRAWINGS AND SUPPORT.


### WRGT-FL POST DETAILS



#### NOTES SPECIFIC TO WRGT-FL POST DETAIL

- ROPE HEIGHTS SHALL BE  $\pm 1"$  TO GROUND LINE.
- POST SHALL BE  $\pm 4"$  FROM VERTICAL PLUMB.
- POST CAPS SHALL BE USED IF SPECIFIED.
- REFLECTORS SHALL BE SPACED ACCORDING TO AGENCY SPECIFICATIONS.
- REFLECTORS CAN BE PLACED ON THE POST CAP OR POST.
- Z EXCLUDER (Z41) SHALL BE USED.
- POST A & SOCKET SHALL BE PLACED  $79^\circ (\pm 4^\circ)$  TOWARD END ANCHOR FROM THE HORIZONTAL PLANE.
- POST A SOCKET SHALL BE PLACED IN 14" (MIN) CONCRETE FOUNDATION. DEPTH TO BE DETERMINED FROM SOIL CONDITIONS AND PROJECT CONDITIONS.
- FOUNDATIONS FOR POST 2 THRU 4 SHALL BE THE SAME AS THE LINE POST ASSEMBLY'S FOR THE PROJECT.
- WEAKENED CUTS SHALL FACE END ANCHOR.


### END ANCHOR DETAILS



#### NOTES SPECIFIC TO END ANCHOR DETAIL

- THE END ANCHOR ASSEMBLY SHALL BE PLACED 12" (+3", -1") BELOW HORIZONTAL PLANE.
- POST 1 & SOCKET SHALL BE PLACED  $79^\circ (\pm 4^\circ)$  TOWARD END ANCHOR FROM THE HORIZONTAL PLANE.
- POST 1 SOCKET SHALL BE PLACED IN 14" (MIN) CONCRETE FOUNDATION. DEPTH TO BE DETERMINED FROM SOIL CONDITIONS AND PROJECT CONDITIONS.

### END ANCHOR COMPONENTS



SHEET 3 OF 3



**BRIFEN**  
**WIRE ROPE SAFETY FENCE**  
**(TL-4)**


**BRIFEN(TL4) - 14**

FILE: brifentl414.dgn	DN: TxDOT	CK: RM	DW: VP	CK:
© TxDOT: MARCH 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
	DIST	COUNTY		SHEET NO.
	HOU	WALLER, ETC.		66


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**Preferred Installation:** Locate post #2 away from nearest traffic. System has been successfully tested with opposite installation.



**Length-of-Need Cass Cable Terminal (CCT):**  
**Departure Installation:** Length-of-Need: 44'-9" (At Post #8)  
**Approach Installation:** Length-of-Need: 19'-9" (12" Post Post #4)



**PLAN VIEW**




**ELEVATION VIEW (TYPICAL LAY-OUT)**




**SECTION E-E**


**SECTION F-F**




**SECTION G-G**




**VIEW A-A (CABLE RELEASE POST 1-3)**




**VIEW B-B (TERMINAL LINE POST 4-7)**



**SECTION C-C (SOCKETED POST)**



**SECTION D-D (BASE PLATED POST)**



**STANDARD POST & CONCRETE FOOTING (SOCKETED POST)**

- GENERAL NOTES**
- This drawing is a general overview of CASS TL-4 Barrier System. See SS-740 (latest version) for specific details of CASS cable terminal (CCT) and cable safety system (CASS) requirements, proper installation, options and specification.
  - CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity (800-527-6050) or consult the design, installation, or repair manual(s) for additional information.
  - All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
  - All posts shall be socketed unless otherwise specified. All cables shall be pre-stretched unless otherwise specified.
  - For payment see Special Specification "Cable Barrier System".
  - CASS-TL4 shall be installed on shoulders or medians with slopes of 6:1 or flatter without obstructions, depressions, etc. That may significantly affect the stability of an erring vehicle. Grading of site and/or appropriate fill materials may be required. The designer/installer shall "Flatten" or "Round" various topographical inconsistencies that could interfere with the ability of the installer to consistently maintain the design height (in relation to the terrain) of the cables. Please consult manual(s) and / or TxDOT Memo(s) for installations in "Ditch Sections".
  - CASS TL-4 post spacing may be modified to avoid obstacles that conflict with the installation of cass-tl4 line posts or to reduce deflection on radiuses. No post space can exceed the maximum post TxDOT space limit of 20'. Reducing or increasing post spacing affects deflection. CASS TL-4 may be laterally transferred at a rate not to exceed 30:1.
  - Post foundations may be drilled through existing pavement. Please see line post foundation chart for minimum footing requirements in various applications.
  - For aesthetic purposes Trinity recommends all sleeves, driven posts, and lower cable release posts to be installed reasonably plumb (approximately 1/8" per foot).
  - CASS TL-4 shall be installed in well-drained, compacted, NCHRP Report 350 Standard soil. If soil does not meet this classification, if solid rock/concrete is encountered below grade or if soil is susceptible to severe freeze/thaw cycles, please contact Trinity about alternate footing design(s). Trinity suggests the use of "Mow strips" for erosion prevention and ease of maintenance / installation.
  - See the Texas MUTCD for proper "Barrier" Delineation.

MOW STRIP DETAIL*			CONCRETE FOOTING CHART		
MOW STRIP	DEPTH	WIDTH	FOOTING	TUBE SLEEVE	REBAR RING
NONE			30" Min.	27" Min.	YES
HMA	6" Min.	3' Min.	27" Min.	15" Min.	NO
HMA	8" Min.	3' Min.	24" Min.	15" Min.	NO
RC	3" Min.	3' Min.	24" Min.	15" Min.	NO

Chart does not apply to Terminal Posts 1 thru 9.  
 \* Mow strip or pavement.  
 HMA = Hot Mix Asphalt (Not Recycled Asphalt Pavement).  
 RC = Reinforced Concrete (TxDOT Class A Minimum).

Trinity Highway Products, LLC.  
 2525 Stemmons Freeway  
 Dallas, TX 75207  
 Phone: (800) 644-7976  
 Product: INFO@TRIN.NET


CABLE TENSION CHART	
FAHRENHEIT DEGREES	PRE-STRETCHED LB / FORCE
-10	7300
0	7000
10	6600
20	6300
30	6000
40	5600
50	5300
60	5000
70	4600
80	4300
90	4000
100	3600
110	3300
120	3000
130	2700
140	2500
150	2300

Allowable deviation from chart in tangent sections: +800, -200 pounds/force. Cable tension readings are typically higher in curved cable sections.

Texas Department of Transportation  
**TRINITY CABLE SAFETY SYSTEM (TL-4)**  
**CASS (TL4) - 14**

FILE: casst1414.dgn	DN: TxDOT	CK: RM	DW: VP	CK:
©TxDOT: March 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US290
	DIST	COUNTY	SHEET NO.	
	HOU	WALLER, ETC.	67	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**GENERAL NOTES**

- For additional information contact Gibraltar, Inc. at 1-800-495-8957, 830-798-5444, or see the manufacturer's product manual.
- All concrete shall be CLASS A.
- The Cable Barrier System shall be installed on shoulders or on medians with slopes of 6:1 or flatter. If installed on slopes steeper than 6:1 up to 4:1 the TL-4 system performs as a TL-3 and Gibraltar must be contacted for various guidelines related to placement.
- The Cable Barrier System is accepted by the FHWA Test Level - 4.
- See the Texas MUTCD for proper "Barrier" delineation.
- Rock Clause: Where solid rock is encountered:
  - For socketed post, continue digging 12" diameter, 15" deep into rock or the required plan depth, whichever comes first.
  - For driven post, core drill a 4" diameter hole 18" deep into rock or the required plan depth, whichever comes first.
  - For Anchor post, continue digging 24" diameter, 30" deep into rock or the required plan depth, whichever comes first.
- Tolerances:
  - \* LP = 3" out of plumb, at top
  - \* Cable height = 1"
  - \* Anchor Post = 5" off of Cable Reference Line
- The Gibraltar cable barrier system shall be installed in NCHRP Report 350 standard compacted soil. Soil must be well drained.
- All non-welded rebar by others.
- Minimum recommended line post foundation.
  - Without mowstrip, 36" Deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long
  - With 4" minimum depth hot mix asphalt, 30" deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long.
  - With 3" minimum depth concrete mowstrip, 24" deep x 12" diameter foundations. (No rebar required)
  - Direct drive post 42" deep.

**CABLE TENSION CHART\***

-10 °F	8000
0 °F	7600
10 °F	7200
20 °F	6800
30 °F	6400
40 °F	6000
50 °F	5600
60 °F	5200
70 °F	4800
80 °F	4400
90 °F	4000
100 °F	3600
110 °F	3200

**DEFLECTION**

Deflection	Post Spacing
8'-0"	20 FT
7'-0"	12 FT
6'-8"	10 FT

\* Allowable Deviation from Chart +/- 10%

Design Division Standard

**GIBRALTAR CABLE BARRIER SYSTEM (TL-4)**



**GBRL TR (TL4) - 14**

FILE: gbrl tr t1414.dgn	DN: TxDOT	CK: RM	DW: VP	CK:
© TxDOT: March 2014	CONT: 0114	SECT: 11	JOB: 094, ETC.	HIGHWAY: US 290
REVISIONS		DIST: HOU	COUNTY: WALLER, ETC.	SHEET NO.: 68

DATE: \$DATES\$  
FILE: \$FILES\$



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- GENERAL NOTES**
- FOR ADDITIONAL INFORMATION CONTACT YOUR DISTRIBUTOR OR NUCOR STEEL MARION, INC. AT (740) 383-4011.
  - FOR PAYMENT SEE SPECIAL SPECIFICATION "CABLE BARRIER SYSTEM".
  - FOR ADDITIONAL INFORMATION SEE THE MANUFACTURER'S PRODUCT MANUAL.
  - THE NU-CABLE SYSTEM IS DESIGNED FOR BI-DIRECTIONAL TRAFFIC FLOWS. SEE THE MANUFACTURER'S PRODUCT MANUAL FOR PLACEMENT ADJACENT TO GUARDRAIL END TREATMENTS.
  - THE NU-CABLE SYSTEM SHALL BE INSTALLED ON MEDIANS WITH SLOPES OF 6:1 OR FLATTER WITHOUT OBSTRUCTIONS, DEPRESSIONS, ETC; THAT MAY SIGNIFICANTLY AFFECT THE STABILITY OF AN ERRANT VEHICLE.
  - THE NU-CABLE SYSTEM MAY BE INSTALLED ON EITHER SIDE OF THE ROADWAY. Rib-Bak™ CABLE LINE POSTS MAY BE SOCKETED OR DRIVEN DESIGN.
  - THE TL-4 FOR 6:1 SLOPES CAN USE 4# / LF POST. SEE TABLE #1 FOR POST SIZE PER SPACING.
  - SEE (TABLE 2) FOR TENSION AMOUNT AT SPECIFIC CABLE TEMPERATURE FOR INITIAL INSTALLATION.
  - SEE (TABLE 3) FOR TENSION AMOUNT AT SPECIFIC CABLE TEMPERATURE FOR MAINTENANCE.
  - FOURTH (LOWEST) CABLE IS NOT OPTIONAL ON THE TL-4 SYSTEM.
  - CONSULT YOUR PROJECT PLAN SHEETS AND CABLE BARRIER SPECIFICATIONS FOR DESIRED SOCKET MATERIAL.
  - ALL FOUNDATION DESIGNS ARE BASED ON NCHRP 350 STRONG (S1) SOIL. CONSULT THE MANUFACTURER FOR SPECIFIC FOUNDATION DESIGN IF SOIL TYPES DIFFER.

⑦ TABLE 1

POST SIZE TABLE	
POST SPACING	POST SIZE
0' - 17'-6"	4# / LF X 4' OR 6' POST
17'-6" - 20'	5# / LF X 4' POST







POST SPACING IS PER 8 FOOT DEFLECTION REQUIREMENTS. CONSULT PRODUCT MANUAL IF GREATER DEFLECTION IS PERMISSIBLE.

⑧ TABLE 2

CABLE TENSION CHART	
INITIAL INSTALL	
F	LBF
120	4624
110	4986
100	5350
90	5713
80	6077
70	6440
60	7167
50	7894
40	8619
30	9346
20	10073
10	10800
0	11525
-10	12252
-20	12979
-30	13706

⑨ TABLE 3

CABLE TENSION CHART	
MAINTENANCE	
F	LBF
120	4021
110	4336
100	4652
90	4968
80	5284
70	5600
60	6232
50	6864
40	7495
30	8127
20	8759
10	9391
0	10022
-10	10654
-20	11286
-30	11918



SHEET 1 OF 2

Design Division Standard


**NU-CABLE BARRIER SYSTEM**  
**(TL-4)**  
**(4 CABLE)**  
**NU-CABLE (TL4) - 14**

FILE: nucable1414	DN: TxDOT	CK: RM	DW: VP	CK:
©TxDOT: March 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
	DIST	COUNTY	SHEET NO.	
	HOU	WALLER, ETC.	69	


DATE: \$DATE\$  
 FILE: \$FILES\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: \$DATE\$  
FILE: \$FILES\$




**SECTION B-B**  
(CABLE RELEASE POST)



**DETAIL A - CRP IN CONCRETE FOOTING**  
(3000 PSI MIN CONCRETE)




**DRIVEN SOCKET OPTION**



**NU-TEN CONCRETE FOOTING DETAIL**


**TABLE 4**

CRP END TERMINAL CABLE HEIGHTS - TL-4						
	LP 1	LP 2	LP 3	LP 4	LP 5	LP 6
TOP CABLE	34"	34"	34"	34"	34"	34"
UPPER-MIDDLE CABLE	27"	27"	27"	27"	28"	31"
BOTTOM-MIDDLE CABLE	24"	24"	24"	24"	24"	24"
BOTTOM CABLE	15"	15"	15"	15"	15"	15"



**CRP POST END TERMINAL SYSTEMS**

① THE OPPOSING END TREATMENTS ON A PARTICULAR RUN ARE MIRRORED IN THEIR LAYOUT.



**NU-TEN END TERMINAL SYSTEM**

**NOTES**

1. THE OPPOSING END TREATMENTS ON A PARTICULAR RUN ARE MIRRORED IN THEIR LAYOUT. SYSTEM PAYMENT IS PER EACH (EA). REFER TO PROJECT SPECIFICATIONS FOR ADDITIONAL PAYMENT INFORMATION
2. REFER TO INSTALLATION MANUAL FOR CABLE END ASSEMBLY DETAIL.
3. ALL FOUNDATION DESIGNS ARE BASED ON NCHRP 350 STRONG (S1) SOIL. CONSULT THE MANUFACTURER FOR SPECIFIC FOUNDATION DESIGNS IF SOIL TYPES DIFFER.
4. SEE TABLE 4 CABLE HEIGHTS IN CRP TRANSITION SECTION.

SHEET 2 OF 2



**NU-CABLE BARRIER SYSTEM (TL-4) (4 CABLE)**

**NU-CABLE (TL4) - 14**

FILE: nucable1414	DN: TxDOT	CK: RM	DW: VP	CK:
© TxDOT: March 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
	DIST	COUNTY		SHEET NO.
	HOU	WALLER, ETC.		70

**DISCLAIMER:**  
 The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)**

This project is adjacent or parallel work, not within RR ROW:  
 DOT No.: 743131F  
 Crossing Type: Underpass  
 RR Company Operating Track at Crossing: Union Pacific Railroad Company (UP)  
 RR Company Owning Track at Crossing: UPRR  
 RR MP: 46.350  
 RR Subdivision: Eureka Sub  
 City: Hempstead  
 County: Waller  
 CSJ at this Crossing: 0114-11-094  
 Latitude: 30°06'55.60"N  
 Longitude: 96°04'50.10"W

Scope of Work, including any TCP, to be performed by State Contractor:

- 1) Install median cable barrier.
- 2) Using TCP(1-5)-18 and TCP(2-6)-18 for traffic control.

Scope of Work to be performed by Railroad Company:

N/A

**II. FLAGGING & INSPECTION**

No. of Days of Railroad Flagging Expected: 0  
 On this project, night or weekend flagging is:  
 Expected  
 Not Expected

Flagging services will be provided by:

- Railroad Company: 1) Txdot will pay flagging invoices. Flagging Agreement with railroad will be needed or, 2) Permitted crossing. Railroad company to provide flagging.
- Outside Party: Contractor will pay flagging invoices to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30-day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

- UPRR** UP.info@railpros.com  
Call Center 877-315-0513, Select #1 for flagging  
UP.request@nrssinc.net  
Call Center 877-984-6777
- BNSF** BNSFinfo@railprofs.com  
Call Center 877-315-0513, Select #1 for flagging
- CPKCR** KCS.info@railpros.com  
Call Center 877-315-0513, Select #1 for flagging  
Bottom Line On-Track Safety Services  
bottomline076@aol.com, 903-767-7630

OTHERS:

Contractor must incorporate railroad construction inspection into anticipated construction schedule.

- Not Required
- Required. Contact Information for Construction Inspection:

**III. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD**

- Required.
  - Not Required
- Railroad Point of Contact: \_\_\_\_\_

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

**IV. RAILROAD INSURANCE REQUIREMENTS**

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies and corresponding certificates of insurance must be issued by the contractor on behalf of the Railroad. Separate insurance policies and certificates are required when more than one Railroad Company is operating on the same right of way, or when several Railroad Companies are involved and operate on their own separate right of ways.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Escalated Limits	
Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$2,000,000 / \$4,000,000
Business Automobile	\$2,000,000

Railroad Protective Liability Limits	
<input type="checkbox"/> Not Required	
<input checked="" type="checkbox"/> Non - Bridge/Typical Maintenance Projects. Includes repairs to overpass/underpass and culvert structures	\$2,000,000 / \$6,000,000
<input type="checkbox"/> Bridge Structure Projects. Includes new construction or replacement of overpass/underpass structures	\$5,000,000 / \$10,000,000
<input type="checkbox"/> Other: _____	

**V. CONTRACTOR'S RIGHT OF ENTRY (CROE)**

- Not Required
- Required: UPRR Maintenance Consent Letter. TxDOT to assist
- Required: TxDOT to assist in obtaining the UPRR CROE
- Required: Contractor to obtain
  - BNSF: \_\_\_\_\_  
https://bnsf.railpermitting.com
  - CPKCR  
https://jllrpg.360works.com/fmi/webd/rpo\_web\_kcs.fmp12
  - Other Railroads: \_\_\_\_\_

To view previously approved CROE templates agreed upon between the State and Railroad, see: <https://www.txdot.gov/business/resources/railroad-highway-crossing/sample-right-of-entry-agreements.html>

Approved CROE templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed CROE between the Contractor and the Railroad if required on project.

**VI. RAILROAD COORDINATION MEETING**

A Railroad Coordination Meeting is required. See item 5, Article 8.1, of the Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges Manual for more details.

**VII. RAILROAD SAFETY ORIENTATION**

A. Complete the Railroad's course "Orientation for Contractor's Safety," and maintain registration prior to working on the Railroad's property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

UPRR, BNSF, CPKCR will not accept on-track safety training certificates from other Railroads. Refer to each Railroad's specific contractor right of entry for training information.

Know and follow the Contractor's Right of Entry Agreement EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

**VIII. SUBCONTRACTORS**

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are subject to the same insurance requirements as the Prime Contractor.

**IX. EMERGENCY NOTIFICATION**

**In Case of Railroad Emergency**

Call: UPRR \_\_\_\_\_

Railroad Emergency Line at: 800-848-8715

Location: DOT\_DOT 743131F


RR Milepost: 46.350

Subdivision: Eureka Sub

**RRD Review Only**

Initials: AB

Date: 10/25/23

		<b>Rail Division</b>
<p><b>RAILROAD SCOPE OF WORK</b>          PROJECT SPECIFIC DETAILS          SH 6 @ UPRR          DOT NO. 921035U</p>		
FILE: rr-scope-of-work.pdf	DN: TxDOT	CK: _____
© TxDOT June 2014	CONT	SECT
	0114	11
	JOB	
	094, ETC	
	HIGHWAY	
	US 290	
6/2023	DIST	COUNTY
	HOU	WALLER, ETC.
		SHEET NO.
		71

**PART 1 - GENERAL**

**1.01 DESCRIPTION**

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

**1.02 REQUEST FOR INFORMATION / CLARIFICATION**

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

**1.03 PLANS / SPECIFICATIONS**

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

**PART 2 - UTILITIES AND FIBER OPTIC**

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

**PART 3 - CONSTRUCTION**

**3.01 GENERAL**

- A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.
- B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.
- C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.
- D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.
- E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.
- F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.
- G. All permanent clearances shall be verified before project closing.

**3.02 RAILROAD OPERATIONS**

- A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.
- B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. Railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.
- C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:
  - 1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.
  - 2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

**3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES**

- A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.
- B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.
- C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.
- D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
  - 1. Exactly what the work entails.
  - 2. The days and hours that work will be performed.
  - 3. The exact location of work, and proximity to the tracks.
  - 4. The type of window requested and the amount of time requested.
  - 5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.
- E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

**3.04 INSURANCE**

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

**3.05 RAILROAD SAFETY ORIENTATION**

- A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.
 

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."
- B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

**3.06 COOPERATION**

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

**3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES**

Abide by the following minimum temporary clearances during the course of construction:


- A. 15' - 0" (BNSF) (UPRR) and 14' - 0" (KCS) horizontal from centerline of track
- B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

**3.08 APPROVAL OF REDUCED CLEARANCES**

- A. Maintain minimum track clearances during construction as specified in Section 3.07.
- B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.
- C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

DATE: \$DATE\$  
FILE: \$FILE\$

				Rail Division	
<b>RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS</b>					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS March 2020	0114	11	094, ETC.	US 290	
	DIST		COUNTY		SHEET NO.
	HOU		WALLER, ETC.		72

**3.09 MAINTENANCE OF RAILROAD FACILITIES**

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractors's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

**3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE**

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
  1. Pre-construction meetings.
  2. Pile driving/drilling of caissons or drilled shafts.
  3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
  4. Erection of precast concrete or steel bridge superstructure.
  5. Placement of waterproofing (prior to placing ballast on bridge deck).
  6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

**3.11 RAILROAD REPRESENTATIVES**

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

**3.12 COMMUNICATIONS AND SIGNAL LINES**

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

**3.13 TRAFFIC CONTROL**

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

**3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK**

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193  
7:00 AM to 9:00 PM CST Monday-Friday except holidays,  
staffed 24 hrs/day for emergencies  
48 hrs notice required

BNSF 1-800-533-2891  
24 hour number  
5 working days notice required

KCS 1-800-344-8377  
Texas One Call, a 24 hour number  
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.

- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

**3.15 RAILROAD FLAGGING**

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

**3.16 CLEANING OF RIGHT-OF-WAY**

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.



**RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS**

FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT October 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS March 2020	0114	11	094, ETC.	US 290
	DIST	COUNTY	SHEET NO.	
	HOU	WALLER, ETC.	73	

DATE: \$DATE\$  
FILE: \$FILE\$  
TIME: \$TIME\$

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with soil disturbing activity and for projects that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**

0114-11-094, etc.

**1.2 PROJECT LIMITS:**

From: Washington County Line

To: Fields Store Road

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 30° 07' 46" N, (Long) 95° 11' 09" W

END: (Lat) 30° 04' 08" N, (Long) 95° 55' 18" W

**1.4 TOTAL PROJECT AREA (Acres):** 6.05

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** 4.34

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

Construction consisting of the installation of a median cable barrier system.

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
Brazoria-Norwood	Nearly level to gently sloping, somewhat poorly drained, clayey and loamy soils
Tabor-Tremona-Chazos	Gently sloping to sloping, moderately well drained and somewhat poorly drained, loamy and sandy soils
Kenney-Tabor-Chazos	Gently sloping to sloping, well drained and moderately well drained, sandy and loamy soils

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s
N/A	N/A

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
  - Blade existing topsoil into windrows, prep ROW, clear and grub
  - Remove existing pavement
- Grading operations, excavation, and embankment
  - Excavate and prepare subgrade for proposed pavement widening
  - Remove existing culverts, safety end treatments (SETs)
  - Remove existing metal beam guard fence (MBGF), bridge rail
  - Install proposed pavement per plans
  - Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
  - Place flex base
  - Rework slopes, grade ditches
  - Blade windrowed material back across slopes
  - Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
  - Other: \_\_\_\_\_
  - Other: \_\_\_\_\_
  - Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- 
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Segment 1202: Brazos River Below, Brazos River Basin	Classified, Freshwater Stream
Segment 1202P: Pond Creek, Brazos River Basin	Unclassified

\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**


- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity



*Robert S. Bissett, Jr.*  
01/10/24

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

© 2023 July 2023 Sheet 1 of 2  
Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
			74
STATE	STATE DIST.	COUNTY	
TEXAS	HOU	WALLER	
CONT.	SECT.	JOB	HIGHWAY NO.
0114	11	094, ETC.	US 290

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

**T / P**

- Sediment Trap
  - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
  - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
  - Not required (<10 acres disturbed)
  - Required (>10 acres) and implemented.
    - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
    - 3,600 cubic feet of storage per acre drained
  - Required (>10 acres), but not feasible due to:
    - Available area/Site geometry
    - Site slope/Drainage patterns
    - Site soils/Geotechnical factors
    - Public safety
    - Other: \_\_\_\_\_

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To
N/A	N/A	N/A

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To
N/A	N/A	N/A

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 DEWATERING:**

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.


**2.9 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

When dewatering activities are present, a daily inspection will be conducted once per day during those activities and documented in accordance with CGP and TxDOT requirements.

**2.10 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.



*Robert S. Bissett, Jr.*


01/10/24 **STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

© 2023 July 2023 Sheet 2 of 2  
**Texas Department of Transportation**

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
			75
STATE	STATE DIST.	COUNTY	
TEXAS	HOU	WALLER	
CONT.	SECT.	JOB	HIGHWAY NO.
0114	11	094, ETC.	US 290



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

\$DATE\$  
\$FILE\$



**TEMPORARY SEDIMENT CONTROL FENCE**

SCF



**HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL**

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

**SEDIMENT CONTROL FENCE USAGE GUIDELINES**

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT<sup>2</sup>. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


**LEGEND**

Sediment Control Fence

SCF

**GENERAL NOTES**

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




**VERTICAL TRACKING**

				Design Division Standard	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE &amp; VERTICAL TRACKING</b> <b>EC(1)-16</b>					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0114	11	094, ETC.	US 290	
	DIST	COUNTY		SHEET NO.	
	HOU	WALLER, ETC.		76	




## CURB INLETS 8" DIAMETER LOGS

ITEM 506-6040 BIODEG EROSN CONT LOGS (INSTL) (8")




## DROP INLETS AND OTHER LOCATIONS 12" DIAMETER LOGS


ITEM 506-6041 BIODEG EROSN CONT LOGS (INSTL)(12")



**DROP INLETS**



**PLAN VIEW**



**SECTION C-C  
DRAINAGE SWALE OR DITCH**

### MATERIAL REQUIREMENTS

#### FILL:


Use 100% shredded mulch or other non-compost biodegradable material as fill for logs.

No compost or fines.


DO NOT USE MATERIAL WHICH PROHIBITS WATER INFILTRATION.

#### LOG MESH:


Use mesh with 1/4" openings or larger. Mesh must allow water infiltration but also hold fill material in place.




**PLAN VIEW**




**SECTION A-A  
SLOPE TO ROADWAY EDGE**



**PLAN VIEW**



**SECTION B-B  
SLOPE AWAY FROM ROADWAY EDGE**



**END OF LOG OVERLAP**

### SEDIMENT BASIN & TRAP USAGE GUIDELINES

A sediment trap (erosion control log) may be used to filter sediment out of runoff draining from an unstabilized area.

**Traps:** The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).


Sediment traps should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way

The trap should be cleaned when the capacity has been reduced by 1/2 or the sediment has accumulated to a depth of 1', whichever is less.

#### REQUIRED ITEMS:

- ITEM 506-6040 BIODEG EROSN CONT LOGS (INSTL) (8") LF
- ITEM 506-6041 BIODEG EROSN CONT LOGS (INSTL) (12") LF
- ITEM 506-6043 BIODEG EROSN CONT LOGS (REMOVE) LF




**DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS**

Texas Department of Transportation  
Houston District

## EROSION CONTROL LOG

ECL-12

FILE: STDG4a.DGN	DW: TxDot	CK: TxDot	DW: TxDot	CK: TxDot
©TXDOT 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0114	11	094, ETC.	US 290
3/15 MINOR CORRECTIONS	DIST	COUNTY		SHEET NO.
	HOU	WALLER, ETC.		77

<p><b>I. STORMWATER POLLUTION PREVENTION</b></p> <p>Texas Pollutant Discharge Elimination System (TPDES) TXR 150000: Stormwater Discharge Permit or Construction General Permit is required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506. Refer to the TxDOT SWP3 Summary Sheets, SWP3 Binder Template, and Form 2118.</p> <p style="text-align: center;">No Additional Comments</p>	<p><b>III. CULTURAL RESOURCES</b></p> <p>Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the area and contact the Engineer immediately.</p> <p style="text-align: center;">No Additional Comments</p>	<p><b>VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES</b></p> <p>Refer to TxDOT Standard Specifications in the event potentially contaminated materials are observed, such as dead or distressed vegetation, trash disposal areas, drums, canisters, barrels, leaching or seepage of substances, unusual smells or odors, or stained soil, cease work in the area and contact the Engineer immediately.</p> <p style="text-align: center;">No Additional Comments</p>																									
<p><b>II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS</b></p> <p>United States Army Corps of Engineers (USACE) Permit is required for filling, dredging, excavating or other work in water bodies, rivers, creeks, streams, wetlands or wet areas. The Contractor must adhere to all of the terms and general conditions associated with the following permit(s). If additional work not represented in the plans is required, contact the Engineer immediately.</p> <p><input checked="" type="checkbox"/> No United States Army Corps (USACE) Permit Required</p> <p><input type="checkbox"/> Work is authorized by the United States Army Corps of Engineers (USACE) under a Nationwide Permit (NWP) without a Pre-Construction Notification (PCN). Project specific permit was not issued by USACE, therefore is not in the plan set. The USACE general conditions are in the "General Notes."</p> <p><input type="checkbox"/> Work is authorized by the United States Army Corps of Engineers (USACE) under a Nationwide Permit (NWP) with a Pre-Construction Notification (PCN). The project specific permit issued by the United States Army Corps of Engineers (USACE) is included in the plan set. The USACE general conditions are in the "General Notes."</p> <p><input type="checkbox"/> Work is authorized by the United States Army Corps of Engineers (USACE) under a Individual Permit (IP). The project specific permit issued by the United States Army Corps of Engineers (USACE) is included in the plan set.</p> <p><input type="checkbox"/> Work would be authorized by the United States Army Corps of Engineers (USACE) permit. The project specific permit issued by the USACE will be provided to the contractor.</p> <p>United States Coast Guard (USCG) Permit is required for projects that involve the construction or modification (including changes to lighting) of a bridge or causeway across a water body determined to be navigable by the United States Coast Guard (USCG) under Section 9 of the Rivers and Harbors Act. If additional work not represented in the plans is required, contact the Engineer immediately.</p> <p><input checked="" type="checkbox"/> No United States Coast Guard (USCG) Coordination Required</p> <p><input type="checkbox"/> United States Coast Guard (USCG) Permit</p> <p><input type="checkbox"/> United States Coast Guard (USCG) Exemption</p> <p style="text-align: center;">No Additional Comments</p>	<p><b>IV. VEGETATION RESOURCES</b></p> <p>Preserve native vegetation to the extent practical. Refer to TxDOT Standard Specifications in order to comply with requirements for invasive species, beneficial landscaping and tree/brush removal.</p> <p style="text-align: center;">No Additional Comments</p>	<p><b>V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS</b></p> <p>If any of the listed species below are observed, cease work in the area, do not disturb species or habitat and contact the Engineer immediately.</p> <p>The work may not remove active nests (from bridges, structures, or vegetation adjacent to the roadway, etc.) during nesting season (February 15 to October 1). If removal of structures or vegetation is necessary during the nesting season, the Contractor shall conduct a bird survey no more than 3 days in advance of the clearing/demolish start date. All bird surveys shall be conducted by a Field Biologist and adhere to the guidance document "Avoiding Migratory Birds and Handling Potential Violations" found in the TxDOT Environmental Compliance Toolkits at the time of the survey. (See below for Field Biologist and Ornithologist qualifications)</p> <p style="text-align: center;">No Additional Comments</p>																									
		<p><b>VII. OTHER ENVIRONMENTAL ISSUES</b></p> <p>Comments:</p>																									
 <span style="float: right;">TxDOT Houston District</span>																											
<p><b>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</b></p> <p><b>EPIC</b></p>																											
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>FILE: EPIC Sheet.dgn</td> <td>DN:</td> <td>CK:</td> <td>DW:</td> <td>CK:</td> </tr> <tr> <td>© TxDOT: March 2017</td> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>REVISIONS</td> <td>0114</td> <td>11</td> <td>094, ETC.</td> <td>US 290</td> </tr> <tr> <td>UPDATED section V, text and added definition (10/17)</td> <td>DIST</td> <td colspan="2">COUNTY</td> <td>SHEET NO.</td> </tr> <tr> <td>ADDED USCG and USACE notes in Section VII (04/18)</td> <td>HOU</td> <td colspan="2">WALLER, ETC.</td> <td>78</td> </tr> </table>			FILE: EPIC Sheet.dgn	DN:	CK:	DW:	CK:	© TxDOT: March 2017	CONT	SECT	JOB	HIGHWAY	REVISIONS	0114	11	094, ETC.	US 290	UPDATED section V, text and added definition (10/17)	DIST	COUNTY		SHEET NO.	ADDED USCG and USACE notes in Section VII (04/18)	HOU	WALLER, ETC.		78
FILE: EPIC Sheet.dgn	DN:	CK:	DW:	CK:																							
© TxDOT: March 2017	CONT	SECT	JOB	HIGHWAY																							
REVISIONS	0114	11	094, ETC.	US 290																							
UPDATED section V, text and added definition (10/17)	DIST	COUNTY		SHEET NO.																							
ADDED USCG and USACE notes in Section VII (04/18)	HOU	WALLER, ETC.		78																							

DATE: Apr 20, 2023  
FILE: