

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION
PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT
PROJECT: MMC 6463-28-001
COUNTY: LAMAR, ETC.
HIGHWAY: US 82, ETC
CALLOUT CONTRACT

FOR THE PURCHASE OF MATERIALS ONLY, FLEXIBLE BASE & ASPHALT TREATMENT (PLANT-MIX)


Note: See Project Summary Sheets for complete listing of limits, lengths, equations and exceptions.


Index of Sheets:

- 2 General Notes
- 3 Estimate & Quantity Sheet
- 4 Plan Sheet

RECOMMENDED FOR LETTING:

APPROVED FOR LETTING:

DocuSigned by:

7D68DA3054CC40D...
2/26/2024
District Maintenance Administrator

DocuSigned by:

102795D7AE194E0...
2/26/2024
Director of Operations

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

DISTRICT	COUNTY	HIGHWAY	CONTROL
PARIS	LAMAR, ETC.	US 82, ETC	6463-28-001

© 2023 BY Texas Department of Transportation
All Rights Reserved.

Project Number: MMC – 646328001

Sheet 2

County: LAMAR, ETC.

Control: 6463-28-001

Highway: US 82, Etc.

GENERAL NOTES:

PROJECT DESCRIPTION – The primary intent of this on-call contract is to purchase roadway materials only.

This project consists of supplying Flexible Base and Asphalt Treated (Plant-Mixed), also known as “*Black Base*”, at locations in the Paris district as specified in the plans.

Contractor questions on this project are to be addressed to the following individual(s):

District Maintenance Office:

Tad Eudy – Tad.Eudy@txdot.gov

Tommy Henderson, P.E. – Tommy.Henderson@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

TXDOT PROJECT SUPERVISOR – All work on this contract will be scheduled and directed by the following person(s). Payments will be made on a monthly basis for work completed and accepted according to specifications. All payment requests will be directed to the same:

Site 1 – Fannin County, Jerry Hale, Maintenance Supervisor.
2405 N. Center, Bonham, Texas 75418, Phone: 903-583-7566

Site 2 – Red River County, Casey Davis, Maintenance Supervisor
2002 W. Main St., Clarksville, Texas 75426, Phone: 903-427-3561

Site 3 – Delta County, Micah Mathis, Assistant Maintenance Supervisor
131 Hwy 64, Cooper, Texas 75432, Phone: 903-395-2139

Project Number: MMC – 646328001

Sheet 2

County: LAMAR, ETC.

Control: 6463-28-001

Highway: US 82, Etc.

Site 4 – Rains County, Kevin Wilson, Assistant Maintenance Supervisor
1520 W US 69, Emory, Texas 75440, Phone: 903-473-2682

Site 5 – Hunt County, Duane Andrus, Maintenance Supervisor
3001 IH30 East, Greenville, Texas 75402, Phone: 903-455-2303

Site 6 – Franklin County, Shane Bolton, Maintenance Supervisor
104 East IH30, Mount Vernon, Texas 75457, Phone: 903-537-4976

Site 7 – Lamar County, David Escobedo, Maintenance Supervisor
3600 S. W. Loop 286, Paris, Texas 75460, Phone: 903-785-4468

Site 8 – Grayson County, James Alexander, Maintenance Supervisor
3904 Hwy 75 South, Sherman, Texas 75090, Phone: 903-892-6529

Site 9 – Hopkins County, Josh Redar, Maintenance Supervisor
1100 North Hillcrest Drive, Sulphur Springs, Texas 75482, Phone: 903-885-9514

Contract Prosecution: Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

The work performed, equipment used, and materials furnished for a complete project will be paid for directly as indicated elsewhere in the plans and specifications. Payment for complete work will be made upon accepted of the work by the department.

Section 10.2 – Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Section 10.4 – Scope of Work:

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for

Project Number: MMC – 646328001**Sheet 2****County:** LAMAR, ETC.**Control:** 6463-28-001**Highway:** US 82, Etc.

the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended **once** not to exceed **365 calendar** days for the entire contract term if mutually agreed.

Section 10.8 - Prosecution and Progress:

There are **182** calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Each work order will specify a delivery site by the bid item in the contract and quantity to be supplied.

For Delivery Operations:

- Supply tarp and components necessary to tarp material during transport.
- Make all deliveries between the hours of 8 A.M. and 3:30 P.M. CST unless prior arrangements have been made with the Maintenance Supervisor.

ITEM 8021 – Flexible Base:

Grading requirements

Tests to be in accordance with TxDOT Standard Test Methods

Item Desc.	Soil Constants			
	Linear Shrinkage	LL	Wet Ball	WBMV(incr. passing #40 sieve)
Item 247 Flex Base	6.0 max.	40 max.	40 max.	20% max.

PERCENT RETAINED ON SIEVE:

1-3/4"	7/8"	3/8"	No. 4	No. 40
0	10-35	30-50	45-65	70-85

Flexible Base will not contain more than 1% by weight of clay balls.

Project Number: MMC – 646328001**Sheet 2****County:** LAMAR, ETC.**Control:** 6463-28-001**Highway:** US 82, Etc.**ITEM 8021 – Asphalt Treatment (Plant-Mixed):**

Grading requirements

Tests to be in accordance with TxDOT Standard Test Methods

Item Desc.	Linear Shrinkage	Soil Constants			WBMV(incr. passing #40 sieve)
		LL	Wet Ball		
Item 247 Flex Base	6.0 max.	40 max.	40 max.		20% max.

PERCENT RETAINED ON SIEVE:

1-3/4"	7/8"	3/8"	No. 4	No. 40
0	10-35	30-50	45-65	70-85

Flexible Base will not contain more than 1% by weight of clay balls.

RAP or RAS is not permitted.

Furnish AC 1.5 binder at a minimum of 4.6% that meets requirements of Item 300, "Asphalts, Oil, and Emulsions".

Upon completion of batching material, retain material in silo a minimum of 12 hrs. prior to delivery or pick up.

ITEM	DESCRIPTION	QTY	UOM
8021	6001 FL BS (SITE DEL)(TY A GR 4)(SITE 1)	2,000	TON
8021	6002 FL BS (SITE DEL)(TY A GR 4)(SITE 2)	2,000	TON
8021	6003 FL BS (SITE DEL)(TY A GR 4)(SITE 3)	2,000	TON
8021	6004 FL BS (SITE DEL)(TY A GR 4)(SITE 4)	2,000	TON
8021	6005 FL BS (SITE DEL)(TY A GR 4)(SITE 5)	2,000	TON
8021	6006 FL BS (SITE DEL)(TY A GR 4)(SITE 6)	2,000	TON
8021	6007 FL BS (SITE DEL)(TY A GR 4)(SITE 7)	2,000	TON
8021	6008 FL BS (SITE DEL)(TY A GR 4)(SITE 8)	2,000	TON
8021	6009 FL BS (SITE DEL)(TY A GR 4)(SITE 9)	2,000	TON
8021	6010 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 1)	750	TON
8021	6011 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 2)	1,500	TON
8021	6012 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 3)	1,500	TON
8021	6013 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 4)	1,500	TON
8021	6014 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 5)	750	TON
8021	6015 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 6)	750	TON
8021	6016 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 7)	1,500	TON
8021	6017 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 8)	750	TON
8021	6018 ASPHLT TRTMNT (PLANT-MIX)(DEL)(GR 4)(ST 9)	750	TON

PLAN SHEET

CONT	SECT	JOB	HIGHWAY
6463	28	001	US 82, ETC.
DIST	COUNTY		SHEET NO.
01	LAMAR. Etc.		4