

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6462-02-001
 CSJ: 6462-02-001
 HIGHWAY: IH20. ETC
 LIMITS OF WORK: PARKER COUNTY, ETC


FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
 DESCRIPTION: DENSE GRADE HOT MIX ASPHALT (MATERIAL ONLY)

RECOMMENDED FOR LETTING: 2/22/2024
 Date


RECOMMENDED FOR LETTING: 2/22/2024
 Date

DocuSigned by:

 6536CC6BE43A490... ENGINEER

DocuSigned by:

 4848DA2AA1AB440... MAINTENANCE ENGINEER


RECOMMENDED FOR LETTING: 2/22/2024
 Date

DocuSigned by:

 1FDBBDF41B5F486... DIRECTOR OF MAINTENANCE

INDEX OF SHEETS

- 1 TITLE SHEET
- 2A-D GENERAL NOTES
- 3 ESTIMATE & QUANTITY SHEET
- 4 DELIVERY SITES SHEET

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2024	 Texas Department of Transportation		
FED.RD. DIV. NO	PROJECT NO.	SHEET NO.	
6	6462-02-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	PARKER, ETC	
CONTROL	SECTION	JOB	HWY NO.
6462	02	001	IH20. ETC
FILENAME			DATE
MMC 6462-02-001			4/19/2022

Project Number: MMC 6462-02-001

Control: 6462-02-001

County: Parker

Highway: IH 20 Etc.

GENERAL NOTES:

General:

The purpose of this contract is to supply “**Dense Graded Hot Mix Asphalt (MATERIAL ONLY)**” to locations provided to the Contractor by Work Order.

Site 1	Various Locations within Parker County
--------	--

Provide and maintain a dedicated email address for receipt of work orders and correspondence throughout the term of this contract. Acknowledgment of emailed work order/call outs is required no more than 12 hr. from notification.

Contractor’s attention is called to the fact that all Department property will be protected during all phases of the execution of the contract and any damages incurred due to Contractor’s operation will be repaired and replaced at the Contractor’s expense.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Prior to beginning operations, the Department will arrange a preconstruction meeting between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

Coordinate work through the Maintenance Section Supervisor or Representative:

Parker
1427 W Bankhead Hwy Weatherford TX 76086 682-229-2800

Bids will be received at 2501 Southwest Loop 820, Fort Worth, TX 76133

Project Number: MMC 6462-02-001**Control:** 6462-02-001**County:** Parker**Highway:** IH 20 Etc.

Contractor questions on this project are to be emailed to the following individual:

Area Engineer: Korey Coburnkorey.coburn@txdot.gov

Maintenance Supervisor: Clinton Hyatt

Clinton.Hyatt@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. The webpage can be accessed from the Notice to Contractors dashboard located at the following Address: <https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Attention is directed to the possible presence of underground utilities owned by the Texas Department of Transportation (irrigation, signal, illumination and surveillance, communication, and control) on the right of way. Call TxDOT for locates at 817-370-6500, or the appropriate department of the local city or town a minimum of 48 hr. in advance of excavation.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Cost associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

Section 10.2 - Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Section 10.4 – Scope of Work:

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the

Project Number: MMC 6462-02-001

Control: 6462-02-001

County: Parker

Highway: IH 20 Etc.

use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended twice, not to exceed 540 calendar days for the entire contract term if mutually agreed.

Section 10.8 - Prosecution and Progress:

There are 180 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Types of accepted haul vehicles include End Dumps.

Each Work Order will have **no less than 7 calendar days to begin material delivery** or to make material available for pick-up, as described in the Work Order in accordance with Article 10.8.3., "Work Orders".

Each Work Order will specify a delivery site by the bid item in the contract and quantity to be supplied.

Unless otherwise directed, prosecute the work continuously to completion of the Work Order.

Item 500 – Mobilization:

Mobilization does not apply to this Maintenance Materials Contract.

Project Number: MMC 6462-02-001

Control: 6462-02-001

County: Parker

Highway: IH 20 Etc.

Item 8011 – Dense-Graded Hot Mix Asphalt (Materials Only):

No Blending, of the material to meet SAC A will be allowed.

Substitute binders are not allowed on this project.

RAP and RAS are not permitted in any surface and level-up mixes on this project.

Furnish a mix design to the State's representative to be sent to the District Laboratory for verification testing.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Use only Department MPL approved asphalt release agents. Diesel and/or solvents in the production, transportation, and/or construction of the mix is prohibited.

No material shall be left in the haul vehicle overnight.

Canvas covers and insulating of the truck bodies will be required.

Contractor must have equipment and personnel to supply a minimum of 500 ton per day for below item codes:

8011 6002

8011 6017

Contractor must have equipment and personnel to supply a minimum of 1000 ton per day for below item code:

8011 6040

Include the approved mix design number on each delivery ticket.

