



# INDEX OF SHEETS

| <u>SHEET NO.</u>                                    | <u>DESCRIPTION</u>   |
|---|--|
| <b>GENERAL</b>                                      |  |
| 1   | TITLE SHEET  |
| 2   | INDEX OF SHEETS  |
| 3-5   | GENERAL NOTES  |
| 6-7   | ESTIMATE AND QUANTITY SHEET  |
| <b>TRAFFIC CONTROL PLAN STANDARDS</b>               |  |
| 8-19  | # BC (1)-21 THRU BC (12)-21  |
| 20-24   | # TCP (2-1)-18, TCP (2-2)-18, TCP (2-3)-23, TCP (2-4)-18, TCP (2-6)-18 |
| 25-27   | # TCP (3-1)-13, TCP (3-2)-13, TCP (3-4)-13                             |
| 28-31   | # TCP (6-1)-12 THRU (6-4)-12   |
| 32  | # WZ (RS)-22   |
| <b>ROADWAY DETAIL STANDARDS</b>                     |  |
| 33  | # MBGF-19  |
| 34  | # MBGF (TR)-19   |
| 35  | # MBGF (T101)-19   |
| 36  | # MBGF (MS)-19   |
| 37  | # GF (31)-19   |
| 38  | # GF (31) DAT-19   |
| 39  | # GF (31) LS-19  |
| 40  | # GF (31) TRTL2-19   |
| 41-42   | # GF (31) TRTL3-20   |
| 43  | # GF (31) T101-19  |
| 44  | # GF (31) T6-19  |
| 45  | # GF (31) MS-19  |
| 46  | # SGT (10S) 31-16  |
| 47  | # SGT (11S) 31-18  |
| 48  | # SGT (12S) 31-18  |
| 49  | # SGT (13S) 31-18  |
| 50  | # SGT (14W) 31-18  |
| 51-53   | # SRG (TL-3)-21  |
| 54  | # RAIL-ADJ (B)-19  |
| 55-57   | # BRIFEN (TL4)-14  |
| 58  | # CASS (TL4)-14  |
| 59  | # GBRLTR (TL4)-14  |
| 60-61   | # NU-CABLE (TL4)-14  |
| <b>PAVEMENT MARKING &amp; DELINEATION STANDARDS</b> |  |
| 62  | # D&OM (1)-20  |
| 63  | # D&OM (2)-20  |
| 64  | # D&OM (3)-20  |
| 65  | # D&OM (5)-20  |
| 66  | # D&OM (VIA)-20  |

# THE STANDARD SHEETS SPECIFICALLY IDENTIFIED  
HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE  
SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

DocuSigned by:  
*Cal Hays, P.E.* 4/8/2024  
A2B0DD676470482  
Cal W. Hays, P.E. Date



| FHWA DIVISION | PROJECT NO. |              | SHEET NO.   |
|---------------|-------------|--------------|-------------|
| 6             | 6460-98-001 |              | 2           |
| STATE         | DISTRICT    | COUNTY       |             |
| TEXAS         | ABL         | SCURRY, ETC. |             |
| CONTROL       | SECTION     | JOB          | HIGHWAY NO. |
| 6460          | 98          | 001          | US 84, ETC. |

**Control:** 6460-98-001  
**County:** Scurry, etc.  
**Highway:** US 84, etc.

**Item 2 Instructions to Bidders**

Contractor questions will be accepted through email, phone, and in person by the below individuals:

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:  
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

**Item 4 Scope of Work**

This contract will consist of “Call Out” metal beam guard fence repair and metal / concrete bridge rail repair including pertinent miscellaneous items.

If agreed upon in writing by both parties to the contract, the contract may be extended for an additional period of time not to exceed the original contract time period. The extended contract will be for the original bid quantities, terms and conditions plus any applicable change orders.

**Item 5 Control of the Work**

Prior to issuance of work orders, TxDOT underground utilities will be marked to indicate points of potential conflicts with the proposed work. Notify the Engineer of conflicts between proposed work and underground utilities. Repair damaged TxDOT utilities in accordance with current electrical regulations, or as directed by the Engineer when damage is due to failure to notify the Engineer of conflicts between the proposed work and TxDOT underground utilities. Repair work will be performed at the Contractor’s expense.

**Item 6 Control of Materials**

The contractor will provide all materials for this project.

**Item 7 Legal Relations and Responsibilities**

Provide access to all businesses and residences with minimum disruption and as directed. Materials, labor and maintenance for these temporary accesses is considered subsidiary to the various bid items.

**Item 8 Prosecution and Progress**

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process and/or execute all contracts at the same time.

General Notes

Sheet A

**Control:** 6460-98-001  
**County:** Scurry, etc.  
**Highway:** US 84, etc.

**“Call-Out” Scope of Work:**

This contract includes non-site specific work. Multiple concurrent work orders will be issued to procure work of the type identified in the contract at locations that have not been determined yet. Multiple concurrent work orders with a single location on each work order may be issued for emergency work. Emergency work orders and work locations may be prioritized at the engineer’s discretion.

For each repair, the Engineer will determine the work to be done and specify this on the work order issued to the contractor. This includes determining whether the guardrail and associated elements will be upgraded to current standards or not.

Perform work in Kent, Stonewall, Haskell, Scurry and Fisher Counties.

Provide notice the morning of performing work to the requesting Maintenance Section or appropriate contact person. Failure to provide prior notification may result in nonpayment of work performed.

Work orders will be classified as Emergency or Routine. Emergency work orders will be issued as needed and will take precedence over the Routine work orders as determined by the Engineer.

**Emergency Work Orders:**

Be available to make repairs Monday through Friday and weekends if directed. Begin work within **48** hours after notification.

Emergency work will be defined as:

- All SGT repair or replacement
- MBGF repair consisting of 3 or more consecutive posts
- Any disconnect of steel rail element
- Other repair not listed above as determined by the Engineer

**Routine Work Orders:**

Be available to make repairs Monday through Friday and weekends if directed. Begin work within **5 calendar days** after notification.

**Routine and Emergency Work Order Production Rates:**

Working days allowed to complete each work order will be determined by dividing the total linear feet of rail required to complete the work order by the production rate of 175 lf of rail per working day and/or four SGT’s per working day. Production rates for cable median barrier will be 25 posts per working day, and/or 250 lf of cable per working day. Cable median barrier terminal sections will be 1 per working day. A fraction of a day will be rounded up to the nearest whole number. If the total number of working days is not used per work order, they will not be carried forward to future work orders. Working days for items other than what has been listed will be as determined by the Engineer.

General Notes

Sheet B

\$DATE\$  
\$FILES\$



GENERAL NOTES

| CONT | SECT         | JOB | HIGHWAY    |
|------|--------------|-----|------------|
| 6460 | 98           | 001 | US84, etc. |
| DIST | COUNTY       |     | SHEET NO.  |
| ABL  | Scurry, etc. |     | 3          |

**Control:** 6460-98-001  
**County:** Scurry, etc.  
**Highway:** US 84, etc.

The contractor must maintain an adequate supply of materials in order to fulfill the emergency work order response requirement within 48 hours. Time will not be suspended due to lack of materials on emergency work orders. It is the contractor's responsibility to determine and provide materials necessary to complete the defined scope of work within each work order and within the time allotment.

**Item 500 Mobilization**

One Mobilization bid item will be paid per work order. Work orders will include no more than five (5) locations per work order.

**Item 502 Barricades, Signs, and Traffic Handling**

Additional signs, barricades and traffic handling may be necessary to complete the work shown herein and will be provided by the contractor as required and will be considered subsidiary to the various bid items.

If any workers or equipment are present in the median of divided highways, the entire median width will be considered to be the work area. Any work in the median will require, at a minimum, two shoulder closures with signs, channelizing devices and TMAs as per the TCPs.

For cable median barrier repair, use TCP (6-1a) in both directions of travel including providing a TMA in each direction.

In sections where traffic is restricted to one lane, two-way traffic, flaggers stationed at each end of that section will control operations with two-way communication devices.

Traffic control shall be in compliance with the "Texas Manual on Uniform Traffic Control Devices Revision 2, October 2014", the TCP standards included in the plans, and the "Compliant Work Zone Traffic Control Device, December 2017" list.

Temporary work zone rumble strips, in accordance with WZ(RS)-22, may be required for this project. Install and maintain temporary work zone rumble strips in accordance with WZ(RS)-22, utilizing traffic control in accordance with applicable traffic control standards, or as approved by the Engineer. This work will not be paid for directly but will be considered subsidiary to the various bid items of the contract.

Equip all work vehicles within 30 feet of the traveled way with a functioning amber strobe light or rotating beacon visible from all directions.

All workers are required to wear appropriate OSHA approved personal protective equipment, (fluorescent safety vest, hard hats, safety toed shoes, etc.), at all times while outside of vehicles on the project.

General Notes

Sheet C

**Control:** 6460-98-001  
**County:** Scurry, etc.  
**Highway:** US 84, etc.

**Item 540 Metal Beam Guard Fence**

This item will pay for the anchor plate assembly for the thrie-beam transition to bridge rail.

**Item 658 Delineators and Object Marker Assemblies**

Delineation (GF2 reflectors) will be installed on a complete run of rail when rail is damaged and repaired or replaced. The delineation installation will be paid by the each of the type specified. Remove all GF1 reflectors on the run of rail. Removal of the GF1 reflectors will be considered subsidiary to the various bid items.

Guard Fence Delineator posts shall be 33" in length and permanently sealed at the top and have a 3-1/2" wide x 13" flattened surface to accommodate up to a 3" x 12" reflective sheet on both sides. They shall be flattened on both ends and transition to 2-3/8" round in the center for 360-degree visibility.

The contractor will not be called out for delineation placement only.

**Item 770 Guard Fence Repair**

New rail elements will be required under Item 770 where the bid description includes the phrase "Repair Rail Element" or "Rep Rail Elmnt".

When necessary, field drill and cut steel posts with method approved by the Engineer to proper height. Cold galvanize locations that are cut or drilled. This work will be subsidiary to this item.

Posts provided for repaired sections of guardrail will match existing adjacent posts in type and height.

When blockouts are damaged, they will be replaced with composite blockouts.

Install SGT's according to the manufacturers recommendations. Lag screws will not be driven in with a hammer.

SGT heads must remain level for a minimum of one year. Leveling of the SGT head will be at the contractor's expense.

SGT's will be repaired if damage is limited to the first rail element and first five posts.

SGT's will be replaced if damage has occurred beyond the first rail element and the first five posts, or as determined by the Engineer.

Posts to be paid with or without concrete foundation will be determined as follows:

If concrete must be removed to make the repair or to replace the post, Bid Item 770-6011 "Rem/Repl Tim/Stl Post w/ Conc Fnd" will be paid. All other applicable repairs or replacements will be paid under Bid Item 770-6010 "Rem/Repl Tim/Stl Post w/o Conc Fnd."

General Notes

Sheet D

\$DATE\$  
\$TIME\$  
\$FILE\$

| CONT | SECT         | JOB | HIGHWAY    |
|------|--------------|-----|------------|
| 6460 | 98           | 001 | US84, etc. |
| DIST | COUNTY       |     | SHEET NO.  |
| ABL  | Scurry, etc. |     | 4          |

**Control:** 6460-98-001  
**County:** Scurry, etc.  
**Highway:** US 84, etc.

**Item 771 Repair Cable Barrier System**

Provide a tension meter and use it to verify that repaired or replaced cables are properly tensioned. Re-tension the cable(s) when needed. This work will be considered subsidiary to the various bid items.

For posts not being replaced, straightening of the posts, new spacers and re-threading the cable will be considered subsidiary to the various bid items.

Item No. 771-6011 "Check/Re-Tension Cable" will only be utilized and paid when no other cable barrier repair is required.

**Item 6185 Truck Mounted Attenuator**

For this contract, a worksite will be defined as any work location within the five (5) counties shown in this contract. If a TMA unit is utilized at multiple work locations during a single day, only one day will be measured and paid for the unit.

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project. The Contractor must get approval from the Engineer for any changes in the number of TMA as shown in the plans.

| BASIS OF ESTIMATE FOR STATIONARY TMAs |   |                  |            |       |
|---------------------------------------|---|------------------|------------|-------|
| Phase                                 | Standard  | TMA (Stationary) |            |       |
|                                       |   | Required         | Additional | TOTAL |
| Stationary                            | TCP's (1-2) thru (1-5) – 18;<br>TCP's (2-1), (2-2), (2-6)-18        | 2 max            | 0          | 2     |
| Mobile                                | TCP's (3-1), (3-2), (3-4) – 13;<br>TCP's (3-3) – 14, TCP (3-5) – 18 | 3 max            | 0          | 3     |
| Stationary Freeway                    | TCP's (6-1) thru (6-5) - 12   | 2 max            | 0          | 2     |

General Notes

Sheet E

\$DATE\$  
\$TIME\$  
\$FILE\$



GENERAL NOTES

|      |              |     |            |
|------|--------------|-----|------------|
| CONT | SECT         | JOB | HIGHWAY    |
| 6460 | 98           | 001 | US84, etc. |
| DIST | COUNTY       |     | SHEET NO.  |
| ABL  | Scurry, etc. |     | 5          |



CONTROLLING PROJECT ID 6460-98-001

DISTRICT Abilene  
HIGHWAY US0084

# Estimate & Quantity Sheet

COUNTY Scurry

| CONTROL SECTION JOB |          |   |      | 6460-98-001 |       | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|---|------|-------------|-------|------------|-------------|
| PROJECT ID          |          |   |      | A00205963   |       |            |             |
| COUNTY              |          |   |      | Scurry      |       |            |             |
| HIGHWAY             |          |   |      | US0084      |       |            |             |
| ALT                 | BID CODE | DESCRIPTION                             | UNIT | EST.        | FINAL |            |             |
|                     | 500-6033 | MOBILIZATION (CALLOUT)                  | EA   | 4.000       |       | 4.000      |             |
|                     | 500-6034 | MOBILIZATION (EMERGENCY)                | EA   | 34.000      |       | 34.000     |             |
|                     | 540-6016 | DOWNSTREAM ANCHOR TERMINAL SECTION      | EA   | 4.000       |       | 4.000      |             |
|                     | 540-6039 | MTL BM GD FEN TRANS (31"-28")(25')      | EA   | 4.000       |       | 4.000      |             |
|                     | 542-6002 | REMOVE TERMINAL ANCHOR SECTION          | EA   | 26.000      |       | 26.000     |             |
|                     | 658-6061 | INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2       | EA   | 32.000      |       | 32.000     |             |
|                     | 658-6062 | INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)   | EA   | 109.000     |       | 109.000    |             |
|                     | 658-6063 | INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BR)   | EA   | 4.000       |       | 4.000      |             |
|                     | 658-6064 | INSTL DEL ASSM (D-SY)SZ 1(BRF)GF2       | EA   | 5.000       |       | 5.000      |             |
|                     | 658-6065 | INSTL DEL ASSM (D-SY)SZ 1(BRF)GF2(BR)   | EA   | 4.000       |       | 4.000      |             |
|                     | 658-6067 | INSTL DEL ASSM (D-DW)SZ 1(BRF)GF2       | EA   | 4.000       |       | 4.000      |             |
|                     | 770-6001 | REPAIR RAIL ELEMENT (W - BEAM)          | LF   | 9,200.000   |       | 9,200.000  |             |
|                     | 770-6002 | REPAIR RAIL ELEMENT (THRIE - BEAM)      | LF   | 10.000      |       | 10.000     |             |
|                     | 770-6003 | REP RAIL ELMNT(THRIE-BM TRANS TO W -BM) | LF   | 40.000      |       | 40.000     |             |
|                     | 770-6004 | REPAIR RAIL ELEMENT (CURVED RAIL)       | LF   | 250.000     |       | 250.000    |             |
|                     | 770-6010 | REM / REPL TIMBER/STL POST W/O CONC FND | EA   | 1,091.000   |       | 1,091.000  |             |
|                     | 770-6011 | REM / REPL TIMBER / STL POST W/CONC FND | EA   | 166.000     |       | 166.000    |             |
|                     | 770-6016 | REPAIR STEEL POST WITH BASE PLATE       | EA   | 2.000       |       | 2.000      |             |
|                     | 770-6017 | REALIGN POSTS                           | EA   | 21.000      |       | 21.000     |             |
|                     | 770-6018 | INSTALL BLOCKOUT (TYPE SPECIFIED)       | EA   | 1,206.000   |       | 1,206.000  |             |
|                     | 770-6021 | REPLACE SINGLE GDRAIL TERMINAL RAIL     | LF   | 167.000     |       | 167.000    |             |
|                     | 770-6022 | REPLACE SINGLE GDRAIL TERMINAL POST     | EA   | 16.000      |       | 16.000     |             |
|                     | 770-6023 | REPAIR OF TERMINAL ANCHORS POSTS        | EA   | 2.000       |       | 2.000      |             |
|                     | 770-6024 | REPLACE TERMINAL ANCHOR POSTS           | EA   | 4.000       |       | 4.000      |             |
|                     | 770-6027 | REMOVE GDRAIL END TRT / REPL WITH SGT   | EA   | 85.000      |       | 85.000     |             |
|                     | 770-6028 | REPL SINGLE GDRAIL TERM IMPACT HEAD     | EA   | 4.000       |       | 4.000      |             |
|                     | 770-6029 | REM & RESET SGT IMPACT HEAD             | EA   | 8.000       |       | 8.000      |             |
|                     | 770-6033 | REPLACE SGT OBJECT MARKER               | EA   | 10.000      |       | 10.000     |             |
|                     | 770-6060 | REMOVE AND REPLACE DAT                  | EA   | 3.000       |       | 3.000      |             |
|                     | 771-6002 | REPLACE POSTS (TL-4)                    | EA   | 735.000     |       | 735.000    |             |
|                     | 771-6004 | CABLE SPLICE / TURNBUCKLE (TL-4)        | EA   | 11.000      |       | 11.000     |             |
|                     | 771-6006 | REPAIR CONCRETE FOUNDATION (TL-4)       | EA   | 1.000       |       | 1.000      |             |
|                     | 771-6008 | REPR OR REPLC CABLE BARR TERM SEC(TL-4) | EA   | 16.000      |       | 16.000     |             |
|                     | 771-6010 | REPLACE CABLE (TL-4)                    | LF   | 846.000     |       | 846.000    |             |
|                     | 771-6011 | CHECK / RE-TENSION CABLE                | EA   | 3.000       |       | 3.000      |             |
|                     | 776-6001 | REPAIR (STEEL POST W/ W-BEAM - T101)    | LF   | 2.000       |       | 2.000      |             |
|                     | 776-6035 | REPAIR (W-BEAM - T101 RAIL)             | LF   | 62.000      |       | 62.000     |             |

|          |        |             |       |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ        | SHEET |
| Abilene  | Scurry | 6460-98-001 | 6     |



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6460-98-001

DISTRICT Abilene  
HIGHWAY US0084

COUNTY Scurry

| CONTROL SECTION JOB |           |                                  |      | 6460-98-001 |       | TOTAL EST. | TOTAL FINAL |
|---------------------|-----------|----------------------------------|------|-------------|-------|------------|-------------|
| PROJECT ID          |           |                                  |      | A00205963   |       |            |             |
| COUNTY              |           |                                  |      | Scurry      |       |            |             |
| HIGHWAY             |           |                                  |      | US0084      |       |            |             |
| ALT                 | BID CODE  | DESCRIPTION                      | UNIT | EST.        | FINAL |            |             |
|                     | 776-6051  | REPAIR (TY T1)                   | LF   | 36.000      |       | 36.000     |             |
|                     | 6001-6001 | PORTABLE CHANGEABLE MESSAGE SIGN | DAY  | 5.000       |       | 5.000      |             |
|                     | 6185-6002 | TMA (STATIONARY)                 | DAY  | 99.000      |       | 99.000     |             |

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

|   |
|---|
| <p>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT<br/> <a href="http://www.txdot.gov">http://www.txdot.gov</a></p> |
| COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)   |
| DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)  |
| MATERIAL PRODUCER LIST (MPL)  |
| ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"  |
| STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)  |
| TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)  |
| TRAFFIC ENGINEERING STANDARD SHEETS   |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
 FILE:




**BARRICADE AND CONSTRUCTION  
 GENERAL NOTES  
 AND REQUIREMENTS**

**BC(1)-21**

|         |               |      |              |     |             |     |       |     |       |
|---------|---------------|------|--------------|-----|-------------|-----|-------|-----|-------|
| FILE:   | bc-21.dgn     | DN:  | TxDOT        | CK: | TxDOT       | DW: | TxDOT | CK: | TxDOT |
| © TxDOT | November 2002 | CONT | SECT         | JOB | HIGHWAY     |     |       |     |       |
|         |               | 6460 | 98           | 001 | US 84, ETC. |     |       |     |       |
|         |               | DIST | COUNTY       |     | SHEET NO.   |     |       |     |       |
|         |               | ABL  | SCURRY, ETC. |     | 8           |     |       |     |       |




TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING


| Sign Number or Series                 | SIZE              |                    | SPACING          |                                |
|---------------------------------------|-------------------|--------------------|------------------|--------------------------------|
|                                       | Conventional Road | Expressway/Freeway | Posted Speed MPH | Sign Spacing "X" Feet (Apprx.) |
| CW20 <sup>4</sup>                     | 48" x 48"         | 48" x 48"          | 30               | 120                            |
| CW21                                  |                   |                    | 35               | 160                            |
| CW23                                  |                   |                    | 40               | 240                            |
| CW25                                  |                   |                    | 45               | 320                            |
| CW1, CW2, CW7, CW8, CW9, CW11, CW14   | 36" x 36"         | 48" x 48"          | 50               | 400                            |
| CW3, CW4, CW5, CW6, CW8-3, CW10, CW12 | 48" x 48"         | 48" x 48"          | 60               | 600 <sup>2</sup>               |
|                                       |                   |                    | 65               | 700 <sup>2</sup>               |
|                                       |                   |                    | 70               | 800 <sup>2</sup>               |
|                                       |                   |                    | 75               | 900 <sup>2</sup>               |
|                                       |                   |                    | 80               | 1000 <sup>2</sup>              |
| *                                     |                   |                    | *                | *                              |

- For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.


SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



LEGEND

|       |   |
|-------|---|
| —     | Type 3 Barricade  |
| ○ ○ ○ | Channelizing Devices  |
| ■     | Sign  |
| X     | See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements. |

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

|                       |            |           |                   |                      |
|-----------------------|------------|-----------|-------------------|----------------------|
| FILE: bc-21.dgn       | DN: TxDOT  | CK: TxDOT | DW: TxDOT         | CK: TxDOT            |
| © TxDOT November 2002 | CONT: 6460 | SECT: 98  | JOB: 001          | HIGHWAY: US 84, ETC. |
| REVISIONS: 9-07 8-14  |            |           | DIST: COUNTY      | SHEET NO. 9          |
| 7-13 5-21             |            |           | ABL: SCURRY, ETC. |                      |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
  - 40 mph and greater 0.2 to 2 miles
  - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Low enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:

SHEET 3 OF 12




## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

|                       |           |              |           |             |
|-----------------------|-----------|--------------|-----------|-------------|
| FILE: bc-21.dgn       | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| © TxDOT November 2002 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS             | 6460      | 98           | 001       | US 84, ETC. |
| 9-07 8-14             | DIST      | COUNTY       | SHEET NO. |             |
| 7-13 5-21             | ABL       | SCURRY, ETC. | 10        |             |


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\* \* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nois shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectorized when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



| SHEETING REQUIREMENTS (WHEN USED AT NIGHT) |        |  |
|--|--------|--|
| USAGE                                      | COLOR  | SIGN FACE MATERIAL                               |
| BACKGROUND                                 | RED    | TYPE B OR C SHEETING                             |
| BACKGROUND                                 | ORANGE | TYPE B <sub>TL</sub> OR C <sub>TL</sub> SHEETING |
| LEGEND & BORDER                            | WHITE  | TYPE B OR C SHEETING                             |
| LEGEND & BORDER                            | BLACK  | ACRYLIC NON-REFLECTIVE FILM                      |

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCO list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
  2. Wooden sign posts shall be painted white.
  3. Barricades shall NOT be used as sign supports.
  4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
  5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
  6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCO) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
  7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
  8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
  9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.
- DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**
- a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCO lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B or Type C<sub>TL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCO list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.



**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**



**BC(4)-21**

|                       |            |           |                   |                      |
|-----------------------|------------|-----------|-------------------|----------------------|
| FILE: bc-21.dgn       | DN: TxDOT  | CK: TxDOT | DW: TxDOT         | CK: TxDOT            |
| © TxDOT November 2002 | CONT: 6460 | SECT: 98  | JOB: 001          | HIGHWAY: US 84, ETC. |
| REVISIONS: 9-07 8-14  |            |           | DIST: COUNTY      | SHEET NO. 11         |
| 7-13 5-21             |            |           | ABL: SCURRY, ETC. |                      |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





### SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTC and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



### SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

### WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTC LIST. SEE BC(1) FOR WEBSITE LOCATION.

### GENERAL NOTES

1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTC List.
3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.

- \* See BC(4) for definition of "Work Duration."
- \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
- See the CWZTC for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



## BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

|                       |           |              |           |             |
|-----------------------|-----------|--------------|-----------|-------------|
| FILE: bc-21.dgn       | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| © TxDOT November 2002 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS             | 6460      | 98           | 001       | US 84, ETC. |
| 9-07 8-14             | DIST      | COUNTY       | SHEET NO. |             |
| 7-13 5-21             | ABL       | SCURRY, ETC. | 12        |             |

DATE: FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

| WORD OR PHRASE         | ABBREVIATION | WORD OR PHRASE       | ABBREVIATION |
|------------------------|--------------|----------------------|--------------|
| Access Road            | ACCS RD      | Major                | MAJ          |
| Alternate              | ALT          | Miles                | MI           |
| Avenue                 | AVE          | Miles Per Hour       | MPH          |
| Best Route             | BEST RTE     | Minor                | MNR          |
| Boulevard              | BLVD         | Monday               | MON          |
| Bridge                 | BRDC         | Normal               | NORM         |
| Canal                  | CANT         | North                | N            |
| Center                 | CTR          | Northbound (route) N |              |
| Construction Ahead     | CONST AHD    | Parking              | PKING        |
| CROSSING               | XING         | Road                 | RD           |
| Detour Route           | DETOUR RTE   | Right Lane           | RT LN        |
| Do Not                 | DONT         | Saturday             | SAT          |
| East                   | E            | Service Road         | SERV RD      |
| Eastbound (route) E    |              | Shoulder             | SHLDR        |
| Emergency              | EMER         | Slippery             | SLIP         |
| Emergency Vehicle      | EMER VEH     | South                | S            |
| Entrance, Enter        | ENT          | Southbound (route) S |              |
| Express Lane           | EXP LN       | Speed                | SPD          |
| Expressway             | EXPWY        | Street               | ST           |
| XXXX Feet              | XXXX FT      | Sunday               | SUN          |
| Fog Ahead              | FOG AHD      | Telephone            | PHONE        |
| Freeway                | FRWY, FWY    | Temporary            | TEMP         |
| Freeway Blocked        | FWY BLKD     | Thursday             | THURS        |
| Friday                 | FRI          | To Downtown          | TO DWNTN     |
| Hazardous Driving      | HAZ DRIVING  | Traffic              | TRAF         |
| Hazardous Material     | HAZMAT       | Travelers            | TRVLR        |
| High Occupancy Vehicle | HOV          | Tuesday              | TUES         |
| Hour(s)                | HR, HRS      | Time Minutes         | TIME MIN     |
| Information            | INFO         | Upper Level          | UPR LEVEL    |
| It Is                  | ITS          | Vehicles (s)         | VEH, VEHs    |
| Junction               | JCT          | Warning              | WARN         |
| Left                   | LFT          | Wednesday            | WED          |
| Left Lane              | LFT LN       | Weight Limit         | WT LIMIT     |
| Lane Closed            | LN CLOSED    | West                 | W            |
| Lower Level            | LWR LEVEL    | Westbound (route) W  |              |
| Maintenance            | MAINT        | Wet Pavement         | WET PVMT     |
|                        |              | Will Not             | WONT         |

Roadway designation = IH-number, US-number, SH-number, FM-number

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

|                       |
|-----------------------|
| FREEWAY CLOSED X MILE |
| ROAD CLOSED AT SH XXX |
| ROAD CLSD AT FM XXXX  |
| RIGHT X LANES CLOSED  |
| CENTER LANE CLOSED    |
| NIGHT LANE CLOSURES   |
| VARIOUS LANES CLOSED  |
| EXIT CLOSED           |
| MALL DRIVEWAY CLOSED  |
| XXXXXXXX BLVD CLOSED  |

### Other Condition List

|                          |
|--------------------------|
| FRONTAGE ROAD CLOSED     |
| SHOULDER CLOSED XXX FT   |
| RIGHT LN CLOSED XXX FT   |
| RIGHT X LANES OPEN       |
| DAYTIME LANE CLOSURES    |
| I-XX SOUTH EXIT CLOSED   |
| EXIT XXX CLOSED X MILE   |
| RIGHT LN TO BE CLOSED    |
| X LANES CLOSED TUE - FRI |

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

|                      |
|----------------------|
| MERGE RIGHT          |
| DETOUR NEXT X EXITS  |
| USE EXIT XXX         |
| STAY ON US XXX SOUTH |
| TRUCKS USE US XXX N  |
| WATCH FOR TRUCKS     |
| EXPECT DELAYS        |
| REDUCE SPEED XXX FT  |
| USE OTHER ROUTES     |
| STAY IN LANE         |

### Location List

|                          |
|--------------------------|
| AT FM XXXX               |
| BEFORE RAILROAD CROSSING |
| NEXT X MILES             |
| PAST US XXX EXIT         |
| XXXXXXXX TO XXXXXXX      |
| US XXX TO FM XXXX        |

### Warning List

|                       |
|-----------------------|
| SPEED LIMIT XX MPH    |
| MAXIMUM SPEED XX MPH  |
| MINIMUM SPEED XX MPH  |
| ADVISORY SPEED XX MPH |
| RIGHT LANE EXIT       |
| USE CAUTION           |
| DRIVE SAFELY          |
| DRIVE WITH CARE       |

### \* \* Advance Notice List

|                     |
|---------------------|
| TUE-FRI XX AM-X PM  |
| APR XX-XX X PM-X AM |
| BEGINS MONDAY       |
| BEGINS MAY XX       |
| MAY X-X XX PM-XX AM |
| NEXT FRI-SUN        |
| XX AM TO XX PM      |
| NEXT TUE AUG XX     |
| TONIGHT XX PM-XX AM |

\* \* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS should be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flogger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.




## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21

|                       |                   |            |           |                      |
|-----------------------|-------------------|------------|-----------|----------------------|
| FILE: bc-21.dgn       | DN: TxDOT         | CK: TxDOT  | DW: TxDOT | CK: TxDOT            |
| © TxDOT November 2002 | CONT: 6460        | SECT: 98   | JOB: 001  | HIGHWAY: US 84, ETC. |
| REVISIONS: 9-07 8-14  | DIST: COUNTY      | SHEET NO.: |           |                      |
| 7-13 5-21             | ABL: SCURRY, ETC. | 13         |           |                      |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edge line being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

**LOW PROFILE CONCRETE BARRIER (LPCB)**

See D & OM (VIA)



Install a minimum of 3 Barrier Reflectors as per manufacturer's recommendations.

**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B or C sheeting, meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning light certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

| REQUIREMENTS |              |                               |                             |
|--------------|--------------|-------------------------------|-----------------------------|
| TYPE         | MINIMUM SIZE | MINIMUM NUMBER OF PANEL LAMPS | MINIMUM VISIBILITY DISTANCE |
| B            | 30 x 60      | 13                            | 3/4 mile                    |
| C            | 48 x 96      | 15                            | 1 mile                      |

**ATTENTION**  
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is on an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC(7)-21**

|                                 |            |                      |               |                      |
|---------------------------------|------------|----------------------|---------------|----------------------|
| FILE: bc-21.dgn                 | DN: TxDOT  | CK: TxDOT            | DW: TxDOT     | CK: TxDOT            |
| © TxDOT November 2002           | CONT: 6460 | SECT: 98             | JOB: 001      | HIGHWAY: US 84, ETC. |
| REVISIONS: 9-07 8-14, 7-13 5-21 | DIST: ABL  | COUNTY: SCURRY, ETC. | SHEET NO.: 14 |                      |

DATE:  
FILE:

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B or Type C Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**


**BC(8)-21**

|                       |                   |           |              |                      |
|-----------------------|-------------------|-----------|--------------|----------------------|
| FILE: bc-21.dgn       | DN: TxDOT         | CK: TxDOT | DW: TxDOT    | CK: TxDOT            |
| © TxDOT November 2002 | CONT: 6460        | SECT: 98  | JOB: 001     | HIGHWAY: US 84, ETC. |
| REVISIONS: 4-03 8-14  | DIST: COUNTY      |           | SHEET NO. 15 |                      |
| 9-07 5-21             | ABL: SCURRY, ETC. |           |              |                      |
| 7-13                  |                   |           |              |                      |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panels is 36 inches or greater, a panel stripe of 6 inches shall be used.




**PORTABLE**

**VERTICAL PANELS (VPs)**



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B or Type C conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B or Type C conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long cones and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

| Posted Speed | Formula                  | Minimum Desirable Taper Lengths x x |            |            | Suggested Maximum Spacing of Channelizing Devices |              |
|--------------|--------------------------|-------------------------------------|------------|------------|---|--------------|
|              |                          | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |
| 30           | L = WS <sup>2</sup> / 60 | 150'                                | 165'       | 180'       | 30'   | 60'          |
| 35           |                          | 205'                                | 225'       | 245'       | 35'   | 70'          |
| 40           |                          | 265'                                | 295'       | 320'       | 40'   | 80'          |
| 45           | L = WS                   | 450'                                | 495'       | 540'       | 45'   | 90'          |
| 50           |                          | 500'                                | 550'       | 600'       | 50'   | 100'         |
| 55           |                          | 550'                                | 605'       | 660'       | 55'   | 110'         |
| 60           |                          | 600'                                | 660'       | 720'       | 60'   | 120'         |
| 65           |                          | 650'                                | 715'       | 780'       | 65'   | 130'         |
| 70           | 700'                     | 770'                                | 840'       | 70'        | 140'  |              |
| 75           | 750'                     | 825'                                | 900'       | 75'        | 150'  |              |
| 80           | 800'                     | 880'                                | 960'       | 80'        | 160'  |              |

x x Taper lengths have been rounded off.  
L=Length of Taper (FT.) W=Width of Offset (FT.)  
S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(9)-21**

|                       |            |                      |               |                      |
|-----------------------|------------|----------------------|---------------|----------------------|
| FILE: bc-21.dgn       | DN: TxDOT  | CK: TxDOT            | DW: TxDOT     | CK: TxDOT            |
| © TxDOT November 2002 | CONT: 6460 | SECT: 98             | JOB: 001      | HIGHWAY: US 84, ETC. |
| REVISIONS: 9-07 8-14  | DIST: ABL  | COUNTY: SCURRY, ETC. | SHEET NO.: 16 |                      |
| 7-13 5-21             |            |                      |               |                      |

DATE: FILE:




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

| LEGEND |   |
|--------|---|
|        | Plastic drum  |
|        | Plastic drum with steady burn light or yellow warning reflector |
|        | Steady burn warning light or yellow warning reflector           |




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined in BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.

**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC(10)-21**

|                       |            |                      |              |                      |
|-----------------------|------------|----------------------|--------------|----------------------|
| FILE: bc-21.dgn       | DN: TxDOT  | CK: TxDOT            | DW: TxDOT    | CK: TxDOT            |
| © TxDOT November 2002 | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US 84, ETC. |
| REVISIONS: 9-07 8-14  | DIST: ABL  | COUNTY: SCURRY, ETC. | SHEET NO. 17 |                      |
| 7-13 5-21             |            |                      |              |                      |

DATE: FILE:

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
2. Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
3. Additional supplemental pavement marking details may be found in the plans or specifications.
4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ1STPMJ.
6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
7. All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

1. Raised pavement markers are to be placed according to the patterns on BC(12).
2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
2. Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
3. Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
7. Over-painting of the markings SHALL NOT BE permitted.
8. Removal of raised pavement markers shall be as directed by the Engineer.
9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
10. Block-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
3. Small design variances may be noted between tab manufacturers.
4. See Standard Sheet WZ1STPMJ for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

1. Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
2. All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
3. Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

| DEPARTMENTAL MATERIAL SPECIFICATIONS                 |          |
|--|----------|
| PAVEMENT MARKERS (REFLECTORIZED)                     | DMS-4200 |
| TRAFFIC BUTTONS                                      | DMS-4300 |
| EPOXY AND ADHESIVES                                  | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS             | DMS-6130 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS            | DMS-8240 |
| TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS   | DMS-8242 |

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:

SHEET 11 OF 12





## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS



BC(11)-21

|                       |           |              |           |             |
|-----------------------|-----------|--------------|-----------|-------------|
| FILE: bc-21.dgn       | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| © TxDOT February 1998 | CONT      | SECT         | JOB       | HIGHWAY     |
|                       | 6460      | 98           | 001       | US 84, ETC. |
| REVISIONS             |           |              |           |             |
| 2-98                  | 9-07      | 5-21         |           |             |
| 1-02                  | 7-13      |              |           |             |
| 11-02                 | 8-14      |              |           |             |
|                       | DIST      | COUNTY       | SHEET NO. |             |
|                       | ABL       | SCURRY, ETC. | 18        |             |


## PAVEMENT MARKING PATTERNS




Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




Prefabricated markings may be substituted for reflectORIZED pavement markings.




## EDGE & LANE LINES FOR DIVIDED HIGHWAY




Prefabricated markings may be substituted for reflectORIZED pavement markings.



## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS




Prefabricated markings may be substituted for reflectORIZED pavement markings.





## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


|                           |            |                      |               |                      |
|---------------------------|------------|----------------------|---------------|----------------------|
| FILE: bc-21.dgn           | DN: TxDOT  | CK: TxDOT            | DW: TxDOT     | CK: TxDOT            |
| © TxDOT February 1998     | CONT: 6460 | SECT: 98             | JOB: 001      | HIGHWAY: US 84, ETC. |
| REVISIONS: 1-97 9-07 5-21 |            |                      |               |                      |
| 2-98 7-13                 |            |                      |               |                      |
| 11-02 8-14                |            |                      |               |                      |
|                           | DIST: ABL  | COUNTY: SCURRY, ETC. | SHEET NO.: 19 |                      |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




TCP (2-1a)

**WORK SPACE NEAR SHOULDER**  
Conventional Roads



TCP (2-1b)

**WORK SPACE ON SHOULDER**  
Conventional Roads



TCP (2-1c)

**WORK VEHICLES ON SHOULDER**  
Conventional Roads

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flogger                                 |

| Posted Speed<br>x | Formula             | Minimum Desirable Taper Lengths x |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing "x" Distance | Suggested Longitudinal Buffer Space "B" |
|-------------------|---------------------|-----------------------------------|------------|------------|---|--------------|-----------------------------------|---|
|                   |                     | 10' Offset                        | 11' Offset | 12' Offset | On a Taper  | On a Tangent |                                   |   |
| 30                | L = $\frac{WS}{60}$ | 150'                              | 165'       | 180'       | 30'   | 60'          | 120'                              | 90'                                     |
| 35                |                     | 205'                              | 225'       | 245'       | 35'   | 70'          | 160'                              | 120'                                    |
| 40                | L = WS              | 265'                              | 295'       | 320'       | 40'   | 80'          | 240'                              | 155'                                    |
| 45                |                     | 450'                              | 495'       | 540'       | 45'   | 90'          | 320'                              | 195'                                    |
| 50                |                     | 500'                              | 550'       | 600'       | 50'   | 100'         | 400'                              | 240'                                    |
| 55                |                     | 550'                              | 605'       | 660'       | 55'   | 110'         | 500'                              | 295'                                    |
| 60                |                     | 600'                              | 660'       | 720'       | 60'   | 120'         | 600'                              | 350'                                    |
| 65                |                     | 650'                              | 715'       | 780'       | 65'   | 130'         | 700'                              | 410'                                    |
| 70                |                     | 700'                              | 770'       | 840'       | 70'   | 140'         | 800'                              | 475'                                    |
| 75                | 750'                | 825'                              | 900'       | 75'        | 150'  | 900'         | 540'                              |   |

x Conventional Roads Only  
 x x Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               | ✓              | ✓                     | ✓                            | ✓                    |

**GENERAL NOTES**


- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.

**TRAFFIC CONTROL PLAN**  
**CONVENTIONAL ROAD**  
**SHOULDER WORK**


**TCP(2-1)-18**

|   |            |                      |               |                      |
|---|------------|----------------------|---------------|----------------------|
| FILE: tcp2-1-18.dgn                               | DN:        | CK:                  | DW:           | CK:                  |
| © TxDOT December 1985                             | CONT: 6460 | SECT: 98             | JOB: 001      | HIGHWAY: US 84, ETC. |
| REVISIONS:<br>2-94 4-98<br>8-95 2-12<br>1-97 2-18 | DIST: Ab1  | COUNTY: SCURRY, ETC. | SHEET NO.: 20 |                      |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-2a)  
2-LANE ROADWAY WITHOUT PAVED SHOULDERS  
ONE LANE TWO-WAY  
CONTROL WITH YIELD SIGNS  
(Less than 2000 ADT - See Note 9)



TCP (2-2b)  
2-LANE ROADWAY WITHOUT PAVED SHOULDERS  
ONE LANE TWO-WAY  
CONTROL WITH FLAGGERS

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed *<br>x | Formula                  | Minimum Desirable Taper Lengths * x |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing "x"<br>Distance | Suggested Longitudinal Buffer Space "B" | Stopping Sight Distance |
|---------------------|--------------------------|-------------------------------------|------------|------------|---|--------------|--------------------------------------|---|-------------------------|
|                     |                          | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |                                      |   |                         |
| 30                  | L = WS <sup>2</sup> / 60 | 150'                                | 165'       | 180'       | 30'   | 60'          | 120'                                 | 90'                                     | 200'                    |
| 35                  |                          | 205'                                | 225'       | 245'       | 35'   | 70'          | 160'                                 | 120'                                    | 250'                    |
| 40                  |                          | 265'                                | 295'       | 320'       | 40'   | 80'          | 240'                                 | 155'                                    | 305'                    |
| 45                  | L = WS                   | 450'                                | 495'       | 540'       | 45'   | 90'          | 320'                                 | 195'                                    | 360'                    |
| 50                  |                          | 500'                                | 550'       | 600'       | 50'   | 100'         | 400'                                 | 240'                                    | 425'                    |
| 55                  |                          | 550'                                | 605'       | 660'       | 55'   | 110'         | 500'                                 | 295'                                    | 495'                    |
| 60                  |                          | 600'                                | 660'       | 720'       | 60'   | 120'         | 600'                                 | 350'                                    | 570'                    |
| 65                  |                          | 650'                                | 715'       | 780'       | 65'   | 130'         | 700'                                 | 410'                                    | 645'                    |
| 70                  |                          | 700'                                | 770'       | 840'       | 70'   | 140'         | 800'                                 | 475'                                    | 730'                    |
| 75                  |                          | 750'                                | 825'       | 900'       | 75'   | 150'         | 900'                                 | 540'                                    | 820'                    |

\* Conventional Roads Only  
 x x Taper lengths have been rounded off.  
 L- Length of Taper (FT) W- Width of Offset (FT) S- Posted Speed (MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               | ✓              | ✓                     | ✓                            |                      |

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

**TCP (2-2a)**

- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
- The R1-2oP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support of a 7 foot minimum mounting height.

**TCP (2-2b)**

- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**ONE-LANE TWO-WAY**  
**TRAFFIC CONTROL**



**TCP(2-2)-18**

|                       |      |              |           |             |
|-----------------------|------|--------------|-----------|-------------|
| FILE: tcp2-2-18.dgn   | DN:  | CK:          | DW:       | CK:         |
| © TxDOT December 1985 | CONT | SECT         | JOB       | HIGHWAY     |
| REVISIONS             | 6460 | 98           | 001       | US 84, ETC. |
| 8-95 3-03             | DIST | COUNTY       | SHEET NO. |             |
| 1-97 2-12             | Ab1  | SCURRY, ETC. | 21        |             |
| 4-98 2-18             |      |              |           |             |

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



| LEGEND |                                      |  |                                  |
|--------|--------------------------------------|--|----------------------------------|
|        | Type 3 Barricade                     |  | Channelizing Devices             |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)   |
|        | Trailer Mounted Flashing Arrow Board |  | Raised Pavement Markers Ty II-AA |
|        | Sign                                 |  | Traffic Flow                     |
|        | Flag                                 |  | Flagger                          |

| Posted Speed<br>x | Formula                  | Minimum Desirable Taper Lengths<br>x x |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing<br>"x"<br>Distance | Suggested Longitudinal Buffer Space<br>"B" |
|-------------------|--------------------------|--|------------|------------|---|--------------|---|--|
|                   |                          | 10' Offset                             | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |  |
| 30                | L = WS <sup>2</sup> / 60 | 150'                                   | 165'       | 180'       | 30'   | 60'          | 120'                                    | 90'  |
| 35                |                          | 205'                                   | 225'       | 245'       | 35'   | 70'          | 160'                                    | 120'                                       |
| 40                | L = WS                   | 265'                                   | 295'       | 320'       | 40'   | 80'          | 240'                                    | 155'                                       |
| 45                |                          | 450'                                   | 495'       | 540'       | 45'   | 90'          | 320'                                    | 195'                                       |
| 50                | L = WS                   | 500'                                   | 550'       | 600'       | 50'   | 100'         | 400'                                    | 240'                                       |
| 55                |                          | 550'                                   | 605'       | 660'       | 55'   | 110'         | 500'                                    | 295'                                       |
| 60                | L = WS                   | 600'                                   | 660'       | 720'       | 60'   | 120'         | 600'                                    | 350'                                       |
| 65                |                          | 650'                                   | 715'       | 780'       | 65'   | 130'         | 700'                                    | 410'                                       |
| 70                | L = WS                   | 700'                                   | 770'       | 840'       | 70'   | 140'         | 800'                                    | 475'                                       |
| 75                |                          | 750'                                   | 825'       | 900'       | 75'   | 150'         | 900'                                    | 540'                                       |

x Conventional Roads Only  
 xx Taper lengths have been rounded off.  
 L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               |                |                       | ✓                            | ✓                    |
|               |                |                       |                              | TCP(2-3b) ONLY       |

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
  - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
  - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
  - Conflicting pavement marking shall be removed for long term projects.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This lighter device spacing is intended for the area of the conflicting markings, not the entire work zone.

Texas Department of Transportation  
Traffic Safety Division Standard

## TRAFFIC CONTROL PLAN TRAFFIC SHIFTS ON TWO-LANE ROADS


### TCP(2-3)-23

|                       |       |              |           |             |
|-----------------------|-------|--------------|-----------|-------------|
| FILE: tcp(2-3)-23.dgn | DN:   | CK:          | DW:       | CK:         |
| © TxDOT April 2023    | CONT: | SECT:        | JOB:      | HIGHWAY:    |
| REVISIONS             | 6460  | 98           | 001       | US 84, ETC. |
| 12-85 4-98 2-18       | DIST: | COUNTY:      | SHEET NO. |             |
| 8-95 3-03 4-23        | Ab1   | SCURRY, ETC. | 22        |             |
| 1-97 2-12             |       |              |           |             |

163


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (2-4a)

**ONE LANE CLOSED**



TCP (2-4b)

**TWO LANES CLOSED**

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed<br>x | Formula               | Minimum Desirable Taper Lengths<br>x x |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing<br>"x"<br>Distance | Suggested Longitudinal Buffer Space<br>"B" |
|-------------------|-----------------------|--|------------|------------|---|--------------|---|--|
|                   |                       | 10' Offset                             | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |  |
| 30                | L = $\frac{WS^2}{60}$ | 150'                                   | 165'       | 180'       | 30'   | 60'          | 120'                                    | 90'  |
| 35                |                       | 205'                                   | 225'       | 245'       | 35'   | 70'          | 160'                                    | 120'                                       |
| 40                | L = WS                | 265'                                   | 295'       | 320'       | 40'   | 80'          | 240'                                    | 155'                                       |
| 45                |                       | 450'                                   | 495'       | 540'       | 45'   | 90'          | 320'                                    | 195'                                       |
| 50                | L = WS                | 500'                                   | 550'       | 600'       | 50'   | 100'         | 400'                                    | 240'                                       |
| 55                |                       | 550'                                   | 605'       | 660'       | 55'   | 110'         | 500'                                    | 295'                                       |
| 60                | L = WS                | 600'                                   | 660'       | 720'       | 60'   | 120'         | 600'                                    | 350'                                       |
| 65                |                       | 650'                                   | 715'       | 780'       | 65'   | 130'         | 700'                                    | 410'                                       |
| 70                | L = WS                | 700'                                   | 770'       | 840'       | 70'   | 140'         | 800'                                    | 475'                                       |
| 75                |                       | 750'                                   | 825'       | 900'       | 75'   | 150'         | 900'                                    | 540'                                       |

x Conventional Roads Only  
 x x Taper lengths have been rounded off.  
 L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               |                | ✓                     | ✓                            |                      |


**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
  - For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3oP supplemental plaque.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-4a)**
- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.
- TCP (2-4b)**
- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of conflicting markings, not the entire work zone.


|   |      |                                      |             |
|---|------|--------------------------------------|-------------|
|   |      | Traffic Operations Division Standard |             |
| <b>TRAFFIC CONTROL PLAN<br/>         LANE CLOSURES ON MULTILANE<br/>         CONVENTIONAL ROADS</b> |      |                                      |             |
| <b>TCP(2-4)-18</b>  |      |                                      |             |
| FILE: tcp2-4-18.dgn   | DN:  | CK:                                  | DW: CK:     |
| © TxDOT December 1985   | CONT | SECT                                 | JOB         |
| REVISIONS   | 6460 | 98                                   | 001         |
| 8-95 3-03   |      |                                      | US 84, ETC. |
| 1-97 2-12   | DIST | COUNTY                               | SHEET NO.   |
| 4-98 2-18   | Ab1  | SCURRY, ETC.                         | 23          |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



TCP (2-6a)  
ONE LANE CLOSURE



TCP (2-6b)  
LANE CLOSURE NEAR EXIT RAMP



TCP (2-6c)  
LANE CLOSURE NEAR ENTRANCE RAMP

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed<br>x | Formula               | Minimum Desirable Taper Lengths<br>x x |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing<br>"x"<br>Distance | Suggested Longitudinal Buffer Space<br>"B" |
|-------------------|-----------------------|--|------------|------------|---|--------------|---|--|
|                   |                       | 10' Offset                             | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |  |
| 30                | $L = \frac{WS^2}{60}$ | 150'                                   | 165'       | 180'       | 30'   | 60'          | 120'                                    | 90'  |
| 35                |                       | 205'                                   | 225'       | 245'       | 35'   | 70'          | 160'                                    | 120'                                       |
| 40                |                       | 265'                                   | 295'       | 320'       | 40'   | 80'          | 240'                                    | 155'                                       |
| 45                | $L = WS$              | 450'                                   | 495'       | 540'       | 45'   | 90'          | 320'                                    | 195'                                       |
| 50                |                       | 500'                                   | 550'       | 600'       | 50'   | 100'         | 400'                                    | 240'                                       |
| 55                |                       | 550'                                   | 605'       | 660'       | 55'   | 110'         | 500'                                    | 295'                                       |
| 60                |                       | 600'                                   | 660'       | 720'       | 60'   | 120'         | 600'                                    | 350'                                       |
| 65                |                       | 650'                                   | 715'       | 780'       | 65'   | 130'         | 700'                                    | 410'                                       |
| 70                |                       | 700'                                   | 770'       | 840'       | 70'   | 140'         | 800'                                    | 475'                                       |
| 75                |                       | 750'                                   | 825'       | 900'       | 75'   | 150'         | 900'                                    | 540'                                       |

x Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               |                |                       | ✓                            | ✓                    |

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
- The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

Texas Department of Transportation  
 Traffic Operations Division Standard


TRAFFIC CONTROL PLAN  
 LANE CLOSURES ON  
 DIVIDED HIGHWAYS

TCP(2-6)-18


|                       |       |              |            |             |
|-----------------------|-------|--------------|------------|-------------|
| FILE: tcp2-6-18.dgn   | DN:   | CK:          | DW:        | CK:         |
| © TxDOT December 1985 | CONT: | SECT:        | JOB:       | HIGHWAY:    |
| REVISIONS             | 6460  | 98           | 001        | US 84, ETC. |
| 2-94 4-98             | DIST: | COUNTY:      | SHEET NO.: |             |
| 8-95 2-12             | Abi   | SCURRY, ETC. | 24         |             |
| 1-97 2-18             |       |              |            |             |



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**TCP (3-1a)**  
**UNDIVIDED MULTILANE ROADWAY**




**TRAIL/SHADOW VEHICLE A**  
with RIGHT Directional display Flashing Arrow Board

| LEGEND |                                | ARROW BOARD DISPLAY |   |
|--------|--------------------------------|---------------------|---|
| *      | Trail Vehicle                  |                     |   |
| **     | Shadow Vehicle                 |                     |   |
| ** *   | Work Vehicle                   |                     | RIGHT Directional                               |
|        | Heavy Work Vehicle             |                     | LEFT Directional                                |
|        | Truck Mounted Attenuator (TMA) |                     | Double Arrow                                    |
|        | Traffic Flow                   |                     | CAUTION (Alternating Diamond or 4 Corner Flash) |


| TYPICAL USAGE                       |                          |                          |                              |                          |
|-------------------------------------|--------------------------|--------------------------|------------------------------|--------------------------|
| MOBILE                              | SHORT DURATION           | SHORT TERM STATIONARY    | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY     |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/>     | <input type="checkbox"/> |

**GENERAL NOTES**


- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.




**TCP (3-1b)**  
**TWO-WAY ROADWAY WITH PAVED SHOULDERS**



**TCP (3-1c)**  
**TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS**



**TRAIL/SHADOW VEHICLE B**  
with Flashing Arrow Board in CAUTION display



**STRIPING FOR TMA**

Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
MOBILE OPERATIONS  
UNDIVIDED HIGHWAYS**



**TCP(3-1)-13**

|                       |            |              |           |                      |
|-----------------------|------------|--------------|-----------|----------------------|
| FILE: tcp3-1.dgn      | DN: TxDOT  | CK: TxDOT    | DW: TxDOT | CK: TxDOT            |
| © TxDOT December 1985 | CONT: 6460 | SECT: 98     | JOB: 001  | HIGHWAY: US 84, ETC. |
| REVISIONS:            | DIST:      | COUNTY:      | SHEET NO. |                      |
| 2-94 4-98             |            |              |           |                      |
| 8-95 7-13             |            |              |           |                      |
| 1-97                  | Abi        | SCURRY, ETC. | 25        |                      |



DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



**RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(3-2a)**




**INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(3-2b)**

| LEGEND |                                |                     |   |
|--------|--------------------------------|---------------------|---|
| *      | Trail Vehicle                  | ARROW BOARD DISPLAY |   |
| **     | Shadow Vehicle                 |                     |   |
| ***    | Work Vehicle                   |                     | RIGHT Directional                               |
|        | Heavy Work Vehicle             |                     | LEFT Directional                                |
|        | Truck Mounted Attenuator (TMA) |                     | Double Arrow                                    |
|        | Traffic Flow                   |                     | CAUTION (Alternating Diamond or 4 Corner Flash) |

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| ✓             |                |                       |                              |                      |

**GENERAL NOTES**

- ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the Barricade and Construction (BC) standards. Arrow boards on WORK vehicles will be optional based on the type of work being performed. The arrow boards shall be operated from inside the vehicle.
- For TCP(3-2a) the Engineer will determine if the TRAIL VEHICLE is required based on prevailing roadway conditions, traffic volume, and sight distance restrictions. All other vehicles shown for both TCP(3-2a) and TCP(3-2b) are required.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DMS 8300, Type A.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
- Standard 48" X 48" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
- The signs shown should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or a truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board, must be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The principles on this sheet may be used to close lanes from the left side of the roadway considering the number of lanes, shoulder width, sight distance, and ramp frequency.
- Signs and flashing arrow board modes shall be appropriately altered when implementing left lane closures or interior closures which close the left lanes.
- The Advance Warning Vehicle may straddle the edgeline when shoulder width makes it necessary.






**STRIPING FOR TMA**

|  |                      |                                      |           |
|--|----------------------|--------------------------------------|-----------|
|  |                      | Traffic Operations Division Standard |           |
| <b>TRAFFIC CONTROL PLAN<br/>MOBILE OPERATIONS<br/>DIVIDED HIGHWAYS</b> |                      |                                      |           |
| <b>TCP(3-2)-13</b>   |                      |                                      |           |
| FILE: tcp3-2.dgn   | DN: TxDOT            | CK: TxDOT                            | DW: TxDOT |
| © TxDOT December 1985  | CONT: 6460           | SECT: 98                             | JOB: 001  |
| REVISIONS:   | 2-94                 | 4-98                                 | 8-95      |
|  | 1-97                 | 7-13                                 |           |
| DIST: Abil   | COUNTY: SCURRY, ETC. | SHEET NO. 26                         |           |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



| LEGEND |                                |                      |
|--------|--------------------------------|----------------------|
| * * *  | Trailer Vehicle                | ARROW BOARD DISPLAY  |
| * * *  | Shadow Vehicle                 |                      |
| * * *  | Work Vehicle                   | RIGHT Directional    |
| ☐      | Heavy Work Vehicle             | LEFT Directional     |
| ☐      | Truck Mounted Attenuator (TMA) | Double Arrow         |
| ↔      | Traffic Flow                   | Channelizing Devices |


| Posted Speed<br>x | Formula                  | Minimum Desirable Taper Lengths<br>x x |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing<br>"x"<br>Distance | Suggested Longitudinal Buffer Space<br>"B" |
|-------------------|--------------------------|--|------------|------------|---|--------------|---|--|
|                   |                          | 10' Offset                             | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |  |
| 30                | L = WS <sup>2</sup> / 60 | 150'                                   | 165'       | 180'       | 30'   | 60'          | 120'                                    | 90'  |
| 35                |                          | 205'                                   | 225'       | 245'       | 35'   | 70'          | 160'                                    | 120'                                       |
| 40                |                          | 265'                                   | 295'       | 320'       | 40'   | 80'          | 240'                                    | 155'                                       |
| 45                | L = WS                   | 450'                                   | 495'       | 540'       | 45'   | 90'          | 320'                                    | 195'                                       |
| 50                |                          | 500'                                   | 550'       | 600'       | 50'   | 100'         | 400'                                    | 240'                                       |
| 55                |                          | 550'                                   | 605'       | 660'       | 55'   | 110'         | 500'                                    | 295'                                       |
| 60                |                          | 600'                                   | 660'       | 720'       | 60'   | 120'         | 600'                                    | 350'                                       |
| 65                |                          | 650'                                   | 715'       | 780'       | 65'   | 130'         | 700'                                    | 410'                                       |
| 70                |                          | 700'                                   | 770'       | 840'       | 70'   | 140'         | 800'                                    | 475'                                       |
| 75                |                          | 750'                                   | 825'       | 900'       | 75'   | 150'         | 900'                                    | 540'                                       |

x Conventional Roads Only  
 x x Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
| ✓             |                |                       |                              |                      |

**GENERAL NOTES**

1. This traffic control plan is for use on conventional roads posted at 45 mph or less and is intended for mobile operations that move continuously or intermittently (stopping up to approximately 15 minutes) such as short-line striping and in-lane rumble strips. When activities are anticipated to take longer amounts of time or traffic conditions warrant, a short duration or short-term stationary traffic control plan should be used.
2. A Truck Mounted Attenuator shall be used on Shadow Vehicle. Striping on the back panel of all truck mounted attenuators shall be 8" red and white reflective sheeting placed in an inverted "V" design. Reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental material specification DMS-8300, Type A.
3. All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD), latest edition.
4. The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the drivers side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
5. Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C as per BC Standards. The arrow board operation shall be controlled from inside the truck.




Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
 MOBILE OPERATIONS FOR  
 ISOLATED WORK AREAS  
 UNDIVIDED HIGHWAYS  
 TCP(3-4)-13**


|                    |              |           |           |             |
|--------------------|--------------|-----------|-----------|-------------|
| FILE: tcp3-4.dgn   | DN: TxDOT    | CK: TxDOT | DW: TxDOT | CK: TxDOT   |
| © TxDOT July, 2013 | CONT         | SECT      | JOB       | HIGHWAY     |
| REVISIONS          | 6460         | 98        | 001       | US 84, ETC. |
| DIST               | COUNTY       |           | SHEET NO. |             |
| ABL                | SCURRY, ETC. |           | 27        |             |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (6-1a)  
TYPICAL FREEWAY  
ONE LANE CLOSURE



TCP (6-1b)  
TYPICAL FREEWAY  
TWO LANE CLOSURE

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
|              |         | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |
| 45           | L = WS  | 450'                                | 495'       | 540'       | 45'   | 90'          | 195'                                    |
| 50           |         | 500'                                | 550'       | 600'       | 50'   | 100'         | 240'                                    |
| 55           |         | 550'                                | 605'       | 660'       | 55'   | 110'         | 295'                                    |
| 60           |         | 600'                                | 660'       | 720'       | 60'   | 120'         | 350'                                    |
| 65           |         | 650'                                | 715'       | 780'       | 65'   | 130'         | 410'                                    |
| 70           |         | 700'                                | 770'       | 840'       | 70'   | 140'         | 475'                                    |
| 75           |         | 750'                                | 825'       | 900'       | 75'   | 150'         | 540'                                    |
| 80           |         | 800'                                | 880'       | 960'       | 80'   | 160'         | 615'                                    |

\*\* Taper lengths have been rounded off.  
L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               | ✓              | ✓                     | ✓                            |                      |

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the median side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 7' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.




TRAFFIC CONTROL PLAN  
FREEWAY LANE CLOSURES

TCP(6-1)-12


|                       |           |              |           |             |
|-----------------------|-----------|--------------|-----------|-------------|
| FILE: tcp6-1.dgn      | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| © TxDOT February 1998 | CONT      | SECT         | JOB       | HIGHWAY     |
| 8-12                  | REVISIONS | 6460 98      | 001       | US 84, ETC. |
|                       | DIST      | COUNTY       | SHEET NO. |             |
|                       | Ab1       | SCURRY, ETC. | 28        |             |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (6-2a)  
ENTRANCE RAMP OPEN  
WORK WITHIN 500' OF RAMP



TCP (6-2b)  
ENTRANCE RAMP CLOSED

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
|              |         | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |
| 45           | L = WS  | 450'                                | 495'       | 540'       | 45'   | 90'          | 195'                                    |
| 50           |         | 500'                                | 550'       | 600'       | 50'   | 100'         | 240'                                    |
| 55           |         | 550'                                | 605'       | 660'       | 55'   | 110'         | 295'                                    |
| 60           |         | 600'                                | 660'       | 720'       | 60'   | 120'         | 350'                                    |
| 65           |         | 650'                                | 715'       | 780'       | 65'   | 130'         | 410'                                    |
| 70           |         | 700'                                | 770'       | 840'       | 70'   | 140'         | 475'                                    |
| 75           |         | 750'                                | 825'       | 900'       | 75'   | 150'         | 540'                                    |
| 80           |         | 800'                                | 880'       | 960'       | 80'   | 160'         | 615'                                    |

x x Taper lengths have been rounded off.  
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               | ✓              | ✓                     | ✓                            |                      |

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainline can be seen from both roadways.
- See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

x A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN  
WORK AREA NEAR RAMP**

TCP(6-2)-12


|                      |           |              |           |             |
|----------------------|-----------|--------------|-----------|-------------|
| FILE: tcp6-2.dgn     | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| ©TxDOT February 1994 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS            | 6460      | 98           | 001       | US 84, ETC. |
| 1-97 8-98            | DIST      | COUNTY       | SHEET NO. |             |
| 4-98 8-12            | Ab1       | SCURRY, ETC. | 29        |             |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:  
FILE:



TCP (6-3a)  
ENTRANCE RAMP OPEN



TCP (6-3b)  
EXIT RAMP CLOSED  
TRAFFIC EXITS PRIOR TO CLOSED RAMP



| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices                    |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
|              |         | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |
| 45           | L = WS  | 450'                                | 495'       | 540'       | 45'   | 90'          | 195'                                    |
| 50           |         | 500'                                | 550'       | 600'       | 50'   | 100'         | 240'                                    |
| 55           |         | 550'                                | 605'       | 660'       | 55'   | 110'         | 295'                                    |
| 60           |         | 600'                                | 660'       | 720'       | 60'   | 120'         | 350'                                    |
| 65           |         | 650'                                | 715'       | 780'       | 65'   | 130'         | 410'                                    |
| 70           |         | 700'                                | 770'       | 840'       | 70'   | 140'         | 475'                                    |
| 75           |         | 750'                                | 825'       | 900'       | 75'   | 150'         | 540'                                    |
| 80           |         | 800'                                | 880'       | 960'       | 80'   | 160'         | 615'                                    |

\*\* Taper lengths have been rounded off.  
L=Length of Taper(F) W=Width of Offset(F) S=Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               | ✓              | ✓                     | ✓                            |                      |

GENERAL NOTES:  
1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

\* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation  
Traffic Operations Division Standard


TRAFFIC CONTROL PLAN  
WORK AREA BEYOND RAMP

TCP(6-3)-12

|                      |           |              |           |             |
|----------------------|-----------|--------------|-----------|-------------|
| FILE: tcp6-3.dgn     | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| ©TxDOT February 1994 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS            | 6460      | 98           | 001       | US 84, ETC. |
| 1-97 8-98            | DIST      | COUNTY       | SHEET NO. |             |
| 4-98 8-12            | Ab1       | SCURRY, ETC. | 30        |             |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




**TCP (6-4a)**  
**EXIT RAMP CLOSED**  
**TRAFFIC EXITS PAST CLOSED RAMP**

|                            |                         |
|----------------------------|-------------------------|
| STREET A<br>EXIT<br>CLOSED | USE<br>STREET B<br>EXIT |
| EXIT XX<br>CLOSED          | USE<br>EXIT XY          |

Or, as an option when exits are numbered

Place 1 mile (approx.) in advance of closed ramp.



**TCP (6-4b)**  
**EXIT RAMP OPEN**

| LEGEND |                                      |  |   |
|--------|--------------------------------------|--|---|
|        | Type 3 Barricade                     |  | Channelizing Devices (CDs)              |
|        | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|        | Trailer Mounted Flashing Arrow Board |  | Portable Changeable Message Sign (PCMS) |
|        | Sign                                 |  | Traffic Flow                            |
|        | Flag                                 |  | Flagger                                 |

| Posted Speed | Formula | Minimum Desirable Taper Lengths "L" |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Suggested Longitudinal Buffer Space "B" |
|--------------|---------|-------------------------------------|------------|------------|---|--------------|---|
|              |         | 10' Offset                          | 11' Offset | 12' Offset | On a Taper  | On a Tangent |   |
| 45           | L = WS  | 450'                                | 495'       | 540'       | 45'   | 90'          | 195'                                    |
| 50           |         | 500'                                | 550'       | 600'       | 50'   | 100'         | 240'                                    |
| 55           |         | 550'                                | 605'       | 660'       | 55'   | 110'         | 295'                                    |
| 60           |         | 600'                                | 660'       | 720'       | 60'   | 120'         | 350'                                    |
| 65           |         | 650'                                | 715'       | 780'       | 65'   | 130'         | 410'                                    |
| 70           |         | 700'                                | 770'       | 840'       | 70'   | 140'         | 475'                                    |
| 75           |         | 750'                                | 825'       | 900'       | 75'   | 150'         | 540'                                    |
| 80           |         | 800'                                | 880'       | 960'       | 80'   | 160'         | 615'                                    |

x x Taper lengths have been rounded off.  
L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

| TYPICAL USAGE |                |                       |                              |                      |
|---------------|----------------|-----------------------|------------------------------|----------------------|
| MOBILE        | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|               | ✓              | ✓                     | ✓                            |                      |

- GENERAL NOTES**
- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
  - See BC Standards for sign details.

x A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation  
Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**WORK AREA AT EXIT RAMP**

**TCP(6-4)-12**

|                      |           |              |             |           |
|----------------------|-----------|--------------|-------------|-----------|
| FILE: tcp6-4.dgn     | DN: TxDOT | CK: TxDOT    | DW: TxDOT   | CK: TxDOT |
| ©TxDOT February 1994 | CONT      | SECT         | JOB         | HIGHWAY   |
| REVISIONS            | 6460 98   | 001          | US 84, ETC. |           |
| 1-97 8-98            | DIST      | COUNTY       | SHEET NO.   |           |
| 4-98 8-12            | Ab1       | SCURRY, ETC. | 31          |           |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


Warning sign and rumble strip sequence in opposite direction is same as below.

| Flagger to Flagger (Length of Work Area) | ADT     | # of Rumble Strip Arrays |
|--|---------|--------------------------|
| 1/8 Mile                                 | < 4,500 | 1                        |
|  | ≥ 4,500 | 2                        |
| 1/4 Mile                                 | < 3,500 | 1                        |
|  | ≥ 3,500 | 2                        |
| 1/2 Mile                                 | < 2,600 | 1                        |
|  | ≥ 2,600 | 2                        |
| 1 Mile                                   | < 1,600 | 1                        |
|  | ≥ 1,600 | 2                        |
| > 1 Mile                                 | N/A     | 2                        |

Rumble Strip Array (See note 1)


Rumble Strip Array (See note 1)

The second Rumble Strip Array is required when the ADT thresholds in Table 1 indicate the need for 2 Arrays.



WZ(RS-1a)

**RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION**



WZ(RS-1b)

**RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY**

**GENERAL NOTES**

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

| Speed               | Approximate distance between strips in an array |
|---------------------|---|
| ≤ 40 MPH            | 10'   |
| > 40 MPH & ≤ 55 MPH | 15'   |
| = 60 MPH            | 20'   |
| ≥ 65 MPH            | • 35'+  |

|  |                                      |  |   |
|--|--------------------------------------|--|---|
|  | Type 3 Barricade                     |  | Channelizing Devices                    |
|  | Heavy Work Vehicle                   |  | Truck Mounted Attenuator (TMA)          |
|  | Trailer Mounted Flashing Arrow Panel |  | Portable Changeable Message Sign (PCMS) |
|  | Sign                                 |  | Traffic Flow                            |
|  | Flag                                 |  | Flagger                                 |

| Posted Speed * | Formula                  | Minimum Desirable Taper Lengths ** |            |            | Suggested Maximum Spacing of Channelizing Devices |              | Minimum Sign Spacing "X" Distance | Suggested Longitudinal Buffer Space "B" |
|----------------|--------------------------|------------------------------------|------------|------------|---|--------------|-----------------------------------|---|
|                |                          | 10' Offset                         | 11' Offset | 12' Offset | On a Taper  | On a Tangent |                                   |   |
| 30             | L = WS <sup>2</sup> / 60 | 150'                               | 165'       | 180'       | 30'   | 60'          | 120'                              | 90'                                     |
| 35             |                          | 205'                               | 225'       | 245'       | 35'   | 70'          | 160'                              | 120'                                    |
| 40             | L = WS                   | 265'                               | 295'       | 320'       | 40'   | 80'          | 240'                              | 155'                                    |
| 45             |                          | 450'                               | 495'       | 540'       | 45'   | 90'          | 320'                              | 195'                                    |
| 50             | L = WS                   | 500'                               | 550'       | 600'       | 50'   | 100'         | 400'                              | 240'                                    |
| 55             |                          | 550'                               | 605'       | 660'       | 55'   | 110'         | 500'                              | 295'                                    |
| 60             | L = WS                   | 600'                               | 660'       | 720'       | 60'   | 120'         | 600'                              | 350'                                    |
| 65             |                          | 650'                               | 715'       | 780'       | 65'   | 130'         | 700'                              | 410'                                    |
| 70             | L = WS                   | 700'                               | 770'       | 840'       | 70'   | 140'         | 800'                              | 475'                                    |
| 75             |                          | 750'                               | 825'       | 900'       | 75'   | 150'         | 900'                              | 540'                                    |

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper(FT) W=Width of Offset(FT)  
 S=Posted Speed(MPH)

| MOBILE | SHORT DURATION | SHORT TERM STATIONARY | INTERMEDIATE TERM STATIONARY | LONG TERM STATIONARY |
|--------|----------------|-----------------------|------------------------------|----------------------|
|        | ✓              | ✓                     |                              |                      |

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.

• For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation Traffic Safety Division Standard

## TEMPORARY RUMBLE STRIPS


### WZ(RS)-22

|                           |            |                      |              |                      |
|---------------------------|------------|----------------------|--------------|----------------------|
| FILE: wzs22.dgn           | DN: TxDOT  | CK: TxDOT            | DW: TxDOT    | CK: TxDOT            |
| © TxDOT November 2012     | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US 84, ETC. |
| REVISIONS: 2-14 1-22 4-16 | DIST: Abil | COUNTY: SCURRY, ETC. | SHEET NO. 32 |                      |


DATE: FILE:




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TYPICAL POST



WOOD BLOCK TO ROUND WOOD POST




WOOD BLOCK TO RECTANGULAR WOOD POST




WOOD BLOCK TO STEEL POST


Note: See Rail Splice Detail for the required hardware.




ELEVATION 12 1/2 (INOM.) W-BEAM SECTION  
25 foot sections may also be supplied (See General Note 2)



\* LOW FILL CULVERT POST  
FOR USE ON NON-BRIDGE CLASS CULVERTS ONLY




\* Post(s) may require field modifications to ensure proper guardrail height.




RAIL SPLICE DETAIL

GENERAL NOTES

- The type of post (round wood post, rectangular wood post, or steel post) will be shown elsewhere in the plans. The exact position of MBSG shall be shown elsewhere in the plans or as directed by the Engineer. Steel posts to be galvanized in accordance with Item 445, "Galvanizing."
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans. The Contractor may furnish rail elements of 12 1/2 or 25 foot nominal lengths.
- Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the slab (ASTM A563) and Type A (1 1/4" O.D.) washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 3/8" x 1 1/4" (or 2" long at triple rail splices) with a 3/8" double recessed nut (ASTM A563).
- Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item.
- Crown shall be widened to accommodate the Metal Beam Guard Fence.
- The lateral approach to the guard fence, shall have a slope rate of not more than 1V:10H.
- Unless otherwise shown in the plans, guard fence placed in the vicinity of curbs shall be positioned so that the face of curb is located directly below or behind the face of the block. Rail placed over curbs shall be installed so that the post bolt is located approximately 21 inches above the gutter pan or roadway surface.
- If solid rock is encountered within 0 to 18" of the finished grade, drill a 22" dia. hole, 24" into the rock, or drill two 12" dia. front to back overlapping holes, 24" into the rock. If solid rock is encountered below 18", drill a 12" dia. hole, 12" into the rock or to the standard embedment depth, whichever is less. Any excess post length, after meeting these depths, may be field cut to ensure proper guardrail mounting height. Backfill with a cohesionless material.
- Posts shall not be set in concrete, of any depth.
- Special fabrication will be required at installations having a curvature of less than 150 ft. radius.
- The terminal anchor section (TAS) post shall be set in Class A concrete (unless otherwise shown in the plans) in accordance with Item 421, "Hydraulic Cement Concrete." Concrete shall be subsidiary to the bid item requiring construction of the terminal anchor section (TAS). Terminal anchor post to be galvanized in accordance with Item 445, "Galvanizing."
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.




\*\* TERMINAL ANCHOR SECTION (TAS)  
Terminal anchor sections are only for downstream use, when located outside the horizontal clearance area of opposing traffic.



OPTION (1)

Note: This anchor post requires four additional 3/4 inch holes (shop or field) in the rail member with eight 3/8 inch hex bolts with nut and plate washer.




OPTION (2)

Note: This anchor post requires the use of the 10 ga. terminal connector with four 3/8 inch hex bolts with nut and washer.


TERMINAL ANCHOR POST OPTIONS  
(See General Note 11)

Notes:


- Either concrete anchor may be used with either post option above.
- No construction joint is allowed in the concrete anchor.
- Terminal rail may be bolted to post and in twist position prior to placing concrete anchor.
- If concrete anchor is precast, the area should be compacted as directed by the Engineer, when placed in the field.



TERMINAL CONCRETE ANCHOR OPTIONS  
(See General Note 11)



TERMINAL CONNECTOR  
Place face of post approx. on C of anchor



TERMINAL CONNECTOR

For connection hardware to concrete rails, see the MBSG transition standards.

ONLY FOR USE IN MAINTENANCE REPAIRS OR HIGHLY CONSTRAINED SITE CONDITIONS.



METAL BEAM GUARD FENCE

MBGF - 19



|                       |            |                      |              |                      |
|-----------------------|------------|----------------------|--------------|----------------------|
| FILE: mbgf19.dgn      | DN: TxDOT  | CK: KM               | DW: BD       | CK: VP               |
| © TxDOT NOVEMBER 2019 | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US 84, ETC. |
| REVISIONS             | DIST: Abil | COUNTY: SCURRY, ETC. | SHEET NO. 33 |                      |

DATE: FILE:




DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: FILE:




5/8" Button head post bolt with nut & washer (See General Note 3)




SECTION A-A



WOOD BLOCK TO ROUND WOOD POST



WOOD BLOCK TO RECTANGULAR WOOD POST



WOOD BLOCK TO STEEL POST

**GENERAL NOTES**

- The type of post (round wood post, rectangular wood post, or steel post) will be shown elsewhere in the plans. The exact position of transitions shall be shown elsewhere in the plans or as directed by the Engineer.
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans.
- Button head "post" bolts (ASTM A307) shall be of sufficient length to extend through the full thickness of the nut (ASTM A563) and the Type A 1 3/4" O.D. washer and not more than 1" beyond it. Button head "splice" bolts (ASTM A307) are 5/8" x 2" (at triple rail splices) with a 5/8" double recessed nuts (ASTM A563).
- Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, "Galvanizing." Fittings shall be subsidiary to the bid item requiring construction of the transition.
- Crown will be widened to accommodate transitions.
- If solid rock is encountered. See the MBGF standard sheet for proper installation guidance.
- Posts shall not be set in concrete.
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and/or blocks of similar dimensions. The Construction Division, TxDOT, maintains a Material Producer List (MPL) for producers of materials conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.
- Refer to MBGF Standard Sheet for additional details.


**ONLY FOR USE IN MAINTENANCE REPAIRS.**



**METAL BEAM GUARD FENCE  
 TRANSITION (T101)  
 (T101 BRIDGE RAIL)  
 MBGF (T101)-19**

|                       |           |              |        |             |
|-----------------------|-----------|--------------|--------|-------------|
| FILE: mbgft1019.dgn   | DN: TxDOT | CK: KM       | DW: BD | CK: VP      |
| © TxDOT NOVEMBER 2019 | CONT      | SECT         | JOB    | HIGHWAY     |
| REVISIONS             | 6460      | 98           | 001    | US 84, ETC. |
|                       | DIST      | COUNTY       |        | SHEET NO.   |
|                       | Abil      | SCURRY, ETC. |        | 35          |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




### GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

**Note: Site Condition(s)**  
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.  
 Approach grading or mow strip may be decreased or eliminated. As directed by the Engineer.


#### GENERAL NOTES

1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments (See SGT standards for proper SGT installation).
2. Mow strips shall be asphaltic pavement or reinforced concrete (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item of work. Asphaltic pavement shall meet the requirements of the item, and be placed in accordance with the pertinent bid item as shown on the plans. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
3. The leaveout behind the post shall be a minimum of 7".
4. The type of approved post will be shown elsewhere in the plans. See the applicable standard sheets for additional details and information.
5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
6. Depth of mow strip will be 4".
7. The limits of payment for asphaltic pavement or reinforced concrete will include leaveouts for posts.
8. The leave-outs shall be filled with no more than a 2-sack grout mixture (1 part cement, 5 parts water, and 14 parts sand by volume) with a 28-day compressive strength of approximately 120 psi or less. Provide grout of a consistency that will flow into and completely fill all voids. Due to ouger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of rip rap mow strip.




#### PLAN

Regular MBGF shown with Mow Strip



#### SECTION A-A


Typical



#### MOW STRIP DETAIL


Reinforced Concrete or Asphaltic Pavement Mow Strip with 18" x 18" or 18" dia. minimum leaveout.

Fill leaveout with 2-Sack grout. (See General Note 8)




#### CURB OPTION (1)

This option will increase the post embedment through out the system.



#### CURB OPTION (2)

Curb shown on top of mow strip



#### CURB OPTION (3)

**ONLY FOR USE IN MAINTENANCE REPAIRS.**





## METAL BEAM GUARD FENCE (MOW STRIP)

### MBGF(MS)-19

|                       |           |              |           |            |
|-----------------------|-----------|--------------|-----------|------------|
| FILE: mbgfms19.dgn    | DN: TxDOT | CK: KM       | DW: TxDOT | CK: CL     |
| © TxDOT NOVEMBER 2019 | CONT      | SECT         | JOB       | HIGHWAY    |
| REVISIONS             | 6460      | 98           | 001       | US 84, ETC |
|                       | DIST      | COUNTY       |           | SHEET NO.  |
|                       | Abi       | SCURRY, ETC. |           | 36         |


DATE:  
FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




**GENERAL NOTES**

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBSG SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAY BE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.



**ELEVATION MID-SPAN RAIL SPLICE**  
SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)




**ELEVATION 25'-0" (NOM.) W-BEAM SECTION**

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

\* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.

9" MIN. FILL DEPTH CULVERT SLAB



**LOW FILL CULVERT POST**

NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 3/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.

2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 3/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: TRANSITIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.

SPLICE BOLT LENGTH VARIES

FBB01 - 1 1/4"

FBB02 - 2"


POST & BLOCK LENGTH

FBB03 - 10"

FBB04 - 18"

**BUTTON HEAD BOLT**

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



**MID-SPAN RAIL SPLICE DETAIL**

(8) 3/8" x 1 1/4" BUTTON HEAD SPLICE BOLTS WITH RECESSED NUTS.

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

|   |           |                          |           |
|---|-----------|--------------------------|-----------|
|   |           | Design Division Standard |           |
| <h1>METAL BEAM GUARD FENCE</h1> <h2>TL-3 MASH COMPLIANT</h2> <h3>GF(31)-19</h3> |           |                          |           |
| FILE: gf3119.dgn  | DN: TxDOT | CK: KM                   | DW: VP    |
| © TxDOT: NOVEMBER 2019  | CONT      | SECT                     | JOB       |
| REVISIONS   | 6460      | 98                       | 001       |
|   | DIST      | COUNTY                   | SHEET NO. |
|   | Abi       | SCURRY, ETC.             | 37        |

DATE: FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:

BREAKAWAY CABLE TERMINAL (BCT) CABLE ANCHOR ASSEMBLY WITH CABLE BRACKET, BEARING PLATE AND STANDARD HARDWARE. (11) (15) (17)

C3 x 5 x 80" (3) GROUND STRUTS


7 1/4" x 5 1/4" x 46" (2) DAT TERMINAL POST

NON-SYMMETRICAL TRANSITION RAIL SECTION (SEE APPLICABLE TRANSITION STANDARD)


**GENERAL NOTES**

1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
5. REFER TO GF(31) SHEET FOR TERMINAL CONNECTION DETAILS.







**MOW STRIP INSTALLATION**  
 IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.



**DOWNSTREAM ANCHOR TERMINAL (DAT)**  
 NOTE: ONLY FOR DOWNSTREAM USE. WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.



| (DAT) PARTS LIST               | QTY |
|--------------------------------|-----|
| 1 STEEL FOUNDATION TUBE        | 2   |
| 2 DAT TERMINAL POST            | 2   |
| 3 CHANNEL STRUT                | 2   |
| 4 TERMINAL RAIL ELEMENT        | 1   |
| 5 SHELF ANGLE BRACKET          | 1   |
| 6 BCT BEARING PLATE            | 1   |
| 7 BCT POST SLEEVE              | 1   |
| 8 GUARDRAIL ANCHOR BRACKET     | 1   |
| 9 (ROUNDED) W-BEAM END SECTION | 1   |
| 10 BCT CABLE ANCHOR            | 1   |
| 11 RECESSED NUT, GUARDRAIL     | 20  |
| 12 1 1/4" BUTTON HEAD BOLT     | 4   |
| 13 10" BUTTON HEAD BOLT        | 2   |
| 14 5/8" X 2" HEX HEAD BOLT     | 8   |
| 15 5/8" X 8" HEX HEAD BOLT     | 4   |
| 16 5/8" X 10" HEX HEAD BOLT    | 2   |
| 17 5/8" FLAT WASHER            | 18  |




Texas Department of Transportation  
 Design Division Standard

**METAL BEAM GUARD FENCE (DOWNSTREAM ANCHOR TERMINAL) TL-3 MASH COMPLIANT GF(31)DAT-19**

|                                  |            |                      |              |                      |
|----------------------------------|------------|----------------------|--------------|----------------------|
| FILE: gf31dat19.dgn              | DN: TxDOT  | CK: KM               | DW: VP       | CK: CGL / AG         |
| © TxDOT: NOVEMBER 2019 REVISIONS | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US 84, ETC. |
|                                  | DIST: Abil | COUNTY: SCURRY, ETC. | SHEET NO. 38 |                      |


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.



**RECTANGULAR CRT POST  
(6" X 8" X 6' LONG)**

(6) CRT REQUIRED  
SEE ELEVATION DETAIL FOR LOCATIONS




**LATERAL OFFSET BETWEEN THE  
GUARDRAIL AND THE CULVERT HEADWALL**

**GENERAL NOTES**

1. THE TYPE OF LINE POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF THE TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENT SHALL MEET ALL REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 12'- 6" OR 25'- 0" NOMINAL LENGTHS.
3. RAIL POST HOLES ARE OFFSET 3'- 1/2" FROM STANDARD GUARDRAIL TO ACCOMMODATE THE MIDSPAN SPlicing.
4. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NO MORE THAN 1" BEYOND IT.
5. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
6. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
7. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
8. REFER TO GF(31) STANDARD SHEET FOR ADDITIONAL DETAILS.
9. FLAME CUTTING OF HOLES IN GUARDRAIL SHALL NOT BE PERMITTED. IF YOU ENCOUNTER MIS-ALIGNED BOLT HOLES IN GUARDRAIL CONTACT THE DESIGN DIVISION FOR ADDITIONAL INFORMATION & OPTIONS.

NOTE: SEE GF(31) STANDARD FOR STANDARD LINE POSTS.

DIRECTION OF TRAFFIC




**ELEVATION DETAIL  
LONG SPAN GUARDRAIL**

|   |           |                          |           |
|---|-----------|--------------------------|-----------|
|   |           | Design Division Standard |           |
| <b>METAL BEAM GUARD FENCE<br/>LONG SPAN<br/>TL-3 MASH COMPLIANT</b> |           |                          |           |
| <b>GF(31)LS-19</b>  |           |                          |           |
| FILE: gf31ls19.dgn  | DN: TxDOT | CK: KM                   | DW: VP    |
| © TxDOT: NOVEMBER 2019  | CONT      | SECT                     | JOB       |
| REVISIONS   | 6460      | 98                       | 001       |
|   | DIST      | COUNTY                   | SHEET NO. |
|   | Abi       | SCURRY, ETC.             | 39        |

DATE:  
FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT"; NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: FILE:






- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (ASTM A325 OR A449)
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 3/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563)

NOTE: HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL. LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE: CHAMFER REQUIRED ON CONCRETE RAILS THAT EXTEND BEYOND THE FACE OF GUARDRAIL TRANSITION.



- ### GENERAL NOTES
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. REFER TO GF(31) STANDARD SHEET.
  2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS.
  3. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
  4. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM BOLT LENGTH TO MEET REQUIRED LENGTH.
  5. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  6. CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
  7. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
  8. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT, MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
  9. REFER TO GF(31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
  10. FOR ROUND WOOD POSTS SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE TRANSITION.





- (2) 5/8" BUTTON HEAD POST BOLTS & NUTS:(FBB04)
- (1) 5/8" FLAT WASHER:(FWC14a) UNDER EACH NUT


- (1) 5/8" BUTTON HEAD POST BOLT & NUT:(FBB04)
- (1) 5/8" FLAT WASHER:(FWC14a) UNDER EACH NUT

PLATE WASHER INSTRUCTIONS



**BRIDGE APPROACH - UPSTREAM:** THE SHORT RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.  
**BRIDGE EXIT - DOWNSTREAM:** THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.



NOTE: \*WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.




**LOW-SPEED TRANSITION**




|   |           |                          |               |
|---|-----------|--------------------------|---------------|
|   |           | Design Division Standard |               |
| <b>METAL BEAM GUARD FENCE<br/>THRIE-BEAM TRANSITION<br/>TL-2 MASH COMPLIANT<br/>GF(31)TR TL2-19</b> |           |                          |               |
| FILE: gf31trtl219.dgn   | DN: TxDOT | CK: KM                   | DW: VP        |
| © TxDOT: NOVEMBER 2019  | CON: 6460 | SECT: 98                 | JOB: 001      |
| REVISIONS   | DIST: Abi | COUNTY: SCURRY, ETC.     | SHEET NO.: 40 |



DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
  - CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET, WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II (5'- 3/4" HEIGHT); SEE CURRENT CCGG STANDARD SHEET FOR FURTHER DETAILS. IF OTHER CURB HEIGHTS ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE-17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
  - CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH GUARDRAIL WILL BE PAID FOR BY THE LINEAR FOOT.
  - UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
  - FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
  - THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF(31) STANDARD SHEET.
  - THE POST LENGTH SHALL BE MARKED ON ALL 7'- 0" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1 FT. REGION OF THE POST, AT LEAST 3/8" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
  - POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  - RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
  - BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
  - FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
  - WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
  - UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TxDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
  - REFER TO GF(31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
  - THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
  - IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRIE-BEAM TRANSITION SECTION. (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED)(TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED)(STEEL POST)" AS APPLICABLE FOR POST TYPE. SEE SHT.2 FOR ADDITIONAL INFORMATION.



**THRIE-BEAM TERMINAL - CURB TABLE**

PRECAST CURB FULL LENGTH EQUALS 12'- 2"

THE PRECAST CURB MAY BE FORMED INTO TWO SECTIONS.

CURB (1) LENGTH 5'- 8"

CURB (2) LENGTH 6'- 6"

TAPER CURB (2) TO A HEIGHT OF 4" AT POST 7

CONNECTING PRECAST CURB SECTIONS (1) & (2):

FORM OR CORE 1" DIA. HOLE 9" LONG INTO EACH CURB END.

USE (1) \*5 GR.60 REBAR 18" LONG TO CONNECT BOTH CURBS.

SECURING PRECAST OR CAST-IN-PLACE TO FINISHED GRADE :

FORM OR CORE (4) 1" DIA. HOLES, SEE PLAN AND ELEVATION VIEWS FOR HOLE LOCATIONS. DRIVE (4) \*5 GR.60 REBAR STAKES 18" LONG INTO THE GROUND AND 1/2" BELOW TOP OF CURB.


FILL HOLES WITH APPROVED GROUT MIXTURE.

\* NOTES: NOT NEEDED FOR CAST-IN-PLACE.

SEE TYPE II CURB DETAIL FOR REBAR AND COVER REQUIREMENTS.

PERCUSSION DRILLING IS NOT PERMITTED WITH: TYPE II CURB, BRIDGE RAIL OR CONCRETE TRAFFIC RAIL.

**TYPE II CURB DETAILS**



**HIGH-SPEED TRANSITION**

**SHEET 1 OF 2**

Texas Department of Transportation

Design Division Standard

**METAL BEAM GUARD FENCE**

**THRIE-BEAM TRANSITION**

**TL-3 MASH COMPLIANT**

**GF(31)TR TL3-20**


|                        |           |              |           |              |
|------------------------|-----------|--------------|-----------|--------------|
| FILE: gf31trtl320.dgn  | DN: TxDOT | CK: KM       | DW: VP    | CK: CGL / AG |
| © TxDOT: NOVEMBER 2020 | CONT      | SECT         | JOB       | HIGHWAY      |
| REVISIONS              | 6460      | 98           | 001       | US 84, ETC.  |
|                        | DIST      | COUNTY       | SHEET NO. |              |
|                        | Abi       | SCURRY, ETC. | 41        |              |

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE:  
FILE:

REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)


END PAYMENT FOR METAL BEAM GUARD FENCE TRANSITION.  
BEGIN PAYMENT FOR METAL BEAM GUARD FENCE.



ELEVATION VIEW



SECTION D-D



THRIE BEAM TRANSITION BLOCKOUT DETAILS

HIGH-SPEED TRANSITION

SHEET 2 OF 2




METAL BEAM GUARD FENCE  
THRIE-BEAM TRANSITION  
TL-3 MASH COMPLIANT  
GF(31)TR TL3-20


|                        |           |              |           |             |
|------------------------|-----------|--------------|-----------|-------------|
| FILE: gf31trtl320.dgn  | DN: TxDOT | CK: KM       | DW: KM    | CK: CGL/AG  |
| © TxDOT: NOVEMBER 2020 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS              | 6460      | 98           | 001       | US 84, ETC. |
|                        | DIST      | COUNTY       | SHEET NO. |             |
|                        | Abi       | SCURRY, ETC. | 42        |             |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: \_\_\_\_\_  
 FILE: \_\_\_\_\_




- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
  2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE TRANSITION SECTIONS OF GUARDRAIL.
  3. BUTTON HEAD "POST" BOLTS (ASTM A307 GR.A) SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT (ASTM A563) AND 3/8" ROUND WASHER (ASTM F436) AND NOT MORE THAN 1" BEYOND IT. BUTTON HEAD "SPlice" BOLTS (ASTM A307) ARE 3/8" X 1-1/4" WITH 3/8" NUTS (ASTM A563).
  4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
  5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  6. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
  7. POSTS SHALL NOT BE SET IN CONCRETE.
  8. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
  9. REFER TO STANDARD GF(31) AND APPLICABLE BRIDGE RAILING STANDARD FOR ADDITIONAL DETAILS.




(8) 5/8" DIA. X 2" GUARDRAIL SPLICE BOLTS (FBB02)  
 WITH 3/8" GUARDRAIL NUTS (ASTM A563)  
 (SEE GENERAL NOTE 3)

\* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




|  |            |                                |               |
|--|------------|--------------------------------|---------------|
| <br>Texas Department of Transportation   |            | Design<br>Division<br>Standard |               |
| <b>METAL BEAM GUARD FENCE<br/>         TRANSITION<br/>         (T101)<br/>         GF(31)T101-19</b> |            |                                |               |
| FILE: gf31t10119   | DN: TxDOT  | CK: KM                         | DW: VP        |
| © TxDOT: NOVEMBER 2019   | CONT: 6460 | SECT: 98                       | JOB: 001      |
| REVISIONS:   |            |                                | US 84, ETC.   |
|  | DIST: Abil | COUNTY: SCURRY, ETC.           | SHEET NO.: 43 |

DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
  2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE TRANSITION SECTIONS OF GUARDRAIL.
  3. BUTTON HEAD "POST" BOLTS (ASTM A307 GR.A) SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT (ASTM A563) AND 5/8" ROUND WASHER (ASTM F436) AND NOT MORE THAN 1" BEYOND IT. BUTTON HEAD "SPLICE" BOLTS (ASTM A307) ARE 5/8" X 1-1/4" WITH 5/8" NUTS (ASTM A563).
  4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
  5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  6. WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
  7. POSTS SHALL NOT BE SET IN CONCRETE.
  8. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
  9. REFER TO STANDARD GF(31) & APPLICABLE BRIDGE RAILING STANDARD FOR ADDITIONAL DETAILS.


\* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



DATE:  
FILE:

|   |            |                          |                      |
|---|------------|--------------------------|----------------------|
|   |            | Design Division Standard |                      |
| <b>METAL BEAM GUARD FENCE TRANSITION (T6)</b> |            |                          |                      |
| <b>GF(31)T6-19</b>                            |            |                          |                      |
| FILE: g1311619.dgn                            | DN: TxDOT  | CK: KM                   | DW: VP               |
| © TXDOT: NOVEMBER 2019                        | CONT: 6460 | SECT: 98                 | JOB: 001             |
| REVISIONS:                                    | DIST: Abi  |                          | COUNTY: SCURRY, ETC. |
|   |            |                          | SHEET NO.: 44        |


DISCLAIMER: THE USE OF THIS STANDARD IS COVERED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



**GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS**


Note: Site Condition(s)

Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments. Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




**PLAN**

GF(31) shown with Mow Strip (See GF(31) standard sheet for proper installation)



**SECTION A-A**


Typical



**MOW STRIP DETAIL**


Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBSG or GF(31) Transition Standard sheet for additional information.
  2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
  3. The leave-out behind the post shall be a minimum of 7".
  4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
  5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
  6. Thickness of the mow strip will be 4".
  7. The limits of payment for reinforced concrete will include leave-outs for the posts.
  8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




**CURB OPTION (1)**

This option will increase the post embedment throughout the system.



**CURB OPTION (2)**

Curb shown on top of mow strip






**CURB OPTION (3)**

|   |           |              |           |                                |
|---|-----------|--------------|-----------|--------------------------------|
|   |           |              |           | Design<br>Division<br>Standard |
| <b>METAL BEAM GUARD FENCE<br/>(MOW STRIP)<br/>TL-3 MASH COMPLIANT<br/>GF(31)MS-19</b> |           |              |           |                                |
| FILE: gf31ms19.dgn  | DN: TxDOT | CK: KM       | DW: VP    | CK: CGL/AG                     |
| © TxDOT: NOVEMBER 2019  | CONT      | SECT         | JOB       | HIGHWAY                        |
| REVISIONS   | 6460      | 98           | 001       | US 84, ETC.                    |
|   | DIST      | COUNTY       | SHEET NO. |                                |
|   | Abi       | SCURRY, ETC. | 45        |                                |

DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 18881323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: SoftStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL, PN:6202378
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - IT IS ACCEPTABLE TO INSTALL THE SoftStop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
  - DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

|        |   |
|--------|---|
| NOTE-A | THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.  |
| NOTE-B | PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)<br>PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)   |
| NOTE-C | W-BEAM SPLICE LOCATED BETWEEN LINE POST(4) AND LINE POST(5)<br>GUARDRAIL PANEL 25'-0" PN:61G<br>ANCHOR RAIL 25'-0" PN:15215G<br>LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW. |

| PART    | QTY | MAIN SYSTEM COMPONENTS                             |
|---------|-----|--|
| 6202378 | 1   | PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)  |
| 15208A  | 1   | SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH) |
| 15215G  | 1   | SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS      |
| 61G     | 1   | SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25'-0")    |
| 15205A  | 1   | POST #0 - ANCHOR POST (6'-5 1/8")                  |
| 15203G  | 1   | POST #1 - (SYTP) (4'-9 1/2")                       |
| 15000G  | 1   | POST #2 - (SYTP) (6'-0")                           |
| 533G    | 6   | POST #3 THRU #8 - I-BEAM (W6 x 8.5) (6'-0")        |
| 4076B   | 7   | BLOCKOUT - WOOD (ROUTED) (6" x 8" x 14")           |
| 6777B   | 7   | BLOCKOUT - COMPOSITE (4" x 7 1/2" x 14")           |
| 15204A  | 1   | ANCHOR PADDL                                       |
| 15207G  | 1   | ANCHOR KEEPER PLATE (24 GA)                        |
| 15206G  | 1   | ANCHOR PLATE WASHER (1/2" THICK)                   |
| 15201G  | 2   | ANCHOR POST ANGLE (10" LONG)                       |
| 15202G  | 1   | ANGLE STRUT  |

| HARDWARE |    |   |
|----------|----|---|
| 4902G    | 1  | 1" ROUND WASHER F436                            |
| 3908G    | 1  | 1" HEAVY HEX NUT A563 GR.DH                     |
| 3717G    | 2  | 3/4" x 2 1/2" HEX BOLT A325                     |
| 3701G    | 4  | 3/4" ROUND WASHER F436                          |
| 3704G    | 2  | 3/4" HEAVY HEX NUT A563 GR.DH                   |
| 3360G    | 16 | 5/8" x 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR      |
| 3340G    | 25 | 5/8" W-BEAM RAIL SPLICE NUTS HGR                |
| 3500G    | 7  | 3/8" x 10" HGR POST BOLT A307                   |
| 3391G    | 1  | 5/8" x 1 3/4" HEX HD BOLT A325                  |
| 4489G    | 1  | 3/8" x 9" HEX HD BOLT A325                      |
| 4372G    | 4  | 3/8" WASHER F436                                |
| 105285G  | 2  | 3/8" x 2 1/2" HEX HD BOLT GR-5                  |
| 105286G  | 1  | 3/8" x 1 1/2" HEX HD BOLT GR-5                  |
| 3240G    | 6  | 3/8" ROUND WASHER (WIDE)                        |
| 3245G    | 3  | 3/8" HEX NUT A563 GR.DH                         |
| 5852B    | 1  | HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE-B |

Design Division Standard

**TRINITY HIGHWAY  
SOFTSTOP END TERMINAL  
MASH - TL-3  
SGT(10S)31-16**


|                   |            |                      |              |             |
|-------------------|------------|----------------------|--------------|-------------|
| FILE: sgt10s3116  | DN: TxDOT  | CK: KM               | DW: VP       | CK: MB/VP   |
| ©TxDOT: JULY 2016 | CONT: 98   | SECT: JOB            | HIGHWAY      |             |
| REVISIONS         | 6460       | 98                   | 001          | US 84, ETC. |
|                   | DIST: Abil | COUNTY: SCURRY, ETC. | SHEET NO. 46 |             |

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.





DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: FILE:



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445. "GALVANIZING", FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
  - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN THEIR PLACE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

| ITEM                  | QTY | MAIN SYSTEM COMPONENTS                      | ITEM NUMBERS |
|-----------------------|-----|---|--------------|
| A                     | 1   | MSKT IMPACT HEAD                            | MS3000       |
| B                     | 1   | W-BEAM GUARDRAIL END SECTION, 12 Go.        | SF1303       |
| C                     | 1   | POST 1 - TOP (6" X 6" X 1/8" TUBE)          | MTPHP1A      |
| D                     | 1   | POST 1 - BOTTOM (6" W6X15)                  | MTPHP1B      |
| E                     | 1   | POST 2 - ASSEMBLY TOP                       | UHP2A        |
| F                     | 1   | POST 2 - ASSEMBLY BOTTOM (6" W6X9)          | HP2B         |
| G                     | 1   | BEARING PLATE                               | E750         |
| H                     | 1   | CABLE ANCHOR BOX                            | S760         |
| J                     | 1   | BCT CABLE ANCHOR ASSEMBLY                   | E770         |
| K                     | 1   | GROUND STRUT                                | MS785        |
| L                     | 6   | W6X9 OR W6X8.5 STEEL POST                   | P621         |
| M                     | 6   | COMPOSITE BLOCKOUTS                         | CBSP-14      |
| N                     | 1   | W-BEAM MGS RAIL SECTION (9'-4 1/2")         | G12025       |
| O                     | 2   | W-BEAM MGS RAIL SECTION (12'-6")            | G1203A       |
| P                     | 6   | WOOD BLOCKOUT 6" X 8" X 14"                 | P675         |
| Q                     | 1   | W-BEAM MGS RAIL SECTION (25'-0")            | G1209        |
| <b>SMALL HARDWARE</b> |     |   |              |
| o                     | 2   | 3/8" x 1" HEX BOLT (GRD 5)                  | B5160104A    |
| b                     | 4   | 3/8" WASHER                                 | W0516        |
| c                     | 2   | 3/8" HEX NUT                                | N0516        |
| d                     | 25  | 3/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)     | B580122      |
| e                     | 2   | 3/8" Dia. x 9" HEX BOLT (GRD A449)          | B580904A     |
| f                     | 3   | 3/8" WASHER                                 | W050         |
| g                     | 33  | 3/8" Dia. H.G.R. NUT                        | N050         |
| h                     | 1   | 3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)      | B340854A     |
| j                     | 1   | 3/4" Dia. HEX NUT                           | N030         |
| k                     | 2   | 1 ANCHOR CABLE HEX NUT                      | N100         |
| l                     | 2   | 1 ANCHOR CABLE WASHER                       | W100         |
| m                     | 8   | 1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER | S812A        |
| n                     | 8   | 1/2" STRUCTURAL NUTS                        | N012A        |
| o                     | 8   | 1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS  | W012A        |
| p                     | 1   | BEARING PLATE RETAINER TIE                  | CT-100ST     |
| q                     | 6   | 3/8" x 10" H.G.R. BOLT                      | B581002      |
| r                     | 1   | OBJECT MARKER 18" X 18"                     | E3151        |



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Texas Department of Transportation

Design Division Standard

## SINGLE GUARDRAIL TERMINAL


### MSKT-MASH-TL-3

### SGT(12S)31-18

|                      |           |              |           |             |
|----------------------|-----------|--------------|-----------|-------------|
| FILE: sgt12s3118.dgn | DN: TxDOT | CK: KM       | DW: VP    | CK: CL      |
| © TxDOT: APRIL 2018  | CONT SECT | JOB          | HIGHWAY   |             |
| REVISIONS            | 6460      | 98           | 001       | Us 84, ETC. |
|                      | DIST      | COUNTY       | SHEET NO. |             |
|                      | Abi       | SCURRY, ETC. |           | 48          |





DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



**GENERAL NOTES**

1. FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
2. FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
3. APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
4. FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
5. HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
6. IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, AND REFER TO THE LATEST ROADWAY MGF STANDARD FOR INSTALLATION GUIDANCE.
7. POSTS SHALL NOT BE SET IN CONCRETE.
8. THE EXISTING SKT 31" STANDARD STEEL POST SYSTEM MUST BE THOROUGHLY INSPECTED, AND DETERMINED TO BE INTACT, AND FREE OF ANY DAMAGE OR DEFECTS BEFORE RETROFITTING. THIS INSPECTION INCLUDES COMPLETING THE MSKT RETROFIT INSPECTION CHECKLIST FOR THE EXISTING SKT 31" STEEL POST NCHRP 350 SYSTEM. ALL EXISTING, AND REUSABLE PARTS MUST BE FREE OF ANY DAMAGE FOR A MASH COMPLIANT RETROFIT.
9. UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
10. A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
11. SPECIAL DRIVING CAP TO BE USED WHEN DRIVING (LOWER POSTS 1 & 2) TO PREVENT DAMAGE TO THE WELDED PLATES.



| ITEMS | QTY | MAIN SYSTEM COMPONENTS             | PART NUMBERS |
|-------|-----|------------------------------------|--------------|
| 1     | 1   | MSKT IMPACT HEAD                   | MS3000       |
| 2     | 1   | POST 1 - TOP (6" X 6" X 1/8" TUBE) | MTPHP1A      |
| 3     | 1   | POST 1 - BOTTOM (6" W6X15)         | MTPHP1B      |
| 4     | 1   | POST 2 - ASSEMBLY BOTTOM (6" W6X9) | HP2B         |
| 5     | 1   | GROUND STRUT                       | MS785        |
| 6     | 1   | 5/8" X 9" HEX BOLT (GRD A449)      | B580904A     |
| 7     | 2   | 5/8" WASHERS                       | W050         |
| 8     | 1   | 5/8" H.G.R NUT                     | N050         |
| 9     | 1   | CABLE TIE-STEEL                    | CT-100ST     |
| 10    | 1   | OBJECT MARKER 18" X 18"            | E3151        |

COMPONENTS REQUIRED TO RETROFIT: EXISTING 31" STEEL POST (NCHRP 350 SKT) GUARDRAIL TERMINAL WITH THE NEW 31" (MASH COMPLIANT MSKT IMPACT HEAD).  
 \* IF THE EXISTING NCHRP 350 (31" STEEL POST SKT) ALREADY HAS THE MSKT IMPACT HEAD THERE IS NO NEED TO REPLACE THE IMPACT HEAD OR OBJECT MARKER AS LONG AS IT IS NOT DAMAGED.

Texas Department of Transportation  
 Design Division Standard

**RETROFIT STANDARD  
 SKT 31" STEEL POST SYSTEM  
 TO MASH MSKT  
 SGT(13S)31-18**

|                      |           |              |           |             |
|----------------------|-----------|--------------|-----------|-------------|
| FILE: sgt13s3118.dgn | DN: TxDOT | CK: KM       | DW: VP    | CK: CL      |
| © TxDOT: APRIL 2018  | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS            | 6460      | 98           | 001       | US 84, ETC. |
|                      | DIST      | COUNTY       | SHEET NO. |             |
|                      | Abi       | SCURRY, ETC. | 49        |             |




NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE EXISTING SKT END TERMINAL RETROFIT TO THE MSKT MASH COMPLIANT TERMINAL. IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DATE:  
FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

**GENERAL NOTES**

1. FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
2. FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO: MSKT END TERMINAL. PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
3. APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
4. FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
5. HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
6. IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, AND REFER TO THE LATEST ROADWAY MBSG STANDARD FOR INSTALLATION GUIDANCE.
7. POSTS SHALL NOT BE SET IN CONCRETE.
8. THE EXISTING SKT 31" STANDARD WOOD POST SYSTEM MUST BE THOROUGHLY INSPECTED, AND DETERMINED TO BE INTACT, AND FREE OF ANY DAMAGE OR DEFECTS BEFORE RETROFITTING. THIS INSPECTION INCLUDES COMPLETING THE MSKT RETROFIT INSPECTION CHECKLIST FOR THE EXISTING SKT 31" WOOD POST NCHRP 350 SYSTEM. ALL EXISTING, AND REUSABLE PARTS MUST BE FREE OF ANY DAMAGE FOR A MASH COMPLIANT RETROFIT.
9. UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
10. A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
11. SPECIAL DRIVING CAP TO BE USED WHEN DRIVING (LOWER POSTS 1 & 2) TO PREVENT DAMAGE TO THE WELDED PLATES.



| ITEMS | QTY | MAIN SYSTEM COMPONENTS             | PART NUMBERS |
|-------|-----|------------------------------------|--------------|
| 1     | 1   | MSKT IMPACT HEAD                   | MS3000       |
| 2     | 1   | POST 1 - TOP (6" X 6" X 1/8" TUBE) | MTPHP1A      |
| 3     | 1   | POST 1 - BOTTOM (6" W6X15)         | MTPHP1B      |
| 4     | 1   | POST 2 - ASSEMBLY TOP              | UHP2A        |
| 5     | 1   | POST 2 - ASSEMBLY BOTTOM (6" W6X9) | HP2B         |
| 6     | 1   | GROUND STRUT                       | MS785        |
| 7     | 2   | 5/16" X 1" HEX BOLT (GRD 5)        | B516014A     |
| 8     | 4   | 5/16" WASHERS                      | W0516        |
| 9     | 2   | 5/16" HEX NUT                      | N0516        |
| 10    | 2   | 5/8" X 9" HEX BOLT (GRD A449)      | B580904A     |
| 11    | 3   | 5/8" WASHERS                       | W050         |
| 12    | 3   | 5/8" H.G.R NUT                     | N050         |
| 13    | 1   | 5/8" X 1 1/4" SPLICE BOLT          | B580122      |
| 14    | 1   | 3/4" X 8 1/2" HEX BOLT (GRD 5)     | B340854A     |
| 15    | 1   | 3/4" HEX NUT                       | N030         |
| 16    | 1   | CABLE TIE-STEEL                    | CT-100ST     |
| 17    | 1   | OBJECT MARKER 18" X 18"            | E3151        |





**RETROFIT STANDARD  
SKT 31" WOOD POST SYSTEM  
TO MASH MSKT  
SGT(14W)31-18**

|                      |            |                      |              |                      |
|----------------------|------------|----------------------|--------------|----------------------|
| FILE: sgt14w3118.dgn | DN: TxDOT  | CK: KM               | DW: VP       | CK: CL               |
| © TxDOT: APRIL 2018  | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US 84, ETC. |
| REVISIONS            | DIST: Abi  | COUNTY: SCURRY, ETC. | SHEET NO. 50 |                      |


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE EXISTING SKT END TERMINAL RETROFITTED TO THE MSKT MASH COMPLIANT TERMINAL. IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DATE: FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



| ANCHOR POST 1 FABRICATION DETAILS |              |
|-----------------------------------|--------------|
| SHEET DESCRIPTION                 | SHEET NUMBER |
| ANCHOR POST                       | SHEET 1 OF 8 |
| ANCHOR SLEEVE                     | SHEET 2 OF 8 |
| RADIUS RAIL                       | SHEET 3 OF 8 |
| THRIE-BEAM RAILS                  | SHEET 4 OF 8 |
| BCT TIMBER POST                   | SHEET 5 OF 8 |
| STRUT RADIUS ANCHOR               | SHEET 6 OF 8 |
| FOUNDATION TUBE                   | SHEET 7 OF 8 |
| ANCHOR CABLE                      | SHEET 8 OF 8 |



(MASH TL-3 COMPLIANT)  
TESTED TO MASH TL-3 WITH A 3:1 SLOPE











SHEET 1 OF 3

Texas Department of Transportation  
Design Division Standard

**TL-3  
SHORT RADIUS GUARDRAIL  
MASH COMPLIANT  
SRG(TL-3)-21**

|                        |       |              |           |             |
|------------------------|-------|--------------|-----------|-------------|
| FILE: srgtl321         | TxDOT | CK:KM        | DN:VP     | CK:CGL      |
| © TxDOT: FEBRUARY 2021 | CONT  | SECT         | JOB       | HIGHWAY     |
| REVISIONS              | 8460  | 98           | 001       | US 84, ETC. |
|                        | DIST  | COUNTY       | SHEET NO. |             |
|                        | Abi   | SCURRY, ETC. | 51        |             |

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



(MASH TL-3 COMPLIANT)  
TESTED TO MASH TL-3 WITH A 3:1 SLOPE

SHEET 2 OF 3

|  |          |                          |           |
|--|----------|--------------------------|-----------|
|  |          | Design Division Standard |           |
| <b>TL-3<br/>SHORT RADIUS GUARDRAIL<br/>MASH COMPLIANT<br/>SRG(TL-3)-21</b> |          |                          |           |
| FILE: srgtl321   | TxDOT    | CK:KM                    | DN:VP     |
| © TxDOT: FEBRUARY 2021   | CONTRACT | SECTION                  | JOB       |
| REVISIONS  | 6460     | 98                       | 001       |
|  | DIST     | COUNTY                   | SHEET NO. |
|  | Abi      | SCURRY, ETC.             | 52        |

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE:  
FILE:

| ITEM | ALL LARGE & SMALL COMPONENT DESCRIPTIONS                         |
|------|--|
| A    | POST 1 TOP (SCH.80 PIPE) (8" X 80" LENGTH)                       |
| B    | POST 1 TOP (WELDED SUPPORT COLLAR 10" X 10" X 1/2" ASTM A36)     |
| C    | POST 1 TUBE (HSS 10" X 10" X 1/2" X 72" LENGTH) A500 GR.B        |
| D    | POST 1 (WELDED PLATE 9 1/4" X 9 1/4" X 1/8") A36                 |
| E    | POST 1 STRUT BRACKET (C8 X 11.50 A36)                            |
| F    | (POST 1 & 2) CHANNEL STRUTS (4" X 7 1/2" X 1/4") (C4 X 7.25) A36 |
| G    | THRIE-BEAM RAIL (END ANCHOR - ROUNDED TYPE) 12GA. (RTE02a)       |
| H    | THRIE-BEAM RAIL (ANCHOR) (6'-3" LENGTH) 12GA. (RWM14a)           |
| I    | THRIE-BEAM RAIL (8 SPACE) (12'-6" LENGTH) 12GA. (RTM08)          |
| J    | THRIE-BEAM RAIL (RADIUS 8'-4 1/2") (SLOTTED) 12GA.               |
| K    | THRIE-BEAM RAIL (3 SPACE) (9'-4 1/2" LENGTH) 12GA.               |
| L    | THRIE BEAM RAIL (TERMINAL CONNECTOR) (BRIDGE-RAIL) (RTE01b)      |
| M    | POST 2,4,5,6 BCT TIMBER (5 1/2" X 7 1/2" X 46") (PDF04)          |
| N    | POST 2,4, BCT TUBE (6" X 8" X 3/16" X 72" LENGTH) (PTE05)        |
| O    | POST 5,6 MODIFIED BCT TUBES (FOR WELDED CABLE SADDLES)           |
| P    | POST 3,4,6,7,8 THRIE-BEAM BLOCK-OUT (6" X 8" X 22") (PDB02a)     |
| Q    | POST 3,7,8 CRT TIMBER POSTS (6" X 8" X 72" LENGTH) (PDE09)       |
| R    | POST 9,10,11-BEAM POSTS (W6X8.5 X 72" LENGTH) (PWE01)            |
| S    | POST 9,10,11 ROUTED W-BEAM BLOCK-OUT (6" X 8" X 14") (PDB01b)    |
| T    | POST 12 THRU 17 I-BEAM POSTS (W6X8.5 X 84" LENGTH) (PWE07)       |
| U    | POST 12 THRU 17 ROUTED BLOCK-OUT (6" X 8" X 18") (PDB??)         |
| V    | SAND BARRELS 700-715 LBS   |
| A1   | BCT CABLE ANCHOR ASSEMBLIES (3/4" X 6'-6 3/4" LENGTH) (FCA01)    |
| A2   | BCT CABLE ANCHOR BRACKET (FPA01)                                 |
| A3   | 5/8" X 2" HEX BOLT A307 GRD.5 (FOR CABLE BRACKETS)               |
| A4   | 5/8" FLAT WASHER A307 GRD.5 (1 WASHER UNDER BOLT HEAD & 1 NUT)   |
| A5   | 5/8" RECESSED H.G.R NUT (NUTS FOR HEX BOLTS)                     |
| A6   | STRUT BRACKET HARDWARE (1/2" X 1 1/2") HEX BOLT A307 GRD.5       |
| A7   | CHANNEL STRUT HARDWARE (5/8" X 10") HEX BOLT A307 GRD.5          |
| A8   | BCT CABLE ANCHOR ASSEMBLY (FCA02) (3/4" X 18'-5" LENGTH)         |
| A9   | BCT POST SLEEVE (FMM02a) (POST 4 ONLY)                           |
| A10  | BCT CABLE BEARING PLATE (5/8" X 8" X 8" (FPB01) (POST 4 ONLY)    |
| A11  | 5/8" X 1 1/4" H.G.R. BOLTS (FBB01) (SPICES AT POST 2,4,6,7)      |
| A12  | 5/8" X 2" H.G.R. BOLTS (FBB02) (ROUND TERM-POST 10-END SPLICE)   |
| A13  | 5/8" X 10" H.G.R. BOLTS (FBB03) (I-BEAM POSTS RAIL & BLOCKOUT)   |
| A14  | 5/8" X 18" H.G.R. BOLTS (FBB04) (POSTS 3,4,6,7,8)                |
| A15  | 5/8" X 7 1/2" HEX BOLTS A307 GRD.5 (BCT POSTS 2,4,5,6)           |
| A16  | 5/8" X 10" HEX BOLTS A307 GRD.5 (BCT POSTS 2,4,5,6)              |
| A17  | RECTANGULAR WASHERS (FWR03) (FOR TERMINAL CONNECTOR RTE01b)      |
| A18  | 7/8" X (LENGTH VARIES) HEX BOLTS A325 OR A449 GR.5               |
| A19  | 1 3/4" O.D. HARDENED FLAT WASHER A325                            |
| A20  | 7/8" HEX NUT GR.5 A325   |

| END ANCHOR<br>(POST 1 & POST 2) |     |
|---------------------------------|-----|
| ITEM                            | QTY |
| A                               | 1   |
| B                               | 1   |
| C                               | 1   |
| D                               | 1   |
| E                               | 1   |
| F                               | 2   |
| G                               | 1   |
| H                               | 1   |
| A1                              | 2   |
| A2                              | 2   |
| A3                              | 18  |
| A4                              | 36  |
| A5                              | 22  |
| A6                              | 2   |
| A7                              | 2   |
| A12                             | 4   |

| TL-3 SHORT RADIUS<br>(POST 2 TO POST 7) |     |
|---|-----|
| ITEM                                    | QTY |
| H                                       | 1   |
| I                                       | 1   |
| J                                       | 1   |
| M                                       | 4   |
| N                                       | 2   |
| O                                       | 2   |
| P                                       | 4   |
| Q                                       | 2   |
| A8                                      | 1   |
| A9                                      | 1   |
| A10                                     | 1   |
| A11                                     | 48  |
| A14                                     | 8   |
| A15                                     | 8   |
| A16                                     | 4   |

| TL-3 TRANSITION<br>(POST 7 TO POST 17) |     |
|--|-----|
| ITEM                                   | QTY |
| I                                      | 2   |
| K                                      | 1   |
| L                                      | 1   |
| P                                      | 1   |
| Q                                      | 1   |
| R                                      | 3   |
| S                                      | 3   |
| T                                      | 6   |
| U                                      | 6   |
| A12                                    | 24  |
| A13                                    | 18  |
| A14                                    | 2   |
| A17                                    | 12  |
| A18                                    | 5   |
| A19                                    | 10  |
| A20                                    | 5   |

| TL-3 SHORT RADIUS GUARDRAIL<br>COMPLETE SYSTEM |           |
|--|-----------|
| ITEM   | TOTAL QTY |
| A  | 1         |
| B  | 1         |
| C  | 1         |
| D  | 1         |
| E  | 1         |
| F  | 2         |
| G  | 1         |
| H  | 2         |
| I  | 3         |
| J  | 1         |
| K  | 1         |
| L  | 1         |
| M  | 4         |
| N  | 2         |
| O  | 2         |
| P  | 5         |
| Q  | 3         |
| R  | 3         |
| S  | 3         |
| T  | 6         |
| U  | 6         |
| V  | 6         |
| A1   | 2         |
| A2   | 3         |
| A3   | 26        |
| A4   | 76        |
| A5   | 42        |
| A6   | 2         |
| A7   | 2         |
| A8   | 1         |
| A9   | 1         |
| A10  | 1         |
| A11  | 48        |
| A12  | 28        |
| A13  | 18        |
| A14  | 10        |
| A15  | 8         |
| A16  | 4         |
| A17  | 12        |
| A18  | 5         |
| A19  | 10        |
| A20  | 5         |


- GENERAL NOTES**
- FOR ADDITIONAL INSTALLATION INFORMATION AND GUIDANCE CONTACT: TEXAS DEPARTMENT OF TRANSPORTATION, (TXDOT'S DESIGN DIVISION), (512) 416-2678. THE EXACT POSITION OF MBGF SHALL BE SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER. THE SIGHT DISTANCE OF THE INSTALLATION WILL NEED TO BE VERIFIED WITH RESPECT TO THE SPECIFIC SITE PLACEMENT.
  - STEEL POSTS ARE NOT PERMITTED AT CRT OR BCT POST POSITIONS.
  - RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 12 1/2" OR 25 FOOT NOMINAL LENGTHS.
  - BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16a) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
  - FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  - THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A SLOPE RATE OF NOT MORE THAN 1V:10H.
  - IT IS NOT RECOMMENDED THAT GUARD FENCE BE PLACED IN THE VICINITY OF CURBS.
  - GUARDRAIL POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
  - SPECIAL FABRICATION WILL BE REQUIRED FOR THRIE BEAM RAIL RADIUS (ITEM J).
  - ALL MATERIAL AND WORK INVOLVED IS SUBSIDIARY TO SHORT RADIUS BID ITEM, INCLUDING, BUT NOT LIMITED TO FOUNDATIONS, GRADING, THRIE BEAM RAIL, SAND BARRELS, AND OTHER PARTS.
  - ALL CABLE ASSEMBLIES SHOULD BE TAUT AFTER INSTALLATION. WHEN CABLES ARE MANIPULATED BY HAND THE CABLES SHOULD NOT MOVE MORE THAN 1" IN ANY DIRECTION PERPENDICULAR TO THE CABLE.
  - THE BCT BEARING PLATE INSTALLED AT POST 4 SHOULD BE ORIENTED SUCH THAT THE 3" DIMENSION FROM PLATE EDGE TO CENTER OF BOLT HOLE IS ON THE BOTTOM AND 5" DIMENSION FROM PLATE EDGE TO CENTER OF BOLT HOLE IS ON THE TOP.
  - FOUNDATION AT POST 1 SHALL BE CLASS C CONCRETE.
  - POST (1) IS NOT A CRASHWORTHY TERMINAL. THE DESIGN AND PLACEMENT OF POST (1) MUST BE OUTSIDE OF THE CLEAR ZONE OF THE SECONDARY ROADWAY USING THE RESPECTIVE CLEAR ZONE CRITERIA. PLEASE CONTACT THE DESIGN DIVISION (512) 416-2678 FOR ASSISTANCE IN DETERMINING THE APPROPRIATE USE AND/OR PLACEMENT OF THE SYSTEM IN CONSTRAINED LOCATIONS. THE PAYMENT OF THE COMPLETE SYSTEM WILL BE WITH BID ITEMS: 540 XXXX TL-3 31" SHORT RADIUS (COMPLETE).
  - TESTED TO MASH WITH A 3:1 SLOPE OR SHALLOWER IS PREFERABLE IN THE LIMITS OF THE TOP AND BOTTOM OF THE SLOPE AS SHOWN IN THE PLAN VIEW. IF FIELD CONDITIONS REQUIRE A STEEPER SLOPE, THIS MAY BE ALLOWABLE UP TO A 2:1 SLOPE. CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE.
  - THE BARRELS ARE ENERGY ABSORPTION ENERGITE III, MODEL 640 FILLED WITH 715 LB (-/-15) SAND; OR AN APPROVED EQUIVALENT. THE APPROXIMATE HEIGHT OF THE BARREL IS 41" (-/-).
  - ALTERNATE METHODS TO TERMINATE THE SRG ALONG THE PRIMARY ROADWAY ARE AVAILABLE WHEN SITE CONDITIONS DICTATE. CONTACT DESIGN DIVISION FOR DETAILS: 512 416-2678
- NOTE: SEE SHEET 1 OF 3.

**SPECIAL APPLICATION NOTES.**


- THIS IS A MASH COMPLIANT TL-3 SHORT RADIUS GUARDRAIL SYSTEM WITH A TOP RAIL HEIGHT OF 31". AVAILABLE FOR USE ON ANY SPEED ROADWAY. THE SYSTEM REQUIRES A MINIMUM PLACEMENT FOOTPRINT OF 34'-10" ALONG THE PRIMARY ROAD AND A 35'-0" ALONG SECONDARY DRIVEWAY.
  - IT IS CRITICAL THAT THE PRIMARY GUARDRAIL MAINTAIN A (4 DEGREE FLARE) WITH THE SECONDARY DRIVEWAY.
  - THE SYSTEM REQUIRES A MINIMUM 5' WIDE (WORK ZONE) DIRECTLY BEHIND THE GUARDRAIL SYSTEM WITH A SLOPE AT 1V:10H OR FLATTER FROM THERE A MAXIMUM 3:1 SLOPE IS RECOMMENDED. SEE SHEET 1 OF 3 FOR FLARE AND SLOPE DETAILS.
  - NOTE FOR INSTALLER: THE THREE (3) CRT POSTS ITEM (Q), AT POST LOCATIONS, 3, 7, & 8.), REQUIRE THE FOLLOWING FIELD ADJUSTMENT. USING A 3/4" X 10" LONG SPADE BIT DRILL ONE (1) ADDITIONAL HOLE 7-7/8" DIRECTLY BELOW THE EXISTING TOP HOLE TO ACCOMMODATE THE HARDWARE FOR THE 22" LONG BLOCKOUT.
- OPTION FOR ADDITIONAL 3/4" HOLE. THE 22" LONG BLOCKOUT (PDB01a) IS MANUFACTURED WITH TWO 3/4" DRILLED HOLES FOR THE POST HARDWARE, THEREFORE THE BLOCKOUT CAN BE USED AS A TEMPLATE GUIDE FOR THE BOTTOM 3/4" HOLE. AFTER INSTALLING THE CRT POST USE THE TOP HOLE TO MOUNT THE 22" LONG BLOCKOUT TO POST, USE THE BLOCKOUT'S PRE-DRILLED HOLE AS A GUIDE FOR THE BOTTOM 3/4" HOLE.

**(MASH TL-3 COMPLIANT)  
TESTED TO MASH TL-3 WITH A 3:1 SLOPE**


SHEET 3 OF 3

|   |              |                                |
|---|--------------|--------------------------------|
| <br>Texas Department of Transportation   |              | Design<br>Division<br>Standard |
| <h2 style="margin: 0;">TL-3</h2> <h3 style="margin: 0;">SHORT RADIUS GUARDRAIL</h3> <h3 style="margin: 0;">MASH COMPLIANT</h3> <h2 style="margin: 0;">SRG(TL-3)-21</h2> |              |                                |
| FILE: srgtl321  | TxDOT        | CK:KM DN: VP CK: CGL           |
| © TXDOT: FEBRUARY 2021  | CONT SECT    | JOB HIGHWAY                    |
| REVISIONS   | 6460 98      | 001 US 84, ETC.                |
| DIST  | COUNTY       | SHEET NO.                      |
| Abi   | SCURRY, ETC. | 53                             |

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



\* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
  2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE TRANSITION SECTIONS OF GUARDRAIL.
  3. BUTTON HEAD "POST" BOLTS (ASTM A307) SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT (ASTM A563) AND 5/8" ROUND WASHER (ASTM F436) AND NOT MORE THAN 1" BEYOND IT. BUTTON HEAD "SPlice" BOLTS (ASTM A307) ARE 5/8" X 1-1/4" WITH 5/8" NUTS (ASTM A563).
  4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
  5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
  6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
  7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
  8. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. SEE GF(31) STANDARD FOR INSTALLATION GUIDANCE.
  9. POSTS SHALL NOT BE SET IN CONCRETE.
  10. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
  11. REFER TO STANDARD GF(31) FOR ADDITIONAL DETAILS.
  12. RAIL HEIGHT ADJUSTMENT IS ASSESSED AT TL-3 MASH COMPLIANT FOR STEEL POST HEIGHT TRANSITION TO 28" STEEL POST GUARDRAIL.

| HARDWARE LIST |  |
|---------------|--|
| QTY           | DESCRIPTION  |
| 1             | 25'-0" W-BEAM RAIL ELEMENT 12GA. (TYP)   |
| 5             | 7 1/2" DIA X 6'-0" DOMED ROUND WOOD POSTS (TYP)                                    |
| 5             | 6" X 8" X 68" RECTANGULAR WOOD POSTS (TYP)   |
| 5             | W6 X 8.5 OR W6 X 9 X 72" STEEL POSTS (TYP)   |
| 5             | 6" X 8" X 14" WOOD BLOCKS OR COMPOSITE (TYP)                                       |
| 5             | 5/8" X 18" GUARDRAIL BOLTS AND NUTS (FBB04)  |
| 5             | 5/8" ROUND WASHERS (ASTM F436)(FWC16a)   |
| 5             | 5/8" X 10" GUARDRAIL BOLTS AND NUTS (FBB03)  |
| 16            | 5/8" X 1-1/4" GUARDRAIL SPLICE BOLTS WITH DOUBLE RECESSED NUTS (ASTM A563) (FBB01) |

POST AND BLOCK-OUT TYPES AVAILABLE

FOR WOOD POST

FOR STEEL POST

NOTE: HARDWARE SHALL MEET THE FOLLOWING REQUIREMENTS.

GUARDRAIL POST BOLTS (ASTM A307 GR.A)  
GUARDRAIL ROUND WASHERS (ASTM F436)  
GUARDRAIL DOUBLE RECESSED NUTS (ASTM A563)  
GUARDRAIL SPLICE BOLTS (ASTM A307 GR.A)  
GUARDRAIL SPLICE NUTS (ASTM A563)

Texas Department of Transportation  
Design Division Standard



**METAL BEAM GUARD FENCE  
RAIL HEIGHT ADJUSTMENT  
(28" TO 31")  
TL-3 MASH COMPLIANT  
RAIL-ADJ(B)-19**

|                       |           |              |        |             |
|-----------------------|-----------|--------------|--------|-------------|
| FILE: railadjb19      | DN: TxDOT | CK: KM       | DW: VP | CK: CGL/AG  |
| ©TxDOT- NOVEMBER 2019 | CONT      | SECT         | JOB    | HIGHWAY     |
| REVISIONS             | 6460      | 98           | 001    | US 84, ETC. |
|                       | DIST      | COUNTY       |        | SHEET NO.   |
|                       | Abi       | SCURRY, ETC. |        | 54          |

DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:



| ROPE TENSION TABLE |               |              |
|--------------------|---------------|--------------|
| ROPE TEMP (°F)     | TENSION (LBS) | TENSION (kN) |
| 0                  | 5700          | 25.4         |
| 5                  | 5550          | 24.7         |
| 10                 | 5400          | 24.0         |
| 15                 | 5250          | 23.4         |
| 20                 | 5100          | 22.7         |
| 25                 | 4950          | 22.0         |
| 30                 | 4800          | 21.4         |
| 35                 | 4650          | 20.74        |
| 40                 | 4500          | 20.0         |
| 45                 | 4350          | 19.3         |
| 50                 | 4200          | 18.7         |
| 55                 | 4050          | 18.0         |
| 60                 | 3900          | 17.3         |
| 65                 | 3750          | 16.7         |
| 70                 | 3600          | 16.0         |
| 75                 | 3450          | 15.3         |
| 80                 | 3300          | 14.7         |
| 85                 | 3150          | 14.0         |
| 90                 | 3000          | 13.3         |
| 95                 | 2850          | 12.7         |
| 100                | 2700          | 12.0         |
| 105                | 2550          | 11.3         |
| 110                | 2400          | 10.7         |
| 115                | 2250          | 10.0         |
| 120                | 2100          | 9.3          |
| 125                | 1950          | 8.7          |
| 130                | 1800          | 8.0          |
| 135                | 1650          | 7.3          |
| 140                | 1500          | 6.7          |

**GENERAL NOTES:**

- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. AT 1-866-427-4336.
- THE BRIFEN WRSF HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-4 CONDITIONS ON SLOPES 6:1 OR FLATTER AND NCHRP 350 TL-3 CONDITIONS ON SLOPES 4:1 TO 6:1.
- THE POST SPACING SHALL BE DETERMINED BY THE SPECIFYING AGENCY. POST SPACING MAY BE DECREASED TO AVOID OBSTRUCTIONS OR UTILITIES. IN NO EVENT SHALL THE POST SPACING EXCEED 21'-0".
- BRIFEN WRSF SHALL BE PLACED ON A SMOOTH SURFACE, WITHOUT HUMPS, DROP-OFFS, HOLES, ETC THAT WOULD INTERFERE WITH THE STABILITY OF THE ERRANT VEHICLE. GRADING, FILL AND COMPACT MAY BE REQUIRED TO ASSURE THAT ROPES ARE INSTALLED AT THE DESIGN HEIGHT.
- THE WRGT-FL END ANCHOR HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-3 CONDITIONS. THE LENGTH OF NEED BEGINS 31'-0" FROM THE END ANCHOR. POSTS A THROUGH POST B3, SPACED 6'-6" APART, HAVE WEAKENED CUTS AT THE GROUND THAT SHALL FACE THE ANCHOR.
- ANCHOR AND LINE POST DIMENSIONS AND STEEL REINFORCEMENT WILL BE DETERMINED ON PROJECT SPECIFIC SOIL CLASSIFICATION, PROPERTIES AND TEMPERATURE EXTREMES. CONTACT BRIFEN USA, INC. FOR ADDITIONAL INFORMATION.
- ALL REINFORCEMENT AND CONCRETE FOR THE ANCHORS AND LINE POSTS PROVIDED BY OTHERS.
- REINFORCEMENT AND CONCRETE PROPERTIES SHALL MEET AGENCY SPECIFICATIONS.
- FOR PLACEMENT NEAR GUARDRAIL OR OTHER OBSTACLES CONTACT BRIFEN USA, INC. FOR ADDITIONAL DRAWINGS AND SUPPORT.
- TAPER RATES FOR THE BRIFEN WRSF ARE AS FOLLOWS:  
HORIZONTAL: 25:1 MAXIMUM, 50:1 PREFERABLE  
VERTICAL: 25:1 MAXIMUM, 50:1 PREFERABLE

\*ROPE TENSION: ± 20% AFTER 2-WEEK INTERVAL

SHEET 1 OF 3






**BRIFEN  
WIRE ROPE SAFETY FENCE  
(TL-4)**

**BRIFEN(TL4)-14**

|                     |           |              |        |             |
|---------------------|-----------|--------------|--------|-------------|
| FILE: brifentl4.dgn | DN: TxDOT | CK: RM       | DW: VP | CK:         |
| ©TxDOT: MARCH 2014  | CONT      | SECT         | JOB    | HIGHWAY     |
| REVISIONS           | 6460      | 98           | 001    | US 84, ETC. |
|                     | DIST      | COUNTY       |        | SHEET NO.   |
|                     | Abi       | SCURRY, ETC. |        | 55          |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




- GENERAL NOTES:**
1. BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. 1-866-427-4336.
  2. THE BRIFEN WRSF HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-4 CONDITIONS ON SLOPES 6:1 OR FLATTER AND NCHRP 350 TL-3 CONDITIONS ON SLOPES 4:1 TO 6:1.
  3. THE POST SPACING SHALL BE DETERMINED BY THE SPECIFYING AGENCY. POST SPACING MAY BE DECREASED TO AVOID OBSTRUCTIONS OR UTILITIES. IN NO EVENT SHALL THE POST SPACING EXCEED 21'-0".
  4. BRIFEN WRSF SHALL BE PLACED ON A SMOOTH SURFACE, WITHOUT HUMPS, DROP-OFFS, HOLES, ETC THAT WOULD INTERFERE WITH THE STABILITY OF THE ERRANT VEHICLE. GRADING, FILL AND COMPACTION MAY BE REQUIRED TO ASSURE THAT ROPES ARE INSTALLED AT THE DESIGN HEIGHT.

|   |            |                          |                      |
|---|------------|--------------------------|----------------------|
|   |            | Design Division Standard |                      |
| <h2 style="margin: 0;">BRIFEN</h2> <h3 style="margin: 0;">WIRE ROPE SAFETY FENCE</h3> <p style="margin: 0;">(TL-4)</p> <h2 style="margin: 0;">BRIFEN(TL4)-14</h2> |            |                          |                      |
| FILE: brifentl414.dgn   | DN: TxDOT  | CK: RM                   | DW: VP               |
| © TxDOT: MARCH 2014   | CONT: 6460 | SECT: 98                 | JOB: 001             |
| REVISIONS   | DIST: Abi  | COUNTY: SCURRY, ETC.     | HIGHWAY: US B4, ETC. |
|   |            |                          | SHEET NO.: 56        |

DATE: FILE:




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**GENERAL NOTES:**

- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. AT 1-866-427-4336.
- THE WRGT-FL END ANCHOR HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-3 CONDITIONS. THE LENGTH OF NEED BEGINS 31'-0" FROM THE END ANCHOR. POSTS A THROUGH POST B3, SPACED 6'-6" APART, HAVE WEAKENED CUTS AT THE GROUND THAT SHALL FACE THE ANCHOR.
- ANCHOR AND LINE POST DIMENSIONS AND STEEL REINFORCEMENT WILL BE DETERMINED ON PROJECT SPECIFIC SOIL CLASSIFICATION, PROPERTIES AND TEMPERATURE EXTREMES. CONTACT BRIFEN USA, INC. FOR ADDITIONAL INFORMATION.
- ALL REINFORCEMENT AND CONCRETE FOR THE ANCHORS AND LINE POSTS PROVIDED BY OTHERS.
- REINFORCEMENT AND CONCRETE PROPERTIES SHALL MEET AGENCY SPECIFICATIONS.
- FOR PLACEMENT NEAR GUARDRAIL OR OTHER OBSTACLES CONTACT BRIFEN USA, INC. FOR ADDITIONAL DRAWINGS AND SUPPORT.


**WRGT-FL POST DETAILS**



**NOTES SPECIFIC TO WRGT-FL POST DETAIL**

- ROPE HEIGHTS SHALL BE  $\pm 1"$  TO GROUND LINE.
- POST SHALL BE  $\pm 4"$  FROM VERTICAL PLUMB.
- POST CAPS SHALL BE USED IF SPECIFIED.
- REFLECTORS SHALL BE SPACED ACCORDING TO AGENCY SPECIFICATIONS.
- REFLECTORS CAN BE PLACED ON THE POST CAP OR POST.
- Z EXCLUDER (Z41) SHALL BE USED.
- POST A & SOCKET SHALL BE PLACED  $79^\circ (\pm 4^\circ)$  TOWARD END ANCHOR FROM THE HORIZONTAL PLANE.
- POST A SOCKET SHALL BE PLACED IN 14" (MIN) CONCRETE FOUNDATION. DEPTH TO BE DETERMINED FROM SOIL CONDITIONS AND PROJECT CONDITIONS.
- FOUNDATIONS FOR POST 2 THRU 4 SHALL BE THE SAME AS THE LINE POST ASSEMBLY'S FOR THE PROJECT.
- WEAKENED CUTS SHALL FACE END ANCHOR.


**END ANCHOR DETAILS**



**NOTES SPECIFIC TO END ANCHOR DETAIL**

- THE END ANCHOR ASSEMBLY SHALL BE PLACED 12" (+3", -1") BELOW HORIZONTAL PLANE.
- POST 1 & SOCKET SHALL BE PLACED  $79^\circ (\pm 4^\circ)$  TOWARD END ANCHOR FROM THE HORIZONTAL PLANE.
- POST 1 SOCKET SHALL BE PLACED IN 14" (MIN) CONCRETE FOUNDATION. DEPTH TO BE DETERMINED FROM SOIL CONDITIONS AND PROJECT CONDITIONS.

**END ANCHOR COMPONENTS**



SHEET 3 OF 3



**BRIFEN  
WIRE ROPE SAFETY FENCE  
(TL-4)**


**BRIFEN(TL4)-14**

|                     |           |              |           |             |
|---------------------|-----------|--------------|-----------|-------------|
| FILE: brifentl4.dgn | DN: TxDOT | CK: RM       | DW: VP    | CK:         |
| © TxDOT: MARCH 2014 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS           | 6460      | 98           | 001       | US 84, ETC. |
|                     | DIST      | COUNTY       | SHEET NO. |             |
|                     | Abi       | SCURRY, ETC. | 57        |             |


DATE:  
FILE:

Preferred Installation: Locate post #2 away from nearest traffic.  
System has been successfully tested with opposite installation.









Length-of-Need Cass Cable Terminal (CCT):  
Departure Installation: Length-of-Need: 44'-9" (At Post #8)  
Approach Installation: Length-of-Need: 19'-9" (12" Post Post #4)



PLAN VIEW



ELEVATION VIEW  
(TYPICAL LAY-OUT)



GENERAL NOTES

- This drawing is a general overview of CASS TL-4 Barrier System. See SS-740 (latest version) for specific details of CASS cable terminal (CCT) and cable safety system (CASS) requirements, proper installation, options and specification.
- CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity (800-527-6050) or consult the design, installation, or repair manual(s) for additional information.
- All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
- All posts shall be socketed unless otherwise specified. All cables shall be pre-stretched unless otherwise specified.
- For payment see Special Specification "Cable Barrier System".
- CASS-TL4 shall be installed on shoulders or medians with slopes of 6:1 or flatter without obstructions, depressions, etc. That may significantly affect the stability of an errant vehicle. Grading of site and/or appropriate fill materials may be required. The designer/installer shall "Flatten" or "Round" various topographical inconsistencies that could interfere with the ability of the installer to consistently maintain the design height (in relation to the terrain) of the cables. Please consult manual(s) and / or TxDOT Memo(s) for installations in "Ditch Sections".
- CASS TL-4 post spacing may be modified to avoid obstacles that conflict with the installation of coss-tl4 line posts or to reduce deflection on radiuses. No post space can exceed the maximum post TxDOT space limit of 20'. Reducing or increasing post spacing affects deflection. CASS TL-4 may be laterally transferred at a rate not to exceed 30:1.
- Post foundations may be drilled through existing pavement. Please see line post foundation chart for minimum footing requirements in various applications.
- For aesthetic purposes Trinity recommends all sleeves, driven posts, and lower cable release posts to be installed reasonably plumb (approximately 1/8" per foot).
- CASS TL-4 shall be installed in well-drained, compacted, NCHRP Report 350 Standard soil. If soil does not meet this classification, if solid rock/concrete is encountered below grade or if soil is susceptible to severe freeze/thaw cycles, please contact Trinity about alternate footing design(s). Trinity suggests the use of "Mow strips" for erosion prevention and ease of maintenance / installation.
- See the Texas MUTCD for proper "Barrier" Delineation.

| MOW STRIP DETAIL |         |         | CONCRETE FOOTING CHART |             |            |
|------------------|---------|---------|------------------------|-------------|------------|
| MOW STRIP        | DEPTH   | WIDTH   | FOOTING                | TUBE SLEEVE | REBAR RING |
| NONE             |         |         | 30" Min.               | 27" Min.    | YES        |
| HMA              | 6" Min. | 3' Min. | 27" Min.               | 15" Min.    | NO         |
| HMA              | 8" Min. | 3' Min. | 24" Min.               | 15" Min.    | NO         |
| RC               | 3" Min. | 3' Min. | 24" Min.               | 15" Min.    | NO         |

Chart does not apply to Terminal Posts 1 thru 9.  
- Mow strip or pavement.  
HMA - Hot Mix Asphalt (Not Recycled Asphalt Pavement).  
RC - Reinforced Concrete (TxDOT Class A Minimum).

Trinity Highway Products, LLC.  
2525 Stemmons Freeway  
Dallas, TX 75207  
Phone: (800) 644-7976  
Product.INFO@TRIN.NET

| CABLE TENSION CHART |                          |
|---------------------|--------------------------|
| FAHRENHEIT DEGREES  | PRE-STRETCHED LB / FORCE |
| -10                 | 7300                     |
| 0                   | 7000                     |
| 10                  | 6600                     |
| 20                  | 6300                     |
| 30                  | 6000                     |
| 40                  | 5600                     |
| 50                  | 5300                     |
| 60                  | 5000                     |
| 70                  | 4600                     |
| 80                  | 4300                     |
| 90                  | 4000                     |
| 100                 | 3600                     |
| 110                 | 3300                     |
| 120                 | 3000                     |
| 130                 | 2700                     |
| 140                 | 2500                     |
| 150                 | 2300                     |

Allowable deviation from chart in tangent sections:  
+800, -200 pounds/force. Cable tension readings are typically higher in curved cable sections.

Texas Department of Transportation  
**TRINITY CABLE SAFETY SYSTEM (TL-4)**  
**CASS(TL4)-14**









|                     |            |                      |              |                      |
|---------------------|------------|----------------------|--------------|----------------------|
| FILE: casstl414.dgn | DN: TxDOT  | CK: RM               | DW: VP       | CK:                  |
| ©TxDOT: March 2014  | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US B4, ETC. |
| REVISIONS           | DIST: Abi  | COUNTY: SCURRY, ETC. | SHEET NO. 58 |                      |

Design Division Standard

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- ### GENERAL NOTES
- For additional information contact Gibraltar, Inc. at 1-800-495-8957, 830-798-5444, or see the manufacturer's product manual.
  - All concrete shall be CLASS A.
  - The Cable Barrier System shall be installed on shoulders or on medians with slopes of 6:1 or flatter. If installed on slopes steeper than 6:1 up to 4:1 the TL-4 system performs as a TL-3 and Gibraltar must be contacted for various guidelines related to placement.
  - The Cable Barrier System is accepted by the FHWA Test Level - 4.
  - See the Texas MUTCD for proper "Barrier" delineation.
  - Rock Clause: Where solid rock is encountered:
    - For socketed post, continue digging 12" diameter, 15" deep into rock or the required plan depth, whichever comes first.
    - For driven post, core drill a 4" diameter hole 18" deep into rock or the required plan depth, whichever comes first.
    - For Anchor post, continue digging 24" diameter, 30" deep into rock or the required plan depth, whichever comes first.
  - Tolerances:
    - LP = 3" out of plumb, at top
    - Cable height = 1"
    - Anchor Post = 5" off of Cable Reference Line
  - The Gibraltar cable barrier system shall be installed in NCHRP Report 350 standard compacted soil. Soil must be well drained.
  - All non-welded rebar by others.
  - Minimum recommended line post foundation.
    - Without mowstrip, 36" Deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long
    - With 4" minimum depth hot mix asphalt, 30" deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long.
    - With 3" minimum depth concrete mowstrip, 24" deep x 12" diameter foundations. (No rebar required)
    - Direct drive post 42" deep.

| Temperature (°F) | Tension |
|------------------|---------|
| -10 °F           | 8000    |
| 0 °F             | 7600    |
| 10 °F            | 7200    |
| 20 °F            | 6800    |
| 30 °F            | 6400    |
| 40 °F            | 6000    |
| 50 °F            | 5600    |
| 60 °F            | 5200    |
| 70 °F            | 4800    |
| 80 °F            | 4400    |
| 90 °F            | 4000    |
| 100 °F           | 3600    |
| 110 °F           | 3200    |

| Deflection | Post Spacing |
|------------|--------------|
| 8'-0"      | 20 FT        |
| 7'-0"      | 12 FT        |
| 6'-8"      | 10 FT        |

Allowable Deviation from Chart +/- 10%

Texas Department of Transportation  
**GIBRALTAR CABLE BARRIER SYSTEM (TL-4)**  
**GBRLTR(TL4)-14**


|                      |            |                      |              |                      |
|----------------------|------------|----------------------|--------------|----------------------|
| FILE: gbrltr1414.dgn | DN: TxDOT  | CK: RM               | DW: VP       | CK:                  |
| © TxDOT: March 2014  | CONT: 6460 | SECT: 98             | JOB: 001     | HIGHWAY: US 84, ETC. |
| REVISIONS            | DIST: Abil | COUNTY: SCURRY, ETC. | SHEET NO. 59 |                      |

Design Division Standard

DATE: FILE: CABLE RELEASE AND ANCHOR POST


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



- GENERAL NOTES**
- FOR ADDITIONAL INFORMATION CONTACT YOUR DISTRIBUTOR OR NUCOR STEEL MARION, INC. AT (740) 383-4011.
  - FOR PAYMENT SEE SPECIAL SPECIFICATION "CABLE BARRIER SYSTEM".
  - FOR ADDITIONAL INFORMATION SEE THE MANUFACTURER'S PRODUCT MANUAL.
  - THE NU-CABLE SYSTEM IS DESIGNED FOR BI-DIRECTIONAL TRAFFIC FLOWS. SEE THE MANUFACTURER'S PRODUCT MANUAL FOR PLACEMENT ADJACENT TO GUARDRAIL END TREATMENTS.
  - THE NU-CABLE SYSTEM SHALL BE INSTALLED ON MEDIANS WITH SLOPES OF 6:1 OR FLATTER WITHOUT OBSTRUCTIONS, DEPRESSIONS, ETC; THAT MAY SIGNIFICANTLY AFFECT THE STABILITY OF AN ERRANT VEHICLE.
  - THE NU-CABLE SYSTEM MAY BE INSTALLED ON EITHER SIDE OF THE ROADWAY. Rib-Bok™ CABLE LINE POSTS MAY BE SOCKETED OR DRIVEN DESIGN.
  - THE TL-4 FOR 6:1 SLOPES CAN USE 4# / LF POST. SEE TABLE #1 FOR POST SIZE PER SPACING.
  - SEE (TABLE 2) FOR TENSION AMOUNT AT SPECIFIC CABLE TEMPERATURE FOR INITIAL INSTALLATION.
  - SEE (TABLE 3) FOR TENSION AMOUNT AT SPECIFIC CABLE TEMPERATURE FOR MAINTENANCE.
  - FOURTH (LOWEST) CABLE IS NOT OPTIONAL ON THE TL-4 SYSTEM.
  - CONSULT YOUR PROJECT PLAN SHEETS AND CABLE BARRIER SPECIFICATIONS FOR DESIRED SOCKET MATERIAL.
  - ALL FOUNDATION DESIGNS ARE BASED ON NCHRP 350 STRONG (S1) SOIL. CONSULT THE MANUFACTURER FOR SPECIFIC FOUNDATION DESIGN IF SOIL TYPES DIFFER.

STAGGER PLACEMENT OF TURNBUCKLES LINE TO LINE BETWEEN POSTS.  
 NOTE: TURNBUCKLES MAY BE SWAGED OR WEDGE FITTINGS.



NOTE: CABLE HEIGHTS ARE TO THE MIDDLE OF THE CABLE.  
 HEIGHT TOLERANCES:  
 ALL CABLES: ±1"

7 TABLE 1

| POST SIZE TABLE |                         |
|-----------------|-------------------------|
| POST SPACING    | POST SIZE               |
| 0' - 17'-6"     | 4# / LF X 4' OR 6' POST |
| 17'-6" - 20'    | 5# / LF X 4' POST       |


POST SPACING IS PER 8 FOOT DEFLECTION REQUIREMENTS. CONSULT PRODUCT MANUAL IF GREATER DEFLECTION IS PERMISSIBLE.

8 TABLE 2





| CABLE TENSION CHART |       |
|---------------------|-------|
| INITIAL INSTALL     |       |
| F                   | LBF   |
| 120                 | 4624  |
| 110                 | 4986  |
| 100                 | 5350  |
| 90                  | 5713  |
| 80                  | 6077  |
| 70                  | 6440  |
| 60                  | 7167  |
| 50                  | 7894  |
| 40                  | 8619  |
| 30                  | 9346  |
| 20                  | 10073 |
| 10                  | 10800 |
| 0                   | 11525 |
| -10                 | 12252 |
| -20                 | 12979 |
| -30                 | 13706 |

9 TABLE 3


| CABLE TENSION CHART |       |
|---------------------|-------|
| MAINTENANCE         |       |
| F                   | LBF   |
| 120                 | 4021  |
| 110                 | 4336  |
| 100                 | 4652  |
| 90                  | 4968  |
| 80                  | 5284  |
| 70                  | 5600  |
| 60                  | 6232  |
| 50                  | 6864  |
| 40                  | 7495  |
| 30                  | 8127  |
| 20                  | 8759  |
| 10                  | 9391  |
| 0                   | 10022 |
| -10                 | 10654 |
| -20                 | 11286 |
| -30                 | 11918 |



LENGTH OF NEED POSTS  
 MEDIAN CONFIGURATION  
**INSTALLATION DETAIL**  
 4 CABLE 6:1



11 **SOCKETED POST OPTION**  
 (TYPE S POST)



**ALTERNATE SOCKET PLACEMENT**  
 (TYPE S POST)


Texas Department of Transportation  
 Design Division Standard

**NU-CABLE BARRIER SYSTEM (TL-4) (4 CABLE)**


**NU-CABLE(TL4)-14**

|            |       |              |      |             |
|------------|-------|--------------|------|-------------|
| FILE:      | DN:   | CK:          | DW:  | CK:         |
| © TxDOT:   | CONT: | SECT:        | JOB: | HIGHWAY:    |
| REVISIONS: | 6460  | 98           | 001  | US 84, ETC. |
|            | DIST: | COUNTY:      |      | SHEET NO.:  |
|            | Abi   | SCURRY, ETC. |      | 60          |


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**SECTION B-B**  
(CABLE RELEASE POST)



**DETAIL A - CRP IN CONCRETE FOOTING**  
(3000 PSI MIN CONCRETE)




**DRIVEN SOCKET OPTION**



**NU-TEN CONCRETE FOOTING DETAIL**


**TABLE 4**  
CRP END TERMINAL CABLE HEIGHTS - TL-4

|                     | LP 1 | LP 2 | LP 3 | LP 4 | LP 5 | LP 6 |
|---------------------|------|------|------|------|------|------|
| TOP CABLE           | 34"  | 34"  | 34"  | 34"  | 34"  | 34"  |
| UPPER-MIDDLE CABLE  | 27"  | 27"  | 27"  | 27"  | 28"  | 31"  |
| BOTTOM-MIDDLE CABLE | 24"  | 24"  | 24"  | 24"  | 24"  | 24"  |
| BOTTOM CABLE        | 15"  | 15"  | 15"  | 15"  | 15"  | 15"  |



**CRP POST END TERMINAL SYSTEMS**

① THE OPPOSING END TREATMENTS ON A PARTICULAR RUN ARE MIRRORED IN THEIR LAYOUT.



**NU-TEN END TERMINAL SYSTEM**

**NOTES**

1. THE OPPOSING END TREATMENTS ON A PARTICULAR RUN ARE MIRRORED IN THEIR LAYOUT. SYSTEM PAYMENT IS PER EACH (EA). REFER TO PROJECT SPECIFICATIONS FOR ADDITIONAL PAYMENT INFORMATION
2. REFER TO INSTALLATION MANUAL FOR CABLE END ASSEMBLY DETAIL.
3. ALL FOUNDATION DESIGNS ARE BASED ON NCHRP 350 STRONG (S1) SOIL. CONSULT THE MANUFACTURER FOR SPECIFIC FOUNDATION DESIGNS IF SOIL TYPES DIFFER.
4. SEE TABLE 4 CABLE HEIGHTS IN CRP TRANSITION SECTION.

SHEET 2 OF 2



**NU-CABLE BARRIER SYSTEM**  
(TL-4)  
(4 CABLE)

**NU-CABLE(TL4)-14**

| FILE:     | DN:  | CK:          | DW:       | CK:         |
|-----------|------|--------------|-----------|-------------|
| © TxDOT:  | CONT | SECT         | JOB       | HIGHWAY     |
| REVISIONS | 6460 | 98           | 001       | US B4, ETC. |
|           | DIST | COUNTY       | SHEET NO. |             |
|           | Abi  | SCURRY, ETC. | 61        |             |

DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

| REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS |   |        |        | DELINEATORS |   |     |            | D & OM DESCRIPTIVE CODES |  |
|---|---|--------|--------|-------------|---|-----|------------|--------------------------|--|
| DEVICE  | SIZE 1  | SIZE 2 | SIZE 3 | SIZE 4      | SINGLE  |     | DOUBLE     |                          | INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX)<br>NUMBER OF REFLECTORS<br>S - Single<br>D - Double<br>COLOR OF REFLECTORS<br>W - White<br>Y - Yellow<br>R - Red<br>REFLECTOR UNIT SIZE<br>1 or 2<br>TYPE OF POST OR DELINEATOR<br>WC - Wing Channel Post<br>YFLX - Yellow Flexible Post<br>WFLX - White Flexible Post<br>BRFL - Barrier Reflector<br>TYPE OF MOUNT<br>GND - Embedded (drivable or set in concrete)<br>CTB - Concrete Barrier Mount<br>GF1 or GF2 - Guard Fence Attachment<br>SRF - Surface Mount<br>DIRECTION<br>If Required<br>Bi - Bi-Directional<br>BR - Bi-Directional with red on back |
|   |   |        |        |             |   |     |            |                          |  |
| SHEETING  | Yellow, White or Red Type B or C reflective sheeting  |        |        |             | SHEETING Yellow, White or Red Type B or C Reflective Sheeting |     |            |                          |  |
| NOTE  | 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx).<br>2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes. |        |        |             | POST TYPE   | WC  | YFLX, WFLX | WC                       | YFLX, WFLX   |
|   |   |        |        |             | MOUNT TYPE  | GND | GND, SRF   | GND                      | GND, SRF   |

| OBJECT MARKERS |                                |                               |       |          |   |       |       | D & OM DESCRIPTIVE CODES  |  |
|----------------|--------------------------------|-------------------------------|-------|----------|---|-------|-------|---------------------------|--|
| DEVICE         | Type 1 (OM-1)                  | Type 2 (OM-2)                 |       |          | Type 3 (OM-3)   |       |       | Type 4 (OM-4)             | INSTL OM ASSM (OM-XX) (XXXX)XXX(XX)<br>TYPE OF OBJECT MARKER<br>1, 2, 3, or 4<br>NUMBER OF REFLECTORS OR DIRECTION<br>X - 3-Size 2 reflector units (Type 2 only)<br>Y - 1-Size 3 reflector unit (Type 2 only)<br>Z - 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only)<br>L - Left Side (Type 3 Object Marker only)<br>R - Right Side (Type 3 Object Marker only)<br>C - Center (Type 3 Object Marker only)<br>TYPE OF POST<br>WC - Wing Channel Post<br>WFLX - White Flexible Post<br>TWT - Thin Walled Tubing<br>TYPE OF MOUNT<br>GND - Embedded (drivable)<br>SRF - Surface Mount<br>WAS - Wedge Anchor Steel<br>WAP - Wedge Anchor Plastic<br>DIRECTION<br>If Required<br>Bi - Bi-Directional |
|                |                                | OM-1                          | OM-2X | OM-2Y    | OM-2Z   | OM-3L | OM-3R | OM-3C                     |  |
|                |                                |                               |       |          |   |       |       |                           |  |
| SHEETING       | Yellow-Type B or C Sheeting FL | Yellow - Type B or C Sheeting |       |          | Alternating acrylic black and retroreflective yellow - Type B or C Sheeting |       |       | Red -Type B or C Sheeting |  |
| POST TYPE      | TWT                            | WC                            | WC    | WFLX     | TWT   |       |       | TWT                       |  |
| MOUNT TYPE     | WAS, WAP                       | GND                           | GND   | GND, SRF | WAS, WAP  |       |       | WAS, WAP                  |  |

| DEPARTMENTAL MATERIAL SPECIFICATIONS                                       |          |
|--|----------|
| FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES) | DMS-4400 |
| SIGN FACE MATERIALS  | DMS-8300 |
| DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS                         | DMS-8600 |

| BARRIER REFLECTORS (BRF) |   |     | CHEVRONS |                 |  |                                  | ONE DIRECTION LARGE ARROW |                     | NOTE:<br>Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative. |                          |                                  |
|--------------------------|---|-----|----------|-----------------|--|----------------------------------|---------------------------|---------------------|--|--------------------------|----------------------------------|
| DEVICE                   | GF1   | GF2 | CTB      | <br>W1-8        |  |                                  |                           | <br>W1-6            |  |                          |                                  |
|                          | 1. Barrier reflectors shall meet the requirements of DMS 8600.<br>2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov. |     |          | SIZE (W x L)    | 18"x 24" (Conventional)  | 24"x 30" (Conventional Oversize) | 30"x 36" (Expressway)     | 36" x 48" (Freeway) | SIZE (W x L)   | 48" x 24" (Conventional) | 60" x 30" (Expressway & Freeway) |
|                          |   |     |          | MOUNTING HEIGHT | 4'-0" or 7'-0"   |                                  | 7'-0" Only                |                     | MOUNTING HEIGHT  | 7'-0"                    |                                  |
|                          |   |     |          | NOTE            | 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies).<br>2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6). |                                  |                           |                     |  |                          |                                  |
| SHEETING                 | Yellow, White, Red  |     |          |                 |  |                                  |                           |                     |  |                          |                                  |
| NOTE                     | 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.  |     |          |                 |  |                                  |                           |                     |  |                          |                                  |











### DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

#### D & OM(1)-20


|                     |           |              |             |           |
|---------------------|-----------|--------------|-------------|-----------|
| FILE: dom1-20.dgn   | DN: TXDOT | CK: TXDOT    | DW: TXDOT   | CK: TXDOT |
| © TXDOT August 2004 | CONT      | SECT         | JOB         | HIGHWAY   |
| REVISIONS           | 646098    | 001          | US 84, ETC. |           |
| 10-09 3-15          | DIST      | COUNTY       | SHEET NO.   |           |
| 4-10 7-20           | Abi       | SCURRY, ETC. | 62          |           |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

| POST TYPE AND SUPPORT FOUNDATION DETAILS  |  |   |   | TYPE OF BARRIER MOUNTS  |   |   |
|---|--|---|---|---|---|---|
| WING CHANNEL (WC)   | FLEXIBLE POSTS (YFLX, WFLX)  |   | WEDGE ANCHOR SYSTEMS  |   | GUARD FENCE ATTACHMENT  |   |
| GND   | GND  | SRF   | WAS   | WAP   | GF1   |   |
|    |    |  |  |  |    |  |
|   | EMBEDDED   |   | SURFACE MOUNT   | STEEL   | PLASTIC   | GF2   |
| <b>NOTES</b><br>1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only.<br>2. 1.12 lbs/ft steelper ASTM A 1011 SS Gr. 50, or ASTM A499. | <b>NOTES</b><br>1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices.<br>2. Install per manufacturer's recommendations.<br>3. Post length may vary to meet field conditions.<br>4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow. |   | <b>NOTE</b><br>1. Install per manufacturer's recommendations.                       |   | <b>CONCRETE TRAFFIC BARRIER (CTB)</b><br> |   |


- GENERAL NOTES**
- Place delineators on a section of roadway at a consistent distance from the edge of pavement.
  - Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
  - When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
  - Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
  - Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
  - Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

**TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS**




**NOTE**  
 Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

**CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN**




**NOTE**  
 Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

**DELINEATORS AND TYPE 2 OBJECT MARKERS**



See general notes 1, 2 and 3.



Texas Department of Transportation  
Traffic Safety Division Standard

**DELINEATOR & OBJECT MARKER INSTALLATION**

**D & OM(2)-20**


|                     |           |              |           |             |
|---------------------|-----------|--------------|-----------|-------------|
| FILE: dom2-20.dgn   | DN: TXDOT | CK: TXDOT    | DW: TXDOT | CK: TXDOT   |
| © TXDOT August 2004 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS           | 646098    |              | 001       | US 84, ETC. |
| 10-09 3-15          | DIST      | COUNTY       |           | SHEET NO.   |
| 4-10 7-20           | Abi       | SCURRY, ETC. |           | 63          |

DATE:  
FILE:

### MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

| Amount by which Advisory Speed is less than Posted Speed | Curve Advisory Speed   |   |
|--|--|---|
|  | Turn (30 MPH or less)  | Curve (35 MPH or more)  |
| 5 MPH & 10 MPH   | • RPMs   | • RPMs  |
| 15 MPH & 20 MPH  | • RPMs and One Direction Large Arrow sign  | • RPMs and Chevrons; or<br>• RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons. |
| 25 MPH & more  | • RPMs and Chevrons; or<br>• RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons | • RPMs and Chevrons   |


### SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



**NOTE**

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

### SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



**NOTE**

At least one chevron pair is installed beyond the point of tangent in tangent section.

### DELINEATOR AND CHEVRON SPACING

| WHEN DEGREE OF CURVE OR RADIUS IS KNOWN |                 |                  |                         |                          |
|---|-----------------|------------------|-------------------------|--------------------------|
| Degree of Curve                         | FEET            |                  |                         |                          |
|   | Radius of Curve | Spacing in Curve | Spacing in Straightaway | Chevron Spacing in Curve |
|   |                 | A                | 2A                      | B                        |
| 1                                       | 5730            | 225              | 450                     | —                        |
| 2                                       | 2865            | 160              | 320                     | —                        |
| 3                                       | 1910            | 130              | 260                     | 200                      |
| 4                                       | 1433            | 110              | 220                     | 160                      |
| 5                                       | 1146            | 100              | 200                     | 160                      |
| 6                                       | 955             | 90               | 180                     | 160                      |
| 7                                       | 819             | 85               | 170                     | 160                      |
| 8                                       | 716             | 75               | 150                     | 160                      |
| 9                                       | 637             | 75               | 150                     | 120                      |
| 10                                      | 573             | 70               | 140                     | 120                      |
| 11                                      | 521             | 65               | 130                     | 120                      |
| 12                                      | 478             | 60               | 120                     | 120                      |
| 13                                      | 441             | 60               | 120                     | 120                      |
| 14                                      | 409             | 55               | 110                     | 80                       |
| 15                                      | 382             | 55               | 110                     | 80                       |
| 16                                      | 358             | 55               | 110                     | 80                       |
| 19                                      | 302             | 50               | 100                     | 80                       |
| 23                                      | 249             | 40               | 80                      | 80                       |
| 29                                      | 198             | 35               | 70                      | 40                       |
| 38                                      | 151             | 30               | 60                      | 40                       |
| 57                                      | 101             | 20               | 40                      | 40                       |

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

### DELINEATOR AND CHEVRON SPACING

| WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN |                  |                         |                          |
|---|------------------|-------------------------|--------------------------|
| Advisory Speed (MPH)                        | Spacing in Curve | Spacing in Straightaway | Chevron Spacing in Curve |
|   | A                | 2xA                     | B                        |
| 65  | 130              | 260                     | 200                      |
| 60  | 110              | 220                     | 160                      |
| 55  | 100              | 200                     | 160                      |
| 50  | 85               | 170                     | 160                      |
| 45  | 75               | 150                     | 120                      |
| 40  | 70               | 140                     | 120                      |
| 35  | 60               | 120                     | 120                      |
| 30  | 55               | 110                     | 80                       |
| 25  | 50               | 100                     | 80                       |
| 20  | 40               | 80                      | 80                       |
| 15  | 35               | 70                      | 40                       |

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

### DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

| CONDITION  | REQUIRED TREATMENT  | MINIMUM SPACING   |
|--|---|---|
| Fwy./Exp. Tangent  | RPMs  | See PM-series and FPM-series standard sheets  |
| Fwy./Exp. Curve  | Single delineators on right side  | See delineator spacing table  |
| Fwy./Exp. Ramp   | Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))                      | 100 feet on ramp tangents<br>Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)                                       |
| Acceleration/Deceleration Lane                             | Double delineators (see Detail 3 on D&OM(4))  | 100 feet (See Detail 3 on D & OM (4))   |
| Truck Escape Ramp  | Single red delineators on both sides  | 50 feet   |
| Bridge Rail (steel or concrete) and Metal Beam Guard Fence | Bi-Directional Delineators when undivided with one lane each direction<br>Single Delineators when multiple lanes each direction | Equal spacing (100' max) but not less than 3 delineators  |
| Concrete Traffic Barrier (CTB) or Steel Traffic Barrier    | Barrier reflectors matching the color of the edge line  | Equal spacing 100' max  |
| Cable Barrier  | Reflectors matching the color of the edge line  | Every 5th cable barrier post (up to 100' max)   |
| Guard Rail Terminus/Impact Head                            | Divided highway - Object marker on approach end<br>Undivided 2-lane highways - Object marker on approach and departure end      | Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end<br>See D & OM (5) and D & OM (6) |
| Bridges with no Approach Rail                              | Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail  | See D & OM(5)   |
| Reduced Width Approaches to Bridge Rail                    | Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge   | Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end<br>See D & OM (5)                |
| Culverts without MBGF                                      | Type 2 Object Markers   | See Detail 2 on D & OM(4)   |
| Crossovers   | Double yellow delineators and RPMs  | See Detail 1 on D & OM (4)  |
| Pavement Narrowing (lane merge) on Freeways/Expressway     | Single delineators adjacent to affected lane for full length of transition  | 100 feet  |

**NOTES**

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

**LEGEND**

|  |                           |
|--|---------------------------|
|  | Bi-directional Delineator |
|  | Delineator                |
|  | Sign                      |



### DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

#### D & OM(3)-20


|                     |           |              |             |           |
|---------------------|-----------|--------------|-------------|-----------|
| FILE: dom3-20.dgn   | DN: TXDOT | CK: TXDOT    | DW: TXDOT   | CK: TXDOT |
| © TXDOT August 2004 | CONT      | SECT         | JOB         | HIGHWAY   |
| REVISIONS           | 6460 98   | 001          | US 84, ETC. |           |
| 3-15 8-15           | DIST      | COUNTY       | SHEET NO.   |           |
| 8-15 7-20           | Ab1       | SCURRY, ETC. | 64          |           |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




**TWO-WAY, TWO LANE ROADWAY  
WITH REDUCED WIDTH APPROACH RAIL**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY  
WITH METAL BEAM GUARD FENCE (MBGF)**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY  
BRIDGE WITH NO APPROACH RAIL**



**LEGEND**

|  |                          |
|--|--------------------------|
|  | Bidirectional Delineator |
|  | Delineator               |
|  | OM-3                     |
|  | OM-2                     |
|  | Terminal End             |
|  | Traffic Flow             |



**DELINEATOR &  
OBJECT MARKER  
PLACEMENT DETAILS**








**D & OM(5)-20**

|                     |           |              |           |             |
|---------------------|-----------|--------------|-----------|-------------|
| FILE: dom5-20.dgn   | DN: TxDOT | CK: TxDOT    | DW: TxDOT | CK: TxDOT   |
| © TxDOT August 2015 | CONT      | SECT         | JOB       | HIGHWAY     |
| REVISIONS           | 6460      | 98           | 001       | US 84, ETC. |
| 7-20                | DIST      | COUNTY       | SHEET NO. |             |
|                     | Abi       | SCURRY, ETC. | 65        |             |

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




OBJECT MARKERS SMALLER THAN 3 FT<sup>2</sup>

**NOTES**

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

**NOTES**

- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- Mounting should be flush with top of attenuator. Minimum size 96" x 24".



DATE:  
FILE:

|   |           |                                  |             |
|---|-----------|----------------------------------|-------------|
|   |           | Traffic Safety Division Standard |             |
| <b>DELINEATOR &amp; OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</b><br><b>D &amp; OM(VIA)-20</b> |           |                                  |             |
| FILE: domvia20.dgn  | DN: TXDOT | CK: TXDOT                        | DW: TXDOT   |
| © TXDOT December 1989   | CONT      | SECT                             | JOB         |
| REVISIONS   | 646098    | 001                              | US 84, ETC. |
| 4-92 8-04   | DIST      | COUNTY                           | SHEET NO.   |
| 8-95 3-15   | Ap        | SCURRY, ETC.                     | 66          |
| 4-98 7-20   |           |                                  |             |