

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6462-50-001
 CSJ: 6462-50-001
 HIGHWAY: IH0820, ETC.
 LIMITS OF WORK: TARRANT COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
 DESCRIPTION: DENSE GRADED HOT MIX ASPHALT (MATERIAL ONLY)


RECOMMENDED FOR LETTING: 3/25/2024
 Date

DocuSigned by:

 7B89CC87CF28477...


 AREA ENGINEER

RECOMMENDED FOR LETTING: 3/25/2024
 Date

DocuSigned by:

 4848DA2AA1AB440...

 MAINTENANCE ENGINEER

RECOMMENDED FOR LETTING: 3/25/2024
 Date


DocuSigned by:

 1FD8BDF41B5F486...

 DIRECTOR OF MAINTENANCE

INDEX OF SHEETS

- 1 TITLE SHEET
- 2A-D GENERAL NOTES
- 3 ESTIMATE & QUANTITY SHEET
- 4 DELIVERY SITES SHEET

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2024			
FED.RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	6462-50-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	TARRANT	
CONTROL	SECTION	JOB	HWY NO.
6462	50	001	IH0820, ETC.
FILENAME			DATE
MMC 6462-50-001			3/25/2024

Project Number: MMC-6462-50-001**Control:** 6462-50-001**County:** Tarrant**Highway:** IH0820, Etc.**GENERAL NOTES:****General:**

This purpose of this contract is to supply **Dense Graded Hot Mix Asphalt and Asphaltic Concrete Patching Material** at the following locations:

Site 1	Various Locations within North Tarrant County
--------	---

This contract includes an item for pickup. Materials shall be available for pickup within 40 miles of the TxDOT office located at 508 Blue Mound Rd Saginaw, TX 76131. Load material into TxDOT equipment at time of pickup.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through the Maintenance Section Supervisor or Representative:

North Tarrant
508 Blue Mound Road Saginaw, TX 76131 (817) 232-1304

Bids will be received at 6230 East Stassney Lane, Austin, TX 78744.

Contractor questions on this project are to be emailed to the following individuals:

Area Engineer: Minh Tran, P.E.

Minh.Tran@Txdot.gov

Project Manager: Dustin Marten

Dustin.Marten@Txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. The webpage can be accessed from the Notice to Contractors dashboard located at the following Address:
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All Contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

Project Number: MMC-6462-50-001

Control: 6462-50-001

County: Tarrant

Highway: IH0820, Etc.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Section 10.2 - Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Section 10.4 – Scope of Work:

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended twice, not to exceed 540 calendar days for the entire contract term if mutually agreed.

Section 10.8 - Prosecution and Progress:

There are 365 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Types of accepted haul vehicles include End Dumps.

Each Work Order will have **no less than 7 calendar days to begin material delivery** or to make material available for pick-up, as described in the Work Order in accordance with Article 10.8.3., "Work Orders".

Each Work Order will specify a delivery site by the bid item in the contract and quantity to be supplied.

Unless otherwise directed, prosecute the work continuously to completion of the Work Order.

Project Number: MMC-6462-50-001

Control: 6462-50-001

County: Tarrant

Highway: IH0820, Etc.

Item 8006 – Superpave Mixtures (Materials Only):

Design and produce the mixture with a gradation that passes below the reference zone as shown in Table 9 for Item 8006.

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class A.

An approved anti-stripping agent will be required.

No Blending, of the material to meet SAC A will be allowed.

Natural (field) sands are not allowed.

Provide a PG 70-28 asphalt for the surface course.

Warm Mix Asphalt (WMA) is not permitted in any mix type on this project.

Substitute binders are not allowed on this project.

RAP and RAS are not permitted in any surface and level-up mixes on this project.

Furnish a mix design to the State's representative to be sent to the District Laboratory for verification testing.

No material shall be left in the haul vehicle overnight.

Canvas covers and insulating of the truck bodies will be required.

Contractor must have equipment and personnel to supply a minimum of 500 ton per day.

Include the approved mix design number on each delivery ticket.

Item 8011 – Dense-Graded Hot Mix Asphalt (Materials Only):

No Blending, of the material to meet SAC A will be allowed.

Substitute binders are not allowed on this project.

RAP and RAS are not permitted in any surface and level-up mixes on this project

Furnish a mix design to the State's representative to be sent to the District Laboratory for verification testing.

Project Number: MMC-6462-50-001

Control: 6462-50-001

County: Tarrant

Highway: IH0820, Etc.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Use only Department MPL approved asphalt release agents. Diesel and/or solvents in the production, transportation, and/or construction of the mix is prohibited.

No material shall be left in the haul vehicle overnight.

Canvas covers and insulating of the truck bodies will be required.

Contractor must have equipment and personnel to supply a minimum of 500 ton per day.

Include the approved mix design number on each delivery ticket.

Item 8019 – Asphaltic Conc Patch Material (Materials Only):

This item will be measured by the ton as defined in the plans and specifications. Delivery location will be listed in each Work Order.


ESTIMATE SUMMARY

ITEM-CODE			DESCRIPTION	UNIT	TOTAL	
ITEM NO.	DESC. CODE	SP NO.			EST.	FINAL
8011	6038		D-GR HMA(SQ) TY B SAC B PG64-22(DEL)	TON	1,500	
8011	6039		D-GR HMA(SQ) TY B SAC B PG64-22(PICKUP)	TON	1,500	
8011	6040		D-GR HMA(SQ) TY C SAC A PG70-28(DEL)	TON	1,000	
8019	6007		ASPHALTIC CONC PATCH MATERIAL (PICKUP)	TON	200	
8019	6010		ASPHALTIC CONC PATCH MATERIAL (DEL)	TON	200	
8006	6088		SP MIXTURES SP-C PG70-28 (DEL)(ST1)	TON	5000	

Texas Department of Transportation			
ESTIMATE AND QUANTITIES			
DESIGN	FED RD. DIV. NO.	MAINTENANCE PROJECT NO.	HIGHWAY NO.
	6	6462-50-001	IH0820, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY
	TEXAS	FTW	TARRANT
CHECK	CONTROL	SECTION	JOB
	6462	50	001
			SHEET NO. 3

SITE NO.	MAINTENANCE OFFICE	DELIVERY SITE	ITEM NO.	DES. NO.	UNIT	QUANTITY
1	NORTH TARRANT	VARIOUS WITHIN NORTH TARRANT COUNTY	8011	6038	TON	1,500
1	NORTH TARRANT	VARIOUS WITHIN NORTH TARRANT COUNTY	8011	6040	TON	1,000
1	NORTH TARRANT	VARIOUS WITHIN NORTH TARRANT COUNTY	8019	6010	TON	200
1	NORTH TARRANT	VARIOUS WITHIN NORTH TARRANT COUNTY	8006	6088	TON	5000

* APPROXIMATE LOCATIONS FOR DELIVERY

 Texas Department of Transportation				
DELIVERY SITE SHEET				
DESIGN	FED RD. DIV. NO.	MAINTENANCE PROJECT NO.		HIGHWAY NO.
	6	6462-50-001		IH0820, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	FTW	TARRANT	
CHECK	CONTROL	SECTION	JOB	4
	6462	50	001	