STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

STP 2B24(174)HES STATE DIST. TEXAS SAT BEXAR CONT. SECT. JOB HIGHWAY NO. 0073 02 088,ETC US 281

FEDERAL AID PROJECT NO.

INDEX OF SHEETS

SEE SHEET 3 FOR INDEX OF SHEETS

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT PROJECT NO.: STP 2B24(174) HES CCSJ: 0073-02-088, ETC.

BEXAR, ETC

LIMITS FROM: MARTHA WALK TO: BEXAR/ATASCOSA COUNTY | INF

NET LENGTH OF PROJECT = 12.51MI

FINAL PLANS

DESIGN SPEED = 70 MPH

ADT: 5931


AREA OF DISTURBED SOIL:

CSJ: 0073-02-088 = 0.54 AC

CSJ: 0073-03-072 = 6.03 AC CSJ: 0073-04-051 = 2.49 AC

LETTING DATE: ____ DATE CONTRACTOR BEGAN WORK: DATE WORK WAS ACCEPTED: _____ FINAL CONTRACT COST: \$ CONTRACTOR: ____

FOR WORK CONSISTING OF HAZARD ELIMINATION & SAFETY - INSTALL MEDIAN CABLE BARRIER FOR PROJECT LOCATIONS SEE LOCATION MAP



PAPE-DAWSON **ENGINEERS** SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS

2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000 TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #10028800

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023)

EXCEPTIONS: NONE EQUATIONS: NONE R.R. CROSSINGS: NONE

SUBMITTED 4/1/2024 FOR LETTING: —DocuSigned by Orlando Gallegos, P.E.

4460458C802A430 ENGINEER SUPERVISOR

REVIEWED 4/1/2024 FOR LETTING: -DocuSigned by: DCROgorio, P.E. - F29100BAA508499 TRANSPORTATION ENGINEER SUPERVISOR

APPROVED FOR LETTING: 4/1/2024

4/1/2024

Charles C. Benavidez, P.E.

-3BB8A8580ACE44CRICT ENGINEER

RECOMMENDED

-- DocuSigned by:

Clayton Ripps, PE


74F59ACB883D4EBDISTRICT ENGINEER

FOR LETTING:

PROJ. I LETTING DATE NO._____l ACCEPTED_

PLANS PREPARED BY:

© 2024 by Texas Department of Transportation; all rights reserved



```
Plotted on: 3/19/2024
```


DESCRIPTION SHEET NO. **GENERAL** TITLE LOCATION MAP PROJECT INDEX GENERAL NOTES 4 - 8 9-11 QUANTITY SUMMARY 12 TMA SUMMARY ESTIMATE AND QUANTITY 13 14-16 TYPICAL SECTIONS <u>TCP</u> 17 TCP NARRATIVE 18 SCHEDULE OF BARRICADES AND DEVICES 19 TCP TYPICAL SECTIONS TCP STANDARDS 20 * TCP(5-1)-18 21 22 23 24 * TCP(6-1)-12 * BC(1)-21 * BC(2) - 21 * BC(3) - 21 25 26 27 28 * BC(4) - 21 * BC(5)-21 * BC(6) - 21 * BC(7) - 21 29 * BC(8) - 21 30 * BC(9) - 21 * BC(10) - 21 32 33 * BC(11)-21 * BC(12) - 21 ROADWAY PROPOSED CABLE BARRIER LAYOUT 34-67 ROADWAY - STANDARDS * BRIFEN(TL4)-14 68-70 71 * CASS(TL-4)-14 72 * GBRLTR(TL-4)-14 73-74 * NU-CABLE(TL-4)-14 SW3P * STORM WATER POLLUTION PLAN (SW3P) 75-80 ENVIRONMENTAL - STANDARDS * EPIC 81 * EC(1)-16 83-85 * EC(9)-16



REV. NO. DATE DESCRIPTION BY



SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

PROJECT INDEX

DGN:	FED. RD. DIV. NO.	STATE	FEDER	HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
CHK DWG:	SAT	BEXAR	0073	02	088,ЕТС	3

County: BEXAR, ETC.

Highway: US 281

--General--

Contact the Engineer or the City when construction operations are within 400 feet of a signalized intersection to determine/verify the location of loop detectors, conduit, ground-boxes, etc. Repair or replace any signal equipment damaged by construction operations. The method of repair or replacement shall be pre-approved and inspected. Depending on the type and extent of the damage, the Engineer reserves the right to perform the repair or replacement work and the Contractor will be billed for this work.

City of San Antonio: (210) 207-8642

Any materials removed and not reused and determined to be salvageable shall be stored within the project limits at an approved location or delivered undamaged to the storage yard as directed. Deface traffic signs so that they will not reappear in public as signs.

Any sign panels that are adjusted or removed and replaced, shall be done the same workday unless otherwise approved. This work shall be considered subsidiary to Item 502.

Notify the Engineer at least two weeks prior to a proposed traffic pattern change(s) that will require a revision to traffic signals.

Locate and reference all manholes and valves within the construction area with station and offset or GPS. Each manhole and valve shall be identified by its owner (SAWS, CPS, etc.). No roadwork will begin until this list has been submitted. All valves and manhole covers have to be accessible at all times, therefore; temp. CTB, material stockpiles, etc. cannot be placed over these valves or covers.

The Contractor has the option to adjust or construct all manholes and valves to final pavement elevations prior to the final mat of HMA or after final mat of HMA. If between the final elevation adjustment and the final mat of HMA, the manholes and valves are going to be exposed to traffic, place temporary asphalt around the manhole and valve to provide a +/- 50:1 taper. The cost of elevation adjustment and the concrete apron around the manhole and valve will be part of the manhole and valve work. The asphalt tapers are part of the HMA work.

Hurricane Evacuation

Hurricane Season is from June 1 thru November 30. As the closest metropolitan city inland from the Texas Coast, the City of San Antonio is a major shelter destination during mandatory hurricane evacuations. As such, planned work zone lane or road closures may be restricted and/or suspended during mandatory hurricane evacuation operations. The District will coordinate these restrictions at a minimum H-120 from any projected impact to the Texas Coast.

Control: 0073-02-088, ETC. Sheet 4

County: BEXAR, ETC.

Highway: US 281

No time charges will be made if the Engineer determines that work on the project was impacted by the hurricane.

The Engineer may order changes in the Traffic Control Plan to accommodate evacuation traffic, and may suspend the work, all or in part, to ensure timely completion of this work. All work to implement changes in the Traffic Control Plan will be paid through existing bid prices or through Item 9.5, Force Account. However, the Department will not entertain any request for delay damages, loss of efficiency that may be attributed to the restriction or suspension of road or lane closures, or to changes in the Traffic Control Plan.

Submit locate request for SAWS water and sewer to TXDOTlocates@saws.org.

In accordance with the Underground Facility Damage Prevention Act (One Call Bill) the phone number for a utility locator is 811. It is the Contractor's responsibility to plan for utility locators as needed.

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way. Call or email the TxDOT offices listed below for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages incurred to the above-mentioned utilities when working without having the utilities located prior to excavation.

For signal and ITS locates call TransGuide at 210-731-5136 or email sat_its_locates@txdot.gov for ITS locates and signal.request@txdot.gov for signal locates.

Contractor questions on this project are to be addressed to the following individual(s): Orlando Gallegos,Orlando.Gallegos@TxDOT.gov
Thanya Tarrosa, Thanya.Tarrosa@TxDOT.gov

Contractor questions will be accepted through email, phone and in person by the above individuals. Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

General Notes Sheet A General Notes Sheet B

County: BEXAR, ETC.

Highway: US 281

--Item 5--

Taper ACP placed at curb inlets, traffic inlets and slotted drains.

A horizontal boom or equivalent equipment is required for construction in the vicinity of the CPS Energy electric lines to provide vertical clearance of equipment during construction. Contact CPS Energy Utility Coordination Group sixteen (16) week in anticipation of pole bracing. The estimated duration for pole bracing is 6 to 10 weeks (or longer if temporary construction easements are required) after invoice is paid. For de-energizing or sleeving of the overhead electrical lines depicted on the plans, please contact CPS Energy Utility Coordination Group sixteen (16) week in anticipation of needed de-energization. The estimated duration for de-energizing is approximately 4 to 6 weeks (after invoice is paid) but could vary on system scenario and back feed requirements. De-energizing may not be possible in all instances or may be restricted during specific periods of time due to load demand. Contractor will be reimbursed for the invoice cost for pole bracing and/or de-energizing or sleeving through force account.

Prevention of Migratory Bird Nesting

It is anticipated that migratory birds, a protected group of species, may try to nest on bridges, culverts, vegetation, or gravel substrate, at any time of the year. The preferred nesting season for migratory birds is from February 15 through October 1. When practicable, schedule construction operations outside of the preferred nesting season. Otherwise, nests containing migratory birds must be avoided and no work will be performed in the nesting areas until the young birds have fledged.

Structures

Bridge and culvert construction operations cannot begin until swallow nesting prevention is implemented, until after October 1 if it's determined that swallow nesting is actively occurring, or until it's determined swallow nests have been abandoned. If the State installed nesting deterrent on the bridges and culverts, maintain the existing nesting deterrent to prevent swallow nesting until October 1 or completion of the bridge and culvert work, whichever occurs earlier. If new nests are built and occupied after the beginning of the work, do not perform work that can interfere with or discourage swallows from returning to their nests. Prevention of swallow nesting can be performed by one of the following methods:

1. By February 15 begin the removal of any existing mud nests and all other mud placed by swallows for the construction of nests on any portion of the bridge and culverts. The Engineer will inspect the bridges and culverts for nest building activity. If swallows begin nest building, scrape, or wash down all nest sites. Perform these activities daily unless the Engineer determines the need to do this work more frequently. Remove nests and mud through October 1 or until bridge and culvert construction operations are completed.

Control: 0073-02-088, ETC. Sheet 5

County: BEXAR, ETC.

Highway: US 281

2. By February 15 place a nesting deterrent (which prevents access to the bridge and culvert by swallows) on the entire bridge (except deck and railing) and culverts. This work is subsidiary to the various bid items.

No extension of time or compensation payment will be granted for a delay or suspension of work caused by nesting swallows.

Excavation within 5 feet of an existing CPS Energy pole will require pole bracing. Contact CPS Energy utility coordination to request pole bracing (Customer Engineering 210-353-4050). The estimated duration for the pole bracing process is approximately 10 to 15 weeks.

--Item 6--

Show the stockpile lot and/or sub lot numbers on all tickets for all materials.

Steel Wrapped or Asbestos Utility Lines:

Existing steel wrapped natural gas and/or asbestos cement (AC) water lines that will no longer be in service are usually abandoned in place (AIP). However, if any of these lines have to be removed for whatever reason (in the way of other construction, to make tie-ins, etc.), comply with Item 6.

If removal of AC water lines is included in the construction contract, then notify the Engineer of proposed dates of removal of the AC water lines in accordance to Item 6. Excavate to the top of the AC water line to allow a separate contractor hired by the State to remove the AC water line. The excavation for the AC water line removal is subsidiary to the work that created the need for the removal (excavation for structures, roadway, a new line, tie-ins, etc.).

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product. Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html for clarification on material categorization.

--Item 7--

The project's total disturbed area is 9.06 acres. The disturbed area in all project locations and Contractor project specific locations (PSL's), within 1/4 mile of the project limits, will further establish the authorization requirements for storm water discharges. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality

General Notes Sheet C General Notes Sheet D

County: BEXAR, ETC.

Highway: US 281

(TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any PSL's on or off the ROW. When the total area disturbed on the project and PSL's within 1/4 mile of the project exceeds 5 acres, provide a copy of the Contractor NOI for PSL's to the Engineer (to the appropriate MS4 operator when the project is on an off-state system route).

No significant traffic generators events identified.

Law Enforcement patrol vehicles must be marked as "Police".

--Item 8--

Working days will be computed and charged in accordance with Article 8.3.1.4. Standard Work Week.

A Special Provision to Item 8 for a delayed authorized date to begin work has been included in the contract. The reason for including the Special Provision is for material processing or contractor mobilization.

Create and maintain a Bar Chart schedule.

--Item 9--

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" (Course #133119) which can be found online at the following site: www.nhi.fhwa.dot.gov

Certificates of completion should be available to all who finish the course. These should be kept by the officers to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case-by-case basis.

Control: 0073-02-088, ETC. Sheet 6

County: BEXAR, ETC.

Highway: US 281

--Item 132--

TY C Embankment shall meet the following specifications:

ITEM	Description		Percent.	Retained-Siev	е	LL Max	PI Max	PI Min
HEM	Description	3"	3/8"	#4	#40	LL Max	FI Max	
132	Embankment (ORD COMP)(TY C)	0	-	30-75	50-85	50	20	6

--Item 164--

Drill seeding of permanent grasses requires the use of approved grass seeding equipment capable of properly storing and metering the release of small seeds (such as Bermuda grass) separately from fluffy type seeds (such as bluestems). Equipment manufactured for planting grain crops is acceptable for planting temporary cool season seeds, but not for planting the permanent seed mix.

If performing a permanent seeding in an area with established temporary grass cover and mowing is performed instead of tilling, seed and fertilizer may be distributed simultaneously during "Broadcast Seeding" operations, provided each component is applied at the specified rate.

--Item 168--

Apply vegetative watering as needed to supplement natural rainfall during the vegetation establishment period. Plan quantity of irrigation water is based on the application of a total of 1.3 gal of water each week for each sq. yd. of area that is sodded or seeded. Establishment time is estimated to be 12 weeks for both sod and permanent seed mixes. Temporary seeding will require less time for establishment. Provide a schedule and coordinate watering cycles and rates per cycle with the Engineer. Obtain approval if the quantity of water to be applied is expected to exceed the plan quantity. Adjust the amount of water applied with each cycle and the number of cycles each wk. according to actual site conditions. Drought or other conditions, as determined by the Engineer, may require the application of supplemental irrigation during hours other than normal working hours.

--Item 500--

"Materials on Hand" payments will not be considered in determining percentages for mobilization payments.

--Item 502--

General

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 2 hours or within a reasonable time frame as specified by the Engineer.

General Notes Sheet E General Notes Sheet F

County: BEXAR, ETC.

Highway: US 281

Treat the pavement drop-offs as shown in the TCP.

Avoid placing stockpiles, equipment, and other construction materials within the roadway's horizontal clear zone or at any location that will constitute a hazard and will endanger traffic. If a stockpile is placed within the clear zone, address in accordance with the TMUTCD.

If Nighttime work is required and work is not behind positive barrier then full Class 3 reflective gear is required to be worn by all workers, hard hat halos are required to be worn by the flaggers at flagging stations, TY III barricades are required to be spaced at 500 ft, and a mandatory night work meeting is required.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Mounting and moving the mailbox as needed for the various construction phases is subsidiary to Item 502.

Access to adjoining property must be maintained at all times.

Barricades, Signs, and Traffic Control Devices

When advanced warning flashing arrow panels and/or changeable message sign is specified, have one standby unit in good condition at the job site. Standby time shall be considered subsidiary to the bid item.

After written notification, the time frame is provided on the Form 599 to provide properly maintained signs and barricades before considered in non-compliance with this item.

Moving an existing sign to a temporary location is subsidiary to Item 502. Installations with permanent supports at permanent locations will be paid for under the applicable bid item(s).

Cover permanent signs if not used. This is subsidiary to Item 502.

Lane and Ramp Closures and Detours

Notify the Engineer in writing 10 business days in advance of any temporary or permanent lane, ramp, connector, etc. closures/detours, restrictions to lane widths, alterations to vertical clearances, or modifications to radii. Any other modifications to the roadway that may adversely

Control: 0073-02-088, ETC. Sheet 7

County: BEXAR, ETC.

Highway: US 281

affect the mobility of oversized/overweight trucks also require 10 business days advance written notice to the Engineer. At least one lane must always remain open.

For closures not listed in the TCP; the lane closures are limited to between the hours of <u>9AM-4PM</u>, and at least one lane must remain open at all times.

At no time shall two consecutive intersecting roadways be closed at one time during construction.

At no time shall two consecutive ramps be closed at one time during construction or overlay operations.

Unless otherwise noted in the plans and/or as directed by the Engineer, daily lane closures shall be limited according to the following restrictions:

Nighttime: Ask the Area Engineer for the days and hours for nighttime work if the Area Engineer agrees to nighttime work.

Weekend closures when approved by the Engineer: Ask the Area Engineer for the days and hours for nighttime work if the Area Engineer agrees to nighttime work.

No lane closures will be permitted for the following dates and/or special events:

Between December 15 and January 1

Fiesta Week and Sales Tax Holidays (Bexar County Only)

Wednesday before Thanksgiving thru the Sunday after Thanksgiving

Saturday and Sunday before Memorial Day and Labor Day

Saturday or Sunday when July 4 falls on a Friday or Monday

Election days (Bexar County Only)

During major events at the AT&T Center (Spurs home games, Rodeo, concerts, etc.)

Alamodome, and/or Convention Center (Bexar County Only)

Saturday before and Monday After Easter – April 18-21, 2025

Hauling

The use of rubber-tired equipment will be required for moving dirt or other materials along or across pavement surfaces. Where the contractor desires to move any equipment not licensed for operation on public highways, on or across pavement, they shall protect the pavement from damage as directed/approved by the Engineer.

Throughout construction operations, the Contractor will be required to conduct their hauling operations in a manner such that vehicles will not haul over previously recompacted subgrade or compacted base material, except in short sections for dumping manipulations.

General Notes Sheet G General Notes Sheet H

County: BEXAR, ETC.

Highway: US 281

The Contractor shall keep the roadway clean and free of dirt or other materials during hauling operations. If the Contractor does not maintain a clean roadway, they shall cease all construction operations, when directed by the Engineer, to clean the roadway to the satisfaction of the Engineer.

--Item 506--

An Inspector will perform a regularly scheduled SWP3 inspection every 7 calendar days.

Failure to address items noted on the SW3P inspection report within two report cycles may result in the Department stopping all construction operations, exclusive of time charges, or withholding that month's estimate until the SW3P deficiencies are corrected unless the Engineer determines that the area is too wet to correct SW3P deficiencies.

Failure to correctly maintain daily monitoring reports and submitting to TxDOT on a daily/weekly basis may result in the monthly estimate being withheld.

--Item 543--

Withing 15 days of Notice to Proceed, Contractor shall provide correspondence from post and cable supplier on expected delivery date of material. Contractor shall execute the work to complete all work except the post and cable installation. Time will be suspended when this work is complete. Time will resume when installation of post and cable begins, within 20 days upon receipt of post and cable material, or within 20 days upon expected delivery date of material; whichever comes first.

--Item 6185--


6185-1 One (1) shadow vehicle with TMA will be required for this project. The TMA's will be measured and paid for by the DAY for each TMA/TA set up and operational on the worksite. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project. See TMA and TA Summary sheet in the plans.

General Notes Sheet I

ITEM	0132-6021 *	0150-6002	0164-6035	0164-6051	0168-6001	0169-6001	0432-6066	0502-6001	0543-6002	0543-6020
LOCATION	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	BLADING	DRILL SEEDING (PERM) (RURAL) (CLAY)	DRILL SEED (TEMP) (WARM OR COOL)	VEGETATIVE WATERING	SOIL RETENTION BLANKETS (CL 1) (TY A)	RIPRAP (CL A) (MOW STRIP) (3 IN)	BARRICADES, SIGNS AND TRAFFIC HANDLING	CABLE BARRIER SYSTEM (TL-4)	CABLE BARRIER TERMINAL SECTION (TL-4)
	CY	HR	SY	SY	MG	SY	CY	MO	LF	EA
CABLE BARRIER LAYOUT BEGIN PROJECT TO STA 1020+00	1.1	8.0	1056	1056	16.47	1056	44		1584	3
CABLE BARRIER LAYOUT STA 1020+00 TO STA 1030+00	7	5.0	667	667	10.41	667	28		1000	
TRAFFIC CONTROL PLAN								1		
TOTALS	18	13.0	1723	1723	26.88	1723	72	1	2584	3

^{*} CONTRACTOR TO USE AS NEEDED IF BLADING ALONE IS NOT SUFFICIENT FOR GRADING

ITEM	6001-6002	6185-6002	
LOCATION	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	
	EA	DAY	
CABLE BARRIER LAYOUT BEGIN PROJECT TO STA 1020+00			
CABLE BARRIER LAYOUT STA 1020+00 TO STA 1030+00			
TRAFFIC CONTROL PLAN	2	7	
TOTALS	2	7	





SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

QUANTITY SUMMARY

SHEET	1	OF	3

N:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.
(N:	6	TEXAS	SEE	TITLE S	SHEET	US 281
G:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
(3:	SAT	BEXAR	0073	02	088,ETC	9

CSJ: 0073-03-072

ITEM	0132-6021 *	0150-6002	0164-6035	0164-6051	0168-6001	0169-6001	0432-6066	0502-6001	0506-6038	0506-6039
LOCATION	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	BLADING	DRILL SEEDING (PERM) (RURAL) (CLAY)	DRILL SEED (TEMP) (WARM OR COOL)	VEGETATIVE WATERING	SOIL RETENTION BLANKETS (CL 1) (TY A)	RIPRAP (CL A) (MOW STRIP) (3 IN)	BARRICADES, SIGNS AND TRAFFIC HANDLING	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	CY	HR	SY	SY	MG	SY	CY	MO	LF	LF
CABLE BARRIER LAYOUT STA 1030+00 TO STA 1040+00	2	3.0	180	180	2.81	180	8		100	100
CABLE BARRIER LAYOUT STA 1040+00 TO STA 1060+00	1 1	8.0	997	997	15.55	997	42			
CABLE BARRIER LAYOUT STA 1060+00 TO STA 1080+00	12	9.0	1134	1134	17.69	1134	47		100	100
CABLE BARRIER LAYOUT STA 1080+00 TO STA 1100+00	2	2.0	199	199	3.10	199	8		100	100
CABLE BARRIER LAYOUT STA 1100+00 TO STA 1120+00	12	10.0	1185	1185	18.49	1185	49		100	100
CABLE BARRIER LAYOUT STA 1120+00 TO STA 1140+00	1 1	8.0	1017	1017	15.87	1017	42			
CABLE BARRIER LAYOUT STA 1140+00 TO STA 1160+00	12	10.0	1158	1158	18.06	1158	48		100	100
CABLE BARRIER LAYOUT STA 1160+00 TO STA 1180+00	10	9.0	972	972	15.16	972	41		100	100
CABLE BARRIER LAYOUT STA 1180+00 TO STA 1200+00	12	10.0	1166	1166	18.19	1166	49		100	100
CABLE BARRIER LAYOUT STA 1200+00 TO STA 1220+00	12	10.0	1166	1166	18.19	1166	49			
CABLE BARRIER LAYOUT STA 1220+00 TO STA 1240+00	12	9.0	1143	1143	17.83	1143	48		100	100
CABLE BARRIER LAYOUT STA 1240+00 TO STA 1260+00	10	10.0	990	990	15.44	990	41		100	100
CABLE BARRIER LAYOUT STA 1260+00 TO STA 1280+00	6	5.0	605	605	9.44	605	25			
CABLE BARRIER LAYOUT STA 1300+00 TO STA 1320+00	8	8.0	784	784	12.23	784	33			
CABLE BARRIER LAYOUT STA 1320+00 TO STA 1340+00	9	8.0	857	857	13.37	857	36		100	100
CABLE BARRIER LAYOUT STA 1340+00 TO STA 1360+00	2	5.0	197	197	3.07	197	8			
CABLE BARRIER LAYOUT STA 1360+00 TO STA 1380+00	12	9.0	1129	1129	17.61	1129	47		100	100
CABLE BARRIER LAYOUT STA 1380+00 TO STA 1400+00	12	10.0	1160	1160	18.10	1160	48			
CABLE BARRIER LAYOUT STA 1400+00 TO STA 1420+00	8	8.0	761	761	11.87	761	32		48	48
CABLE BARRIER LAYOUT STA 1420+00 TO STA 1440+00	1.1	8.0	1079	1079	16.83	1079	45			-
CABLE BARRIER LAYOUT STA 1440+00 TO STA 1460+00	7	8.0	646	646	10.08	646	27		300	300
CABLE BARRIER LAYOUT STA 1460+00 TO STA 1480+00	5	4.0	433	433	6.75	433	18			
CABLE BARRIER LAYOUT STA 1480+00 TO STA 1500+00	5	4.0	500	500	7.80	500	21			
TRAFFIC CONTROL PLAN								3		
TOTALS	203	175.0	19458	19458	303.53	19458	812	3	1448	1448


^{*} CONTRACTOR TO USE AS NEEDED IF BLADING ALONE IS NOT SUFFICIENT FOR GRADING

ITEM	0506-6040	0506-6043	0543-6002	0543-6020	6001-6002	6185-6002
LOCATION	BIODEG EROSN CONT LOGS (INSTL) (8")	BIODEG EROSN CONT LOGS (REMOVE)	CABLE BARRIER SYSTEM (TL-4)	CABLE BARRIER TERMINAL SECTION (TL-4)	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)
	LF	LF	LF	EA	EA	DAY
CABLE BARRIER LAYOUT STA 1030+00 TO STA 1040+00			270	1		
CABLE BARRIER LAYOUT STA 1040+00 TO STA 1060+00			1 4 9 5	3		
CABLE BARRIER LAYOUT STA 1060+00 TO STA 1080+00	20	20	1 701	2		
CABLE BARRIER LAYOUT STA 1080+00 TO STA 1100+00	20	20	298	2		
CABLE BARRIER LAYOUT STA 1100+00 TO STA 1120+00	20	20	1778	2		
CABLE BARRIER LAYOUT STA 1120+00 TO STA 1140+00			1525	2		
CABLE BARRIER LAYOUT STA 1140+00 TO STA 1160+00	20	20	1737	3		
CABLE BARRIER LAYOUT STA 1160+00 TO STA 1180+00	20	20	1458	3		
CABLE BARRIER LAYOUT STA 1180+00 TO STA 1200+00	20	20	1749	2		
CABLE BARRIER LAYOUT STA 1200+00 TO STA 1220+00			1749	2		
CABLE BARRIER LAYOUT STA 1220+00 TO STA 1240+00	20	20	1714	2		
CABLE BARRIER LAYOUT STA 1240+00 TO STA 1260+00	20	20	1485	4		
CABLE BARRIER LAYOUT STA 1260+00 TO STA 1280+00			908	1		
CABLE BARRIER LAYOUT STA 1300+00 TO STA 1320+00	20	20	1176	3		
CABLE BARRIER LAYOUT STA 1320+00 TO STA 1340+00	20	20	1285	3		
CABLE BARRIER LAYOUT STA 1340+00 TO STA 1360+00	20	20	296	1		
CABLE BARRIER LAYOUT STA 1360+00 TO STA 1380+00	20	20	1694	2		
CABLE BARRIER LAYOUT STA 1380+00 TO STA 1400+00	20	20	1740	2		
CABLE BARRIER LAYOUT STA 1400+00 TO STA 1420+00	40	40	1142	4		
CABLE BARRIER LAYOUT STA 1420+00 TO STA 1440+00			1619	2		
CABLE BARRIER LAYOUT STA 1440+00 TO STA 1460+00			969	1		
CABLE BARRIER LAYOUT STA 1460+00 TO STA 1480+00	20	20	650	2		
CABLE BARRIER LAYOUT STA 1480+00 TO STA 1500+00			750	2		
TRAFFIC CONTROL PLAN					2	50
TOTALS	320	320	29188	51	2	50



PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

QUANTITY SUMMARY

SHEET	2	OF	3


1	FED. RD. DIV. NO.	STATE	FEDER	HIGHWAY NO.		
:	6	TEXAS	SEE 1	US 281		
	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
:	SAT	BEXAR	0073	02	088,ETC	10

CSJ: 0073-04-051

ITEM	0132-6021 *	0150-6002	0164-6035	0164-6051	0168-6001	0169-6001	0432-6066	0502-6001	0506-6038	0506-6039
LOCATION	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	BLADING	DRILL SEEDING (PERM) (RURAL) (CLAY)	DRILL SEED (TEMP) (WARM OR COOL)	VEGETATIVE WATERING	SOIL RETENTION BLANKETS (CL 1) (TY A)	RIPRAP (CL A) (MOW STRIP) (3 IN)	BARRICADES, SIGNS AND TRAFFIC HANDLING	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	CY	HR	SY	SY	MG	SY	CY	MO	LF	LF
CABLE BARRIER LAYOUT BEGIN PROJECT TO STA 2020+00	9	7.0	824	824	12.85	824	34			
CABLE BARRIER LAYOUT STA 2020+00 TO STA 2040+00	1.1	9.0	1017	1017	15.87	1017	42		100	100
CABLE BARRIER LAYOUT STA 2040+00 TO STA 2060+00	11	9.0	1034	1034	16.13	1034	43		125	125
CABLE BARRIER LAYOUT STA 2060+00 TO STA 2080+00	12	10.0	1141	1141	17.80	1141	48		175	1 75
CABLE BARRIER LAYOUT STA 2080+00 TO STA 2100+00	1 4	10.0	1 3 3 1	1 3 3 1	20.76	1331	55		200	200
CABLE BARRIER LAYOUT STA 2100+00 TO STA 2120+00	1.1	9.0	1062	1062	16.57	1062	44		100	100
CABLE BARRIER LAYOUT STA 2120+00 TO STA 2140+00	1.1	9.0	1066	1066	16.63	1066	44		100	100
CABLE BARRIER LAYOUT STA 3040+00 TO STA 3060+00	6	5.0	569	569	8.88	569	24		100	100
TRAFFIC CONTROL PLAN								2		
TOTALS	85	68.0	8044	8044	125.49	8044	334	2	900	900

* CONTRACTOR TO USE AS NEEDED IF BLADING ALONE IS NOT SUFFICIENT FOR GRADING

ITEM	0543-6002	0543-6020	6001-6002	6185-6002
LOCATION	CABLE BARRIER SYSTEM (TL-4)	CABLE BARRIER TERMINAL SECTION (TL-4)	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)
	LF	EA	EA	DAY
CABLE BARRIER LAYOUT BEGIN PROJECT TO STA 2020+00	1236	2		
CABLE BARRIER LAYOUT STA 2020+00 TO STA 2040+00	1525	2		
CABLE BARRIER LAYOUT STA 2040+00 TO STA 2060+00	1551	3		
CABLE BARRIER LAYOUT STA 2060+00 TO STA 2080+00	1711	2		
CABLE BARRIER LAYOUT STA 2080+00 TO STA 2100+00	1996			
CABLE BARRIER LAYOUT STA 2100+00 TO STA 2120+00	1593	2		
CABLE BARRIER LAYOUT STA 2120+00 TO STA 2140+00	1599	2		
CABLE BARRIER LAYOUT STA 3040+00 TO STA 3060+00	854	1		
TRAFFIC CONTROL PLAN			2	30
TOTALS	12065	1 4	2	30





SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800

Texas Department of Transportation © 2024


US 281: CABLE BARRIER

QUANTITY SUMMARY

SH	EET	3	OF

N:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.
K N:	6	TEXAS	SEE	TITLE S	SHEET	US 281
G:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
K G:	SAT	BEXAR	0073	02	088,ETC	11

							6185 6002	6185 6005
CSJ	TCP PHASE	SPECIFIC TCP PLAN SHEET OR TCP STANDARD SHEET	FURNISH TMA/TA	RELOCATE/REUSE TMA/TA	PER SET UP	TMA/TA SET UP	TMA (STATIONARY)	TMA (MOBILE OPERATION)
		SHEET NUMBER	EA	EA	EA	DAYS PER TMA/TA USE		DAY
0073-02-088	1		1				7	
0073-03-072	1			1			50	
0073-04-051	1			1			30	
		TOTALO						
		TOTALS	1	2			87	



NOTE.
FURNISH TMA/TA - THE NUMBER OF ATTENUATORS BEING FURNISHED FOR THE SPECIFIC TCP.
RELOCATE/REUSE TMA/TA - THE NUMBER OF ATTENUATORS BEING REUSED FROM A PREVIOUS TCP FOR THE SPECIFIC TCP.
TOTAL TMA/TA PER SET UP = (FURNISH TMA/TA) + (RELOCATE/REUSE TMA/TA)

DURATION OF TMA/TA SET UP - THE NUMBER OF DAYS THE ATTENTUATORS WILL BE USED FOR THE SPECIFIC TCP.
TMA/TA (STATIONARY) = (TOTAL TMA/TA PER SET UP) X (THE DURATION OF TMA/TA SET UP)
TMA/TA (MOBILE OPERATION) = (TOTAL TMA/TA PER SET UP) X (THE DURATION OF TMA/TA SET UP)

TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA) SUMMARY SHEET

FILE: tma.dgn	DN: T×D	TC	CK:	1	CK:	
© T×DOT	CONT	SE	СТ ЈОВ		ΗIG	HWAY
REVISIONS	0073	0	2 C	88,ETC	US	281
3/2018	DIST		C	COUNTY		
	SAT			BEXAR		
	FEDERA	L A	ΙD	PROJECT	SHEE	T NO.
	SEE	TIT	LΕ	SHEET	1	2



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0073-02-088

DISTRICT San Antonio **HIGHWAY** US 281


COUNTY Atascosa, Bexar


Report Created On: Mar 28, 2024 2:46:18 PM

		CONTROL SECTION	N JOB	0073-02	-088	0073-0	3-072	0073-0	4-051	_	
		PROJI	ECT ID	A00203	288	A0020	3289	A0020	3292		
		CC	YTNUC	Веха	ır	Atasc	osa	Ataso	osa	TOTAL EST.	TOTAL FINAL
		HIG	HWAY	US 28	31	US 2	81	US 2	281		
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	132-6021	EMBANKMENT (VEHICLE)(ORD COMP)(TY C)	CY	18.000		203.000		85.000		306.000	
	150-6002	BLADING	HR	13.000		175.000		68.000		256.000	
	164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1,723.000		19,458.000		8,044.000		29,225.000	
	164-6051	DRILL SEED (TEMP)(WARM OR COOL)	SY	1,723.000		19,458.000		8,044.000		29,225.000	
	168-6001	VEGETATIVE WATERING	MG	26.880		303.530		125.490		455.900	
	169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1,723.000		19,458.000		8,044.000		29,225.000	
	432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	72.000		812.000		334.000		1,218.000	
	500-6001	MOBILIZATION	LS	1.000						1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	1.000		3.000		2.000		6.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF			1,448.000		900.000		2,348.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF			1,448.000		900.000		2,348.000	
	506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF			320.000				320.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF			320.000				320.000	
	543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	2,584.000		29,188.000		12,065.000		43,837.000	
	543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EA	3.000		51.000		14.000		68.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000		2.000		6.000	
	6185-6002	TMA (STATIONARY)	DAY	7.000		50.000		30.000		87.000	
	18	LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000						1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000						1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000						1.000	



DISTRICT	COUNTY	CCSJ	SHEET
San Antonio	Bexar	0073-02-088	13






JUSTIN W. CLARK JUSTIN W. CLARK, P.E. APPROVAL CILMER D. GASTON BO472 GILMER D. GASTON GILMER D. GASTON GILMER D. GASTON GILMER D. GASTON BO472 J3/26/2024 J3/26/2024 DATE


NOTES:

- 1. FOR ADDITIONAL INFORMATION ON CABLE BARRIER AND FOUNDATION DETAILS, SEE APPLICABLE STANDARDS.
- 2. MOW STRIPS SHALL BE REINFORCED WITH (WIRE MESH OR SYNTHETIC FIBER), AS SHOWN ON THE PLANS AND WILL BE PAID FOR UNDER THE PERTINENT BID ITEM. REINFORCED CONCRETE SHALL BE PLACED IN ACCORDANCE WITH ITEM 432, "RIPRAP". THE USE OF SYNTHETIC FIBER IN LIEU OF STEEL REINFORCING IS ACCEPTABLE PROVIDED THE FIBER PRODUCER IS ON THE DEPARTMENT MATERIAL PRODUCER LIST (MPL), MAINTAINED BY TXDOT, CONSTRUCTION DIVISION.
- 3. THE CABLE BARRIER SYSTEM(S) SELECTED FOR EACH PROJECT SHALL BE INSTALLED BASED ON THE STANDARDS, GUIDELINES, AND RECOMMENDATIONS PROVIDED BY THE SELECTED MANUFACTURER(S) OF EACH INDIVIDUAL SYSTEM.
- 4. USE CLASS "A" CONCRETE IN ACCORDANCE WITH ITEM 421.



CABLE BARRIER
MOW STRIP DETAIL

NTS



CABLE BARRIER MOW STRIP

SECTION A-A

NTS

TYPICAL SECTIONS

DGN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	14

REV. NO, DATE DESCRIPTION BY


PAPE-DAWSO ENGINEERS


SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000

Texas Department of Transportation © 2024

US 281: CABLE BARRIER

SHEET 1 OF 3





REV. NO. DATE DESCRIPTION BY

PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM MAZO I TEXAS SURVEYING FIRM #10028000




US 281: CABLE BARRIER

TYPICAL SECTIONS


SHEET 2 OF 3

l											
DGN:	FED. RD. DIV. NO.	STATE	FEDER	FEDERAL AID PROJECT NO.							
CHK DGN:	6	TEXAS	SEE 1	TITLE S	HEET	US 281					
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.					
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	15					



NTS STA 2104+18 TO STA 2123+37





PAPE-DAWSON **ENGINEERS**

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000



US 281: CABLE BARRIER

TYPICAL SECTIONS

SHEET 3 OF 3

N:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.
(N:	6	TEXAS	SEE	TITLE S	SHEET	US 281
G:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
(3:	SAT	BEXAR	0073	02	088,ETC	16

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE REQUIREMENTS OF ITEM 7, "LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC", OF THE STANDARD SPECIFICATIONS. IN ADDITION TO THESE REQUIREMENTS, THE FOLLOWING PROVISIONS SHALL ALSO GOVERN ON THIS CONTRACT:

GENERAL

- (1) TRAFFIC MUST BE HANDLED THROUGHOUT THE PROJECT DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SAFE AND COMFORTABLE PASSAGE FOR VEHICULAR AND PEDESTRIAN TRAFFIC WITH MINIMAL INCONVENIENCE TO THE PUBLIC, AS SHOWN IN THE PLANS OR AS DIRECTED/APPROVED BY THE ENGINEER.
- (2) THE CONTRACTOR MAY PROPOSE/RECOMMEND MODIFICATIONS TO THE SEQUENCE OF WORK FOR CONSIDERATION BY THE ENGINEER. ANY MAJOR RECOMMENDED MODIFICATION BY THE CONTRACTOR SHALL INCLUDE ANY CHANGES TO THE VARIOUS BID ITEMS, IMPACT TO TRAFFIC, EFFECT OF OVERALL PROJECT IN TIME AND COST, ETC. IF THIS PROPOSAL IS IMPLEMENTED, THE CONTRACTOR WILL BE RESPONSIBLE FOR DEVELOPING DETAILED PLAN SHEETS TO BE SEALED BY
- (3) A LICENSED PROFESSIONAL ENGINEER FOR INCLUSION WITH THE CHANGE ORDER. THE CONTRACTOR CANNOT PROCEED WITH ANY CONSTRUCTION OPERATIONS BASED ON A REVISED PHASE/SEQUENCE UNTIL WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER. IF AT ANY TIME DURING CONSTRUCTION THE CONTRACTOR'S PROPOSED PLAN OF OPERATION FOR HANDLING TRAFFIC DOES NOT PROVIDE FOR SAFE AND COMFORTABLE MOVEMENT, THE CONTRACTOR WILL IMMEDIATELY CHANGE THEIR OPERATION TO CORRECT THE UNSATISFACTORY CONDITION.
- (4) DO NOT STORE ANY CONSTRUCTION MATERIAL OR EQUIPMENT AT ANY LOCATION THAT WILL CONSTITUTE HAZARD AND WILL ENDANGER TRAFFIC. DO NOT PLACE SPOILS, EQUIPMENT, ETC. WITHIN THE CENTER MEDIAN. POSITIVE FLOW MUST BE MAINTAINED AT ALL TIMES
- (5) TEMPORARY DRAINAGE IS THE RESPONSIBILITY OF THE CONTRACTOR.
- (6) COORDINATE WITH ADJACENT PROJECTS.

TRAFFIC CONTROL PLAN SEQUENCE OF WORK

- (1) THIS PROJECT WILL BE CONSTRUCTED IN ONE PHASE (2 STEPS). BEFORE THE COMMENCEMENT OF EACH PHASE, INSTALL ADVANCE WARNING SIGNS, TEMPORARY SIGNS AND BARRICADES AS SHOWN ON THE PLANS AND/OR AS DIRECTED/APPROVED BY THE ENGINEER. DAILY LANE CLOSURES WILL BE USED IN ACCORDANCE WITH STATE TCP STANDARDS. DROP OFF CONDITIONS OF GREATER THAN 2" MUST HAVE A 3:1 SLOPE AT THE END OF EACH DAY, AS WELL AS THROUGHOUT THE PROJECT WHERE ACCESS TO ADJACENT PROPERTIES IS ALLOWED TO DRIVEWAYS AND SIDE STREETS. PLACE PCMS 10 DAYS IN ADVANCE OF STARTING WORK AT FACH LOCATION
- (2) PREPARING ROW / REMOVAL OF EXISTING ITEMS TO BE DONE ONLY IN AREAS WHERE WORK IS OCCURRING, AS PER THE PHASES NOTED BELOW.
- (3) THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE REQUIREMENTS OF ITEM 7, "LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC" AND ITEM 502, "BARRICADES, SIGNS, AND TRAFFIC HANDLING", OF THE STANADARD SPECIFICATIONS, AND TO THE GENERAL NOTES
- (4) A SEGMENT MUST BE COMPLETED PRIOR TO BEGINNING WORK ON ANOTHER SEGMENT. PRIOR TO BEGINNING WORK ON ANOTHER SEGMENT, THE TRAFFIC MUST BE BROUGHT TO FULL OPERATION. ALL BID ITEM WORK FOR EACH SEGMENT MUST BE COMPLETED BEFORE MOVING TO THE SUBSEQUEST LOCATION. THIS INCLUDES COMPLETING VEGETATION ITEMS, PUNCHLIST AND CLEAN-UP ITEMS.
- (5) A BRIEF DESCRIPTION OF THESE PHASES ARE AS FOLLOWS:

PHASE 1:

- (1) MOBILIZATION.
- (2) INSTALL ADVANCE WARNING SIGNS, TEMPORARY SIGNS, CONSTRUCTION SIGNS, BARRICADES, CHANNELIZING DEVICES AS SHOWN ON THE TYPICAL TRAFFIC CONTROL PLAN.
- (3) CLOSE THE INSIDE LANE IN ONE DIRECTION (NEAR THE PROPOSED CABLE BARRIER) AND THE SHOULDER IN THE OTHER DIRECTION AS SHOWN IN THE TCP TYPICAL SECTIONS.
- (4) INSTALL MOW STRIP AND CABLE BARRIER POST FOUNDATIONS.
- (5) OPEN ALL LANES AND SHOULDERS DURING NON-WORKING HOURS.

PHASE 1 STEP 2:

- (1) INSTALL ADVANCE WARNING SIGNS, TEMPORARY SIGNS, CONSTRUCTION SIGNS, BARRICADES, CHANNELIZING DEVICES AS SHOWN ON THE TYPICAL TRAFFIC CONTROL PLAN.
- (2) CLOSE THE INSIDE SHOULDERS IN BOTH DIRECTIONS AS SHOWN IN THE TCP TYPICAL SECTIONS.
- (3) INSTALL CABLE BARRIER POSTS AND CABLES.
- (4) OPEN ALL LANES AND SHOULDERS DURING NON-WORKING HOURS.
- (5) PERFORM FINAL CLEANUP.

SAFETY:

THE CONTRACTOR WILL PROVIDE, CONSTRUCT AND MAINTAIN BARRICADES AND SIGNS IN ACCORDANCE WITH STATE STANDARDS BC (1-2)-21. ANY SIGNS REQUIRED THAT ARE NOT DETAILED IN THE STANDARD SHEETS SHALL BE IN CONFORMANCE WITH STATE STANDARDS BC (1-2)-21. ANY SIGNS REQUIRED THAT ARE NOT DETAILED IN THE STANDARD SHEETS SHALL BE IN CONFORMANCE WITH THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AND THE "STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS."

BARRICADES AND WARNING SIGNS SHALL BE PLACED AS INDICATED ON THE PLANS. THIS SHALL BE CONSIDERED THE MINIMUM REQUIRED TO PROVIDE FOR THE SAFETY OF TRAFFIC DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN OTHER BARRICADES AND SIGNS DEEMED NECESSARY BY THE ENGINEER OR AS DIRECTED BY FIELD CONDITIONS, TO PROVIDE FOR THE PASSAGE OF TRAFFIC IN SAFETY AT ALL TIMES. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN FLAGGERS AS DIRECTED/APPROVED BY THE ENGINEER, AT SUCH POINTS, AND FOR SUCH PERIODS OF TIME AS MAY BE REQUIRED, TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC AND THE CONTRACTOR'S PERSONNEL. THE CONTRACTOR SHALL KEEP THE ROADWAY CLEAN AND FREE OF DIRT OR OTHER MATERIALS DURING HAULING OPERATIONS. IF THE CONTRACTOR SOR SONT MAINTAIN A CLEAN ROADWAY, THEY SHALL CONSTRUCTION OPERATIONS, WHEN DIRECTED BY THE ENGINEER. TO CLEAN THE ROADWAY TO THE SATISFACTION OF THE ENGINEER.

HAULING EQUIPMENT:

THE USE OF RUBBER-TIRED EQUIPMENT WILL BE REQUIRED FOR MOVING DIRT OR OTHER MATERIALS ALONG OR ACROSS PAVEMENTED SURFACES. WHERE THE CONTRACTOR DESIRES TO MOVE ANY EQUIPMENT NOT LICENSED FOR OPERATION ON PUBLIC HIGHWAYS, ON OR ACROSS PAVEMENT. THEY SHALL PROTECT THE PAVEMENT FROM DAMAGE AS DIRECTED/APPROVED BY THE ENGINEER. THROUGHOUT CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL BE REQUIRED TO CONDUCT THEIR HAULING OPERATIONS IN A MANNER SUCH THAT VEHICLES WILL NOT HAUL OVER PREVIOUSLY RECOMPACTED SUBGRADE OR COMPACTED BASE MATERIAL, EXCEPT IN SHORT SECTIONS FOR DUMPING MANIPULATIONS.

FINAL CLEAN UP:

UPON COMPLETION OF THE WORK AND BEFORE FINAL ACCEPTANCE AND FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL CLEAR AND REMOVE FROM THE SITE ALL SURPLUS AND DISCARDED MATERIALS AND DEBRIS OF EVERY KIND AND LEAVE THE ENTIRE PROJECT IN SMOOTH, NEAT AND SIGHTLY CONDITION.

PAYMENT:


ALL BARRICADES, SIGNS, AND FLAGGERS SHALL BE SUBSIDIARY TO ITEM 502 BARRICADES, SIGNS AND TRAFFIC HANDLING. ALL EROSION AND SEDIMENT CONTROL DEVICES WILL BE PAID FOR UNDER ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS. ALL WORK ZONE PAVEMENT MARKINGS WILL BE PAID FOR UNDER ITEM 662 WORK ZONE PAVEMENT MARKINGS. ALL OTHER WORK AND MATERIALS SHALL BE SUBSIDIARY TO THE VARIOUS SID ITEMS UNLESS OTHERWISE INDICATED IN THE PLANS.



REV. NO. DATE DESCRIPTION BY



SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

TCP NARRATIVE

SHEET 1 OF 1

GN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.
HK GN:	6	TEXAS	SEE	TITLE S	SHEET	US 281
WG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
HK WG:	SAT	BEXAR	0073	02	088.ETC	17

					PROJ	ECT LIMIT S	IGNING							
	ROAD WORK AHEAD	END WORK ZONE	EN D Road Work	NAME ADDRESS CITY STATE CONTRACTOR	BEGIN WORK ZONE	Give Us A BRAKE	OBEY WARNING SIGNS STATE LAW	WHEN WORKERS ARE PRESENT	TRAFFIC FINES DOUBLE	ONE LANE ROAD 500 FT	NARROW LANES AHEAD	STAY ALERT TALK OR TEXT LATER	DO NOT PASS	NO CENTER LINE
LOCATION	CW20-1D (36"×36")	G20-2bT (36"x18")	G2-2 (36"x18")	G20-6T (48"x30")	G20-9TP (24"×24")	CW21-1T (36"×36")	R20-3T (48"×42")	R20-5aTP (24"×12")	R20-5T (24"x30")	CW20-4C (36"×36")	CW20-8T (36"×36")	G20-10T (60"×48")	R4-1 (24"×30")	CW8-12 (36"×36")
BEGINNING OF THE PROJECT	X			X	X		X	X	X	X		X		
AND ENTERING SIDE STREETS														
LEAVING PROJECT LIMITS AND		X	X											
EXITING SIDE STREETS														
USED THROUGHOUT PROJECT	X					X					X		X	X
AS DIRECTED BY THE ENGINEER														

					PROJ	ECT LIMIT S	IGNING							
	ROAD	SPEED LIMIT 18	XX	ROAD WORK NEXT X MILES	ROAD WORK	ROAD CLOSED						LEFT SHOULDER CLOSED	1/2 MILE	LEFT LANE CLOSED
LOCATION	CW5-1 (36"×36")	R2-1 (24"×30")	CW13-1P (24"x24")	G20-1bTL (72"x24")	G20-1bTR (72"x24")	R11-2 (48"×30")	Р.С.М.В.	ARROW BOARD	TY 3 BARRICADE	VERTICAL PANEL	PLASTIC BARRELS	CW21-5aL (48"X48")	CW16-3aP (30"X12")	CW20-5TL (48"X48")
BEGINNING OF THE PROJECT			X	X	Х									
AND ENTERING SIDE STREETS														
LEAVING PROJECT LIMITS AND														
EXITING SIDE STREETS														
USED THROUGHOUT PROJECT	X	Х	X			X	Х	X	X	Х	X	X	X	Х
AS DIRECTED BY THE ENGINEER													X	X








SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375,9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER


SCHEDULE OF BARRICADES AND DEVICES

GN:	FED. RD. DIV. NO.	STATE	FEDER	HIGHWAY NO.		
HK GN:	6	TEXAS	SEE	TITLE S	SHEET	US 281
WG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
HK wc•	SAT	BEXAR	0073	02	088.ETC	18




TCP TYPICAL SECTIONS

PHASE 1 - INSTALLING MOW STRIP, CABLE
BARRIER POST FOUNDATIONS



TCP TYPICAL SECTIONS

PHASE 1 - STEP 2 - INSTALLING CABLE
BARRIER POSTS AND TENSIONING THE CABLE



REV. NO.	DATE	DESCRIPTION	BY					

PAPE-DAWSON ENGINEERS SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS


2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

TCP TYPICAL SECTIONS

N:	FED. RD. DIV. NO.	STATE	FEDER	HIGHWAY NO.		
: 4:	6	TEXAS	SEE	TITLE S	SHEET	US 281
G:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
: :	SAT	BEXAR	0073	02	088,ETC	19



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any Kind is made by TXD01 for any purpose whatsoever. TXD01 assumes no responsibility for the conversion ofw.Abl&r&HandoRdnto other formats or for incorrect results or <u>damages resulting from</u> its use. END ROAD WORK See Note 13 Shadow Vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights-Shadow Vehicle with TMA and ¥,ŏ\ ≓ high intensity rotating, flashing, oscillating or strobe lights See note and 7 48" X 48' (See note 10) 1000 FT CW16-2aP 30" X 12 1/3 See note and 7-RIGHT LANE CLOSED CW20-5TR 48" X 48" (See note 10) 1/2 MILE See note CW16-3aP and 7 RIGHT LN X X X XM CLOSED XXXXXXXX AHEAD See note PHASE 1 PHASE 2 1 and 7 📥 -(See note 6) ROAD WORK 1 MILE CW20-1F See note 48" X 48' 1 and 7 🔼 TCP (6-1a) TCP (6-1b) TYPICAL FREEWAY TYPICAL FREEWAY ONE LANE CLOSURE TWO LANE CLOSURE

	LEGEND								
	Type 3 Barricade		Channelizing Devices						
□坤	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)						
•	Sign	7	Traffic Flow						
\Diamond	Flag	4	Flagger						

Posted Speed	Formula	Desirable Taper Lengths "L"			Spaci Channe		Suggested Longitudinal Buffer Space
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	"B"
45		450′	4951	540′	45′	90′	195′
50		500′	550′	600′	50′	100′	240′
55	L=WS	550′	605′	660′	55′	110′	295′
60] ["]	600′	660′	720′	60′	120′	350′
65		650′	715′	780′	65′	130′	410′
70		700′	770′	840′	70′	140′	475′
75		750′	825′	900′	75′	150′	540′
80		800′	880′	960′	80′	160′	615′

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	1	1	1					

GENERAL NOTES

END ROAD WORK G20-2 48" X 24"

See Note 13

CW20-5TR 48" X 48" (See note 10)

CW20-5TR

CW20-5aTR

(See note 10)

XXXX

XXXX

X X X X

PHASE 2

48" X 48"

1000 FT

CW16-2aP 30" X 12

CLOSED

1000 FT

CW16-2aP 30" X 12"

RIGHT LANES

CLOSED

1/2 MILE

CW16-3aP 30" X 12

ROAD

WORK

1 MILE

CW20-1F

2 RIGHT

LANES

CLOSED

PHASE 1

×ÿŲĘ

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- 2. Drums or 42"cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- 3. All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- 4. The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- 5. Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- 6. Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- 7. Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- 8. The number of closed lanes may be increased provided the spacing of traffic control
- devices, taper lengths and tangent lengths meet the requirements of the TMUTCD. 9. Warning signs for intermediate term stationary work should be mounted at 7^\prime to the bottom of the sign.
- 10. Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- 11. When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- 12. For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- 13. The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shal be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.



TRAFFIC CONTROL PLAN FREEWAY LANE CLOSURES

TCP(6-1)-12

	. •		_		-	_		
FILE:	tcp6-1.dgn	DN: T>	OOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
© TxD0T	February 1998	CONT	SECT	т јов		н	HIGHWAY	
8-12	REVISIONS	0073	02	088,ETC (US	281	
0-12		DIST	COUNTY			SHEET NO.		
		SAT		BEXA	?		21	

3/19/2024 9:37:06 PM P:\122\96\02\TG8K\$\13 US 281 0

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12



Standard


BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS

BC(1)-21

	DC	٠,	•	~ '			
FILE:	bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDO</td><td>T CK: TXDOT</td></dot<>	ck: TxDOT	DW:	TxDO	T CK: TXDOT
© ⊺xD0T	November 2002	CONT	SECT	JOB			HIGHWAY
4-03 7-13 9-07 8-14		0073	02	088,ETC US		JS 281	
		DIST	COUNTY			SHEET NO.	
5-10	T 0 11		BEXAR			22	

٣.

9:37:07



- # May be mounted on back of "ROAD WORK AHEAD"(CW20-1D) sign with approval of Engineer.
- 1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- 4. The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- 5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- 6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

BEGIN T-INTERSECTION \times \times G20-9TP ZONE ★ X R20-5T FINES DOLIBL X R20-5aTP WHEN WORKERS ARE PRESENT ROAD WORK <⇒ NEXT X MILES FND * X G20-25T WORK ZONE G20-1bTI INTERSECTED 1000' -1500' Hwy 1 Block - City 1000'-1500' - Hwy 1 Block - City ROADWAY \Rightarrow ROAD WORK G20-1bTR NEXT X MILES ⇒ 80' WORK ZONE G20-26T X X BEGIN WORK \times \times G20-9TP ZONE TRAFFI G20-6T * * R20-5T FINES DOUBLE \times \times R20-5aTP ROAD WORK G20-2

CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING $^{\text{I,5,6}}$

SIZE

Sign Number or Series	Conventional Road	Expressway/ Freeway					
CW20 ⁴ CW21 CW22 CW23 CW25	48" × 48"	48" × 48"					
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" × 36"	48" × 48"					
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" × 48"					


Posted Speed	Sign∆ Spacing "X"
MPH	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500 ²
60	600²
65	700 ²
70	800 ²
75	900 ²
80	1000 ²
*	* 3

SPACING

- * For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- \triangle Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. $36" \times 36"$ "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design



X X G20-5T

★ ★G20-9TF ZONE STAY ALERT OBEY SPEED ROAD WORK TRAFFIC ROAD LIMIT ROAD ROAL ¥ ¥R20-5T FINES SIGNS WORK CLOSED R11-2 CW1 - 4 WORK DOUBLE STATE LAW ⅓ MIL TALK OR TEXT LATER AHEAD \times \times R20-5aTF Type 3 \times \times G20-6T R20-3 R2-1 Barricade or CW20-1D CW13-1P CONTRACTOR CW20-1F channelizina devices \triangleleft -CSJ Limi Channelizina \Rightarrow B SPEED R2-1 END ROAD WORK LIMIT END WORK ZONE G20-26T * G20-2 * *

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer.

- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- imes CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D)sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at $\Diamond \Diamond$ the end of the work zone.

LEGEND						
горов Туре 3 Barricade						
000 Channelizing Devices						
•	Sign					
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.					

SHEET 2 OF 12



Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2) - 21

ILE:	bc-21.dgn	DN: T>	OOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
C) TxDOT	November 2002	CONT	SECT	JOB		HIGHWAY		
REVISIONS		0073	02	088,ETC (U:	JS 281	
9-07	8-14	DIST	COUNTY			SHEET NO.		
7-13	5-21	SAT	BEXAR			23		

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present. signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:

40 mph and greater 0.2 to 2 miles

35 mph and less

0.2 to 1 mile

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- 6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC(3)-21

Ē:	bc-21.dgn	DN: Tx[)OT	ck: TxDOT	DW:	TxDOT	ck: TxDOT		
TxDOT	November 2002	CONT	SECT	JOB		ні	HIGHWAY		
	8-14 5-21	0073	02	088,ET	C	US	US 281		
9-07 7-13		DIST	DIST COUNTY				SHEET NO.		
1-13		SAT		BEXA		24			

0'-6'


Paved

shou I der


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS 12′ min. ROAD ROAD ROAD ROAD WORK minimum WORK WORK WORK from AHEAD AHEAD AHEAD curb AHEAD min. * * | 25 7.0' min. 7.0' min. 9.0' max. 7.0' min. 9.0' max. 6.0' min. 9.0' max. greater Paved shou I der

* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

* X When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

STOP/SLOW PADDLES

- 1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24". STOP/SLOW paddles shall be retroreflectorized when used at night.
- 3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING RE	QUIREMEN ⁻	TS (WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{fl} OR C _{fl} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- 1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- 2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- 4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports. the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- 9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - a. Long-term stationary work that occupies a location more than 3 days.
 - Intermediate-term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration work that occupies a location up to 1 hour.
- e. Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plagues mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- 3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- 2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background. 3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL} , shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- 1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- 2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- 3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- 4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs. Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a

constant weight.

Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.

Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used. Rubber ballasts designed for channelizing devices should not be used for

ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or

hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face. SHEET 4 OF 12



BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

Traffic Safety Division Standard

BC(4) - 21


FILE:	bc-21.dgn	DN: To	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
© TxD0T	November 2002	CONT	CONT SECT JOB			HIGHWAY	
	REVISIONS	0073	02	088,ETC		US 281	
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	SAT		BEXA	₹ _		25

9:37:08

3/19/2024 P:\122\96\

¥ Maximum 12 sq. ft. of ★ Maximum wood sign face 21 sq. ft. of post sign face X4×4 4×4 4×4 wood block block 72" post __<u>\</u> Top Length of skids may $\times \times 4 \times 4$ be increased for wood additional stability. See BC(4) post for sign Top 2×4 × 40" 30" See BC(4) height 24" 2x4 brace requirement for sign height 3/8" bolts w/nuts requirement or 3/8" x 3 1/2" (min.) lag screws Front 4x4 block 40" 4x4 block 36" Side Front SKID MOUNTED WOOD SIGN SUPPORTS * LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

SINGLE LEG BASE




GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support.

The maximum sign square footage shall adhere to the manufacturer's recommendation.

Two post installations can be used for larger signs.



WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
 - \star See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE: bc-21.dgn	DN: To	<dot< th=""><th>ck: TxDOT</th><th>DW:</th><th>TxDOT</th><th>ck: TxDOT</th></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
CTxDOT November 2002	CONT	SECT	JOB		н	HIGHWAY	
	0073	02	088,ET	С	U:	5 281	
9-07 8-14	DIST		COUNTY			SHEET NO.	
7-13 5-21	SAT		BEXAR	₹		26	

SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS
*LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

32′

of this standard is governed by the "Texas Engineering Practice Act". No warranty of by TxDOI for any purpose whatsoever. TxDOI assumes no responsibility for the conversional to other formats or for incorrect results or damages resulting from its use.

PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- 2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message. 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT"
- on a PCMS. Drivers do not understand the message. 13. Do not display messages that scroll horizontally or vertically across
- the face of the sian. 14. The following table lists abbreviated words and two-word phrases that
- are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canno+	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	F	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle		South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD ST
Expressway	EXPWY	Street Sunday	SUN
XXXX Feet	XXXX FT		PHONE
Fog Ahead	FOG AHD	Telephone	TEMP
Freeway	FRWY, FWY	Temporary Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving			
Hazardous Material		Travelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour(s)	HR. HRS	Vehicles (s)	VEH, VEHS
Information	INFO	Warning	WARN
It Is	ITS	Wednesday	WED
Junction	JCT	Weight Limit	WT LIMIT
Left	LFT	West Westbound	(route) W
Left Lane	LFT LN	Westbound Wet Pavement	WET PVMT
Lane Closed	LN CLOSED		
Lower Level	LWR LEVEL	Will Not	WONT
Maintenance	MAINT		

9:37:09)2\Tqsks\

3/19/2024 P:\122\96

designation # IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES (The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp	Closure List	Other Co	ndi	tion List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT		ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT		LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT		TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT		CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT		UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE		ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX		ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT		US XXX EXIT X MILES

XXXXXXXX BLVD * LANES SHIFT in Phase 1 must be used with STAY IN LANE in P CLOSED

TRAFFIC

SIGNAL

XXXX FT

Phase 2: Possible Component Lists

А		Effect on Travelist	Location List	Warning List	* * Advance Notice List
	MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
	DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- 27 X PM-X AM
	USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
	STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
	TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
	WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
	EXPECT DELAYS	PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
	REDUCE SPEED XXX FT	END SHOULDER USE		DRIVE WITH CARE	NEXT TUE AUG XX
*	USE OTHER ROUTES	WATCH FOR WORKERS			TONIGHT XX PM- XX AM
Phase 2.	STAY IN LANE	- -	* * Se	ee Application Guideline	es Note 6.

APPLICATION GUIDELINES

X LANES

CLOSED

TUE - FRI

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- 2. Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- 3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary.
- 7. FT and MI. MILE and MILES interchanged as appropriate.
- 8. AT. BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

LANES

SHIFT

FULL MATRIX PCMS SIGNS


MALL

DRIVEWAY

CLOSED

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6) - 21


FILE:	bc-21.dgn	DN: T>	OOT	ck: TxDOT	DW:	TxD0	T ck: TxD0	Τ
C TxDOT	November 2002	CONT	SECT	ст јов		HIGHWAY		
	REVISIONS	0073	02	088,ET	С	Ĺ	JS 281	٦
9-07	8-14	DIST	T COUNTY			SHEET NO.	٦	
7-13	5-21	SAT		BEXA	₹		27	

- 1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of pregualified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- 4. Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10.Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- 11. Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB)

manufacturer's recommendations.




DELINEATION OF END TREATMENTS


END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

WARNING LIGHTS

- 1. Warning lights shall meet the requirements of the TMUTCD.
- 2. Warning lights shall NOT be installed on barricades.
- 3. Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control
- devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices. 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- 3. A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the toper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- 5. Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacina for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- 2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- 4. The Flashing Arrow Board should be able to display the following symbols:



- 5. The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- 9. The sequential arrow display is NOT ALLOWED.
 10. The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- 11. The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
 12. A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
 13. A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility,
- flash rate and dimming requirements on this sheet for the same size arrow.
- 14. Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS										
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE							
В	30 x 60	13	3/4 mile							
С	48 × 96	15	1 mile							

ATTENTION Flashing Arrow Boards shall be equipped with automatic dimmina devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- 1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted n the plans
- 5. A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- 6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC(7) - 21

ILE:	bc-21.dgn	DN: To	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) T×DOT	November 2002	CONT	SECT	JOB		HIGHWAY	
	REVISIONS 8-14 5-21	0073	02	088,ET	088,ETC (S 281
9-07		DIST	DIST COUNTY			SHEET NO.	
7 - 1 3		SAT	BEXAR			28	

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWYTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:

- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- to be held down while separating the drum body from the base.


 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10.Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.





DETECTABLE PEDESTRIAN BARRICADES

- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5. Worning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- 3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- 8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

		•	_				
LE: bc-21.dgn	DN: T>	OOT	ck: TxDOT	DW:	TxDOT	ck: TxDOT	
TxDOT November 2002	CONT	SECT	JOB		ні	GHWAY	
	0073	02	088,ET	C	US	281	
1-03 8-14 3-07 5-21	DIST	COUNTY				SHEET NO.	
7-13	SAT		BEXA	₹ _		29	


9:37:10






- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
 Self-righting supports are available with portable base.
- Self-righting supports are available with portable base See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)



- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)




- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by erront vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final povement surfaces, including povement surface discoloration or surface integrity. Driveable bases shall not be permitted on final povement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

Min.

36

Fixed Base w/ Approved Adhesive

(Driveable Base, or Flexible

Support can be used)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	Desirable Taper Lengths XX			Suggested Maximum Spacing of Channelizing Devices		
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	2	150′	165′	180′	30′	60′	
35	$L = \frac{WS^2}{60}$	205′	225′	245′	35′	70′	
40	60	265′	295′	320′	40′	80′	
45		450′	495′	540′	45′	90′	
50		500′	550′	600′	50′	100′	
55	L=WS	550′	605′	660′	55′	110′	
60		600′	660′	720′	60′	120′	
65		650′	715′	780′	65 <i>′</i>	130′	
70		700′	770′	840′	70′	140′	
75		750′	825′	900′	75′	150′	
80		800′	800′ 880′ 960′		80′	160′	

XTaper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF
CHANNELIZING DEVICES AND
MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21


			,				
ILE:	bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C) TxDOT	November 2002	CONT	SECT	JOB		н	GHWAY
REVISIONS		0073	02	088,ET	C	US	281
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	SAT		BEXA	₹ _		30

TYPE 3 BARRICADES

- Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- 2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- 6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- 7. Warning lights shall NOT be installed on barricades.
- 8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION

Two-Piece cones



3"-4"

4" min. orange

2" min.

4" min. white

4" min. orange


4" min. white

6" min. 6" min. 2" min. 4" min. 2" max. 3" min. 2" to 6" 3" min. 28" min.

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

One-Piece cones

Tubular Marker



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

 \Rightarrow

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- 3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- 7. Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

Traffic Safety Division Standard

BC(10)-21

			•				
ILE:	bc-21.dgn	DN: T	<dot< td=""><td>ck: TxDOT</td><td>DW:</td><td>TxDOT</td><td>ck: TxDOT</td></dot<>	ck: TxDOT	DW:	TxDOT	ck: TxDOT
C)TxDOT November 2002		CONT	SECT	JOB		HIGHWAY	
REVISIONS		0073	02	088,ET	C	U:	S 281
9-07	8-14 5-21	DIST		COUNTY			SHEET NO.
7-13		SAT		BEXA	₹ _		31

104

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing povement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- 4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- 7. All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- 5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Fnaineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10. Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - A. Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.
- Guidemarks shall be designated as: YELLOW - (two amber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIO	NS
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12




BARRICADE AND CONSTRUCTION
PAVEMENT MARKINGS

Traffic Safety Division Standard

BC(11) - 21

E: bc-21.dgn	DN: T>	OOT	ck: TxDOT	DW:	TxDO	CK: TXDOT	
TxDOT February 1998	CONT	SECT	JOB			HIGHWAY	
REVISIONS -98 9-07 5-21	0073	02	088,ET	C	U	IS 281	
-98 9-07 5-21 -02 7-13	DIST		COUNTY			SHEET NO.	
-02 8-14	SAT		BEXA	₹ _		32	




2-98 7-13 1-02 **8-14**

BEXAR




1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE. VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH THE FLOWLINE OF DITCH. CABLE BARRIERS LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANG. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE DITCHLINE, OFFSET OF AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED.




NOTES CONTINUED:
5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS
WITH, OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER. SHOWN ON PLANS)
9. DRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

TIEM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	11
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1056
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1056
0168-6001	VEGETATIVE WATERING	MG	16.47
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1056
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	44
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1584
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΔ	3

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 1000+00 TO STA 1020+00

SHEET 1 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDER	FEDERAL AID PROJECT NO.				
CHK DGN:	6	TEXAS	SEE	SEE TITLE SHEET				
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	34		



ES CONTINUED:
THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS
WITH, OR DAMAGE TO, THESE UTILITIES.
WITH, OR DAMAGE TO, THESE UTILITIES.
NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENCINEER.
DRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

100 150

UNIT QTY

SY 180

3.0

180

2.81

180

8

100

100

270

CY

SY

MG

LF

EΑ

PAPE-DAWSON **ENGINEERS**

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1020+00 TO STA 1040+00

SHEET 2 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	TATE FEDERAL AID PROJECT NO. H						
CHK DGN:	6	TEXAS	SEE	SEE TITLE SHEET					
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.			
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	35			




1. ALI RIGHT-OF-WAY LINES ARE APPROXIMATE, VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.6%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH
THE FLOW INE OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE
DITCHLINE, OFFSET OF AT LEAST 5 FEET FROM THE BOGE OF ILLUMINATION POLE IS RECCOMMENDED.




ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	11
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	997
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	997
0168-6001	VEGETATIVE WATERING	MG	15.55
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	997
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	42
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1495
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΔ	٦

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1040+00 TO STA 1060+00

	SHEET 3 O								
DGN:	FED. RD. DIV. NO.	STATE	FEDER	HIGHWAY NO.					
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET					
DWG:	DIST.	COUNTY	CONT. NO.	CONT. NO. SECT. NO. JOB NO.					
CHK DWG:	SAT	BEXAR	088,ETC	36					




SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER. THE TRAVELLANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE




WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS

ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	12
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1134
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1134
0168-6001	VEGETATIVE WATERING	MG	17.69
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1134
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	47
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1701
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΔ	2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000



US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 1060+00 TO STA 1080+00


SHEET 4 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	SEE TITLE SHEET				
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	37		




NOTES CONTINUED:
5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS WITH OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT, NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
9. DRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WEEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

LIEM	DESCRIPTION	UNII	QIT
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	2
0150-6002	BLADING	HR	2.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	199
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	199
0168-6001	VEGETATIVE WATERING	MG	3.10
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	199
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	8
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	298
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΔ	2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 1080+00 TO STA 1100+00

				5	SHEET 5 C	F 34
DGN:	DGN: FED. RD. STATE FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	38



IESE UTILITIES.

IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.

ILL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)

INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.


RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3.

RETENTION BLANKETS SHALL BE A MINIMU


COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS

DESCRIPTION 0132-6021 EMBANKMENT (VEHICLE) (ORD COMP) (TY C) CY 12 0150-6002 BLADING 0164-6035 DRILL SEEDING (PERM) (RURAL) (CLAY) SY 1185 0164-6051 DRILL SEED (TEMP) (WARM OR COOL) SY 1185 0168-6001 VEGETATIVE WATERING 18.49 0169-6001 SOIL RETENTION BLANKETS (CL 1) (TY A) SY 1185 49 0432-6066 RIPRAP (CL A) (MOW STRIP) (3 IN) CY 0506-6038 TEMP SEDMT CONT FENCE (INSTALL) 100 0506-6039 TEMP SEDMT CONT FENCE (REMOVE) 100 LF 20 0506-6040 BIODEG EROSN CONT LOGS (INSTL) (8") 0506-6043 BIODEG EROSN CONT LOGS (REMOVE) 20 0543-6002 CABLE BARRIER SYSTEM (TL-4) 0543-6020 CABLE BARRIER TERMINAL SECTION (TL-4) EA 2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1100+00 TO STA 1120+00

SHEET 6 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	TITLE S	ITLE SHEET			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088 , ETC	39		




1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE. VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES, TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH THE FLOWLINE OF DITCH, CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE BOTTOM OF STREET OF AT LEAST 5 FEET FROM THE BOTTOM OF STREET OF AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE BOTTOM OF STREET OF AT LEAST 5 FEET FROM THE BOTTOM OF STREET OF AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OF STREET FROM THE BOTTOM OF THE DITCHLINE.




ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	11
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1017
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1017
0168-6001	VEGETATIVE WATERING	MG	15.87
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1017
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	42
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1525
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1120+00 TO STA 1140+00

SHEET 7 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.			
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET		US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.			
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	40			




SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER. THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE S RECCOMMENDED. AND BY THE TRAVEL FOR THE SHORT OF THE SALE AS FROM THE BOTTOM OF THE SALE AS THE SALE AS




ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	12
0150-6002	BLADING	HR	10.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1158
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1158
0168-6001	VEGETATIVE WATERING	MG	18.06
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1158
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	48
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1737
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	3

LEGEND







PAPE-DAWSON **ENGINEERS**

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 1140+00 TO STA 1160+00

	SHEET 8 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.				
CHK DGN:	6	TEXAS	SEE	SEE TITLE SHEET						
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.				
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	41				




1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE. VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.6%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH THE FLOWLINE OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED.
4. UTILITY LOCATIONS ARE APPROXIMATE. ALL UTILITIES ARE SHOWN BASED ON AVAILABLE AS-BUILT DRAWINGS AND 811 UTILITY LOCATE. CONTRACTOR MUST FIELD VERIFY THE EXACT LOCATION OF EXISTING ROW, POLES, ELECTRICAL SERVICES, GROUND BOXES, AND OTHER PERTINENT ITEMS BEFORE COMMENCING WORK.

NOTES CONTINUED:


5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS
WITH, OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
9. DRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	10
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	972
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	972
0168-6001	VEGETATIVE WATERING	MG	15.16
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	972
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	41
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1458
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	3

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1160+00 TO STA 1180+00

	SHEET 9 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.				
CHK DGN:	6	TEXAS	SEE TITLE SHEET			US 281				
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.				
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	42				




1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE, VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH THE FLOWLINE OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED.
4. UITLITY LOCATIONS ARE APPROXIMATE. ALL UTLITIES ARE SHOWN BASED ON AVAILABLE AS-BUILT DRAWINGS AND 811 UTLITITY LOCATE. CONTRACTOR MUST FIELD VERIFY THE EXACT LOCATION OF EXISTING ROW, POLES, ELECTRICAL SERVICES, GROUND BOXES, AND OTHER PERTINENT ITEMS BEFORE COMMENCING WORK.




TIFM	DESCRIPTION	ITMU	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	12
0150-6002	BLADING	HR	10.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1166
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1166
0168-6001	VEGETATIVE WATERING	MG	18.19
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1166
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	49
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1749
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1180+00 TO STA 1200+00

SHEET 10 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.			
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET		US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.			
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	43			



SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER. THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE S. RECCOMMENDED.




WILL THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS


NOTES CONTINUED:
5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO WITH, OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER. SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED AT A MINIMUM OF 3. FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

DESCRIPTION 0132-6021 EMBANKMENT (VEHICLE) (ORD COMP) (TY C) 12 CY 0150-6002 BLADING 10.0 0164-6035 DRILL SEEDING (PERM) (RURAL) (CLAY) SY 1166 0164-6051 DRILL SEED (TEMP) (WARM OR COOL) SY 1166 0168-6001 VEGETATIVE WATERING 0169-6001 SOIL RETENTION BLANKETS (CL 1) (TY A) SY 1166 CY 49 0432-6066 RIPRAP (CL A) (MOW STRIP) (3 IN) 0543-6002 CABLE BARRIER SYSTEM (TL-4) LF 1749 0543-6020 CABLE BARRIER TERMINAL SECTION (TL-4) EA 2

LEGEND







PAPE-DAWSON **ENGINEERS**

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1200+00 TO STA 1220+00

SHEET 11 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.			
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281				
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.			
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	44			



1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE, VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH THE FLOWLING OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED.
4. LITLITY LOCATIONS ARE APPROXIMATE. VERIFY THE FXACT LOCATION



WITH, OR DAMAGE TO, THESE UTILITIES.

STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT, NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)


MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
DRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.

FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.


WILL THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS

TIFM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	12
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1143
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1143
0168-6001	VEGETATIVE WATERING	MG	17.83
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1143
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	48
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1714
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΔ	2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT


STA 1220+00 TO STA 1240+00

SHEET 12 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	45		


ES CONTINUED:
THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS WITH, OR DAMAGE TO, THESE UTILITIES.
STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENCINEER.
BRILL SEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED ATA MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	10
0150-6002	BLADING	HR	10.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	990
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	990
0168-6001	VEGETATIVE WATERING	MG	15.44
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	990
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	41
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1485
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EA	4

LEGEND







PAPE-DAWSON ENGINEERS

N

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1240+00 TO STA 1260+00


SHEET 13 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.			
CHK DGN:	6	TEXAS	SEE 1	TITLE S	HEET	US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.			
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	46			



TIFM	DESCRIPTION	ITMU	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	6
0150-6002	BLADING	HR	5.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	605
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	605
0168-6001	VEGETATIVE WATERING	MG	9.44
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	605
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	25
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	908
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	1







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT


STA 1260+00 TO STA 1280+00

	SHEET14 OF 34										
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.					
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET							
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.					
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	47					



1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE. VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH
THE FLOWLINE OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE


3. CABLET BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANG. CABLE BARRIERS SHALL BE PLACED AT LEAST 5 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED.
4. UTILITY LOCATIONS ARE APPROXIMATE. ALL UTILITIES ARE SHOWN BASED ON AVAILABLE AS BUILD DRAWINGS AND 811 UTILITY LOCATE. CONTRACTOR MUST FIELD VERIFY THE EXACT LOCATION




WITH, OR DAMAGE TO, THESE UTILITIES.

STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
BRILL SEEDING AND SOIL RETENTION BLANKEITS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 1280+00 TO STA 1300+00

SHEET 15 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	TITLE S	HEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	48		



LIGHT-OF-WAY LINES ARE APPROXIMATE, VERIFY LOCATIONS AS NECESSARY

CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH
THE FLOWLINE OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OF SET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE
DITCHLINE, OFFSET OF ATLEAST. SEET FROM THE LEGGE OF ILLUMINATION POLE IS RECCOMMENDED.

TED. T. DRAWINGS AND 811 UTILITY LOCATE. CONTRACTOR MUST FIELD VERIFY THE EXACT LOCATION REFORE COMMENCING WORK. INSTALL: -CABLE BARRIER TERMINAL SECTION CABLE BARRIER SYSTEM (TL-4) @ 750 LF

14.00' FROM INSIDE OF NB US 281 TRAVEL LANE
RIP RAP (MOW STRIP) @ 21 CY PI STATION S = 1314+19.74

DELTA = 5° 44′ 53.91" (LT)

DECREE OF CURVE = 1° 35′ 29.58"


TANGENT = 180.74

LENGTH = 361.18


RADIUS = 3,600.00 NB US = 3,600.00 = 1312+39.00 = 1316+00.18 PC STATION PT STATION 132 0 1311+00 1319+00 1318+00 1317+00 1316+00 1314+00 1315+00 \mathcal{C} Ż SB US 281 BEGIN INSTALL: CABLE BARRIER SYSTEM (TL-4) @ 1083 LF 14.00' FROM INSIDE OF SB US 281 TRAVEL LANE RIP RAP (MOW STRIP) @ 30 CY \forall INSTALL: CABLE BARRIER TERMINAL SECTION @1 EA NOTES CONTINUED:
5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO WITH, OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
9. DRILL SEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024. THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS

ITEM	DESCRIPTION	UNIT	QTY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	8
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	784
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	784
0168-6001	VEGETATIVE WATERING	MG	12.23
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	784
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	33
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1176
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΛ	マ

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1300+00 TO STA 1320+00


SHEET 16 OF 34									
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.			
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281				
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.			
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	49			



TIEM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	9
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	857
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	857
0168-6001	VEGETATIVE WATERING	MG	13.37
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	857
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	36
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1285
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	3







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1320+00 TO STA 1340+00


SHEET 17 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET		US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	50		



TIFM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	2
0150-6002	BLADING	HR	5.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	197
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	197
0168-6001	VEGETATIVE WATERING	MG	3.07
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	197
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	8
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	296
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	1







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1340+00 TO STA 1360+00


SHEET 18 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	51		



TIFM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	12
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1129
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1129
0168-6001	VEGETATIVE WATERING	MG	17.61
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1129
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	47
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1694
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800





US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 1360+00 TO STA 1380+00


	SHEET 19 OF 34							
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	52		





DESCRIPTION 0132-6021 EMBANKMENT (VEHICLE) (ORD COMP) (TY C) CY 0150-6002 BLADING SY 761 0164-6035 DRILL SEEDING (PERM) (RURAL) (CLAY 0164-6051 DRILL SEED (TEMP) (WARM OR COOL) SY 761 0168-6001 VEGETATIVE WATERING 0169-6001 SOIL RETENTION BLANKETS (CL 1) (TY A) SY 761 0432-6066 RIPRAP (CL A) (MOW STRIP) (3 IN) CY 32 0506-6038 TEMP SEDMT CONT FENCE (INSTALL) 48 0506-6039 TEMP SEDMT CONT FENCE (REMOVE) 48 40 0506-6040 BIODEG FROSN CONT LOGS (INSTL) (8" LF 0506-6043 BIODEG EROSN CONT LOGS (REMOVE 40 0543-6002 CABLE BARRIER SYSTEM (TL-4) 0543-6020 CABLE BARRIER TERMINAL SECTION (TL-4) EΑ LEGEND EXIST OVERHEAD ELECTRIC LINE OH C EXIST OVERHEAD COMMUNICATION LINE EXIST DRAINAGE STRUCTURE APPARENT R.O.W. PROPOSED CABLE BARRIER FENCE WITH 3' MOW STRIP TL-4 CABLE BARRIER TERMINAL TEMP SEDMT CONT FENCE \triangleleft TRAFFIC FLOW ARROWS DESIGN 118715 GILMER D. GASTON, P.E. 100 150 PAPE-DAWSON ENGINEERS SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 Texas Department of Transportation ©2024 US 281: CABLE BARRIER PROPOSED CABLE BARRIER LAYOUT STA 1400+00 TO STA 1420+00 SHEET 21 OF 34 FEDERAL AID PROJECT NO. 6 TEXAS SEE TITLE SHEET

DIST. COUNTY CONT. NO. SECT. NO. JOB NO. SHEET NO. SAT BEXAR 0073 02 088,ET0 54




WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS

NOTES CONTINUED:
5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO WITH, OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF TROUBLY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
9. DRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.


ES CONTINUED:
THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS
WITH, OR DAMAGE TO, THESE UTILITIES.
STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENCINEER.
BRILL SEEDING AND SOIL RETENTION BLANKETS SHALL BE APPLIED AT A MINIMUM OF FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

LIFM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	1 1
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1079
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1079
0168-6001	VEGETATIVE WATERING	MG	16.83
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1079
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	45
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1619
0543-6020	CARLE BARRIER TERMINAL SECTION (TL-4)	FΛ	2

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT


STA 1420+00 TO STA 1400+00


SHEET 22 OF 34							
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.	
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.	
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	55	



LIFM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	7
0150-6002	BLADING	HR	8.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	646
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	646
0168-6001	VEGETATIVE WATERING	MG	10.08
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	646
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	27
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	300
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	300
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	969
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	1







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1440+00 TO STA 1460+00


	SHEET 23 OF 34							
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE 1	TITLE S	US 281			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	56		



IIEM	DESCRIPTION	UNII	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	5
0150-6002	BLADING	HR	4.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	433
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	433
0168-6001	VEGETATIVE WATERING	MG	6.75
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	433
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	18
0506-6040	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	20
0506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	20
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	650
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2








PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 1460+00 TO STA 1480+00


SHEET 24 OF 34								
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO. H			HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	SEE TITLE SHEET				
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	57		



LIEM	DESCRIPTION	UNII	QIT
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	5
0150-6002	BLADING	HR	4.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	500
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	500
0168-6001	VEGETATIVE WATERING	MG	7.80
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	500
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	21
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	750
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800



US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT


STA 1480+00 TO STA 1500+00


SHEET 25 OF 34							
DGN:	FED. RD. DIV. NO.	STATE	FEDER	FEDERAL AID PROJECT NO. HIGHWA			
CHK DGN:	6	TEXAS	SEE 1	SEE TITLE SHEET			
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO. JOB NO.		SHEET NO.	
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	58	




TIMES ARE APPROXIMATE. VERITY LOCATIONS AS NECESSARY (REDESTOR OF THE METERS) AND THE PROJECT. BASELINE COINCIDENCES WITH DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER. HALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE TOP OF AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED. IS ARE APPROXIMATE. ALL UTILITIES ARE SHOWN BASED ON AVAILABLE AS-BUILT DRAWINGS AND 811 UTILITY LOCATE. CONTRACTOR MUST FIELD VERIFY THE EXACT LOCATION POLES, ELECTRICAL SERVICES, GROUND BOXES, AND OTHER PERTINENT ITEMS BEFORE COMMENCING WORK.

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT


STA 1500+00 TO END PROJECT


SHEET 26 OF 34							
DGN:	FED. RD. DIV. NO.	STATE	FEDER	FEDERAL AID PROJECT NO. HIGH			
CHK DGN:	6	TEXAS	SEE TITLE SHEET			US 281	
DWG:	DIST.	COUNTY	CONT. NO.	SECT, NO. JOB NO.		SHEET NO.	
CHK DWG:	SAT	BEXAR	0073	02	088,ET0	59	


THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS



LIFM	DESCRIPTION	I I MU	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	9
0150-6002	BLADING	HR	7.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	824
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	824
0168-6001	VEGETATIVE WATERING	MG	12.85
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	824
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	34
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1236
05/13-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	FΛ	2








PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT


BEGIN PROJECT TO STA 2020+00


			SHEET 27 OF 34					
DGN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	60		



LIEM	DESCRIPTION	UNII	Q I I
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	11
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1017
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1017
0168-6001	VEGETATIVE WATERING	MG	15.87
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1017
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	42
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1525
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT


STA 2020+00 TO STA 2040+00

SHEET 28 OF 34							
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO. HIGHWAY NO				
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281	
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.	
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	61	



1. ALL RIGHT-OF-WAY LINES ARE APPROXIMATE. VERIFY LOCATIONS AS NECESSARY
2. CABLE BARRIERS ARE DESIGNED TO BE PLACED ON 6:1 (16.67%) OR FLATTER SIDE SLOPES. TOPOGRAPHICAL SURVEYING WAS NOT PERFORMED ON THIS PROJECT. BASELINE COINCIDENCES WITH THE FLOWLING OF DITCH. CABLE BARRIER LOCATIONS MAY BE ADJUSTED AS NEEDED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVELLAND. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE


3. CABLE BARRIERS SHALL BE PLACED WITH AT LEAST 12 FEET OFFSET FROM EDGE OF THE TRAVEL LANE. CABLE BARRIERS SHALL BE PLACED AT LEAST 8 FEET FROM THE BOTTOM OF THE DITCHLINE. OFFSET OF AT LEAST 5 FEET FROM THE EDGE OF ILLUMINATION POLE IS RECCOMMENDED.
4. UTILITY LOCATIONS ARE APPROXIMATE. ALL UTILITIES ARE SHOWN BASED ON AVAILABLE AS-BUILT DRAWINGS AND 811 UTILITY LOCATE. CONTRACTOR MUST FIELD VERIFY THE EXACT LOCATION OF EXISTING ROW, POLES, ELECTRICAL SERVICES, GROUND BOXES, AND OTHER PERTINENT ITEMS BEFORE COMMENCING WORK.




NOTES CONTINUED:
5. THE CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS
WITH, OR DAMAGE TO, THESE UTILITIES.
6. STATIONING IS NOT TRUE IDENTIFICATION OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
7. CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
8. MOW STRIP SHALL BE 36 INCHES WIDE UNLESS OTHERWISE SPECIFIED BE THE ENGINEER.
9. DRILL SEEDING AND SOIL RETENTION BLANKEIS SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
10. NO WORK THAT COULD HAVE AN IMPACT TO THE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
11. FPA NOTIFICATION FOR ATASCOSA COUNTY WAS SUBMITTED IN WRITING ON MARCH, 19, 2024.

TIEM	DESCRIPTION	UNII	QIT
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	11
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1034
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1034
0168-6001	VEGETATIVE WATERING	MG	16.13
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1034
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	43
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	125
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	125
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1551
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	3

LEGEND







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 2040+00 TO STA 2060+00

			SHEET 29 OF 34					
DGN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	62		




THE UTILITY COMPANIES TO VERIFY THE LOCATION OF EXISTING OVERHEAD AND UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICTS


OF THE ROADWAY ALIGNMENT. NO TOPOGRAPHIC FILE WAS USED AS A BASIS FOR STATIONING.
IMENT CONTROL FENCES AS NEEDED (NOT SHOWN ON PLANS)
SS OTHERWISE SPECIFIED BE THE ENGINEER.
ESTO SHALL BE APPLIED AT A MINIMUM OF 3 FEET ON EITHER SIDE OF CABLE BARRIER MOW STRIP FOR A TOTAL WIDTH OF 6 FEET.
HE EXISTING FEMA 100YR WSEL IS BEING PROPOSED FOR THIS PROJECT.
AS SUBMITTED IN WRITING ON MARCH, 19, 2024.

TIEM	DESCRIPTION	DIATI	uii
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	12
0150-6002	BLADING	HR	10.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1141
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1141
0168-6001	VEGETATIVE WATERING	MG	17.80
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1141
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	48
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	175
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	175
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1711
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2

LEGEND







 ∞

PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT


STA 2060+00 TO STA 2080+00


			SHEET 30 OF 34					
DGN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ET0	63		



LIEM	DESCRIPTION	I I MU	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	14
0150-6002	BLADING	HR	10.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1331
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1331
0168-6001	VEGETATIVE WATERING	MG	20.76
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1331
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	55
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	200
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	200
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1996







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000 TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 2080+00 TO STA 2100+00

			SHEET 31 OF 34					
DGN:	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO. HIGHWAY NO					
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	64		



UNIT QTY

CY | 11

SY 1062

SY 1062 CY 44

LF 100

LF 1593

100


150

SHEET 32 OF 34


FEDERAL AID PROJECT NO.


9.0 SY 1062


100



IIEM	DESCRIPTION	I I MU	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	11
0150-6002	BLADING	HR	9.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	1066
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	1066
0168-6001	VEGETATIVE WATERING	MG	16.63
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	1066
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	44
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	1599
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	2







PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS
2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000
TEXAS ENGINEERING FIRM #470 I TEXAS SURVEYING FIRM #10028800




US 281: CABLE BARRIER


PROPOSED CABLE BARRIER LAYOUT

STA 2120+00 TO STA 2140+00


			SHEET 33 OF 34					
DGN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	66		



TIFM	DESCRIPTION	ITMU	QIY
0132-6021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	6
0150-6002	BLADING	HR	5.0
0164-6035	DRILL SEEDING (PERM) (RURAL) (CLAY)	SY	569
0164-6051	DRILL SEED (TEMP) (WARM OR COOL)	SY	569
0168-6001	VEGETATIVE WATERING	MG	8.88
0169-6001	SOIL RETENTION BLANKETS (CL 1) (TY A)	SY	569
0432-6066	RIPRAP (CL A) (MOW STRIP) (3 IN)	CY	24
0506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	100
0506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	100
0543-6002	CABLE BARRIER SYSTEM (TL-4)	LF	854
0543-6020	CABLE BARRIER TERMINAL SECTION (TL-4)	EΑ	1








PAPE-DAWSON ENGINEERS

SAN ANTONIO I AUSTIN I HOUSTON I FORT WORTH I DALLAS 2000 NW LOOP 410 I SAN ANTONIO, TX 78213 I 210.375.9000



US 281: CABLE BARRIER

PROPOSED CABLE BARRIER LAYOUT

STA 2140+00 TO END PROJECT

			SHEET 34 OF 34					
DGN:	FED. RD. DIV. NO.	STATE	FEDER	AL AID PROJE	CT NO.	HIGHWAY NO.		
CHK DGN:	6	TEXAS	SEE	TITLE S	SHEET	US 281		
DWG:	DIST.	COUNTY	CONT. NO.	SECT. NO.	JOB NO.	SHEET NO.		
CHK DWG:	SAT	BEXAR	0073	02	088,ETC	67		

125

130

135

140

1950

1800

1650

1500


*ROPE TENSION: ± 20% AFTER 2-WEEK INTERVAL

8.7


8.0

7.3

6.7







WRGT-FL END ANCHOR

CENERAL NOTES:

- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. AT 1-866-427-4336.
- 2. THE BRIFEN WRSF HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-4 CONDITIONS ON SLOPES 6:1 OR FLATTER AND NCHRP 350 TL-3 CONDITIONS ON SLOPES 4:1 TO 6:1.
- 3. THE POST SPACING SHALL BE DETERMINED BY THE SPECIFYING AGENCY. POST SPACING MAY BE DECREASED TO AVOID OBSTRUCTIONS OR UTILITIES. IN NO EVENT SHALL THE POST SPACING EXCEED 21'-0".
- 4. BRIFEN WRSF SHALL BE PLACED ON A SMOOTH SURFACE, WITHOUT HUMPS, DROP-OFFS, HOLES, ETC THAT WOULD INTERFERE WITH THE STABILITY OF THE ERRANT VEHICLE. GRADING, FILL AND COMPACT MAY BE REQUIRED TO ASSURE THAT ROPES ARE INSTALLED AT THE DESIGN HEIGHT.
- 5. THE WRGT-FL END ANCHOR HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-3 CONDITIONS. THE LENGTH OF NEED BEGINS 31'-0" FROM THE END ANCHOR. POSTS A THROUGH POST B3, SPACED 6'-6" APART, HAVE WEAKENED CUTS AT THE GROUND THAT SHALL FACE THE ANCHOR.
- 6. ANCHOR AND LINE POST DIMENSIONS AND STEEL REINFORCEMENT WILL BE DETERMINED ON PROJECT SPECIFIC SOIL CLASSIFICATION, PROPERTIES AND TEMPERATURE EXTREMES. CONTACT BRIFEN USA, INC. FOR ADDITIONAL INFORMATION.
- 7. ALL REINFORCEMENT AND CONCRETE FOR THE ANCHORS AND LINE POSTS PROVIDED BY OTHERS.
- B. REINFORCEMENT AND CONCRETE PROPERTIES SHALL MEET AGENCY SPECIFICATIONS.
- 9. FOR PLACEMENT NEAR GUARDRAIL OR OTHER OBSTACLES CONTACT BRIFEN USA, INC. FOR ADDITIONAL DRAWINGS AND SUPPORT.
- O. TAPER RATES FOR THE BRIFEN WRSF ARE AS FOLLOWS:
 HORIZONTAL: 25:1 MAXIMUM, 50:1 PREFERABLE
 VERTICAL: 25:1 MAXIMUM, 50:1 PREFERABLE

SHEET 1 OF 3



Division Standard

BRIFEN
WIRE ROPE SAFETY FENCE
(TL-4)

BRIFEN(TL4)-14

LE: brifent 414.dgn	DN: Tx[OOT CK: RM DW: VP		P	CK:	
TxDOT: MARCH 2014	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0073	02	088,ETC		US 281	
	DIST	COUNTY		SHEET NO.		
	SAT	BEXAR				68


δρ is made results warranty of any kind lats or for incorrect Engineering Practice Act". of this standard to other "Texas this standard is governed by les no responsibility for the

LINE POST ASSEMBLY [Z11] Z POST CAP [Z80] (IF SPECIFIED) LOCATING PEG 36-1/2" [A42] 30-1 24-1/2 18-1/2" Z EXCLUDER [Z41] **ELEVATION** 2-3/16" PLAN

NOTES SPECIFIC TO LINE POST ASSEMBLY

- 1. ROPE HEIGHTS SHALL BE \pm 1" TO GROUND LINE.
- 2. POST SHALL BE \pm 4" FROM VERTICAL PLUMB.
- 3. POST CAPS SHALL BE USED IF SPECIFIED.
- 4. REFLECTORS SHALL BE SPACED ACCORDING TO AGENCY SPECIFICATIONS.
- 5. REFLECTORS CAN BE PLACED ON THE POST CAP OR POST.


ROPE CONNECTION DETAIL



NOTES SPECIFIC TO ROPE CONNECTION DETAIL

- 1. THE WIRE ROPE TERMINALS SHALL BE THREADED A MINIMUM OF 1-1/2" INTO RIGGING SCREW.
- 2. AFTER FINAL TENSIONING, THE TERMINALS SHALL BE VISIBLE IN THE INSPECTION HOLES.


SOCKET ASSEMBLY





NOTES SPECIFIC TO CONCRETE FOOTING

- 1. SIZE OF FOOTING WILL BE DETERMINED BY SOIL CONDITIONS, FOUNDATION TYPE AND PROJECT CONDITIONS.
- 2. CONCRETE BASED ON AGENCY SPECIFICATIONS.
- 3. CONCRETE BY OTHERS.
- 4. REINFORCING RING (BY OTHERS) WILL BE USED ACCORDING TO FOUNDATION SIZE AND TYPE. THE REINFORCEING RING MAY BE OMITTED IF THE FOOTING IS PLACED IN A CONTINOUS CONCRETE MOW STRIP.
- 5. FOOTING SHALL BE FLUSH WITH THE GROUND LINE, TO A MAXIMUM OF 1 INCH BELOW OR ABOVE GROUND LINE.
- 6. SOCKET SHALL BE $\pm 2^{\circ}$ OF VERTICAL PLUMB.



NOTES SPECIFIC TO DRIVE SOCKETS

- 1. SIZE OF SOIL PLATE WILL BE DETERMINED BY SOIL CONDITIONS AND PROJECT CONDITIONS.
- 2. THE SOIL PLATE SHALL BE PARALLEL TO ROADWAY AND CAN FACE TOWARD OR AWAY FROM THE TRAVEL LANE.
- 3. FOOTING SHALL BE FLUSH WITH THE GROUND LINE, TO A MAXIMUM OF 1 INCH BELOW OR ABOVE GROUND LINE.
- 4. SOCKET SHALL BE $\pm 2^{\circ}$ OF VERTICAL PLUM.
- 5. SOCKETS SHALL BE DRIVEN IN A MANNER TO NOT DISTORT OR DESTROY THE TOP OF SOCKET TO A DEGREE THAT PLACES THE SOCKET OR LINE POST OUT OF CONSTRUCTION TOLERANCES.

GENERAL NOTES:

- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. 1-866-427-4336.
- 2. THE BRIFEN WRSF HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-4 CONDITIONS ON SLOPES 6:1 OR FLATTER AND NCHRP 350 TL-3 CONDITIONS ON SLOPES 4:1 TO 6:1.
- 3. THE POST SPACING SHALL BE DETERMINED BY THE SPECIFYING AGENCY. POST SPACING MAY BE DECREASED TO AVOID OBSTRUCTIONS OR UTILITIES. IN NO EVENT SHALL THE POST SPACING EXCEED 21'-0".
- 4. BRIFEN WRSF SHALL BE PLACED ON A SMOOTH SURFACE, WITHOUT HUMPS, DROP-OFFS, HOLES, ETC THAT WOULD INTERFERE WITH THE STABILITY OF THE ERRANT VEHICLE. GRADING, FILL AND COMPACTION MAY BE REQUIRED TO ASSURE THAT ROPES ARE INSTALLED AT THE DESIGN HEIGHT.


SHEET 2 OF 3



BRIFEN WIRE ROPE SAFETY FENCE (TL-4)


BRIFEN(TL4)-14


ILE: brifentl414.dgn	DN: TxDOT		ck: RM Dw: VP		VP	CK:
C)TxDOT: MARCH 2014	CONT	SECT	JOB	н		GHWAY
REVISIONS	0073	02	088,E	TC	US	281
	DIST		COUNTY			SHEET NO.
	SAT		BEXAR	₹		69



GENERAL NOTES:


- BRIFEN DRAWINGS, SPECIFICATIONS, AND PRODUCT MANUAL SHOULD BE REVIEWED PRIOR TO STARTING AN INSTALLATION. FOR ADDITIONAL INFORMATION OR QUESTIONS, CONTACT BRIFEN USA, INC. AT 1-866-427-4336.
- THE WRGT-FL END ANCHOR HAS BEEN SUCCESSFULLY TESTED TO NCHRP 350 TL-3 CONDITIONS.
 THE LENGTH OF NEED BEGINS 31'-0" FROM THE END ANCHOR. POSTS A THROUGH POST B3, SPACED 6'-6" APART, HAVE WEAKENED CUTS AT THE GROUND THAT SHALL FACE THE ANCHOR.
- ANCHOR AND LINE POST DIMENSIONS AND STEEL REINFORCEMENT WILL BE DETERMINED ON PROJECT SPECIFIC SOIL CLASSIFICATION, PROPERTIES AND TEMPERATURE EXTREMES. CONTACT BRIFEN USA, INC. FOR ADDITIONAL INFORMATION.
- 4. ALL REINFORCEMENT AND CONCRETE FOR THE ANCHORS AND LINE POSTS PROVIDED BY OTHERS.
- 5. REINFORCEMENT AND CONCRETE PROPERTIES SHALL MEET AGENCY SPECIFICATIONS.
- 6. FOR PLACEMENT NEAR GUARDRAIL OR OTHER OBSTACLES CONTACT BRIFEN USA, INC. FOR ADDITIONAL DRAWINGS AND SUPPORT.





NOTES SPECIFIC TO WRGT-FL POST DETAIL

- 1. ROPE HEIGHTS SHALL BE ±1" TO GROUND LINE.
- 2. POST SHALL BE ±4" FROM VERTICAL PLUMB.
- 3. POST CAPS SHALL BE USED IF SPECIFIED.
- 4. REFLECTORS SHALL BE SPACED ACCORDING TO AGENCY SPECIFICATIONS.
- 5. REFLECTORS CAN BE PLACED ON THE POST CAP OR POST.
- 6. Z EXCLUDER (Z41) SHALL BE USED.
- 7. POST A & SOCKET SHALL BE PLACED 79* (±4*) TOWARD END ANCHOR FROM THE HORIZONTAL PLANE.
- 8. POST A SOCKET SHALL BE PLACED IN 14" (MIN) CONCRETE FOUNDATION. DEPTH TO BE DETERMINED FROM SOIL CONDITIONS AND PROJECT CONDITIONS.
- 9. FOUNDATIONS FOR POST 2 THRU 4 SHALL BE THE SAME AS THE LINE POST ASSEMBLY'S FOR THE PROJECT.
- 10. WEAKENED CUTS SHALL FACE END ANCHOR.




NOTES SPECIFIC TO END ANCHOR DETAIL


- 1. THE END ANCHOR ASSEMBLY SHALL BE PLACED 12° $(+3^{\circ}, -1^{\circ})$ BELOW HORIZONTAL PLANE.
- POST 1 & SOCKET SHALL BE PLACED 79* (±4*)
 TOWARD END ANCHOR FROM THE HORIZONTAL PLANE.
- 3. POST 1 SOCKET SHALL BE PLACED IN 14" (MIN) CONCRETE FOUNDATION. DEPTH TO BE DETERMINED FROM SOIL CONDITIONS AND PROJECT CONDITIONS.

END ANCHOR COMPONENTS

ANCHOR FRAME ASSEMBLY

ANCHOR FRAME [A70]





SHEET 3 OF 3



Division Standard

BRIFEN
WIRE ROPE SAFETY FENCE
(TL-4)

BRIFEN(TL4)-14

E: brifentl414.dgn	DN: Tx[:DOT CK:RM DW:		DW: VP	CK:
TxDOT: MARCH 2014	CONT	SECT	JOB		HIGHWAY
REVISIONS	0073	02	088,E	088,ETC US 2	
	DIST		COUNTY		SHEET NO.
	SAT		BEXA	۲	70

.TE:

Preferred Installation: Locate post #2 away from nearest traffic. Length-of-Need Cass Cable Terminal (CCT): System has been successfully tested with opposite installation. Departure Installation: Length-of-Need: 44'-9" (At Post #8)
Approach Installation: Length-of-Need: 19'-9" (12" Past Post #4) any purpose w esulting from Direction of Nearest Traffic PLAN VIEW 51'-3" ±1" NCHRP 350 TL-3 Approved CASS CABLE TERMINAL (CCT - PAYMENT EACH) PAY ITEM - CASS-TL4 SYSTEM (PAYMENT - LINEAR FEET) δy (3) POST SPACES AT (5) POST SPACES AT 6'-6"=32'-6' MAXIMUM 1000 FEET BETWEEN CABLE SPLICES 6'-3"=18'-9" 6'-6" TO 20' (TYPICAL U.N.)_ D 9 kind rect ty of for i 30" 36' 12" Dia. CASS TL4 Post in Concrete. a P 12" (4) CCT-TL3 Line Post (See Drawing SS740) Dia. 18" Dia. (3) CCT Terminal Cable CASS TL4 Post- Base plated (2) CCT-TL4 Line Post Release Post Turnbuckles may be staggered (For use on concrete) (See Drawing SS740) between line posts. Minimum (1) turnbuckle per cable required for installations of Attach to Post with 600 ft. or Less. ELEVATION VIEW Line post near a splice may Practice ndard to c 3/4" Dia. Cable (3 X 7 Strands) two (2) Heavy Hex Nut (TYPICAL LAY-OUT) require a special splice post. Turnbuckle &(1) Flat Washer (See manufacture's product **=[]-**|| manual for details) CABLE SPLICE WITH TURNBUCKLE CABLE STUD ASSEMBLY TORPEDO CABLE SPLICE (OPEN BODY STYLE) Engi 18" Min. dia. 12" Min. dia. 12" Min. dia. concrete footing (cast in place or precast) concrete footing (cast in place or precast) concrete footing exds sion (cast in place or precast) (concrete and reinforcing (by others) (concrete and reinforcing) Post sleeve by others) HDPE Post cap - by others) - TS5 × 3 ½ × 11 GA × 2′ 3" 1 -1/2 " (Optional) the con Post sleeve TS5 x 3 1/4 #4 rebar rods (2) places, (I) rned for + placed at post sleeve corners facing oncoming \bigcirc CASS-TL4 traffic. Tie rods to S4×7.7 rebar ring. -12" Dia. 8-¾" Dia. 8-3/4" Dia. Post i.s Direction of Nearest Traffic SECTION F-F SECTION G-G SECTION E-E Concrete -Sleeve cap (by others) Cable Stud Assembly SEE DRAWING SS-740 FOR LOCATIONS OF CABLE LOCK BOLTS Top of bottom CRP-Post (See detail) Post weakening holes placed at ground level Ground CONCRETE FOOTING line (IN QUALIFYING MOW STRIP SEE CHART) -Ground line .. %/ Gab #3 Rebar ring 12" Dia.x 30" -(See chart) Concrete footing -Ground line \bigcirc Concrete (by others) 74 Min. See ch ب ALLOWABLE CABLE HEIGHT DEVIATION
(+1" -1") 3/1 SECTION D-D STANDARD POST & CONCRETE FOOTING VIEW B-B SECTION C-C VIEW A-A (TERMINAL LINE POST 4-7) (BASE PLATED POST: (CABLE RELEASE POST 1-3) (SOCKETED POST) (SOCKETED POST)

GENERAL NOTES

- 1. This drawing is a general overview of CASS TL-4 Barrier System. See SS-740 (latest version) for specific details of CASS cable terminal (CCT) and cable safety system (CASS) requirements, proper installation, options and specification.
- 2. CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity (800-527-6050) or consult the design, installation, or repair manual(s) for additional information.
 - All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
- 4. All posts shall be socketed unless otherwise specified.
 All cables shall be pre-stretched unless otherwise specified.
- For payment see Special Specification "Cable Barrier System".
- CASS-TL4 shall be installed on shoulders or medians with slopes of 6:1 or flatter without obstructions, depressions, etc. That may significantly affect the stability of an errant vehicle. Grading of site and/or appropriate fill materials may be required. The designer/installer shall "Flatten" or "Round" various topographical inconsistencies that could interfere with the ability of the installer to consistently maintain the design height (in relation to the terrain) of the cables. Please consult manual(s) and/or TXDOT Memo(s) for installations in "Ditch Sections".
- CASS TL-4 post spacing may be modified to avoid obstacles that conflict with the installation of cass-tl4 line posts or to reduce deflection on radiuses. No post space can exceed the maximum post TxDOT space limit of 20'. Reducing or increasing post spacing affects deflection. CASS TL-4 may be laterally transferred at a rate not to exceed 30:1.
- 8. Post foundations may be drilled through existing pavement. Please see line post foundation chart for minimum footing requirements in various applications.
- 9. For aesthetic purposes Trinity recommends all sleeves, driven posts, and lower cable release posts to be installed reasonably plumb (approximately 1/8" per foot).
- 10.CASS TL-4 shall be installed in well-drained, compacted, NCHRP Report 350 Standard soil. If soil does not meet this classification, if soild rock/concrete is encountered below grade or if soil is susceptable to severe freeze/thaw cycles, please contact Trinity about alternate footing design(s). Trinity suggests the use of "Mow strips" for erosion prevention and ease of maintenance / installation.
- 11. See the Texas MUTCD for proper "Barrier" Delineation.

MOW STRIP DETAIL*			CONCRETE FOOTING CHART						
MOW STRIP	DEPTH	WIDTH	FOOTING	TUBE SLEEVE	REBAR RING				
NONE			30" Min.	27" Min.	YES				
HMA	6" Min.	3′ Min.	27" Min.	15" Min.	NO				
HMA	8" Min.	3′ Min.	24" Min.	15" Min.	NO				
RC	3" Min.	3′ Min.	24" Min.	15" Min.	NO				

Chart does not apply to Terminal Posts 1 thru 9.

* Mow strip or pavement.

HMA = Hot Mix Asphalt (Not Recycled Asphalt Pavement).
RC = Reinforced Concrete (TXDOT Class A Minimum).

Trinity Highway Products, LLC. 2525 Stemmons Freeway Dallas, TX 75207

Phone: (800) 644-7976 Product. INFO@TRIN. NET

HDPE Cable spacer

Stainless steel

HDPE Cable spacer with reflector when required.

HDPE Sleeve cover (Optional)

Post sleeve

TS 5 \times 3 $\frac{1}{4}$ \times 11 GA \times 2′ 3

Sleeve cap

#3 Rebar ring

(See chart)

with reflector when required.

post strap

	DEGREES	LB / FORCE
	-10	7300
	0	7000
	10	6600
	20 30	6300
	30	6000
	40	5600
	50	5300
	60	5000
	70	4600
	80	4300
	90	4000
	100	3600
	110	3300
	120	3000
	130	2700
	140	2500
	150	2300
m	chart in ta	naent sections:

CABLE TENSION CHART

FAHRENHEIT | PRE-STRETCHED

Allowable deviation from chart in tangent sections: +800, -200 pounds/force. Cable tension readings are typically higher in curved cable sections.



Standard

CABLE SAFETY SYSTEM (TL-4)

TRINITY

CASS (TI 4) - 14

LE: casst 414, dgn	DN: Tx[OT CK: RM DW: VP		VP	CK:	
)TxD0T: March 2014	CONT	SECT	JOB	HIGHW		IGHWAY
REVISIONS	REVISIONS 0073 02 088, ETC		US	5 281		
	DIST	COUNTY			SHEET NO.	
	SAT		BEXA	₹		71

GENERAL NOTES 2000' Nominal between splices. (3) 3/4" Wire Ropes -27'-6" Minimum one set of splices per run 1. For additional information contact Gibraltar, Inc. at 1-800-495-8957, Begin Length of Need for System Begin 20' Post Spacing 830-798-5444, or see the manufacturer's product manual. any purpose w esulting from 1-1/4" ± 1/2" 2. All concrete shall be CLASS A. ~ 12" 3. The Cable Barrier System shall be installed on shoulders or on medians with slopes of 6:1 or flatter. If installed on slopes steeper than 6:1 up to 4:1 the TL-4 system performs as a TL-3 and Gibraltar must → Line Post (TYP) Driven or Socketed be contacted for various guidelines related to placement. 4. The Cable Barrier System is accepted by the FHWA Test Level - 4. TxDOT . 5. See the Texas MUTCD for proper "Barrier" delineation. 6. Rock Clause: Where solid rock is encountered: TP4-4 δy A. For socketed post, continue digging 12" diameter, 15" deep into made sults Anchor Post rock or the required plan depth, whichever comes first. HSS 8" x 8"x 3' B. For driven post, core drill a 4" diameter hole 18" deep into 2' Dia. x 8' Min. Deep rock or the required plan depth, whichever comes first. any kind incorrect Reinforced Foundation C. For Anchor post, continue digging 24" diameter, 30" deep into (No Rebar Shown) rock or the required plan depth, whichever comes first. 7. Tolerances: 6'-3" ±1' 6'-3" ±1' 7'-6" ±1' 7'-6" ±1' anty of or for : * LP = 3" out of plumb, at top * Cable height = 1" Alternate posts for barrier installation * Anchor Post = 5" off of Cable Reference Line 8. The Gibraltar cabte barrier system shall be installed in NCHRP Cable Reference Line Report 350 standard compacted soil. Soil must be well drained. 9. All non-welded rebar by others. Lockplate Hairpin Engineering Practice Act". of this standard to other (3) Anchor Terminal Fittings 10. Minimum recommended line post foundation. 4 - 5/8" A. Without mowstrip, 36" Deep x 12" diameter foundations with #3 Delineator 3/4" MIN 3/4" MIN Concrete wedge rebar ring x 8" diameter with two #4 rebar vertical bars 30" long T/B CABLE SPLICE FITTING TERMINAL FITTING anchors per Bolt @ 3-3 B. With 4" minimum depth hot mix asphalt, 30" deep x 12" diameter Manufacturer's (8) Vertical #6 Bar foundations with #3 rebar ring \times 8" diameter with two #4 rebar Recommendation X 7'-10' vertical bars 30" long. @ 2-6 C. With 3" minimum depth concrete mowstrip, 24" deep x 12" diameter Line of Cable Line of Cable Rebar Bars Rebar Ring foundations. (No rebar required) (10) Horz. #4 Rings @ 1-8" Welded to Socket and Bars X 18" Dia. D. Direct drive post 42" deep. (By Others) "Texas /ersion 2-1/2 " GRADE CABLE TENSION CHART* 3-1/4' this standard is governed by es no responsibility for the -10 ° F 8000 C-SECTION POST LINE POST 7600 C-Section Post SECTION A SECTION B (BASE-PLATED OPTION) 3-1/4" X 2-1/2" X 4'-9" Low-Fill Box Culvert Less than 15" Fill 10 ° F 7200 C-Section Post C-Section Post 20 ° F 7 Rings Spaced 6800 3-1/4" X 2-1/2" X 4'-9" - 3-¹/₄" X 2-¹/₂" X 4'-9' @ 6" O.C. C-Section Post 30 ° F 6400 DEFLECTION (TP1-2) $3-\frac{1}{4}$ " X $2-\frac{1}{2}$ " X 4' 40 ° F 6000 (TP3-4) $3-\frac{1}{4}$ " X $2-\frac{1}{2}$ " X 4'-9" Post 50 ° F 5600 "C" slot this side Deflection Spacing for TP1-4 60 °F 5200 8'-0" 20 FT 70 ° F 4800 ¾" Dia. Wire Rope 3/4" J-Bol+ -7'-0" 12 FT 80 ° F 4400 3"X4"X15" 90 ° F 4000 10 FT 6'-8" 3" x 4" x 15" 3" × 4" × 15" Steel Socket 3/6" X 3" X 4" Steel or Plastic 100 ° F 3600 Steel or Plastic $1-\frac{1}{2}$ " Dia. Hole W/4 #4 Driven Socket * Allowable Deviation Socket Socket 110 ° F 3 Sides 3200 Rebar Welded from Chart +/- 10% (TP1 & TP2 Only) to Socket GRADE GRADE GRADE Texas Department of Transportation 15' #3 Ring x 8"Dia. GIBRALTAR 4" Overlap 3" Min. Post Below Grade Stop CABLE BARRIER SYSTEM (By Others) -#4 Rebar x 30" (TL-4)(By Others) 12"-Plastic or Plastic or Steel Cap 36" Steel Cap GBRLTR (TL4) - 14 LINE POST DN:T×DOT CK:RM DW:VP ILE: gbr|trt|414.dgn (DRIVEN OPTION) TERMINAL POST LINE POST SOCKETED C)TxDOT: March 2014 CONT SECT JOB HIGHWAY LINE POST SOCKETED (SHOWN WITH CONCRETE MOWSTRIP) (Shown with Driven 0073 02 088,ETC US 281 (Shown with Rebar Ring/Bars Socket Option) (Shown with Welded Rebar Socket Option) Socket Option) (Shown with Tube Plate Option) CABLE RELEASE AND ANCHOR POST (See Note 9) (See Note 9) (See Note 9) (See Note 10) SAT BEXAR

GENERAL NOTES

- FOR ADDITIONAL INFORMATION CONTACT YOUR DISTRIBUTOR OR NUCOR STEEL MARION, INC. AT (740) 383-4011.
- 2. FOR PAYMENT SEE SPECIAL SPECIFICATION "CABLE BARRIER SYSTEM".
- 3. FOR ADDITIONAL INFORMATION SEE THE MANUFACTURER'S PRODUCT MANUAL.
- THE NU-CABLE SYSTEM IS DESIGNED FOR BI-DIRECTIONAL TRAFFIC FLOWS. SEE THE MANUFACTURER'S PRODUCT MANUAL FOR PLACEMENT ADJACENT TO GUARDRAIL END TREATMENTS.
- THE NU-CABLE SYSTEM SHALL BE INSTALLED ON MEDIANS WITH SLOPES OF 6:1 OR FLATTER WITHOUT OBSTRUCTIONS, DEPRESSIONS, ETC; THAT MAY SIGNIFICANTLY AFFECT THE STABILITY OF AN ERRANT VEHICLE.
- THE NU-CABLE SYSTEM MAY BE INSTALLED ON EITHER SIDE OF THE ROADWAY. RID-BUTM CABLE LINE POSTS MAY BE SOCKETED OR DRIVEN DESIGN.
- 7. THE TL-4 FOR 6:1 SLOPES CAN USE 4# / LF POST. SEE TABLE #1 FOR POST SIZE PER SPACING.
- 8. SEE (TABLE 2) FOR TENSION AMOUNT AT SPECIFIC CABLE TEMPERATURE FOR INITIAL INSTALLATION.
- 9. SEE (TABLE 3) FOR TENSION AMOUNT AT SPECIFIC CABLE TEMPERATURE FOR MAINTENANCE.
- 10. FOURTH (LOWEST) CABLE IS NOT OPTIONAL ON THE TL-4 SYSTEM.
- 11. CONSULT YOUR PROJECT PLAN SHEETS AND CABLE BARRIER SPECIFICATIONS FOR DESIRED SOCKET MATERIAL.
- 12. ALL FOUNDATION DESIGNS ARE BASED ON NCHRP 350 STRONG (S1) SOIL. CONSULT THE MANUFACTURER FOR SPECIFIC FOUNDATION DESIGN IF SOIL TYPES DIFFER.

7 TABLE 1

POS1	POST SIZE TABLE			
POST SPACING	POST SIZE			
0' - 17'-6"	4# / LF X 4' OR 6' POST			
17'-6" - 20'	5# / LF X 4' POST			

POST SPACING IS PER 8 FOOT DEFLECTION REQUIRMENTS.
CONSULT PRODUCT MANUAL IF GREATER DEFLECTION IS PERMISSIBLE.

8 TABLE 2

- IADLE Z				
CABLE TEN	SION CHART			
INITIAL	INSTALL			
F	LBF			
120	4624			
110	4986			
100	5350			
90	5713			
80	6077			
70	6440			
60	7167			
50	7894			
40	8619			
30	9346			
20	10073			
10	10800			
0	11525			
-10	12252			
-20	12979			
- 30	13706			

9 TABLE 3

CABLE TEN	SION CHART
MAINT	ENANCE
F	LBF
120	4021
110	4336
100	4652
90	4968
80	5284
70	5600
60	6232
50	6864
40	7495
30	8127
20	8759
10	9391
0	10022
-10	10654
-20	11286
- 30	11918

SHEET 1 OF 2



NU-CABLE BARRIER SYSTEM (TL-4)(4 CABLE)

NU-CABLE (TL4) -14

ILE:	DN:		CK: DW:			CK:
TxDOT:	CONT	SECT	JOB		HIC	SHWAY
REVISIONS	0073	02	088,ET	·c	US	281
	DIST		COUNTY			SHEET NO.
	SAT		BEXA	۲		73

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For projects with less than one acre of soil disturbing activity and that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

0073-02-088

1.2 PROJECT LIMITS:

From: MARTHA WALK

To: BEXAR/ATASCOSA COUNTY LINE

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 29.1483°N

,(Long) 98.4835°W

END: (Lat) 29.1407°N

,(Long) 98.4839°W

1.4 TOTAL PROJECT AREA (Acres): 3.80 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.54 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:

INSTALL CABLE BARRIER

1.7 MAJOR SOIL TYPES:

Soil Type	Description
CLAY/SAND	VARIES BY LOCATION

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

☐ PSLs determined during preconstruction meeting PSLs determined during construction

X No PSLs planned for construction

Туре	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

X Mobilization

X Install sediment and erosion controls

Blade existing topsoil into windrows, prep ROW, clear and grub

Remove existing pavement

X Grading operations, excavation, and embankment

- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs) Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- X Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- X Revegetation of unpaved areas
- X Achieve site stabilization and remove sediment and erosion control measures

Other:			

Other:			
-			

Other:			
-			

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- X Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment,
- Solvents, paints, adhesives, etc. from various construction
- ☐ Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Discharges from concrete washout activities, runoff from concrete cutting activities, and other concrete related activities

□ Otner.			

□ Other:			
•			

Other:

1.11 RECEIVING WATERS: Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
N/A	
* Add (*) for impaired waterbodies	s with pollutant in ().

	* Add (*)	for impaired	waterbodies	with pollutant	t in ()
--	-----------	--------------	-------------	----------------	--------	---

1.12 ROLES AND RESPONSIBILITIES: TxDOT

X Development of plans and specifications

X Perform SWP3 inspections

X Maintain SWP3 records and update to reflect daily operations

Other:				
•				

Other:			
·			

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

X Day To Day Operational Control

X Maintain schedule of major construction activities

X Install, maintain and modify BMPs

□ Other:			
☐ Other:			

STORMWATER POLLUTION **PREVENTION PLAN (SWP3)** (Less Than 1 Acre)



* July 2023

Sheet 1 of 2

FED. RD. DIV. NO.		PROJECT NO.					SHEET NO.
6		SEE	TITLE	SHE	ET		75
STATE		STATE DIST.		С	OUNTY		
TEXAS	S	SAT		В	EXAR		
CONT.		SECT.	JOB		HI GHW	AY I	NO.
0073	3	02	088,E1	C	US	28	81

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND **MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP

SWI 3 of the COI .						
2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:						
T/P						
 Protection of Existing Vegetation Vegetated Buffer Zones X Soil Retention Blankets Geotextiles Mulching/ Hydromulching Soil Surface Treatments Temporary Seeding X Permanent Planting, Sodding or Seeding Biodegradable Erosion Control Logs 						
□ □ Rock Filter Dams/ Rock Check Dams						
□ □ Vertical Tracking						
□ □ Interceptor Swale □ □ Riprap						
□ □ Diversion Dike						
□ □ Temporary Pipe Slope Drain						
□ □ Embankment for Erosion Control						
□ Paved Flumes						
Other:						
□ Other:						
□ Other:						
- Outer.						
2.2 SEDIMENT CONTROL BMPs:						
T/P						
X □ Biodegradable Erosion Control Logs						
□ □ Dewatering Controls						
□ □ Inlet Protection						
□ □ Rock Filter Dams/ Rock Check Dams						
□ Sandbag BermsX □ Sediment Control Fence						
□ Stabilized Construction Exit						
□ Floating Turbidity Barrier						
□ Vegetated Buffer Zones						
□ Vegetated Filter Strips						
□ □ Other:						
□ □ Other:						
□ Other:						
□ Other:						
Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets						

located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

Turno	Stationing From To			
Туре	From To			

2.4 OFFSITE VEHICLE TRACKING CONTROLS:
X Excess dirt/mud on road removed daily
□ Haul roads dampened for dust control
□ Loaded haul trucks to be covered with tarpaulin
□ Stabilized construction exit
□ Daily street sweeping
□ Other:
□ Other:
□ Other:
□ Other:

2.5 POLLUTION PREVENTION MEASURES:

- X Chemical Management
- X Concrete and Materials Waste Management
- X Debris and Trash Management
- X Dust Control

□ Other:

Other:

□ Other: _			
□ Other: _			

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Statio	oning
Туре	From	То

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

2.10 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)



* July 2023 Sheet 2 of 2

FED. RD. DI V. NO.		PROJECT NO.				
6		SEE TITLE SHEET				
STATE	STATE COUNTY					
TEXAS		SAT	BEXAR			
CONT.		SECT.	JOB	HI GHWAY NO.		
0073		02	088,ETC	US 2	81	

STORMWATER POLLUTION PREVENTION PLAN (SWP3): This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP), The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project. For all projects with soil disturbing activity and for projects that have Environmental, Permits, Issues, and Commitments measures TxDOT will maintain a SWP3 with all pertinent

(EPICs) dependent on stormwater controls and water quality records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT	CONTROL	SECTION	JOB	(CSJ)
0073-03-072				

1.2 PROJECT LIMITS:

From: BEXAR/ATASCOSA COUNTY LINE

To: FM 3006

1.3 PROJECT COORDINATES:

,(Long) 98.4839°W BEGIN: (Lat) 29.1407°N

,(Long) 98.4773°W END: (Lat) 29.0112°N

1.4 TOTAL PROJECT AREA (Acres): 66.18 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 6.03 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY: **INSTALL CABLE BARRIER**

1.7 MAJOR SOIL TYPES:

Soil Type	Description

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below: PSLs determined during preconstruction meeting PSI's determined during construction

O_O GO.O	milou uumi	9 0011011 401
X No PSLs pla	nned for co	nstruction

Туре	Sheet #s		

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

X Mobilization

X Install sediment and erosion controls

☐ Blade existing topsoil into windrows, prep ROW, clear and grub

Remove existing pavement

X Grading operations, excavation, and embankment

- Excavate and prepare subgrade for proposed pavement widening
- ☐ Remove existing culverts, safety end treatments (SETs)
- ☐ Remove existing metal beam guard fence (MBGF), bridge rail
- ☐ Install proposed pavement per plans
- ☐ Install culverts, culvert extensions, SETs
- X Install mow strip, MBGF, bridge rail
- □ Place flex base

□ Other

- ☐ Rework slopes, grade ditches
- ☐ Blade windrowed material back across slopes
- X Revegetation of unpaved areas
- X Achieve site stabilization and remove sediment and erosion control measures

Other:			
_			

Ourior.			

1	10	DU.	TEN	TIAI	DΩI	LUT	2TINA	VND	SOL	JRCES:
	. I U	Γ	$ \square $	IIAL	PUL	LUI1	41Y I O	AND	300	IKCES.

- X Sediment laden stormwater from stormwater conveyance over disturbed area Fuels, oils, and lubricants from construction vehicles, equipment,
- and storage Solvents, paints, adhesives, etc. from various construction
- Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction
- Contaminated water from excavation or dewatering pump-out
- ☐ Sanitary waste from onsite restroom facilities
- ☐ Trash from various construction activities/receptacles
- □ Long-term stockpiles of material and waste

□ Other:			

☐ Other:			

1.11 RECEIVING WATERS:

Tributaries

Other:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Classified Waterbody

* Add (*) for impaired waterbodies	s with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- X Development of plans and specifications
- X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- X Post Construction Site Notice
- X Submit NOI/CSN to local MS4
- X Perform SWP3 inspections

Other:

- X Maintain SWP3 records and update to reflect daily operations
- X Complete and submit Notice of Termination to TCEQ
- M Maintain SWP3 records for 3 years

A Maintain Syn	3 lecolus	101	J	years
□ Other				•

□ Other:			
_ 0			

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- M Day To Day Operational Control
- X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- X Post Construction Site Notice

□ Other:

- X Submit NOI/CSN to local MS4
- X Maintain schedule of major construction activities
- X Install, maintain and modify BMPs
- X Complete and submit Notice of Termination to TCEQ
- X Maintain SWP3 records for 3 years

□ Other:			
□ Other:			

1,14 LOCAL MUNICIPAL SEPARATE STORM SEWER **SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity

STORMWATER POLLUTION PREVENTION PLAN (SWP3)



* July 2023 Sheet 1 of 2

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.	
6		SEE TITLE SHEET			77
STATE		STATE DIST.	c	OUNTY	
TEXAS SAT		BEXAR			
CONT.		SECT.	JOB	HI GHWAY	NO.
007	3	02	088,ETC	US 2	81

STORMWATER POLLUTION PREVENTION PLAN (SWP3): 2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND **MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this

SWP3 or the CGP.				
2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:				
T/P				
 □ Protection of Existing Vegetation □ Vegetated Buffer Zones □ X Soil Retention Blankets □ Geotextiles □ Mulching/ Hydromulching □ Soil Surface Treatments □ Temporary Seeding □ X Permanent Planting, Sodding or Seeding □ Biodegradable Erosion Control Logs 				
□ Rock Filter Dams/ Rock Check Dams				
 □ Vertical Tracking □ Interceptor Swale □ Riprap □ Diversion Dike □ Temporary Pipe Slope Drain □ Embankment for Erosion Control □ Paved Flumes □ Other: □ Other: 				
Other:				
□ □ Other:				
2.2 SEDIMENT CONTROL BMPs:				
 X				
□ Vegetated Filter Strips				

□ □ Other:

□ □ Other: □ □ Other:_____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets

located in Attachment 1.2 of this SWP3

□ Other:

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

T/P

□ □ Sediment Trap

□ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
$\hfill \Box$ 3,600 cubic feet of storage per acre drained
Sedimentation Basin
□ Not required (<10 acres disturbed)
□ Required (>10 acres) and implemented.
□ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
$\ \square$ 3,600 cubic feet of storage per acre drained
□ Required (>10 acres), but not feasible due to:
☐ Available area/Site geometry
☐ Site slope/Drainage patterns
☐ Site soils/Geotechnical factors
□ Public safety
□ Other:

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

From	oning To
	То

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

X Excess dirt/mud on road removed daily	
☐ Haul roads dampened for dust control	
☐ Loaded haul trucks to be covered with tarpaulin	
☐ Stabilized construction exit	
□ Daily street sweeping	
□ Other:	
2.5 POLLUTION PREVENTION MEASURES:	
X Chemical Management	
X Concrete and Materials Waste Management	
X Debris and Trash Management	
X Dust Control	
X Sanitary Facilities	
□ Other:	
-	

2.6 VEGETATED BUFFER ZONES:

□ Other: _____

□ Other: _____

□ Other:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing		
Туре	From	То	

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

When dewatering activities are present, a daily inspection will be conducted once per day during those activities and documented in accordance with CGP and TxDOT requirements.

2.10 MAINTENANCE: Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

STORMWATER POLLUTION **PREVENTION PLAN (SWP3)**



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.	
6		SEE TITLE SHEET 78			78
STATE		STATE DIST.			
TEXAS	S	SAT	BEXAR		
CONT.		SECT.	JOB	HI GHWAY	NO.
007	3	02	088,ETC	US 2	81

STORMWATER POLLUTION PREVENTION PLAN (SWP3): This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP), The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project. For all projects with soil disturbing activity and for projects that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL	SECTION	JOB (CSJ):
0073-04-051			

1.2	PRO	JECT	LIMITS:
-----	------------	-------------	---------

From: SOUTH OF EUROSTAR DR.

To: IH 37

1.3 PROJECT COORDINATES:

,(Long) 98.4731°W BEGIN: (Lat) 28.9373°N

,(Long) 98.4388°W END: (Lat) 28.9116°N

1.4 TOTAL PROJECT AREA (Acres): 19.64 AC

1.5 TOTAL AREA TO BE DISTURBED (Acres): 2.49 AC

1.6 NATURE OF CONSTRUCTION ACTIVITY:

1.7 MAJOR SOIL TYPES:

117 MAGGIC GOIL 111 EG.		∣ □ Excavat
Soil Type	Description	widenir
		☐ Remove
		☐ Remove
		─
		□ Install c
		X Install m
		☐ Place fle
		☐ Rework
		□ Blade w
		X Reveget
		X Achieve
		erosion
		□ Other: _
		☐ Other: _
		☐ Other: _

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below: PSLs determined during preconstruction meeting ☐ PSLs determined during construction

X No PSLs planned for construction

Туре	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

X Mobilization

X Install sediment and erosion controls

☐ Blade existing topsoil into windrows, prep ROW, clear and grub

Remove existing pavement

X Grading operations, excavation, and embankment

Excavate and prepare subgrade for proposed pavement widening

☐ Remove existing culverts, safety end treatments (SETs)

☐ Remove existing metal beam guard fence (MBGF), bridge rail

☐ Install proposed pavement per plans

☐ Install culverts, culvert extensions, SETs

X Install mow strip, MBGF, bridge rail

□ Place flex base

☐ Rework slopes, grade ditches

☐ Blade windrowed material back across slopes

X Revegetation of unpaved areas

X Achieve site stabilization and remove sediment and

erosion control measures

Other:			

□ Other:		

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- X Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction
- Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction
- Contaminated water from excavation or dewatering pump-out
- ☐ Sanitary waste from onsite restroom facilities
- ☐ Trash from various construction activities/receptacles
- ☐ Long-term stockpiles of material and waste

□ Other:			

Other:			
·			

Other:		
_		

1.11 RECEIVING WATERS:

Tributaries

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Classified Waterbody

* Add (*) for impaired waterbodies	s with pollutant in ()

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- X Development of plans and specifications
- X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- X Post Construction Site Notice
- X Submit NOI/CSN to local MS4
- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations
- X Complete and submit Notice of Termination to TCEQ

· · · · · ·	
Other:	
Unner	
_ 00	

☐ Other:			

□ Other:

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- M Day To Day Operational Control
- X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- X Post Construction Site Notice

□ Other:

- X Submit NOI/CSN to local MS4
- X Maintain schedule of major construction activities
- X Install, maintain and modify BMPs
- X Complete and submit Notice of Termination to TCEQ
- X Maintain SWP3 records for 3 years

□ Other: _____

□ Other:			
•			

1,14 LOCAL MUNICIPAL SEPARATE STORM SEWER **SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity

STORMWATER POLLUTION PREVENTION PLAN (SWP3)



* July 2023 Sheet 1 of 2

DIV. NO.		PROJECT NO.			NO.
6	SEE		TITLE SHEET		79
STATE	STATE STATE DIST.				
TEXAS	S	SAT	BEXAR		
CONT.		SECT.	JOB	HI GHWAY	NO.
007	3	02	088,ETC	US 2	81

STORMWATER POLLUTION PREVENTION PLAN (SWP3): 2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND **MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this

SWP3 or the CGP.			
2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:			
T/P			
□ Protection of Existing Vegetation□ Vegetated Buffer Zones			
□ X Soil Retention Blankets			
□ □ Geotextiles			
□ Mulching/ Hydromulching			
□ □ Soil Surface Treatments			
□ □ Temporary Seeding			
□ ★ Permanent Planting, Sodding or Seeding			
□ □ Biodegradable Erosion Control Logs			
□ Rock Filter Dams/ Rock Check Dams			
□ Vertical Tracking			
☐ ☐ Interceptor Swale			
□ □ Riprap			
□ □ Diversion Dike			
□ □ Temporary Pipe Slope Drain			
□ □ Embankment for Erosion Control			
□ □ Paved Flumes			
Other:			
Other:			
Other:			
□ Other:			
2.2 SEDIMENT CONTROL BMPs:			
T/P			
X Biodegradable Erosion Control Logs			
□ □ Dewatering Controls □ □ Inlet Protection			
□ Rock Filter Dams/ Rock Check Dams□ Sandbag Berms			
X Sediment Control Fence			
□ □ Stabilized Construction Exit			
□ Floating Turbidity Barrier			
□ Vegetated Buffer Zones			
□ □ Vegetated Filter Strips			

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

□ □ Other:_____

□ □ Other: □ □ Other: _____

□ Other:

Sediment control BMPs requiring design capacity calculations
(See SWP3 Attachment 1.3.):

T/P

□ □ Sediment Trap

□ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
□ 3,600 cubic feet of storage per acre drained
Sedimentation Basin
□ Not required (<10 acres disturbed)
□ Required (>10 acres) and implemented.
□ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
$\hfill \hfill $
□ Required (>10 acres), but not feasible due to:
☐ Available area/Site geometry
☐ Site slope/Drainage patterns
☐ Site soils/Geotechnical factors
□ Public safety
□ Other:

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

From	oning To
	То

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:
X Excess dirt/mud on road removed daily
☐ Haul roads dampened for dust control
☐ Loaded haul trucks to be covered with tarpaulin
☐ Stabilized construction exit
☐ Daily street sweeping
□ Other:
2.5 POLLUTION PREVENTION MEASURES:
X Chemical Management

- X Concrete and Materials Waste Management
- X Debris and Trash Management
- X Dust Control
- M Sanitary Excilition

	y raciliues		
□ Other:			
□ Other:			

Other:		

2.6 VEGETATED	BUFFER ZONES:

□ Other:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

T	Statio	oning
Туре	From	То

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

When dewatering activities are present, a daily inspection will be conducted once per day during those activities and documented in accordance with CGP and TxDOT requirements.

2.10 MAINTENANCE: Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

STORMWATER POLLUTION **PREVENTION PLAN (SWP3)**



© 2023 Sheet 2 of 2

FED. RD. DIV. NO.		SHEET NO.				
6		SEE	TITLE SHE	80		
STATE		STATE DIST.	COUNTY			
TEXA:	S	SAT	BEXAR			
CONT.		SECT.	JOB HI GHWAY NO.			
007	3	02	088,ETC US 28		81	

	I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402					
f any sion	Texas Pollutant Discharge Elimination System (TPDES) TXR 150000: Stormwater Discharge Permit or Construction General Permit (CGP) required for projects or more acres distrubed soil. Projects with any disturbed soil must protect erosion and sedimentation in accordance with Item 506.					
anty o conver se.	☐ No Action Required ☐ Required Action Action No.					
"Texas Engineering Practice Act". No warranty of any . TxDOT assumes no responsibility for the conversion ct results or damages resulting from its use.	 Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000. Comply with the Storm Water Pollution Prevention Plan (SW3P) and revise necessary to control pollution or required by the Engineer. Post Construction Site Notice (CSN) with SW3P information on or near the accessible to the public and Texas Commission on Environmental Quality (Environmental Protection Agency (EPA) or other inspectors. When Contractor project specific locations (PSL's) increase disturbed so to 5 acres or more, Contractor shall submit Notice of Intent (NOI) to To the Engineer. NOI required: Yes No 					
as Eng kDOT a						
rned by the "Tex e whatsoever. T for incorrect r	II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404					
ned by whatso	US Army Corps of Engineers (USACE) Permit required for filling, dredging, excavating or other work in any potential USACE jurisdictional water, such as, rivers, creeks, streams, or wetlands.					
randard is governed for any purpose who ther formats or for	The Contractor shall adhere to all of the terms and conditions associated the following permit(s):					
and is	No Permit Required					
stand)T for other	Nationwide Permit (NWP) 14 - Pre-construction Notice (PCN) not Require					
s st DOT o ot	Nationwide Permit 14 - PCN Required					
÷×÷	☐ Individual 404 Permit Required					
of by	Other Nationwide Permit Required: NWP#					
DISCLAIMER: The use of kind is made by æđwåþì&pst@r@gA	Required Actions: List waters of the US permit applies to, location in project on the check Best Management Practices (BMPs) planned to control erosion, sedimentation and post-project total suspended solids (TSS).					
0	1.					
ar d¢	2.					
pup	3.					
1/8+	4.					
;- > :-	··					
ع\ الر						
90.0						
7.0						
Barrier\Design\Civil\Standards\R						
	401 Best Management Practices: (Not applicable if no USACE permi-					
Cab le	Erosion Sedimentation Post-Construction					
	☐ Temporary Vegetation ☐ Silt Fence ☐ Vegetative Filter Str					
281	☐ Blankets/Matting ☐ Rock Berm ☐ Retention/Irrigation					
- NS	☐ Mulch ☐ Triangular Filter Dike ☐ Extended Detention Ba					
2024 9:44:58 PM 22\96\02\Tasks\13_US	Sodding Sand Bag Berm Constructed Wetlands					
4: 58 18Ks	☐ Interceptor Swale ☐ Straw Bale Dike ☐ Wet Basin					
9: 44	☐ Diversion Dike ☐ Brush Berms ☐ Erosion Control Compo					
5/02	☐ Erosion Control Compost ☐ Erosion Control Compost ☐ Mulch Filter Berm and					
2024	Mulch Filter Berm and Socks					
19/3	☐ Compost Filter Berm and Socks ☐ Compost Filter Berm and Socks ☐ Vegetation Lined Ditc ☐ Stone Outlet Sediment Traps ☐ Sand Filter Systems					
>						

MATERIALS OR CONTAMINATION ISSUES

plies to all projects):

lazard Communication Act (the Act) for personnel who will be working with als by conducting safety meetings prior to beginning construction and ware of potential hazards in the workplace. Ensure that all workers are rsonal protective equipment appropiate for any hazardous materials used. on-site Material Safety Data Sheets (MSDS) for all hazardous products ect, which may include, but are not limited to the following categories: olvents, asphalt products, chemical additives, fuels and concrete curing itives. Provide protected storage, off bare ground and covered, for ay be hazardous. Maintain product labelling as required by the Act. uate supply of on-site spill response materials, as indicated in the MSDS. spill, take actions to mitigate the spill as indicated in the MSDS, th safe work practices, and contact the District Spill Coordinator Contractor shall be responsible for the proper containment and cleanup oills.

neer if any of the follwing are detected:

- stressed vegetation (not identified as normal)
- s, drums, canister, barrels, etc.
- smells or odors
- leaching or seepage of substances

erials or Contamination Issues Specific to this Project:

No Action Required ■	Required Action
Action No.	
1.	
2.	

ect involve the demolition of a span bridge?

	Yes	\boxtimes	No	(No	further	action	required)
--	-----	-------------	----	-----	---------	--------	-----------

re- demolition notification must be submitted to the Texas Department th Services. The contractor shall contact TxDOT's Project Engineer 25 prior to the demolition of the bridges(s) on the project to assist fication.

VIRONMENTAL ISSUES

regional issues such as Edwards Aquifer District, etc.)

No Action Required	Required	Action
Action No.		



Texas Department of Transportation San Antonio District Standard

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

EPIC

FILE: epic_2015-10-09_SAT.dgn | DN: TxDOT | CK: TxDOT | DW: BW | CK: GAG CTxDOT OCTOBER 2015 CONT SECT JOB 0073 02 088,ETC US 281 BEXAR 81

. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402	III. CULTURAL RESOURCES	VI. HAZARDOUS
Texas Pollutant Discharge Elimination System (TPDES) TXR 150000: Stormwater Discharge Permit or Construction General Permit (CGP) required for projects with or more acres distrubed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.	Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.	General (app Comply with the H hazardous materia making workers aw
☐ No Action Required	No Action Required	provided with per Obtain and keep o used on the proje
Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.	Action No.	Paints, acids, so compounds or addi products which ma
 Comply with the Storm Water Pollution Prevention Plan (SW3P) and revise when necessary to control pollution or required by the Engineer. Post Construction Site Notice (CSN) with SW3P information on or near the site accessible to the public and Texas Commission on Environmental Quality (TCEQ) Environmental Protection Agency (EPA) or other inspectors. When Contractor project specific locations (PSL's) increase disturbed soil ar to 5 acres or more, Contractor shall submit Notice of Intent (NOI) to TCEQ an the Engineer. NOI required:	ea	Maintain an adequ In the event of a in accordance wit immediately. The of all product sp Contact the Engin * Dead or dis * Trash piles
Note: If amount of soil disturbance changes, permit requirements may change.		* Undesirable * Evidence of
	IV. <u>VEGETATION RESOURCES</u>	Hazardous Mate
I WODY IN OD NEAD STREAMS WATERPORTES AND WETLANDS CLEAN WATER	Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162,164, 192, 193, 506,	No Acti
I. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404 US Army Corps of Engineers (USACE) Permit required for filling, dredging,	730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.	Action No.
excavating or other work in any potential USACE jurisdictional water, such as, rivers, creeks, streams, or wetlands.	No Action Required	2.
The Contractor shall adhere to all of the terms and conditions associated with the following permit(s):	Action No.	3.
No Permit Required	1.	Does the proje
☐ Nationwide Permit (NWP) 14 - Pre-construction Notice (PCN) not Required	2.	Yes
☐ Nationwide Permit 14 - PCN Required		If "Yes", a pr
☐ Individual 404 Permit Required		of State Heal- calendar days
Other Nationwide Permit Required: NWP# Required Actions: List waters of the US permit applies to, location in project	V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.	with the noti-
and check Best Management Practices (BMPs) planned to control erosion, sedimentation and post-project total suspended solids (TSS).	AND WIGHT BINDS:	VII. OTHER ENV
1.	☐ No Action Required ☐ Required Action	(includes r
2.	Action No.	No Actio
3.	1. MIGRATORY BIRD NESTS: Schedule construction activities as needed to meet the following requirements:	Action No.
4.	A. Do not remove or destroy any active migratory bird nests (nests containing eggs and/or flightless birds) at any time of year. If there are any active nests, they shall not be removed until the nests become inactive.	1.
	B. On/in structures, if there are any active nests, they shall not be removed until all nests become inactive. After inactive nests are removed and/or before nest activity begins, deterrent materials may be applied to the structures to prevent future nest building. 2. See Item 5 in General Notes. 3.	
401 Best Management Practices: (Not applicable if no USACE permit)	4.	
Erosion Sedimentation Post-Construction TSS	If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The	
☐ Temporary Vegetation ☐ Silt Fence ☐ Vegetative Filter Strips	work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes	
☐ Blankets/Matting ☐ Rock Berm ☐ Retention/Irrigation Systems		
☐ Mulch ☐ Triangular Filter Dike ☐ Extended Detention Basin	Engineer immediately.	
☐ Sodding ☐ Sand Bag Berm ☐ Constructed Wetlands		
☐ Interceptor Swale ☐ Straw Bale Dike ☐ Wet Basin		
□ Diversion Dike □ Brush Berms □ Erosion Control Compost □ Fracion Control Compost □ Mylich Filter Porm and Socks		
☐ Erosion Control Compost ☐ Erosion Control Compost ☐ Mulch Filter Berm and Socks ☐ Mulch Filter Berm and Socks ☐ Compost ☐ Com		
Mulch Filter Berm and Socks	70	
☐ Compost Filter Berm and Socks ☐ Compost Filter Berm and Socks ☐ Vegetation Lined Ditches ☐ Stone Outlet Sediment Traps ☐ Sand Filter Systems		
Sediment Basins Sedimentation Chambers		

Galvanized hinge joint knot woven mesh (12.5 GA.SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Embed posts 18" min. or Anchor if in rock.

Sediment Control Fence

GENERAL NOTES

- 1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
- 2. Perform vertical tracking on slopes to temporarily stabilize soil.
- 3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
- 4. Do not exceed 12" between track impressions.
- 5. Install continous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING



TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

FENCE & VERTICAL TRACKING

EC(1)-16

ILE: ec116	DN: TxDOT		CK: KM	DW: '	VP DN/CK: LS		
TxDOT: JULY 2016	CONT	SECT	JOB		H	HIGHWAY	
REVISIONS	0073	02	088,ETC (U	JS 281	
DIST COUNTY		SHEET NO.		l			
	SAT	BEXAR				82	1

TEMP. EROSION 7

MIN

SECTION A-A

EROSION CONTROL LOG DAM

CL-D

— EROSION CONTROL LOG AT BACK OF CURB

EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING

EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING

- EROSION CONTROL LOG AT DROP INLET

EROSION CONTROL LOG AT CURB INLET

- EROSION CONTROL LOG AT CURB & GRATE INLET

- EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

LEGEND

- EROSION CONTROL LOG DAM

CONTROL LOG

(TYP.

COMPOST CRADLE UNDER EROSION

CONTROL LOG

CL-D

-(CL-BOC)∙

(CL-ROW)

(CL-SST

-(CL-SSL

CL-DI

(CL-CI

CL-GI

anty of or for i this standard is nes no responsibil 3/19/2024 P: \122\96 DATE:

STAKE ON DOWNHILL SIDE OF LOG AT 8' (ON CENTER) MAX. AS NEEDED TO SECURE LOG, FLOW ADDITIONAL UPSTREAM (TYP.) OR AS DIRECTED BY THE STAKES FOR HEAVY TEMP. EROSION FLOW ENGINEER. RUNOFF EVENTS CONTROL LOG SECURE END ADDITIONAL UPSTREAM -STAKES FOR HEAVY OF LOG TO STAKE AS RUNOFF EVENTS DISTURBED AREA DIRECTED FLOW SECURE END BACK OF CURB SECURE END OF LOG TO OF LOG TO -LIP OF GUTTER STAKE LOG ON DOWNHILL STAKE AS STAKE AS SIDE AT THE CENTER, DIRECTED DIRECTED AT EACH END, AND AT STAKE ON DOWNHILL SIDE OF ADDITIONAL POINTS AS TEMP. EROSION LOG AT 8' (ON CENTER) MAX. ADDITIONAL UPSTREAM NEEDED TO SECURE LOG CONTROL LOG AS NEEDED TO SECURE LOG, STAKES FOR HEAVY (4' MAX. SPACING), OR AS DIRECTED BY THE RUNOFF EVENTS OR AS DIRECTED BY ENGINEER. THE ENGINEER. PLAN VIEW

R.O.W.

STAKE LOG ON DOWNHILL

SIDE AT THE CENTER,

AT EACH END, AND AT

ADDITIONAL POINTS AS

NEEDED TO SECURE LOG

AS DIRECTED BY THE

ENGINEER.


(4' MAX. SPACING), OR

ADDITIONAL UPSTREAM

STAKES FOR HEAVY

RUNOFF EVENTS

PLAN VIEW



SECTION C-C

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROV

EROSION CONTROL LOG AT BACK OF CURB

TEMP. EROSION

COMPOST CRADIT

UNDER EROSION

CONTROL LOG

CONTROL LOG

CL-BOC

SECTION B-B

REBAR STAKE DETAIL

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

The drainage area for a sediment trap should not exceed Log Traps: 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets
- 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

GENERAL NOTES:

- 1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
- 2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.

TEMPORARY

-DISTURBED AREA

LIP OF GUTTER


EROSION

CONTROL

LOG

BACK OF CURB

- UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
- FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
- STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
- 6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
- 7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
- SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
- TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE
- 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

SHEET 1 OF 3



TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

EROSION CONTROL LOG

EC(9) - 16

FILE: ec916	LE: ec916 DN:TxDOT		ск: КМ	DW:	LS/PT	ck: LS
© TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0073	02	02 088,ETC		US 281	
	DIST	DIST COUNTY			SHEET NO.	
	SAT BEXAR			83		

SECURE END > OF LOG TO STAKE AS

TEMP. EROSION-CONTROL LOG

FLOW

3/19/2024 P:\122\96\

EROSION CONTROL LOG AT CURB & GRADE INLET

SANDBAG

OVERLAP ENDS TIGHTLY 24" MINIMUM


---- FLOW


EROSION CONTROL LOG AT DROP INLET

CURB AND GRATE INLET


-STAKE OR USE SANDBAGS ON DOWNHILL SIDE OF LOG AS NEEDED TO HOLD IN PLACE (TYPICAL)

COMPLETELY SURROUND
DRAINAGE ACCESS TO
AREA DRAIN INLETS WITH
EROSION CONTROL LOG







EROSION CONTROL LOG AT CURB INLET



EROSION CONTROL LOG AT CURB INLET



NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



SANDBAG DETAIL

SHEET 3 OF 3



TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES EROSION CONTROL LOG

EC(9) - 16

		•					
ILE: ec916 DN:TxDOT		ск: КМ	DW:	LS/PT	ck: LS		
© TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY		
REVISIONS	0073	02	088,ETC		US	US 281	
	DIST COUNTY		SHEET NO.				
		BEXAR				85	