

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	F 2B24(172)		1
STATE	STATE DIST.	COUNTY	
TEXAS	SAT	BEXAR, ETC	
CONT.	SECT.	JOB	HIGHWAY NO.
0915	00	268	VARIOUS

INDEX OF SHEETS

SEE SHEET 2 FOR INDEX OF SHEETS

DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT  
 NO. F 2B24(172)  
 CSJ: 0915-00-268

COUNTY: GUADALUPE AND KERR  
 ROADWAY: VARIOUS


LIMITS: VARIOUS LOCATIONS DISTRICTWIDE ON THE IH-10 CORRIDOR

DESIGN SPEED = N/A  
 AREA OF DISTURBED SOIL = 0.23 ACRES  
 ADT: N/A

FOR WORK CONSISTING OF INSTALLATION OF DYNAMIC PARKING AVAILABILITY SIGNS (DPAS) FOR TRUCK PARKING AVAILABILITY SYSTEMS (TPAS)

FINAL PLANS

LETTING DATE: \_\_\_\_\_  
 DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_  
 DATE WORK WAS ACCEPTED: \_\_\_\_\_  
 FINAL CONTRACT COST: \$ \_\_\_\_\_  
 CONTRACTOR: \_\_\_\_\_



FINAL PLANS STATEMENT:

THE CONSTRUCTION WORK WAS PERFORMED IN ACCORDANCE WITH THE PLANS.

\_\_\_\_\_ P.E. \_\_\_\_\_ DATE \_\_\_\_\_  
 AREA ENGINEER

TEXAS DEPARTMENT OF TRANSPORTATION

EXCEPTIONS: NONE  
 EQUATIONS: NONE  
 RAILROAD CROSSINGS: NONE

COUNTY \_\_\_\_\_ PROJ. NO. \_\_\_\_\_  
 HWY. NO. \_\_\_\_\_ LETTING DATE \_\_\_\_\_  
 DATE ACCEPTED \_\_\_\_\_



HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 TBPE Firm Registration No. 420

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023)



Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED

SUBMITTED FOR LETTING 3/21/2024  
 DocuSigned by: *Vazge Ramos*  
 TRANSPORTATION ENGINEER SUPERVISOR

RECOMMENDED FOR LETTING 3/22/2024  
 DocuSigned by: *Clayton Kipps, P.E.*  
 DISTRICT ENGINEER

REVIEWED FOR LETTING 3/22/2024  
 DocuSigned by: *D. Rayno, P.E.*  
 TRANSPORTATION ENGINEER SUPERVISOR

APPROVED FOR LETTING 3/25/2024  
 DocuSigned by: *Charles Benavides*  
 DISTRICT ENGINEER

pw: \\pw-int.hntb.org:PWCentralID\Documents\Son Antonio Projects\73627 SAT Traffic-ITS\WA03\Design and Engineering\SAT\02\_General\Sheet DGN\73627\_WA03\_SAT\_01\_S-GEN-TTL.dgn

I. GENERAL

1	TITLE SHEET
2	INDEX OF SHEETS
3, 3A-3E	GENERAL NOTES
4, 4A	ESTIMATE AND QUANTITY
5-6	SUMMARY OF QUANTITIES
7	SUMMARY OF LARGE SIGNS
8	TMA AND TA SUMMARY
9	I-10 TPAS LOCATION MAP

II. TRAFFIC CONTROL PLAN STANDARDS

10-21	* BC(1)-21 THRU BC (12)-21
22	* TCP (1-5)-18
23	* TCP (5-1)-18
24-28	* TCP (6-1)-12 THRU TCP (6-5)-12
29	TPAS TCP WITHIN SRA/TIC - TYPICAL

III. ROADWAY STANDARDS

30	* GF (31)-19
31	* GF (31)DAT-19
32	* GF (31)MS-19
33	* SGT (10S)31-16
34	* SGT (11S)31-18
35	* SGT (12S)31-18

IV. ITS ITEMS


36	KERR COUNTY LAYOUT SHEET ID
37	KERR COUNTY SRA I-10 EB ITS LAYOUT
38	KERR COUNTY SRA I-10 EB SIGN LAYOUT
39-41	KERR COUNTY SRA I-10 WB ITS LAYOUT
42-43	KERR COUNTY SRA I-10 WB SIGN LAYOUT
44	KERR COUNTY LARGE SIGN DETAILS
45	GUADALUPE COUNTY LAYOUT SHEET ID
46-47	GUADALUPE COUNTY SRA I-10 EB ITS LAYOUT
48	GUADALUPE COUNTY SRA I-10 EB SIGN LAYOUT
49-52	GUADALUPE COUNTY SRA I-10 WB ITS LAYOUT
53	GUADALUPE COUNTY SRA I-10 WB SIGN LAYOUT
54	GUADALUPE COUNTY LARGE SIGN DETAILS
55	ELECTRICAL SERVICE SUMMARY
56-59	VOLTAGE DROP
60	TYPICAL DPAS COMMUNICATIONS DETAIL
61	TYPICAL CCTV COMMUNICATIONS DETAIL

V. TRAFFIC STANDARDS

62-66	* TSR (1)-13 THRU TSR(5)-13
67	* SMD (2-1)-08
68	* SMD (2-2)-08
69	* SMD (2-3)-08
70	* SMD (2-6)-01
71-72	* SMD (8W1)-08 THRU SMD (8W2)-08
73	** WV & IZ-14
74	** WV & IZ (LTS2013)-14
75-76	** D & OM (1)-20 THRU D & OM (2)-20
77	** ED (1)-14
78-82	** ED (3)-14 THRU ED (7)-14
83	** ED (10)-14
84	** ITS (1)-15
85	** ITS (2)-15
86	** ITS (3)-16
87	** ITS (4)-15
88	** ITS (4A)-15
89	** ITS (5)-15
90	** ITS (6)-15
91	** ITS (7)-15
92	** ITS (14)-15
93	** ITS (15)-15
94	** ITS (17)-15
95	** ITS (18)-15
96	** ITS (19)-17
97	** ITS (21)-15
98	** ITS (22)-15

VI. ENVIRONMENTAL ISSUES

99	** EPIC
100-101	** SW3P




*Charles D. Koonce III*

3/15/2024

CHARLES D. KOONCE III

DATE

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED BY (\*) HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



*Sai Geetha*

3/15/2024

SAI GEETHA KOGANTI

DATE

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED BY (\*\*) HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

© 2024  
 Texas Department of Transportation

INDEX OF SHEETS

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	2



\*\*\*\*\*GENERAL NOTES\*\*\*\*\*

**--General--**

Work under this contract shall consist of the installation of ITS equipment for a Truck Parking Availability System at various locations along IH-10.

Abbreviations:

- “TPAS” – Truck Parking Availability System
- “DPAS” – Dynamic Parking Availability Sign
- “ITS” – Intelligent Transportation System
- “SRA” – Safety Rest Area
- “TIC” – Travel Information Center

The following TPAS equipment will be furnished by the Department and shall be installed by the contractor at each SRA/TIC site as shown on the plans:

- Pole mounted integrated enclosures (Dimensions approx 295.5mm x 351mm x 150mm (WxHxD))
- Parking area PTZ cameras (Axis, PN01146-001, M5525-E PTZ Axis Surveillance Camera)
- Vehicle detectors (Omnisight MEGARADAR-V4; Dimensions approx 102mm x 151.3mm x 25.56 mm (WxHxD))
- All cabling/connectors from PTZ camera to pole mounted integrated enclosure
- All cabling/connectors from vehicle detector to pole mounted integrated enclosure
- All mounting hardware

TxDOT’s TPAS vendor, EX2 Technology, LLC, will ship the equipment to the contractor. Do not begin installation work until the vendor representative is on-site. The vendor will provide on-site installation oversight, calibration, and system acceptance testing. The contractor shall coordinate scheduling of the installation and testing work with the vendor. Please contact Bill Loghry with EX2 Technology, LLC at (402) 506-9649 to coordinate shipping the equipment, scheduling the work, and for any questions about the above listed equipment. The contractor shall mount the Department supplied cameras, vehicle detectors, and integrated enclosure cabinets on the ITS poles per the vendor recommendations.

Overhead and underground utilities exist in the vicinity of this project. The exact location of underground utilities is not known. Locate and verify all overhead and underground utilities in the project area prior to beginning work so that conflicts are avoided. Provide all equipment necessary for locating the utilities, locate and mark the utilities prior to doing any earthwork in

the area. Consider this work incidental to the various bid items. Coordinate with the utility companies and notify the Engineer of any possible conflicts. Caution should be taken prior to excavation where underground utilities may exist and run in conflict with the proposed route of the new conduits. It is the contractor’s responsibility to locate all of them before excavation. In the event that any part of the existing underground utilities are damaged during construction, the contractor will repair or replace the damaged equipment immediately at no cost to the Department. Consider the cost for locating existing underground utilities subsidiary to various bid items.

Location of overhead utilities shown on the plans are approximate and are not based on survey data. The contractor shall ensure that all work meets requirements for minimum clearance to overhead utilities.

Utility contact information is as follows:

Location Name	Rest Area or DPAS	Utility Company Name	Contact Person	Email	Phone	Address
Kerr Co EB	Rest Area	CTEC	Mitch Elmore	<a href="mailto:mitch.elmore@ctec.com">mitch.elmore@ctec.com</a>	830-997-2126	386 Friendship Lane, Fredericksburg, TX 78624
Kerr Co WB	Rest Area	CTEC				
Kerr Co WB	DPAS	CTEC				
Kerr Co EB	DPAS	KPUB	Yesenia Bernal	<a href="mailto:ybernal@kpub.com">ybernal@kpub.com</a>	830-257-3050	2250 Memorial Blvd, Kerrville, TX 78028
Guadalupe Co EB	Rest Area	GVEC	Gerald Bazan	<a href="mailto:gbazan@gvec.org">gbazan@gvec.org</a>	830-203-8902	6400 W. IH-10, Seguin, TX 78155
Guadalupe Co EB	DPAS	GVEC				
Guadalupe Co WB	Rest Area	GVEC				
Guadalupe Co WB	DPAS	Bluebonnet	Rodney Gerik	<a href="mailto:Rodney.gerik@bluebonnet.coop">Rodney.gerik@bluebonnet.coop</a>	979-542-8527	P.O. Box 729, 155 Electric Ave., Bastrop, TX 78602

The contractor shall be responsible for contacting all electrical power companies to have services installed and established for each ITS equipment location. Have the electrical service initially established under the contractor’s name and then transfer ownership of the electrical service to TxDOT after the project is completed.

ITS equipment and conduit locations are approximate; the precise location is to be determined in the field, therefore the Contractor should not scale equipment off of plan sheets. Plan sheets are to be used for visual location (vicinity). Equipment locations may have to be adjusted due to conflicts with utilities or other structures, as approved by the Engineer.

As-builts or plans of the safety rest areas, that were available at the time these plans were developed, were used to make some adjustments to locations of the proposed ITS infrastructure including conduit, ground boxes, and poles in order to avoid utilities. However, the exact

location of underground utilities is not known. The contractor shall verify and locate all utilities before beginning construction. These as-builts and plans may not reflect the current site conditions. The contractor may request a copy of these as-builts and plans from the district office.

Assume full responsibility for the preservation of all sod, shrubbery, and trees at the site during construction. Carefully preserve and replace, in their original position, all sod and shrubbery removed. Replace all Contractor damaged sod or shrubbery at the Contractor's own expense. Any materials removed and not reused and determined to be salvageable shall be stored within the project limits at an approved location or delivered undamaged to the storage yard as directed. Deface traffic signs so that they will not reappear in public as signs.

Any sign panels that are adjusted or removed and replaced, shall be done the same workday unless otherwise approved. This work shall be considered subsidiary to Item 502. Locate and reference all manholes and valves within the construction area with station and offset or GPS. Each manhole and valve shall be identified by its owner (SAWS, CPS, etc.). No roadwork will begin until this list has been submitted. All valves and manhole covers have to be accessible at all times, therefore; temp. CTB, material stockpiles, etc. cannot be placed over these valves or covers.

**Hurricane Evacuation**

Hurricane Season is from June 1 thru November 30. As the closest metropolitan city inland from the Texas Coast, the City of San Antonio is a major shelter destination during mandatory hurricane evacuations. As such, planned work zone lane or road closures may be restricted and/or suspended during mandatory hurricane evacuation operations. The District will coordinate these restrictions at a minimum H-120 from any projected impact to the Texas Coast.

No time charges will be made if the Engineer determines that work on the project was impacted by the hurricane.

The Engineer may order changes in the Traffic Control Plan to accommodate evacuation traffic, and may suspend the work, all or in part, to ensure timely completion of this work. All work to implement changes in the Traffic Control Plan will be paid through existing bid prices or through Item 9.5, Force Account. However, the Department will not entertain any request for delay damages, loss of efficiency that may be attributed to the restriction or suspension of road or lane closures, or to changes in the Traffic Control Plan.

In accordance with the Underground Facility Damage Prevention Act (One Call Bill) the phone number for a utility locator is 811. It is the Contractor's responsibility to call and plan for utility locators.

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way. Call or email the TxDOT offices listed below for locates a minimum of 48

hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a minimum of 48 hours in advance of excavation. The Contractor is liable for all damages incurred to the above-mentioned utilities when working without having the utilities located prior to excavation.

For signal and ITS locates call TransGuide at 210-731-5136 or email [sat\\_its\\_locates@txdot.gov](mailto:sat_its_locates@txdot.gov) for ITS locates and [signal.request@txdot.gov](mailto:signal.request@txdot.gov) for signal locates.

Contractor questions on this project are to be addressed to the following individual(s):  
Area Engineer, Dale Picha,P.E., [Dale.Picha@txdot.gov](mailto:Dale.Picha@txdot.gov)  
Assistant Area Engineer, Jorge Ramos,P.E., [Jorge.Ramos@txdot.gov](mailto:Jorge.Ramos@txdot.gov)

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:  
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

The contractor shall limit all work activities to within the right of way. The contractor shall ensure that all infrastructure installation is within the right of way. No provisions have been made for work activities or storage of materials or equipment on private property.

**--Item 2--**

This project includes technical qualification for ITS work. See special provision to Item 2 for more information.

**--Item 5--**

Prevention of Migratory Bird Nesting

It is anticipated that migratory birds, a protected group of species, may try to nest on bridges, culverts, vegetation, or gravel substrate, at any time of the year. The preferred nesting season for migratory birds is from February 15 through October 1. When practicable, schedule construction operations outside of the preferred nesting season. Otherwise, nests containing migratory birds must be avoided and no work will be performed in the nesting areas until the young birds have fledged.

Structures

Bridge and culvert construction operations cannot begin until swallow nesting prevention is implemented, until after October 1 if it's determined that swallow nesting is actively occurring, or until it's determined swallow nests have been abandoned. If the State installed nesting deterrent on the bridges and culverts, maintain the existing nesting deterrent to prevent swallow nesting until October 1 or completion of the bridge and culvert work, whichever occurs earlier. If new nests are built and occupied after the beginning of the work, do not perform work that can interfere with or discourage swallows from returning to their nests. Prevention of swallow nesting can be performed by one of the following methods:

1. By February 15 begin the removal of any existing mud nests and all other mud placed by swallows for the construction of nests on any portion of the bridge and culverts. The Engineer will inspect the bridges and culverts for nest building activity. If swallows begin nest building, scrape, or wash down all nest sites. Perform these activities daily unless the Engineer determines the need to do this work more frequently. Remove nests and mud through October 1 or until bridge and culvert construction operations are completed.
2. By February 15 place a nesting deterrent (which prevents access to the bridge and culvert by swallows) on the entire bridge (except deck and railing) and culverts. This work is subsidiary to the various bid items.

No extension of time or compensation payment will be granted for a delay or suspension of work caused by nesting swallows.

Excavation within 5 feet of an existing CPS Energy pole will require pole bracing. Contact CPS Energy utility coordination to request pole bracing (Customer Engineering 210-353-4050). The estimated duration for the pole bracing process is approximately 10 to 15 weeks.

**--Item 6--**

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

**--Item 7--**

The total disturbed area within the project is anticipated at less than one (1) acre. Due to this type of construction, the project qualifies for exclusion under the Construction General Permit

(CGP) issued by the Texas Commission on Environmental Quality (TCEQ). However, should the sum of the Engineer's anticipated disturbances and the Contractor's (On ROW and off ROW) PSL's equal or exceed the one (1) acre threshold; both TxDOT and the Contractor have project responsibilities under the CGP that reverts to non-exclusion status. Obtain approval for all non-depicted areas of disturbance that increases the initial soil and vegetation disturbed area estimates before work starts at these locations.

Notify the Engineer of the disturbed acreage within one (1) mile of the project limits. Obtain authorization from the TCEQ for Contractor PSL's for construction support activities on or off ROW.

No significant traffic generators events identified.

**--Item 8--**

Working days will be computed and charged in accordance with Article 8.3.1.4 standard work week.

A Special Provision to Item 8 has been included in the contract to allow work to begin within 90 days after the authorization date to begin work. The reason for including the Special Provision is for material processing or contractor mobilization.

Create and maintain a Bar Chart schedule.

**--Item 9--**

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" (Course #133119) which can be found online at the following site: [www.nhi.fhwa.dot.gov](http://www.nhi.fhwa.dot.gov) Certificates of completion should be available to all who finish the course. These should be kept by the officers to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case-by-case basis.

**Control: 0915-00-268**

**County:** Bexar, Etc.

**Highway:** Various

**--Item 416--**

Stake all Foundations, for approval, before beginning drilling operations. Obtain approval of placement prior to placing concrete.

Remove spoils from site at the end of each work day.

Cover drilled shafts with plywood and delineate them with cones, to the satisfaction of the Engineer, when not working in them and after work hours.

**--Item 421--**

Use an automated ticket that contains the same information as shown in the standard specification. Submit the ticket for approval prior to use. The concrete producer will contact the District Laboratory or the Engineer's Office (outside the San Antonio area) to inform TxDOT of scheduled structural concrete batching. The Engineer may suspend concrete operations if ticket information is incomplete/incorrect.

Entrained air is allowed for Class P and Class HES concrete only. Air content testing is waived for all classes of concrete.

The curing facilities and strength testing equipment is not required for this project.

Poly-fiber reinforced concrete may be used as an option, with the approval by the Engineer, for riprap, sidewalk, curb/gutter, and mow strip. Use a TxDOT approved manufacturer or producer for the poly-fiber. The poly-fibers shall be combined with the concrete in proportions as recommended by the manufacturer. A concrete mix design must be approved by the Engineer.

**--Item 500--**

"Materials on Hand" payments will not be considered in determining percentages for mobilization payments.

**--Item 502--**

General

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 2 hours or within a reasonable time frame as specified by the Engineer.

Avoid placing stockpiles, equipment, and other construction materials within the roadway's horizontal clear zone or at any location that will constitute a hazard and will endanger traffic. If a stockpile is placed within the clear zone, address in accordance with the TMUTCD.

**Control: 0915-00-268**

**County:** Bexar, Etc.

**Highway:** Various

If Nighttime work is required and work is not behind positive barrier then full Class 3 reflective gear is required to be worn by all workers, hard hat halos are required to be worn by the flaggers at flagging stations, TY III barricades are required to be spaced at 500 ft, and a mandatory night work meeting is required.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access to adjoining property must be maintained at all times.

Barricades, Signs, and Traffic Control Devices

When advanced warning flashing arrow panels and/or changeable message sign is specified, have one standby unit in good condition at the job site. Standby time shall be considered subsidiary to the bid item.

After written notification, the time frame is provided on the Form 599 to provide properly maintained signs and barricades before considered in non-compliance with this item.

Moving an existing sign to a temporary location is subsidiary to Item 502. Installations with permanent supports at permanent locations will be paid for under the applicable bid item(s).

Cover permanent signs if not used. This is subsidiary to Item 502.

Provide orange construction fencing as approved at all work locations, including but not limited to all bore pit locations, to protect pedestrians. This material and its placement will be considered subsidiary to Item 502.

Lane and Ramp Closures and Detours

Notify the Engineer in writing 10 business days in advance of any temporary or permanent lane, ramp, connector, etc. closures/detours, restrictions to lane widths, alterations to vertical clearances, or modifications to radii. Any other modifications to the roadway that may adversely affect the mobility of oversized/overweight trucks also require 10 business days advance written notice to the Engineer. At least one lane must always remain open.

For closures not listed in the TCP; the lane closures are limited to between the hours of 9 AM to 4 PM Mon. – Fri. for daytime closures and 9 PM to 5 AM Mon. – Fri. for nighttime closures, and at least one lane must remain open at all times.

**Control: 0915-00-268**

**County:** Bexar, Etc.

**Highway:** Various

At no time shall two consecutive ramps be closed at one time during construction or overlay operations.

No lane closures will be permitted for the following dates and/or special events:

Between December 15 and January 1

Fiesta Week and Sales Tax Holidays (Bexar County Only)

Wednesday before Thanksgiving thru the Sunday after Thanksgiving

Saturday and Sunday before Memorial Day and Labor Day

Saturday or Sunday when July 4 falls on a Friday or Monday

Election days (Bexar County Only)

During major events at the AT&T Center (Spurs home games, Rodeo, concerts, etc.)

Alamodome, and/or Convention Center (Bexar County Only)

Hauling

The use of rubber-tired equipment will be required for moving dirt or other materials along or across pavement surfaces. Where the contractor desires to move any equipment not licensed for operation on public highways, on or across pavement, they shall protect the pavement from damage as directed/approved by the Engineer.

Throughout construction operations, the Contractor will be required to conduct their hauling operations in a manner such that vehicles will not haul over previously recompacted subgrade or compacted base material, except in short sections for dumping manipulations.

The Contractor shall keep the roadway clean and free of dirt or other materials during hauling operations. If the Contractor does not maintain a clean roadway, they shall cease all construction operations, when directed by the Engineer, to clean the roadway to the satisfaction of the Engineer.

**--Item 506--**

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7. An Inspector will perform a regularly scheduled SW3P inspection every 7 calendar days if erosion control measures are installed.

Failure to address items noted on the SW3P inspection report within two report cycles may result in the Department stopping all construction operations, exclusive of time charges, or withholding that month's estimate until the SW3P deficiencies are corrected unless the Engineer determines that the area is too wet to correct SW3P deficiencies.

**Control: 0915-00-268**

**County:** Bexar, Etc.

**Highway:** Various

Failure to correctly maintain daily monitoring reports and submitting to TxDOT on a daily/weekly basis may result in the monthly estimate being withheld.

**--Item 540--**

Guard fence posts placed in proposed and/or existing areas of riprap, sidewalks or other concrete shall have an 18 inch +/- (square or round) leave-out in the concrete as shown in the state standard for MBGF Mow Strip. After the posts are installed, fill the leave-outs with a Grout mixture as shown in the state standard for MBGF Mow Strip.

Complete the installation of metal beam guard fence before installing DPAS and cabinet.

When connecting a Thrie-Beam to a concrete wingwall, bridge rail, CTB, etc., drill the holes for bolt placement using rotary or core type equipment. Use a core type drill when reinforcing steel is encountered. Do not use percussion or impact drilling. Repair damage to the concrete and spalls exceeding 1/2" from the edge of the hole.

**--Item 542--**

Salvage all undamaged/acceptable radius guardrail and deliver to the TxDOT maintenance section yard.

**--Item 618--**

It might be necessary to cut concrete for placement of conduit. Saw cut existing concrete, remove the concrete from the steel reinforcement (bars or fabric) and bend the steel to install the conduit. After the conduit has been placed, bend the steel back to its original position and back-fill the trench with an approved concrete. This work is subsidiary to this Item.

Use materials from Material Producers list as shown on the Construction Division's (CST) web site. Category is "Roadway Illumination and Electrical Supplies."

The locations of conduit and ground boxes are diagrammatic and may be shifted, as directed, to accommodate field conditions.

Ensure open trenches and excavations are filled at the end of each work day.

Close the bore pit holes during non-working hours.

**--Item 620--**

Electrical conductor sizes and quantities are based on estimated location of power source. Final location of utility provider power source to be approved by TxDOT to ensure location is within allowable distance.

**Control: 0915-00-268**

**County:** Bexar, Etc.

**Highway:** Various

**--Item 624--**

Location and estimated number of ground boxes are diagrammatic only and may vary to accommodate field conditions as directed.

**--Item 628--**

Make all arrangements for electrical service, and compliance with local standards and practices for proper installations.

The location of the service poles as shown are approximate. All cost associated with the installation and connection of service to the electrical utility company will be considered incidental to the item, "Electrical Services". This includes conduit, conduit fittings and electrical conductors.

Primary line extensions, connection charges, meter charges, and other charges by the utility company providing power to the location shown, when required, are paid for by force account work. Obtain the Engineer's approval for the costs associated with these charges before engaging the utility company to perform the work.

**--Item 636--**

Use established industry and utility safety practices and comply with Federal, State and Local regulations when erecting signs near any overhead or underground utility. Consult with the appropriate utility company prior to beginning such work.

**--Item 647--**

The post lengths shown on the Summary Of Large Signs are approximations only. Verify the post lengths to meet the existing field conditions, and submit actual post lengths to the Engineer for approval. Post lengths and size shall be approved the Engineer before fabrication.

Stake all new ground mounted large sign supports locations and obtain approval from the Engineer before beginning construction of sign supports and assemblies. Proposed DPAS sign location coordinates shown on the plans are approximate. Verify proposed locations to meet existing field conditions.

Ensure lateral placement and sign heights for all proposed signs are in accordance the TMUTCD (2A.18) and TxDOT standards.

**-Item 6028--**

All three-character dynamic message sign modules and cabinets for the DPAS signs will be furnished by TxDOT. Three-character dynamic message sign modules will be Daktronics VM-1020-7X15-66. DPAS cabinet will be Daktronics type 334 ground mount. Contact Chris Delazerda at 210-669-2647 with the San Antonio District, Rodney Coursey with the San Antonio District at 830-257-8444, or Travis Young with the San Antonio District at 830-303-0130 in

**Control: 0915-00-268**

**County:** Bexar, Etc.

**Highway:** Various

advance to schedule pick up. All costs associated with pick up and transport of the sign modules and cabinets from the storage site to the final project locations shall be considered incidental to this Item.

See ITS (21)-15 for ground mounted cabinet foundation.

**--Item 6064--**

ITS poles within the Safety Rest Areas shall be located a minimum of 10 ft from the edge of pavement as shown in the plans or as directed by the Engineer.

**--Item 6185--**

The TMA's will be measured and paid for by the DAY for each TMA/TA set up and operational on the worksite. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project. See TMA and TA Summary sheet in the plans.

**--Items 6123 Ethernet Switch (Install Only) and 6511 Cellular Modem (Install Only)--**

Cellular modems and Ethernet switches with power supplies will be furnished by the department. Equipment provided by the department shall be stored by the department for pick up at the TxDOT San Antonio TransGuide Office, 3500 NW Loop 410 San Antonio, TX 78229.





# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0915-00-268

DISTRICT San Antonio

COUNTY Bexar

HIGHWAY Various

CONTROL SECTION JOB				0915-00-268		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00193285			
COUNTY				Bexar			
HIGHWAY				Various			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	416-6004	DRILL SHAFT (36 IN)	LF	105.000		105.000	
	416-6006	DRILL SHAFT (48 IN)	LF	84.000		84.000	
	416-6018	DRILL SHAFT (SIGN MTS) (24 IN)	LF	113.000		113.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY	13.750		13.750	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	43.790		43.790	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	12.000		12.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	775.000		775.000	
	540-6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	4.000		4.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000	
	618-6023	CONDT (PVC) (SCH 40) (2")	LF	4,210.000		4,210.000	
	618-6029	CONDT (PVC) (SCH 40) (3")	LF	495.000		495.000	
	618-6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	550.000		550.000	
	618-6054	CONDT (PVC) (SCH 80) (3") (BORE)	LF	1,450.000		1,450.000	
	618-6070	CONDT (RM) (2")	LF	160.000		160.000	
	620-6003	ELEC CONDR (NO.12) BARE	LF	260.000		260.000	
	620-6004	ELEC CONDR (NO.12) INSULATED	LF	520.000		520.000	
	620-6007	ELEC CONDR (NO.8) BARE	LF	505.000		505.000	
	620-6008	ELEC CONDR (NO.8) INSULATED	LF	4,495.000		4,495.000	
	620-6009	ELEC CONDR (NO.6) BARE	LF	1,735.000		1,735.000	
	620-6010	ELEC CONDR (NO.6) INSULATED	LF	7,275.000		7,275.000	
	620-6011	ELEC CONDR (NO.4) BARE	LF	1,090.000		1,090.000	
	620-6012	ELEC CONDR (NO.4) INSULATED	LF	9,730.000		9,730.000	
	620-6015	ELEC CONDR (NO.2) BARE	LF	1,820.000		1,820.000	
	620-6016	ELEC CONDR (NO.2) INSULATED	LF	8,950.000		8,950.000	
	620-6019	ELEC CONDR (NO.1/0) BARE	LF	2,165.000		2,165.000	
	620-6020	ELEC CONDR (NO.1/0) INSULATED	LF	4,210.000		4,210.000	
	624-6002	GROUND BOX TY A (122311)W/APRON	EA	43.000		43.000	
	628-6152	ELC SRV TY D 120/240 060(NS)SS(N)SP(O)	EA	7.000		7.000	
	636-6002	ALUMINUM SIGNS (TY G)	SF	707.000		707.000	
	647-6001	INSTALL LRSS (STRUCT STEEL)	LB	4,041.810		4,041.810	
	658-6015	INSTL DEL ASSM (D-SW)SZ (BRF)GF1	EA	31.000		31.000	
	6010-6002	CCTV FIELD EQUIPMENT (DIGITAL)	EA	4.000		4.000	
	6010-6011	CCTV FIELD EQUIP (DIGITAL) (INSTL ONLY)	EA	4.000		4.000	
	6028-6002	INSTALL DMS (FOUNDATION MTD CABINET)	EA	4.000		4.000	
	6064-6010	ITS POLE (30 FT)(90 MPH)	EA	7.000		7.000	
	6064-6055	ITS POLE (60 FT)(90 MPH)	EA	4.000		4.000	

DISTRICT	COUNTY	CCSJ	SHEET
San Antonio	Bexar	0915-00-268	04



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0915-00-268

DISTRICT San Antonio

COUNTY Bexar

HIGHWAY Various


CONTROL SECTION JOB				0915-00-268		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00193285			
COUNTY				Bexar			
HIGHWAY				Various			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	6064-6080	ITS POLE MNT CAB (TY 2)(CONF 1)	EA	4.000		4.000	
	6064-6097	ITS POLE MNT CAB (SPL)(INTEGRATED)(INS)	EA	11.000		11.000	
	6123-6001	ETHERNET SWITCH (INSTALL ONLY)	EA	8.000		8.000	
	6185-6002	TMA (STATIONARY)	DAY	24.000		24.000	
	6511-6001	CELLULAR MODEM (INSTALL ONLY)	EA	8.000		8.000	
	6513-6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	8.000		8.000	
	16	MATERIAL FURNISHED BY THE STATE (PARTICIPATING)	LS	1.000		1.000	
	18	ELECTRICAL: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	

SUMMARY OF QUANTITIES	416 6004 DRILL SHAFT (36 IN)	416 6006 DRILL SHAFT (48 IN)	416 6018 DRILL SHAFT (SIGN MTS) (24 IN)	432 6001 RIPRAP (CONC) (4 IN)	432 6045 RIPRAP (MOW STRIP) (4 IN)	500 6001 MOBILIZATION	502 6001 BARRICADES, SIGNS, AND TRAFFIC HANDLING	540 6001 MTL W-BEAM GD FEN (TIM POST)	540 6016 DOWNSTREAM ANCHOR TERMINAL SECTION	544 6001 GUARDRAIL END TREATMENT (INSTALL)	618 6023 CONDT (PVC) (SCH 40) (2")	618 6029 CONDT (PVC) (SCH 40) (3")	618 6047 CONDT (PVC) (SCH 80) (2") (BORE)
SHEET NAME	LF	LF	LF	CY	CY	LS	MO	LF	EA	EA	LF	LF	LF
KERR CO DPAS EB SHT 1 OF 1			26		10.70			187.50	1	1	355		
KERR CO EB SHT 1 OF 1	15	21		2.50							905		75
KERR CO DPAS WB SHT 1 OF 2											140		100
KERR CO DPAS WB SHT 2 OF 2			29		10.80			187.50	1	1	305		
KERR CO WB SHT 1 OF 3	15			1.25							170		55
KERR CO WB SHT 2 OF 3											280		225
KERR CO WB SHT 3 OF 3	15	21		2.50							610		
GUADALUPE CO DPAS EB SHT 1 OF 1			29		10.10			175.00	1	1	370		
GUADALUPE CO EB SHT 1 OF 2	15			1.25							225		95
GUADALUPE CO EB SHT 2 OF 2	15	21		2.50							640		
GUADALUPE CO DPAS WB SHT 1 OF 1			29		12.19			225.00	1	1	180		
GUADALUPE CO WB SHT 1 OF 4	15			1.25							10	375	
GUADALUPE CO WB SHT 2 OF 4												60	
GUADALUPE CO WB SHT 3 OF 4												10	
GUADALUPE CO WB SHT 4 OF 4	15	21		2.50							20	50	
TOTAL	105	84	113	13.75	43.79	1	12	775.00	4	4	4210	495	550

SUMMARY OF QUANTITIES	618 6054 CONDT (PVC) (SCH 80) (3") (BORE)	618 6070 CONDT (RM) (2")	620 6003 ELEC CONDR (NO. 12) BARE	620 6004 ELEC CONDR (NO. 12) INSULATED	620 6007 ELEC CONDR (NO. 8) BARE	620 6008 ELEC CONDR (NO. 8) INSULATED	620 6009 ELEC CONDR (NO. 6) BARE	620 6010 ELEC CONDR (NO. 6) INSULATED	620 6011 ELEC CONDR (NO. 4) BARE	620 6012 ELEC CONDR (NO. 4) INSULATED	620 6015 ELEC CONDR (NO. 2) BARE	620 6016 ELEC CONDR (NO. 2) INSULATED	620 6019 ELEC CONDR (NO. 1/0) BARE
SHEET NAME	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF
KERR CO DPAS EB SHT 1 OF 1		40	65	130	345	1035							
KERR CO EB SHT 1 OF 1						2340	820	1490		1980	330	660	
KERR CO DPAS WB SHT 1 OF 2							290	870					
KERR CO DPAS WB SHT 2 OF 2		40	60	120			285	855					
KERR CO WB SHT 1 OF 3											255	510	
KERR CO WB SHT 2 OF 3										2220	535	1070	
KERR CO WB SHT 3 OF 3										1520	700	250	
GUADALUPE CO DPAS EB SHT 1 OF 1		40	70	140			340	1020					
GUADALUPE CO EB SHT 1 OF 2						640		1440	380	720			
GUADALUPE CO EB SHT 2 OF 2								1600	710	1340			
GUADALUPE CO DPAS WB SHT 1 OF 1		40	65	130	160	480							
GUADALUPE CO WB SHT 1 OF 4	425									1140		3360	860
GUADALUPE CO WB SHT 2 OF 4	100									360		720	180
GUADALUPE CO WB SHT 3 OF 4	195									450		900	225
GUADALUPE CO WB SHT 4 OF 4	730											1480	900
TOTAL	1450	160	260	520	505	4495	1735	7275	1090	9730	1820	8950	2165

SUMMARY OF QUANTITIES	620 6020 ELEC CONDR (NO. 1/0) INSULATED	624 6002 GROUND BOX TY A (122311) W/APR ON	628 6152 ELC SRV TY D 120/240 060 (NS) SS (N) S P (O)	636 6002 ALUMINUM SIGNS (TY G)	647 6001 INSTALL LRSS (STRUCT STEEL)	658 6015 INSTL DEL ASSM (D-SW) SZ (BRF) GF1	6010 6002 CCTV FIELD EQUIPMENT (DIGITAL)	6010 6011 CCTV FIELD EQUIP (DIGITAL) (INSTL ONLY)	6028 6002 INSTALL DMS (FOUNDATION MTD CABINET)	6064 6010 ITS POLE (30 FT) (90 MPH)
SHEET NAME	LF	EA	EA	SF	LB	EA	EA	EA	EA	EA
KERR CO DPAS EB SHT 1 OF 1		3	1	147	884.25	7			1	
KERR CO EB SHT 1 OF 1		6	1				1			1
KERR CO DPAS WB SHT 1 OF 2		4	1							
KERR CO DPAS WB SHT 2 OF 2		1		182	1020.18	7			1	
KERR CO WB SHT 1 OF 3		2								1
KERR CO WB SHT 2 OF 3		1								
KERR CO WB SHT 3 OF 3		4					1		1	
GUADALUPE CO DPAS EB SHT 1 OF 1		2	1	196	1086.84	7			1	
GUADALUPE CO EB SHT 1 OF 2		4	1							1
GUADALUPE CO EB SHT 2 OF 2		3					1		1	
GUADALUPE CO DPAS WB SHT 1 OF 1		2	1	182	1050.54	10			1	
GUADALUPE CO WB SHT 1 OF 4	1680	3								1
GUADALUPE CO WB SHT 2 OF 4	360	1								
GUADALUPE CO WB SHT 3 OF 4	450	1	1							
GUADALUPE CO WB SHT 4 OF 4	1720	6					1		1	1
TOTAL	4210	43	7	707	4041.81	31	4	4	4	7

**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420

  
Texas Department of Transportation

**SUMMARY OF QUANTITIES**


SHEET 1 OF 2

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	5

SUMMARY OF QUANTITIES	6064 6055 ITS POLE (60 FT) (90 MPH)	6064 6080 ITS POLE MNT CAB (TY 2) (CONF 1)	6064 6097 ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	6123 6001 ETHERNET SWITCH (INSTALL ONLY)	6185 6002 TMA (STATIONARY)	6511 6001 CELLULAR MODEM (INSTALL ONLY)	6513 6001 TPAS VEH DET SYS (INSTALL ONLY)
SHEET NAME	EA	EA	EA	EA	DAY	EA	EA
KERR CO DPAS EB SHT 1 OF 1				1		1	
KERR CO EB SHT 1 OF 1	1	1	2	1		1	2
KERR CO DPAS WB SHT 1 OF 2							
KERR CO DPAS WB SHT 2 OF 2				1		1	
KERR CO WB SHT 1 OF 3			1				1
KERR CO WB SHT 2 OF 3							
KERR CO WB SHT 3 OF 3	1	1	2	1		1	1
GUADALUPE CO DPAS EB SHT 1 OF 1				1		1	
GUADALUPE CO EB SHT 1 OF 2			1				1
GUADALUPE CO EB SHT 2 OF 2	1	1	2	1		1	1
GUADALUPE CO DPAS WB SHT 1 OF 1				1		1	
GUADALUPE CO WB SHT 1 OF 4			1				1
GUADALUPE CO WB SHT 2 OF 4							
GUADALUPE CO WB SHT 3 OF 4							
GUADALUPE CO WB SHT 4 OF 4	1	1	2	1		1	1
TOTAL	4	4	11	8	24	8	8

SUMMARY OF QUANTITIES	* CELLULAR ROUTER	* FIELD ETHERNET SWITCH	* TPAS VEHICLE DETECTION SYSTEM	* AXIS PTZ CAMERA	* POLE MOUNTED INTEGRATED ENCLOSURE CABINET	* SINGLE LINE DMS 3-CHARACTER (AMBER)	* CONTROLLER AND GROUND MOUNT CABINET
SHEET NAME	EA	EA	EA	EA	EA	EA	EA
KERR CO DPAS EB SHT 1 OF 1	1	1				2	1
KERR CO EB SHT 1 OF 1	1	1	2	1	2		
KERR CO DPAS WB SHT 1 OF 2							
KERR CO DPAS WB SHT 2 OF 2	1	1				3	1
KERR CO WB SHT 1 OF 3			1		1		
KERR CO WB SHT 2 OF 3							
KERR CO WB SHT 3 OF 3	1	1	1	1	2		
GUADALUPE CO DPAS EB SHT 1 OF 1	1	1				2	1
GUADALUPE CO EB SHT 1 OF 2			1		1		
GUADALUPE CO EB SHT 2 OF 2	1	1	1	1	2		
GUADALUPE CO DPAS WB SHT 1 OF 1	1	1				3	1
GUADALUPE CO WB SHT 1 OF 4			1		1		
GUADALUPE CO WB SHT 2 OF 4							
GUADALUPE CO WB SHT 3 OF 4							
GUADALUPE CO WB SHT 4 OF 4	1	1	1	1	2		
TOTAL	8	8	8	4	11	10	4


NOTES:  
 \* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

<b>HNTB</b> <small>HNTB Corporation The HNTB Companies Infrastructure Solutions Firm Registration Number 420</small>			
 © 2024			
<b>SUMMARY OF QUANTITIES</b>			
SHEET 2 OF 2			
STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	6

3/12/2024  
 PW:\pw-int.hntb.org\pwc\central\Documents\San Antonio Projects\73627 SAT Traffic-ITS\WA03\Design and Engineering\SAT\13\*Sign-Sheet DGN\73627\*WA03\*SAT\*SK\*SOI.001.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

# SUMMARY OF LARGE SIGNS

PLAN SHEET NO.	SIGN NO.	SIGN BACK-GROUND COLOR	SIGN TEXT	SIGN DIMENSIONS	PLAQUES, & OTHER ATTACHMENTS		BACKGROUND SUBSTRATE (SQ FT)				TYPE OF MOUNT	"X" DIMENSION			GALVANIZED STRUCTURAL STEEL				DRILLED SHAFT					
					DIRECT APPLY	ALUMINUM (TYPE A)	GROUND MOUNT (TYPE G)		OVERHEAD (TYPE O)			post ①	post ②	post ③	SIZE	LINEAR FEET			TOTAL WEIGHT LBS.	LINEAR FEET REINFORCED				
							REPLACE	INSTALL	REPLACE	INSTALL						post ①	post ②	post ③		12"φ	24"φ	30"φ	36"φ	
38	DPAS #1	BLUE		2'0" X 2'0" 14'0" X 10'6"	4.00						221	0.93	1.92		W8X21	18.43	19.42		884.25		26.00			
43	DPAS #2	BLUE		2'0" X 2'0" 14'0" X 13'0"	4.00						221	1.06	1.13		W10X22	21.06	21.13		1020.18		29.00			
48	DPAS #3	BLUE		2'0" X 2'0" 14'0" X 14'0"	4.00						221	1.05	2.17		W10X22	22.05	23.17		1086.84		29.00			
53	DPAS #4	BLUE		2'0" X 2'0" 14'0" X 13'0"	4.00						221	1.16	2.41		W10X22	21.16	22.41		1050.54		29.00			
<b>PAGE TOTALS</b>																				<b>4041.81</b>		<b>113.00</b>		



The "X" dimension is the elevation difference at the post between the ground and the edge of pavement or top of curb.  
 Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.  
 The post lengths listed here are approximations. The corrected post lengths will be furnished by the Contractor after the stud posts are placed.  
 Tower heights shall be verified with the Engineer before fabrication.

\* This column is for aluminum Type A and not direct apply. Direct apply is subsidiary to the sign.

**SIGN TYPE**  
 Wind Design Zone  
 Series No.  
 0 Aluminum/Fiberglass  
 1 Aluminum  
 2 Fiberglass  
 SIGN TYPE 1 3 0  
 SCALE : NTS  
 No. of Posts  
 See sheet SMD(8W1)

**I-10**  
 SHEET 1 OF 1

## SUMMARY OF LARGE SIGNS SOLS

© TxDOT Mgy. 1987

DN. - TxDOT	REVISIONS
0915	11-93 1-04
0915	8-95 9-08
0915	5-01

CONT	SECT	JOB	HIGHWAY
0915	00	268	VARIOUS
DIST	COUNTY		SHEET NO.
SAT	BEXAR, ETC.		7



LOC NO.	DPAS LOCATION					6185
		FURNISH	RELOCATE/REUSE	TOTAL TMA/TA	DURATION OF	6002
		TMA/TA	TMA/TA	PER SET UP	TMA/TA SET UP	TMA (STATIONARY)
		EA	EA	EA	DAYS PER TMA/TA USE	DAY
DPAS #1	KERR COUNTY EB	1		1	6	6
DPAS #2	KERR COUNTY WB	1		1	6	6
DPAS #3	GUADALUPE COUNTY EB	1		1	6	6
DPAS #4	GUADALUPE COUNTY WB	1		1	6	6
TOTALS		4				24

<b>HNTB</b> <small>HNTB Corporation The HNTB Companies Infrastructure Solutions Firm Registration Number 420</small>			
 <b>Texas Department of Transportation</b> <small>© 2024</small>			
<b>TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA) SUMMARY SHEET</b>			
<small>SHEET 1 OF 1</small>			
<small>STATE</small>	<small>DISTRICT</small>	<small>COUNTY</small>	<small>HWY NUMBER</small>
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
<small>CONTROL</small>	<small>SECTION</small>	<small>JOB</small>	<small>SHEET NUMBER</small>
0915	00	268	8



**LEGEND**

- EXISTING SAFETY REST AREA
- △ PROPOSED SIGN
- CITY LOCATION



SCALE : NTS

**HNTB**  
HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420



**I-10 TPAS  
 LOCATION MAP**

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	9

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:11 AM  
 FILE: bc-21.dgn

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<p><b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b>  <a href="http://www.txdot.gov">http://www.txdot.gov</a></p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS) "
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

		<b>Traffic Safety Division Standard</b>
<p><b>BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS</b></p> <p><b>BC (1) - 21</b></p>		
FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT SECT	JOB HIGHWAY
4-03 7-13	0915 00	268 VARIOUS
9-07 8-14	DIST	COUNTY SHEET NO.
5-10 5-21	SAT	BEXAR, ETC. 10

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL LOCATION OF CROSSROAD SIGNS**



† May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)

- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
- The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			80	1000 <sup>2</sup>
*			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

† Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
- Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-21**


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	091500		268	VARIOUS
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	SAT	BEXAR, ETC.		11

DATE: 2/27/2024 11:09:11 AM  
 FILE: bc-21.dgn

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:09:12 AM  
FILE: bc-21.dgn

SHEET 3 OF 12

		<b>Traffic Safety Division Standard</b>	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT SECT:	0915 00
REVISIONS:		JOB:	268
9-07 8-14		HIGHWAY:	VARIOUS
7-13 5-21		DIST:	COUNTY
		SAT:	BEXAR, ETC.
		SHEET NO.:	12

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short, duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

SHEET 4 OF 12





**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

BC (4) - 21


FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915 00		268	VARIOUS
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	SAT	BEXAR, ETC.		13

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





### SKID MOUNTED WOOD SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



### GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



### SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

### WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

### OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- ### GENERAL NOTES
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."
  - \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



## BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
©TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0915	00	268	VARIOUS				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	SAT	BEXAR, ETC.	14					

DATE: 2/27/2024 11:09:13 AM  
FILE: bc-21.dgn



WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

### Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE	

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	Hwy	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number




## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0915	00	268	VARIOUS				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	SAT	BEXAR, ETC.	15					


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE: 2/27/2024 11:09:14 AM  
FILE: bc-21.dgn

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	SAT	BEXAR, ETC.	16	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:14 AM  
 FILE: bc-21.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0915	00	268	VARIOUS				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	SAT	BEXAR, ETC.	17					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * X			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\*X Taper lengths have been rounded off.  
L=Length of Taper (FT.) W=Width of Offset (FT.)  
S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	SAT	BEXAR, ETC.	18	


DATE: 2/27/2024 11:09:15 AM  
FILE: bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**


Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




PLAN VIEW

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

These drums are not required on one-way roadway. Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	SAT	BEXAR, ETC.	19	

DATE: 2/27/2024 11:09:15 AM  
FILE: bc-21.dgn

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS		0915	00	268
2-98	9-07	5-21		
1-02	7-13			
11-02	8-14			
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	<b>20</b>	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:09:16 AM  
FILE: bc-21.dgn



## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



(FOR LEFT TURN CHANNELIZING LINE OR CHANNELIZING LINE USED TO DISCOURAGE LANE CHANGING.)




### BROKEN LINES



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	SAT	BEXAR, ETC.	21	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:09:16 AM  
FILE: bc-21.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:09:18 AM  
FILE: tcp1-5-18.dgn



TCP (1-5a)  
**ONE LANE CLOSURE**



TCP (1-5b)  
**LANE CLOSURE NEAR EXIT RAMP**



TCP (1-5c)  
**LANE CLOSURE NEAR ENTRANCE RAMP**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

**Texas Department of Transportation**

**Traffic Operations Division Standard**


## TRAFFIC CONTROL PLAN LANE CLOSURES FOR DIVIDED HIGHWAYS

### TCP (1-5) - 18


FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0915 00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	22	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:21 AM  
FILE: tcp5-1-18.dgn



TCP (5-1a)  
WORK AREA ON SHOULDER



TCP (5-1b)  
WORK AREA ON SHOULDER

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	90'
35		205'	225'	245'	35'	70'	120'
40		265'	295'	320'	40'	80'	155'
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\* Conventional Roads Only  
\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)	

- GENERAL NOTES**
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
  - 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.




TRAFFIC CONTROL PLAN  
SHOULDER WORK FOR  
FREEWAYS / EXPRESSWAYS

TCP (5-1) - 18


FILE: tcp5-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	REVISIONS	0915 00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	23	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:22 AM  
FILE: tcp6-1.dgn



TCP (6-1a)  
**TYPICAL FREEWAY  
ONE LANE CLOSURE**



TCP (6-1b)  
**TYPICAL FREEWAY  
TWO LANE CLOSURE**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80	800'	880'	960'	80'	160'	615'	

\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD.
- Warning signs for intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

\* A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.




**TRAFFIC CONTROL PLAN  
FREEWAY LANE CLOSURES**

**TCP (6-1) - 12**


FILE:	tcp6-1.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	February 1998	CONT	SECT	JOB	HIGHWAY				
8-12	REVISIONS	0915	00	268	VARIOUS				
		DIST	COUNTY	SHEET NO.					
		SAT	BEXAR, ETC.	24					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:25 AM  
 FILE: tcp6-2.dgn



TCP (6-2a)  
**ENTRANCE RAMP OPEN**  
**WORK WITHIN 500' OF RAMP**



TCP (6-2b)  
**ENTRANCE RAMP CLOSED**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainlane can be seen from both roadways.
- See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN**  
**WORK AREA NEAR RAMP**

**TCP (6-2) - 12**


FILE:	tcp6-2.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	February 1994	CONT	SECT	JOB	268	HIGHWAY	VARIOUS		
REVISIONS	0915 00	DIST	COUNTY	SHEET NO.	25				
1-97	8-98	SAT	BEXAR, ETC.						
4-98	8-12								

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:26 AM  
FILE: tcp6-3.dgn



TCP (6-3a)  
ENTRANCE RAMP OPEN



TCP (6-3b)  
EXIT RAMP CLOSED  
TRAFFIC EXITS PRIOR TO CLOSED RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" **			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES:  
1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

STREET B EXIT CLOSED	USE STREET A EXIT
EXIT XY CLOSED	USE EXIT XX

Or, as an option when exits are numbered

Place 1 mile (approx.) in advance of Street A exit.

Texas Department of Transportation  
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN  
WORK AREA BEYOND RAMP


TCP (6-3) - 12

FILE: tcp6-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	091500	268	VARIOUS	
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	SAT	BEXAR, ETC.	26	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:29 AM  
FILE: tcp6-4.dgn



TCP (6-4a)  
**EXIT RAMP CLOSED**  
**TRAFFIC EXITS PAST CLOSED RAMP**



TCP (6-4b)  
**EXIT RAMP OPEN**

LEGEND			
	Type 3 Barricade		Channelizing Devices (CDs)
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC Standards for sign details.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN**  
**WORK AREA AT EXIT RAMP**

**TCP (6-4) - 12**


FILE: tcp6-4.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1994	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915 00	268	VARIOUS	
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	SAT	BEXAR, ETC.	27	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:09:31 AM  
 FILE: tcp6-5.dgn



TCP (6-5a)  
 EXIT RAMP OPEN



TCP (6-5b)  
 EXIT RAMP OPEN  
 TWO LANE CLOSURE WITHIN  
 1500' PAST EXIT RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"			Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
45	L = WS	450'	495'	540'	45'	90'	195'
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60		600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

\*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- See BC standards for sign details.
- If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

\*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




**TRAFFIC CONTROL PLAN  
 WORK AREA BEYOND EXIT RAMP**

**TCP (6-5) - 12**

FILE: tcp6-5.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
1-97 8-98	DIST	COUNTY	SHEET NO.	
4-98 8-12	SAT	BEXAR, ETC.	28	






PROPOSED TCP AT DRIVEWAY OR PARKING AREA  
WORK SPACE ON LEFT SIDE  
N. T. S

WORK VEHICLES OR OTHER EQUIPMENT NECESSARY FOR THE WORK OPERATION, SUCH AS TRUCKS, MOVABLE CRANES, ETC., SHALL REMAIN IN AREAS SEPARATED FROM TRAFFIC BY CHANNELIZING DEVICES AT ALL TIMES.

MAINTAIN 12' MIN





PROPOSED TCP AT DRIVEWAY OR PARKING AREA  
WORK SPACE ON RIGHT SIDE  
N. T. S

LEGEND	
	Heavy Work Vehicle
	Channelizing Devices
	Sign
	Traffic Flow
	Flag

NOTES:

1. THESE TYPICAL DETAILS ARE INTENDED FOR WORK AT VARIOUS LOCATIONS WITHIN THE SAFETY REST AREAS (SRA) OR TRAVEL INFORMATION CENTERS (TIC) WHERE WORK VEHICLES AND/OR EQUIPMENT MAY NEED TO BE TEMPORARILY LOCATED IN THE DRIVEWAY AND PARKING LOT AREAS.
2. FURNISH, PLACE AND MAINTAIN ALL TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE TMUTCD AND THE BC STANDARDS.
3. SEE THE GENERAL NOTES FOR ADDITIONAL WORK ZONE REQUIREMENTS.
4. THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE REQUIREMENTS OF ITEM 7, "LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC", ITEM 502, "BARRICADES, SIGNS, AND TRAFFIC HANDLING" AND TO THE GENERAL NOTES.
5. THE ASSUMED POSTED SPEED IS 15 MPH. FOR OTHER POSTED SPEEDS, ADJUST SPACING AND LENGTHS FOR THE TRAFFIC CONTROL DEVICES SHOWN ON THIS SHEET IN ACCORDANCE WITH THE TMUTCD AND THE BC STANDARDS.
6. SEE BC STANDARDS FOR ADDITIONAL REQUIRED SIGNS.



PROPOSED TCP SIGNING AT SRA/TIC

**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420

**Texas Department of Transportation**


TYPICAL TCP WITHIN SRA / TIC FOR TPAS

SHEET 1 OF 1				
DSGN	STATE	DISTRICT	COUNTY	HWY NUMBER
DSGN-CHK	TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
DRWN	CONTROL	SECTION	JOB	SHEET NUMBER
DRWN-CHK	0915	00	268	29


DATE: i lename: ###.pdf

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: 2/27/2024  
FILE: gf3119.dgn



**TYPICAL POST PLACEMENT**




**WOOD BLOCK TO ROUND WOOD POST**



**WOOD BLOCK TO RECTANGULAR WOOD POST**


**ROUTED WOOD BLOCK TO I-BEAM STEEL POST**



**GENERAL NOTES**


1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16G) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

NOTE: \*\* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



**ELEVATION MID-SPAN RAIL SPLICE**


SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



**ELEVATION 25'-0" (NOM.) W-BEAM SECTION**

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

\* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



**LOW FILL CULVERT POST**

NOTE: TWO INSTALLATION OPTIONS.

1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.


SPLICE BOLT LENGTH VARIES

FBB01 = 1 1/4"  
FBB02 = 2"

POST & BLOCK LENGTH  
FBB03 = 10"  
FBB04 = 18"

**BUTTON HEAD BOLT**

NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.




**MID-SPAN RAIL SPLICE DETAIL**

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

				<b>Design Division Standard</b>
<b>METAL BEAM GUARD FENCE</b> <b>TL-3 MASH COMPLIANT</b> <b>GF(31)-19</b>				
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	30	

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.










**DOWNSTREAM ANCHOR TERMINAL (DAT)**  
NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.

- GENERAL NOTES**
1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
  2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE SHELF ANGLE BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
  3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4" ABOVE THE FINISHED GRADE.
  4. ALL HARDWARE FOR DAT SHALL BE ASTM A307 UNLESS OTHERWISE SHOWN.
  5. REFER TO GF(31) SHEET FOR TERMINAL CONNECTION DETAILS.

**MOW STRIP INSTALLATION**  
IF A MOW STRIP IS REQUIRED WITH THE DAT INSTALLATION THE LEAVE-OUT AREA AROUND THE STEEL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.

#	(DAT) PARTS LIST	QTY
1	STEEL FOUNDATION TUBE	2
2	DAT TERMINAL POST	2
3	CHANNEL STRUT	2
4	TERMINAL RAIL ELEMENT	1
5	SHELF ANGLE BRACKET	1
6	BCT BEARING PLATE	1
7	BCT POST SLEEVE	1
8	GUARDRAIL ANCHOR BRACKET	1
9	(ROUNDED) W-BEAM END SECTION	1
10	BCT CABLE ANCHOR	1
11	RECESSED NUT, GUARDRAIL	20
12	1 1/4" BUTTON HEAD BOLT	4
13	10" BUTTON HEAD BOLT	2
14	5/8" X 2" HEX HEAD BOLT	8
15	5/8" X 8" HEX HEAD BOLT	4
16	5/8" X 10" HEX HEAD BOLT	2
17	5/8" FLAT WASHER	18




*Design Division Standard*

**METAL BEAM GUARD FENCE  
(DOWNSTREAM ANCHOR TERMINAL)  
TL-3 MASH COMPLIANT  
GF(31)DAT-19**

FILE: gf31dot19.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG
©TXDOT: NOVEMBER 2019 REVISIONS	CONT	SECT	JOB	HIGHWAY
	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	31	


DATE: 2/27/2024  
FILE: gf31dot19.dgn

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




**GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS**

Note: Site Condition(s)  
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.  
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




**PLAN**

GF(31) shown with Mow Strip  
 (See GF(31) standard sheet for proper installation)



**SECTION A-A**


Typical



**MOW STRIP DETAIL**


Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
  2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
  3. The leave-out behind the post shall be a minimum of 7".
  4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
  5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
  6. Thickness of the mow strip will be 4".
  7. The limits of payment for reinforced concrete will include leave-outs for the posts.
  8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




**CURB OPTION (1)**

This option will increase the post embedment throughout the system.



**CURB OPTION (2)**

Curb shown on top of mow strip



**CURB OPTION (3)**




**METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF (31) MS-19**

FILE: gf31ms19.dgn	DN:TxDOT	CK: KM	DW: VP	CK: CGL/AG
©TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	32	

DATE: 2/27/2024  
 FILE: gf31ms19 (1).dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.







- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; SoftStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MGBF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - IT IS ACCEPTABLE TO INSTALL THE SoftStop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
  - DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoaching ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

**NOTE: A** THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

**NOTE: B** PART PN:5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

**NOTE: C** W-BEAM SPLICE LOCATED BETWEEN LINE POST(4) AND LINE POST(5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25' - 0")
15205A	1	POST #0 - ANCHOR POST (6' - 5 3/8")
15203G	1	POST #1 - (SYTP) (4' - 9 1/2")
15000G	1	POST #2 - (SYTP) (6' - 0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 X 8.5) (6' - 0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	7	BLOCKOUT - COMPOSITE (4" X 7 1/2" X 14")
15204A	1	ANCHOR PADDDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT
<b>HARDWARE</b>		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" X 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" X 10" HGR POST BOLT A307
3391G	1	5/8" X 1 3/4" HEX HD BOLT A325
4489G	1	5/8" X 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" X 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" X 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE:B



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

**Texas Department of Transportation**  
**Design Division Standard**


**TRINITY HIGHWAY**  
**SOFTSTOP END TERMINAL**  
**MASH - TL-3**  
**SGT(10S)31-16**

FILE: sgt10s3116	DW: TxDOT	CR: KM	DW: VP	CR: MB/VP
©TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
DIST	COUNTY	SHEET NO.		
SAT	BEXAR, ETC.			<b>33</b>

DATE: 2/27/2024  
FILE: sgt10s3116.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.







DATE: 2/27/2024  
FILE: sgt11s3118 (1).dgn



- NOTES:
- ITEM 10 COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (9) THRU LINE POST (2).
  - DO NOT INSTALL A BLOCKOUT AT LINE POST (1).

NOTE: RECESSED HEX NUTS FACING TRAFFIC-SIDE SEE DETAIL (C)

NOTE: SECURE THE (TSS) PANEL TO OUTSIDE OF RAIL 2 WITH THE PANEL ARROWS POINTING TOWARDS THE HEAD.




- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
  - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL. P/N MANMAX REV D (ECN 3516).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
  - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
  - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
  - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
  - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
  - THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
  - A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT. -GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST - GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	5/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	5/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev- (D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

\* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.

\*\* ALTERNATIVE ITEMS NOT SHOWN.  
ITEM (26) 8" WOOD-BLOCKOUTS  
ITEM (27) 25' GUARD FENCE PANELS



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

APPROACH GRADING AT GUARDRAIL END TREATMENTS

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

**Texas Department of Transportation**  
Design Division Standard

## MAX-TENSION END TERMINAL MASH - TL-3


### SGT (11S) 31-18

FILE: sgt11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915 00	268	VARIOUS	
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	34	



DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



DATE: 2/27/2024  
 FILE: sgt12s3118 (2).dgn




- NOTES:
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
  - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
  - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
  - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
  - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
  - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
  - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
  - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
  - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
  - POSTS SHALL NOT BE SET IN CONCRETE.
  - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
  - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
  - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
  - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
  - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R. NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. \* \*  
 \* ITEM (P) 8" WOOD-BLOCKOUT  
 \* \* ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard



## SINGLE GUARDRAIL TERMINAL

### MSKT-MASH-TL-3

### SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CL
© TxDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	35	





*SAI Geetha*  
2/27/2024



**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420




**KERR COUNTY  
LAYOUT  
SHEET ID**

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEJAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	36





**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- ⊞ PROP VEHICLE DETECTOR
- ⊞ PROP CCTV
- ⊙ PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE- EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE

**SUMMARY OF QUANTITIES**

BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
416 6006	DRILL SHAFT (48 IN)	LF	21
432 6001	RIPRAP (CONC) (4 IN)	CY	2.50
618 6023	CONDT (PVC) (SCH 40) (2")	LF	905
618 6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	75
620 6008	ELEC CONDR (NO. 8) INSULATED	LF	2340
620 6009	ELEC CONDR (NO. 6) BARE	LF	820
620 6010	ELEC CONDR (NO. 6) INSULATED	LF	1490
620 6012	ELEC CONDR (NO. 4) INSULATED	LF	1980
620 6015	ELEC CONDR (NO. 2) BARE	LF	330
620 6016	ELEC CONDR (NO. 2) INSULATED	LF	660
624 6002	GROUND BOX TY A (122311) W/APRON	EA	6
628 6152	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	EA	1
6010 6002	CCTV FIELD EQUIPMENT (DIGITAL)	EA	1
6010 6011	CCTV FIELD EQUIP (DIGITAL) (INSTL ONLY)	EA	1
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6055	ITS POLE (60 FT) (90 MPH)	EA	1
6064 6080	ITS POLE MNT CAB (TY 2) (CONF 1)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	2
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	2
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	2
*	AXIS PTZ CAMERA	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	2

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.



**KERR CO EB SHT 1 OF 1  
CONDUIT & CABLE CHART**

RUN NUMBER	618 6023 CONDT (PVC) (SCH 40) (2")	618 6047 CONDT (PVC) (SCH 80) (2") (BORE)	620 6008 ELEC CONDR (NO. 8) INSULATED	620 6009 ELEC CONDR (NO. 6) BARE	620 6010 ELEC CONDR (NO. 6) INSULATED	620 6012 ELEC CONDR (NO. 4) INSULATED	620 6015 ELEC CONDR (NO. 2) BARE	620 6016 ELEC CONDR (NO. 2) INSULATED	RUN LENGTH FEET
1	2		6	1	2	6	1	2	10
2	2		6	1	2	6	1	2	60
3	2		6	1	2	6	1	2	180
4		1	6	1	2				75
5	1		6	3					15
6	1			1	2				190
7	1			1	2				150
8	1			1	2				10
9	1					6	1	2	40
WIRE SLACK			30	10	14	24	4	8	10
TOTAL	LF 905	LF 75	LF 2340	LF 820	LF 1490	LF 1980	LF 330	LF 660	

**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


**Texas Department of Transportation**  
© 2024

**KERR COUNTY  
SAFETY REST AREA  
I-10 EASTBOUND  
ITS LAYOUT**

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	37





**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- ▣ PROP GROUND BOX TY A W/ APRON
- PROP DYNAMIC PARKING AVAILABILITY SIGN
- ☒ PROP GROUND MOUNTED DMS CABINET
- OHE- EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE

**SUMMARY OF QUANTITIES**

BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6018	DRILL SHAFT (SIGN MTS) (24 IN)	LF	26
432 6045	RIPRAP (MOW STRIP) (4 IN)	CY	10.70
540 6001	MTL W-BEAM GD FEN (TIM POST)	LF	187.50
540 6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	1
544 6001	GUARDRAIL END TREATMENT (INSTALL)	EA	1
618 6023	CONDT (PVC) (SCH 40) (2")	LF	355
618 6070	CONDT (RM) (2")	LF	40
620 6003	ELEC CONDR (NO. 12) BARE	LF	65
620 6004	ELEC CONDR (NO. 12) INSULATED	LF	130
620 6007	ELEC CONDR (NO. 8) BARE	LF	345
620 6008	ELEC CONDR (NO. 8) INSULATED	LF	1035
624 6002	GROUND BOX TY A (122311)W/APRON	EA	3
628 6152	ELC SRV TY D 120/240 060(NS)SS(N)SP(O)	EA	1
636 6002	ALUMINUM SIGNS (TY G)	SF	147
647 6001	INSTALL LRSS (STRUCT STEEL)	LB	884.25
658 6015	INSTL DEL ASSM (D-SW)SZ (BRF)GF1	EA	7
6028 6002	INSTALL DMS (FOUNDATION MTD CABINET)	EA	1
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	SINGLE LINE DMS 3-CHARACTER (AMBER)	EA	2
*	CONTROLLER AND GROUND MOUNT CABINET	EA	1

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

**KERR CO DPAS EB SHT 1 OF 1 CONDUIT & CABLE CHART**

RUN NUMBER	618 6023	618 6070	620 6003	620 6004	620 6007	620 6008	RUN LENGTH
	CONDT (PVC) (SCH 40) (2")	CONDT (RM) (2")	ELEC CONDR (NO. 12) BARE	ELEC CONDR (NO. 12) INSULATED	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 8) INSULATED	
1	1				1	3	10
2	1				1	3	70
3	1				1	3	205
4	1				1	3	20
5	2		1	2			25
6		2	1	2			20
WIRE SLACK			2	4	4	12	10
TOTAL	LF	LF	LF	LF	LF	LF	
	355	40	65	130	345	1035	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO DMS CONNECTION POINTS SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB** HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


**Texas Department of Transportation**

**KERR COUNTY SAFETY REST AREA I-10 EASTBOUND SIGN LAYOUT**


SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	38





- LEGEND**
- EXIST CONDUIT
  - - - PROP CONDUIT (TRENCH)
  - SP PROP CONDUIT (BORE)
  - ◆ PROP ELECTRICAL SERVICE
  - PROP GROUND BOX TY A
  - ▣ PROP GROUND BOX TY A W/ APRON
  - Ⓜ PROP VEHICLE DETECTOR
  - Ⓜ PROP CCTV
  - PROP ITS POLE W/ POLE MOUNTED CABINET
  - OHE— EXIST OVER HEAD ELECTRIC LINE
  - ⊙ EXIST POWER POLE



SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
432 6001	RIPRAP (CONC) (4 IN)	CY	1.25
618 6023	CONDT (PVC) (SCH 40) (2")	LF	170
618 6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	55
620 6015	ELEC CONDR (NO.2) BARE	LF	255
620 6016	ELEC CONDR (NO.2) INSULATED	LF	510
624 6002	GROUND BOX TY A (122311)W/APRON	EA	2
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	1

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

KERR CO WB SHT 1 OF 3 CONDUIT & CABLE CHART					
RUN NUMBER	618 6023	618 6047	620 6015	620 6016	RUN LENGTH FEET
	CONDT (PVC) (SCH 40) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO.2) BARE	ELEC CONDR (NO.2) INSULATED	
1	1		1	2	160
2		1	1	2	55
3	1		1	2	10
WIRE SLACK			3	6	10
TOTAL	LF 170	LF 55	LF 255	LF 510	

**NOTES:**

- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POT HOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
- CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
- LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
- CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB** HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


**Texas Department of Transportation** © 2024

**KERR COUNTY  
SAFETY REST AREA  
I-10 WESTBOUND  
ITS LAYOUT**

SHEET 1 OF 3


STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	39





**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- SP PROP CONDUIT (BORE)
- ◆ PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- ▣ PROP GROUND BOX TY A W/ APRON
- Ⓜ PROP VEHICLE DETECTOR
- Ⓜ PROP CCTV
- PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE- EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
618 6023	CONDT (PVC) (SCH 40) (2")	LF	280
618 6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	225
620 6012	ELEC CONDR (NO.4) INSULATED	LF	2220
620 6015	ELEC CONDR (NO.2) BARE	LF	535
620 6016	ELEC CONDR (NO.2) INSULATED	LF	1070
624 6002	GROUND BOX TY A (122311)W/APRON	EA	1

RUN NUMBER	KERR CO WB SHT 2 OF 3 CONDUIT & CABLE CHART					RUN LENGTH FEET
	618 6023 CONDT (PVC) (SCH 40) (2")	618 6047 CONDT (PVC) (SCH 80) (2") (BORE)	620 6012 ELEC CONDR (NO.4) INSULATED	620 6015 ELEC CONDR (NO.2) BARE	620 6016 ELEC CONDR (NO.2) INSULATED	
1	1		6	1	2	125
2		1	6	1	2	225
3	1			1	2	155
WIRE SLACK			12	3	6	10
TOTAL	LF 280	LF 225	LF 2220	LF 535	LF 1070	

**NOTES:**

- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
- CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
- LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
- CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB** HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


**Texas Department of Transportation**

**KERR COUNTY  
SAFETY REST AREA  
I-10 WESTBOUND  
ITS LAYOUT**

SHEET 2 OF 3




STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	40





### LEGEND

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- Ⓜ PROP VEHICLE DETECTOR
- Ⓜ PROP CCTV
- ⊙ PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE— EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
416 6006	DRILL SHAFT (48 IN)	LF	21
432 6001	RIPRAP (CONC) (4 IN)	CY	2.50
618 6023	CONDT (PVC) (SCH 40) (2")	LF	610
620 6012	ELEC CONDR (NO. 4) INSULATED	LF	1520
620 6015	ELEC CONDR (NO. 2) BARE	LF	700
620 6016	ELEC CONDR (NO. 2) INSULATED	LF	250
624 6002	GROUND BOX TY A (122311)W/APRON	EA	4
6010 6002	CCTV FIELD EQUIPMENT (DIGITAL)	EA	1
6010 6011	CCTV FIELD EQUIP (DIGITAL) (INSTL ONLY)	EA	1
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6055	ITS POLE (60 FT) (90 MPH)	EA	1
6064 6080	ITS POLE MNT CAB (TY 2) (CONF 1)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	2
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	1
*	AXIS PTZ CAMERA	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	2

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

RUN NUMBER	KERR CO WB SHT 3 OF 3 CONDUIT & CABLE CHART				RUN LENGTH FEET
	618 6023 CONDT (PVC) (SCH 40) (2")	620 6012 ELEC CONDR (NO. 4) INSULATED	620 6015 ELEC CONDR (NO. 2) BARE	620 6016 ELEC CONDR (NO. 2) INSULATED	
1	1		1	2	95
2	1	2	1		315
3	1	2	1		55
4	1	2	1		10
5	1	6	1	2	10
6	1	4	1		115
7	1	4	2		10
WIRE SLACK		20	8	4	10
TOTAL	LF 610	LF 1520	LF 700	LF 250	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER. CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.


HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420

Texas Department of Transportation

## KERR COUNTY SAFETY REST AREA I-10 WESTBOUND ITS LAYOUT


SHEET 3 OF 3				
STATE	DISTRICT	COUNTY	HWY NUMBER	
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS	
CONTROL	SECTION	JOB	SHEET NUMBER	
0915	00	268	41	





**LEGEND**

- EXIST CONDUIT
- PROP CONDUIT (TRENCH)
- === PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- PROP DYNAMIC PARKING AVAILABILITY SIGN
- ☒ PROP GROUND MOUNTED DMS CABINET
- OHE- EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



STATE OF TEXAS  
 CHARLES D. KOONCE III  
 87785  
 LICENSED PROFESSIONAL ENGINEER  
*Charles D. Koonce III*  
 3/12/2024

0' 30' 60'  
 SCALE : 1" = 60'

KERR CO DPAS WB SHT 1 OF 2  
 CONDUIT & CABLE CHART

RUN NUMBER	618 6023	618 6047	620 6009	620 6010	RUN LENGTH FEET
	CONDT (PVC) (SCH 40) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	
1	1		1	3	10
2		1	1	3	60
3	1		1	3	115
4		1	1	3	40
5	1		1	3	15
WIRE SLACK			5	15	10
TOTAL	LF 140	LF 100	LF 290	LF 870	

SUMMARY OF QUANTITIES

BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
618 6023	CONDT (PVC) (SCH 40) (2")	LF	140
618 6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	100
620 6009	ELEC CONDR (NO. 6) BARE	LF	290
620 6010	ELEC CONDR (NO. 6) INSULATED	LF	870
624 6002	GROUND BOX TY A (122311)W/APRON	EA	4
628 6152	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	EA	1

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO DMS CONNECTION POINTS SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB**  
 HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

**Texas Department of Transportation**  
 © 2024


**KERR COUNTY  
 SAFETY REST AREA  
 I-10 WESTBOUND  
 SIGN LAYOUT**

SHEET 1 OF 2

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	42





MATCH LINE A




**LEGEND**

- EXIST CONDUIT
- PROP CONDUIT (TRENCH)
- ===== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- PROP DYNAMIC PARKING AVAILABILITY SIGN
- PROP GROUND MOUNTED DMS CABINET
- OHE- EXIST OVER HEAD ELECTRIC LINE
- EXIST POWER POLE



*Charles D. Koonce III*  
3/12/2024



SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6018	DRILL SHAFT (SIGN MTS) (24 IN)	LF	29
432 6045	RIPRAP (MOW STRIP) (4 IN)	CY	10.80
540 6001	MTL W-BEAM GD FEN (TIM POST)	LF	187.50
540 6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	1
544 6001	GUARDRAIL END TREATMENT (INSTALL)	EA	1
618 6023	CONDT (PVC) (SCH 40) (2")	LF	305
618 6070	CONDT (RM) (2")	LF	40
620 6003	ELEC CONDR (NO.12) BARE	LF	60
620 6004	ELEC CONDR (NO.12) INSULATED	LF	120
620 6009	ELEC CONDR (NO.6) BARE	LF	285
620 6010	ELEC CONDR (NO.6) INSULATED	LF	855
624 6002	GROUND BOX TY A (122311)W/APRON	EA	1
636 6002	ALUMINUM SIGNS (TY G)	SF	182
647 6001	INSTALL LRSS (STRUCT STEEL)	LB	1020.18
658 6015	INSTR DEL ASSM (D-SW)SZ (BRF)GF1	EA	7
6028 6002	INSTALL DMS (FOUNDATION MTD CABINET)	EA	1
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	SINGLE LINE DMS 3-CHARACTER (AMBER)	EA	3
*	CONTROLLER AND GROUND MOUNT CABINET	EA	1

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

RUN NUMBER	KERR CO DPAS WB SHT 2 OF 2 CONDUIT & CABLE CHART						RUN LENGTH FEET
	618 6023 CONDT (PVC) (SCH 40) (2")	618 6070 CONDT (RM) (2")	620 6003 ELEC CONDR (NO.12) BARE	620 6004 ELEC CONDR (NO.12) INSULATED	620 6009 ELEC CONDR (NO.6) BARE	620 6010 ELEC CONDR (NO.6) INSULATED	
1	1				1	3	215
2	1				1	3	50
3	2		1	2			20
4		2	1	2			20
WIRE SLACK			2	4	2	6	10
TOTAL	LF 305	LF 40	LF 60	LF 120	LF 285	LF 855	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO DMS CONNECTION POINTS SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


**Texas Department of Transportation**

**KERR COUNTY SAFETY REST AREA I-10 WESTBOUND SIGN LAYOUT**


SHEET 2 OF 2

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	43





DPAS #1 KERR CO. EB;  
 12.0" Radius, 2.0" Border, White on Blue;  
 D9-16; "SPACES OPEN", D; "REST AREAS", D;  
 "8 MILES", D; Rectangle Black; "113 MILES", D;  
 Rectangle Black;  
 Table of distances between letter and object lefts



DPAS #2 KERR CO WB;  
 12.0" Radius, 2.0" Border, White on Blue;  
 D9-16; "SPACES OPEN", D; "REST AREAS", D;  
 "11 MILES", D; Rectangle Black;  
 "131 MILES", D; Rectangle Black;  
 "292 MILES", D; Rectangle Black;



**HNTB** HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420


© 2024  
 Texas Department of Transportation

**KERR COUNTY  
 LARGE SIGN  
 DETAILS**

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	44






**GUADALUPE COUNTY  
SAFETY REST AREAS  
LAYOUT SHEET ID**

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEJAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	45





**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP
- ◆ PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- Ⓜ PROP VEHICLE DETECTOR
- Ⓜ PROP CCTV
- PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE— EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
432 6001	RIPRAP (CONC) (4 IN)	CY	1.25
618 6023	CONDT (PVC) (SCH 40) (2")	LF	225
618 6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	95
620 6008	ELEC CONDR (NO. 8) INSULATED	LF	640
620 6010	ELEC CONDR (NO. 6) INSULATED	LF	1440
620 6011	ELEC CONDR (NO. 4) BARE	LF	380
620 6012	ELEC CONDR (NO. 4) INSULATED	LF	720
624 6002	GROUND BOX TY A (122311)W/APRON	EA	4
628 6152	ELC SRV TY D 120/240 060(NS)SS(N)SP(O)	EA	1
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	1

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

RUN NUMBER	GUADALUPE CO EB SHT 1 OF 2 CONDUIT & CABLE CHART						RUN LENGTH FEET
	618 6023 CONDT (PVC) (SCH 40) (2")	618 6047 CONDT (PVC) (SCH 80) (2") (BORE)	620 6008 ELEC CONDR (NO. 8) INSULATED	620 6010 ELEC CONDR (NO. 6) INSULATED	620 6011 ELEC CONDR (NO. 4) BARE	620 6012 ELEC CONDR (NO. 4) INSULATED	
1	1		2	4	1	2	10
2		1	2	4	1	2	95
3	1		2	4	1	2	115
4	1		2	4	1	2	40
5	1		2		1		10
6	1			4	1	2	50
WIRE SLACK			10	20	6	10	10
TOTAL	225	95	640	1440	380	720	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB** HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


**Texas Department of Transportation** TEXAS 2024

**GUADALUPE COUNTY SAFETY REST AREA I-10 EASTBOUND ITS LAYOUT**



SHEET 1 OF 2

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	46





- LEGEND**
- EXIST CONDUIT
  - - - PROP CONDUIT (TRENCH)
  - ==== PROP CONDUIT (BORE)
  - SP
  - ◆ PROP ELECTRICAL SERVICE
  - PROP GROUND BOX TY A
  - ▣ PROP GROUND BOX TY A W/ APRON
  - Ⓜ PROP VEHICLE DETECTOR
  - Ⓜ PROP CCTV
  - PROP ITS POLE W/ POLE MOUNTED CABINET
  - OHE— EXIST OVER HEAD ELECTRIC LINE
  - ⊙ EXIST POWER POLE



*K. Sai Geetha*  
2/27/2024

0' 30' 60'  
SCALE : 1" = 60'

SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
416 6006	DRILL SHAFT (48 IN)	LF	21
432 6001	RIPRAP (CONC) (4 IN)	CY	2.50
618 6023	CONDT (PVC) (SCH 40) (2")	LF	640
620 6010	ELEC CONDR (NO.6) INSULATED	LF	1600
620 6011	ELEC CONDR (NO.4) BARE	LF	710
620 6012	ELEC CONDR (NO.4) INSULATED	LF	1340
624 6002	GROUND BOX TY A (122311)W/APRON	EA	3
6010 6002	CCTV FIELD EQUIPMENT (DIGITAL)	EA	1
6010 6011	CCTV FIELD EQUIP (DIGITAL) (INSTL ONLY)	EA	1
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6055	ITS POLE (60 FT) (90 MPH)	EA	1
6064 6080	ITS POLE MNT CAB (TY 2) (CONF 1)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	2
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	1
*	AXIS PTZ CAMERA	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	2

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

GUADALUPE CO EB SHT 2 OF 2 CONDUIT & CABLE CHART					
RUN NUMBER	618 6023	620 6010	620 6011	620 6012	RUN LENGTH FEET
	CONDT (PVC) (SCH 40) (2")	ELEC CONDR (NO.6) INSULATED	ELEC CONDR (NO.4) BARE	ELEC CONDR (NO.4) INSULATED	
1	1	4	1	2	165
2	1	4	1	2	195
3	1	4	2		10
4	1		1	2	260
5	1		1	2	10
WIRE SLACK		12	6	8	10
TOTAL	LF 640	LF 1600	LF 710	LF 1340	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420


© 2024  
Texas Department of Transportation

**GUADALUPE COUNTY  
SAFETY REST AREA  
I-10 EASTBOUND  
ITS LAYOUT**

SHEET 2 OF 2

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	47





**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- PROP DYNAMIC PARKING AVAILABILITY SIGN
- ☒ PROP GROUND MOUNTED DMS CABINET
- OHE- EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE

**SUMMARY OF QUANTITIES**


BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6018	DRILL SHAFT (SIGN MTS) (24 IN)	LF	29
432 6045	RIPRAP (MOW STRIP) (4 IN)	CY	10.10
540 6001	MTL W-BEAM GD FEN (TIM POST)	LF	175
540 6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	1
544 6001	GUARDRAIL END TREATMENT (INSTALL)	EA	1
618 6023	CONDT (PVC) (SCH 40) (2")	LF	370
618 6070	CONDT (RM) (2")	LF	40
620 6003	ELEC CONDR (NO.12) BARE	LF	70
620 6004	ELEC CONDR (NO.12) INSULATED	LF	140
620 6009	ELEC CONDR (NO.6) BARE	LF	340
620 6010	ELEC CONDR (NO.6) INSULATED	LF	1020
624 6002	GROUND BOX TY A (122311)W/APRON	EA	2
628 6152	ELC SRV TY D 120/240 060(NS)SS(N)SP(O)	EA	1
636 6002	ALUMINUM SIGNS (TY G)	SF	196
647 6001	INSTALL LRSS (STRUCT STEEL)	LB	1086.84
658 6015	INSTL DEL ASSM (D-SW)SZ (BRF)GF1	EA	7
6028 6002	INSTALL DMS (FOUNDATION MTD CABINET)	EA	1
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	SINGLE LINE DMS 3-CHARACTER (AMBER)	EA	2
*	CONTROLLER AND GROUND MOUNT CABINET	EA	1

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

**GUADALUPE CO DPAS EB SHT 1 OF 1  
CONDUIT & CABLE CHART**

RUN NUMBER	618 6023 CONDT (PVC) (SCH 40) (2")	618 6070 CONDT (RM) (2")	620 6003 ELEC CONDR (NO.12) BARE	620 6004 ELEC CONDR (NO.12) INSULATED	620 6009 ELEC CONDR (NO.6) BARE	620 6010 ELEC CONDR (NO.6) INSULATED	RUN LENGTH FEET
1	1				1	3	10
2	1				1	3	275
3	1				1	3	25
4	2		1	2			30
5		2	1	2			20
WIRE SLACK			2	4	3	9	10
TOTAL	LF 370	LF 40	LF 70	LF 140	LF 340	LF 1020	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO DMS CONNECTION POINTS SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.



**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420

**Texas Department of Transportation**

**GUADALUPE COUNTY  
SAFETY REST AREA  
I-10 EASTBOUND  
SIGN LAYOUT**

SHEET 1 OF 1


STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	48






PDF Filename: 0025 - GUADALUPE COUNTY SAFETY REST AREA I-10 WEST BOUND ITS LAYOUT SHEET 1 OF 4.pdf

SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
432 6001	RIPRAP (CONC) (4 IN)	CY	1.25
618 6023	CONDT (PVC) (SCH 40) (2")	LF	10
618 6029	CONDT (PVC) (SCH 40) (3")	LF	375
618 6054	CONDT (PVC) (SCH 80) (3") (BORE)	LF	425
620 6012	ELEC CONDR (NO. 4) INSULATED	LF	1140
620 6016	ELEC CONDR (NO. 2) INSULATED	LF	3360
620 6019	ELEC CONDR (NO. 1/0) BARE	LF	860
620 6020	ELEC CONDR (NO. 1/0) INSULATED	LF	1680
624 6002	GROUND BOX TY A (122311)W/APRON	EA	3
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	1

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.




LEGEND	
----	EXIST CONDUIT
----	PROP CONDUIT (TRENCH)
====	PROP CONDUIT (BORE)
SP	PROP ELECTRICAL SERVICE
■	PROP GROUND BOX TY A
■	PROP GROUND BOX TY A W/ APRON
⊗	PROP VEHICLE DETECTOR
⊗	PROP CCTV
⊙	PROP ITS POLE W/ POLE MOUNTED CABINET
—OHE—	EXIST OVER HEAD ELECTRIC LINE
⊙	EXIST POWER POLE




GUADALUPE CO WB SHT 1 OF 4 CONDUIT & CABLE CHART								
RUN NUMBER	618 6023 CONDT (PVC) (SCH 40) (2")	618 6029 CONDT (PVC) (SCH 40) (3")	618 6054 CONDT (PVC) (SCH 80) (3") (BORE)	620 6012 ELEC CONDR (NO. 4) INSULATED	620 6016 ELEC CONDR (NO. 2) INSULATED	620 6019 ELEC CONDR (NO. 1/0) BARE	620 6020 ELEC CONDR (NO. 1/0) INSULATED	RUN LENGTH FEET
1		1		2	4	1	2	375
2			1	2	4	1	2	155
3	1			2		1		10
4			1		4	1	2	205
5			1		4	1	2	65
WIRE SLACK				6	16	5	8	10
TOTAL	LF 10	LF 375	LF 425	LF 1140	LF 3360	LF 860	LF 1680	

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.



HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420



© 2024  
Texas Department of Transportation

**GUADALUPE COUNTY  
SAFETY REST AREA  
I-10 WESTBOUND  
ITS LAYOUT**

SHEET 1 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	49




MATCH LINE D



GUADALUPE COUNTY  
SAFETY REST AREA  
WESTBOUND

**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP
- ◆ PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- ▣ PROP GROUND BOX TY A W/ APRON
- ⊖ PROP VEHICLE DETECTOR
- ⊗ PROP CCTV
- PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE— EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



SUMMARY OF QUANTITIES

BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
618 6029	CONDT (PVC) (SCH 40) (3")	LF	60
618 6054	CONDT (PVC) (SCH 80) (3") (BORE)	LF	100
620 6012	ELEC CONDR (NO. 4) INSULATED	LF	360
620 6016	ELEC CONDR (NO. 2) INSULATED	LF	720
620 6019	ELEC CONDR (NO. 1/0) BARE	LF	180
620 6020	ELEC CONDR (NO. 1/0) INSULATED	LF	360
624 6002	GROUND BOX TY A (122311) W/APRON	EA	1

GUADALUPE CO WB SHT 2 OF 4  
CONDUIT & CABLE CHART

RUN NUMBER	618 6029 CONDT (PVC) (SCH 40) (3")	618 6054 CONDT (PVC) (SCH 80) (3") (BORE)	620 6012 ELEC CONDR (NO. 4) INSULATED	620 6016 ELEC CONDR (NO. 2) INSULATED	620 6019 ELEC CONDR (NO. 1/0) BARE	620 6020 ELEC CONDR (NO. 1/0) INSULATED	RUN LENGTH FEET
1		1	2	4	1	2	100
2	1		2	4	1	2	60
WIRE SLACK			4	8	2	4	10
TOTAL	LF 60	LF 100	LF 360	LF 720	LF 180	LF 360	

**NOTES:**

1. CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
2. CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
3. LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
4. CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420



GUADALUPE COUNTY  
SAFETY REST AREA  
I-10 WESTBOUND  
ITS LAYOUT

SHEET 2 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	50







MATCH LINE D

**LEGEND**

- EXIST CONDUIT
- PROP CONDUIT (TRENCH)
- ==== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- Ⓜ PROP VEHICLE DETECTOR
- Ⓜ PROP CCTV
- ⊙ PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE— EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



*K. Sai Geetha*  
2/27/2024



SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
618 6029	CONDT (PVC) (SCH 40) (3")	LF	10
618 6054	CONDT (PVC) (SCH 80) (3") (BORE)	LF	195
620 6012	ELEC CONDR (NO. 4) INSULATED	LF	450
620 6016	ELEC CONDR (NO. 2) INSULATED	LF	900
620 6019	ELEC CONDR (NO. 1/0) BARE	LF	225
620 6020	ELEC CONDR (NO. 1/0) INSULATED	LF	450
624 6002	GROUND BOX TY A (122311) W/APRON	EA	1
628 6152	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	EA	1

GUADALUPE CO WB SHT 3 OF 4 CONDUIT & CABLE CHART							
RUN NUMBER	618 6029 CONDT (PVC) (SCH 40) (3")	618 6054 CONDT (PVC) (SCH 80) (3") (BORE)	620 6012 ELEC CONDR (NO. 4) INSULATED	620 6016 ELEC CONDR (NO. 2) INSULATED	620 6019 ELEC CONDR (NO. 1/0) BARE	620 6020 ELEC CONDR (NO. 1/0) INSULATED	RUN LENGTH FEET
1	1		2	4	1	2	10
2		1	2	4	1	2	195
WIRE SLACK			4	8	2	4	10
TOTAL	LF 10	LF 195	LF 450	LF 900	LF 225	LF 450	

**NOTES:**

- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
- CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
- LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
- CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.




**GUADALUPE COUNTY  
SAFETY REST AREA  
I-10 WESTBOUND  
ITS LAYOUT**

SHEET 3 OF 4				
STATE	DISTRICT	COUNTY	HWY NUMBER	
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS	
CONTROL	SECTION	JOB	SHEET NUMBER	
0915	00	268	51	




MATCH LINE A



**LEGEND**

- EXIST CONDUIT
- - - PROP CONDUIT (TRENCH)
- SP --- PROP CONDUIT (BORE)
- SP --- PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- Ⓜ PROP VEHICLE DETECTOR
- Ⓜ PROP CCTV
- PROP ITS POLE W/ POLE MOUNTED CABINET
- OHE— EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



**INSTALL ITS POLE #1**  
 LAT: 29.615924°  
 LONG: -97.804787°  
 IH-10 AT MM 619.14  
 15 LF - DRILL SHAFT (36 IN)  
 1.25 CY - RIPRAP (CONC) (4 IN)  
 1 EA - ITS POLE (30 FT) (90 MPH)  
 1 EA - ITS POLE MNT CAB (SPL)  
 (INTEGRATED) (INSTALL ONLY)  
 1 EA - TPAS VEH DET SYS (INSTALL ONLY)

**INSTALL CCTV POLE**  
 LAT: 29.615654°  
 LONG: -97.806020°  
 IH-10 AT MM 619.04  
 21 LF - DRILL SHAFT (48 IN)  
 1.25 CY - RIPRAP (CONC) (4 IN)  
 1 EA - CCTV FIELD EQUIPMENT (DIGITAL)  
 1 EA - CCTV FIELD EQUIPMENT  
 (DIGITAL) (INSTALL ONLY)  
 1 EA - ITS POLE MNT CAB (SPL)  
 (INTEGRATED) (INSTALL ONLY)  
 1 EA - ITS POLE (60 FT) (90 MPH)  
 1 EA - ITS POLE MNT CAB (TY 2) (CONF 1)  
 1 EA - ETHERNET SWITCH (INSTALL ONLY)  
 1 EA - CELLULAR MODEM (INSTALL ONLY)

- NOTES:**
- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
  - CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO VEHICLE DETECTION SYSTEM SHALL BE AS SPECIFIED BY THE MANUFACTURER.
  - LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
  - CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.

SUMMARY OF QUANTITIES			
BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6004	DRILL SHAFT (36 IN)	LF	15
416 6006	DRILL SHAFT (48 IN)	LF	21
432 6001	RIPRAP (CONC) (4 IN)	CY	2.50
618 6023	CONDT (PVC) (SCH 40) (2")	LF	20
618 6029	CONDT (PVC) (SCH 40) (3")	LF	50
618 6054	CONDT (PVC) (SCH 80) (3") (BORE)	LF	730
620 6016	ELEC CONDR (NO. 2) INSULATED	LF	1480
620 6019	ELEC CONDR (NO. 1/0) BARE	LF	900
620 6020	ELEC CONDR (NO. 1/0) INSULATED	LF	1720
624 6002	GROUND BOX TY A (122311)W/APRON	EA	6
6010 6002	CCTV FIELD EQUIPMENT (DIGITAL)	EA	1
6010 6011	CCTV FIELD EQUIP (DIGITAL) (INSTL ONLY)	EA	1
6064 6010	ITS POLE (30 FT) (90 MPH)	EA	1
6064 6055	ITS POLE (60 FT) (90 MPH)	EA	1
6064 6080	ITS POLE MNT CAB (TY 2) (CONF 1)	EA	1
6064 6097	ITS POLE MNT CAB (SPL) (INTEGRATED) (INS)	EA	2
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
6513 6001	TPAS VEH DET SYS (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	TPAS VEHICLE DETECTION SYSTEM	EA	1
*	AXIS PTZ CAMERA	EA	1
*	POLE MOUNTED INTEGRATED ENCLOSURE CABINET	EA	2

\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

GUADALUPE CO WB SHT 4 OF 4 CONDUIT & CABLE CHART							
RUN NUMBER	618 6023 CONDT (PVC) (SCH 40) (2")	618 6029 CONDT (PVC) (SCH 40) (3")	618 6054 CONDT (PVC) (SCH 80) (3") (BORE)	620 6016 ELEC CONDR (NO. 2) INSULATED	620 6019 ELEC CONDR (NO. 1/0) BARE	620 6020 ELEC CONDR (NO. 1/0) INSULATED	RUN LENGTH FEET
1			1	4	1	2	145
2			1	4	1	2	185
3	1			4	2		10
4			1		1	2	85
5			1		1	2	260
6			1		1	2	55
7		1			1	2	50
8	1				1	2	10
WIRE SLACK				12	9	14	10
TOTAL	LF 20	LF 50	LF 730	LF 1480	LF 900	LF 1720	

**HNTB** HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

**Texas Department of Transportation**

**GUADALUPE COUNTY SAFETY REST AREA I-10 WESTBOUND ITS LAYOUT**


SHEET 4 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	52



**LEGEND**

- EXIST CONDUIT
- PROP CONDUIT (TRENCH)
- ===== PROP CONDUIT (BORE)
- SP PROP ELECTRICAL SERVICE
- PROP GROUND BOX TY A
- PROP GROUND BOX TY A W/ APRON
- PROP DYNAMIC PARKING AVAILABILITY SIGN
- ☒ PROP GROUND MOUNTED DMS CABINET
- OHE— EXIST OVER HEAD ELECTRIC LINE
- ⊙ EXIST POWER POLE



**SUMMARY OF QUANTITIES**

BID ITEM & DESC CODE	DESCRIPTION	UNITS	QTY
416 6018	DRILL SHAFT (SIGN MTS) (24 IN)	LF	29
432 6045	RIPRAP (MOW STRIP) (4 IN)	CY	12.19
540 6001	MTL W-BEAM GD FEN (TIM POST)	LF	225
540 6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	1
544 6001	GUARDRAIL END TREATMENT (INSTALL)	EA	1
618 6023	CONDT (PVC) (SCH 40) (2")	LF	180
618 6070	CONDT (RM) (2")	LF	40
620 6003	ELEC CONDR (NO.12) BARE	LF	65
620 6004	ELEC CONDR (NO.12) INSULATED	LF	130
620 6007	ELEC CONDR (NO.8) BARE	LF	160
620 6008	ELEC CONDR (NO.8) INSULATED	LF	480
624 6002	GROUND BOX TY A (122311)W/APRON	EA	2
628 6152	ELC SRV TY D 120/240 060(NS)SS(N)SP(O)	EA	1
636 6002	ALUMINUM SIGNS (TY G)	SF	182
647 6001	INSTALL LRSS (STRUCT STEEL)	LB	1050.54
658 6015	INSTL DEL ASSM (D-SW)SZ (BRF)GF1	EA	10
6028 6002	INSTALL DMS (FOUNDATION MTD CABINET)	EA	1
6123 6001	ETHERNET SWITCH (INSTALL ONLY)	EA	1
6511 6001	CELLULAR MODEM (INSTALL ONLY)	EA	1
*	CELLULAR ROUTER	EA	1
*	FIELD ETHERNET SWITCH	EA	1
*	SINGLE LINE DMS 3-CHARACTER (AMBER)	EA	3
*	CONTROLLER AND GROUND MOUNT CABINET	EA	1



\* ITEM TO BE FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR.

**GUADALUPE CO DPAS WB SHT 1 OF 1  
CONDUIT & CABLE CHART**

RUN NUMBER	618 6023 CONDT (PVC) (SCH 40) (2")	618 6070 CONDT (RM) (2")	620 6003 ELEC CONDR (NO.12) BARE	620 6004 ELEC CONDR (NO.12) INSULATED	620 6007 ELEC CONDR (NO.8) BARE	620 6008 ELEC CONDR (NO.8) INSULATED	RUN LENGTH FEET
1	1				1	3	10
2	1				1	3	70
3	1				1	3	50
4	2		1	2			25
5		2	1	2			20
WIRE SLACK			2	4	3	9	10
TOTAL	LF 180	LF 40	LF 65	LF 130	LF 160	LF 480	

**NOTES:**


- CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITIES BEFORE BEGINNING CONSTRUCTION. ANY DAMAGE TO UTILITIES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT. CONTRACTOR SHALL CALL FOR LOCATES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL POTHOLE INFRASTRUCTURE LOCATIONS AS NECESSARY PRIOR TO CONSTRUCTION. SUE WAS NOT PERFORMED FOR THIS PROJECT. CONTRACTOR SHALL EXERCISE CAUTION AND COORDINATE ALL REQUIRED UTILITY ADJUSTMENTS WITH THE ENGINEER.
- CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO DMS CONNECTION POINTS SHALL BE AS SPECIFIED BY THE MANUFACTURER.
- LOCATION OF PROPOSED ITS INFRASTRUCTURE ON THE PLAN SHEETS IS SHOWN DIAGRAMMATIC ONLY. THESE LOCATIONS MAY BE ADJUSTED BY THE ENGINEER TO SECURE A MORE DESIRABLE LOCATION OR AVOID CONFLICT WITH UTILITIES.
- CONTRACTOR SHALL ENSURE THAT ALL PROPOSED ITS INFRASTRUCTURE WORK INCLUDING BUT NOT LIMITED TO CONDUIT, ITS POLES, CABINETS, DPAS, AND ELECTRICAL SERVICES MEET MINIMUM CLEARANCE REQUIREMENTS TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES AND INFRASTRUCTURE.




**GUADALUPE COUNTY  
SAFETY REST AREA  
I-10 WESTBOUND  
SIGN LAYOUT**

SHEET 1 OF 1


STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	53



DPAS #3 GUADALUPE CO EB;  
 12.0" Radius, 2.0" Border, White on Blue;  
 D9-16; "SPACES OPEN", D; "REST AREA", D;  
 "3 MILES", D; Rectangle Black;  
 "TRUCK PARKING", D; "42 MILES", D;  
 Rectangle Black;




DPAS #3 GUADALUPE CO EB;  
 No border, White on Blue;  
 "REST AREA", D;




DPAS #3 GUADALUPE CO EB;  
 No border, White on Blue;  
 "76", D;

\* NOTE: BEFORE INSTALLING DPAS #3 THE CONTRACTOR SHALL CONTACT THE ENGINEER TO VERIFY THE STATUS OF THE PROPOSED FAYETTE CO TRUCK PARKING SITES LOCATED AT APPROXIMATE LAT 29.691914°, LONG -97.176697°. IF THE FAYETTE CO TRUCK PARKING SITES ARE NOT OPEN AT THE TIME DPAS #3 IS READY TO BE INSTALLED, THEN ATTACH THE PROPOSED TEMPORARY OVERLAYS AS SHOWN ON THIS SHEET AND AS DIRECTED BY THE ENGINEER WHEN INSTALLING DPAS #3. THE OVERLAYS MUST BE INSTALLED SO THAT THEY CAN BE EASILY REMOVED ONCE THE FAYETTE CO SITES ARE OPEN, REVEALING "TRUCK PARKING" AND "42" MILES UNDERNEATH FOR THE PERMANENT SIGN MESSAGE.



DPAS #3 GUADALUPE CO EB WITH TEMPORARY OVERLAYS;  
 12.0" Radius, 2.0" Border, White on Blue;  
 D9-16; "SPACES OPEN", D; "REST AREA", D;  
 "3 MILES", D; Rectangle Black; Rectangle Blue;  
 "MILES", D; Rectangle Black;



DPAS #4; GUADALUPE CO WB;  
 12.0" Radius, 2.0" Border, White on Blue;  
 D9-16; "SPACES OPEN", D; "REST AREAS", D;  
 "8 MILES", D; Rectangle Black; "113 MILES", D;  
 Rectangle Black; "233 MILES", D;  
 Rectangle Black;



**HNTB** HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

**Texas Department of Transportation**


**GUADALUPE COUNTY  
 LARGE  
 SIGN DETAILS**

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	54

ELECTRIC SERVICE SUMMARY																								
LOCATION	SHEET NO	ITEM & CODE	SERVICE NUMBER	ELECTRICAL SERVICE DESCRIPTION DATA (SEE ED(5) - 14 AND ED(6) - 14)	SERVICE CONDUIT SIZE (RMC) *	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK. POLE/AMP	TWO-POLE CONTACT OR AMPS	PANEL BD. / LOADCENTER AMP RATING (MIN)	CIRCUIT NO.	BRANCH CKT. BRK. POLE/AMPS	BRANCH CIRCUIT AMPS	VOLTAGE	KVA LOAD									
KERR CO DPAS EB	38	628 6152	ELECTRIC SERVICE 1	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	60	DPAS #1	2P/40	25	240	6									
KERR CO SRA EB	37	628 6152	ELECTRIC SERVICE 2	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	70	ITS POLE #1	1P/20	10	120	1.2									
												1P/20	10	120	1.2									
ITS POLE #2	1P/20										10	120	1.2											
	1P/20										10	120	1.2											
KERR CO SRA WB	37																			ITS POLE #1	1P/20	10	120	1.2
																				CCTV POLE	1P/20	10	120	1.2
											ITS POLE #2	1P/20	10	120	1.2									
KERR CO DPAS WB	42	628 6152	ELECTRIC SERVICE 3	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	60	DPAS #2	2P/40	25	240	6									
GUADALUPE CO DPAS EB	48	628 6152	ELECTRIC SERVICE 4	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	60	DPAS #3	2P/40	25	240	6									
GUADALUPE CO SRA EB	46	628 6152	ELECTRIC SERVICE 5	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	70	ITS POLE #1	1P/20	10	120	1.2									
												1P/20	10	120	1.2									
											CCTV POLE	1P/20	10	120	1.2									
	1P/20										10	120	1.2											
GUADALUPE CO DPAS WB	53										628 6152	ELECTRIC SERVICE 6	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	60	DPAS #4	2P/40	25	240	6
GUADALUPE CO SRA WB	51										628 6152	ELECTRIC SERVICE 7	ELC SRV TY D 120/240 060 (NS) SS (N) SP (O)	1 1/4"	3/#6	N/A	2P/60	N/A	70	ITS POLE #1	1P/20	10	120	1.2
			1P/20	10	120	1.2																		
		CCTV POLE	1P/20	10	120	1.2																		
	1P/20	10	120	1.2																				

\*VERIFY SERVICE CONDUIT SIZE WITH UTILITY. SIZE MAY CHANGE DUE TO UTILITY METER REQUIREMENTS. ENSURE CONDUIT SIZE MEETS THE NATIONAL ELECTRICAL CODE.  
ITS POLE #1 = POLE AT SRA ENTRANCE; ITS POLE #2 = POLE AT SRA EXIT



*Kevin D. Tyer*  
02/28/2024

SCALE : NTS

NO.	REVISIONS	BY	DATE

**TRAF-IQ**  
14811 ST. MARY'S LANE, SUITE 180  
HOUSTON, TEXAS 77079  
832.399.1100  
TEXAS PE FIRM REG # F-18726

**HNTB**  
HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420

**Texas Department of Transportation**

**ELECTRICAL SERVICE SUMMARY**


SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	55



VOLTAGE DROP CALCULATION SUMMARY

LAYOUT SHEET	ELECTRIC SERVICE ID AND BRANCH	RUN ID	RUN VOLTAGE (VOLTS)	CURRENT THIS RUN (AMPS)	LENGTH OF RUN (FEET)	ITEM NUMBER	CONDUCTOR DESCRIPTION	WIRE LOOP RESISTANCE 2 X (OHM / 1000 FT)	VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP NOT TO EXCEED 5% DROP
	DPAS #1	6	240	25.00	20	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.65	10.6275	4.43%
		5	240	25.00	25	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.82	10.7910	4.50%
		4	240	25.00	20	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.65	9.9735	4.16%
		3	240	25.00	205	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	6.70	9.3195	3.88%
		2	240	25.00	70	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	2.29	2.6160	1.09%
		1	240	25.00	10	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.33	0.3270	0.14%
		START	240	25.00	START					0.0000	
	ITS POLE #1	8	120	10.00	10	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.08	5.5350	4.61%
		7	120	10.00	150	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.23	5.4530	4.54%
		6	120	10.00	190	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.56	4.2230	3.52%
		4	120	10.00	75	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.62	2.6650	2.22%
		3	120	10.00	180	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.48	2.0500	1.71%
		2	120	10.00	60	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.49	0.5740	0.48%
		1	120	10.00	10	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.08	0.0820	0.07%
		START	120	10.00	START					0.0000	
	ITS POLE #2	5	120	10.00	15	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.20	4.4472	3.71%
		4	120	10.00	75	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.98	4.2510	3.54%
		3	120	10.00	180	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	2.35	3.2700	2.73%
		2	120	10.00	60	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.78	0.9156	0.76%
		1	120	10.00	10	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.13	0.1308	0.11%
		START	120	10.00	START					0.0000	
	ITS POLE #2	5	120	10.00	15	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.20	4.4472	3.71%
		4	120	10.00	75	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.98	4.2510	3.54%
		3	120	10.00	180	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	2.35	3.2700	2.73%
		2	120	10.00	60	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.78	0.9156	0.76%
		1	120	10.00	10	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.13	0.1308	0.11%
		START	120	10.00	START					0.0000	
	ITS POLE #2	5	120	10.00	15	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.20	4.4472	3.71%
		4	120	10.00	75	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.98	4.2510	3.54%
		3	120	10.00	180	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	2.35	3.2700	2.73%
		2	120	10.00	60	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.78	0.9156	0.76%
		1	120	10.00	10	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.13	0.1308	0.11%
		START	120	10.00	START					0.0000	
	DPAS #2	4	240	25.00	20	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.41	11.1725	4.66%
		3	240	25.00	20	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.41	10.7625	4.48%
		2	240	25.00	50	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.03	10.3525	4.31%
		1	240	25.00	215	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	4.41	9.3275	3.89%
		5	240	25.00	15	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.31	4.9200	2.05%
		4	240	25.00	40	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.82	4.6125	1.92%
		3	240	25.00	115	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	2.36	3.7925	1.58%
		2	240	25.00	60	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.23	1.4350	0.60%
		1	240	25.00	10	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.21	0.2050	0.09%
		START	240	25.00	START					0.0000	
	ITS POLE #1	4	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	5.0505	4.21%
		3	120	10.00	55	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.28	5.2836	4.40%
		2	120	10.00	315	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	1.63	4.9987	4.17%
		5	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	3.3670	2.81%
		2	120	10.00	225	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	1.17	3.3152	2.76%
		1	120	10.00	125	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.65	2.1497	1.79%
		9	120	10.00	40	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.21	1.5022	1.25%
		3	120	10.00	180	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.93	1.2950	1.08%
		2	120	10.00	60	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.31	0.3626	0.30%
		1	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	0.0518	0.04%
		START	120	10.00	START					0.0000	



**HNTB**  
HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

**Texas Department of Transportation**  
© 2024

## VOLTAGE DROP

SHEET 1 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	56

PDF Filename: 0034 - DPAS COMMUNICATIONS DETAIL SHEET 1 OF 2.pdf

pw: \\pw-int.hntb.org\p\Central\I\Documents\San Antonio Projects\73627 SAT Traffic-ITS\WA03\Design and Engineering\SAT\04\_Quantities\Sheet DGN\73627\_WA03\_SAT\_S\_VOLT\_01.dgn



VOLTAGE DROP CALCULATION SUMMARY

LAYOUT SHEET	ELECTRIC SERVICE ID AND BRANCH	RUN ID	RUN VOLTAGE (VOLTS)	CURRENT THIS RUN (AMPS)	LENGTH OF RUN (FEET)	ITEM NUMBER	CONDUCTOR DESCRIPTION	WIRE LOOP RESISTANCE 2 X (OHM / 1000 FT)	VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP NOT TO EXCEED 5% DROP
KERR CO WB SHT 3 OF 3	CCTV POLE	7	120	10.00	10	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.05	4.0145	3.35%
KERR CO WB SHT 3 OF 3		6	120	10.00	115	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.60	3.9627	3.30%
KERR CO WB SHT 3 OF 3		5	120	10.00	10	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.05	3.3670	2.81%
KERR CO WB SHT 2 OF 3		2	120	10.00	225	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	1.17	3.3152	2.76%
KERR CO WB SHT 2 OF 3		1	120	10.00	125	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.65	2.1497	1.79%
KERR CO EB SHT 1 OF 1		9	120	10.00	40	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.21	1.5022	1.25%
KERR CO EB SHT 1 OF 1		3	120	10.00	180	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.93	1.2950	1.08%
KERR CO EB SHT 1 OF 1		2	120	10.00	60	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.31	0.3626	0.30%
KERR CO EB SHT 1 OF 1		1	120	10.00	10	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.05	0.0518	0.04%
CIRCUIT "2E" START		START	120	10.00	START					0.0000	
KERR CO WB SHT 3 OF 3	CCTV POLE	7	120	10.00	10	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.05	4.0145	3.35%
KERR CO WB SHT 3 OF 3		6	120	10.00	115	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.60	3.9627	3.30%
KERR CO WB SHT 3 OF 3		5	120	10.00	10	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.05	3.3670	2.81%
KERR CO WB SHT 2 OF 3		2	120	10.00	225	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	1.17	3.3152	2.76%
KERR CO WB SHT 2 OF 3		1	120	10.00	125	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.65	2.1497	1.79%
KERR CO EB SHT 1 OF 1		9	120	10.00	40	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.21	1.5022	1.25%
KERR CO EB SHT 1 OF 1		3	120	10.00	180	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.93	1.2950	1.08%
KERR CO EB SHT 1 OF 1		2	120	10.00	60	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.31	0.3626	0.30%
KERR CO EB SHT 1 OF 1		1	120	10.00	10	620 6012	ELEC CONDR (NO. 4) INSULATED	0.518	0.05	0.0518	0.04%
CIRCUIT "2F" START		START	120	10.00	START					0.0000	
KERR CO WB SHT 1 OF 3	ITS POLE #2	3	120	10.00	10	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.03	3.6450	3.04%
KERR CO WB SHT 1 OF 3		2	120	10.00	55	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.18	3.6126	3.01%
KERR CO WB SHT 1 OF 3		1	120	10.00	160	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.52	3.4344	2.86%
KERR CO WB SHT 2 OF 3		3	120	10.00	155	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.50	2.9160	2.43%
KERR CO WB SHT 3 OF 3		1	120	10.00	95	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.31	2.4138	2.01%
KERR CO WB SHT 3 OF 3		5	120	10.00	10	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.03	2.1060	1.76%
KERR CO WB SHT 2 OF 3		2	120	10.00	225	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.73	2.0736	1.73%
KERR CO WB SHT 2 OF 3		1	120	10.00	125	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.41	1.3446	1.12%
KERR CO EB SHT 1 OF 1		9	120	10.00	40	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.13	0.9396	0.78%
KERR CO EB SHT 1 OF 1		3	120	10.00	180	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.58	0.8100	0.68%
KERR CO EB SHT 1 OF 1		2	120	10.00	60	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.19	0.2268	0.19%
KERR CO EB SHT 1 OF 1		1	120	10.00	10	620 6016	ELEC CONDR (NO. 2) INSULATED	0.324	0.03	0.0324	0.03%
CIRCUIT "2G" START		START	120	10.00	START					0.0000	
GUADALUPE CO DPAS EB SHT 1 OF 1	DPAS #3	5	240	25.00	20	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.41	7.3800	3.08%
GUADALUPE CO DPAS EB SHT 1 OF 1		4	240	25.00	30	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.62	6.9700	2.90%
GUADALUPE CO DPAS EB SHT 1 OF 1		3	240	25.00	25	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.51	6.3550	2.65%
GUADALUPE CO DPAS EB SHT 1 OF 1		2	240	25.00	275	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	5.64	5.8425	2.43%
GUADALUPE CO DPAS EB SHT 1 OF 1		1	240	25.00	10	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.21	0.2050	0.09%
CIRCUIT "3A" START		START	240	25.00	START					0.0000	
GUADALUPE CO EB SHT 1 OF 2	ITS POLE #1	5	120	10.00	10	620 6008	ELEC CONDR (NO. 8) INSULATED	1.308	0.13	3.0084	2.51%
GUADALUPE CO EB SHT 1 OF 2		4	120	10.00	40	620 6008	ELEC CONDR (NO. 8) INSULATED	1.308	0.52	3.4008	2.83%
GUADALUPE CO EB SHT 1 OF 2		3	120	10.00	115	620 6008	ELEC CONDR (NO. 8) INSULATED	1.308	1.50	2.8776	2.40%
GUADALUPE CO EB SHT 1 OF 2		2	120	10.00	95	620 6008	ELEC CONDR (NO. 8) INSULATED	1.308	1.24	1.3734	1.14%
GUADALUPE CO EB SHT 1 OF 2		1	120	10.00	10	620 6008	ELEC CONDR (NO. 8) INSULATED	1.308	0.13	0.1308	0.11%
CIRCUIT "5A" START		START	120	15.00	START					0.0000	
GUADALUPE CO EB SHT 2 OF 2	CCTV POLE	3	120	10.00	10	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.08	3.9770	3.31%
GUADALUPE CO EB SHT 2 OF 2		2	120	10.00	195	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	1.60	5.4940	4.58%
GUADALUPE CO EB SHT 2 OF 2		1	120	10.00	165	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	1.35	3.8950	3.25%
GUADALUPE CO EB SHT 1 OF 2		6	120	10.00	50	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.41	2.5420	2.12%
GUADALUPE CO EB SHT 1 OF 2		4	120	10.00	40	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.33	2.1320	1.78%
GUADALUPE CO EB SHT 1 OF 2		3	120	10.00	115	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.94	1.8040	1.50%
GUADALUPE CO EB SHT 1 OF 2		2	120	10.00	95	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.78	0.8610	0.72%
GUADALUPE CO EB SHT 1 OF 2		1	120	10.00	10	620 6010	ELEC CONDR (NO. 6) INSULATED	0.82	0.08	0.0820	0.07%
CIRCUIT "5B" START		START	120	10.00	START					0.0000	



**HNTB**  
HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

**Texas Department of Transportation**  
© 2024

**VOLTAGE DROP**

SHEET 2 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	57

VOLTAGE DROP CALCULATION SUMMARY

LAYOUT SHEET	ELECTRIC SERVICE ID AND BRANCH	RUN ID	RUN VOLTAGE (VOLTS)	CURRENT THIS RUN (AMPS)	LENGTH OF RUN (FEET)	ITEM NUMBER	CONDUCTOR DESCRIPTION	WIRE LOOP RESISTANCE 2 X (OHM / 1000 FT)	VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP NOT TO EXCEED 5% DROP
GUADALUPE CO EB SHT 2 OF 2	CCTV POLE	3	120	10.00	10	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.08	3.9770	3.31%
GUADALUPE CO EB SHT 2 OF 2		2	120	10.00	195	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.60	5.4940	4.58%
GUADALUPE CO EB SHT 2 OF 2		1	120	10.00	165	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	1.35	3.8950	3.25%
GUADALUPE CO EB SHT 1 OF 2		6	120	10.00	50	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.41	2.5420	2.12%
GUADALUPE CO EB SHT 1 OF 2		4	120	10.00	40	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.33	2.1320	1.78%
GUADALUPE CO EB SHT 1 OF 2		3	120	10.00	115	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.94	1.8040	1.50%
GUADALUPE CO EB SHT 1 OF 2		2	120	10.00	95	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.78	0.8610	0.72%
GUADALUPE CO EB SHT 1 OF 2		1	120	10.00	10	620 6010	ELEC CONDR (NO.6) INSULATED	0.82	0.08	0.0820	0.07%
CIRCUIT "5C" START		START	120	10.00	START					0.0000	
GUADALUPE CO EB SHT 2 OF 2	ITS POLE #2	5	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	4.8692	4.06%
GUADALUPE CO EB SHT 2 OF 2		4	120	10.00	260	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	1.35	4.8174	4.01%
GUADALUPE CO EB SHT 2 OF 2		2	120	10.00	195	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	1.01	3.4706	2.89%
GUADALUPE CO EB SHT 2 OF 2		1	120	10.00	165	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.85	2.4605	2.05%
GUADALUPE CO EB SHT 1 OF 2		6	120	10.00	50	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.26	1.6058	1.34%
GUADALUPE CO EB SHT 1 OF 2		4	120	10.00	40	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.21	1.3468	1.12%
GUADALUPE CO EB SHT 1 OF 2		3	120	10.00	115	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.60	1.1396	0.95%
GUADALUPE CO EB SHT 1 OF 2		2	120	10.00	95	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.49	0.5439	0.45%
GUADALUPE CO EB SHT 1 OF 2		1	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	0.0518	0.04%
CIRCUIT "5D" START		START	120	10.00	START					0.0000	
GUADALUPE CO DPAS WB SHT 1 OF 1	DPAS #4	5	240	25.00	20	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.65	5.7225	2.38%
GUADALUPE CO DPAS WB SHT 1 OF 1		4	240	25.00	25	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.82	5.0685	2.11%
GUADALUPE CO DPAS WB SHT 1 OF 1		3	240	25.00	50	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	1.64	4.2510	1.77%
GUADALUPE CO DPAS WB SHT 1 OF 1		2	240	25.00	70	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	2.29	2.6160	1.09%
GUADALUPE CO DPAS WB SHT 1 OF 1		1	240	25.00	10	620 6008	ELEC CONDR (NO.8) INSULATED	1.308	0.33	0.3270	0.14%
CIRCUIT "7A" START		START	240	25.00	START					0.0000	
GUADALUPE CO WB SHT 4 OF 4	ITS POLE #1	7	120	10.00	50	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.10	3.2232	2.69%
GUADALUPE CO WB SHT 4 OF 4		6	120	10.00	55	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.11	3.2334	2.69%
GUADALUPE CO WB SHT 4 OF 4		5	120	10.00	260	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.53	3.1212	2.60%
GUADALUPE CO WB SHT 4 OF 4		4	120	10.00	85	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.17	2.5908	2.16%
GUADALUPE CO WB SHT 4 OF 4		3	120	10.00	10	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.02	2.4174	2.01%
GUADALUPE CO WB SHT 4 OF 4		1	120	10.00	145	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.30	2.3970	2.00%
GUADALUPE CO WB SHT 1 OF 4		5	120	10.00	65	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.13	2.1012	1.75%
GUADALUPE CO WB SHT 1 OF 4		4	120	10.00	205	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.42	1.9686	1.64%
GUADALUPE CO WB SHT 1 OF 4		2	120	10.00	155	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.32	1.5504	1.29%
GUADALUPE CO WB SHT 1 OF 4		1	120	10.00	375	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.77	1.2342	1.03%
GUADALUPE CO WB SHT 2 OF 4		2	120	10.00	60	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.12	0.4692	0.39%
GUADALUPE CO WB SHT 2 OF 4		1	120	10.00	100	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.20	0.3468	0.29%
GUADALUPE CO WB SHT 2 OF 4		2	120	10.00	60	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.12	0.1428	0.12%
GUADALUPE CO WB SHT 3 OF 4		1	120	10.00	10	620 6020	ELEC CONDR (NO.1/0) INSULATED	0.204	0.02	0.0204	0.02%
CIRCUIT "6A" START		START	120	10.00	START					0.0000	
GUADALUPE CO WB SHT 4 OF 4	CCTV POLE	2	120	10.00	185	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.60	4.8438	4.04%
GUADALUPE CO WB SHT 4 OF 4		1	120	10.00	145	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.47	4.2444	3.54%
GUADALUPE CO WB SHT 1 OF 4		5	120	10.00	65	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.21	3.7746	3.15%
GUADALUPE CO WB SHT 1 OF 4		4	120	10.00	205	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.66	3.5640	2.97%
GUADALUPE CO WB SHT 1 OF 4		2	120	10.00	155	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.50	2.8998	2.42%
GUADALUPE CO WB SHT 1 OF 4		1	120	10.00	375	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	1.22	2.3976	2.00%
GUADALUPE CO WB SHT 2 OF 4		2	120	10.00	60	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.19	1.1826	0.99%
GUADALUPE CO WB SHT 2 OF 4		1	120	10.00	100	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.32	0.9882	0.82%
GUADALUPE CO WB SHT 3 OF 4		2	120	10.00	195	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.63	0.6642	0.55%
GUADALUPE CO WB SHT 3 OF 4		1	120	10.00	10	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.03	0.0324	0.03%
CIRCUIT "6B" START		START	120	10	START					0.0000	



**HNTB**  
HNTB Corporation  
 The HNTB Companies  
 Infrastructure Solutions  
 Firm Registration Number 420

**Texas Department of Transportation**  
© 2024

**VOLTAGE DROP**


SHEET 3 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	58

pw: \\pw-int.hntb.org\p\Central\Documents\Son Antonio\Project\73627 SAT Traffic\ITS\WA03\Design and Engineering\SAT\04\_Quantities\Sheet DGN\73627\_WA03\_SAT\_S\_VOLT\_03.dgn

VOLTAGE DROP CALCULATION SUMMARY

LAYOUT SHEET	ELECTRIC SERVICE ID AND BRANCH	RUN ID	RUN VOLTAGE (VOLTS)	CURRENT THIS RUN (AMPS)	LENGTH OF RUN (FEET)	ITEM NUMBER	CONDUCTOR DESCRIPTION	WIRE LOOP RESISTANCE 2 X (OHM / 1000 FT)	VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP (VOLTS)	RUNNING TOTAL VOLTAGE DROP NOT TO EXCEED 5% DROP
GUADALUPE CO WB SHT 4 OF 4	CCTV POLE	2	120	10.00	185	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.60	4.8438	4.04%
GUADALUPE CO WB SHT 4 OF 4		1	120	10.00	145	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.47	4.2444	3.54%
GUADALUPE CO WB SHT 1 OF 4		5	120	10.00	65	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.21	3.7746	3.15%
GUADALUPE CO WB SHT 1 OF 4		4	120	10.00	205	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.66	3.5640	2.97%
GUADALUPE CO WB SHT 1 OF 4		2	120	10.00	155	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.50	2.8998	2.42%
GUADALUPE CO WB SHT 1 OF 4		1	120	10.00	375	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	1.22	2.3976	2.00%
GUADALUPE CO WB SHT 2 OF 4		2	120	10.00	60	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.19	1.1826	0.99%
GUADALUPE CO WB SHT 2 OF 4		1	120	10.00	100	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.32	0.9882	0.82%
GUADALUPE CO WB SHT 3 OF 4		2	120	10.00	195	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.63	0.6642	0.55%
GUADALUPE CO WB SHT 3 OF 4		1	120	10.00	10	620 6016	ELEC CONDR (NO.2) INSULATED	0.324	0.03	0.0324	0.03%
CIRCUIT "6C" START		START	120	10	START					0.0000	
GUADALUPE CO WB SHT 1 OF 4	ITS POLE #2	3	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	4.6879	3.91%
GUADALUPE CO WB SHT 1 OF 4		2	120	10.00	155	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.80	4.6361	3.86%
GUADALUPE CO WB SHT 1 OF 4		1	120	10.00	375	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	1.94	3.8332	3.19%
GUADALUPE CO WB SHT 2 OF 4		2	120	10.00	60	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.31	1.8907	1.58%
GUADALUPE CO WB SHT 2 OF 4		1	120	10.00	100	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.52	1.5799	1.32%
GUADALUPE CO WB SHT 3 OF 4		2	120	10.00	195	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	1.01	1.0619	0.88%
GUADALUPE CO WB SHT 3 OF 4		1	120	10.00	10	620 6012	ELEC CONDR (NO.4) INSULATED	0.518	0.05	0.0518	0.04%
CIRCUIT "6D" START		START	120	10.00	START					0.0000	




**HNTB** HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420

© 2024  
Texas Department of Transportation


## VOLTAGE DROP

SHEET 4 OF 4

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	59



LED SIGN PANEL DETAIL (DAKTRONICS VM-1020-7X15-66)



- NOTES:
1. THIS SHEET DEPICTS A CONCEPTUAL EQUIPMENT LAYOUT. ALL REQUIRED EQUIPMENT AND/OR CABLE CONNECTIONS MAY NOT BE SHOWN ON THIS SHEET.
  2. ONE 1-1/2" CONDUIT HUB PER LED SIGN SUPPLIED BY DAKTRONICS. FIELD DRILLING AND HUB INSTALL IS RESPONSIBILITY OF THE CONTRACTOR.
  3. EYE BOLTS SHOULD BE REMOVED AFTER INSTALLATION AND REPLACED WITH 3/8"-16 STAINLESS STEEL BOLTS.
  4. NEATLY ROUTE ALL CABLES.
  5. METHOD FOR ATTACHING LED SIGNS TO STATIC SIGN SHALL BE PER MANUFACTURER RECOMMENDATION. USE ALL MOUNTING HOLES FOR DIRECT MOUNT.
  6. CABLING AND CONNECTORS FROM POWER SOURCE AND COMMUNICATIONS SOURCE TO DMS CONNECTION POINTS SHALL BE AS SPECIFIED BY DMS MANUFACTURER.



NOT TO SCALE



TYPICAL DPAS COMMUNICATIONS DETAIL

SHEET 1 OF 1

STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	60

CCTV FURNISHED AND INSTALLED BY CONTRACTOR. SEE NOTE 4.

AXIS PTZ CAMERA FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR. SEE NOTE 4.

60' ITS POLE

INTEGRATED ENCLOSURE CABINET FURNISHED BY TXDOT AND INSTALLED BY THE CONTRACTOR. SEE NOTE 4.

ITS POLE MOUNTED CABINET TYPE 2

ITS POLE MOUNTED CABINET TYPE 2

CELLULAR MODEM ANTENNA PROVIDED BY TXDOT

COAX

FIELD ETHERNET SWITCH PROVIDED BY TXDOT

CAT6 CABLE

CAT6 CABLE

CELLULAR MODEM PROVIDED BY TXDOT

POWER DISTRIBUTION, BREAKERS, AND SURGE PROTECTION

TYPE A GROUND BOX WITH APRON TO BE PLACED WITHIN 10' OF CABINET


CCTV CABLE TO CAMERA LOCATED AT TOP OF POLE

2" PVC SCH 40 WITH 120 VAC POWER

2" PVC SCH 40 TO 120 VAC FROM POWER SERVICE

NOTES:

1. CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT TO ENSURE A FULLY OPERATIONAL SYSTEM.
2. THIS SHEET DEPICTS A CONCEPTUAL EQUIPMENT LAYOUT. ALL REQUIRED EQUIPMENT AND/OR CABLE CONNECTIONS MAY NOT BE SHOWN ON THIS SHEET.
3. NEATLY ROUTE ALL CABLES.
4. THE STATE FURNISHED AXIS PTZ CAMERA AND INTEGRATED ENCLOSURE CABINET SHALL BE MOUNTED ON THE SAME POLE AS THE CONTRACTOR FURNISHED CAMERA AND TY 2 CABINET AS GIVEN ON THE LAYOUT SHEETS AND IN ACCORDINACE WITH THE VENDOR'S RECOMMENDATIONS. COORDINATE WITH THE VENDOR FOR MOUNTING AND LOCATION OF AXIS PTZ CAMERA AND INTEGRATED ENCLOSURE CABINET. INSTALLATION OF THE AXIS PTZ CAMERA WILL BE PAID UNDER ITEM 6010 6011. INSTALLATION OF THE INTEGRATED ENCLOSURE CABINET WILL BE PAID UNDER ITEM 6064-6097.



NOT TO SCALE

**HNTB** HNTB Corporation  
The HNTB Companies  
Infrastructure Solutions  
Firm Registration Number 420



TYPICAL  
CCTV COMMUNICATIONS  
DETAIL

SHEET 1 OF 1




STATE	DISTRICT	COUNTY	HWY NUMBER
TEXAS	SAN ANTONIO	BEXAR, ETC.	VARIOUS
CONTROL	SECTION	JOB	SHEET NUMBER
0915	00	268	61



# REQUIREMENTS FOR OVERHEAD AND LARGE GROUND-MOUNTED SIGNS

## TYPICAL EXAMPLES

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



### GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign summary sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Black legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod, or F). White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white FHWA lettering, when not specified in the SHSD or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius need not be trimmed or rounded if fabricated from an extruded material.
- Sign substrate for ground-mounted signs shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative. Sign substrate for overhead signs shall be any material that meets DMS-7110. Exit Number Panels attached above the parent sign shall be made with the same substrate and sheeting as the parent sign.
- Mounting details of attachments to parent sign face are shown on Standard Plan Sheet TSR(5). Mounting details of exit number panels above parent sign are shown in the "SMD series" Standard Plan Sheets.
- Background sheeting shall be applied to the substrate per sheeting manufacturer's recommendations. Sheeting will not be allowed to bridge the horizontal gap between panels.
- Cut all legend, symbols, borders, and direct applied sign attachments at panel joints.

### DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>

### SHEETING REQUIREMENTS

USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE B OR C SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM



## TYPICAL SIGN REQUIREMENTS

### TSR(1) - 13






FILE:	fstr1-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0915	00	268	VARIOUS				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		SAT	BEXAR, ETC.	62					

DATE: 2/27/2024 11:38:58 AM  
 FILE: fstr1-13.dgn



# REQUIREMENTS FOR ATTACHMENTS TO OVERHEAD AND LARGE GROUND MOUNTED SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TYPICAL EXAMPLES

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B OR C SHEETING

## GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Route Marker legends (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod, or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to white background sheeting, or combination thereof.
- Route markers and other attachments within the parent sign face shall be direct applied unless otherwise specified in the plans. Attachments not direct applied shall use 0.063 inch thick one piece sheet aluminum signs (Type A).
- General Service Plaques shall be 0.080 inch thick and Routing Plaques shall be 0.100 inch thick.
- The priority for Routing Plaques shall be (left to right) Hazardous Material, Airport then Hospital. See examples for mounting location.
- Mounting details of attachments to parent signs face are shown on Standard Plan Sheet TSR(5). Mounting details of sign plaque attachments above and below parent sign are shown in the "SMD series" Standard Plan Sheets.
- Plaques shall be horizontally centered at the top of the parent sign. If an exit number panel exists, the plaque shall be centered between the edge of the parent sign and the edge of the exit number panel. The plaque may be placed above the exit number panel when there is insufficient space.



TYPICAL EXAMPLES

# REQUIREMENTS FOR EXIT ONLY AND LEFT EXIT PANELS

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

SHEETING REQUIREMENTS FOR OVERHEAD EXIT PANELS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLUORESCENT YELLOW	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND	BLACK	ACRYLIC NON-REFLECTIVE FILM


## GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD). Individual panel sizes shown in the plans may be adjusted to fit actual parent sign sizes if necessary.
- Exit Panel legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets E Series.
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend shall be applied by screening process or cut-out acrylic non-reflective black film to yellow background sheeting, or combination thereof.
- Exit Only and Left Exit panels within the parent sign face shall be direct applied unless otherwise specified in the plans. Panels not direct applied shall use 0.063 inch thick one piece sheet aluminum signs (Type A).
- Mounting details of Exit Only and Left Exit panel attachments to parent signs face are shown on Standard Plan Sheet TSR(5).

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>

## TYPICAL EXAMPLES






<h2>TYPICAL SIGN REQUIREMENTS</h2>			
<h3>TSR(2) - 13</h3>			
FILE: tsr2-13.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT October 2003	CONF: 0915	SECT: 00	JOB: 268
REVISIONS		HIGHWAY	
12-03 7-13	DIST: SAT	COUNTY: BEXAR, ETC.	SHEET NO. 63
9-08			2

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:01 AM  
 FILE: tsr3-13.dgn

## REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

## REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

## GENERAL NOTES

1. Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
2. White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

3. Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
4. Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
5. Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
6. Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
7. Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
8. Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS

### TSR(3) - 13


FILE: tsr3-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	SAT	BEXAR, ETC.	64	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:03 AM  
 FILE: tsr-4-13.dgn

### REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

### REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR WARNING SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR SCHOOL SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

### GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

#### ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

#### DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS

### TSR(4) - 13

FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0915	00	268	VARIOUS				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		SAT	BEXAR, ETC.	65					




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:39:05 AM  
 FILE: tsr5-13.dgn

### ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	

CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT


**NOTE**

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.


<http://www.txdot.gov/>

### SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5




EXIT ONLY PANEL

### MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

- NOTE:**
- Sheeting for legend, symbols, and borders must be cut at panel joints.
  - Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".




SCREW ATTACHMENT




NUT/BOLT ATTACHMENT

- NOTE:**
- Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

### ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.










## TYPICAL SIGN REQUIREMENTS

### TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915 00		268	VARIOUS
12-03 7-13	DIST	COUNTY		SHEET NO.
9-08	SAT	BEXAR, ETC.		66






DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:07 AM  
FILE: smd21-08.dgn



WINDBEAM CROSS SECTION

Windbeam to be extruded aluminum (1.175 lbs/ft) or approved alternative



DEPARTMENTAL MATERIAL SPECIFICATIONS	
SIGN HARDWARE	DMS-7120

- GENERAL NOTES:
- Design conforms with AASHTO Specifications for the design and construction of structural supports for highway signs.
  - Materials and fabrication shall conform to the requirements of the Department material specifications.
  - Structural steel shall be "low-alloy steel" for non-bridge structures per Item 442, "Metal For Structures."
  - For fiberglass substrate connection details, see manufacturer's recommendations.

Texas Department of Transportation  
Traffic Operations Division


**SIGN MOUNTING DETAILS-  
EXTRUDED ALUMINUM  
SIGN PANELS & HARDWARE**

**SMD(2-1)-08**


© TxDOT 2001	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0915	00	268	VARIOUS
		DIST	COUNTY	SHEET NO.	
		SAT	BEXAR, ETC.	67	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:09 AM  
FILE: smd22-08.dgn




ELEVATION




SECTION A-A

- ① Back up weld to be made before installing stiffener plate
- ② Weld W may be continued across clips to seal joint


SIGN POST AND STUB POST  
(For W Shapes)



BOLT KEEPER PLATE  
30 Ga galv. sheet steel




STIFFENER PLATE  
DETAIL



ELEVATION

FOUNDATION DETAIL

\*Note: For signs with electrical apparatus, see ED(10) for conduit required in foundation.




SHIM DETAIL


- BOLTING PROCEDURE FOR ASSEMBLY OF BASE CONNECTION:**
1. Assemble sign post, BOLT KEEPER PLATE and stub post with bolts and three flat washers per bolt as shown.
  2. Shim as required to plumb post.
  3. Tighten all bolts the maximum possible with a 12 to 15 inch wrench to clean bolt threads and to bed washers and shims.
  4. Loosen each bolt in sequence and retighten bolts in a systematic order to the prescribed torque. Do not over-tighten.
  5. To prevent nut loosening, burr threads of bolt at junction with nut using a center punch.

Dimensions Post Size	Base Connection Data Table											Perforated Fuse Plate Data Table							Bolt Keeper Data			Foundation Data							
	Bolt Size & Torque	A	B	C	D	E	t <sub>1</sub>	t <sub>2</sub>	W	R	F	G	J	K	M	d <sub>1</sub>	d <sub>2</sub>	t <sub>3</sub>	Bolt Dia.	Wt. (ea.) (lbs.)	Bolt length	P	S	U	Stub length	Stub projection	Dr. Shaft diameter	Bar V Size	
W6x9	5/8" φ × 2 3/4"										4 1/4"	2"	4"	2 1/4"	1"	9/16"	3/4"	1/4"	1/2"	1.01	1 1/2"	8 3/8"		9 7/8"	2'-0"	3"			#5
W6x12	440-450 inch pounds	5"	2"	1 1/4"	2 3/4"	1 1/8"	3/4"	1/2"	1/4"	11/32"	5"	2 1/2"	6"	3 1/2"	1 1/2"	1/16"	1/4"	3/8"	5/8"	2.51	2 1/4"	8 1/2"	1"	10"	2'-0"	3"			#5
W6x15	36-38 foot pounds										5"	2 1/2"	5 1/4"	2 3/4"	1 1/4"	1/16"	1/16"	3/8"	5/8"	2.26	2 1/4"	10 5/8"		12 1/8"	2'-6"	3"			#6
W8x18											5 1/2"	2 1/2"	5 1/4"	2 3/4"	1 1/4"	13/16"	1"	1/2"	3/4"	3.35	2 1/4"	11"		12 3/4"	3'-0"	2 1/2"			#7
W8x21	3/4" φ × 3 1/2"										6"	3"	5 3/4"	2 3/4"	1 3/8"	13/16"	1 1/8"	1/2"	3/4"	4.03	2 1/4"	12 7/8"	1 1/2"	14 5/8"	3'-0"	2 1/2"			#8
W10x22	740-750 inch pounds	6"	2 1/4"	1 3/8"	3 1/2"	1 1/4"	1"	3/4"	5/16"	13/32"	6"	3"	6 1/2"	3 1/2"	1 5/8"	13/16"	1 5/16"	1/2"	3/4"	4.47	2 1/4"	15"		16 3/4"	3'-0"	2 1/2"			#9
W10x26	62-63 foot pounds										6"	3"	6 1/2"	3 1/2"	1 5/8"	13/16"	1 5/16"	1/2"	3/4"	4.47	2 1/4"	15"		16 3/4"	3'-0"	2 1/2"			#10
W12x26											6"	3"	6 1/2"	3 1/2"	1 5/8"	13/16"	1 5/16"	1/2"	3/4"	4.47	2 1/4"	15"		16 3/4"	3'-0"	2 1/2"			#11
S3x5.7	1/2" φ × 2 1/2"	See Detail Below									3 3/4"	1 1/2"	2 5/8"	1 1/2"	5/8"	9/16"	3/8"	1/4"	1/2"	0.60	1 1/2"	See Detail Below			3'-3 1/2"	3 1/2"	12"	Non-reinforced	
S4x7.7	440-450 inch pounds	See Detail Below									3 3/4"	1 1/2"	2 5/8"	1 1/2"	5/8"	9/16"	3/8"	1/4"	1/2"	0.60	1 1/2"	See Detail Below			3'-3 1/2"	3 1/2"	12"	Non-reinforced	


③ Foundation design shall be Type G Mount, see SMD (TY G).



ELEVATION



SIGN POST AND STUB POST  
(For S4x7.7 and S3x5.7)



DETAIL "A"

PERFORATED FUSE PLATE DETAIL

Use H.S. hex head bolts, hex head nut and bevel or flat washer (where req'd) under nut. All holes shall be drilled, sub-punched and reamed. All plate cuts shall preferably be saw cuts. However, flame cutting will be permitted provided all edges are ground. Metal projecting beyond the plane of the plate face will not be permitted. Steel fuse plates shall conform to the requirements of ASTM A36. ASTM A572 Grade 50 or ASTM A588 may be substituted for A36 at the option of the fabricator. Mill test reports shall be submitted for Fuse Plates. Steel used shall have an ultimate tensile strength not to exceed 80 KSI. For alternative Fuse Plate contact Traffic Operations Division.

Texas Department of Transportation  
Traffic Operations Division

SIGN MOUNTING DETAILS-  
LARGE ROADSIDE SIGNS  
FOUNDATION & STUB


SMD(2-2)-08

© TxDOT August 1995	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
4-98 REVISIONS	CON: 0915	SECT: 00	JOB: 268	HIGHWAY: VARIOUS
9-08	DIST: SAT	COUNTY: BEXAR, ETC.	SHEET NO.: 68	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:39:11 AM  
FILE: smd23-08 (1).dgn



REAR VIEW  
ALUMINUM PARENT SIGN & EXIT NUMBER PANEL MOUNTING DETAILS




SIDE VIEW



SIGN PLAQUE MOUNTING DETAIL TO ALUMINUM PARENT SIGN

30' or more desirable. May be reduced depending on cross section, viewing conditions and other related factors.



TYPICAL SIGN INSTALLATION AND LOCATION

LATERAL CLEARANCE NOTES:

Lateral clearances of signs mounted on median side of main lanes are the same as shown above where space will permit.

Where a sign is to be located behind guardrail, an allowable minimum clearance of five feet may be used, measured from the face of the guardrail to the near edge of sign.

\* - 6' minimum and desirable may be used only in areas of limited lateral clearance and when approved by the Engineer.

POST SPACING NOTES:

Post spacing on a two post sign may vary a maximum of plus or minus 10% of total sign width to fit field conditions.

Post spacing on a three post sign may vary a maximum of plus or minus 5% of total sign width to fit field conditions.

SIGN HEIGHT NOTES:

\*\* The 8' 6" maximum may be exceeded when placing signs on extreme slopes. In these conditions, a 7' minimum from natural ground to bottom of sign must be maintained.

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN HARDWARE	DMS-7120

GENERAL NOTES:

- Exit number panel shall be mounted to the right hand side of the parent sign for right exits and to the left hand side for left exits. The number panel shall be mounted with two uprights so its right edge is even with the right edge of the parent sign or vice-versa for left hand exits.
- Exit number panel support shall be symmetrical about number panel centerline.
- Exit number panel support shall be ASTM A36 structural steel galvanized after fabrication, or ASTM B221 aluminum alloy 6061-T6 or approved alternative.
- All bolts, nuts and washers shall be galvanized per ASTM Designation: B695 Class 50, or A153 Class C or D.
- Posts, parent sign panels, and exit number panels shall comply with notes on sheets SMD(2-1) and SMD(2-2).
- Signs (such as exit number panels) attached above a parent sign shall be made of the same type material as the parent sign. General Service and Routing signs may be fabricated from flat sheet aluminum.
- Exit number panel support and other connection hardware required to fasten exit number panel to parent sign shall be subsidiary to "Aluminum Signs" or "Fiberglass Signs."
- For fiberglass sign installation details, see manufacturer's recommendations.




SIGN MOUNTING DETAILS-  
LARGE ROADSIDE SIGNS

SMD(2-3)-08


© TxDOT August 1995	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CON: 0915	SECT: 00	JOB: 268
		DIST: SAT	COUNTY: BEXAR, ETC.	HIGHWAY: VARIOUS
				SHEET NO.: 69

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:13 AM  
FILE: smd26-01.dgn




PLAN VIEW



DETAIL C


⚠ Pull connector down tight against conduit then clamp in ground box. See Detail "D"



ELECTRICAL CONNECTION DETAIL


Enclosure cover not shown for clarity  
Detail shows channel greater than 4 inches.  
Less than 4 inches similar, see Detail A.

Use RMC ELLs, provide grounding bushings. Terminate bonding jumper to ground rod and equipment grounding conductors.




DETAIL D

Pull cable so opposite end connector is tight against conduit end, clamp cable at top of conduit as shown.




SECTION A-A

Stub-post connection  
conduit, bolts and enclosure  
(cover not shown)




ENCLOSURE

make from 12 gauge galvanized sheet metal




DETAIL B

enclosure connection  
(4 places)  
(use 2 inch bolt for 3 and 4 inch channels)



DETAIL E

steel pipe spacer  
(1" for 3" channel,  
1 1/4" for 4" channel)  
See detail B



DETAIL A

Stub-post connection  
conduit, bolts and enclosure  
for 3 and 4 inch channel  
(cover not shown)

NOTES:

- Breakaway connector shall be rated for 300 VAC, 30 amps and shall be waterproof. Connector shall be a three pole (two line conductors and neutral) polarized elastomer connector made from thermosetting synthetic polymer which remains flexible over the temperature range of -40 degrees C to 90 degrees C. The pins on the connector shall be overmolded 1/4" from the face of the connector toward the tips of the pins with the same material used in the construction of the connector body. This overmolding of the pins shall provide a non-conductive double taper which prevents the intrusion of water into the connection when the connectors are fully engaged. The pin receptors shall have current carrying barrels recessed 1/2" from the face of the connector and surrounded by beryllium copper spring sleeves. The plug/receptacle combination shall be listed by an approved testing facility (UL or Factory Mutual) as suitable for outdoor use and shall have passed a rain test and a watertight (immersion) test as approved by the Engineer.
- The female connector shall be integrally molded to a 13' length of type S0 cord containing three number 10 or number 8 AWG conductors. The male connector shall be integrally molded to a 20' length of Type S0 cord containing three number 10 or number 8 AWG conductors. Cord conductors shall have colored insulation, two black and one white, or shall be taped or painted to be two black and one white. Tape or paint marking shall cover entire exposed length. The contractor shall make a brochure submittal on cord connectors. Breakaway connector and cord shall not be paid for separately, but shall be subsidiary to the various items.
- The contractor shall install in-line waterproof fuseholders for each line conductor in the ground box. Fuses shall be fast-acting 5 amp (Bussman KTK5, Gould ATM5, Littelfuse KLK5 or equal).
- ⚠ Conduit shall convert to 3/4" liquidtight flexible metallic conduit below the fuse plate or knee joint and shall revert to 3/4" RMC above the fuse plate or knee joint. The length of liquidtight flexible metal conduit shall not exceed 6".
- Ground rod clamp shall be Blackburn GG 5/8H, Weaver W5.8 or equal.
- Ground rod to be driven to a depth to leave between 2 to 4 inches of rod above the gravel placed under the ground box. See ED(2) standard sheet for ground box details.

Texas Department of Transportation  
Traffic Operations Division

SIGN MOUNTING DETAILS-  
LARGE ROADSIDE SIGNS  
ELECTRICAL CONNECTION

SMD(2-6)-01




11-01 Revision

- ⚠ Liquidtight conduit size corrected.
- ⚠ Editing of minor notes.

© TxDOT April 1998		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
11-98	REVISIONS	CONT	SECT	JOB	HIGHWAY
11-01		0915	00	268	VARIOUS
		DIST	COUNTY		SHEET NO.
		SAT	BEXAR, ETC.		70


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:18 AM  
FILE: smd8-08.dgn



\* NOTE: "X" EQUALS THE AVERAGE HEIGHT FROM THE GROUND LINE TO THE BOTTOM EDGE OF THE SIGN.

SHADED AREA DENOTES 3 POST SUPPORTS




POST SIZE	WEIGHT OF ONE POST (#)	WEIGHT OF TWO POSTS (#)	WEIGHT OF THREE POSTS (#)
W6x9*	123.2	246.4	369.6
W6x12*	160.3	320.6	480.9
W6x15*	167.8	335.6	503.4
W8x18*	201.8	403.6	605.4
W8x21*	254.7	509.4	764.1
W10x22*	266.0	532.0	798.0
W10x26*	308.0	616.0	924.0
W12x26*	308.6	617.2	925.8
S3x5.7*	85.9	171.8	257.7
S4x7.7*	112.2	224.4	336.6

\*LAST FIGURES=POST WT. PER FT.

Weight Data is the weight of items shown for one, two or three posts - (includes top 6' of post, bottom 4' of post, post foundation stub, related base connection plates and stiffeners, friction fuse plate and all high strength bolts, nuts and washers).

**SIGN TYPE**



Note: Footings for S3x5.7 and S4x7.7 post sizes shall be non-reinforced with Class A concrete, while footing for all other post sizes shall be reinforced with Class C concrete.



**LARGE ROADSIDE SIGN SUPPORTS  
POST SELECTION  
WORKSHEET**






**SMD (8W1) - 08**

© TxDOT July 1978	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
1-82	CONT	SECT	JOB	HIGHWAY
5-01	0915	00	268	VARIOUS
9-08	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	71	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:19 AM  
 FILE: smd8-08.dgn




LEGEND:

L = Required embedment of concrete drilled shaft, in feet  
 C = Cohesive shear strength of soil, in psf  
 phi = Angle of internal friction of soil, in degrees

For values of C and phi which are intermediate to those on the charts, embedments may be determined by straight-line interpolation.

### DRILLED CONCRETE FOOTING DEPTH CHART (COHFRIC DESIGN)

NOTE: THESE CHARTS MAY BE USED AS AN ALTERNATE TO THE CHART BELOW, PROVIDED THAT SOIL COHESION AND INTERNAL FRICTION (COHFRIC) DATA ARE AVAILABLE.



### DRILLED CONCRETE FOOTING DEPTH CHART (TXDOT PENETROMETER DESIGN)

NOTE: ESTIMATED N SHOULD BE BASED AT APPROXIMATELY THE UPPER ONE-THIRD POINT OF THE DRILLED CONCRETE FOOTING BELOW THE GROUND LINE

Note:  
 1. Curves shown on this sheet are applicable for reinforced concrete footings only.



### LARGE ROADSIDE SIGN SUPPORTS FOUNDATION WORKSHEET

SMD (8W2) -08

© TxDOT July 1972		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS		CONT	SECT	JOB	HIGHWAY
5-74		0915	00	268	VARIOUS
4-78		DIST	COUNTY		SHEET NO.
9-08		SAT	BEXAR, ETC.		72

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:21 AM  
FILE: windice.dgn

APPLICABLE STANDARDS SHEETS

OVERHEAD SIGN BRIDGE STANDARDS:

- OSB-SE
- OSB-Z#
- OSB-Z#1
- HOSB-Z#
- HOSB-Z1L
- HOSB-Z#1
- OSBT
- OSBC
- OSBC-SC-Z#
- OSBS-SC
- OSB-FD
- OSB-FD-SC

CANTILEVER OVERHEAD SIGN SUPPORT STANDARDS:

- COSS-SE
- COSS-Z#-10
- HCOSS-Z#-10
- COSS-Z21-10
- COSS-Z#&Z#1-10
- COSSD
- COSSF
- COSS-FD

Note: # = Wind Zone number 1, 2, 3 or 4

HIGH MAST ILLUMINATION POLE STANDARDS:


- HMIP-98
- HMIF-98

WALKWAYS AND BRACKETS STANDARDS:

- SWW
- SB(SWL-1)

TRAFFIC SIGNAL POLE STANDARDS:

- SP-80
- SP-100
- SMA-80
- SMA-100
- DMA-80
- DMA-100
- MA-C
- MAC (ILSN)
- MAD-D
- TS-FD
- LUM-A
- CFA
- LMA
- TS-C
- MA-DPD



NOTE: Structures north of ice line to be designed for ice.

LEGEND

- ZONE 1 - [diagonal lines] = (100 MPH WIND)
- ZONE 2 - [diagonal lines] = ( 90 MPH WIND)
- ZONE 3 - [white box] = ( 80 MPH WIND)
- ZONE 4 - [diagonal lines] = ( 70 MPH WIND)
- [dashed line with circles] = (ICE LINE)
- [solid line] = (DISTRICT LINES)

WIND VELOCITY & ICE ZONES FOR APPLICABLE OVERHEAD SIGN SUPPORTS, HIGH MAST POLES, AND TRAFFIC SIGNAL POLES

Based on 50 Year Mean Recurrence Interval of Fastest Mile Wind Velocity at 33 feet height.

THIS SHEET TO BE INCLUDED IN ALL P.S.&E. PACKAGES CONTAINING ONE OR MORE OF THE APPLICABLE STANDARD SHEETS LISTED HEREON


FOR HARRIS CO. ONLY  
Zone line is just North of US 90, around the North, West and South sides of IH 610 and down the West side of SH 288.

FOR JACKSON CO. ONLY  
Zone line is just North of SH 616.

		<b>Traffic Operations Division Standard</b>	
<h2>WIND VELOCITY AND ICE ZONES</h2> <h3>WV &amp; IZ-14</h3>			
FILE: windice.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT April 1996	CONT	SECT	JOB
REVISIONS	0915	00	268
<small>8-14-Added list of applicable standards, restricting use to structures designed for Fastest Mile wind speeds.</small>			SHEET NO.
DIST	COUNTY	SAT BEXAR, ETC.	
			73

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

NOTE: Structures in zone above Ice Line to be designed for ice.



SPECIAL WIND REGION  
Special wind regions shall be examined for unusual wind conditions

THIS SHEET IS TO BE INCLUDED IN ALL P.S.&E.'s HAVING STRUCTURAL SUPPORTS FOR SIGNS, LUMINAIRES, AND/OR TRAFFIC SIGNALS DESIGNED IN ACCORDANCE WITH THE AASHTO 2001 THRU 2013 LTS DESIGN SPEC

BASIC WIND VELOCITY ZONES FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS DESIGNED IN ACCORDANCE WITH THE AASHTO 2001 THRU 2013 LTS DESIGN SPEC

Values are nominal design 3-sec gust wind speeds in mph at 33 ft above ground for Exposure C category. (50-year mean recurrence interval)

FOR HARRIS CO. ONLY  
Zone line is just North of US 90, around on the North, West and South sides of IH 610 and down the West side of SH 288.

FOR VICTORIA & JACKSON COUNTIES ONLY  
Zone line is just South of US 59.

Zone line is just East of both CO 1847 & FM 511

NOTE: AASHTO 2001 THRU 2013 LTS DESIGN SPEC =AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals, 4th thru 6th Edition






DATE: 2/27/2024 11:39:24 AM  
FILE: I+s2013.dgn


		<b>Traffic Operations Division Standard</b>	
<b>WIND VELOCITY AND ICE ZONES (AASHTO 2001-2013 LTS DESIGN SPEC) WV &amp; IZ(LTS2013)-14</b>			
FILE: I+s2013.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT August 2014	CONT: 0915	SECT: 00	JOB: 268
REVISIONS	COUNTY		SHEET NO.
	SAT BEXAR, ETC.		74





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:39:26 AM  
 FILE: dom1-20 (2).dgn

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back
						1-Size 2 reflector unit	1-Size 1 reflector unit	2-Size 2 reflector units	
SHEETING	Yellow, White or Red Type B or C reflective sheeting				Yellow, White or Red Type B or C Reflective Sheeting				
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF

OBJECT MARKERS								D & OM DESCRIPTIVE CODES	
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)	INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
		OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	
SHEETING	Yellow-Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting			Red -Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	
POST TYPE	TWT	WC	WC	WFLX	TWT			TWT	
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP	

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.		
DEVICE	GF1	GF2	CTB	 W1-8				 W1-6			
	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
				MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only	MOUNTING HEIGHT	7'-0"		
NOTE	1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			NOTE	1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).						
SHEETING	Yellow, White, Red										

  
**DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION**  
**D & OM(1)-20**

FILE: dom1-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	SAT	BEXAR, ETC.	75	

20A

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**POST TYPE AND SUPPORT FOUNDATION DETAILS**








**TYPE OF BARRIER MOUNTS**

**WING CHANNEL (WC)**

**FLEXIBLE POSTS (YFLX, WFLX)**

**WEDGE ANCHOR SYSTEMS**

**GUARD FENCE ATTACHMENT**



**NOTES**

1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only.
2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.


**NOTES**

1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices.
2. Install per manufacturer's recommendations.
3. Post length may vary to meet field conditions.
4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.

**NOTE**

1. Install per manufacturer's recommendations.

**CONCRETE TRAFFIC BARRIER (CTB)**




**GENERAL NOTES**

1. Place delineators on a section of roadway at a consistent distance from the edge of pavement.
2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

**TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS**


**CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN**

**DELINEATORS AND TYPE 2 OBJECT MARKERS**




**NOTE**

Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)



**NOTE**

Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.



See general notes 1, 2 and 3.



**DELINEATOR & OBJECT MARKER INSTALLATION**

**D & OM(2)-20**

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	SAT	BEXAR, ETC.	76	

DATE: 2/27/2024 11:39:28 AM  
 FILE: dom2-20 (2).dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:30 AM  
 FILE: ed1-14.dgn

**GENERAL NOTES FOR ALL ELECTRICAL WORK**

1. The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
2. Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
3. Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is 1/2 in. or less in diameter.
4. Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
5. Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
6. When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

**CONDUIT**

**A. MATERIALS**

1. Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
2. Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
3. Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.


AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" x 8" x 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" x 8" x 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" x 8" x 4"	8" x 8" x 4"	10" x 10" x 4"
#8	8" x 8" x 4"	8" x 8" x 4"	8" x 8" x 4"

4. Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
5. Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
6. Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
7. Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

8. Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
9. When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
10. Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.

**B. CONSTRUCTION METHODS**

1. Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
2. Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
3. Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
4. Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
5. When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
6. Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
7. During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
8. Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
9. Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
10. Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
11. At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
12. Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
13. Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
14. File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.

				<b>Traffic Operations Division Standard</b>	
<h1>ELECTRICAL DETAILS CONDUITS &amp; NOTES</h1>					
<h2>ED(1) - 14</h2>					
FILE:	ed1-14.dgn	DWG:	CK:	DW:	CK:
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0915	00	268	VARIOUS
	DIST	COUNTY		SHEET NO.	
	SAT	BEXAR, ETC.		77	



# ELECTRICAL CONDUCTORS

## A. MATERIAL INFORMATION

- Provide Type XHHW insulated conductors in accordance with Departmental Material Specification (DMS) 11040 "Conductors" and Item 620 "Electrical Conductors." Provide conductors as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 620. Color code insulated conductors in conformance with the NEC. Identify grounded (neutral) conductors with white insulation. Identify grounding conductors (ground wires) with green insulation or bare conductors. Identify ungrounded (hot) conductors with any color insulation except green, white, or gray. Keep color scheme consistent throughout the wiring system. Identify conductors 6 American Wire Gauge (AWG) and smaller by continuous color jacket. Identify electrical conductors 4 AWG and larger by continuous color jacket or by colored tape. When identifying conductors with colored tape, mark at least 6 in. of the conductor's insulation with half laps of tape.
- Provide a solid copper 6 AWG grounding electrode conductor to bond the electrical service equipment to the concrete encased grounding electrode or the ground rod at the service location. Connect the grounding electrode conductor to the ground rod with a UL listed connector in accordance with DMS 11040. Connect the grounding electrode conductor to the concrete encased grounding electrode as shown in the plans.
- Where two or more circuits are present in one conduit or enclosure, permanently identify the conductors of each branch circuit by attaching a non-metallic tag around both circuit conductors at each accessible location. Provide tags with two straps, large enough to indicate circuit number, letter, or other identification as shown in the plans. Print circuit identification on the tag with a permanent marker.
- Use listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors for splicing as specified in DMS 11040. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Provide UL listed gel-filled insulating splice covers. Splicing materials, insulating materials, breakaway disconnects, splice covers, and fuse holders are subsidiary to various bid items.

## B. CONSTRUCTION METHODS

- Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the conduit system. After installing conductors in conduit, perform conductor pull test. If a conductor cannot be freely pulled, make any needed alterations or repairs at no additional cost to the department. Perform insulation resistance tests in accordance with Item 620. Coordinate with the Engineer to witness the tests.
- Leave 2 ft. minimum, 3 ft. maximum length for each conductor up to the splice in ground boxes. Leave 3 ft. minimum, 4 ft. maximum length of conductor in ground boxes when pulled through with no splice. Leave 1 ft. minimum, 1.5 ft. maximum length of conductor at enclosures, weatherheads and pole bases.
- Make splices only in junction boxes, ground boxes, pole bases, or electrical enclosures and use only listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors. Insulate splices with heavy wall heat shrink tubing or gel-filled insulating splice covers to provide a watertight splice. Overlap conductor insulation with heat shrink tubing a minimum of 2 in. past both sides of the splice. Where heat shrink tubing may not shrink sufficiently to provide a watertight seal around the individual conductors, prior to heating the tubing, increase the diameter of the conductor insulation using hot melt adhesive tape to provide a watertight seal between the individual conductors and the heat shrink tubing. Ensure the tape extends past the heat shrink tubing. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Heat shrink tubing that appears to have been burned, or overheated, is considered defective and must be replaced.
- Size and install gel-filled insulating splice covers according to manufacturer's specifications when used in place of heat shrink tubing.
- Wire nuts with factory applied waterproof sealant may be used for 8 AWG or smaller conductors in above ground junction boxes, but not in pole bases or ground boxes. Install wire nuts in an upright position to prevent the accumulation of water.
- Support conductors in illumination poles with a J-hook at the top of the pole.
- When terminating conductors, remove the insulation and jacketing material without nicking the individual strands of the conductor. Conductors with nicked individual conductor strands or removed strands will be considered damaged.
- Replace conductors and cables that are damaged beyond repair or that fail an insulation resistance test at no additional cost to the department.
- Do not repair damaged conductors with duct tape, electrical tape, or wire nuts. Use only approved splicing methods.
- Do not terminate more than one conductor under a single connector, unless the connector is rated for multiple conductors. Do not exceed the pressure connector's listing for maximum number and size of conductors allowed.
- Install breakaway connectors on conductors bid under Item 620 whenever those conductors pass through a breakaway support device. Follow manufacturer's instructions when terminating conductors to breakaway connectors. Properly torque threaded connections. Proper terminations are critical to the safe operation of breakaway devices. Trim waterproofing boots on breakaway connectors to fit snugly around the conductor to ensure waterproof connection. Only one conductor may enter a single opening in a boot. Provide waterproof boots with the correct number of openings. Leave unused openings factory sealed. Use prequalified breakaway connectors as shown on the MPL.

- Provide and install a separate stranded equipment grounding conductor (EGC) in all conduits that contain circuit wiring of 50 volts or more. Unless shown elsewhere, size the EGC to be the same size as the largest current carrying conductor contained in the conduit. Ensure all EGCs are bonded together at every accessible location. For traffic signal installations, provide a minimum size 8 AWG EGC. The EGC is paid for under Item 620.

## C. TEMPORARY WIRING

- Install temporary conductors and electrical equipment in accordance with the NEC article "Temporary Installations" and Department standard sheets.
- Provide a ground fault circuit interrupter (GFCI) for power outlets for portable electrical equipment, power tools, ice machines, ice storage bins and refrigerators located outdoors at grade. GFCI may be any one of the following: molded cord and plug set, receptacle, or circuit breaker type.
- Use listed wire nuts with factory applied sealant for temporary wiring where approved.
- Enclose conductor splices within a listed enclosure or ground box, or ensure the splices are more than 10 ft. above grade vertically and more than 5 ft. horizontally from any metal structure. Where installing temporary conductors in areas subject to vehicle traffic or mobile construction equipment, ensure the vertical clearance to ground is at least 18 ft. when measured at the lowest point. Ground messenger wires that support power conductors in conformance with the NEC.
- Protect and when necessary repair any existing electrical conduits uncovered during the construction process in a timely manner and in conformance with the NEC.


## GROUND RODS & GROUNDING ELECTRODES

### A. MATERIAL INFORMATION


- Provide and install a grounding electrode at electrical services. Provide ground rods according to DMS 11040 and the plans. Larger diameter or longer length rods may be called for in some specific locations, see the individual plans sheets. Concrete encased grounding electrodes may be called for in specific locations including electrical service, see individual plan sheets.

### B. CONSTRUCTION METHODS


- Furnish auxiliary ground rods for lightning protection and install in soil, concrete, or both, as called for in the plans. For ground rods installed in concrete, ensure the connection of the conductor to the ground rod is readily accessible for inspection or repairs. For ground rods installed in soil, ensure that the upper end is between 2 to 4 in. below finished grade.
- Do not place ground rods in the same drilled hole as a timber pole.
- Install ground rods so the imprinted part number is at the upper end of the rod.
- Remove all non-conductive coatings such as concrete splatter from the rod at the clamp location.
- Route all conductors as short and straight as possible for connection to lightning protection ground rods. When a bend is required, ensure a minimum radius bend of four inches for these conductors.
- Unless otherwise called for in the plans, protect grounding electrode conductors with non-metallic conduit. When protecting grounding electrode conductors with metal conduit, provide and install a grounding type bushing and properly sized bonding jumper on each end of the metal conduit.
- Written authorization is required before installing a ground rod in a horizontal trench for rocky soil or a solid rock bottom.



**SPLICE OPTION 1  
Compression Type**



**SPLICE OPTION 2  
Split Bolt Type**




**SPLICE OPTION 3  
Listed Screw Type**

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:32 AM  
FILE: ed3-14.dgn

		<b>Traffic Operations Division Standard</b>	
<h2>ELECTRICAL DETAILS CONDUCTORS</h2>			
<h3>ED(3) - 14</h3>			
FILE: ed3-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT October 2014	CONT: 0915	SECT: 00	JOB: 268
REVISIONS		HIGHWAY	
		VARIOUS	
DIST: SAT	COUNTY: BEXAR, ETC.	SHEET NO. 78	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**APRON FOR GROUND BOX**

- (1) Uniformly space ends of conduits within the ground box. Position ends of conduits so that ground box walls do not interfere with the installation of grounding bushings or bell end fittings.
- (2) Maintain sufficient space between conduits to allow for proper installation of bushing.
- (3) Place aggregate under the box, not in the box. Aggregate should not encroach on the interior volume of the box.
- (4) Install a grounding bushing on the upper end of all RMC terminating in a ground box. Ground RMC elbows when any part of the elbow is less than 18 in. below the bottom of the ground box. Install a PVC bushing or bell end fitting on the upper end of all PVC conduits terminating in a ground box.

GROUND BOX DIMENSIONS	
TYPE	OUTSIDE DIMENSIONS (INCHES) (Width x Length X Depth)
A	12 X 23 X 11
B	12 X 23 X 22
C	16 X 29 X 11
D	16 X 29 X 22
E	12 X 23 X 17

GROUND BOX COVER DIMENSIONS								
TYPE	DIMENSIONS (INCHES)							
	H	I	J	K	L	M	N	P
A, B & E	23 1/4	23	13 3/4	13 1/2	9 7/8	5 1/8	1 3/8	2
C & D	30 1/2	30 1/4	17 1/2	17 1/4	13 1/4	6 3/4	1 3/8	2



**GROUND BOX COVER**

**GROUND BOXES**

**A. MATERIALS**

1. Provide polymer concrete ground boxes measuring 16x30x24 in. (WxLxD) or smaller in accordance with Departmental Material Specification (DMS) 11070 "Ground Boxes" and Item 624 "Ground Boxes."
2. Provide Type A, B, C, D, and E ground boxes as shown in the plans, and as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 624.
3. Ensure ground box cover is correctly labeled in accordance with DMS 11070.
4. Provide larger ground boxes in accordance with Item 624 and as shown in the plans.

**B. CONSTRUCTION METHODS**

1. Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure aggregate bed is in place and at least 9 inches deep, prior to setting the ground box. Install ground box on top of aggregate.
2. Cast ground box aprons in place. Reinforcing steel may be field bent. Ensure the depth of concrete for the apron extends from finished grade to the top of the aggregate bed under the box. Ground box aprons, including concrete and reinforcing steel, are subsidiary to ground boxes when called for by descriptive code.
3. Keep bolt holes in the box clear of dirt. Bolt covers down when not working in ground boxes.
4. Install all conduits and ells in a neat and workmanlike manner. Uniformly space conduits so grounding bushings and bell end fittings can easily be installed.
5. Temporarily seal all conduits in the ground box until conductors are installed.
6. Permanently seal conduits immediately after the completion of conductor installation and pull tests. Permanently seal the ends of all conduits with duct seal, expandable foam, or other method as approved. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a sealant.
7. When a ground rod is present in a ground box, bond all equipment grounding conductors together and to the ground rod with listed connectors.
8. When a type B or D ground box is stacked to meet volume requirements, it is allowable to cut an appropriately sized hole for conduit entry in the side wall at least 18 inches below grade.
9. If an existing ground box in the contract has a metal cover, bond the cover to the equipment grounding conductor with a 3 ft. long stranded bonding jumper the same size as the grounding conductor. The bonding jumper is subsidiary to various bid items. Verify existing ground boxes with metal covers are shown on the plans, with notes fully describing the work required.
10. If other ground boxes with metal covers are within the project limits but are not part of the contract, the Engineer may direct the Contractor to bond the metal covers, identifying the specific boxes in writing. This work will be paid for separately.
11. Bond metal ground box covers to the grounding conductor with a tank ground type lug.

DATE: 2/27/2024 11:39:35 AM  
 FILE: ed4-14.dgn

				<b>Traffic Operations Division Standard</b>	
<h2>ELECTRICAL DETAILS GROUND BOXES</h2> <h3>ED(4) - 14</h3>					
FILE:	ed4-14.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0915	00	268	VARIOUS
DIST	COUNTY		SHEET NO.		
SAT	BEXAR, ETC.		79		

**ELECTRICAL SERVICES NOTES**

- Provide new materials. Ensure installation and materials comply with the applicable provisions of the National Electrical Code (NEC) and National Electrical Manufacturers Association (NEMA) standards. Ensure material is Underwriters Laboratories (UL) listed. Provide and install electrical service conduits, conductors, disconnects, contactors, circuit breaker panels, and branch circuit breakers as shown on the Electrical Service Data chart in the plans. Faulty fabrication or poor workmanship in material, equipment, or installation is justification for rejection. Where manufacturers provide warranties and guarantees as a customary trade practice, furnish these to the State.
- Provide electrical services in accordance with Electrical Details standard sheets, Departmental Material Specification (DMS) 11080 "Electrical Services," DMS 11081 "Electrical Services-Type A," DMS 11082 "Electrical Services-Type C," DMS 11083 "Electrical Services-Type D," DMS 11084 "Electrical Services-Type T," DMS 11085 "Electrical Services-Pedestal (PS)", and Item 628 "Electrical Services" of the Standard Specifications. Provide electrical service types A, C, and D, as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 628. Provide other service types as detailed on the plans.
- Provide all work, materials, services, and any incidentals needed to install a complete electrical service as specified in the plans.
- Coordinate with the Engineer and the utility provider for metering and compliance with utility requirements. Primary line extensions, connection charges, meter charges, and other charges by the utility company to provide power to the location are paid for in accordance with Item 628. Get approval for the costs associated with these charges prior to engaging the utility company to do the work. Consult with the utility provider to determine costs and requirements, and coordinate the work as approved.
- The enclosure manufacturer will provide Master Lock Type 2 with brass tumblers keyed #2195 for all custom electrical enclosures. Installing Contractor is to provide Master Lock #2195 Type 2 with brass tumblers for "off the shelf" enclosures. Master Lock #2195 keys and locks become property of the State. Unless otherwise approved, do not energize electrical service equipment until locks are installed.
- Enclosures with external disconnects that de-energize all equipment inside the enclosure do not need a dead front trim. Protect incoming line terminations from incidental contact as required by the NEC.
- When galvanized is specified for nuts, screws, bolts or miscellaneous hardware, stainless steel may be used.
- Provide wiring and electrical components rated for 75°C. Provide red, black, and white colored XHHW service entrance conductors of minimum size 6 American Wire Gauge (AWG). Identify size 6 AWG conductors by continuous color jacket. Identify electrical conductors sized 4 AWG and larger by continuous color jacket or by colored tape. Mark at least 6 inches of the conductor's insulation with half laps of colored tape, when identifying conductors. Ensure each service entrance conductor exits through a separately bushed non-metallic opening in the weatherhead. The lengths of the conductors outside the weatherhead are to be 12 inches minimum, 18 inches maximum, or as required by utility.
- All electrical service conduit and conductors attached to the electrical service including the riser or the elbow below ground are subsidiary to the electrical service. For an underground utility feed, all service conduit and conductors after the elbow, including service conduit and conductors for the utility pole riser when furnished by the Contractor, will be paid for separately.
- Provide rigid metal conduit (RMC) for all conduits on service, except for the 1/2 in. PVC conduit containing the electrical service grounding electrode conductor. Size the service entrance conduit as shown in the plans. Ensure conduit for branch circuit entry to enclosure is the same size as that shown on the layout sheets for branch circuit conduit. Extend all rigid metal conduits a minimum of 6 inches underground and then couple to the type and schedule of the conduit shown on the layout for that particular branch circuit. Install a grounding bushing on the RMC where it terminates in the service enclosure.
- Use of liquidtight flexible metal conduit (LFMC) is allowed between the meter and service enclosure when they are mounted 90 to 180 degrees to each other. Size the LFMC the same size as service entrance conduit. LFMC must not exceed 3 feet in length. Strap LFMC within 1 foot of each end. LFMC less than 12 inches in length need not be strapped. Each end of LFMC must have a grounding bushing or be terminated with a grounding fitting. The LFMC must contain a grounded (neutral) conductor. Ensure any bend in LFMC never exceeds 180 degrees. A pull test is required on all installed conductors, with at least six inches of free conductor movement demonstrated to the satisfaction of the Engineer.
- Ensure all mounting hardware and installation details of services conform to utility company specifications.
- For all electrical service enclosures listed under Item 628 on the MPL, the UL 508 enclosure manufacturers will prepare and submit a schematic drawing unique to each service. Before shipment to the job site, place the applicable laminated schematic drawings and the laminated plan sheet showing the electrical service data chart used to build the enclosure in the enclosure's data pocket. The installing contractor will copy and laminate the actual project plan sheets detailing all equipment and branch circuits supplied by that service. The laminated plan sheets are to be placed in the service enclosure's document pocket. Reduce 11 in. x 17 in. plan sheets to 8 1/2 in. x 11 in. before laminating. If the installation differs from the plan sheets, the installing contractor is to redline plan sheets before laminating.
- When providing an "Off The Shelf" Type D or Type T service, provide laminated plan sheets detailing equipment and branch circuits supplied by that service. Reduce 11 in. x 17 in. plan sheets to 8 1/2 in. x 11 in. before laminating. Deliver these drawings before completion of the work to the Engineer, instead of placing in enclosure that has no door pocket.
- Do not install conduit in the back wall of a service enclosure where it would penetrate the equipment mounting panel inside the enclosure. Provide grounding bushings on all metal conduits, and terminate bonding jumpers to grounding bus. Grounding bushings are not required when the end of the metal conduit is fitted with a conduit sealing hub or threaded boss, such as a meter base hub.

**SERVICE ASSEMBLY ENCLOSURE**

- Provide threaded hub for all conduit entries into the top of enclosure.
- Type galvanized steel (GS) enclosures may be used for Type C panelboards and for Type D and T services that do not use an enclosure mounted photocell or lighting contactor. Provide GS enclosures in accordance with DMS 11080, 11082, 11083, and 11084.
- Provide aluminum (AL) and stainless steel (SS) enclosures for Types A, C, and D in accordance with DMS 11080, 11081, 11082, 11083, and 11084. Do not paint stainless steel.
- Provide pedestal service (PS) enclosures in accordance with ED(9) and DMS 11080 and 11085. Do not provide GS pedestal services. If GS is shown in the PS descriptive code, provide an AL enclosure.

**MAIN DISCONNECT & BRANCH CIRCUIT BREAKERS**

- Field drill flange-mounted remote operator handle if needed, to ensure handle is lockable in both the "On" and "Off" positions.
- When the utility company provides a transformer larger than 50 KVA, verify that the available fault current is less than the circuit breaker's ampere interrupting capacity (AIC) rating and provide documentation from the electric utility provider to the Engineer.



**PHOTOELECTRIC CONTROL**

- Provide photocell as listed on the MPL. Move, adjust, or shield the photocell from stray or ambient night time light to ensure proper operation. Mount photocell facing north when practical. Mount top of pole photocells as shown on Top Mounted Photocell Detail.

* ELECTRICAL SERVICE DATA												
Elec. Service ID	Plan Sheet Number	Electrical Service Description	Service Conduit *xSize	Service Conductors No./Size	Safety Switch Amps	Main Ckt. Bkr. Pole/Amps	Two-Pole Contractor Amps	Panelbd/ Loadcenter Amp Rating	Branch Circuit ID	Branch Ckt. Bkr. Pole/Amps	Branch Circuit Amps	KVA Load
SB 183	289	ELC SRV TY A 240/480 100(SS)AL(E)SF(U)	2"	3/#2	100	2P/100	100	N/A	Lighting NB	2P/40	26	28.1
									Lighting SB	2P/40	25	
									Underpass	1P/20	15	
NB Access	30	ELC SRV TY D 120/240 060(NS)SS(E)TS(O)	1 1/4"	3/#6	N/A	2P/60		100	Sig. Controller	1P/30	23	5.3
							30		Luminaires	2P/20	9	
									CCTV	1P/20	3	
2nd & Main	58	ELC SRV TY T 120/240 000(NS)GS(N)SP(O)	1 1/4"	3/#6	N/A	N/A	N/A	70	Flashing Beacon 1	1P/20	4	1.0
									Flashing Beacon 2	1P/20	4	

\* Example only, not for construction. All new electrical services must have electrical service data chart specific to that service as shown in the plans.  
 \*\* Verify service conduit size with utility. Size may change due to utility meter requirements. Ensure conduit size meets the National Electrical Code.

**EXPLANATION OF ELECTRICAL SERVICE DESCRIPTIVE CODE**



**TOP MOUNTED PHOTOCELL**


Install conduit strap maximum 3 feet from box. 5 foot maximum spacing between straps supporting conduit.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 2/27/2024 11:39:37 AM  
 FILE: ed5-14.dgn

				<b>Traffic Operations Division Standard</b>	
<h2>ELECTRICAL DETAILS SERVICE NOTES &amp; DATA</h2> <h3>ED(5) - 14</h3>					
FILE: ed5-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2014	CONT	SECT	JOB	HIGHWAY	
REVISIONS		0915	00	268	VARIOUS
DIST	COUNTY		SHEET NO.		
SAT	BEXAR, ETC.				80



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**SCHEMATIC TYPE A  
THREE WIRE**


Red insulation or color code 6" length of Line 1 or Line 2 conductors' insulation with red tape where conductor exits the weatherhead.

White insulation or color code 6" length of neutral conductors' insulation with white tape where conductor exits the weatherhead.


⑧ Two Photocell viewing windows not shown but required when photocell is listed as enclosure mounted. Windows not required when photocell is listed as pole top mounted.

Do not bond this bus to the enclosure

WIRING LEGEND	
————	Power Wiring
-----	Control Wiring
—N—	Neutral Conductor
—G—	Equipment grounding conductor-always required




**SCHEMATIC TYPE C  
THREE WIRE**



**SCHEMATIC TYPE D - CUSTOM  
120/240 VOLTS - THREE WIRE**

Red insulation or color code 6" length of Line 1 or Line 2 conductors' insulation with red tape where conductor exits the weatherhead.

White insulation or color code 6" length of neutral conductors' insulation with white tape where conductor exits the weatherhead.



**SCHEMATIC TYPE T  
120/240 VOLTS - THREE WIRE**  
Galvanized steel-"Buy Off The Shelf" only. When required install photocell top of the pole or on luminaire only, no lighting contractor will be installed.

SCHEMATIC LEGEND	
1	Safety Switch (when required)
2	Meter (when required-verify with electric utility provider)
3	Service Assembly Enclosure
4	Main Disconnect Breaker (See Electrical Service Data)
5	Circuit Breaker, 15 Amp (Control Circuit)
6	Auxiliary Enclosure
7	Control Station ("H-O-A" Switch)
8	Photo Electric Control (enclosure-mounted shown)
9	Lighting Contactor
10	Power Distribution Terminal Blocks
11	Neutral Bus
12	Branch Circuit Breaker (See Electrical Service Data)
13	Separate Circuit Breaker Panelboard
14	Load Center
15	Ground Bus

DATE: 2/27/2024 11:39:39 AM  
FILE: ed6-14.dgn

				<b>Traffic Operations Division Standard</b>	
<b>ELECTRICAL DETAILS SERVICE ENCLOSURE AND NOTES ED(6) - 14</b>					
FILE:	ed6-14.dgn	DN:	TxDOT	CK:	TxDOT
©TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0915	00	268	VARIOUS
DIST	COUNTY	SHEET NO.			
SAT	BEXAR, ETC.	81			


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**SUPPORT TYPE STEEL POLE (SP) AND STEEL FRAME (SF)**

1. Provide steel pole and steel frame supports as per TxDOT Departmental Material Specification (DMS) 11080 "Electrical Services." Mount all equipment and conduit on 12 gauge galvanized steel or stainless steel channel strut, 1 1/2 in. or 1 3/8 in. wide by 1 in. up to 3 3/4 in. deep Unistrut, Kindorf, B-line or equal. Bolt or weld all channel and hardware to vertical members as approved. Do not stack channel. File smooth and paint field cut ends of all channel with zinc-rich paint before installing.
2. Provide poles for overhead service with an eyebolt or similar fitting for attachment of the service drop to the pole in conformance with the electric utility provider's specifications.
3. Provide and install galvanized 3/4 in. x 18 in. x 4 in. (dia. x length x hook length) anchor bolts for underground service supports. Provide and install galvanized 3/4 in. x 56 in. x 4 in. anchor bolts for overhead service supports. Ensure anchor bolts have 3 in of thread, with 3 1/4 in. to 3 1/2 in. of the exposed anchor bolt projecting above finished foundation. Provide and install leveling nuts for all anchor bolts.
4. Bond one of the anchor bolts to the rebar cage with 6 AWG bare stranded copper conductor. Use listed mechanical connectors rated for embedment in concrete. See Inset B.
5. Furnish and install rigid metallic ells in all steel pole and steel frame foundations for all conduits entering the service from underground.
6. Use class C concrete for foundations. Ensure reinforcing steel is Grade 60 with 3" of unobstructed concrete cover.
7. Drill and tap steel poles and frames for 1/2 in. X 13 UNC tank ground fitting. For steel pole service supports, provide and install tank ground fitting 4 in. to 6 in. below electrical service enclosure. Provide properly sized hole through the bottom of the enclosure for the service grounding electrode conductor. Ensure electrical service grounding electrode conductor is as short and straight as possible from the enclosure to the tank ground fitting. For steel frame service supports, provide and install tank ground fitting on steel frame post. Install service grounding electrode conductor in a non-metallic conduit or tubing from the enclosure to the steel frame post. Connect electrical service grounding electrode conductor to the tank ground fitting. See steel frame and steel pole details and Inset A for more information. Size service entrance conduit and branch circuit conduit as shown in the plans. For underground conduit runs from the electrical service, extend RMC from the service enclosure to an RMC elbow, and then connect the schedule type and size of conduit shown in the plans. Provide and install grounding bushings where RMC terminates in the enclosure. Grounding bushings are not required when RMC is fitted into a sealing hub or threaded boss.
8. If Steel pole or frame is painted, bond each separate painted piece with a bonding jumper attached to a tapped hole.
9. Provide 1/4" - 20 machine screws for bonding. Do not use sheet metal screws. Remove all non-conductive material at contact points. Terminate bonding jumpers with listed devices. Install minimum size 6 AWG stranded copper bonding jumpers. Make up all threaded bonding connections wrench tight.
10. Avoid contact of the service drop and service entrance conductors with the metal pole to prevent abrasion of the insulated conductors.
11. Shop drawings are not required for service support structure unless specifically stated elsewhere or directed by the Engineer.


White insulation or color code 6" of neutral conductor's insulation with white tape where conductor exits weatherhead.

Red insulation or color code 6" length of Line 1 or Line 2 conductor's insulation with red tape where conductor exits the weatherhead. Conductor slack length, 12" min., 18" max.




WITH SAFETY SWITCH  
WITHOUT SAFETY SWITCH  
**SERVICE SUPPORT TYPE SP (O) - OVERHEAD SERVICE**


Drill, tap, and thread 1/2" X 13 UNC. Install tank ground fitting, connect electrical service grounding electrode conductor. See Note 7.





FRONT VIEW  
INSET A  
INSET B




WITH SAFETY SWITCH  
**SERVICE SUPPORT TYPE SP (U) - UNDERGROUND SERVICE**




WITH SAFETY SWITCH  
FRONT VIEW  
**SERVICE SUPPORT TYPE SF (U) - UNDERGROUND SERVICE**




TOP VIEW  
**SERVICE SUPPORT TYPE SF (O) & SF (U)**




**POLE TOP PLATE**



**BASE PLATE DETAIL**



**BOTTOM OF POLE**



**HOOKED ANCHOR DETAIL**

**ELECTRICAL DETAILS  
SERVICE SUPPORT  
TYPES SF & SP  
ED(7)-14**

FILE: ed7-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
DIST	COUNTY	SHEET NO.		
SAT	BEXAR, ETC.	82		

DATE: 2/27/2024 11:39:41 AM  
 FILE: ed7-14.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:44 AM  
FILE: ed10-14.dgn

### TIMBER POLE (TP) SERVICE SUPPORT NOTES

1. Ensure electrical service support is a class 5 treated timber pole as per Item 627 "Treated Timber Poles." Embed timber pole to depth required in Item 627.
2. Conduit and electrical conductors attached to the electrical service pole and underground within 12 in. of service pole are not paid for directly but are subsidiary to the electrical service.
3. Install pole-top mounted photocell (T) on north side of pole, or in service enclosure (E) as required. See Electrical Service Data chart in plan set.
4. Gain pole as required to provide flat surface for each channel. Gain timber pole to  $\frac{3}{8}$  in. max. depth and  $1\frac{1}{8}$  in. max. height. Gain pole in a neat and workmanlike manner.
5. Mount meter and service equipment on stainless steel or galvanized channel (Unistrut, Kindorf, or equal). Provide channel sized 1 in. to  $3\frac{3}{4}$  in. maximum depth, and  $1\frac{1}{2}$  in. to  $1\frac{5}{8}$  in. maximum width. File smooth the cut ends of galvanized channel and paint with zinc rich paint before installing on pole. Secure each channel section to timber pole with two galvanized or SS lag bolts,  $\frac{1}{4}$  in. minimum diameter by  $1\frac{1}{2}$  in. minimum length. Use a galvanized or SS flat washer on each lag bolt. Do not stack channel.
6. When excess length must be trimmed from poles, trim from the top end only.

- 1 Class 5 pole, height as required
- 2 Service drop from utility company (attached below weatherhead)
- 3 Service conduit (RMC) and service entrance conductors - One Red, One Black, One White (See Electrical Service Data)
- 4 Safety switch (when required)
- 5 Meter (when required)
- 6 Service enclosure
- 7 6 AWG bare grounding electrode conductor in  $\frac{1}{2}$  in. PVC to ground rod - extend  $\frac{1}{2}$  in. PVC 6 in. underground.
- 8  $\frac{5}{8}$  in. x 8 ft. Copper clad ground rod - drive ground rod to a depth of 2 in. to 4 in. below grade.
- 9 RMC same size as branch circuit conduit.
- 10 See pole-top mounted photocell detail on ED(5).
- 11 When required by the serving utility provide bare 6 AWG copper conductor. Run wire from pole top to butt wrap or copper butt plate. Protect conductor with non-conductive material to a height of 8 ft. above finished grade.
- 12 When required by utility, cut top of pole at an angle to enhance rain run off.




SERVICE SUPPORT TYPE TP (O)


### GRANITE CONCRETE (GC) & OTHER CONCRETE (OC) NOTES

Ensure electrical service support structures bid as type Granite Concrete (GC) or Other Concrete (OC) meet the following requirements.


1. Provide GC and OC poles that meet the requirements of DMS 11080 "Electrical Services."
2. Provide prestressed concrete poles suitable for direct embedment into the ground without special foundations.
3. Verify poles are marked as required on DMS 11080. Location of marking should be approximately 4' above final grade. Use the two-point pickup locations when handling pole in horizontal position, and one-point pickup location for use in raising the pole to a vertical position. These marks are small but conspicuous.
4. Embed poles 42 in. or 10% of the length plus 2 ft., whichever is greater.
5. Ensure all installation details of services are in accordance with utility company specifications.
6. Install a one point rack or eye bolt bracket 6 inches to 12 inches below the weatherhead as an overhead service drop anchoring point for the electric utility.
7. Furnish and install galvanized or stainless steel channel strut  $1\frac{1}{2}$  in. or  $1\frac{5}{8}$  in. wide by 1 in. up to  $3\frac{3}{4}$  in. deep (Unistrut, Kindorf, B-line or equal). Attach channel strut with stainless steel concrete anchors (max. 1" depth), square U-bolts or back to back channel strut with long bolts, or other secure mounting as approved by the Engineer. Ensure bolts are galvanized in accordance with ASTM A153. Do not stack channel struts.
8. Backfill the holes thoroughly by tamping in 6 in. lifts. After tamping to grade, place additional backfill material in a 6 inch high cone around the pole to allow for settling. Use material equal in composition and density to the surrounding area. Backfilling will not be paid for directly but is subsidiary to various bid items.



CONCRETE SERVICE SUPPORT Overhead (O)



CONCRETE SERVICE SUPPORT Underground (U)



### DETAIL A









See Note 7. Before installing channel that has been cut, file sharp edges and paint with zinc-rich paint. Ensure there is no paint splatter on the pole.

					<b>Traffic Operations Division Standard</b>				
<b>ELECTRICAL DETAILS SERVICE SUPPORT TYPES GC, OC, &amp; TP</b>									
<b>ED(10)-14</b>									
FILE:	ed10-14.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0915	00	268	VARIOUS				
		DIST	COUNTY		SHEET NO.				
		SAT	BEXAR, ETC.		83				



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:47 AM  
 FILE: i+s(1)-15.dgn



**General Notes**

- Designed according to Sixth Edition 2013 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications.
- Unless otherwise noted, all parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."
- Deviation from the design criteria, values, and dimensions shown herein and on ITS(4), constitutes an alternative design and will require submission of shop drawings and calculations for approval, sealed by a Texas Professional Engineer.
- Direct substitution of twelve sided or round poles, matching the design criteria, values, and dimensions shown herein, require submission of shop drawings for approval to confirm design criteria and values on ITS(4) is met.
- Locate handholes opposite of the direction of travel.
- Appropriate number of anchor bolts for base plate determined by height of pole. See 'L' on sheet ITS(4).
- Location for ITS equipment mount may vary by device. Locate mid span handhole and pipe nipple to accommodate location for ITS equipment as identified in the plans or per manufacturer recommendations. Identify location for mid span handhole and pipe nipple on shop drawings for approval.

**Reference Notes:**

- See tables on Sheet ITS(4) for values of dimension variables.
- See lap joint note for 55' and 60' pole heights on ITS(4) at the bottom of each table.

Texas Department of Transportation

Traffic Operations Division Standard









**ITS POLE DETAILS OCTAGONAL POLE (EIGHT SIDED POLE)**

**ITS(1)-15**

FILE: i+s(1)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
DIST	COUNTY	SHEET NO.		
SAT	BEXAR, ETC.			<b>84</b>

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:39:51 AM  
FILE: i+s(2)-15.dgn



- General Notes**
- Designed according to Sixth Edition 2013 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications.
  - Unless otherwise noted, all parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing."
  - Deviation from the design criteria, values, and dimensions shown herein and on ITS(4), constitutes an alternative design and will require submission of shop drawings and calculations for approval, sealed by a Texas Professional Engineer.
  - Direct substitution of round poles, matching the design criteria, values, and dimensions shown herein, require submission of shop drawings for approval to confirm design criteria and values on ITS(4) is met.
  - Locate handholes opposite of the direction of travel.
  - Appropriate number of anchor bolts for base plate determined by height of pole. See 'L' on sheet ITS(4).
  - Location for ITS equipment mount may vary by device. Locate mid span handhole and pipe nipple to accommodate location for ITS equipment as identified in the plans or per manufacturer recommendations. Identify location for mid span handhole and pipe nipple on shop drawings for approval.
- Reference Notes:**
- See tables on Sheet ITS(4) for values of dimension variables.
  - See lap joint note for 55' and 60' pole heights on ITS(4) at the bottom of each table.


Texas Department of Transportation  
Traffic Operations Division Standard

## ITS POLE DETAILS DODECAHEDRAL POLE (TWELVE SIDED POLE) (ALTERNATIVE) ITS(2)-15


FILE: i+s(2)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	<b>85</b>	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:39:54 AM  
 FILE: ITS(3)-16.dgn




**Top and Bottom Template (Four Bolt)**  
Detail A




**Top and Bottom Template (Six Bolt)**  
Detail B




**Top and Bottom Template (Eight Bolt)**  
Detail C



**Foundation Details (Typical)**  
Elevation  
 Not to Scale



**Top and Bottom Template (Twelve Bolt)**  
Detail D



**Anchor Bolt Detail**  
Detail D

- General Notes:**
1. Drilled shaft concrete shall be Class "C" ( $f'c = 3,600$  PSI) in accordance with Item 416, "Drilled Shaft Foundations."
  2. Reinforcing bars shall be Grade 60 ( $F_y = 60$  KSI) and conform to ASTM A-615. All reinforcing shall conform to Item 440, "Reinforcing Steel."
  3. Provide ASTM A-36 steel for templates. Top and bottom templates need not be galvanized.
  4. Anchor bolts shall be rigidly held in position during concrete placement using steel templates at the top and bottom. Top templates shall remain in place until the concrete has cured in place beyond initial set time.
  5. Lubricate and tighten anchor bolts, when erecting pole, in accordance with Item 449, "Anchor Bolts."
  6. Anchor bolts shall conform to ASTM F1554 Grade 55, or ASTM A193 B7 with ASTM A194 Grade 2H or A563 heavy hex nuts with F436 washers. Galvanize a minimum of the top end thread length plus 6 inches for all anchor bolts unless otherwise noted. Exposed washers and exposed nuts shall be galvanized. All galvanizing shall be in accordance with Item 445, "Galvanizing."
  7. All vertical reinforcement shall be carried to the bottom of the drilled shaft.
  8. Place three flat turns of the spiral bar at the top and one flat turn at the bottom of the drilled shaft.
  9. Drilled shaft shall be measured by the linear foot and paid under Item 416, "Drill Shaft Foundations."
  10. If rock is encountered, the drilled shaft to extend a minimum of two diameters into solid rock.
  11. Location for conduit entering foundation may vary. Orient conduit entering foundation to coincide with location of ground boxes and primary ground rod.
  12. Bond anchor bolts to rebar with #2/0 AWG jumper and two mechanical connectors or by bending No. 3 bar on bottom template as shown and wire tightly with ten turns of No. 10 wire or one mechanical connector. Mechanical connectors shall be UL Listed for concrete encasement.

**Reference Notes:**

- ① See tables on Sheet ITS(4) for values of dimension variables.

**Texas Department of Transportation**  
 Traffic Operations Division Standard

**ITS POLE FOUNDATION DETAILS**

**ITS(3) - 16**

FILE: its(3)-16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
April 2016	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	86	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TABLE 1: ITS POLE - 90 MPH (W/ 2 SOLAR PANELS) ④**

POLE TYPE	POLE HEIGHT (FT)	POLE SHAFT ① ⑩				BASE PLATE ①					TOP PLATE ②	ANCHOR BOLT ③					FOUNDATION ③			
		BOTTOM OUTSIDE DIA. (IN)	TOP OUTSIDE DIA. (IN)	WALL THICKNESS (IN)	INSIDE DIA. (IN)	OUTSIDE DIA. (IN)	BOLT CIRCLE DIA. (IN)	BOLT HOLE DIA. (IN)	THICKNESS (IN)	OUTSIDE DIA. (IN)	DIA. (IN)	NO. OF BOLTS	LENGTH OF BOLT MIN. (IN)	TEMPLATE INSIDE DIA. (IN)	TEMPLATE OUTSIDE DIA. (IN)	TEMPLATE WIDTH (IN)	DRILL SHAFT DEPTH - TEXAS CONE PENETROMETER (N - BLOWS/FT.) (SEE NOTE 5)			DRILLED SHAFT DIA. (IN)
		'A'	'B'	'C'	'D'	'E'	'F'	'G'	'H'	'I'	'J'	'K'	'L'	'M'	'N'	'O'	'P'	N = 10	N = 15	N = 40
8 SIDED	20	10	8	1/2	10-1/16	21	16	1-1/4	1-1/2	9	1	4	29	14	18	2	12	11	10	36
	30	13	9	1/2	13-1/16	24	19	1-9/16	1-1/2	10	1-1/4	4	35	16-1/2	21-1/2	2-1/2	15	13	10	36
	40	15	9	1/2	15-1/16	26	21	1-9/16	1-1/2	10	1-1/4	6	35	18-1/2	23-1/2	2-1/2	17	14	11	42
	45	16	10	1/2	16-1/16	27	22	1-9/16	1-1/2	11	1-1/4	6	35	19-1/2	24-1/2	2-1/2	18	16	12	42
	50	17	10	1/2	17-1/16	28	23	1-9/16	1-1/2	11	1-1/4	6	35	20-1/2	25-1/2	2-1/2	19	16	12	42
	55 ⑦	19	11	5/8	19-1/16	30	25	1-13/16	2	12	1-1/2	6	40	22	28	3	21	18	13	42
60 ⑦	20	11	5/8	20-1/16	31	26	1-13/16	2	12	1-1/2	6	40	23	29	3	21	19	14	48	

**TABLE 2: ITS POLE - 110 MPH (W/ 2 SOLAR PANELS) ④**

POLE TYPE	POLE HEIGHT (FT)	POLE SHAFT ① ⑩				BASE PLATE ①					TOP PLATE ②	ANCHOR BOLT ③					FOUNDATION ③			
		BOTTOM OUTSIDE DIA. (IN)	TOP OUTSIDE DIA. (IN)	WALL THICKNESS (IN)	INSIDE DIA. (IN)	OUTSIDE DIA. (IN)	BOLT CIRCLE DIA. (IN)	BOLT HOLE DIA. (IN)	THICKNESS (IN)	OUTSIDE DIA. (IN)	DIA. (IN)	NO. OF BOLTS	LENGTH OF BOLT MIN. (IN)	TEMPLATE INSIDE DIA. (IN)	TEMPLATE OUTSIDE DIA. (IN)	TEMPLATE WIDTH (IN)	DRILL SHAFT DEPTH - TEXAS CONE PENETROMETER (N - BLOWS/FT.) (SEE NOTE 5)			DRILLED SHAFT DIA. (IN)
		'A'	'B'	'C'	'D'	'E'	'F'	'G'	'H'	'I'	'J'	'K'	'L'	'M'	'N'	'O'	'P'	N = 10	N = 15	N = 40
8 SIDED	20	10	8	1/2	10-1/16	21	16	1-1/4	1-1/2	9	1	4	29	14	18	2	14	12	10	36
	30	13	9	1/2	13-1/16	24	19	1-9/16	1-3/4	10	1-1/4	6	35	16-1/2	21-1/2	2-1/2	18	15	11	36
	40	15	9	1/2	15-1/16	25	21	1-9/16	1-3/4	10	1-1/4	6	35	18-1/2	23-1/2	2-1/2	20	17	12	42
	45	16	10	1/2	17-1/16	27	22	1-9/16	1-3/4	11	1-1/4	8	35	19-1/2	24-1/2	2-1/2	21	18	13	42
	50	17	10	1/2	18-1/16	28	23	1-9/16	1-3/4	11	1-1/4	8	35	20-1/2	25-1/2	2-1/2	22	19	14	42
	55 ⑦	19	11	5/8	19-1/16	30	25	1-9/16	2	12	1-1/4	8	35	22-1/2	27-1/2	2-1/2	24	20	14	42
60 ⑦	20	11	5/8	20-1/16	31	26	1-13/16	2	12	1-1/2	6	40	23	29	3	25	21	15	48	

**TABLE 3: ITS POLE - 130 MPH (W/ 1 SOLAR PANEL) ⑤**

POLE TYPE	POLE HEIGHT (FT)	POLE SHAFT ① ⑩				BASE PLATE ①					TOP PLATE ②	ANCHOR BOLT ③					FOUNDATION ③			
		BOTTOM OUTSIDE DIA. (IN)	TOP OUTSIDE DIA. (IN)	WALL THICKNESS (IN)	INSIDE DIA. (IN)	OUTSIDE DIA. (IN)	BOLT CIRCLE DIA. (IN)	BOLT HOLE DIA. (IN)	THICKNESS (IN)	OUTSIDE DIA. (IN)	DIA. (IN)	NO. OF BOLTS	LENGTH OF BOLT MIN. (IN)	TEMPLATE INSIDE DIA. (IN)	TEMPLATE OUTSIDE DIA. (IN)	TEMPLATE WIDTH (IN)	DRILL SHAFT DEPTH - TEXAS CONE PENETROMETER (N - BLOWS/FT.) (SEE NOTE 5)			DRILLED SHAFT DIA. (IN)
		'A'	'B'	'C'	'D'	'E'	'F'	'G'	'H'	'I'	'J'	'K'	'L'	'M'	'N'	'O'	'P'	N = 10	N = 15	N = 40
8 SIDED	20	10	8	1/2	10-1/16	21	16	1-9/16	1-3/4	9	1-1/4	4	35	13-1/2	18-1/2	2-1/2	16	14	10	36
	30	13	9	1/2	15-1/16	24	19	1-9/16	1-3/4	10	1-1/4	6	35	16-1/2	21-1/2	2-1/2	18	16	11	36
	40	15	9	1/2	15-1/16	26	21	1-9/16	1-3/4	10	1-1/4	6	35	18-1/2	23-1/2	2-1/2	21	18	13	42
	45	16	10	1/2	16-1/16	27	22	1-9/16	1-3/4	11	1-1/4	8	35	19-1/2	24-1/2	2-1/2	23	19	14	42
	50	17	10	1/2	17-1/16	28	23	1-9/16	2	11	1-1/2	8	40	20	26	3	24	20	14	42
	55 ⑦	19	11	5/8	19-1/16	30	25	1-13/16	2	12	1-1/2	8	40	22	28	3	27	22	15	42
60 ⑦	20	11	5/8	20-1/16	31	26	1-13/16	2	12	1-1/2	8	40	23	29	3	28	23	16	48	

**TABLE 4: ITS POLE WITH STIFFENERS - 90 MPH (W/ 4 SOLAR PANELS) ⑧**

POLE TYPE	POLE HEIGHT (FT)	POLE SHAFT ①				BASE PLATE ①					TOP PLATE ②	ANCHOR BOLT ③					FOUNDATION ③			
		BOTTOM OUTSIDE DIA. (IN)	TOP OUTSIDE DIA. (IN)	WALL THICKNESS (IN)	INSIDE DIA. (IN)	OUTSIDE DIA. (IN)	BOLT CIRCLE DIA. (IN)	BOLT HOLE DIA. (IN)	THICKNESS (IN)	OUTSIDE DIA. (IN)	DIA. (IN)	NO. OF BOLTS	LENGTH OF BOLT MIN. (IN)	TEMPLATE INSIDE DIA. (IN)	TEMPLATE OUTSIDE DIA. (IN)	TEMPLATE WIDTH (IN)	DRILL SHAFT DEPTH - TEXAS CONE PENETROMETER (N - BLOWS/FT.) (SEE NOTE 5)			DRILLED SHAFT DIA. (IN)
		'A'	'B'	'C'	'D'	'E'	'F'	'G'	'H'	'I'	'J'	'K'	'L'	'M'	'N'	'O'	'P'	N = 10	N = 15	N = 40
8 SIDED	30	13	9	3/8	13-1/16	28	22	1-1/4	1-3/4	10	1	8	29	20	24	2	17	15	11	42
	40	15	9	1/2	15-1/16	30	24	1-1/4	2	10	1	8	29	22	26	2	20	17	12	42
	45	16	10	1/2	16-1/16	31	25	1-9/16	2	11	1-1/4	8	35	22-1/2	27-1/2	2-1/2	21	18	13	42
	50	17	10	1/2	17-1/16	32	26	1-9/16	2	11	1-1/4	8	35	23-1/2	28-1/2	2-1/2	21	18	13	42
	55 ⑦	19	11	5/8	19-1/16	34	27	1-9/16	2	12	1-1/4	12	35	24-1/2	29-1/2	2-1/2	21	18	13	48
60 ⑦	20	12	5/8	20-1/16	35	28	1-9/16	2	13	1-1/4	12	35	25-1/2	30-1/2	2-1/2	22	19	14	48	

**TABLE 5: ITS POLE WITH STIFFENERS - 110 MPH (W/ 4 SOLAR PANELS) ⑧**

POLE TYPE	POLE HEIGHT (FT)	POLE SHAFT ①				BASE PLATE ①					TOP PLATE ②	ANCHOR BOLT ③					FOUNDATION ③			
		BOTTOM OUTSIDE DIA. (IN)	TOP OUTSIDE DIA. (IN)	WALL THICKNESS (IN)	INSIDE DIA. (IN)	OUTSIDE DIA. (IN)	BOLT CIRCLE DIA. (IN)	BOLT HOLE DIA. (IN)	THICKNESS (IN)	OUTSIDE DIA. (IN)	DIA. (IN)	NO. OF BOLTS	LENGTH OF BOLT MIN. (IN)	TEMPLATE INSIDE DIA. (IN)	TEMPLATE OUTSIDE DIA. (IN)	TEMPLATE WIDTH (IN)	DRILL SHAFT DEPTH - TEXAS CONE PENETROMETER (N - BLOWS/FT.) (SEE NOTE 5)			DRILLED SHAFT DIA. (IN)
		'A'	'B'	'C'	'D'	'E'	'F'	'G'	'H'	'I'	'J'	'K'	'L'	'M'	'N'	'O'	'P'	N = 10	N = 15	N = 40
8 SIDED	30	13	9	1/2	13-1/16	28	22	1-9/16	2-1/4	10	1-1/4	8	35	19-1/2	24-1/2	2-1/2	20	17	12	42
	40	16	10	1/2	16-1/16	31	25	1-9/16	2-1/4	11	1-1/4	8	35	22-1/2	27-1/2	2-1/2	24	20	14	42
	45	17	11	1/2	17-1/16	32	26	1-9/16	2-1/4	12	1-1/4	8	35	23-1/2	28-1/2	2-1/2	25	21	15	42
	50	18	11	1/2	18-1/16	32	26	1-13/16	2-1/2	12	1-1/2	8	40	23	29	3	25	21	15	48
	55 ⑦	19	11	5/8	19-1/16	34	27	1-9/16	2-1/4	12	1-1/4	12	35	24-1/2	29-1/2	2-1/2	24	21	15	48
60 ⑦	20	12	5/8	20-1/16	35	28	1-9/16	2-1/4	13	1-1/4	12	35	25-1/2	30-1/2	2-1/2	25	22	15	48	

**TABLE 6: ITS POLE WITH STIFFENERS - 130 MPH (W/ 3 SOLAR PANELS) ⑨**

POLE TYPE	POLE HEIGHT (FT)	POLE SHAFT ①				BASE PLATE ①					TOP PLATE ②	ANCHOR BOLT ③					FOUNDATION ③			
		BOTTOM OUTSIDE DIA. (IN)	TOP OUTSIDE DIA. (IN)	WALL THICKNESS (IN)	INSIDE DIA. (IN)	OUTSIDE DIA. (IN)	BOLT CIRCLE DIA. (IN)	BOLT HOLE DIA. (IN)	THICKNESS (IN)	OUTSIDE DIA. (IN)	DIA. (IN)	NO. OF BOLTS	LENGTH OF BOLT MIN. (IN)	TEMPLATE INSIDE DIA. (IN)	TEMPLATE OUTSIDE DIA. (IN)	TEMPLATE WIDTH (IN)	DRILL SHAFT DEPTH - TEXAS CONE PENETROMETER (N - BLOWS/FT.) (SEE NOTE 5)			DRILLED SHAFT DIA. (IN)
		'A'	'B'	'C'	'D'	'E'	'F'	'G'	'H'	'I'	'J'	'K'	'L'	'M'	'N'	'O'	'P'	N = 10	N = 15	N = 40
8 SIDED	30	13	9	1/2	13-1/16	28	22	1-9/16	2-1/2	10	1-1/4	8	35	19-1/2	24-1/2	2-1/2	23	19	14	42
	40	16	10	1/2	16-1/16	31	25	1-9/16	2-1/2	11	1-1/2	8	40	22	28	3	25	21	14	42
	45	17	11	1/2	17-1/16	32	26	1-13/16	2-1/2	12	1-1/2	8	40	23	29	3	26	22	16	48
	50	18	11	1/2	18-1/16	33	27	1-13/16	2-1/2	12	1-1/2	8	40	24	30	3	27	23	16	48
	55 ⑦	19	11	5/8	19-1/16	34	27	1-9/16	2-1/4	12	1-1/4	12	35	24-1/2	29-1/2	2-1/2	26	22	16	48
60 ⑦	20	12	5/8	20-1/16	35	28	1-9/16	2-1/4	13	1-1/4	12	35	25 1/2	30 1/2	2-1/2	27	23	16	48	

**General Notes:**

- Designed according to Sixth Edition 2013 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications thereto.
- Table 1 and Table 4 design wind speed equals 90 MPH (3-Second Wind Gusts) with a 1.14 gust factor. A wind importance factor of 1.00 is applied to adjust the wind speed to a 50 year recurrence interval at 33 FT above the ground for Exposure C category in accordance with TxDOT WV&I2(LTS2013). Design values listed in the table allow the base of the pole to be elevated above the surrounding ground level no more than 20 FT.
- Table 2 and Table 5 design wind speed equals 110 MPH (3-Second Wind Gusts) with a 1.14 gust factor. A wind importance factor of 1.00 is applied to adjust the wind speed to a 50 year recurrence interval at 33 FT above the ground for Exposure C category in accordance with TxDOT WV&I2(LTS2013). Design values listed in the table allow the base of the pole to be elevated above the surrounding ground level no more than 20 FT.
- Table 3 and Table 6 design wind speed equals 130 MPH (3-Second Wind Gusts) with a 1.14 gust factor. A wind importance factor of 1.00 is applied to adjust the wind speed to a 50 year recurrence interval at 33 FT above the ground for Exposure C category in accordance with TxDOT WV&I2(LTS2013). Design values listed in the table allow the base of the pole to be elevated above the surrounding ground level no more than 20 FT.
- Recommended embedment lengths are for information purposes only. Foundation embedment depth is based off Texas Cone Penetrometer Value N = 10 blows/ft. for soft soils and up to 40 blows/ft. for hard soils. Foundation lengths shall be as shown on the plans, or as directed by the Engineer. Foundations will be paid for under Item 416, "Drilled Shaft Foundations" unless otherwise shown on the plans.


- Deviation from the design criteria and values contained in the tables above constitute and alternative design and will require submission of shop drawings and calculations for approval, sealed by a Texas Professional Engineer.
- 12-sided or round poles as a direct substitution for 8-sided and round poles as a direct substitution for 12-sided poles, meeting the design criteria and values contained in the tables above, require submission of shop drawings for approval.

**Reference Notes**


- See the following ITS Pole Standard sheets:
  - 8-sided Pole - ITS(1)
  - 12-sided Pole - ITS(2)
- Provision for 2" Dia. opening in top plate for poles requiring cameras mounted on top.
  - See ITS Pole Mounting Details - ITS(6)
- See ITS Pole Foundation Details - ITS(3)
- Designed to support the following:
  - Two Type 3 ITS pole mounted cabinets (280 LBS/EA and EPA = 14.50 sq. ft. per cabinet). See ITS(16).
  - Two 250 W (50 LBS/EA and EPA = 30.70 sq. ft. per panel) solar panels (see ITS(24) "Solar Panel Matrix Table")
  - Combined ITS equipment dead load of 170 LBS with an EPA = 6 sq. ft.
- Designed to support the following:
  - Two Type 3 ITS pole mounted cabinets (280

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:40:00 AM  
 FILE: its(4a)-15.dgn



8-sided Pole Base Plate Detail




12-sided Pole Base Plate Detail

General Notes:

1. Steel stiffening plates shall conform to ASTM A36.
2. Make all welds conform to Item 441, "Steel Structures."
3. Galvanize in accordance with Item 445, "Galvanizing" unless otherwise noted.
4. Submit shop drawings detailing stiffening plate orientation along with ITS equipment intended for mounting for review and approval prior to fabrication.
5. HH = Handhole
6. Ts = Thickness


Reference Notes:

- ① Complete Joint Penetration Weld per AWS
- ② Wrap Fillet Weld Around Tip of Stiffener




Stiffening Plate Detail

Not to Scale



Stiffening Detail - Elevation View

Not to Scale



Stiffening Detail - Front View

Not to Scale




ITS POLE STIFFENER PLATE DETAILS

ITS(4A)-15


FILE: its(4a)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	88	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:40:03 AM  
 FILE: ITS(5)-15.dgn




**ITS Pole with Cabinet**




**Detail A**  
Not to Scale

**General Notes:**

- Provide lightning protection using air terminals on structures utilizing the rolling sphere method. Provide lightning protection system consisting of air terminals, down conductor, and grounding system installed in accordance with NFPA 780 and tested in accordance with IEEE 142. Meet the following requirements:
  - A. Position - in center of least utilized field of view.
  - B. Height - camera equipment to be within 45 degree protective zone of air terminal.
  - C. Material - 1/2" ETP alloy 110 copper air terminal (Class II)
  - D. Clearance - 24" minimum height above highest point of ITS equipment.
  - E. Bonding - attach air terminal to bracket by exothermic weld or with approved clamping.
  - F. Structure wind rating in accordance with TxDOT WV & IZ (LTS2013).
  - G. Galvanize air terminal bracket in accordance with Item 445, "Galvanizing."
- Alternative orientation for air terminal and pole mounted cabinet due to project specific needs to be indicated on the plans and detailed in shop drawing submittal for approval.
- Weld air terminal bracket to ITS pole in accordance with Item 448 "Structural Field Welding." Bracket may be welded by the fabricator in the shop prior to delivery. A bolted connection for the air terminal bracket is acceptable in lieu of a welded connection with approval by the Engineer and detailed in the shop drawings.



**Section A-A**  
Not to Scale



**Detail B**  
Not to Scale

**ITS POLE AIR TERMINAL DETAILS**

**ITS(5) - 15**


FILE: ITS(5)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	89	






DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:40:08 AM  
 FILE: its(7)-15.dgn




Top View  
Riprap - Non-Sloped Conditions




Top View  
Step and Riprap - Sloped Conditions

**General Notes:**

1. For non-sloped grassy areas, an 8' x 8' concrete riprap apron shall be poured around ITS pole foundations (see detail on this sheet), estimated at 1.25 CY per site, paid for under Item 432 "Riprap."
2. For sloped grassy areas, a concrete "step" (for maintenance personnel to access cabinet) shall be poured as part of the riprap apron. The step shall vary in height depending on slope, but shall extend 6' horizontally from ITS pole drilled shaft foundation and be the same width as riprap apron (8'). Step shall be poured at same time as riprap apron (see detail on this sheet). Any additional concrete necessary to fabricate step (over and above the 1.25 CY) shall be considered subsidiary to the various bid items and no direct payment shall be made.
3. For sloped areas where riprap exists, a 6' (horizontal from drilled shaft foundation) x 4' wide step shall be installed (see detail this sheet). Concrete for step shall be considered subsidiary to the various bid items and no direct payment shall be made.
4. Cabinet orientation may vary depending on field conditions or project constraints. Accommodate configuration of platform according to cabinet orientation.
5. Slopes greater than a 2:1 or when 3'-0" Max. step wall height is exceeded, an alternative design with safety railing is required and shall be detailed in the shop drawings for approval.



Elevation View  
Riprap Apron Detail - Non-Sloped Conditions



Elevation View  
Riprap Apron/Step Detail - Sloped Conditions  
 (Slopes Exceeding 4:1)




**ITS POLE  
 RIPRAP DETAILS**

**ITS(7)-15**


FILE: its(7)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	91	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



DATE: 2/27/2024 11:40:10 AM  
 FILE: i-ts(14)-15.dgn




**Pole Mounted Cabinet - Type 1 Front View**  
 Not to Scale




**Pole Mounted Cabinet - Type 1 Side View**  
 Not to Scale



**Mounting Bracket Detail**  
 Not to Scale



**Interior - Type 1 Without 19" EIA Rack - Front View**  
 Not to Scale



**Interior - Type 1 With 19" EIA Rack - Front View**  
 Not to Scale

Typical Equipment Layout Legend	
Example Equipment	
①	CCTV Interface Panel, Radar Vehicle Sensing Device (RVSD) Equipment, Environmental Sensor Station (ESS) Equipment, Bluetooth Equipment, or ITS Radio Equipment (See General Note 1)
②	Ethernet Switch, Video Encoder, Terminal Server, Fiber Optic Transceivers, or Media Conversion Equipment (See General Note 1)
③	Power Distribution Assembly, Service Entrance Breakers, Primary AC Power, Auxiliary Power Strip, Ground Bus Bar Surge Protection Equipment

**General Notes:**

- Layout of hardware equipment and configuration shown is diagrammatic in nature and intended to represent a preferred Type 1 pole mounted cabinet setup. Hardware needed for each Type 1 cabinet varies and not all cabinet equipment may be shown. The contractor will be responsible for configuring cabinets with all appropriate ITS hardware and power supplies in accordance with the plans and specifications. The contractor may alter the cabinet configuration shown to maximize space and ensure easy access for maintenance.
- Mount cabinet as detailed on ITS(14) or ITS(17). Orientation of cabinet on ITS pole may vary depending on field conditions. Mount the pole mounted cabinet to the backside of the ITS pole, to allow maintenance personnel to access the cabinet while being able to view oncoming traffic.
- For ITS pole sites located on slopes greater than 4H:1V, mount the cabinet to the backside of the ITS pole as detailed on ITS(7). Mounting height to accommodate maintenance pad for easy access.
- All dimensions are approximate and represent minimum cabinet dimensions.
- Provide conduit entrances at the bottom of the cabinet.
- Paid under Special Specification "ITS Pole with Cabinet" (Configuration 1) without 19" EIA rack. Paid under Special Specification "ITS Pole with Cabinet" (Configuration 2) with 19" EIA rack.



**Orientation of Type 1 Cabinet on ITS Pole (Typical)**  
 Not to Scale



**ITS POLE MOUNTED CABINET TYPE 1 DETAILS**


**ITS(14)-15**

FILE: i-ts(14)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	92	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:40:13 AM  
 FILE: ITS(15)-15.dgn




**Pole Mounted Cabinet - Type 2 Front View**

Not to Scale



**Pole Mounted Cabinet - Type 2 Side View**


Not to Scale



Note: ITS Pole May be Round, Octagonal (8 Sided), or Dodecahedron (12 Sided). See ITS(1), and ITS(2) for Details.


**Mounting Bracket Detail**

Not to Scale



**Interior - Type 2 Without 19" EIA Rack - Front View**

Not to Scale





**Interior - Type 2 With 19" EIA Rack - Front View**

Not to Scale

Typical Equipment Layout Legend	
Example Equipment	
①	CCTV Interface Panel, Radar Vehicle Sensing Device (RVSD) Equipment, DMS/LCS Controller, Environmental Sensor Station (ESS) Equipment, Bluetooth Equipment, or ITS Radio Equipment (See General Note 1)
②	Ethernet Switch, Video Encoder, Terminal Server, Fiber Optic Transceivers, or Media Conversion Equipment (See General Note 1)
③	Power Distribution Assembly, Service Entrance Breakers, Primary AC Power, Auxiliary Power Strip, Ground Bus Bar, Surge Protection Equipment

**General Notes:**

- Layout of hardware equipment and configuration shown is diagrammatic in nature and intended to represent a preferred Type 2 pole mounted cabinet setup. Hardware needed for each Type 2 cabinet varies and not all cabinet equipment may be shown. The contractor will be responsible for configuring cabinets with all appropriate ITS hardware and power supplies in accordance with the plans and specifications. The contractor may alter the cabinet configuration shown to maximize space and ensure easy access for maintenance.
- Mount cabinet as detailed on ITS(15) or ITS(17). Orientation of cabinet on ITS pole may vary depending on field conditions. Mount the pole mounted cabinet to the backside of the ITS pole, to allow maintenance personnel to access the cabinet while being able to view oncoming traffic.
- For ITS pole sites located on slopes greater than 4H:1V, mount the cabinet to the backside of the ITS pole as detailed on ITS(7). Mounting height to accommodate maintenance pad for easy access.
- All dimensions are approximate and represent minimum cabinet dimensions.
- Provide conduit entrances at the bottom of the cabinet.
- Paid under Special Specification "ITS Pole with Cabinet" (Configuration 1) without 19" EIA rack.  
 Paid under Special Specification "ITS Pole with Cabinet" (Configuration 2) with 19" EIA rack.



**Orientation of Type 2 Cabinet on ITS Pole (Typical)**

Not to Scale

Texas Department of Transportation  
 Traffic Operations Division Standard


## ITS POLE MOUNTED CABINET TYPE 2 DETAILS

### ITS(15)-15


FILE: its(15)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
DIST	COUNTY		SHEET NO.	
SAT	BEXAR, ETC.		93	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 2/27/2024 11:40:15 AM  
 FILE: i-ts(17)-15.dgn




**ITS Pole Mount**  
Not to Scale




**OSB Truss Mount**  
Not to Scale




**Retaining Wall Mount**  
Not to Scale



**Section A-A**  
Not to Scale



**Detail C-1 and C-2**  
Not to Scale



**Mounting Bracket Detail**  
Not to Scale

**General Notes:**

1. Mount cabinet as detailed on ITS(14), ITS(15), ITS(16), or ITS(17). Orientation of cabinet on ITS pole may vary depending on field conditions. Mount the pole mounted cabinet to the backside of the ITS pole, to allow maintenance personnel to access the cabinet while being able to view oncoming traffic.
2. For ITS pole sites located on slopes greater than 4V:1H, mount the cabinet to the backside of the ITS pole as detailed on ITS(7). Mounting height to accommodate maintenance pad for easy access.
3. All dimensions are approximate and represent minimum dimensions.
4. Provide conduit entrances at the bottom of the cabinet.



		<b>Traffic Operations Division Standard</b>	
<h2>ITS POLE MOUNTED CABINET MISC. MOUNTING DETAILS</h2> <h3>ITS(17)-15</h3>			
FILE: i-ts(17)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT	REVISIONS	CONT	SECT
0915	00	268	VARIOUS
DIST	COUNTY	SHEET NO.	
SAT	BEXAR, ETC.	94	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:40:18 AM  
 FILE: ITS(18)-15.dgn

**General Notes:**

1. Grounding System:
  - A. Description:
    1. Provide ground system consisting of copper wires, ground rods, and concrete-encased grounding electrodes (Ufers), of the configuration shown to minimize potential gradient irregularities, drain leakage, and fault currents to earth.
  - B. Performance:
    1. Provide a grounding system, consisting of a minimum one ground rod, having a resistance not greater than 5 Ohms to ground. Additional ground rods may be added to the system to achieve less than 5 Ohms resistance.
  - C. Design Criteria:
    1. The combined ground resistance of separate systems bonded together below grade may be used to meet the specified ground resistance, but the minimum number of rods indicated shall still be provided.
    2. Measure the resistance of systems requiring separate ground resistance separately before bonding below grade.
    3. Only provide UL-approved materials listed for grounding systems.
    4. Do not combine materials that can form an electrolytic couple that will accelerate corrosion in the presence of moisture, unless moisture is permanently excluded from the junction of such materials.
    5. Submit product data for the materials and products used to perform the work of this section.
  - D. Materials:
    1. Conductors:
      - a. Bare Ground Conductor:
        - 1) For No. 8 AWG or larger bare ground wire sizes, provide soft drawn copper, Class A or Class B, stranded wire meeting the requirements of ASTM B 8.
      2. Ground Compression Connectors:
        - a. Provide molds, thermite packages, and other material for ground compression connectors that are full-rated to carry 100% of the cable rating and which meet IEEE 837.
          - 1) Provide the compression materials from a single manufacturer throughout the project.
          - 2) Provide the items necessary for connecting cable to ground rods.
      3. Ground Rods:
        - a. Provide copper-clad steel ground rods conforming to the requirements specified in UL 467.
          - 1) Diameter: 5/8 in.
          - 2) Length: 10 Ft.
  2. Installation:
    - A. Install grounding components and systems in accordance with the requirements specified in UL 467, IEEE 81, and IEEE 142.
    - B. System Grounding:
      1. Ground Rods:
        - a. Drive ground rods into the ground until the tops of the rods are approximately 18 in. below finished grade.
        - b. If multiple ground rods are needed to meet the minimum resistance of 5 Ohms, space ground rods as evenly as possible, at least 6 feet apart, and so conductors will be connected below grade.
      2. Conductors:
        - a. Provide minimum No. 4 AWG ground wire for system and equipment grounding.
        - b. Using suitable fasteners, securely attach exposed ground wires to structural supports at not more than 2 ft. intervals, where applicable.
        - c. Bends in ground wires greater than 45 degrees are unacceptable.
      3. Cable Connections:
        - a. Use approved exothermic-welded connections for conductor splices and connections between conductors and other components.
    3. Testing:
      - A. Resistance Test:
        1. Test Procedure:
          - a. The ground-resistance measurements of each ground Rod shall be taken.
            - 1) The resistance to ground shall be measured in accordance with the fall-of-potential method specified in IEEE 81 and IEEE 142.
            - 2) Ground-resistance measurements shall be made in normally dry weather, not less than 48 hours after rainfall, and with the ground under test isolated from other grounds.
          - b. Test reports shall be prepared that indicate the location of the ground rod, the grounding system, and the resistance and soil conditions at the time the test was performed.
        2. Acceptance Criteria:
          - a. The grounding system must have a resistance not greater than 5 Ohms.
          - b. Do not energize any part of the electrical distribution system prior to the resistance testing of that system's ground rods and grounding system, and submission of the test results for approval.
        3. Inspections:
          - a. Prepare and submit as-built record drawings of the grounding system as installed and test reports for approval.



				<b>Traffic Operations Division Standard</b>	
<h2>ITS CABINET GROUNDING DETAILS</h2>					
<h3>ITS(18)-15</h3>					
FILE: ITS(18)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT June 2015	CONT: 0915	SECT: 00	JOB: 268	HIGHWAY: VARIOUS	
REVISIONS		DIST: SAT	COUNTY: BEXAR, ETC.	SHEET NO.: 95	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024 11:40:20 AM  
 FILE: i-ts(19)-17.dgn


**General Notes:**

1. Grounding System:
  - A. Description:
    1. Provide ground system consisting of copper wires, ground rods, and concrete-encased grounding electrodes (Ufers), of the configuration shown to minimize potential gradient irregularities, drain leakage, and fault currents to earth.
  - B. Performance:
    1. Provide a grounding system, consisting of a minimum one ground rod, having a resistance not greater than 5 Ohms to ground. Provide up to 2 additional supplemental ground rods if necessary to achieve a resistance not greater than 5 Ohms to ground. If a total of 3 ground rods is needed then install as as part of a ground ring.
    2. If a ground ring is required, provide a minimum conductor length of 20 ft. placed at a minimum depth of 30 in..
  - C. Design Criteria:
    1. The grounding system of the ITS pole may be bonded below grade to the grounding systems of other nearby equipment to meet the specified grounding resistance. A minimum of one ground rod for the ITS pole is still required.
    2. Separately measure the grounding resistance of each system before bonding together below grade.
    3. Only provide UL-approved materials listed for grounding systems.
    4. Do not combine materials that can form an electrolytic couple that will accelerate corrosion in the presence of moisture, unless moisture is permanently excluded from the junction of such materials.
    5. Submit product data for the materials and products used to perform the work of this section.
  - D. Materials:
    1. Conductors:
      - a. Bare Ground Conductor:
        - 1) Provide prequalified copper conductors appearing on the Material Producers List according to Item 618.
      2. Ground Compression Connectors:
        - a. Provide molds, thermite packages, and other material for exothermic welding of grounding connections.
        - b. Provide listed compression connectors fully rated to carry 100% of the cable rating and that meet IEEE 837. Provide compression materials from a single manufacturer throughout the project.
      3. Ground Rods:
        - a. Provide copper-clad steel ground rods conforming to the requirements specified in DMS 11040.
          - 1) Diameter: 5/8 in.
          - 2) Length: 10 ft.
  2. Installation:
    - A. Install grounding components and systems in accordance with the requirements specified in IEEE 142.
    - B. System Grounding:
      1. Ground Rods:
        - a. Drive ground rods into the ground until the tops of the rods are a minimum of 18 in. below finished grade.
        - b. If multiple ground rods are needed to meet the minimum resistance of 5 Ohms, space ground rods as evenly as possible, at least 6 feet apart, so conductors will be connected below grade.
      2. Conductors:
        - a. Provide minimum No. 2/0 AWG ground wire for lightning protection from air terminal.
        - b. Provide minimum No. 4 AWG ground wire for system and equipment grounding.
        - c. Using suitable fasteners, securely attach exposed ground wires to structural supports at not more than 2 ft. intervals, where applicable.
        - d. Bends in ground wires greater than 45 degrees are unacceptable.
      3. Cable Connections:
        - a. Use exothermic-welded connections or listed compression connectors for conductor splices and connections between conductors and other components.
  3. Testing:
    - A. Resistance Test:
      1. Test Procedure:
        - a. The ground-resistance measurements of each ground Rod shall be taken.
          - 1) The resistance to ground shall be measured in accordance with the fall-of-potential method specified in IEEE 81 and IEEE 142.
          - 2) Ground-resistance measurements shall be made in normally dry weather, not less than 48 hours after rainfall, and with the ground under test isolated from other grounds.
        - b. Test reports shall be prepared that indicate the location of the ground rod, the grounding system, and the resistance and soil conditions at the time the test was performed.
      2. Acceptance Criteria:
        - a. The grounding system must have a resistance not greater than 5 Ohms.
        - b. Do not energize any part of the electrical distribution system prior to the resistance testing of that system's ground rods and grounding system, and submission of the test results for approval.
      3. Inspections:
        - a. Prepare and submit as-built record drawings of the grounding system as installed and test reports for approval.



**Grounding System**

Not to Scale



**Grounding System with Pole Mounted Cabinet**


Not to Scale

**Reference Notes:**


- ① Bond anchor bolts to rebar with #2/0 AWG jumper and two mechanical connectors or by bending No. 3 bar on bottom template as shown and wire tightly with ten turns of No. 10 wire or one mechanical connector. Mechanical connectors shall be UL Listed for concrete encasement.
- ② Cut PVC approximately 1 in. above concrete and install bell or bushing. Align conduit as close as possible to point of attachment to base plate to minimize bends in #2/0 wire.
- ③ Bond grounding conductors via cadweld or mechanical connector, rated for size and number of conductors.
- ④ Provide and install a grounding type bushing on metal conduit terminations. Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor.

		<b>Traffic Operations Division Standard</b>	
<h2 style="margin: 0;">ITS POLE GROUNDING DETAILS</h2>			
<h3 style="margin: 0;">ITS(19)-17</h3>			
FILE: i-ts(19)-17.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT June 2015	CONT: 0915	SECT: 00	JOB: 268
7-17	REVISIONS	HIGHWAY: VARIOUS	
	DIST: SAT	COUNTY: BEXAR, ETC.	SHEET NO.: 96

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**Type 4 (Small) Cabinet**



**Type 5 (Medium) & Type 6 (Large) Cabinet**



**General Notes:**

1. Details of anchor bolt location to be furnished by the cabinet manufacturer. Size and length of anchor bolts shown in details may vary by manufacturer.
2. Modify concrete base dimensions to fit required cabinet type.
3. Ensure conduit area has gravel drain, 12" depth, coarse aggregate, grade No. 1.
4. All concrete to be Class "A" in accordance with Item 421.
5. Set the cabinet foundation level with the pavement surface, in unpaved area. The foundation shall be a minimum of 4" above surrounding grade, or as approved by the Engineer.
6. Furnish any additional concrete which may be necessary to stabilize foundation at unusual locations.
7. Foundation will be subsidiary to Special Specification "ITS Ground Mounted Cabinet."
8. Ground cabinet as required in cabinet specifications and as detailed on ITS(18) in accordance with the National Electric Code (NEC).
9. Treat cabinet foundation with moisture sealant.
10. Type 5 cabinet foundation will have a slightly larger foundation than Type 6. See foundation notes on details.
11. Drain pipe shall be screened for drainage portion below foundation in gravel.


<p>Texas Department of Transportation</p>		<p>Traffic Operations Division Standard</p>	
<h2>ITS GROUND MOUNTED CABINET FOUNDATION DETAILS</h2> <h3>ITS(21)-15</h3>			
FILE: its(21)-15.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT June 2015	CONT	SECT	JOB
REVISIONS	0915	00	268
DIST	COUNTY	SHEET NO.	
SAT	BEXAR, ETC.	97	

DATE: 2/27/2024 11:40:23 AM  
FILE: its(21)-15.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**Reinforcement Bar L**  
#4 Bar @ 12" Spacing



**Reinforcement Bar U**  
#4 Bar @ 6" Spacing



**Sloped Grade Cabinet**  
Side View



**Sloped Grade Cabinet**  
Front View

**General Notes:**

- Details of anchor bolt location to be furnished by the cabinet manufacturer. See ITS(21) for size and type of anchor bolts. May vary by manufacturer.
- Modify concrete base dimensions to fit required cabinet type.
- Ensure conduit area has gravel drain, 12" depth, coarse aggregate, Grade No. 1.
- All concrete to be Class "A" in accordance with Item 421.
- Set the cabinet foundation level with the pavement surface, in unpaved area. The foundation shall be a minimum of 6" above surrounding grade, or as approved by the Engineer.
- Furnish any additional concrete which may be necessary to stabilize foundation at unusual locations.
- Foundation will be considered subsidiary to Special Specification "ITS Ground Mounted Cabinet."
- Ground cabinet as required in cabinet specifications and as per National Electric Code (NEC).
- Treat cabinet foundation with moisture sealant.
- Type 5 cabinet foundation will have a slightly larger foundation than Type 6. See foundation notes on details.
- Drain pipe shall be screened for drainage portion below foundation in gravel.
- Pipe for pipe rail must conform to ASTM A53 GR B, or A500 GR B. Posts and plates must be ASTM A36. All steel components to be galvanized unless otherwise shown in plans.
- Pedestrian rail anchor bolts must be 3/8" diameter ASTM A307 Grade A bolts (or A36 threaded rods with one tack welded hex nut each) with one hex nut and one hardened steel washer at each bolt. Threaded rods may be 0.557" minimum diameter with rolled threads. Nuts must conform to A563 requirements.
- Exposed edges of pipe rail and pipe rail posts must be rounded or chamfered to approximately 1/16" by grinding. Provide an end cap at either end of pipe railing.
- Welded wire mesh not required in maintenance pad area when retaining wall rebar is integrated into maintenance pad.

Texas Department of Transportation  
Traffic Operations Division Standard

## ITS GROUND MOUNTED CABINET FOUNDATION ON SLOPE DETAILS

### ITS(22)-15

FILE: its(22)-15.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT June 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	0915	00	268	VARIOUS
	DIST	COUNTY	SHEET NO.	
	SAT	BEXAR, ETC.	<b>98</b>	

DATE: 2/27/2024 11:40:42 AM  
FILE: its(22)-15.dgn



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 2/27/2024  
FILE: epic.dgn

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.  
2.  
 No Action Required     Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required  
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)  
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)  
 Individual 404 Permit Required  
 Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.  
2.  
3.  
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

<b>Erosion</b>	<b>Sedimentation</b>	<b>Post-Construction TSS</b>
<input type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input checked="" type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

**III. CULTURAL RESOURCES**

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

**IV. VEGETATION RESOURCES**

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

- No Action Required     Required Action

Action No.

1.  
2.  
3.  
4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes     No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes     No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required     Required Action

Action No.

1.  
2.  
3.


**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required     Required Action

Action No.

1.  
2.  
3.

 Texas Department of Transportation		<i>Design Division Standard</i>	
<b>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC</b>			
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (DS) REVISIONS	0915	00	268
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	SAT	BEXAR, ETC.	99

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For projects with less than one acre of soil disturbing activity and that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**  
0915-00-268

**1.2 PROJECT LIMITS:**  
From: SEE TITLE SHEET

To: SEE TITLE SHEET

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) N/A, (Long) N/A

END: (Lat) N/A, (Long) N/A

**1.4 TOTAL PROJECT AREA (Acres):** 0.23

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** 0.23

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**  
SEE TITLE SHEET

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
N/A	

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures
- Other: BORE AND TRENCH ACTIVITIES FOR PROPOSED CONDUIT INSTALLATION
- Other: INSTALLATION OF ITS POLES AND DPAS

Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Discharges from concrete washout activities, runoff from concrete cutting activities, and other concrete related activities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
N/A	


\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_



**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)**

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				100
STATE	STATE DIST.	COUNTY		
TEXAS	SAT	BEXAR, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
0915	00	268	VARIOUS	

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To
N/A		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To
N/A		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 DEWATERING:**

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.


**2.9 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

**2.10 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)**



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				101
STATE	STATE DIST.	COUNTY		
TEXAS	SAT	BEXAR, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
0915	00	268	VARIOUS	