

SHEET NO. DESCRIPTION

GENERAL

TITLE SHEET	
IIILE SHEET	

INDEX OF SHEETS 2

3-4 5-6 GENERAL NOTES

- ESTIMATED QUANTITIES ESTIMATE AND QUANTITY 7

TRAFFIC CONTROL PLAN STANDARDS


8	[D] TCP GENERAL NOTES
9-14	CLEAN AND SEAL JOINTS SEQUENCE OF CONTRUCTION
15-26	[S] BC(1) THRU BC(12)-21
27	[S] WZ (RCD) - 13
28	[S] WZ (TD) - 17
29	[S] TCP (6-6) - 12

BRIDGES

30-32	CLEANING AND SEALING EXISTING BRIDGE JOINTS
33	CLEANING AND SEALING EXISTING BRIDGE JOINTS (PAN GIRDER BRIDGES)
34	CLEAN AND SEAL JOINTS HIDALGO COUNTY LOCATION MAP
35	CLEAN AND SEAL JOINTS HIDALGO COUNTY
36	CLEAN AND SEAL JOINTS CAMERON COUNTY LOCATION MAP
37	CLEAN AND SEAL JOINTS CAMERON COUNTY (SHEET 1 OF 2)
38	CLEAN AND SEAL JOINTS CAMERON COUNTY (SHEET 2 OF 2)
39	CLEAN AND SEAL JOINTS ZAPATA COUNTY LOCATION MAP
40	CLEAN AND SEAL JOINTS ZAPATA COUNTY


ENVIRONMENTAL ISSUES

- ENVIRONMENTAL PERMITS, ISSUES & COMMITMENTS (EPIC) TPWD BMPS 41-42 43-45



Х

•THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



Project Number:

County: Various

Highway: Various

2014 SPECS GENERAL NOTES:

General Requirements and Covenants to ITEMS 1 thru 9: For all pits or quarries, comply with the "Texas Aggregate Quarry and Pit Safety Act."

Provide on a weekly basis a list of equipment, including idle equipment, utilized on the project that week.

The 1-800 call services for utility locations do not include TxDOT facilities. Contact the Pharr District Signal Section (956-702-6225) for coordination regarding TxDOT underground lines.

ITEM 2: Instructions to Bidders Contractor questions on this project are to be addressed to the following individual(s):

Eugene Palacios, P.E., District Maintenance;

Eugene.Palacios@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals. Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Information found on TxDOT's FTP server will be considered for informational purposes only. Index of /pub/txdot-info/Pre-Letting Responses/Pharr District/21-Pharr District (Construction) (state.tx.us)

ITEM 4: Scope of Work

This Contract includes non-site-specific work. Multiple work orders will be used to procure work of the type identified in the contract at locations that have not yet been determined.

Project Number:

County: Various

Highway: Various

ITEM 7: Legal Relations and Responsibilities

Roadway or Lane closures during the following key dates and/or special events are prohibited:

- National Holidays
- The day before a National Holiday

ITEM 8: Prosecution and Progress

Working days will be computed and charged in accordance with Article 8.3.1.6. defined as follows:

Work and time charges will continue until the start of the bird nesting season. Upon the start of the bird nesting season, work and time charges will stop for a maximum period of 120-Working days for the bird nesting season delay to be completed. Time charges in accordance with Article 8.3.1.4. will resume at the end of the 120-day bird nesting season delay or earlier if mutually agreed in writing by the Engineer and Contractor.

Prepare progress schedules as a Bar Chart.

ITEM 502: Barricades, Signs, and Traffic Handling

Replace/relocate all regulatory signs removed due to construction operations with the same sign on fixed support(s) immediately upon its removal. First obtain Project Engineer approval before removing any regulatory roadway sign. Required flaggers are to be available to direct traffic during sign intermediate down time.

Relocate any Directional Sign Assemblies removed during construction operations immediately upon their removal.

These signs shall be relocated to a location in accordance with the Latest Version of the "Texas Manual on Uniform Traffic Control Devices". In no case will a sign be removed without a replacement sign and support(s) being readily available and a location established. Removal and relocation of these signs required for traffic control will not be paid for directly but shall be considered subsidiary to Item 502.

From the beginning to the end of the project, all traffic control devices need to be in acceptable condition as per the Texas Quality Guidelines for Work Zone Traffic Control Devices.

Sheet 3

Control: 6462-60-001

General Notes

Sheet 3

Control: 6462-60-001

• During emergency events such as natural disasters or as directed by the Engineer

Project Number:

Sheet 4

County: Various

Control: 6462-60-001

Highway: Various

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The "Safety Contingency" is not intended to be used in lieu of bid Items established by the contract.

Remove and dispose of all litter, debris, objectionable material, excess materials that accumulate at the base of all traffic control devices as directed by the Engineer.

ITEM 504: Field Office and Laboratory

For this project a field office will not be required at the project site.

ITEM 5088: Bird Exclusion Methods

Contractor's attention is directed to the plan's EPIC sheets, Bird Exclusion Detail standard sheets and shall refer to the Migratory Bird Treaty Act requirements. Also, refer to the TPWD BMPSs sheets for specific adherence to the environmental requirements of the Best Management Practices.

ITEM 6185: Truck Mounted Attenuator/Trailer Attenuator

In addition to the shadow vehicles with truck mounted attenuator (TMA) that are specified as being required on the traffic control plan for the project, provide <u>0</u> additional shadow vehicle(s) with TMA;

Therefore, <u>3</u> total shadow vehicles with TMA will be required on this project for the type of work as shown on the plans. The Contractor will be responsible for determining if one or more of his construction operations will be ongoing at the same time and thus determine the total number of TMAs needed for the project.

	HIDA	LGO COUI	NTY ESTIMA	ΓED	QUA	ΝΤΙΤΙ	ES			C	CAMERON	COUNTY EST	'IMA'	ΓED	QUAN	ΝΤΙΤΙΕ	S
RIDGE NO.	NBI	HIĞHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REPAIR LENGTH	TOTAL (LF)	TOTAL NO. OF REPAIR BENTS	CLEANING AND SEALING EXIST JOINTS 438 6001 LF	BRIDGE NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REPAIR LENGTH	TOTAL (LF)	TOTAL NO. OF REPAIR BENTS	CLEA AN SEA EXI JOIR 4.
1	0255-07-294	US 281 SB	RAYMONDVILLE DRAIN	1 4	57 57	114	2	114	13	0039-07-125	US 77 NB	UPRR, BUS 77 & PRIMERA RD.	ALL	34	782	23	78
2	0255-07-293	US 281 NB	RAYMONDVILLE DRAIN	4	57	57	1	57					1 2				
3	0255-07-046	US 281 NB	BU 281 NB	1 2 3	68 69 68	332	5	332	14	0039-07-206	US 77 NB	DRAINAGE DITCH, BUS 77 RR & MATZ AVE.	3 4 5 6	43	258	6	2
				4 5	65 62	_			15	0039-19-289	US 83	RVSC & PALM COURT DR.	1 4	56 66	122	2	1;
4	0255-07-048	FM 1925 NB	MONTE CRISTO RD	ALL	45	180	4	180	16	0039-08-233	US 77 SB	ROBERTA RD.	1 4	- 55	110	2	1
5	0255-07-050	US 281 NB	CHAPIN ST	ALL	74	296	4	296	17	0039-08-232	US 77 NB	ROBERTA RD.	1 4	- 55	110	2	1
6	0255-07-049	US 281 SB	CHAPIN ST	ALL	60	240	4	240	18	0039-08-355	US 77 SB	CARMEN RD.	1	- 56	112	2	1
7	0255-07-043	US 281 SB	UPRR (ABANDONED)	ALL	58	348	6	348	19	0039-08-354	US 77 NB	CARMEN RD.	1	- 56	112	2	1
				1 2	72 74				20	0039-08-353	US 77 SB	RANCHO VIEJO DR.	1 4 1	- 56	112	2	1
8	0255-07-044	US 281 NB	UPRR (ABANDONED)	3 4 5	78 83 90	494	6	494	21 22	0039-08-226 0039-08-227	US 77 SB US 77 NB	FM 511 FM 511	4	72	144 144	2 2	1
9	0255-07-053	US 281 SB	SH 107	6 ALL	97 70	280	4	280	23	0039-08-239	US 77 NB	OLD ALICE RD	1 4	- 56	112	2	
10	0255-07-054	US 281 NB	SH 107	ALL	70	280	4	280	24	0684-01-247	SH 550 NB	DRAINAGE DITCH	1 4	40	80	2	8
11	0255-08-061	US 281 SB	FREDDY GONZALEZ DR	5	70	70	1	70	25 26	0684-01-250 0684-01-253	SH 550 NB SH 550 NB	FM 1847 UPRR •2 SPUR	1 1 4	86 - 49	86 98	1 2	<u>ع</u> ۽
12	0255-08-060	US 281 NB	FREDDY GONZALEZ DR	3	70 70	140	2	140	27	0684-01-256	FM 511 NB	SH 550	4	49	49	1 TOTAL	2

GENERAL NOTES: Refer to Item 438 for application instruction.

Refer to CLEAN AND SEAL JOINTS Sheets for locations and quantities.

Perform Traffic Control Operations as per TCP(6-6)-12.

ESTIMATED QUANTITIES									
1 OF	2								
FILE:			DN: RRE		ск:	DW: F	RRE	CK:	
CTXDOT	August 2017		CONT	SECT	JOB		ŀ	IGHWAY	
	REVISIONS		6462	60	001		V	ARIOUS	
			DIST	<u> </u>	COUNTY	, . ,		SHEET NO.	
			PHR		VARIOU	10		5	

	ZAP	ATA COUN	ITY ESTIMAT	ΈD	QUAN	ΙΤΙΤΙ	ES	
BRIDGE NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REPAIR LENGTH	TOTAL (LF)	TOTAL NO. OF REPAR BENTS	CLEANING AND SEALING EXIST JOINTS
							BENTS	438
								6001 LF
				1				LF
28	0038-04-058	US 83 SB	ARROYO BURRO	1 4 8 12 16 24 27-28 30-31 34	28	380	11	308
29	0038-04-095	US 83	ARROYO VELENO	1 3 6 9 12 15 15	82	574	7	574
							TOTAL	882

SUMMARY OF WORKZONE TRAFFIC CONTROL	ITEMS			
CATEGORY OF WORK	Barricades	Maintenance	Mobilization	Work zone
BID CODE	502-6001	438-6001	500-6001	6185-6005
DESCRIPTION	BARRICADES, SIGNS AND TRAFFIC HANDLING	CLEANING AND SEALING EXISTING JOINTS	MOBILIZATION	TMA (MOBILE OPERATION)
ALTERNATE BID GROUP				
PLAN SET LOCATION UNIT	MO Monthly	LF Linear Feet	LS Lump Sum	DAY Day
	6.000	6,144.000	1.000	120.000
PROJECT TOTALS	6.000	6,144.000	1.000	120.000

GENERAL NOTES: Refer to Item 438 for application instruction.

Refer to CLEAN AND SEAL JOINTS Sheets for locations and quantities.

Perform Traffic Control Operations as per TCP(6-6)-12.

Texas Department of Transportation									
ESTIMATED QUANTITIES									
2 OF	2								
FILE:		DN: RRE		ск:	DW: RR	E	CK:		
C TxDOT	August 2017	CONT	SECT	JOB		HIG	GHWAY		
	REVISIONS	6462	60	01		VA	RIOUS		
		DIST		COUNT	Y		SHEET NO.		
		PHR		VARIO	JS		6		



CONTROLLING PROJECT ID 6462-60-001

Estimate & Quantity Sheet

COUNTY Cameron

DISTRICT Pharr HIGHWAY BU0077W

		CONTROL SECTION	ON JOB	6462-60	0-001		
		PROJ	PROJECT ID				
	COUNTY				ron	TOTAL EST.	TOTAL FINAL
		ніс	GHWAY	BU0077W			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	438-6001	CLEANING AND SEALING EXISTING JOINTS	LF	6,144.000		6,144.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	6.000		6.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	120.000		120.000	
	08	CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS	1.000		1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Pharr	Cameron	6462-60-001	7

GENERAL NOTES AND SPECIFICATIONS DATA:

USE A POWER-BROOM WHEN CLEANING THE ROADWAY AS NEEDED.

REMOVE & DISPOSE ALL MATERIAL NOT DEEMED SALVAGEABLE BY THE ENGINEER, UNLESS OTHERWISE SHOWN ON THE PLANS.

ON EXISTING PAVEMENT THAT WILL REMAIN IN PLACE, SAND BLAST OR SURFACE TREAT IN ORDER TO REMOVE EXISTING STRIPING.

DO NOT BLOCK DRAINAGE WHEN HANDLING & STOCKPILING EXCAVATED MATERIAL.

MAINTAIN ACCESS TO DRIVEWAYS AND INTERSECTIONS THROUGH ALL PHASES OF CONSTRUCTION.

MAINTAIN POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.

TRAFFIC CONTROL DEVICES:

AT THE COMMENCEMENT OF THE PROJECT, ALL TRAFFIC CONTROL DEVICES SHALL BE IN ACCEPTABLE CONDITION, AND MAINTAINED THROUGHOUT THE DURATION OF THE PROJECT, AS PER GUIDELINES FOR TEMPORARY TRAFFIC CONTROL DEVICES AND FEATURES.

NOTIFY THE AREA ENGINEER(AE) IN WRITING(E-MAIL IS ACCEPTABLE) ONCE THE TRAFFIC CONTROL PLAN(TCP) AND ALL TRAFFIC CONTROL DEVICES HAVE BEEN INSTALLED AS PER PLANS ON THE PROJECT SO THAT THE DEPARTMENT'S RESPONSIBLE PERSON ACCOMPANIED BY THE CONTRACTOR'S RESPONSIBLE PERSON CAN CONDUCT A NIGHT INSPECTION ON THE SAID TCP AND TRAFFIC CONTROL DEVICES. COMMENCEMENT OF WORK WILL NOT BE AUTHORIZED NOR ALLOWED UNTIL THE AE NOTIFIES THE CONTRACTOR IN WRITING(E-MAIL IS ACCEPTABLE) TO PROCEED WITH THE WORK.

CONTRACTOR SHALL HAVE A SUFFICIENT AMOUNT OF TRAFFIC CONTROL DEVICES IN ACCEPTABLE CONDITION TO REPLACE ANY DAMAGED TRAFFIC CONTROL DEVICE WITHIN 24 HOURS OF NOTIFICATION.

PROVIDE ADDITIONAL SIGNS AND BARRICADES AS NECESSARY TO ADDRESS FIELD CONSTRUCTIBILITY & VISIBILITY. THESE ADDITIONAL SIGNS WILL BE CONSIDERED SUBSIDIARY TO ITEM 502.

REMOVE OR COMPLETELY COVER ALL EXISTING SIGNS WHICH ARE IN CONFLICT WITH THE TRAFFIC CONTROL PLAN.

ADJUST STOP SIGNS AS NEEDED ON INTERSECTING STREETS DURING THE VARIOUS CONSTRUCTION PHASES. DO NOT REMOVE ANY EXISTING STOP SIGNS UNTIL TEMPORARY SIGNS ARE IN PLACE.

COORDINATE THE TRAFFIC CONTROL PLAN AND THE VARIOUS SEQUENCES OF CONSTRUCTION WITH ADJACENT CONSTRUCTION PROJECTS IF APPLICABLE, TO ENSURE THE UNINTERRUPTED AND SAFE FLOW OF TRAFFIC.

NOTIFY THE ENGINEER IN WRITING WHEN MAJOR TRAFFIC CHANGES ARE TO BE MADE. NOTIFICATIONS MUST BE GIVEN A MINIMUM OF THREE WORKING DAYS PRIOR TO THE CHANGE.

PROJECT SPECIFIC NOTES:

EXAMPLES:

1. DRAINAGE & IRRIGATION CROSSING WORK DESCRIPTION AND APPLICABLE TCP STATE STANDARDS.

2. TREATMENT OF PAVEMENT DROP-OFF IN WORK ZONE NOTES AS APPLICABLE.

ADD PROJECT SPECIFIC NOTES AS NEEDED. SIGN & SEAL STANDARD WHEN USING PROJECT SPECIFIC NOTES

MAINTENANCE REQUIRING ROAD CLOSURES SHALL BE DURING NIGHTTIME HOURS. DURING THE PEAK HOURS, OFF-PEAK HOURS, AND WEEKEND HOURS THE CONTRACTOR SHALL MAINTAIN THE MINIMUM LANES TO BE OPEN TO TRAFFIC.

FOR THE PURPOSES OF THIS TRAFFIC CONTROL PLAN, THE FOLLOWING DEFINITIONS SHALL APPLY:

PEAK HOURS MON.-FRI. 6:00 A.M. TO 8:30 A.M. MON.-FRI. 4:00 P.M. TO 7:00 P.M. OFF-PEAK HOURS MON.-FRI. 9:00 A.M. TO 4:00 P.M. NIGHTTIME HOURS MON.-FRI. 7:00 P.M. TO 6:00 A.M. WEEKEND HOURS FRI, 9:00 A.M. TO MON. 6:00 A.M.

TRAFFIC CONTROL PLAN NOTES SHEET I OF I SHEETS

SAFETY:

PROTECT EXPOSED PITS THAT MUST REMAIN OPEN DURING NON-WORKING HOURS AS PER OSHA REQUIREMENTS.

PHARR DISTRICT STANDARD

.

	©TxDOT 2017 Rev 03/22/2017										
STATE	FED.RD. DIV.NO.	FEDER	AL AID	PROJECT N	١0.	SHEET NO.					
TEXAS	6					8					
DIST.	COUNTY	CONT.	SECT.	JOB	нісни	AY NO.					
PHR	PHR VARIOUS 6462 60 001 VARIOUS										

THE CONTRACTOR MAY OPT TO SUBMIT AN ALTERNATE CONSTRUCTION SEQUENCE AND TRAFFIC CONTROL PLAN, SIGNED AND SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF TEXAS. SUCH PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR CONSIDERATION. HOWEVER, THE CONTRACTOR MUST FOLLOW THE TCP CONSTRUCTION PHASES AS SHOWN ON THE TCP PLANS.

THE CONTRACTOR SHALL BE PROHIBITED FROM WORKING SIMULTANOUSLY ON MULTIPLE PHASES. THE CONTRACTOR SHALL COMPLETE ALL STEPS IN EACH PHASE PRIOR TO INITIATING AND COMMENCING THE SUBSEQENT CONSTRUCTION PHASE.

IN ADDITION TO THE GENERAL NOTES REQUIREMENTS, THE FOLLOWING PROVISIONS GOVERN THIS CONTRACT.

SEQUENCE OF CONSTRUCTION.

CONSTRUCT THE VARIOUS ROADWAY IMPROVEMENTS IN SIXTEEN (16) MAIN PHASES AS NOTED IN THIS NARRATIVE.

INSTALL PROJECT LIMIT SIGNS, ADVANCE WARNING SIGNS, AND CROSSROAD BARRICADES/SIGNS AS SHOWN ON THE TRAFFIC CONTROL PLANS (TCP), AND IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD), LATEST EDITION, AND/OR AS DIRECTED BY THE ENGINEER. THESE SIGNS SHALL BE ERECTED AND PLACED PRIOR TO COMMENCING ANY PROPOSED ROADWAY CONSTRUCTION AND SHALL REMAIN IN PLACE FOR THE DURATION OF THE PROJECT AND UNTIL FINAL ACCEPTANCE OF THE PROJECT BY TXDOT.

PORTABLE CHANGEABLE MESSAGE BOARDS SHALL BE PLACED TO NOTIFY TRAVELING PUBLIC ON PLANNED ROADWAY CLOSURE DATE(S) OR MOVEMENTS RESTRICTIONS A MINIMUM OF FIVE (5) WORKING DAYS IN ADVANCE OF ROADWAY CLOSURE.

PHASE I: US 281 (I 69C) NORTHBOUND (3.0 MILES):

LOCATIONS:

LOCATION 8 - NBI: 0255-07-044 CROSSING UPRR (ABANDONED) LOCATION 10 - NBI: 0255-07-054 CROSSING SH 107 (UNIVERSITY DR.) LOCATION 12 - NBI: 0255-07-060 CROSSING FREDDY GONZALEZ DR.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH 25TH AVE, FRONTAGE RD., AND EXPRESSWAY 281.
- 3. DURING THIS PHASE, ACCESS TO US 281 (I 69C) NORTHBOUND SHALL NOT BE ALLOWED FROM CANTON RD. TO MILE 17 $\frac{1}{2}$ RD. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC DURING. THRU TRAFFIC WILL 4. NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 2: US 281 (I 69C) NORTHBOUND (4.0 MILES):

LOCATIONS:

LOCATION 3 - NBI: 0255-07-046 CROSSING BU 281 NORTHBOUND. LOCATION 4 - NBI: 0255-07-048 CROSSING FM1925 (MONTE CRISTO RD.) LOCATION 5 - NBI: 0255-07-050 CROSSING CHAPIN ST.

- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- DETOUR TRAFFIC THROUGH 25TH AVE, FRONTAGE RD., AND EXPRESSWAY 281.
- 3. DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4 NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

DURING THIS PHASE, ACCESS TO US 281 (I 69C) NORTHBOUND SHALL NOT BE ALLOWED FROM FM 107 (UNIVERSITY DR) TO DAVIS RD. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL

T exas Department of Transportation									
CLEAN AND SEAL JOINTS SEQUENCE OF CONSTRUCTION									
1 OF 6									
FLE:	DN: RRE		ск:	dw: F	RRE	ск:			
CTxDOT August 2017	CONT	SECT	JOB		1	HIGHWAY			
REVISIONS	6462	60	001		V	ARIOUS			
	DIST	COUNTY				SHEET NO.			
	PHR		VARIOL	JS		9			

PHASE 3: US 281 (I 69C) BOTH DIRECTIONS (6.0 MILES):

LOCATIONS:

LOCATION 1 - NBI: 0255-07-294 CROSSING RAYMONDVILLE DRAINAGE DITCH. LOCATION 2 - NBI: 0255-07-293 CROSSING RAYMONDVILLE DRAINAGE DITCH.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- DETOUR TRAFFIC THROUGH EXPRESSWAY 281 (FRONTAGE RD.).
- 3. DURING THIS PHASE, ACCESS TO US 281 (I 69C) NORTH BOUND AND SOUTHBOUND SHALL NOT BE ALLOWED FROM EL CIBOLO RD TO FM 490. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 4: US 281 (I 69C) SOUTHBOUND (1.0 MILES):

LOCATIONS:

LOCATION 6 - NBI: 0255-07-049 CROSSING CHAPIN ST.

- LOCATION 7 NBI: 0255-07-043 CROSSING UPRR (ABANDONED)
- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD. (EXPRESSWAY 281).
- 3. DURING THIS PHASE, ACCESS TO US 281 (I 69C) SOUTHBOUND SHALL NOT BE ALLOWED FROM RUSSEL RD. (MILE 17 $\frac{1}{2}$ RD.) TO RICHARDSON RD. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4. NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.

REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 5: US 281 (I 69C) SOUTHBOUND (2.0 MILES):

LOCATIONS: LOCATION 9 - NBI: 0255-07-053 CROSSING SH 107 (UNIVERSITY DR.) LOCATION 11 - NBI: 0255-07-061 CROSSING FREDDY GONZALEZ DR.

- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD. (24TH AVE.).
- TO IOWA RD. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

3. DURING THIS PHASE, ACCESS TO US 281 (I 69C) SOUTHBOUND SHALL NOT BE ALLOWED FROM SCHUNIOR.

	★ [®] iexas Department (of Tra	nsp	ortation	,	Di	idge vision andard
	CLEAN AN QUENCE O						-
2 OF	6						
FILE:		DN: RRE		ск:	DW: F	RRE	CK:
C TxDOT	August 2017	CONT	SECT	JOB		I	HIGHWAY
	REVISIONS	6462	60	001		V	ARIOUS
		DIST		COUNTY			SHEET NO.
		PHR		VARIOL	JS		10

PHASE 6: US 77 (I 69E) NORTHBOUND (1.4 MILES):

LOCATIONS:

LOCATION 13 - NBI: 0039-07-125 CROSSING UPRR, BUS 77, PRIMERA RD. LOCATION 14 - NBI: 0039-07-206 CROSSING UPRR, BUS 77, MATZ RD., DRAINAGE DITCH.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD AND LOOP 499.
- 3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) SOUTHBOUND SHALL NOT BE ALLOWED FROM WILSON RD. TO TEXAS AVE. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4 NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 7: US 83 (I 2) WESTBOUND (3.0 MILES):

LOCATIONS:

LOCATION 15 - NBI: 0039-19-289 CROSSING RVSC, PALM COURT DR.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD. (24TH AVE.).
- 3. DURING THIS PHASE, ACCESS TO US 83 (I 2) SOUTHBOUND SHALL NOT BE ALLOWED FROM EXIT 26B TOWARD MCALLEN. (NORTHBOUND AND SOUTHBOUND HWY 77 (I 69E)) TO LEWIS LANE. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4 NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 8: US 77 (I 69E) SOUTHTHBOUND (3.0 MILES):

LOCATIONS:

LOCATION 16 - NBI: 0039-08-233 CROSSING ROBERTA RD. LOCATION 19 - NBI: 0039-08-354 CROSSING CARMEN RD. LOCATION 20 - NBI: 0039-08-353 CROSSING RANCHO VIEJO DR.

- 1. ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- 3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) SOUTHBOUND SHALL NOT BE ALLOWED FROM EXIT 13 (ROBERTA RD) TO RANCHO VIEJO DR. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4 NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

Image: Texas Department of Transportation Bridge Division Standard									
SEQU	LEAN AN JENCE O								
3 OF 6	i								
FILE:		dn: RRE		ск:	DW: RRE		ск:		
CTxDOT A	ugust 2017	CONT	SECT	JOB		1	HIGHWAY		
F	REVISIONS	6462	60	001		V	ARIOUS		
		DIST		COUNTY			SHEET NO.		
		PHR		VARIOL	JS		11		

PHASE 9: US 77 (I 69E) (2.0 MILES):

LOCATIONS:

LOCATION 21 - NBI: 0039-08-226 CROSSING FM 511. LOCATION 23 - NBI: 0039-08-239 CROSSING OLD ALICE RD.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- 3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) SOUTHBOUND SHALL NOT BE ALLOWED FROM EXIT 10A (PORT OF BROWNSVILLE). TO LA ROCHE ST.

ACCESS TO US 77 (I 69E) NORTHBOUND SHALL NOT BE ALLOWED FROM EXIT 7 (STILLMAN RD. AND OLD ALICE RD.). TO ON RAMP NORTH OF OLD ALICE RD.

CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.

- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4. NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 10:FM 511 NORTHBOUND (0.6 MILES):

LOCATIONS:

LOCATION 27 - NBI: 0684-01-256 CROSSING FM 550

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- DETOUR TRAFFIC THROUGH SH 48 (BROWNSVILLE-PORT ISABEL HWY) AND SH 550.
- DURING THIS PHASE, ACCESS TO FM 511 NORTHBOUND SHALL NOT BE ALLOWED FROM DES MOINES 3. AVE TO OLD PORT ISABEL RD. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.

6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 11: SH 550 NORTHBOUND (3.5 MILES):

LOCATIONS: LOCATION 25 - NBI: 0684-01-250 CROSSING FM 1847 (PAREDES LANE RD.). LOCATION 26 - NBI: 0684-01-253 CROSSING UPRR #2 SPUR.

- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FM 3248 (DR. HUGH EMERSON RD.).
- DURING THIS PHASE, ACCESS TO SH 550 NORTHBOUND SHALL NOT BE ALLOWED FROM 3. FM 3248 (DR. HUGH EMERSON RD.) TO FM 1847 (PAREDES LANE RD.). CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

Texas Department	of Tra	nsp	ortation	,	Di	ridge ivision randard
CLEAN AN SEQUENCE O 4 OF 6						-
FILE:	DN: RRE		ск:	DW:	RRE	CK:
CTxDOT August 2017	CONT	SECT	JOB			HIGHWAY
REVISIONS	6462	60	001		1	/ARIOUS
	DIST		COUNTY			SHEET NO.
	PHR		VARIOL	JS		12

PHASE 12: FM 511 NORTHWESTBOUND (0.9 MILES):

LOCATIONS:

LOCATION 24 - NBI: 0684-01-247 CROSSING DRAINAGE DITCH.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FM 1847 (PAREDES LANE RD.) AND SH 550.
- 3. DURING THIS PHASE, ACCESS TO FM 511 NORTHWESTBOUND SHALL NOT BE ALLOWED FROM FM 1847 (PAREDES LANE RD.) TO RANCHO ALTO DR. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4. NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 13: US 77 (I 69E) NORTHBOUND (0.8 MILES):

LOCATIONS:

LOCATION 22 - NBI: 0039-08-227 CROSSING FM 511.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- 3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) NORTHWESTBOUND SHALL NOT BE ALLOWED FROM EXIT 10A (PORT OF BROWNSVILLE) TO SH 550. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL 4. NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 14: US 77 (I 69E) NORTHBOUND (1.7 MILES):

LOCATIONS: LOCATION 17 - NBI: 0039-08-232 CROSSING ROBERTA RD. LOCATION 18 - NBI: 0039-08-355 CROSSING CARMEN RD.

- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- 3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) SOUTHBOUND SHALL NOT BE ALLOWED FROM EXIT 12 (CARMEN AVE.) TO ROBERTA RD. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY - FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

Texas Department	of Tra	nsp	ortation	,		lge ision ndard
CLEAN AN SEQUENCE O 5 OF 6						
FILE:	DN: RRE		ск:	DW:	RRE	ск:
CTxDOT August 2017	CONT	SECT	JOB		HI	GHWAY
REVISIONS	6462	60	001		VA	Rious
	DIST		COUNTY			SHEET NO.
	PHR		VARIOL	JS		13

PHASE 15: US 83 SOUTHBOUND (0.7 MILES):

LOCATIONS:

LOCATION 28 - NBI: 0038-04-058 CROSSING ARROYO BURRO

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- 3. DURING THIS PHASE, ACCESS TO US 83 SOUTHBOUND SHALL NOT BE ALLOWED FROM WILSON RD. TO TEXAS AVE. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 16: US 83 NORTH BOUND AND SOUTHBOUND (0.8 MILES):

LOCATIONS:

LOCATION 29 - NBI: 0038-04-095 CROSSING ARROYO VELENO

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- 3. DURING THIS PHASE, ACCESS TO US 83 SHALL NOT BE ALLOWED FROM MADISON AVE. TO IOWA ST. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRU TRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED MONDAY FRIDAY 7:00 P.M. TO 6:00 A.M.
- 5. CLEAN AND SEAL EXISTING JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

Texas Department	Div	Bridge Division Standard				
CLEAN AN SEQUENCE O						
6 OF 6						
FLE:	DN: RRE		ск:	dw: F	RRE	CK:
CTxDOT August 2017	CONT	SECT	JOB		н	IGHWAY
REVISIONS	6462	60	001		VA	RIOUS
	DIST		COUNTY			SHEET NO.
	PHR		VARIOL	JS		14

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- 3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessory worning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- 7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travellanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- 1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


INE AT

ST (CWZTCD)

NUALS)"

(TMUTCD)

	SH	EET 1 (OF	12			
	★* Texas Departme	nt of Tra	nsp	ortation		Sa Div	affic afety vision ndard
BAR	RICADE A GENE AND R		N	OTES	5		ON
	B	C(1)	-2	1			
FILE:	bc-21.dgn	dn: Tx	DOT	ск: ТхDOT	DW:	TxDOT	ск: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB		HIG	HWAY
4-03	REVISIONS	6462	60	001		VA	rious
	DIST		COUNTY			SHEET NO.	
9-07	8-14	UIST					SHEET NO.




Proctice Act". No warranty of any no responsibility for the conversion resulting from its use. Texos Engineering P . TxDOT ossumes r esults or domoges r rerned by the "Te bose whatsoever. " for incorrect res si po vo this standar TxDOT for a to other for DISCL AIMER: The use of 11 kind is mode by T of this standard to

DATE

	TYPICAL CONS	STRUCTION	N WAR	NING SIGN S	SIZE A			
		SIZE			r	SF	ACING	
	Sign Number or Series	Conventio Rood	-	Expressway/ Freeway	ן ו	Posted Speed	Sign Spacing "X"	* 9
	Cw20 ⁴ Cw21				┨┠	МРН 30	Feel (Apprx 120	
	CW22 CW23 CW25	48" ×	48"	48" × 48"		35 40	160 240	
	CW1, CW2,					45	320	
	CW7, CW8, CW9, CW11,	36" × 36"	48'	× 48"		50 55	400 500	
	CW14					60	600	
	CW3, CW4,					65	700	
		48" × 48"	48	× 48"		70	800	
	CW8-3,					75	900	
	CW10, CW12					80	1000	2 3
	* For typicalsign spi	aciona an divi	ded hish			*	*	
	work area and/or GENERAL NOTES 1. Special or larger size 2. Distance between si advance warning.	signs may t	be used (os necessory.) have 15	00 feet		
	3. Dislance between si or more advance	worning.		-	have 1			
, . , .		warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap	D)signs may be u ineer as per TMU1 road Signs". are indicated. apendix or the "Si	o have 1 used on k ICD Part	ow volume 5. See lighwoy		
, . , .	or more advance 4. 36" x 36" "ROAD V crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap	D)signs may be u ineer as per TMU1 road Signs". are indicated. apendix or the "Si	o have 1 used on li ICD Port landard H ble sign (ow volume 5. See lighwoy		
, , ,	or more advance 4. 36" x 36" "ROAD V crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap	D)signs may be u ineer as per TMU1 road Signs". are indicated. opendix or the "Si opendix or the "Si opelete list of availa	o have 1 used on lu ICD Port Landard H ble sign (END	ow volume 5. See lighway design		
, , ,	or more advance 4. 36" x 36" "ROAD V crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap for comp	D)signs may be u neer as per TMUT road Signs". are indicated. opendix or the "Si plete list of availa LEGE Type 3 Ba Channelizin	o have 1 used on li ICD Port Landard H ble sign (END arricade	ow volume 5. See lighway design		
, , ,	or more advance 4. 36" x 36" "ROAD V crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap for comp	D)signs may be u neer as per TMUT road Signs". are indicated. opendix or the "Si blete list of availa LEGE Type 3 Ba	o have 1 used on li ICD Port Landard H ble sign (END arricade	ow volume 5. See lighway design		
- -	or more advance 4. 36" x 36" "ROAD V crossroads at the Note 2 under "Ty 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap for comp	D)signs may be u neer as per TMUT road Signs". are indicated. opendix or the "Si plete list of availa LEGE Type 3 Ba Channelizin	o have 1 used on li ICD Part landard H ble sign (END arricade ign Size hart or or sign	ow volume 5. See lighway design es ruction the		
-	or more advance 4. 36" x 36" "ROAD ¥ crossroads at the Note 2 under "Tyl 5. Only diamond shope 6. See sign size listing Sign Designs for T sizes.	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross n sizes (", Sign Ap lfor comp	D)signs may be u neer as per TMUT road Signs". are indicated. opendix or the "Si plete list of availad LEGE Type 3 Ba Channelizin Sign See Typic. Warning Si Spacing ct TMUTCD f spacing re	a have 1 used on k (CD Part landard H ble sign (<u>END</u> arricade ug Devic al Const ign Size hart or or sign equirement	ow volume 5. See lighway design es ruction the ents.		
N N N N N N N N N N N N N N N N N N N	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.	warning. NORK AHEAD" discretion of pical Location ed warning sig g in "TMUTCD"	(CW20-1 the Engi of Cross In sizes (", Sign Ap I for com	D)signs may be u incer as per TMUT road Signs". are indicated. opendix or the "St polete list of availat LEGE Type 3 Ba Channelizin Sign See Typic. Warning Si Spacing ct TMUTCD f	a have 1 used on k (CD Part landard H ble sign (<u>END</u> arricade ug Devic al Const ign Size hart or or sign equirement	ow volume 5. See lighway design es ruction the ents.		ffic
N Central Cent	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.	worning. WORK AHEAD" discretion of pical Location ed warning sig p in "TMUTCD" exos" manual	(CW20-1 the Engi of Cross In sizes (", Sign Ap I for comp I for comp X	D)signs may be u neer as per TMUT road Signs". are indicated. opendix or the "Si plete list of availad LEGE Type 3 Ba Channelizin Sign See Typic. Warning Si Spacing ct TMUTCD f spacing re	andard H andard H ble sign of END arricade a Const ign Size hart or or sign squiremone OF 1	ow volume 5. See lighway design e es ruction and the ents.	Tra	ffic fety sion dard
N Central Cent	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.) ject. er. (G20-2bT) Ce he	worning. WORK AHE AD" discretion of pical Location ed warning sig p in "TMUTCD" exos" manual	(CW20-1 the Engi of Cross in sizes (", Sign Ap lfor comp 	Disigns may be u incer as per TMUT road Signs". are indicated. appendix or the "Si plete list of availal LEGE Type 3 Ba Channelizin Sign See Typic: Warning Si Spacing ct TMUTCD f spacing re SHEET 2	andard H andard H ble sign (END arricade a Const ign Size hart or or sign squirement 2 OF 1 anspor	ov volume 5. See lighway design e ees ruction and the ents. 2 12 tation	Tra Sat Divi. Stan	fety sion dard
The second secon	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes. 9 ject. er. IE" (G20-2bT) ce he ble	worning. WORK AHE AD" discretion of pical Location ed warning sig p in "TMUTCD" exos" manual	(CW20-1 the Engi of Cross in sizes of ", Sign Ap ifor com ifor com X X	Disigns may be u incer as per TMUT road Signs". are indicated. appendix or the "Si plete list of availal <u>LEGE</u> Type 3 Ba Channelizin Sign See Typic: Warning Si Spacing ct TMUTCD f spacing re <u>SHEET 2</u>	anspor CON	ow volume 5. See lighway design eses e and the ents. 2 2 4 2 4 4 4 4 4 4 4 4 4 4 4 5 5 7 8 4 8 4 8 4 8 4 8 4 8 8 8 8 8 8 8 8 8	Tra Sat Divi. Stan	fety sion dard
N N N N N N N N N N N N N N N N N N N	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.) ject. er. IE" (G20-2bT) ce he ble 5.	worning. WORK AHE AD" discretion of pical Location ed warning sig p in "TMUTCD" exos" manual	(CW20-1 the Engi of Cross in sizes of ", Sign Ap ifor com ifor com X X	Disigns may be unified on sper TMUT road Signs". Sare indicated. Spendix or the "Signet ist of availad LEGE Type 3 Big Channelizin Sign See Typic. Warning Si Spacing cl TMUTCD f spacing re SHEET 2 Deartment of Tr	andard H andard H ble sign (CD Part andard H ble sign (CD Part) andard H ble	ov volume 5. See lighway design e e es ruction the ents. 12 tation	Tra Sat Divi. Stan	fety sion dard
Tonke RROAD proj Jed nginet ZONIU dvance rm th dvance i and ations	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.) ject. er. IE" (G20-2bT) ce he ble 5.	Worning. WORK AHE AD" discretion of pical Location ed warning sig p in "TMUTCD" fexos" manual Tex BARR FLE: bo	(CW20-1 the Engi of Cross in sizes (", Sign Ap ilor com 0 0 0 0 x x x ilor com F con x	Disigns may be unified on sper TMUT road Signs". Sare indicated. Spendix or the "Signet ist of availad LECE Type 3 Bac Channelizin Sign See Typic. Sourcing Signet ist of availad Sign See Typic. See T	anspor CON CON CON CON CON CON CON CON	by volume 5. See tighway design eses ruction the ents. 2 tation STRU 11	Tra Sa Divi Stan	fety sion dard
Tonke RROAD proj Jed nginet ZONIU dvance rm th dvance i and ations	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.) ject. er. IE" (G20-2bT) ce he ble 5.	Worning. WORK AHE AD" discretion of pical Location ed warning sig p in "TMUTCD" exos" manual Tex BARR FILE: bac © TxDOT No	(CW20-1 the Engi of Cross in sizes (", Sign Ap ilor com 0 0 0 0 x x x ilor com F con x	Disigns may be unified on sper TMUT road Signs". Sare indicated. Spendix or the "Signet ist of availad LECE Type 3 Bac Channelizin Sign See Typic. Sourcing Signet ist of availad Sign See Typic. See T	andard F ble sign (CD Port landard F ble sign (CD Port CON corricade anspor const anspor CON LIN) - 21	ov volume 5. See tighway design exes ruction ents. 2 dents. 2 tation STRU	Tra Sat Divi Stan	fety sion dard
Tonke RROAD proj Jed nginet ZONIU dvance rm th dvance i and ations	or more advance 4. 36" x 36" "ROAD W crossroads at the Note 2 under "Typ 5. Only diamond shape 6. See sign size listing Sign Designs for T sizes.) ject. er. IE" (G20-2bT) ce he ble 5.	Worning. WORK AHE AD" discretion of pical Location ed warning sig p in "TMUTCD" exos" manual EARR BARR FILE: br © TxDOT No 9-07 8	(CW20-1 the Engi of Cross in sizes of ", Sign Ap ifor comp in in 0 0 0 0 x x x t * CAD F	Disigns may be unified on a per TMUT rood Signs". are indicated. appendix or the "Signet ist of availad LEGE Type 3 Br Channelizin Sign See Typic: Warning Signet Spacing re SHEET 2 Determent of Tr DE AND PROJECT BC(2 DEC 2	andard F ble sign (CD Port landard F ble sign (CD Port CON corricade anspor const anspor CON LIN) - 21	es ruction and the ents. 2 tation STRU AT	Тга Sat Divistan JC Т IC	fety sion dard

1.5.6



DISCLAMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose wholsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

97

··___]

9-07 8-14

7-13 5-21

DIST


PHR

COUNT

VARIOUS

SHEET NO

17



GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer. Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- 5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texos" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been amilted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the inspector's TxDOT diary and having both the inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.

9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

- <u>QURATION OF WORK (as defined by the "Texas Manualon Uniform Traffic Control Devices" Part 6</u>
- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days. b. Intermediate term stationary - work that occupies a location more than one daylight period up to 3 days, or night lime work lasting
- more than one hour. c. Short-term stationary - daylime work that occupies a location for more than 1 hour in a single daylight period.
- d. Short, duration work that occupies a location up to 1 hour. e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)
- SIGN MOUNTING HEIGHT. 1. The bollom of Long-term/intermediate-term signs shallbe at least 7 feet, but not more than 9 feet, above the paved surface, except
- as shown for supplemental plaques mounted below other signs. 2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above
- the ground. 3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing. 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to
- appropriate Long-term/Intermediate sign height.

SIZE OF SIGNS

l. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- 1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- While sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.

SIGN LETTERS

- 1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway
- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
 Long-term stationary or intermediate stationary signs installed on square metal lubing may be turned away from traffic 90 degrees when
- intersections where the sign may be seen from approaching traffic. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely
- covered when not required.
- . Burlap shall NOT be used to cover signs.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use
- constant weight.
- impact. Rubber (such as lire inner lubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for boliost on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sondbags shallonly be placed along or loid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbaas shall be placed
- along the length of the skids to weigh down the sign support. Sondbags shall NOT be placed under the skid and shall not be used to level sion supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or lorger and shall be arange or fluorescent red-arange in color. Flags shall not be allowed to cover any partian of the sign face.

- Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications. REMOVING OR COVERING
 - the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any

 - When signs are covered, the material used shall be opaque, such as heavy mitblack plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- 6. Duct tope or other adhesive material shall NOT be affixed to a sign face.

- of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain
- Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights. Sondbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sondbags should be made of a durable material that tears upon vehicular

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

3. Orange sheeting, meeting the requirements of DMS-8300 Type B $\,$ or Type G , shall be used for rigid signs with orange backgrounds.

SHEET 4 OF 12 Traffic Safety Division Standard * Texas Department of Transportation BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES BC(4)-21 bc-21.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: TxDO CTxDOT November 2002 CONT SECT JOB HIGHWAY REVISION 6462 60 001 VARIOUS 9-07 8-14

7-13 5-21

98


COUNT

VARIOUS

PHR

SHEET NO

18



DISCLAMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- 2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- 6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnigh Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flosh" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- 11. Do not use the word "Danger" in message. 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches
- and must be legible from at least 400 feet. 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Rood	CCS RD	Najor MAJ	
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Nor thbound	(route) N
Construction Ahead	CONST AHD	Parking	PK ING RD
CROSSING	XING	Rood	
Detour Route	DETOUR RTE	Right Lone	RT LN SAT
Do Not	DONT	Soturdoy	SERV RD
East	E	Service Road	SHLDR
Eastbound	(route) E		SLIP
Emergency	EMER	Slippery South	I SLIP
Emergency Vehicle		Southbound	(route) S
Entrance, Enter	ENT	1	SPD
Express Lone		Speed Street	IST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freewoy	FRWY, FWY	Thursday	
Freewoy Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving			
Hazardous Material		Trovelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour (s)	HR, HRS	Vehicles (s)	VEH, VEHS
Information	INFO	Worning	WARN
It is		Wednesdoy	WED
Junction		Weight Limit	
Left		West	W
Left Lone	LFT LN	Westbound	(route) W
Lone Closed	LN CLOSED	Wet Povement	WET PVMT
Lower Level		Will Not	WONT
Maintenance	MAINT	1	

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

Action to Take/Effect on Travel

MERGE

DETOUR

NEXT

X EXITS

USE

STAY ON

US XXX

SOUTH

TRUCKS

USE

US XXX N

WATCH

TRUCKS

FOR

EXPECT

DELAYS

REDUCE

SPEED

XXX FT

USE

OTHER

ROUTES

STAY IN

LANE

EXIT XXX

RIGHT

List

FORM

X LINES

RIGHT

USE

XXXXX

RD EXIT

USE EXIT

I-XX

NORTH

USE

I-XX F

TO I-XX N

WATCH

FOR

TRUCKS

EXPECT

DELAYS

PREPARE

TO

STOP

END

SHOULDER

USE

WATCH

WORKERS

FOR

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

KOOO/Lone/Kom	p closure List	Uther Co
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT
XXXXXXXX BL VD CLOSED	× LANES SHIFT in Pho	se 1 must be used with S

Other Cond	dition List
ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN	TWO-WAY
NARROWS	TRAFFIC
XXXX FT	XX MILE
MERGING	CONST
TRAFFIC	TRAFFIC
XXXX FT	XXX FT
LOOSE	UNEVEN
GRAVEL	LANES
XXXX FT	XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK	ROADWORK
PAST	NEXT
SH XXXX	FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC	L ANE S
SIGNAL	SHIF T

STAY IN LANE in Phose 2.

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the
- "Road/Lane/Ramp Closure List" and the "Other Condition List". 3. A 2nd phose can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phose Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced w days of the week. Advance notification should typically be for no more than one week prior to the work.

1. The words RIGHT, LEFT and ALL can be interchanged as appropriate. 2. Roadway designations IH, US, SH, FM and LP can be interchanged as

WORDING ALTERNATIVES

- appropriate. 3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate. 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed. 6. AHEAD may be used instead of distances if necessary.
- 7. FT and MI, MILE and MILES interchanged as appropriate 8. AT, BEFORE and PAST interchanged as needed. 9. Distances or AHEAD can be eliminated from the message if a location phase is used.
- PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the some size arrow.

Roodway


designation . IH-number, US-number, SH-number, FM-number

Phase 2: Possible Component Lists



x x See Application Guidelines Note 6.

	SHEE	ET 6	OF	12			
	╋ [®] Texas Department	of Tra	nsp	ortation		Sá Div	affic afety /ision ndard
 BAR	RICADE AN PORTABLE MESSAGE	C	A	NGE A	BLE		N
	BC	:(6)	-2	21			
FILE:	bc-21.dgn	DN: T:	DOT	ск: ТхDOT (ow∘Tx	DOT	ск: ТхDOT
© TxDOT	November 2002	CONT	SECT	т јов		ню	SHWAY
	REVISIONS	6462	60	001		VA	rious
9-07	8-14	DIST	['	COUNTY			SHEET NO.
7-13	5-21	PHR		VARIOUS			20
100							



ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

	SI	HEET 7 OF 12				
	Texas Departm	ent of Transportatio	on ,	Traffic Safety Division Standard		
OT focilities Janual for	BARRICADE	AND CONST	RUC1	ION		
Level 2 or	ARROW PA	NEL. REFLE	CTO	RS.		
IMAs. ise noted	WARNING LIG	•		•		
positioned rew exposure nance.	BC(7)-21					
d is when a work ork crew is an	F⊪LE: bc-21.dgn	DN: TXDOT CK: TXDO	DT DW: TxD	OT CK: TxDOT		
UN CIEW IS UN	CTxDOT November 2002	CONT SECT JOE	•	HIGHWAY		
	REVISIONS	6462 60 001		VARIOUS		
	9-07 8-14	DIST COUM	NTY .	SHEET NO.		
	7-13 5-21	PHR VARI	ous	21		

GENERAL NOTES

- 1. For long term stationary work zones on freeways, drums shall be used as the primory channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD)
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS


- Pre-qualified plastic drums shall meet the following requirements:
- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air lurbulence created by passing vehicles.
- 3. Plostic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The lop of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material. 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10.Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING


- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retrorellectivity requirements of Deportune tal Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballost material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavemen surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- 3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to povement.









DETECTABLE PEDESTRIAN BARRICADES


- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- 2. Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5. Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.





- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or lurn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spocing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B or Aype C conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stalionary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

12"

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact. 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travellanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballosted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with povement markings. 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements
- specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballasted systems used as barriers should not be used for a merging laper except in low speed (less than 45 MPH) urban areas. When used on a laper in a low speed urban area, the laper shall be delineated and the laper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top I the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS


Practice Act". No warranty of any no responsibility for the conversion resulting from its use. DISCLANKER: The use of this standard is governed by the "Texas Engineering F kind is mode by TADOT for any purpose whatsoever. TADOT assumes of this standard to other formats or for incorrect results or domages

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roodways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manualon Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone oreos where channelizing devices are frequently impacted by erront vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, foded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spocing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the odhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final povement surfaces, including povement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posled Speed	Formula	Minimum Desirable Taper Lenglhs x x		Desirable Formula Taper Lengths			Suggested Maximum Spacing of Channelizing Devices		
		10° Offset	11 [.] Offset	12° Offset	On a Taper	On a Tangent			
30		150'	165'	180'	30'	60'			
35	L. <u>WS²</u>	205'	225'	245	35'	70'			
40	- 60	265'	295'	320'	40'	80'			
45		450'	495'	540'	45'	90'			
50		500 [.]	550'	600'	50'	100'			
55	L-WS	550'	605'	660.	55'	110 [.]			
60] - "3	600 [.]	660'	720'	60 [.]	120'			
65]	650'	715'	780'	65'	130'			
70]	700'	770'	840'	70'	140'			
75]	750'	825'	900.	75'	150 [.]			
80		800'	880'	960'	80'	160'			


x x Toper lengths have been rounded off. L-Length of Taper (FT.) W-Width of Offset (FT.) S-Posted Speed (MPH)



SHEET 9 OF 12	
✓ Texas Department of Transportation	Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21									
FILE:	LE: bc-21.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: TxDO							ск: TxDOT	
© TxDOT	November 2002		CONT	CONT SECT JOB		HIGHWAY			
REVISIONS			6462	60	001		VAF	RIOUS	
9-07	8-14		DIST	DIST COUNTY		SHEET NO.			
7-13	5-21		Phr	HR VARIOUS				23	



BC(10)-21									
FILE:	bc-21.dgn		DN: T>	DOT	ск: TxDOT	DW:	TxDOT	ск: TxDOT	
© TxDOT	November 2002		CONT SECT JOB			HIGHWAY			
REVISIONS			6462	60	60 001			VARIOUS	
	9-07 8-14		DIST	COUNTY			SHEET NO.		
7-13	5-21		Phr	PHR VARIOUS				24	
104									

WORK ZONE PAVEMENT MARKINGS

GENERAL

- 1. The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- 2. Color, patterns and dimensions shall be in conformance with the "Texos Monual on Uniform Traffic Control Devices" (TMUTCD).
- 3. Additional supplemental pavement marking details may be found in the plans or specifications.
- 4. Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- 5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPW).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- 7. All work zone povement markings shall be installed in accordance with Item 662, "Work Zone Povement Markings."

RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns on BC(12).
- 2. All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS


- 1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- 2. Non-removable prefabricated pavement markings (fail back) shall meet the requirements of DMS-8240.

MAINTAINING WORK ZONE PAVEMENT MARKINGS

- 1. The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- 2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- 1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- 2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- 3. Povement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Povement Markings and Markers".
- 4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- 5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised pavement markers shall be as directed by the
- 9. Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.



is usually more than 1/4" and less than 1". STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- 1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- 2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - A Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic povement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- 1. Raised povement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- 2. All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- 3. Adhesive for guidemarks shall be bituminous material hot applied or butylrubber pod for all surfaces, or thermoplastic for concrete surfaces

Guidemarks shall be designated as:


YELLOW - (Iwo amber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242


A list of pregualified reflective raised pavement markers. non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SH	EET 11	OF	12				
Texas Departme	ent of Tra	nsp	ortation		Sa Div	affic afety /ision ndard	
BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS BC(11)-21							
 Е	BC(11))-:	21				
FILE: bc-21.dgn) – 2	21 ск: ТхDOT	DW:	TxDOT	ск: ТхD01	
				DW:		ck: TxDO	
FILE: bc-21.dgn CTxDOT February 1998 REVISIONS	DN: Tx	DOT	ск: ТхDOT	DW:	ню		
FILE: bc-21.dgn ©TxDOT February 1998	DN: TX CONT	(DOT SECT	ск: TxDOT JOB	DW:	HIC VA	GHWAY	

105



DATE



DISCLAMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any is made by TXDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or domoges resulting from its use.

LEGEND					
Type 3 Borricode					
4	Sign				


Posled Speed X	Minimum Sign Spocing "X" Distance
30	120 [.]
35	160'
40	240'
45	320'
50	400'
55	500 [.]
60	600'
65	700 [.]
70	800'
75	900'

× Conventional Roads Only

GENERAL NOTES

- 1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
- 2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
- 3. Stockpiled materials shall not be placed on the traffic side of barricades.
- 4. Barricades at the road closure should extend from povement edge to povement edge.
- Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
- 6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
- The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
- 8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-30) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500, ET (CW20-3C) sign. 500 FT (CW20-3C) signs.
- 9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.

Те	✔* xas Departmer	nt of Tra	nsp	ortation	Ope Div	affic rations vision ndard
	ROAD	ETA	.0 LS	SURE		
FILE:	wzrcd-13.dgn	DN: Tx	DOT	CK: TxDOT DW:	TxDOT	ск: ТхDOT
	August 1995	CONT	SECT	JOB	н	GHWAY
© TxDOT			2 60 001 VARIO			
© TxDOT	REVISIONS	6462	60	001	1	/ARIOUS
© TxDOT 1-97 4-98	REVISIONS	6462 DIST	60	COUNTY		SHEET NO.



	LEGEND				
	Type 3 Barricade				
• • Channelizing Devices					
Ê	Trailer Mounted Flashing Arrow Boar	d			
-	Sign				
~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~	Safety glare screen				
DEPAR	TMENTAL MATERIAL SP	ECIFICATIONS			
DEPARTMENTAL MATERIAL SPECIFICATIONS SIGN FACE MATERIALS DMS-8300					

DMS-8600

DMS-8610

DELINEATORS AND OBJECT MARKERS

MODULAR GLARE SCREENS FOR HEADLIGHT BARRIER


Only pre-qualified products shall be used. A copy of the Compliant Work Zone Traffic Control Devices List"

CWZTCD)describes pre-qualified products and their sources and may be found at the following web address:

http://www.txdot.gov/business/resources/producer-list.html

ice	Texas Departmen	nt of Tra	nsp	ortation		Traffic perations Division tandard
o e on	TRAFFIC	CONT	R	DI PI		landara
)	TYPICA					
ote	w	Z(TI	D)	- 17		
orkers	FILE: wztd-17.dgn	dn: Tx	DOT	ск: ТхDOT	ow∶TxDO	Т ск: ТхDOT
le	© TxDOT February 1998	CONT	SECT	JOB		HIGHWAY
	REVISIONS 4-98 2-17	6462	60	001	<u>۱</u>	ARIOUS
	3-03	DIST		COUNTY		SHEET NO.
	7-13	PHR		VARIOUS		28

110



DISCLAMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any that is made by TxDOT for any purpose whatsaever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or domages resulting from its use.

LEGEND									
e 7 7 7	⊿	Туре 3	ype 3 Borricode				Channelizing) Devices	
	3	Heavy Work Vehicle					Truck Mounted Attenuator (TMA)		
			Mounte g Arrow		t I		Portable Changeable Message Sign (PCMS)		
					I	\diamondsuit	Traffic Flow		
-	Sign								
Posted Speed	Fa	ormula	Minimum Desirable Toper Lengths "L" x x 10: 11: 12:			Spo Chan	ed Maximum cing of nelizing evices On a	Suggested Longitudinal Buffer Space "B"	
			Offset	Offset	Offset	Toper	Tangent	_	
45			450'	495'	540'	45'	90'	195'	
50			500 [.]	550'	600'	50'	100'	240'	
55	Ι.	•ws	550 [.]	605 [,]	660'	55'	110'	295'	
60	יו	- 11 3	600 [.]	660 [.]	720 [.]	60'	120'	350 [.]	
65	1		650'	715'	780'	65 [.]	130'	4 10'	
70	1		700 [.]	770 [.]	840'	70 [.]	140'	475'	
75	1		750'	825'	900'	75 [.]	150'	540'	
80			800 [.]	880'	960'	80'	160'	615'	

x x Taper lengths have been rounded off. L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

TYPICAL USAGE							
MOBILE	E SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY						


GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "WERGE RIGHT," recommended speed, delay, exit information, or other specific warnings.
- 3. Where queuing is anticipated beyond signing shown, additional PCMS signs, other warning signs, devices or Law Enforcement Officers should be available to warn approaching high speed traffic of the end of the queue, as directed by the Engineer.
- Entrance ramps located from the advance warning area to the exit ramp should be closed whenever possible.
- The END ROAD WORK (G20-2) sign may be omilted when it conflicts with G20-2 signs already in place on the project.

A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the orea of crew exposure without adversely offecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation Traffic Operations Division Standard									
TRAFFIC CONTROL PLAN FREEWAY CLOSURE									
T T	CP(6	5-(6)-12						
FILE: tcp6-6.dgn	DN: T)	DOT	ск: TxDOT dw	: TxDOT	ск: TxDOT				
©⊺xDOT February 1994	CONT	SECT	JOB	HIC	HWAY				
REVISIONS 6462 60 001 VARIOUS									
RE VISIONS		1-97 8-98 DIST COUNTY SHEET NO.							
		– '	COUNTY						



- (1) Use Class 7 joint sealant in accordance with DMS-6310, "Joint Sealants and Fillers." Prepare joint and seal in accordance with Item 438 "Cleaning and Sealing Joints."
- Provide backer rod 25% larger than joint opening and compatible with the sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as shown.
- (3) Use Class 3 joint sealant in accordance with DMS-6310, "Joint Sealants and Fillers". Prepare joint and seal in accordance with Item 438 "Cleaning and Sealing Joints."
- 4 Backer rod must be compatible with the hot poured rubber sealant and rated for a minimum of 400°F.


GENERAL NOTES:


Cleaning existing joint opening (full depth) of all debris, providing and placing backer rod, saw-cutting asphalt overlay, and sealing joint is paid for by Item 438, "Cleaning and Sealing Joints" and measured by the linear foot. Obtain approval for all tools, equipment, materials and

- techniques proposed to clean and seal the joint. Provide Class 3 joint sealant in accordance with DMS-6310, "Joint Sealants and Fillers" for joints in asphalt overlay.
- Provide Class 7 joint sealants in accordance with DMS-6310, "Joint Sealants and Fillers" for joints in concrete.

Extend sealant up into rail or curb 3 inches on low side or sides of deck. If the Class 7 joint sealant cannot be effectively placed in the vertical position, a Class 4 joint sealant compatible with the Class 7 joint sealant is allowed for the extension of the seal into the curb or rail. Prepare surfaces where sealant is to be placed in accordance with Manufacturer's specifications.

SHEET 1 OF 3





- 3) Clean the voided region of all materials that could inhibit the bond between header material and concrete or steel.
- 4) Form the joint opening to the required width and place header material to fill voided region. Repair header material in accordance with Item 785, "Bridge Joint Repair or Replacement."
- 5) Place backer rod into joint opening 1" below the top of header material. When sealing joints for slab spans, slab beam spans, or box beam spans, fill void below backer rod with extruded polystyrene foam before placing backer rod.

See Detail "D"

-

Class 7 joint

(1)

 $\overline{(7)}$

Concrete slab

sealant

Field

verify

HEADER JOINT

WITH SILICONE SEAL

(used with ACP overlay with

joints more than 100 ft apart)

Field verify

(2)

Field verifv

(5)

DETAIL "D'


Cap

ACP overlay


Clean all debris from joint extending down

to the top of the cap.

6) Seal the joint opening with a Class 7 joint sealant. Recess seal 1/2" below top of header in travel lanes and $\frac{1}{4}$ " below top of header in shoulders.




- 1) Clean joint opening of all old expansion materials/devices, dirt, and all other deleterious materials in accordance with Item 438, "Cleaning and Sealing Joints." When sealing joints for slab spans, slab beam spans, pan girder spans, or box beam spans, fill void below proposed seal with extruded polystyrene foam.
- 2) Correctly size joint seal based on field measurement and in accordance with Manufacturer's specifications. Multiple seal widths may be required. Ensure proper seal is selected for each joint.
- 3) Abrasive blast clean existing joint surfaces where seal is to be applied.
- 4) Wipe down joint surfaces to remove contaminants.
- 5) Mask areas adjacent to joint opening sufficiently to keep epoxy off deck surface
- 6) Apply epoxy to joint opening side surfaces.
- 7) While epoxy is still tacky, remove shrink wrap from seal and install in joint opening.
- 8) Recess top of joint seal 1/2" in travel lanes and 1/4" in shoulders.
- 9) Inject silicone adhesive along top interface of seal with joint side surface according to Manufacturer's recommendations. Tool to spread adhesive as necessary. See Silicone Injection detail.



- 1 Use Class 7 joint sealant in accordance with DMS-6310, "Joint Sealants and Fillers." Prepare joint and seal in accordance with Item 438 "Cleaning and Sealing Joints."
- Provide backer rod 25% larger than joint opening and compatible with the sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as shown.
- 5 Match existing joint opening or set at a minimum: a. 1" at 70°F when the distance between joints is 150 ft or less b. 2" at 70°F when the distance between joints is greater than 150 ft. c. As directed by the Engineer
- (6) Cleaning and sealing existing header joints does not necessitate replacement of existing header material. If replacement of header material is necessary, as determined by the Engineer, use header material in accordance with DMS-6140, "Polymer Concrete for Bridge Joint Systems." Match the thickness of the header material with the thickness of the overlay as shown in the plans, but do not exceed 4". Place header material flush with roadway surface. Do not cantilever header material over the joint opening. Repair of header material will be paid for in accordance with Item 785-6006, "Bridge Joint Repair (Header)."
- (7) Maximum thickness is 4".
- 8 See table of Approved Precompressed Foam Seal Manufacturers on Sheet 3 of 3.





SHEET 2 OF 3


*

Bridge Division Texas Department of Transportation

CLEANING AND SEALING EXISTING BRIDGE JOINTS

FILE;		DN: RE		ск:	DW:	RE		ск:
CTXDOT	December 2023	CONT	SECT	JOB			HIG	HWAY
	REVISIONS	6462	60	001			VAF	RIOUS
		DIST		COUNTY			1	SHEET NO.
		PHR		VARIOUS	S			31

	TABLE OF ESTIMA	ATED QUANTIT	IES		
STRUCTURE NUMBER (FEATURE CROSSED)	JOINT TYPE	ITEM	DESCRIPTION	NUMBER OF JOINTS	QUANTITY (LF)
21-109-0255-07-043	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	6	348
21-109-0255-07-044	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	6	494
21-109-0255-07-046	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	5	332
21-109-0255-07-048	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	4	180
21-109-0255-07-049	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	4	240
21-109-0255-07-050	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	4	288
21-109-0255-07-053	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	4	280
21-109-0255-07-054	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL7)	4	280
21-109-0255-07-055	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	7	287
21-109-0255-07-293	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	1	57
21-109-0255-07-294	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	114
21-109-0255-07-295	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	114
21-109-0255-07-296	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	114
21-109-0255-08-060	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	140
21-109-0255-08-061	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	1	70
21-031-0039-08-232	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	110
21-031-0039-08-233	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	110
21-031-0039-08-226	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	14 4
21-031-0039-08-227	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	14 4
21-031-0039-08-353	EXPANSION	470 0004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	112
21-031-0039-08-354	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	112
21-031-0039-08-355	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL7)	2	112
21-031-0039-19-289	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL7)	2	122
21-031-0684-01-247	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	80
21-031-0684-01-250	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL7)	1	86
21-031-0684-01-253	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL7)	2	98
21-031-0684-01-256	EXPANSION	470 6004	CLEANING AND SEALING EXIST JOINTS(CL7)	1	98
21-031-0039-08-239	EXPANSION	470 0004	CLEANING AND SEALING EXIST JOINTS(CL7)	2	112
21-031-0039-07-125	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL7)	23	782
21-253-0038-04-058	EXPANSION		CLEANING AND SEALING EXIST JOINTS(CL3)	9	252
21-253-0038-04-095	EXPANSION	438-6004	CLEANING AND SEALING EXIST JOINTS(CL7)	7	574



APPROVED PRECOMPRESSED OAM SEAL MANUFACTURERS								
MANUFACTURER	SEAL TYPE							
Watson Bowman Acme	Wabo FS							
SSI	Silspec SES							
Sealtite	Sealtite 50N							

EMSEAL

BEJS

DATE







SHEET 3 OF 3


Bridge Division


CLEANING AND SEALING **EXISTING BRIDGE JOINTS**

Texas Department of Transportation

*

FILE:		dn: RE		ск:	DW:	RE		CK:
CTXDOT	December 2023	CONT	SECT	JOB			HIGHWAY	
	REVISIONS	6462	60	001			VAF	NOUS
		DIST	COUNTY			:	SHEET NO.	
		PHR		VARIOU	S			32





SHOWN AT CURB

OF

汝

EUGENE PALACIOS

105110

SSIONAL ENGLA

4/30/2

. .

- (1) Use Class 7 joint sealant. Prepare joint and seal in accordance with Item 438, "Cleaning and Sealing Joints.'
- 2 Provide backer rod 25% larger than joint opening and compatible with the sealant. Use of multiple pieces to create a backer rod cross section is not permitted. Top of backer rod must be convex as . shown
- (3) Backer rod may be omitted if existing joint depth is less than 1 $\frac{1}{2}$ ".
- (4) Backer rod must be compatible with the hot poured rubber sealant and rated for a minimum of 400°F.


GENERAL NOTES:

Cleaning existing joint opening (full depth) of all debris, providing and placing backer rod, saw-cutting asphalt overlay, and sealing joint is paid for by Item 438, "Cleaning and Sealing Joints" and measured by the linear foot. Obtain approval for all tools, equipment, materials and

techniques proposed to clean and seal the joint. Provide Class 7 joint sealant in accordance with DMS-6310, "Joint Sealants and Fillers" for joints in concrete.

Extend sealant up into rail or curb 3 inches on low side or sides of deck. If the Class 7 joint sealant cannot be effectively placed in the vertical position, a Class 4 joint sealant compatible with the Class 7 joint sealant is allowed for the extension of the seal into the curb or rail. Prepare surfaces where sealant is to be placed in accordance with Manufacturer's specifications.

Texas Departm	Bridge I Texas Department of Transportation							
EXISTING	CLEANING AND SEALING EXISTING BRIDGE JOINTS (PAN GIRDER BRIDGES)							
FILE:	DN: RE		CK:	DW:	RE	CK:		
CTxDOT December 2023	CTXDOT December 2023 CONT SECT JOB HIGHWAY							
REVISIONS	6462	60	001			VARIOUS		
	DIST		COUNTY			SHEET NO.		
	PHR VARIOUS 33							




HIDALGO COUNTY LOCATION MAP

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose wha TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


)A	LGO COUN	ITY BRIDGE	LOCATIONS						
	HIGHWAY	CROSSED FEATURE/ ROADWAY	GPS COORDINATES						
94	US 281 SB	RAYMONDVILLE DRAIN	26° 25'41.99"N, 98° 08'07.84"W						
93	US 281 NB	RAYMONDVILLE DRAIN	26° 25'38.88"N, 98° 08'07.51"W						
46	US 281 NB	BU 281 NB	26° 20'37.32"N, 98° 08'51.45"W						
48	FM 1925 NB	MONTE CRISTO RD	26° 20'7.25"N, 98° 08'42.34"W						
50	US 281 NB	CHAPIN ST	26° 18'49.96''N, 98° 08'47.83''W						
49	US 281 SB	CHAPIN ST	26° 18'48.90"N, 98° 08'48.34"W						
43	US 281 SB	UPRR (ABANDONED)	26° 18'37.42''N, 98° 08'46.89''W						
44	US 281 NB	UPRR (ABANDONED)	26° 18'34.32"N, 98° 08'45.83"W						
53	US 281 SB	SH 107	26° 17'58.28"N, 98° 08'49.20"W						
54	US 281 NB	SH 107	26° 17'55.83''N, 98° 08'48.81''W						
61	US 281 SB	FREDDY GONZALEZ DR	26° 17'5.36"N, 98° 08'58.39"W						
50	US 281 NB	FREDDY GONZALEZ DR	26° 17'3.08"N, 98° 08'57.96"W						

Texas Department of Transportation						
CLEAN AND SEAL JOINTS						
	LGO CATIC					
FILE:	DN: RRE		ск:	DW: RRE	ск:	
CTxDOT August 2017	CONT	SECT	JOE	3	HIGHWAY	
REVISIONS	6462	60	00	1	VARIOUS	
	DIST		COU	NTY	SHEET NO.	
	PHR		VARI	SUS	34	

	HIDA	LGO COU	NTY ESTIMA	ΓED	QUA	ΝΤΙΤΙ	ES			
BRIDGE NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REPAIR	TOTAL (LF)	TOTAL NO. OF REPAR BENTS	CLEANING AND SEALING EXIST JOINTS		
							BENTS	438		
								6001		
								LF		
1	0255-07-294	US 281 SB	RAYMONDVILLE	1	57	114	2	114		
•	0255-07-294	03 201 30	DRAIN	4	57		-	114		
2	0255-07-293	US 281 NB	RAYMONDVILLE DRAIN	4	57	57	1	57		
				1	68					
				2	69					
3	0255-07-046	US 281 NB	BU 281 NB	3	68	332	332 5	332	2 5	332
				4	65					
				5	62					
4	0255-07-048	FM 1925 NB	MONTE CRISTO RD	ALL	45	180	4	180		
5	0255-07-050	US 281 NB	CHAPIN ST	ALL	74	296	4	296		
6	0255-07-049	US 281 SB	CHAPIN ST	ALL	60	240	4	240		
7	0255-07-043	US 281 SB	UPRR (ABANDONED)	ALL	58	348	6	348		
				1	72					
				2	74					
8	0255-07-044	US 281 NB	UPRR (ABANDONED)	3	78	494	6	494		
0	0255-07-044	03 201 10		4	83	- 3-	0	+ 3 +		
				5	90					
				6	97					
9	0255-07-053	US 281 SB	SH 107	ALL	70	280	4	280		
10	0255-07-054	US 281 NB	SH 107	ALL	70	280	4	280		
11	0255-08-061	US 281 SB	FREDDY GONZALEZ DR	5	70	70	1	70		
12	0255 08 060	US 281 NB	FREDDY GONZALEZ DR	3	70	140	2	140		
12	0255-08-060	03 201 140	GONZALEZ DR	4	70	14U	۷	1 4 0		
							TOTAL	2861		



LOCATION 1 - 2



LOCATION 5 - 10

SEQUENCE OF CONSTRUCTION: 1. SETUP TCP.

- 2. PREPARE AND CLEAN JOINTS AS PER PLANS & SPEC.
- 3. SEAL JOINTS AS PER PLANS & SPEC.
- 4. REMOVE TCP ONCE SEAL HAS DRIED.
- 5. MOVE TO NEXT LOCATION/PHASE.

GENERAL NOTES:

LUCERO

DULCE SR


SAR


121

EBON

SR-


any ģ made of any kind is ş Practice exas standard is governed by DISCLAIMER: The use of this s TYDOT assume





ſΕ	RON COUN	NTY BRIDGE	LOCATIONS
	HIGHWAY	CROSSED FEATURE/ ROADWAY	GPS COORDINATES
•	US 77 NB	UPRR, BUS 77 & PRIMERA RD.	26° 13'40.01"N, 97° 43'15.53"W
5	US 77 NB	DRAINAGE DITCH, BUS 77 RR, & MATZ AVE.	26° 12'54.80''N, 97° 43'16.01''W
)	US 83	RVSC & PALM COURT DR.	26° 11'11.78"N, 97° 43'43.32"W
5	US 77 SB	ROBERTA RD.	26° 04'2.96"N, 97° 34'13.68"W
2	US 77 NB	ROBERTA RD.	26° 04'2.29"N, 97° 34'12.43"W
6	US 77 SB	CARMEN RD.	26° 03'23.25"N, 97° 33'43.97"W
L.	US 77 NB	CARMEN RD.	26° 03'22.62"N, 97° 33'44.22"W
5	US 77 SB	RANCHO VIEJO DR.	26° 02'34.15"N, 97° 32'49.89"W
5	US 77 SB	FM 511	26° 01'44.93"N, 97° 32'0.35"W
7	US 77 NB	FM 511	26° 01'44.57''N, 97° 31'59.48''W
9	US 77 NB	OLD ALICE RD	25° 59'25.83''N, 97° 31'15.48''W
,	SH 550 NB	DRAINAGE DITCH	26° 01'12.21''N, 97° 29'26.60''W
)	SH 550 NB	FM 1847	26° 00'49.45"N, 97° 28'52.52"W
5	SH 550 NB	UPRR •2 SPUR	25° 59'57.46"N, 97° 27'49.65"W
i	FM 511 NB	SH 550	25° 58'39.52"N, 97° 26'11.96"W
_			

N.T.S						
Image: StandardBridge DivisionImage: StandardStandard					Division	
CLEAN AND SEAL JOINTS CAMERON COUNTY LOCATION MAP						
FILE:	DN: RRE		ск.	DW: RRE	CK:	
CTxDOT August 2017	CONT	SECT	JOB		HIGHWAY	
REVISIONS	6462	60	001		VARIOUS	
	DIST		COUNTY		SHEET NO.	
	PHR		VARIOL	JS	36	





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whe TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

MERON C	COUNTY EST	IMA1	ED (QUAN	ITITIE	S
HIGHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REPAIR LENGTH	TOTAL (LF)	TOTAL NO. OF REPAR BENTS	CLEANING AND SEALING EXIST JOINTS 438
						6001
						LF
						Lr
US 77 NB	UPRR, BUS 77 & PRIMERA RD.	ALL	34	782	23	782
US 77 NB	DRAINAGE DITCH, BUS 77 RR, & MATZ AVE.	1 2 3 4 5 6	43	258	6	258
US 83	RVSC & PALM COURT DR.	1 4	56 66	122	2	122
US 77 SB	ROBERTA RD.	1 4	55	110	2	110
US 77 NB	ROBERTA RD.	1 4	55	110	2	110
US 77 SB	CARMEN RD.	1 4	56	112	2	112
US 77 NB	CARMEN RD.	1 4	56	112	2	112
US 77 SB	RANCHO VIEJO DR.	1 4	56	112	2	112
US 77 SB	FM 511	1 4	72	14.4	2	144
US 77 NB	FM 511	1 4	72	14.4	2	14.4
				SHEET	TOTAL	2006

GENERAL NOTES: Refer to Item 438 for application instructionn

Perform Traffic Control Operations as per TCP(6-6)-12






MERON (COUNTY EST	IMA1	IED (QUAN	ITITIE	S
HIGHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REP AIR LENGTH	TOTAL (LF)	TOTAL NO. OF REPAIR BENTS	CLEANING AND SEALING EXIST JOINTS
						438
						6001
						LF
US 77 NB	OLD ALICE RD	1	56	112	2	112
05 // 10		4			2	112
SH 550 NB	DRAINAGE DITCH	1	40	80	2	80
51 550 115		4	40		2	00
SH 550 NB	FM 1847	1	86	86	1	86
SH 550 NB	UPRR •2 SPUR	1	49	98	2	98
3H 330 ND	UPKK 2 SPUK	4 49	-9	30	2	30
FM 511 NB	SH 550	4	49	49	1	49
				SHEET	TOTAL	425

GENERAL NOTES: Refer to Item 438 for application instructionn

Perform Traffic Control Operations as per TCP(6-6)-12

N.T.S					
Texas Department	of Tra	nsp	ortation	D	ridge ivision tandard
CLEAN AND SEAL JOINTS CAMERON COUNTY					
2 OF 2					
FILE:	DN: RRE		ск:	DW: RRE	CK:
CTxDOT August 2017	CONT	SECT	JOB		HIGHWAY
REVISIONS	6462	60	001		VARIOUS
	DIST		COUNTY		SHEET NO.
	PHR		VARIOU	S	38




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


AP.	ATA COUN	TY BRIDGE L	OCATIONS				
	HIGHWAY	CROSSED FEATURE/ ROADWAY	GPS COORDINATES				
58	US 83 SB	ARROYO BURRO	27° 00'7.13"N, 99° 22'46.27"W				
95	US 83	ARROYO VELENO	26° 53'4.65"N, 99° 15'34.04"W				

N.T.S						
Texas Department of Transportation Standard				Division		
CLEAN AND SEAL JOINTS ZAPATA COUNTY LOCATION MAP						
FILE:	DN: RRE		ск:	DW: RRE	CK:	
CTxDOT August 2017	CONT	SECT	JOB		HIGHWAY	
REVISIONS	SIONS 6462 60 001 VARIOUS				VARIOUS	
	DIST		COUNTY		SHEET NO.	
	PHR		VARIOU	IS	39	

ZAPATA







- SEQUENCE OF CONSTRUCTION: 1. SETUP TCP.
- 2. PREPARE AND CLEAN JOINTS AS PER PLANS & SPEC.
- 3. SEAL JOINTS AS PER PLANS & SPEC.
- 4. REMOVE TCP ONCE SEAL HAS DRIED.
- 5. MOVE TO NEXT LOCATION/PHASE.

A COUNTY ESTIMATED QUANTITIES						
IIGHWAY	CROSSED FEATURE/ ROADWAY	BENT NO.	REPAIR LENGTH	TOTAL (LF)	TOTAL NO. OF REPAIR	CLEANING AND SEALING EXIST JOINTS
					BENTS	4 3 8
						6001
						LF
S 83 SB	ARROYO BURRO	1 4 8 12 16 24 27-28 30-31 34	28	308	11	308
US 83	ARROYO VELENO	1 3 6 9 12 15 17	82	574	7	574
					TOTAL	882

GENERAL NOTES: Refer to Item 438 for application instructionn

Perform Traffic Control Operations as per TCP(6-6)-12

N.T.S						
Texas Department of Transportation					Bridge Division Standard	
CLEAN AND SEAL JOINTS ZAPATA COUNTY						
FILE:	DN: RRE		ск:	DW: RRE	CK:	
CTxDOT August 2017	CONT	SECT	JOB		HIGHWAY	
REVISIONS	6462	60	001		VARIOUS	
	DIST		COUNTY		SHEET NO.	
	PHR		VARIOL	JS	40	

During the planning phase of project develop	ment, the following Environmental Permits,	Issues and Commitments have been	II. Clean Water Act, Sections 401 and 404 Complia	nce - Conlinued:
developed during coordination with resource orders and/or deviations from the final desig activities as additional environmental clearance	an must be reported to the Engineer prio	r to the commencement of construction	4. The Contractor's designated and qualified project site daily to ensue compliance will shall be provided to TxDOT within 48 hou	h SW3P and TPDE
I <u>. Clean Water Act, Section 402; Stormwater Po</u>	Dilution Prevention		5. 🗌 Other Project Specific Actions:	
Action Items Required :	🔀 No Action Required		1. Xxxxxxxx Yyyyyyyyy Zzzzzzzzz	
1. The contractor must implement the SW3 plans and maintained appropriately throw The SW3P may need to be revised as	uahout construction. BMPs must be in pla	s (BMPs) as indicated in the construction ce prior to the start of construction.	2. Xxxxxxxx Yyyyyyyyy Zzzzzzzzz	
2. For all construction PSL's off the ROW, regulations pertaining to the preservation	the contractor must certify compliance w on of cultural resources, natural resources	ith all applicable laws, rules and and the environment.		
3. 🗌 Based on the acreage of impact, select	the appropriate box below:		II. Cultural Resources	
therefore, a NOI and TPDES Site No	acre of soil and is not part of a larger co tice are not required for this project.	mmon plan of development;	Action Items Required : 1. Refer to the 2014 TxDOT Standard Speci Bridges, Item 7.7.1., in the event historica	fications For Cons lissues or archeolo
or	more than 1 acre of soilbut less than 5 (α and α is not	Upon discovery of archeological artifacts (area and contact the Engineer immediately	bones, burnt rock,
required but a TPDES Site Notice is	s required. The Construction Site Notice (accessible location for review by the publ	CSN) is required to be posted at	2. Other Project Specific Actions:	
or	accession receiver for review by the public		1. Xxxxxxxx Yyyyyyyy Zzzzzzzzzz	
This project will disturb equal to or The NOLand Site Notice are require	more than 5 acres of soil and will require ad to be posted at the construction site	a NOI and TPDES Site Notice. in a publicly accessible location		
4. Need to address MS4 requirements (Cameron & Hidalgo Counties only)	MS4 requirements no		2. Xxxxxxxx Yyyyyyyyy Zzzzzzzzz	
Conneron & Findingo Councies only			Ny Veneletine Deservene	
I. Clean Water Act, Sections 401 and 404 Comp	liance		IV. Vegelation Resources	
Action Items Rquired :	🔀 No Action Required		Action Items Required :	
1. Filling, dredging or excavating in any wa unless specified in the USACE permit an mitigation plans and BMPs required by	ter bodies, rivers, creeks, streams, wetland ad approved by the Engineer. The contra the NWP as regulated by the USACE.	ls or wet areas is prohibited ctor shall adhere to all agreements,	 In accordance with the 2014 TxDOT Stan install temporary or permanent seeding for for all seeding and replanting of right of w 	erosion controlas
The Contractor must adhere to all of th	e terms and conditions associated with t		 In accordance with Executive Order 13112 scaping, native species of plants shall be u for ruralroadways. (Required for Rural Set 	ised for all seeding
No Permit Required			3. Preserve vegetation where possible throu	ghout the project (
	quired (less than 1/10th acre waters or w		stream banks, bed and approach sections	5.
	ed (1/10th to <1/2 acre, 1/3 in tidalwate	rs)	4. Other Project Specific Actions:	
Individual 404 Permit Required			1. Xxxxxxxx Yyyyyyyyy Zzzzzzzzz	
Other Nationwide Permit Required: N				
2. The contractor is responsible for obtain construction methods that change Impac the water quality of the State will be mo	cts To Waters Of The U.S., including wetle) for Contractor initiated changes in Inds. The Contractor willensure that	2. Xxxxxxxx Yyyyyyyyy Zzzzzzzzz	
3. 🗌 Best Management Practices for applicabl	le Section 401 General Conditions:			
General Condition 12 - Categories Land L Category L(Erosion Control)	IBMPs required			
Temporary Vegetation	Interceptor Swale	Mulch Filter Berms and/or Socks		
Blankets, Matting	 Diversion Dike Erosion Control Compost 	 Compost Filter Berms and/or Socks Compost Blankets 		
Mulch Sodding	Erosion Control Compost	Compost Blankets		
Category II (Sedimentation Control)				
Silt FenceRock Berm	☐ Hay (Straw) Bale Dike ☐ Brush Berms	 Mulch Filter Berms and/or Socks Compost Filter Berms and/or Socks 	Pharr District Contact No. 956-702-6100	
— Triangular Filter Dike	Sediment Basins	Stone Outlet Sediment Traps	List of Abbrevia	
Sand Bag Berm	Erosion Control Compost		CGP: Construction General Permit PC	/P: Nationwide Permit N: Pre-Construction Notif J: Project Specific Locat
General Condition 21 - Category III BMPs Category III (Post-Construction TSS Con	required trol)		CKP'e: Contractor Responsible Person Environmental PS DSHS: Texas Department of State Health Services SF FEMA: Federal Emergency Management Agency SV FHWA: Federal Highway Administration TC MOA: Memorandum of Agreement TF MOU: Memorandum of Understanding TF MS4: Municipal Separate Stormwater Sewer System TF MSAT: Mobile Source Air Toxic Tx MBTA: Microtorx Tid Leadty. Act TX	L: Project Specific Locat CC: Spill Prevention Contro 13P: Storm Water Pollution
Vegetative Filter Strips	🗌 Wet Basins	Mulch Filter Berms and/or Socks		
 Retention/Irrigation Extended Detention Basin 	 Grassy Swales Vegetation-Lined Ditches 	 Compost Filter Berms and/or Socks Sand Filter Systems 	MUU: Memorandum of Understanding MS4: Municipal Separate Stormwater Sewer System MS4: Muhile Seurce Air Lovie	C: Texos Historical Comm DES:Texos Historical Comm DES:Texos Pollutant Disch WD:Texos Porks and Wild DOT:Texos Department of E: Threatened and Endan ACE:U.S. Army Corp of Er FWS:U.S. Fish and Wildlife
Constructed Wetlands	Erosion Control Compost	Sedimentation Chambers	MBAF Monie Source Arr Toxic 1x MBTA: Migrotory Bird Treoty Act 18 NOI: Notice of Intent US	E: Threatened and Endan
			NOI: Notice of Intent US NOT: Notice of Termination US	FWS:U.S. Fish and Wildlife

—X

—X

—X

onsible Person Environmental(CRPe) will monitor the DES General Permit TXR 150000. Daily Monitoring Reports with Item 506.3.1.

No Action Required


struction And Maintenance Of Highways, Streets, And ological artifacts are found during construction. (, flint, pottery, etc.) cease work in the immediate

No Action Required

ns:Item 164 - Seeding For Erosion Control:provide and as shown on the plans or as directed by the Engineer e. (Required for Urban Settings)

es and the Executive Memorandum on BeneficialLand-g and replanting of right of way where possible

and minimize clearing, grubbing and excavation within



ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)

		SHEET 1	OF 2
FED.RD. DIV.NO.		PROJECT NO.	HIGHWAY NO.
6			VARIOUS
STATE	DISTRICT	COUNTY	VARIOUS
TEXAS	PHR	VARIOUS	SHEET
CONTROL	SECTION	JOB	NO.
6462	60	001	41

Revised 01/30/2017

ification ation rol and Countermeasure ion Prevention Plan on Environmental Quality mission charge Elimination System /ildlife Department of Transportation T&E: Threatened and Endangered Species USACE:U.S. Army Corp of Engineers USFWS:U.S. Fish and Wildlife Service

V. FederalListed, and Proposed Threatened and Endangered Species, CriticalHabital, <u>State Listed Species, Candidate Species and Migratory Birds</u>	VI. Hozardous Materials on Contamination Issues - Continued:
Action Items Required :	Does the project involve any bridge class structure rehabilitation not including box culverts)?
1. X Under the Migratory Bird Treaty Act (MBTA) of 1918, codified at 16 U.S.C. 703-712 and as esforced by the USFWS, the proposed construction work will not remove active nests from bridges, trees, ground and other structures during migratory bird nesting season, (February 1st. through October 1st.). If the Contractor needs to perform work within the right of way during nesting season, a qualified Biologist shall conduct a survey to determine if active nests are present. If present, the Contractor shall maintain a buffer zone around the nest(s) as directed by the Biologist. The buffer zone will be protected from clearing and disturbance until such time as the Biologist has determined that the nest(s) is no longer active. Prior to the nesting season, existing bridges and culverts should be treated against migratory bird nesting by utilizing Bird Exclusion Methods. Bird Exclusion Methods	 Yes ∑No If "No", then no further action required. If "Yes", then TxDOT is responsible for completing an asbesto 3. Are the results of the asbestos inspection positive (is asbestos Yes ∑No
 2. There is the potential for the presence of state-listed species & species of concern in the project area and state law prohibits the taking (incidental or otherwise) of state-listed species. Taking is defined as the collection, hooking, hunting, netting, shooting, or share by any means or devices. If any listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. 	If "Yes", then TxDOT must retain a Texas Department of Stat consultant to assist with the notification, develop abatement/r activities as necessary. The notification form to DSHS must prior to scheduled abatement activities and/or demolition.
3. 🗌 Other Project Specific Actions:	If "No", then TxDOT is still required to notify DSHS 15 working
1. Xxxxxxxx Yyyyyyyy Zzzzzzzz	4. The Contractor is responsible for providing the date(s) for at careful coordination between the Engineer and an Asbestos Codelays and subsequent claims.
2. Xxxxxxxx Yyyyyyyy Zzzzzzzzz	
	VII. Other Environmental Issues
	Action Items Required :
3. Xxxxxxxx Yyyyyyyyy Zzzzzzzzz	1. 🗶 Noise
	Contractor shall make every reasonable effort to minimize co as work hour controls and proper maintenance of equipment r
	2. 🔀 Air
	Contractor shall practice common dust control techniques such unpaved road surfaces and vehicle speed reduction shall be in during construction.
I. Hazardous Malerials on Conlamination Issues	Contractor should minimize MSAT by utilizing measures to end
Action Items Required :	limits on idling, increase use of cleaner burning dieselengines, as appropriate.
General (applies to all projects):	
Comply with the Hazard Communication Act (HCA) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.	
Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the HCA.	
Maintain an adequate supply of on-site spill response materials as indicated in the MSDS. In the event of a spill, take immediate action to mitigate the spill as indicated in the MSDS and in accordance with safe work practices. Contact the TxDOT Pharr District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.	
Contact the Engineer if any of the following are detected:	
 Dead or distressed vegetation (identified as not normal) Trash piles, drums, canisters, barrels, etc. Undesirable smells or odors Evidence of leaching or seepage of contaminant substances 	
Any other evidence indicating possible hazardous materials or contamination discovered on site.	Pharr District Contact No. 956-702-6100
1. If potentially hazardous material and/or contaminated media (i.e.: soil, groundwater, surface water, sediment,	List of Abbreviations
building materials) are unexpectedly encountered during construction, assure that such materials and contami- nation are handled according to applicable federal and state regulations, cease work in the immediate area and contact the Engineer immediately.	BMP: Best Management Practice NWP: Nationwide Permit CGP: Construction General Permit PCN: Pre-Construction Notificat CRPe: Contractor Responsible Person Environmental PSL: Project Specific Location DSHS: Texas Department of State Health Services SPCC: Spill Prevention Control of FEMA: Federal Highway Administration TEGD: Texas Department FHWA: Federal Highway Administration TCED: Texas Schemission on E MOA: Memorandum of Understanding TPDES: Texas Pollutant Dischar MO4: Memorandum of Understanding TPWD: Texas Pollutant Dischar MS4: Municipal Separate Stormwater Sever System Tx0D1: Texas Department of T MBTA: Migratory Bird Treaty Act T&E: Threatened and Endange NOI: Notice of Intent USACE:U.S. Frish and Wildlife NOT: Notice of Termination USFWS:U.S. Fish and Wildlife

—X

—X

—X

ion or replacements (bridge class structures

tos assessment/inspection.

os present)?

te Health Services (DSHS) licensed asbestos mitigation procedures, and perform management at be postmarked at least 15 working days

ng days prior to any scheduled demolition.

batement activities and/or demolition with consultant in order to minimize construction

lo Action Required

onstruction noise through abatement measures such mufflers.

h as surface chemical treatment or watering of implemented to minimize and prevent airborne dust

ncourage use of EPA required cleaner dieselfuels, and other emission limitation techniques,



ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)

		SHEET 2	OF 2	
FED.RD. DIV.NO.		HIGHWAY NO.		
6			VARIOUS	
STATE	DISTRICT	COUNTY	VARIOUS	
TEXAS	PHR	VARIOUS	SHEET	
CONTROL	SECTION	JOB	NO.	
6462	60	001	42	

Revised 01/30/2017

cation and Countermeasure Prevention Plan Environmental Quality ssion Irge Elimination System ife Department Transportation pered Species gineers Service

TPWD BMPs

_X

Under Section 12.0011 of the Texas Parks and Wildlife Code, Texas Parks and Wildlife Department (TPWD) is charged with "providing recommendations that will protect fish and wildlife resources to local, state, and federal agencies that approve, permit, license, or construct developmental projects" and "providing information on fish and wildlife resources to any local, state, and federal agencies or private organizations that make decisions affecting those resources."

The purpose of this section is to provide beneficial management practices (BMP) that should be implemented during construction, and maintenance activities statewide for transportation projects with the goal of avoidance and minimization of impacts to natural resources. Statewide Standard BMP pertain to all fish and wildlife species, including state-listed species and other Species of Greatest Conservation Need (SGCN). Implementing the recommendations as outlined below will improve conservation of species and their habitat.

- General Design/Construction BMPs
 - Prior to start of construction, information will be provided to personnel of the potential for all state-listed threatened species or other SGCN to occur within the project area and should be advised of relevant rules and regulations to protect plants, fish, and wildlife.
 - Contractor should avoid harming all wildlife species if encountered and allow them to safely leave the project site. Due diligence should be used to avoid killing or harming any wildlife species in the implementation of transportation projects.
 - Contractors should install wildlife exclusion fencing and should examine the inside of the exclusion area daily to determine if any wildlife species have been trapped inside the area of impact and provide safe egress opportunities prior to initiation of construction activities.
 - Apply hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas around wetlands and in riparian areas.
 - Contractor should use woven natural fiber netting in which the mesh design allows the threads to move, therefore allowing expansion of the mesh openings. Plastic netting should be avoided.
 - Project staging areas, stockpiles, temporary construction easements, and other project related sites should be situated in previously disturbed areas to avoid or minimize impacts to sensitive or unique habitats including intact native vegetation, floodplains, riparian corridors, wetlands, playa
 - lakes, and habitat for wildlife species. pollution and incorporating dark-sky practices into design strategies. Minimize sky glow by focusing light downward, with full cutoff luminaries to avoid light emitting above the horizontal. The minimum amount of night-time lighting needed for safety and security should be used.

Vegetation BMPs

- Minimize the amount of vegetation cleared. Removal of native vegetation, particularly mature native trees and shrubs should be avoided. Impacted vegetation should be replaced with in-kind on- site replacement /restoration of native vegetation.
- \square It is strongly recommended that trees greater than 12 inches in diameter at breast height (DBH) that are removed be replaced. TPWD $\frac{5}{32}$ s experience indicates that for ecologically effective replacement, a ratio of three trees for every one (3:1) lost should be provided to either on-site or off-site. Trees less than 12 inches DBH should be replaced at a 1:1 ratio.
- The use of any non-native vegetation in landscaping and revegetation is discouraged. Locally adapted native species should be used.
- \square The use of seed mix that contains seeds from only regional ecotype native species is recommended

Invasive Species BMPs

- For all work in water bodies designated as $\frac{3}{32}$ infested $\frac{5}{32}$ or $\frac{3}{32}$ positive $\frac{5}{32}$ for invasive zebra (Dreissena polymorpha) OR quagga mussels (Dreissena bugensis) as well as waters downstream of these lakes, all machinery, equipment, vessels, or vehicles coming in contact with such waters should be cleaned prior to leaving the site to remove any mud, plants, organisms, or debris, water drained (if applicable), and dried completely before use in another water body to prevent the potential spread of invasive mussels. Care should be taken to prevent the spread of aquatic and
- \square
- terrestrial invasive plants during construction activities. Care should be taken to avoid the spread of aquatic invasive plants such as giant Salvinia (Salvinia molesta), common \square salvinia (Salvinia minima), hydrilla (Hydrilla verticillata), water hyacinth (Eichhornia spp.), Eurasian watermilfoil (Myriophyllum spicatum), water lettuce (Pistia stratiotes), and alligatorweed (Alternanthera philoxeroides) from infested water bodies into areas not currently infested. All machinery, equipment, vessels, boat trailers, or vehicles coming in contact with waters containing aquatic invasive plant species should be cleaned prior to leaving the site to remove all aquatic plant material and dried completely before use on another water body to prevent the potential spread of invasive plants. Removed plants should be transported for disposal in a secure manner to prevent dispersal.
- Only native or non-invasive plants should be planted. Care should be taken to avoid mowing invasive giant school be planted. Carundo donax), which spreads by fragmentation, and to clean equipment if inadvertently mowed to prevent spread. If using hav bales for sediment control, use locally grown weed-free hay to prevent the spread of invasive species. Leave the hay bales in place and allow them to break down, as this acts as mulch assisting in revegetation.

□ Stream Crossings BMPs

Riparian buffer zones should remain undisturbed.

Dewatering BMPs

Impact avoidance measures for aquatic organisms, including all native fish and freshwater mussel species, regardless of state-listing status, should be considered during project planning and construction activities.

□ Wildlife Crossing BMPs

Incorporate wildlife crossings with fencing, particularly in areas that bisect wildlife travel corridors or seasonal movement routes to avoid further habitat fragmentation and minimize wildlife-vehicle interactions.

Rare Plant BMPs

BMP: Best Management Practice

Avoid impacts and minimize unavoidable impacts. Plant locations should be protected with temporary barrier fencing and contractors should be instructed to avoid protected areas. Conducting construction outside of the growing season or after a plant has produced mature fruit is the preferred way to avoid/minimize impacts to SGCN plant populations. Staging areas, stockpiles, and other project related sites on TxDOT ROW should not impact SGCN plant populations. After construction begins, minimize herbicide use near SGCN plant populations (if possible, use hand-held spot sprayers, several meters from rare plants, on still or days with little wind).

Pharr District Contact No. 956-702-6100

List of Abbreviations

MSAT: Mobile Source Air Toxic CCP: Construction Ceneral Permit CRPe: Contractor Responsible Person Environmental DSHS: Texas Department of State Health Services MBTA: Migratory Bird Treaty Act NOI: Notice of Intent NOT: Notice of Termination FEMA: Federal Emergency Management Agency NWP: Nationwide Permit PCN: Pre-Construction Notification FHWA: Federal Highway Administration MOA: Memorandum of Agreement PSL: Project Specific Location SPCC: Spill Prevention Control and Countermeasure MOU: Memorandum of Understanding MS4: Municipal Separate Stormwater Sewer System SW3P: Storm Water Pollution Prevention Plan

TCEQ: Texas Commission o THC: Texas Historical Comm TPDES:Texas Pollutant Disch [PWD: Texas Parks and Wile TxDOT:Texas Department of T&E: Threatened and Endar USACE:U.S. Army Corp of E USFWS:U.S. Fish and Wildlife

ed:

--X

Rare Plants BMPs (Continued)

☐ If there are unintended impacts to SGCN populations, these impacts should be reported to TPWD Transportation Staff. During project period, conduct work during times of the year when plants are dormant and/or conditions minimize disturbance of the habitat.

 \square

🕱 Bird BMPs

 \square

 \square

 \square

 \square

- Avoid vegetation clearing activities during the general bird nesting season, February 15th to October 1st to minimize adverse impacts to birds.
 - Do not collect, capture, relocate, or transport birds,
 - eggs, young, or active nests without a permit. Minimize extended human presence near nesting birds during construction and maintenance activities. Protect sensitive habitat areas with temporary barriers or fencing to limit human foot- traffic and off-road vehicle
 - use to alert and discourage contractors from causing any unintentional impacts.
 - Minimize construction noise above ambient levels during general bird nesting season to minimize adverse impacts on birds.
 - Minimize construction lighting during the general bird nesting season by scheduling work activities between dawn and dusk.

🗌 Rookeries BMPs

In general, nesting dates for herons and egrets range from early February to late August in Texas, depending on the species. Great blue herons (GBHE) (Ardea herodis) are usually the first to nest. When GBHE get disrupted from the nest and abandon nesting, then the other species of herons and egrets may not attempt to nest at the colony that year. If rookeries are encountered, avoid and minimize disturbance during nesting to protect rookery species and their habitat

Vegetation clearing in a primary buffer area of 300 meters (984 feet) from a rookery or heronry periphery should be avoided. Utilizing areas that have already been cleared within this buffer area may be acceptable depending on site-specific characteristics. Additionally, human foot-traffic or machinery use should not occur within this buffer area during the nesting season.

Clearing activities or construction using heavy machinery in a secondary buffer area of 1000 meters (3281 feet) from the heronry periphery should be avoided during the breeding season (courting and nesting).

	PHARR DISTRICT			
	EPIC	SHEET	SUPPLEME	NTALS
Revised 02/24/2022		TPW	D BMP	5
			SHEET	1 OF 3
on Environmental Quality	FED.RD. DIV.NO.	PROJECT NO.		HIGHWAY NO.
charge Elimination System	6			VARIOUS
Vildlife Department of Transportation	STATE	DISTRICT	COUNTY	VARIOUS
angered Species Engineers	TEXAS	PHR	VARIOUS	SHEET
Engineers fe Service	CONTROL	SECTION	JOB	NO.
	6462	60	001	43

🗌 Fish BMPs

_X

—X

- $\hfill \Box$ The following Fish BMP apply to projects for all fish species in waters of the state to minimize impacts to water quality and aquatic passage from transportation projects.
- \square For projects in waters of the state and work is adjacent to water: follow Water Quality and Stream Crossing BMPs.
- For projects in waters of the state and work is in the water:
- follow Water Quality, Stream Crossing, and Dewatering BMP.

Aquatic Invertebrate BMPs

- For projects within the range of a SGCN or state-listed species and work is adjacent to water: Water Quality and Stream Crossing BMP
- For projects within the range of a SGCN or state-listed species and work is in the water: Water Quality, Stream Crossing, and Dewatering BMP.
- For spring-seep associated caddisflies (Cheumatopsyche morsei, Chimarra holzenthali, and Hydroptila ouachita): Avoid or minimize impacts to the natural riparian buffer along stream channelincluding native shrubs and trees.

Cravfish BMP

- For projects within the range of a SGCN or state-listed species and work is adjacent to water: Water Quality and Stream Crossing BMP.
- For projects within the range of a SGCN or state-listed species and work is in the water: Water Quality, Stream Crossing, and Dewatering BMP.
- Avoid or minimize impacts to the natural riparian buffer that provides terrestrial and aquatic plant matter for the diet of most crayfish species.

Freshwater Mussel BMP

- □ In addition to Water Quality and Stream Crossing BMP, follow the most recent, 1/32TPWD¹³/32TxDOT Annual Work Plan for Pre-Construction Surveys, Aquatic Resources Relocations, and Other Best Management Practices to Avoid, Minimize, and
- Mitigate Impacts to Freshwater Resources.⁷₃₂ When work is adjacent to the water: Water Quality BMP implemented as part of the Texas Commission on Environmental Quality (TCEQ) Stormwater Pollution Prevention Plan (SWPPP) for a construction general permit or any conditions of the 401 Water Quality Certification for the project will be implemented.

Insect Pollinator BMP

- Deep soil disturbances, such as, tilling or deep disking in areas that host aggregations of ground- nesting bees should be avoided. Tilling and disking also may promote the invosion or germination of non-native plants. Different species of native ground-nesting bees prefer different soil conditions, although research suggests that many ground nesting bees prefer sandy, loamy sand or sandy loam soils. In areas with these soil types consider leaving open patches of soil.
- Allow dead trees to stand (so long as they do not pose a risk to property or people) and protect shrubs and herbaceous plants with pithy or hollow stems (e.g., cane fruits, sumac, elderberry), as these provide nesting habitat for tunnel-nesting native bees. Retain dead or dying branches whenever it is safe and practical at the edges of the ROW. Wood- boring beetle larvae often fill dead trees and branches with narrow tunnels into which tunnel- nesting bees will establish nests. Additionally, bumble bees may choose to nest in wood
- Retain rotting logs at edges of the ROW where some bee species may burrow tunnels in which to nest.

□ Insect Pollinator BMP (Continued)

- Protect sloped or well-drained ground sites where plants are sparse and direct access to soil is available. These are the areas where around-nesting bees may dig nests. Turning the soil destroys all around nests that are present at that depth and hinders the emergence of bees that are nesting deeper in the ground.
- Protect grassy thickets, or other areas of dense, low cover from mowing or other disturbance. These are the sites where bumble bees might find the nest cavities they need, as well as annual and perennial wildflowers that can provide important food resources.
- Where available and economical, native plants and seed should be procured from local eco-type providers. Seed mixes should be diverse and include as many ecoregion natives as possible ensuring full season floral resources. Species by Texas corregion can be found in the Texas Management Recommendations for Native Insect Pollinators in Texas document: https://tpwd.texas.gov/publications/pwdpubs/media/pwd_bk_w7000_1813.pdf
- Planting at least three different native flowering plants within each of three blooming periods are recommended (spring, summer, early fall) in high rainfall regions of Texas. In drier regions of the state, a target of three native flowering plants within each of two blooming periods can be used.

Small Mammal BMP

For Coues' rice rat (Oryzomys couesi aquaticus):

- Minimize impacts to wetland, resaca, oxbow Conversion of property containing cave or cliff features to transportation purposes should be avoided lake, and marsh habitats
- Water Quality BMP

🗌 Fossorial Mammal BMP

MOU: Memorandum of Understanding MS4: Municipal Separate Stormwater Sewer System

- When a construction zone is adjacent to active BTPD burrows or pocket gopher mounds, erect barriers to discourage individuals moving through or into the construction area.
- \square When seeding or revegetation is planned in an area adjacent to BTPD burrows or pocket gopher mounds, a vegetative barrier should be considered in the planting to discourage dispersalinto the ROW

🗶 <u>Bat BMP</u>

- For activities that have the potential to impact structures, cliffs or caves, or trees; a qualified biologist will perform a habitat assessment and occupancy survey of the feature(s) with roost potential as early in the planning process as possible or within one year before project letting.
- For roosts where occupancy is strongly suspected but unconfirmed during the initial survey, revisit feature(s) at most four weeks prior to scheduled disturbance to confirm absence of bats. \square
- If bats are present or recent signs of occupation (i.e., piles of guano, distinct musky odor, or staining and rub marks at potential entry points) are observed, take appropriate measures to ensure that bats are not harmed, such as implementing non-lethal
- exclusion activities or timing or phasing of construction. Exclusion devices can be installed by a qualified individual between September 1 and March 31. Exclusion devices should be used for a minimum of seven days when minimum nighttime temperatures are above 50°F AND minimum daytime temperatures are above 70°F. Prior to exclusion, ensure that alternate roosting habitat is available in the immediate area. If no suitable roosting habitat is available, installation of alternate roosts is recommended to replace the loss of an occupied roost. If alternate roost sites are not provided, bats may seek shelter in other inappropriate sites, such as buildings, in the surrounding area.

Pharr District Contact No. 956-702-6100

BMP: Best Management Practice CCP: Construction Ceneral Permit CRPe: Contractor Responsible Person Environmental DSHS: Texas Department of State Health Services FEMA: Federal Emergency Management Agency FHWA: Federal Highway Administration MOA: Memorandum of Agreement

MSAT: Mobile Source Air Toxic MBTA: Migratory Bird Treaty Act NOI: Notice of Intent NOT: Notice of Termination NWP: Nationwide Permit PCN: Pre-Construction Notification PSL: Project Specific Location SPCC: Spill Prevention Control and Countermeasure SW3P: Storm Water Pollution Prevention Plan

List of Abbreviations

TCEQ: Texas Commission a THC: Texas Historical Com TPDES:Texas Pollutant Disc [PWD: Texas Parks and Wi TxDOT:Texas Department o T&DOT:Texas Department o T&E: Threatened and Enda USACE:U.S. Army Corp of E USFWS:U.S. Fish and Wildlife

Printed:

—X

Bat BMP (Continued)

 \square

 \square

 \square

 \square

If feature(s) used by bats are removed as a result of construction, replacement structures should incorporate bat-friendly design or artificial roosts should be constructed to replace these features.

Avoid unnecessary removal of dead fronds on native and ornamental palm trees in south Texas (Cameron, Hidalgo, Willacy, Kenedy, Brooks, Kleberg, Nueces, and San Patricio counties) from April 1 through October 31. If removal of

dead fronds is necessary at other times of the year, limit frond removal to extended warms periods (nighttime temperatures = 55°F for at least two consecutive nights), so bats can move away from the disturbance and find new roosts.

Large hollow trees, snags (dead standing trees), and trees with shaqqy bark should be surveyed for colonies and, if found, should not be disturbed until the bats are no longer occupying these features. Post-occupancy surveys should be conducted by a qualified biologist prior to tree removal from the landscape.

Retain mature, large diameter hardwood forest species and native/ornamentalpalm trees.

In all instances, avoid harm or death to bats. Bats should only be handled as a last resort and after communication with TPWD.

Aquatic Amphibian and Reptile BMP

For projects within existing right-of-way (ROW) when work is in water or will permanently impact a water feature and potential habitat exists for the target species complete the following:

 \Box Minimize impacts to wetlands, temporary and permanent open water features, including depressions, and riverine habitats.

Maintain the existing hydrologic regime and any connections between wetlands and other aquatic features.

Use barrier fencing to direct animal movements away from construction activities and areas of potential wildlife-vehicle collisions in construction areas directly

adjacent, or that may directly impact, potential habitat for the target species.

Apply hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas around wetlands and in riparian areas. If erosion control blankets or mats will be used, the product should not contain netting, but should only contain loosely woven natural fiber netting in which the mesh design allows the threads to move, therefore allowing expansion of the mesh openings. Plastic netting should be avoided.

Project specific locations (PSLs) proposed within state-owned ROW should be located in uplands away from aquatic features.

When work is directly adjacent to the water, minimize impacts to shoreline basking sites (e.g., downed trees, sand bars, exposed bedrock) and refugia/overwinter sites (e.g., brush and debris piles, crayfish burrows, aquatic logiams, and leaf packs).

	PHARR DISTRICT			
	EPIC	SHEET	SUPPLEMEN	TALS
TPWD BMPs				
Revised 02/24/2022				
			SHEET 2	2 OF 3
on Environmental Quality Imission	FED.RD. DIV.NO.			HIGHWAY NO.
charge Elimination System Vildlife Department	6			
Vildlife Department of Transportation	STATE	DISTRICT	COUNTY	VARIOUS
angered Species	TEXAS	PHR	VARIOUS	SHEET
Engineers fe Service	CONTROL	SECTION	JOB	NO.
	6462	60	001	44

Aquatic Amphibian and Rootile RNR (Continued)	Terrestrial Amphibian and Restile RMD (Continued)	OTHER PERTIN
Aquatic Amphibian and Reptile BMP (Continued) If gutters and curbs are part of the roadway design, install gutters that do not include the side box inlet and include sloped (i.e., mountable) curbs to allow small animals to leave roadway. If this modification to the entire curb system is not possible, install sections of sloped curb on either side of the storm water drain for several feet to allow small animals to leave the roadway. Priority areas for these design recommendations are those with nearby wetlands or other aquatic features.	☐ <u>Terrestrial Amphibian and Reptile BMP (Continued)</u> ☐ After project is complete, revegetate disturbed areas with an appropriate locally sourced native seed mix. If erosion control blankets or mats will be used, the product should not contain nylon netting, but should only contain loosely woven natural fiber netting in which the mesh design allows the threads to move, therefore allowing expansion of the mesh openings. Plastic netting should be avoided.	☐ <u>Trifold Availab</u> ☐ Ocelot ☐ Pelicar ☐ Ashy o
For projects that require acquisition of additional ROW and work within that new ROW is in water or will permanently impact a water feature, implement BMP for projects within existing ROW above plus those below:	Black-spotted newt/Mexican Burrowing toad/ Mexican treefrog/ <u>Strecker's chorus frog/White-lipped frog/Woodhouse's toad</u> Aquatic Amphibian and Reptile BMP Terrestrial Amphibian and Reptile BMP Water Quality BMP Vegetation BMP	☐ Mitigat ☐ Texas ☐ Harves
 For sections of roadway adjacent to wetlands or other aquatic features, install wildlife barriers that prevent climbing. Barriers should terminate at culvert openings in order to funnel animals under the road. The barriers should be of the same length as the adjacent feature or 80 feet long in each direction, or whichever is the lesser of the two. For culvert extensions and culvert replacement/installation, incorporate measures to funnel animals toward culverts such as concrete wingwalls and barrier walls with overhangs. When riprap or other bank stabilization devices are necessary, their placement should not impede the movement of terrestrial or aquatic wildlife through the water 	Sheep Frog Minimize disturbance to burrows or downed woody debris Aquatic Amphibian and Reptile BMP Terrestrial Amphibian and Reptile BMP Water Quality BMP Vegetation BMP South Texas Siren (Large Form) Minimize impacts to warm, shallow waters with vegetative cover such as ponds and ditches	
feature. Biotechnical streambank stabilization methods using live native vegetation, or a combination of vegetative and structural materials should be used.	Aquatic Ámphibian and Reptile BMP Water Quality BMP Black-striped snake/ Eastern box turtle/Northern cat-eyed snake/Plateau spot-tailed earless lizard/ Reticulate collared lizard/ Slender glass lizard/ Speckler racer/Tamgulipan spot-tailed earless	
 For open trenches and excavated pits, install escape ramps at an angle of less than 45 degrees (1:1) in areas left uncovered. Visually inspect excavation areas for trapped wildlife prior to backfilling Avoid or minimize disturbing or removing cover objects, such as downed trees, rotting stumps, brush piles, and leaf litter. If avoidance or minimization is not practicable, consider removing cover objects prior to the start of the project and 	lizard/ Texas Indigo snake/ Western box turtle/Western hognose <u>snake/Western massasauga</u> Terrestrial Amphibian and Reptile BMP Vegetation BMP <u>Rio Grande River Cooter</u>	
replace them at project completion. Examine heavy equipment stored on site before use, particularly after rain events when reptile and amphibian movements occur more often, to ensure use will not harm	Aquatic Amphibian and Reptile BMP Water Quality BMP	
 individuals that might be seeking temporary refuge. Due to increased activity (mating) of reptiles and amphibian during the spring, construction activities like clearing or grading should attempt to be scheduled outside of the spring (March-May) season. Also, timing ground disturbing activities before October when reptiles and amphibians become less active and may be using burrows in the project area is also encouraged. 	 <u>Texas Horned Lizard</u> Avoid harvester ant mounds in the selection of Project Specific Locations (PSLs). Terrestrial Amphibian and Reptile BMP Vegetation BMP 	
If Texas tortoises (Gopherus berlandieri) or box turtles (Terrepene spp.) are present in a project area, they should be removed from the area and relocated between 100 and 200 meters from the project area. After removal of the individuals, the area that will be disturbed during active construction and project specific locations should be fenced off to exclude reentry by turtles, tortoises, and other reptiles. The exclusion fence should be constructed and maintained as follows:	 <u>Texas Tortoise</u> Utility trenches should be covered overnight or visually inspected before filling to avoid burial of the species Terrestrial Amphibian and Reptile BMP Vegetation BMP 	
 The exclusion fence should be constructed with metal flashing or drift fence material. Rolled erosion control mesh material should not be used. The exclusion fence should be buried at least 6 inches deep and be at least 24 inches high. The exclusion fence should be maintained for the life of 	Pharr District Contact No. 956-702-6100	
 The exclusion rence should be maintained for the life of the project and only removed after the construction is completed and the disturbed site has been revegetated. 	List of Abbreviations BMP: Best Management Practice MSAT: Mobile Source Air Toxic CGP: Construction General Permit MBTA: Migratory Bird Treaty Act CRPe: Contractor Responsible Person Environmental NOI: Notice of Intent DSHS: Texas Department of State Health Services NOI: Notice of Termination FEMA: Federal Emergency NWP: Notionwide Permit FHWA: Federal Highway Administration PCN: Pre-Construction Notification MOU: Memorandum of Agreement SPCC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPCC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPC: Splil Prevention Control and Countermeasure MOU: Memorandum of Lagreement SPC: Splil Prevention Control and Countermeasure	ICEQ: Texas Commission on E THC: Texas Historical Commis TPDES: Texas Pollutant Dischar TPWD: Texas Parks and Wildlif TxDOT: Texas Department of T&E: Threatened and Endange USACE:U.S. Army Corp of Eng USFWS:U.S. Fish and Wildlife S

—X

—X

-X

TINENT INFORMATION

able

ot information an information ' dogweed

Available

atory Bird Treaty Act as Tortoise vester Ants and Horn Lizards

	-	TPW	D BMPs	5
Revised 02/24/2022	2			
			SHEET	3 OF 3
n on Environmental Quality ommission	FED.RD. DIV.NO.	PROJECT NO.		HIGHWAY NO.
ischarge Flimingtion System	6			
Wildlife Department t of Transportation ndangered Species of Engineers dlife Service	STATE	DISTRICT	COUNTY	VARIOUS
	TEXAS	PHR	VARIOUS	SHEET
	CONTROL	SECTION	JOB	NO.
	6462	60	001	45
		•		

PHARR DISTRICT

EPIC SHEET SUPPLEMENTALS