## SEE SHEET 2 FOR INDEX OF SHEETS

# STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED


# HIGHWAY ROUTINE MAINTENANCE CONTRACT

## TYPE OF WORK:

VAN HORN AND DELL CITY MOWING

> PROJECT NO.: RMC 6466-22-001 ALPINE AREA OFFICE

HIGHWAY: IH 10, ETC. LIMITS OF WORK: VARIOUS



EXCEPTIONS: N/A EQUATIONS: N/A RAILROAD CROSSINGS: N/A

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

	STATE MAINTENANCE PROJECT NO.				
	6466-22-001				
CONT	CONT SECT JOB HIGHWAY				
6466	5 22	001	ΙH	10, E	TC.
DIST		COUNTY		SHEET	NO.
ELP	CU	LBERSON,	ETC.	1	



RECOMMENDED FOR LETTING:	4/15/2024
DocuSigned by:	
Norma Dur	an
MAINTENANC 35824181EB4D451	MANAGER
APPROVED FOR LETTING: DocuSigned by: DIRI 2D8D99B8F78048	4/15/2024 drid, P.E.

# INDEX OF SHEETS

# SHEET NO.DESCRIPTIONGENERAL11TITLE SHEET2INDEX OF SHEETS2CENERAL NOTES

- 3 GENERAL NOTES
- 4 ESTIMATE & QUANTITY
- 5 LOCATION TABLE

## TRAFFIC CONTROL PLAN

6-17 BC (1) - 21 THRU BC (12) -21

- 18 RS TCP 05
- 19 TCP (1-1) 18
- 20 TCP (5-1)-18

i. V	N	*',		
CYNTHIA M.	BALD			
150	0695			
Nor LICE	INSED.	CALL OF		
SION	ALEN	منزن م		
	1110			
THE STANDARD SHEE	ETS SF	PECIFICAL	LY	
IDENTIFIED ON THI				
BY ME AND ARE APP	PLICAE	BLE TO TH	IS P	ROJECT.
	$\square$			
	mu	2	4/1	0/2024 E
	P		DAT	E
/				
	GE	NERAL		
	Y (	OF SH		тс
INDL	.^ `			
		Sн	ЕЕТ	1 OF 1
	<b>*</b> ®	511		
		partment of Tra		
CONT	SECT	JOB	LL MIGNT	HIGHWAY
			7.1.1	10 570
6466	22	001	IH	10, ETC.
6466 DIST ELP		OO1 COUNTY		SHEET NO.

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

#### **GENERAL NOTES:**

General Project Description – This routine maintenance contract is for mowing highway rightof-way on various highways in Culberson and Hudspeth Counties.

The Contract will be managed by the Alpine Area Office with participating Area Engineer (AE) and Maintenance Section Supervisor (MSS) listed below:

Rene Romero, P.E., East AE 1430 Joe Battle Blvd. El Paso, Texas 79936 (915) 757-5910

Javier Castillo, Dell City/Pine Springs MSS 600 South Main Dell City, Texas 79837 (915) 964-2345

Armando Ramirez, P.E., Alpine AE 2400 N. SH 118 Alpine, Texas 79830 (915) 217-5257

Rudy Valdez, Van Horn/Sierra Blanca MSS US 90, 1.5 Miles S of IH 10 Van Horn, Texas 79855 (432) 283-2501

Each Contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process all contracts at the same time.

#### **General Requirements**

Various bid items and their associated quantities have been provided within this Contract to establish unit bid prices for the proposed work. The bid items and quantities provided are based on historical data and are not guaranteed. Actual guantities of work to be performed and paid will be determined in the field by the Engineer and will be paid utilizing these unit bid prices with no further compensation made regardless of the final quantities.

Maintain the entire project area in a neat and orderly manner throughout the duration of the work. Remove all construction litter and undesirable vegetation within the right of way inside the project limits. This work will be subsidiary to the various bid items.

All lane closures and traffic control items, except truck mounted attenuators (TMA) and portable changeable message signs (PCMS), required to accomplish work under this Contract will not be paid for directly but will be subsidiary to the various bid items. TMAs will be measured and paid as described in Special Specification 6185, "Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)".

#### **ITEM 2 – INSTRUCTIONS TO BIDDERS**

This Contract includes plan sheets that are not part of the bid proposal.

Order plans from any of the plan reproduction companies shown on the web at: http://www.dot.state.tx.us/business/contractors consultants/repro companies.htm CONTROL: 6466-22-001

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address: https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Request a proposal electronically from the Department's website: http://www.txdot.gov/business-cq/pr.htm

Or use the electronic bidding site: http://www.txdot.gov/business/letting-bids/ebs.html

#### **ITEM 3 – AWARD AND EXECUTION**

This Contract includes non-site-specific work and as-needed work. The type of work identified in the Contract is for locations that have not yet been determined.

Time charges and work will start on the date stated on the Work Authorization letter. The Contract will be in effect until the work on the last callout is completed.

#### **ITEM 5 – CONTROL OF WORK**

Maintain all operations, equipment, and personnel within TxDOT right-of-way always.

#### **ITEM 7 – LEGAL RELATIONS AND RESPONSIBILITIES**

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

Occupational Safety & Health Administration (OSHA) regulations prohibit operations that bring people or equipment within 10 ft. of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all necessary adjustments to ensure the safety of workers near the energized line.

No significant traffic generator events identified.

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

#### **ITEM 8 – PROSECUTION AND PROGRESS**

This project is to be completed in 144 working days in accordance with Section 8.3.1.4, "Standard Workweek."

Provide enough manpower and equipment to accomplish the required work under this contract during the hours agreed upon by the Contractor and Engineer. Failure to do so will constitute grounds for a Noncompliance Penalty.

Work must start within 72 hours of notification or by the time agreed upon with the Engineer.

A Noncompliance Penalty will be assessed for each instance the Contractor is in noncompliance. A noncompliance instance is defined by any of the following:

- 1. Contractor fails to begin work at the specified time or location(s);
- 2. Contractor fails to complete work by the time agreed upon with the Engineer;
- 3. Contractor does not have all the necessary resources (i.e. personnel, equipment, and material) to fulfill the requirement of the Item(s) called out at the specified time or location(s).
- 4. Contractor fails to submit proper material documentation for material sources by the time agreed upon with the Engineer.

The Noncompliance Penalty will be deducted from any money due or to become due for any completed Item(s) or work. The Noncompliance Penalty will be assessed as follows: \$1,000 per instance, per location.

#### **ITEM 500 – MOBILIZATION**

Mobilization will be paid in accordance with the associated Item based on work performed. This will fully compensate for all associated activities.

#### ITEM 502 - BARRICADES, SIGNS AND TRAFFIC HANDLING

Contractor and his employees will wear fluorescent orange safety vests, safety shoes/boots, eye protection and hard hats while outside vehicles within the Department's right of way.

Contractor must have enough manpower and equipment to perform any revised traffic control as directed by the Engineer.

Furnish and place additional TMAs, Flaggers, Pilot Cars, or Truck Mounted forward facing arrow boards not shown on the TCP plan sheets, as directed by the Engineer.

Provide two-way radio communication for all flaggers.

Additional signs and barricades placed as directed, will be considered subsidiary to the various bid items on the contract.

CONTROL: 6466-22-001

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

In accordance with Section 7.2.6.1, designate in writing, a Contractor Responsible Person (CRP) and a CRP alternate to take full responsibility for the set-up, maintenance, and necessary corrective measures of the traffic control plan. The CRP or CRP alternate must be present at site and implement the initial set up of every traffic control phase/stage, at each location, and/or each call out, for the entire duration of the contract.

At the written request of the Engineer, immediately remove the CRP or CRP alternate from the project if, in the opinion of the Engineer, is not competent, not present at initial TCP set-ups, or does not perform in a proper, skillful, or safe manner. These individuals shall not be reinstated without written consent of the Engineer.

CRP and CRP alternate must be trained using Department approved training. Provide a copy of the certificate of completion to the Engineer for project records.

All contractor workers involved with the traffic control implementation and maintenance must participate and complete a department approved training course. Provide a copy of the certificate of completion to the Engineer for project records. Refer to "Traffic Control Training" Material Producer List <u>https://ftp.txdot.gov/pub/txdot-info/cmd/mpl/tct.pdf</u> for Department approved training.

Contractor may choose to train workers involved with the traffic control implementation and maintenance with a contractor developed training in lieu of Department approved training. Contractor developed training must be equivalent to the Department approved training. Provide the Engineer a copy of the course curriculum for pre-approval, prior to conducting the contractor developed training. Provide the Engineer a copy of the log of attendees after training completion for project records.

Notify the Department officials when major traffic changes are to be made, such as detours. Coordinate with the Department on all traffic changes. Advance notification for the following week's work must be made by 5 P.M. on Wednesdays.

Any approved change to the sequence of work or TCP, must be signed and sealed by a Contractor's Licensed Professional Engineer assuming full responsibility for any additional barricade signs and devices needed.

Some signs, barricades, and channelization devices may not be shown at the precise or measured position. Place the barricades, devices, or signs, with approval, in positions to meet field conditions.

Remove signs that do not apply to current conditions at the end of each day's work.

#### **Safety Contingency**

The contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancement, to improve the effectiveness of the TCP that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

#### ITEM 730 - ROADSIDE MOWING

Provide adequate resources to complete one full width mowing cycle including all hand trimming, gaps, slivers, and around all appurtenances in 48 days.

The Department will issue a written notice to begin a mowing cycle. The Contractor will be provided the number of acres required to be mowed, the number of working days allowed to complete the mowing cycle, and the date when time charges for the mowing cycle will start.

The Department will inspect the equipment to ensure that all mowers are adjusted properly for the correct mowing height and meet all safety requirements prior to beginning mowing operations and at any time during the Contract period.

For this Contract, no less than two (2) mowers in operation at all times, unless otherwise approved.

In some locations a maximum seven (7) foot mower deck will be required to provide for a safe mowing operation on narrow roadway and right of way widths as directed.

Transition mowing will be those areas outside the normal strip mow area required to delineate fixed objects adjacent to the roadway such as signs, bridge ends, culvert ends, etc.

Safety mowing shall be those areas outside the normal mow area required, as determined by the Engineer, to protect the traveling public. Included are areas adjacent to driveways, intersecting roadways, inside curves, etc.

Transition or safety mowing (divided or undivided roadway) will be as follows: all transition mowing around signs will start and terminate not less than 100 feet in advance of and beyond the signs. All safety transitions at private driveways will start and terminate not less than 50 feet in advance of and beyond the driveways. Transitions at intersecting roadways will start and terminate not less than 500 feet in advance and beyond the intersection. Transitions at curves will start and terminate not less than 100 feet in advance and beyond the curves on the inside of the curve. Transition around culvert ends to make them visible from the roadway. The transition will start and stop not less than 100 feet in advance of and beyond the culvert. The width around the ends of the culvert will not be less than 7 feet. All transitions will be mowed as stated above or as directed by the Engineer.

When mowing along guardrail, the Contractor will cut all vegetation between the pavement edge and the face of the guardrail and mow not less than a 7-foot strip behind the guardrail. CONTROL: 6466-22-001

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

Each location will be completed prior to beginning work on the next location, unless otherwise approved by the engineer.

Provide a slope mower in areas too steep to mow with conventional equipment. Provide equipment capable of mowing the slope while traveling on the pavement. Do not damage existing slope surfaces or injure existing growth.

Non-Mow Areas are marked by delineator posts. Contact the Engineer for any questions concerning location.

Repair damage caused by the Contractor's operations, to the highway right of way, signs, fences, delineators, plant materials or any other appurtenances, part of or adjacent to the highway facility. The Department has the authority to charge the Contractor for any damage not repaired.

Mowers will be adjusted for a cutting height of six (6) inches.

Where hand trimming is required, the vegetation will be cut to a height of approximately three (3) inches. All hand trimming shall be completed within 24 hours after mowing is completed on any section of highway right of way.

No additional compensation will be made to the Contractor for pre-existing conditions or excessive growth between cycles. The Contractor shall be available throughout the one-year duration of the Contract to perform items under this Contract.

In some locations, it may be necessary to remove litter and debris to mow vegetation in the entire right of way, except for non-mow areas. The Contractor will remove litter and debris, prior to mowing. All litter and debris collected by the Contractor becomes the property of the Contractor and will be disposed of at an approved solid waste site. This will be subsidiary to Item 730.

All center medians and outer separations (outer separation is defined as the space between the interstate outside lane and the frontage road) less than 30 feet will be mowed full width. The rate of transition between the designated strip width and other safety and transition mowing will be 1:6 (width: parallel to highway).

## ITEM 6185 – TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA)

All TMA Operators must participate in a TMA workshop to be conducted by the El Paso District Safety Office on the proper use of TMAs, prior to work. All TMA Operators must participate in a TMA workshop provided by the Department or equivalent approved by the Engineer. A truck mounted attenuator completion card will be issued to TMA Operators that successfully complete the TMA workshop. The workshop completion card must be carried by TMA Operators at all times while working on Department right of way.

COUNTY: CULBERSON, ETC.

HIGHWAY: IH 10, ETC.

Acquire the TCP and TMA Operator's workshop completion prior to the authorization to begin work. No time suspension will be granted, and no traffic control work will be allowed without the workshop completion card.

TMAs will be used and positioned per the applicable Traffic Control Plan standard or as directed by the Engineer. Additional TMAs required due to changes in project phasing by contractor or the Engineer will be provided by the contractor.

The supporting vehicle for the TMA shall have a minimum gross (i.e. ballasted) vehicular weight of 19,000 pounds.

SHEET 3C



## CONTROLLING PROJECT ID 6466-22-001

**DISTRICT** El Paso **HIGHWAY** IH0010 **COUNTY** Culberson

**Estimate & Quantity Sheet** 

		CONTRO	L SECTIO	N JOB	6466-22-001			
			PROJE	CT ID	A00208686			
			COUNTY		Culbe	rson	TOTAL EST.	TOTAL FINAL
			HIGHWAY		IH0010			
ALT	BID CODE	DESCRIPTION		UNIT	EST.	FINAL		
	500-6001	MOBILIZATION		LS	1.000		1.000	
	730-6002	FULL - WIDTH MOWING		AC	11,324.000		11,324.000	
	6185-6003	TMA (MOBILE OPERATION)		HR	700.000		700.000	



DISTRICT	COUNTY	CCSJ	SHEET
El Paso	Culberson	6466-22-001	4

	LIMITS						
HIGHWAY	DESCRIPTION		APPROX. REFERENCE MARKER		LENGTH	ACRES PER CYCLE	TOTAL ACRES (3 CYCLES)
	FROM	ТО	FROM	ТО	(MI)	(ACRES)	(CYCLES)
SH 54	CITY LIMITS	31.2 MI NORTH	350+0.00	380+0.00	30	115	345
FM 2185	JCT 54	END OF SECTION	326+0.00	368+0.00	42	155	465
FM 2809	JCT 2185	END OF PAVEMENT	360+0.00	364+0.00	4.9	18	54
US 90	SOUTH FRONTAGE IH 10	JEFF DAVIS COUNTY	112+0.00	132+0.00	20	181	543
FM 1523	JCT US 90 NORTH	JCT US 90 SOUTH	392+0.00	400+0.00	8	29	87
FM 2017	JCT FM 1523	JEFF DAVIS COUNTY	396+0.00	400+0.00	4.1	15	45
RM 2424	JCT IH 10	END OF PAVEMENT	368+0.00	381+0.00	13.7	50	150
SH 118	JCT IH 10	JEFF DAVIS COUNTY	382+0.00	383+0.00	1.5	6	18
RM 1111	SIERRA BLANCA	END OF SECTION	361+0.00	375+0.00	14	51	153
IH 10	2 MI EAST FM 34	SIERRA BLANCA	88+0.00	108+0.00	20	309	927
IH 10	SIERRA BLANCA	9 MI WEST OF CULBERSON COUNTY	108+0.00	126+0.00	18	274	822
IH 10	MILE MARKER 126	VAN HORN	126+0.00	140+0.00	14	247	741
IH 10	VAN HORN	JEFF DAVIS COUNTY/REEVES COUNTY LINE	140+0.00	186+0.00	46	883	2649
*SEE NOTES					TOTAL	2333	6999

		LIMITS					
HIGHWAY	DESCRIPTION		APPROX. REFERENCE MARKER		LENGTH	ACRES PER CYCLE	TOTAL ACRES (3 CYCLES)
	FROM	ТО	FROM	ТО	(MI)	(ACRES)	(CYCLES)
FM 1576	JCT US 62/180	END OF STATE MAINTENANCE	106+0.00	314+0.00	23.8	235	705
FM 2249	JCT 1576	5.1 MI WEST OF FM 1576	94+0.00	98+0.00	5.1	50	149
SH 54	CITY LIMITS	54.9 MI NORTH	328+0.00	384+0.00	54.9	532	1596
RM 2317	JCT 62/180	RM 1111 INTERSECTION	76+0.00	88+0.00	12.3	30	90
RM 1111	JCT 62/180	47 MI SOUTH	328+0.00	374+0.00	47.0	109	327
RM 1108	RM 652 INTERSECTION	END OF STATE MAINTENANCE	320+0.00	328+0.00	9.8	24	72
RM 1165	RM 652 INTERSECTION	1.0 MI NORTH OF RM 652	144+0.00	144+0.00	1.0	2	6
RM 652	JCT 62/180	END OF STATE MAINTENANCE	134+0.00	194+0.00	58.5	127	381
FM 3541	RM 652 INTERSECTION	6.2 MI SOUTH OF RM 652	328+0.00	334+0.00	6.2	20	60
US 62/180	HUDSPETH COUNTY	END OF STATE MAINTENANCE	50+0.00	148+0.00	98.1	250	750
FM 1437	JCT 62/180	16.4 MI NORTH	330+0.00	314+0.00	16.4	63	189
SEE NOTES					TOTAL	1442	4325

JCT = JUNCTION MI = MILES

		ACRES PER CYCLE	TOT ACRE CYCI
730-6002	FULL-WIDTH MOWING TOTAL	3775	113

- 1. THE QUANTITIES AND LOCATIONS IDENTIFIED IN THE LOCATION TABLES ARE NOT GUARANTEED. VERIFY WITH AREA ENGINEER FOR LOCATIONS BEFORE STARTING WORK.ACTUAL QUANTITIES AND LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- 2. EACH CYCLE IS 48 DAYS. EACH CYCLE WILL CONSIST OF APPROXIMATELY 3775 ACRES, AVERAGING APPROXIMATELY 79 ACRES PER DAY.
- 3. REFER TO ITEM 730 ROADSIDE MOWING FOR MORE DETAILS.



# ALPINE AREA OFFICE VAN HORN/DELL CITY MAINTENANCE SECTION

GENERAL LOCATION TABLES

		S	HEET	1	OF	1	
Texas Department of Transportation							
CONT	SECT	JOB		HIGHW	NAY		
6466	22	001	IH	10,	ΕT	с.	
DIST		COUNTY		SH	EET NO	) <b>.</b>	
ELP	CUL	BERSON.	ETC.		5		

#### BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the 2. responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed 3. by a licensed professional engineer for approval. The Engineer may develop. sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the 9. BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown ON BC(2). THE OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES. CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, ČSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

#### WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

#### COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- 1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-aualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov					
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)					
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)					
MATERIAL PRODUCER LIST (MPL)					
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"					
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)					
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)					
TRAFFIC ENGINEERING STANDARD SHEETS					

AN +


8: 48: 08

/9/2024

DATE:

**			
Texas Department of Transpo	Traffic Safety Division Candard		
BARRICADE AND CO GENERAL N AND REQUIRE BC(1)-	OTES Ement		TION
FILE: bc-21.dgn DN: TxDOT	ск: TxDOT Dw:	TxDO	T ск: TxDOT
CTxDOT November 2002 CONT SECT	JOB		HIGHWAY
4-03 7-13 6466 22	001	IH	10, ETC.
9-07 8-14 DIST	COUNTY		SHEET NO.
5-10 5-21 ELP CUL	BERSON, I	ETC.	6

SHEET 1 OF 12



TYPICAL	CONSTRUCTION	WARNING	SIGN	SIZE	AND	SPACING <sup>1,5,6</sup>

SIZE

Sign Number or Series	Conventional Road	Expressway/ Freeway
CW20 <sup>4</sup> CW21 CW22 CW23 CW25	48" × 48"	48" × 48"
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" × 36"	48" × 48"
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" × 48"	48" × 48"

SF	PACING
Posted Speed	Sign∆ Spacing "X"
MPH	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500 <sup>2</sup>
60	600 <sup>2</sup>
65	700 <sup>2</sup>
70	800 <sup>2</sup>
75	900 <sup>2</sup>
80	1000 <sup>2</sup>
*	* 3

X For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

ightarrow Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

#### GENERAL NOTES


- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.

7-13 5-21

6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

			L	EGEN	ID				
			Туре	3 Bar	ricade				
		000	Chanr	nelizi	ng Devices	;			
		-	Sign						
-]		x	Warn Spac TMUT(	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.					
			SHEE	T 2 (	OF 12		-		
r.	Те	🔶 ° exas Depa	rtment	of Tran	sportation		Traffic Safety Division Standard		
e	BAR		_		CONSTR LIMIT	NC	TION		
			BC		-21				
- H-		bc-21.dgn November 200	12	DN: TXD	OT CK:TXDOT DI	n: TxDC	DT CK: TXDOT		
Ē		REVISIONS	-	6466 2		IH			
	9-07	8-14		DIST	COUNTY		SHEET NO.		

ELP CULBERSON, ETC. 7



## GUIDANCE FOR USE:

#### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width

f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

#### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).


#### GENERAL NOTES

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.

4. Frequency of work zone speed limit signs should be: 40 mph and greater 0.2 to 2 miles 35 mph and less 0.2 to 1 mile


- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- 6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
  - B. Flagger stationed next to sign.
  - C. Portable changeable message sign (PCMS).
  - D. Low-power (drone) radar transmitter.
  - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.





#### BC(3)-21 DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO ILE: bc-21.dgn C)TxDOT November 2002 CONT SECT JOB HIGHWAY 6466 22 001 IH 10, ETC REVISIONS 9-07 8-14 COUNTY SHEET NO. 7-13 5-21 ELP CULBERSON, ETC.

WORK ZONE SPEED LIMIT



to Item 502.

#### GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white. Barricades shall NOT be used as sign supports
- guide the traveling public safely through the work zone.
- 5. the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- the Engineer can verify the correct procedures are being followed.
- damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- for identification shall be 1 inch.

#### The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

- <u>DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)</u>
- regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary work that occupies a location more than 3 days. more than one hour.
- Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period. c.
- Short, duration work that occupies a location up to 1 hour. d. e.

#### SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- the ground. Long-term/Intermediate-term Signs may be used in Lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to
- appropriate Long-term/Intermediate sign height.

#### SIZE OF SIGNS

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

#### SIGN SUBSTRATES

- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave. centers. The Engineer may approve other methods of splicing the sign face.

#### REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300

#### SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway first class workmanship in accordance with Department Standards and Specifications.

#### REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- intersections where the sign may be seen from approaching traffic. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely
- covered when not required. 4.
- entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting. Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

#### SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight. Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list. Sandbags shall only be placed along or laid over the base supports of the
- traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

#### FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and

The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in

The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZICD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a guestion regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so

The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or

Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used

The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in

Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting

Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZICD lists each substrate that can be used on the different types and models of sign supports. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6"

for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1). White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background. 3. Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of

Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any

When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the


SHEET 4 OF 12

Texas Department of Transportation

Traffic Safety Divisiór Standaro

## BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

	BC	(4	) -	21				
_E:	bc-21.dgn	DN: T>	DOT	ск: TxDOT	DW:	TxDO	T C	κ:TxDOT
)TxDOT	November 2002	CONT	SECT	JOB			HIGH	WAY
	REVISIONS	6466	22	001		ΙH	10,	ETC.
9-07	8-14	DIST		COUNTY			SH	EET NO.
7-13	5-21	ELP	CUL	BERSON	, E	TC.		9



DocuSign Envelope ID: F79FA98A-D5BA-4BDC-AA7C-0EDE4AE431B3

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

#### PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to 2. eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED," Do not use the term "RAMP,"
- Always use the route or interstate designation (IH, US, SH, FM) 5. along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to 7. start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are avail-8. able for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message 9. should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line. 11. Do not use the word "Danger" in message.
- 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together, Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Nor thbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN SAT
Do Not	DONT	Saturday	
East	F	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S SPD
Express Lane	EXP LN	Speed	SPU
Expressway	EXPWY	Street	
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	TEMP
Freeway	FRWY, FWY	Temporary	THURS
Freeway Blocked	FWY BLKD	Thursday	TO DWNTN
Friday	FRI	To Downtown Traffic	
Hazardous Driving			
Hazardous Material		Travelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour (s)	HR, HRS	Vehicles (s)	VEH, VEHS
Information	INFO	Warning	WARN
It Is	ITS	Wednesday	WED
Junction	JCT	Weight Limit	WT LIMIT
Left	LFT	West	W
Left Lane	LFT LN	Westbound	(route) W
Lane Closed	LN CLOSED	Wet Pavement	WET PVMT
Lower Level	LWR LEVEL	Will Not	WONT
Maintenance	MAINT		

## RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES (The Engineer may approve other messages not specifically covered here.)

## Phase 1: Condition Lists

#### Road/Lane/Ramp Closure List

		Uther Con	dition List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT X
XXXXXXXX BLVD CLOSED	* LANES SHIFT in Phase	1 must be used wit	th STAY IN LANE in Phos

Other Co	ndition List
ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	L ANE S SHIFT

#### Action to Take/Effect on Travel List MERGE FORM RIGHT X LINES RIGHT DETOUR USE XXXXX NEXT RD EXIT X EXITS USE USE EXIT EXIT XXX I-XX NORTH STAY ON USE US XXX I-XX F SOUTH TO I-XX N TRUCKS WATCH USE FOR US XXX N TRUCKS WATCH EXPECT FOR DELAYS TRUCKS PREPARE EXPECT DELAYS ΤO STOP REDUCE END SPEED SHOULDER XXX FT USE USE WATCH OTHER FOR ROUTES WORKERS STAY ΤN LANE

#### APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS. 2. The 1st phase (or both) should be selected from the
- "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

#### WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- appropriate.
- be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary. 7. FT and MI. MILE and MILES interchanged as appropriate.
- 8. AT. BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a
- location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

#### FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above
- 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the some size arrow.

# Roadway

60


8:48:

4/9/2024 T: \FI PMA

DATE:

designation # IH-number, US-number, SH-number, FM-number


## Phase 2: Possible Component Lists




X X See Application Guidelines Note 6.


XX AM


2. Roadway designations IH, US, SH, FM and LP can be interchanged as EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can





#### DocuSign Envelope ID: F79FA98A-D5BA-4BDC-AA7C-0EDE4AE431B3














#### GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

#### GENERAL DESIGN REQUIREMENTS

- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Drum and base shall be marked with manufacturer's name and model number.

#### RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

#### BALLAST

N S


60


8:48: \Coo+

2024

шü

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- 3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.







#### DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.

с С С


of (er





- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the out side of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

#### WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on
- 2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements
- 4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length
- should be designed to optimize road user operations considering the available geometric conditions. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

#### HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

#### GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Desirable Taper Lengths X X			Spacir Channe	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30		150'	165'	180'	30′	60′
35	$L = \frac{WS^2}{60}$	205′	225′	245'	35′	70′
40	00	265'	295′	320'	40′	80′
45		450′	495′	540'	45′	90′
50		500'	550'	600'	50 <i>'</i>	100'
55	L=WS	550'	605′	660'	55 <i>'</i>	110′
60	L - # 5	600'	660 <i>'</i>	720′	60 <i>'</i>	120′
65		650′	715′	780'	65 <i>1</i>	130'
70		700′	770′	840′	70′	140'
75		750′	825′	900'	75′	150′
80		800'	880′	960'	80 <i>'</i>	160′


L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)


XX Toper lengths have been rounded off.

## SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12	
Texas Department of Transportation	Traffic Safety Division Standard
BARRICADE AND CONSTR CHANNELIZING DEVI	

		BC	(9	) -	·21				
FILE:	bc-21.dgn		DN: T>	DOT	ск: TxDOT	DW:	TxDC	Тс	ĸ: T×DOT
C TxDOT	November 2002		CONT	SECT	JOB			HIGHW	VAY
	REVISIONS		6466	22	001		IΗ	10,	ETC.
9-07	8-14		DIST		COUNTY			SHE	EET NO.
7-13	5-21		ELP	CUL	BERSON,	, E	TC.		14
103									





rranty of any he conversion S p e Practice Act". N responsibility as resulting from δç this st T×DOT ISCLAIMER: The use ind is mode f this stan

> AM 8:48:10 2024 DATE:

	SHEET	10	0	F 12				
	<b>*</b> * Texas Department of	of Tra	nsp	ortation		Ĺ	Traff Safe Divisi tand	ty on
BAR	RICADE AI CHANNELIZ	ZIN	IG					ON
FILE:	bc-21.dgn	DN: T)	<dot< th=""><th>ск: TxDOT</th><th>DW:</th><th>TxDC</th><th>T CK</th><th>: TxDOT</th></dot<>	ск: TxDOT	DW:	TxDC	T CK	: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB			HIGHW	AY
	REVISIONS	6466	22	001		ΙH	10,	ETC.
9-07 7-13	8-14 5-21	DIST		COUNTY			SHE	ET NO.
7-13	J-21	ELP	CUL	BERSON,	, E	TC.		15

### WORK ZONE PAVEMENT MARKINGS

#### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ (STPM).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

#### RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns on  $\mathsf{BC}\left(\mathsf{12}\right)$  .
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

#### PREFABRICATED PAVEMENT MARKINGS

- 1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


#### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

#### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- 4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

#### Temporary Flexible-Reflective Roadway Marker Tabs



#### STAPLES OR NAILS SHALL NOT BE USED TO SECU TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARK TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guiden shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by Engineer or designated representative. Sampling and testing is m normally required, however at the option of the Engineer, either or "B" below may be imposed to assure quality before placement or roadway.
  - A. Select five (5) or more tabs at random from each lot or sh and submit to the Construction Division, Materials and Pav Section to determine specification compliance.
  - B. Select five (5) tabs and perform the following test. Affix (5) tabs at 24 inch intervals on an asphaltic pavement in straight line. Using a medium size passenger vehicle or pir run over the markers with the front and rear tires at a sp of 35 to 40 miles per hour, four (4) times in each direction more than one (1) out of the five (5) reflective surfaces be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. Standard Sheet TCP(7-1) for tab placement on seal coat work.

#### RAISED PAVEMENT MARKERS USED AS GUIDEMARK

- Raised pavement markers used as guidemarks shall be from the ap product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applie butyl rubber pad for all surfaces, or thermoplastic for concretsurfaces.

#### Guidemarks shall be designated as:

YELLOW - (two amber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

AA AA


8:48:10 \Controc


2024 I PMAINT

DATE:

	DEPARTMENTAL MATERIAL SPECIFICA	TIONS
	PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
	TRAFFIC BUTTONS	DMS-4300
	EPOXY AND ADHESIVES	DMS-6100
VIEW	BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
	PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
	TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
	TEMPORARY FLEXIBLE, REFLECTIVE	DMS-8242
î ve pad	ROADWAY MARKER TABS	5110 02 12
E	A list of prequalified reflective raised pavement non-reflective traffic buttons, roadway marker pavement markings can be found at the Material I web address shown on BC(1).	tabs and othe
R		
rks		
he ot "A" o the		
pment ment		
five kup, ed n. No hall		
ee		
•		
roved		
or		
	SHEET 11 OF 12	
	**************************************	Traffic Safety
		Division
	Texas Department of Transportation	División Standard
	Texas Department of Transportation	Division Standard
		Standard
	BARRICADE AND CONST	RUCTION
		RUCTION
	BARRICADE AND CONST	RUCTION
	BARRICADE AND CONST PAVEMENT MARKIN	RUCTION
	BARRICADE AND CONST PAVEMENT MARKIN BC(11)-21	RUCTION
	BARRICADE AND CONST PAVEMENT MARKIN BC(111)-21 FILE: bc-21.dgn DN: TXDOT CK: TXDOT © TXDOT February 1998 CONT SECT JOB	Standard   RUCTION   NGS   Image: DW: TxDOT CK: TxD   HIGHWAY
	BARRICADE AND CONST PAVEMENT MARKIN BC(111)-21	Standard   RUCTION   NGS   DW: TXDOT CK: TXD   HIGHWAY   IH   10, ETC

105





#### GENERAL NOTES FOR WORK ZONE SIGNS

- 1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white. 2.
- Barricades shall NOT be used as sian supports. 3.
- Nails shall NOT be used to attach signs to any support. 4.
- 5.
- quide the traveling public safely through the work zone. 6.
- requested by the Engineer/Inspector shall not be subsidiary. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD). The Contractor can verify the correct procedures are being followed.
- reflective sheeting as directed by the Engineer/Inspector. 9.
- for identification shall be 1".

- Duration of Work (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part VI) 1. The Contractor is responsible for ensuring the sign support and substrate meets crashworthiness. For mowing operation all signs and supportS are Short-term Duration for daytime work.
- 2. The Contractor shall furnish the sign sizes shown on this sheet or as directed by the Engineer.

#### SIGN SUBSTRATES

- 1. substrate that can be used on the different types and models of sign supports. "Mesh" type materials are NOT an approved sign substrate.
- centers. The Engineer may approve other methods of splicing the sign faces.

#### REFLECTIVE SHEETING

- 1. The DMS specifications can be accessed from the following web address: http://manuals.dot.state.tx.us:80/dynaweb/colmates/@Generic\_CollectionView;cs=default;ts=default
- and channelizing devices.

#### SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway first class workmanship in accordance with Department Standards and Specifications.

#### REMOVING OR COVERING

- Signs should be removed or completely covered when not mowing.
- 2. Duct tape or other adhesive material shall NOT be affixed to a sign face.
- 3. Signs and supports shall be removed by the end of the day.

#### SIGN SUPPORT WEIGHTS

- 2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights. 3.
- 4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. 5.
- Rubber (such as tire inner tubes) shall NOT be used for sandbags. 6.
- 7
- 8. supports.
- 9.

Any sign, sign support or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced or repaired as soon as possible by the Contractor at the Contractor's expense.

Only pre-qualified products shall be used. A copy of the											
"Compliant Work Zone Traffic Control Devices List" (CWZICD) describes pre-qualified products and their sources and may be obtained by contacting:		Tex	kas L	Depai	rtmen	t of Tr	ansp	orte	atio	n	
Standards Engineer Traffic Operations Division - TE Texas Department of Transportation						e Divisio d Plans					
125 East 11th Street Austin, Texas 78701-2483 Phone (512) 416-3120 Fax (512) 416-3299	ROADSIDE TRAFFIC CONTROL								PLAN		
Instructions to locate the "CWZTCD" on TxDOT website are:											
Start at website - www.dot.state.tx.us Click on "About TxDOT",	S	HEET 1 OF 1	F	RS-T	CP-	05		NO	T TO	SCALE	
Click on "Organizational Chart",	FILE	RSTCP05.DGN	DN:	LJB	ск: ЈС	DW: -	СК: -	N	EG NO.:		
Click on Traffic Operations Box,		(C) TxDOT FEBRUAR	1 2005	STATE	FEDERAL REGION	FEDER/	L AID PRO.	ECT		SHEET	
Click on "Compliant Work Zone Traffic Control Devices", Click on "View PDF".		SED: September 17, 2004		N/A	N/A		N/A			18	
This site is printable.	REV1 Sign	ISED: FEBRUARY 2, 2005 n placement in TCP			COUNT	ſY	CONTROL	SECTION	JOB	HIGHWAY	
	REVI	SED:		(	CULBERS	ON, ETC.	6466	22	001	IH10, ETC	

All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and

The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes. The additional signs

shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so that the Engineer

The Contractor is responsible for sign installations and replacing signs with damaged or cracked substrates and/or damaged or marred

Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used

10. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

The Contractor shall ensure that the sign substrate is allowed for the type of sign support that is being used. The CWZTCD lists each

All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat. 1/2" thick by 6" wide. fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6

Reflectorized signs shall be constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 or DMS-8310. White sheeting, meeting the requirements of DMS-8300 Type C (High Specific Intensity), shall be used for signs with white background

Orange sheeting, meeting the requirements of DMS-8300 Type E (Fluorescent Prismatic), shall be used for signs with orange backgrounds.

Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of


Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry cohesionless sand is recommended.

Rubber ballasts (such as those used with cones or edgeline channelizers) shall NOT be used as sign support weights.

Sandbaas shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above around level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign

Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.


CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS




	LEGEND								
~~~~~	Type 3 Barricade		Channelizing Devices						
□¤	Heavy Work Vehicle	X	Truck Mounted Attenuator (TMA)						
	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)						
-	Sign	$\langle$	Traffic Flow						
$\Diamond$	Flag	٩	Flagger						

Speed	Formula	D	Minimur esirab er Lena X X	le	Špacir Channe		Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space
*		10' 11' 12' Offset Offset Offset		On a Taper	On a Tangent	Distance	"В"	
30		150'	165'	180'	30′	60′	120′	90'
35	$L = \frac{WS^2}{60}$	205'	225′	245'	35′	70′	160′	120'
40	60	265′	295′	320'	40′	80′	240′	155′
45		450'	495′	540′	45′	90′	320′	195′
50		500'	550ʻ	600′	50 <i>'</i>	100′	400′	240'
55	L=WS	550'	605 <i>'</i>	660 <i>'</i>	55′	110′	500 <i>'</i>	295′
60	L - # 5	600 <i>'</i>	660′	720'	60′	120'	600 <i>'</i>	350′
65		650'	715′	780′	65′	130'	700′	410′
70		700′	770'	840'	70'	140'	800′	475′
75		750'	825′	900′	75′	150′	900′	540 <i>′</i>

TYPICAL USAGE									
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY					
	1	1							





LEGEND								
<u>e 7 7 7 7</u>	Type 3 Barricade		Channelizing Devices					
□¤	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)					
Ē	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)					
-	Sign	$\Diamond$	Traffic Flow					
$\bigtriangleup$	Flag	LO	Flagger					

Posted Speed <del>X</del>	Formula	Desirable			Spa Chan	ted Maximum cing of nelizing evices On a	Suggested Longitudinal Buffer Space "B"	
				Offset		Tangent	_	
30	ws <sup>2</sup>	150'	165′	180'	30'	60′	90'	
35	$L = \frac{WS}{60}$	205'	225'	245'	35′	70′	120'	
40	60	265′	295′	320'	40′	80′	155'	
45		450'	495′	540'	45′	90′	195′	
50		500'	550'	600′	50 <i>'</i>	100′	240'	
55	L=WS	550'	605′	660′	55′	110′	295 <i>'</i>	
60	L-#5	600 <i>'</i>	660 <i>'</i>	720'	60′	120'	350'	
65		650'	715′	780'	65′	130′	410'	
70		700'	770'	840'	70′	140′	475′	
75		750'	825′	900′	75′	150′	540′	
80		800'	880'	960 <i>'</i>	80′	160′	615′	

\* Conventional Roads Only

\*\*Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH

	TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY					
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)						

#### GENERAL NOTES

- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely effecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
- 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.

~	L									
$\langle \rangle$		Те	exas Departme	nt of Tra	nsp	ortation	1	Traffic peratic Divisio Standa	ons n	
AD RK EAD D-1D X 48"		TRAFFIC CONTROL PLAN SHOULDER WORK FOR FREEWAYS / EXPRESSWAYS								
			TCP	(5-1		-18				
		FILE: †C	cp5-1-18.dgn	DN:		CK:	DW:	CK:		
		C TxDOT	February 2012	CONT	SECT	JOB		HIGHWAY	r	
			REVISIONS	6466	22	001	IH	10, 1	ETC.	
	2-1	2-18		DIST		COUNTY		SHEE 1	T NO.	
				ELP	CUL	BERSON,	ETC.	2	0	
		190								