

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX SHEET
3,3A-3E	GENERAL NOTES
4	ESTIMATE AND QUANTITY SUMMARY
5-14	REPAIR LOCATION SUMMARIES
15-16	DETOUR LAYOUTS
17-22	TCP LAYOUTS
23	CRASH CUSHION SUMMARY SHEET
24-29	TXDOT TCP(I-I)-18 THROUGH (I-6)-18
30-31	TXDOT TCP (2-1) - 18 THROUGH (2-2) - 18
32	TXDOT TCP (2-3) - 23
33-35	TXDOT TCP (2-4) - 18 THROUGH (2-6) - 18
36-37	TXDOT TCP (2-7) - 23 THROUGH (2-8) - 23
38	TXDOT TCP(S-I)-08A
39	TXDOT TCP(S-2)-08A
40	TXDOT TCP(S-2C)-IO
41	TXDOT TCP(S-3)-08
42	TXDOT TCP(S-5)-08
43-54	TXDOT BC (1)-21 THROUGH (12)-21
55-56	TXD0T TCP(6-1)-12 THR0UGH (6-2)-12
57	TREATMENT OF VARIOUS EDGE CONDITION
58	TXDOT - SLED-19
59	TXDOT - ABSORB(M)-19
60-6/	TXDOT - CSB(I)-IO
62	TXDOT AJ-19
63-64	TXDOT SRR-19
65	TXDOT WZ(RS)-22
66	TXDOT WZ(STPM)-23
67-72	TXDOT D&OM(1)-20 THROUGH D&OM(6)-20
73	TXDOT D&OM VIA-20
74-75	STEAL BEAM REPAIR
76	CFRP INSTALLATION DETAILS
77	ELASTOMERIC BEARING REPLACEMENT DETAILS FOR CONCRETE BEAMS
78	JOINT REPAIR AND REPLACEMENT DETAILS BRIDGES WITH ASPHALT OVERLAY
79	JOINT REPAIR AND REPLACEMENT DETAILS BRIDGES WITHOUT ASPHALT OVERLAY
80-82	MISCELLANEOUS REPAIR DETAILS
83-85	STORMWATER PROLLUTION PREVENTION PLAN (LESS THAN I ACRE)
86	EPIC
THE STANDA	NOA SHEETS ASWATEA WITH THE "TYAAT" ODEELY

THE STANDARD SHEETS DENOTED WITH THE 'TXDOT' PREFIX HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



INDEX SHEET

CTXDOT	OCT 2023	CONT	SECT	JOB		HIGHWAY
	REVISIONS	6447	58	001	1	/ARIOUS
		DIST		COUNTY		SHEET NO.
		05		Lubbock		2

MEDICA , P.E. 04/23/2024

County: Lubbock

Control: BPM 6447-58-001

Highway: Various

Sheet 3

GENERAL NOTES:

General Requirements and Covenants - Items 1 thru 9

Contractor questions on this project are to be addressed to the following individual(s):

Mike Stroope, P.E Director of Maintenance mike.stroope@txdot.gov Surafel Sintayehu, P.E Bridge Engineer surafel.sintayehu@txdot.gov 806-748-4332

Contractor questions will be accepted through email to the above individuals. Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 1 – Abbreviations and Definitions

Contract Prosecution – Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any and all contracts at the same time.

Item 2 – Instructions to Bidders

The construction time determination schedule will be posted on the Letting Pre-Bid Q&A web page.

View the plans on-line or download from the web at:

http://www.dot.state.tx.us/business/plansonline/agreement.htm

Choose "I Agree" then, "Click here", then "State-Let-Construction", pick the letting month, then "Plans" and then choose the plans set.

Order plans from any of the plan reproduction companies shown on the web at:

http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

By signing this proposal, a bidder acknowledges that he/she has a copy of the "Standard Specifications for Construction of Highways, Streets and Bridges", adopted by the Texas Department of Transportation, November 1, 2014. This specification book may be purchased from the Department or downloaded at:

http://www.txdot.gov/business/resources/txdot-specifications.html

Utilities

Overhead and underground utility installations exist within the project limits. Contractor responsible for contacting 811 and Lubbock District Traffic office to obtain utility locates before start of construction activities.

If any lights, signals, or other systems not part of the project are disconnected by the contactor, the contractor must restore all affected systems to working condition.

Item 5 - Control of the Work

Perform construction surveying in accordance with Article 5.9.3, "Method C."

Replace all damaged ROW and USGS monuments at the contractor's expense.

When deviation from the plans is requested by the Contractor, but not required for installation, the Contractor will bear any additional costs associated with the deviation.

Restore all disturbed areas due to trenching or any construction activity to a condition equivalent to the original condition within 14 working days from the time work began in the area including all necessary seeding.

The construction, operation, and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

At the end of each day remove from the ROW, inside or outside the project limits, any excess material and debris resulting from construction.

Correct any deficiencies identified during the final inspection including required paperwork.

Submit all required paperwork within 60 days of project acceptance.

Allow 5 business days for subcontractor approval.

General Notes

В

Control: BPM 6447-58-001

Sheet 3

DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF	5	
County: Lubbock	Control: BPM 6447-58-001	Control: BPM 6447-58-001
Highway: Various	Sheet 3A	Sheet 3A
<u>Item 6 – Control of Materials</u>		Notify, in writing, each residence and business 10 days prior to beginning construction of the phase/phases
	st of material producers pre-qualified by the Construction sportation (TxDOT) can be found at the following website:	that are expected to affect their ingress and egress. This notice may be hand delivered or mailed.
http://www.txdot.gov/business/resources/		When applicable, comply with all requirements of the Environmental Permits Issues and Commitments (EPIC) sheets.
installed, modified, tested, or otherwise used on t functional within the manufacturer normal specif	pecifications, make all material and equipment furnished, his contract, and becoming the property of TxDOT, fully ications, warranties, and guarantees. Make any additional / supplied by the manufacturer, but not specified by TxDOT,	Provide 2 lidded dumpsters per crew, one on either side of the bridge, to be used by contractor's personnel on the job site. The lid or covering to the dumpsters needs to be able to stay closed in high winds to prevent trash from being blown out. This shall be considered subsidiary to the various bid items.
completely functional.	supplied by the manufacturer, out not specified by TXDOT,	Dispose of all waste materials in compliance with local, state, and federal regulations. Submit a list of all approved waste sites to the Engineer for review.
To comply with the latest provisions of Build Am Bipartisan Infrastructure Law, the contractor mus	st submit a notarized original of the TxDOT Construction	All vehicles in the work zone shall use flashing amber strobe lights visible 360 degrees.
required for materials classified as manufactured	items classified as construction materials. This form is not products.	No significant traffic generator events identified.
Refer to Buy America Material Classification She	eet for clarification on material categorization.	Concrete trucks operating on interstate highways will not be allowed to carry more than 6 cubic yards (CY) of concrete unless the truck utilizes a lift (third) axle.
The Buy America Material Classification Sheet is	s located at the below link.	Prior to and during construction, Contractor shall remove empty barn swallow nests if found on the bridge
<u>https://www.txdot.gov/business/resource</u> sheet.html	<u>es/materials/buy-america-material</u> -classification-	structures. Payment for this work will be with the environmental force account. Contact the Lubbock District Environmental Coordinator Ayssa Trevino at 806-748-4417 prior to any nest removals.
Provide the State 30 days to test all materials, app	prove, and resolve any disputes.	Item 8 - Prosecution and Progress
Provide the state minimum of 48hrs before concr	ete pour for inspection.	This project is to be completed in 230 days and 14 months of barricades in accordance with the contract documents.
Article 6.6		
Store material off TxDOT property or Right of W	/ay unless approved by the project supervisor.	Monthly schedule updates are a very important aspect of managing the progress of this project. The Engineer may withhold the monthly estimate if the schedule update has not been received.
Article 6.11		A bar chart will be required for this project.
Repair damage to the Right of Way to the satisfac	ction of the project supervisor.	Do not begin work before sunrise or end work after sunset unless authorized by the Engineer and remove all equipment from the roadway before sundown.
Item 7 – Legal Relations and Responsibilities		
Coordinate street closures with the local fire, poli	ice, and other emergency personnel.	Work around existing culverts, signs, mailboxes, object markers and delineators. Any damages resulting from the Contractor's operation shall be repaired by the Contractor to the satisfaction of the Engineer.

Working days will be computed and charged in accordance with Article 8.3.1.4 Standard Workweek.

General Notes

Maintain access to adjacent property at all times.

Control: BPM 6447-58-001

Control: BPM 6447-58-001

Sheet 3B

Highway: Various

County: Lubbock

Sheet 3B

Е

Contract time charges shall begin upon issuance of "Authorization of Begin Work" letter.

Shut down operations the working day before the following major traffic generating holidays: January 1st (New Year's); Last Monday in May (Memorial Day); July 4th (Independence Day); First Monday in September (Labor Day); Fourth Thursday in November (Thanksgiving); and December 24th (Christmas Eve).

Payment for a final 3% mobilization will be made once all project signage has been removed and all other items according to Article 500.3. Timeliness for submittal of required paperwork and correction of deficiencies is a consideration in developing the final contractor evaluation score.

Pre-Work Meeting - Prior to beginning work, a conference between the Contractor's representative and the Department will be arranged by the Department. Lifting plan shall be submitted at the pre-work meeting.

Item 9 - Measurement and Payment

Submit material-on-hand payment requests by the 25^{th} of each month. If the 25^{th} falls on a weekend, submit it by the Friday preceding the 25^{th} of that month. Failure to do so may result in the rejection of additional MOH payment for that month.

Material-on-hand will be paid item for item regardless of how the work was bid.

Item 401 – Flowable Backfill

Provide excavatable backfill material.

Item 420 - Concrete Substructures

Consolidate concrete for bridge components reinforced with epoxy coated reinforcing steel with vibrators having rubber or non-metallic heads in order to prevent damage to the epoxy.

Tie epoxy-coated reinforcing steel with epoxy-coated tie wire.

Furnish a temperature recorder with the minimum capabilities of a 7-day recording time, 2-degree F division, and 120 VAC with 9-volt backup, for each curing tank used on the project. Supply all charts, recording pins, and other equipment necessary for complete operation of the temperature recorder during the project. The temperature recorder and all associated equipment will not be paid directly but will be subsidiary to the various bid items.

Cold weather protection requirements within 72 hours of a concrete paving pour as per the following table:

PROJECTED LOW TEMP	PROTECTION REQUIRED
< 20 degrees	DO NOT POUR
20-27 degrees	cover with plastic, then a insulating blanket, and plastic on top

General Notes

 28-35 degrees
 cover with plastic, then a insulating blanket

 > 35 degrees
 no protection required

All projected temperatures will be based on the NOAA website. None of the above actions releases the Contractor from the responsibility for freeze damaged concrete for whatever reason.

Furnish and place preformed fiber material, a minimum one-half (1/2)-inch thick, as shown on the plans or directed by the Engineer.

Use Grade 3 or Grade 4 coarse aggregate in all concrete structures.

Coring of structural classes of concrete will not be allowed. All coring of miscellaneous concrete shall be at the Contractor's expense including all prep work. Coring must be completed within 3 days of notice of failing 28-day samples; otherwise pay deductions apply using 28-day compressive strength.

Provide TY II curing compound for riprap.

When doweling into concrete, clean out the hole, fill completely with epoxy, then place the dowel. Do not dip the dowel into epoxy first and shove it into the hole.

Do not place concrete when the wind gusts get to over 25 miles per hour.

Vibrate all concrete.

Provide 48 hours notice for all other concrete pours.

Tarp and heat the underside of the bridge during cold weather as directed by the Engineer.

Provide the Engineer a cold weather concrete pour plan for approval before each cold weather pour.

Item 421 - Hydraulic Cement Concrete

Class S concrete without silica fume will be allowed.

Class S concrete must contain Shrinkage Reducing Agents (SRA) and Micro/Macro fibers.

If fly ash is used, a maximum of 35% will be allowed.

Micro/Macro Fibers:

Provide 100% virgin polypropelene fibrillated fibers in all bridge slabs at a rate of 5 lbs/CY. The fibers shall conform to ASTMc1116, Type III and shall have a minimum length of ³/₄ inch. The following 100% virgin polypropelene fibrillated fibers are approved for this project: Tuf-Strand SF

DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-8	7BF09A89AF5	
County: Lubbock	Control: BPM 6447-58-001	Control: BPM 6447-58-001
Highway: Various	Sheet 3C	Sheet 3C
Use in accordance with manufacturer's Shrinkage Reducing Agents:	the above listed materials may be used if approved by the Engineer. specifications. Its and respective dosages are approved for this project:	Some repairs may extend into the bridge overhang. No additional compensation will be made for this work. Full-depth repairs will require formwork on the underside of the bridge. The contactor should expect to use a man-lift or other acceptable means to install these forms. No additional compensation will be made for this work. Drill and dowel repair areas into existing bridge deck. Do not cut existing precast panels. Hydro demolition is not allowed.
members. Target an entrained air conte concrete requiring air entrainment. Ens of concrete.	except for concrete used in drilled shafts and precast concrete int of 4.0% +/- 1% for concrete pavement and 5.5% +/- 1% for all other sure the minimum entrained air content is at least 3.0% for all classes	Item 432 - Riprap Provide 4-inch thick concrete riprap, unless otherwise indicated in the plans. Reinforce with steel reinforcing using either #3 bars on 12"x12" spacing or #4 bars on 18"x18" spacing centered in the slab. Fiber reinforcement or welded wire will not be allowed.
Air entrainment chemicals will not be a The Engineer will perform all concrete jo		In large areas of riprap, provide one-half (1/2)-inch thick expansion joint material at approximately 15-foot intervals, or as determined by the Engineer.
Use 4-inch by 8-inch cylinder molds fo cylinder molds and lids subsidiary to th	r concrete with Grade 3 or smaller coarse aggregate. Supply new ne various bid items.	All riprap associated with bridge header banks, under the bridge and along the header slopes, will be placed as shown on the CRR standard. This standard will not apply to all other miscellaneous riprap placements.
Concrete plant must be capable of prov aggregate.	iding automated moisture content control for both coarse and fine	Place asphalt expansion joint material between proposed riprap and utility poles, guy wires, vent pipes, stand pipes and as directed.
<u>Item 429 – Concrete Structure Repai</u>	ir .	Place felt or filter fabric at open joints as required by the Engineer. This will be considered subsidiary.
Utilize the latest TxDOT Concrete Rep	air Manual for repairs.	Follow cold weather protection requirements listed under Item 420.
1	ed by TxDOT forces prior to the beginning of work and will be as measured on the specified horizontal surface.	Seal between concrete boundaries.
Match existing surface finishes for all r Standard Specifications, payment will Follow cold weather protection require:	-	<u>Item 454 – Armor Joints</u> Limits of pay are 1' on either side of the armor joint. Deck repair required beyond that will be paid as applicable Item 429.
Some steel may be epoxy coated. Apply	y epoxy if the existing bridge decks is epoxy coated rebar.	
	General Notes G	Н

DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89	AF5		
County: Lubbock	Control: BPM 6447-58	3-001	Control: BPM 6447-58-001
Highway: Various	Shee	et 3D	Sheet 3D
Item 502 - Barricades, Signs And Traffic Ha			The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could
Prior to beginning construction, the Engineer s	hall approve the routing of traffic and sequence of	of work.	not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible
Contractor-requested modification of proposed Department.	TCP resulting in additional cost will not be paid	l for by The	Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.
Confirmation speed limit signs shall be placed	after END ROAD WORK sign.		Correct all noted deficiencies within 7 calendar days, otherwise, cease all operations until the noted deficiencies are corrected.
Traffic control signs are required on the media	n barrier.		Stockpiles that meet the barricade requirements as shown on the BC(10) Standard are required to be erected at
Additional signs and barricades as directed by	the Engineer shall be considered subsidiary to Ite	em 502.	the time of material delivery in the Right-of-Way and maintained as long as the stockpile exists. Payment for Material-on-Hand will be withheld from the estimate for inadequate barricades or the failure to maintain
Only one month of barricade payment will be p locations worked.	provided for each month worked, regardless of th	ne number of	barricades on a per stockpile basis as determined by the Engineer. Like new traffic control devices will be required at the initial setup for all projects or as approved by the
Provide flashing portable arrow panels for all le	ane closures.		Engineer.
Wash the channelizing devices and barricades increasing by the Engineer.	following each rainfall or snowfall event and at t	imes deemed	Provide flags and a CW8-15P "MOTORCYCLE WARNING" plaque on all CW20-1D "ROAD WORK AHEAD" signs except on side roads.
	, flaggers may be required when construction ma les carrying traffic. If considered necessary by th lired.		Use only the work zone speed limit and TCP signs that are relevant to the active work area and as directed. Reset signs for subsequent work phases as work progresses and approved by the Engineer. Reset normal speed limit signs at the ends of work zones.
Fill any holes left by barricade or sign supports	s and restore the area to its original condition.		Project limit signage is required on both sides of the roadway on a divided highway.
Barricades, Signs and Traffic Handling is a pla compensation will be made.	n quantity item. If time is suspended, no addition	nal	All detours and requisite signage shall be installed before long-term TCP measures (PCTB) are installed.
Traffic switches will not be permitted on Frida	ys or any working day preceding a holiday unles	s authorized by	All bid items and work requiring traffic control is the responsibility of the contractor, even when not explicitly detailed in the plans. Consider this work subsidiary to Item 502.
the Engineer.			TMAs and Portable Changeable Message Boards will not be used as Arrow Boards.
	n shown in the plans. Any proposed alterations to e submitted to the Engineer at least 10 days prior		The contractor is required to respond on-site within 30 minutes to any traffic control maintenance after wind events, storms, etc, and as directed by the Engineer.
	mporary construction signs. Aluminum and woo led into the ground. Square tubing supports on sl		When the roadway is open to traffic and final striping is completed, any subsequent work shall be done under day time traffic control.
	support signs made of light weight flutted plasti		Ground mount all signs if possible.
Gene	ral Notes	Ι	J

DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5 **County: Lubbock** Control: BPM 6447-58-001 Control: BPM 6447-58-001 **Highway: Various** Sheet 3E Sheet 3E ROAD WORK AHEAD signage is required on adjacent service roads. **Item 545 - Crash Cushion Attenuators** Reflective tabs will be installed on all temporary barrier rail as shown in BC Reimbursable repair or replacement will be paid at contract bid prices. This project is for daytime work only. If you elect to work at night, all expenses for night work will not be Crash cushion attenuators require object marker stickers in accordance with D&OM (VIA). compensated for. Item 503 - Portable Changeable Message Sign Item 6001 - Portable Changeable Message Sign Provide messages as directed by the Engineer. Provide messages as directed by the Engineer. Inform the public 2 weeks before construction begins. Provide 2 solar powered changeable message signs for the duration of this project. Item 506 - Temporary Erosion, Sedimentation, and Environmental Controls Inform the public 2 weeks before construction begins. No SWP3 is required for this project, but should it be determined a plan is needed, it will be developed by the State Item 6185 - Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA) and implemented by the Contractor. Provide 2 TMAs for stationary use for the duration of the project. Stationary TMAs will be used during the No N.O.I. is required for this project. various phases of work required for this project. Payment will be made by the day for each TMA used in stationary operations. Estimate for stationary TMA is based on 2 per day. Water pumped off the project must have sediment and any other solids in suspension removed before discharging. Sediments removed from BMPs shall be paid for by force account. The Contractor shall submit an invoice for the work. Correct all noted deficiencies within 7 calendar days, otherwise, cease all operations until the noted deficiencies are corrected. Item 512 - Portable Concrete Traffic Barrier

Source of portable traffic barrier & stockpile location is south of New Deal, Texas on IH27 East Frontage Road GPS Coordinates: 33 42'01.66" North, 101 50'19.13" West (Coordinates obtained from Google Earth Pro) or contact Project Manager.

If hardware is missing from the barrier at the designated source then contractor will provide necessary components for installation.

Reimbursable repair or replacement will be paid at contract bid prices.

Reflectors are required every 100 ft per BC Standards.

Estimate & Quantity Sheet



 CONTROLLING PROJECT ID
 6447-58-001
 DISTRICT
 Lubbock


 HIGHWAY
 HI0027
 HI027
 HI027


COUNTY Lubbock


		CONTROL SECTIO	IN JOB	6447-5	8-001		
		PROJI	ECT ID	A0019	9585	1	
		cc	DUNTY	Lubb	ock	TOTAL EST.	TOTAL FINAL
		HIG	HWAY	ІНОО	27	1	TINAL
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	1	
	104-6009	REMOVING CONC (RIPRAP)	SY	100.000		100.000	
	401-6001	FLOWABLE BACKFILL	CY	130.000		130.000	
	429-6003	CONC STR REPAIR(DECK REP(PART DEPTH))	SF	1,000.000		1,000.000	
	429-6005	CONC STR REPAIR(DECK REP (FULL DEPTH))	SF	400.000		400.000	
	429-6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	1,110.000		1,110.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY	28.000		28.000	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	726.000		726.000	
	454-6004	ARMOR JOINT (SEALED)	LF	1,194.000		1,194.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	14.000		14.000	
	512-6017	PORT CTB (DES SOURCE)(F-SHAPE)(TY 1)	LF	2,010.000		2,010.000	
	512-6021	PORT CTB (DES SOURCE)(LOW PROF)(TY 1)	LF	420.000		420.000	
	512-6029	PORT CTB (MOVE)(F-SHAPE)(TY 1)	LF	2,100.000		2,100.000	
	512-6033	PORT CTB (MOVE)(LOW PROF)(TY 1)	LF	420.000		420.000	
	512-6041	PORT CTB (STKPL)(F-SHAPE)(TY 1)	LF	2,010.000		2,010.000	
	512-6045	PORT CTB (STKPL)(LOW PROF)(TY 1)	LF	420.000		420.000	
	512-6105	PCTB MOVE&RESET(F-SHAPE OR SNGL SLPTY1	LF	4,110.000		4,110.000	
	545-6003	CRASH CUSH ATTEN (MOVE & RESET)	EA	8.000		8.000	
	545-6005	CRASH CUSH ATTEN (REMOVE)	EA	2.000		2.000	
	545-6019	CRASH CUSH ATTEN (INSTL)(S)(N)(TL3)	EA	2.000		2.000	
	780-6002	CNC CRACK REPAIR (DISCRETE)(INJECT)	LF	50.000		50.000	
	784-6002	REP STL BRIDGE MEMBER (BEAM)	EA	3.000		3.000	
	786-6001	CARBON FIBER REINF POLYMER PROTECTION	SF	246.000		246.000	
	4002-6001	REPLACE ELASTOMERIC BEARING PADS	EA	24.000		24.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	350.000		350.000	
	6185-6002	TMA (STATIONARY)	DAY	350.000		350.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		ENVIRONMENTAL: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	





DISTRICT	COUNTY	CCSJ	SHEET
Lubbock	Lubbock	6447-58-001	04












Repair Location

			TABLE	OF REPAIRS A	ND ESTIMATED	QUANTITIES				SURAFEL TILAHUN SINTAYEHU
LOCATION #5	0104 6009	0401 6001	1 0429 6007	2 0432 6001	30454 6004	0512 6017	0512 6029	0512 6105	0545 6003	141567
LAT 33.53066201	REMOVING CONC	FLOWABLE	CONC STR REPAIR						CRASH CUSH ATTEN	1007 (/ CENSED
LONG -101.84423507	(RIPRAP)	BACKFILL	(VERTICAL & OVERHEAD)	(CONC) (4 IN)	(SEALED)	(F-SHAPE) (TY 1)	(F-SHAPE) (TY 1)	(F-SHAPE OR SNGL SLP)TY1	(MOVE & RESET)	SS/ONAL ENG
LUBBOCK COUNTY	SY	CY	SF	CY	LF	LF	LF	LF	EA	
TOTAL	40	50	100	10	141	1500	1500	1500	2	
	LAT 33.53066201 LONG -101.84423507 LUBBOCK COUNTY	LAT 33.53066201 LONG -101.84423507 LUBBOCK COUNTY SY	LAT 33.53066201 LONG -101.84423507 LUBBOCK COUNTY LUBBOCK COUNTY SY CY	LOCATION #5 0104 6009 0401 6001 ① 0429 6007 LAT 33.53066201 REMOVING CONC FLOWABLE CONC STR REPAIR (VERTICAL & OVERHEAD) LONG -101.84423507 (RIPRAP) BACKFILL (VERTICAL & OVERHEAD) LUBBOCK COUNTY SY CY SF	LOCATION #5 0104 6009 0401 6001 ① 0429 6007 ② 0432 6001 LAT 33.53066201 REMOVING CONC (RIPRAP) FLOWABLE BACKFILL CONC STR REPAIR (VERTICAL & OVERHEAD) RIPRAP (CONC) (4 IN) LUBBOCK COUNTY SY CY SF CY	LOCATION #5 0104 6009 0401 6001 1 0429 6007 2 0432 6001 3 0454 6004 LAT 33.53066201 REMOVING CONC FLOWABLE CONC STR REPAIR (VERTICAL & OVERHEAD) RIPRAP (CONC) (4 IN) ARMOR JOINT (SEALED) LUBBOCK COUNTY SY CY SF CY LF	LAT 33.53066201 LONG -101.84423507 LUBBOCK COUNTY SY CY SF CONC STR REPAIR (RIPRAP) CONC STR REPAIR (VERTICAL & OVERHEAD) CONC (4 IN) CONC (4 IN) (SEALED) (F-SHAPE) (TY 1) LUBBOCK COUNTY SY CY SF CY LF LF	LOCATION #5 0104 6009 0401 6001 1 0429 6007 2 0432 6001 3 0454 6004 0512 6017 0512 6029 LAT 33.53066201 REMOVING CONC FLOWABLE CONC STR REPAIR (VERTICAL & OVERHEAD) RIPRAP (CONC) (4 IN) ARMOR JOINT (SEALED) PORT CTB (DESSOURCE) (F-SHAPE) (TY 1) PORT CTB (MOVE) (F-SHAPE) (TY 1) LUBBOCK COUNTY SY CY SF CY LF LF LF	LOCATION #5 0104 6009 0401 6001 1 0429 6007 2 0432 6001 3 0454 6004 0512 6017 0512 6029 0512 6105 LAT 33.53066201 REMOVING CONC FLOWABLE CONC STR REPAIR (VERTICAL & OVERHEAD) RIPRAP (CONC) (4 IN) ARMOR JOINT (SEALED) PORT CTB (DESSOURCE) (F-SHAPE) (TY 1) PORT CTB (MOVE) PCTB MOVE&RESET (F-SHAPE) (TY 1) LUBBOCK COUNTY SY CY SF CY LF LF LF LF LF	LOCATION #5 0104 6009 0401 6001 1 0429 6007 2 0432 6001 3 0454 6004 0512 6017 0512 6029 0512 6105 0545 6003 LAT 33.53066201 REMOVING CONC (RIPRAP) FLOWABLE BACKFILL CONC STR REPAIR (VERTICAL & OVERHEAD) RIPRAP (CONC) (4 IN) ARMOR JOINT (SEALED) PORT CTB (DESSOURCE) (F-SHAPE) (TY 1) PORT CTB MOVE& (F-SHAPE) (TY 1) PORT CTB MOVE (F-SHAPE) (TY 1) PORT CTB MOVE& (F-SHAPE) (TY 1) PORT CTB MOVE (F-SHAPE) (TY 1) </td

0545 6019
CRASH CUSH ATTEN (INSTL)(S)(N)(TL3)
EA
1

* The repair locations depicted above are for illustrative purpose only. The actual area to be repaired may vary in size or may not correspond precisely ot the depicted location. Texas Department of Transportation LOCATION 5 SUMMARY NBI# 05-152-0-0068-01-088 S LP 289 EB CONN AT IH 27 AND S LP 289

CONT	SECT	JOB		HIGHWAY
6447	58 001			IH 27
DIST	COUNTY			SHEET NO.
05		LUBBOCK		9
	6447 DIST	6447 58 DIST	6447 58 001 DIST COUNTY	6447 58 001 DIST COUNTY



Repair Location

SURAFEL TILAHUN SINTAYE

TABLE OF REPAIRS AND ESTIMATED QUANTITIES												
LOCATION #6	0104 6009	0401 6001	1 0429 6003	2 0429 6007	3 0432 6001	4 0454 6004	0512 6017	0512 6029	0512 6041	0512 6105		
LAT 33.53723086	REMOVING CONC	FLOWABLE	CONC STR REPAIR	CONC STR REPAIR	RIPRAP		PORT CTB (DES SOURCE)	PORT CTB(MOVE)	PORT CTB (STKPL)	PCTB MOVE&RESET		
LONG -101.84339453	(RIPRAP) BACKFIL	(RIPRAP) BACKFILL	3 (RIPRAP) BA	BACKFILL	(DECK REP(PART DEPTH))	(VERTICAL & OVERHEAD)	(CONC) (4 IN)	(SEALED)	(F-SHAPE)(TY 1)	(F-SHAPE)(TY 1)	(F-SHAPE)(TY 1)	(F-SHAPE OR SNGL SLP)TY1
LUBBOCK COUNTY	SY	CY	SF	SF	CY	LF	LF	LF	LF	LF		
TOTAL	40	50	400	100	10	440	510	300	1710	2010		

0545 6003	0545 6005	0545 6019
CRASH CUSH ATTEN (MOVE & RESET)	CRASH CUSH ATTEN (REMOVE)	CRASH CUSH ATTEN (INSTL)(S)(N)(TL3)
EA	EA	EA
3	1	1

* The repair locations depicted above are for illustrative purpose only. The actual area to be repaired may vary in size or may not correspond precisely ot the depicted location.



6447 58


DIST

001

LUBBO

IH 27


SHEET NO




* The repair locations depicted above are for illustrative purpose only. The actual area to be repaired may vary in size or may not correspond precisely ot the depicted location.

S LP 289 EB AT INDIANA AVE

CTXDOT OCT 2023 CONT SECT JOB 6447 58 001 LP 289 DIST SHEET NO 05 LUBBOO






			TAB	LE OF REPAIRS AI	ND ESTIMATED QUANTITIES			
	LOCATION #9	1 0429 6003	0429 6007	2 0454 6004	0512 6021	0512 6033	0512 6045	3 4002 6001
[LAT 33.59908802	CONC STR REPAIR(DECK	CONC STR REPAIR	ARMOR JOINT	PORT CTB (DES SOURCE)	PORT CTB (MOVE)	PORT CTB (STKPL)	REPLACE ELASTOMERIC
[LONG -101.84292151	REP(PART DEPTH))	(VERTICAL & OVERHEAD)	(SEALED)	(LOW PROF)(TY 1)	(LOW PROF)(TY 1)	(LOW PROF)(TY 1)	BEARING PADS
[LUBBOCK COUNTY	SF	SF	LF	LF	LF	LF	EA
	TOTAL	200	200	96	420	420	420	16

* The repair locations depicted above are for illustrative purpose only. The actual area to be repaired may vary in size or may not correspond precisely ot the depicted location. Texas Department of Transportation

MUNICIPAL DRIVE AT YH DRAW/ CESAR CHAVEZ DR

©TxDOT	OCT 2023	CONT	SECT	JOB		HIGHWAY
REVISIONS		6447	6447 58 001		H 27	
		DIST		COUNTY		SHEET NO.
		05		LUBBOCK		13





Repair Location

TABLE OF REPAIRS AND ESTIMATED QUANTITIES													
LOCATION #10	0104 6009	0401 6001	1 0429 6003	0429 6007	0432 6001	2 0454 6004	3 4002 6001						
LAT 33.5801783	REMOVING CONC	FLOWABLE BACKFILL	CONC STR REPAIR	CONC STR REPAIR	RIPRAP (CONC)(4 IN)	ARMOR JOINT	REPLACE ELASTOMERIC						
LONG -101.84009504	(RIPRAP)	FLOWADLE DAGKFILL	(DECK REP(PART DEPTH))	(VERTICAL & OVERHEAD)	RIFRAF (CONC)(4 IN)	(SEALED)	BEARING PADS						
LUBBOCK COUNTY	SY	CY	SF	SF	CY	LF	EA						
TOTAL	20	30	200	60	8	57	8						




SURAFEL TILAHUN SINTAYE


Texas Department of Transportation LOCATION 10 SUMMARY NBI# 05-152-0-0067-11-187 IH 27 SB ON-RAMP AT IH 27 SB OFF-RAMP CTxDOT OCT 2023 CONT SEC 6447 58 H 27 001 DIST SHEET NO. 14

05


LUBBOO


* The repair locations depicted above are for illustrative purpose only. The actual area to be repaired may vary in size or may not correspond precisely ot the depicted location.































				l											CR	RASH CUSHIO	N				
		PLAN				DIRECTION	FOUNDA	TION PAD	BACKUP SUPPORT	BACKUP SUPPORT	BACKUP SUPPORT	т		AVAILABLE			MOVE /	RESET	ιI		
LOC NO.	TCP PHASE	SHEET NUMBER	LOCATION	STA	TEST LEVEL	TRAFFIC (UNI/BI)	PROPOSED MATERIAL	PROPOSED THICKNESS	DESCRIPTION	WIDTH	HEIGHT	SITE LENGTH	INSTALL	REMOVE	MOVE/ RESET	FROM LOC.*	N 1	w N			
5	I		S LP 289 EB CONN AT IH 27 AND S LP 289		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'		1		1						
	н		S LP 289 EB CONN AT IH 27 AND S LP 289		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'				1	5					
6	I.		US 84 ML AT IH 27		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'		1		2						
	н		US 84 ML AT IH 27		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'			1	1	6					
7	I.		S LP 289 EB AT INDIANA AVE		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'				1						
	н		S LP 289 EB AT INDIANA AVE		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'				1	7					
8	I.		S LP 289 WB AT INDIANA AVE		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'				1						
	н		S LP 289 WB AT INDIANA AVE		TL-3	UNI			PORTABLE TRAFFIC BARRIER	40'	32'			1		8					
					-																
																		-			
																		-			
																		-			
																		-			
				1	-													-			
				i											<u> </u>				1		
					-													-			
				i	-														1		
					+												-				
					+									<u> </u>	<u> </u>		+	+			
				1								TOTALS	2	2	8	I			•		
USA	MAINTENANCE ABLE FICIAL	Ξ	Image: CRASH CUSHIC											USHIOI	N SUMA	IAR	r Sł	- +			
WIDE														E: CCSS.dg	յո			т Ск:			
													©	T×DOT REVISIO				58			


05 LUBBOCK FEDERAL AD PROJECT SHEET NO. BPM 6447-58-001 23


FOR DEFINITIONS SEE THE "CRASH CUSHION CATEGORIZATION CHART.PDF" AT TH DESIGN DIVISION (ROADWAY STANDARDS) WEBSITE. USE QUICK LINKS TO ACCESS ATTENUATORS / CRASH CUSHIONS SECTION.


http://www.dot.state.tx.us/insdtdot/orgchart/cmd/cserve/standard/rdwylse.htm





















































DSCLMARE: The use of this stondard is governed by the "Teras Engineering Practice Act". No servary of ony that is made by TADOT for ony purpose stateserver. TOOT oscurate no responsibly for the conversion to this standard to other formatic and incorrect results or domoges resulting from the use.

DATE

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manualon Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate worning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texos," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- 9. The temporary traffic controldevices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic controldevices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manualon Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits, For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travellanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility sofety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.


COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES


- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT
http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEE	τ1	OF	12			
Texas Department	of Tra	nsp	ortation		Sa Div	affic fety fision ndard
BARRICADE AN GENER AND RE BC	2AL QUI	N RE	OTES MEN1	5		ON
FILE: bc-21.dgn	-	DOT	CK: TxDOT	DW:	TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB		HG	HWAY
4-03 7-13	6447	58	001		VA	RIOUS
9-07 8-14	DIST		COUNTY			SHEET NO.
5-10 5-21	05		LUBBOCK	t i		43
95						









DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5

WHEN NOT IN USE, REMOVE THE POWS FROM THE RIGHT-OF-WAY OR PLACE THE POWS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- 2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO,"
- "FOR," "AT," etc. Kessages should consist of a single phase or two phases that alternate. Three phase messages are not allowed. Each phase of the
- message should convey a single thought, and must be understood by last
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway: i.e.,
- "EXIT CLOSED." Do not use the term "RAMP." 5. Alwoys use the route or interstate designation (IH, US, SH, FM)
- along with the number when referring to a roadway. 6. When in use, the bottom of a stationary PCMS message panel should be
- a minimum 7 feel above the radius, where possible. 7. The message term "WEEKEND" should be used only if the work is to
- start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work
- accountings and mous of work should be displayed on the runs in work in the figure of the runs in work should be displayed on the runs in work work of the run of
- Do not "llash" messages or words included in a message. The message should be steady burn or continuous while displayed. 10. Do not present redundant information on a two-phase message: i.e.,
- keeping two lines of the message the same and changing the third line.
- Resping two lims of the message the same and changing the timo lime.
 10. on out display the message "LANES SHIFT ICET" or "LANES SHIFT RICHT" on 0 PCMS. Drivers do no understand the message.
 13. Do not display messages that scrollhorizontally or vertically across
- the face of the sign. 14. The following table lists abbreviated words and two-word phrases that
- are acceptable for use on a PCMS. Both words in a phrase must be displayed tagether. Words or phrases not on this list should not be obbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text umits, ney snouto ce visible from ot least 1/2 (.3) mile and the text should be leigble from ot least 600 feet of indipit and 800 feet in doylight. Truck mounted units must have a character height of 10 inches and must be leigble from al least 400 feet. 16, Each line of text should be centered on the message board rother than better in the line in the line.

- 15. Each fine of text should be centered on the message wave return the left or right justified.
 17. If disobled, the PCMS should default to an illegible displot that will not dorm motorists and will which be used to dert envires that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Access Rood A	CCS RD	Najor MAJ	
Alternate	ALT	Wiles	MI
Avenue	AVE	Wiles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevord	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction			PKING
Ahead	CONST AND	Parking	
CROSSING	XING	Rood	RD
Detour Route	DETOUR RTE	Right Lane	RTLN
Do Not	DONT	Saturday	SAT
		Service Rood	SERV RD
East	E (route) E	Shoulder	SHLDR
Eastbound		Slippery	SLIP
Emergency	EMER	South	S
Emergency Vehicle		Southbound	(route) S
Entrance, Enter	ENT	Speed	SPD
Express Lone	EXP LN	Street	ST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freewoy Blocked	FWY BLKD	To Downtown	TO DWNTN
Fridoy	FRI	Troffic	TRAF
Hozordous Driving		Trovelers	TRVLRS
Hazardous Material		Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway		Vehicles (s)	VEH, VEHS
Hour (s)	HR, HRS	Warning	WARN
Information	INFO	Wednesday	#ED
It is	ITS	Weight Limit	WT LIWIT
Junction	JCT	West	
Left	LFT	Westbound	(route) W
Left Lone	LFT LN	Westbound	WET PVMT
Lone Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL		INCINI
Maintenance	MAINT	1	

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES (The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Phase 2: Possible Component Lists

* * Advance

Notice List

TUE-FRI

XX AM-

X PM

APR XX-

XX

X PM-X AM

BEGINS

MONDAY

BEGINS

MAY XX

MAY X-X

XX PM -XX AM

NEXT

FRI-SUN

XX AM

то

XX PM

NEXT

TUE

AUG XX TONIGHT XX PM-

XX AM

Road/Lane/Ram	p Closure List	Other Condit	ion List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAY TIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	L ANES SHIFT
XXXXXXXX BLVD CLOSED	* LANES SHIFT in Phose	1 must be used with STAY	IN LANE in Phose 2.

APPLICATION GUIDELINES

Phose Lists"

1. Only 1 or 2 phases are to be used on a PCMS.

and should be understandable by themselves.

L Univ for 2 prosessore to be used on a Pues. 2. The sts phoses (or both should be selected from the "Road/Lone/Romp Closure List" and the "Other Candition List". 3. A 2nd phose can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice

4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
 If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases,

6. For advance notice, when the current date is within seven days

of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for


Action to Take/Effe List		Location List		Warning List	
MERGE RIGHT	FORM X LINES RIGHT	AT FM XXXX		SPEED LIMIT XX MPH	
DETOUR NEXT X EXITS	USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING		Maximum Speed XX Mph	
USE EXIT XXX	USE EXIT I-XX NORTH	NEXT X MILES		MINIMUM SPEED XX MPH	
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N	PAST US XXX EXIT		ADVISORY SPEED XX MPH	
TRUCKS USE US XXX N	WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX		RIGHT LANE EXIT	
WATCH FOR TRUCKS	EXPECT DELAYS	US XXX TO FM XXXX		USE CAUTION	
EXPECT DELAYS	PREPARE TO STOP			DRIVE SAFELY	
REDUCE SPEED XXX FT	END SHOULDER USE			DRIVE WITH CARE	
USE OTHER ROUTES	WATCH FOR WORKERS				
STAY IN LANE ×		* *	See Ap	plication Guidelines I	Note 6.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate. 2. Roadway designations IH, US, SH, FM and LP can be interchanged as
- appropriate
- 3. EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can
- be interchanged as appropriate. 4. Highway names and numbers replaced as appropriate. 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
 FT and NI, MILE and MILES interchanged as appropriate.
 AT, BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a
- location phase is used.

XPWY XXX FT	Sunday	SUN PHONE		SHEET 6 OF 12	
OG AHD	Telephone Temporary	TEMP		Traffic	
RWY, FWY	Thur sdoy	THURS	PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR	Safety Division	,
WY BLKD RI	To Downtown	TO DWNTN	CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4)	Texas Department of Transportation Standard	ď
AZ DRIVING	Troffic	TRAF	PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE		
IAZMAT	Trovelers	TRVLRS	UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION		
IOV	Tuesday Time Minutes	TUES TIME MIN		BARRICADE AND CONSTRUCTION	
MIY .	Upper Level		OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS		
	Vehicles (s)	VEH, VEHS	SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.	PORTABLE CHANGEABLE	
R,HKS I	Warning	WARN			
NFO TS ICT	Wednesday	WED	FULL MATRIX PCMS SIGNS	MESSAGE SIGN (PCMS)	
	Weight Limit	WT LIMIT	1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as isted in Nate 15 under "PORTABLE		
FT	West	W	CHNICATE MISSING SIGNS' show.		
FTLN	Westbound Wet Povement	(route) W WET PVMT	2. When symbolisins, such as the "Flager Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it	BC(6)-21	
	Will Not	WONT	shall maintain the legibility/visibility requirement listed above.	FILE: bc-21.dgn DN: TxDOT CK: TxDOT DW: TxDOT CK: Tx	*DOT
WR LEVEL		WORT	3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute	C TxDOT November 2002 CONT SECT JOB HIGHWAY	
IA I NT			for, or replace that sign.	REVISIONS 6447 58 001 VABIOUS	
			4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the	9-07 8-14 DIST COUNTY SHEET P	10
JS-number, SH-nu	umber, FM-number		some size orrow.	7-13 5-21 05 LUBBOCK 48	
			-		_

DATE



DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device. 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections. one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the
- cones in proper position and location. For short lerm stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as
- opproved by the Engineer. 4. Drums and all related items shall comply with the requirements of the current version of the "Texos Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely offect their appearance or serviceability. 6. The Contractor shall have a maximum of 24 hours to replace any plastic
- drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

- Pre-auglified plastic drums shall meet the following requirements:
- Plastic drums shall be a two piece design: the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air lurbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight (lexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports. 4. Drums shall present a profile that is a minimum of 18 inches in width
- at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches. 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle
- shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign. 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than
- 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- stic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material. 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10 Drum, and have shall be marked with manufacturer's name and model number

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300."Sign face Materials. Type A or Type B reflective sheeting shalt be supplied unless otherwise specified in the planes.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surfoce

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbaas separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- 2. Bases with built-in bollost shall weigh between 40 lbs. and 50 lbs. Built-in ballost can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.

€<u></u> 4" mox 4." min 8" max Each drum shall have (typ) a minimum of 2 orange and 2 white stripes using Type A or Type B retroreflective 2" max sheeting with the (typ.) top stripe being or onge. Toper to allow for stacking a minimum of 5 See Ballasi drums Note 3 This detail is not intended for fabrication. See note 3 and the CWZTCD list for providers of opproved **Detectable Pedestrian** Rorricode Continuous smooth rail for hand trailing 36' Detectoble Edge

2" Mox

9/16" dia. (typ)

for mounting

worning lights

signs and

DETECTABLE PEDESTRIAN BARRICADES

18" min

Hondle

Too should not

allow collection


of water or

debris

-E

<u>ت</u> ا

- DETECTABLE PEDESTRIAN BARRICADES I. When esiting predistrion foculities or dirupted, closed, or relocated in a TTC zone, the temporary facilities shatibe detectable and include accessibility features consistent with the features present in the existing pedestrion facility. Refer to WZ(815:2) for Pedestrian Control requirements for Sidewalk. Diversions, Sidewalk Detours and Crossenik Closures. 2. Where pedestrians aith visual disabilities normally use the closed addreads, to Detectable Pedestrian Barricode shall be of a Type 3. Barricode. 3. Detectable pedestrian barricode similar to the one pictured above, longluidand channeling devices, space concrete barriers, and ead or chain link fancing with a continuous detectable edging can satisfactoriny delives a pedestrian
- detectable edging can satisfactorily d eate a pedestrion
- Tope, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements
- 5. Warning lights shall not be attached to detectable pedestrian borricodes
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



8 R9-9 R9-10 R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.


Texas Departme			Sa Div Stai	affic fety ision ndard
CHANNEL			S	
B	C(8)-	21	-	au 1-001
File: bc-21.dgn	C(8)-	21	T×DOT	ск: ТхDO
В <u>г. с. 21.dgn</u> © ТхЮОТ November 2002	C(8)-	21	T×DOT	ck: TxDO
B FILE: bc-21.dgn © TXDOT November 2002 REVISIONS	C(8)-	21 T CK: TxDOT DW: T JOB	ТхDOT	
В <u>г. с. 21.dgn</u> © ТхЮОТ November 2002	C(8)-	21 T CK: TxDOT DW: T JOB	TxDOT HIG VA	HWAY


OATE:

this standard is governed by the "Texas Engineering Proclice Act". No sorronly of 1.4011 for any purpose mailsource. T1.4001 assumes no responsibility for the conner to other formals or for incorrect results or domoges resulting from its use. 295 AIMER: The use of s mode to s standar


DISCLA the is

yn Nois







DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5




DSCLAMER: The use of this standord is governed by the "Texos Engineering Proctice Act". No worronly of ony the dis mode by Tst001 for ony purpose wholssever. Tst001 ossumes no responsibility for the conversion of this standord to other formots or for incorrect results or domoges resulting from its use.








SHEET NO.


55
























































HEAT STRAIGHTENING



IMPACT DAMGE SPAN 3 GIRDER 5



IMPACT DAMAGE SPAN 3 GIRDER 1

HEAT STRAIGHTENING PROCEDURE: 1. Set traffic control. Close lanes on top of the bridge as directed by the Engineer.

Check gap (if any) between top of top flange and bottom of deck for any debns and clear to allow complete contact to occur.

3. Remove the diaphragms, if necessary, for heat straightening.

4. Heat straighten distorted beam and repair torn web in accordance with Item 784, "Steel Member Repair."

5. Remove defects and grind the flange smooth in the damaged area.

Repair/replace/re-weld damaged dlaphragms as shown in the detail after the beam is restored in both shape and alignment.

7. Clean and paint the repair area as directed by the Engineer.

Inject epoxy into any remaining gap between top flange and deck. The length of flange separation that must be injected is approximately 5 feet.

9. Open the roadways to normal traffic as directed by the Engineer.

GENERAL NOTES:


GENERAL NOTES: Notify TXDOT Bridge Division at least two weeks in advance by e-mailing BRG-FO-STL@Ndot.gov prior to beginning work to allow for inspection of repairs by a Bridge Division structural steel inspector. Use heat-staghtening to repair and restore the shape of beams and dispiragms, Heat stradgitten the members in accordance with Item 784, "Steel Member Repair," Apply sufficient force combined with heat to accomplish work but do not fracture member, Repair additional damage caused by our strategies and replacement of dispiragm members is an accordance with a drog for any additional payment will be made for removal and replacement of dispiragms.


payment vill be made for removal and replacement of diaphragms. Provide temporary supports and jacks to allow jacking of beam to restore contact of fange to bottom of deck. Provide ASTIM A709 steel with minimum Grade 36 in aphragms with them 442, Wated to Structures for new Radlographic Inspection of flange and web welds are required.


Radlographic Inspection of tiange and web welds are required. Provide Type IX epoxy for gap injection in accordance with DMS 6100 "Epoxies and Adhesives." Restore the path protection for repaired beams and disphragms with System XX per Item 446, "Faled Cleaning and Painting Steel." and as directed by the Engineer. Match the appearance could with the existing structed. Assume exhapting paint coating contains hazardous materials, unless otherwise noted.


ATE OF TEL	Texas Department of Transportation								
*	STEEL BEAM								
SURAFEL TILAHUN SINTAYEHU	REPAIR								
Consel News	Location 2 NBI: 05-152-0053-18-078								
	FILE:		DN:		CK:	DW:	CK:		
01/23/2024	CTxDOT	August 2022	CONT	SECT	JOB		HIGHWAY		
MANNOLA, P.E. 04/25/2024	REVISIONS 6447 58 001					VARIOUS			
			DIST		COUNTY		SHEET NO.		
			05	1	LUBBOCK	(75		

DATE









DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5

VERTICAL AND OVERHEAD REAPIR NOTES:

Identify and mark all repair locations prior to beginning work. Verify areas and quantities with Engineer. Provide access for the Engineer to Inspect and verify repair areas. Identify repair areas over traffic prior to beginning work.

Prepare detailed repair procedure in accordance with Chapter 3, Section 2 of the TxDOT Concrete Repair Manual and Intermediate Concrete Spall Repair Detail.

Repairs are paid for as Item 429, "Concrete Structure Repair".

Remove damged, delaminated and all previously applied repair material.

Excavate 3/4" min. behind exposed reinforcement.


Square patch perimeters 1/2" deep minimum.


Roughen concrete substrate to promote bond of patch material.

Apply coarse aggregate If using a non-extended repair mortar.


Contain patch material in intended repair area. Do not smear onto adjacent surfaces.

Apply patch material to clean, SSD substrate,





REFLECTED PLAN



DECK SOFFIT SPALL REPAIR

Scale: 1/4" = 1'-0", Unless noted otherwise


BEAM END SPALL REPAIR NOTES:

Identify and mark all repair locations prior to beginning work. Verify areas and quantities with the Engineer. Provide access for the Engineer to inspect and verify repair areas.

Prepare a detailed repair procedure for each location. Provide photographs in the repair procedure in order to verify locations. Spalled concrete shall be repaired in accordance with the Concrete Repair Manual Chapter 3. Section 2 and detail below, Creates scherding outside of the Intermediate spall repair in otherwise sound concrete shall be epoxy injected according to the Concrete Repair Manual Chapter 3. Section 3.

For repairs deeper than 2" with no other mild reinforcing present, install stainless steel pins in existing concrete to anchor repair material.

Repairs are paid for as Item 429, "Concrete Structure Repair".



DIAPHRAGM SPALL REPAIR NOTES:


Identify and mark all repair locations prior to beginning work. Verify areas and quantities with the Engineer, Provide access for the Engineer to inspect and verify repair areas,

Prepare detailed repair procedure in accordance with Chapter 3, Section 2 of the TxDOT Concrete Repair Manual and detail below.

For repairs deeper than 2" with no other mild reinforcing present, install stainless steel pins in existing concrete to anchor repair material.


Trowel apply repair materials to a maximum depth of 6". Form and place material is repair depth exceeds 6".

Repairs are paid for as Item 429, "Concrete Structure Repair".





Scale: 1/4" = 1'-0"



Grind to 1" radius


(Typ)

Bearing pad

Prestressed

REFLECTED PLAN

beam



18

SECTION B-B

BEAM END SPALL REPAIR Scale: 1/4" = 1'-0"



______ P.E. 04/23/2024




	MISCELL	ANE(DETA	ous IL	REPAIR		
CIXDOT	OCT 2023	CONT	SECT	JOB	HIGHWAY	1
	REVISIONS	6447	58	001	VARIOUS	1
		DIST		COUNTY	SHEET NO.	
		05		Lubbock	80	1


ž


07:40

06/13/2023 DOCUMENT N










JOINT AT INTERIOR BENT & ABUTMENT



ž

07:40 ME

06/13/2023 DOCUMENT NA

NOTES

Preformed fibe material board

- 1. SAW CUT AND REMOVE SLAB 1' ON BOTH SIDES OF JOINT OR AS DIRECTED BY THE ENGINEER. DECK REPAIR (FULL DEPTH) WITHIN 1' ON EACH SIDE IS SUBSIDIARY TO ITEM 0454-6004 "ARMOR JOINT (SEALED) (LF)". ANY FULL DEPTH DECK REPAIR BEYOND 1' ON EACH SIDE IS PAID BY ITEM 0429-6005 "CONC STR REPR(DECK REP (FULL DEPTH)) (SF)".
- REMOVAL OF ARMOR JOINT AND CUTTING BACK AND RECONSTRUCTING SLAB ENDS WILL BE GOVERNED BY THE METHODS OUTLINED IN ITEM 429 - CONCRETE STRUCTURE REPAIR, EXISTING STEEL SHALL NOT BE CUT OR REMOVED.
- 3. CONCRETE STRUCTURE REPAIRS (ITEM 429) MUST BE FORMED IN A MANNER THAT WILL NOT REDUCE THE VERTICAL THICKNESS OF THE BRIDGE DECK OR AS APPROVED BY THE ENGINEER.
- 4. PROVIDE CONCRETE SURFACE FINISH AS APPROVED BY THE ENGINEER.
- LATERAL REINFORCING STEEL BARS FULLY EXPOSED WHILE BREAKING BACK SLAB SHALL BE REPLACED AND WELDED TO EXPOSED LONGITUDINAL BARS IN ACCORDANCE WITH ITEM 448 -STRUCTURAL FIELD WELDING, ENGINEER APPROVAL IS REQUIRED PRIOR TO PLACING CONCRETE.
- 6. LATERAL LIMITS OF REPAIR WILL BE AS CLOSE AS IS PRACTICAL TO THE FACE OF THE BRIDGE RAIL OR AS DETERMINED BY THE ENGINEER.
- CONCRETE SHALL BE POURED TO MATCH THE THICKNESS OF THE ADJOINING CONCRETE BRIDGE DECK. COPE TOP EDGE OF THE JOINT TO MATCH THE SURROUNDING PAVEMENT. INSURE A SMOOTH RIDING SURFACE ACROSS JOINTS.
- 8. CURE CONCRETE ACCORDING TO ITEM 420 OR AS DIRECTED BY THE ENGINEER.
- 9. SALVAGE EXISTING REINFORCING STEEL WHERE POSSIBLE. ALL EXISTING STEEL SHALL BE CLEANED AND EXTENDED INTO REPAIR. WHEN STEEL SHOWN IS NOT PRESENT, ADDITIONAL STEEL SHALL BE PLACED AS SHOWN. REPLACE STEEL WHEN NOT SALVAGABLE. THIS STEEL SHALL NOT BE PAID FOR DIRECTLY, BUT CONSIDERED SUBSIDIARY TO OTHER BID ITEMS.

10. USE ARMOR JOINT DETAIL (AJ) FOR ARMOR JOINT PLACEMENT.

11. SAME PROCEDURE SHALL BE USED FOR BOTH INTERIOR JOINTS AND ABUTMENT JOINTS.



ALL P.I. 04/23/2024

SHEET 2 OF 3


 MISCELLANEOUS REPAIR DETAIL

 ©n007
 0CT223
 corr
 J08
 HERMAN

 10007
 0CT223
 corr
 J08
 HERMAN

 10007
 0CT223
 corr
 J001
 VARIOUS

 1001
 1001
 VARIOUS
 BRT PACABARY



DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5

STORMWATER POLLUTION PRVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For projects with less than one acre of soil disturbing activity and that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ): BPM 6447-58-001

1.2 PROJECT LIMITS:

From: VARIOUS

To: VARIOUS

1.3 PROJECT COORDINATES:

Location 1: (Lat) 33.51791859,(Long) -101.77395919 Location 2: (Lat) 33.52962615,(Long) -101.81923748 Location 3: (Lat) 33.57802138,(Long) -101.82553068 Location 4: (Lat) 33.59221018,(Long) -101.82133689 Location 5: (Lat) 33.53066201,(Long) -101.84423507 Location 6: (Lat) 33.53723086,(Long) -101.84339453 Location 7: (Lat) 33.52891781,(Long) -101.84760103 Location 9: (Lat) 33.5290968,(Long) -101.88760403 Location 9: (Lat) 33.5801783,(Long) -101.8470403

1.4 TOTAL PROJECT AREA (Acres): XXX Acres 1.5 TOTAL AREA TO BE DISTURBED (Acres): 0

1.6 NATURE OF CONSTRUCTION ACTIVITY:

ARMORED JOINTS REPLACEMENT, STRUCTURAL PATCHING BEARING PAD REPLACEMENT, AND RIPRAP REPAIR

Description

1.7 MAJOR SOIL TYPES: Soil Type

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):
PSLs must be depicted on the Environmental Layout Sheets

in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

PSLs determined during preconstruction meeting
X PSLs determined during construction

No PSLs planned for construction

Туре	Sheet #s	activi
		Conta Date
		🛛 Sanita
		🛛 Trash
		🗆 Long-
		⊠ Discha runof other
		Other:
		Other:
II off-ROW PSLs required by the	Contractor are the Contractor's	Other:

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.) & Mobilization

- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and gr
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
 - Remove existing metal beam guard fence (MBGF), bridge rai
- Install proposed pavement per plans
- □ Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
 Place flex base
- Rework slopes, grade ditches

Other:

- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

X Other: ARMORED JOINT REPLACEMENT, STRUCTURAL PATCHING, AND POLYESTER POLYMER CONCRETE OVERLAY

Other:

1.10 POTENTIAL POLLUTANTS AND SOURCES:
Sediment laden stormwater from stormwater conveyance over

- disturbed area X Fuels, oils, and lubricants from construction vehicles, equipment,
- and storage Solvents, paints, adhesives, etc. from various construction activities
- X Transported soils from offsite vehicle tracking
- X Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- X Sanitary waste from onsite restroom facilities
- ⊠ Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
 Discharges from concrete washout activities,
- runoff from concrete cutting activities, and
- other concrete related activities

Other:

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

	Tributarles	Classifled Waterbody
	DOUBLE MOUNTAIN FORK	*D.M.F.B.R. (1241)
	BRAZOS RIVER	Impaired for bacteria
rub		
ail		
	* Add (*) for impaired waterbodies	s with pollutant in ().

LBB DISTRICT ADVISEMENT:

Within the project area there area identified Waters of the United States (W.O.T.U.S.). Please review the EPIC for any applicable permits, best management practices, or environmental commitments that may apply. Listed Below are the identified WOTUS(s) in the project limits:

1.12 ROLES AND RESPONSIBILITIES: TxDOT X Development of plans and specifications

- X Perform SWP3 inspections
- X Maintain SWP3 records and update to reflect daily operations Other:

Other:

NOTE: Environmental Documentation shall be uploaded to Site	
Manager and Projectwise within 7 calendar days per CGP Part III	i.E

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

X Day To Day Operational Control X Maintain schedule of major construction activities X Install, maintain and modify BMPs Other:

Other	

NOTE: Environmental Documentation must be readily available

LBB DISTRICT NOTE:

Concrete truck wash-out is allowed if the following are provided: a) wash-out of concrete trucks to surface waters in the state, including storm sewer drains and inlets is prohibited. b) washout shall be to a structural control c) the direct discharge of wash-out water is prohibited at all times d) the discharge shall not contribute to groundwater contamination e) wash-out areas must be shown on the site map; f) wash-out pits shall be bermed and lined with plastic

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

© 2223 Sheet 1 of 3								
FED. RD. DIV. NO.		SHEET NO.						
6		BPM	1 6447-58-0	83				
STATE		STATE DIST.		OUNTY				
TEXA	S	Ø5	LUBBOCK					
CONT.		SECT.	JOB HIGHWAY NO.					
6447	7	58	ØØ1 VARIOUS					

TORMWATER POLLUTION PRVENTION PLAN (SWP3):									
2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE	2.3 PERMANENT CONTR (Coordinate post-construction maintenance sections.) BMPs To Be Left In Place Per	n BMPs with appropriate TxDOT	2.5 POLLUTION PREVENTION MEASURES: X Chemical Management Concrete and Materials Waste Management Debris and Trash Management			2.7 ALLOWABLE NON-STORMWATER DISCHARGES: X Fire hydrant flushings X Irrigation drainage X Pavement washwater (where spills or leaks have not occurred,			
The Contractor shall be the responsible party for implementing	_	Stationing	Dust Control			and detergents are	not used)		
he BMPs described herein and for complying with the SWP3	Туре	From To	⊠ Sanitary Facilities			X Potable water source	es		
or control of erosion and sedimentation during day-to-day			X Other: Lidded Dumpster (Pa	rt III.G.4.c in CGP)		X Springs			
operations. The Contractor shall implement changes to this						X Uncontaminated gro			
SWP3 approved by TxDOT within the times specified in this			Other:			X Water used to wash X Other allowable non-			Il
SWP3 or the CGP.			Other:			TPDES GP TXR15		discharges as	s allowed by
2.1 EROSION CONTROL AND SOIL						NOTE: Discharges from		activities are	e prohibited u
STABILIZATION BMPs:			Other:		managed by appropria				
Г/Р									
Protection of Existing Vegetation						2.8 DEWATERING:			
□ □ Vegetated Buffer Zones			2.6 VEGETATED BUFFER Z	ONES		Dewatering discharges			
Soil Retention Blankets			Natural vegetated buffers shall		easible to	and surface water inclu			
Geotextiles			protect adjacent surface waters			trenches, excavations, foundations, va accumulation are prohibited unless m			
□ □ Mulching/ Hydromulching			zones are not feasible due to s			controls to prevent an			
 Soil Surface Treatments Temporary Seeding 			additional sediment control me	asures have been i	ncorporated	sediment and other po			5
 Permanent Planting, Sodding or Seeding 	Refer to the Environmental I	_ayout Sheets/ SWP3 Layout Sheets	into this SWP3.						
 Biodegradable Erosion Control Logs 	located in Attachment 1.2 of			Stat	onIng	All disturbed areas and erosion and sediment control dev			
 Blodegradable Elosion Control Eggs Rock Filter Dams/ Rock Check Dams 			Туре	From	То				
Vertical Tracking						shall be inspected at le		• • • • •	
□ Interceptor Swale						Inspections shall be pe Field Inspection and M			
Riprap						retained in Attachment			2 110 anu
 Diversion Dike Temporary Pipe Slope Drain 									
 Temporary Pipe Slope Drain Embankment for Erosion Control 	2.4 OFFSITE VEHICLE T	RACKING CONTROLS:				2.10 MAINTENANCE			
 Paved Flumes 	x Excess dirt/mud on road					Control measures shall		inotellad acc	ording to
Other:	Haul roads dampened for					specifications. If it is de			
Other:	Loaded haul trucks to be					measure is not operation			
Other:	Stabilized construction ex	, it				accomplished as soon			
Other:	Daily street sweeping					anticipated rain event,			
2.2 SEDIMENT CONTROL BMPs:	Other:					days after being able to	o access the	site. Mainten	ance shall b
	Other:					performed by the Cont			
「 / P 〕 □ Biodegradable Erosion Control Logs						Inspection and Mainter		t Form 2118 a	and retained
 Dewatering Controls 	Other:		Refer to the Environmental Lay		Layout Sheets	in Attachment 2.3 of th	is SWP3.		
Inlet Protection			located in Attachment 1.2 of thi	is SWP3					
Rock Filter Dams/ Rock Check Dams	Other:								
Sandbag Berms			Inspection of Controls:						
□ □ Sediment Control Fence			Lubbock District, an Informal in work day; a formal Inspection of			1	STOR	MWATER	POLLUT
Stabilized Construction Exit			inspection report using Form 2				PREV	ENTION F	PLAN (SW
 □ Floating Turbidity Barrier □ Vegetated Buffer Zones 	Litter and Construction I	Debris:	days. Inspectors must Inspect	disturbed areas tha	have not been		(Less	Than 1 A	cre)
 Vegetated Burrer Zones Vegetated Filter Strips 	Storage of construction and	l waste materials on-site shall be	finally stabilized, areas that are				o		-
		ractor shall establish a schedule for	that are exposed to rain, dischar for evidence of, or the potentia				C) 2023		Sheet 2 of 3
Other:		and construction debris; this schedule oject engineer; and, once approved,	system. The SWP3 must be m				Texas	Department	of Transpor
Other:		oject engineer, and, once approved, ctor. As needed, the project engineer	Inspections to better control po	Ilutants In runoff. R	evisions to the		FED. RO. DIV. NO.	PROJECT N	
Other:	shall direct the contractor to	establish good housekeeping	SWP3 must be completed with inspection. If existing BMPs are				<u>ріу. но.</u> 6	BPM 6447-	
Other:		ne TCEQ's Construction General	necessary, an Implementation					TATE IST.	COUNTY
	Permit.					1	TEXAS 0	25	LUBBOCK

DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5

DESCRIPTION OF BMPs USED TO MINIMIZE POLLUTION IN RUNOFF: EROSION AND SEDIMENT CONTROLS: If its necessory to pump worder, BMP's shall be used to reduce the off-site transport of sediment. BMP's shall be installed per the manufacture specifications or as directed by the Engineer. SEDIMENT CONTROL PRACTICES SELVMENT LUMINUL PRAFILES: I.Sandbags: the purpose of a sondbag is to intercept sediment laden storm water from disturbed areas, create a detention pond, detain sediment and release water in a steef flow. Sandbag berns are a general purpose sediment control device and will be used throughout the project to detain sediment on site.Sandbags will be placed in differe and channels to form sedimentation basins. Sandbags will also be used where runolf exits the construction site to enter readving waters and to support other storm water controls. GENERAL SCHEDULE FOR IMPLEMENTATION OF SW3P CONTROLS REMOVAL SCHEDULE general,various controls control measures are to be provided at a time and in a manner that will minimize impacts to receiving waters at final stabilization at the resumption of construction (temporary measures), at the direction of the SW3P plan; at the direction of the project manager 2.Slif fence: slif fence is to be installed with construction near the perimeter of a disturbed area to intercept sediment while allowing water to percolate through. This is a general use control that will be used to create detention basins that retain sediment on-site they will also be used in support of other in bogin this is obtained use of the wind with the used in the end of the end of the international end of the rock filter dams to be installed prior to soil disturbing activities in the surrounding areas at final stabilization or as directed by the project enninee 3. Rack Filter Dams: the purpose of a rack filter dam is to intercept and slaw sediment laden water runoff from disturbed areas, retain the sediment and release the water in steet flow. Rack filter dams will generally be used in high water velocity flow channels. at final stabilization or as directed by the project sandbaa berms to be installed prior to the start of construction; sondbag berms are to serve as water velocity dissipaters, as ditch blacks, as sedimentation basins, in support of other control devices, and as a final multiple enginee 4. Stabilized Construction Exili the purpose of the stabilized exil is to reduce the tracking of sediment and dirt onto public roadways beyond the construction zone. Stabilized Construction Exits are to be in-place at exit points to streets and tharoughtares in urban areas and are to be used by all construction vehicles regardless of size. They are to be supported where appropriate with slit fence and mechanized brooms. control for water leaving the construction zone sill fence will be installed prior to the start of construction along at final stabilization or as directed by the project engineer at final stabilization or as directed by the project engineer at the removal of the construction exil, at final Sediment basins are required where feasible for common drainage locations that serve an area with IO or more acres disturbed at one time. Temporary or silt fence Sediment basins are required where reasible for common drainage locations ind serve an area with to or more acres disturbed at one time, let permanent sediment basins that provide weler storage capacity are located on the project; the following controls provide, where feasible, structural controls / sediment basins: 1. Sandbag Berm as a Sediment Basine, temporary basin designed to intercept sediment-loden storm, water runoff and to trap sediment on-site, 2.Vegetative Buffer, Strip, vegetative buffer strips reduce water velocity which reduces the potential of water erosion and a lows sediments to sill fence will be installed as quickly as feasible (where it is reasonable to do so) at the toe of header bank and other slopes ilization or as directed by the project engl sill fence may be installed at the start of construction, during construction as appropriate, and during construction to support other controls as needed fall out of the storm water water from construction area. erosion controls that are designed to remain in-place for a indefinite period, such as mulches and fiber mais, are not required to be removed or scheduled for removal (CGP, page 23) tackifiers/emuision: soll tackifiers may be used to control dust STABILIZATION PRACTICES AND OTHER REQUIRED CONTROLS AND BMPs: erosion controls that are designed to remain in-place for a Indefinite period, such as mulches and fiber mats.are not required to be removed or scheduled for removal (CGP,page 23) to be used to suppress dust and compact dirt on an as needed 2.Water:water will be used to temporarily suppress dust and compact dirt. (dust) & water erosion. erosion controls that are designed to remain in-place for a indefinite period, such as mulches and fiber mais, are not required to be removed or scheduled for removal (CGP, page 23) seed.temporary to be installed, when appropriate, in disturbed areas where construction has temporarily ceased for 21 days erosion controls that are designed to remain in-place for a indefinite period, such as mulches and fiber mais, are not required to be removed or scheduled for removal (CGP, page 23) to be installed as a final stabilization measure where construction is complete or as directed by the Engineer is required. 7. Tracking and Dust: Off-site tracking and generation of dust must be minimized. ON-SITE STORAGE OF CONSTRUCTION AND WASTE WATERIALS: to be installed at all construction vehicle exit points to publicly traveled ways prior to the use of these exits by construction as directed by construction conditions or by the Engineer construction exits to be installed prior to the start of construction erosion control logs are to serve as water velocity dissipaters, as ditchblocks, as sedimentation basins, and in support of as directed by construction conditions or by the Engineer ston control logs to pump or channel standing water from the site. erosion controls that are designed to remain in-place for a indefinite period, such as mulches and fiber mats, are not required to be removed or scheduled for removal (CGP, page 23) to be installed as a final stabilization measure where construction is complete or as directed by the Engineer soil retention blankets oved or scheduled for petroleum products from contaminating the surrounding soil. to be installed to cover curb inlets with support from sandbags or as directed by the Engineer Inlet protectors as directed by construction conditions or by the Engineer 5. Potential Pollutant Sources from Areas Other than Construction: to be installed as channel blocks, inlet protectors, and to support sandbag berms, sill fences or as directed by the Engineer as directed by construction conditions or by the Engineer compost socks sediment laden stormwater disturbed soil from concrete batch plant and field office

Notes from the Lubback Districty

This is a general schedule for the installation of and removal of SW3P best management practice controls. The final determination of the Implementation and removal of controls is at the discretion of the project engineer. Control messures must be properly selected, installed, and maintainde according to the manufacturer's or designer's specifications. If periodic inspections or other information indicates control has been used incorrectly, or that the control is performing inadequaley, the operator must replace or modify the control as practicable offer the discovery that the control has been used incorrectly. Is performing inadequaley, the operator must replace or modify the control as soon as practicable offer the discovery that the control has been used incorrectly. Is performing Indedequiately or is damaged. -Sediment must be removed from traps and sedimentation ponds no later than the time that design capacity has been reduced by 50

percent. if sediment escapes the site accumulations must be removed at a frequency to minimize further negative effects and whenever feasible.

prior to the next rain event Controls must be developed to limit to the extent practicable, the off-site transport of litter, construction debris, and construction materials.

Inter closs. Erasion and sediment controls must be designed to retain sediment on-site to the extent procticable with consideration for local tapograph, soil type, and rainfail, Controls must also be designed and utilized to reduce the off-site transport of suspended sediments and after guidands if it is necessary to pump or channel standing water.

MAINTENANCE REQUIREMENTS:

MANTERNANCE REQUIREMENTS: Control measures shall be properly installed and maintained according to the manufacturer's specifications. Sediment must be removed from BMP's as directed by the SM3P pian requirements, and as directed by the manufacturer's recommendations, but no later than the time at which the capacity of the BMP has been reduced by 50 percent. If sediment or other pollutionis escope the site, accumulations, but no later than the time at which the capacity of the BMP has been reduced by 50 percent. If sediment or other pollutionis escope the site, accumulations will be removed to reduce turther negative effects. If inspections or other information indicates a control has been installed.used, or is performing inadequately, the contractor must modify or replace the control as soon as practicable offer the problem is discovered. Controls shall be maintained in effective operating condition, if inspections determine that BMPs are not operating effective, maintenance shall be performed as necessary to confinue the effectiveness of the controls. Controls that have been intentionally disabled, run over, removed, or dherwise made late field-ture.must be corrected or replaced at discovery. LITTER AND CONSTRUCTION DEBRIS:

UTEEN AND CONSTRUCT AN DEBASS The project contractor shall establish a schedule for the regular removal of litter and construction debris; this schedule shall be approved by the project engineer and, ance approved, implemented by the contractor. As needed, the project engineer shall direct the contractor to establish good housekeeping measures consistent with the TCEO's Construction General Permit.

DESCRIPTION OF PERMANENT STORM WATER CONTROLS:

PERMANENT STORM WATER CONTROLS: A description of controls that will stay in-place after construction is completed must be included in the SW3P

- Riprag: concrete riprag can be installed as a permanent stabilization measure at locations where construction is completed must be included in the SW3P. Existing Vegetation & Vegetative Buffers: to the extent practicable,existing vegetation will not be disturbed by construction activities, and,where feasible (especially at some water discrete sites),existing vegetation will remain undisturbed to form a vegetative buffer between construction permanent Sociality/Sociality (Sociality), this is the establishment of permanent permanent vegetation, vegetative buffer between construction permanent Sociality/Sociality (Sociality), this is the establishment of permanent permanent vegetation, vegetation stabilizes soil by holding soil particles implace.Vegetation filters settiments, helps soil absorb water, improves wildlife habitat, and enhances oesthetics of the site. 1. 2.
- 3.

- Permanent vegetation will remain in vegetated channels. 4.

3.5111 Fence will be used to reduce the loss of sediment from roadway front slopes ad jacent to playa lakes by filtering out silt laden storm

Erosion control and stabilization measures must be initiated immediately in portions of the site where construction activities have ceased and will not resume for a period exceeding 14 colendor days. Stabilization measures that provide a protective cover must be initiated immediately in portions of the site where construction activities have permanently cased (CGP - Part III Sect. F2BUII) page 33.

3. FobUrget Construction Exit a stabilized pool of stone, linker, or other stabilized surface located at points where construction traffic will leave the construction zone to enter a public roadway. The purpose of the stabilized surface locate the tracking of sediment and dirt onto public roadways beyond the construction are. Stabilized Construction Exits will be locade as needed.

3. Tackifiers: tackifiers such as asphalt emulsion, guar, (and other natural tackifiers), and synthetic tackifiers will be used to control air

(dust) & water erosion. A.Existing vegetation & Vegetative Buffers:to the extent practicable, existing vegetation will not be disturbed by construction activities; where feasible (especially at storm water discorge sites), existing vegetation will remain undisturbed to form a vegetative buffer between construction areas and areas undisturbed by construction. 5. Cleaning and Sweeping:team and sweep ourb and gutter sections twice a month to reduce dirt and trash or as directed,

6. Riprapi concrete riprapi can be installed as a permanent stabilization measure at locations where construction is complete and permanent stabilization

Units a structure of Construction who was a set and an angement requirements. No construction waste shall be buried or burned on-site. Spoils of disposal, indierial storage, and waste materials from the demolition of existing roads and structures shall be stored in oreas designated by the project engineer, and prevented from becoming a pollulari source with appropriate BWPS. Construction and waste materials that might be temporarily stored on-site include concrete and steel pipe, steel reinforcing bor, forms and fromes, sand a gravel-wite, accorete and steel bards, and borricades. All stor construction store that materials that might be temporarily stored on-site contraits, construction signs and borricades. All stor construction and waste materials stored on site and carries with be froget Engineer. 2. Contractor shall design and utilize appropriate controls to minimize the offsite transport of suspended sediments and other pollutants, if it is necessary

3.Litter.construction debris.and construction material exposed to stormwater shall be managed in a manner that prevents this material from becoming a poliutant. A regular sweep of the project shall be made to pick up litter. No construction material of any kind (including dirit) shall be discharged to a water of the United States (sphemera is treams and piopa lakes) without a permit from the Carps of Engineers.

4.011, gasoline, grease, solvents, and other petroleum products are not to be stored on-site, Major vehicle maintenance shall occur on-site only under emergency conditions, and when this maintenance type is necessary, a plastic cover shall be used (and properly disposed of) to prevent

oil, arease, and other petroleum fluids construction traffic at concrete plant and field office

litter, motorists driving through the project

All best management practices available to this construction project are available to control non-construction generated pollulants including sand bag berms, slit fence, stabilized construction exits, sedimentation basins, and iliter management programs among other controls listed in this document. STORAGE TANKS

Storage lanks is that are above ground, regardless of whether they are used to store petroleum products, hazardous waste, or other hazardous material must follow the Summary of Federal Requirements.

Aboveground storage tanks (ASTs) used for the storage of petroleum products is regulated primarily under 40 CFR II2. These containers are used for purposes including, but not limited to the storage of all prior to use, while being used, or prior to further distribution in commerce.

A bulk storage containers is 55 gal.or greater and may be aboveground, partially burled, bunkered, or completely burled. AST's include mobile storage containers such as trailers and tanked vehicles, OII-filled electrical, operating, or manufacturing equipment is not a bulk storage container. All bulk storage container installations must be constructed so a secondary means of containment is provided for the entire capacity of the largest single container and sufficient freeboard to contain precipitation, Diked areas must be sufficiently impervious to contain discharged oil. Mobile/Portable AST:

Woble or portable all bulk starage containers must be positioned or located to prevent a discharge and furnished with a secondary means of containment, such as a dike or catchment basin, sufficient to contain the capacity of the largest single compartment or container with sufficient freeboard to contain precipitation.

DETERMINATION OF REPORTABLE QUANTITIES:

A list of each substance designed as historia due to CFR Part II6 is found in the project's SWSP folder. The 40 CFR life registration applies to quantities when discharged into ar upon the Waters of the United States.od joining shorelines, into ar upon the conliguous zone, or beyond the conliguous zone as provided in the Act.

addiment basins are not feasible on the project because right-of-way is limited and the construction of a sedimentation basin would be within the boundaries of the roadway's clear zone and for the solery of mation is sedimentation basins control be constructed within the clear zone. Since sedimentation basins are not feasible due to lack of right-of-way, mathematical calculations have not

STORMWATER POLLUTION **PREVENTION PLAN (SWP3)** NARRATIVE - UNDER 1 ACRE

© 2023	Sheet 3 of 3
Texas Depai	rtment of Transportatio

ſ	FED. RD. DIV. NO.		SHEET NO.				
- [6		BPM	1 6447-58-0	85		
- [STATE		STATE DIST.	COUNTY			
[TEXAS	5	Ø5	LUE	JBBOCK		
- [CONT.		SECT.	JOB	HIGHWAY NO.		
- [6447	7	58	001	VARIOUS		

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402 TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506. List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities. 1. Lubbock use. 2 purpose v from its No Action Required Action No. for any r resulting 1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000. kind is mode by TxDOT ect results or domoges 2. This project disturbs less than one acre of surface area. The contractor is responsible for any PSL's as defined in the Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges (2014 Edition, Item 7, Section 7.7, Page 43). The total disturbed acreage is the combined acreage to be disturbed on the project and any contractor PSL's. This EPIC must be updated if the disturbed area increases to one or more acres during the course of construction. It may become necessary to post a site notice and/or NOI for the project and/or PSL's. No worranty of any formats or for incorr ACT SECTIONS 401 AND 404 water bodies, rivers, creeks, streams, wetlands or wet areas. MER: to livis standard is governed by the "Texas Engineering Proctice Act" assumes no responsibility for the conversion of this standard to other the following permit(s): No Permit Required wetlands offected) Individual 404 Permit Required and post-project TSS. 2 3 Best Management Practices Erosion

DocuSign Envelope ID: 4D54B2AA-19B7-4BCD-9B4A-87BF09A89AF5

II. CULTURAL RESOURCES Refer to TxDOT Standard Specifications in the event historicalissues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately. Required Action No Action Required IV. VEGETATION RESOURCES Preserve notive vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments, Required Action No Action Required Action No. 1. Comply with Executive Order 13112 on Invasive Plant Species. 2. Comply with TxDOT Executive Memorandum on beneficial landscaping. 3. Comply with temporary and permanent vegetation stabilization protocols of the SW3P. V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS. No Action Required Required Action Action No. 1. Do not handle or harm Texas horned lizards, prairie doas, barn swallows or burrowing owls. No prairie dog towns can be damaged or crossed with equipment without approval of the Engineer. 3. No nests of burrowing owls (in prairie dog holes) can be disturbed or damaged (See General Notes). 4. No nests of barn swallows (likely on structures such as bridges) can be disturbed or damaged (See General Notes). 5. Obey the Bold and Golden Eagle Protection Act. Do not handle, harm, capture, disturb, or kill the species. Do not handle, harm, or take nests, eggs, feothers, bones, or eogles. 6. Obey the Migratory Bird Treaty Act of 1916, of which details there cannot be any handling or harming of migratory bird species; including their eggs, nests, or feathers. If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately. VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES General (applies to all projects): working with hazardous materials by conducting safety meetings prior to beginning

products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

LIST OF ABBREVIATIONS

Best Monogement Proctice SPCC: SWOP: Spill Prevention Control and Countermeasure Construction General Permit Storm Water Pollution Prevention Plan Texos Deportment of State Health Services PON Pre-Construction Notification Federal Highway Administration PSL: Project Specific Location TOPO Texas Commission on Environmental Quality Texos Pollutant Discharge Elimination System Texos Porks and Wildlife Department TPDES: Municipal Separate Stormater Sever System Migratory Bird Treaty Act Notice of Termination TPWD: TxDOT: Texas Department of Transportation T&E: Threatened and Endangered Species USACE: U.S. Army Corps of Engineers USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects)

Maintain an adequate supply of on-site soil response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc. Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- X Yes □ No

If "No", then no further action is required. If "Yes", then TxDOT is responsible for completing asbestas assessment/inspection.

- Are the results of the asbestos inspection positive (is asbestos present)?
- No No ☐ Yes

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and ashestas consultant in order to minimize construction delays and subsequent claims

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

No Action Required Required Action

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

Required Action No Action Required

Action No.

1. Maintain equipment muffler systems and work hour restrictions to reduce traffic noise.

- 2. No PSL's may be located in the prairie dog towns, playa lakes (wet or dry) or stream beds (wet or dry).
- 3. No dumping of construction material in playa lakes or stream beds regardless of property owner requests.
- 4. Contractor must obtain historical and archaeological clearances for off-site PSL's.
- 5. Contractor is responsible for air quality permits for concrete and asphalt batch and similar plants.
- 6. Contractor is responsible for water appropriation or impoundment TCEO permits. 7. Contractor will protect environmentally sensitive areas with fencing, work
- sequencing or scheduling as directed.
- 8. PSL's beyond the project right-of-way have "individual operator" status under the TPDES Construction General Permit and the Contractor is responsible for the SW3P and any TCEQ permits.
- 9. No waste material of any type may be placed at any location where it could be washed into a water of the U.S. or a surface water of Texas.

4

- 10. Flood elevations will not be increased to a level that would violate flood
- plain regulations or ordinances. 11. Contractor shall remove all
- construction debris doily from the waterway by close of business, where applicable. 12. The SW3P, including best
- management practices, must be in-place prior to disturbing

Texas Departme	ent of Tra	nsp	ortatior	,	Divi: Star	sion ndard
ENVIRONM	ENT	٩L	PE	RM	ITS	5,
SSUES AN	ID C	0	иміт	M	ENT	S
	EPI	С				
: epic.dgn	DN: Tx[100	ск: RG	ow: V	P	ck: AR
TxDOT: February 2015	CONT	SECT	JOB		HIG	WAY
REVISIONS	6447	58	001		VAS	bous

Deside

- Memor andum of Aar eement Memor and um of Under standing
- MRTA NOT: NWP:
- Notionwide Permit NO: Notice of Intent

DATE

12-12-2011 (DS) 05-07-14 ADDED NOTE SECTION IV DIST SHEET NO.

COUNTY

Comply with the Hazard Communication Act (the Act) for personnel who will be construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Required Actions: List waters of the US permit applies to, location in project

WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER USACE Permit required for filling, dredging, excavating or other work in any

The Contractor must adhere to all of the terms and conditions associated with

Required Action

and check Best Management Practices planned to control erosion, sedimentation

Other Nationwide Permit Required: NWP*

□ Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Lavouts.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous

Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or

DocuSign

Certificate Of Completion

Envelope Id: 4D54B2AA19B74BCD9B4A87BF09A89AF5	89AF5	Status: Completed
Subject: Complete with DocuSign: BPM 6447-58-001 PLAN SET.pdf	01 PLAN SET.pdf	
Source Envelope:		
Document Pages: 91	Signatures: 2	Envelope Originator:
Certificate Pages: 2	Initials: 0	Surafel Sintayehu P.E
AutoNav: Enabled		125 E. 11th Street
Envelopeld Stamping: Enabled		Austin, TX 78701
Time Zone: (UTC-06:00) Central Time (US & Canada)	ıda)	Surafel.Sintayehu@txdot.gov
		IP Address: 204.64.21.251
Record Tracking		
Status: Original 4/23/2024 4:23:36 PM	Holder: Surafel Sintayehu P.E Surafel.Sintayehu@txdot.gov	Location: DocuSign
Security Appliance Status: Connected	Pool: StateLocal	
Storage Appliance Status: Connected	Pool: Texas Department of Transportation	Location: DocuSign
Signer Events	Signature	Timestamp
Surafel Sintayehu, P.E surafel.sintayehu@txdot.gov Bridge Engineer	Surafil Sintayulun, P.E	Sent: 4/23/2024 4:26:18 PM Viewed: 4/23/2024 4:26:34 PM Simed: 4/23/2024 4:26:47 PM
TVDOT		

Security Level: Email, Account Authentication (Optional) TXDOT

Electronic Record and Signature Disclosure: Not Offered via DocuSign

Security Level: Email, Account Authentication (Optional) Texas Department of Transportation Director of Operations Mike.Stroope@txdot.gov Michael Stroope, P.E.

Electronic Record and Signature Disclosure: Not Offered via DocuSign

In Person Signer Event:

Signature Adoption: Pre-selected Style Using IP Address: 204.64.21.251

Muchael Strape, DocuSigned by: Э.С.

C0CB990D620C4DD..

Using IP Address: 166.205.58.44 Signature Adoption: Pre-selected Style Signed using mobile

> Signed: 4/24/2024 6:08:05 AM Viewed: 4/24/2024 6:07:57 AM Sent: 4/23/2024 4:26:56 PM

Envelope Sent H	Envelope Summary Events S	Notary Events S	Witness Events S	Carbon Copy Events S	Certified Delivery Events S	Intermediary Delivery Events S	Agent Delivery Events S	Editor Delivery Events	In Person Signer Events
Hashed/Encrypted	Status	Signature	Signature	Status	Status	Status	Status	Status	Signature
4/23/2024 4:26:19 PM	Timestamps	Timestamp	Timestamp	Timestamp	Timestamp	Timestamp	Timestamp	Timestamp	Timestamp

Envelope Summary Events	Status	Timestamps
Certified Delivered	Security Checked	4/24/2024 6:07:57 AM
Signing Complete	Security Checked	4/24/2024 6:08:05 AM
Completed	Security Checked	4/24/2024 6:08:05 AM
Payment Events	Status	Timestamps