

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 646645001
 CSJ: 6466 - 45 - 001
 HIGHWAY: US038
 LIMITS OF WORK: DENTON COUNTY

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
 DESCRIPTION: FLEXIBLE BASE

RECOMMENDED FOR LETTING:	3/28/2024
	Date
DocuSigned by: <i>Amanda Miller</i>	
AREA ENGINEER	

RECOMMENDED FOR LETTING:	3/29/2024
	Date
DocuSigned by: <i>David Morren, P.E.</i>	
MAINTENANCE ENGINEER	

RECOMMENDED FOR LETTING:	4/1/2024
	Date
DocuSigned by: <i>JEFFREY BUSH</i>	
DIRECTOR OF OPERATIONS	

INDEX OF SHEETS		© 2024	
1	TITLE SHEET	FED.RD. DIV. NO.	PROJECT NO.
2	ESTIMATE & QUANTITY SHEET	6	MMC 646645001
3A-3B	GENERAL NOTES		SHEET NO. 1
SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.		STATE	DISTRICT
		TEXAS	DALLAS
		COUNTY	
		DENTON	
		CONTROL	SECTION
		6466	45
		JOB	HWY NO.
		001	US0380
		FILENAME	
		DATE	
		MMC 646645001	
		3/28/2024	



Estimate & Quantity Sheet

COUNTY Denton

DISTRICT Dallas
HIGHWAY US0380

CONTROLLING PROJECT ID 6466-45-001

ALT	BID COD	DESCRIPTION	UNIT	EST.	FINAL
	8007-6077	FL BS (SITE DEL) (TY A GR 4) (SITE 3)	TON	250.000	



Report Generated By: txdotconnect_internal_ext

Report Created On: Mar 27, 2024 2:34:06 PM

DISTRICT	COUNTY	CCSJ	SHEET
Dallas	Denton	6466-45-001	2

Project Number: MMC-646645001

Control: 6466-45-001

County: Denton

Highway: US0380

GENERAL NOTES:

General:

The purpose of this contract is to supply Flex Base, materials only, at the following locations:

Site 1	Stockpile Area between US0380 and US0377 (33.232012, -97.008634)
--------	--

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through:

Wayne Powell, Maintenance Section Supervisor
2624 West Prairie Street
940-387-1414

Bids will be received at 4777 E. Hwy 80, Mesquite, Texas 75150-6643

Contractor questions on this project are to be addressed to the following individual(s):

Amanda Miller, P.E.
Wayne Powell,

Amanda.Miller@txdot.gov
Wayne.Powell@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Section 10.2 - Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Project Number: MMC-646645001**Control:** 6466-45-001**County:** Denton**Highway:** US0380**Section 10.4 – Scope of Work:**

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended twice not to exceed 360 calendar days for the entire contract term if mutually agreed.

Section 10.8 – Prosecution and Progress:

There are 120 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Each work order will specify a delivery site by the bid item in the contract and quantity to be supplied. The minimum amount of material to be ordered on an individual work order is 25. There are 7 working days allowed to complete each work order.

Item 500 – Mobilization:

Mobilization does not apply to this Maintenance/Traffic Materials Contract.

Item 8007 – Flexible Base (Materials Only):**GRADING REQUIREMENTS**

Tests to be in accordance with TxDOT Standard Test Methods

SOIL CONSTANTS

Item Desc.	Linear Shrinkage	LL	Wet Ball	WBMV (incr. passing #40 sieve)
Item 247 Flex Base	6.0 max	40 max.	40 max.	20% max.

PERCENT RETAINED ON SIEVE:

1-3/4"	7/8"	3/8"	No. 4	No. 40
0	10-35	30-50	45-65	70-85

Flexible Base will not contain more than 1% by weight of clay balls.