

**INDEX OF SHEETS**

SEE SHEET 2 FOR INDEX OF SHEETS.

**STATE OF TEXAS  
DEPARTMENT OF TRANSPORTATION**

**PLANS OF PROPOSED  
STATE HIGHWAY IMPROVEMENT**

PROJECT NO. C 1584-02-013, E+c

**FM 1745, FM 2097  
CSJ 1584-02-013, ETC.  
TYLER COUNTY**

CSJ 1584-02-013 NET LENGTH OF ROADWAY= 14,271.84 FT. = 2.703 MI.  
CSJ 2271-01-011 NET LENGTH OF ROADWAY= 20,125.44 FT. = 3.823 MI.  
CSJ 2271-01-011 NET LENGTH OF BRIDGE = 60.00 FT. = 0.011 MI.  
NET LENGTH OF PROJECT= 34,560.45 FT. = 6.574 MI.

LIMITS: FROM: POLK COUNTY LINE, EAST TO: US 287

FOR THE CONSTRUCTION OF A REHABILITATE EXISTING ROADWAY PROJECT  
CONSISTING OF A SURFACING/ROADWAY RESTORATION, FULL DEPTH BASE REPAIR, OCST,

FEDERAL AID PROJECT NO.			
C1584-2-13, ETC.			
CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		1

DESIGN SPEED = 60 MPH  
A.D.T. (2022)= FM 1745 (282) FM 2097 (329)  
A.D.T. (2042)= FM 1745 (395) FM 2097 (461)

**FINAL PLANS**


LETTING DATE: \_\_\_\_\_  
DATE CONTRACTOR BEGAN WORK: \_\_\_\_\_  
DATE WORK WAS COMPLETED & ACCEPTED: \_\_\_\_\_  
FINAL CONTRACT COST: \$ \_\_\_\_\_  
CONTRACTOR : \_\_\_\_\_

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

END PROJECT  
CSJ: 2271-01-011  
STA: 202+47  
REF MRK: 384+0.009

BEGIN CSJ: 2271-01-011  
STA: 2+03  
REF MRK: 724+0.761  
END CSJ: 1584-02-013  
STA: 145+65  
REF MRK: 386+1.831

BEGIN PROJECT  
CSJ: 1584-02-013  
STA: 0+02  
REF MRK: 722+0.05



NOT TO SCALE

EXCEPTIONS: NONE  
EQUATIONS: NONE  
RAILROAD CROSSINGS: NONE

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, JULY 5, 2022 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED SPECIAL LABOR PROVISIONS FOR ALL STATE CONSTRUCTION PROJECTS. (SP000--008)

© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED.



4/29/2024

SUBMITTED FOR LETTING:

DocuSigned by: *[Signature]*  
5023808510 DISTRICT ENGINEER

4/29/2024

RECOMMENDED FOR LETTING:

DocuSigned by: *[Signature]*  
5023808510 DISTRICT DIRECTOR OF TRANSPORTATION PLANNING AND DEVELOPMENT

4/29/2024

APPROVED FOR LETTING:

DocuSigned by: *[Signature]*  
578CD749508D4E0 DISTRICT ENGINEER

DATE: 3/22/2024 7:21:37 AM  
FILE: c:\ttdot\pw\_online\ttdot5\francisco.molinari\1044287\tile\_sheet.dgn

CK: DW: CK: DW:

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS
3-4	TYPICAL SECTIONS
5-12	GENERAL NOTES
13-14	ESTIMATE & QUANTITY
15-18	QUANTITY SUMMARY

<b>TRAFFIC CONTROL PLAN</b>	
19	SEQUENCE OF WORK
## 20-31	BC (1)-21 THRU BC (12)-21
## 32	TCP(2-1)-18
## 33	TCP(2-2)-18
## 34	TCP(3-1)-13
## 35	TCP(3-3)-14
## 36	TCP(SC-1)-22
## 37	TCP(SC-7)-22
## 38	TCP(SC-8)-22
## 39	WZ(RS)-22
## 40	WZ(STPM)-23
## 41	WZ(UL)-13


<b>ROADWAY DETAILS</b>	
42-46	HORIZONTAL AND VERTICAL SURVEY CONTROL INDEX SHEET
47	FM 1745 & FM 2097 HORIZONTAL ALIGNMENT DATA
48-54	FM 1745 ROADWAY LAYOUTS
55-63	FM 2097 ROADWAY LAYOUTS
64	DRIVEWAY AND PUBLIC ROAD DETAILS
65	CLEARING DETAIL
66	TRANSITION DETAIL
## 67	RS(2)-23
## 68	RS(4)-23
## 69-72	MB(1)-21 THRU MB(4)-21
## 73-74	MBP(1)-22 THRU MBP(2)-22
## 75	TE(HMAC)-11

SHEET NO.	DESCRIPTION
<b>DRAINAGE DETAILS</b>	
## 76	PSET-RC
## 77	PSET-RP
## 78	PSET-SC
## 79	PSET-SP
## 80	PSET-RR
## 81	PW
## 82-83	SETB-CD
## 84-85	SETP-CD
## 86	SETP-PD

<b>PAVEMENT MARKINGS &amp; DELINEATION</b>	
87-93	FM 1745 SIGNS & PAVEMENT MARKINGS LAYOUT
94-102	FM 2097 SIGNS & PAVEMENT MARKINGS LAYOUT
103-106	SUMMARY OF SMALL SIGNS
107	NON-STANDARD SIGN DETAILS
## 108	D & OM(1)-20
## 109	D & OM(2)-20
## 110	D & OM(3)-20
## 111	D & OM(5)-20
## 112	D & OM(6)-20
## 113	D & OM(VIA)-20
## 114	FGA-15
## 115	PM(1)-22
## 116	PM(2)-22
## 117	SMD(GEN)-08
## 118	SMD(SLIP-1)-08
## 119	SMD(SLIP-2)-08
## 120	SMD(SLIP-3)-08
## 121	TSR(3)-13
## 122	TSR(4)-13
## 123	TSR(5)-13
## 124	SPRFBA(3)-13

SHEET NO.	DESCRIPTION
<b>UTILITY DETAILS</b>	
125	UTILITY NOTES
126-132	FM 1745 UTILITY LAYOUT
133-141	FM 2097 UTILITY LAYOUT

<b>ENVIRONMENTAL ISSUES</b>	
142	SWP3-B
143	EPIC
144-150	1747 SW3P Layout
151-159	2097 SW3P Layout
## 160	EC(1)-16
## 161	EC(2)-16
## 162 - 164	EC(9)-16
## 165 - 166	SWP3



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A "##" HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.


P.E. 04/29/2024  
 NAME DATE

DATE: 4/29/2024 1:42:20 PM  
 FILE: c:\pwworking\txdotp\mxdot5\samantha.harris\1044287\index.dgn


**FM 1745, ETC.**  
  
**INDEX OF SHEETS**

© TxDOT 2024		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	2	


DW:   
 CK:   
 DW:   
 CK:



P.E.   
 04/29/2024



EXISTING TYPICAL SECTION   
 STA 0+02 TO STA 145+78



PROPOSED TYPICAL SECTION   
 STA 0+02 TO STA 145+78

Texas Department of Transportation   
 FM 1745 ETC.   
 TYPICAL SECTIONS



©TxDOT 2023		SHEET 1 OF 2	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	3	



\* Note" 2' Strip seal use item 316-6405 & 316-6408


DATE: 4/19/2024 9:43:35 AM   
 FILE: c:\txdot\p\online\txdot\5\francisco.molinar\1044287\typical section.dgn

CK:  
DW:  
CK:  
DW:



**EXISTING TYPICAL SECTION**

STA 2+03 TO STA 15+95  
BRIDGE STA. 15+59 TO 16+95  
STA. 16+55 TO 204+00



**PROPOSED TYPICAL SECTION**

STA 2+03 TO STA 15+95  
BRIDGE STA. 15+59 TO 16+95  
STA. 16+55 TO 202+47



DATE: 4/19/2024 9:47:17 AM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molinar\1044287\typical section.dgn

Texas Department of Transportation

**FM 2097**

**TYPICAL SECTIONS**

©TxDOT 2023		SHEET 2 OF 2	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	4	

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**GENERAL NOTES:**

Contractor questions on this project are to be addressed to the following individual(s):

Name Dave Collins, P.E.

Email [Dave.Collins@txdot.gov]

Name Richard Bradley Jr, P.E.

Email [[Richard.Bradley@txdot.gov](mailto:Richard.Bradley@txdot.gov)]

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Assume full responsibility for the preservation of all sod, shrubbery, and trees at the site during construction. Carefully preserve and replace, in their original position, all sod and shrubbery removed. Replace all Contractor damaged sod or shrubbery at the Contractor's own expense.

Maintain adequate drainage throughout the limits of the project during all construction phases. Provide a weekly a list of equipment, including idle equipment, used on the project each week.

**Item 000 Utilities**

Consider the locations of utilities depicted on the plans as approximate and employ responsible care to avoid damaging or accommodate utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities. If utility damage (breaks, leaks, nicks, dents, gouges, etc.) occurs, contact the utility facility owner or operator immediately. In the event utility lines needing unforeseen adjustments are encountered during construction operations, alter operations and continue to prosecute the contract in such a manner that will allow utility adjustments to be made by others.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**Item 4 Scope of Work**

Remove all vegetation from pavement edges, intersections and driveways before planing or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

It is the Contractors responsibility to field verify all drainage structure's shown in the plans.

It is the Contractors responsibility to mark the location of all existing striping and place proposed striping back in the same location or as shown in the plans.

**Item 5 Control of the Work**

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

Verify all horizontal and vertical control, approach grades to structures and driveways before beginning work. Notify the Engineer immediately if discrepancies are discovered.

Furnish, to the Engineer, a list of the final centerline elevations based on the alignment stationing shown on the plans.

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impact to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

**Item 6 Control of Materials**

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

Mixing of materials, storing of materials, storing of equipment, or repairing of equipment on top of concrete pavement or bridge decks will not be permitted unless specifically authorized.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**Item 7 Legal Relations and Responsibilities**

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Maintain ingress and egress to the adjacent property at all times. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

No significant traffic generator events have been identified in the project limits.

**Item 8 Prosecution and Progress**

SP008-056 (90 day delay) has been added to this project for contractor convenience.

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Submit monthly progress schedules in accordance with 8.5.5.2.3. Failure to supply updated project schedule may result in the Engineer withholding progress (monthly) payments.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Notify the Engineer 72 hours in advance of any temporary or permanent lane closures or restrictions to lane widths or modifications to alignment/radii. Any other modification to the roadway that may adversely affect the mobility of oversized/overweight trucks will require 5 business day advance written notice to the Engineer.

Maintain one lane open to traffic during construction, unless otherwise approved.

Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

Limit lane closures to 1 mile unless otherwise approved.

The Contractor will be expected to schedule this work so that the base placement operations will follow the subgrade work as closely as practical in order to reduce the hazard to the traveling public and prevent undue delay from wet weather.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

All edges must be backfilled by the end of the day with a 3:1 or flatter slope. No drop offs will be left overnight.

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

The construction sequence may be modified as directed and approved.

Wait three hours after applying prime to base before using blotter or allowing traffic on base unless approved otherwise.

Provide a 100-foot minimum temporary longitudinal grade taper at the end of the section being reworked before opening the lanes to traffic.

Working days will be charged during the observed curing times if there is other work within the project that may be done.

**HURRICANE**

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes, cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

**Item 100 Preparing Right of Way**

When tree trimming or tree/brush removal is required from February 15 to September 30, the contractor will provide a qualified biologist with a bachelor's degree in biology and demonstrated bird nest survey experience to conduct nesting surveys before work can begin and until vegetation work is completed to ensure compliance with the Migratory Bird Treaty Act (MBTA). See EPIC sheet for details.

Heavy equipment rutting will be graded to the existing terrain profile. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor's attention is directed to potential regulations against burning within the project limits. Abide by all local ordinances and county-imposed burn bans. When burning is prohibited, dispose of material in accordance with regulations set forth by other regulatory agencies including the Texas Commission for Environmental Quality. The cost of burning disposal of any product is subsidiary to various bid items. During burn bans obtain written approval from the Commissioners Court before burning brush.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

Do not burn trash, debris, etc. within the city limits.

**Item 112 Subgrade Widening**

Remove excess material daily unless otherwise directed.

Fill all excavated areas by the end of the workday.

Material is to be removed by milling.

Provide a clean vertical edge by milling or saw cutting full depth. Consider this work to be subsidiary to the various bid items of the contract.

Subgrade widening will be used to excavate material from earth shoulders and to correct minor deficiencies, such as adding embankment on high sides of horizontal curves. It is not expected that additional embankment will be required.

**Item 132 Embankment**

Compaction method specified as ordinary compaction.

It is the Contractor's responsibility to advise the Engineer of the location of the material source enough in advance to avoid delay due to testing requirements.

Any earthwork cross-sections, computer printouts, data files and any other information provided is for non-construction purposes only and it is the responsibility of the prospective bidder to validate the data with the appropriate plans, specifications and estimates for the projects. Contact the Area Office for information on availability.

Embankment Type C will conform to the following specification requirements:

1. Liquid Limit – 40 maximum.
2. Plasticity Index – 25 maximum, 8 minimum
3. A cohesionless sand will not be permitted

All slopes requiring embankment will be tracked immediately upon final grading to prevent erosion. Tracking consists of operating a tracked vehicle or equipment up and down the slopes.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**Item 134 Backfilling Pavement Edges**

Use RAP salvaged from within the project limits to the maximum extent possible. Size RAP so that all material passes the two-inch sieve. Use RAP that does not contain deleterious material such as clay or organic material.

Embankment quantity by station includes both sides of the roadway. No deduction in payment will be made when in the opinion of the Engineer only one side of a roadbed section requires backfilling.

As base is placed, backfill the pavement edges daily so that no drop-off conditions exist. Type A or B material will meet one of the following requirements:

1. Item 132, Type C
2. Use material from subgrade widening for backfilling pavement edges.

**Item 164 Seeding for Erosion Control**

Final grading and stabilization (seeding) will be achieved as soon as possible and not scheduled only for the end of the project. Final grading and stabilization should be initiated as the overall work progresses.

Multiple mobilizations of the seeding crews will be expected to comply with the Construction General Permit of the Texas Pollution Elimination Discharge System requirements for re-vegetating disturbed soils.

Eliminate seeding in areas of natural growth determined to have enough cover.

**Item 166 Fertilizer**

Fertilize all the seeded areas of project.

**Item 168 Vegetative Watering**

Equip water trucks with sprinkler systems capable of covering the entire area to be seeded or sodded from the roadway.

Water all newly placed sod or seeded areas the same day of installation. Thereafter, maintain the sod or seeded areas in a well-watered condition and at no time allow the areas to dry to the condition that water stress is evident.

Mechanical watering may not be required during periods of adequate moisture as determined.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

Furnish and apply water at a rate of 6.788 Mega gallons per acre per cycle or as directed on the plans.

Comply with stabilization requirements for 70% grass coverage; uniform vegetative coverage is required. During this period, meter and operate water equipment under pumping pressure capable of delivering the required quantities of water necessary. For Permanent seeding each cycle will be executed weekly for 12 weeks, unless directed otherwise. For Temporary seeding each cycle will be executed weekly for 6 weeks, unless directed otherwise.

Provide a logbook showing daily water usage and receipts of water applied, in addition to metering the water equipment.

**Item 247 Flexible Base**

Use Type A, Grade 1-2 flexible base.

The minimum plasticity index for this material will be 4.

Use ordinary compaction.

Do not damage existing or proposed structures during base operations.

**Item 275 Cement Treatment (Road-Mixed)**

For FM 2097:

In order to provide a uniform mixture as specified under item 275.4.3, a truck mounted spreader, trailer mounted metered spreader, or custom designed spreader is required in the application of cement slurry at the required rate or percentage shown in the plans. Consider this necessary equipment and method of placement subsidiary to Item 275. 275 Cement Treatment

Treat 8" with Cement at a rate of 17.7 LBS / SY

Maintain moisture content of the finished cement treated base for a period of 24 to 48 hours.

During this time, but not sooner than 24 hours, induce the microcracking in the finished cement treated base as shown in Article 275.47 Microcracking.

**Item 302 Aggregates for Surface Treatments**

The Contractor will designate a responsible person for receiving and resolving damage claims from the public. This person must be available to receive calls during normal business hours

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

every day, Monday through Friday, during the course of this project. Before beginning work this person's name, mailing address, and a toll free number will be provided to the Engineer to be made available to persons who contact the Department with claims

The aggregate for the surface treatment will be surface dry before application unless otherwise directed.

Aggregate stockpile locations will be approved before stockpiling.

When directed, flush aggregate stockpiled for surface treatment with water to remove excessive dust particles, in such sequence that will permit free water to drain from the stockpiled aggregate before surfacing operations. This work will be considered subsidiary to various bid items.

**Item 320 Equipment for Asphalt Concrete Pavement**

Material Transfer Device is required. Remixing equipment is required.

Use of motor grader is allowed.

A field laboratory is not required for this project.

**Item 351 Flexible Pavement Structure Repair**

The repair areas will require full depth saw-cut when milling is not used. Consider this work to be subsidiary to the various bid items of the contract.

Provide Flexible Pavement Repair with Item 3076, Type B (PG 64-22) unless approved otherwise. Place Hot Mix with a constant longitudinal surface grade and tie in flush with the existing surface at each end and both sides of the repair area.

Unless otherwise directed, place new ASB with maximum 4" lifts. The minimum patch sizes will be 6' in width and 10' in length.

Match the existing cross slope in the repair areas, unless directed otherwise.

All repair locations must be filled the same day they are excavated. No open cut areas will be allowed overnight.

All excavated materials will be removed from the project daily.

Ordinary compaction will be used on this project.

Station limits may be adjusted as directed to meet varying field conditions.

Seal the perimeter of the repair areas with hot poured rubber in accordance with Item 712.

Consider this work to be subsidiary to the various bid items of the contract.



Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**Item 354 Planing and Texturing Pavement**

Where the underlying flexible base is exposed during the planing operation, prime this area with an asphalt at a rate as directed and patch with an approved HMA material, at the end of the day's operation in which it occurs. These items of work will not be paid for directly but will be subsidiary to Item 354.

Complete planing operations in adjacent lanes and shoulders to the same point at the end of each day.

Retain ownership of planed materials.

Stockpile salvaged materials at 30°54'59.33"N 94°36'24.16"W Contact Woodville Maintenance Section Supervisor at 409-283-2451 prior to stockpiling materials at this location.

Schedule the work so that a seal coat or HMA is placed no more than two weeks after milling has been performed on any pavement surface, unless otherwise approved. The Engineer may require the seal coat to be placed sooner than two weeks in cases when base materials are exposed or when the pavement structure is showing signs of distress.

**Item 400 Excavation and Backfill for Structures**

Cut and restore pavement to the depth and dimensions shown on the plans with proposed driveway material as shown in plans.

**Item 467 Safety End Treatment**

At driveway locations where the contract requires modifying pipe installations, provide a 6:1 maximum embankment slope from the edge of the driveway to the top of the SET.

Grading required for shaping driveways and side road turnouts, including embankment for pipe culverts at these access locations, will be considered subsidiary to various bid items.

**Item 502 Barricades, Signs, and Traffic Handling**

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

<u>Square Feet</u>	<u>Minimum Thickness</u>
Less than 7.5	0.080 inches

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

7.5 to 15

0.100 inches

Greater than 15

0.125 inches

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

If the Engineer approves placement of temporary stockpiles in the right of way, delineation of the stockpile must follow the detail shown on the BC(10) standard.

Arrange asphalt laydown schedule to meet plan striping requirements. Limit length of lane closures to 1 mile unless otherwise approved.

Restrict work to one side of the roadway at a time.

The following roadways have been determined to be high volume for the purpose identified in Note 4 of the "Typical Location of Crossroad Signs" on the BC(2) standard sheet: US 287

The following roadways have been determined to be low volume for the purpose identified in Note 2 of the "Typical Location of Crossroad Signs" on the BC(2) standard sheet: CR 2600, Fade Rd, Valley Rd, Dew Berry Rd

Use drums as channelizing devices.

Remove all traffic control devices from the right of way when they are not in use. Devices scheduled to be used within 3 days may be placed along the shoulder of the roadway or along the right of way when not in use or stored in other approved areas on the project. Cover any construction signs that are not in effect and are installed in a fashion that will not allow them to be removed from the right of way easily.

Provide construction fencing as approved at all work locations to protect pedestrian or bicycle traffic. This material and its placement will be considered subsidiary to Item 502.

Arrange construction operations to prevent the hauling of materials through the completed pavement sections unless otherwise approved.

Provide all flaggers and pilot vehicle drivers with two-way radio communication capability. Provide flaggers at each side road intersection.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**Item 506 Temporary Erosion, Sedimentation, and Environmental Controls**

Construct all side slopes on rock filter dams with 6:1 slope.

The Contractor is prohibited from removing grass vegetation throughout the entire project limits and then ceasing construction for long periods, typically over three weeks. The Contractor schedule will be developed based on staged vegetation removal, limiting disturbed soil to no more than 25 percent at one time, unless otherwise approved. Should the Contractor not be able to adequately control sediment and erosion for areas disturbed, the Department will substantially reduce the size of areas that the Contractor may disturb soil.

Should the project be evaluated to have sediment control problems as a result of the Contractor disturbing excessive amounts of soil, the Contractor will be required to immediately re-vegetate (seed and water) those disturbed areas at no cost to the Department.

The Contractor will designate a clean out area for concrete trucks. No other area will be allowed without approval of the Engineer.

**Item 540 Metal Beam Guard Fence**

Provide Type II galvanization metal beam rail elements.

Provide round timber posts.

Provide timber posts on all metal beam guard fence installations except where CRT low-fill culvert posts are required in accordance with details shown on the Long Span Metal Beam Guard Fence standard sheet.

Field fabricates low-fill culvert posts to insure proper metal beam guard fence height.

At the close of work each day, protect the ends of metal beam guard fence in an approved manner, so that no blunt ends are exposed to approaching traffic.

**Item 542 Removing Metal Beam Guard Fence**

Accept ownership of removed metal beam guard fence and terminal anchors.

**Item 560 Mailbox Assemblies**

Retain and reuse or, if necessary, replace newspaper holders removed, relocated, or damaged by construction operations for placement on new mailbox assemblies in accordance with mailbox standard sheets. Consider this work subsidiary to this Item.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

Coordinate and verify temporary and final mailbox locations with the Department and the US Postmaster.

**Item 585 Ride Quality for Pavement Surfaces**

Use Surface Test Type B pay adjustment schedule 3 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

**Item 644 Small Roadside Sign Assemblies**

The contractor will refer to the Sign Crew Field Book for installation of all signs.

A strip of retroreflective material wrapped around a sign support to omni-directionally identify the support as an object adjacent to the roadway is required.

The omni-directionally retroreflective wrap will be approximately 12 inches in height, visible in all directions and should be placed approximately 4 feet above the edge of the roadway. The color of the wrap should be yellow, except for the YIELD and STOP sign posts which should be red.

**Item 658 Delineator and Object Marker Assemblies**

Mount reflectors on a steel or concrete bridge rail, where the bridge is 200' or less in length, at the same height as the butterfly reflectors in the MBGF rail element.

Use bolt-on attachment for delineator assemblies attached to guard fence.

Install delineators when directed. This may require installation of delineators on portions of guardrail and bridge rail that is not being repaired in order to maintain consistency with adjacent sections.

MBGF will receive GF2 delineators installed on 100' maximum spacing.

Type C delineators will be installed using Adhesive 795A manufactured by Davidson Traffic Control Products or an equivalent approved in writing.

**Item 666 Retroreflectorized Pavement Markings**

Furnish Type II drop-on glass beads.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

**Item 672 Raised Pavement Markers**

Remove all existing traffic buttons before the application of the seal coat. Consider this work to be subsidiary to the various bid items of the contract. Location and details of the existing buttons are available at the Area Engineer 's office.

**Item 3076 Dens Graded Hot Mix Asphalt**

Prepare Mix Designs and QC testing using the Superpave Gyratory compactor.

For narrow widenings, six feet (6') or less, place the DG-HMA Base Course with a widener, such that the outside edge of the widening closely follows the alignment of the inside edge, resulting in a uniform outside edge. Do not place the DG-HMA Base Course using a Motor Grader, Skid Steer, Front End Loader, Bull Dozer, or paving machine that is too large for the operation

**Item 3077 Superpave Mixtures**

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC" Superpave Gyratory Compactor" and

TGC "Texas Gyratory Compactor". All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the

project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within a range of (68°F through 72°F).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

- 1.A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
- 2.Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
- 3.Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
- 4.An operational telephone system.
- 5.Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
- 6.Water (for testing purposes) from an approved source
- 7.Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and
- 8.fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.
- 9.A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment
10. A laboratory sink measuring 24 × 30 in. and 12 in. deep
11. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's, then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.
- 12.Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17

Highway: FM 1745, Etc.

Control: 1584-02-013, Etc.

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes. RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements. Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

Station limits may be adjusted as directed to meet varying field conditions.

#### Item 6185

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMA's for mobile operations.

Therefore, 3 total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 1584-02-013

DISTRICT Beaumont  
HIGHWAY FM 1745, FM 2097

COUNTY Tyler

CONTROL SECTION JOB				1584-02-013		2271-01-011		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00196587		A00196576			
COUNTY				Tyler		Tyler			
HIGHWAY				FM 1745		FM 2097			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	100-6002	PREPARING ROW	STA	145.760		199.840		345.600	
	112-6001	SUBGRADE WIDENING (ORD COMP)	STA	145.760		199.840		345.600	
	134-6004	BACKFILL (TY A OR B)	STA	145.760		199.840		345.600	
	164-6021	CELL FBR MLCH SEED(PERM)(RURAL)(SANDY)	SY	9,717.000		13,323.000		23,040.000	
	164-6023	CELL FBR MLCH SEED(PERM)(RURAL)(CLAY)	SY	3,239.000		4,441.000		7,680.000	
	164-6029	CELL FBR MLCH SEED(TEMP)(WARM)	SY	6,478.000		8,882.000		15,360.000	
	164-6031	CELL FBR MLCH SEED(TEMP)(COOL)	SY	6,478.000		8,882.000		15,360.000	
	168-6001	VEGETATIVE WATERING	MG	109.000		149.000		258.000	
	247-6231	FL BS (CMP IN PLACE)(TY A GR 1-2)(10")	SY			22,205.000		22,205.000	
	275-6001	CEMENT	TON			550.000		550.000	
	275-6014	CEMENT TREAT (MX EXST MTL & NW BS)(8")	SY			62,173.000		62,173.000	
	316-6029	ASPH (RC-250)	GAL			12,435.000		12,435.000	
	316-6094	AGGR(TY-D GR-4 SAC-A)	CY			497.000		497.000	
	316-6405	ASPH (AC-20-5TR OR AC-20XP)	GAL	2,332.000				2,332.000	
	316-6408	AGGR(TY-PD GR-4 OR TY-PL GR-4)	CY	50.000				50.000	
	400-6006	CUT & RESTORING PAV	SY	26.000		4.000		30.000	
	438-6008	CLEANING AND SEALING JOINTS (CL 7)	LF			160.000		160.000	
	467-6358	SET (TY II) (18 IN) (RCP) (4: 1) (C)	EA	2.000				2.000	
	467-6363	SET (TY II) (18 IN) (RCP) (6: 1) (P)	EA	14.000		6.000		20.000	
	467-6390	SET (TY II) (24 IN) (RCP) (4: 1) (C)	EA	8.000		8.000		16.000	
	467-6395	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA			6.000		6.000	
	467-6463	SET (TY II) (42 IN) (RCP) (4: 1) (C)	EA	2.000				2.000	
	496-6007	REMOV STR (PIPE)	LF	56.000		24.000		80.000	
	500-6001	MOBILIZATION	LS	1.000				1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	12.000				12.000	
	506-6002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	193.000		267.000		460.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	193.000		267.000		460.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	1,537.000		2,123.000		3,660.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,537.000		2,123.000		3,660.000	
	530-6005	DRIVEWAYS (ACP)	SY	917.000		1,100.000		2,017.000	
	530-6008	TURNOUTS (ACP)	SY	356.000		492.000		848.000	
	530-6016	DRIVEWAYS (BASE)	SY	1,317.000		1,655.000		2,972.000	
	533-6002	RUMBLE STRIPS (CENTERLINE)	LF	14,576.000		19,984.000		34,560.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF			400.000		400.000	
	540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA			4.000		4.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF			400.000		400.000	
	542-6002	REMOVE TERMINAL ANCHOR SECTION	EA			4.000		4.000	



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 1584-02-013

DISTRICT Beaumont  
HIGHWAY FM 1745, FM 2097

COUNTY Tyler

CONTROL SECTION JOB				1584-02-013		2271-01-011		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00196587		A00196576			
COUNTY				Tyler		Tyler			
HIGHWAY				FM 1745		FM 2097			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	542-6004	RM MTL BM GD FENCE TRANS (THRIE-BEAM)	EA			4.000		4.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA			4.000		4.000	
	560-6011	MAILBOX INSTALL-S (TWW-POST) TY 4	EA	9.000		14.000		23.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	22.000		18.000		40.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	2.000		2.000		4.000	
	644-6027	IN SM RD SN SUP&AM TYS80(1)SA(P)	EA	2.000		3.000		5.000	
	644-6030	IN SM RD SN SUP&AM TYS80(1)SA(T)	EA	2.000		2.000		4.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	28.000		25.000		53.000	
	658-6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA			4.000		4.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA			10.000		10.000	
	658-6100	INSTL OM ASSM (OM-2Z)(WFLX)GND(BI)	EA	12.000		8.000		20.000	
	662-6035	WK ZN PAV MRK NON-REMOV (Y)6"(BRK)	LF			10,040.000		10,040.000	
	662-6037	WK ZN PAV MRK NON-REMOV (Y)6"(SLD)	LF	62,296.000		40,088.000		102,384.000	
	662-6111	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	1,560.000		2,513.000		4,073.000	
	666-6317	RE PM W/RET REQ TY I (Y)6"(BRK)(090MIL)	LF			5,020.000		5,020.000	
	666-6320	RE PM W/RET REQ TY I (Y)6"(SLD)(090MIL)	LF	31,148.000		20,044.000		51,192.000	
	672-6009	REFL PAV MRKR TY II-A-A	EA	389.000		501.000		890.000	
	734-6001	LITTER REMOVAL	AC	2.680		3.670		6.350	
	3076-6001	D-GR HMA TY-B PG64-22	TON	5,647.000		363.000		6,010.000	
	3076-6066	TACK COAT	GAL	972.000		66.000		1,038.000	
	3077-6021	SP MIXES SP-C PG70-22	TON	5,124.000		7,026.000		12,150.000	
	3077-6075	TACK COAT	GAL	972.000		3,730.000		4,702.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000		4.000	
	6185-6002	TMA (STATIONARY)	DAY	68.000		87.000		155.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	7.000		8.000		15.000	
	6294-6011	AWPT W/PROFILE PM (W)6"(SLD)(175 MIL)	LF	31,148.000		40,088.000		71,236.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000				1.000	
1	464-6003	RC PIPE (CL III)(18 IN)	LF	90.000		24.000		114.000	
1A	4216-6001	THERMOPLASTIC PIPE (PP) (18")	LF	90.000		24.000		114.000	

DATE: 5/9/2024 9:33:20 AM  
 FILE: c:\xdo\p\online\tdot\5\seamantha.harris\1044287\Quantity\_Summary.dgn

ROADWAY ITEMS

CSJ	STA	TO STA	LENGTH (FT)	WIDTH (FT)	SURFACE AREA (SY)	100	112	134	247	275	316				354	3076		3077		533		
						6002	6001	6004	6231	6001	6014	6029	6094	6405	6408	6017	6001	6066	6021	6075	6002	
						PREPARING ROW	SUBGRADE WIDENING (ORD COMP)	BACKFILL (TY A OR TY B)	FL BS (CMP IN PLACE) (TY A GR 1-2) (10")	CEMENT	CEMENT TREAT (MX EXST MTL & NW BS) (8")	ASPH (RC-250)	AGGR (TY-D GR-4 SAC-A)	ASPH (AC-20-5TR OR AC-20XP)	AGGR(TY-PD GR-4 OR TY-PL GR-4)	PLAN & TEXT CONC PAV (0"- 2")	D-GR HMA TY-B PG64-22	TACK COAT	SP MIXES SP-C PG70-22	TACK COAT	RUMBLE STRIPS (CENTERLINE)	
						SY	SY	SY	SY	SY	SY	SY	SY	SY	SY	SY	SY	SY	SY	SY	LF	
1584-02-013	0+02	TO 145+78	14,576	28	45,348	145.76	145.76	145.76	-	-	-	-	-	6,478	6,478	622	16,196	16,196	45,348	45,348	14,576	
	DRIVEWAYS & INTERSECTIONS					-	-	-	-	-	-	-	-	-	-	-	917	-	-	-	-	-
2271-01-011	2+03	TO 15+95	1,392	28	4,331	13.92	13.92	13.92	1,547	4,331	4,331	4,331	4,331	-	-	622	-	-	4,331	4,331	1,392	
	15+95	TO 16+55	60	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	16+55	TO 202+47	18,592	28	57,842	185.92	185.92	185.92	20,658	57,842	57,842	57,842	57,842	-	-	622	-	-	57,842	57,842	18,592	
	DRIVEWAYS & INTERSECTIONS					-	-	-	-	-	-	-	-	-	-	-	1,100	1,100	-	-	-	-
	CSJ: 1584-02-013 SUBTOTAL:					145.76	145.76	145.76	0	0	0	0	0	6,478	6,478	622	17,113	16,196	45,348	45,348	14,576	
	CSJ: 2271-01-011 SUBTOTAL:					199.84	199.84	199.84	22,205	62,173	62,173	62,173	62,173	62,173	0	0	1,244	1,100	1,100	62,173	62,173	19,984
	PROJECT TOTAL:					345.6	345.6	345.6	22,205	62,173	62,173	62,173	62,173	6,478	6,478	1,866	18,213	17,296	107,521	107,521	34,560	

\* FOR CONTRACTOR'S INFORMATION ONLY. SEE BASIS OF ESTIMATE. # USED FOR STRIP SEAL

BASIS OF ESTIMATE

ITEM	CODE	DESCRIPTION	QUANTITY	RATE	DEPTH	QUANTITY
168	6001	VEGETATIVE WATERING	6.35 AC	6.788 MG/AC/CYCLE, 6 CYCLES	-	258 MG
275	6001	CEMENT	62,173 SY	17.7 LB/SY	-	550 TON
316	6029	ASPH (RC-250)	62,173 SY	0.20 GAL/SY	-	12,435 GAL
316	6094	AGGR (TY-D GR-4 SAC-A)	62,173 SY	1/125 CY/SY	-	497 CY
316	6405	ASPH (AC-20-5TR OR AC-20XP)	6,478 SY	0.36 GAL/SY	-	2,332 GAL
316	6408	AGGR(TY-PD GR-4 OR TY-PL GR-4)	6,478 SY	1/130 CY/SY	-	50 CY
3076	6001	D-GR HMA TY-B PG64-22	18,213 SY	110 LB/SY/IN	6 IN	6,010 TON
3076	6066	TACK COAT	17,296 SY	0.06 GAL/SY	-	1,038 GAL
3077	6021	SP MIXES SP-C PG70-22	107,521 SY	113 LB/SY/IN	2 IN	12,150 TON
3077	6075	TACK COAT	107,521 SY	0.06 GAL/SY	-	4,702 GAL

MISCELLANEOUS ITEMS

CSJ	734	6001	6185	
	6001	6002	6002	6005
	LITTER REMOVAL	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	TMA (MOBILE OPERATION)
	AC	EA	DAY	DAY
1584-02-013:	2.68	2	68	7
2271-01-011:	3.67	2	87	8
PROJECT TOTAL:	6.35	4	155	15

PAVEMENT MARKING ITEMS

CSJ	STA	TO STA	LENGTH (FT)	# 6" White Solid	# 6" Yellow Solid	# 6" Yellow Broken	662			666		672	6294
							6035	6037	6111	6317	6320	6009	6011
							WK ZN PAV MRK NON-REMOV (Y) 6" (BRK)	WK ZN PAV MRK NON-REMOV (Y) 6" (SLD)	WK ZN PAV MRK SHT TERM (TAB) TY Y-2	RE PM W/RET REQ TY I (Y) 6" (BRK) (090MIL)	RE PM W/RET REQ TY I (Y) 6" (SLD) (090MIL)	REFL PAV MRKR TY II-A-A	AWPT W/PROFILE PM (W)6"(SLD)(1
							LF	LF	EA	LF	LF	EA	LF
1584-02-013	0+02	TO 155+76	15,574	2	2	0	-	62,296	1,560	-	31,148	389	31,148
2271-01-011	2+03	TO 202+47	20,044	2	1	1	10,040	40,088	2,513	5,020	20,044	501	40,088
	PROJECT TOTAL:						10,040	102,384	4,073	5,020	51,192	890	71,236

SW3P ITEMS

CSJ	STA	TO STA	164				166	168	506				
			6021	6023	6029	6031	6001	6001	6002	6011	6041	6043	
			CELL FBR MLCH SEED (PERM)	CELL FBR MLCH SEED (PERM)	CELL FBR MLCH SEED (TEMP)	CELL FBR MLCH SEED (TEMP) (COOL)	FERTILIZER	VEGETATIVE WATERING	ROCK FILTER DAMS (INSTALL) (TY)	ROCK FILTER DAMS (REMOVE)	BIODEG EROSN CONT LOGS (INSTL) (12")	BIODEG EROSN CONT LOGS (REMOVE)	
			SY	SY	SY	SY	AC	AC	LF	LF	LF	LF	
1584-02-013	0+02	TO 145+78	9,717	3,239	6,478	6,478	2.68	2.68	-	-	-	-	
2271-01-011	2+03	TO 15+95	928	309	619	619	0.26	0.26	-	-	-	-	
	15+95	TO 16+55	-	-	-	-	-	-	-	-	-	-	
	16+55	TO 202+47	12,395	4,132	8,264	8,264	3.41	3.41	-	-	-	-	
	SEE SW3P LAYOUT								460	460	3,660	3,660	
	CSJ: 1584-02-013 SUBTOTAL:			9,717	3,239	6,478	6,478	2.68	2.68	193	193	1,537	1,537
	CSJ: 2271-01-011 SUBTOTAL:			13,323	4,441	8,882	8,882	3.67	3.67	267	267	2,123	2,123
	PROJECT TOTAL:			23,040	7,680	15,360	15,360	6.35	6.35	460	460	3,660	3,660

\* FOR CONTRACTOR'S INFORMATION ONLY.

FM 1745 ETC.

QUANTITY SUMMARY

© TxDOT 2024 SHEET 1 OF 4


CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	15	

DATE: 5/9/2024 9:33:36 AM  
 FILE: c:\xdo\pw\_online\txdot\5\seamantha.harris\1044287\Quantity\_Summary.dgn

DRIVEWAY AND INTERSECTION ITEMS

CSJ	DRIVEWAY/ INTERSECTION No.	DESCRIPTION	LT/RT	MATERIAL	R1 (FT)	R2 (FT)	W1 (FT)	W2 (FT)	L (FT)	A (SY)	# OF BARRELS	CULVERT DIAMETER (IN)	530		400	464	467		496	4216
													6005	6016	6006	6003	6363	6395	6007	6001
													DRIVEWAYS (ACP) SY	DRIVEWAYS (BASE) SY	CUT & RESTORING PAV SY	RC PIPE (CL III) (18 IN) LF	SET (TY II) (18 IN) (RCP) (6: 1) (P) EA	SET (TY II) (24 IN) (RCP) (6: 1) (P) EA	REMOV STR (PIPE) LF	THERMOPLAST IC PIPE (PP) (18") LF
	1	DRIVEWAY	RT	GRAVEL	16	16	12	44	35	59	0	0	-	59	-	-	-	-	-	-
	2	DRIVEWAY	RT	GRAVEL	13	13	8	34	38	42	0	0	-	42	-	-	-	0	-	-
	3	DRIVEWAY	RT	GRAVEL	9	9	17	34	38	75	-	-	-	75	-	-	-	-	-	-
	4	DRIVEWAY	LT	GRAVEL	11	11	14	36	54	90	-	-	-	90	-	-	-	-	-	-
	5	DRIVEWAY	LT	GRAVEL	19	19	22	59	38	109	-	-	-	109	-	-	-	-	-	-
	6	DRIVEWAY	RT	GRAVEL	28	28	15	70	48	117	-	-	-	117	-	-	-	-	-	-
	7	DRIVEWAY	LT	GRAVEL	8	8	14	30	60	96	-	-	-	96	-	-	-	-	-	-
	8	DRIVEWAY	RT	ASPHALT	13	13	40	15	58	265	-	-	265	-	-	-	-	-	-	-
	9	DRIVEWAY	RT	ASPHALT	7	7	9	22	50	52	1	18	52	-	8	8	2	-	8	8
	10	DRIVEWAY	LT	ASPHALT	5	5	12	21	26	36	1	18	36	-	7	8	2	-	8	8
	11	DRIVEWAY	LT	GRAVEL	16	16	18	50	40	92	1	18	-	-	-	8	2	-	8	8
	12	DRIVEWAY	RT	GRAVEL	19	19	17	54	45	101	-	-	-	101	-	-	-	-	-	-
	13	DRIVEWAY	LT	GRAVEL	40	40	28	108	32	242	1	18	-	242	-	8	2	-	8	8
	14	DRIVEWAY	LT	ASHPALT	2	2	15	18	40	67	-	-	67	-	-	-	-	-	-	-
	15	DRIVEWAY	RT	GRAVEL	14	14	13	40	42	70	1	18	-	70	-	8	2	-	8	8
	16	DRIVEWAY	LT	ASPHALT	9	9	11	28	43	56	-	-	56	-	-	-	-	-	-	-
	17	DRIVEWAY	RT	GRAVEL	19	19	12	50	50	84	1	18	84	-	-	8	2	-	8	8
	18	DRIVEWAY	RT	GRAVEL	12	12	17	48	39	80	-	-	80	-	-	-	-	-	-	-
	19	DRIVEWAY	LT	GRAVEL	7	7	12	25	21	30	-	-	30	-	-	-	-	-	-	-
	20	DRIVEWAY	RT	GRAVEL	42	42	16	100	43	161	-	-	161	-	-	-	-	-	-	-
	21	DRIVEWAY	LT	ASHPALT	5	5	19	28	21	44	1	18	-	-	-	8	2	-	8	8
	22	DRIVEWAY	RT	ASHPALT	14	14	10	37	38	51	-	-	51	-	-	-	-	-	-	-
	23	DRIVEWAY	RT	ASPHALT	8	8	11	26	26	35	-	-	35	-	-	-	-	-	-	-
	24	DRIVEWAY	LT	GRAVEL	37	37	21	94	35	224	-	-	-	224	-	-	-	-	-	-
CSJ 1584-02-013 SUBTOTAL:													917	1,317	15	56	14	0	56	56

\* ALTERNATE BID ITEMS

 Texas Department of Transportation

FM 1745, ETC.  
 QUANTITY  
 SUMMARY

© TxDOT 2024 SHEET 2 OF 4

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		16



DATE: 5/9/2024 9:33:52 AM  
 FILE: c:\xdo\p\online\tdot5\seamant\harris\1044287\Quantity\_Summary.dgn

DRIVEWAY AND INTERSECTION ITEMS CONTINUED

CSJ	DRIVEWAY/ INTERSECTION No.	DESCRIPTION	LT/RT	MATERIAL	R1 (FT)	R2 (FT)	W1 (FT)	W2 (FT)	L (FT)	A (SY)	# OF BARRELS	CULVERT DIAMETER (IN)	530		400	464	467		496	4216	
													6005	6016	6006	6003	6363	6395	6007	6001	
													DRIVEWAYS (ACP)	DRIVEWAYS (BASE)	CUT & RESTORING PAV	RC PIPE (CL III) (18 IN)	SET (TY II) (18 IN) (RCP) (6: 1) (P)	SET (TY II) (24 IN) (RCP) (6: 1) (P)	REMOV STR (PIPE)	THERMOPLAST IC PIPE (PP) (18")	
SY	SY	SY	LF	EA	EA	LF	LF														
	1	DRIVEWAY	RT	ASPHALT	1	1	10	12	35	39	-	-	39	-	-	-	-	-	-	-	-
	2	DRIVEWAY	RT	ASPHALT	67	67	78	212	40	644	-	-	644	-	-	-	-	-	-	-	-
	3	DRIVEWAY	LF	ASPHALT	4	4	11	18	30	37	-	-	37	-	-	-	-	-	-	-	-
	4	DRIVEWAY	RT	GRAVEL	1	1	11	12	30	37	-	-	-	-	-	-	-	-	-	-	-
	5	DRIVEWAY	LF	ASPHALT	2	2	7	11	30	24	-	-	24	-	-	-	-	-	-	-	-
	6	DRIVEWAY	RT	ASPHALT	0	0	10	10	30	33	1	18	33	-	4	8	2	-	8	-	8
	7	DRIVEWAY	RT	ASPHALT	7	7	12	25	35	49	-	-	49	-	-	-	-	-	-	-	-
	8	DRIVEWAY	LF	GRAVEL	5	5	14	23	36	57	-	-	-	57	-	-	-	-	-	-	-
	9	DRIVEWAY	RT	GRAVEL	8	8	9	24	50	53	-	-	-	53	-	-	-	-	-	-	-
	10	DRIVEWAY	RT	GRAVEL	5	5	8	17	52	47	-	-	-	47	-	-	-	-	-	-	-
	11	DRIVEWAY	RT	GRAVEL	16	16	13	44	50	84	-	-	-	84	-	-	-	2	-	-	-
	12	DRIVEWAY	RT	GRAVEL	15	15	10	40	38	53	-	-	-	53	-	-	-	2	-	-	-
	13	DRIVEWAY	LT	GRAVEL	10	10	10	30	24	31	-	-	-	31	-	-	-	-	-	-	-
	14	DRIVEWAY	RT	DIRT	7	7	8	22	42	40	-	-	-	-	-	-	-	-	-	-	-
	15	DRIVEWAY	LT	GRAVEL	15	15	10	40	27	41	-	-	-	41	-	-	-	-	-	-	-
	16	DRIVEWAY	LT	GRAVEL	19	19	11	48	38	63	-	-	-	63	-	-	-	-	-	-	-
	17	DRIVEWAY	LT	GRAVEL	10	10	9	28	42	46	-	-	-	46	-	-	-	-	-	-	-
	18	DRIVEWAY	LT	GRAVEL	1	1	10	11	42	47	-	-	-	47	-	-	-	-	-	-	-
	19	DRIVEWAY	LT	GRAVEL	8	8	10	25	42	49	-	-	-	49	-	-	-	-	-	-	-
	20	DRIVEWAY	LT	GRAVEL	4	4	10	18	27	31	-	-	-	-	-	-	-	-	-	-	-
	21	DRIVEWAY	LT	GRAVEL	23	23	10	55	58	90	-	-	-	90	-	-	-	-	-	-	-
	22	DRIVEWAY	LT	GRAVEL	13	13	10	35	28	39	-	-	-	39	-	-	-	-	-	-	-
	23	DRIVEWAY	LT	GRAVEL	10	10	13	32	44	68	-	-	-	68	-	-	-	-	-	-	-
	24	DRIVEWAY	LT	GRAVEL	2	2	35	32	36	140	-	-	-	140	-	-	-	-	-	-	-
	25	DRIVEWAY	LT	GRAVEL	47	47	12	105	70	199	-	-	-	199	-	-	-	-	-	-	-
	26	DRIVEWAY	LT	DIRT	1	1	12	10	40	53	-	-	-	-	-	-	-	-	-	-	-
	27	DRIVEWAY	RT	GRAVEL	1	1	8	9	42	35	-	-	-	35	-	-	-	-	-	-	-
	28	DRIVEWAY	RT	GRAVEL	15	15	13	42	40	68	-	-	-	68	-	-	-	-	-	-	-
	29	DRIVEWAY	LT	GRAVEL	8	8	12	27	47	66	-	-	-	66	-	-	-	-	-	-	-
	30	DRIVEWAY	RT	GRAVEL	8	8	15	30	32	56	-	-	-	56	-	-	-	-	-	-	-
	31	DRIVEWAY	LT	GRAVEL	10	10	9	28	37	42	-	-	-	42	-	-	-	-	-	-	-
	32	DRIVEWAY	RT	GRAVEL	3	3	10	16	27	30	1	18	-	30	-	8	2	-	8	-	8
	33	DRIVEWAY	RT	GRAVEL	1	1	11	12	26	32	-	-	-	32	-	-	-	-	-	-	-
	34	DRIVEWAY	RT	GRAVEL	1	1	10	12	38	42	-	-	-	42	-	-	-	-	-	-	-
	35	DRIVEWAY	LT	GRAVEL	18	18	11	46	37	61	1	18	-	61	-	8	2	-	8	-	8
	36	DRIVEWAY	RT	GRAVEL	11	11	10	32	40	50	-	-	-	50	-	-	-	-	-	-	-
	37	DRIVEWAY	RT	GRAVEL	10	10	12	32	46	66	-	-	-	66	-	-	-	-	-	-	-
	38	DRIVEWAY	LT	DIRT	5	5	10	19	50	57	-	-	-	-	-	-	-	-	-	-	-
	39	DRIVEWAY	LT	ASPHALT	14	14	10	37	46	60	-	-	60	-	-	-	-	-	-	-	-
	40	DRIVEWAY	RT	ASPHALT	8	8	15	30	33	58	-	-	58	-	-	-	-	-	-	-	-
	41	COUNTY ROA	RT	ASPHALT	31	31	10	72	44	95	-	-	95	-	-	-	-	-	-	-	-
	42	DRIVEWAY	LF	ASPHALT	20	20	9	49	42	61	-	-	61	-	-	-	2	-	-	-	-
CSJ 1584-02-013 SUBTOTAL:													917	1,317	15	56	14	0	56	56	
CSJ 2271-01-011 SUBTOTAL:													1,100	1,655	4	24	6	6	24	24	
PROJECT TOTAL:													2,017	2,972	19	80	20	6	80	80	

\* ALTERNATE BID ITEMS

BRIDGE ITEMS

CSJ	STA TO STA	438	540		542		544	658		
		6008	6001	6006	6001	6002	6004	6001	6014	6062
		CLEANING AND SEALING JOINTS (CL 7)	MTL W-BEAM GD FEN (TIM POST)	MTL BEAM GD FEN TRANS (THRIE-BEAM)	REMOVE METAL BEAM GUARD FENCE	REMOVE TERMINAL ANCHOR SECTION	RM MTL BM GD FENCE TRANS (THRIE-BEAM)	GUARDRAIL END TREATMENT (INSTALL)	INSTL DEL ASSM (D-SW)SZ (BRF) CTB (BI)	INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)
		LF	LF	EA	LF	EA	EA	EA	EA	EA
2271-01-011	15+95 TO 16+55	160	400	4	400	4	4	4	4	10
TOTAL:		160	400	4	400	4	4	4	4	10

FM 1745, ETC.

QUANTITY  
SUMMARY

© TxDOT 2024 SHEET 3 OF 4

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		17

CROSS STRUCTURES


CSJ	STA	EXISTING DESCRIPTION	PROPOSED	400	464	467			658
				6006	6003	6358	6390	6463	6100
				CUT & RESTORING PAV SY	RC PIPE (CL III) (18 IN) LF	SET (TY II) (18 IN) (RCP) (4:1) (C) EA	SET (TY II) (24 IN) (RCP) (4:1) (C) EA	SET (TY II) (42 IN) (RCP) (4:1) (C) EA	INSTL OM ASSM (OM-22) (WFLX) GND EA
CSJ 1584-02-013	6+03	24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-	2
	17+47	42" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	-	2	2
	64+43	24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-	2
	84+19	24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-	2
	134+57	12" RCP	REMOVE EXIST. 12" RCP, ADD 18" RCP, SETs EACH	11	34	2	0	-	2
	145+07	24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-	2
	CSJ 2271-01-011	55+61	24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-
112+97		24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-	2
126+53		24" RCP	ADD 4:1 SETs EACH SIDE	-	-	-	2	-	2
141+30		24" RCP	ADD 4:1 SETs	-	-	-	2	-	2
CSJ 1584-02-013 SUBTOTAL:				11	34	2	8	2	12
CSJ 2271-01-011 SUBTOTAL:				0	0	0	8	0	8
PROJECT TOTAL:				11	34	2	16	2	20

MAILBOX ITEMS

CSJ	STA	MAILBOX #	# OF MAILBOXES	SIDE OF ROAD	560	530
					6011	6008
					MAILBOX INSTALL-S (TWW-POST) EA	TURNOUTS (ACP) SY
CSJ: 1584-02-013	125+50	1	2	LF	1	55
	127+41	2	1	LF	1	43
	128+24	3	1	RT	1	42
	131+15	4	1	LF	1	-
	131+41	5	1	RT	1	61
	133+70	6	1	RT	1	42
	137+42	7	1	RT	1	40
	139+55	8	1	LT	1	33
	140+78	9	1	RT	1	40
CSJ: 2271-01-011	5+08	1	1	LF	1	50
	7+06	2	1	LF	1	38
	11+07	3	1	LF	1	44
	76+61	4	1	LF	1	37
	79+18	5	1	LF	1	38
	79+55	6	1	LF	1	-
	82+92	7	1	LF	1	42
	99+02	8	1	LF	1	34
	134+96	9	1	LF	1	32
	137+48	10	1	LF	1	38
	146+30	11	1	LF	1	31
	162+47	12	1	LF	1	40
	198+59	13	1	LF	1	36
	200+60	14	1	LF	1	32
CSJ: 1584-02-013 SUBTOTAL:					9	356
CSJ: 2271-01-011 SUBTOTAL:					14	492
PROJECT TOTAL:					23	848

SIGNS

CSJ	644				
	6001	6004	6027	6030	6076
	IN SM RD SN SUP&AM TY10BWG (1) SA (P)	IN SM RD SN SUP&AM TY10BWG (1) SA (T)	IN SM RD SN SUP&AM TYS80(1) SA (P)	IN SM RD SN SUP&AM TYS80(1) SA (T)	REMOVE SM RD SN SUP&AM
1584-02-013:	22	2	2	2	28
2271-01-011:	18	2	3	2	25
PROJECT TOTAL:	40	4	5	4	53

 Texas Department of Transportation

FM 1745, ETC.  
QUANTITY SUMMARY

© TxDOT 2024 SHEET 4 OF 4

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		18


**SEQUENCE OF WORK:**

**FM 1745:**

1. MOBILIZE & INSTALL CONSTRUCTION BARRICADES, SIGNS, AND EROSION CONTROL DEVICES AS DIRECTED, MAINTAIN THESE ITEMS THROUGHOUT THE DURATION OF THIS PROJECT.
2. PERFORM FLEXIBLE PAVEMENT STRUCTURE REPAIRS AS DIRECTED.
3. PERFORM SUBGRADE WIDENING AS SHOWN IN THE PLANS.
4. PERFORM MILL AND FILL OPERATIONS TO REMOVE EXISTING CENTERLINE RUMBLE STRIPS.
  - 4a. PLACE NON-REMOVABLE CENTERLINE PAVMENT MARKINGS.
5. PLACE SUPERPAVE OVERLAY AND WORK ZONE TABS.
6. PLACE MILLED CENTERLINE RUMBLE STRIPS, PLACE MILLED EDGELINE RUMBLE STRIP AT EDGELINES FOLLOWING THE CURRENT STANDARDS.
7. PLACE PERMANENT PAVEMENT MARKING AS SHOWN IN THE PLANS AND IN ACCORDANCE WITH THE CURRENT PAVEMENT MARKING STANDARDS. NO LATER THAN 14 CALENDAR DAYS AFTER THE PLACEMENT OF THE SUPERPAVE
8. PERFORM SIGN AND MAILBOX UPGRADES
9. CLEAN SITE AND REMOVE BARRICADES, SIGNS, AND ANY EROSION CONTROL DEVICES AFTER FINAL ACCEPTANCE.

**NOTES:**


- PREPARE THE BID ACCORDING TO THIS SEQUENCE OF WORK. THE ENGINEER MAY MAY APPROVE ADJUSTMENTS TO THE SCHEDULE OF WORK AFTER LETTING.
- REFER TO THE GENERAL NOTES AND PLAN SHEETS FOR ADDITIONAL DIRECTION.



STOCK PILE LOCATION : 30°54'59.33"N 94°36'24.16"W

**FM 2097:**

1. MOBILIZE & INSTALL CONSTRUCTION BARRICADES, SIGNS, AND EROSION CONTROL DEVICES AS DIRECTED, MAINTAIN THESE ITEMS THROUGHOUT THE DURATION OF THIS PROJECT.
2. PERFORM FLEXIBLE PAVEMENT STRUCTURE REPAIRS AS DIRECTED.
3. PERFORM SUBGRADE WIDENING AS SHOWN IN THE PLANS.
4. PERFORM REMIX WITH EXISTING MATERIAL WITH CEMENT TREAT IT FULL WIDTH, PLACE INVERTED PRIME THE SAME DAY
5. PLACE NON-REMOVABLE PAVMENT MARKINGS
6. PLACE SUPERPAVE OVERLAY AND WORK ZONE TABS.
7. PLACE MILLED CENTERLINE RUMBLE STRIPS, PLACE MILLED EDGELINE RUMBLE STRIP AT EDGELINES FOLLOWING THE CURRENT STANDARDS.
8. PLACE PERMANENT PAVEMENT MARKING AS SHOWN IN THE PLANS AND IN ACCORDANCE WITH THE CURRENT PAVEMENT MARKING STANDARDS. NO LATER THAN 14 CALENDAR DAYS AFTER THE PLACEMENT OF THE SUPERPAVE
9. PERFORM SIGN AND MAILBOX UPGRADES
10. CLEAN SITE AND REMOVE BARRICADES, SIGNS, AND ANY EROSION CONTROL DEVICES AFTER FINAL ACCEPTANCE.



*[Signature]* P.E.  
04/29/2024



**FM 1745, ETC.**  
**SEQUENCE OF WORK**

© TxDOT 2023 SHEET 1 OF 1

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	19	

DATE: 4/23/2024 3:36:34 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinari\1044291\ISOW.dgn

DW: CK: DW: CK: CK:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/23/2024 3:47:01 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044291\bc-21.dgn

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b> <a href="http://www.txdot.gov">http://www.txdot.gov</a>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

 Texas Department of Transportation		Traffic Safety Division Standard	
<b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b>			
<b>BC (1) - 21</b>			
FILE:	bc-21.dgn	DN:	TxDOT
© TxDOT	November 2002	CK:	TxDOT
		DW:	TxDOT
		CR:	TxDOT
		HW:	TxDOT
		CON:	1584
		SECT:	02
		JOB:	013, ETC.
		HIGHWAY:	FM1745, ETC
REVISIONS		DIST:	TYLER
4-03	7-13	COUNTY:	
9-07	8-14	SHEET NO.:	20
5-10	5-21		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			75	900 <sup>2</sup>
			80	1000 <sup>2</sup>
			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - Contractor will install a regulatory speed limit sign at the end of the work zone.

**LEGEND**

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC(2)-21**


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	TYLER	21	

DATE: 4/23/2024 4:02:10 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\d1044291\bc-21.dgn

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
  - 40 mph and greater 0.2 to 2 miles
  - 35 mph and less 0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:06:54 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.mollinar\1044291\bc-21.dgn


SHEET 3 OF 12

		Traffic Safety Division Standard	
<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) - 21</h3>			
FILE:	bc-21.dgn	DW:	TxDOT
© TxDOT	November 2002	CONT:	1584
REVISIONS		SECT:	02
9-07	8-14	JOB:	013, ETC.
7-13	5-21	DIST:	FM1745, ETC
		COUNTY:	
		SHEET NO.:	22
		BMT:	TYLER

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:08:56 AM  
 FILE: c:\t\dot\p\_w\_online\t\dot5\francisco.mallinar\d1044291\bc-21.dgn


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




**Nails shall NOT be allowed.**  
 Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflective when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTC list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTC) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short, duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTC lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTC list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12





**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

BC (4) - 21


FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1584	02	013, ETC.		FM1745, ETC			
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	TYLER			23			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

**WEDGE ANCHORS**  
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**  
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."
  - \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC(5) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	1584	SECT:	02	JOB:	013, ETC.	FM1745,	ETC
REVISIONS									
9-07	8-14	DIST:		COUNTY:		SHEET NO.:			
7-13	5-21	BMT:		TYLER					24

DATE: 4/24/2024 7:12:38 AM  
FILE: c:\txdot\pw\_online\francisco.mollinar\1044291\bc-21.dgn



WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

### Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:15:15 AM  
FILE: c:\txdot\p\_w\_online\txdot5\francisco.molinar\1044291\bc-21.dgn

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Hour(s)	HR, HRS	Time Minutes	TIME MIN
Information	INFO	Upper Level	UPR LEVEL
It Is	ITS	Vehicles (s)	VEH, VEHS
Junction	JCT	Warning	WARN
Left	LFT	Wednesday	WED
Left Lane	LFT LN	Weight Limit	WT LIMIT
Lane Closed	LN CLOSED	West	W
Lower Level	LWR LEVEL	Westbound	(route) W
Maintenance	MAINT	Wet Pavement	WET PVMT
		Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

SHEET 6 OF 12



## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	1584	SECT:	02	JOB:	013, ETC.	FM:	1745, ETC
REVISIONS									
9-07	8-14	DIST:		COUNTY:		SHEET NO.:			
7-13	5-21	BMT:		TYLER		25			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/24/2024 7:16:53 AM  
 FILE: c:\txdot\p\_w\_online\txdot5\francisco.mallinar\1044291\bc-21.dgn

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) -21**

FILE:	bc-21.dgn	DN:	TxDOT	CR:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1584	02	013, ETC.		FM1745, ETC			
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BMT	TYLER	26					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:19:10 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.m\linarc\dl1044291\bc-21.dgn

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:



- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**

FILE:	bc-21.dgn	DW:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT:	1584	SECT:	02	JOB:	013, ETC.	DIST:	FM1745, ETC
REVISIONS									
4-03	8-14								
9-07	5-21								
7-13									
		BMT		TYLER				SHEET NO. 27	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:19:45 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.mollinar\1044291\bc-21.dgn



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

\* \* \*Taper lengths have been rounded off.  
 L=Length of Taper (FT.) W=Width of Offset (FT.)  
 S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	TYLER	28	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:20:27 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.molinar\d1044291\bc-21.dgn


**TYPE 3 BARRICADES**

- Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
- Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
- Warning lights shall NOT be installed on barricades.
- Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**




**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

- Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
- Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**

- Where positive redirection capability is provided, drums may be omitted.
- Plastic construction fencing may be used with drums for safety as required in the plans.
- Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
- When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
- Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector



Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
- Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) -21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BMT	TYLER	29	

## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

**BC(11)-21**

FILE: bc-21.dgn	DN: TxDOT	CR: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	BMT	TYLER	30	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:21:39 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044291\bc-21.dgn

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.



RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




### SOLID LINES



### BROKEN LINES




### AUXILIARY OR LANEDROP LINE



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
1-97 9-07 5-21				
2-98 7-13				
11-02 8-14	BMT		TYLER	SHEET NO. 31

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:22:32 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\d1044291\bc-21.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:31:08 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.mollinar\1044297\tcp2-1-18.dgn




TCP (2-1a)

**WORK SPACE NEAR SHOULDER**  
 Conventional Roads



TCP (2-1b)

**WORK SPACE ON SHOULDER**  
 Conventional Roads



TCP (2-1c)

**WORK VEHICLES ON SHOULDER**  
 Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	700'	770'	840'	70'	140'	800'	475'	
75	750'	825'	900'	75'	150'	900'	540'	

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
- Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
- Additional work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.



**TRAFFIC CONTROL PLAN**  
**CONVENTIONAL ROAD**  
**SHOULDER WORK**



**TCP (2-1) - 18**

FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	BMT	TYLER	32	
1-97 2-18				



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 7:34:59 AM  
 FILE: c:\txdot\pw\_online\francisco.mollinar\1044297\tcp2-2-18.dgn



**LEGEND**

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**TYPICAL USAGE**

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
  - Flaggers should use two-way radios or other methods of communication to control traffic.
  - Length of work space should be based on the ability of flaggers to communicate.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
  - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
  - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
  - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

**Texas Department of Transportation** Traffic Operations Division Standard


**TRAFFIC CONTROL PLAN**  
**ONE-LANE TWO-WAY**  
**TRAFFIC CONTROL**

**TCP (2-2) - 18**


FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT	REVISIONS	CON	SECT	JOB
8-95 3-03	1584	02	013, ETC.	FM1745, ETC
1-97 2-12				
4-98 2-18				
	DIST	COUNTY	SHEET NO.	
	BMT	TYLER	33	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/24/2024 7:40:04 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.mollinar\d1044291\tcp3-1.dgn




TCP (3-1a)  
**UNDIVIDED MULTILANE ROADWAY**




TCP (3-1b)  
**TWO-WAY ROADWAY WITH PAVED SHOULDERS**



TCP (3-1c)  
**TWO-WAY ROADWAY WITHOUT PAVED SHOULDERS**



**TRAIL/SHADOW VEHICLE A**  
 with RIGHT Directional display Flashing Arrow Board




**TRAIL/SHADOW VEHICLE B**  
 with Flashing Arrow Board in CAUTION display

LEGEND			
*	Trail Vehicle	ARROW BOARD DISPLAY	
**	Shadow Vehicle		
***	Work Vehicle		RIGHT Directional
	Heavy Work Vehicle		LEFT Directional
	Truck Mounted Attenuator (TMA)		Double Arrow
	Traffic Flow		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**GENERAL NOTES**

1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY" (CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.



**STRIPING FOR TMA**









Texas Department of Transportation  
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN  
 MOBILE OPERATIONS  
 UNDIVIDED HIGHWAYS**

**TCP (3-1) - 13**

FILE: tcp3-1.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT December 1985	CONT: 1584	SECT: 02	JOB: 013, ETC.	HIGHWAY: FM 1745, ETC
REVISIONS				
2-94 4-98				
8-95 7-13				
1-97				
BMT		COUNTY: TYLER	SHEET NO.: 34	

DATE: 4/24/2024 7:41:42 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\tcp3-3.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LEGEND		
* Trail Vehicle	ARROW BOARD DISPLAY	
** Shadow Vehicle		
*** Work Vehicle		RIGHT Directional
		LEFT Directional
		Double Arrow
		CAUTION (Alternating Diamond or 4 Corner Flash)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓				

**GENERAL NOTES**

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- For divided highways with two or three lanes in one direction, the appropriate LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
- A double arrow shall not be displayed on the arrow board on the Advance Warning Vehicle.
- For divided highways with three or four lanes in each direction, use TCP(3-2).
- Standard diamond shape versions of the CW20-5 series signs may be used as an option if the rectangular signs shown are not available.
- The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessary.
- On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.


Texas Department of Transportation

Traffic Operations Division Standard


## TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL TCP (3-3) - 14

FILE: tcp3-3.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT September 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
2-94 4-98	DIST	COUNTY		SHEET NO.
8-95 7-13	BMT	TYLER		35
1-97 7-14				

DATE: 4/24/2024 8:14:57 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\tcpsc-1-22.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (SC-1a)  
**ONE LANE TWO-WAY (TWO LANES)  
 CONTROL WITH PILOT VEHICLE**



TCP (SC-1b)  
**ONE LANE TWO-WAY (THREE LANES)  
 CONTROL WITH PILOT VEHICLE  
 AND CHANNELIZING DEVICES**

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing Distance "x"	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L = Length of Taper (FT) W = Width of Offset (FT) S = Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

**GENERAL NOTES**

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except: if project signing is present, END ROAD WORK (G20-2) sign is optional with approval by the Engineer.
- Sign spacing may be increased or an additional ROAD WORK AHEAD (CW20-1D) sign may be used if advance warning ahead of the flagger sign is less than 1500 feet.
- Flaggers should use two-way radios or other methods of communication at all times for traffic control coordination.
- Flaggers should use 24" STOP (CW20-8) / SLOW (CW20-8aT) paddles to control traffic. Flags should be limited to emergency situations.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- If the seal coat operation crosses intersections, traffic in these areas must be controlled. Care must be taken to prevent vehicles from crossing the asphalt before the aggregate is placed. This may require positioning additional traffic control personnel (flaggers) at the intersection.
- Temporary rumble strips are not required on seal coat operations.
- The pilot car is used to guide vehicles through traffic control zone. The pilot car shall have an identification name displayed and PILOT CAR, FOLLOW ME (G20-4) sign or message board mounted in a conspicuous position on rear.

**TCP (SC-1a)**


- Channelizing devices on the centerline are not required when a pilot car is leading traffic, unless directed by the Engineer.

SHEET 1 OF 8


		Traffic Safety Division Standard	
<b>TRAFFIC CONTROL PLAN SEAL COAT OPERATIONS ONE-LANE TWO-WAY</b>			
<b>TCP (SC-1) - 22</b>			
FILE: tcpsc-1-22.dgn	DN:	CK:	DW:
© TxDOT October 2022	CONT	SECT	JOB
REVISIONS	1584	02	013, ETC.
4-21	DIST	COUNTY	SHEET NO.
10-22	BMT	TYLER	36

DATE: 4/24/2024  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\tcpssc-7-22.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


### WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS (TABS)




CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO LANE TWO-WAY HIGHWAYS



LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



LANE LINES FOR DIVIDED HIGHWAY




TWO-WAY LEFT TURN LANE

### WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS (TABS)

SOLID LINES	DOUBLE NO-PASSING LINE	
	SINGLE NO-PASSING LINE OR CHANNELIZATION LINE	
	8" WIDE SOLID LINE	
BROKEN LINES (FOR CENTER LINE OR LANE LINE)		
WIDE DOTTED LINES (FOR LANE DROP LINES)		
WIDE GORE MARKINGS		

### TABS ON CENTERLINES OF TWO-LANE TWO-WAY ROADS



#### TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS

- Temporary markings for surfacing projects shall be Temporary Flexible-Reflective Roadway Marker Tabs with protective cover unless otherwise approved by the Engineer. Tabs are to be installed to provide true alignment for striping crews or as directed by the Engineer. Tabs will be placed at the spacing indicated. Tabs should be applied to the pavement no more than two days before the surfacing is applied. After the surfacing is rolled and swept, the protective cover over the reflective strip shall be removed.
- Temporary Flexible-Reflective Roadway Marker Tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with a yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Temporary Flexible-Reflective Roadway Marker Tabs will require normal maintenance replacement when used on roadways with an Average Daily Traffic (ADT) per lane of up to 7500 vehicles with no more than 10% truck mix. When roadway volumes exceed these values, additional maintenance replacement of these devices should be planned for.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 4.
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- Tabs shall NOT be used to simulate edge lines.

#### NOTES:


- The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For exit gores where a lane is being dropped, place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are NOT acceptable.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.

#### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above may be found along with embedded links to their respective MPLs at the following website: <http://www.txdot.gov>

SHEET 7 OF 8

#### TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS




### TEMPORARY PAVEMENT MARKINGS FOR SEAL COAT OPERATIONS

#### TCP (SC-7) -22

FILE:	tcpssc-7-22.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	October 2022	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1584	02	013, ETC.	FM1745, ETC				
4-21	10-22	DIST	COUNTY	SHEET NO.					
		BMT	TYLER	37					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 8:26:05 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\tcpsc-8-22.dgn



**NOTE**  
 Signing shown for one direction of travel only.

**NO PASSING ZONES ON TWO-LANE TWO-WAY ROADS**

**DO NOT PASS (R4-1) SIGN and NO-PASSING ZONES**

- A. Prior to the beginning of construction, all currently striped no-passing zones shall be signed with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone for each direction of travel, except as otherwise provided herein. Signs marking these individual no-passing zones need not be covered prior to construction if the signs supplement the existing pavement markings.
- B. At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If passing is to be prohibited over one or more lengthy sections, a DO NOT PASS sign and a NEXT XX MILES (R20-1TP) plaque may be used at the beginning of such zones. The DO NOT PASS sign and the NEXT XX MILES plaque should be repeated every mile to the end of the no-passing zone. In areas where there is a considerable distance between no-passing zones, the end of the no-passing zone may be signed with a PASS WITH CARE sign and a NEXT XX MILES plaque.
- C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent damage to windshields and lights. The DO NOT PASS sign and NEXT XX MILES plaque should be used and repeated as often as necessary for this purpose. Where several existing zones are to be combined into one individual no-passing zone, the sign at the beginning of the zone should be covered until the surfacing operation has passed this location so as not to have the DO NOT PASS sign conflict with the existing pavement markings. Also, unless one day of operation completes the entire length of such combined zones, appropriate DO NOT PASS and PASS WITH CARE signs should be placed at the beginning and end of the no-passing zones where the surfacing operation has stopped for the day.
- D. DO NOT PASS and PASS WITH CARE signs are to remain in place until permanent pavement markings are installed.

**NO CENTER LINE (CW8-12) SIGN**

- A. Center line markings are yellow pavement markings that delineate the separation between lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.
- B. At the time construction activity obliterates the existing center line markings (low volume roads may not have an existing center line), a NO CENTER LINE (CW8-12) sign should be erected at the beginning of the work area, at approximately two mile intervals within the work area, beyond major intersections, and other locations deemed necessary by the Engineer.
- C. The NO CENTER LINE signs are to remain in place until permanent pavement markings are installed.

**LOOSE GRAVEL (CW8-7) SIGN**

- A. When construction begins, a LOOSE GRAVEL (CW8-7) sign should be erected at each end of the work area and repeated at intervals of approximately two miles in rural areas and closer in urban areas.
- B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

**COORDINATION OF SIGN LOCATIONS**

- A. The location of warning signs at the beginning and end of a work area are to be coordinated with other signing typically shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.
- B. Where possible, the ROAD WORK AHEAD (CW20-1D), LOOSE GRAVEL (CW8-7), and NO CENTER LINE (CW8-12) signs should be placed:
  - a.) In the sequence shown following the OBEY WARNING SIGNS STATE LAW (R20-3T) sign and the TRAFFIC FINES DOUBLE (R20-5T) sign; and
  - b.) One "X" sign spacing prior to the CONTRACTOR (G20-6T) sign typically located at or near the limits of surfacing.
 LOOSE GRAVEL and NO CENTER LINE sign placements will then be repeated as described above.

Posted Speed *	Minimum Sign Spacing Distance "x"
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

\* Conventional Roads Only

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

**GENERAL NOTES**

1. Surfacing operations that cover or obliterate existing pavement markings must first have the passing zones clearly marked with tabs as well as having any of the traffic control devices detailed on this sheet furnished and erected as directed by the Engineer.
2. The devices shown on this sheet are to be used to supplement those required by the BC Standards or others required elsewhere in the plans.
3. Signs shall be erected as detailed on the BC Standards or the Compliant Work Zone Traffic Control Devices List (CWZTCD) on supports approved for Short Duration / Short Term Stationary Work Zone Sign Supports.
4. When surfacing operations take place on divided highways, freeways or expressways, the size of diamond shaped construction warning signs shall be 48" x 48".
5. Signs on divided highways, freeways and expressways should be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.


SHEET 8 OF 8

		Traffic Safety Division Standard	
<b>TRAFFIC CONTROL DETAILS FOR SEAL COAT OPERATIONS</b>			
<b>TCP (SC-8) -22</b>			
FILE: tcpsc-8-22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT October 2022	CONT	SECT	JOB
REVISIONS	1584 02	013, ETC.	FM1745, ETC
4-21	DIST	COUNTY	SHEET NO.
10-22	BMT	TYLER	38


DATE: 4/24/2024 8:30:32 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\wzrs22.dgn

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



**RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION**



**RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY**

**GENERAL NOTES**

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT)  
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.  
 \* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

Texas Department of Transportation  
 Traffic Safety Division Standard

## TEMPORARY RUMBLE STRIPS


### WZ (RS) - 22

FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	BMT	TYLER	39	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 8:37:09 AM  
 FILE: c:\txdot\pw\_onlinetxdot\5\francisco.mollinar\1044297\wz(stpm)-23.dgn

## WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS





### NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

### TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

## WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



### PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

### RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

### DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

[http://www.txdot.gov/business/contractors\\_consultants/material\\_specifications/default.htm](http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm)



## WORK ZONE SHORT TERM PAVEMENT MARKINGS





### WZ(STPM)-23

FILE:	wzstpm-23.dgn	DN:		CK:		DW:		CK:	
© TxDOT	February 2023	CONTRACT	1584	SECT	02	JOB	013.ETC.	HIGHWAY	FM1745.ETC
REVISIONS		DIST	COUNTY		SHEET NO.				
4-92	7-13	BMT	TYLER		40				
1-97	2-23								
3-03									



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 8:40:13 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\wzul-13.dgn



DEPARTMENTAL MATERIAL SPECIFICATIONS	
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B <sub>FL</sub> OR TYPE C <sub>FL</sub> SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

**GENERAL NOTES**

- If spalling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
- UNEVEN LANES (CW8-11) signs shall be installed in advance of the condition and repeated every mile. Signs installed along the uneven lane condition may be supplemented with the NEXT XX MILES (CW7-3aP) plaque or Advisory Speed (CW13-1P) plaque.
- NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
- Signs shall be spaced at the distances recommended as per BC standards.
- Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
- Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list.
- Short term markings shall not be used to simulate edge lines.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

Edge Condition	Edge Height (D)	* Warning Devices
①	Less than or equal to: 1/4" (maximum-planing) 1/2" (typical-overlay)	Sign: CW8-11
②	Less than or equal to 3"	Sign: CW8-11
③	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".	

**TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.**


MINIMUM WARNING SIGN SIZE	
Conventional roads	36" x 36"
Freeways/expressways, divided roadways	48" x 48"




**SIGNING FOR UNEVEN LANES**

**WZ (UL) - 13**

FILE: wzul-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT	APRIL 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC	
8-95 2-98 7-13	DIST	COUNTY	SHEET NO.		
1-97 3-03	BMT	TYLER	41		



LOCATION MAP



NOTES:  
 HORIZONTAL COORDINATES SHOWN ARE IN U.S. SURVEY FEET, AND ARE BASED UPON THE TEXAS COORDINATE SYSTEM OF NAD83 (2011) EPOCH 2010.00. TEXAS CENTRAL ZONE (4203), WITH A SURFACE ADJUSTMENT FACTOR OF 1.00012. VALUES WERE DERIVED UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

ELEVATIONS ARE BASED UPON NAVD 88 DATUM (GEOID 18) DERIVED FROM UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

LEGEND

△ 3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



*Stephen J. Dial*  
 STEPHEN J. DIAL  
 RPLS NO. 6697

10/26/23  
 DATE

NO.	REVISION	BY	DATE

**CP&Y**  
 an STV Company  
 1820 REGAL ROW, SUITE 150  
 DALLAS, TEXAS 75235  
 PHONE NUMBER: 214-638-0500  
 TBPELS FIRM REGISTRATION NUMBER 10194115


©2023 Texas Department of Transportation


FM 1745  
**HORIZONTAL AND VERTICAL CONTROL INDEX SHEET**

CSJ 1584-01-013 SHEET 1 OF 1

DESIGNED: AJ	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CHECKED: SJD		TEXAS			FM 1745
DRAFTED: JDS	DIST.	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
CHECKED: SJD	BMT	TYLER	1584	02	013
					SHEET NO. 42


CONTROL POINT	SURFACE COORDINATES		NAVD 88 ELEVATION	GRID COORDINATES		DESCRIPTION
	NORTHING	EASTING		NORTHING	EASTING	
2290001	10,338,919.05	4,084,200.92	293.24	10,337,678.53	4,083,710.88	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290002	10,341,317.60	4,087,733.44	316.05	10,340,076.79	4,087,242.97	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290003	10,343,905.70	4,091,765.80	330.52	10,342,664.58	4,091,274.84	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290004	10,348,277.14	4,093,792.09	252.70	10,347,035.50	4,093,300.90	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR





2290001: A 3-1/4-inch Aluminum Disk stamped "2290001" set on a 18" long 5/8" rebar. Being located northwest of FM 1745, 2.7± miles south of the intersection of FM 1745 and US 287 in the Town of Chester, Tyler County, Texas. Being 20± feet northwest of the northwest pavement edge of FM 1745, 360± feet northeast of a POLK COUNTY LINE sign, and 200± feet southwest of a drainage structure on the northwest side of FM 1745.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.




2290002: A 3-1/4-inch Aluminum Disk stamped "2290002" set on a 18" long 5/8" rebar. Being located southeast of FM 1745, 1.9± miles south of the intersection of FM 1745 and US 287 in the Town of Chester, Tyler County, Texas. Being 25± feet southeast of the southeast pavement edge of FM 1745, 24± feet west of a power pole, and 50± feet west of a TxDOT (Texas Department of Transportation) TYPE I monument on the southeast side of FM 1745.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.

NOTES:  
 HORIZONTAL COORDINATES SHOWN ARE IN U.S. SURVEY FEET, AND ARE BASED UPON THE TEXAS COORDINATE SYSTEM OF NAD83 (2011) EPOCH 2010.00. TEXAS CENTRAL ZONE (4203), WITH A SURFACE ADJUSTMENT FACTOR OF 1.00012. VALUES WERE DERIVED UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.


ELEVATIONS ARE BASED UPON NAVD 88 DATUM (GEOID 18) DERIVED FROM UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

**LEGEND**  
 △ 3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR



2290003: A 3-1/4-inch Aluminum Disk stamped "2290003" set on a 18" long 5/8" rebar. Being located southeast of FM 1745, 0.9± miles south of the intersection of FM 1745 and US 287 in the Town of Chester, Tyler County, Texas. Being 23± feet southeast of the southeast pavement edge of FM 1745, 91± feet northeast of a SPEED LIMIT 55 sign, and 190± feet southwest of the edge of pavement of Valley Road on the southeast side of FM 1745.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.



2290004: A 3-1/4-inch Aluminum Disk stamped "2290004" set on a 18" long 5/8" rebar. Being located at the southwest intersection of FM 1745/FM 2097 and US 287 in the Town of Chester, Tyler County, Texas. Being 31± feet northwest of the northwest pavement edge of FM 1745, 39± feet southeast of a power pole, and 34± feet southwest of a directional sign at the southwest intersection of FM 1745/FM 2097 and US 287.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



*Stephen J. Dial*  
 Stephen J. Dial  
 RPLS NO. 6697  
 10/26/23  
 DATE


NO.	REVISION	BY	DATE

**CP&Y**  
 an STV Company  
 1820 REGAL ROW, SUITE 150  
 DALLAS, TEXAS 75235  
 PHONE NUMBER: 214-638-0500  
 TBPELS FIRM REGISTRATION NUMBER 10194115

©2023 Texas Department of Transportation  
 FM 1745

**HORIZONTAL AND VERTICAL CONTROL SHEET**  
**CSJ 1584-01-013 SHEET 1 OF 1**

DESIGNED:	AJ	FED. RD. DIV. NO.:	STATE:	FEDERAL AID PROJECT NO.:	HIGHWAY NO.:	
CHECKED:	SJD		TEXAS		FM 1745	
DRAFTED:	JDS	DIST.:	COUNTY:	CONTROL SECTION NO.:	JOB NO.:	SHEET NO.:
CHECKED:	SJD	BMT	TYLER	1584 02	013	43



LOCATION MAP




NOTES:  
 HORIZONTAL COORDINATES SHOWN ARE IN U.S. SURVEY FEET, AND ARE BASED UPON THE TEXAS COORDINATE SYSTEM OF NAD83 (2011) EPOCH 2010.00. TEXAS CENTRAL ZONE (4203), WITH A SURFACE ADJUSTMENT FACTOR OF 1.00012. VALUES WERE DERIVED UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

ELEVATIONS ARE BASED UPON NAVD 88 DATUM (GEOID 18) DERIVED FROM UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

LEGEND

△ 3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR



THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



*Stephen J. Dial*  
 STEPHEN J. DIAL  
 RPLS NO. 6697  
 10/11/23  
 DATE

NO.	REVISION	BY	DATE


CONTROL POINT	SURFACE COORDINATES		NAVD 88 ELEVATION	GRID COORDINATES		DESCRIPTION
	NORTHING	EASTING		NORTHING	EASTING	
2290004	10,348,277.14	4,093,792.09	252.70	10,347,035.50	4,093,300.90	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290005	10,350,979.25	4,090,613.35	245.52	10,349,737.29	4,090,122.53	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290006	10,356,093.26	4,089,556.96	295.81	10,354,850.68	4,089,066.27	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290007	10,360,466.57	4,090,268.29	267.71	10,359,223.47	4,089,777.51	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR
2290008	10,363,843.23	4,093,409.48	265.13	10,362,599.72	4,092,918.33	3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR

**CP&Y**  
 an STV Company  
 1820 REGAL ROW, SUITE 150  
 DALLAS, TEXAS 75235  
 PHONE NUMBER: 214-638-0500  
 TBPELS FIRM REGISTRATION NUMBER 10194115

©2023 Texas Department of Transportation


FM 2097  
**HORIZONTAL AND VERTICAL CONTROL INDEX SHEET**  
 CSJ 1584-01-013 SHEET 1 OF 1

DESIGNED: AJ	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.		HIGHWAY NO.
CHECKED: SJD		TEXAS			FM 2097
DRAFTED: JDS	DIST.	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.
CHECKED: SJD	BMT	TYLER	1584	02	013
					SHEET NO. 44




2290008: A 3-1/4-inch Aluminum Disk stamped "2290008" set on a 18" long 5/8" rebar. Being located at the southeast intersection of FM 2097 and FM 2600, 3.8± miles north of the intersection of FM 2097 and US 287 in the Town of Chester, Tyler County, Texas. Being 43± feet east of the centerline of the pavement of FM 2097, 6± feet west of a barbed wire fence, and 44± feet northeast of a pavement ends sign on the east side of FM 2097.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.




2290007: A 3-1/4-inch Aluminum Disk stamped "2290007" set on a 18" long 5/8" rebar. Being located southeast of FM 2097, 2.8± miles north of the intersection of FM 2097 and US 287 in the Town of Chester, Tyler County, Texas. Being 29± feet southeast of the centerline of the pavement of FM 2097, 80± feet southeast of a power pole on the northwest side of FM 2097, and 204± feet northeast of a "curved arrow left" 45 MPH sign on the northwest side of FM 2097.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.



2290006: A 3-1/4-inch Aluminum Disk stamped "2290006" set on a 18" long 5/8" rebar. Being located southeast of FM 2097, 1.9± miles north of the intersection of FM 2097 and US 287 in the Town of Chester, Tyler County, Texas. Being 81± feet northeast of a "curved arrow left" sign on the southeast side of FM 2097, and 241± feet northeast of a power pole on the southeast side of FM 2097.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.



2290005: A 3-1/4-inch Aluminum Disk stamped "2290005" set on a 18" long 5/8" rebar. Being located southwest of FM 2097, 0.8± miles north of the intersection of FM 2097 and US 287 in the Town of Chester, Tyler County, Texas. Being 44± feet southwest of the centerline of the pavement of FM 2097, 73± feet southwest of a power pole on the southwest side of FM 2097, and 122± feet northwest of a power pole on the southwest side of FM 2097.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18 TXDOT VRS NETWORK.

NOTES:  
 HORIZONTAL COORDINATES SHOWN ARE IN U.S. SURVEY FEET, AND ARE BASED UPON THE TEXAS COORDINATE SYSTEM OF NAD83 (2011) EPOCH 2010.00. TEXAS CENTRAL ZONE (4203), WITH A SURFACE ADJUSTMENT FACTOR OF 1.00012. VALUES WERE DERIVED UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

ELEVATIONS ARE BASED UPON NAVD 88 DATUM (GEOID 18) DERIVED FROM UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

**LEGEND**  
 △ 3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



*Stephen J. Dial*  
 Stephen J. Dial  
 RPLS NO. 6697  
 10/11/23  
 DATE

NO.	REVISION	BY	DATE

**CP&Y**  
 an STV Company  
 1820 REGAL ROW, SUITE 150  
 DALLAS, TEXAS 75235  
 PHONE NUMBER: 214-638-0500  
 TBPELS FIRM REGISTRATION NUMBER 10194115

©2023 Texas Department of Transportation

FM 2097  
**HORIZONTAL AND VERTICAL CONTROL SHEET**  
 CSJ 1584-01-013 SHEET 1 OF 2


DESIGNED:	AJ	FED. PROJ. NO.	STATE	FEDERAL AID PROJECT NO.	HIGHWAY NO.
CHECKED:	SJD		TEXAS		FM 2097
DRAFTED:	JDS	DIST.	COUNTY	CONTROL SECTION	JOB SHEET NO.
CHECKED:	SJD	BMT	TYLER	2271 01	011 45



N. T. S.




N. T. S.



NOTES:  
 HORIZONTAL COORDINATES SHOWN ARE IN U.S. SURVEY FEET, AND ARE BASED UPON THE TEXAS COORDINATE SYSTEM OF NAD83 (2011) EPOCH 2010.00. TEXAS CENTRAL ZONE (4203), WITH A SURFACE ADJUSTMENT FACTOR OF 1.00012. VALUES WERE DERIVED UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

ELEVATIONS ARE BASED UPON NAVD 88 DATUM (GEOID 18) DERIVED FROM UTILIZING THE TXDOT STATE VIRTUAL REFERENCE STATION NETWORK IN SEPTEMBER, 2023. THREE, 3-MINUTE (180 EPOCH) OBSERVATIONS.

**LEGEND**

 3 1/4" ALUMINIUM DISK on 18"-5/8" DIAMETER REBAR

2290004

2290004: A 3-1/4-inch Aluminum Disk stamped "2290004" set on a 18" long 5/8" rebar. Being located at the southwest intersection of FM 1745/FM 2097 and US 287 in the Town of Chester, Tyler County, Texas. Being 31± feet northwest of the northwest pavement edge of FM 1745, 39± feet southeast of a power pole, and 34± feet southwest of a directional sign at the southwest intersection of FM 1745/FM 2097 and US 287.

US SURVEY FEET  
 DATA SET: SEPTEMBER 2023  
 MONUMENT: 3-1/4" ALUMINIUM DISK ON A 18" LONG 5/8" REBAR  
 SURFACE ADJUSTMENT FACTOR 1.00012  
 ELEVATIONS ARE NAVD 88 BASED UPON GEOID 18  
 TXDOT VRS NETWORK.

THE CONTROL POINTS SHOWN HEREIN WERE DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION.



  
 STEPHEN J. DIAL  
 RPLS NO. 6697

10/11/23  
 DATE

NO.	REVISION	BY	DATE

**CP&Y**  
 an STV Company  
 1820 REGAL ROW, SUITE 150  
 DALLAS, TEXAS 75235  
 PHONE NUMBER: 214-638-0500  
 TBPELS FIRM REGISTRATION NUMBER 10194115

©2023  Texas Department of Transportation

FM 2097  
**HORIZONTAL AND VERTICAL CONTROL SHEET**

CSJ 1584-01-013 SHEET 2 OF 2

DESIGNED:	AJ	FED. RD. DIV. NO.	STATE	FEDERAL AID PROJECT NO.	HIGHWAY NO.		
CHECKED:	SJD		TEXAS		FM 2097		
DRAFTED:	JDS	DIST.	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	SHEET NO.
CHECKED:	SJD	BMT	TYLER	1584	02	013	46



N. T. S.



N. T. S.

CK: DW: CK: DW:

# HORIZONTAL CURVE DATA

FM 1745 HORIZONTAL CURVES							**EXISTIT. SUPERELEVATION RATE, e
PC	PI	PT	DELTA	D	L	T	
28+74.29	33+69.22	28+88.45	19.446° RIGHT	1.984°	980.353	494.937	NO SUPERELEVATION
67+67.75	71+09.93	74+44.09	21.469° LEFT	3.174°	676.333	342.179	NO SUPERELEVATION
94+61.46	98+68.00	102+43.42	38.678° LEFT	4.946°	781.959	406.536	NO SUPERELEVATION
109+90.59	114+34.86	118+59.02	29.789° RIGHT	3.430°	868.419	444.293	NO SUPERELEVATION
120+39.40	121+90.21	123+40.10	11.016° LEFT	3.663°	300.236	150.814	NO SUPERELEVATION
131+97.74	134+11.40	136+21.96	16.762° RIGHT	3.951°	424.217	213.634	NO SUPERELEVATION
138+08.81	140+58.41	142+98.11	27.901° LEFT	5.702°	489.299	249.602	NO SUPERELEVATION


\*\*SUPERELEVATION RATES ARE APPROXIMATE AND SHOULD BE FIELD VERIFIED

# HORIZONTAL CURVE DATA

FM 2097 HORIZONTAL CURVES							**EXISTIT. SUPERELEVATION RATE, e
PC	PI	PT	DELTA	D	L	T	
146+60.82	147+23.70	147+85.86	14.972° LEFT	11.973°	125.533	62.881	NO SUPERELEVATION
147+86.73	148+39.32	148+91.19	16.201° LEFT	15.795°	104.469	52.599	NO SUPERELEVATION
154+04.54	154+70.96	155+37.37	1.986° LEFT	1.495°	132.836	66.425	NO SUPERELEVATION
155+37.37	157+49.75	159+61.51	7.536° LEFT	1.777°	424.133	212.373	NO SUPERELEVATION
174+28.70	177+74.12	181+12.67	19.765° RIGHT	2.890°	683.963	345.413	NO SUPERELEVATION
200+23.86	204+07.90	207+90.75	7.769° RIGHT	1.013°	766.886	384.032	NO SUPERELEVATION
211+36.05	216+78.39	221+92.71	31.821° RIGHT	3.011°	1056.663	542.344	NO SUPERELEVATION
228+57.84	233+98.19	239+10.39	31.947° RIGHT	3.035°	1052.545	540.345	NO SUPERELEVATION
250+04.03	256+62.46	262+37.30	49.690° LEFT	4.029°	1233.269	658.429	NO SUPERELEVATION
277+46.54	281+65.41	285+01.82	61.662° RIGHT	8.164°	755.271	418.867	
285+69.03	286+75.02	287+81.02	0.798° RIGHT	0.337°	211.99	105.997	NO SUPERELEVATION
299+01.23	301+82.32	304+59.49	16.533° RIGHT	2.961°	558.259	281.083	NO SUPERELEVATION
324+87.72	326+99.71	329+05.02	22.822° RIGHT	5.469°	417.309	211.458	NO SUPERELEVATION
330+51.85	335+06.90	339+20.60	42.119° LEFT	4.848°	868.751	455.054	NO SUPERELEVATION
344+54.79	345+28.48	346+01.63	11.998° LEFT	8.170°	146.848	73.694	NO SUPERELEVATION

\*\*SUPERELEVATION RATES ARE APPROXIMATE AND SHOULD BE FIELD VERIFIED

- NOTES:
- 1) NO SUBSTANTIAL CHANGES TO THE EXISTING HORIZONTAL OR VERTICAL ALIGNMENTS. THIS SHEET IS FOR CONTRACTOR INFORMATION ONLY.
  - 2) HORIZONTAL CURVE DATA GENERATED FROM DESIGN SOFTWARE USING TOPOGRAPHICAL SURVEY DATA.
  - 3) MATCH THE EXISTING ROADWAY SLOPE AS SHOW ON THE TYPICAL SECTIONS.




**FM 1745 ETC,  
CURVE DATA**

© TxDOT 2023			
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		47


DATE: 4/24/2024 10:46:07 AM  
 FILE: c:\tdot\pw\_onlinetx\tdot5\francisco.molinar\1159509\CURVE DATA PLACE HOLDER.dgn

DATE: 4/24/2024 11:31:20 AM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\159509\BL-CL-101 - FM 1745 ROADWAY LAYOUTS.dgn




- LEGEND**
- WS 6" WHITE PROFILE PAVEMENT MARKING
  - YD 6" DOUBLE YELLOW
  - YB 6" YELLOW BROKEN
  - YS 6" YELLOW SOLID
  - EOP EDGE OF PAVEMENT
  - ROW RIGHT OF WAY

- LEGEND**
- DRIVEWAY & INTERSECTION
  - MAILBOX TURNOUT
  - MAILBOX
  - METAL BEAM GUARD FENCE
  - CULVERT
  - SAFETY END TREATMENT



*Samantha Jo Harris* P.E.  
 04/29/2024





**FM 1745**  
**ROADWAY**  
**LAYOUT**

© TxDOT 2023 SHEET 1 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	48	




CK: DW: CK: DN:




**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT



*SJ Harris* P.E.  
 04/29/2024





**FM 1745**  
**ROADWAY LAYOUT**

© TxDOT 2023 SHEET 2 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	49	

DATE: 4/24/2024 12:01:12 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\191978\FM1745\_RL\_1 - Plan 5.dgn

DW: CK: DW: CK: DW: CK:




**LEGEND**


EOP EDGE OF PAVEMENT  
ROW RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT



*S. Harris* P.E.  
04/29/2024



FM 1745

ROADWAY LAYOUT

©TxDOT 2023 SHEET 3 OF 7




CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	50	

DATE: 4/24/2024 1:07:34 PM  
 FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molinar\191978\FM1745\_RL\_1 - Plan 7.dgn


CK: DW: CK: DW: CK: DW:

**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**  
 DRIVEWAY & INTERSECTION  
 MAILBOX TURNOUT  
 MAILBOX  
 METAL BEAM GUARD FENCE  
 CULVERT  
 SAFETY END TREATMENT



*[Signature]* P.E.  
 04/29/2024



Texas Department of Transportation

FM 1745

ROADWAY LAYOUT

©TxDOT 2023 SHEET 4 OF 7




CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	51	

DATE: 4/24/2024 1:13:54 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\191978\FM1745\_RL\_1 - Plan 9.dgn


CK:  
DW:  
CK:  
DN:

**LEGEND**  
EOP EDGE OF PAVEMENT  
ROW RIGHT OF WAY

**LEGEND**  
DRIVEWAY & INTERSECTION  
MAILBOX TURNOUT  
MAILBOX  
METAL BEAM GUARD FENCE  
CULVERT  
SAFETY END TREATMENT



*[Signature]* P.E.  
04/29/2024



FM 1745


ROADWAY LAYOUT

©TxDOT 2023 SHEET 5 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	52	

DATE: 4/24/2024 1:23:48 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\191978\FM1745\_RL\_1 - Plan 11.dgn


CK: DW: CK: DW:



**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT



STATE OF TEXAS  
 SAMANTHA JO HARRIS  
 134616  
 LICENSED PROFESSIONAL ENGINEER  
  
 P.E.  
 04/29/2024

0 50 100  
 SCALE IN FEET

Texas Department of Transportation

FM 1745


ROADWAY LAYOUT

©TxDOT 2023 SHEET 6 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	53	

DATE: 4/24/2024 1:37:18 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\191978\FM1745\_RL\_1 - Plan 13.dgn

CK: DW: CK: DW: CK: DW:




**LEGEND**


EOP EDGE OF PAVEMENT  
ROW RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT
- MILL TRANSITION



*S. Harris* P.E.  
04/29/2024



FM 1745

ROADWAY LAYOUT


©TxDOT 2023 SHEET 7 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	54	

DATE: 4/24/2024 1:41:59 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\01191978\FM1745\_RL\_1 - Plan 15.dgn

CK: DW: CK: DW:

DATE: 4/24/2024 2:01:24 PM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molinar\169043\146+11.168+00 - FM 2097 ROADWAY LAYOUT.dgn




**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY



**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT
- MILL TRANSITION

NOTES:  
 1. SEE TRANSITION DETAIL SHEET FOR DETAILS



*Samantha Jo Harris*  
 P.E.  
 04/29/2024





**FM 2097**  
**ROADWAY LAYOUT**

©TxDOT 2023 SHEET 1 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	55	


CK: DW: CK: DW:





**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT



*Samantha Jo Harris* P.E.  
 04/29/2024



**FM 2097**  
**ROADWAY LAYOUT**



© TXDOT 2023 SHEET 2 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST		COUNTY	SHEET NO.
BMT		TYLER	56

DATE: 4/24/2024 2:07:54 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinaro\169043\168+00 - 192+00 - FM 2097 ROADWAY LAYOUT-2.dgn




CK: DW: CK: DN:




**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**  
 DRIVEWAY & INTERSECTION  
 MAILBOX TURNOUT  
 MAILBOX  
 METAL BEAM GUARD FENCE  
 CULVERT  
 SAFETY END TREATMENT



*S. Harris* P.E.  
 04/29/2024




FM 2097  
 ROADWAY LAYOUT

©TxDOT 2023 SHEET 3 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	57	

DATE: 4/24/2024 2:16:25 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\169043192+00 - 216+00 - FM 2097 ROADWAY LAYOUT-4.dgn



CK: DW: CK: DW: CK: DW:




**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION (#)
- MAILBOX TURNOUT (#)
- MAILBOX (#)
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT



04/29/2024



Texas Department of Transportation

FM 2097

ROADWAY LAYOUT

©TxDOT 2023 SHEET 4 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	58	

DATE: 4/24/2024 2:25:00 PM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\011690431216+00 - 240+00 - FM 2097 ROADWAY LAYOUT-6.dgn

DW: CK: DW: CK: DW: CK:

**LEGEND**

EOP EDGE OF PAVEMENT

ROW RIGHT OF WAY

**LEGEND**

DRIVEWAY & INTERSECTION

MAILBOX TURNOUT

MAILBOX

METAL BEAM GUARD FENCE

CULVERT

SAFETY END TREATMENT

SAMANTHA JO HARRIS  
134616  
LICENSED PROFESSIONAL ENGINEER

*S. Harris* P.E.  
04/29/2024

0 50 100  
SCALE IN FEET



Texas Department of Transportation

**FM 2097**

**ROADWAY LAYOUT**

©TxDOT 2023 SHEET 5 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	59	




STA. 112+97  
EXIST. 24" RCP  
ADD 4:1 SETs EACH SIDE

DATE: 4/24/2024 2:38:46 PM  
 FILE: c:\txdot\pw\_onlinetx\dtd5\francisco.molinar\1690431240+00 - 264+00 FM 2097 ROADWAY LAYOUT-8.dgn

CK: DW: CK: DW:





**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY




**LEGEND**  
 DRIVEWAY & INTERSECTION  
 MAILBOX TURNOUT  
 MAILBOX  
 METAL BEAM GUARD FENCE  
 CULVERT  
 SAFETY END TREATMENT

DATE: 4/24/2024 2:43:44 PM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molinar\1690431264+00 - 288+00 - FM 2097 ROADWAY LAYOUT-10.dgn



*S. Harris* P.E.  
 04/29/2024



Texas Department of Transportation


**FM 2097**

**ROADWAY LAYOUT**

©TxDOT 2023 SHEET 6 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	60	




CK: DW: CK: DN:



**LEGEND**  
 EOP EDGE OF PAVEMENT  
 ROW RIGHT OF WAY

**LEGEND**  
 DRIVEWAY & INTERSECTION  
 MAILBOX TURNOUT  
 MAILBOX  
 METAL BEAM GUARD FENCE  
 CULVERT  
 SAFETY END TREATMENT

DATE: 4/24/2024 2:52:39 PM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\1690431288+00-312+00 - FM 2097 ROADWAY LAYOUT-12.dgn



*[Signature]* P.E.  
 04/29/2024



Texas Department of Transportation			
FM 2097			
ROADWAY LAYOUT			
©TxDOT 2023		SHEET 7 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	61	



DW: CK: DW: CK: DW: CK:

**LEGEND**

- EOP      EDGE OF PAVEMENT
- ROW      RIGHT OF WAY

**LEGEND**

- DRIVEWAY & INTERSECTION
- MAILBOX TURNOUT
- MAILBOX
- METAL BEAM GUARD FENCE
- CULVERT
- SAFETY END TREATMENT




**FM 2097**

**ROADWAY LAYOUT**

© TxDOT 2023 SHEET 8 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	62	







DATE: 4/24/2024 3:36:23 PM  
 FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molinar\1690431312+00-336+00-FM 2097 ROADWAY LAYOUT-14.dgn



CK:  
DW:  
CK:  
DW:

**LEGEND**


EOP EDGE OF PAVEMENT  
ROW RIGHT OF WAY


**LEGEND**

DRIVEWAY & INTERSECTION   
 MAILBOX TURNOUT   
 MAILBOX   
 METAL BEAM GUARD FENCE   
 CULVERT   
 SAFETY END TREATMENT 



*SJH* P.E.  
04/29/2024



 **Texas Department of Transportation**

**FM 2097**





**ROADWAY LAYOUT**

©TxDOT 2023 SHEET 9 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	63	

DATE: 4/24/2024 3:46:14 PM  
 FILE: c:\txdot\pw\_onlinetxdat5\francisco.molinar\1690431336+00-346+34 - FM 2097 ROADWAY LAYOUT-16.dgn

CK: DW: CK: DN:



*[Signature]* P.E.

04/29/2024

DATE: 4/24/2024 4:01:51 PM  
 FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molina\1044292\DrivewayDetails.dgn

**Texas Department of Transportation**

FM 1745 ETC.


DRIVEWAY & PUBLIC ROAD DETAILS

2023 SHEET 1 OF 1


CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	64	




CK  
DW  
CK  
DW




**INTERSECTING ROADWAY CLEARING**




**TYPICAL CLEARING SECTION**



**CURVED ROADWAY CLEARING**



**STUMP GRINDING DETAIL**




PE.  
04/29/2024



**NOTES:**

1. ALL TREE LIMBS EXTENDING INTO THE CLEARING LIMITS WILL BE REMOVED TO A MINIMUM HEIGHT OF SIXTEEN FEET (16') ABOVE THE ADJACENT PAVEMENT EDGE ELEVATION.
2. CLEARING OPERATIONS SHALL BE PERFORMED IN ACCORDANCE WITH ITEM 100, "PREPARING THE RIGHT OF WAY", EXCEPT THOSE SHOWN BY THESE DETAILS.
3. ALL STUMPS WITHIN THE CLEARING LIMITS SHALL BE REMOVED BY GRUBBING, EXCEPT IN AREAS NEAR UNDERGROUND UTILITIES.
4. WHERE CLEARING IS REQUIRED NEAR EXISTING UNDERGROUND UTILITIES, TREES AND STUMPS ARE NOT TO BE GRUBBED. FOR THOSE CONDITIONS, THE RIGHT OF WAY SHALL BE PREPARED BY CUTTING AND GRINDING OF STUMPS AND ROOTS AS DIRECTED.
5. ON AREAS TO BE COVERED BY AT LEAST THREE (3) FEET OF EMBANKMENT, TREES AND STUMPS MAY BE CUT OFF AS CLOSE TO NATURAL GROUND AS PRACTICABLE.
6. WHERE STEEP SLOPES MAKE GRINDING OPERATIONS IMPRACTICAL, AND THE ENGINEER AGREES IN WRITING, THE CONTRACTOR MAY CUT STUMPS OFF EVEN WITH THE GROUND.
7. AT ALL INTERSECTING ROADWAYS, CLEARING SHALL EXTEND TO THE RIGHT OF WAY LINE FOR 200'.



**TYPICAL CROSS-CULVERT DETAIL**







FM 1745, ETC.  
CLEARING DETAIL

© TxDOT		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	65	

DATE: 4/24/2024 4:09:58 PM  
FILE: c:\tdot\pw\_onlinetxdat5\francisco.molinard\1044292\CLEARING DETAIL.dgn

DW: CK: DW: CK: DW: CK:



*[Signature]* P.E.


04/29/2024

DATE: 4/29/2024 1:52:36 PM  
 FILE: c:\tdot\pw\_online\tdot5\samantha.harris\044292\TransitionDetail.dgn


<p>FM 1745, ETC.</p>			
<p>TRANSITION DETAIL</p>			
2024		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		66

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 5/1/2024 9:02:24 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044292\rs(2)-23.dgn




PROFILE VIEW  
OPTION 1




PROFILE VIEW  
OPTION 2




PROFILE VIEW  
OPTION 3



PROFILE VIEW  
OPTION 4




PLAN VIEW




PLAN VIEW

\* This distance may vary based on width of shoulder



PLAN VIEW

\* This distance may vary based on width of shoulder




PLAN VIEW

**CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)**

**CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)**


**CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)**

**CONTINUOUS MILLED DEPRESSIONS (Rumble Strips)**




PLAN VIEW  
OPTION 5

**RAISED EDGE LINE (Rumble Strips)**




PLAN VIEW  
OPTION 6

**PROFILE EDGE LINE MARKINGS (Rumble Strips)**



PLAN VIEW  
OPTION 7

**PREFORMED THERMOPLASTIC EDGE LINE (Rumble Strips)**



PLAN VIEW  
OPTION 8

**PREFORMED THERMOPLASTIC EDGE LINE (Rumble Strips)**

**GENERAL NOTES**

- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) and FPM(1) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings, and profile markings.
- See the Shoulder Width Table below for determining what options may be used for edge line rumble strips.
- Breaks in edge line rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections, or driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration or deceleration lanes, crossovers, gore areas, or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
- Consideration shall be given to bicyclists. See RS(6).

**WHEN INSTALLING MILLED DEPRESSION EDGE LINE RUMBLE STRIPS:**

- See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
- Pavement markings can be applied over milled shoulder rumble strips to create an edge line rumble strip.

**WHEN INSTALLING RAISED OR PROFILE EDGE LINE RUMBLE STRIPS:**

- Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edge line when used as a rumble strip. The color of the button should match the color of the adjacent edge line marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- The minimum distance between the edge line and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edge lines may substitute for buttons.



SHOULDER WIDTH TABLE		
EQUAL TO OR LESS THAN 2 FEET	GREATER THAN 2 FEET LESS THAN 4 FEET	EQUAL TO OR GREATER THAN 4 FEET
Option 1, 5, 6 or 8	Option 1, 2, 3, 5, 6 or 7	Option 2, 4, 5, 6 or 7

		<b>Texas Department of Transportation</b>		<b>Traffic Safety Division Standard</b>	
<b>EDGE LINE RUMBLE STRIPS ON UNDIVIDED OR TWO LANE HIGHWAYS RS(2)-23</b>					
FILE:	rs(2)-23.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	January 2023	CONTRACT:	1584	SECTION:	02
REVISIONS		JOB:	013,ETC.		HIGHWAY:
10-13	1-23	DIST:	COUNTY:	SHEET NO.	
		BMT:	TYLER	67	

DISCLAIMER:  
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 4:47:00 PM  
FILE: c:\t\dot\pw\_online\txdot5\francisco.m\linarc\1044292\rs(4)-23.dgn

## CENTERLINE RUMBLE STRIPS



TWO LANE TWO-WAY  
HIGHWAYS

MILLED CENTERLINE  
RUMBLE STRIPS

RAISED CENTERLINE  
RUMBLE STRIPS

PREFORMED THERMOPLASTIC  
RUMBLE STRIPS

PROFILE CENTERLINE MARKINGS  
AND PREFORMED THERMOPLASTIC  
RUMBLE STRIPS

### GENERAL NOTES

1. This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
2. Centerline and edge line rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections or driveways with high usage of large trucks.
6. Use standard sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings and profile markings.
7. Consideration should be given to noise levels when centerline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
8. Pavement markings must be applied over milled centerline rumble strips.

### WHEN INSTALLING CENTERLINE RUMBLE STRIPS:

9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
11. The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.
12. Consideration shall be given to bicyclists. See RS(6).


### WHEN INSTALLING EDGE LINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

13. See standard sheet RS(2).


		<b>Texas Department of Transportation</b>		<b>Traffic Safety Division Standard</b>	
<b>CENTERLINE RUMBLE STRIPS ON TWO LANE TWO-WAY HIGHWAYS RS(4)-23</b>					
FILE:	rs(4)-23.dgn	DN:	TxDOT	CK:	TxDOT
© TxDOT	January 2023	CONTRACT:	1584	SECT:	02
REVISIONS		JOB:	013.ETC.	HIGHWAY:	FM1745.ETC
10-13		DIST:	TYLER	COUNTY:	
1-23		BMT:		SHEET NO.:	68

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

### TYPE 1 - MULTIPLE



### TYPE 4 - MULTIPLE



### MAILBOX SIZES


MAILBOX SIZE	TYPICAL DIMENSIONS			MAX **
	LENGTH	WIDTH	HEIGHT	
SMALL	19 1/2"	6"	7"	6 LBS
MEDIUM	22 1/2" *	8" *	11 1/2" *	8 LBS
LARGE	23 1/2"	11 1/2"	13 1/2"	11 LBS
EXTRA LARGE	18"	14"	12"	13 LBS
LOCKABLE	18"	11 1/2"	15"	23 LBS

#### GENERAL NOTES:

- Dimensions shown (length, width, and height) are typical, not maximums. However, anytime a medium size mailbox is mounted on a single/double mount or on the outside position on a multi mount, the dimensions shown are maximums.
- Mailboxes shall be made of light weight sheet metal or light weight plastic. Heavy steel, cast iron or decorative mailboxes shall not be used on the state highway system.



\* See Note 1.  
 \*\* Excluding Molded Plastic on 4 X 4 Post

### TYPICAL INSTALLATION MEASUREMENTS




#### NOTE:


Mailbox installations in sidewalk areas shall be in accordance with the latest TxDOT Design Standard sheets PED-Pedestrian Facilities Curb Ramps.




### TYPE 2 and 4 - SINGLE/DOUBLE



### TYPE 3 - SINGLE/DOUBLE





### PLACEMENT OF EMERGENCY LOCATION NUMBER




#### NOTES:

- Location numbers are provided by homeowner. Minimum size 1" height.
- Location number is typically placed on the mailbox in a contrasting color.
- Black numbers may be placed on the Type 2 object marker if the numbers cannot be placed on the mailbox.
- Alternatively, a green or blue plate with white numbers attached may be mounted below the object marker. Other contrasting color configuration, as approved, may be used.
- See 3 of 4 for Foundation details.
- See 4 of 4 for Hardware details.



**NOTE:**  
 Double mailbox mounts are not allowed with a type 4 multiple mailbox installation

### TYPE 5



Maintenance Division Standard

## MAILBOX MOUNTING AND ASSEMBLY


### MB(1)-21

FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
2/2005	11/2009	4/2015		
6/2005	1/2011			
11/2006	7/2014			
DIST	COUNTY	SHEET NO.		
BMT	TYLER	69		


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 1 - MULTI LOCKABLE AND XL MAILBOX**



**TYPE 2/4 - SINGLE LOCKABLE MAILBOX**




**TYPE 2/4 - SINGLE XL MAILBOX**




**NOTE:**  
Follow same configuration when mounting an XL mailbox on a Type 4 multi post.


**TYPE 1 MULTI - LOCKABLE ARCHITECTURAL (LA)**



**TYPE 1 MULTI - XL MAILBOX**



**TYPE 3 - XL MAILBOX MOUNTING**



SHEET 2 OF 4

		Maintenance Division Standard	
<h2>XL AND LOCKABLE ARCHITECTURAL MAILBOX ASSEMBLY</h2> <h3>MB (2) - 21</h3>			
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT March 2004	CONT	SECT	JOB
REVISIONS	1584	02	013, ETC.
2/2005	11/2009	4/2015	FM1745, ETC
6/2005	1/2011		
11/2006	7/2014		
DIST	COUNTY	SHEET NO.	
BMT	TYLER	70	


DATE:  
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/24/2024 4:52:33 PM  
 FILE: c:\tomb\p\word\1\text\16\sc\mail\brca\mb044282\p\042752.dgn

### TYPE 1 - SUPPORT/FOUNDATION

Thin Wall Tube w/ V-LOC Anchorage




### TYPE 3 - SUPPORT/FOUNDATION




#### NOTES:

1. Attach Object Marker (OM) facing direction of traffic.
2. OM will also be required on opposite side if installed on a 2-Lane, 2-Way roadway.

### TYPE 5 - SUPPORT/FOUNDATION



### TYPE 6 - TEMPORARY MAILBOX SUPPORT




Plastic Drum NIGP: 55093383655  
 Rubber Collar NIGP: 55093387102

#### NOTES:

1. Place on approved plastic drum as shown in the Compliant Work Zone Traffic Control Devices (CWZTCD).
2. Existing attachment hardware shall be used unless damaged. Damaged hardware shall be replaced.


### TYPE 2 - SUPPORT/FOUNDATION

Thin Wall Steel Tube w/Wedge Anchor System



### TYPE 4 - SUPPORT/FOUNDATION

Whitecoated steel post NIGP: 45057561107  
 Multiple post NIGP: 45057257409  
 Recycled Rubber post (RR) NIGP: 45057561057



#### GENERAL NOTES:

1. Erect post plumb or vertical.
2. When galvanized part is required galvanize in accordance with Item 445.
3. Use a concrete footing as shown or when directed. Concrete footing will be required when soils do not hold the support/foundations in a stable condition, only on Type 1, Type 2, and Type 4

SHEET 3 OF 4



## MAILBOX SUPPORT AND FOUNDATION


MB (3) - 21

FILE: MB-21.dgn	DN:	CK:	DW:	CK:
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
2/2005	11/2009	4/2015	DIST	COUNTY
6/2005	1/2011		BMT	TYLER
11/2006	7/2014			SHEET NO. 71


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/24/2024 4:53:18 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044292\mb-21(1).dgn


TYPE	TYPE 1	TYPE 2	TYPE 3	TYPE 4	TYPE 5	TYPE 6
Configuration	Multiple	Single or Double	Single or Double	Single	Double	Multiple
Mailbox Size NIGP #	Outside Position: S or M Inside Position: S, M, L, XL, or LA	Single: S, M, L, XL, or LA Double: SS, SM, MM	Single: S, M, L, or XL Double: SS, SM, MM	S, M, L, XL, or LA	SS, SM, or MM	Outside Position: S or M Inside Position: S, M, L, or XL
Mailbox Post NIGP #	45057255254 (Galvanized Multiple)	45057561404 (Thin Walled Govanize)	57044325108 (Wing Channel Post)	45057561107 (Thin walled white powder coated) 45057561057 (Recycled Rubber Post: S or M only)	45057561107 (Thin Walled White Powder Coated)	45057257409 (White Powder Coated Multiple)
Post and Mailbox Hardware NIGP #	45057259009 (Wedge) 45057256500 (V-Wing Socket) 45057253002 (Bracket Extension) 45057252251 (Mailbox Bracket) 45057258001 (Part A Angle Bracket x2) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	80130598701 (Wedge) 80130238407 (Wedge Anchor) 45057253002 (Bracket Extension) 45057252343 (Double MB Bracket) 45057252350 (S. Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	45057541653 (Type 3 Double Mailbox Bracket) 45057252251 (Mailbox Bracket) 45057253002 (Bracket Extension) 45057258001 (Part A Angle Bracket) 45057258027 (Part B Angle Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057252350 (Single Mailbox Bracket) 45057253002 (Bracket Extension) 45057250255 (Plate Washer for XL/LA x2) 45057250263 (L-Bracket for XL x4)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252343 (Double Mount Bracket) 45057252251 (Mailbox Bracket x2)	55083571053 (Wedge) 55083571004 (Socket) 45057253002 (Bracket Extension) 45057252350 (Single Mount Bracket) 45057250255 (Plate Washer for XL x2) 45057250263 (L-Bracket for XL x4)
Foundation Used	Class B Concrete (Required for LA Mailboxes)	Class B Concrete (Required for LA Mailboxes)	None	Class B Concrete (not used with recycled rubber post, required for LA Mailboxes)	Class B Concrete (not required)	Class B Concrete




NIGP: 45057250263  
L-Bracket x4 for XL sized mailboxes




NIGP: 45057252343  
Double Mailbox Bracket For Type 2 and Type 4 double mount




NIGP: 45057252350  
Single Mailbox Bracket For Type 2 single and for Type 4 single and multi mount




NIGP: 45057258001  
Part "A" Angle Bracket For Type 1 multi (2 per mailbox) and Type 3 single and double




NIGP: 45057251055  
Type 6 Angle Bracket (2 per mailbox)




NIGP: 45057252251  
Mailbox Bracket For Type 1 multi and any double mount (use 2)




NIGP: 45057253002  
Bracket Extension Use 1 for a medium Mailbox Use 2 for a Large Mailbox




NIGP: 45057258027  
Part "B" Angle Bracket For Type 3 single and double




NIGP: 80130598701  
Wedge for Type 2




NIGP: 45057250255  
Plate Washer for Architecural and XL Mailboxes




NIGP: 45057541653  
Type 3 double mailbox bracket




NIGP: 55083571053  
Type 4 Mailbox Wedge




NIGP: 55083571004  
Type 4 Mailbox Socket



NIGP: 80130238407  
Type 2 Wedge Anchor



NIGP: 45057259009  
Wedge for Type 1 V-wing Socket




NIGP: 45057256500  
V-wing Socket for Type 1 Foundation

NIGP #	OBJECT MARKERS AND CONFORMABLE SHEETING
55008311759	Type 2 OM 4"x4" (3 Needed) for Type 3 Wing Channel Post
55008312906	Type 2 OM 6"x12" (1 needed) for Type 3 Wing Channel Post
80149872006	12" Conformable Reflective Yellow Sheeting for Flexible Posts


**NOTES:**

- Type 2 object marker in accordance with Traffic Engineering Standard Delineators & Object Markers.
- A light weight receptacle for newspaper delivery can be attached to mailbox posts if the receptacle does not touch the mailbox, present a hazard to traffic or delivery of the mail, extend beyond the front of the mailbox, or display advertising, except the publication title.

**BID CODES FOR CONTRACTS**




SHEET 4 OF 4

 Texas Department of Transportation				Maintenance Division Standard	
<h2>NIGP PARTS LIST AND COMPATIBILITY</h2> <h3>MB(4)-21</h3>					
FILE: MB-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT March 2004	CONT	SECT	JOB	HIGHWAY	
2/2005	11/2009	4/2015	1584 02	013, ETC. FM1745, ETC	
6/2005	1/2011		DIST	COUNTY	SHEET NO.
11/2006	7/2014		BMT	TYLER	72



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 7:18:04 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.mollinar\1044292\mbp-22.dgn



CASE 1. OFF TRAVEL WAY DELIVERY


CASE 2. BACK SIDE DELIVERY

CASE 3. DELIVERY NEAR RIGHT OF WAY LINE



**GENERAL NOTES:**

1. CASE 1 IS THE MOST COMMON METHOD.
2. TURN OUT BEHIND MAILBOX FOR CASE 2 WILL NORMALLY BE ALLOWED FOR NATURAL TERRAIN THAT WILL SERVE AS AN ALL WEATHER SURFACE.
3. ALL WEATHER DRIVEWAYS FOR CASE 3 MAILBOXES LOCATED AT THE RIGHT OF WAY LINE SHOULD NORMALLY BE PLACED IN CONJUNCTION WITH COUNTY ROADS OR OTHER CONNECTING COMMUNITY ROADS OR STREETS. WHEN 3 OR MORE MULTI-RACKS ARE ANTICIPATED, THE USE OF AN NDCBU IS RECOMMENDED. ONLY RURAL PATRONS LOCATED ON STATE MAINTAINED HIGHWAYS MAY HAVE A MAILBOX OR NDCBU SLOT ON TxDOT RIGHT OF WAY.



TYPICAL SECTION CASE 1

SHEET 1 OF 2



*Guideline*  
**MAILBOX SIDE ROAD PLACEMENT AND TURNOUTS**

**MBP(1)-22**

FILE: MBP-22.DGN	DN: VS	CK:	DW: VS	CK:
© TxDOT OCTOBER 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
12/2012	DIST	COUNTY	SHEET NO.	
5/2014	BMT	TYLER		73


\* NDCBU MAY BE INSTALLED ON COUNTY ROAD ROW WITH APPROVAL OF COUNTY.

↑ MAIL DELIVERY VEHICLE TRAVEL DIRECTION


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 7/25/2024 7:19:23 AM  
 FILE: \\pw\_online\txdot\francis\moinor\1044292\mbp-22.dgn


**MAILBOX PLACEMENT AT RURAL LOCATIONS**  
 THROUGH HIGHWAY SPEEDS  
 LESS THAN 55 MPH



**MAILBOX PLACEMENT AT RURAL LOCATIONS**  
 THROUGH HIGHWAY SPEEDS  
 GREATER THAN OR EQUAL TO 55 MPH



**CURB AND GUTTER MAILBOX INSTALLATION**



- NOTES:
1. A NON-TRAVERSABLE SURFACE MUST BE INSTALLED NEAR THE MAILBOX (NATURAL VEGETATION OR OTHER) IN THE BUFFER ZONE. ALTERNATIVELY, A BASE WITH A MINIMUM HEIGHT OF 2.5 INCHES MAY BE INSTALLED SO THAT THE EDGE OF THE MAILBOX DOES NOT EXTEND OUT MORE THAN 4 INCHES HORIZONTALLY BEYOND THE BASE.
  2. THE SIDEWALK WIDTH MAY BE REDUCED TO 4 FOOT FOR SHORT DISTANCES AROUND THE MAILBOX IF NEEDED.
  3. MAINTAIN A MINIMUM OF 5 FEET BETWEEN OBSTRUCTIONS IN THE PEDESTRIAN ACCESS ROUTE.

SHEET 2 OF 2




**MAILBOX PLACEMENT  
 CURBS & INTERSECTIONS**

**MBP(2)-22**

FILE: MBP-22.DGN	DN: VS	CK:	DW: VS	CK:
© TxDOT OCTOBER 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
12/2012	DIST	COUNTY	SHEET NO.	
5/2014	BMT	TYLER	74	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinard\1044292\tehmact1.dgn



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS


**CONDITION - 1**  
 THIN HMAC SURFACES OR HMAC OVERLAY  
 WITH THICKNESS OF 2.5" OR LESS



\*\* EXISTING ROADSIDE EMBANKMENT TO BE GRADED TO PRODUCE A SMOOTH LEVEL SURFACE FOR PLACEMENT OF TAPERED EDGE. THIS WORK IS SUBSIDIARY TO THE VARIOUS BID ITEMS.


\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 2**  
 OVERLAY OF EXISTING PAVEMENT  
 HMAC THICKNESS 2.5" TO 5"



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 3**  
 NEW OR RECONSTRUCTED PAVEMENT  
 HMAC THICKNESS 2.5" TO 5"



\*\*\* SEE TYPICAL SECTION FOR ROADSIDE DETAILS

**CONDITION - 4**  
 NEW OR RECONSTRUCTED PAVEMENT  
 HMAC THICKNESS 5" OR GREATER

**GENERAL NOTES**


- UNLESS OTHERWISE SHOWN IN THE PLANS, A VERTICAL EDGE IS PERMISSIBLE FOR HMAC PLACED GREATER THAN 5" BELOW THE EDGE OF PAVEMENT AND FOR THICKNESS OF HMAC LESS THAN 2.5".
- FOR FURTHER INFORMATION REGARDING THE ROADSIDE AND PAVEMENT DETAILS, SEE TYPICAL SECTIONS.
- PAYMENT FOR TAPERED EDGE WILL BE IN ACCORDANCE WITH APPLICABLE ITEMS IN THE CONTRACT.
- THE SLOPE OF THE TAPERED EDGE SHALL BE 1.75H:1V OR FLATTER.
- THE TAPERED EDGE SHALL BE PRODUCED BY USE OF A SCREED ATTACHMENT CAPABLE OF PRODUCING A SMOOTH COMPACTED SURFACE. ADDITIONAL COMPACTING EFFORT BEHIND THE SCREED IS NOT REQUIRED.

(NOT TO SCALE)


					Design Division Standard
<b>TAPERED EDGE DETAILS          HMAC PAVEMENT</b>					
<b>TE (HMAC) - 11</b>					
FILE: tehmact1.dgn	DN: TxDOT	CK: RL	DW: KB	CK:	
© TxDOT January 2011	CONT	SECT	JOB	HIGHWAY	
REVISIONS		1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY			SHEET NO.	
BMT	TYLER			75	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 7:32:51 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.molinar\d1044294\psetrcss-20.dgn




**PLAN VIEW**  
 (Showing spigot end connection.)




**LONGITUDINAL ELEVATION**  
 (Showing spigot end connection.)




**END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS**  
 (If required)



**INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS**  
 (If required)




**OPTION A**




**OPTION B**

**DETAIL A**



**SECTION A-A**



**MULTIPLE PIPE INSTALLATION**

**MAX SAFETY PIPE RUNNER LENGTHS AND REQUIRED SAFETY PIPE RUNNER SIZES**

Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"

- Slope as shown elsewhere in the plans. Slope of 3:1 or flatter is required for vehicle safety.
- Provide cement stabilized bedding and backfill in accordance with the Item, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap be considered subsidiary to the Item "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.

**REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS**

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. / ft. of pipe)	Slope	Minimum Length of Unit	Single Pipe		Multiple Pipe	
							Skew	Pipe Runners Required	Skew	Pipe Runners Required
12"	2"	16"	16"	0.07 Circ.	3:1	2' - 0"	≤ 45°	No	≤ 45°	No
						2' - 8"				
						4' - 0"				
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	3:1	2' - 10"	≤ 45°	No	≤ 45°	No
						3' - 9"				
						5' - 8"				
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	3:1	3' - 8"	≤ 45°	No	≤ 45°	No
						4' - 10"				
						7' - 3"				
24"	3"	30"	27"	0.07 Circ.	3:1	5' - 3"	≤ 45°	No	≤ 30°	No
						4' - 10"			> 30°	Yes
						10' - 6"				
30"	3 1/2"	37"	31"	0.18 Circ.	3:1	6' - 3"	≤ 15°	No	≤ 15°	No
						8' - 2"			> 15°	Yes
						12' - 1"				
36"	4"	44"	36"	0.19 Ellip.	3:1	7' - 10"	= 0°	No	≥ 0°	No
						10' - 4"			> 0°	Yes
						15' - 4"				
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	3:1	9' - 6"	≥ 0°	Yes	≥ 0°	Yes
						12' - 6"				
						18' - 7"				

**MATERIAL NOTES:**


Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
 Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**

Precast safety end treatment for reinforced concrete pipe (CRP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".  
 When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.  
 Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.  
 Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.  
 Methods of lifting shall be provided by the manufacturer for ease of loading, unloading, and installation.  
 Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.


				<b>Bridge Division Standard</b>	
<b>PRECAST SAFETY END TREATMENT</b> <b>TYPE II ~ CROSS DRAINAGE</b> <b>PSET-RC</b>					
FILE:	psetrcss-20.dgn	DN:	RLW	CK:	KLR
DESIGNER:	February 2020	SECT:		JOB:	013, ETC.
REVISIONS:		CONTRACT NO.:	1584 02	COUNTY:	TYLER
		SHEET NO.:			76

DATE: 4/25/2024 8:34:47 AM  
 FILE: c:\txdot\pw\_online\francisco.molinar\1044294.psetrpss-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**PLAN VIEW - 12" THRU 24"**

(Showing spigot end connection.)




**LONGITUDINAL ELEVATION - 12" THRU 24"**

(Showing spigot end connection.)




**SECTION A-A**




**MULTIPLE PIPE INSTALLATION**

- ① Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- ② Provide cement stabilized bedding and backfill in accordance with the Item, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- ③ Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- ④ Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- ⑤ Safety pipe runners are required for multiple pipe culverts with more than two pipes.




**INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS**

(If required)



**OPTION A**



**OPTION B**

**END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS**

(If required)

**REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS**

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. per ft. of Pipe)	Max Slope	Min Length of Unit	Pipe Runner Requirements		Required Pipe Runner Sizes		
							Single Pipe	Multiple Pipe	Nominal Dia	O.D.	I.D.
12"	2"	16"	16"	0.07 Circ.	6:1	4' - 0"	No	⑤	3" STD	3.500"	3.068"
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	6:1	5' - 8"	No	⑤	3" STD	3.500"	3.068"
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	6:1	7' - 3"	No	⑤	3" STD	3.500"	3.068"
24"	3"	30"	27"	0.07 Circ.	6:1	10' - 6"	No	⑤	3" STD	3.500"	3.068"
30"	3 1/2"	37"	31"	0.18 Circ.	6:1	12' - 1"	No	Yes	4" STD	4.500"	4.026"
36"	4"	44"	36"	0.19 Ellip.	6:1	15' - 4"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	6:1	18' - 7"	Yes	Yes	4" STD	4.500"	4.026"

**MATERIAL NOTES:**

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
 Galvanize steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**

Precast safety end treatment for reinforced concrete pipe (RCP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".  
 When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.  
 Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.  
 Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.  
 Methods of lifting shall be provided by the manufacturer for ease of loading, unloading and installation.  
 Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.

Texas Department of Transportation  
Bridge Division Standard

PRECAST SAFETY END TREATMENT  
 TYPE II ~ PARALLEL DRAINAGE  
 PSET-RP


FILE: psetrpss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.	
BMT	TYLER		77	

## REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness (8)	"D" (1)	Slope	Min Length of Unit	Single Pipe		Multiple Pipes	
						Skew	Pipe Runners Required	Skew	Pipe Runners Required
12"	2"	1.15"	17.00"	3:1	2' - 11"	≤ 45°	No	≤ 45°	No
				4:1	3' - 6"				
				6:1	4' - 9"				
15"	2 1/4"	1.30"	20.50"	3:1	3' - 8"	≤ 45°	No	≤ 45°	No
				4:1	4' - 7"				
				6:1	6' - 5"				
18"	2 1/2"	1.60"	24.00"	3:1	4' - 6"	≤ 45°	No	≤ 45°	No
				4:1	5' - 8"				
				6:1	8' - 0"				
24"	3"	1.95"	31.00"	3:1	6' - 2"	≤ 45°	No	= 30°	No
				4:1	7' - 10"				
				6:1	11' - 3"				
30"	3 1/2"	2.65"	38.50"	3:1	7' - 10"	= 15°	No	= 15°	No
				4:1	10' - 1"				
				6:1	14' - 8"				
36"	4"	2.75"	45.50"	3:1	9' - 5"	= 0°	No	≥ 0°	Yes
				4:1	12' - 3"				
				6:1	17' - 11"				
42"	4 1/2"	2.7"	52.50"	3:1	11' - 1"	≥ 0°	Yes	≥ 0°	Yes
				4:1	14' - 5"				
				6:1	21' - 2"				


## SAFETY PIPE RUNNER DIMENSIONS

Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"



### PLAN

(Showing bell end connection.)



### LONGITUDINAL ELEVATION

(Showing bell end connection.)

- 1 Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- 2 Slope as shown elsewhere in plans. Slope of 3:1 or flatter is required for vehicle safety.
- 3 Toewall to be used only when dimension is shown elsewhere in the plans.
- 4 Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- 5 Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- 6 Measured along slope.
- 7 Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- 8 Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

#### GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".

When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.

Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:

A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).

B. For precast (steel formed) sections, provide Class "C" concrete (f<sub>c</sub> = 3,600 psi).

At the option and expense of the Contractor, the next larger size of safety end treatment may be furnished as long as the "D" dimension cast is that of the required size of pipe.


Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.

Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.

Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.


Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464 "Reinforced Concrete Pipe". Connect TP by grouting. See Pipe and Box Grouted Connections (PBGC) standard for grouted connections with TP and precast safety end treatment.

DATE: 4/25/2024 8:41:10 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.molinar\1044294\psetscs-21.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




### END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS

(If required)




### OPTIONAL JOINT FOR RCP

(Showing joint between RCP and precast safety end treatment)




### OPTION A      DETAIL A      OPTION B

(If required)




### MULTIPLE PIPE INSTALLATION




### OPTION WITH SQUARE BOTTOM

### SECTION A-A



### OPTION WITH INVERT BOTTOM



### INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS

(If required)

Bridge Division Standard

## PRECAST SAFETY END TREATMENT


### TYPE II ~ CROSS DRAINAGE

### PSET-SC

FILE: psetscs-21.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS 12-21: Added 42" TP	1584 02	013, ETC.	FM1745, ETC	
DIST	COUNTY	SHEET NO.		
BMT	TYLER	78		


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 8:59:40 AM  
 FILE: c:\t\dot\pw\_online\t\dot5\francisco.molinar\d1044294\psetspss-21.dgn




**PLAN**

(Showing bell end connection.)




**LONGITUDINAL ELEVATION**

(Showing bell end connection.)




**INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS**

(If required)




**OPTION A**




**OPTION B**

**END DETAILS FOR INSTALLATION OF SAFETY PIPE RUNNERS**

(If required)




**MULTIPLE PIPE INSTALLATION**




**OPTION WITH SQUARE BOTTOM**

**SECTION A-A**



**OPTION WITH INVERT BOTTOM**



**OPTIONAL JOINT FOR RCP**

(Showing joint between RCP and precast safety end treatment.)

**REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS**

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness	"D"	Slope	Min Length	Pipe Runners Required		Required Pipe Runner Size		
						Single Pipe	Multiple Pipe	Nominal Dia.	O.D.	I.D.
12"	2"	1.15"	17.00"	6:1	4' - 9"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
15"	2 1/4"	1.30"	20.50"	6:1	6' - 5"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
18"	2 1/2"	1.60"	24.00"	6:1	8' - 0"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
24"	3"	1.95"	31.00"	6:1	11' - 3"	No	Yes, for > 2 pipes	3" STD	3.500"	3.068"
30"	3 1/2"	2.65"	38.50"	6:1	14' - 8"	No	Yes	4" STD	4.500"	4.026"
36"	4"	2.75"	45.50"	6:1	17' - 11"	Yes	Yes	4" STD	4.500"	4.026"
42"	4 1/2"	2.7"	52.50"	6:1	21' - 2"	Yes	Yes	4" STD	4.500"	4.026"

- Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- Slope as shown elsewhere in the plans. Slope of 6:1 or flatter is required for vehicle safety.
- Toewall to be used only when dimension is shown elsewhere in the plans.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

**GENERAL NOTES:**

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".  
 When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.  
 Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:  
 A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).  
 B. For precast (steel formed) sections, provide Class "C" concrete (f'c = 3,600 psi).  
 At the option and expense of the Contractor the next larger size of safety end treatment may be furnished; as long as the "D" dimension cast is that of the required size of pipe.  
 Pipe runners are designed for a traversing load of 10,000 Lbs at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981.  
 Provide pipe runners meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.  
 Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.  
 Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464, "Reinforced Concrete Pipe". Connect TP by grouting. See Pipe and Box Grouted Connections (PBGC) standard for grouted connections with TP and precast safety end treatment.

**Bridge Division Standard**


**PRECAST SAFETY END TREATMENT**  
**TYPE II ~ PARALLEL DRAINAGE**

**PSET-SP**


FILE: psetspss-21.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
12-21: Added 42" TP	DIST	COUNTY	SHEET NO.	
	BMT	TYLER	79	

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY)



Nominal Culvert (Pipe) I.D.	PSET-SC and PSET-SP Standards					PSET-RC and PSET-RP Standards		
	Unit Width "W"	Side Slope			Unit Width "W"	Side Slope		
		3:1	4:1	6:1		3:1	4:1	6:1
12"	23.0"	0.1	0.2	0.2	16.0"	0.1	0.1	0.2
15"	26.5"	0.2	0.2	0.3	19.5"	0.1	0.2	0.2
18"	30.0"	0.2	0.2	0.3	23.0"	0.2	0.2	0.3
24"	37.0"	0.3	0.3	0.5	30.0"	0.2	0.3	0.4
30"	44.5"	0.3	0.4	0.6	37.0"	0.3	0.3	0.5
36"	51.5"	0.4	0.5	0.7	44.0"	0.3	0.4	0.6
42"	58.5"	0.5	0.6	0.8	51.0"	0.4	0.5	0.7




PLAN



LONGITUDINAL ELEVATION



MULTIPLE PIPE INSTALLATION



SINGLE PIPE INSTALLATION

SECTION A-A

- (1) Riprap placed beyond the limits shown will be paid as concrete riprap in accordance with Item 432, "Riprap". When riprap is cast integrally with the precast safety end treatment, this dimension is 1'-0" minimum.
- (2) 1#2" Dia ASTM A307 Gr A threaded anchor rod with 2 nuts and 2 washers. Galvanize all components in accordance with Item 445, "Galvanizing". Repair galvanizing that is damaged during transport or construction in accordance with the specifications.
- (3) 3/4" through holes in walls of safety end treatment for riprap anchor rods may be drilled with rotary (coring or masonry) type drilling equipment or may be formed. Do not use percussive (star) type drilling equipment. If holes are drilled, patch spalls in the inside face of the wall exceeding 1#2" from the holes.
- (4) Provide riprap toe wall when dimension is shown elsewhere in the plans or when field conditions require a toe wall.
- (5) Quantities shown are for one end of one reinforced concrete pipe culvert. For multiple pipe culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only. Quantities are based on the minimum unit lengths shown on the Precast Safety End Treatment (SET) standard sheets.

MATERIAL NOTES:

Provide Class "B" riprap in accordance with Item 432, "Riprap". Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. The anchor rods shown are always required.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment". Refer to PSET-SC or PSET-SP standard sheets for details of square safety end treatments not shown. Refer to PSET-RC or PSET-RP standard sheets for details of round safety end treatments not shown. For precast units with integrally cast riprap, substitute reinforcing steel in the amount on 0.26 in./ft. minimum for the threaded anchor rods shown. When requested, submit sealed engineering drawings for approval prior to construction. Shop drawings will not be required. Note that a proprietary precast unit with integral riprap is available from L&R Precast Concrete Works, Inc. (956) 583-6293 or www.lrpccast.com. Payment for riprap and toewalls is included in the price bid for each safety end treatment.

These riprap details are only applicable when notes that require placement of riprap with precast safety end treatments are shown elsewhere in the plans.  
 Precast units with integrally cast riprap are permitted unless noted otherwise on the plans.

DATE: 4/25/2024 9:02:33 AM  
 FILE: c:\t\dot\pw\_online\txdot5\francisco.m\linar\1044294\psetrr-se-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

		Bridge Division Standard	
<b>PRECAST SAFETY END TREATMENT TYPE II RIPRAP DETAILS</b> PSET-RR			
FILE: psetrrse-20.dgn	DN: GAF	CK: TxDOT	DW: JRP
©TxDOT February 2020	CON: 1584	SECT: 02	JOB: 013, ETC.
REVISIONS	COUNTY: TYLER		HIGHWAY: FM1745, ETC SHEET NO.: 80



DATE: 4/25/2024 9:07:25 AM  
 FILE: c:\t\dot\p\_w\_online\francis.sco.molinar\1189494\p\_wstde01-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TABLE OF DIMENSIONS AND REINFORCING STEEL**  
(Wings for one structure end)




Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings)		Estimated Quantities per ft of Toewall (1-toewall)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

**TABLE OF WINGWALL REINFORCING**  
(2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

**TABLE OF TOEWALL REINFORCING**

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



**WING DIMENSION FORMULAS:**  
(All values are in feet.)

Hw = H + T + C  
 Lw = (Hw) (SL) + cosine (θ) for Type PW-1  
 = (Hw - 1') (SL) + cosine (θ) for Type PW-2 and Hw 4'  
 = (Hw - 0.5') (SL) + cosine (θ) for Type PW-2 and Hw 4'








For cast-in-place culverts:  
 Ltw = [(N) (S) + (N + 1) (U)] + cosine (θ)

For precast culverts:  
 Ltw = [(N) (2U + S) + (N - 1) (0.5')] + cosine (θ)  
 Total Wingwall Area (two wings ~ SF)  
 = (2)(Hw)(Lw) for Type PW-1  
 = (2)(Hw)(Lw) - 6 SF for Type PW-2 and Hw 4'  
 = (2)(Hw)(Lw) - 1.5 SF for Type PW-2 and Hw 4'

Hw = Height of wingwall  
 Lw = Length of wingwall  
 Ltw = Culvert toewall length  
 N = Number of culvert spans  
 SL:1 = Channel slope ratio. (horizontal: 1 vertical, usual value is 2:1)  
 θ = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.

- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"  
For 30° skew ~ 2"  
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above finished grade.
  - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.



**DESIGNER NOTES:**  
 Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall. Type PW-2 can only be used for applications without a railing mounted to the wingwall.

**MATERIAL NOTES:**  
 Provide Class C concrete (f'c=3,600 psi).  
 Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.

**GENERAL NOTES:**  
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.  
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.  
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information. Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.

**Bridge Division Standard**



**CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2**

**PW**

FILE: pwstde01-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
	1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.	
BMT	TYLER		81	

DATE: 4/25/2024 9:12:50 AM  
 FILE: c:\t\dot\p\_w\_online\t\dot5\francisco.molinar\1044294\setbcdse-20.dgn

DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**WING DIMENSION CALCULATIONS:**

$$Hw = H + T + C - 0.25'$$

$$Lw = (Hw - 0.333') (SL)$$

For cast-in-place culverts:  
 $Atw = (N) (S) + (N + 1) (U)$

For precast culverts:  
 $Atw = (N) (2U + S) + (N - 1) (0.500')$

Total Wingwall Area (SF)  
 $= (0.5) (Hw + 0.333') (Lw) (N + 1)$

Total Concrete Volume (CY)  
 $= [(Wingwall Area) (0.583') + (Lw) (Atw) (0.583') + (Atw) (1.167') (1.167' - 0.583')] + (27)$

---

**PIPE RUNNER DIMENSION CALCULATIONS:**

Pipe Runner Length  
 $= (Lw) (K1) (1.917')$

Total Reinforcing (Lb)  
 $= (1.55) (Lw) (Atw) + (4.43) (Atw) + (K2) (Hw) (N + 1) (Lw) \sqrt{\quad}$

C = Height of curb above top of top slab (feet)  
 Hw = Height of wingwall (feet)  
 K = Constant value for use in formulas  
 Slope SL: 1 K1 K2  
 3:1 ~ 1.054 ~ 7.45  
 4:1 ~ 1.031 ~ 8.49  
 6:1 ~ 1.014 ~ 10.30

Atw = Anchor toewall length (feet)  
 Lw = Length of wingwall (feet)  
 N = Number of culvert barrels  
 SL:1 = Side slope ratio (horizontal : 1 vertical)

See applicable box culvert standard for H, S, T, and U values.






**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
 Provide galvanized reinforcing steel if required elsewhere in the plans.  
 Adjust reinforcing as necessary to provide a minimum clear cover of 1 1/2".  
 Provide Class "C" concrete (f'c = 3,600 psi).  
 Provide pipe runners, cross pipes, and anchor pipes meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
 Provide ASTM A307 bolts.  
 Galvanize all steel components, except the concrete reinforcing, unless required elsewhere in the plans, after fabrication.  
 Repair galvanizing damaged during transport or construction in accordance with the Item 445, "Galvanizing".

**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications.  
 The safety end treatments shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.  
 Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.  
 The quantities for pipe runners, reinforcing steel, and concrete resulting from the formulas given herein are for Contractor's information only.  
 See the Box Culvert Supplement (BCS) standard sheet for additional dimensions and information.  
 Alternate design drawings bearing the seal of a professional engineer will be acceptable for precast construction of the safety end treatments.

Cover dimensions are clear dimensions, unless noted otherwise.  
 Reinforcing dimensions are out-to-out of bars.




**PLAN VIEWS OF CORNER DETAILS**

- Recommended values of slope are: 3:1, 4:1, and 6:1. Provide 3:1 or flatter slope.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures without railing and curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet.
- Wingwall and slab thicknesses may be the same as the adjacent culvert wall and slab thicknesses (7" minimum). If thicknesses greater than the minimum (7") are used, no changes will be made in quantities and no additional compensation will be allowed.
- For vehicle safety, reduce curb height, if necessary, to provide a maximum 3" projection. No changes will be made in quantities and no additional compensation will be allowed for this work.
- For culverts with C = 0", the precast culvert reinforcing may extend 1'-0" minimum into wingwall. Wingwall Bars D and R may be omitted. Otherwise, refer to the Wingwall Connection detail on the Box Culvert Precast Miscellaneous Details (SCP-MD) standard sheet.

**TABLE OF REINFORCING BAR SIZES AND SPACING**

Bar	Size	Spacing
C	#4	10' Max
D	#4	Match F and E
E	#4	1'-0" Max
F	#4	1'-3" Max
G	#6	As shown
J	#4	10' Max
K	#4	1'-0" Max
R	#4	As shown



Texas Department of Transportation  
 Bridge Division Standard


**SAFETY END TREATMENT FOR 0° SKEW BOX CULVERTS (MAXIMUM Hw = 7'-0") TYPE I ~ CROSS DRAINAGE**

**SETB-CD**

FILE: setbcdse-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.	
BMT	TYLER		82	


DATE: 4/25/2024 9:14:31 AM  
 FILE: c:\t\dot\pw\_online\francisco.molinar\104294\set+bcdae-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- ⑥ Cross pipe is the same size as the pipe runner. Cross pipe stub out is the same size as the anchor pipe.
- ⑦ Note that actual slope of safety pipe runner may vary slightly from side slope.
- ⑧ Take care to ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1#2" hole to ensure that the lap of the safety pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.




NOTE: At Contractor's option, make the cross pipe continuous across the inside wingwalls. If option is selected, omit the sleeve pipe and make a 3" diameter through hole in the cross pipe to accept the anchor bolt at the centerline of each inside wingwall.

**CROSS PIPE INSTALLATION DETAILS**




OPTION A2  
FOR USE IN OUTSIDE CULVERT BAY




OPTION A2  
FOR USE IN INSIDE CULVERT BAY

**CROSS PIPE AND CONNECTIONS DETAILS**




**BOTTOM ANCHOR PIPE DETAILS**




OPTION B1  
OPTION B2  
**BOTTOM ANCHOR TOEWALL DETAILS**

(Wingwall not shown for clarity.)



**CROSS PIPE SLEEVE PIPE DETAILS**




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

**PIPE RUNNER DETAILS**

**MAXIMUM PIPE RUNNER LENGTHS AND REQUIRED PIPE RUNNER AND ANCHOR PIPE SIZES**

Maximum Pipe Runner Length	Required Pipe Runner Size			Required Anchor Pipe Size		
	Pipe Size	Pipe O.D.	Pipe I.D.	Pipe Size	Pipe O.D.	Pipe I.D.
10'-0"	3" STD	3.500"	3.068"	2" STD	2.375"	2.067"
19'-8"	4" STD	4.500"	4.026"	3" STD	3.500"	3.068"
34'-2"	5" STD	5.563"	5.047"	4" STD	4.500"	4.026"



**SIDE ELEVATION**

(Showing pipe runner with Cross Pipe Connection Option A1 and Bottom Anchor Toewall Option B2. Wingwall not shown for clarity.)

SHEET 2 OF 2


**Safety End Treatment**  
 FOR 0° SKEW BOX CULVERTS  
 (MAXIMUM Hw = 7'-0")  
 TYPE I ~ CROSS DRAINAGE  
  
**SETB-CD**

FILE: setbdse-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.	
BMT	TYLER		83	

CROSS PIPE LENGTHS AND PIPE RUNNER LENGTHS

① ②


Nominal Culvert I.D.	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length											
			3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
			0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
24"	1' - 7"	3' - 5"	N/A	N/A	N/A	5' - 10"	N/A	N/A	N/A	8' - 1"	N/A	N/A	N/A	12' - 9"
27"	1' - 8"	3' - 8"	N/A	N/A	5' - 5"	6' - 11"	N/A	N/A	7' - 7"	9' - 0"	N/A	N/A	11' - 11"	14' - 11"
30"	1' - 10"	3' - 11"	N/A	N/A	6' - 4"	8' - 0"	N/A	N/A	8' - 9"	11' - 0"	N/A	N/A	13' - 8"	17' - 0"
33"	1' - 11"	4' - 2"	6' - 2"	6' - 5"	7' - 3"	9' - 1"	8' - 6"	8' - 10"	10' - 0"	12' - 5"	13' - 3"	13' - 9"	15' - 5"	19' - 2"
36"	2' - 1"	4' - 5"	6' - 11"	7' - 3"	8' - 2"	10' - 2"	9' - 6"	9' - 11"	11' - 2"	13' - 10"	14' - 9"	15' - 3"	17' - 2"	21' - 3"
42"	2' - 4"	4' - 11"	8' - 6"	8' - 10"	9' - 11"	12' - 4"	11' - 7"	12' - 0"	13' - 6"	16' - 8"	17' - 9"	18' - 5"	20' - 8"	25' - 7"
48"	2' - 7"	5' - 5"	10' - 1"	10' - 5"	11' - 9"	N/A	13' - 7"	14' - 2"	15' - 10"	N/A	20' - 9"	21' - 6"	24' - 2"	N/A
54"	3' - 0"	5' - 11"	11' - 8"	12' - 1"	N/A	N/A	15' - 8"	16' - 3"	N/A	N/A	23' - 10"	24' - 8"	N/A	N/A
60"	3' - 3"	6' - 5"	13' - 3"	N/A	N/A	N/A	17' - 9"	N/A	N/A	N/A	26' - 10"	N/A	N/A	N/A



NOTE: All pipe runners, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER

(Showing corrugated metal pipe (CMP) culvert. Details of reinforced concrete pipe (RCP) culvert are similar.)



SIDE ELEVATION OF CAST-IN-PLACE CONCRETE

(Showing reinforced concrete pipe (RCP) culvert. Details of corrugated metal pipe (CMP) culvert are similar. Pipe runners not shown for clarity)

TYPICAL PIPE CULVERT MITERS

③

Side Slope	0° Skew	15° Skew	30° Skew	45° Skew
3:1	3:1	3.106:1	3.464:1	4.243:1
4:1	4:1	4.141:1	4.619:1	5.657:1
6:1	6:1	6.212:1	6.928:1	8.485:1

CONDITIONS WHERE PIPE RUNNERS ARE NOT REQUIRED

②

Nominal Culvert I.D.	Single Pipe Culvert	Multiple Pipe Culverts
12" thru 21"	Skews thru 45°	Skews thru 45°
24"	Skews thru 45°	Skews thru 30°
27"	Skews thru 30°	Skews thru 15°
30"	Skews thru 15°	Skews thru 15°
33"	Skews thru 15°	Always required
36"	Normal (no skew)	Always required
42" thru 60"	Always required	Always required

STANDARD PIPE SIZES AND MAX PIPE RUNNER LENGTHS


①

Pipe Size	Pipe O.D.	Pipe I.D.	Max Pipe Runner Length
2" STD	2.375"	2.067"	N/A
3" STD	3.500"	3.068"	10' - 0"
4" STD	4.500"	4.026"	19' - 8"
5" STD	5.563"	5.047"	34' - 2"

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY)

⑤

Nominal Culvert I.D.	3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
12"	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.6	0.7	0.7	0.7	0.8
15"	0.5	0.5	0.5	0.6	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9
18"	0.5	0.5	0.6	0.6	0.6	0.7	0.7	0.8	0.8	0.8	0.9	1.0
21"	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9	0.9	0.9	1.0	1.2
24"	0.6	0.7	0.7	0.8	0.8	0.8	0.8	1.0	1.0	1.0	1.1	1.3
27"	0.7	0.7	0.8	0.9	0.8	0.9	0.9	1.1	1.1	1.1	1.2	1.4
30"	0.8	0.8	0.8	0.9	0.9	0.9	1.0	1.2	1.2	1.2	1.3	1.6
33"	0.8	0.8	0.9	1.0	1.0	1.0	1.1	1.3	1.3	1.4	1.5	1.7
36"	0.9	0.9	0.9	1.1	1.1	1.1	1.2	1.4	1.4	1.5	1.6	1.8
42"	1.0	1.0	1.1	1.3	1.2	1.3	1.3	1.6	1.6	1.7	1.8	2.1
48"	1.1	1.1	1.2	N/A	1.4	1.4	1.5	N/A	1.9	1.9	2.1	N/A
54"	1.3	1.3	N/A	N/A	1.6	1.6	N/A	N/A	2.1	2.1	N/A	N/A
60"	1.4	N/A	N/A	N/A	1.7	N/A	N/A	N/A	2.3	N/A	N/A	N/A



ISOMETRIC VIEW OF TYPICAL INSTALLATION

(Showing installation with no skew.)

① Provide pipe runner of the size shown in the tables. Provide cross pipe of the same size as the pipe runner. Provide cross pipe stub out and bottom anchor pipe of the next smaller size pipe as shown in the Standard Pipe Sizes and Max Pipe Runner Lengths table.

② This standard allows for the placement of only one pipe runner across each culvert pipe opening. In order to limit the clear opening to be traversed by an errant vehicle, the following conditions must be met:

For 60" culvert pipes, the skew must not exceed 0°.  
 For 54" culvert pipes, the skew must not exceed 15°.  
 For 48" culvert pipes, the skew must not exceed 30°.  
 For all culvert pipe sizes 42" and less, the skew must not exceed 45°.

If the above conditions cannot be met, the designer should consider using a safety end treatment with flared wings. For further information, refer to the TxDOT Roadway Design Manual.

③ Miter = slope of mitered end of pipe culvert.

④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".


⑤ Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only.

SHEET 1 OF 2


<p><b>SAFETY END TREATMENT</b>                  FOR 12" DIA TO 60" DIA                  PIPE CULVERTS                  TYPE II ~ CROSS DRAINAGE</p>			
<p><b>SETP-CD</b></p>			
FILE: setpdse-20.dgn	DN: GAF	CK: CAT	DW: JRP
©TxDOT February 2020	CONT: 1584	SECT: 02	JOB: 013, ETC.
REVISIONS	DIST: BMT	COUNTY: TYLER	SHEET NO.: 84

DATE: 4/25/2024 9:18:21 AM  
 FILE: c:\t\dot\pw\_online\txdot5\francisco.molinari\1044294\setpdse-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 9:19:23 AM  
 FILE: c:\t\dot\pw\_online\tdot5\francisco.m\l\nc\1044294\setp\cdse-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**CROSS PIPE AND CONNECTIONS DETAILS**




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

**PIPE RUNNER DETAILS**



**BOTTOM ANCHOR PIPE DETAILS**




**BOTTOM ANCHOR TOEWALL DETAILS**

(Culvert and riprap not shown for clarity.)


**MATERIAL NOTES:**  
 Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
 Provide pipe runners, cross pipes, and anchor pipes conforming to the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
 Provide ASTM A307 bolts and nuts.  
 Galvanize all steel components, except concrete reinforcing, after fabrication.  
 Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**  
 Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.  
 Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.  
 Payment for riprap and toewall is included in the price bid for each safety end treatment.  
 Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap".




**SIDE ELEVATION OF SAFETY END TREATMENT INSTALLATION**


(Showing pipe runner with Cross Pipe Connection Option A1 and Anchor Pipe Option B2 on corrugated metal pipe (CMP) culvert. Reinforced concrete pipe culvert (RCP) details are similar. Riprap not shown for clarity.)



**PLAN OF SKEWED INSTALLATION**



**SECTION A-A**



**SHOWING TYPICAL PIPE CULVERT AND RIPRAP**


- ④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- ⑥ Recommended values of side slope are 3:1, 4:1, and 6:1. All quantities, calculations, and dimensions shown herein are based on these recommended values. Slope of 3:1 or flatter is required for vehicle safety.
- ⑦ Note that actual slope of pipe runner may vary slightly from side slope of riprap and trimmed culvert pipe edge.
- ⑧ Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1/2 inch hole to ensure that the lap of the pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.

**SECTION A-A**

SHEET 2 OF 2

		<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT</b> FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE			
<b>SETP-CD</b>			
FILE:	setpdcse-20.dgn	DN:	GAF
©/TxDOT	February 2020	CK:	CAT
REVISIONS		DW:	JRP
		CK:	GAF
		CON:	1584
		SECT:	02
		JOB:	013, ETC.
		HIGHWAY:	FM 1745, ETC
		DIST:	TYLER
		COUNTY:	
		SHEET NO.:	85


DATE: 4/25/2024 9:24:37 AM  
 FILE: c:\t\dot\p\_w\_online\francisco\line\txdot5\francisco\set\ppdse-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




NOTE: All cross pipes, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

**SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER**

(Showing corrugated metal pipe (CMP) culvert. Details at reinforced concrete pipe (RCP) culvert are similar.)




**ISOMETRIC VIEW OF TYPICAL INSTALLATION**




**SIDE ELEVATION OF CAST-IN-PLACE CONCRETE**


(Showing reinforced concrete pipe (RCP) culvert. Details at corrugated metal pipe (CMP) culvert are similar.)



**PIPE WITH BOLTED ANCHOR**




**PIPE WITH ANCHOR BARS**




**SECTION C-C**

**CROSS PIPE DETAILS**


Limits of riprap (to be included with SET for payment)



**SHOWING TYPICAL PIPE CULVERT AND RIPRAP**




**SHOWING CROSS PIPE WITH ANCHOR BAR**




**SHOWING CROSS PIPE WITH BOLTED ANCHOR**

**SECTION A-A**



**DETAIL "A"**

(Showing invert with corrugated metal pipe (CMP) culvert. Reinforced concrete pipe (RCP) culvert details are similar. Cross pipes not shown for clarity.)



**SECTION B-B**

(Cross pipes not shown for clarity.)

**CROSS PIPE LENGTHS, REQUIRED PIPE SIZES, AND RIPRAP QUANTITIES**

Nominal Culvert I.D.	Conc Riprap (CY) (6)	Pipe Culvert Spa ~ G	Single Barrel ~ Q1	Multi-Barrel ~ Q1	Q2	Conditions for Use of Cross Pipes	Cross Pipe Sizes
12"	0.6	0' - 9"	N/A	2' - 1"	1' - 9"	3 or more pipe culverts	3" Std (3.500" O.D.)
15"	0.7	0' - 11"	N/A	2' - 5"	2' - 2"		
18"	0.8	1' - 2"	N/A	2' - 10"	2' - 8"		
21"	0.9	1' - 4"	N/A	3' - 2"	3' - 1"		
24"	0.9	1' - 7"	N/A	3' - 6"	3' - 7"	3 or more pipe culverts	3 1/2" Std (4.000" O.D.)
27"	1.0	1' - 8"	N/A	3' - 10"	3' - 11"	2 or more pipe culverts	
30"	1.1	1' - 10"	N/A	4' - 2"	4' - 4"	All pipe culverts	4" Std (4.500" O.D.)
33"	1.2	1' - 11"	4' - 2"	4' - 5"	4' - 8"	All pipe culverts	
36"	1.3	2' - 1"	4' - 5"	4' - 9"	5' - 1"	All pipe culverts	4" Std (4.500" O.D.)
42"	1.5	2' - 4"	4' - 11"	5' - 5"	5' - 10"		
48"	1.7	2' - 7"	5' - 5"	6' - 0"	6' - 7"	All pipe culverts	5" Std (5.563" O.D.)
54"	2.0	3' - 0"	5' - 11"	6' - 9"	7' - 6"		
60"	2.2	3' - 3"	6' - 5"	7' - 4"	8' - 3"		
66"	2.4	3' - 3"	6' - 11"	7' - 10"	8' - 9"		
72"	2.7	3' - 4"	7' - 5"	8' - 5"	9' - 4"		

- The proper installation of the first cross pipe is critical for vehicle safety. Place the top of the first cross pipe no more than 6" above the flow line.
- Provide cross pipes, except the first bottom pipe, of the size shown in the table. Provide a 3 1/2" standard pipe (4" O.D.) for the first bottom pipe.
- Install the third cross pipe from the bottom of the culvert using a bolted connection. Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access. At the Contractor's option, install all other cross pipes using the bolted connection details.
- Match cross slope as shown elsewhere in the plans. Cross slope of 6:1 or flatter is required for vehicle safety.
- Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for contractor's information only.

**MATERIAL NOTES:**

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. Provide cross pipes that meet the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 (Gr B), or API 5LX52. Provide ASTM A307 bolts and nuts. Galvanize all steel components, except concrete reinforcing, after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**

Cross pipes are designed for a traversing load of 10,000 pounds at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981. Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the cross pipes. Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap". Payment for riprap and toewall is included in the Price Bid for each Safety End Treatment.


**Bridge Division Standard**

**SAFETY END TREATMENT**  
FOR 12" DIA TO 72" DIA  
PIPE CULVERTS  
TYPE II ~ PARALLEL DRAINAGE

**SETP-PD**


FILE: setppdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT	February 2020	CONT	SECT	JOB
REVISIONS	1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.	
BMT	TYLER		86	

CK: DW: CK: DN:




**LEGEND**

WS	6" WHITE PROFILE PAVEMENT MARKING
YD	6" DOUBLE YELLOW
YB	6" YELLOW BROKEN
YS	6" YELLOW SOLID
EOP	EDGE OF PAVEMENT
ROW	RIGHT OF WAY
	SIGNS



*Samantha Jo Harris* P.E.  
04/29/2024




**FM 1745**  
**PAVEMENT MARKINGS & SIGN LAYOUT**

©TxDOT 2023 SHEET 1 OF 7


CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	87	

DATE: 4/25/2024 9:36:52 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molina\01192089.PM\_1.dgn



CK: DW: CK: DN:



- LEGEND**
- WS 6" WHITE PROFILE PAVEMENT MARKING
  - YD 6" DOUBLE YELLOW
  - YB 6" YELLOW BROKEN
  - YS 6" YELLOW SOLID
  - EOP EDGE OF PAVEMENT
  - ROW RIGHT OF WAY
  - ⊙ SIGNS



*S. Harris* P.E.  
04/29/2024



**FM 1745**  
**PAVEMENT & SIGNS LAYOUTS**


©TxDOT 2023 SHEET 2 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	88	

DATE: 4/25/2024 9:46:24 AM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\01192089.PM\_2.dgn




DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_





**LEGEND**

WS	6" WHITE PROFILE PAVEMENT MARKING
YDS	6" DOUBLE YELLOW SOLID
YB	6" YELLOW BROKEN
YS	6" YELLOW SOLID
EOP	EDGE OF PAVEMENT
ROW	RIGHT OF WAY
	SIGNS



*Samantha Jo Harris* P.E.  
04/29/2024



**FM 1745**

**PAVEMENT  
& SIGNS LAYOUTS**

©TxDOT 2023 SHEET 3 OF 7




CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	89	

DATE: 4/25/2024 10:53:59 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\192089.PM\_3.dgn


CK: DW: CK: DW:

LEGEND

- WS 6" WHITE PROFILE PAVEMENT MARKING
- YDS 6" DOUBLE YELLOW SOLID
- YB 6" YELLOW BROKEN
- YS 6" YELLOW SOLID
- EOP EDGE OF PAVEMENT
- ROW RIGHT OF WAY
- ⊙ SIGNS



*S. Harris* P.E.  
04/29/2024





**FM 1745**  
**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023 SHEET 4 OF 7


CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	90	

DATE: 4/25/2024 10:59:17 AM  
FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molina\dot1192089.PM\_4.dgn


DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_



- LEGEND**
- WS 6" WHITE PROFILE PAVEMENT MARKING
  - YDS 6" DOUBLE YELLOW SOLID
  - YB 6" YELLOW BROKEN
  - YS 6" YELLOW SOLID
  - EOP EDGE OF PAVEMENT
  - ROW RIGHT OF WAY
  - (⊙) SIGNS



P.E.  
 04/29/2024



**FM 1745**  
  
**PAVEMENT**  
**& SIGN LAYOUTS**

©TxDOT 2023 SHEET 5 OF 7


CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	91	

DATE: 4/25/2024 11:03:49 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\192089\PM\_5.dgn



CK:  
DW:  
CK:  
DW:

**LEGEND**

WS	6" WHITE PROFILE PAVEMENT MARKING
YDS	6" DOUBLE YELLOW SOLID
YB	6" YELLOW BROKEN
YS	6" YELLOW SOLID
EOP	EDGE OF PAVEMENT
ROW	RIGHT OF WAY
⊙	SIGNS



*S. Harris* P.E.  
04/29/2024




**FM 1745**  
**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023 SHEET 6 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	92	

DATE: 4/25/2024 11:14:09 AM  
FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molinar\192089.PM 6.dgn


CK: DW: CK: DW: CK: DW:




**LEGEND**

- SIGN
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*S. Harris* P.E.  
04/29/2024



**FM 1745**



**PAVEMENT & SIGNS LAYOUTS**

© TxDOT 2023 SHEET 7 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	93	


DATE: 4/25/2024 11:25:47 AM  
FILE: c:\txdot\pw\_onlinetxdat5\francisco.molinar\01192089\PM\_7.dgn

CK:  
DW:  
CK:  
DW:




- LEGEND**
- SIGN
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:**
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*[Signature]* P.E.

04/29/2024



**FM 2097**



**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023 SHEET 1 OF 9


CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	94	

DATE: 4/25/2024 11:49:45 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\192093\PAVEMENT\_1.dgn


DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_



**LEGEND**

- SIGN 
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.




**FM 2097**

**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023		SHEET 2 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	95	

DATE: 4/25/2024 1:14:30 PM  
 FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molinar\01192093\PAVEMENT\_2.dgn


DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_



**LEGEND**

- SIGN
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
- SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  - SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*S. Harris* P.E.  
04/29/2024



**FM 2097**


**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023		SHEET 3 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	96	


DATE: 4/25/2024 1:18:59 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\01192093\PAVEMENT\_3.dgn




CK: DW: CK: DN:




**LEGEND**

- SIGN 
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
- SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  - SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*SJH* P.E.  
04/29/2024




**FM 2097**

**PAVEMENT & SIGNS LAYOUTS**


©TxDOT 2023		SHEET 4 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	97	

DATE: 4/25/2024 1:36:45 PM  
FILE: c:\txdot\pw\_onlinetx\dot5\francisco.molina\011920931\PAVEMENT\_4.dgn




CK: DW: CK: DW:


**LEGEND**

- SIGN 
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID PAVEMENT MARKINGS
- DY 6" DOUBLE YELLOW PAVEMENT MARKINGS
- YB 6" YELLOW BROKEN PAVEMENT MARKINGS

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.





*SJH* P.E.  
04/29/2024



**FM 2097**

**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023		SHEET 5 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	98	




DATE: 4/25/2024 1:47:33 PM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molinar\192093\PAVEMENT\_5.dgn

CK: DW: CK: DN:


**LEGEND**

- SIGN 
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.




*S. Harris* P.E.  
04/29/2024



**FM 2097**


**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023		SHEET 6 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	99	



DATE: 4/25/2024 2:06:28 PM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\1920931\PAVEMENT\_6.dgn


CK: DW: CK: DN:





**LEGEND**

- SIGN
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*S. Harris* P.E.  
04/29/2024



**FM 2097**

**PAVMENT & SIGNS LAYOUTS**

©TxDOT 2023 SHEET 7 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	100	


DATE: 4/25/2024 2:12:34 PM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\01192093\PAVEMENT\_7.dgn

DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_




**LEGEND**

- SIGN 
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*S. Harris* P.E.  
04/29/2024




**FM 2097**

**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023		SHEET 8 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	101	

DATE: 4/25/2024 2:21:54 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1920931\PAVEMENT\_8.dgn


DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_




**LEGEND**

- SIGN
- WS 6" WHITE SOLID PAVEMENT MARKINGS
- YS 6" YELLOW SOLID SOLID
- DY 6" DOUBLE YELLOW
- YB 6" YELLOW BROKEN

- NOTES:
1. SEE QUANTITY SUMMARY SHEETS FOR PAVEMENT MARKING STATION LIMITS AND QUANTITIES.
  2. SEE SUMMARY OF SMALL SIGNS SHEETS FOR SIGN DETAILS.



*S. Harris* P.E.  
04/29/2024



**FM 2097**

**PAVEMENT & SIGNS LAYOUTS**

©TxDOT 2023		SHEET 9 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	102	

DATE: 4/25/2024 2:30:47 PM  
 FILE: c:\txdot\pw\_onlinetxdat5\francisco.molinar\192093\PAVEMENT\_9.dgn

# SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 4/25/2024 2:36:51 PM  
 FILE: c:\t\dot\pw\_online\tdot5\francisco.molinar\1044297\S0SS.dgn

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
										PREFABRICATED		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
	1	I-2dT	Tyler County Line	48 x 24	X		10BWG	1	SA	T		
	2	I-2dT	Polk County Line	48 x 24	X		10BWG	1	SA	T		
	3	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P		
	4	R2-1	SPEED LIMIT (60)	30 x 36	X		10BWG	1	SA	P		
	5	W1-2L W13-1P	SYMBOL - HORIZ CURVE LEFT (50MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	6	W1-2R W13-1P	SYMBOL - HORIZ CURVE RIGHT (50MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	7	W3-5	SYMBOL <REDUCED SPEED AHD> (55MPH)	36 x 36	X		10BWG	1	SA	P		
	8	W1-2L W13-1P	SYMBOL - HORIZ CURVE LEFT (50MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	9	R2-1	SPEED LIMIT (60)	30 x 36	X		10BWG	1	SA	P		
	10	R2-1	SPEED LIMIT (55)	30 x 36	X		10BWG	1	SA	P		
	11	W1-4R W13-1P	SYMBOL - REVERSE CURVE RIGHT (45MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	12	M1-6F D10-7aT	FM 1745 RM 724	24 x 24 3 x 10	X		10BWG	1	SA	P		
	13	W1-2R W13-1P	SYMBOL - HORIZ CURVE RIGHT (50MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	14	R2-1	SPEED LIMIT (45)	30 x 36	X		10BWG	1	SA	P		
	15	I-2aT	(CHESTER) CITY LIMIT POP 270	48 x 24	X		10BWG	1	SA	T		
	16	R2-1	SPEED LIMIT (55)	30 x 36	X		10BWG	1	SA	P		
	17	I-2aT	(CHESTER) CITY LIMIT POP 270	48 x 24	X		10BWG	1	SA	T		
	18	W1-2R W13-1P	SYMBOL - HORIZ CURVE RIGHT (45MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	19	M2-1 M1-4(3 dgt) M1-6F	JCT <AUXILIARY SIGN> US HIGHWAY 287 <FM SHIELD> FARM ROAD (ROUTE #)	21 x 15 30 x 24 24 x 24	X		10BWG	1	SA	P		
	20	D2-1	CAMDEN (10)	78 x 18	X		10BWG	1	SA	T		
	21	W3-1	SYMBOL - STOP AHEAD	30 x 30	X		10BWG	1	SA	P		
	22	W1-2L W13-1P	SYMBOL - HORIZ CURVE LEFT (45MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	23	D1-2	(LEFT)CORRIGAN / WOODVILLE(RIGHT)	90 x 30	X		S80	1	SA	U		
	24	R2-1	SPEED LIMIT (45)	30 x 36	X		10BWG	1	SA	P		
	25	M3-4 M1-6F	WEST <AUXILIARY SIGN> FM 1745	24 x 12 24 x 24	X		10BWG	1	SA	P		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.  
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
  - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
  - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



## SUMMARY OF SMALL SIGNS

### S0SS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	TYLER	103	

# SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 4/25/2024 2:37:51 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\S055.dgn

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
	26	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P	
	27	R1-2	YIELD	48 x 48 x 48	X		10BWG	1	SA	P	
	28	M3-2	EAST <AUXILIARY SIGN>	24 x 12	X		S80	1	SA	U	1EXT
		M1-6F	FM 1745	24 x 24							
		M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21x 15							
		M1-6F	FM 1745	24 x 24							
		M6-3	<ARROW - VERTICAL STRGHT> <AUX. SIGN>	21x 15							
		M1-4(3 dgt)	US HIGHWAY 287	30 x 24							
		M6-4	<ARROW - DUAL LEFT & RIGHT> <AUX. SIGN>	21x 15							
	29	R1-1	STOP	36 x 36	X		10BWG	1	SA	P	
	30	M3-2	EAST <AUXILIARY SIGN>	24 x 12	X		S80	1	SA	U	1EXT
		M1-6F	FM 1745	24 x 24							
		M6-3	<ARROW - VERTICAL STRGHT> <AUX. SIGN>	21x 15							
		M3-2	EAST <AUXILIARY SIGN>	24 x 12							
		M1-6F	FM 2097	24 x 24							
		M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21x 15							
		M3-4	WEST <AUXILIARY SIGN>	24 x 12							
		M1-6F	FM 1745	24 x 24							
		M6-1	<ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	21x 15							

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.  
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
  - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
  - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



## SUMMARY OF SMALL SIGNS

### S055

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	TYLER	104	



# SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 4/25/2024 2:38:35 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.m\lincor\1044297\S055.dgn

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)	
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION		
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"		1EXT or 2EXT = # of Ext BM = Extruded Wind Beam WC = 1.12 #/ft Wing Channel EXAL= Extruded Alum Sign Panels
	31	M1-6F M6-3 M3-1 M1-4(3 dgt) M6-1 M3-3 M1-4(3 dgt) M4-5 M3-2 M1-6F M6-1	FM 2097 <ARROW - VERTICAL STRGHT> <AUX. SIGN> NORTH <AUXILIARY SIGN> US HIGHWAY 287 <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN> SOUTH <AUXILIARY SIGN> US HIGHWAY 287 TO <AUXILIARY SIGN> EAST <AUXILIARY SIGN> FM 1745 <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	24 x 24 21x 15 24 x 12 30 x 24 21x 15 24 x 12 30 x 24 24 x 12 24 x 12 24 x 24 21x 15	X		S80	1	SA	U	2EXT	
	32	R1-1	STOP	36 x 36	X		10BWG	1	SA	P		
	33	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P		
	34	M3-2 M1-6F	EAST <AUXILIARY SIGN> FM 2097	24 x 12 24 x 24	X		10BWG	1	SA	P		
	35	R2-1	SPEED LIMIT (45)	30 x 36	X		10BWG	1	SA	P		
	36	D1-2	(LEFT)WOODVILLE/CORRIGAN(RIGHT)	90 x 30	X		S80	1	SA	U		
	37	W8-13aT	BRIDGE MAY ICE IN COLD WEATHER	36 x 36	X		10BWG	1	SA	P		
	38	W3-1	SYMBOL - STOP AHEAD	30 x 30	X		10BWG					
	39	I-3	DRY CREEK	30 x 18	X		10BWG	1	SA	P		
	40	I-3	DRY CREEK	30 x 18	X		10BWG	1	SA	P		
	41	M2-1 M1-4(3 dgt)	JCT <AUXILIARY SIGN> US HIGHWAY 287	21x 15 30 x 24	X		10BWG	1	SA	P		
	42	R2-1	SPEED LIMIT (60)	30 x 36	X		10BWG	1	SA	P		
	43	I-2aT	(CHESTER) CITY LIMIT POP 270	48 x 24	X		10BWG	1	SA	T		
	44	R2-1	SPEED LIMIT (45)	30 x 36	X		10BWG	1	SA	P		
	45	I-2aT	(CHESTER) CITY LIMIT POP 270	48 x 24	X		10BWG	1	SA	T		
	46	W8-13aT	BRIDGE MAY ICE IN COLD WEATHER	36 x 36	X		10BWG	1	SA	P		
	47	M1-6F D10-7AT D10-7AT	FM 2097 RM 386 RM 386	24 x 24 3 x 10 3 x 10	X		10BWG	1	SA	P		
	48	W1-2L	SYMBOL - HORIZ CURVE LEFT	36 x 36	X		10BWG	1	SA	P		
	49	W1-2R W13-1P	SYMBOL - HORIZ CURVE RIGHT (45MPH) AVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P		
	50	W1-2R	SYMBOL - HORIZ CURVE RIGHT	36 x 36	X		10BWG	1	SA	P		
	51	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P		
	52	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P		

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.  
<http://www.txdot.gov/>

- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
  - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
  - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).



## SUMMARY OF SMALL SIGNS

### SOSS

FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	TYLER	105	

# SUMMARY OF SMALL SIGNS

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 4/29/2024 8:36:23 AM  
 FILE: c:\txdot\pw\_online\txdot5\francis.sco.molinar\1044297\S055.dgn

PLAN SHEET NO.	SIGN NO.	SIGN NOMENCLATURE	SIGN	DIMENSIONS	FLAT ALUMINUM (TYPE A)	EXAL ALUMINUM (TYPE G)	SM RD SGN ASSM TY XXXXX (X) XX (X-XXXX)				BRIDGE MOUNT CLEARANCE SIGNS (See Note 2)
							POST TYPE	POSTS	ANCHOR TYPE	MOUNTING DESIGNATION	
							FRP = Fiberglass TWT = Thin-Wall 10BWG = 10 BWG S80 = Sch 80	1 or 2	UA=Universal Conc UB=Universal Bolt SA=Slipbase-Conc SB=Slipbase-Bolt WS=Wedge Steel WP=Wedge Plastic	PREFABRICATED P = "Plain" T = "T" U = "U"	
	53	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	54	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	55	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	56	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	57	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	58	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	59	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	60	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	61	W1-8R W1-8L	<CHEVRON RIGHT> <CHEVRON LEFT>	18 x 24 18 x 24	X		10BWG	1	SA	P	
	62	W1-2L W13-1P	SYMBOL - HORIZ CURVE LEFT (45MPH) ADVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P	
	63	R2-1	SPEED LIMIT (60)	30 x 36	X		10BWG	1	SA	P	
	64	D20-5T	CO RD 2650 <ARROW - VERTICAL STRGHT> <AUX. SIGN> CO RD 2600 <ARROW - HORIZ. STRGHT> <AUXILIARY SIGN>	36 x 42	X		10BWG	1	SA	T	
	65	W8-3	PAVEMENT ENDS	36 x 36	X		10BWG	1	SA	P	
	66	W1-2R W13-1P	SYMBOL - HORIZ CURVE RIGHT (50MPH) ADVISORY SPEED PLAQUE	36 x 36 18 x 18	X		10BWG	1	SA	P	
	67	R1-1 D3-3T	STOP CR 2600	36 x 36 30 x 8	X		10BWG	1	SA	P	
	68	R12-1T	WEIGHT LIMIT/GROSS (WEIGHT) LBS	24 x 36	X		10BWG	1	SA	P	

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080"
7.5 to 15	0.100"
Greater than 15	0.125"

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.  
<http://www.txdot.gov/>


- NOTE:**
- Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
  - For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
  - For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).




## SUMMARY OF SMALL SIGNS

### SOSS


FILE: slums16.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT May 1987	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
4-16	DIST	COUNTY	SHEET NO.	
8-16	BMT	TYLER	106	




I-2dT 8in;  
 1.5" Radius, 0.8" Border, White on Green;  
 "Tyler", ClearviewHwy-5-W-R;  
 "COUNTY LINE", ClearviewHwy-3-W;




I-2dT 8in;  
 1.5" Radius, 0.8" Border, White on Green;  
 "Polk", ClearviewHwy-5-W-R;  
 "COUNTY LINE", ClearviewHwy-3-W;




I-2aT 6in;  
 1.5" Radius, 0.8" Border, White on Green;  
 "Chester", ClearviewHwy-5-W-R;  
 "CITY LIMIT", ClearviewHwy-3-W;  
 "POP 270", ClearviewHwy-3-W;




D20-5T(5-6)\_36x42;  
 2.3" Radius, 0.8" Border, White on Green;  
 "CO RD", ClearviewHwy-3-W;  
 "2650", ClearviewHwy-3-W;  
 Standard Arrow Custom 7.5" X 6.1" 90°;  
 "2600", ClearviewHwy-3-W;  
 Standard Arrow Custom 14.0" X 6.1" 0°;




D1-2 8in LT-RT;  
 1.9" Radius, 0.8" Border, White on Green;  
 Standard Arrow Custom 12.0" X 7.1" 180°; "Corrigan", ClearviewHwy-3-W;  
 1.9" Radius, 0.8" Border, White on Green;  
 "Woodville", ClearviewHwy-3-W; Standard Arrow Custom 12.0" X 7.1" 0°;




D1-2 8in LT-RT;  
 1.9" Radius, 0.8" Border, White on Green;  
 Standard Arrow Custom 12.0" X 7.1" 180°; "Woodville", ClearviewHwy-3-W;  
 1.9" Radius, 0.8" Border, White on Green;  
 "Corrigan", ClearviewHwy-3-W; Standard Arrow Custom 12.0" X 7.1" 0°;





D10-7aT 3in;  
 No border, White on Green;  
 "7", ClearviewHwy-4-W;  
 "2", ClearviewHwy-4-W;  
 "4", ClearviewHwy-4-W;




D10-7aT 3in;  
 No border, White on Green;  
 "3", ClearviewHwy-4-W;  
 "8", ClearviewHwy-4-W;  
 "6", ClearviewHwy-4-W;



D2-1 8in;  
 1.5" Radius, 0.5" Border, White on Green;  
 "Camden", ClearviewHwy-3-W; "10", ClearviewHwy-3-W;



R12-IT\_24x36;  
 1.5" Radius, 0.6" Border, 0.4" Indent, Black on White;  
 "WEIGHT", C;  
 "LIMIT", C;  
 "GROSS", C;  
 "58,420", C;  
 "LBS", C;



04/29/2024

Texas Department of Transportation

FM 1745, ETC.

NON STANDARD SIGNS

© TxDOT 2023		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	107	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 3:39:39 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297.dgn

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES			
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	DEVICE	SINGLE	DOUBLE	INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX(XX)			
								NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount		SHEETING: Yellow, White or Red Type B or C reflective sheeting NOTE: 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (fix). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.	
SHEETING: Yellow, White or Red Type B or C reflective sheeting				SHEETING: Yellow, White or Red Type B or C Reflective Sheeting				DIRECTION: If Required BI = Bi-Directional BR = Bi-Directional with red on back		INSTL OM ASSM (OM-XX) (XXXX)XXX(XX)	
POST TYPE: WC, YFLX, WFLX				MOUNT TYPE: GND, SRF				TYPE OF OBJECT MARKER: 1, 2, 3, or 4		NUMBER OF REFLECTORS OR DIRECTION: X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST: WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT: GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION: If Required BI = Bi-Directional	

OBJECT MARKERS								
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4
								SHEETING: Yellow-Type B or C Sheeting POST TYPE: TWT MOUNT TYPE: WAS, WAP
SHEETING: Yellow-Type B or C Sheeting		SHEETING: Yellow - Type B or C Sheeting			SHEETING: Alternating acrylic black and retroreflective yellow - Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting			SHEETING: Red -Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting
POST TYPE: TWT		POST TYPE: WC	POST TYPE: WC	POST TYPE: WFLX	POST TYPE: TWT			POST TYPE: TWT
MOUNT TYPE: WAS, WAP		MOUNT TYPE: GND	MOUNT TYPE: GND	MOUNT TYPE: GND, SRF	MOUNT TYPE: WAS, WAP			MOUNT TYPE: WAS, WAP

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600













BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.	
DEVICE	GF1	GF2	CTB	DEVICE				W1-6		
									DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION <b>D &amp; OM(1)-20</b>	
SHEETING: Yellow, White, Red NOTE: 1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)		48" x 24" (Conventional)
MOUNTING HEIGHT			4'-0" or 7'-0"		7'-0" Only		MOUNTING HEIGHT		7'-0"	
NOTE			1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).							



FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	BMT	TYLER	108	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 3:42:11 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.mollinar\d1044297\dom2-20.dgn


POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS																											
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT																										
GND	GND	SRF	WAS	WAP	GF 1																										
 <p style="text-align: center;">2'-0" Usual</p>	 <p style="text-align: center;">Reflective material</p> <p style="text-align: center;">Post</p> <p style="text-align: center;">Stub</p>	 <p style="text-align: center;">Reflective material</p> <p style="text-align: center;">Post</p> <p style="text-align: center;">Base</p>	 <p style="text-align: center;">12" Dia.</p> <p style="text-align: center;">27" 30"</p>	 <p style="text-align: center;">3" (Approx.)</p> <p style="text-align: center;">15" 17" 20"</p> <p style="text-align: center;">12" Dia.</p> <p style="text-align: center;">3.5" 17" 30° 2" 1"</p>	 <p style="text-align: center;">Centerline of MBCF rail element</p>	 <p style="text-align: center;">Attached to post or block</p> <p style="text-align: center;">2'-6" Min. 4" Min. 4'-0"</p>																									
	EMBEDDED		SURFACE MOUNT	STEEL	PLASTIC	<b>CONCRETE TRAFFIC BARRIER (CTB)</b>  <p style="text-align: center;">Place Barrier Reflector on top or on side(s) of CTB.</p>																									
<b>NOTES</b> 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.		<b>NOTES</b> 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		<b>NOTE</b> 1. Install per manufacturer's recommendations.		<b>GENERAL NOTES</b> 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.																									
<b>TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS</b>  <p style="text-align: center;">4'-0" Pavement surface Ground Line</p>		<b>CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN</b>  <p style="text-align: center;">7'-0" Pavement surface Ground Line</p>		<b>DELINEATORS AND TYPE 2 OBJECT MARKERS</b>  <p style="text-align: center;">Approximately 4'-0" Pavement surface Ground Line</p> <p style="text-align: center;">2'-0" to 8'-0" or in front of object being marked</p>																											
<b>NOTE</b> Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		<b>NOTE</b> Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		See general notes 1, 2 and 3.		 <p style="text-align: center;">Texas Department of Transportation</p> <p style="text-align: right;">Traffic Safety Division Standard</p> <h2 style="text-align: center;">DELINEATOR &amp; OBJECT MARKER INSTALLATION</h2> <h3 style="text-align: center;">D &amp; OM(2) -20</h3> <table border="1" style="width: 100%; border-collapse: collapse; font-size: small;"> <tr> <td>FILE: dom2-20.dgn</td> <td>DN: TxDOT</td> <td>CK: TxDOT</td> <td>DW: TxDOT</td> <td>CK: TxDOT</td> </tr> <tr> <td>© TxDOT August 2004</td> <td>CONT</td> <td>SECT</td> <td>JOB</td> <td>HIGHWAY</td> </tr> <tr> <td>REVISIONS</td> <td>1584</td> <td>02</td> <td>013, ETC.</td> <td>FM1745, ETC</td> </tr> <tr> <td>10-09 3-15</td> <td>DIST</td> <td>COUNTY</td> <td colspan="2">SHEET NO.</td> </tr> <tr> <td>4-10 7-20</td> <td>BMT</td> <td>TYLER</td> <td colspan="2" style="text-align: center;">109</td> </tr> </table>	FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY	REVISIONS	1584	02	013, ETC.	FM1745, ETC	10-09 3-15	DIST	COUNTY	SHEET NO.		4-10 7-20	BMT	TYLER	109	
FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT																											
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY																											
REVISIONS	1584	02	013, ETC.	FM1745, ETC																											
10-09 3-15	DIST	COUNTY	SHEET NO.																												
4-10 7-20	BMT	TYLER	109																												

DATE: 4/25/2024 3:46:07 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.mallinar\d1044297\dom3-20.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

### MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


### SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



**NOTE**

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

### SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



**NOTE**

At least one chevron pair is installed beyond the point of tangent in tangent section.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

### DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

### DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

**NOTES**

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign


Traffic Safety Division Standard

## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

### D & OM(3) -20

FILE: dom3-20.dgn	DW: TXDOT	CK: TXDOT	OW: TXDOT	CR: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS		1584 02	013, ETC.	FM1745, ETC
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	BMT	TYLER	110	


**TWO-WAY, TWO LANE ROADWAY  
WITH REDUCED WIDTH APPROACH RAIL**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY  
WITH METAL BEAM GUARD FENCE (MBGF)**



**NOTE:**

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY  
BRIDGE WITH NO APPROACH RAIL**



**LEGEND**

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &  
OBJECT MARKER  
PLACEMENT DETAILS**

**D & OM(5) - 20**

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
7-20	DIST	COUNTY	SHEET NO.	
	BMT	TYLER	111	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 3:53:23 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\dom5-20.dgn


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 3:55:48 PM  
 FILE: c:\txdot\pw\_online\francisco.molinar\1044297\dom6-20.dgn


### CONTINUOUS CONCRETE OR STEEL BARRIER




### MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



### DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



### EMERGENCY CROSSOVER



#### NOTES

1. Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delineators. On Continuous Barrier, equal spacing (100' max.)
2. Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delineators.
3. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

#### LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



## DELINEATOR & OBJECT MARKER PLACEMENT DETAILS








### D & OM(6)-20

FILE: dom6-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
7-20	1584	02	013, ETC.	FM1745, ETC
	DIST	COUNTY	SHEET NO.	
	BMT	TYLER	112	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 3:59:27 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.mollinar\1044297\domvia-20.dgn



OBJECT MARKERS SMALLER THAN 3 FT<sup>2</sup>

- NOTES**
- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
  - Mounting should be flush with top of attenuator. Minimum size 96" x 24".




- NOTES**
- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
  - Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
  - Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
  - Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
  - Object Marker at nose of attenuator is subsidiary to the attenuator.
  - See D & OM (1-4) for required barrier reflectors.

		Traffic Safety Division Standard	
<b>DELINEATOR &amp; OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</b> <b>D &amp; OM(VIA) -20</b>			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT	SECT	JOB
REVISIONS		1584 02	013, ETC. FM1745, ETC
4-92 8-04	DIST	COUNTY	SHEET NO.
8-95 3-15	BMT	TYLER	113
4-98 7-20			
20G			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 4:03:30 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinari\1044297\fga-15.dgn



DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300


ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLUORESCENT YELLOW	TYPE B <sub>FL</sub> & C <sub>FL</sub> SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM

### GENERAL NOTES

- Each flood gauge assembly shall consist of the FLOOD GAUGE sign (W8-19aTP) and DEPTH MARKER (W8-19). Two assemblies should be erected, one along each approach, at the low water crossing location on the right side of the roadway.
- The flood gauge assembly should be of sufficient height to register depth of water to a minimum of five (5) Feet above the lowest travel lane pavement surface. Actual height of depth marker required for each location is shown elsewhere in the plans, but should not be in excess of ten (10) feet.
- The flood gauge assembly should be located not more than ten (10) feet from the pavement edge. Consideration should be given to placement with regard to the following factors:
  - Accurate register of depth of water over roadway.
  - Daytime and nighttime visibility of the flood gauge assembly along roadway approaches.
  - Outside the main flow of water during both normal and flood conditions.
- In areas where flood conditions would likely obscure the flood gauge assembly, a second pair of gauges, one on each approach, registering depths greater than shown on the first flood gauge assembly, is recommended.
- The Engineer will approve all flood gauge assembly locations before installation.
- The alphabets and lateral spacing between letters and numerals shall conform with the Texas "Manual on Uniform Traffic Control Devices for Streets and Highways", latest edition, and any approved changes thereto. Lateral Spacing of text shall provide a balanced appearance. All materials shall conform to Department Specifications.
- FLOOD GAUGE signs and depth marker shall be mounted in accordance with Standard SMD (series). The recommended mounting is three (3) inch fiberglass reinforced pipe (FRP) pipe as shown on Standard SMD (GEN) and SMD (FRP). ROAD MAY FLOOD sign (W8-18) along the approach roadway may be required in areas where rainfall causes frequent roadway flooding.


The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:  
<http://www.txdot.gov/>




		Traffic Operations Division Standard	
<h2>FLOOD GAUGE ASSEMBLY</h2> <h3>FGA-15</h3>			
FILE:	fga-15.dgn	DN:	TxDOT
© TxDOT	January 1997	CK:	TxDOT
REVISIONS		DW:	TxDOT
		CR:	TxDOT
3-15		CONT	SECT
		1584	02
		JOB	
		013, ETC.	
		HIGHWAY	
		FM1745, ETC	
		DIST	COUNTY
		BMT	TYLER
		SHEET NO.	114

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 4:06:58 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.mollinar\1044297\pml-22.dgn




**EDGE LINE AND LANE LINES  
ONE-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**



**TYPICAL TWO-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**CENTERLINE AND LANE LINES  
FOUR LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**DETAIL "A"**


\* 2" minimum for restripe projects when approved by the Engineer.  
 \*\* 8" minimum for restripe projects when approved by the Engineer.



**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT  
MARKINGS THROUGH INTERSECTIONS**




**TWO LANE TWO-WAY ROADWAY  
WITH OR WITHOUT SHOULDERS**




**DETAIL "B"**

\* 2" minimum for restripe projects when approved by the Engineer.



**YIELD LINES**



For posted speed on road being marked equal to or less than 40 MPH.

**NOTES**


- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.

**GENERAL NOTES**

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.


MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,  
EDGE LINE & CENTERLINE**  
Based on Traveled Way and Pavement Widths for Undivided Roadways



**FOUR LANE DIVIDED ROADWAY CROSSOVERS**

**TYPICAL STANDARD  
PAVEMENT MARKINGS**


**PM(1) - 22**

FILE:	pml-22.dgn	DN:		CK:		DW:		CK:	
© TxDOT	December 2022	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1584	02	013, ETC.	FM1745, ETC				
11-78	8-00 6-20	DIST	COUNTY	SHEET NO.					
8-95	3-03 12-22	BMT	TYLER	115					
5-00	2-12								


# REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 4:09:37 PM  
 FILE: c:\txdot\pw\_online\francisco.molinar\1044297\pm2-22.dgn



**CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS**




**CENTERLINE & LANE LINES  
FOR FOUR LANE TWO-WAY ROADWAYS**




**DETAIL "A"**

**DETAIL "B"**

**DETAIL "C"**





**CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE**




**LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)**

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.  
 See Note 3.



**REFLECTORIZED PROFILE  
PATTERN DETAIL**

USING REFLECTIVE PROFILE PAVEMENT MARKINGS




A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

**NOTES**


1. Edge lines should typically be 6" wide and the materials shall be specified in the plans.
2. Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**Type I (Top View)**



**Type II (Top View)**



**SECTION A**

**RAISED PAVEMENT MARKERS**



**POSITION GUIDANCE USING  
RAISED MARKERS  
REFLECTORIZED PROFILE  
MARKINGS  
PM(2) - 22**

FILE: pm2-22.dgn	DN:	CK:	DW:	CK:
© TxDOT December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
4-77 8-00 6-20	DIST	COUNTY	SHEET NO.	
4-92 2-10 12-22	BMT	TYLER	116	
5-00 2-12				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

## SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)


**Post Type**  
 FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))  
 TWT = Thin-Walled Tubing (see SMD(TWT))  
 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))  
 S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

**Number of Posts (1 or 2)**

**Anchor Type**  
 UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))  
 UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))  
 WS = Wedge Anchor Steel - (see SMD(TWT))  
 WP = Wedge Anchor Plastic (see SMD(TWT))  
 SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))  
 SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

**Sign Mounting Designation**  
 P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))  
 T = Prefab. "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))  
 IF REQUIRED  
 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))  
 BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))  
 WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))  
 EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


## REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


## SIGN LOCATION

### PAVED SHOULDERS



#### LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



#### GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

### T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.


No more than 2 sign posts should be located within a 7 ft. circle.



### BEHIND BARRIER




#### BEHIND GUARDRAIL



#### BEHIND CONCRETE BARRIER

\*\*Sign clearance based on distance required for proper guard rail or concrete barrier performance.

## TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

### SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

### CURB & GUTTER OR RAISED ISLAND




### RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

\*\*\* Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.



\* Signs shall be mounted using the following condition that results in the greatest sign elevation:

- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:  
<http://www.txdot.gov/publications/traffic.htm>

Texas Department of Transportation  
 Traffic Operations Division


## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD (GEN) - 08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		1584	02	013, ETC.	FM1745, ETC
		DIST	COUNTY		SHEET NO.
		BMT	TYLER		117

DATE: 4/25/2024 4:13:50 PM  
 FILE: c:\txdot\pwworking\online\txdot5\francisco.molinar\d1044297\smagen.dgn

# TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



## NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. [http://www.txdot.gov/business/producer\\_list.htm](http://www.txdot.gov/business/producer_list.htm) The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

## GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
  - 10 BWG Tubing (2.875" outside diameter)
    - 0.134" nominal wall thickness
    - Seamless or electric-resistance welded steel tubing or pipe
    - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
    - Other steels may be used if they meet the following:
      - 55,000 PSI minimum yield strength
      - 70,000 PSI minimum tensile strength
      - 20% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
    - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
    - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
  - Schedule 80 Pipe (2.875" outside diameter)
    - 0.276" nominal wall thickness
    - Steel tubing per ASTM A500 Gr C
    - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
      - 46,000 PSI minimum yield strength
      - 62,000 PSI minimum tensile strength
      - 21% minimum elongation in 2"
    - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
    - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
    - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

## ASSEMBLY PROCEDURE


### Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

### Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

## CONCRETE ANCHOR



Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 4:17:50 PM  
FILE: c:\txdot\pwworking\online\txdot5\francisco.molinard\1044297\smads1.dgn



## SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

















SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
9-08	REVISIONS				
	CONT	SECT	JOB	HIGHWAY	
	1584	02	013, ETC.	FM1745, ETC	
DIST		COUNTY		SHEET NO.	
BMT		TYLER		118	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 4:22:05 PM

FILE: c:\t\dot\p\online\txdot5\francisco.mollinar\d1044297\smds2.dgn



Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.

- GENERAL NOTES:**
- SIGN SUPPORT # OF POSTS MAX. SIGN AREA
 

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
  - The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
  - Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
  - Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
  - Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
  - For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
  - When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
  - Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
  - Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
  - Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
  - Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
  - Post open ends shall be fitted with Friction Caps.
  - Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
SIGN DESCRIPTION	SUPPORT	
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
Warning	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)	
Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)	


**Texas Department of Transportation**  
Traffic Operations Division

**SIGN MOUNTING DETAILS**  
**SMALL ROADSIDE SIGNS**  
**TRIANGULAR SLIPBASE SYSTEM**  
**SMD(SLIP-2)-08**


© TxDOT July 2002		DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		1584	02	013, ETC.	FM1745, ETC
		DIST	COUNTY	SHEET NO.	
		BMT	TYLER	119	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 4:25:34 PM  
 FILE: c:\txdot\pww\online\txdot5\francisco.mollinar\d1044297\smads3.dgn




SM RD SGN ASSM TY XXXX(1)XX(T-2EXT)  
 (\* - See Note 12)




Detail B



Detail C  
 Splices shall only be allowed behind the sign substrate.




SM RD SGN ASSM TY XXXX(1)XX(U-XX)




Typical Sign Mount  
 SM RD SGN ASSM TY S80(2)XX(IP-EXAL)


\* Additional stiffener placed at approximate center of signs when sign width is greater than 10'.



Detail E




Detail A




Detail D

EXTRUDED ALUMINUM SIGN WITH T BRACKET



Extruded Aluminum Sign With T Bracket



Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details  
 See Detail E for clamp installation

GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG       | 1          | 16 SF          |
| 10 BWG       | 2          | 32 SF          |
| Sch 80       | 1          | 32 SF          |
| Sch 80       | 2          | 64 SF          |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Texas Department of Transportation  
 Traffic Operations Division

SIGN MOUNTING DETAILS  
 SMALL ROADSIDE SIGNS  
 TRIANGULAR SLIPBASE SYSTEM  
 SMD (SLIP-3) -08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		1584	02	013, ETC.	FM1745, ETC
		DIST	COUNTY	SHEET NO.	
		BMT	TYLER	120	





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/25/2024 4:31:54 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\tsr3-13.dgn

## REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

## REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

## GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS


### TSR(3) - 13

FILE:	tsr3-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
©TxDOT	October 2003	CONT	SECT	JOB	HIGHWAY				
REVISIONS		1584	02	013, ETC.	FM1745, ETC				
12-03	7-13	DIST	COUNTY	SHEET NO.					
9-08		BMT	TYLER	121					

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.  
 DATE: 4/25/2024 4:34:31 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\tsr4-13.dgn

### REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

### REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR WARNING SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

### REQUIREMENTS FOR SCHOOL SIGNS



#### TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

### GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

#### ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

#### DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>



## TYPICAL SIGN REQUIREMENTS

### TSR(4) - 13


FILE:	tsr4-13.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CR:	TxDOT
© TxDOT	October 2003	CONT	SECT	JOB	SECT	HIGHWAY			
REVISIONS	1584	02	013, ETC.		FM1745, ETC				
12-03	7-13	DIST	COUNTY		SHEET NO.				
9-08		BMT	TYLER		122				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 4:37:30 PM  
 FILE: c:\t\dot\pw\_online\txdot5\francisco.mollinar\1044297\tsr-5-13.dgn

### ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs




Type A




Type B



E-3



E-4



Down Arrow

TYPE	LETTER SIZE	USE
A-1	10.67" U/L and 10" Caps	Single Lane Exits
A-2	13.33" U/L and 12" Caps	
A-3	16" & 20" U/L	
B-1	10.67" U/L and 10" Caps	Multiple Lane Exits
B-2	13.33" U/L and 12" Caps	
B-3	16" & 20" U/L	


CODE	USED ON SIGN NO.
E-3	E5-1aT
E-4	E5-1bT

**NOTE**

Arrow dimensions are shown in the "Standard Highway Sign Designs for Texas" manual.


The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:  
<http://www.txdot.gov/>

### SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)




INTERSTATE ROUTE MARKERS

A	C	D	E
36	21	15	1 1/2
48	28	20	1 3/4




U.S. ROUTE MARKERS

Sign Size	"Y"
24x24	2
30x24	3
36x36	3
45x36	4
48x48	4
60x48	5




STATE ROUTE MARKERS

No. of Digits	W	X
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5



EXIT ONLY PANEL


### MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




DIRECT APPLIED ATTACHMENT

**NOTE:**

- Sheeting for legend, symbols, and borders must be cut at panel joints.
- Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".



SCREW ATTACHMENT




NUT/BOLT ATTACHMENT


**NOTE:**

Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

### ARROW DETAILS for Destination Signs (Type D)



Standard arrow to be used with 6 inch letters.



Standard arrow to be used with 8 inch letters.



## TYPICAL SIGN REQUIREMENTS

### TSR (5) - 13

FILE: tsr5-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT October 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
12-03 7-13	DIST	COUNTY	SHEET NO.	
9-08	BMT	TYLER	123	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 4/25/2024 4:45:48 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1044297\spb3-13.dgn

**GENERAL NOTES:**


- Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
- See Item 685, "Roadside Flashing Beacon Assemblies" for further requirements.
- See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered flashing beacon assemblies.
- When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
- Use materials specifically designed for attaching cabinets, beacon heads, solar panels, etc., to poles.
- Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening on connection.
- Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on poles.
- Install the cable clamp in the bottom third of the back of the cabinet. See Detail A.
- Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL in the file "Roadway Illumination and Electrical Supplies". Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse (slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
- Install the batteries in a battery box. Place the batteries on a 3/16" thick plastic sheet and connect together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and 3/16" plastic sheet are subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies." When required, install batteries in the flasher cabinet. Wire batteries according to manufacturer's recommendations. Provide the number of batteries as required by the manufacturer.
- See standard sheet Electrical Details (ED) for additional requirements regarding the installation of ground boxes/battery boxes, conduit, and cabinets.
- Unless otherwise shown on the plans or recommended by the manufacturer, use the following table to determine the wire size from cabinet to beacons.

Distance from Cabinet to Beacons (ft.)	Minimum Required Wire Size (AWG)
0 - 35	#14
35 - 60	#12
60 - 100	#10
> 100	#8

- Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- Orient solar panel for optimum exposure to sunlight (face to the south). Prior to installation, check the location to ensure there is no overhead obstruction that would block the solar panel from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- Ensure height of conduit is below top of anchor bolts.




**DETAIL FOR SOLAR PANEL, CABINET, AND BATTERIES LOCATED OUT OF CLEAR ZONE ON SEPARATE ALUMINUM POLE ASSEMBLY**




Pull conductors to remove slack in run between cabinet and ground box. Clamp cable at conduit end in ground box and in cabinet at entry as shown.


**DETAIL A**




**DETAIL B**



**DETAIL C**



**NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS**



**NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS EXPLODED VIEW**




**SOLAR POWERED ROADSIDE FLASHING BEACON ASSEMBLY DETAILS (ALUMINUM) SPRFBA (3) - 13**

FILE: spb3-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT May 2003	CONT	SECT	JOB	HIGHWAY
REVISIONS	1584	02	013, ETC.	FM1745, ETC
12-04	DIST	COUNTY	SHEET NO.	
3-13	BMT	TYLER	124	

DN: DW: CK: CK:

UTILITY NOTES:

1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES ARE ASSUMED FROM ABOVE GROUND INDICATORS. PERFORM TEXAS 811 CALL PRIOR TO BEGINNING CONSTRUCTION.
2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED NEAR PIPELINE CROSSINGS. ENERGY TRANSFER AND SUNOCO PIPELINE L.P. HAVE PIPELINE CROSSINGS WITHIN THE PROJECT LIMITS.
3. PROVIDE A LIST OF EQUIPMENT TYPES/MODELS AND THE WEIGHTS OF THE EQUIPMENT TYPES/MODELS THAT WILL BE USED NEAR THESE PIPELINES TO THE REPRESENTATIVES OF THESE PIPELINES PRIOR TO BEGINNING CONSTRUCTION.
4. CONTACT ENERGY TRANSFER REPRESENTATIVE THOMAS PURVIS PRIOR TO BEGINNING WORK NEAR ENERGY TRANSFER/ETC TEXAS PIPELINE, LTD PIPELINES.  
 THOMAS PURVIS: 713-253-1273  
 THOMAS.PURVIS@ENERGYTRANSFER.COM
5. CONTACT SUNOCO PIPELINE L.P. REPRESENTATIVE DALTON WHITE PRIOR TO BEGINNING WORK NEAR SUNOCO PIPELINE L.P. PIPELINES.  
 DALTON WHITE: 409-291-0837, SOUR LAKE FIELD OFFICE  
  
 SUNOCO PIPELINE EMERGENCY CONTACT NUMBER  
 HOUSTON: 1-800-753-5531
6. ALL EXCAVATION NEAR PIPELINES CROSSINGS WILL CONFORM TO THE GENERAL GUIDELINES FOR THIRD PARTY CONSTRUCTION OR MAINTENANCE ACTIVITIES - AVAILABLE UPON REQUEST.



*[Signature]* P.E.  
 05/22/2024

DATE: 5/22/2024 2:40:34 PM  
 FILE: c:\p\g\m\15175414\UtilityNotes.dgn


<b>FM 1745, ETC.</b>			
<b>UTILITY NOTES</b>			
2024		SHEET 1 OF 1	
CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		125

CK: DW: CK: DN:


**LEGEND**

- CENTERPOINT GAS
- GAS PIPELINE
- GAS METER/VALVE
- OVERHEAR ELECTRIC
- POWER POLE
- FIBEROPTIC
- TELEPHONE PEDESTAL
- ELECTRIC JUNCTION BOX
- WATER
- WATER METER

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.




*SJH* PE.  
04/29/2024





**FM 1745**  
  
**UTILITY LAYOUT**

© TxDOT 2023		SHEET 1 OF 7	
CONT 1584	SECT 02	JOB 013, ETC.	HIGHWAY FM1745, ETC
DIST BMT		COUNTY TYLER	SHEET NO. 126




DATE: 4/26/2024 8:54:31 AM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\1175414\BL-CL-101 - FM 1745 Utilities\_LAYOUTS.dgn

CK: DW: CK: DW: CK: DW:



- LEGEND**
- CENTERPOINT GAS ————
  - GAS PIPELINE .....-.....
  - GAS METER/VALVE (⊗) (⊗)
  - OVERHEAR ELECTRIC ————
  - POWER POLE (⊙)
  - FIBEROPTIC - - - - -
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER - - - - -
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



PE.  
04/29/2024



**FM 1745**


**UTILITY LAYOUT**

© TxDOT 2023 SHEET 2 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	127	


DATE: 4/26/2024 8:59:34 AM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\1175414\BL CL-101 - FM 1745 UTILITIES LAYOUTS-2.dgn

CK: DW: CK: DW: CK: DW:



- LEGEND**
- CENTERPOINT GAS
  - GAS PIPELINE
  - GAS METER/VALVE
  - OVERHEAR ELECTRIC
  - POWER POLE
  - FIBEROPTIC
  - TELEPHONE PEDESTAL
  - ELECTRIC JUNCTION BOX
  - WATER
  - WATER METER

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*S. Harris* P.E.  
04/29/2024



**FM 1745**  
**UTILITY LAYOUT**



© TXDOT 2023 SHEET 3 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	128	

DATE: 4/26/2024 9:06:28 AM  
FILE: c:\txdot\pw\_onlinetxdot5\francisco.molina\1175414\BL CL-101 - FM 1745 UTILITIES LAYOUTS-4.dgn




CK: DW: CK: DN:




- LEGEND**
- CENTERPOINT GAS ————
  - GAS PIPELINE - - - - -
  - GAS METER/VALVE (G) (X)
  - OVERHEAR ELECTRIC ————
  - POWER POLE (●)
  - FIBEROPTIC - - - - -
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER - - - - -
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*S. Harris* P.E.  
04/29/2024



**FM 1745**  
**UTILITY LAYOUT**

©TxDOT 2023 SHEET 4 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	129	


DATE: 4/26/2024 9:18:30 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molina\1175414\BL CL-101 - FM 1745 UTILITIES LAYOUTS-6.dgn

CK:  
DW:  
CK:  
DN:


**LEGEND**

- CENTERPOINT GAS
- GAS PIPELINE
- GAS METER/VALVE
- OVERHEAR ELECTRIC
- POWER POLE
- FIBEROPTIC
- TELEPHONE PEDESTAL
- ELECTRIC JUNCTION BOX
- WATER
- WATER METER

- NOTES:
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*[Signature]* P.E.  
04/29/2024




**FM 1745**

**UTILITY LAYOUT**

© TxDOT 2023 SHEET 5 OF 7


CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	130	



DATE: 4/26/2024 9:28:29 AM  
 FILE: c:\t\dot\pw\_online\txdot5\francisco.molinar\1175414\BL CL-101 - FM 1745 UTILITIES LAYOUTS-8.dgn

DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_

DATE: 4/26/2024 9:43:29 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\175414\BL CL-101 - FM 1745 UTILITIES LAYOUTS-10.dgn



**LEGEND**

CENTERPOINT GAS ————

GAS PIPELINE ..... (dotted line)

GAS METER/VALVE (⊗) (⊗)

OVERHEAR ELECTRIC ————

POWER POLE (⊙)

FIBEROPTIC ————

TELEPHONE PEDESTAL (T)


ELECTRIC JUNCTION BOX (E)

WATER - - - - -

WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.

STATE OF TEXAS  
 SAMANTHA JO HARRIS  
 134616  
 LICENSED PROFESSIONAL ENGINEER  
 PE.  
 04/29/2024



Texas Department of Transportation


**FM 1745**

**UTILITIES LAYOUT**

©TxDOT 2023 SHEET 6 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	131	

DN: DW: CK: CK: DW: CK: DN:




**LEGEND**

- CENTERPOINT GAS — ······
- GAS PIPELINE — ······
- GAS METER/VALVE (Symbol)
- OVERHEAR ELECTRIC — ······
- POWER POLE (Symbol)
- FIBEROPTIC — ······
- TELEPHONE PEDESTAL (Symbol)
- ELECTRIC JUNCTION BOX (Symbol)
- WATER — ······
- WATER METER (Symbol)

**NOTES:**

1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*[Signature]*  
P.E.  
04/29/2024



**Texas Department of Transportation**

**FM 1745**

**UTILITY LAYOUT**


© TxDOT 2023 SHEET 7 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	132	

DATE: 4/26/2024 9:52:19 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\01175414\BL CL-101 - FM 1745 UTILITIES LAYOUTS-12.dgn


CK:  
DW:  
CK:  
DN:

DATE: 4/26/2024 10:04:33 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\11754151146+11.168+00 - FM 2097 UTILITIES\_LAYOUT.dgn




- LEGEND**
- CENTERPOINT GAS ————
  - GAS PIPELINE .....
  - GAS METER/VALVE (G) (X)
  - OVERHEAR ELECTRIC ————
  - POWER POLE (P)
  - FIBEROPTIC - - - - -
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER - - - - -
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*[Signature]*  
P.E.  
04/29/2024





**FM 2097**  
  
**UTILITY LAYOUT**

©TxDOT 2023 SHEET 1 OF 9


CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	133	

CK: DW: CK: DN:




- LEGEND**
- CENTERPOINT GAS ————
  - GAS PIPELINE .....
  - GAS METER/VALVE (G) (V)
  - OVERHEAR ELECTRIC ————
  - POWER POLE (P)
  - FIBEROPTIC - - - - -
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER - - - - -
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*S. Harris* P.E.  
04/29/2024



FM 2097


UTILITY LAYOUT

©TxDOT 2023 SHEET 2 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	134	


DATE: 4/26/2024 10:49:41 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151\168+00 - 192+00 - FM 2097 UTILITIES LAYOUT-2.dgn

DATE: 4/26/2024 10:57:20 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151192+00-216+00 - FM 2097 UTILITIES LAYOUT-4.dgn




- LEGEND**
- CENTERPOINT GAS ————
  - GAS PIPELINE .....
  - GAS METER/VALVE (⊗) (⊗)
  - OVERHEAD ELECTRIC ————
  - POWER POLE (⊙)
  - FIBEROPTIC - - - - -
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER - - - - -
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.





*[Signature]* P.E.  
 04/29/2024



**FM 2097**  
  
**UTILITY LAYOUT**


©TxDOT 2023		SHEET 3 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	135	

CK:  
DW:  
CK:  
DN:




- LEGEND**
- CENTERPOINT GAS
  - GAS PIPELINE
  - GAS METER/VALVE
  - OVERHEAR ELECTRIC
  - POWER POLE
  - FIBEROPTIC
  - TELEPHONE PEDESTAL
  - ELECTRIC JUNCTION BOX
  - WATER
  - WATER METER

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



PE.  
04/29/2024



Texas Department of Transportation

**FM 2097**

**UTILITY LAYOUT**

©TxDOT 2023 SHEET 4 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	136	

DATE: 4/26/2024 11:07:19 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151216+00 - 240+00 - FM 2097 UTILITIES LAYOUT-6.dgn




CK: \_\_\_\_\_  
 DW: \_\_\_\_\_  
 CK: \_\_\_\_\_  
 DW: \_\_\_\_\_

**LEGEND**

- CENTERPOINT GAS
- GAS PIPELINE
- GAS METER/VALVE
- OVERHEAR ELECTRIC
- POWER POLE
- FIBEROPTIC
- TELEPHONE PEDESTAL
- ELECTRIC JUNCTION BOX
- WATER
- WATER METER

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.




*S. Harris* P.E.  
 04/29/2024




<b>FM 2097</b>			
<b>UTILITY LAYOUT</b>			
© TxDOT 2023		SHEET 5 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY		SHEET NO.
BMT	TYLER		137

DATE: 4/26/2024 11:14:27 AM  
 FILE: c:\txdot\pw\_onlinetx\d05\francisco.molinar\175415\BL CL-57 - FM 2097 UTILITIES LAYOUT-8.dgn



CK: DW: CK: DW: CK: DW:





**LEGEND**

- CENTERPOINT GAS
- GAS PIPELINE
- GAS METER/VALVE
- OVERHEAD ELECTRIC
- POWER POLE
- FIBEROPTIC
- TELEPHONE PEDESTAL
- ELECTRIC JUNCTION BOX
- WATER
- WATER METER

**NOTES:**

1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*[Signature]* P.E.

04/29/2024



FM 2097


UTILITY LAYOUT

© TxDOT 2023 SHEET 6 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	138	


DATE: 4/26/2024 11:22:20 AM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151264+00 - 288+00 - FM 2097 UTILITIES LAYOUT-10.dgn

CK: DW: CK: DW: CK: DW:




- LEGEND**
- CENTERPOINT GAS -----
  - GAS PIPELINE .....
  - GAS METER/VALVE (G) (X)
  - OVERHEAR ELECTRIC -----
  - POWER POLE (C) (X)
  - FIBEROPTIC -----
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER -----
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*S. Harris* P.E.  
04/29/2024



FM 2097

UTILITY LAYOUT

©TxDOT 2023 SHEET 7 OF 9



CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST		COUNTY	SHEET NO.
BMT		TYLER	139

DATE: 4/26/2024 11:32:27 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151288+00-312+00 - FM 2097 UTILITIES LAYOUT-12.dgn

DATE: 4/26/2024 11:32:27 AM


FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151288+00-312+00 - FM 2097 UTILITIES LAYOUT-12.dgn

CK: DW: CK: DN:



- LEGEND**
- CENTERPOINT GAS ————
  - GAS PIPELINE .....
  - GAS METER/VALVE (B) (X)
  - OVERHEAR ELECTRIC ————
  - POWER POLE (C)
  - FIBEROPTIC - - - - -
  - TELEPHONE PEDESTAL (T)
  - ELECTRIC JUNCTION BOX (E)
  - WATER - - - - -
  - WATER METER (W)

- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*S.J. Harris* P.E.  
04/29/2024



**FM 2097**  
**UTILITY LAYOUT**


©TxDOT 2023		SHEET 8 OF 9	
CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	140	

DATE: 4/26/2024 11:39:46 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151312+00-336+00-FM 2097 UTILITIES LAYOUT-14.dgn


DN: DW: CK: CK: DW: CK: CK:

**LEGEND**


- CENTERPOINT GAS ————
- GAS PIPELINE .....
- GAS METER/VALVE (B) (X)
- OVERHEAR ELECTRIC ————
- POWER POLE (C)
- FIBEROPTIC - - - - -
- TELEPHONE PEDESTAL (T)
- ELECTRIC JUNCTION BOX (E)
- WATER - - - - -
- WATER METER (W)



- NOTES:**
1. UTILITIES SHOWN ARE APPROXIMATE. SUBSURFACE UTILITIES PERFORM 811 CALL PRIOR TO EXCAVATION ACTIVITIES.
  2. USE OF VIBRATORY EQUIPMENT IS PROHIBITED IN THE VICINITY OF UNDERGROUND PIPELINE CROSSINGS.
  3. SEE UTILITY NOTES FOR ADDITIONAL NOTES AND UTILITY CONTACT INFORMATION.



*S.J. Harris* P.E.  
04/29/2024



**FM 2097**  
  
**UTILITY LAYOUT**

©TxDOT 2023 SHEET 9 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	141	

DATE: 4/26/2024 11:50:43 AM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1754151336+00-346+34 - FM 2097 UTILITIES LAYOUT-16.dgn

**NOTES:**

For projects disturbing 5 or more acres, place laminated copies of the TxDOT and Contractor Construction Site Notices and the TxDOT and Contractor Notices of Intent on the SW3P Notification Board.


For projects disturbing between 1 and 5 acres, place laminated copies of the TxDOT and Contractor Construction Site Notices on the SW3P Notification Board.

For projects with an Individual Permit with the US Army Corp of Engineer, place a laminated copy of the Permit Certificate on the Notification Board.

Center all postings.

Notification Boards are to be constructed from chloroplast and placed at a location within the right-of-way but outside the clear zone as directed by the Engineer. This work will not be paid for directly, but will be considered subsidiary to other items.

CSN - Construction Site Notice, Large for projects greater than 5 acres, Small for projects greater than 1 and less than 5 acres.



2.3" Radius, 0.9" Border, White on Blue;  
 [TxDOT PROJECT] E Mod; [SW3P] E Mod; [INFORMATION] E Mod;



**BEAUMONT DISTRICT**  
**SW3P**  
**NOTIFICATION BOARD**  
**DETAIL**  
**(SW3P-B)**

REVISIONS	FHWA TEXAS DIVISION	FEDERAL AID PROJECT NO.	SHEET NO.
© 2022			142
STATE	DISTRICT	COUNTY	
TEXAS	BMT	TYLER	
CONTROL	SECTION	JOB	HIGHWAY NO.
1584	02 013, ETC	EM1745, ETC	

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/26/2024 1:14:58 PM  
 FILE: c:\txdot\p\_w\_online\txdot5\samantha\_harris\d1044298\epic\_6-21-2019.dgn

**I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402**

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1. TxDOT - Beaumont District

No Action Required  Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or as required by the Engineer.
- Comply with TCEQ Permit 150000 as this project is estimated to disturb more than five acres. TxDOT will file for an NOI first under TCEQ Permit 150000 as the Primary Operator. Contractor will be supplied a copy of the NOI and TCEQ Authorization Certificate. Contractor must use the TxDOT information to complete their own NOI per SP 506-003/ SP 007-004. Contractor files a NOI as the Primary Operator for Day-to-Day Operational Control and provides copies of their NOI, TCEQ Authorization Certificate, and Contractor Site Notice to the District. To ensure the Permit reflects a single construction site, the Regulated Entity Number (RN) must be the same for TxDOT and the Contractor. Contact the Beaumont District Construction Office with questions regarding TCEQ Permit 150000.
- Take measures to prevent construction materials and debris including, but not limited to wastewater (i.e., cooling liquid, etc.) associated with concrete removal from entering any inlets, ditches, or waterways.

**II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404**

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions, including Regional conditions for the State of Texas, associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required: Permit # \_\_\_\_\_
- Other Nationwide Permit Required: NWP# \_\_\_\_\_

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

- Permit applies to Dry Creek located at STA 156+96 and tributary to Russell Creek located at STA 126+53 on FM 1745. No work is to occur in Dry Creek located at STA 15+80 on FM 2097.
- Maintain a neat and clean worksite next to the water and do not allow any debris to fall into the water.
- Comply with "Work In or Near Waters/Wetlands Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input type="checkbox"/> Temporary Vegetation	<input type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input checked="" type="checkbox"/> Mulch Filter Berm and Socks	<input checked="" type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	

**III. CULTURAL RESOURCES**

No Action Required  Required Action

Action No.

- Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

**IV. VEGETATION RESOURCES**

No Action Required  Required Action

Action No.

- Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.
- Comply with "Vegetation and Habitat Impacts: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.

**V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.**

No Action Required  Required Action

Action No.

- This project area contains habitat for southern crawfish frog, Big Thicket burrowing crayfish, eastern spotted skunk, long-tailed weasel, northern scarlet snake, eastern box turtle, slender glass lizard, timber rattlesnake, western box turtle, Rafinesque's big eared tricolored bat, big brown bat, eastern red bat, hoary bat, long-sepaled false dragon-head, Mohlenbrock's sedge, scarlet catchfly, Texas ladies tresses, and Monarch Butterfly.
- If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own.
- If caves or sinkholes are discovered on site, cease work in the area and contact the TxDOT Inspector or DEQC for guidance.
- Comply with "Wildlife: Regulatory Requirements and Best Management Practices" section found in the Beaumont District Environmental Field Guide.
- Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and (TPW) Code Section 64.002. For compliance with MBTA and TPW Code, bridge demolition, clearing of vegetation, and tree trimming activities are to be scheduled from October 1 to February 14 (outside of migratory bird nesting season). Contractor is responsible for securing a qualified biologist to conduct a nest survey for any bridge demolition, tree trimming, or vegetation clearing that occurs during migratory bird nesting season. The qualified biologist must submit a survey protocol for approval by District environmental staff prior to construction. A nesting survey will remain valid up to five days. Any activity not completed within 5 days of a nesting survey will require another survey. Migratory bird nesting season is from February 15 to September 30. No removal of active nests is allowed during migratory bird nesting season; therefore, any structure or vegetation containing an active nest may not be disturbed, cleared, or trimmed. No removal of inactive nests is allowed during migratory bird nesting season except by an approved, qualified biologist. are removed prior to the start of nesting season. The full TxDOT MBTA guidance may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/toolkit/350-01-gui.pdf>
- Resource specific BMPs (Section I) from the 'Updated Best Management Practices (BMPs) for TxDOT Maintenance Activities' guidance under the TxDOT Maintenance Program EA shall be reviewed and implemented where appropriate. The maintenance EA BMPs may be found here: <https://ftp.txdot.gov/pub/txdot-info/env/080-01-bmp.pdf>

**LIST OF ABBREVIATIONS**

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NMP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

**VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES**

No Action Required  Required Action

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- \* Dead or distressed vegetation (not identified as normal)
- \* Trash piles, drums, canister, barrels, etc.
- \* Undesirable smells or odors
- \* Evidence of leaching or seepage of substances
- \* Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable. If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

Provide results below:

Structure Location	PSN	Element	Lead	Asbestos
FM 2097 @ Dry Creek	202290227101001	NA	Not Tested	Not Tested

If Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

If Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

Action No.

- Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hazardous materials or contamination is noted during construction.
- Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.


**VII. OTHER ENVIRONMENTAL ISSUES**

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required  Required Action

Action No.

- Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.

		Beaumont District Standard
<h2>ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS</h2> <h3>EPIC</h3>		
FILE: epic.dgn	DW: TxDOT	CK: AM
©TxDOT February 2019	CONT: 1584	SECT: 02
	JOB: 013, ETC.	HIGHWAY: FM1745, ETC
	DIST: BMT	COUNTY: TYLER
		SHEET NO.: 143

Jerrod Justice

APPROVED BY



04/29/2024

DATE

DISTRICT ENVIRONMENTAL DEPARTMENT

CK:  
DW:  
CK:  
DW:

- LEGEND**
- EROSION CONTROL LOGS (ECL)
  - ROCK FILTER DAM TY 2 (RFD2)



**FM 1745**

**SWP3 LAYOUT**



©TxDOT 2024 SHEET 1 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST		COUNTY	SHEET NO.
BMT		TYLER	144


DATE: 4/26/2024 1:57:54 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molina\01187125\BL-CL-101 - FM 1745 SW3P LAYOUTS.dgn



CK: DW: CK: DW:



- LEGEND**
- EROSION CONTROL LOGS (ECL)
  - ROCK FILTER DAM TY 2 (RFD2)



**FM 1745**

**SWP3 LAYOUT**




©TxDOT 2024 SHEET 2 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	145	


DATE: 4/26/2024 2:00:49 PM  
 FILE: c:\txdot\pw\_onlinetxdot5\francisco.molinar\187125\BL-CL-101 - FM 1745 SW3P LAYOUTS-2.dgn

CK: DW: CK: DW:

**LEGEND**  
 EROSION CONTROL LOGS (ECL)  
 ROCK FILTER DAM TY 2 (RFD2)



*[Signature]* P.E.  
05/22/2024



**FM 1745**  
  
**SWP3 LAYOUT**

©TxDOT 2024 SHEET 3 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	146	


DATE: 4/26/2024 2:06:43 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\1187125\BL CL-101 - FM 1745 SW3P LAYOUTS-4.dgn

CK: DW: CK: DN:

LEGEND

EROSION CONTROL LOGS (ECL)

ROCK FILTER DAM TY 2 (RFD2)




SW3P #25,26 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #23,24 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #27,28 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #29,30 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #31,32 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



PE.  
 05/22/2024



FM 1745

SWP3  
 LAYOUT



©TxDOT 2024 SHEET 4 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	147	

DATE: 4/26/2024 2:10:28 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\187125\BL-CL-101 - FM 1745 SW3P LAYOUTS-6.dgn

CK:  
DW:  
CK:  
DW:

**LEGEND**  
 EROSION CONTROL LOGS (ECL)  
 ROCK FILTER DAM TY 2 (RFD2)



STATE OF TEXAS  
 SAMANTHA JO HARRIS  
 134616  
 LICENSED PROFESSIONAL ENGINEER  
 P.E.  
 05/22/2024



Texas Department of Transportation

FM 1745

SWP3 LAYOUT


©TxDOT 2024 SHEET 5 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	148	

DATE: 4/26/2024 2:14:06 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\187125\BL CL-101 - FM 1745 SWP3 LAYOUTS-8.dgn

CK:  
DW:  
CK:  
DW:

**LEGEND**  
 EROSION CONTROL LOGS (ECL)  
 ROCK FILTER DAM TY 2 (RFD2)




SW3P #41, 42 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #43, 44 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #45, 46 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #47, 48 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



Texas Department of Transportation

FM 1745

SWP3 LAYOUT


©TxDOT 2024 SHEET 6 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST		COUNTY	SHEET NO.
BMT		TYLER	149


DATE: 4/26/2024 2:18:16 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\187125\BL CL-101 - FM 1745 SW3P LAYOUTS-10.dgn

DATE: 4/26/2024 2:21:42 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\01187125\BL CL-101 - FM 1745 SW3P LAYOUTS-12.dgn


DW: CK: DW: CK: DW: CK:



- LEGEND**
- EROSION CONTROL LOGS
  - ROCK FILTER DAM TY 2



*[Signature]* P.E.  
 05/22/2024



FM 1745

SWP3  
 LAYOUT




©TxDOT 2024 SHEET 7 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	150	


CK:  
DW:  
CK:  
DN:

LEGEND

- EROSION CONTROL LOGS (ECL)
- ROCK FILTER DAM TY 2 (RFD2)



*[Signature]* P.E.  
04/29/2024



Texas Department of Transportation

**FM 2097**


**SWP3 LAYOUT**

©TxDOT 2024 SHEET 1 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	151	

DATE: 4/26/2024 2:24:52 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\187126146+11.168+00 - FM 2097 SW3P LAYOUT.dgn

CK:  
DW:  
CK:  
DW:




SW3P #11,12 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #13,14 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

**LEGEND**


- EROSION CONTROL LOGS (ECL)
- ROCK FILTER DAM TY 2 (RFD2)




SW3P #15 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #16 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #17,18 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



PE.  
04/29/2024



FM 2097

SWP3  
LAYOUT

©TxDOT 2024 SHEET 2 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	152	

DATE: 4/26/2024 2:29:39 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1187126168+00 - 192+00 - FM 2097 SW3P LAYOUT-2.dgn





CK:  
DW:  
CK:  
DW:


LEGEND

EROSION CONTROL LOGS (ECL)

ROCK FILTER DAM TY 2 (RFD2)



*S. Harris* P.E.  
04/29/2024



FM 2097

SWP3 LAYOUT

©TxDOT 2024 SHEET 3 OF 7

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	153	

DATE: 4/26/2024 2:33:50 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molina\01187126192+00-216+00 - FM 2097 SWP3 LAYOUT-4.dgn

CK:  
DW:  
CK:  
DN:

SW3P #27, 28 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #31, 32 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:


SW3P #29, 30 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #33, 34 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #35, 36 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

LEGEND

- EROSION CONTROL LOGS (ECL)
- ROCK FILTER DAM TY 2 (RFD2)




FM 2097

SWP3 LAYOUT

©TxDOT 2024 SHEET 4 OF 9


CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	154	

DATE: 4/26/2024 2:37:07 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\011871261216+00 - 240+00 - FM 2097 SW3P LAYOUT-6.dgn




CK:  
DW:  
CK:  
DW:

**LEGEND**  
 EROSION CONTROL LOGS (ECL)  
 ROCK FILTER DAM TY 2 (RFD2)




SW3P #37, 38 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



SW3P #39, 40 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #41, 42 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #43, 44 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



*[Signature]* P.E.  
 04/29/2024



Texas Department of Transportation

**FM 2097**

**SWP3 LAYOUT**

© TxDOT 2024 SHEET 5 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013, ETC.	FM1745, ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	155	

DATE: 4/26/2024 2:41:34 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\187126\240+00-264+00 - FM 2097 SWP3 LAYOUT-8.dgn

CK: DW: CK: DW: CK: DW:

LEGEND

EROSION CONTROL LOGS (ECL)

ROCK FILTER DAM TY 2 (RFD2)

MATCHLINE STA. 19+92.00

MATCHLINE STA. 132+00.00

121+00 122+00 123+00 124+00 125+00 126+00 127+00 128+00 129+00 130+00 131+00

SW3P #45,46 EROSION CONTROL LOGS - 20FT  
INSTALLED DATE:  
INSPECTOR INITIAL:  
REMOVED DATE:  
INSPECTOR INITIAL:

SW3P #47,48 EROSION CONTROL LOGS - 20FT  
INSTALLED DATE:  
INSPECTOR INITIAL:  
REMOVED DATE:  
INSPECTOR INITIAL:

SW3P #49,50 EROSION CONTROL LOGS - 20FT  
INSTALLED DATE:  
INSPECTOR INITIAL:  
REMOVED DATE:  
INSPECTOR INITIAL:



SW3P #53,54 EROSION CONTROL LOGS - 20FT  
INSTALLED DATE:  
INSPECTOR INITIAL:  
REMOVED DATE:  
INSPECTOR INITIAL:

SW3P #51,52 EROSION CONTROL LOGS - 20FT  
INSTALLED DATE:  
INSPECTOR INITIAL:  
REMOVED DATE:  
INSPECTOR INITIAL:


SW3P #55,56 EROSION CONTROL LOGS - 20FT  
INSTALLED DATE:  
INSPECTOR INITIAL:  
REMOVED DATE:  
INSPECTOR INITIAL:

MATCHLINE STA. 131+92.00

MATCHLINE STA. 144+00.00



PE.  
04/29/2024



FM 2097

SWP3  
LAYOUT


©TxDOT 2024 SHEET 6 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST		COUNTY	SHEET NO.
BMT		TYLER	156

DATE: 4/26/2024 2:45:21 PM  
FILE: c:\txdot\pw\_online\txdot5\francisco.molina\011871261264+00 - 288+00 - FM 2097\_SW3P LAYOUT-10.dgn


CK:  
DW:  
CK:  
DN:

**LEGEND**  
EROSION CONTROL LOGS (ECL)  
ROCK FILTER DAM TY 2 (RFD2)



SW3P #57,58 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:


SW3P #59,60 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



SW3P #61,62 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #65,66 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #63,64 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



*S. Harris* P.E.  
04/29/2024



FM 2097

SWP3  
LAYOUT

©TxDOT 2024 SHEET 7 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	157	


DATE: 4/26/2024 2:48:59 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molinar\1871261288+00-312+00 - FM 2097 - SW3P\_LAYOUT-12.dgn

CK: DW: CK: DN:

**LEGEND**


EROSION CONTROL LOGS 

ROCK FILTER DAM TY 2 




SW3P #67, 68 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #69, 70 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:





SW3P #71, 72 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #73, 74 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



*S. Harris* P.E.  
 04/29/2024



 **Texas Department of Transportation**

**FM 2097**

**SWP3 LAYOUT**


©TxDOT 2024 SHEET 8 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST	COUNTY	SHEET NO.	
BMT	TYLER	158	

DATE: 4/26/2024 2:52:04 PM  
 FILE: c:\txdot\pw\_online\txdot5\francisco.molina\1871261312+00-336+00 - FM 2097 SW3P LAYOUT-14.dgn


CK:  
DW:  
CK:  
DW:

**LEGEND**  
 EROSION CONTROL LOGS (ECL)  
 ROCK FILTER DAM TY 2 (RFD2)




SW3P #75,76 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:

SW3P #77,78 EROSION CONTROL LOGS - 20FT  
 INSTALLED DATE:  
 INSPECTOR INITIAL:  
 REMOVED DATE:  
 INSPECTOR INITIAL:



*[Signature]* P.E.  
 04/29/2024



Texas Department of Transportation

FM 2097

SWP3  
 LAYOUT


©TxDOT 2024 SHEET 9 OF 9

CONT	SECT	JOB	HIGHWAY
1584	02	013,ETC.	FM1745,ETC
DIST		COUNTY	SHEET NO.
BMT		TYLER	159

DATE: 4/26/2024 2:56:15 PM  
 FILE: c:\txdot\pw\_onlinetxdat5\francisco.molinar\011871261336+00-346+34 - FM 2097 SW3P LAYOUT-16.dgn


DISCLAIMER: This standard is made by TxDOT for any purpose whatsoever. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for incorrect results or damages resulting from its use.

402862024  
 c:\ttdot\pw\_online\txdot5\francisco.molinar\d1044298\ec116.dgn



**TEMPORARY SEDIMENT CONTROL FENCE**

SCF



**HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL**

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

**SEDIMENT CONTROL FENCE USAGE GUIDELINES**

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT<sup>2</sup>. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


**LEGEND**

Sediment Control Fence

SCF

**GENERAL NOTES**


1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



				Design Division Standard	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE &amp; VERTICAL TRACKING</b> <b>EC(1) - 16</b>					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	1584	02	013, ETC.	FM1745, ETC	
	DIST	COUNTY		SHEET NO.	
	BMT	TYLER		160	




DATE: 4/26/2024  
 FILE: c:\txdot\pw\_online\txdot5\francis.sco.molinar\d1044298\ec216.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**FILTER DAM AT TOE OF SLOPE**

(RFD1)




**FILTER DAM AT SEDIMENT TRAP**

(RFD1) OR (RFD2)




**FILTER DAM AT CHANNEL SECTIONS**

(RFD1) OR (RFD2) OR (RFD3)




**"V" SHAPE PLAN VIEW**




**PLAN VIEW**

**TYPE 4 (SACK GABIONS)**


(RFD4)




**SECTION B-B**



**SECTION A-A**



**PROFILE**



**SECTION C-C**

**ROCK FILTER DAM USAGE GUIDELINES**

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT<sup>2</sup> of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

**Type 1** (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

**Type 2** (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

**Type 3** (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

**Type 4** (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

**Type 5:** Provide rock filter dams as shown on plans.

**GENERAL NOTES**


1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4"
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

**PLAN SHEET LEGEND**


- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)

		<b>Design Division Standard</b>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>ROCK FILTER DAMS</b> <b>EC(2) - 16</b>			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	1584	02	013, ETC.
	DIST	COUNTY	SHEET NO.
	BMT	TYLER	161


DATE: 4/26/2024  
 FILE: c:\txdot\p\_w\_online\txdot5\francis.sco.molinar\d1044298\ec916.dgn  
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PLAN VIEW



PLAN VIEW




PLAN VIEW



SECTION A-A

EROSION CONTROL LOG DAM


CL-D



SECTION B-B

EROSION CONTROL LOG AT BACK OF CURB


CL-BOC



SECTION C-C


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

CL-ROW



DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

- LEGEND**
- CL-D EROSION CONTROL LOG DAM
  - CL-BOC EROSION CONTROL LOG AT BACK OF CURB
  - CL-ROW EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY
  - CL-SST EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING
  - CL-SSL EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING
  - CL-DI EROSION CONTROL LOG AT DROP INLET
  - CL-CI EROSION CONTROL LOG AT CURB INLET
  - CL-GI EROSION CONTROL LOG AT CURB & GRATE INLET



REBAR STAKE DETAIL

**SEDIMENT BASIN & TRAP USAGE GUIDELINES**

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.

**Log Traps:** The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min. 500' on center
2. Immediately preceding ditch inlets or drain inlets
3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

**GENERAL NOTES:**


1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
4. FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
5. STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
6. DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.
7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
9. TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE LOG.
10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SHEET 1 OF 3

		<i>Design Division Standard</i>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT SECT	JOB	HIGHWAY
REVISIONS	1584 02	013, ETC.	FM1745, ETC
	DIST	COUNTY	SHEET NO.
	BMT	TYLER	162


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/26/2024  
 FILE: c:\txdot\pw\_online\txdot5\francis.sco.molinar\d1044298\ec916.dgn




**EROSION CONTROL LOGS ON SLOPES  
STAKE AND TRENCHING ANCHORING**

CL-SST




SLOPE	LOG DIAMETER			
	6"	8"	12"	18"
1:1 OR STEEPER	5'	10'	15'	20'
2:1	10'	20'	30'	40'
3:1	15'	30'	45'	60'
4:1 OR FLATTER	20'	40'	60'	80'

\* ADJUSTMENTS CAN BE MADE FOR SOIL TYPE:  
 SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER;  
 HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART




**EROSION CONTROL LOGS ON SLOPES  
STAKE AND LASHING ANCHORING**

CL-SSL





**STAKE AND TRENCHING ANCHORING DETAIL**

CL-SST



**STAKE AND LASHING ANCHORING DETAIL**

CL-SSL



**STAKE NOTCH DETAIL**


LOG DIAMETER	DEPTH
6"	2"
8"	3"
12"	4"
18"	5"

SHEET 2 OF 3

		Design Division Standard	
<b>TEMPORARY EROSION,          SEDIMENT AND WATER          POLLUTION CONTROL MEASURES          EROSION CONTROL LOG          EC(9) - 16</b>			
FILE: ec116	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	1584	02	013, ETC.
DIST	COUNTY	SHEET NO.	
BMT	TYLER	163	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 4/26/2024  
 FILE: c:\txdot\pw\_online\txdot5\francis.sco.molinar\d1044298\ec916.dgn




**EROSION CONTROL LOG AT DROP INLET**

CL-DI



**EROSION CONTROL LOG AT CURB INLET**


CL-CI



**EROSION CONTROL LOG AT CURB INLET**


CL-CI

NOTE:  
 EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



**EROSION CONTROL LOG AT CURB & GRADE INLET**

CL-GI



SHEET 3 OF 3

		<i>Design Division Standard</i>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES</b> <b>EROSION CONTROL LOG</b> <b>EC (9) - 16</b>			
FILE: ec916	DN: TxDOT	CK: KM	DW: LS/PT
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS	1584	02	013, ETC.
DIST	COUNTY		SHEET NO.
BMT	TYLER		164

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with soil disturbing activity and for projects that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**

1584-02-013, 2271-01-011

**1.2 PROJECT LIMITS:**

From: Polk County Line, East to SH 287 and from SH 287, East

To: End of Maintenance

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) 30.9020129, (Long) -94.6325748

END: (Lat) 30.9702447, (Long) -94.5993059

**1.4 TOTAL PROJECT AREA (Acres):** 165.4

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** 25.3

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

Roadway Widening, Culvert Extension, Installation of SETs

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
DoB - Doucette Loamy Sand	Well Drained 1 to 5% slopes
ReB - Redco Clay	Moderately Well Drained 1 to 3% slopes
WnB - Woodville Very Fine Sandy Loam	Somewhat Poorly Drained 1 to 5% slopes
WnD - Woodvill Fine Sandy Loam	Somewhat Poorly Drained 1 to 5% slopes
HhD - Hillister Loamy Sand	Well Drained 5 to 15% slopes
BuB - Burkeville Clay	Well Drained 3 to 5% slopes
WcB - Wiergate Clay	Somewhat Poorly Drained 1 to 3% slopes

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste

- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Dry Creek, Russel Creek	*0604 - Neches River Below Lake Palestine - Impared: 5c - Bacteria 5b - Depressed dissolved oxygen

\* Add (\*) for impaired waterbodies with pollutant in ( ).

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years

- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_


**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
- Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years

- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity



**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

© 2023 July 2023 Sheet 1 of 2  
Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
			165
STATE	STATE DIST.	COUNTY	
TEXAS	BMT	TYLER	
CONT.	SECT.	JOB	HIGHWAY NO.
1584	02	013, ETC.	FM1745, ETC.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

**T / P**

- Sediment Trap
  - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
  - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
  - Not required (<10 acres disturbed)
  - Required (>10 acres) and implemented.
    - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
    - 3,600 cubic feet of storage per acre drained
- Required (>10 acres), but not feasible due to:
  - Available area/Site geometry
  - Site slope/Drainage patterns
  - Site soils/Geotechnical factors
  - Public safety
  - Other: \_\_\_\_\_

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 DEWATERING:**

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.


**2.9 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

When dewatering activities are present, a daily inspection will be conducted once per day during those activities and documented in accordance with CGP and TxDOT requirements.

**2.10 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.



*[Signature]* P.E.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

© 2023 July 2023 Sheet 2 of 2

Texas Department of Transportation

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
			166
STATE	STATE DIST.	COUNTY	
TEXAS	BMT	TYLER	
CONT.	SECT.	JOB	HIGHWAY NO.
1584	02	013, ETC.	FM1745, ETC.