

INDEX OF SHEETS

SEE SHEET NO. 2

**STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION**

FUNCTIONAL CLASS = PRINCIPAL ARTERIAL

FEDERAL-AID PROJECT NUMBER			
F2B24(366)			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		1

FINAL PLANS

Letting Date: _____

Name of Contractor: _____

Date Work Began: _____

Date Work Completed: _____

Date Work Accepted: _____

Final Contract Cost: _____

**PLANS OF PROPOSED
STATE HIGHWAY IMPROVEMENT**

FEDERAL AID PROJECT NO. F2B24(366)


**US 87
TOM GREEN COUNTY**

**REPLACE TRAFFIC SIGNAL AND
PEDESTRIAN IMPROVEMENTS**


Project was built according to the Plans & Specifications. These final plans reflect the work done and the quantities shown thereon and on the Final Estimate are Final Quantities.

Area Engineer _____ Date _____

LOCATION NO.	HIGHWAY	CONTROL NO.	LIMITS	2022/2042 ADT	REFERENCE MARKERS		TOTAL LENGTH	BRIDGE LENGTH	RDWY LENGTH
					BEGIN	END			
1	N BRYANT BLVD	0069-07-116	FROM: AT W 23RD ST	21,307/31,961	RM 466+0.883 MI	RM 466+0.909 MI	0.026	0.000	0.026
2	S KOENIGHEIM ST	0069-07-117	FROM: AT W HARRIS AVE	26,359/36,903	RM 468+0.309 MI	RM 468+0.386 MI	0.076	0.000	0.076
3	ABE ST	0069-07-117	FROM: AT W HARRIS AVE						
4	ABE ST	0069-07-118	FROM: AT CONCHO AVE	31,549/44,169	RM 468+0.613 MI	RM 468+0.648 MI	0.034	0.000	0.034
5	S BRYANT BLVD	0070-02-100	FROM: S JACKSON ST	20,556/28,788	RM 470+0.832 MI	RM 470+0.860 MI	0.028	0.000	0.028



Summary of Change Orders:



**Registered Accessibility Specialist
(RAS) inspection required**

TDLR PROJECT NO. TABS2024021971

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, NOVEMBER 1, 2014 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023).

EXCEPTIONS
NONE

EQUATIONS
NONE

RAILROAD CROSSINGS
NONE



SUBMITTED FOR LETTING: 5/30/2024

DocuSigned by:
Nicholas Greenly
DDF89C6522AF49E...
District Design Engineer

RECOMMENDED FOR LETTING: 5/30/2024

DocuSigned by:
John L. ... P.E.
826185212F51427...
District Director of TP&D

APPROVED FOR LETTING: 5/31/2024

DocuSigned by:
...
BC10B17FA709437...
District Engineer

SHEET	GENERAL
1	TITLE SHEET
2	INDEX OF SHEETS
3	SAN ANGELO LOCATION MAP
4 - 7	SURVEY CONTROL SHEETS
8	QUANTITIES
9	SUMMARY OF SMALL SIGNS
10 - 10B	GENERAL NOTES
11A - 11C	ESTIMATE AND QUANTITY SHEET

SHEET	TRAFFIC CONTROL PLANS
STANDARDS	
12 - 23	#TXDOT BC(1-12)-21
24 - 28	#TXDOT TCP(1-(1-5))-18
29 - 30	#TXDOT TCP(2-(1-2))-18
31	#TXDOT TCP(2-3)-23
32 - 34	#TXDOT TCP(2-(4-6))-18
35	#TXDOT TCP(2-8)-23
36	#TXDOT WZ(BRK)-13
37 - 38	#TXDOT WZ(BTS-(1-2))-13
39	#TXDOT WZ(STPM)-23
40	#TXDOT TRAFFIC CONTROL PLAN GENERAL REQUIREMENTS
41	#TXDOT TRAFFIC CONTROL PLAN WORK SPACE NEAR SHOULDER

SHEET	TRAFFIC
42	SIGNAL CONSTRUCTION NOTES
43	EXISTING CONDITIONS AND REMOVALS BRYANT AT 23RD
44	SIGNAL LAYOUTS BRYANT AT 23RD
45 - 46	CONDUITS, CABLES AND QUANTITIES BRYANT AT 23RD
47	SIGN DETAILS BRYANT AT 23RD
48	PAVEMENT MARKINGS AND PEDESTRIAN RAMPS BRYANT AT 23RD
49	EXISTING CONDITIONS AND REMOVALS KOENIGHEIM AT HARRIS
50	SIGNAL LAYOUTS KOENIGHEIM AT HARRIS
51 - 52	CONDUITS, CABLES AND QUANTITIES KOENIGHEIM AT HARRIS
53	SIGN DETAILS KOENIGHEIM AT HARRIS
54	PAVEMENT MARKINGS AND PEDESTRIAN RAMPS KOENIGHEIM AT HARRIS
55	EXISTING CONDITIONS AND REMOVALS ABE AT HARRIS
56	SIGNAL LAYOUTS ABE AT HARRIS
57 - 58	CONDUITS, CABLES AND QUANTITIES ABE AT HARRIS
59	SIGN DETAILS ABE AT HARRIS
60	PAVEMENT MARKINGS AND PEDESTRIAN RAMPS ABE AT HARRIS
61	EXISTING CONDITIONS AND REMOVALS ABE AT CONCHO
62	SIGNAL LAYOUTS ABE AT CONCHO
63 - 64	CONDUITS, CABLES AND QUANTITIES ABE AT CONCHO
65	SIGN DETAILS ABE AT CONCHO
66	PAVEMENT MARKINGS AND PEDESTRIAN RAMPS ABE AT CONCHO
67	EXISTING CONDITIONS AND REMOVALS BRYANT AT JACKSON
68	SIGNAL LAYOUTS BRYANT AT JACKSON
69 - 70	CONDUITS, CABLES AND QUANTITIES BRYANT AT JACKSON
71	SIGN DETAILS BRYANT AT JACKSON
72	PAVEMENT MARKINGS AND PEDESTRIAN RAMPS BRYANT AT JACKSON


STANDARDS	
73 - 84	#TXDOT ED(1-12)-14
85	#TXDOT TS-FD-12
86	#TXDOT TS-CF-21
87	#TXDOT TS-BP-20
88 - 89	#TXDOT SMA-80(1-2)-12
90 - 94	#TXDOT LMA(1-5)-12
95	#TXDOT MA-C-12
96	#TXDOT MA-D-12
97	#TXDOT MA-DPD-20
98	#TXDOT LUM-A-12
99	#TXDOT CFA-12
100	#TXDOT WV & IZ-14
101	#TXDOT TRAFFIC SIGNAL DETAILS
102	#TXDOT VIVDS CAMERA DETAILS
103	#TXDOT MTS-18
103 - 106	#TXDOT PM(1-3)-22
107	#TXDOT PM(4)-22A
108	#TXDOT PAVEMENT MARKING DETAILS (URBAN)
109	#TXDOT SMD(GEN)-08
110 - 112	#TXDOT SMD(SLIP-(1-3))
113 - 114	#TXDOT TSR(3-4)-13
115	#TXDOT CONCRETE RIPRAP FOR SMALL SIGN ASSEMBLIES
116	#TXDOT CCGG-22
117 - 120	#TXDOT PED-18
121 - 123	#TXDOT PRD-13
124	#TXDOT CURB DETAILS
125	#TXDOT SIDEWALK DETAILS
126	#TXDOT UTILITY ADJUSTMENT DETAILS

SHEET	ENVIRONMENT
127 - 128	STORMWATER POLLUTION PREVENTION PLAN
129	EPIC

DATE: 5/28/2024 1:02:33 PM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38151\td10240091aa_index.dgn

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE BY A #
HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

Bryce Jamir P.E.



05/28/2024
DATE

5/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87


INDEX OF SHEETS

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	2	


DATE: 6/25/2024 8:56:57 AM
 FILE: c:\pwworking\freese-pw.bentley.com_freese-pw-01\dms38151\td10240091ab_prj\01.dgn





NOT TO SCALE




LOCATION 1
 CSJ: 0069-07-116
 N BRYANT BLVD AT W 23RD ST
 RM 466+0.883 MI TO
 RM 466+0.909 MI




LOCATION 3
 CSJ: 0069-07-117
 ABE ST AT
 W HARRIS AVE
 RM 468+0.309 MI TO
 RM 468+0.386 MI



LOCATION 2
 CSJ: 0069-07-117
 S KOENIGHEIM ST AT
 W HARRIS AVE
 RM 468+0.309 MI TO
 RM 468+0.386 MI



LOCATION 4
 CSJ: 0069-07-118
 ABE ST AT
 CONCHO AVE
 RM 468+0.613 MI TO
 RM 468+0.648 MI



LOCATION 5
 CSJ: 0070-02-100
 S BRYANT BLVD ST AT
 JACKSON ST
 RM 470+0.832 MI TO
 RM 470+0.860 MI



6/25/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144





US 87
 SAN ANGELO
 LOCATION MAP

© TxDOT 2024


CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		3

CK:
DW:
CK:
DW:

CONTROL POINT	SURFACE COORDINATES		GRID COORDINATES		LATITUDE	LONGITUDE	ELEVATION	DESCRIPTION
	NORTHING	EASTING	NORTHING	EASTING				
136	10,504,052.78	2,258,480.07	10,501,952.39	2,258,028.46	31.479771906	-100.457014562	1,864.63'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
137	10,504,186.46	2,258,683.84	10,502,086.04	2,258,232.19	31.480139970	-100.456361475	1,867.52'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
138	10,504,238.62	2,258,626.51	10,502,138.19	2,258,174.87	31.480283168	-100.456545541	1,868.05'	SET "X" CUT IN CONCRETE
139	10,504,068.70	2,258,789.21	10,501,968.31	2,258,337.54	31.479816611	-100.456023115	1,864.94'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
140	10,504,386.17	2,258,831.94	10,502,285.71	2,258,380.26	31.480689343	-100.455887180	1,870.50'	SET MAG NAIL WITH WASHER STAMPED "GORRONDONA & ASSOC FT WORTH"
141	10,504,346.71	2,258,505.67	10,502,246.26	2,258,054.06	31.480579908	-100.456933500	1,866.47'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"



I, CHRIS T. ABBOTT, A REGISTERED PROFESSIONAL LAND SURVEYOR, DO HERBY DECLARE THAT THE SURVEY CONTROL FOR THIS PROJECT WAS COMPLETED UNDER MY SUPERVISION.



CHRIS T. ABBOTT
REGISTERED PROFESSIONAL LAND SURVEYOR TEXAS NO. 6407



- NOTES:
1. ALL BEARINGS AND COORDINATES ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983 TEXAS CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (NAD83), 2011 ADJUSTMENT, (EPOCH 2010). ALL DISTANCES AND HORIZONTAL COORDINATES ARE SURFACE VALUES AND MAY BE CONVERTED TO GRID BY DIVIDING BY A COMBINED ADJUSTMENT FACTOR OF 1.0002.
 2. ALL SECONDARY HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED USING GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA). ALL HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED BY PERFORMING MULTIPLE 180 EPOCH OBSERVATIONS.
 3. UNIT OF MEASUREMENT IS U.S. SURVEY FOOT.
 4. VERTICAL DATUM IS NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88), BASED ON GEOID18 DERIVED ORTHOMETRIC HEIGHTS FROM GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA).
 5. FIELD SURVEYS WERE PERFORMED DURING FEBRUARY 2024

DATE: 5/20/2024 1:19:50 PM
FILE: 006907116-US-87 AT W. 23RD STREET.dgn

US 87 @ W. 23RD STREET					
FED. RD. DIV. NO.	COUNTY	CONT	SEC	JOB	HIGHWAY
6	TOM GREEN	0069	07	116	US 87
STATE DIST. NO.	STATE	FEDERAL AID PROJECT NO.		SHEET	
7	TEXAS	SEE TITLE SHEET		4	

DATE: 5/20/2024 2:34:22 PM
 FILE: 006907117-US 87 AT W. HARRIS AVENUE.dgn

CONTROL POINT	SURFACE COORDINATES		GRID COORDINATES		LATITUDE	LONGITUDE	ELEVATION	DESCRIPTION
	NORTHING	EASTING	NORTHING	EASTING				
107	10,497,233.39	2,262,402.64	10,495,134.36	2,261,950.24	31.461039054	-100.444411931	1,842.93'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
108	10,497,483.57	2,262,620.48	10,495,384.49	2,262,168.05	31.461727316	-100.443714174	1,844.25'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
109	10,497,402.48	2,262,432.38	10,495,303.42	2,261,979.99	31.461503915	-100.444317087	1,845.23'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
110	10,497,315.07	2,262,166.89	10,495,216.03	2,261,714.55	31.461262936	-100.445168140	1,841.98'	SET MAG NAIL WITH WASHER STAMPED "GORRONDONA & ASSOC FT WORTH"
111	10,497,465.04	2,262,307.85	10,495,365.97	2,261,855.48	31.461675538	-100.444716627	1,844.24'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
112	10,497,561.62	2,262,372.02	10,495,462.53	2,261,919.63	31.461941192	-100.444511161	1,845.71'	SET "X" CUT IN CONCRETE
113	10,497,817.49	2,262,819.54	10,495,718.34	2,262,367.07	31.462645700	-100.443076906	1,846.83'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
114	10,497,614.52	2,262,730.18	10,495,515.41	2,262,277.73	31.462087554	-100.443362810	1,846.39'	SET "X" CUT IN CONCRETE
115	10,497,696.89	2,262,959.08	10,495,597.77	2,262,506.58	31.462314604	-100.442629059	1,845.69'	SET "X" CUT IN CONCRETE
116	10,497,674.97	2,263,155.80	10,495,575.86	2,262,703.26	31.462254874	-100.441998181	1,845.34'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
117	10,497,357.12	2,262,994.67	10,495,258.07	2,262,542.16	31.461380781	-100.442513866	1,845.81'	SET "X" CUT IN CONCRETE



I, CHRIS T. ABBOTT, A REGISTERED PROFESSIONAL LAND SURVEYOR, DO HERBY DECLARE THAT THE SURVEY CONTROL FOR THIS PROJECT WAS COMPLETED UNDER MY SUPERVISION.

CHRIS T. ABBOTT
 REGISTERED PROFESSIONAL LAND SURVEYOR TEXAS NO. 6407

- NOTES:
- ALL BEARINGS AND COORDINATES ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983 TEXAS CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (NAD83), 2011 ADJUSTMENT, (EPOCH 2010). ALL DISTANCES AND HORIZONTAL COORDINATES ARE SURFACE VALUES AND MAY BE CONVERTED TO GRID BY DIVIDING BY A COMBINED ADJUSTMENT FACTOR OF 1.0002.
 - ALL SECONDARY HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED USING GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA). ALL HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED BY PERFORMING MULTIPLE 180 EPOCH OBSERVATIONS.
 - UNIT OF MEASUREMENT IS U. S. SURVEY FOOT.
 - VERTICAL DATUM IS NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88), BASED ON GEOID18 DERIVED ORTHOMETRIC HEIGHTS FROM GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA).
 - FIELD SURVEYS WERE PERFORMED DURING FEBRUARY 2024

GORRONDONA & ASSOCIATES, INC.
 2800 NE LOOP 820, SUITE 660
 FORT WORTH, TX 76137
 FIRM NO. 10106900 / PH. 817-496-1424



© 2024
 Texas Department of Transportation

US 87 @
 W. HARRIS AVENUE

FED. RD. DIV. NO.	COUNTY	CONT	SEC	JOB	HIGHWAY
6	TOM GREEN	0069	07	116	BUS 67
STATE DIST. NO.	STATE	FEDERAL AID PROJECT NO.		SHEET	
7	TEXAS	SEE TITLE SHEET		5	

CK:
DW:
CK:
DW:

CONTROL POINT	SURFACE COORDINATES		GRID COORDINATES		LATITUDE	LONGITUDE	ELEVATION	DESCRIPTION
	NORTHING	EASTING	NORTHING	EASTING				
118	10,496,224.48	2,262,765.42	10,494,125.65	2,262,312.95	31.458266880	-100.443245418	1,835.93'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
119	10,496,085.36	2,262,907.62	10,493,986.56	2,262,455.13	31.457884884	-100.442788984	1,833.36'	SET "X" CUT IN CONCRETE
120	10,496,090.63	2,263,081.85	10,493,991.84	2,262,629.33	31.457899850	-100.442230333	1,833.17'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
121	10,495,858.76	2,262,895.25	10,493,760.01	2,262,442.76	31.457262006	-100.442827937	1,831.60'	SET "X" CUT IN CONCRETE
122	10,495,999.11	2,262,674.80	10,493,900.33	2,262,222.36	31.457647170	-100.443535271	1,837.45'	SET "X" CUT IN CONCRETE
123	10,495,998.15	2,262,845.98	10,493,899.37	2,262,393.50	31.457644991	-100.442986382	1,833.05'	SET "X" CUT IN CONCRETE



I, CHRIS T. ABBOTT, A REGISTERED PROFESSIONAL LAND SURVEYOR, DO HERBY DECLARE THAT THE SURVEY CONTROL FOR THIS PROJECT WAS COMPLETED UNDER MY SUPERVISION.

- NOTES:
1. ALL BEARINGS AND COORDINATES ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983 TEXAS CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (NAD83), 2011 ADJUSTMENT, (EPOCH 2010). ALL DISTANCES AND HORIZONTAL COORDINATES ARE SURFACE VALUES AND MAY BE CONVERTED TO GRID BY DIVIDING BY A COMBINED ADJUSTMENT FACTOR OF 1.0002.
 2. ALL SECONDARY HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED USING GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA). ALL HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED BY PERFORMING MULTIPLE 180 EPOCH OBSERVATIONS.
 3. UNIT OF MEASUREMENT IS U.S. SURVEY FOOT.
 4. VERTICAL DATUM IS NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88), BASED ON GEOID18 DERIVED ORTHOMETRIC HEIGHTS FROM GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA).
 5. FIELD SURVEYS WERE PERFORMED DURING FEBRUARY 2024

DATE: 5/20/2024 1:09:27 PM
FILE: 006907118-US 87 AT W. CONCHO AVENUE.dgn

GORRONDONA & ASSOCIATES, INC.
2800 NE LOOP 820, SUITE 660
FORT WORTH, TX 76137
FIRM NO. 10106900 / PH. 817-496-1424



© 2024
Texas Department of Transportation

US 87 @ W. CONCHO AVENUE

FED. RD. DIV. NO.	COUNTY	CONT	SEC	JOB	HIGHWAY
6	TOM GREEN	0069	07	116	US 87
STATE DIST. NO.	STATE	FEDERAL AID PROJECT NO.		SHEET	
7	TEXAS	SEE TITLE SHEET		6	

CK:
DW:
CK:
DW:

CONTROL POINT	SURFACE COORDINATES		GRID COORDINATES		LATITUDE	LONGITUDE	ELEVATION	DESCRIPTION
	NORTHING	EASTING	NORTHING	EASTING				
124	10,484,230.84	2,263,126.22	10,482,134.41	2,262,673.68	31.425301085	-100.442050902	1,836.68'	SET MAG NAIL WITH WASHER STAMPED "GORRONDONA & ASSOC FT WORTH"
125	10,484,297.55	2,263,255.96	10,482,201.11	2,262,803.40	31.425484791	-100.441635222	1,837.94'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
126	10,484,465.03	2,263,325.43	10,482,368.56	2,262,872.86	31.425945337	-100.441413054	1,837.01'	SET "X" CUT IN CONCRETE
127	10,484,001.59	2,263,345.31	10,481,905.21	2,262,892.73	31.424671526	-100.441347893	1,844.13'	SET "X" CUT IN CONCRETE
128	10,484,208.68	2,263,416.07	10,482,112.25	2,262,963.48	31.425240938	-100.441121717	1,840.77'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"
129	10,484,294.10	2,263,565.72	10,482,197.66	2,263,113.10	31.425476144	-100.440642302	1,840.37'	SET 5/8" IRON ROD WITH CAP STAMPED "REFERENCE POINT"



I, CHRIS T. ABBOTT, A REGISTERED PROFESSIONAL LAND SURVEYOR, DO HERBY DECLARE THAT THE SURVEY CONTROL FOR THIS PROJECT WAS COMPLETED UNDER MY SUPERVISION.



- NOTES:
1. ALL BEARINGS AND COORDINATES ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983 TEXAS CENTRAL ZONE (4203), NORTH AMERICAN DATUM OF 1983 (NAD83), 2011 ADJUSTMENT, (EPOCH 2010). ALL DISTANCES AND HORIZONTAL COORDINATES ARE SURFACE VALUES AND MAY BE CONVERTED TO GRID BY DIVIDING BY A COMBINED ADJUSTMENT FACTOR OF 1.0002.
 2. ALL SECONDARY HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED USING GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA). ALL HORIZONTAL CONTROL FOR THIS PROJECT WAS ESTABLISHED BY PERFORMING MULTIPLE 180 EPOCH OBSERVATIONS.
 3. UNIT OF MEASUREMENT IS U.S. SURVEY FOOT.
 4. VERTICAL DATUM IS NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88), BASED ON GEOID18 DERIVED ORTHOMETRIC HEIGHTS FROM GPS OBSERVATIONS UTILIZING THE TXDOT REGIONAL REFERENCE POINT SAN ANGELO (TXSA).
 5. FIELD SURVEYS WERE PERFORMED DURING FEBRUARY 2024

DATE: 5/20/2024 1:01:34 PM
FILE: 007002100-US 87 AT S. JACKSON STREET.dgn

GORRONDONA & ASSOCIATES, INC.
2800 NE LOOP 820, SUITE 660
FORT WORTH, TX 76137
FIRM NO. 10106900 / PH. 817-496-1424

© 2024
Texas Department of Transportation

US 87 @ S. JACKSON STREET

FED. RD. DIV. NO.	COUNTY	CONT	SEC	JOB	HIGHWAY
6	TOM GREEN	0070	02	116	US 87
STATE DIST. NO.	STATE	FEDERAL AID PROJECT NO.		SHEET	
7	TEXAS	SEE TITLE SHEET		7	

CC: BG
 DW: TA
 CC: BG
 DW: MS

SIGNING AND PAVEMENT MARKING ITEMS														
INTERSECTION	ITEM 105	ITEM 636	ITEM 644	6036	6048	6054	6078	6225	ITEM 666	6230	6231	6232	6306	6309
	6011	6001	6004						6226					
	REMOVING STAB BASE AND ASPH PAV	ALUMINUM SIGNS (TY A)	IN SM RD SN SUP&AM TY10BWG (1) SA (T)						REFL PAV MRK TY I (W)8"(SLD)(100MIL)					
SY	SF	EA	LF	EA	EA	EA	LF	LF	LF	EA	EA	LF		
BRYANT AT 23RD		46	6	329	384	4	4	852	329	384	4	4	722	51
KOENIGHEIM AT HARRIS					395			290		395			1160	
ABE AT HARRIS					384			281		384			1122	
ABE AT CONCHO		18	2		316			355		316			1127	73
BRYANT AT JACKSON	19	46	6	339	507	4	4	934	339	507	4	4	1017	
TOTAL	19	110	14	668	1986	8	8	2712	668	1986	8	8	5148	124

SIGNING AND PAVEMENT MARKING ITEMS															
INTERSECTION	ITEM 666	ITEM 672	ITEM 677				ITEM 432	ITEM 529	ITEM 690						
	6321	6010	6001	6002	6007	6008	6012	6002	6021	6054	6056	6057	6059	6060	6062
	RE PM W/RET REQ TY I (Y) 6" (SLD) (100MIL)	REFL PAV MRK TY II-C-R	ELIM EXT PAV MRK & MRKS (4")	ELIM EXT PAV MRK & MRKS (6")	ELIM EXT PAV MRK & MRKS (24")	ELIM EXT PAV MRK & MRKS (ARROW)	ELIM EXT PAV MRK & MRKS (WORD)	RIPRAP (CONC)(4 IN)	CONCRETE CURB AND GUTTER (SLOTTED)	REMOVAL OF CURBS	INSTALL OF CURBS	REMOVAL OF PEDESTRIAN RAMPS	INSTALL OF PEDESTRIAN RAMPS	REMOVAL OF SIDEWALK	INSTALL OF SIDEWALK
LF	EA	LF	LF	LF	EA	EA	CY	LF	LF	LF	EA	EA	SF	SF	
BRYANT AT 23RD	620	9	1308	339	423	2	2	1.6		56	33	2	4	355	208
KOENIGHEIM AT HARRIS		15	1065		756			1.6		103	98	5	5	737	206
ABE AT HARRIS		14	1073		870			0.6		32	27	4	4	290	427
ABE AT CONCHO		14	1081		660			0.4	10	41	64	2	4	304	140
BRYANT AT JACKSON	680	13	1813	419	151	2	2	4.6		69	75	6	6	580	243
TOTAL	1300	65	6340	758	2860	4	4	8.8	10	301	297	19	23	2266	1224

TRAFFIC SIGNAL ITEMS															
INTERSECTION	ITEM 416				ITEM 624		ITEM 682								
	SPREAD FOOTING FOUNDATION	DRILL SHAFT (TRF SIG POLE) (24 IN)	DRILL SHAFT (TRF SIG POLE) (30 IN)	DRILL SHAFT (TRF SIG POLE) (36 IN)	DRILL SHAFT (TRF SIG POLE) (48 IN)	GROUND BOX TY D (162922)	GROUND BOX TY D (162922) W/ APRON	VEH SIG SEC (12") LED (GRN)	VEH SIG SEC (12") LED (GRN ARW)	VEH SIG SEC (12") LED (YEL)	VEH SIG SEC (12") LED (YEL ARW)	VEH SIG SEC (12") LED (RED)	VEH SIG SEC (12") LED (RED ARW)	BACKPLATE W/REF BRDR (3 SEC) (VENT)	BACKPLATE W/REF BRDR (4 SEC) (VENT)
	EA	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
BRYANT AT 23RD	3	36	11	26			11	8	2	8	4	8	2	8	2
KOENIGHEIM AT HARRIS		42	11	13		1	9	8	1	8	2	8	1	8	1
ABE AT HARRIS		42	11	13	22		11	8	1	8	2	8	1	8	1
ABE AT CONCHO		42	11				8	8		8		8		8	
BRYANT AT JACKSON		60		26	22		10	10	4	10	8	10	4	10	1
TOTAL	3	222	44	78	44	1	49	42	8	42	16	42	8	42	5

TRAFFIC SIGNAL ITEMS										
INTERSECTION	ITEM 686					ITEM 687		ITEM 688		
	6027	6035	6043	6047	6051	6063	6001	6002	6001	6003
	INST TRF SIG PL AM (S) 1 ARM (24') LUM	INST TRF SIG PL AM (S) 1 ARM (32') LUM	INST TRF SIG PL AM (S) 1 ARM (40') LUM	INST TRF SIG PL AM (S) 1 ARM (44') LUM	INST TRF SIG PL AM (S) 1 ARM (48') LUM	INST TRF SIG PL AM (S) 1 ARM (60') LUM	PED POLE ASSEMBLY	PEDESTRIAN PUSH BUTTON	PED DETECT PUSH BUTTON (APS)	PED DETECTORS CONTROLLER UNIT
EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	
BRYANT AT 23RD	1			1	1	1	9	9	10	1
KOENIGHEIM AT HARRIS		1			1		7	7	8	1
ABE AT HARRIS		1	1			1	7	7	7	1
ABE AT CONCHO	1						7	7	8	1
BRYANT AT JACKSON							10	10	10	1
TOTAL	2	2	1	1	2	1	40	40	43	5

TRAFFIC SIGNAL - CONDUIT AND CONDUCTOR ITEMS													
INTERSECTION	ITEM 618					ITEM 620			ITEM 621	ITEM 684			
	6046	6047	6053	6058	6059	6007	6009	6010	6005	6007	6031	6033	
	CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	CONDT (PVC) (SCH 80) (3")	CONDT (PVC) (SCH 80) (4")	CONDT (PVC) (SCH 80) (4") (BORE)	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	TRAY CABLE (4 CNDR) (12AWG)	TRF SIG CBL (TY C) (12 AWG) (2 CNDR)	TRF SIG CBL (TY C) (14 AWG) (5 CNDR)	TRF SIG CBL (TY C) (14 AWG) (7 CNDR)	
LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	
BRYANT AT 23RD	184	337	116	304	491	1418	14	28	640	1340	100	572	
KOENIGHEIM AT HARRIS	134	234	152	254	482	1256	10	20	403	1336	80	616	
ABE AT HARRIS	174	320	114	327	473	1408	10	20	910	987	80	616	
ABE AT CONCHO	44	256	214	127	256	651	14	28	98	879	80	568	
BRYANT AT JACKSON	168	440	212	204	658	1682			890	1703	100	1036	
TOTAL	704	1587	808	1216	2360	6415	48	96	2941	6245	440	3408	

TRAFFIC SIGNAL - CONDUIT AND CONDUCTOR ITEMS					
INTERSECTION	ITEM 684		OPTICOM	SERIAL COMMUNICATIONS	GRIDSMAST SYSTEM
	6036	6046	N/A	N/A	N/A
	TRF SIG CBL (TY C) (14 AWG) (10 CNDR)	TRF SIG CBL (TY C) (14 AWG) (20 CNDR)	CAT-5	CAT 6	CAT-6
LF	LF	LF	LF	LF	
BRYANT AT 23RD	1262	559	427	64	64
KOENIGHEIM AT HARRIS	1296	416	95	95	95
ABE AT HARRIS	1273	645	326	137	137
ABE AT CONCHO	839	257	293	88	293
BRYANT AT JACKSON	1653	658		157	103
TOTAL	6323	2535	1141	541	692

6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87

QUANTITIES

© TxDOT 2024

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		8

DATE: 6/28/2024 4:06:09 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38151\td10240091\af.qsum01.dgn

GENERAL NOTES

The following Standard Sheets have been modified: None.

Locate the project bulletin board at an approved location within the project limits such as at a field office, staging area, or stockpile, and make accessible to the public at all times. Do not remove the bulletin board from the project until approved. If a construction site notice is required for the project, post a copy at each geographically separated work location.

Do not use salt water with solids in excess of 10,000 parts per million, as determined by evaporation.

Contractor questions on this project are to be addressed by the following individual:

Chukwuma Osemeke, P.E.; email Chukwuma.Osemeke@txdot.gov and Jesse Mendoza, P.E.; email Jesse.Mendoza@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following address: <https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 5, "Control of the Work"

State Highway right of way markers destroyed by the Contractor shall be replaced by a Texas Registered Professional Land Surveyor (RPLS) at no cost to the State. Provide written documentation from the RPLS attesting to the replacement of the right of way markers.

Make suitable advance notification to affected non-participating municipalities regarding Class B underground facilities, call the Department's San Angelo District Traffic Office at telephone number (325) 947-9208 to have the Department's existing traffic signal and illumination utilities located, and call the Department's San Angelo District Maintenance Office at telephone number (325) 947-9322 to have the Department's existing irrigation utilities located.

Responsibility for construction surveying shall conform to Section 5.9.3., "Method C."

Submit shop drawings electronically for the fabrication of structural items and other items specifically listed in the plans to SJT_ShopPlanReview@txdot.gov. For instructions on submitting shop drawings electronically see "Guide to Electronic Shop Drawing Submittal" at <http://www.txdot.gov/business/resources/specifications/shop-drawings.html>.

Item 6, "Control of Materials"

When allowed, store materials and equipment in approved areas within the right of way.

Access the work area from the right of way.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit an original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Item 7, "Legal Relations and Responsibilities"

No significant traffic generator events have been identified.

Item 8, "Prosecution and Progress"

Submit the sequence of work and estimated progress schedule on paper or as a Portable Document Format (PDF) electronic file compatible with Adobe Systems Incorporated "Acrobat Reader XI".

A delayed start provision is included in the contract to allow time to procure construction materials including traffic signal components and roadway illumination components.

Nighttime work is allowed. Provide adequate lighting to allow satisfactory inspection.

Restricted work hours are from 7:30 A.M to 8:30 A.M.

Restricted work hours are from 5:00 P.M. to 6:00 P.M.

Highway: US 87

Control: 0069-07-116, ETC.

Item 9, "Measurement and Payment"

The progress payment period shall end two working days before the last working day of the month. Deliver invoices to be paid as material on hand on or before the end of the progress payment period.

For projects that include a disadvantaged business enterprises (DBE) goal, provide a conversion rate for units of payment for work subcontracted to DBE if units of payments differ from those shown on the plans.

Item 421, "Hydraulic Cement Concrete"

Provide sulfate-resistant concrete (containing Type II cement) for all concrete identified as structural concrete in Table 8, except for the following: bridge railing, approach slabs, concrete traffic barrier, prestressed concrete panels, Class H concrete, and Class S concrete.

Entrained air is required in all slip formed concrete, but is not required for other structural concrete. Adjust the dosage of air entraining agent for low air content as directed by the Engineer. If entrained air is provided where not required, only the upper limits of the applicable Special Provision will be enforced.

Provide only the following items listed in 421.3.3, "Testing Equipment": test molds and wheelbarrow.

Item 432, "Riprap"

Furnish and install 1/2-in. thick joint filler board conforming to DMS-6310, "Joint Sealants and Fillers" between concrete riprap and adjacent existing concrete, and where directed.

Item 496, "Removing Structures"

This item shall include the complete removal and proper disposal of existing structures, including but not limited to the following: culvert barrels, railing, wingwalls, headwalls, retaining walls, safety end treatments, pipe runners, riprap, deck, overlay, approach slabs, joints, beams, bracing, drains, conduits, pipes, bents, abutments, columns, pilings, footings, web-walls, drilled shafts, reinforcing steel, bridge protective assemblies, clearance signs, etc. Portions of the structure at least 2 ft. below the permanent ground line may be left in place as directed.

Item 502, "Barricades, Signs and Traffic Handling"

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing

Highway: US 87

Control: 0069-07-116, ETC.

bid items if it does not slow the implementation of enhancement.

Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls"

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7.

Item 636, "Signs"

Install the prismatic sheeting for overhead signs material to within 30 degrees of the manufacturer-specified orientation.

Before removal from the project site, spray-paint (with an oil-based paint), an "X" across the face of non-salvageable signs as directed.

Item 644, "Small Roadside Sign Assemblies"

Furnish and install omni-directional sign post wrap (12 in. by 12 in. Type C retroreflective sheeting with pressure sensitive backing) on sign posts that have sign faces that do not face the predominant direction of traffic, as directed. Sign post wrap shall be yellow for signs R6-1 "ONE WAY" and shall be red for signs R1-2 "YIELD", R5-1 "DO NOT ENTER", R5-1a "WRONG WAY", and R1-1 "STOP". Place the bottom of sign post wrap a height of 4 ft. above the edge of travel lane.

Where foundations protrude through riprap or other concrete areas, wrap the foundation with 1/4-in. thick bituminous fiber sheets before placing concrete or repairing the concrete area. Bituminous fiber sheet tubes may be used for forming sign foundations instead of removable forms and shall be left in place below the finished concrete or riprap surface. Neatly trim the bituminous fiber sheets flush with the finished surface after the concrete has cured.

Drill and pour small roadside sign foundations on the same day or suitably cover the drilled hole.

Signs indicated to be mounted on the back of another sign or on a traffic signal pole or mast arm may require punch spacing different from that shown on the Standard Sheets. Adjust punch spacing on affected signs.

Cover each unfinished sign base with a reflectorized traffic cone.

After paving operations are complete, the Engineer will determine and provide vertical clearances to be placed on signs W12-2 and W12-2a.

Item 658, “Delineator and Object Marker Assemblies”

Remove existing object markers and delineators. Removal is not a pay item.

Item 666, “Retroreflectorized Pavement Markings”

Place glass beads for pavement markings in accordance with the following table:

Marking Types	Glass Bead (Double Drop) Types	Glass Bead Rates	
		Surface Treatment	Asphalt Concrete Pavement, Microsurfacing, Concrete Pavement
TY I markings	Type II	12 LB per 100 SF	6 LB per 100 SF
	Type III	12 LB per 100 SF	6 LB per 100 SF
TY II markings	Type II	12 LB per GAL	6 LB per GAL
	Type III	12 LB per GAL	6 LB per GAL

Apply TY II marking material at a rate of 25 gallons per mile.

The striper speed shall not exceed 5 MPH during application. Convert to gravity-flow bead-ers (if not in use) to obtain optimum bead application, when directed.

Clean striper tanks before use if there is a build-up of dry paint, as directed. Flush lines and guns before use.

Reference existing markings before performing work that disturbs the markings, so that the markings can be re-established.

Provide a double-drop of Type II and Type III glass beads.

Item 678, “Pavement Surface Preparation for Markings”

Some stop bars on existing pavement are covered in material from adjacent unpaved roads. Provide cleaning tools. Locations of these stop bars are referenced in the plans.

Item 6185. Truck Mounted Attenuators (TMA)

No additional shadow vehicle(s) with TMA other than those shown in the TCP Standard Sheets and as detailed on the General Note(s) of these Standard Sheets.

Therefore, 1 total shadow vehicle with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0069-07-116

DISTRICT San Angelo
HIGHWAY US 87

COUNTY Tom Green

CONTROL SECTION JOB				0069-07-116		0069-07-117		0069-07-118		0070-02-100		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00196818		A00196822		A00196823		A00196826			
COUNTY				Tom Green		Tom Green		Tom Green		Tom Green			
HIGHWAY				US 87		US 87		US 87		US 87			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	105-6011	REMOVING STAB BASE AND ASPH PAV (2"-6")	SY							19.000		19.000	
	416-6030	DRILL SHAFT (TRF SIG POLE) (24 IN)	LF	36.000		84.000		42.000		60.000		222.000	
	416-6031	DRILL SHAFT (TRF SIG POLE) (30 IN)	LF	11.000		22.000		11.000				44.000	
	416-6032	DRILL SHAFT (TRF SIG POLE) (36 IN)	LF	26.000		26.000				26.000		78.000	
	416-6034	DRILL SHAFT (TRF SIG POLE) (48 IN)	LF			22.000				22.000		44.000	
	432-6001	RIPRAP (CONC)(4 IN)	CY	1.600		2.400		0.400		4.600		9.000	
	500-6001	MOBILIZATION	LS	1.000								1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	7.000								7.000	
	506-6042	BIODEG EROSN CONT LOGS (INSTL) (18")	LF	100.000		100.000		100.000		100.000		400.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	100.000		100.000		100.000		100.000		400.000	
	529-6021	CONC CURB & GUTTER (SLOTTED)	LF					10.000				10.000	
	618-6046	CONDT (PVC) (SCH 80) (2")	LF	184.000		308.000		44.000		168.000		704.000	
	618-6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	337.000		554.000		256.000		440.000		1,587.000	
	618-6053	CONDT (PVC) (SCH 80) (3")	LF	116.000		266.000		214.000		212.000		808.000	
	618-6058	CONDT (PVC) (SCH 80) (4")	LF	304.000		581.000		127.000		204.000		1,216.000	
	618-6059	CONDT (PVC) (SCH 80) (4") (BORE)	LF	491.000		955.000		256.000		658.000		2,360.000	
	620-6007	ELEC CONDR (NO.8) BARE	LF	1,418.000		2,664.000		651.000		1,682.000		6,415.000	
	620-6009	ELEC CONDR (NO.6) BARE	LF	14.000		20.000		14.000				48.000	
	620-6010	ELEC CONDR (NO.6) INSULATED	LF	28.000		40.000		28.000				96.000	
	621-6005	TRAY CABLE (4 CONDR) (12 AWG)	LF	640.000		1,313.000		98.000		890.000		2,941.000	
	624-6010	GROUND BOX TY D (162922)W/APRON	EA	11.000		20.000		8.000		10.000		49.000	
	628-6145	ELC SRV TY D 120/240 060(NS)SS(E)SP(O)	EA	1.000		2.000		1.000		1.000		5.000	
	636-6001	ALUMINUM SIGNS (TY A)	SF	46.000				18.000		46.000		110.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	6.000				2.000		6.000		14.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	329.000						339.000		668.000	
	666-6048	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF	384.000		779.000		316.000		507.000		1,986.000	
	666-6054	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA	4.000						4.000		8.000	
	666-6078	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA	4.000						4.000		8.000	
	666-6225	PAVEMENT SEALER 6"	LF	852.000		571.000		355.000		934.000		2,712.000	
	666-6226	PAVEMENT SEALER 8"	LF	329.000						339.000		668.000	
	666-6230	PAVEMENT SEALER 24"	LF	384.000		779.000		316.000		507.000		1,986.000	
	666-6231	PAVEMENT SEALER (ARROW)	EA	4.000						4.000		8.000	
	666-6232	PAVEMENT SEALER (WORD)	EA	4.000						4.000		8.000	
	666-6306	RE PM W/RET REQ TY I (W)6"(BRK)(100MIL)	LF	722.000		2,282.000		1,127.000		1,017.000		5,148.000	
	666-6309	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL)	LF	51.000				73.000				124.000	
	666-6321	RE PM W/RET REQ TY I (Y)6"(SLD)(100MIL)	LF	620.000						680.000		1,300.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA	9.000		29.000		14.000		13.000		65.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0069-07-116

DISTRICT San Angelo
HIGHWAY US 87

COUNTY Tom Green

CONTROL SECTION JOB				0069-07-116		0069-07-117		0069-07-118		0070-02-100		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00196818		A00196822		A00196823		A00196826			
COUNTY				Tom Green		Tom Green		Tom Green		Tom Green			
HIGHWAY				US 87		US 87		US 87		US 87			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	677-6001	ELIM EXT PAV MRK & MRKS (4")	LF	1,308.000		2,138.000		1,081.000		1,813.000		6,340.000	
	677-6002	ELIM EXT PAV MRK & MRKS (6")	LF	339.000						419.000		758.000	
	677-6007	ELIM EXT PAV MRK & MRKS (24")	LF	423.000		1,626.000		660.000		151.000		2,860.000	
	677-6008	ELIM EXT PAV MRK & MRKS (ARROW)	EA	2.000						2.000		4.000	
	677-6012	ELIM EXT PAV MRK & MRKS (WORD)	EA	2.000						2.000		4.000	
	680-6003	INSTALL HWY TRF SIG (SYSTEM)	EA	1.000		2.000		1.000		1.000		5.000	
	680-6004	REMOVING TRAFFIC SIGNALS	EA	1.000		2.000		1.000		1.000		5.000	
	682-6001	VEH SIG SEC (12")LED(GRN)	EA	8.000		16.000		8.000		10.000		42.000	
	682-6002	VEH SIG SEC (12")LED(GRN ARW)	EA	2.000		2.000				4.000		8.000	
	682-6003	VEH SIG SEC (12")LED(YEL)	EA	8.000		16.000		8.000		10.000		42.000	
	682-6004	VEH SIG SEC (12")LED(YEL ARW)	EA	4.000		4.000				8.000		16.000	
	682-6005	VEH SIG SEC (12")LED(RED)	EA	8.000		16.000		8.000		10.000		42.000	
	682-6006	VEH SIG SEC (12")LED(RED ARW)	EA	2.000		2.000				4.000		8.000	
	682-6051	BACKPLATE W/REFL BRDR(3 SEC)ALUM	EA	8.000		16.000		8.000		10.000		42.000	
	682-6052	BACKPLATE W/REFL BRDR(4 SEC)ALUM	EA	2.000		2.000				4.000		8.000	
	684-6007	TRF SIG CBL (TY A)(12 AWG)(2 CONDR)	LF	1,340.000		2,323.000		879.000		1,703.000		6,245.000	
	684-6031	TRF SIG CBL (TY A)(14 AWG)(5 CONDR)	LF	100.000		160.000		80.000		100.000		440.000	
	684-6033	TRF SIG CBL (TY A)(14 AWG)(7 CONDR)	LF	572.000		1,232.000		568.000		1,036.000		3,408.000	
	684-6036	TRF SIG CBL (TY A)(14 AWG)(10 CONDR)	LF	1,262.000		2,569.000		839.000		1,653.000		6,323.000	
	684-6046	TRF SIG CBL (TY A)(14 AWG)(20 CONDR)	LF	559.000		1,061.000		257.000		658.000		2,535.000	
	686-6027	INS TRF SIG PL AM(S)1 ARM(24')LUM	EA	1.000				1.000				2.000	
	686-6035	INS TRF SIG PL AM(S)1 ARM(32')LUM	EA			2.000						2.000	
	686-6043	INS TRF SIG PL AM(S)1 ARM(40')LUM	EA			1.000						1.000	
	686-6047	INS TRF SIG PL AM(S)1 ARM(44')LUM	EA	1.000						1.000		2.000	
	686-6051	INS TRF SIG PL AM(S)1 ARM(48')LUM	EA	1.000		1.000				1.000		3.000	
	686-6063	INS TRF SIG PL AM(S)1 ARM(60')LUM	EA			1.000				2.000		3.000	
	687-6001	PED POLE ASSEMBLY	EA	9.000		14.000		7.000		10.000		40.000	
	687-6002	PEDESTRIAN PUSH BUTTON POLE	EA	9.000		14.000		7.000		10.000		40.000	
	688-6001	PED DETECT PUSH BUTTON (APS)	EA	10.000		15.000		8.000		10.000		43.000	
	688-6003	PED DETECTOR CONTROLLER UNIT	EA	1.000		2.000		1.000		1.000		5.000	
	690-6054	REMOVAL OF CURBS	LF	56.000		135.000		41.000		69.000		301.000	
	690-6056	INSTALL OF CURBS	LF	33.000		125.000		64.000		75.000		297.000	
	690-6057	REMOVAL OF PEDESTRIAN RAMPS	EA	2.000		9.000		2.000		6.000		19.000	
	690-6059	INSTALL OF PEDESTRIAN RAMPS	EA	4.000		9.000		4.000		6.000		23.000	
	690-6060	REMOVAL OF SIDEWALKS	SF	355.000		1,027.000		304.000		580.000		2,266.000	
	690-6062	INSTALL OF SIDEWALKS	SF	208.000		633.000		140.000		243.000		1,224.000	
	6001-6001	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	40.000		80.000		40.000		40.000		200.000	



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0069-07-116

DISTRICT San Angelo
HIGHWAY US 87

COUNTY Tom Green

CONTROL SECTION JOB				0069-07-116		0069-07-117		0069-07-118		0070-02-100		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00196818		A00196822		A00196823		A00196826			
COUNTY				Tom Green		Tom Green		Tom Green		Tom Green			
HIGHWAY				US 87		US 87		US 87		US 87			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	6058-6001	BBU SYSTEM (EXTERNAL BATT CABINET)	EA	1.000		2.000		1.000		1.000		5.000	
	6062-6042	RELOCATE ITS RADIO	EA	1.000		2.000		1.000		1.000		5.000	
	6185-6002	TMA (STATIONARY)	DAY	40.000		80.000		40.000		40.000		200.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	20.000		20.000		20.000		20.000		80.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000								1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000								1.000	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

<p>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov</p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

BC (1) -21

FILE: bc-21.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
	0069	07	116, ETC.	US 87
4-03 7-13	REVISIONS		DIST	COUNTY
9-07 8-14			SJT	TOM GREEN
5-10 5-21				SHEET NO.
				12


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
			60	600 ²
			65	700 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	70	800 ²
			75	900 ²
			80	1000 ²
			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND

—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DW: TxDOT	CR: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
REVISIONS: 9-07 8-14 7-13 5-21	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 13	

DATE: FILE:

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

SHEET 3 OF 12

<h2>BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT</h2>			
<h3>BC (3) -21</h3>			
FILE:	bc-21.dgn	DNR TxDOT	CR: TxDOT
© TxDOT	November 2002	CONT SECT	JOB HIGHWAY
REVISIONS		0069 07	116, ETC. US 87
9-07 8-14		DIST	COUNTY SHEET NO.
7-13 5-21		SJT	TOM GREEN 14

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflective when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) -21


FILE#	bc-21.dgn	DWG	TxDOT	CHK	TxDOT	DATE	TxDOT	CRK	TxDOT	
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY	REVISIONS	0069	07	116, ETC.	US 87
DATE	9-07	8-14	DIST	COUNTY	SHEET NO.	7-13	5-21	SJT	TOM GREEN	15

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DW:	TxDOT	CHK:	TxDOT	DWG:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		0069	07	116, ETC.		US 87			
9-07	8-14	DIST:		COUNTY:	SHEET NO.:				
7-13	5-21	SJT		TOM GREEN	16				

DATE:
FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT
RIGHT X LANES CLOSED	RIGHT X LANES OPEN
CENTER LANE CLOSED	DAYTIME LANE CLOSURES
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE
EXIT CLOSED	RIGHT LN TO BE CLOSED
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI
XXXXXXXX BLVD CLOSED	

Other Condition List

ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT	FORM X LINES RIGHT
DETOUR NEXT X EXITS	USE XXXXX RD EXIT
USE EXIT XXX	USE EXIT I-XX NORTH
STAY ON US XXX SOUTH	USE I-XX E TO I-XX N
TRUCKS USE US XXX N	WATCH FOR TRUCKS
WATCH FOR TRUCKS	EXPECT DELAYS
EXPECT DELAYS	PREPARE TO STOP
REDUCE SPEED XXX FT	END SHOULDER USE
USE OTHER ROUTES	WATCH FOR WORKERS
STAY IN LANE *	

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

** See Application Guidelines Note 6.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation * IH-number, US-number, SH-number, FM-number

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

SHEET 6 OF 12



BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)


BC (6) - 21

FILE: bc-21.dgn	DW: TxDOT	CHK: TxDOT	DWG: TxDOT	CHK: TxDOT
© TxDOT November 2002	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
REVISIONS: 9-07 8-14	DIST: 7-13	COUNTY: 5-21	SHEET NO.: TOM GREEN	17

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE: FILE:

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE#	bc-21.dgn	DWG	TxDOT	CHK	TxDOT	DWG	TxDOT	CHK	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0069	07	116, ETC.		US 87			
9-07	8-14			DIST	COUNTY	SHEET NO.			
7-13	5-21			SJT	TOM GREEN	18			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) -21

FILE:	bc-21.dgn	DWG:	TxDOT	CHK:	TxDOT	APP:	TxDOT	CR:	TxDOT
© TxDOT	November 2002	CONT:	SECT:	JOB:	HIGHWAY:				
REVISIONS		0069	07	116, ETC.		US 87			
4-03	8-14			DIST:	COUNTY:	SHEET NO.			
9-07	5-21			SJT	TOM GREEN	19			
7-13									

DATE:
FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




PORTABLE

VERTICAL PANELS (VPs)




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * * Taper lengths have been rounded off.
L = Length of Taper (FT.) W = Width of Offset (FT.)
S = Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE: bc-21.dgn	DW: TxDOT	CR: TxDOT	DR: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	SJT	TOM GREEN	20	


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary, (minimum of 2 and maximum of 4 drums)




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DW: TxDOT	CHK: TxDOT	DRW: TxDOT	CR: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	SJT	TOM GREEN	21	

DATE: FILE:

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:


SHEET 11 OF 12

Texas Department of Transportation		Traffic Safety Division Standard
<h2 style="margin: 0;">BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS</h2> <h3 style="margin: 0;">BC(11)-21</h3>		
FILE: bc-21.dgn	DNR: TxDOT	CHK: TxDOT
© TxDOT February 1998	CONT: 0069	SECT: 07
REVISIONS	JOB: 116, ETC.	HIGHWAY: US 87
2-98 9-07 5-21	DIST: COUNTY	SHEET NO.
1-02 7-13	SJT	TOM GREEN
11-02 8-14		22

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.





RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS




SOLID LINES



BROKEN LINES




AUXILIARY OR LANEDROP LINE



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 21


Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

FILE: bc-21.dgn	DW: TxDOT	CHK: TxDOT	DWG: TxDOT	CR: TxDOT
©TxDOT February 1998	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
REVISIONS	DIST: COUNTY		SHEET NO.	
1-97 9-07 5-21	SJT		TOM GREEN	
2-98 7-13			23	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TCP (1-1a)

WORK SPACE NEAR SHOULDER
Conventional Roads



TCP (1-1b)

WORK SPACE ON SHOULDER
Conventional Roads



TCP (1-1c)

WORK VEHICLES ON SHOULDER
Conventional Roads

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.



TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK



TCP (1-1) - 18

FILE: tcp1-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
2-94 4-98				
8-95 2-12				
1-97 2-18	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	24	

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance warning ahead of the flagger or R1-2 "YIELD" sign is less than 150 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

- R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.


TCP (1-2b)

- Flaggers should use two-way radios or other methods of communication to control traffic.
- Length of work space should be based on the ability of flaggers to communicate.
- If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagger and a queue of stopped vehicles (see table above).
- Channelizing devices on the center-line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

		Traffic Operations Division Standard	
TRAFFIC CONTROL PLAN			
ONE-LANE TWO-WAY			
TRAFFIC CONTROL			
TCP (1-2) - 18			
FILE: tcp1-2-18.dgn	DN:	CKI	DW: CKI
© TxDOT December 1985	CONT	SECT	JOB
REVISIONS	0069	07	116, ETC.
4-90 4-98			US 87
2-94 2-12			
1-97 2-18	DIST	COUNTY	SHEET NO.
	SJT	TOM GREEN	25

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




BE PREPARED TO STOP

CW3-4 48" X 48"▲ CW20-7 48" X 48"▲

For either TCP(1-3a) or TCP(1-3b)

USE ONLY WHEN FLAGGERS CONTROL TRAFFIC

(See Notes 2 & 3)



LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x"	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Additional flaggers may be positioned in advance of traffic queues to alert traffic to reduce speed.
 - DO NOT PASS, PASS WITH CARE and construction regulatory speed zone signs may be installed downstream of the ROAD WORK AHEAD signs.
 - When the work zone is made up of several work spaces, channelizing devices should be placed laterally across the closed lane to re-emphasize closure. Laterally placed channelizing devices should be repeated every 500 to 1000 feet in urban areas and every 1/4 to 1/2 mile in rural areas.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
 - Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20', or 15' if posted speed are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the area of conflicting markings not the entire work zone.


Texas Department of Transportation Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO LANE ROADS
TCP (1-3) - 18


FILE: tcp1-3-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	SJT	TOM GREEN	26	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (1-4a)
ONE LANE CLOSED



TCP (1-4b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	$L = WS$	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW20-1D "ROAD WORK AHEAD" sign may be repeated if the visibility of the work zone is less than 1500 feet.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline where needed to protect the work space from opposing traffic with the arrow panel placed in the closed lane near the end of the merging taper.

TCP (1-4b)

- Where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2S where S is the speed in mph. This tighter device spacing is intended for the areas of conflicting markings, not the entire work zone.

Texas Department of Transportation
Traffic Operations Division Standard


TRAFFIC CONTROL PLAN LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS

TCP (1-4) - 18


FILE: tcp1-4-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
2-94 4-98				
8-95 2-12				
1-97 2-18				
	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	27	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



TCP (1-5a) ONE LANE CLOSURE



TCP (1-5b) LANE CLOSURE NEAR EXIT RAMP



TCP (1-5c) LANE CLOSURE NEAR ENTRANCE RAMP

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓		

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.






TRAFFIC CONTROL PLAN
 LANE CLOSURES FOR
 DIVIDED HIGHWAYS

TCP (1-5) - 18

FILE: tcp1-5-18.dgn	DN:	CK:	DW:	CK:
© TxDOT February 2012	CONT	SECT	JOB	HIGHWAY
2-18	0069	07	116, ETC.	US 87
	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	28	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
 - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
 - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
 - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
 - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.


Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 CONVENTIONAL ROAD
 SHOULDER WORK**


TCP (2-1) - 18

FILE: tcp2-1-18.dgn	DN:	CKI:	DW:	CKI:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	SJT	TOM GREEN	29	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-2a)
2-LANE ROADWAY WITHOUT PAVED SHOULDERS
ONE LANE TWO-WAY
CONTROL WITH YIELD SIGNS
(Less than 2000 ADT - See Note 9)



TCP (2-2b)
2-LANE ROADWAY WITHOUT PAVED SHOULDERS
ONE LANE TWO-WAY
CONTROL WITH FLAGGERS

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	575'
65		650'	715'	780'	65'	130'	700'	410'	645'
70	700'	770'	840'	70'	140'	800'	475'	730'	
75	750'	825'	900'	75'	150'	900'	540'	820'	

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 - Flaggers should use two-way radios or other methods of communication to control traffic.
 - Length of work space should be based on the ability of flaggers to communicate.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
 - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
 - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
 - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.



**TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL**



TCP (2-2) - 18

FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
8-95 3-03				
1-97 2-12				
4-98 2-18	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	30	

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Raised Pavement Markers Ty II-AA
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * S	Formula L = WS ² / 60	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30		150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45		450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓
				TCP (2-3b) ONLY

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - When work space will be in place less than three days existing pavement markings may remain in place. Channelizing devices shall be used to separate traffic.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Flagger should be positioned at end of traffic queue.
 - The R4-1 "DO NOT PASS," R4-2 "PASS WITH CARE" and construction regulatory speed zone signs may be installed within CW20-1D "ROAD WORK AHEAD" signs. Proper spacing of signs shall be maintained.
 - Conflicting pavement marking shall be removed for long term projects.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-3a)**
- Conflicting pavement markings shall be removed for long-term projects. For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter device spacing is intended for the area of the conflicting markings, not the entire work zone.




TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS

TCP (2-3) - 23


FILE: tcp(2-3)-23.dgn	DW: CK1	DW: DW1	CK1
© TxDOT April 2023	CONT: 0069	SECT: 07	JOB: 116, ETC.
REVISIONS: 12-85 4-98 2-18	DIST: COUNTY	SHEET NO.:	US 87
8-95 3-03 4-23	SJT	TOM GREEN	31
1-97 2-12			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TCP (2-4a)
ONE LANE CLOSED



TCP (2-4b)
TWO LANES CLOSED

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The downstream taper is optional. When used, it should be 100 feet minimum length per lane.
- For short term applications, when post mounted signs are not used, the distance legend may be shown on the sign face rather than on a CW16-3aP supplemental plaque.
- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-4a)

- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic with the arrow board placed in the closed lane near the end of the merging taper.

TCP (2-4b)

- For shorter durations where traffic is directed over a yellow centerline, channelizing devices which separate two-way traffic should be spaced on tapers at 20' or 15' if posted speeds are 35 mph or slower, and for tangent sections, at 1/2(S) where S is the speed in mph. This tighter devices spacing is intended for the area of conflicting markings, not the entire work zone.





**TRAFFIC CONTROL PLAN
LANE CLOSURES ON MULTILANE
CONVENTIONAL ROADS**

TCP (2-4) - 18

FILE: tcp2-4-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	SJT	TOM GREEN	32	
4-98 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths %		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"	
		10' Offset	11' Offset	12' Offset	On a Taper			On a Tangent
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.
 - The downstream taper is optional. When used, it should be 100 feet approximately per lane, with channelizing devices spaced at 20 feet.
- TCP (2-5a)**
- If this TCP is used for a left lane closure, CW20-5TL "LEFT LANE CLOSED" signs shall be used and channelizing devices shall be placed on the centerline to protect the work space from opposing traffic, with the arrow board placed in the closed lane near the end of the merging taper.
- TCP (2-5b)**
- Conflicting pavement markings shall be removed for long-term projects.

Traffic Operations Division Standard




TRAFFIC CONTROL PLAN
LONG TERM LANE CLOSURES
MULTILANE CONVENTIONAL RDS.

TCP (2-5) - 18

FILE: tcp2-5-18.dgn	DWG: CK:	DWG: DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB
REVISIONS	0069	07	116, ETC.
8-95 2-12			US 87
1-97 3-03	DIST	COUNTY	SHEET NO.
4-98 2-18	SJT	TOM GREEN	33

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * X	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70	700'	770'	840'	70'	140'	800'	475'	
75	750'	825'	900'	75'	150'	900'	540'	

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
 - Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
 - Channelizing devices used along the work space or along tangent sections may be supplemented with vertical panels (VP) placed on every other channelizing device. If night time conditions make it difficult to see at least two VPs, the VPs may be placed on each channelizing device.
 - The placement of pavement markings may be omitted on intermediate-term stationary work zones with the approval of the Engineer.
 - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.




**TRAFFIC CONTROL PLAN
LANE CLOSURES ON
DIVIDED HIGHWAYS**


TCP (2-6) - 18

FILE: tcp2-6-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	SJT	TOM GREEN	34	
1-97 2-18				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (2-8a)
ONE LANE TWO-WAY
TRAFFIC CONTROL WITH YIELD SIGNS
 (Less Than 2000 ADT-See Note 5)



TCP (2-8b)
ONE LANE TWO-WAY
TRAFFIC CONTROL WITH TRAFFIC SIGNAL

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Sign		Traffic Flow
	Flag		Flagger
	Raised Pavement Markers Ty II-AA		Temporary or Portable Traffic Signal

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
			✓	✓

GENERAL NOTES

- Flags attached to signs where shown are REQUIRED.
- When this TCP is used at a location which does not involve a bridge, a 48" x 48" CW20-4D "ONE LANE ROAD AHEAD" signs should be used in lieu of the CW5-3 "ONE LANE BRIDGE" signs. The CW13-1P Advisory Speed Plaque is required with either warning sign.
- Raised pavement markers shall be placed 40 feet c-c between DO NOT PASS signs and stop or yield lines.
- For intermediate term situations, when it is not feasible to remove and restore pavement markings, the channelization must be made dominant by using a very close spacing. This is especially important in locations of conflicting information, such as where traffic is directed over a double yellow centerline. In such locations a maximum channelizing device spacing of 20 feet is recommended. The 20 foot channelizing device spacing recommendation is intended for the area of conflicting information and not the entire work zone.

TCP (2-8a)

- Traffic control by CW3-2 "YIELD AHEAD" symbol signs for one lane two-way traffic control operations should be limited to work spaces less than 400 feet long and roadways with less than 2000 ADT. Otherwise, portable traffic signals should be used.
- If power is available, a flashing beacon should be attached to the CW3-2 "YIELD AHEAD" symbol sign for emphasis.
- The R1-2 "YIELD" and R1-2aP "TO ONCOMING TRAFFIC" signs and other regulatory signs shall be installed at 7 foot minimum mounting height.

TCP (2-8b)

- A list of approved Portable Traffic Signals can be found in the "Compliant Work Zone Traffic Control Devices" list.
- Portable traffic signals should be located to provide adequate stopping sight distance for approaching motorist (See table above).

Texas Department of Transportation
 Traffic Safety Division Standard

TRAFFIC CONTROL PLAN LONG TERM ONE-LANE TWO-WAY CONTROL


TCP (2-8) -23

FILE: tcp2-8-23.dgn	DN:	CK:	DW:	CK:
© TxDOT April 2023	CONT:	SECT:	JOB:	HIGHWAY:
REVISIONS	0069	07	116, ETC.	US 87
12-85 4-98 2-18	DIST:	COUNTY:	SHEET NO.	
8-95 3-03 4-23	SJT	TOM GREEN	35	
1-97 2-12				

DATE:
 FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



SIGNS ARE SHOWN FOR ONE DIRECTION OF TRAVEL

* When the optional larger WORKING FOR YOU GIVE US A BRAKE (G20-7T) 192" x 96" sign is required, the locations shall be noted elsewhere in the plans.

SUMMARY OF LARGE SIGNS

BACKGROUND COLOR	SIGN DESIGNATION	SIGN	SIGN DIMENSIONS	REFLECTIVE SHEETING	SQ FT	GALVANIZED STRUCTURAL STEEL		DRILLED SHAFT
						Size	(LF)	
							① ②	24" DIA. (LF)
Orange	G20-7T		96" X 48"	Type B _{FL} or C _{FL}	32	▲	▲ ▲	▲
Orange	G20-7T		192" X 96"	Type B _{FL} or C _{FL}	128	W8x18	16 17	12

▲ See Note 6 Below

LEGEND

	Sign
	Large Sign
	Traffic Flow

DEPARTMENTAL MATERIAL SPECIFICATIONS

PLYWOOD SIGN BLANKS	DMS-7100
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL}
BLACK	LEGEND & BORDERS	NON-REFLECTIVE ACRYLIC FILM

GENERAL NOTES

- See BC and SMD sheets for additional sign support details.
- Sign locations shall be approved by the Engineer.
- For projects more than two miles in length, Give Us a BRAKE signs should be repeated halfway through the project. The Give Us a Brake (CW21-1T) may be used for this purpose.
- Work zone speed limits are sometimes used in conjunction with GIVE US A BRAKE signing. See BC(3) for location and spacing of construction speed zone signing when required.
- Give Us a Brake (CW21-1T) signs and supports shall be considered subsidiary to Item 502, "Barricades, Signs and Traffic Handling."
- The 96" X 48" Working For You Give Us A BRAKE (G20-7T) may use a 1/2" or 5/8" plywood substrate or 0.125" aluminum sheeting substrate and may be supported by two 4" x 6" wood posts with drilled holes for breakaway as per BC(5) and will be subsidiary to Item 502.
- The Working For You Give Us A BRAKE (G20-7T) 192" X 96" sign shall be paid for under the following specification items:
 Item 636 - Aluminum Signs
 Item 647 - Large Roadside Sign Supports and Assemblies.
 Item 416 - Drilled Shaft Foundations
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.

Texas Department of Transportation Traffic Operations Division Standard


WORK ZONE "GIVE US A BRAKE" SIGNS

WZ (BRK) - 13


FILE: wzbrk-13.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
©TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
6-96 5-98 7-13	DIST	COUNTY	SHEET NO.	
8-96 3-03	SJT	TOM GREEN	36	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



NEAR SIDE LANE CLOSURE
SHORT DURATION OR SHORT TERM STATIONARY



FAR SIDE RIGHT LANE CLOSURE
SHORT DURATION OR SHORT TERM STATIONARY




FAR SIDE LEFT LANE CLOSURE
SHORT DURATION OR SHORT TERM STATIONARY

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger


Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS ² / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

WORKERS IN BUCKET TRUCKS SHALL NOT WORK ABOVE OPEN LANES OF TRAFFIC.



OPERATIONS IN THE INTERSECTION
SHORT DURATION



GENERAL NOTES

- The minimum size channelizing device is the 28" cone. 42" Two-piece cones, drums, vertical panels or barricades will be required when the device must be left unattended at night.
- Obstructions or hazards at the work area shall be clearly marked and delineated at all times.
- Flaggers and Flagger Symbol (CW20-7) signs may be required according to field conditions.
- Vehicles parked in roadway shall be equipped with at least two high intensity rotating, flashing, oscillating or strobe type lights.
- High level warning devices (flag trees) may be used at corners of the vehicle.
- When work operations are performed on existing signals, the signals may be placed in flashing red mode when approved by the engineer. If existing signals do not have power, All-Way Stop (R1-1 and R1-3P) signs may be implemented when approved by the engineer.
- For Short-Term Stationary work the buffer space "B" from the above table should be used if field conditions permit. For Short Duration (less than 1 hour) any buffer space provided will enhance the safety of the setup.
- The arrow board at this location may be omitted for Short Duration work if the work vehicle has an arrow board in operation. As an option, the arrow board may be placed at the end of the taper in the closed lane if space is not available at the beginning of the taper.
- Signs and devices for the NEAR SIDE LANE CLOSURE may be altered for a left lane closure by using a LEFT LANE CLOSED (CW20-5TL) and adding channelizing devices on the centerline to protect the work space from opposing traffic.




TRAFFIC SIGNAL WORK TYPICAL DETAILS

WZ(BTS-1)-13

FILE: wzbts-13.dgn	DN: TxDOT	CR: TxDOT	DN: TxDOT	CR: TxDOT
© TxDOT April 1992	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
2-98 10-99 7-13	DIST	COUNTY	SHEET NO.	
4-98 3-03	SJT	TOM GREEN	37	

No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect use of this standard.

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect use of this standard.



TYPICAL ADVANCE SIGNAL PROJECT SIGNING
FOR LONG TERM and INTERMEDIATE-TERM STATIONARY WORK OPERATIONS

- NOTES**
1. Project signing as shown shall be in place whenever signal contract work is in progress.
 2. For closely adjoining projects, advance signing may not be required in advance of each intersection, but only in advance of the intersections at the project limits. Actual locations will be as directed by the Engineer.
 3. Advance signs shall be removed when signal construction operations are no longer under way, as directed by the Engineer.
 4. Warning sign spacing shown is typical for both directions.
 5. See the Table on sheet 1 of 2 for Typical warning sign spacing.

GENERAL NOTES FOR WORK ZONE SIGNS

1. Signs shall be installed and maintained in a straight and plumb condition.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. Nails shall NOT be used to attach signs to any support.
5. All signs shall be installed in accordance with the plans or as directed by the Engineer.
6. The Contractor shall furnish the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD).
7. The Contractor shall furnish sign supports and substrates listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD), installed as per the manufacturer's recommendations.
8. Temporary signs that have damaged or cracked substrates and/or damaged or marred reflective sheeting shall be replaced as directed by the Engineer.
9. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1".
10. Damaged wood posts shall be replaced. Splicing wood posts will not be allowed.

DURATION OF WORK

1. Work zone durations are defined in Part 6, Section 60.02 of the Texas Manual on Uniform Traffic Control Devices (TMUTCD).

SIGN MOUNTING HEIGHT

1. Sign height of Long-term/Intermediate-term warning signs shall be as shown on Figure 6F-1 of the TMUTCD.
2. Sign height of Short-term/Short Duration warning signs shall be as shown on Figure 6F-2 of the TMUTCD.
3. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

REMOVING OR COVERING

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered, unless otherwise approved by the Engineer.
2. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night without damaging the sign sheeting. Burlap, or heavy materials such as plywood or aluminum shall not be used to cover signs.
3. Duct tape or other adhesive material shall NOT be affixed to a sign face.
4. Signs and anchor stubs shall be removed and holes back filled upon completion of the work.

REFLECTIVE SHEETING

1. All signs shall be retroreflective and constructed of sheeting meeting the requirements of the DMS and color usage table shown on this sheet.

SIGN SUPPORT WEIGHTS

1. Weights used to keep signs from turning over should be sandbags filled with dry, cohesionless material.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects will not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber, such as tire inner tubes, shall not be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

LEGEND


	Sign
	Channelizing Devices
	Type 3 Barricade

DEPARTMENTAL MATERIAL SPECIFICATIONS


SIGN FACE MATERIALS	DMS-8300
FLEXIBLE ROLL-UP REFLECTIVE SIGNS	DMS-8310

COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
WHITE	BACKGROUND	TYPE A SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING


Only pre-qualified products shall be used. A copy of the "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources and may be found at the following web address:
http://www.txdot.gov/txdot_library/publications/construction.htm



SIDEWALK DIVERSION



SIDEWALK DETOUR



CROSSWALK CLOSURES

PEDESTRIAN CONTROL

1. Holes, trenches or other hazards shall be adequately protected by covering, delineating or surrounding the hazard with orange plastic pedestrian fencing or longitudinal channelizing devices, or as directed by the Engineer.
2. "CROSSWALK CLOSURES" as detailed above will require the Engineer's approval prior to installation.
3. R9 series signs shown may be placed on supports detailed on the BC standards or CWZTCD list, or when fabricated from approved lightweight plastic substrates, they may be mounted on top of a plastic drum at or near the location shown.
4. For speeds less than 45 mph longitudinal channelizing devices may be used instead of traffic barriers when approved by the Engineer. Attenuation of blunt ends and installation of water filled devices shall be as per BC(9) and manufacturer's recommendations.
5. Location of devices are for general guidance. Actual device spacing and location must be field adjusted to meet actual conditions.
6. Where pedestrians with visual disabilities normally use the closed sidewalk Detectable Pedestrian Barricades should be used instead of the Type 3 Barricades shown.
7. The width of existing sidewalk should be maintained if practical.
8. Pavement markings for mid-block crosswalks shall be paid for under the appropriate bid items.
9. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.

SHEET 2 OF 2

Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC SIGNAL WORK BARRICADES AND SIGNS


WZ (BTS-2) - 13

FILE#	wzlbs-13.dgn	DWG	TxDOT	CHK	TxDOT	DATE	TxDOT	CHK	TxDOT
REVISIONS	0069	07	CONT	SECT	JOB	HIGHWAY			
					116, ETC.	US 87			
			DIST	COUNTY	SHEET NO.				
			SJT	TOM GREEN	38				

2-98 10-99 7-13
 4-98 3-03

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORK ZONE SHORT TERM PAVEMENT MARKINGS DETAILS




NOTES:

- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- Short term pavement markings shall NOT be used to simulate edge lines.
- Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent pavement markings should then be placed.
- For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- Tabs shall meet requirements of Departmental Material Specification DMS-8242.
- When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.

WORK ZONE SHORT TERM PAVEMENT MARKINGS PATTERNS



PREFABRICATED PAVEMENT MARKINGS

- Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241.
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Construction-Grade Prefabricated Pavement Markings."

RAISED PAVEMENT MARKERS

- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

- DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS

WZ(STPM)-23

FILE:	wzstpm-23.dgn	DN:		CK:		DW:		CK:	
© TxDOT	February 2023	CONT	0069	SECT	07	JOB	116, ETC.	HIGHWAY	US 87
REVISIONS		DIST		COUNTY		SHEET NO.			
4-92	7-13	SJT		TOM GREEN					39
1-97	2-23								
3-03									

DATE: FILE:

GENERAL NOTES

1. When a contractor force account "Safety Contingency" has been established for the project, it is for work zone enhancements that were unforeseen in the project planning and design stage, but would improve the effectiveness of the traffic control plan. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if doing so does not slow implementation of work zone enhancements.
2. Shadow, lead, trail, and ramp control vehicles shown on the plans are required.
3. Use high level warning flags on advance warning signs during daytime operations.
4. Provide flaggers at such times and locations as directed to ensure the safe passage of traffic through construction areas. When flaggers are used to control traffic, furnish and install signs CW20-7 "FLAGGER SYMBOL", CW20-7aD "FLAGGER AHEAD", and CW3-4 "BE PREPARED TO STOP". Flaggers shall use 24 in. STOP/SLOW paddles.
5. Temporarily relocate existing mailbox assemblies on portable mailbox stands as shown on the plans, or as directed. Use materials conforming to the Compliant Work Zone Traffic Control Device List (CWZTCDL).
6. Prior to each work day, make provisions to exclude vehicles from parking within work areas.
7. Temporarily relocate existing permanent sign assemblies to temporary supports as shown on the plans, or as directed.
8. Omit advance warning signs and furnish and install reduced size signs CW20-1 "ROAD WORK AHEAD" mounted back to back with reduced size signs G20-2 "END ROAD WORK" signs at intersecting city streets and county roads.
9. Furnish and install signs CW20-1D "ROAD WORK AHEAD", G20-1aT "ROAD WORK ←NEXT X MILES, NEXT X MILES→", and G20-2 "END ROAD WORK" at intersecting state highways.
10. Sign and buffer spacing may be altered to fit field conditions, as directed.
11. In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have employee(s) available to respond on the project for emergencies and for taking corrective measures within 30 minutes.
12. Cones may be used as the typical channelizing device for freeway surfacing projects.
13. 28 in. tall cones will be allowed only for short duration or short term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate term stationary work areas should use drums, vertical panels, or 42 in. tall two-piece cones.
14. All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.
15. The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
16. Warning signs for long term stationary work should be mounted at 7 ft. to the bottom of the sign.
17. For long term stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
18. All motor vehicle equipment having an obstructed view to the rear shall have a reverse signal alarm audible above the surrounding noise level.
19. Traffic control devices denoted with the triangle symbol on the plans may be omitted.
20. When sheet WZ(RS) is included in the plans, furnish and install temporary rumble strips for daytime lane closures. Do not use temporary rumble strips on freeways or expressways.
21. When sheet WZ(BRK) is included in the plans, furnish and install signs CW21-1T "GIVE US A BRAKE".
22. Flags attached to signs shown in the plans are required.
23. Signs END ROAD WORK (G20-2) may be omitted when conflicting with G20-2 signs already in place on the project.
24. The Engineer will determine advisory speeds to be shown on plaques CW13-1P.
25. Temporary work zone devices (including portable barriers) manufactured after December 31, 2019 must have been successfully tested to the 2016 edition of Manual for Assessing Safety Hardware (MASH). Such devices manufactured on or before this date, and successfully tested to either National Cooperative Highway Research Program (NCHRP) Report 350 or the 2009 edition of MASH, may continue to be used.

TRUCK MOUNTED ATTENUATOR REQUIREMENTS

Provide the number of vehicles with truck mounted attenuators listed in the table below. The Contractor shall determine if multiple operations will occur at the same time, to determine the total number of truck mounted attenuators needed for the project.

WZ(BTS-1)	4	TCP(2-3)	0	TCP(6-1)	0
TCP(1-1)	2	TCP(2-4)	2	TCP(6-2)	0
TCP(1-2)	0	TCP(2-5)	0	TCP(6-3)	0
TCP(1-3)	0	TCP(2-6)	2	TCP(6-4)	0
TCP(1-4)	2	TCP(3-1)	0	TCP(6-5)	0
TCP(1-5)	0	TCP(3-2)	0	TCP(6-6)	0
TCP(1-6)	0	TCP(3-3)	0	TCP(6-7)	0
TCP(2-1)	2	TCP(3-4)	0	TCP(6-8)	0
TCP(2-2)	0	TCP(5-1)	0	TCP(6-9)	0
TRAFFIC CONTROL PLAN PILOT VEHICLE OPERATION					0
TRAFFIC CONTROL PLAN TWO LANE CLOSURES ON FOUR LANE UNDIVIDED HIGHWAYS					0
TRAFFIC CONTROL PLAN LANE CLOSURES WITH BARRIER					0
TRAFFIC CONTROL PLAN SHOULDER CLOSURES WITH BARRIER					2
TRAFFIC CONTROL PLAN WORK SPACE NEAR SHOULDER					0
TRAFFIC CONTROL PLAN CROSSOVER CLOSURE					0
TRAFFIC CONTROL PLAN TURNAROUND CLOSURE					0
TRAFFIC CONTROL PLAN LANE CLOSURES WITH TRAFFIC SIGNAL AND BARRIER					0
TRAFFIC CONTROL PLAN LANE CLOSURES WITH TRAFFIC SIGNAL					0
TRAFFIC CONTROL PLAN FREEWAY CLOSURE					0

PORTABLE CHANGEABLE MESSAGE SIGN REQUIREMENTS

Provide the portable changeable message signs listed in the table below. The Contractor shall determine if multiple operations will occur at the same time, to determine the total number of portable changeable message signs needed for the project.

TCP(6-1)	0	TCP(6-6)	0	TCP(SC-5)	0
TCP(6-2)	0	TCP(6-7)	0	TCP(SC-6)	0
TCP(6-3)	0	TCP(6-8)	0		
TCP(6-4)	0	TCP(6-9)	0		
TRAFFIC CONTROL PLAN LANE CLOSURES WITH BARRIER					0
TRAFFIC CONTROL PLAN SHOULDER CLOSURES WITH BARRIER					0
TRAFFIC CONTROL PLAN LANE CLOSURES WITH TRAFFIC SIGNAL AND BARRIER					0
TRAFFIC CONTROL PLAN LANE CLOSURES WITH TRAFFIC SIGNAL					4
TRAFFIC CONTROL PLAN FREEWAY CLOSURE					0

TYPICAL USAGE


MOBILE
Work that moves continuously or intermittently (stopping for up to approximately 15 minutes).

SHORT DURATION
Work that occupies a location up to 1 hour.

SHORT TERM STATIONARY
Daytime work that occupies a location for more than 1 hour in a single daylight period.

INTERMEDIATE TERM STATIONARY
Work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than 1 hour.

LONG TERM STATIONARY
Work that occupies a location more than 3 days.



Texas Department of Transportation San Angelo District


TRAFFIC CONTROL PLAN GENERAL REQUIREMENTS

SHEET 1 OF 1 NOT TO SCALE


©TxDOT 2024	CONT	SECT	JOB	HIGHWAY
SHEET ISSUED OR LAST REVISED	0069	07	116, ETC.	US 87
01-24	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	40	

DATE: 5/28/2024 1:11:50 PM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms381551\td10240091bb_sdet33.dgn

DATE: 5/28/2024 1:12:08 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms381551td10240091bb_sdet36.dgn



TYPICAL MULTILANE CONVENTIONAL ROADWAY



TYPICAL DIVIDED HIGHWAY OR FREEWAY OR TYPICAL ONE-WAY FRONTAGE ROAD

LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger
	Raised Pavement Markers Ty II-AA		Pilot Vehicle
	Temporary or Portable Traffic Signal		Automated Flagger Assistance Device (AFAD)

Posted Speed	Formula	Minimum Desirable Taper Lengths * X			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing * X Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	570'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'
80		800'	880'	960'	80'	160'	1000'	615'	910'

**Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

GENERAL NOTES

- Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
- A shadow vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, type 3 barricades or other channelizing devices may be substituted for the shadow vehicle and TMA.
- Additional shadow vehicles with TMA may be positioned off the paved surface, next to those shown in order to protect wider work spaces.
- Warning signs shall be appropriately altered for work space near left shoulder of divided highway, freeway, or one-way frontage road.
- Use END ROAD WORK signs for intermediate term stationary and long term stationary work zones.
- Omit shadow vehicle with TMA when working behind guard rail or barrier.
- Omit flags attached to signs on freeways.

PAY ITEMS
 6185 6002 TMA (STATIONARY) DAY



5/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144



TRAFFIC CONTROL PLAN
 WORK SPACE
 NEAR SHOULDER

SHEET 1 OF 1		NOT TO SCALE	
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
SHEET ISSUED OR LAST REVISED		COUNTY	SHEET NO.
11-19		TOM GREEN	41

NOTES:

1. CONTRACTOR SHALL HAND DIG TEST HOLES PRIOR TO INSTALLATION AT PROPOSED POLE FOUNDATION SITES WHERE BURIED UTILITIES MAY BE PRESENT PRIOR TO INSTALLATION.
2. ALL TRAFFIC SIGNAL HEADS SHALL HAVE BACK PLATES.
3. PROPOSED VEHICLE HEAD ASSEMBLIES (INCLUDING BACKPLATES) SHALL BE INSTALLED TO PROVIDE A MINIMUM OF 18.5 FEET VERTICAL CLEARANCE ABOVE ROADWAY SERVICE.
4. LUMINAIRE SYMBOLS MAY BE SHOWN ROTATED FOR CLARITY. CONTRACTOR SHALL COORDINATE INSTALLATION WITH CITY OF SAN ANGELO INSPECTOR AND TXDOT AREA OFFICE PROVIDING FOR OPTIMAL SAFETY ILLUMINATION AT EACH INTERSECTION.
5. EACH VEHICLE SIGNAL HEAD SHALL BE ALIGNED WITH THE CENTER OF THE LANE IT SERVES UNLESS DIRECTED OTHERWISE BY THE ENGINEER.
6. CONTRACTOR SHALL PROVIDE AND INSTALL ADDITIONAL MAST ARM DAMPING PLATES WHERE REQUIRED TO MEET MINIMUM VERTICAL MOVEMENT LISTED IN DETECTION CAMERA EQUIPMENT SPECIFICATIONS.
7. THE INFORMATION SHOWN ON THESE DRAWINGS CONCERNING THE TYPE AND LOCATION OF UNDERGROUND UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR COMPREHENSIVE. BEFORE CONSTRUCTION, CONTRACTOR SHALL DETERMINE THE TYPE AND LOCATION OF UNDERGROUND UTILITIES PRESENT IN ORDER TO AVOID DAMAGE THERETO.
8. THE LOCATION OF THE PROPOSED SIGNAL POLES, SIGNAL HEADS, DETECTION EQUIPMENT, GROUND BOXES AND CONDUCTORS ARE DIAGRAMMATIC ONLY AND MAY BE SHIFTED BY THE ENGINEER TO ACCOMMODATE FIELD CONDITIONS.
9. CONTRACTOR SHALL ARRANGE AND PAY FOR INSTALLATION, ADJUSTMENT OR REMOVAL OF ANY ELECTRIC SERVICE POLES, METER ENCLOSURES OR OVERHEAD ELECTRIC CABLES AS REQUIRED BY THIS PROJECT. PRIOR TO STARTING WORK, COORDINATE WITH THE AFFECTED UTILITY PROVIDERS, INCLUDING BUT NOT LIMITED TO:

AEP: (877) 373-4858


REFER TO GENERAL NOTES AND TXDOT ELECTRICAL DETAIL SHEETS FOR ADDITIONAL INFORMATION.
10. GRIDSMART DEVICES AND REQUIRED CABLING WILL BE INSTALLED BY THE CONTRACTOR AND PAID FOR UNDER ITEM 680 6002.
11. SIGNAL POLES SHALL BE GALVANIZED STEEL FINISH.
12. IF FIELD CONDITIONS PRECLUDE INSTALLATION OF ANY PROPOSED SIGNAL POLE AT THE LOCATION SHOWN ON THE PLANS, THE CONTRACTOR SHALL CONTACT THE TXDOT AREA OFFICE AND DISTRICT TRAFFIC ENGINEER TO MEET ON SITE TO DISCUSS NEW LOCATIONS.
13. NO LANE CLOSURES ALLOWED DURING PEAK HOURS. OFF-PEAK HOURS ARE 9 AM TO 3 PM AND 9 PM TO 5 AM ON WEEKDAYS.

14. CONTRACTOR IS RESPONSIBLE FOR PROTECTION OF ALL PROPERTY CORNERS AND PINS.
15. CONTRACTOR IS RESPONSIBLE FOR THE REPAIR OF ANY DAMAGE TO EXISTING IMPROVEMENTS DURING CONSTRUCTION, SUCH AS, BUT NOT LIMITED TO: DRAINAGE, UTILITIES, PAVEMENT, STRIPING, CURB, ETC. REPAIRS SHALL BE EQUAL TO OR BETTER THAN EXISTING CONDITIONS.
16. CONTRACTOR SHALL COMPLY WITH THE LATEST STANDARDS OF OSHA DIRECTIVES OR ANY OTHER AGENCY HAVING JURISDICTION FOR EXCAVATION AND TRENCHING PROCEDURE. CONTRACTOR SHALL USE SUPPORT SYSTEMS, SLOPING, BENCHING, OR OTHER MEANS OF PROTECTION, INCLUDING, BUT NOT LIMITED TO ACCESS AND EGRESS FROM ALL EXCAVATION AND TRENCHING. CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH PERFORMANCE CRITERIA FOR OSHA.
17. CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING THE PUBLIC DURING CONSTRUCTION, INCLUDING BUT NOT LIMITED TO: CONSTRUCTION FENCING, BARRICADES, SIGNAGE, TRAFFIC CONTROL DEVICES, SHADOW VEHICLES, ETC.
18. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE PRESENCE OF EXISTING UTILITIES WITHIN THE PROJECT AREA.
19. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND IMPLEMENTING AN ASBESTOS OR OTHER HAZARDOUS MATERIAL ABATEMENT PLAN, IF APPLICABLE.
20. CONTRACTOR SHALL COMPLETE REMOVAL AND PROPER DISPOSAL OF ALL FOUNDATIONS, PAVEMENTS, AND ABANDONED UNDERGROUND UTILITIES ENCOUNTERED THAT ARE NOT REUSED AND ARE IN CONFLICT WITH PROPOSED WORK.
21. ALL FOUNDATIONS SHALL BE REMOVED TO A MINIMUM OF 6" BLOW FINISHED GRADE.
22. CONTRACTOR SHALL REMOVE AND REPLACE VEGETATION, IMPROVEMENTS, OR OBSTRUCTIONS INTERFERING WITH INSTALLATION OF NEW CONSTRUCTION WITHIN THE PROJECT AREA. THIS SHALL BE SUBSIDIARY TO APPLICABLE INSTALLATION ITEMS.
23. DO NOT INTERRUPT EXISTING UTILITIES SERVING FACILITIES OCCUPIED OR IN USE WITHOUT PRIOR WRITTEN APPROVAL FROM UTILITY COMPANY. CONTRACTOR SHALL ENSURE TEMPORARY UTILITY SERVICES, IF APPLICABLE, ARE OPERATIONAL BEFORE INTERRUPTION OF EXISTING SERVICES.
24. PRIOR TO ANY CONSTRUCTION THE CONTRACTOR SHALL BE FAMILIAR WITH CONTRACT DOCUMENTS, SPECIFICATIONS, CONSTRUCTION PLANS, ALL NOTES, CITY STANDARDS AND ANY OTHER SPECIFICATIONS APPLICABLE TO THE PROPER COMPLETION OF THIS PROJECT.
25. PRIOR TO ANY DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL HAVE IN HIS POSSESSION ALL NECESSARY PERMITS AND LICENSES. CONTRACTOR SHALL HAVE AT LEAST ONSET OF APPROVED ENGINEERING PLANS AND SPECIFICATIONS AT ALL TIMES.


26. ALL WORK SHALL CONFORM TO CITY OF SAN ANGELO AND TXDOT SPECIFICATIONS, STANDARDS, AND DETAILS.
27. BARRICADING, TRAFFIC CONTROL AND PROJECT SIGNS SHALL CONFORM TO "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" AS CORRECTLY AMENDED AND CITY STANDARDS.
28. ALL DEMOLITION AND EXCAVATED MATERIALS SHALL BE LEGALLY DISPOSED OF OFF SITE BY THE CONTRACTOR. ALL LANDSCAPE MATERIALS AFFECTED BY THIS WORK SHALL BE SET ASIDE AND REINSTALLED AFTER COMPLETION OF THE WORK.
29. ALL PAVEMENT AND CONCRETE REMOVAL ADJACENT TO EXISTING PAVEMENT SHALL BE REMOVED BY FULL DEPTH SAWCUT.
30. PRIOR TO BID THE CONTRACTOR SHALL VISIT THE SITE.
31. ALL EXISTING SIGNAL EQUIPMENT SHALL BE SALVAGED AND DELIVERED TO CITY OF SAN ANGELO LOCATION. CONTRACTOR SHALL COORDINATE WITH CITY DIRECTLY.

ALL EXISTING SIGNAL EQUIPMENT DEEMED SERVICEABLE BY THE CITY OF SAN ANGELO TRAFFIC OPERATIONS DEPARTMENT SHALL BE SALVAGED AND DELIVERED TO THE CITY SIGNAL SHOP. CONTRACTOR SHALL COORDINATE ASSESSMENT AND DELIVERY OF SALVAGED ITEMS:

ROBERT KARCH
CITY OF SAN ANGELO
TRAFFIC OPERATIONS SUPERVISOR
(325) 657-4377
robert.karch@cosatx.us



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144




Texas Department of Transportation

US 87

SIGNAL CONSTRUCTION
NOTES


©TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		42

DATE: 6/28/2024 3:13:08 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091ha_tsig01b.dgn



LEGEND

- LANE ASSIGNMENT
- SIDEWALK REMOVAL
- EXISTING PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL
- EXISTING MAST ARM ASSEMBLY
- EXISTING VEHICLE SIGNAL HEAD
- EXISTING SIGN
- EXISTING CONTROLLER/ GROUND BOX
- EXISTING LUMINAIRE
- STORM DRAIN MANHOLE
- SANITARY SEWER MANHOLE
- EXISTING FIRE HYDRANT
- EXISTING GAS LINE
- EXISTING OVERHEAD ELECTRIC
- EXISTING TREE
- RIGHT OF WAY



CAUTION !!
 THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT BURIED UTILITIES INCLUDING GAS ARE KNOWN TO EXIST IN THE VICINITY THIS PROJECT. THE CONTRACTOR SHALL CONTACT THE TEXAS 811 ONE CALL UTILITY LOCATION SERVICE A MINIMUM OF 48 HOURS PRIOR TO EXCAVATION AND NOTIFY THE ENGINEER PROMPTLY OF ALL CONFLICTS.

- NOTES:**
1. ALL ITEMS NOT SPECIFICALLY IDENTIFIED ON THIS SHEET FOR REMOVAL SHALL BE RETAINED.
 2. CONTRACTOR SHALL DEFER REMOVAL OF ANY EQUIPMENT NECESSARY TO MAINTAIN CONTINUOUS OPERATION OF THE EXISTING SIGNALIZED INTERSECTION UNTIL THE PROPOSED TRAFFIC SIGNAL IS IN OPERATION.
 3. DEMOLITION OF GROUND MOUNTED SMALL SIGN ASSEMBLIES SHALL BE FINISHED FLUSH WITH SIDEWALK OR AT GRADE.
 4. DEMOLITION OF POLE AND EQUIPMENT FOUNDATIONS SHALL BE CONDUCTED TO A MINIMUM DEPTH OF 6 INCHES BELOW FINISHED GRADE.



6/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87
EXISTING CONDITIONS AND REMOVALS BRYANT AT 23RD

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		43

MS BG TA BG


APS PUSHBUTTONS			
KEY	PB1	PB2	PB3
LEGEND			
DESC	R10-3eR 9" x 15"	R10-3eL 9" x 15"	R10-3eLR 9" x 15"
QTY	4	4	2

TRAFFIC SIGNAL HEADS			
KEY	LEGEND	QTY	DESC
1		8	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
2		2	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
W1 THRU W10		10	16" x 18" LED COUNTDOWN PEDESTRIAN SIGNALS



LEGEND	
	POLE & EQUIPMENT IDENTIFIER
	CABLE / CONDUIT RUN
	VEHICLE SIGNAL HEAD
	PEDESTRIAN SIGNAL
	APS PUSHBUTTON
	TRAFFIC SIGNAL SIGN
	LANE ASSIGNMENT
	MAST ARM ASSEMBLY
	MAST ARM MOUNT SIGN LUMINAIRE
	VEHICLE SIGNAL HEAD
	GRIDSMArt FE3 CAMERA ASSEMBLY
	OPTICOM DETECTOR
	WIRELESS ANTENNA
	PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL & PUSHBUTTON
	SHALLOW FOUNDATION (SEE DETAIL)
	ELECTRIC SERVICE POLE & METER
	TYPE D GROUND BOX W/ CONCRETE APRON
	TRAFFIC SIGNAL CONTROLLER
	CONDUIT RUN (BORE)
	CONDUIT RUN (TRENCH)
	EXISTING GROUND BOX
	EXISTING MAST ARM ASSEMBLY
	GROUND MOUNT SIGN (SEE SIGNING SHEET)
	RIGHT OF WAY

TRAFFIC SIGNAL SIGNS			
KEY	LEGEND	DESC	QTY
T1		SEE SIGN DETAILS	1
T2		SEE SIGN DETAILS	1
T3		SEE SIGN DETAILS	1
T4		R10-5L 30" x 36"	2
T5		R10-17T 30" x 30"	2



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144
FREESE AND NICHOLS
Texas Department of Transportation

US 87			
SIGNAL LAYOUTS BRYANT AT 23RD			
© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		44

DATE: 6/28/2024 3:13:27 PM
FILE: c:\pwworking\freese-pw-bentley.com\freese-pw-01\dms38161\td10240091ha_tsig01.dgn

DATE: 6/28/2024 4:06:23 PM
 FILE: c:\pwworking\freese-pw.com\freese-pw-01\dms38161\td10240091ha_tsq01a.dgn

SCHEDULE OF CONDUIT AND CONDUCTORS																																	
CABLE RUN ID #	RUN LENGTH	INSTALL TYPE	ITEM 618										ITEM 620							ITEM 621					OPTICOM		SERIAL COMMS		GRIDSMAST SYSTEM				
			6046		6047		6053		6058		6059		6007		6009		6010		6005		6007		6031	6033	6036		6046		CAT-5	CAT 6	CAT-6		
			COND (PVC) (SCH 80) (2")	COND (PVC) (SCH 80) (2") (BORE)	COND (PVC) (SCH 80) (3")	COND (PVC) (SCH 80) (4")	COND (PVC) (SCH 80) (4") (BORE)	ELEC COND (NO. 8) BARE	ELEC COND (NO. 6) BARE	ELEC COND (NO. 6) INSULATED	TRAY CABLE (4 CNDR) (12AWG)	TRF SIG CBL (TY C) (12 AWG) (2 CNDR)	TRF SIG CBL (TY A) (14 AWG) (5 CNDR)	TRF SIG CBL (TY A) (14 AWG) (7 CNDR)	TRF SIG CBL (TY A) (14 AWG) (10 CNDR)	TRF SIG CBL (TY A) (14 AWG) (20 CNDR)	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA
ELECTRIC SERVICE CABLES PULLED BY AEP (THIS RUN ONLY)																																	
01	150 LF	A																															
02	14 LF	T	2 28																														
03	23 LF	T	1 23 2 46																														
04	11 LF	T	1 11																														
05	17 LF	T	1 17																														
06	35 LF	T	1 35 2 70																														
07	7 LF	T	1 7																														
08	38 LF	B	1 38 2 76																														
09	16 LF	T	1 16 2 32																														
10	18 LF	T	1 18 2 36																														
11	4 LF	E																															
12	72 LF	B	1 72 2 144																														
13	10 LF	T	1 10																														
14	17 LF	T	1 17																														
15	10 LF	T	1 10																														
16	60 LF	B	1 60 2 120																														
17	27 LF	T	1 27 2 54																														
18	9 LF	T	1 9																														
19	9 LF	T	1 9 2 18																														
20	8 LF	T	1 8																														
21	51 LF	B	1 51 2 102																														
22	14 LF	T	1 14 2 28																														
23	12 LF	T	1 12																														
24	11 LF	T	1 11																														
25	64 LF	B	1 64 2 128 3 192																														
26	18 LF	T	1 18 2 36 3 54																														
27	52 LF	B	1 52 2 104 3 156																														
28	10 LF	T	1 10																														
SUBTOTAL			184	337	116	304	491	1418	14	28	520	1290			1262	559	295	42	42														
POLE & MAST ARM INTERIOR CABLE RUNS																																	
POLE ID	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	
01																																	
02																																	
03																																	
04																																	
05																																	
06																																	
07																																	
08																																	
09																																	
10																																	
11																																	
12																																	
13																																	
14																																	
15																																	
16																																	
17																																	
18																																	
19																																	
20																																	
21																																	
22																																	
23																																	
24																																	
25																																	
26																																	
27																																	
28																																	
SUBTOTAL			184	337	116	304	491	1418	14	28	120	50	100	572	1262	559	427	106	64														

INSTALL TYPE: (A) AERIAL, (B) BORE, (E) EXISTING, (T) TRENCH
 ALL CABLE & CONDUIT RUN LENGTHS PROVIDED FOR CONTRACTOR'S INFORMATION ONLY
 NOTE: CONNECT RUN 11 TO EXISTING CONDUIT FEEDING INTO EXISTING POLE F. BRING NEW 20 CONDUCTOR CABLE TO TERMINAL BLOCK OF POLE F.

N BRYANT BLVD AT W 23RD ST SCHEDULE OF PEDESTAL POLE ASSEMBLIES						
POLE ID	SPREAD FOOTING FND	ITEM 416*		ITEM 687		ITEM 688
		6030	6001	6002	6001	
		DRILL SHAFT (TRF SIG POLE) (24 IN)	PED POLE ASSEMBLY	PEDESTRIAN PUSH BUTTON POLE	PED DETECT PUSH BUTTON (APS)	
EA	LF	EA	LF	EA	LF	EA
C	4	1	1	1		1
E	4	1	1	1		1
G	1	1	1	1		2
H	1	1	1	1		1
K	4	1	1	1		1
L	4	1	1	1		1
M	4	1	1	1		1
N	4	1	1	1		1
O	1	1	1	1		1
TOTAL:	3	24	9	9		10

*THE POLE FOUNDATION LENGTHS ARE FOR EMBEDMENT AND THE CONTRACTOR SHALL VERIFY IN THE FIELD WHAT ADDITIONAL HEIGHT IS REQUIRED ABOVE THE FINAL GRADE PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. PRIOR TO ORDERING FOUNDATION STEEL, FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. DRILL SHAFT LENGTHS ARE SHOWN FOR INFORMATION ONLY.

N BRYANT BLVD AT W 23RD ST SCHEDULE OF TRAFFIC POLE ASSEMBLIES					
POLE ID	ITEM 416		ITEM 686		
	6031	6032	6027	6047	6051
	DRILL SHAFT (TRF SIG POLE) (30 IN) *	DRILL SHAFT (TRF SIG POLE) (36 IN) *	INST TRF SIG PL AM(S)1 ARM(24') LUM	INST TRF SIG PL AM(S)1 ARM(44') LUM	INST TRF SIG PL AM(S)1 ARM(48') LUM
EA	LF	EA	EA	EA	EA
D	13				
J	13				
P	11				
TOTAL:	11	26	1	1	1

*THE POLE FOUNDATION LENGTHS ARE FOR EMBEDMENT AND THE CONTRACTOR SHALL VERIFY IN THE FIELD WHAT ADDITIONAL HEIGHT IS REQUIRED ABOVE THE FINAL GRADE PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. PRIOR TO ORDERING FOUNDATION STEEL, FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD.

N BRYANT BLVD AT W 23RD ST SCHEDULE OF GROUND BOXES	
ITEM 624-6010	GROUND BOX TY D (162922) W/ APRON
TOTAL	11



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144

FRESE & NICHOLS

Texas Department of Transportation

US 87
CONDUITS, CABLES AND QUANTITIES
BRYANT AT 23RD

© TxDOT 2024 SHEET 1 of 2

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	45


CK: BG
 DW: TA
 CK: BG
 DW: MS

APS MESSAGE CHART			
POLE LOCATION	PEDESTRIAN MOVEMENT PHASE ϕ	FUNCTIONS	SPEECH MESSAGE/SOUND DETAILS
BJKM	2, 6	BUTTON PUSH ON DW LOCATOR TONE WALK INDICATOR	WAIT SLOW TICK WALK SIGN IS ON TO CROSS TWENTY THIRD
CGHLNQ	4, 8	BUTTON PUSH ON DW LOCATOR TONE WALK INDICATOR	WAIT SLOW TICK WALK SIGN IS ON TO CROSS BRYANT

N BRYANT BLVD AT W 23RD ST ELECTRICAL SERVICE DATA* ITEM 628-6145											
PLAN ID	ELECTRICAL SERVICE DESCRIPTION (SEE ED (5)-14)	SERVICE CONDUIT SIZE (RMC)	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK	TWO-POLE CONTACTOR AMPS	PANEL BD./LOAD CENTER AMP	CIRCUIT NO.	BRANCH CKT. BRK. POLE/AMPS	BRANCH CIRCUIT AMPS	KVA LOAD
A	ELC SRV TY D 120/240 060 (NS) SS (E) SP (O)	2"	3/#6	N/A	2P/60	40	100	SIGNAL LIGHTING	1P/30 2P/20	5 4	<7.1

* CONTRACTOR SHALL VERIFY WITH POWER COMPANY THE LOCATION OF THE SERVICE, THE TRANSFORMER, ANY INSTALLATION REQUIREMENTS, AND OBTAIN THE APPROPRIATE METER ENCLOSURE TO INSTALL ON THE NEW SERVICE POLE.

SCHEDULE OF TRAFFIC SIGNAL HEADS ITEM 682										
PHASE ϕ	HEAD TYPE ID	QTY	6001	6002	6003	6004	6005	6006	6054	6055
			VEH SIG (12") LED (GRN)	VEH SIG (12") LED (GRN ARW)	VEH SIG (12") LED (YEL)	VEH SIG (12") LED (YEL ARW)	VEH SIG (12") LED (RED)	VEH SIG (12") LED (RED ARW)	BACKPLATE W/REF BRDR (3 SEC) (VENT) ALUM	BACKPLATE W/REF BRDR (4 SEC) (VENT) ALUM
1	2	1	EA	EA	EA	EA	EA	EA	EA	EA
2	1	2	2	1	2	2	2	1	2	1
4	1	2	2		2	2	2		2	
5	2	1		1		2		1		1
6	1	2	2		2		2		2	
8	1	2	2		2		2		2	
TOTAL:			8	2	8	4	8	2	8	2



PEDESTAL POLE DETAIL
FOR POLES G H Q
NOT TO SCALE

POLE & EQUIPMENT INFORMATION				
ID	DESCRIPTION	NORTHING	EASTING	FND. ELEV
A	PROPOSED METER AND SERVICE POLE TO BE BY PROVIDED AND INSTALLED BY AEP.	N/A	N/A	N/A
B	INSTALL TRAFFIC SIGNAL CONTROLLER ASSEMBLY ON BASE-MOUNT FOUNDATION WITH EXTERNAL CABINET-MOUNTED BATTERY BACKUP SYSTEM.	N/A	N/A	FLUSH W/ SIDEWALK
C	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504280.72'	2258672.34'	FLUSH W/ SIDEWALK
D	INSTALL 30 FT SMA-80 ON 13 FT DRILLED SHAFT FND. (36-A) WITH 44 FT MAST ARM, ONE WIND DAMPER ASSEMBLY, ONE LUMINAIRE (LED), ONE GRIDSMART FE3 CAMERA, ONE WIRELESS ANTENNA, ONE OPTICOM EMERGENCY PREEMPTION DETECTOR, ONE STREET NAME SIGN, ONE R10-17T SIGN AND THREE VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10504287.48'	2258663.02'	LEVEL W/ ROADWAY CROWN
E	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504272.36'	2258679.55'	FLUSH W/ SIDEWALK
F	ON EXISTING TRAFFIC SIGNAL POLE, INSTALL ONE R10-5L SIGN AND TWO VEHICLE SIGNAL HEADS AS ILLUSTRATED.	N/A	N/A	N/A
G	INSTALL 10 FT PEDESTAL POLE ON SPREAD FOOTING FND. WITH TWO COUNTDOWN PEDESTRIAN SIGNAL HEADS AND TWO APS PUSH BUTTONS WITH SIGNS AS ILLUSTRATED.	10504234.72'	2258729.62'	FLUSH W/ SIDEWALK
H	INSTALL 10 FT PEDESTAL POLE ON SPREAD FOOTING FND. WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504184.82'	2258677.80'	FLUSH W/ SIDEWALK
J	INSTALL 30 FT SMA-80 ON 13 FT DRILLED SHAFT FND. (36-A) WITH 48 FT MAST ARM, ONE WIND DAMPER ASSEMBLY, ONE LUMINAIRE (LED), ONE OPTICOM EMERGENCY PREEMPTION DETECTOR, ONE STREET NAME SIGN, ONE R10-17T SIGN AND THREE VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10504135.89'	2258641.90'	LEVEL W/ ROADWAY CROWN
K	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504143.44'	2258614.25'	FLUSH W/ SIDEWALK
L	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504136.63'	2258635.64'	FLUSH W/ SIDEWALK
M	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504175.06'	2258572.33'	FLUSH W/ SIDEWALK
N	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504187.86'	2258574.23'	FLUSH W/ SIDEWALK
P	INSTALL 30 FT SMA-80 ON 11 FT DRILLED SHAFT FND. (30-A) WITH 24 FT MAST ARM, ONE LUMINAIRE (LED), ONE STREET NAME SIGN, ONE R10-5L SIGN AND TWO VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10504116.13'	2258571.61'	LEVEL W/ ROADWAY CROWN
Q	INSTALL 10 FT PEDESTAL POLE ON SPREAD FOOTING FND. WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10504230.41'	2258616.91'	FLUSH W/ SIDEWALK



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144




US 87
CONDUITS, CABLES
AND QUANTITIES
BRYANT AT 23RD

©TxDOT 2024		SHEET 2 of 2	
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	46


DATE: 6/28/2024 4:06:38 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091\ha_tsig01aa.dgn

T1




D3-1G;
1.0" Radius, 0.8" Border, White on Green;
"St", Clearview Hwy-3-W; "400", Clearview Hwy-3-W; "W. 23rd", Clearview Hwy-3-W; "Blk", Clearview Hwy-3-W;
"500", Clearview Hwy-3-W;

T2



D3-1G;
1.0" Radius, 0.8" Border, White on Green;
"Blk", Clearview Hwy-3-W; "2200", Clearview Hwy-3-W; "N. Bryant", Clearview Hwy-3-W; "Blvd", Clearview Hwy-3-W; "2300", Clearview Hwy-3-W;

T3



D3-1G;
1.0" Radius, 0.8" Border, White on Green;
"Blk", Clearview Hwy-3-W; "500", Clearview Hwy-3-W; "W. 23rd", Clearview Hwy-3-W; "St", Clearview Hwy-3-W;
"400", Clearview Hwy-3-W;

NOTE: ALL DIMENSIONS ARE IN INCHES.



6/25/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



Texas Department of Transportation


US 87

SIGN DETAILS
BRYANT AT 23RD

© TxDOT 2024

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	47	

CK: BG
DW: TA
CK: BG
DW: MS



LEGEND

- W DETECTABLE WARNING SURFACE
- R RAMP
- L TURNING SPACE
- F FLARE
- - - SLOTTED CURB
- CONCRETE RIPRAP
- (A) REFL PAV MRK TY I (W) 24" (SLD) (100MIL)
- (B) RE PM W/RET REQ TY I (W) 6" (SLD) (100MIL)
- (C) RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
- (D) RE PM W/RET REQ TY I (Y) 6" (SLD) (100MIL)
- (E) REFL PAV MRK TY I (W) (ARROW) (100MIL)
- (F) REFL PAV MRK TY I (W) (WORD) (100MIL)
- (G) REFL PAV MRKR TYII-C-R
- S# SIGN IDENTIFIER
- GROUND MOUNTED SIGN
- - - RIGHT OF WAY




6/25/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87
PAVEMENT MARKINGS
AND PEDESTRIAN RAMPS
BRYANT AT 23RD


© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		48

DATE: 6/25/2024 9:09:09 AM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38156\td1024091ce_rdwy00.dgn




- NOTES:**
1. DIMENSIONS AND DETAILS OF PROPOSED CURB RAMPS ARE FOR GUIDANCE TO THE CONTRACTOR. CONTRACTOR SHALL ENSURE RAMPS ARE BUILT PER STANDARD AND ARE ADA ACCESSIBLE.
 2. ALL REQUIRED WORK TO ENSURE ADA ACCESSIBILITY FOR EACH PROPOSED RAMP SHALL BE SUBSIDIARY TO THE RAMP BID ITEM.
 3. CONTRACTOR SHALL SAWCUT EXISTING CONCRETE AT ALL REMOVAL AND TIE-IN LIMITS.
 4. UNLESS OTHERWISE SHOWN, LANDINGS SHALL BE PAID FOR AS PART OF ITEM 690 6092 INSTALL SIDEWALK.
 5. ALL PAVEMENT MARKINGS WITHIN 200 FT OF EACH CROSSWALK ALONG US 87 SHALL BE REFRESHED AS PART OF THIS PROJECT.

MS BG TA BG



LEGEND

- LANE ASSIGNMENT
- SIDEWALK REMOVAL
- EXISTING PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL
- EXISTING MAST ARM ASSEMBLY
- EXISTING VEHICLE SIGNAL HEAD
- EXISTING SIGN
- EXISTING CONTROLLER/ GROUND BOX
- EXISTING LUMINAIRE
- STORM DRAIN MANHOLE
- SANITARY SEWER MANHOLE
- EXISTING FIRE HYDRANT
- EXISTING GAS LINE
- EXISTING OVERHEAD ELECTRIC
- EXISTING TREE
- RIGHT OF WAY



6/25/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



Texas Department of Transportation

US 87
EXISTING CONDITIONS AND REMOVALS
KOENIGHEIM AT HARRIS

CAUTION !!

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT BURIED UTILITIES INCLUDING GAS ARE KNOWN TO EXIST IN THE VICINITY THIS PROJECT. THE CONTRACTOR SHALL CONTACT THE TEXAS 811 ONE CALL UTILITY LOCATION SERVICE A MINIMUM OF 48 HOURS PRIOR TO EXCAVATION AND NOTIFY THE ENGINEER PROMPTLY OF ALL CONFLICTS.

NOTES:

1. ALL ITEMS NOT SPECIFICALLY IDENTIFIED ON THIS SHEET FOR REMOVAL SHALL BE RETAINED.
2. DEMOLITION OF GROUND MOUNTED SMALL SIGN ASSEMBLIES SHALL BE FINISHED FLUSH WITH SIDEWALK OR AT GRADE.
3. DEMOLITION OF POLE AND EQUIPMENT FOUNDATIONS SHALL BE CONDUCTED TO A MINIMUM DEPTH OF 6 INCHES BELOW FINISHED GRADE.

© TxDOT 2024


CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	49

DATE: 6/25/2024 9:09:25 AM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091\ha_tsig02b.dgn

MS BG TA BG

APS PUSHBUTTONS	
KEY	LEGEND
PB1	
PB2	
QTY	DESC
4	R10-3eR 9" x 15"
4	R10-3eL 9" x 15"

TRAFFIC SIGNAL HEADS			
KEY	LEGEND	QTY	DESC
1		8	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
2		1	16" x 18" LED COUNTDOWN LED PEDESTRIAN SIGNALS
W1		8	16" x 18" LED COUNTDOWN LED PEDESTRIAN SIGNALS
THRU			
W8			



LEGEND	
	POLE & EQUIPMENT IDENTIFIER
	CABLE / CONDUIT RUN
	VEHICLE SIGNAL HEAD
	PEDESTRIAN SIGNAL
	APS PUSHBUTTON
	TRAFFIC SIGNAL SIGN
	LANE ASSIGNMENT
	MAST ARM ASSEMBLY
	MAST ARM MOUNT SIGN LUMINAIRE
	VEHICLE SIGNAL HEAD
	GRIDSMAST FE3 CAMERA ASSEMBLY
	OPTICOM DETECTOR
	WIRELESS ANTENNA
	PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL & PUSHBUTTON
	ELECTRIC SERVICE POLE & METER
	TYPE D GROUND BOX W/ CONCRETE APRON
	TRAFFIC SIGNAL CONTROLLER
	CONDUIT RUN (BORE)
	CONDUIT RUN (TRENCH)
	EXISTING MAST ARM ASSEMBLY
	RIGHT OF WAY

TRAFFIC SIGNAL SIGNS			
KEY	LEGEND	DESC	QTY
T1		SEE SIGN DETAILS	1
T2		SEE SIGN DETAILS	1
T3		R3-2 24" x 24"	1
T4		R6-1R 36" x 12"	1
T5		R3-1 24" x 24"	1
T6		R6-1L 36" x 12"	1
T7		R10-17T 30" x 30"	1

PHASE DIAGRAM			
φ1 NOT USED	φ2 NOT USED	φ3 	φ4 PED
φ5 NOT USED	φ6 PED	φ7 NOT USED	φ8 PED
CONFLICT FLASH: YELLOW PHASE 6 RED PHASES 3, 4, 8			



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87
SIGNAL LAYOUTS
KOENIGHEIM AT HARRIS

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	50	

DATE: 6/28/2024 3:14:23 PM
FILE: c:\pwworking\freese-nichols.com\freese-pw-01\dms38161\td10240091ha_tsig02.dgn

APS MESSAGE CHART			
POLE LOCATION	PEDESTRIAN MOVEMENT PHASE	FUNCTIONS	SPEECH MESSAGE/SOUND DETAILS
C G K M	ϕ	BUTTON PUSH ON DW	WAIT
		LOCATOR TONE	SLOW TICK
		WALK INDICATOR	WALK SIGN IS ON TO CROSS HARRIS
E H K L	4, 8	BUTTON PUSH ON DW	WAIT
		LOCATOR TONE	SLOW TICK
		WALK INDICATOR	WALK SIGN IS ON TO CROSS KOENIGHEIM

N KOENIGHEIM ST AND W HARRIS AVE										
SCHEDULE OF TRAFFIC SIGNAL HEADS										
ITEM 682										
PHASE	HEAD TYPE ID	QTY	6001	6002	6003	6004	6005	6006	6054	6055
			VEH SIG SEC (12") LED (GRN)	VEH SIG SEC (12") LED (GRN ARW)	VEH SIG SEC (12") LED (YEL)	VEH SIG SEC (12") LED (YEL ARW)	VEH SIG SEC (12") LED (RED)	VEH SIG SEC (12") LED (RED ARW)	BACKPLATE W/REF BRDR (3 SEC) (VENT) ALUM	BACKPLATE W/REF BRDR (4 SEC) (VENT) ALUM
			EA	EA	EA	EA	EA	EA	EA	EA
3	2	1		1		2		1		1
4	1	2	2		2		2		2	
6	1	4	4		4		4		4	
8	1	2	2		2		2		2	
TOTAL:			8	1	8	2	8	1	8	1

N KOENIGHEIM ST AND W HARRIS AVE											
ELECTRICAL SERVICE DATA*											
ITEM 628-6145											
PLAN ID	ELECTRICAL SERVICE DESCRIPTION (SEE ED (5)-14)	SERVICE CONDUIT SIZE (RMC)	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK POLE/AMP	TWO-POLE CONTACTOR AMPS	PANEL BD./LOADCENTER AMP RATING (MIN)	CIRCUIT NO.	BRANCH CKT. BRK. POLE/AMPS	BRANCH CIRCUIT AMPS	KVA LOAD
A	ELC SRV TY D 120/240 060 (NS) SS (E) SP (O)	2"	3/#6	N/A	2P/60	40	100	SIGNAL LIGHTING	1P/30 2P/20	5 4	<7.1

* CONTRACTOR SHALL VERIFY WITH POWER COMPANY THE LOCATION OF THE SERVICE, THE TRANSFORMER, ANY INSTALLATION REQUIREMENTS, AND OBTAIN THE APPROPRIATE METER ENCLOSURE TO INSTALL ON THE NEW SERVICE POLE.



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144

FREESE AND NICHOLS


Texas Department of Transportation

US 87

**CONDUITS, CABLES AND QUANTITIES
KOENIGHEIM AT HARRIS**


©TxDOT 2024		SHEET 2 of 2	
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	52

T1



D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 "N. Koenigheim", ClearviewHwy-3-W; "St", ClearviewHwy-3-W; "0", ClearviewHwy-3-W; Standard Arrow Custom 10.9" X 10.9" 0°;

T2



D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 Standard Arrow Custom 10.9" X 10.9" 180°; "St", ClearviewHwy-3-W; "0", ClearviewHwy-3-W; "N. Koenigheim", ClearviewHwy-3-W;

NOTE: ALL DIMENSIONS ARE IN INCHES.



6/25/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144

FRESE AND NICHOLS

Texas Department of Transportation


US 87

SIGN DETAILS
 KOENIGHEIM AT HARRIS

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	53	


© TxDOT 2024

DW: MS CK: BG DW: TA CK: BG



LEGEND

- W DETECTABLE WARNING SURFACE
- R RAMP
- L TURNING SPACE
- F FLARE
- SLOTTED CURB
- CONCRETE RIPRAP
- (A) REFL PAV MRK TY I (W) 24" (SLD) (100MIL)
- (B) RE PM W/RET REQ TY I (W) 6" (SLD) (100MIL)
- (C) RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
- (D) RE PM W/RET REQ TY I (Y) 6" (SLD) (100MIL)
- (E) REFL PAV MRK TY I (W) (ARROW) (100MIL)
- (F) REFL PAV MRK TY I (W) (WORD) (100MIL)
- (G) REFL PAV MRKR TYII-C-R
- [S#] SIGN IDENTIFIER
- GROUND MOUNTED SIGN
- RIGHT OF WAY



- NOTES:**
1. DIMENSIONS AND DETAILS OF PROPOSED CURB RAMP ARE FOR GUIDANCE TO THE CONTRACTOR. CONTRACTOR SHALL ENSURE RAMP ARE BUILT PER STANDARD AND ARE ADA ACCESSIBLE.
 2. ALL REQUIRED WORK TO ENSURE ADA ACCESSIBILITY FOR EACH PROPOSED RAMP SHALL BE SUBSIDIARY TO THE RAMP BID ITEM.
 3. CONTRACTOR SHALL SAWCUT EXISTING CONCRETE AT ALL REMOVAL AND TIE-IN LIMITS.
 4. UNLESS OTHERWISE SHOWN, LANDINGS SHALL BE PAID FOR AS PART OF ITEM 690 6092 INSTALL SIDEWALK.
 5. ALL PAVEMENT MARKINGS WITHIN 200 FT OF EACH CROSSWALK ALONG US 87 SHALL BE REFRESHED AS PART OF THIS PROJECT.

STATE OF TEXAS
BREGGER A. GARRISON
122018
LICENSED PROFESSIONAL ENGINEER
6/25/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144


FREESE AND NICHOLS
Texas Department of Transportation

US 87
PAVEMENT MARKINGS AND PEDESTRIAN RAMPS
KOENIGHEIM AT HARRIS

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		54



DATE: 6/25/2024 9:10:45 AM
FILE: c:\pwworking\freese-pw-bentley.com\freese-pw-01\dms38156\td10240091ce_rdw01.dgn

MS BG TA BG



LEGEND

- LANE ASSIGNMENT
- SIDEWALK REMOVAL
- EXISTING PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL
- EXISTING MAST ARM ASSEMBLY
- EXISTING VEHICLE SIGNAL HEAD
- EXISTING SIGN
- EXISTING CONTROLLER/ GROUND BOX
- EXISTING LUMINAIRE
- STORM DRAIN MANHOLE
- SANITARY SEWER MANHOLE
- EXISTING FIRE HYDRANT
- EXISTING GAS LINE
- EXISTING OVERHEAD ELECTRIC
- EXISTING TREE
- RIGHT OF WAY



6/28/2024 TEXAS REGISTERED ENGINEERING FIRM F-2144



Texas Department of Transportation

US 87
EXISTING CONDITIONS
AND REMOVALS
ABE AT HARRIS

CAUTION !!

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT BURIED UTILITIES INCLUDING GAS ARE KNOWN TO EXIST IN THE VICINITY THIS PROJECT. THE CONTRACTOR SHALL CONTACT THE TEXAS 811 ONE CALL UTILITY LOCATION SERVICE A MINIMUM OF 48 HOURS PRIOR TO EXCAVATION AND NOTIFY THE ENGINEER PROMPTLY OF ALL CONFLICTS.

NOTES:

1. ALL ITEMS NOT SPECIFICALLY IDENTIFIED ON THIS SHEET FOR REMOVAL SHALL BE RETAINED.
2. DEMOLITION OF GROUND MOUNTED SMALL SIGN ASSEMBLIES SHALL BE FINISHED FLUSH WITH SIDEWALK OR AT GRADE.
3. DEMOLITION OF POLE AND EQUIPMENT FOUNDATIONS SHALL BE CONDUCTED TO A MINIMUM DEPTH OF 6 INCHES BELOW FINISHED GRADE.

© TxDOT 2024


CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	55

DATE: 6/28/2024 3:15:21 PM
FILE: c:\pwworking\freese-pw-bentley.com\freese-pw-01\dms38161\td10240091\ha_tsig03b.dgn

MS BG TA BG


APS PUSHBUTTONS			
KEY	LEGEND	DESC	QTY
PB1		R10-3eR 9" x 15"	4
PB2		R10-3eL 9" x 15"	4

TRAFFIC SIGNAL HEADS			
KEY	LEGEND	QTY	DESC
1		8	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
2		1	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
W1 THRU W8		8	16" x 18" LED COUNTDOWN PEDESTRIAN SIGNALS



LEGEND	
	POLE & EQUIPMENT IDENTIFIER
	CABLE / CONDUIT RUN
	VEHICLE SIGNAL HEAD
	PEDESTRIAN SIGNAL
	APS PUSHBUTTON
	TRAFFIC SIGNAL SIGN
	LANE ASSIGNMENT
	MAST ARM ASSEMBLY
	MAST ARM MOUNT SIGN
	LUMINAIRE
	VEHICLE SIGNAL HEAD
	GRIDSMArt FE3 CAMERA ASSEMBLY
	OPTICOM DETECTOR
	WIRELESS ANTENNA
	PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL & PUSHBUTTON
	ELECTRIC SERVICE POLE & METER
	ELECTRIC SERVICE DISCONNECT
	TYPE D GROUND BOX W/ CONCRETE APRON
	TRAFFIC SIGNAL CONTROLLER
	CONDUIT RUN (BORE)
	CONDUIT RUN (TRENCH)
	RIGHT OF WAY

TRAFFIC SIGNAL SIGNS			
KEY	LEGEND	DESC	QTY
T1		SEE SIGN DETAILS	1
T2		SEE SIGN DETAILS	1
T3		SEE SIGN DETAILS	1
T4		R3-2 24" x 24"	1
T5		R6-1R 36" x 12"	1
T6		R3-1 24" x 24"	1
T7		R6-1L 36" x 12"	1
T8		R10-17T 30" x 30"	1



PHASE DIAGRAM			
φ1 NOT USED	φ2 PED ↑ ↓ ↑ ↓ PED	φ3 NOT USED	φ4 PED ← → PED
φ5 NOT USED	φ6 NOT USED	φ7 ← →	φ8 ← → PED

CONFLICT FLASH:
YELLOW PHASE 2 RED PHASES 4, 7, 8



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87			
SIGNAL LAYOUTS ABE AT HARRIS			
© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		56

DATE: 6/28/2024 3:15:36 PM
FILE: c:\pwworking\freese-nichols.com\freese-pw-01\dms38161\td10240091\ha_tsig03.dgn

APS MESSAGE CHART			
POLE ID	PEDESTRIAN MOVEMENT PHASE ϕ	FUNCTIONS	SPEECH MESSAGE/SOUND DETAILS
E H K N	2	BUTTON PUSH ON DW LOCATOR TONE WALK INDICATOR	WAIT SLOW TICK WALK SIGN IS ON TO CROSS HARRIS
F G L M	4, 8	BUTTON PUSH ON DW LOCATOR TONE WALK INDICATOR	WAIT SLOW TICK WALK SIGN IS ON TO CROSS ABE

N ABE ST AND W HARRIS AVE										
SCHEDULE OF TRAFFIC SIGNAL HEADS										
ITEM 682										
PHASE ϕ	HEAD TYPE ID	QTY	6001	6002	6003	6004	6005	6006	6054	6055
			VEH SIG SEC (12") LED (GRN)	VEH SIG SEC (12") LED (GRN ARW)	VEH SIG SEC (12") LED (YEL)	VEH SIG SEC (12") LED (YEL ARW)	VEH SIG SEC (12") LED (RED)	VEH SIG SEC (12") LED (RED ARW)	BACKPLATE W/REF BRDR (3 SEC) (VENT) ALUM	BACKPLATE W/REF BRDR (4 SEC) (VENT) ALUM
			EA	EA	EA	EA	EA	EA	EA	EA
2	1	4	4		4		4		4	ϕ
7	2	1		1		2		1		1
4	1	2	2		2		2		2	
8	1	2	2		2		2		2	
TOTAL:			8	1	8	2	8	1	8	1

N ABE ST AND W HARRIS AVE											
ELECTRICAL SERVICE DATA*											
ITEM 628-6145											
PLAN ID	ELECTRICAL SERVICE DESCRIPTION (SEE ED (5)-14)	SERVICE CONDUIT SIZE (RMC)	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK POLE/AMP	TWO-POLE CONTACTOR AMPS	PANEL BD./LOADCENTER AMP RATING (MIN)	CIRCUIT NO.	BRANCH CKT. BRK. POLE/A	BRANCH CIRCUIT AMPS	KVA LOAD
A	ELC SRV TY D 120/240 060 (NS) SS (E) SP (0)	2"	3/#6	N/A	2P/60	40	100	SIGNAL LIGHTING	1P/30 2P/20	5 4	<7.1

* CONTRACTOR SHALL VERIFY WITH POWER COMPANY THE LOCATION OF THE SERVICE, THE TRANSFORMER, ANY INSTALLATION REQUIREMENTS, AND OBTAIN THE APPROPRIATE METER ENCLOSURE TO INSTALL ON THE NEW SERVICE POLE.




6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87
CONDUITS, CABLES
AND QUANTITIES
ABE AT HARRIS


© TxDOT 2024		SHEET 2 of 2	
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		58

T1




D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 "S. Abe", Clearview Hwy-3-W; "St", Clearview Hwy-3-W; "0", Clearview Hwy-3-W;
 Standard Arrow Custom 10.9" X 10.9" 0°;

T2



D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 "Blk", Clearview Hwy-3-W; "300", Clearview Hwy-3-W; "W. Harris", Clearview Hwy-3-W; "Ave", Clearview Hwy-3-W; "400", Clearview Hwy-3-W;

T3



D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 Standard Arrow Custom 10.9" X 10.9" 180°; "S. Abe", Clearview Hwy-3-W; "St", Clearview Hwy-3-W;
 "0", Clearview Hwy-3-W;

NOTE: ALL DIMENSIONS ARE IN INCHES.



6/25/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144

FREESE AND NICHOLS
 Texas Department of Transportation


US 87

SIGN DETAILS
 ABE AT HARRIS

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	59	


© TxDOT 2024

DW: MS
CK: BG
DW: TA
CK: BG



LEGEND

- W DETECTABLE WARNING SURFACE
- R RAMP
- L TURNING SPACE
- F FLARE
- SLOTTED CURB
- CONCRETE RIPRAP
- (A) REFL PAV MRK TY I (W) 24" (SLD) (100MIL)
- (B) RE PM W/RET REQ TY I (W) 6" (SLD) (100MIL)
- (C) RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
- (D) RE PM W/RET REQ TY I (Y) 6" (SLD) (100MIL)
- (E) REFL PAV MRK TY I (W) (ARROW) (100MIL)
- (F) REFL PAV MRK TY I (W) (WORD) (100MIL)
- (G) REFL PAV MRKR TYII-C-R
- [S#] SIGN IDENTIFIER
- GROUND MOUNTED SIGN
- RIGHT OF WAY



- NOTES:**
1. DIMENSIONS AND DETAILS OF PROPOSED CURB RAMP ARE FOR GUIDANCE TO THE CONTRACTOR. CONTRACTOR SHALL ENSURE RAMP ARE BUILT PER STANDARD AND ARE ADA ACCESSIBLE.
 2. ALL REQUIRED WORK TO ENSURE ADA ACCESSIBILITY FOR EACH PROPOSED RAMP SHALL BE SUBSIDIARY TO THE RAMP BID ITEM.
 3. CONTRACTOR SHALL SAWCUT EXISTING CONCRETE AT ALL REMOVAL AND TIE-IN LIMITS.
 4. UNLESS OTHERWISE SHOWN, LANDINGS SHALL BE PAID FOR AS PART OF ITEM 690 6092 INSTALL SIDEWALK.
 5. ALL PAVEMENT MARKINGS WITHIN 200 FT OF EACH CROSSWALK ALONG US 87 SHALL BE REFRESHED AS PART OF THIS PROJECT.



6/25/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



Texas Department of Transportation


US 87
PAVEMENT MARKINGS AND PEDESTRIAN RAMP
ABE AT HARRIS

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	60	
















DATE: 6/25/2024 9:12:27 AM
FILE: c:\pwworking\freese-pw-bentley.com\freese-pw-01\dms381561td10240091ce_rdw02.dgn

MS BG TA BG

DATE: 6/25/2024 9:12:43 AM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091\ha_tsig04b.dgn



LEGEND

-  LANE ASSIGNMENT
-  SIDEWALK REMOVAL
-  EXISTING PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL
-  EXISTING MAST ARM ASSEMBLY
-  EXISTING VEHICLE SIGNAL HEAD
-  EXISTING SIGN
-  EXISTING CONTROLLER/ GROUND BOX
-  EXISTING LUMINAIRE
-  STORM DRAIN MANHOLE
-  SANITARY SEWER MANHOLE
-  EXISTING FIRE HYDRANT
-  EXISTING GAS LINE
-  EXISTING OVERHEAD ELECTRIC
-  EXISTING TREE
-  RIGHT OF WAY

REMOVE/SALVAGE TRAFFIC SIGNAL POLE, FOUNDATION, MAST ARM ASSEMBLY AND ALL ATTACHED EQUIPMENT. ABANDON BURIED CONDUIT IN PLACE.

W CONCHO AVE
 POSTED SPEED 30MPH

US 87 (S ABE ST)
 POSTED SPEED 35MPH

W CONCHO AVE
 POSTED SPEED 30MPH

REMOVE 18 LF CURB
 REMOVE AND SALVAGE VEHICLE SIGNAL HEAD ASSEMBLIES 4 EA

REMOVE 23 LF CURB

RETAIN EXISTING DUAL MAST ARM TRAFFIC SIGNAL POLE

REMOVE GROUND MOUNTED SIGN POST ASSEMBLY AND ATTACHED "ONE WAY" SIGNS

REMOVE 196 SF SIDEWALK

REMOVE/RELOCATE EXISTING SMALL TREE (CRAPE MYRTLE)

REMOVE 108 SF SIDEWALK


US 87 (S ABE ST)
 POSTED SPEED 35MPH

CAUTION !!

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT BURIED UTILITIES INCLUDING GAS ARE KNOWN TO EXIST IN THE VICINITY THIS PROJECT. THE CONTRACTOR SHALL CONTACT THE TEXAS 811 ONE CALL UTILITY LOCATION SERVICE A MINIMUM OF 48 HOURS PRIOR TO EXCAVATION AND NOTIFY THE ENGINEER PROMPTLY OF ALL CONFLICTS.

NOTES:

1. ALL ITEMS NOT SPECIFICALLY IDENTIFIED ON THIS SHEET FOR REMOVAL SHALL BE RETAINED.
2. DEMOLITION OF GROUND MOUNTED SMALL SIGN ASSEMBLIES SHALL BE FINISHED FLUSH WITH SIDEWALK OR AT GRADE.
3. DEMOLITION OF POLE AND EQUIPMENT FOUNDATIONS SHALL BE CONDUCTED TO A MINIMUM DEPTH OF 6 INCHES BELOW FINISHED GRADE.



6/25/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144



Texas Department of Transportation

US 87
 EXISTING CONDITIONS AND REMOVALS
 ABE AT CONCHO

©TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	61


MS BG TA BG

APS PUSHBUTTONS	
KEY	LEGEND
PB1	
PB2	
QTY	DESC
4	R10-3eR 9" x 15"
4	R10-3eL 9" x 15"

TRAFFIC SIGNAL HEADS			
KEY	LEGEND	QTY	DESC
I		8	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
W1 THRU W8		8	16" x 18" LED COUNTDOWN PEDESTRIAN SIGNALS



LEGEND	
	POLE & EQUIPMENT IDENTIFIER
	CABLE / CONDUIT RUN
	VEHICLE SIGNAL HEAD
	PEDESTRIAN SIGNAL
	APS PUSHBUTTON
	TRAFFIC SIGNAL SIGN LANE ASSIGNMENT
	MAST ARM ASSEMBLY
	MAST ARM MOUNT SIGN LUMINAIRE
	VEHICLE SIGNAL HEAD
	GRIDSMArt FE3 CAMERA ASSEMBLY
	OPTICOM DETECTOR WIRELESS ANTENNA
	PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL & PUSHBUTTON
	ELECTRIC SERVICE POLE & METER
	TYPE D GROUND BOX W/ CONCRETE APRON
	TRAFFIC SIGNAL CONTROLLER
	CONDUIT RUN (BORE)
	CONDUIT RUN (TRENCH)
	EXISTING MAST ARM ASSEMBLY
	GROUND MOUNT SIGN (SEE SIGNING SHEET)
	RIGHT OF WAY



TRAFFIC SIGNAL SIGNS			
KEY	LEGEND	DESC	QTY
T1		SEE SIGN DETAILS	1
T2		SEE SIGN DETAILS	1
T3		R3-2 24" x 24"	1
T4		R6-1R 36" x 12"	1
T5		R3-1 24" x 24"	1
T6		R6-1L 36" x 12"	1

EXISTING SIGNAL POLE (SEE NOTE 1)

PHASE DIAGRAM			
φ1 NOT USED	φ2 PED ↓ ↑ ↓ ↑ PED	φ3 NOT USED	φ4 PED ← →
φ5 NOT USED	φ6 NOT USED	φ7 NOT USED	φ8 ← → PED

CONFLICT FLASH:
YELLOW PHASE 2 RED PHASES 4, 8



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87			
SIGNAL LAYOUTS ABE AT CONCHO			
© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		62

DATE: 6/28/2024 3:16:34 PM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091ha.tsig04.dgn

CABLE RUN ID #	RUN LENGTH	INSTALL TYPE	SCHEDULE OF CONDUIT AND CONDUCTORS																															
			ITEM 618												ITEM 620						ITEM 621						OPTICOM	SERIAL COMMS	GRIDSMART SYSTEM					
			6046		6047		6053		6058		6059		6007		6009		6010		6005		6007		6031		6033					6036		6046		
			CONDT (PVC) (SCH 80) (2")	CONDT (PVC) (SCH 80) (2") (BORE)	CONDT (PVC) (SCH 80) (3")	CONDT (PVC) (SCH 80) (4")	CONDT (PVC) (SCH 80) (4") (BORE)	ELEC CONDR (NO. 8) BARE	ELEC CONDR (NO. 6) BARE	ELEC CONDR (NO. 6) INSULATED	TRAY CABLE (4 CNDR) (12AWG)	TRF SIG CBL (TY A) (12 AWG) (2 CNDR)	TRF SIG CBL (TY A) (14 AWG) (5 CNDR)	TRF SIG CBL (TY A) (14 AWG) (7 CNDR)	TRF SIG CBL (TY A) (14 AWG) (10 CNDR)	TRF SIG CBL (TY A) (14 AWG) (20 CNDR)	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF	EA	LF				
ELECTRIC SERVICE CABLES PULLED BY AEP (THIS RUN ONLY)																																		
01	150 LF	A																																
02	14 LF	T				2	28																											
2A	10 LF	T	1	10				2	20											1	10	8	80			8	80	2	20	1	10	1	10	
03	76 LF	B		1	76					1	76										4	304					4	304						
04	12 LF	T				1	12														1	12					1	12						
05	25 LF	T	1	25				2	50											1	25	3	75			3	75	2	50	1	25	1	25	
06	8 LF	T				1	8														1	8					1	8						
07	9 LF	T	1	9				1	9												1	9					1	9						
08	24 LF	T				2	48														2	48					2	48						
09	15 LF	T				1	15														1	15					1	15						
10	7 LF	T				1	7														1	7					1	7						
11	50 LF	B		1	50					1	50										2	100					2	100						
12	26 LF	T				2	52														1	26					1	26						
13	7 LF	T				1	7														1	7					1	7						
14	82 LF	B		1	82					1	82															1	82	1	82					
15	12 LF	T							1	12											1	12					1	12						
16	13 LF	T				1	13														1	13					1	13						
17	20 LF	T							1	20																1	20	1	20				1	20
18	8 LF	T				1	8														2	16					2	16						
19	16 LF	T				1	16		1	16											2	32					2	32	1	16	1	16		
20	48 LF	B		1	48					1	48										2	96					2	96	1	48	1	48		
SUBTOTAL			44		256		214		127		256		651		14		28		58		839				839		257		213		44	213		

S ABE ST AND W CONCHO AVE SCHEDULE OF PEDESTAL POLE ASSEMBLIES					
POLE ID	ITEM 416*		ITEM 687		ITEM 688
	6030	6001	6002		6001
	DRILL SHAFT (TRF SIG)	PED POLE ASSEMBLY	PEDESTRIAN PUSH		PED DETECT PUSH BUTTON
	LF	EA	EA	EA	EA
D	6	1	1	1	1
E	6	1	1	1	1
F	6	1	1	1	1
G	6	1	1	1	1
H	6	1	1	1	1
J	6	1	1	1	1
K	6	1	1	1	2
TOTAL:	42	7	7	7	8

*THE POLE FOUNDATION LENGTHS ARE FOR EMBEDMENT AND THE CONTRACTOR SHALL VERIFY IN THE FIELD WHAT ADDITIONAL HEIGHT IS REQUIRED ABOVE THE FINAL GRADE PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. DRILL SHAFT LENGTHS ARE SHOWN FOR INFORMATION ONLY.

S ABE ST AND W CONCHO AVE SCHEDULE OF TRAFFIC POLE ASSEMBLIES		
POLE ID	ITEM 416	
	6032	6027
	DRILL SHAFT (TRF SIG POLE) (30 IN) *	INST TRF SIG PL AM(S) 1 ARM (24') LUM
	LF	EA
C	11	1
TOTAL:	11	1

*THE POLE FOUNDATION LENGTHS ARE FOR EMBEDMENT AND THE CONTRACTOR SHALL VERIFY IN THE FIELD WHAT ADDITIONAL HEIGHT IS REQUIRED ABOVE THE FINAL GRADE PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD.

S ABE ST AND W CONCHO AVE SCHEDULE OF GROUND BOXES	
ITEM	GROUND BOX TY D (162922) W/ APRON
624-6010	8
TOTAL	8

INSTALL TYPE: (A) AERIAL, (B) BORE, (E) EXISTING, (T) TRENCH
 ALL CABLE & CONDUIT RUN LENGTHS PROVIDED FOR CONTRACTOR'S INFORMATION ONLY
 NOTE: CONNECT RUN 15 TO EXISTING CONDUIT FEEDING INTO EXISTING POLE K. BRING NEW 20 CONDUCTOR CABLE TO TERMINAL BLOCK OF POLE K.

ID	DESCRIPTION	NORTHING	EASTING	FND. ELEV
A	PROPOSED METER AND SERVICE POLE TO BE BY PROVIDED AND INSTALLED BY AEP.	N/A	N/A	N/A
B	INSTALL TRAFFIC SIGNAL CONTROLLER ASSEMBLY ON BASE-MOUNT FOUNDATION WITH EXTERNAL CABINET-MOUNTED BATTERY BACKUP SYSTEM.	N/A	N/A	N/A
C	INSTALL 30 FT SMA-80 ON 11 FT DRILLED SHAFT FND. (30-A) WITH 24 FT MAST ARM, ONE LUMINAIRE (LED), ONE WIRELESS ANTENNA, ONE STREET NAME SIGN, ONE R3-1 SIGN, ONE R6-1L SIGN AND TWO VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10496048.01'	2262805.55'	LEVEL W/ ROADWAY CROWN
D	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10496056.24'	2262824.91'	FLUSH W/ SIDEWALK
E	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10496048.49'	2262821.03'	FLUSH W/ SIDEWALK
F	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10496087.71'	2262904.66'	FLUSH W/ SIDEWALK
G	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10496090.88'	2262896.51'	FLUSH W/ SIDEWALK
H	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10496033.79'	2262925.33'	FLUSH W/ SIDEWALK
J	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10496024.99'	2262924.75'	FLUSH W/ SIDEWALK
K	ON EXISTING TRAFFIC SIGNAL POLE, INSTALL ONE OPTICOM EMERGENCY PREEMPTION DETECTOR, ONE GRIDSMART FE3 CAMERA, ONE STREET NAME SIGN, ONE R3-2 SIGN, ONE R6-1R SIGN AND SIX VEHICLE SIGNAL HEADS AS ILLUSTRATED.	N/A	N/A	N/A
L	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH TWO COUNTDOWN PEDESTRIAN SIGNAL HEADS AND TWO APS PUSH BUTTONS WITH SIGNS AS ILLUSTRATED.	10495995.24'	2262844.53'	FLUSH W/ SIDEWALK

STATE OF TEXAS
 BREGGER A. GARRISON
 122018
 LICENSED PROFESSIONAL ENGINEER
 6/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144

FREESSE & NICHOLS

Texas Department of Transportation

US 87
 CONDUITS, CABLES
 AND QUANTITIES
 ABE AT CONCHO

©TxDOT 2024 SHEET 1 of 2

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST		COUNTY	SHEET NO.
SJT		TOM GREEN	63

APS MESSAGE CHART			
POLE LOCATION	PEDESTRIAN MOVEMENT PHASE ϕ	FUNCTIONS	SPEECH MESSAGE/SOUND DETAILS
D G H L	2	BUTTON PUSH ON DW LOCATOR TONE	WAIT SLOW TICK
E F J L	4, 8	WALK INDICATOR BUTTON PUSH ON DW LOCATOR TONE	WALK SIGN IS ON TO CROSS CONCHO WAIT SLOW TICK
		WALK INDICATOR	WALK SIGN IS ON TO CROSS ABE


S ABE ST AND W CONCHO AVE SCHEDULE OF TRAFFIC SIGNAL HEADS ITEM 682							
PHASE	HEAD TYPE ID	QTY	6001	6003	6005	6054	BACKPLATE W/REF BRDR (3 SEC) (VENT) ALUM
			VEH SIG SEC (12") LED (GRN)	VEH SIG SEC (12") LED (YEL)	VEH SIG SEC ϕ (12") LED (RED)		
			EA	EA	EA	EA	
2		4	4	4	4	4	
4		2	2	2	2	2	
8		2	2	2	2	2	
TOTAL:			8	8	8	8	

S ABE ST AND W CONCHO AVE ELECTRICAL SERVICE DATA* ITEM 628-6145											
PLAN ID	ELECTRICAL SERVICE DESCRIPTION (SEE ED (5)-14)	SERVICE CONDUIT SIZE (RMC)	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK	TWO-POL E CONTACTOR AMPS	PANEL BD./LOADCENTER AMP	CIRCUIT NO.	BRANCH CKT. BRK. POLE/	BRANCH CIRCUIT AMPS	KVA LOAD
A	ELC SRV TY D 120/240 060 (NS) SS (E) SP (O)	2"	3/#6	N/A	2P/60	40	100	SIGNAL LIGHTING	1P/30 2P/20	5 4	<7.1

* CONTRACTOR SHALL VERIFY WITH POWER COMPANY THE LOCATION OF THE SERVICE, THE TRANSFORMER, ANY INSTALLATION REQUIREMENTS, AND OBTAIN THE APPROPRIATE METER ENCLOSURE TO INSTALL ON THE NEW SERVICE POLE.



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



Freese and Nichols

Texas Department of Transportation


US 87

**CONDUITS, CABLES
AND QUANTITIES
ABE AT CONCHO**

© TxDOT 2024 SHEET 2 of 2


CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	64	

T1



D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 Standard Arrow Custom 10.9" X 10.9" 180°; "S. Abe", ClearviewHwy-3-W; "St", ClearviewHwy-3-W;
 "300", ClearviewHwy-3-W;

T2



D3-1G;
 1.0" Radius, 0.8" Border, White on Green;
 Standard Arrow Custom 10.9" X 10.9" 180°; "S. Abe", ClearviewHwy-3-W; "St", ClearviewHwy-3-W;
 "300", ClearviewHwy-3-W;

NOTE: ALL DIMENSIONS ARE IN INCHES.



FREESE AND NICHOLS

Texas Department of Transportation


US 87

SIGN DETAILS
 ABE AT CONCHO

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	65	

© TxDOT 2024

DW: MS CK: BG DW: TA CK: BG



LEGEND

- W DETECTABLE WARNING SURFACE
- R RAMP
- L TURNING SPACE
- F FLARE
- - - SLOTTED CURB
- [Pattern] CONCRETE RIPRAP
- (A) REFL PAV MRK TY I (W) 24" (SLD) (100MIL)
- (B) RE PM W/RET REQ TY I (W) 6" (SLD) (100MIL)
- (C) RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
- (D) RE PM W/RET REQ TY I (Y) 6" (SLD) (100MIL)
- (E) REFL PAV MRK TY I (W) (ARROW) (100MIL)
- (F) REFL PAV MRK TY I (W) (WORD) (100MIL)
- (G) REFL PAV MRKR TYII-C-R
- [S#] SIGN IDENTIFIER
- GROUND MOUNTED SIGN
- - - RIGHT OF WAY



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144




Texas Department of Transportation


US 87
PAVEMENT MARKINGS
AND PEDESTRIAN RAMPS
ABE AT CONCHO

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	66	

- NOTES:**
1. DIMENSIONS AND DETAILS OF PROPOSED CURB RAMPS ARE FOR GUIDANCE TO THE CONTRACTOR. CONTRACTOR SHALL ENSURE RAMPS ARE BUILT PER STANDARD AND ARE ADA ACCESSIBLE.
 2. ALL REQUIRED WORK TO ENSURE ADA ACCESSIBILITY FOR EACH PROPOSED RAMP SHALL BE SUBSIDIARY TO THE RAMP BID ITEM.
 3. CONTRACTOR SHALL SAWCUT EXISTING CONCRETE AT ALL REMOVAL AND TIE-IN LIMITS.
 4. UNLESS OTHERWISE SHOWN, LANDINGS SHALL BE PAID FOR AS PART OF ITEM 690 6092 INSTALL SIDEWALK.
 5. ALL PAVEMENT MARKINGS WITHIN 200 FT OF EACH CROSSWALK ALONG US 87 SHALL BE REFRESHED AS PART OF THIS PROJECT.
 6. LANDING SHALL BE GRADED AWAY FROM ROADWAY TO ALLOW POSITIVE DRAINAGE THROUGH THE RAMP AND CURB SLOT. LANDING SHALL MEET MINIMUM AND MAXIMUM GRADES FOR ACCESSIBILITY.


DATE: 6/28/2024 3:17:23 PM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms381561td10240091ce_rdw03.dgn





LEGEND

- LANE ASSIGNMENT
- SIDEWALK REMOVAL
- ASPHALT REMOVAL
- EXISTING PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL
- EXISTING MAST ARM ASSEMBLY
- EXISTING VEHICLE SIGNAL HEAD
- EXISTING SIGN
- EXISTING CONTROLLER/ GROUND BOX
- EXISTING LUMINAIRE
- STORM DRAIN MANHOLE
- SANITARY SEWER MANHOLE
- EXISTING FIRE HYDRANT
- EXISTING GAS LINE
- EXISTING OVERHEAD ELECTRIC
- EXISTING TREE
- RIGHT OF WAY



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



Texas Department of Transportation

US 87
EXISTING CONDITIONS AND REMOVALS
BRYANT AT JACKSON

CAUTION !!
THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT BURIED UTILITIES INCLUDING GAS ARE KNOWN TO EXIST IN THE VICINITY THIS PROJECT. THE CONTRACTOR SHALL CONTACT THE TEXAS 811 ONE CALL UTILITY LOCATION SERVICE A MINIMUM OF 48 HOURS PRIOR TO EXCAVATION AND NOTIFY THE ENGINEER PROMPTLY OF ALL CONFLICTS.

- NOTES:**
1. ALL ITEMS NOT SPECIFICALLY IDENTIFIED ON THIS SHEET FOR REMOVAL SHALL BE RETAINED.
 2. DEMOLITION OF GROUND MOUNTED SMALL SIGN ASSEMBLIES SHALL BE FINISHED FLUSH WITH SIDEWALK OR AT GRADE.
 3. DEMOLITION OF POLE AND EQUIPMENT FOUNDATIONS SHALL BE CONDUCTED TO A MINIMUM DEPTH OF 6 INCHES BELOW FINISHED GRADE.

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		67

DATE: 6/28/2024 3:17:46 PM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms381611td10240091ha.tsd05b.dgn


DATE: 6/28/2024 3:18:00 PM
 FILE: c:\pwworking\freese-nichols\project\0069\1161\11610240091\ha_tsig05.dgn

APS PUSHBUTTONS		
KEY	LEGEND	QTY
PB1		4
PB2		4
PB3		2



NOTE:
 1. FOR RUNS 2 AND 3, EXTEND A NEW CONDUIT FROM THE OPENING IN THE BASE OF THE EXISTING CONTROLLER, EXTENDING UNDERNEATH THE EXISTING SLAB FOUNDATION OF THE CABINET TO THE NEW GROUND BOX.
 2. FOR RUN 2, UPGRADE THE EXISTING PANEL TO ADD LIGHTING CIRCUIT.

TRAFFIC SIGNAL SIGNS			
KEY	LEGEND	DESC	QTY
T1		SEE SIGN DETAILS	1
T2		SEE SIGN DETAILS	1
T3		SEE SIGN DETAILS	1
T4		SEE SIGN DETAILS	1
T5		R3-8 50" x 30"	2
T6		R10-17T 30" x 30"	2

TRAFFIC SIGNAL HEADS			
KEY	LEGEND	QTY	DESC
1		10	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
2		4	12" LED VEHICLE SIGNAL SECTIONS WITH REFLECTIVE BACKPLATES
W1		10	16" x 18" LED COUNTDOWN PEDESTRIAN SIGNALS



LEGEND	
	POLE & EQUIPMENT IDENTIFIER
	CABLE / CONDUIT RUN
	VEHICLE SIGNAL HEAD
	PEDESTRIAN SIGNAL
	APS PUSHBUTTON
	TRAFFIC SIGNAL SIGN
	LANE ASSIGNMENT
	MAST ARM ASSEMBLY
	MAST ARM MOUNT SIGN LUMINAIRE
	VEHICLE SIGNAL HEAD
	GRIDSMA RT FE3 CAMERA ASSEMBLY
	WIRELESS ANTENNA
	PED POLE ASSEMBLY W/ PEDESTRIAN SIGNAL & PUSHBUTTON
	GROUND MOUNT SIGN (SEE SIGNING SHEET)
	TYPE D GROUND BOX W/ CONCRETE APRON
	CONDUIT RUN (BORE)
	CONDUIT RUN (TRENCH)
	EXISTING TRAFFIC SIGNAL CONTROLLER
	EXISTING SERVICE POLE & METER
	RIGHT OF WAY



STATE OF TEXAS
 BREGGER A. GARRISON
 122018
 LICENSED PROFESSIONAL ENGINEER

6/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144

FRESE AND NICHOLS
 Texas Department of Transportation

US 87

**SIGNAL LAYOUTS
 BRYANT AT JACKSON**

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		68

DATE: 6/28/2024 4:08:31 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091ha_tsig05a.dgn

CABLE RUN ID #	RUN LENGTH	INSTALL TYPE	SCHEDULE OF CONDUIT AND CONDUCTORS																				SERIAL COMMS		GRIDSMART SYSTEM						
			ITEM 618						ITEM 620		ITEM 621		ITEM 684						CAT 6		CAT-6										
			6046		6047		6053		6058		6059		6007		6005		6007		6031		6033		6036		6046		EA	LF	EA	LF	
(02)	18 LF	T						1	18				1	18	4	72															
(03)	18 LF	T											2	36									10	180							
(04)	26 LF	T	1	26									1	26	5	130							5	130	1	26	1	26			
(05)	82 LF	B					1	82																3	246	2	164				
(06)	10 LF	T											1	10											1	10					
(07)	17 LF	T	1	17									1	17													1	17			
(08)	13 LF	T											1	13																	
(09)	60 LF	B					1	60						2	120	3	180	2	120	2	120			2	120	2	120				
(10)	6 LF	T											1	6																	
(11)	11 LF	T	1	11											2	22	1	11													
(12)	34 LF	T	1	34											2	68	1	34	1	34					1	34	1	34			
(13)	5 LF	T											1	5																	
(14)	80 LF	B					1	80						1	80	2	160	1	80												
(15)	8 LF	T													3	24															
(16)	22 LF	T	1	22											1	22															
(17)	25 LF	T	1	25											1	25	2	50	1	25											
(18)	84 LF	B					1	84								2	168							2	168						
(19)	12 LF	T													1	12															
(20)	16 LF	T													1	16															
(21)	58 LF	B					1	58								2	116							3	174						
(22)	5 LF	T													1	5															
(23)	10 LF	T	1	10													2	20	1	10					1	10	1	10			
(24)	23 LF	T	1	23											2	46	1	23							5	115					
(25)	19 LF	T													1	19															
(26)	12 LF	T													1	12															
(27)	76 LF	B					1	76								2	152	3	228	1	76	5	380			5	380	1	76		
SUBTOTAL			168	440	212	204	658	1682	890	1703	100	1036	1653	658	157	103															

INSTALL TYPE: (A) AERIAL, (B) BORE, (E) EXISTING, (T) TRENCH
 ALL CABLE & CONDUIT RUN LENGTHS PROVIDED FOR CONTRACTOR'S INFORMATION ONLY

S BRYANT BLVD AND S JACKSON ST SCHEDULE PEDESTAL POLE ASSEMBLIES					
LABEL	ITEM 416*		ITEM 687		ITEM 688
	6030	6001	6002	6001	
	DRILL SHAFT (TRF)	PED POLE ASSEMBLY	PEDESTRIAN PUSH	PED DETECT PUSH	
	LF	EA	EA	EA	
(D)	6	1	1	1	
(E)	6	1	1	1	
(F)	6	1	1	1	
(H)	6	1	1	1	
(J)	6	1	1	1	
(L)	6	1	1	1	
(M)	6	1	1	1	
(N)	6	1	1	1	
(O)	6	1	1	1	
(R)	6	1	1	1	
TOTAL:	60	10	10	10	

*THE POLE FOUNDATION LENGTHS ARE FOR EMBEDMENT AND THE CONTRACTOR SHALL VERIFY IN THE FIELD WHAT ADDITIONAL HEIGHT IS REQUIRED ABOVE THE FINAL GRADE PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. PRIOR TO ORDERING FOUNDATION STEEL, FINAL LOCATION OF THE POLES SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD. DRILL SHAFT LENGTHS ARE SHOWN FOR INFORMATION ONLY.

S BRYANT BLVD AND S JACKSON ST SCHEDULE OF TRAFFIC POLE ASSEMBLIES					
LABEL	ITEM 416		ITEM 686		
	6032	6034	6047	6051	6063
	DRILL SHAFT (TRF SIG POLE) (36 IN) *	DRILL SHAFT (TRF SIG POLE) (48 IN) *	INST TRF SIG PL AM(S)1 ARM(44') LUM	INST TRF SIG PL AM(S)1 ARM(48') LUM	INST TRF SIG PL AM(S)1 ARM(60') LUM
	LF	LF	EA		EA
(G)	13	22			1
(P)		22			1
(K)	13		1		
TOTAL:	26	44	1	1	2

*THE POLE FOUNDATION LENGTHS ARE FOR EMBEDMENT AND THE CONTRACTOR SHALL VERIFY IN THE FIELD WHAT ADDITIONAL HEIGHT IS REQUIRED ABOVE THE FINAL GRADE PRIOR TO ORDERING FOUNDATION STEEL. FINAL LOCATION OF THE POLES SHALL BE

S BRYANT BLVD AND S JACKSON ST SCHEDULE OF GROUND BOXES	
ITEM 624-6010	GROUND BOX TY D (162922) W/ APRON
TOTAL	10

ID	POLE & EQUIPMENT INFORMATION DESCRIPTION	NORTHING	EASTING	FND. ELEV
(A)	PROPOSED METER AND SERVICE POLE TO BE BY PROVIDED AND INSTALLED BY AEP.	N/A	N/A	N/A
(B)	EXISTING TXDOT TYPE 2 TRAFFIC SIGNAL CONTROLLER ON FOUNDATION	N/A	N/A	N/A
(C)	INSTALL 30 FT SMA-80 ON 13 FT DRILLED SHAFT FND. (36-A) WITH 48 FT MAST ARM, ONE WIND DAMPER ASSEMBLY, ONE LUMINAIRE (LED), ONE GRIDSMART FE3 CAMERA, ONE STREET NAME SIGN, ONE R3-8 SIGN AND THREE VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10484309.42'	2263265.22'	LEVEL W/ ROADWAY CROWN
(D)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484310.29'	2263257.39'	FLUSH W/ SIDEWALK
(E)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484317.68'	2263263.50'	FLUSH W/ SIDEWALK
(F)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH TWO COUNTDOWN PEDESTRIAN SIGNAL HEADS AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484320.12'	2263334.26'	FLUSH W/ SIDEWALK
(G)	INSTALL 30 FT LMA ON 22FT DRILLED SHAFT FND. (48-A) WITH 60 FT MAST ARM, ONE LUMINAIRE (LED), ONE STREET NAME SIGN, ONE R10-5L SIGN, AND FOUR VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10484337.82'	2263392.55'	LEVEL W/ ROADWAY CROWN
(H)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484323.16'	2263395.75'	FLUSH W/ SIDEWALK
(J)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484304.06'	2263408.81'	FLUSH W/ SIDEWALK
(K)	INSTALL 30 FT SMA-80 ON 13 FT DRILLED SHAFT FND. (36-A) WITH 44 FT MAST ARM, ONE WIND DAMPER ASSEMBLY, ONE LUMINAIRE (LED), ONE STREET NAME SIGN, ONE R3-8 SIGN AND THREE VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10484221.92'	2263423.04'	LEVEL W/ ROADWAY CROWN
(L)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484215.02'	2263413.36'	FLUSH W/ SIDEWALK
(M)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484200.98'	2263395.84'	FLUSH W/ SIDEWALK
(N)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH TWO COUNTDOWN PEDESTRIAN SIGNAL HEADS AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484204.18'	2263318.78'	FLUSH W/ SIDEWALK
(P)	INSTALL 30 FT LMA ON 22FT DRILLED SHAFT FND. (48-A) WITH 60 FT MAST ARM, ONE LUMINAIRE (LED), ONE GRIDSMART FE3 CAMERA, ONE WIRELESS ANTENNA, ONE STREET NAME SIGN, ONE R10-5L SIGN AND FOUR VEHICLE SIGNAL HEADS AS ILLUSTRATED.	10484193.05'	2263262.18'	LEVEL W/ ROADWAY CROWN
(Q)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484207.13'	2263257.16'	FLUSH W/ SIDEWALK
(R)	INSTALL 10 FT PEDESTAL POLE ON 6 FT DRILLED SHAFT FND. (24-A) WITH ONE COUNTDOWN PEDESTRIAN SIGNAL HEAD AND ONE APS PUSH BUTTON WITH SIGN AS ILLUSTRATED.	10484210.84'	2263250.33'	FLUSH W/ SIDEWALK



6/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144

Texas Department of Transportation

US 87
 CONDUITS, CABLES AND QUANTITIES
 BRYANT AT JACKSON

©TxDOT 2024 SHEET 1 of 2

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	69	


CK: BG
 DW: TA
 CK: BG
 DW: MS

APS MESSAGE CHART			
POLE LOCATION	PEDESTRIAN MOVEMENT PHASE ϕ	FUNCTIONS	SPEECH MESSAGE/SOUND DETAILS
D J L R	2, 6	BUTTON PUSH ON DW LOCATOR TONE WALK INDICATOR	WAIT SLOW TICK WALK SIGN IS ON TO CROSS JACKSON
E F H M N Q	4, 8	BUTTON PUSH ON DW LOCATOR TONE WALK INDICATOR	WAIT SLOW TICK WALK SIGN IS ON TO CROSS BRYANT

S BRYANT BLVD AND S JACKSON ST SCHEDULE OF TRAFFIC SIGNAL HEADS ITEM 682									
PHASE ϕ	HEAD TYPE ID	QTY	6001	6002	6003	6004	6005	6006	6054
			VEH SIG SEC (12") LED (GRN)	VEH SIG SEC (12") LED (GRN ARW)	VEH SIG SEC (12") LED (YEL)	VEH SIG SEC (12") LED (YEL ARW)	VEH SIG SEC (12") LED (RED)	VEH SIG SEC (12") LED (RED ARW)	BACKPLATE W/REF BRDR (3 SEC) (VENT) ALUM
1	2	1	EA	EA	EA	EA	EA	EA	EA
2	1	3	3	1	3	2	3	1	3
3	2	1		1		2		1	
4	1	2	2		2		2		2
5	2	1		1		2		1	
6	1	3	3		3		3		3
7	2	1		1		2		1	
8	1	2	2		2		2		2
TOTAL:			10	4	10	8	10	4	10

S BRYANT BLVD AND S JACKSON ST ELECTRICAL SERVICE DATA* ITEM 628-6145											
PLAN ID	ELECTRICAL SERVICE DESCRIPTION (SEE ED (5)-14)	SERVICE CONDUIT SIZE (RMC)	SERVICE CONDUCTORS NO./SIZE	SAFETY SWITCH AMPS	MAIN DISCONNECT CKT. BRK	TWO-POLE CONTACTOR AMPS	PANEL BD./LOADCENTER AMP RATING	CIRCUIT NO.	BRANCH CKT. BRK. POLE/AMPS	BRANCH CIRCUIT AMPS	KVA LOAD
A	ELC SRV TY D 120/240 060 (NS) SS (E) SP (O)	2"	3/#6	N/A	2P/60	40	100	SIGNAL LIGHTING	1P/30 2P/20	5 4	<7.1

* CONTRACTOR SHALL VERIFY WITH POWER COMPANY THE LOCATION OF THE SERVICE, THE TRANSFORMER, ANY INSTALLATION REQUIREMENTS, AND OBTAIN THE APPROPRIATE METER ENCLOSURE TO INSTALL ON THE NEW SERVICE POLE.



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144




US 87
CONDUITS, CABLES
AND QUANTITIES
BRYANT AT JACKSON


©TxDOT 2024		SHEET 2 of 2	
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	70	

DATE: 6/28/2024 4:08:45 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091\ha_tsiq05aa.dgn

T1




T2



T4


T3




"4/00", ClearviewHwy-3-W;

T3

T4





NOTE: ALL DIMENSIONS ARE IN INCHES.



6/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144

FREESE AND NICHOLS			
Texas Department of Transportation			
US 87			
SIGN DETAILS BRYANT AT JACKSON			
© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		71



LEGEND

- W DETECTABLE WARNING SURFACE
- R RAMP
- L TURNING SPACE
- F FLARE
- - - SLOTTED CURB
- [Pattern] CONCRETE RIPRAP
- (A) REFL PAV MRK TY I (W) 24" (SLD) (100MIL)
- (B) RE PM W/RET REQ TY I (W) 6" (SLD) (100MIL)
- (C) RE PM W/RET REQ TY I (W) 6" (BRK) (100MIL)
- (D) RE PM W/RET REQ TY I (Y) 6" (SLD) (100MIL)
- (E) REFL PAV MRK TY I (W) (ARROW) (100MIL)
- (F) REFL PAV MRK TY I (W) (WORD) (100MIL)
- (G) REFL PAV MRKR TYII-C-R
- [S#] SIGN IDENTIFIER
- GROUND MOUNTED SIGN
- - - RIGHT OF WAY



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



US 87
PAVEMENT MARKINGS AND PEDESTRIAN RAMPS
BRYANT AT JACKSON

© TxDOT 2024			
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	72	

DATE: 6/28/2024 3:19:20 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms381561td10240091ce_rdw04.dgn

- NOTES:**
1. DIMENSIONS AND DETAILS OF PROPOSED CUR RAMPS ARE FOR GUIDANCE TO THE CONTRACTOR. CONTRACTOR SHALL ENSURE RAMPS ARE BUILT PER STANDARD AND ARE ADA ACCESSIBLE.
 2. ALL REQUIRED WORK TO ENSURE ADA ACCESSIBILITY FOR EACH PROPOSED RAMP SHALL BE SUBSIDIARY TO THE RAMP BID ITEM.
 3. CONTRACTOR SHALL SAWCUT EXISTING CONCRETE AT ALL REMOVAL AND TIE-IN LIMITS.
 4. UNLESS OTHERWISE SHOWN, LANDINGS SHALL BE PAID FOR AS PART OF ITEM 690 6092 INSTALL SIDEWALK.
 5. ALL PAVEMENT MARKINGS WITHIN 200 FT OF EACH CROSSWALK ALONG US 87 SHALL BE REFRESHED AS PART OF THIS PROJECT.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

GENERAL NOTES FOR ALL ELECTRICAL WORK

- The location of all conduits, junction boxes, ground boxes, and electrical services is diagrammatic and may be shifted to accommodate field conditions.
- Provide new and unused materials. Ensure that all materials and installations comply with the applicable articles of the National Electrical Code (NEC), TxDOT standards and specifications, National Electrical Manufacturers Association (NEMA), and are listed by Underwriters Laboratories (UL) or a Nationally Recognized Testing Lab (NRTL). NRTLs such as Canadian Standard Association (CSA), Intertek Testing Services NA Inc., or FM Approvals LLC can be considered equivalent to UL. Where reference is made to NEMA listed devices, International Electrotechnical Commission (IEC) listed devices will not be considered an acceptable equal to a NEMA listed device. Acceptable devices may have both a NEMA and IEC listing. Faulty fabrication or poor workmanship in any material, equipment, or installation is justification for rejection. Replace or reinstall rejected material or equipment at no additional cost to the Department.
- Miscellaneous nuts, bolts and hardware, except for high strength bolts, may be stainless steel when plans specify galvanized, provided the bolt size is 1/2 in. or less in diameter.
- Provide the following test equipment as required by the Engineer to confirm compliance with the contract and the NEC: voltmeter, ammeter, megohm meter (1000 volt DC), ground resistance tester, torque wrenches, and torque screwdrivers. Ensure all equipment has been properly calibrated within the last year. Provide calibration certification to the Engineer upon request. Operate test equipment during inspection as requested by the Engineer.
- Install grounding as shown on the plans and in accordance with the NEC. Ensure all metallic conduits; metal poles; luminaires; and metal enclosures are bonded to the equipment grounding conductor. Provide stranded bare copper or green insulated grounding conductors. Ground rods, connectors, and bonding jumpers are subsidiary to the various bid items.
- When required by the Engineer, notify the Department in writing of materials from the Material Producers List (MPL) intended for use on each project. Prequalified materials are listed on the MPL on TxDOT's website under "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials on this list.

CONDUIT

A. MATERIALS

- Provide conduit, junction boxes, fittings, and hardware as per TxDOT Departmental Material Specification (DMS) 11030 "Conduit" and Item 618 "Conduit" of TxDOT's "Standard Specifications For Construction And Maintenance Of Highways, Streets, And Bridges," latest edition. Provide conduits listed under Item 618 on the MPL under "Roadway Illumination and Electrical Supplies." Provide conduit types according to the descriptive code or as shown on the plans. Do not substitute other types of conduits for those shown. Provide liquidtight flexible metal conduit (LFMC) when flexible conduit is called for on galvanized steel rigid metallic conduit (RMC) systems. Provide liquidtight flexible nonmetallic conduit (LFNC) when flexible conduit is called for on polyvinyl chloride (PVC) systems.
- Provide galvanized steel RMC for all exposed conduits, unless otherwise shown on the plans. Properly bond all metal conduits.
- Unless otherwise shown on the plans, provide junction boxes with a minimum size as shown in the following table, which applies to the greatest number of conductors entering the box through one conduit with no more than four conduits per box. When a mixture of conductor sizes is present, count the conductors as if all are of the larger size. For situations not applicable to the table, size junction boxes in accordance with NEC.


AWG	3 CONDUCTORS	5 CONDUCTORS	7 CONDUCTORS
#1	10" x 10" x 4"	12" x 12" x 4"	16" x 16" x 4"
#2	8" x 8" x 4"	10" x 10" x 4"	12" x 12" x 4"
#4	8" x 8" x 4"	10" x 10" x 4"	10" x 10" x 4"
#6	8" x 8" x 4"	8" x 8" x 4"	10" x 10" x 4"
#8	8" x 8" x 4"	8" x 8" x 4"	8" x 8" x 4"

- Junction boxes with an internal volume of less than 100 cu. in. and supported by entering raceways must have threaded entries or hubs identified for the intended purpose and supported by connection of two or more rigid metal conduits. Secure conduit within 3 ft. of the enclosure or within 18 in. of the enclosure if all conduit entries are on the same side. Mechanically secure all junction boxes with an internal volume greater than 100 cu. inches.
- Provide hot dipped galvanized cast iron or sand cast aluminum outlet boxes for junction boxes containing only 10 AWG or 12 AWG conductors. Do not use die cast aluminum boxes. Size outlet boxes according to the NEC.
- Do not use intermediate metal conduit (IMC) or electrical metallic tubing (EMT) unless specifically required by the plan sheets. When EMT is called for, provide junction boxes made from galvanized steel sheeting, listed and approved for outdoor use, unless otherwise noted on the plans. Size all galvanized steel junction boxes in accordance with the NEC. Provide junction boxes for IMC conduit systems that meet the same requirements for junction boxes used with RMC systems.
- Provide PVC junction boxes intended for outdoor use on PVC conduit systems, unless otherwise noted on the plans.

- Provide PVC elbows in PVC conduit systems, unless otherwise shown on the plans. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the PVC conduit system. When galvanized steel RMC elbows are specifically called for in the plans and any portion of the RMC elbow is buried less than 18 in., ground the RMC elbow by means of a grounding bushing on a rigid metal extension. Grounding of the rigid metal elbow is not required if the entire RMC elbow is encased in a minimum of 2 in. of concrete. PVC extensions are allowed on these concrete encased rigid metal elbows. RMC or PVC elbows are subsidiary to various bid items.
- When required, provide High-Density Polyethylene (HDPE) conduit with factory installed internal conductors according to Item 622 "Duct Cable." At the Contractor's request and with approval by the Engineer, substitute HDPE conduit with no conductors for bored schedule 40 or schedule 80 PVC conduit bid under Item 618. Ensure bored HDPE substituted for PVC is schedule 40 and of the same size PVC called for in the plans. Ensure the substituted HDPE meets the requirements of Item 622, except that the conduit is supplied without factory-installed conductors. Make the transition of the HDPE conduit to PVC (or RMC elbow when required) at the bore pit. Provide conduit of the size and schedule as shown on the plans. Do not extend substituted conduit into ground boxes or foundations. Provide PVC or galvanized steel RMC elbows as called for at all ground boxes and foundations.
- Use two-hole straps when supporting 2 in. and larger conduits. On electrical service poles, properly sized stainless steel or hot dipped galvanized one-hole standoff straps are allowed on the service riser conduit.


B. CONSTRUCTION METHODS

- Provide and install expansion joint conduit fittings on all structure-mounted conduits at the structure's expansion joints to allow for movement of the conduit. In addition, provide and install expansion joint fittings on all continuous runs of galvanized steel RMC conduit externally exposed on structures such as bridges at maximum intervals of 150 ft. When requested by the project Engineer, supply manufacturer's specification sheet for expansion joint conduit fittings. Repair or replace expansion joint fittings that do not allow for movement at no additional cost to the Department. Provide the method of determining the amount of expansion to the Engineer upon request. Do not use LFMC or LFNC as a substitute for the required expansion conduit fittings.
- Space all conduit supports at maximum intervals of 5 ft. Install conduit spacers when attaching metal conduit to surface of concrete structures. See "Conduit Mounting Options" on ED(2). Install conduit support within 3 ft. of all enclosures and conduit terminations.
- Do not attach conduit supports directly to pre-stressed concrete beams except as shown specifically in the plans or as approved by the Engineer.
- Unless otherwise shown on the plans, jack or bore conduit placed beneath existing roadways, driveways, sidewalks, or after the base or surfacing operation has begun. Backfill and compact the bore pits below the conduit per Item 476 "Jacking, Boring, or Tunneling Pipe or Box" prior to installing conduit or duct cable to prevent bending of the connections.
- When placing conduit in the sub-grade of new roadways, backfill all trenches with excavated material unless otherwise noted on the plans. When placing conduit in the sub-base of new roadways, backfill all trenches with cement-stabilized base as per requirements of Items 110 "Excavation", 400 "Excavation and Backfill for Structures", 401 "Flowable Backfill", 402 "Trench Excavation Protection", and 403 "Temporary Special Shoring."
- Provide and place warning tape approximately 10 in. above all trenched conduit as per Item 618.
- During construction, temporarily cap or plug open ends of all conduit and raceways immediately after installation to prevent entry of dirt, debris and animals. Temporary caps constructed of durable duct tape are allowed. Tightly fix the tape to the conduit opening. Clean out the conduit and prove it clear in accordance with Item 618 prior to installing any conductors.
- Ensure conduit entry into the top of any enclosure is waterproof by installing conduit sealing hubs or using boxes with threaded bosses. This includes surface mounted safety switches, meter cans, service enclosures, auxiliary enclosures and junction boxes. Grounding bushings on water tight sealing hubs are not required.
- Fit the ends of all PVC conduit terminations with bushings or bell end fittings. Provide and install a grounding type bushing on all metal conduit terminations.
- Install a bonding jumper from each grounding bushing to the nearest ground rod, grounding lug, or equipment grounding conductor. Ensure all bonding jumpers are the same size as the equipment grounding conductor. Bonding of conduit used as a casing under roadways for duct cable is not required, if the duct extends the full length through the casing.
- At all electrical services, install a 6 AWG solid copper grounding electrode conductor.
- Place conduits entering ground boxes so that the conduit openings are between 3 in. and 6 in. from the bottom of the box. See the ground box detail on sheet ED(4).
- Seal ends of all conduits with duct seal, expandable foam, or by other methods approved by the Engineer. Seal conduit immediately after completion of conductor installation and pull tests. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a conduit sealant.
- File smooth the cut ends of all mounting strut and conduit. Before installing, paint the field cut ends of all mounting strut and RMC (threaded or non-threaded) with zinc rich paint (94% or more zinc content) to alleviate overspray. Use zinc rich paint to touch up galvanized material as allowed under Item 445 "Galvanizing." Do not paint non-galvanized material with a zinc rich paint as an alternative for materials required to be galvanized.

 Texas Department of Transportation				Traffic Operations Division Standard	
<h1>ELECTRICAL DETAILS CONDUITS & NOTES</h1>					
<h2>ED(1) - 14</h2>					
FILE#	ed1-14.dgn	DWG	CK1	DWG	CK1
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0069	07	116, ETC.	US 87
		DIST	COUNTY		SHEET NO.
		SJT	TOM GREEN		73

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



CONDUIT HANGING DETAIL



CONDUIT MOUNTING CHANNEL		
"SPAN"	"W" x "H"	"T"
less than 2'	1 5/8" x 1 3/8"	12 Ga.
2'-0" to 2'-6"	1 5/8" x 1 5/8"	12 Ga.
>2'-6" to 3'-0"	1 5/8" x 2 1/16"	12 Ga.

Channels with round or short slotted hole patterns are allowed, if the load carrying capacity is not reduced by more than 15%.




HANGER ASSEMBLY DETAIL

ELECTRIC CONDUIT TO BRIDGE DECK ATTACHMENT



CONDUIT MOUNTING OPTIONS

Attachment to concrete surfaces
See ED(1)B.2



TYPICAL CONDUIT ENTRY TO BRIDGE STRUCTURE DETAIL

EXPANSION ANCHOR NOTES FOR BRIDGE DECK ATTACHMENT

1. Use torque controlled mechanical expansion anchors that are approved for use in cracked concrete by the International Code Council, Evaluation Service (ICC-ES). The chosen anchor product shall have a designated ICC-ES Evaluation Report number, and its approval status shall be maintained on the ICC-ES website under Division 031600 for Concrete Anchors.
2. Unless otherwise approved by the Engineer, do not use adhesive anchors; do not use expansion anchors that are not included in the ICC-ES approval list; and do not use expansion anchors that are only approved for use in uncracked concrete.
3. Use anchors manufactured with stainless steel expansion wedges. Anchors manufactured with carbon steel expansion wedges are not allowed. Anchor bodies can be either zinc-plated carbon steel or stainless steel. For application in marine environment, both the anchor body and expansion wedge shall be stainless steel.
4. Install anchors as shown on the plans and in accordance with the anchor manufacturer's published installation instructions. Arrange a field demonstration test to evaluate the procedures and tools. The test shall be witnessed and approved by the Engineer prior to furnishing anchors on the structure.
5. Prior to hole drilling, use rebar locator to ensure clearing of existing deck strands or reinforcement. Install anchors to ensure a minimum effective embedment depth, (h_{ef}), as shown. Increase (h_{ef}) as needed to ensure sufficient thread length for proper torqueing and tightening of anchors.
6. Use anchors of minimum 1600 Lbs tensile capacity (minimum of steel, concrete breakout, and concrete pullout strengths as determined by ACI 318 Appendix D) at the required minimum embedment depth (h_{ef}). No lateral loads shall be introduced after conduit installation.

		Traffic Operations Division Standard	
<h2>ELECTRICAL DETAILS CONDUIT SUPPORTS</h2>			
<h3>ED(2) - 14</h3>			
FILE: ed2-14.dgn	DWG: TxDOT	CHK: TxDOT	CR: TxDOT
© TxDOT October 2014	CONT: 0069	SECT: 07	JOB: 116, ETC. HIGHWAY: US 87
REVISIONS	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 74

ELECTRICAL CONDUCTORS

A. MATERIAL INFORMATION

1. Provide Type XHHW insulated conductors in accordance with Departmental Material Specification (DMS) 11040 "Conductors" and Item 620 "Electrical Conductors." Provide conductors as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 620. Color code insulated conductors in conformance with the NEC. Identify grounded (neutral) conductors with white insulation. Identify grounding conductors (ground wires) with green insulation or bare conductors. Identify ungrounded (hot) conductors with any color insulation except green, white, or gray. Keep color scheme consistent throughout the wiring system. Identify conductors 6 American Wire Gauge (AWG) and smaller by continuous color jacket. Identify electrical conductors 4 AWG and larger by continuous color jacket or by colored tape. When identifying conductors with colored tape, mark at least 6 in. of the conductor's insulation with half laps of tape.

2. Provide a solid copper 6 AWG grounding electrode conductor to bond the electrical service equipment to the concrete encased grounding electrode or the ground rod at the service location. Connect the grounding electrode conductor to the ground rod with a UL listed connector in accordance with DMS 11040. Connect the grounding electrode conductor to the concrete encased grounding electrode as shown in the plans.

3. Where two or more circuits are present in one conduit or enclosure, permanently identify the conductors of each branch circuit by attaching a non-metallic tag around both circuit conductors at each accessible location. Provide tags with two straps, large enough to indicate circuit number, letter, or other identification as shown in the plans. Print circuit identification on the tag with a permanent marker.

4. Use listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors for splicing as specified in DMS 11040. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Provide UL listed gel-filled insulating splice covers. Splicing materials, insulating materials, breakaway disconnects, splice covers, and fuse holders are subsidiary to various bid items.

B. CONSTRUCTION METHODS

1. Use only a flat, high tensile strength polyester fiber pull tape for pulling conductors through the conduit system. After installing conductors in conduit, perform conductor pull test. If a conductor cannot be freely pulled, make any needed alterations or repairs at no additional cost to the department. Perform insulation resistance tests in accordance with Item 620. Coordinate with the Engineer to witness the tests.

2. Leave 2 ft. minimum, 3 ft. maximum length for each conductor up to the splice in ground boxes. Leave 3 ft. minimum, 4 ft. maximum length of conductor in ground boxes when pulled through with no splice. Leave 1 ft. minimum, 1.5 ft. maximum length of conductor at enclosures, weatherheads and pole bases.

3. Make splices only in junction boxes, ground boxes, pole bases, or electrical enclosures and use only listed compression or screw type pressure connectors, terminal blocks, or split bolt connectors. Insulate splices with heavy wall heat shrink tubing or gel-filled insulating splice covers to provide a watertight splice. Overlap conductor insulation with heat shrink tubing a minimum of 2 in. past both sides of the splice. Where heat shrink tubing may not shrink sufficiently to provide a watertight seal around the individual conductors, prior to heating the tubing, increase the diameter of the conductor insulation using hot melt adhesive tape to provide a watertight seal between the individual conductors and the heat shrink tubing. Ensure the tape extends past the heat shrink tubing. Use hot melt adhesive tape to fill the gap and seal the ends of heat shrink tubing. Heat shrink tubing that appears to have been burned, or overheated, is considered defective and must be replaced.

4. Size and install gel-filled insulating splice covers according to manufacturer's specifications when used in place of heat shrink tubing.

5. Wire nuts with factory applied waterproof sealant may be used for 8 AWG or smaller conductors in above ground junction boxes, but not in pole bases or ground boxes. Install wire nuts in an upright position to prevent the accumulation of water.

6. Support conductors in illumination poles with a J-hook at the top of the pole.

7. When terminating conductors, remove the insulation and jacketing material without nicking the individual strands of the conductor. Conductors with nicked individual conductor strands or removed strands will be considered damaged.

8. Replace conductors and cables that are damaged beyond repair or that fail an insulation resistance test at no additional cost to the department.

9. Do not repair damaged conductors with duct tape, electrical tape, or wire nuts. Use only approved splicing methods.

10. Do not terminate more than one conductor under a single connector, unless the connector is rated for multiple conductors. Do not exceed the pressure connector's listing for maximum number and size of conductors allowed.

11. Install breakaway connectors on conductors bid under Item 620 whenever those conductors pass through a breakaway support device. Follow manufacturer's instructions when terminating conductors to breakaway connectors. Properly torque threaded connections. Proper terminations are critical to the safe operation of breakaway devices. Trim waterproofing boots on breakaway connectors to fit snugly around the conductor to ensure waterproof connection. Only one conductor may enter a single opening in a boot. Provide waterproof boots with the correct number of openings. Leave unused openings factory sealed. Use prequalified breakaway connectors as shown on the MPL.

12. Provide and install a separate stranded equipment grounding conductor (EGC) in all conduits that contain circuit wiring of 50 volts or more. Unless shown elsewhere, size the EGC to be the same size as the largest current carrying conductor contained in the conduit. Ensure all EGCs are bonded together at every accessible location. For traffic signal installations, provide a minimum size 8 AWG EGC. The EGC is paid for under Item 620.

C. TEMPORARY WIRING

1. Install temporary conductors and electrical equipment in accordance with the NEC article "Temporary Installations" and Department standard sheets.

2. Provide a ground fault circuit interrupter (GFCI) for power outlets for portable electrical equipment, power tools, ice machines, ice storage bins and refrigerators located outdoors at grade. GFCI may be any one of the following: molded cord and plug set, receptacle, or circuit breaker type.

3. Use listed wire nuts with factory applied sealant for temporary wiring where approved.

4. Enclose conductor splices within a listed enclosure or ground box, or ensure the splices are more than 10 ft. above grade vertically and more than 5 ft. horizontally from any metal structure. Where installing temporary conductors in areas subject to vehicle traffic or mobile construction equipment, ensure the vertical clearance to ground is at least 18 ft. when measured at the lowest point. Ground messenger wires that support power conductors in conformance with the NEC.

5. Protect and when necessary repair any existing electrical conduits uncovered during the construction process in a timely manner and in conformance with the NEC.

GROUND RODS & GROUNDING ELECTRODES

A. MATERIAL INFORMATION

1. Provide and install a grounding electrode at electrical services. Provide ground rods according to DMS 11040 and the plans. Larger diameter or longer length rods may be called for in some specific locations, see the individual plans sheets. Concrete encased grounding electrodes may be called for in specific locations including electrical service, see individual plan sheets.

B. CONSTRUCTION METHODS

1. Furnish auxiliary ground rods for lightning protection and install in soil, concrete, or both, as called for in the plans. For ground rods installed in concrete, ensure the connection of the conductor to the ground rod is readily accessible for inspection or repairs. For ground rods installed in soil, ensure that the upper end is between 2 to 4 in. below finished grade.

2. Do not place ground rods in the same drilled hole as a timber pole.


3. Install ground rods so the imprinted part number is at the upper end of the rod.

4. Remove all non-conductive coatings such as concrete splatter from the rod at the clamp location.


5. Route all conductors as short and straight as possible for connection to lightning protection ground rods. When a bend is required, ensure a minimum radius bend of four inches for these conductors.

6. Unless otherwise called for in the plans, protect grounding electrode conductors with non-metallic conduit. When protecting grounding electrode conductors with metal conduit, provide and install a grounding type bushing and properly sized bonding jumper on each end of the metal conduit.


7. Written authorization is required before installing a ground rod in a horizontal trench for rocky soil or a solid rock bottom.



**SPLICE OPTION 1
Compression Type**



**SPLICE OPTION 2
Split Bolt Type**



**SPLICE OPTION 3
Listed Screw Type**


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

			Traffic Operations Division Standard		
<h2>ELECTRICAL DETAILS CONDUCTORS</h2>					
<h3>ED(3) - 14</h3>					
FILE#	ed3-14.dgn	DWG	TxDOT	CHK	TxDOT
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0069	07	116, ETC.	US 87
		DIST	COUNTY		SHEET NO.
		SJT	TOM GREEN		75

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




APRON FOR GROUND BOX

- (1) Uniformly space ends of conduits within the ground box. Position ends of conduits so that ground box walls do not interfere with the installation of grounding bushings or bell end fittings.
- (2) Maintain sufficient space between conduits to allow for proper installation of bushing.
- (3) Place aggregate under the box, not in the box. Aggregate should not encroach on the interior volume of the box.
- (4) Install a grounding bushing on the upper end of all RMC terminating in a ground box. Ground RMC elbows when any part of the elbow is less than 18 in. below the bottom of the ground box. Install a PVC bushing or bell end fitting on the upper end of all PVC conduits terminating in a ground box.

GROUND BOX DIMENSIONS	
TYPE	OUTSIDE DIMENSIONS (INCHES) (Width x Length X Depth)
A	12 X 23 X 11
B	12 X 23 X 22
C	16 X 29 X 11
D	16 X 29 X 22
E	12 X 23 X 17

GROUND BOX COVER DIMENSIONS								
TYPE	DIMENSIONS (INCHES)							
	H	I	J	K	L	M	N	P
A, B & E	23 1/4	23	13 3/4	13 1/2	9 7/8	5 1/8	1 3/8	2
C & D	30 1/2	30 1/4	17 1/2	17 1/4	13 1/4	6 3/4	1 3/8	2



GROUND BOX COVER

GROUND BOXES

A. MATERIALS

1. Provide polymer concrete ground boxes measuring 16x30x24 in. (WxLxD) or smaller in accordance with Departmental Material Specification (DMS) 11070 "Ground Boxes" and Item 624 "Ground Boxes."
2. Provide Type A, B, C, D, and E ground boxes as shown in the plans, and as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 624.
3. Ensure ground box cover is correctly labeled in accordance with DMS 11070.
4. Provide larger ground boxes in accordance with Item 624 and as shown in the plans.

B. CONSTRUCTION METHODS

1. Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure aggregate bed is in place and at least 9 inches deep, prior to setting the ground box. Install ground box on top of aggregate.
2. Cast ground box aprons in place. Reinforcing steel may be field bent. Ensure the depth of concrete for the apron extends from finished grade to the top of the aggregate bed under the box. Ground box aprons, including concrete and reinforcing steel, are subsidiary to ground boxes when called for by descriptive code.
3. Keep bolt holes in the box clear of dirt. Bolt covers down when not working in ground boxes.
4. Install all conduits and ells in a neat and workmanlike manner. Uniformly space conduits so grounding bushings and bell end fittings can easily be installed.
5. Temporarily seal all conduits in the ground box until conductors are installed.
6. Permanently seal conduits immediately after the completion of conductor installation and pull tests. Permanently seal the ends of all conduits with duct seal, expandable foam, or other method as approved. Do not use duct tape as a permanent conduit sealant. Do not use silicone caulk as a sealant.
7. When a ground rod is present in a ground box, bond all equipment grounding conductors together and to the ground rod with listed connectors.
8. When a type B or D ground box is stacked to meet volume requirements, it is allowable to cut an appropriately sized hole for conduit entry in the side wall at least 18 inches below grade.
9. If an existing ground box in the contract has a metal cover, bond the cover to the equipment grounding conductor with a 3 ft. long stranded bonding jumper the same size as the grounding conductor. The bonding jumper is subsidiary to various bid items. Verify existing ground boxes with metal covers are shown on the plans, with notes fully describing the work required.
10. If other ground boxes with metal covers are within the project limits but are not part of the contract, the Engineer may direct the Contractor to bond the metal covers, identifying the specific boxes in writing. This work will be paid for separately.
11. Bond metal ground box covers to the grounding conductor with a tank ground type lug.

				Traffic Operations Division Standard	
<h2>ELECTRICAL DETAILS</h2> <h3>GROUND BOXES</h3> <h4>ED(4) - 14</h4>					
FILE#	ed4-14.dgn	DWG: TxDOT	CHK: TxDOT	DWG: TxDOT	CHK: TxDOT
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0069	07	116, ETC.	US 87
		DIST	COUNTY		SHEET NO.
		SJT	TOM GREEN		76

ELECTRICAL SERVICES NOTES

- Provide new materials. Ensure installation and materials comply with the applicable provisions of the National Electrical Code (NEC) and National Electrical Manufacturers Association (NEMA) standards. Ensure material is Underwriters Laboratories (UL) listed. Provide and install electrical service conduits, conductors, disconnects, contactors, circuit breaker panels, and branch circuit breakers as shown on the Electrical Service Data chart in the plans. Faulty fabrication or poor workmanship in material, equipment, or installation is justification for rejection. Where manufacturers provide warranties and guarantees as a customary trade practice, furnish these to the State.
- Provide electrical services in accordance with Electrical Details standard sheets, Departmental Material Specification (DMS) 11080 "Electrical Services," DMS 11081 "Electrical Services-Type A," DMS 11082 "Electrical Services-Type C," DMS 11083 "Electrical Services-Type D," DMS 11084 "Electrical Services-Type T," DMS 11085 "Electrical Services-Pedestal (PS)", and Item 628 "Electrical Services" of the Standard Specifications. Provide electrical service types A, C, and D, as listed on the Material Producers List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies," Item 628. Provide other service types as detailed on the plans.
- Provide all work, materials, services, and any incidentals needed to install a complete electrical service as specified in the plans.
- Coordinate with the Engineer and the utility provider for metering and compliance with utility requirements. Primary line extensions, connection charges, meter charges, and other charges by the utility company to provide power to the location are paid for in accordance with Item 628. Get approval for the costs associated with these charges prior to engaging the utility company to do the work. Consult with the utility provider to determine costs and requirements, and coordinate the work as approved.
- The enclosure manufacturer will provide Master Lock Type 2 with brass tumblers keyed #2195 for all custom electrical enclosures. Installing Contractor is to provide Master Lock #2195 Type 2 with brass tumblers for "off the shelf" enclosures. Master Lock #2195 keys and locks become property of the State. Unless otherwise approved, do not energize electrical service equipment until locks are installed.
- Enclosures with external disconnects that de-energize all equipment inside the enclosure do not need a dead front trim. Protect incoming line terminations from incidental contact as required by the NEC.
- When galvanized is specified for nuts, screws, bolts or miscellaneous hardware, stainless steel may be used.
- Provide wiring and electrical components rated for 75°C. Provide red, black, and white colored XHHW service entrance conductors of minimum size 6 American Wire Gauge (AWG). Identify size 6 AWG conductors by continuous color jacket. Identify electrical conductors sized 4 AWG and larger by continuous color jacket or by colored tape. Mark at least 6 inches of the conductor's insulation with half laps of colored tape, when identifying conductors. Ensure each service entrance conductor exits through a separately bushed non-metallic opening in the weatherhead. The lengths of the conductors outside the weatherhead are to be 12 inches minimum, 18 inches maximum, or as required by utility.
- All electrical service conduit and conductors attached to the electrical service including the riser or the elbow below ground are subsidiary to the electrical service. For an underground utility feed, all service conduit and conductors after the elbow, including service conduit and conductors for the utility pole riser when furnished by the Contractor, will be paid for separately.
- Provide rigid metal conduit (RMC) for all conduits on service, except for the 1/2 in. PVC conduit containing the electrical service grounding electrode conductor. Size the service entrance conduit as shown in the plans. Ensure conduit for branch circuit entry to enclosure is the same size as that shown on the layout sheets for branch circuit conduit. Extend all rigid metal conduits a minimum of 6 inches underground and then couple to the type and schedule of the conduit shown on the layout for that particular branch circuit. Install a grounding bushing on the RMC where it terminates in the service enclosure.
- Use of liquidtight flexible metal conduit (LFMC) is allowed between the meter and service enclosure when they are mounted 90 to 180 degrees to each other. Size the LFMC the same size as service entrance conduit. LFMC must not exceed 3 feet in length. Strap LFMC within 1 foot of each end. LFMC less than 12 inches in length need not be strapped. Each end of LFMC must have a grounding bushing or be terminated with a grounding fitting. The LFMC must contain a grounded (neutral) conductor. Ensure any bend in LFMC never exceeds 180 degrees. A pull test is required on all installed conductors, with at least six inches of free conductor movement demonstrated to the satisfaction of the Engineer.
- Ensure all mounting hardware and installation details of services conform to utility company specifications.
- For all electrical service enclosures listed under Item 628 on the MPL, the UL 508 enclosure manufacturers will prepare and submit a schematic drawing unique to each service. Before shipment to the job site, place the applicable laminated schematic drawings and the laminated plan sheet showing the electrical service data chart used to build the enclosure in the enclosure's data pocket. The installing contractor will copy and laminate the actual project plan sheets detailing all equipment and branch circuits supplied by that service. The laminated plan sheets are to be placed in the service enclosure's document pocket. Reduce 11 in. x 17 in. plan sheets to 8 1/2 in. x 11 in. before laminating. If the installation differs from the plan sheets, the installing contractor is to redline plan sheets before laminating.
- When providing an "Off The Shelf" Type D or Type T service, provide laminated plan sheets detailing equipment and branch circuits supplied by that service. Reduce 11 in. x 17 in. plan sheets to 8 1/2 in. x 11 in. before laminating. Deliver these drawings before completion of the work to the Engineer, instead of placing in enclosure that has no door pocket.
- Do not install conduit in the back wall of a service enclosure where it would penetrate the equipment mounting panel inside the enclosure. Provide grounding bushings on all metal conduits, and terminate bonding jumpers to grounding bus. Grounding bushings are not required when the end of the metal conduit is fitted with a conduit sealing hub or threaded boss, such as a meter base hub.

SERVICE ASSEMBLY ENCLOSURE

- Provide threaded hub for all conduit entries into the top of enclosure.
- Type galvanized steel (GS) enclosures may be used for Type C panelboards and for Type D and T services that do not use an enclosure mounted photocell or lighting contactor. Provide GS enclosures in accordance with DMS 11080, 11082, 11083, and 11084.
- Provide aluminum (AL) and stainless steel (SS) enclosures for Types A, C, and D in accordance with DMS 11080, 11081, 11082, 11083, and 11084. Do not paint stainless steel.
- Provide pedestal service (PS) enclosures in accordance with ED(9) and DMS 11080 and 11085. Do not provide GS pedestal services. If GS is shown in the PS descriptive code, provide an AL enclosure.

MAIN DISCONNECT & BRANCH CIRCUIT BREAKERS

- Field drill flange-mounted remote operator handle if needed, to ensure handle is lockable in both the "On" and "Off" positions.
- When the utility company provides a transformer larger than 50 KVA, verify that the available fault current is less than the circuit breaker's ampere interrupting capacity (AIC) rating and provide documentation from the electric utility provider to the Engineer.



PHOTOELECTRIC CONTROL

- Provide photocell as listed on the MPL. Move, adjust, or shield the photocell from stray or ambient night time light to ensure proper operation. Mount photocell facing north when practical. Mount top of pole photocells as shown on Top Mounted Photocell Detail.

* ELECTRICAL SERVICE DATA												
Elec. Service ID	Plan Sheet Number	Electrical Service Description	Service Conduit *#Size	Service Conductors No./Size	Safety Switch Amps	Main Ckt. Bkr. Pole/Amps	Two-Pole Contractor Amps	Panel/Loadcenter Amp Rating	Branch Circuit ID	Branch Ckt. Bkr. Pole/Amps	Branch Circuit Amps	KVA Load
SB 183	289	ELC SRV TY A 240/480 100(SS)AL(E)SF(U)	2"	3/#2	100	2P/100	100	N/A	Lighting NB	2P/40	26	28.1
									Lighting SB	2P/40	25	
									Underpass	1P/20	15	
NB Access	30	ELC SRV TY D 120/240 060(NS)SS(E)TS(O)	1 1/4"	3/#6	N/A	2P/60		100	Sig. Controller	1P/30	23	5.3
							30		Luminares	2P/20	9	
									CCTV	1P/20	3	
2nd & Main	58	ELC SRV TY T 120/240 000(NS)GS(N)SP(O)	1 1/4"	3/#6	N/A	N/A	N/A	70	Flashing Beacon 1	1P/20	4	1.0
									Flashing Beacon 2	1P/20	4	

* Example only, not for construction. All new electrical services must have electrical service data chart specific to that service as shown in the plans.
 ** Verify service conduit size with utility. Size may change due to utility meter requirements. Ensure conduit size meets the National Electrical Code.

EXPLANATION OF ELECTRICAL SERVICE DESCRIPTIVE CODE



TOP MOUNTED PHOTOCELL

Install conduit strap maximum 3 feet from box. 5 foot maximum spacing between straps supporting conduit.

Texas Department of Transportation Traffic Operations Division Standard

ELECTRICAL DETAILS SERVICE NOTES & DATA


ED(5) - 14

FILE#	ed5-14.dgn	DWG	TxDOT	CHK	TxDOT	DWG	TxDOT	CHK	TxDOT
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0069	07	116, ETC.		US 87			
		DIST	COUNTY		SHEET NO.				
		SJT	TOM GREEN		77				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**SCHEMATIC TYPE A
THREE WIRE**



**SCHEMATIC TYPE C
THREE WIRE**



**SCHEMATIC TYPE D - CUSTOM
120/240 VOLTS - THREE WIRE**



**SCHEMATIC TYPE T
120/240 VOLTS - THREE WIRE**
Galvanized steel-"Buy Off The Shelf"
only. When required install photocell
top of the pole or on luminaire only,
no lighting contractor will be installed.

WIRING LEGEND	
—	Power Wiring
- - -	Control Wiring
—N—	Neutral Conductor
—G—	Equipment grounding conductor-always required

SCHEMATIC LEGEND	
1	Safety Switch (when required)
2	Meter (when required-verify with electric utility provider)
3	Service Assembly Enclosure
4	Main Disconnect Breaker (See Electrical Service Data)
5	Circuit Breaker, 15 Amp (Control Circuit)
6	Auxiliary Enclosure
7	Control Station ("H-O-A" Switch)
8	Photo Electric Control (enclosure-mounted shown)
9	Lighting Contactor
10	Power Distribution Terminal Blocks
11	Neutral Bus
12	Branch Circuit Breaker (See Electrical Service Data)
13	Separate Circuit Breaker Panelboard
14	Load Center
15	Ground Bus

				Traffic Operations Division Standard	
ELECTRICAL DETAILS SERVICE ENCLOSURE AND NOTES					
ED(6) - 14					
FILE#	ed6-14.dgn	DWG: TxDOT	CHK: TxDOT	DWG: TxDOT	CHK: TxDOT
©TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0069	07	116, ETC.	US 87
		DIST	COUNTY	SHEET NO.	
		SJT	TOM GREEN	78	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SUPPORT TYPE STEEL POLE (SP) AND STEEL FRAME (SF)

1. Provide steel pole and steel frame supports as per TxDOT Departmental Material Specification (DMS) 11080 "Electrical Services." Mount all equipment and conduit on 12 gauge galvanized steel or stainless steel channel strut, 1 1/2 in. or 1 3/8 in. wide by 1 in. up to 3 3/4 in. deep Unistrut, Kindorf, B-line or equal. Bolt or weld all channel and hardware to vertical members as approved. Do not stack channel. File smooth and paint field cut ends of all channel with zinc-rich paint before installing.
2. Provide poles for overhead service with an eyebolt or similar fitting for attachment of the service drop to the pole in conformance with the electric utility provider's specifications.
3. Provide and install galvanized 3/4 in. x 18 in. x 4 in. (dia. x length x hook length) anchor bolts for underground service supports. Provide and install galvanized 3/4 in. x 56 in. x 4 in. anchor bolts for overhead service supports. Ensure anchor bolts have 3 in. of thread, with 3 1/4 in. to 3 1/2 in. of the exposed anchor bolt projecting above finished foundation. Provide and install leveling nuts for all anchor bolts.
4. Bond one of the anchor bolts to the rebar cage with 6 AWG bare stranded copper conductor. Use listed mechanical connectors rated for embedment in concrete. See Inset B.
5. Furnish and install rigid metallic ells in all steel pole and steel frame foundations for all conduits entering the service from underground.
6. Use class C concrete for foundations. Ensure reinforcing steel is Grade 60 with 3" of unobstructed concrete cover.
7. Drill and tap steel poles and frames for 1/2 in. X 13 UNC tank ground fitting. For steel pole service supports, provide and install tank ground fitting 4 in. to 6 in. below electrical service enclosure. Provide properly sized hole through the bottom of the enclosure for the service grounding electrode conductor. Ensure electrical service grounding electrode conductor is as short and straight as possible from the enclosure to the tank ground fitting. For steel frame service supports, provide and install tank ground fitting on steel frame post. Install service grounding electrode conductor in a non-metallic conduit or tubing from the enclosure to the steel frame post. Connect electrical service grounding electrode conductor to the tank ground fitting. See steel frame and steel pole details and Inset A for more information. Size service entrance conduit and branch circuit conduit as shown in the plans. For underground conduit runs from the electrical service, extend RMC from the service enclosure to an RMC elbow, and then connect the schedule type and size of conduit shown in the plans. Provide and install grounding bushings where RMC terminates in the enclosure. Grounding bushings are not required when RMC is fitted into a sealing hub or threaded boss.
8. If Steel pole or frame is painted, bond each separate painted piece with a bonding jumper attached to a tapped hole.
9. Provide 1/4" - 20 machine screws for bonding. Do not use sheet metal screws. Remove all non-conductive material at contact points. Terminate bonding jumpers with listed devices. Install minimum size 6 AWG stranded copper bonding jumpers. Make up all threaded bonding connections wrench tight.
10. Avoid contact of the service drop and service entrance conductors with the metal pole to prevent abrasion of the insulated conductors.
11. Shop drawings are not required for service support structure unless specifically stated elsewhere or directed by the Engineer.


White insulation or color code 6" of neutral conductor's insulation with white tape where conductor exits weatherhead.

Red insulation or color code 6" length of Line 1 or Line 2 conductor's insulation with red tape where conductor exits the weatherhead. Conductor slack length, 12" min., 18" max.




WITH SAFETY SWITCH WITHOUT SAFETY SWITCH
SERVICE SUPPORT TYPE SP (O) - OVERHEAD SERVICE


Drill, tap, and thread 1/2" X 13 UNC. Install tank ground fitting, connect electrical service grounding electrode conductor. See Note 7.




FRONT VIEW INSET A INSET B




WITH SAFETY SWITCH WITHOUT SAFETY SWITCH
SERVICE SUPPORT TYPE SF (U) - UNDERGROUND SERVICE




WITH SAFETY SWITCH HOOKED ANCHOR DETAIL
SERVICE SUPPORT TYPE SP (U) - UNDERGROUND SERVICE




POLE TOP PLATE



BASE PLATE DETAIL



BOTTOM OF POLE



TOP VIEW
SERVICE SUPPORT TYPE SF (O) & SF (U)



		Traffic Operations Division Standard	
ELECTRICAL DETAILS SERVICE SUPPORT TYPES SF & SP ED(7)-14			
FILE: ed7-14.dgn	DWG: TxDOT	CHK: TxDOT	DWG: TxDOT
©TxDOT October 2014	CONT: 0069	SECT: 07	JOB: 116, ETC.
REVISIONS	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 79

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TRAFFIC SIGNAL NOTES

1. Do not pass luminaire conductors through the signal controller cabinet.
2. Include an equipment grounding conductor in all conduits throughout the electrical system. Bond all exposed metal parts to the grounding conductor.
3. Provide roadway luminaires, when required, in accordance with the material and construction sections of Item 610, "Roadway Illumination Assemblies," except for performance testing of luminaires. Test installed roadway luminaires for proper operation as a part of the associated traffic signal system test.
4. If internally illuminated street name signs are approved for use, ground the fixture to the pole with a 12 AWG green XHHW conductor.
5. Bond anchor bolts to rebar cage in two locations using #3 bars or 6 AWG stranded copper conductors. Use listed mechanical connectors rated for embedment in concrete. See TxDOT standard TS-FD for further details.
6. Drill and tap signal poles for 1/2 in. X 13 UNC tank ground fitting. Provide and install tank ground fitting 4 in. to 6 in. directly below electrical service enclosure. Provide properly sized hole through the bottom of the enclosure for the service grounding electrode conductor. Connect the electrical service grounding electrode conductor to the tank ground fitting. Ensure electrical service grounding electrode conductor is as short and straight as possible from the enclosure to the tank ground fitting. See Inset A detail for further information. Size service entrance conduit and branch circuit conduit as shown in the plans.
7. Mount electrical service enclosure and meter to signal pole with stainless steel bands. Ensure bands are a minimum width of 3/4 in. Secure enclosures to bands using two-bolt brackets. Install brackets near top and bottom of each enclosure. Install properly sized stainless steel washers on each bolt in the enclosure. Band or drill and tap properly sized stand-off straps to signal pole for attaching conduit.
8. Conduct pull tests and insulation resistance tests on all illumination and power conductors as required in Item 620 "Electrical Conductors" and ED(3). To prevent electronics damage, do not conduct insulation resistance tests on traffic signal cables after termination.
9. Lock all enclosures and bolt down all ground box covers before applying power to the signal installation.
10. Terminate conduits entering the top of enclosures with a conduit-sealing hub or threaded boss such as meter hub. Install a grounding bushing on all metal conduits not connected to conduit-sealing hub or threaded boss. Bond the grounding bushing to the ground bus with a bonding jumper. Seal all conduits entering enclosures with duct seal or expanding foam. Do not use silicone to seal conduit ends.
11. For all conduits, ensure the burial depth is a minimum of 18". Ensure the minimum burial depth for conduit placed under a roadway is 24".



SIGNAL CONTROLLER SIDE VIEW


See TS-CF standard for conduit and grounding requirements. See layout sheets for ground box locations and any additional conduits that are required.

				Traffic Operations Division Standard	
ELECTRICAL DETAILS TYPICAL TRAFFIC SIGNAL SYSTEM DETAILS					
ED(8) - 14					
FILE#	ed8-14.dgn	DWG	TxDOT	CHK	TxDOT
© TxDOT	October 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS		0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.			
SJT	TOM GREEN	80			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PEDESTAL SERVICE NOTES


1. Manufacture pedestal electrical services in accordance with Departmental Material Specifications (DMS) 11080 "Electrical Services", 11085 "Electrical Services-Pedestal (PS)" and Item 628 "Electrical Services." Provide pedestal electrical services as listed on the Material Producers List (MPL) on the Department's web site under "Roadway Illumination and Electrical Supplies," Item 628. Ensure all mounting hardware and installation details of services meet utility company specifications. Contact the local utility company for approval of pedestal details prior to installing the electrical pedestal service. Submit any changes required by the utility company prior to manufacturing the pedestal enclosure.
2. When a meter socket is required, provide a socket with a minimum 100 amp rating that complies with local utility requirements.
3. Provide Class A or C concrete for pedestal service foundations in accordance with Item 420, "Concrete Substructures," except that concrete will not be paid for directly but is considered subsidiary to Item 628.
4. Provide #4 reinforcing steel for foundations in accordance with Item 440, "Reinforcement for Concrete."
5. Install 1/2 in. X 2 1/16 in. minimum length concrete single expansion type anchors for mounting pedestal enclosure to foundation. Anchor location to match mounting holes in each corner of enclosure. Secure each of the four corners of the pedestal enclosure to the anchors in the foundation with a 1/2 in. galvanized or stainless steel machine thread bolt, a properly sized locknut and a flat washer.
6. Finish top of concrete foundation in a neat and workmanlike manner. If leveling washers are used, ensure no more than 1/8 in. gap at any corner. Do not exceed a maximum dip or rise in the foundation of 1/8 in. per foot. When properly installed, ensure the top of the service enclosure is level front to back and side to side within 1/4 in. Repair rocking or movement of the service enclosure at no additional cost to the department.
7. Do not use liquidtight flexible metal conduit (LFMC) on pedestal type services.
8. Ensure all elbows in the foundation are sized as per utility provider's conduit requirements for underground conduit and feeders. PVC extensions may be installed provided the ends of the rigid metal conduits are more than 2 in. below the top of the concrete foundation. Where extension conduits are metal, grounding bushings must be installed with a bonding jumper properly terminated.



FRONT VIEW

SIDE VIEW

TYPE C shown, TYPE A similar except that TYPE A shall have individual circuit breakers (CB) mounted on an equipment mounting panel. CB Handles shall protrude through hinged deadfront trim.



SECTION A-A

ANCHOR BOLT DETAIL

LEGEND	
1	Meter Socket, (when required)
2	Meter Socket Window, (when required)
3	Equipment Mounting Panel
4	Photo Electric Control Window, (When required)
5	Hinged Deadfront Trim
6	Load Side Conduit Trim
7	Line Side Conduit Area
8	Utility Access Door, with handle
9	Pedestal Door
10	Hinged Meter Access
11	Control Station (H-O-A Switch)
12	Main Disconnect
13	Branch Circuit Breakers
14	Copper Clad Ground Rod - 5/8" X 10'

		Traffic Operations Division Standard	
ELECTRICAL DETAILS ELECTRICAL SERVICE SUPPORT PEDESTAL SERVICE TYPE PS			
ED(9) - 14			
FILE#	ed9-14.dgn	DWG: TxDOT	CHK: TxDOT
©TxDOT	October 2014	CONT	SECT
REVISIONS		0069	07
		116, ETC.	
		US 87	
DIST	COUNTY		SHEET NO.
SJT	TOM GREEN		81


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TIMBER POLE (TP) SERVICE SUPPORT NOTES

1. Ensure electrical service support is a class 5 treated timber pole as per Item 627 "Treated Timber Poles." Embed timber pole to depth required in Item 627.
2. Conduit and electrical conductors attached to the electrical service pole and underground within 12 in. of service pole are not paid for directly but are subsidiary to the electrical service.
3. Install pole-top mounted photocell (T) on north side of pole, or in service enclosure (E) as required. See Electrical Service Data chart in plan set.
4. Gain pole as required to provide flat surface for each channel. Gain timber pole to $\frac{3}{8}$ in. max. depth and $1\frac{1}{8}$ in. max. height. Gain pole in a neat and workmanlike manner.
5. Mount meter and service equipment on stainless steel or galvanized channel (Unistrut, Kindorf, or equal). Provide channel sized 1 in. to $3\frac{3}{4}$ in. maximum depth, and $1\frac{1}{2}$ in. to $1\frac{5}{8}$ in. maximum width. File smooth the cut ends of galvanized channel and paint with zinc rich paint before installing on pole. Secure each channel section to timber pole with two galvanized or SS lag bolts, $\frac{1}{4}$ in. minimum diameter by $1\frac{1}{2}$ in. minimum length. Use a galvanized or SS flat washer on each lag bolt. Do not stack channel.
6. When excess length must be trimmed from poles, trim from the top end only.

- ① Class 5 pole, height as required
- ② Service drop from utility company (attached below weatherhead)
- ③ Service conduit (RMC) and service entrance conductors - One Red, One Black, One White (See Electrical Service Data)
- ④ Safety switch (when required)
- ⑤ Meter (when required)
- ⑥ Service enclosure
- ⑦ 6 AWG bare grounding electrode conductor in $\frac{1}{2}$ in. PVC to ground rod - extend $\frac{1}{2}$ in. PVC 6 in. underground.
- ⑧ $\frac{5}{8}$ in. x 8 ft. Copper clad ground rod - drive ground rod to a depth of 2 in. to 4 in. below grade.
- ⑨ RMC same size as branch circuit conduit.
- ⑩ See pole-top mounted photocell detail on ED(5).
- ⑪ When required by the serving utility provide bare 6 AWG copper conductor. Run wire from pole top to butt wrap or copper butt plate. Protect conductor with non-conductive material to a height of 8 ft. above finished grade.
- ⑫ When required by utility, cut top of pole at an angle to enhance rain run off.




SERVICE SUPPORT TYPE TP (O)


GRANITE CONCRETE (GC) & OTHER CONCRETE (OC) NOTES

Ensure electrical service support structures bid as type Granite Concrete (GC) or Other Concrete (OC) meet the following requirements.


1. Provide GC and OC poles that meet the requirements of DMS 11080 "Electrical Services."
2. Provide prestressed concrete poles suitable for direct embedment into the ground without special foundations.
3. Verify poles are marked as required on DMS 11080. Location of marking should be approximately 4' above final grade. Use the two-point pickup locations when handling pole in horizontal position, and one-point pickup location for use in raising the pole to a vertical position. These marks are small but conspicuous.
4. Embed poles 42 in. or 10% of the length plus 2 ft., whichever is greater.
5. Ensure all installation details of services are in accordance with utility company specifications.
6. Install a one point rack or eye bolt bracket 6 inches to 12 inches below the weatherhead as an overhead service drop anchoring point for the electric utility.
7. Furnish and install galvanized or stainless steel channel strut $1\frac{1}{2}$ in. or $1\frac{3}{8}$ in. wide by 1 in. up to $3\frac{3}{4}$ in. deep (Unistrut, Kindorf, B-line or equal). Attach channel strut with stainless steel concrete anchors (max. 1" depth), square U-bolts or back to back channel strut with long bolts, or other secure mounting as approved by the Engineer. Ensure bolts are galvanized in accordance with ASTM A153. Do not stack channel struts.
8. Backfill the holes thoroughly by tamping in 6 in. lifts. After tamping to grade, place additional backfill material in a 6 inch high cone around the pole to allow for settling. Use material equal in composition and density to the surrounding area. Backfilling will not be paid for directly but is subsidiary to various bid items.



CONCRETE SERVICE SUPPORT Overhead (O)



CONCRETE SERVICE SUPPORT Underground (U)



DETAIL A

See Note 7. Before installing channel that has been cut, file sharp edges and paint with zinc-rich paint. Ensure there is no paint splatter on the pole.


ELECTRICAL DETAILS SERVICE SUPPORT TYPES GC, OC, & TP			
ED(10)-14			
FILE#	ed10-14.dgn	DWG: TxDOT	CHK: TxDOT
© TxDOT	October 2014	CONT: 0069	SECT: 07
REVISIONS		JOB: 116, ETC.	HIGHWAY: US 87
DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 82	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


DUCT CABLE & HDPE CONDUIT NOTES

1. Provide duct cable in accordance with Departmental Material Specification (DMS) 11060 "Duct Cable" and Item 622 "Duct Cable." Provide duct cable as listed on the Material Producer List (MPL) on the Department web site under "Roadway Illumination and Electrical Supplies" Item 622.
2. Provide High-Density Polyethylene (HDPE) conduit in accordance with DMS 11060 and Item 618, "Conduit." Provide HDPE as listed on the MPL on the Department web site under "Roadway Illumination and Electrical Supplies," Item 618.
3. Supply duct cable with a minimum 2 in. diameter, unless otherwise shown in the plans. Provide duct cable and HDPE conduit as shown by descriptive code or on the plans. Bend duct cable and HDPE conduit as recommended by the manufacturer, with a minimum bending radius of 26 in. for 2 in. duct. Follow manufacturers' recommendations when handling duct cable and HDPE conduit reels and during installation of duct cable and HDPE conduit.
4. Do not splice conductors within duct cable or HDPE conduit. Couple duct cable and HDPE entering a ground box or foundation to a PVC elbow. When galvanized steel RMC elbows are called for in the plans and any portion of the RMC elbow is buried less than 18" from possible contact, ground the RMC elbow.
5. Furnish and install duct cable with factory installed conductors, sized as shown in the plans and as required by the National Electrical Code (NEC). The NEC contains specific requirements for duct cable in Article, "Nonmetallic Underground Conduit with Conductors: Type NUCC."
6. When conduit casing is called for in the plans, extend duct cable or HDPE conduit through the conduit casing in one continuous length without connection to the casing.
7. Seal the ends of duct cable or HDPE conduit with duct seal, expandable foam, or other approved method after completing the pull tests required by Item 622.
8. Provide minimum cover of 24 in. under roadways, 18 in. in other locations, or as shown on the plans.
9. Furnish and install listed fittings to couple duct cable or HDPE conduit to other types of conduit. Duct cable and HDPE conduit may be field-threaded and spliced with PVC or RMC threaded couplings; connected with listed tie-wrap fittings; connected using listed coupling made of HDPE with stainless steel external banding clamps and locking rings; connected with approved electrofusion conduit couplings; or connected using an approved chemical fusion method using an epoxy or adhesive specifically designed for HDPE couplings and connectors all installed in accordance with their manufacturer's instructions. Do not use PVC glue on HDPE. Do not use water pipe fittings, or connect conduit with heat shrink tubing.



DUCT CABLE/HDPE AT GROUND BOX


When the upper end of an RMC EII does not enter the ground box, it may be extended with a SCH-40 PVC conduit nipple and bell end, provided there is a minimum of 18" of cover over all parts of the elbow. If not, a rigid extension and ground bushing is required.




DUCT CABLE / HDPE AT FOUNDATION

Ground rods are not shown on this standard sheet, but may be required elsewhere in plans.


Drill shaft foundation
Class A Concrete



DUCT CABLE/HDPE TO PVC



DUCT CABLE/HDPE TO RMC



BORE PIT DETAIL

				Traffic Operations Division Standard	
ELECTRICAL DETAILS DUCT CABLE/ HDPE CONDUIT					
ED(11)-14					
FILE: ed11-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2014	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87	
REVISIONS		DIST: COUNTY		SHEET NO.	
		SJT TOM GREEN		83	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:


BATTERY BOX GROUND BOXES NOTES

A. MATERIALS


1. Provide polymer concrete or fiberglass reinforced plastic (FRP) battery box ground box and cover in accordance with Departmental Material Specification (DMS) 11071 "Battery Box Ground Boxes." Battery box will accommodate up to 4 batteries, each measuring 8 in. x 13.5 in. x 10 in. (W x L x D). Label battery box ground box cover in accordance with DMS 11071.
2. Supply a marine grade batteries with covers. Secure the marine grade batteries with covers to the stainless steel rack in the bottom of the ground box with tie down straps.

B. CONSTRUCTION METHODS

1. Ensure conduit entry will not interfere with placement of the batteries in the battery box ground box.
2. Remove all gravel and dirt from conduit. Cap all conduits prior to placing aggregate and setting battery box ground box. Provide Grade 3 or 4 coarse aggregate as shown on Table 2 of Item 302 "Aggregates for Surface Treatments." Ensure the aggregate bed is in place and is a minimum of 9 in. deep prior to setting the box. Install battery box ground box on top of aggregate.
3. Cast battery box aprons in place. Reinforcing steel may be field bent. Ensure the depth of concrete for the apron extends from finished grade to the top of the aggregate bed under the box. Battery box ground box aprons, including concrete and reinforcing steel, are subsidiary to battery box ground boxes when called for by descriptive code.
4. Bolt covers down when not working in battery box ground boxes. Keep bolt holes in the box clear of dirt.




PLAN VIEW




SECTION A - A

APRON FOR BATTERY BOX GROUND BOXES


- ① Place aggregate under the box and not in the box. Aggregate should not encroach on the interior volume of the box.
- ② Install bushing or bell end fitting on the upper end of all elbows.
- ③ Install all conduits in a neat and workmanlike manner.




BATTERY BOX TOP VIEW



SECTION X-X



SECTION Y-Y



				Traffic Operations Division Standard	
ELECTRICAL DETAILS BATTERY BOX GROUND BOXES					
ED(12)-14					
FILE: ed12-14.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
©TxDOT October 2014	CONT 0069	SECT 07	JOB 116, ETC.	HIGHWAY US 87	
REVISIONS		DIST	COUNTY	SHEET NO.	
		SJT	TOM GREEN	84	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

FOUNDATION DESIGN TABLE

FDN TYPE	DRILLED SHAFT DIA	REINFORCING STEEL		EMBEDDED DRILLED SHAFT LENGTH-ft (4), (5), (6)			ANCHOR BOLT DESIGN (1)			FOUNDATION DESIGN LOAD (2)		TYPICAL APPLICATION	
		VERT BARS	SPIRAL & PITCH	TEXAS CONE PENETROMETER N Blows/ft			ANCHOR BOLT DIA	Fy (ksi)	BOLT CIR DIA	ANCHOR TYPE	MOMENT k-ft		SHEAR Kips
				10	15	40							
24-A	24"	4- #5	#2 at 12"	5.7	5.3	4.5	3/4"	36	12 3/4"	1	1	Pedestal pole, pedestal mounted controller.	
30-A	30"	8- #9	#3 at 6"	11.3	10.3	8.0	1 1/2"	55	17"	2	3	Mast arm assembly. (see Selection Table)	
36-A	36"	10- #9	#3 at 6"	13.2	12.0	9.4	1 3/4"	55	19"	2	5	Mast arm assembly. (see Selection Table) 30' strain pole with or without luminaire.	
36-B	36"	12- #9	#3 at 6"	15.2	13.6	10.4	2"	55	21"	2	7	Mast arm assembly. (see Selection Table) Strain pole taller than 30' & strain pole with mast arm	
42-A	42"	14- #9	#3 at 6"	17.4	15.6	11.9	2 1/4"	55	23"	2	9	Mast arm assembly. (see Selection Table)	

NOTES:


- Anchor bolt design develops the foundation capacity given under Foundation Design Loads.
- Foundation Design Loads are the allowable moments and shears at the base of the structure.
- Foundations may be listed separately or grouped according to similarity of location and type. Quantities are for the Contractor's information only.
- Field Penetrometer readings at a depth of approximately 3 to 5 feet may be used to adjust shaft lengths.
- If rock is encountered, the Drilled Shaft shall extend a minimum of two diameters into solid rock.
- Decimal lengths in Design Table are to allow interpolation for other penetrometer values. Round to nearest foot for entry into Summary Table.

FOUNDATION SUMMARY TABLE (3)

LOCATION IDENTIFICATION	AVG. N BLOW /ft.	FDN TYPE	NO. EA	DRILLED SHAFT LENGTH (6) (FEET)				
				24-A	30-A	36-A	36-B	42-A
BRYANT BLVD AT 23RD ST								
TS1	10	30A	1		12			
TS2	10	36A	1			14		
TS3	10	36A	1			14		
KOENIGHEIM ST AT HARRIS AVE								
TS1	10	36A	1			14		
TS2	10	36A	1			14		
ABE ST AT HARRIS AVE								
TS1	10	36A	1			14		
TS2	10	36A	1			14		
ABE ST AT CONCHO AVE								
TS1	10	30A	1		12			
BRYANT BLVD AT JACKSON ST								
TS2	10	36A	1			14		
TS4	10	36A	1			14		
TOTAL DRILLED SHAFT LENGTHS					24	112		

FOUNDATION SELECTION TABLE FOR STANDARD MAST ARM PLUS ILSN SUPPORT ASSEMBLIES (ft)

80 MPH DESIGN WIND SPEED	MAX SINGLE ARM LENGTH	FDN 30-A	FDN 36-A	FDN 36-B	FDN 42-A
		MAXIMUM DOUBLE ARM LENGTH COMBINATIONS	24' X 24' 28' X 28' 32' X 28'	32' X 32' 36' X 36' 40' X 36' 44' X 28'	44' X 36'
100 MPH DESIGN WIND SPEED	MAX SINGLE ARM LENGTH	24' X 24' 28' X 28' 32' X 24'	36' X 36' 40' X 36'	44' X 36'	40' X 36'
		MAXIMUM DOUBLE ARM LENGTH COMBINATIONS	32' X 24'	32' X 32' 36' X 36' 40' X 24'	40' X 36'




ANCHOR BOLT & TEMPLATE SIZES



BOLT DIA IN.	BOLT LENGTH	TOP THREAD	BOTTOM THREAD	BOLT CIRCLE	R2	R1
3/4"	1'-6"	3"	—	12 3/4"	7 1/8"	5 5/8"
1 1/2"	3'-4"	6"	4"	17"	10"	7"
1 3/4"	3'-10"	7"	4 1/2"	19"	11 1/4"	7 3/4"
2"	4'-3"	8"	5"	21"	12 1/2"	8 1/2"
2 1/4"	4'-9"	9"	5 1/2"	23"	13 3/4"	9 1/4"

(7) Min dimensions given, longer bolts are acceptable.


- EXAMPLE:**
- For 80mph design wind speed, foundation 30-A can support up to a 32' arm with another arm up to 28'
 - For 100mph design wind speed, foundation 36-A can support a single 36' mast arm.




HOOKED ANCHOR (TYPE 1) NUT ANCHOR (TYPE 2) ANCHOR BOLT ASSEMBLY



(8) Orient anchor bolts orthogonal with the fixed arm direction to ensure that two bolts are in tension under dead load.



TOP VIEW



GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals and interim revisions thereto.

Reinforcing steel shall conform to Item 440, "Reinforcing Steel".

Concrete shall be Class "C".

Threads for anchor bolts and nuts shall be rolled or cut threads of 8UN series up to 2" in diameter or UNC series for all sizes. Bolts and nuts shall have Class 2A and 2B fit tolerances. Galvanized nuts shall be tapped after galvanizing.

Anchor bolts that are larger than 1" in diameter shall conform to "alloy steel" or "medium-strength mild steel" per Item 449, "Anchor Bolts". Anchor bolts that are 1" in diameter or less shall conform to ASTM A36. Galvanize a minimum of the top end thread length plus 6" for all anchor bolts unless otherwise noted. Exposed washers and exposed nuts shall be galvanized. All galvanizing shall be in accordance with Item 445, "Galvanizing".

Templates and embedded nuts need not be galvanized. Lubricate and tighten anchor bolts when erecting the structure in accordance with Item 449, "Anchor Bolts".






TRAFFIC SIGNAL POLE FOUNDATION

TS-FD-12

© TxDOT August 1995		DN: MS	CK: JSY	DN: MAO/MMF	CK: JSY/TEB
REVISIONS		CONT	SECT	JOB	HIGHWAY
		0069	07	116, ETC.	US 87
		DIST	COUNTY	SHEET NO.	
		SJT	TOM GREEN	85	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



TRAFFIC SIGNAL CONTROLLER BASE:

1. Provide a traffic signal controller base (cabinet base) manufactured of polymer concrete material consisting of calcareous and siliceous stone; glass fibers and thermoset polyester resin. The polymer concrete cabinet base must be reinforced on the inside of the cabinet base with fiberglass matting. Provide one of the following bases: Armorcast Part # A6001848X24, Quazite Model # PG3048Z709, or other as approved by TxDOT Traffic Safety Division.
2. The polymer concrete material must have a minimum compressive strength of 10,300 pounds per square inch (psi), minimum flexural strength of 3600 psi, and minimum shear strength of 3600 psi.
3. The polymer concrete cabinet base must conform to the dimensions shown and must accommodate a standard TxDOT basemount cabinet.
4. Supply the cabinet base with four 1#2"-13 UNC stainless steel inserts for attachment of the cabinet to the base. Inserts must withstand a minimum torque of 50 ft-lb and a minimum straight pull out strength of 750 lbs.
5. Provide the cabinet base with 4 cable racks mounted one on each side of the base 2" to 7" from the top edge of the base. Unless approved otherwise, cable racks must be 1-1/2 x 9#16x 3#16inch steel channel with eight T-slots spaced at 1-1/2 inches. The cable racks must easily accommodate the insertion of tie wraps to attach field wiring to the racks to serve as strain relief. Secure cable racks to the base using 1#2"-13 UNC stainless steel screws and inserts.
6. The cabinet base, when secured to the concrete slab with controller cabinet attached, must withstand a minimum wind load of 125 mph or a 850 lb force applied at 49" above the bottom of the base without causing the base or cabinet to come out of their anchored position or cause any permanent deformation. The manufacturer must supply certification by an independent testing laboratory or sealed by a Texas Licensed Professional Engineer. Provide the cabinet base with hardware for attachment to a concrete slab.
7. The traffic signal base must be permanently marked either by impress or by permanent ink with the manufacturer's model number and name or logo.
8. Seal the base to the concrete with a silicone caulk bead and fastened to the slab per manufacturer's instructions.

CONCRETE SLAB:

9. Traffic signal controller pad must be a portland cement concrete slab poured in place, must conform to the dimensions shown, and must be level.
10. Grade earthwork such that it is flush with the concrete pad on all four sides, unless otherwise shown on the plans. Subsidiary to ITEM 680, four inch rip rap may be used in lieu of earthwork. Slopes shall gradually contour to match plans.
11. Bond a #8 AWG copper ground wire and an 8 ft ground rod bonded to the reinforcing mesh by a suitable UL Listed clamp and terminated to the cabinet grounding bus for the purpose of providing a local ground for the electrical grounding conductor. The electrical grounding conductor specified in Item 680-3.A.4 is required and must be terminated to the cabinet ground bus.
12. Install a PVC sleeve to prevent the ground rod from direct embedment in the slab.
13. Provide welded wire mesh 6X6-W2.9 X W2.9 for reinforcement. Provide joints and splices in the mesh with a minimum 6-inch overlap. Center the mesh between top and bottom and provide a minimum 3 inch cover on the edges.
14. Provide Class B concrete minimum for the slab in accordance with Item 421. Construct the slab in accordance with Item 531.

CONDUITS:

15. Stub up and run 3-inch conduits through the slab to the various traffic signal poles and ground boxes as shown on the layouts. Install the number of conduits as shown on layouts plus two additional 3 inch conduits for future use. Terminate the conduits with a bushing between 2 and 4-inches above the slab.
16. Extend conduits for future use at least 18-inches from the edge of the slab, terminate underground with a coupling, and cap and seal so that the seal can be removed without damaging the coupling. This must also apply to unused telephone conduit.
17. Stub up two separate conduits through the slab from the electrical and telephone services. Run the conduit for the electrical feed directly to the electrical service enclosure. Run the conduit for the telephone line directly to the telephone service, usually located on the same pole as the electrical service. Telephone must not under any circumstance share a conduit with any other function.
18. Terminate electric and telephone conduits above the slab with a coupling. After the base is installed, extend the conduits above the top of the base and secure to the base using a steel one-hole strap or similar suitable substitute.

CONTROLLER CABINET:

19. Anchor the controller cabinet to the base using four stainless steel 1/2-13 NC bolts.
20. The silicone caulk bead specified in Item 680.3.B must be RTV 133.


PAYMENT:

21. Bid TS-CF as subsidiary to Item 680.


<h2>TRAFFIC SIGNAL CONTROLLER CABINET BASE AND PAD</h2> <h3>TS-CF-21</h3>			
FILE: ts-cf-21.dgn	DWG:	CK1:	CK2:
© TxDOT October 2000	CONT: 0069	SECT: 07	JOB: 116, ETC.
12-04	REVISIONS		HIGHWAY: US 87
2-21	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 86

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




THREE-SECTION HEAD
HORIZONTAL OR VERTICAL




FOUR-SECTION HEAD
HORIZONTAL OR VERTICAL



FIVE-SECTION HEAD
HORIZONTAL OR VERTICAL



FIVE-SECTION HEAD
CLUSTER



PEDESTRIAN HYBRID
BEACON

GENERAL NOTES:

1. Backplates are optional for traffic signals and pedestrian hybrid beacons. When backplates are used, a 2-inch wide fluorescent yellow AASHTO Type B_{FL} or C_{FL} retroreflective border conforming to TxDOT DMS-8300 is required. Place on all approaches when used.
2. Signal head and backplate compatibility must be verified by the contractor prior to installation.
3. When using backplates on signal heads, venting is preferred to reduce cyclic vibration stress.
4. When a vented backplate is used, the retroreflective border must not be placed over the louvers.
5. This standard sheet applies to all signal heads with backplates, including but not limited to:
 - Pole mounted
 - Overhead mounted
 - Span wire mounted
 - Mast arm mounted
 - Vertical signal heads
 - Horizontal signal heads
 - Clustered signal heads
 - Pedestrian hybrid beacons


		Texas Department of Transportation		Traffic Safety Division Standard	
TRAFFIC SIGNAL HEAD WITH BACKPLATE					
TS-BP-20					
FILE: ts-bp-20.dgn	DWG: TxDOT	CHK: TxDOT	DWG: TxDOT	CHK: TxDOT	
© TxDOT June 2020	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87	
REVISIONS	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 87		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


Arm Length	ROUND POLES					POLYGONAL POLES					Foundation Type
	D _B	D ₁₉	D ₂₄	D ₃₀	① thk	D _B	D ₁₉	D ₂₄	D ₃₀	① thk	
ft.	in.	in.	in.	in.	in.	in.	in.	in.	in.	in.	
20	10.5	7.8	7.1	6.3	.179	11.5	8.5	7.7	6.8	.179	30-A
24	11.0	8.3	7.6	6.8	.179	12.0	9.0	8.2	7.3	.179	30-A
28	11.5	8.8	8.1	7.3	.179	12.5	9.5	8.7	7.8	.179	30-A
32	12.5	9.8	9.1	8.3	.179	12.0	9.0	8.2	7.3	.239	30-A
36	12.0	9.3	8.6	7.8	.239	12.5	9.5	8.7	7.8	.239	36-A
40	12.0	9.3	8.6	7.8	.239	13.5	10.5	9.7	8.8	.239	36-A
44	12.5	9.8	9.1	8.3	.239	14.0	11.0	10.2	9.3	.239	36-A
48	13.0	10.3	9.6	8.8	.239	15.0	12.0	11.2	10.3	.239	36-A

Arm Length	ROUND ARMS					POLYGONAL ARMS				
	L ₁	D ₁	D ₂	① thk	Rise	L ₁	D ₁	② D ₂	① thk	Rise
ft.	ft.	in.	in.	in.		ft.	in.	in.	in.	
20	19.1	6.5	3.8	.179	1'-9"	19.1	7.0	3.5	.179	1'-8"
24	23.1	7.5	4.3	.179	1'-10"	23.1	7.5	3.5	.179	1'-9"
28	27.1	8.0	4.2	.179	1'-11"	27.1	8.0	3.5	.179	1'-10"
32	31.0	9.0	4.7	.179	2'-1"	31.0	9.0	3.5	.179	2'-0"
36	35.0	9.5	4.6	.179	2'-4"	35.0	10.0	3.5	.179	2'-1"
40	39.0	9.5	4.1	.239	2'-8"	39.0	9.5	3.5	.239	2'-3"
44	43.0	10.0	4.1	.239	2'-11"	43.0	10.0	3.5	.239	2'-6"
48	47.0	10.5	4.1	.239	3'-4"	47.0	11.0	3.5	.239	2'-9"

- D_B = Pole Base O.D.
- D₁₉ = Pole Top O.D. with no Luminaire and no ILSN
- D₂₄ = Pole Top O.D. with ILSN w/out Luminaire
- D₃₀ = Pole Top O.D. with Luminaire
- D₁ = Arm Base O.D.
- D₂ = Arm End O.D.
- L₁ = Shaft Length
- L = Nominal Arm Length
- ① Thickness shown are minimums, thicker materials may be used.
- ② D₂ may be increased by up to 1" for polygonal arms.



TRAFFIC SIGNAL ARM
(Fixed Mount)



③ Threaded Coupling for CGB Connector See "ARM COUPLING DETAILS" Sheet 2 of 2

TABLE OF DIMENSIONS "A"							
Arm Length	24'	28'	32'	36'	40'	44'	48'
Arm Type II	10'	11'	12'	13'			
Arm Type III			10'	11'	12'	12'	12'

STRUCTURE ASSEMBLY

SHIPPING PARTS LIST

Ship each pole with the following attached: enlarged hand hole, pole cap, fixed-arm connection bolts and washers and any additional hardware listed in the table.

Nominal Arm Length	30' Poles With Luminaire		24' Poles With ILSN		19' Poles With No Luminaire and No ILSN	
	Designation	Quantity	Designation	Quantity	Designation	Quantity
ft.	ft.		ft.		ft.	
20	20L-80		20S-80		20-80	
24	24L-80	1	24S-80		24-80	1
28	28L-80		28S-80		28-80	
32	32L-80		32S-80		32-80	
36	36L-80		36S-80		36-80	
40	40L-80	1	40S-80	1	40-80	
44	44L-80		44S-80		44-80	3
48	48L-80	1	48S-80		48-80	2

Traffic Signal Arms (1 per Pole) Ship each arm with the listed equipment attached

Nominal Arm Length	Type I Arm (1 Signal)		Type II Arm (2 Signals)		Type III Arm (3 Signals)	
	Designation	Quantity	Designation	Quantity	Designation	Quantity
ft.	ft.		ft.		ft.	
20	20I-80					
24	24I-80		24II-80			
28	28I-80		28II-80			
32			32II-80		32III-80	
36			36II-80		36III-80	
40					40III-80	
44					44III-80	
48					48III-80	

Luminaire Arms (1 per 30' pole)

Nominal Arm Length	Quantity
8' Arm	3

ILSN Arm (Max. 2 per pole) Ship with clamps, bolts and washers

Nominal Arm Length	Quantity
7' Arm	
9' Arm	1

Anchor Bolt Assemblies (1 per pole)

Anchor Bolt Diameter	Anchor Bolt Length	Quantity
1 1/2"	3'-4"	
1 3/4"	3'-10"	10

Each anchor bolt assembly consists of the following: Top and Bottom templates, 4 anchor bolts, 8 nuts, 8 flat washers, and 4 nut anchor devices (Type 2) per Standard Drawing "TS-FD".


Templates may be removed for shipment.

Texas Department of Transportation
 Traffic Operations Division
TRAFFIC SIGNAL SUPPORT STRUCTURES
 SINGLE MAST ARM ASSEMBLY
 (80 MPH WIND ZONE)
SMA-80(1)-12


REVISIONS		DN: MS	CK: JSY	DW: MMF	CK: JSY
5-96	0069	07	116, ETC.		US 87
11-99					
1-12					
DIST		COUNTY		SHEET NO.	
SJT		TOM GREEN		88	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




SLIP JOINT DETAIL



TENON DETAIL

Stainless steel bands (or Cables) and cast bracket as in "Astro-Brac", "Sky Bracket" or "Easy Bracket" with 1 1/2" Dia Threaded Coupling.

BRACKET ASSEMBLY



ARM WELD DETAIL

ARM COUPLING DETAILS

④ 60% Min. penetration
100% penetration within 6" of circumferential base welds.

VIBRATION WARNING

Mast Arms of SMA and DMA structures and clamp-on Arms of LMA structures of approximately 40 ft or longer are subject to harmonic vertical vibrations in light wind conditions due to the aeroelastic characteristics of a few of the myriads of possible combinations of the following: signal numbers, weights and positions; existence/solidity of backplates; presence of additional attachments to the arm, such as signs and cameras; arm-wind orientation; and arm-pole stiffness.

Such vibrations may cause fatigue damage to the structure and may lead to galloping in moderate wind conditions which may further damage the structure and alarm the public. Tests have indicated that when wind is blowing toward the back side of signal heads having un-vented backplates attached the probability of unacceptable harmonic vibration and/or galloping is rather high.

If backplates are not required for improved visibility they should not be applied to the signal heads or, if they must be applied, they should be vented as a first and inexpensive measure to mitigate vibrations.

The traffic signal mast arms shall be visually inspected in 5 to 20 mph wind conditions after installation of signal heads and any attachments, including any required backplates. If vertical movements with a total excursion (maximum upward excursion to maximum downward excursion) of more than approximately 8" are observed at the arm tip, a damping plate shall be fitted to the arm. See "Damping Plate Mounting Details" on standard sheet, MA-DPD-10.

This visual inspection shall be repeated after each modification of the structure that could affect its aeroelastic response. Excessive vibrations shall not be allowed to continue for more than two days.

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications thereto. Design Wind Speed equals 80 mph plus a 1.3 gust factor.

Poles are designed to support one 8'-0" luminaire arm, one 9'-0" internally lighted street name sign and one traffic signal arm with a length as tabulated. The specified luminaire load applied at the end of the luminaire arm equals 60 lbs vertical dead load plus the horizontal wind load on an effective projected area of 1.6 sq ft. The specified internally lighted street name sign load applied 4.5 ft from the centerline of the pole equals 85 lbs vertical dead load plus horizontal wind load on an effective projected area of 11.5 sq ft. The specified signal load applied at the end of the traffic signal arm equals 180 lbs vertical dead load plus the horizontal wind load on an effective projected area of 32.4 sq ft (actual area times drag coefficient).

See Standard Sheet "MA-D" for pole details, "MA-C" for traffic signal arm connection details, "MA-C (ILSN)" for internally lighted street name sign arm connection details, "LUM-A" for luminaire arm and connection details, "SNS" for internally lighted street name sign details, and "TS-FD" for anchor bolt and foundation details. See "MA-C" for material specifications.


Fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Materials, fabrication tolerances, and shipping practices shall meet the requirements of this sheet and Item 686, "Traffic Signal Pole Assemblies (Steel)".

Unless otherwise noted, all parts shall be galvanized in accordance with Item 445, "Galvanizing", after fabrication.

Deviation from the details and dimensions shown herein require submission of shop drawings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.

© TxDOT August 1995	DN: MS	CK: JSY	DW: MMF	CK: JSY
5-96 1-12	REVISIONS	CONT	SECT	JOB
		0069	07	116, ETC.
		DIST	COUNTY	SHEET NO.
		SJT	TOM GREEN	89

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



Note: The arm shall be fabricated straight with the unload rise measured as shown.


Note: The arm shall be fabricated with a 20' or greater radius within 8' of the base so as to produce the unloaded rise measured as shown.

FIXED MOUNT TRAFFIC SIGNAL ARM

① See Sheet 3 of 5 for Arm Rise

CLAMP-ON TRAFFIC SIGNAL ARM (IF REQUIRED)

② See Sheet 4 of 5 for Arm Rise and Clamp-on Arm Details



ELEVATION


(Showing fixed mount arm)

STRUCTURE ASSEMBLY


ELEVATION

(Showing clamp-on arm)

Arm Length	24'	28'	32'	36'	40'	44'	50'	55'	60'	65'
Arm Type II	10'	11'	12'	13'						
Arm Type III			10'	11'	12'	12'				
Arm Type IV							12'	12'	12'	12'



TENON DETAIL



SLIP JOINT DETAIL (FIXED MOUNT ARM)

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals and Interim Specifications thereto. Design Wind Speed can be either 100 mph or 80 mph plus a 1.3 gust factor. If clamp-on traffic signal is required, designs are based on an arm included angle of 90 degrees or more. Angles of less than approximately 75 degrees will require a special design.

Poles are designed to support one 8'-0" luminaire arm, two 9'-0" internally lighted street name (ILSN) signs and two traffic signal arms with limited length combinations.

Each arm with its related attachment is shown below

Arm	Equivalent DL ⑤	WL EPA ⑤⑥
8' Luminaire Arm	Luminaire 60 lbs	1.6 sq ft
9' ILSN Arm	Sign 85 lbs	11.5 sq ft
50' to 65' Fixed Mount Arm	Signal Loads 310 lbs	52 sq ft
Up to 44' Clamp-on Arm	Signal Loads 180 lbs	32.4 sq ft

⑤ Equivalent dead load plus horizontal wind load applied at the end of arm except ILSN arm, which applied 4.5' from the centerline of the pole.

⑥ Effective projected area (actual area times drag coefficient) for the application of horizontal wind load.

Except as noted in Sheet 1 thru 5 of 5, other details not covered shall refer to Standard Sheet "MA-D" for pole details, "LUM-A" for luminaire arm and connection details, "SNS" for internally lighted street name sign details, and "TS-FD" for anchor bolt and foundation details.

Fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. Material, fabrication tolerances, and shipping practices shall also meet the requirements of this sheet and Item 686, "Traffic Signal Pole Assemblies (Steel)".

Unless otherwise noted, all parts shall be galvanized in accordance with Item 445, "Galvanizing" after fabrication.

Deviations from the details and dimensions shown herein require submission of shop drawings in accordance with the Item 441, "Steel Structures". Alternate designs are not acceptable.

Installation of damping plate for the long mast arm is not recommended.

Provision of the bracket assembly used to support the traffic signal heads shall be under the direction of the Engineer for approval.

Design also conforms to NCHRP Report 412 for fatigue resistance except that there are no stiffeners at the base plate. TxDOT is conducting tests to determine if stiffeners at the base plate will or will not result in optimal performance; depending upon the results of the tests, poles may need a retrofit to ensure optimal fatigue performance.

Texas Department of Transportation
Traffic Operations Division

**TRAFFIC SIGNAL SUPPORT STRUCTURES
LONG MAST ARM ASSEMBLY
(50 TO 65 FT)
(80 AND 100 MPH WIND ZONE)
LMA(1)-12**


Sheet 1 of 5

© TxDOT July 2000	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
REVISIONS	CONT	SECT	JOB	HIGHWAY
0069 07			116, ETC.	US 87
	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	90	


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




DETAIL A
(for pole with luminaire)



DETAIL B
(If ILSN applied)




DETAIL C




DETAIL D
(for 30' pole with luminaire and ILSN sign)




POLE ELEVATION




BASE PLATE




ACCESS COMPARTMENT




SECTION Y-Y




DETAIL J



DETAIL F
(for 20.25' pole with no ILSN sign and no luminaire, dual mast arm)



DETAIL G
(for 19.5' pole with no ILSN sign and no luminaire, single mast arm)



SECTION A-A


POLE COUPLING DETAIL

⑨ Longitudinal seam weld must be oriented within 90° (45° rotation each side) along the fixed mount arm. 60% min penetration required, 100% penetration within 6\"/>


MATERIALS	
Round Shafts or Polygonal Shafts ⑦	ASTM A595 Gr. A, A588, A1008 HSLAS Gr.50 Class 2, A1011 HSLAS Gr.50 Class 2, A572 Gr.50 or A1011 SS Gr.50 ⑧
Plates ⑦	ASTM A36, A588, or A572 Gr.50
Connection Bolts	ASTM A325, or A449 except where noted
Pin Bolts	ASTM A325
Pipe ⑦	ASTM A53 Gr. B, A501, A1008 HSLAS-F Gr.50, A1011 HSLAS-F Gr.50
Misc. Hardware	Galvanized steel or stainless steel or as noted

⑦ ASTM A572, A1008 HSLAS, A1011 HSLAS, A1008 HSLAS-F, A1011 HSLAS-F, or A1011 SS may have higher yield strengths but shall not have less elongation than the grade indicated.

⑧ ASTM A1011 SS Gr.50 shall also have a minimum elongation of 18 percent in 8 inches or 23 percent in 2 inches. Material thickness in excess of those stipulated under A1011 SS will be acceptable providing the material meets all other A1011 SS requirements and the requirements of this item.



COPPER GROUND CONNECTOR



SECTION B-B

ACCESS COMPARTMENT NOTES:

- The cover shall be one piece formed from ABS plastic, shall be a pearl gray color, and shall be suitable for exposure to harsh sunlight and extreme weather. Cover shall latch with two screw latches and shall fit tightly to the enclosure ring to create a rainproof seal. Latch screws shall be 1/4-20 stainless flat socket head screws with tamper proof feature.
- The pole manufacturer shall provide with each pole a separate kit consisting of: one cover with two latching assemblies, two terminal strips (Marathon #985G12CU or approved equal), four #8-32 x 1 1/4\"/>


Texas Department of Transportation
Traffic Operations Division

**TRAFFIC SIGNAL SUPPORT STRUCTURES
LONG MAST ARM ASSEMBLY
(50 TO 65 FT)
(80 AND 100 MPH WIND ZONE)
LMA (2) -12**


Sheet 2 of 5

© TxDOT July 2000		DN: JSY	CK: ARC	DW: TGG	CK: JSY
REVISIONS		CONT	SECT	JOB	HIGHWAY
		0069	07	116, ETC.	US 87
		DIST	COUNTY	SHEET NO.	
		SJT	TOM GREEN	91	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




BUILT-UP BOX CONNECTION




REINFORCING STIFFENER




ARM STIFFENER
(Cut to match arm inclination and taper)




DETAIL "K"




SECTION F-F




SECTION C-C



ANCHOR BOLT ASSEMBLY



TEMPLATE DETAIL



SECTION D-D

FDN TYPE	DRILLED SHAFT DIA	REINFORCING STEEL		DRILLED SHAFT LENGTH-FT (16), (17), (18)			ANCHOR BOLT DESIGN (14)			FOUNDATION DESIGN LOAD (15)		TYPICAL APPLICATION	
		VERT BARS	SPIRAL & PITCH	TEXAS CONE PENETROMETER N blows/ft			ANCHOR BOLT DIA	Fy (Ksi)	BOLT CIR DIA	ANCHOR TYPE	MOMENT K-ft		SHEAR Kips
				10	15	40							
48-A	48"	20 #9	#4 at 6"	21.9	19.5	14.7	2 1/2"	55	27"	2	490	10	50' to 65' Mast arm assembly.

SEE SHEET "TS-FD" FOR ADDITIONAL DETAILS.

- (14) Anchor bolt design develops the foundation capacity given under Foundation Design Loads.
- (15) Foundation Design Loads are the allowable moments and shears at the base of the structure.
- (16) Field Penetrometer readings at a depth of approximately 3 to 5 feet may be used to adjust shaft lengths.
- (17) If rock is encountered, the Drilled Shaft shall extend a minimum of two diameters into solid rock.
- (18) Decimal lengths in Design Table are to allow interpolation for other penetrometer values. Round to nearest foot for entry into Summary Table.

Fixed Mount Arm L F	ROUND POLES (13)					Foundation Type
	D _B	D _{19.5} or D _{20.25}	D ₂₄	D ₃₀	(12)thk	
ft.	in.	in.	in.	in.	in.	
50', 55', 60', 65'	21.0	18.2	17.6	16.8	.3125	48-A

Fixed Mount Arm L F	ROUND ARMS (13)				
	L ₁	D ₁	D ₂	(12)thk	Rise
ft.	ft.	in.	in.	in.	
50	49	18.5	11.7	.3125	3'- 3"
55	54	18.5	11.0	.3125	3'- 7"
60	59	18.5	10.3	.3125	3'-11"
65	64	18.5	9.6	.3125	4'- 4"

- D_B = Pole Base O.D.
- D_{19.5} = Pole Top O.D. with no Luminaire and no ILSN (single mast arm)
- D_{20.25} = Pole Top O.D. with no Luminaire and no ILSN (dual mast arm)
- D₂₄ = Pole Top O.D. with ILSN w/out Luminaire
- D₃₀ = Pole Top O.D. with Luminaire
- D₁ = Arm Base O.D.
- D₂ = Arm End O.D.
- L₁ = Shaft Length
- L_F = Fixed Arm Length

- (12) Thickness shown is minimum, thicker materials may be used.
- (13) Shaft profile 16-sided or 18-sided is considered to be equivalent to round section.

GENERAL NOTES:

Built-up Box Connection: For the welded arm-to-pole connection as a built-up box configuration illustrated here is an example only, fabricators are required to submit a shop drawing of box connection for approval. The drawing shall specify the details of each box element, welds of arm-to-pole connection, arm-to-plate socket connection, and arm rise creation. Specify the proper location of drain holes along the pole. 2 1/2 inch dia hole in the pole mounting plate and 4 inch dia hole in the pole need to be aligned for wiring access or drainage. Arm stiffeners cut to match arm inclination and taper shall also be included.

The deviation from flat for either arm or pole mounting plate shall not exceed 1/32 inch, which is measured along the center of mounting plate to a radial distance of 13.5 inch. The deformed-from-flat connection between arm and pole mounting plates shall not be allowed if the center of both mounting plates cannot contact directly.

Fixed mount details are used for single mast arm assemblies and for the first arm on dual mast arm assemblies.

ANCHOR BOLT & TEMPLATE SIZE						
Bolt Dia in.	Length #	Top Thread	Bottom Thread	Bolt Circle	R ₂	R ₁
2 1/2"	5'-2"	10"	6 1/2"	27"	16"	11"

*Min dimension given, longer bolts are acceptable.

Texas Department of Transportation
Traffic Operations Division

**TRAFFIC SIGNAL SUPPORT STRUCTURES
LONG MAST ARM ASSEMBLY
(50 TO 65 FT)
(80 AND 100 MPH WIND ZONE)**

Sheet 3 of 5 **LMA (3) -12**


© TxDOT July 2000

DN: JSY	CK: ARC	DW: TGG	CK: JSY
CON: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 92	

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



CLAMP-ON CONNECTION


80 MPH WIND											
Clamp-on Arm Lc	ROUND ARMS					POLYGONAL ARMS					
	L ₁	D ₁	D ₂	thk (12)	Rise	L ₁	D ₁	D ₂	thk (12)	Rise	
ft.	ft.	in.	in.	in.		ft.	in.	in.	in.		
20	19.1	6.5	3.8	.179	1'-9"	19.1	7.0	3.5	.179	1'-8"	
24	23.1	7.5	4.3	.179	1'-10"	23.1	7.5	3.5	.179	1'-9"	
28	27.1	8.0	4.2	.179	1'-11"	27.1	8.0	3.5	.179	1'-10"	
32	31.0	9.0	4.7	.179	2'-0"	31.0	9.0	3.5	.179	2'-0"	
36	35.0	9.5	4.6	.179	2'-4"	35.0	10.0	3.5	.179	2'-1"	
40	39.0	9.5	4.1	.239	2'-8"	39.0	9.5	3.5	.239	2'-3"	
44	43.0	10.0	4.1	.239	2'-11"	43.0	10.0	3.5	.239	2'-6"	

100 MPH WIND											
Clamp-on Arm Lc	ROUND ARMS					POLYGONAL ARMS					
	L ₁	D ₁	D ₂	thk (12)	Rise	L ₁	D ₁	D ₂	thk (12)	Rise	
ft.	ft.	in.	in.	in.		ft.	in.	in.	in.		
20	19.1	8.0	5.3	.179	1'-8"	19.1	8.0	3.5	.179	1'-7"	
24	23.1	9.0	5.8	.179	1'-9"	23.1	9.0	3.5	.179	1'-8"	
28	27.1	9.5	5.7	.179	1'-10"	27.1	10.0	3.5	.179	1'-9"	
32	31.0	9.5	5.2	.239	1'-11"	31.0	9.5	3.5	.239	1'-10"	
36	35.0	10.0	5.1	.239	2'-0"	35.0	10.0	3.5	.239	1'-11"	
40	39.0	10.5	5.1	.239	2'-3"	39.0	11.0	3.5	.239	2'-1"	
44	43.0	11.0	5.1	.239	2'-8"	43.0	11.5	4.0	.239	2'-3"	



D₁ = Arm Base O.D.
 D₂ = Arm End O.D.
 L₁ = Shaft Length
 Lc = Clamp-on Arm Length

(12) Thickness shown is minimum, thicker materials may be used.

ARM COUPLING DETAIL




ILSN ARM COUPLING DETAIL



SLIP JOINT DETAIL (CLAMP-ON ARM)

Stainless steel bands (or Cables) and cast bracket as in "Astro-Brac", "Sky Bracket" or "Easy Bracket" with 1 1/2" Dia Threaded Coupling.

BRACKET ASSEMBLY



ARM WELD DETAIL

(19) Longitudinal Seam Weld must be oriented within the lower 90° of the signal arm. 60% Min penetration. 100% penetration within 6" of circumferential base welds.

CLAMP-ON ARM CONNECTION

ILSN Arm Size		A	F	4 Conn. Bolts	5/8" Dia. Pin Bolts
Sch 40 pipe Dia	Thick				
in.	in.	in.	in.	in.	ea
3	.216	10	4	3/4	2

Mast Arm Size		A	F	4 Conn. Bolts	5/8" Dia. Pin Bolts
Base Dia	Thick				
in.	in.	in.	in.	in.	ea
6.5	.179	12	6	1	2
7.5	.179	14	8	1	2
8.0	.179	14	8	1	2
9.0	.179	16	10	1	2
9.5	.179	18	12	1 1/4	3
9.5	.239	18	12	1 1/4	3
10.0	.239	18	12	1 1/4	3
10.5	.239	18	12	1 1/4	3
11.0	.239	18	12	1 1/4	3
11.5	.239	18	12	1 1/4	3

GENERAL NOTES:

Clamp-on details are used for the second arm on dual mast arm assemblies or ILSN arm support. For a clamp-on mast arm, a maximum 1 1/2" wide vertical slotted hole may be cut in the front clamp plate to facilitate drainage during galvanizing. The slot shall be centered behind the arm and shall be no longer than the arm diameter minus 1". For an ILSN arm, a 1 1/2" diameter hole shall be cut in the front clamp plate for wire access. A matched hole shall be field drilled through the pole to provide wire access after arm is oriented. Deburr both holes.

Where duplicate parts occur on a detail, welds shown for part shall apply to all similar parts on the detail.

Pin bolts are required to prevent rotation of clamp-on arms under design wind forces. Pin bolts shall be ASTM A325 with threads excluded from the shear plane. Pin bolt and 3/4" diameter pipe shall have 3/16" diameter holes for a 1/8" diameter galvanized cotter pin. Back clamp plate shall be furnished with a 3/4" diameter hole for each pin bolt. An 1/8" diameter hole for each pin bolt shall be field drilled through the pole after arm orientations have been approved by the Engineer.

Texas Department of Transportation
 Traffic Operations Division

**TRAFFIC SIGNAL SUPPORT STRUCTURES
 LONG MAST ARM ASSEMBLY
 (50 TO 65 FT)
 (80 AND 100 MPH WIND ZONE)**

Sheet 4 of 5 LMA (4) -12

© TxDOT November 2000	DN: JK	CK: GRB	DW: FDN	CK: CAL
4-20-01 1-12	REVISIONS	CONT	SECT	JOB
		0069	07	116, ETC.
		DIST	COUNTY	SHEET NO.
		SJT	TOM GREEN	93

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Shipping Parts List							
Ship each pole with the following attached: enlarged hand hole, pole cap, fixed arm connection bolts and washers, and any additional hardware listed in the table.							
Nominal Arm Length	30' Poles with Luminaire	24' Poles with ILSN	19.50' (Single Mast Arm) 20.25' (Dual Mast Arm) Poles with no Luminaire and no ILSN See note above				
	See note above plus: one (or two if ILSN attached) small hand hole, clamp-on simplex	See note above plus one small hand hole					
Single Mast Arm							
Lf ft.	Designation	Quantity	Designation	Quantity	Designation	Quantity	
50	50L		50S		50		
55	55L		55S		55		
60	60L	3	60S		60		
65	65L		65S		65		
Dual Mast Arm							
Lf ft.	Lc ft.	Designation	Quantity	Designation	Quantity	Designation	Quantity
50	20	5020L		5020S		5020	
	24	5024L		5024S		5024	
	28	5028L		5028S		5028	
	32	5032L		5032S		5032	
	36	5036L		5036S		5036	
	40	5040L		5040S		5040	
	44	5044L		5044S		5044	
55	20	5520L		5520S		5520	
	24	5524L		5524S		5524	
	28	5528L		5528S		5528	
	32	5532L		5532S		5532	
	36	5536L		5536S		5536	
	40	5540L		5540S		5540	
	44	5544L		5544S		5544	
60	20	6020L		6020S		6020	
	24	6024L		6024S		6024	
	28	6028L		6028S		6028	
	32	6032L		6032S		6032	
	36	6036L		6036S		6036	
	40	6040L		6040S		6040	
	44	6044L		6044S		6044	
65	20	6520L		6520S		6520	
	24	6524L		6524S		6524	
	28	6528L		6528S		6528	
	32	6532L		6532S		6532	
	36	6536L		6536S		6536	
	40	6540L		6540S		6540	
	44	6544L		6544S		6544	

Foundation Summary Table **

Location Ident.	Avg. N Blow/ft.	No. Each	Drill Shaft *** Length (feet)
ABE ST AT HARRIS AVE			48-A
TS3	10	1	22
BRYANT BLVD AT JACKSON ST			
TS2	10	1	22
TS4	10	1	22
Total Drill Shaft Length			66

Notes


- ** Foundations may be listed separately or grouped according to similarity of location and type. Quantities are for the Contractor's information only.
- *** Decimal lengths in Design Table are to allow interpolation for other penetrometer values. Round to nearest foot for entry into Summary Table.

Abbreviations

- Lf= Fixed Arm Length
- Lc= Clamp-on Arm Length (44' Max.)

Shipping Parts List						
Traffic Signal Arms (Fixed Mount) (1 per pole) Ship each arm with listed equipment attached						
Nominal Arm Length	Type IV Arm (4 Signals) 3 Bracket Assembly and 4 CGB Connectors	Luminaire Arms (1 per 30' pole)				
ft.	Designation	Quantity	Nominal Arm Length	Quantity		
50	50IV		8' Arm	1		
55	55IV		ILSN Arm (Max. 2 per pole) Ship with clamps, bolts and washers			
60	60IV	3	Nominal Arm Length	Quantity		
65	65IV		7' Arm			
			9' Arm			
Traffic Signal Arms (80 MPH Clamp-On Mount) (1 per pole) Ship each arm with listed equipment attached						
Nominal Arm Length	Type I Arm (1 Signal) 2 CGB connector and 1 clamp w/bolts and washers	Type II Arm (2 Signals) 1 Bracket Assembly and 3 CGB connectors, and 1 clamp w/bolts and washers	Type III Arm (3 Signals) 2 Bracket Assembly and 4 CGB connectors, and 1 clamp w/bolts and washers			
ft.	Designation	Quantity	Designation	Quantity	Designation	Quantity
20	20I-80					
24	24I-80		24II-80			
28	28I-80		28II-80			
32			32II-80		32III-80	
36			36II-80		36III-80	
40					40III-80	
44					44III-80	
Traffic Signal Arms (100 MPH Clamp-On Mount) (1 per pole) Ship each arm with listed equipment attached						
Nominal Arm Length	Type I Arm (1 Signal) 2 CGB connector and 1 clamp w/bolts and washers	Type II Arm (2 Signals) 1 Bracket Assembly and 3 CGB connectors, and 1 clamp	Type III Arm (3 Signals) 2 Bracket Assembly and 4 CGB connectors, and 1 clamp			
ft.	Designation	Quantity	Designation	Quantity	Designation	Quantity
20	20I-100					
24	24I-100		24II-100			
28	28I-100		28II-100			
32			32II-100		32III-100	
36			36II-100		36III-100	
40					40III-100	
44					44III-100	
Anchor Bolt Assemblies (1 per pole) Each anchor bolt assembly consists of the following: Top and bottom templates, 4 anchor bolts, 8 nuts, 8 flat washers and 4 nut anchor devices (type 2) per Standard Drawing "TS-FD". Templates may be removed for shipment.						
Anchor Bolt Diameter	Anchor Bolt Length	Quantity				
2 1/2 "	5' - 3"	3				

DATE:
FILE:



**LONG MAST
ARM ASSEMBLY
PARTS LIST**

LMA (5) - 12

Sheet 5 of 5


© TxDOT November 2000

DN: JK	CK: GRB	DW: FDN	CK: CAL
CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 94	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

ARM SIZE		A	B	C	D	E	CONN. BOLT DIA
D ₁	Φ	in.	in.	in.	in.	in.	in.
6.5	.179	12	9	9	6	1 3/4	1
7.5	.179	13	9	10	6	1 3/4	1
8.0	.179	14	10	11	7	2	1 1/4
9.0	.179	16	11	13	8	2	1 1/4
9.5	.179	17	12	14	9	2	1 1/4
9.5	.239	18	12	15	9	2	1 1/4
10.0	.239	18	12	15	9	2	1 1/4
10.5	.239	18	13	15	10	3	1 1/2
11.0	.239	18	13	15	10	3	1 1/2




FIXED MOUNT DETAIL 1

ARM SIZE		A	F	CONN. BOLTS		PIN BOLTS	
D ₁	Φ	in.	in.	No.	Dia	No.	Dia
6.5	.179	12	6	4	1	2	5/8
7.5	.179	14	8	4	1	2	5/8
8.0	.179	14	8	4	1	2	5/8
9.0	.179	16	10	4	1	2	5/8
9.5	.179	18	12	4	1 1/4	3	5/8
9.5	.239	18	12	4	1 1/4	3	5/8
10.0	.239	18	12	4	1 1/4	3	5/8




CLAMP-ON DETAIL 1

ARM SIZE		A	B	C	D	E	CONN. BOLT DIA
D ₁	Φ	in.	in.	in.	in.	in.	in.
7.0	.179	11	11	8	8	1 3/4	1 1/4
7.5	.179	11	11	8	8	1 3/4	1 1/4
8.0	.179	11	11	8	8	2	1 1/4
9.0	.179	13	13	10	10	2	1 1/4
10.0	.179	13	13	10	10	2	1 1/4
9.5	.239	13	13	10	10	2	1 1/4
10.0	.239	14	14	11	11	2	1 1/2
11.0	.239	14	14	11	11	3	1 1/2
11.5	.239	14	14	11	11	3	1 1/2




FIXED MOUNT DETAIL 2

ARM SIZE		A	F	T	CONN. BOLTS		PIN BOLTS	
D ₁	Φ	in.	in.	in.	No.	Dia	No.	Dia
7.0	.179	12	6	3/4	4	3/4	2	5/8
7.5	.179	14	8	3/4	4	3/4	2	5/8
8.0	.179	14	8	3/4	4	3/4	2	5/8
9.0	.179	16	10	7/8	4	1	2	5/8
10.0	.179	18	10	7/8	4	1	2	5/8
9.5	.239	18	10	1	6	1	3	5/8
10.0	.239	18	10	1	6	1	3	5/8




CLAMP-ON DETAIL 2



DETAIL A

DETAIL B




FIXED MOUNT ARM

CLAMP-ON ARM

ARM BASE WELD DETAILS

ARM SIZE		A	F	CONN. BOLTS		PIN BOLTS	
D ₁	Φ	in.	in.	No.	Dia	No.	Dia
6.5	.179	12	6	4	1	2	5/8
7.5	.179	14	8	4	1	2	5/8
8.0	.179	14	8	4	1	2	5/8
9.0	.179	16	10	4	1	2	5/8
9.5	.179	18	12	6	1	3	5/8
9.5	.239	18	12	6	1	3	5/8
10.0	.239	18	12	6	1	3	5/8



CLAMP-ON DETAIL 3

MATERIALS	
Round Shafts or Polygonal Shafts ^①	ASTM A595 Gr. A, A588, A1008 HSLAS Gr. 50 Class 2, A1011 HSLAS Gr. 50 Class 2, A572 Gr. 50 or A1011 SS Gr. 50 ^②
Plates ^①	ASTM A36, A588, or A572 Gr. 50
Connection Bolts	ASTM A325 or A449, except where noted
Pin Bolts	ASTM A325
Pipe ^①	ASTM A53 Gr. B, A501, A1008 HSLAS-F Gr. 50, A1011 HSLAS-F Gr. 50
Misc. Hardware	Galvanized steel or stainless steel or as noted

- ① ASTM A572, A1008 HSLAS, A1011 HSLAS, A1008 HSLAS-F, A1011 HSLAS-F or A1011 SS may have higher yield strengths but shall not have less elongation than the grade indicated.
- ② ASTM A1011 SS Gr. 50 material shall also have a minimum elongation of 18 percent in 8 inches or 23 percent in 2 inches. Material thickness in excess of those stipulated under A1011 SS will be acceptable providing the material meets all other A1011 SS requirements and the requirements of this item.

GENERAL NOTES:

Clamp-on details are used for the second arm on dual mast arm assemblies. A Maximum 1 1/2 inch wide vertical slotted hole shall be cut in the front clamp plate to facilitate drainage during galvanizing. The slot shall be centered behind the arm and shall be no longer than the arm diameter minus 1 inch.

Fixed mount details are used for single mast arm assemblies and for the first arm on dual mast arm assemblies.

Where duplicate parts occur on a detail, welds shown for one part shall apply to all similar parts on the detail.

Pin bolts are required to prevent rotation of clamp-on arms under design wind forces.

NOTE:


Pin bolts shall be A325 with threads excluded from the shear plane. Pin bolt and 3/4 inch dia pipe shall have 3/16 inch dia holes for a 1/8 inch dia galvanized cotter pin. Back clamp plate shall be furnished with a 3/4 inch dia hole for each pin bolt. An 1/16 inch dia hole for the pole after arm orientations have been approved by the Engineer.

Texas Department of Transportation
Traffic Operations Division


**STANDARD ASSEMBLY
FOR TRAFFIC SIGNAL
SUPPORT STRUCTURES
MAST ARM CONNECTIONS
MA-C-12**

© TxDOT August 1995	DN: MS	CK: JSY	DW: MMF	CK: JSY
5-96 5-09 1-12	REVISIONS	CONT	SECT	JOB
		0069	07	116, ETC.
		DIST	COUNTY	SHEET NO.
		SJT	TOM GREEN	95


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




DETAIL A
(for pole with luminaire)




POLE COUPLING DETAIL




DETAIL G




SECTION X-X




DETAIL J




DETAIL B
(If ILSN applied)




DETAIL C




SECTION Y-Y




COPPER GROUND CONNECTOR




ACCESS COMPARTMENT




DETAIL D
(for 30' pole with luminaire and ILSN sign)




DETAIL E
(for 24' pole with ILSN sign and no luminaire)



DETAIL F
(for 19' pole with no ILSN sign and no luminaire)




SECTION V-V




POLE ELEVATION

Anchor Bolt Diameter	Bolt Hole Diameter	Slot Length	Bolt Circle Diameter	Base R Dim. L x T	Adjust. Range
1 1/2"	1 3/4"	3 1/2"	17"	18" x 1 1/2"	13.4°
1 3/4"	2"	4"	19"	20" x 1 3/4"	13.5°
2"	2 1/4"	4 1/2"	21"	22" x 2"	13.6°
2 1/4"	2 1/2"	5"	23"	24" x 2 1/4"	13.7°



DETAIL H



BASE PLATE PLAN

- ① 85% Min. penetration
- ② 60% Min. penetration
100% penetration within 6" of circumferential base welds.

NOTES:

1. The cover shall be one piece formed from ABS plastic, shall be a pearl gray color, and shall be suitable for exposure to harsh sunlight and extreme weather. Cover shall latch with two screw latches and shall fit tightly to the enclosure ring to create a rainproof seal. Latch screws shall be 1/4-20 stainless flat socket head screws with tamper proof feature.
2. The pole manufacturer shall provide with each pole a separate kit consisting of: one cover with two latching assemblies, two terminal strips (Marathon #985GP12CU or approved equal), four #8-32 x 1 1/4" self tapping type "F" stainless steel pan head screws, and one ground connector (Blackburn TTC, Burndy KC22J12T13, or Ilco SSS-5). The traffic signal contractor shall install the kit items in the field.
3. The screw hole spacing on the enclosure back plate shall be for two Marathon #985GP12 terminal strips, one Marathon #985GP06CU terminal strip, and one Bussmann #BM6032B fuse block.
4. Install one Bussmann #BM6032B, Littelfuse #L60030M-2C, or Ferraz-Shawmut #30352 fuse block for poles where luminaires are to be installed.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC SIGNAL SUPPORT STRUCTURES MAST ARM POLE DETAILS


MA-D-12

© TxDOT August 1995		DN: MS	CK: JSY	DW: FDN	CK: CAL
REVISIONS		CONT	SECT	JOB	HIGHWAY
		0069	07	116, ETC.	US 87
		DIST	COUNTY	SHEET NO.	
		SJT	TOM GREEN	96	


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




PLAN




ELEVATION

DAMPING PLATE MOUNTING DETAILS
(Showing alternate placement of signal head)



SECTION A-A

(Showing standard placement of signal head)
(Mounting clamp U-bolt is not shown for clarity)



SECTION A-A


(Showing alternate placement of signal head)
(Mounting clamp U-bolt is not shown for clarity)

① Recommended supporting assemblies to achieve required height for horizontal section heads

Height required	One nipple each length	Two nipples each length plus One coupling each length	
6"-6 3/4"	3"	-	-
7"-8 1/2"	4"	-	-
9"-10 1/2"	6"	-	-
11"-15 1/2"	-	4"	5"
16"-24"	-	6"	10"

GENERAL NOTES:

- In accordance with the findings of TxDOT sponsored research, the installation of a damping plate in accordance with the details shown here at the end of signal mast arms of SMA and DMA standard structures reduces excessive harmonic vertical vibration, and thus fatigue damage. Any deviation from these details may reduce the effectiveness of this damping device.
- Aluminum sign blank for damping plate will conform to Departmental Material Specifications DMS-7110. Materials for mast arm mounting clamp and tube saddle will be aluminum castings or aluminum alloys as in accordance with manufacturers' stipulations. Mounting pipe, pipe nipple and coupling will be aluminum alloy 6061-T6 or 6063-T6. Damping plate mounting clamp and U-bolt assemblies will conform to Standard sheet SMD(GEN). U-bolts for saddle mounting will have a minimum yield strength of 36 ksi.
- Damping plate will be mounted horizontally. Position centerline of damping plate to align with centerline of mast arm or horizontal signal head assembly. Vertical clearance between signal head (with or without backing plate) and bottom of damping plate will be maintained as shown. The attachments shown here are examples only, other supporting details which meet both alignment and vertical clearance requirements are also acceptable.
- Unless stipulated by the manufacturers, all steel parts will be galvanized finish in accordance with Standard Specification Item 445, "Galvanizing".
- Contractor will verify applicable field dimensions before the installation.
- Backplates are optional for traffic signals. When backplates are used, Backplates will have a 2-inch fluorescent yellow AASHTO Type B_{FL} or C_{FL} retroreflective border conforming to TxDOT DMS-8300 "Sign Face Materials." See Sheet TS-BP-20 for backplate details.



SECTION B-B

(Showing damping plate attachment)

Texas Department of Transportation
Traffic Safety Division Standard


MAST ARM DAMPING PLATE DETAILS

MA-DPD-20


FILE: ma-dpd-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
© TxDOT January 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
6-20	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	97	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:



8-FOOT LUMINAIRE ARM



10-FOOT LUMINAIRE ARM



DIRECT ATTACHMENT DETAIL

MATERIALS	
Pole or Arm Simplex	ASTM A27 Gr. 65-35 or A148 Gr. 80-50, A576 Gr. 1021 (3), or A36 (Arm only)
Arm Pipes	ASTM A53 Gr. B, A501, A1008 HSLAS-F Gr. 50 (4), or A1011 HSLAS-F Gr. 50 (4)
Arm Strut Plates (2)	ASTM A36, A572 Gr. 50 (4), or A588
Misc.	ASTM designations as noted

- ① Dimensional limits are given to show acceptable variation in design. All of a Fabricator's production of a particular arm length shall have the same dimensions within specified tolerances.
- ② Any of the materials listed for plates may be used where the drawings do not specify a particular ASTM designation.
- ③ A576 must be suitable for forging and also meet minimum tensile strength of 65 ksi, minimum yield of 35 ksi, and elongation in 2 inches of 22 percent.
- ④ ASTM A572, A1008 HSLAS-F, and A1011 HSLAS-F may have higher yield strengths but shall not have less elongation than the grade indicated.

GENERAL NOTES:

Design conforms to 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminares, and Traffic Signals and Interim Revisions thereto. Design Wind Speed equals 90 mph plus a 1.3 gust factor. Arms are designed to support a 60 lb. luminaire having an effective projected area (actual area times drag coefficient) of 1.6 sq. ft.


Materials and fabrication shall be in accordance with Item 686, "Traffic Signal Pole Assemblies (Steel)" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. In the absence of specified Fabricator tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.

Unless otherwise noted, all parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing".

Deviation from the details and dimensions shown herein require submission of shop drawings in accordance with Item 441, "Steel Structures". Alternate designs are not acceptable.


Each pole simplex fitting shall be supplied with 2 ASTM A325 bolts and 2 lock washers of the size specified. The bolts and lock washers shall be secured to the pole with the other hardware items called for in the plans. When clamp attachment is specified, the Fabricator shall ship the clamp assembly securely attached to the pole at the location shown on the plans.

If clamp assemblies are ordered without poles, the Fabricator shall ship one upper and one lower clamp assembly together in a single package, including all nuts and washers required for the clamps and simplex fittings.




CLAMP ATTACHMENT DETAIL NO. 1 (HALF SECTION)

CLAMP ATTACHMENT DETAIL NO. 2 (HALF SECTION)




UPPER SIMPLEX FITTING

UPPER SIMPLEX FITTING




POLE SIMPLEX DETAIL




CLAMP ATTACHMENT DETAIL NO. 3 (HALF SECTION)

CLAMP ATTACHMENT DETAIL NO. 4 (HALF SECTION)



LOWER SIMPLEX FITTING

LOWER SIMPLEX FITTING



ARM SIMPLEX DETAIL

SECTION A-A


SECTION B-B

Texas Department of Transportation
Traffic Operations Division
STANDARD ASSEMBLY DRAWINGS FOR LUMINAIRE SUPPORT STRUCTURES
ARM DETAILS
LUM-A-12


© TxDOT August 1995	DN: LEH	CK: JSY	DW: LTT	CK: TEB
5-96	REVISIONS	CONT	SECT	HIGHWAY
1-99		0069	07	116, ETC.
1-12		DIST	COUNTY	SHEET NO.
		SJT	TOM GREEN	98

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:



POLE SIMPLEX DETAILS



CLAMP DETAIL



PROJECTION

For 8.9 - 12 inch diameter Signal Poles
(Two req'd for each mast arm)

OTHER MATERIALS:

1. Pole simplex shall be ASTM A27 GR65-35 or A148 GR80-50 or A576 GR1021. ASTM A576 must be suitable for forging and also meet minimum tensile of 65ksi, minimum yield of 35ksi, and a minimum elongation of 22 percent in 2 inches.
2. Welded tabs and backplates shall be ASTM A-36 steel or better.
3. Nylon insert locknuts shall conform to ASTM A563.

GENERAL NOTES:

1. Materials and fabrication shall be in accordance with Standard Sheet "MA-C" and with the details, dimensions, and weld procedures shown herein. Weld references call for preapproved weld procedures which the Fabricator must obtain prior to fabrication. In the absence of specified fabrication tolerances, dimensions shall be within the tolerances generally obtainable in normal fabrication practice.
2. All parts shall be galvanized after fabrication in accordance with Item 445, "Galvanizing". The throat of the Simplex shall be made free of all rough or sharp edges resulting from the galvanizing process.
3. Each simplex fitting shall be supplied with 2 ASTM A325 bolts, 1/2 in. X 1 1/2 in. and 2 lock washers. The bolts and lock washers shall be secured to the clamp with the other hardware items. The Fabricator shall ship clamp assembly together in a single package, including all bolts, nuts, and washers required for the clamp and simplex fitting.
4. Design conforms to 1994 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals" and interim revisions thereto. Design Wind Speed equals 80 mph plus a 1.3 gust factor. Clamps are designed to support a 60 lb. luminaire having an effective projected area (actual area times drag coefficient) of 1.6 sq.ft., 12 ft. maximum arm length.
5. Each assembly shall consist of one upper piece simplex fitting having a smooth lip and one lower piece simplex fitting with the lip removed.
6. Approximately 2 in. diameter hole in upper mast arm clamp.

Texas Department of Transportation
Traffic Operations Division

CLAMP ON
FITTING ASSEMBLY FOR
LUMINAIRE MAST ARM

CFA-12

© TxDOT	DN: KAB	CK: RES	DW: FDN	CK: CAL
11-99 1-12	REVISIONS	CONT	SECT	JOB
		0069	07	116, ETC.
		DIST	COUNTY	SHEET NO.
		SJT	TOM GREEN	99

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

APPLICABLE STANDARDS SHEETS

OVERHEAD SIGN BRIDGE STANDARDS:

- OSB-SE
- OSB-Z#
- OSB-Z#1
- HOSB-Z#
- HOSB-Z1L
- HOSB-Z#1
- OSBT
- OSBC
- OSBC-SC-Z#
- OSBS-SC
- OSB-FD
- OSB-FD-SC

CANTILEVER OVERHEAD SIGN SUPPORT STANDARDS:

- COSS-SE
- COSS-Z#-10
- HCOSS-Z#-10
- COSS-Z21-10
- COSS-Z#&Z#1-10
- COSSD
- COSSF
- COSS-FD

Note: # = Wind Zone number 1, 2, 3 or 4

HIGH MAST ILLUMINATION POLE STANDARDS:


- HMIP-98
- HMIF-98

WALKWAYS AND BRACKETS STANDARDS:

- SWW
- SB(SWL-1)

TRAFFIC SIGNAL POLE STANDARDS:

- SP-80
- SP-100
- SMA-80
- SMA-100
- DMA-80
- DMA-100
- MA-C
- MAC (ILSN)
- MAD-D
- TS-FD
- LUM-A
- CFA
- LMA
- TS-C
- MA-DPD



NOTE: Structures north of ice line to be designed for ice.

LEGEND

- ZONE 1 - [diagonal lines] = (100 MPH WIND)
- ZONE 2 - [diagonal lines] = (90 MPH WIND)
- ZONE 3 - [white box] = (80 MPH WIND)
- ZONE 4 - [diagonal lines] = (70 MPH WIND)
- [dashed line with circles] = (ICE LINE)
- [solid black line] = (DISTRICT LINES)

WIND VELOCITY & ICE ZONES FOR APPLICABLE OVERHEAD SIGN SUPPORTS, HIGH MAST POLES, AND TRAFFIC SIGNAL POLES


Based on 50 Year Mean Recurrence Interval of Fastest Mile Wind Velocity at 33 feet height.

THIS SHEET TO BE INCLUDED IN ALL P.S.&E. PACKAGES CONTAINING ONE OR MORE OF THE APPLICABLE STANDARD SHEETS LISTED HEREON

FOR HARRIS CO. ONLY
Zone line is just North of US 90, around on the North, West and South sides of IH 610 and down the West side of SH 288.


FOR JACKSON CO. ONLY
Zone line is just North of SH 616.

		Traffic Operations Division Standard	
<h2>WIND VELOCITY AND ICE ZONES</h2> <h3>WV & IZ-14</h3>			
FILE:	windice.dgn	DN: TxDOT	CK: TxDOT
© TxDOT	April 1996	CONT: 0069	SECT: 07
REVISIONS:		JOB: 116, ETC.	HIGHWAY: US 87
8-14-Added list of applicable standards, restricting use to structures designed for Fastest Mile wind speeds.		DIST: COUNTY	SHEET NO.
		SJT	TOM GREEN 100



LED COUNTDOWN PEDESTRIAN HEAD DETAILS


Pedestrian signal heads shall be equipped with eggcrate visors and shall comply with material specifications T0-7062 and T0-7063. Both symbolic pedestrian signal indications shall be solid. Outlined indications are not acceptable.




PEDESTRIAN SIGNAL HEAD MOUNTING FOR ONE PEDESTRIAN SIGNAL HEAD

The pole on this drawing is shown as an example only. Poles of similar design for any cross section which meets the specifications shown on these drawings and are approved by the Engineer will be deemed acceptable.

- GENERAL NOTES**
1. Mount pedestrian signal heads with Type 1 clamps and appropriate tubing.
 2. Install pole mounted pedestrian heads on the away-from-traffic side of the pedestal or mast arm pole.
 3. Totally enclose wiring for pedestrian signals within the signal mounting hardware.
 4. All pedestrian signal heads and pushbutton signs shall display the symbolized messages shown.




PUSHBUTTON LOCATION AREA




PEDESTAL POLE

Tactile arrows shall be located on the pushbutton and shall be aligned parallel to the direction of travel on the associated crosswalk (refer to TMUTCD Section 4E.12, P01).




TYPE 1 CLAMP

Clam shell mounting hardware may be used instead of mounting hardware shown above, as approved by the Engineer. These shall be ICC P/N 4805 or McCain Quickmount, or approved equal.




TYPE 2 CLAMP KIT


Furnish and install Type 2 clamp kit when rotation about the horizontal and vertical axes is required.




Use one clamp on signs less than or equal to 10 ft. long. Use two clamps on signs greater than 10 ft. long.



SIGN ATTACHMENT FOR MAST ARMS



PEDESTRIAN SIGNAL HEAD MOUNTING FOR TWO PEDESTRIAN SIGNAL HEADS



SIGN DETAILS



Texas Department of Transportation San Angelo District

TRAFFIC SIGNAL DETAILS


SHEET 1 OF 1 NOT TO SCALE

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	101	


11-19

GENERAL NOTES


1. Install video detection processors inside the controller cabinet.
2. Aim camera so that the horizon is not visible in the field of view.
3. Ensure cable entry and exit points in the mast arms are water tight.
4. Mount a 10-amp single pole (1P) breaker for the VIVDS cameras on a panel installed inside the controller cabinet. Blade-type fuses are not allowed.




**VIVDS CAMERA INSTALLATION
FRONT ELEVATION**




**VIVDS CAMERA INSTALLATION
SIDE VIEW**




**VIVDS/RADAR DETECTION CAMERA INSTALLATION
FRONT ELEVATION**



**VIVDS/RADAR DETECTION CAMERA INSTALLATION
SIDE VIEW**



TYPICAL CAMERA LANE PLACEMENT DETAIL




TYPICAL CAMERA LEFT TURN LANE PLACEMENT DETAIL




		San Angelo District	
<h2>VIVDS CAMERA DETAILS</h2>			
SHEET 1 OF 1		NOT TO SCALE	
©TxDOT 2024 SHEET ISSUED OR LAST REVISED 11-19	CONT 0069	SECT 07	JOB 116, ETC. COUNTY TOM GREEN
			HIGHWAY US 87 SHEET NO. 102

DATE: 5/28/2024 1:28:15 PM
 FILE: c:\pwworking\infreese-pw.bentley.com_freese-pw-01\dms38161\td10240091\hf_sdet34.dgn




TYPICAL MAST ARM INSTALLATION

BACKPLATES ARE NOT SHOWN FOR CLARITY




ANCHOR BOLT PATTERN




CONTROLLER MOUNT NOTES :
 ALL WIRING TERMINATING IN THE CONTROLLER SHALL BE LABELED IN A MANNER THAT CAN BE IDENTIFIED WHEN THE CONTROLLER IS INSTALLED THE CONTRACTOR SHALL CONNECT THE FIELD WIRING TO THE CONTROLLER
 ONE 2" PVC SHALL REMAIN EMPTY FOR FUTURE USE
 CONCRETE SHALL BE TESTED AS MISCELLANEOUS CONCRETE
 ALL MATERIALS SHOWN AND LABOR TO INSTALL THE CONTROLLER FOUNDATION SHALL BE CONSIDERED SUBSIDIARY TO PERTINENT ITEMS
 CONTROLLER FOUNDATION SHALL BE AS SHOWN ON THE PLANS, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

TYPICAL CONTROLLER MOUNT DETAILS




TYPICAL PEDESTAL POLE ASSEMBLY



NOTES:
 SHALL INSTALL CONDUIT ENCASED LOOPS AT THE LOCATIONS SHOWN ON THE PLANS USING 3/4" DIAMETER PVC SCHEDULE 40 OR AT NO ADDITIONAL COST 1" DIAMETER PVC SCHEDULE 80.
 LOOP LOCATIONS MAY BE STAGGERED SLIGHTLY (6") TO ACCOMMODATE HOME RUN PLACEMENT.
 INDIVIDUAL HOME RUN CONDUITS SHALL BE EXTENDED TO THE GROUND BOX SHOWN ON THE PLANS FOR EACH LOOP INSTALLED.
 THE NUMBER OF LOOP WIRE TURNS SHALL BE AS SHOWN ON THE TYPICAL LOOP DETECTOR DETAILS.

CONDUIT ENCASED LOOPS



TYPICAL PED PUSH BUTTON LOCATION

THE ENGINEER SHALL VERIFY ALL PEDESTRIAN SIGNAL AND PEDESTRIAN PUSH BUTTON LOCATIONS PRIOR TO INSTALLATION.

STIMES SPALS
 ACC:
 LEVELS DISPLAYED
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16
 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32
 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48
 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63




6/25/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144


Texas Department of Transportation © 2018			
San Antonio District Standard MISCELLANEOUS TRAFFIC SIGNAL DETAILS			
SCALE: NS			MTS-18
REVISIONS	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	SHEET NO.
FEB 2006			103
OCT 2007		SEE TITLE SHEET	
MAR 2017	STATE	DIST.	COUNTY
MAY 2018	TX	SJT	TOM GREEN
	CONT.	SECT.	JOB
	0069	07	116, ETC.
			HIGHWAY NO.
			US 87

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:





**EDGE LINE AND LANE LINES
ONE-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL TWO-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**





**CENTERLINE AND LANE LINES
FOUR LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**




**TYPICAL MULTI-LANE, TWO-WAY PAVEMENT
MARKINGS THROUGH INTERSECTIONS**



**TWO LANE TWO-WAY ROADWAY
WITH OR WITHOUT SHOULDERS**



YIELD LINES




YIELD LINES

GENERAL NOTES

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




NOTE: Traveled way is exclusive of shoulder widths. Refer to General Note 2 for additional details.

**GUIDE FOR PLACEMENT OF STOP LINES,
EDGE LINE & CENTERLINE**
Based on Traveled Way and Pavement Widths
for Undivided Roadways

NOTES

- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
- Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.



FOUR LANE DIVIDED ROADWAY CROSSOVERS


**TYPICAL STANDARD
PAVEMENT MARKINGS**

PM(1)-22


FILE: pm1-22.dgn	DN: Ckt	DW: Ckt	CK: Ckt
© TxDOT December 2022	CONT	SECT	JOB
0069 07	116, ETC.	US 87	
11-78 8-00 6-20	DIST	COUNTY	SHEET NO.
8-95 3-03 12-22	SJT	TOM GREEN	104
5-00 2-12			

REFLECTIVE RAISED PAVEMENT MARKERS FOR VEHICLE POSITIONING GUIDANCE


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS




**CENTERLINE & LANE LINES
FOR FOUR LANE TWO-WAY ROADWAYS**




DETAIL "A"

DETAIL "B"

DETAIL "C"





CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE




LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised pavement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic.
 See Note 3.



**REFLECTORIZED PROFILE
PATTERN DETAIL**
USING REFLECTIVE PROFILE PAVEMENT MARKINGS




A quick field check for the thickness of base line and profile marking is approximately equal to a stack of 5 quarters to a maximum height of 7 quarters.

NOTES


- Edge lines should typically be 6" wide and the materials shall be specified in the plans.
- Profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I (Top View)



Type II (Top View)



SECTION A

RAISED PAVEMENT MARKERS




**POSITION GUIDANCE USING
RAISED MARKERS
REFLECTORIZED PROFILE
MARKINGS
PM(2) - 22**

FILE: pm2-22.dgn	DWG:	CHK:	DWG:	CHK:
© TxDOT December 2022	CONT:	SECT:	JOB:	HIGHWAY:
REVISIONS	0069	07	116, ETC.	US 87
4-77 8-00 6-20	DIST:	COUNTY:	SHEET NO.	
4-92 2-10 12-22	SJT	TOM GREEN	105	
5-00 2-12				

DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



LANE REDUCTION

NOTES

- Lane reduction pavement markings are used where the number of through lanes is reduced because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane. For Texas Super 2 Passing Lanes, see TS2(PL) standard sheets.
- On divided highways, an additional RIGHT LANE ENDS (W9-1R) sign may be installed in the median aligned with the W9-1R sign on the right side of the highway.
- Lane reduction arrows are required for speeds of 45 mph or greater. An optional third lane reduction arrow may be added based on engineering judgement. If used, the optional third lane reduction arrow should be centered between the first and last lane reduction arrows.
- For lane reductions on Freeways and Expressways, signing shall conform to the TxDOT Freeway Signing Handbook.


ADVANCED WARNING SIGN DISTANCE (D)		
Posted Speed	D (ft)	L (ft)
30 MPH	460	L = WS ² / 60
35 MPH	565	
40 MPH	670	L = WS
45 MPH	775	
50 MPH	885	
55 MPH	990	
60 MPH	1,100	
65 MPH	1,200	
70 MPH	1,250	
75 MPH	1,350	

GENERAL NOTES


- Lane use word and arrow markings shall be used where through lanes approaching an intersection become mandatory turn lanes. Lane use word and arrow markings should be used in auxiliary lanes of substantial length. Lane use arrow markings or word and arrow markings may be used in other lanes and turn bays for emphasis. Details for words and arrows are as shown in the Standard Highway Sign Designs for Texas.
- When lane-use words and arrow markings are used, two sets of arrows should be used if the length of the bay is greater than 180 feet. When a single lane use arrow or word and arrow marking is used for a short turn lane, it should be located at or near the upstream end of the full-width turn lane.
- Use raised pavement marker Type I-C with undivided highways, flush medians and two way left turn lanes. Use raised pavement marker Type II-C-R with divided highways and raised medians.
- Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer. See Chapter 3 of the Roadway Design Manual for additional information on turning lanes or storage lengths.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240


All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




TYPICAL TRANSITION FOR TWLTL AND DIVIDED HIGHWAY




TYPICAL TWLTL AT ONE-WAY STREET AND RIGHT TURN AUXILIARY LANE



TYPICAL TWO-LANE ROADWAY INTERSECTION WITH LEFT TURN BAYS



TYPICAL TWLTL AT TWO-WAY CROSS STREET AND RIGHT TURN LANE DROP



DETAIL A

DETAIL B


* 2" minimum allowed for restripe projects when approved by the Engineer.

Texas Department of Transportation Traffic Safety Division Standard

TWO-WAY LEFT TURN LANES, RURAL LEFT TURN BAYS, AND LANE REDUCTION PAVEMENT MARKINGS PM(3) - 22

FILE: pm3-22.dgn	DWG: CK1	DWG: DW2	CK1
© TxDOT December 2022	CONT: 0069	SECT: 07	JOB: 116, ETC.
4-98 3-03 6-20	DIST: SJT	COUNTY: TOM GREEN	US 87
5-00 2-10 12-22			SHEET NO. 106
8-00 2-12			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




HIGH-VISIBILITY LONGITUDINAL CROSSWALK AT CONTROLLED APPROACH

GENERAL NOTES

1. Longitudinal crosswalk lines should not be placed in the wheel path of vehicles. Center the crosswalk lines on travel lanes, lane lines, and shoulder lines (if present).
2. A minimum 6" clear distance shall be provided to the curb face. If the last crosswalk line falls into this distance it must be omitted.
3. For divided roadways, adjustments in spacing of the crosswalk lines should be made in the median so that the crosswalk lines are maintained in their proper location across the travel portion of the roadway.
4. At skewed crosswalks, the crosswalk lines are to remain parallel to the lane lines.
5. Each crosswalk shall be a minimum of 6' wide.
6. The High-Visibility Longitudinal Crosswalk is the preferred crosswalk pattern on State Highways. Other crosswalk patterns as shown in the "Texas Manual on Uniform Traffic Control Devices" may be used. All crosswalk designs and dimension shall comply with the "Texas Manual on Uniform Traffic Control Devices."
7. Final placement of Stop Bar and Crosswalk shall be approved by the Engineer in the field.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



UNSIGNALIZED MIDBLOCK HIGH-VISIBILITY LONGITUDINAL CROSSWALK

NOTES:

1. Use stop bars with Stop Here For Pedestrians (R1-5b) signs at unsignalized midblock crosswalks.
2. Use stop bars with STOP HERE ON RED (R10-6 or R10-6a) signs at midblock crosswalks controlled by traffic signals or pedestrian hybrid beacons.


Texas Department of Transportation Traffic Safety Division Standard

CROSSWALK PAVEMENT MARKINGS


PM(4) - 22A

FILE#	pm4-22a.dgn	DN#	CK#	DW#	CK#
© TxDOT	December 2022	CONT	SECT	JOB	HIGHWAY
REVISIONS		0069	07	116, ETC.	US 87
6-20		DIST	COUNTY	SHEET NO.	
6-22		SJT	TOM GREEN	107	
12-22					

DATE: FILE:




DETAILS FOR
TYPICAL INTERSECTION
WITH PERPENDICULAR CROSSWALK




DETAIL A

The Engineer will approve final placement of stop bar and crosswalk.




DETAILS FOR
TYPICAL INTERSECTION
WITH SKEWED CROSSWALK




DETAIL C


PROJECT QUANTITIES OF WORDS AND ARROWS						
ONLY	STOP	AHEAD	↶	↷	↕	⌘
8	0	0	8	0	0	0
↕↕	↶↷	↶↷	↶↷	↶↷	↶↷	↶↷
0	0	0	0	0	0	0



DETAILS FOR
TYPICAL INTERSECTION
WITH "CAT TRACKS"



DETAIL B



DETAILS FOR
TYPICAL INTERSECTION
WITH UNCURBED
CHANNELIZING ISLAND



6/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144



PAVEMENT MARKING
DETAILS (URBAN)

SHEET 1 OF 1		NOT TO SCALE	
©TxDOT 2024	CONT	SECT	JOB
SHEET ISSUED OR LAST REVISED	0069	07	116, ETC.
09-20	DIST	COUNTY	SHEET NO.
	SJT	TOM GREEN	108

DATE: 6/28/2024 3:23:26 PM
FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091hg_sdet06.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SIGN SUPPORT DESCRIPTIVE CODES

(Descriptive Codes correspond to project estimate and quantities sheets)

SM RD SGN ASSM TY XXXXX(X)XX(X-XXXX)

Post Type

- FRP = Fiberglass Reinforced Plastic Pipe (see SMD(FRP))
- TWT = Thin-Walled Tubing (see SMD(TWT))
- 10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3))
- S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2)

Anchor Type

- UA = Universal Anchor - Concreted (see SMD(FRP) and (TWT))
- UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))
- WS = Wedge Anchor Steel - (see SMD(TWT))
- WP = Wedge Anchor Plastic (see SMD(TWT))
- SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3))
- SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))


Sign Mounting Designation

- P = Prefab, "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP))
- T = Prefab, "T" (see SMD(SLIP-1) to (SLIP-3), (TWT))
- U = Prefab, "U" (see SMD(SLIP-1) to (SLIP-3))

IF REQUIRED

- 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT))
- BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))
- WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3))
- EXAL = Extruded Aluminum Sign Panels (see SMD(SLIP-3))


REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).


SIGN LOCATION

PAVED SHOULDERS



LESS THAN 6 FT. WIDE


When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.



GREATER THAN 6 FT. WIDE


When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft. from the edge of the shoulder.

T-INTERSECTION




When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roadway. Place as close to ROW as practical.

No more than 2 sign posts should be located within a 7 ft. circle.




BEHIND BARRIER




BEHIND GUARDRAIL

**Sign clearance based on distance required for proper guard rail or concrete barrier performance.



BEHIND CONCRETE BARRIER



* Signs shall be mounted using the following condition that results in the greatest sign elevation:


- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is:
<http://www.txdot.gov/publications/traffic.htm>

TYPICAL SIGN ATTACHMENT DETAIL




Bolts used to mount sign panels to the clamp are 5/16-18 UNC galvanized square head with nut, nylon washer, flat washer and lock washer. The bolt length is 1 inch for aluminum.

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex head per ASTM A307 with nut and helical-spring lock washer. The approximate bolt lengths for various post sizes and sign clamp types are given in the table at right. The bolt length may need to be adjusted depending upon field conditions.

Sign clamps may be either the specific size clamp or the universal clamp.


Pipe Diameter	Approximate Bolt Length	
	Specific Clamp	Universal Clamp
2" nominal	3"	3 or 3 1/2"
2 1/2" nominal	3 or 3 1/2"	3 1/2 or 4"
3" nominal	3 1/2 or 4"	4 1/2"

SIGNS WITH PLAQUES




When a supplemental plaque or secondary sign is used, the 7 ft sign height is measured to the bottom of the supplemental plaque or secondary sign.

CURB & GUTTER OR RAISED ISLAND



RESTRICTED RIGHT-OF-WAY (When 6 ft min. is not possible.)



Right-of-way restrictions may be created by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme slope.

Texas Department of Transportation
 Traffic Operations Division


SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD(GEN)-08

© TxDOT July 2002	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT. SECT.	JOB	HIGHWAY
		0069 07	116, ETC.	US 87
		DIST.	COUNTY	SHEET NO.
		SJT	TOM GREEN	109

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer_list.htm
 The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTES:

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- Material used as post with this system shall conform to the following specifications:
 - 10 BWG Tubing (2.875" outside diameter)
 - 0.134" nominal wall thickness
 - Seamless or electric-resistance welded steel tubing or pipe
 - Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008
 - Other steels may be used if they meet the following:
 - 55,000 PSI minimum yield strength
 - 70,000 PSI minimum tensile strength
 - 20% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"
 - Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"
 - Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.
 - Schedule 80 Pipe (2.875" outside diameter)
 - 0.276" nominal wall thickness
 - Steel tubing per ASTM A500 Gr C
 - Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the following:
 - 46,000 PSI minimum yield strength
 - 62,000 PSI minimum tensile strength
 - 21% minimum elongation in 2"
 - Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"
 - Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"
 - Galvanization per ASTM A123
- See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is: <http://www.txdot.gov/publications/traffic.htm>
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE


Foundation

- Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- The triangular slipbase system is multidirectional and is designed to release when struck from any direction.

Support

- Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and straight.
- Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.

CONCRETE ANCHOR



SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxyes and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

Texas Department of Transportation
 Traffic Operations Division














SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002		DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0069	07	116, ETC.	US 87
		DIST	COUNTY	SHEET NO.	
		SJT	TOM GREEN	110	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



- GENERAL NOTES:**
1. SIGN SUPPORT # OF POSTS MAX. SIGN AREA

10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF
 2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
 3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
 4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
 5. Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
 6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
 7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
 8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
 9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
 10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
 11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.
 12. Post open ends shall be fitted with Friction Caps.
 13. Sign blanks shall be the sizes and shapes shown on the plans.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-Inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
Warning	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Friction caps may be manufactured from hot rolled or cold rolled steel sheets. The minimum sheet metal thickness shall be 24 gauge for all cap sizes. The rim edges shall be reasonably straight and smooth. Caps shall be sized and formed in such a manner as to produce a drive-on friction fit and have no tendency to rock when seated on the pipe. The depth shall be sufficient to give positive protection against entrance of rainwater. They shall be free of sharp creases or indentations and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM B633 Class FE/ZN 8.













**SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-2)-08**

© TxDOT July 2002		DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
9-08	REVISONS	CONT	SECT	JOB	HIGHWAY
		0069	07	116, ETC.	US 87
		DIST	COUNTY		SHEET NO.
		SJT	TOM GREEN		111

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



GENERAL NOTES:

- | SIGN SUPPORT | # OF POSTS | MAX. SIGN AREA |
|--------------|------------|----------------|
| 10 BWG | 1 | 16 SF |
| 10 BWG | 2 | 32 SF |
| Sch 80 | 1 | 32 SF |
| Sch 80 | 2 | 64 SF |
- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- Signs that require specific supports due to reasons in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of greater height.
- When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- Sign blanks shall be the sizes and shapes shown on the plans.
- Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- Post open ends shall be fitted with Friction Caps.

REQUIRED SUPPORT		
	SIGN DESCRIPTION	SUPPORT
Regulatory	48-Inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-Inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
Warning	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)

Texas Department of Transportation
Traffic Operations Division

SIGN MOUNTING DETAILS
SMALL ROADSIDE SIGNS
TRIANGULAR SLIPBASE SYSTEM
SMD(SLIP-3)-08



© TxDOT July 2002		DW: TxDOT	CK1: TxDOT	DW: TxDOT	CK2: TxDOT
9-08	REVISIONS	CONT	SECT	JOB	HIGHWAY
		0069	07	116, ETC.	US 87
		DIST	COUNTY		SHEET NO.
		SJT	TOM GREEN		112

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REQUIREMENTS FOR INDEPENDENT MOUNTED ROUTE SIGNS



SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE A SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & BORDERS	ALL OTHERS	TYPE B or C SHEETING



TYPICAL EXAMPLES

REQUIREMENTS FOR BLUE, BROWN & GREEN D AND I SERIES GUIDE SIGNS

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	ALL	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE D SHEETING
LEGEND, SYMBOLS & BORDERS	ALL OTHERS	TYPE B OR C SHEETING



TYPICAL EXAMPLES

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- White legend shall use the Clearview Alphabet. The following Clearview fonts shall be used to replace the existing white Federal Highway Administration (FHWA) Standard Highway Alphabets, when not specified in the SHSD, or in the plans.

B	CV-1W
C	CV-2W
D	CV-3W
E	CV-4W
Emod	CV-5WR
F	CV-6W

- Route sign legend (ie. IH, US, SH and FM shields) shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Independent mounted route sign with white or colored legend and borders shall be applied by screening process with transparent color ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof. White legend, symbols and borders on all other signs shall be cut-out white sheeting applied to colored background sheeting.
- Information regarding borders and radii for signs is found in the "Standard Highway Sign Designs for Texas". Dimensions shown and described for borders and corner radii on parent sign are nominal. Borders may vary in width as much as 1/2 inch. Corner radii above 3 inches may vary in width as much as 1 inch. Borders and corner radii within a parent sign must be of matching widths. The sign area outside the corner radius should be trimmed or rounded.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details of roadside signs are shown in the "SMD series" Standard Plan Sheets.

DEPARTMENTAL MATERIAL SPECIFICATIONS	
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

ALUMINUM SIGN BLANKS THICKNESS	
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website:
<http://www.txdot.gov/>


Texas Department of Transportation		<i>Traffic Operations Division Standard</i>
<h2 style="margin: 0;">TYPICAL SIGN REQUIREMENTS</h2> <h3 style="margin: 0;">TSR(3) - 13</h3>		
FILE: tsr3-13.dgn © TxDOT October 2003 12-03 7-13 9-08	DNR: TxDOT CONT: 0069 SECT: 07 DIST: SJT	CR: TxDOT JOB: 116, ETC. COUNTY: TOM GREEN HIGHWAY: US 87 SHEET NO.: 113

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REQUIREMENTS FOR RED BACKGROUND REGULATORY SIGNS

(STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	WHITE	TYPE B OR C SHEETING
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING
LEGEND	RED	TYPE B OR C SHEETING

REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS


(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND, BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR WARNING SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING

REQUIREMENTS FOR SCHOOL SIGNS



TYPICAL EXAMPLES

SHEETING REQUIREMENTS		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	WHITE	TYPE A SHEETING
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND, BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM
SYMBOLS	RED	TYPE B OR C SHEETING

GENERAL NOTES

- Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tabulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination thereof.
- White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- Sign substrate shall be any material that meets the Departmental Material Specification requirements of DMS-7110 or approved alternative.
- Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BLANKS THICKNESS

Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIFICATIONS

ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

<http://www.txdot.gov/>




TYPICAL SIGN REQUIREMENTS

TSR(4) - 13


FILE:	tsr4-13.dgn	DW:	TxDOT	CHK:	TxDOT	DWG:	TxDOT	CHK:	TxDOT
© TxDOT	October 2003	CONT:	0069	SECT:	07	JOB:	116, ETC.	HIGHWAY:	US 87
REVISIONS		DIST:	SJT	COUNTY:	TOM GREEN	SHEET NO.:	114		
12-03	7-13								
9-08									

GENERAL NOTES


1. Reinforcing steel shall conform to the requirements of Item 440, "Reinforcement for Concrete."
2. Dimensions shown elsewhere in the plans shall supercede dimensions shown on this sheet.




**SMALL SINGLE POST
ROADSIDE SIGN ASSEMBLY
RIPRAP PLAN**



**SMALL DOUBLE POST
ROADSIDE SIGN ASSEMBLY
RIPRAP PLAN**



**SMALL SINGLE POST
ROADSIDE SIGN ASSEMBLY
RIPRAP SECTION**



**SMALL DOUBLE POST
ROADSIDE SIGN ASSEMBLY
RIPRAP SECTION**



		San Angelo District	
CONCRETE RIPRAP FOR SMALL SIGN ASSEMBLIES			
SHEET 1 OF 1		NOT TO SCALE	
©TxDOT 2024 SHEET ISSUED OR LAST REVISED 11-19	CONT 0069	SECT 07	JOB 116, ETC. COUNTY TOM GREEN
		HIGHWAY US 87	SHEET NO. 115


PAY ITEMS

0432 6001 RIPRAP (CONC)(4 IN) _____ CY


DATE: 5/28/2024 1:31:55 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38161\td10240091hh_sdet07.dgn

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




**TYPE I CURB (MONOLITHIC)
2" - 4" HEIGHT**




**TYPE I CURB
2" - 4" HEIGHT**




**TYPE I CURB AND GUTTER
2" - 4" HEIGHT**




**TYPE II CURB (MONOLITHIC)
5" - 5 3/4" HEIGHT**




**TYPE II CURB
5" - 5 3/4" HEIGHT**




**TYPE II CURB AND GUTTER
5" - 5 3/4" HEIGHT**




**TYPE III CURB (KEYED)
2" - 4" HEIGHT**




**TYPE IIa CURB
5" - 5 3/4" HEIGHT**




**TYPE IIa CURB AND GUTTER
5" - 5 3/4" HEIGHT**



**TYPE IV CURB (KEYED)
5" - 5 3/4" HEIGHT**



EXPANSION JOINT DETAIL




CURB TRANSITION

Note: To be paid for as Highest Curb

GENERAL NOTES

1. All materials and construction shall be in accordance with Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
2. Concrete shall be Class A.
3. When reinforcing bars are used, they shall be No.4 unless otherwise shown. The use of fiber reinforced concrete in lieu of reinforcing steel is acceptable. Use fibers meeting the requirements of DMS 4550, "Fibers for Concrete," and dose fibers in accordance with Material Producers List (MPL) "Fibers for Class A and B Concrete Applications."
4. Round exposed sharp edges with a rounding tool, to a minimum radius of 1/4 inch.
5. All existing curbs and driveways to be removed shall be sawed or removed at existing joints.
6. Where concrete curb is to be placed on existing concrete pavement, Bar B may be drilled and grouted in place, or may be inserted into fresh concrete.
7. Expansion and contraction joints shall be constructed to match pavement joints in all curbs and curb and gutter adjacent to jointed concrete pavement. Where placement of curb or curb and gutter is not adjacent to concrete pavement, expansion joints shall be provided at structures, curb returns at streets, and at locations directed by The Engineer.
8. Vertical and horizontal dowel bars and transverse reinforcing bars shall be placed at four feet C-C.
9. Dimension 'T' shown is the thickness of concrete pavement. When curb is installed adjacent to flexible pavement dimension 'T' is 8" maximum.
10. Usual profile grade line. Refer to typical sections and plan-profile sheets for exact locations.
11. One-half inch expansion joint material shall be provided where curb or curb and gutter is adjacent to sidewalk or riprap.
12. When horizontal permissible construction joints are used, the longitudinal pavement steel shall be placed in accordance with pavement details shown elsewhere in the plans. Reinforcing steel for curb section shall then conform to that required for concrete curb.
13. Bar B placement as needed (typically at four ft. C-C) to support curb reinforcing steel during concrete placement.




CURB TRANSITION NOTE:
Field conditions may require a longer or shorter transition, and shall be shown elsewhere in the plans, or as directed by the Engineer.

		Design Division Standard	
CONCRETE CURB AND GUTTER			
CCCG-22			
FILE: cccg21.dgn	DWG: TxDOT	CHK: AN	DWG: CS
© TxDOT: JUNE 2022	CONT: 0069	SECT: 07	JOB: 116, ETC.
REVISIONS			HIGHWAY: US 87
	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 116

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:

TYPE 1




PERPENDICULAR CURB RAMP

TYPE 2




PARALLEL CURB RAMP

TYPE 3




TYPE 6





COMBINATION CURB RAMPS

TYPE 20





CURB RAMPS AT MEDIAN ISLANDS

TYPE 7




DIRECTIONAL RAMPS WITHIN RADIUS

TYPE 10




TYPE 5



BLENDED TRANSITION (FLUSH LANDING)


INSTALL DETECTABLE WARNING SURFACE AT EACH END OF THE CUT-THROUGH RAMP WITH A MINIMUM 2' USUAL SIDEWALK SURFACE BETWEEN. IF MEDIAN IS LESS THAN 6' WIDE, ELIMINATE DETECTABLE WARNING SURFACES.

TYPE 21




NOTE: CURB DETAILS ARE SHOWN ELSEWHERE IN THE PLANS.

TYPE 22



COMBINATION ISLAND RAMPS

BOTTOM GRADE BREAK OF CURB RAMP WILL NORMALLY BE AT GUTTER LINE. SURFACE SLOPES AT GRADE BREAKS SHALL BE FLUSH.



TYPICAL SECTION OF PERPENDICULAR CURB RAMP AT CONNECTION TO ROADWAY

NOTES / LEGEND:

SEE GENERAL NOTES ON SHEET 2 OF 4 FOR MORE INFORMATION.

DENOTES PLANTING OR NON-WALKING SURFACE NOT PART OF PEDESTRIAN CIRCULATION PATH.



GUTTER LINE



DETECTABLE WARNING SURFACE



GRADE BREAK



DENOTES PREFERRED LOCATION OF PEDESTRIAN PUSH BUTTON IF APPLICABLE.



RAMP LIMITS OF PAYMENT



**PEDESTRIAN FACILITIES
CURB RAMPS**

PED-18

FILE: ped18	DW: TxDOT	DW: VP	CK: KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
REVISED 08, 2009	DIST	COUNTY	SHEET NO.	
REVISED 06, 2012	SJT	TOM GREEN	117	
REVISED 01, 2018				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

CURB RAMPS

1. Install a curb ramp or blended transition at each pedestrian street crossing.
2. All slopes shown are maximum allowable. Cross slopes of 1.5% and lesser running should be used. Adjust curb ramp length or grade of approach sidewalks as directed.
3. Maximum allowable cross slope on sidewalk and curb ramp surfaces is 2%.
4. The minimum sidewalk width is 5'. Where the sidewalk is adjacent to the back of curb, a 6' sidewalk width is desirable. Where a 5' sidewalk cannot be provided due to site constraints, sidewalk width may be reduced to 4' for short distances. 5' x 5' passing areas at intervals not to exceed 200' are required.
5. Turning Spaces shall be 5' x 5' minimum. Cross slope shall be maximum 2%.
6. Clear space at the bottom of curb ramps shall be a minimum of 4' x 4' wholly contained within the crosswalk and wholly outside the parallel vehicular travel path.
7. Provide flared sides where the pedestrian circulation path crosses the curb ramp. Flared sides shall be sloped at 10% maximum, measured parallel to the curb. Returned curbs may be used only where pedestrians would not normally walk across the ramp, either because the adjacent surface is planted, substantially obstructed, or otherwise protected.
8. Additional information on curb ramp location, design, light reflective value and texture may be found in the latest draft of the Proposed Guidelines for Pedestrian Facilities in the Public Right of Way (PROWAG) as published by the U.S. Architectural and Transportation Barriers Compliance Board (Access Board).
9. To serve as a pedestrian refuge area, the median should be a minimum of 6' wide, measured from back of curbs. Medians should be designed to provide accessible passage over or through them.
10. Small channelization islands, which do not provide a minimum 5' x 5' landing at the top of curb ramps, shall be cut through level with the surface of the street.
11. Crosswalk dimensions, crosswalk markings and stop bar locations shall be as shown elsewhere in the plans. At intersections where crosswalk markings are not required, curb ramps shall align with theoretical crosswalks unless otherwise directed.
12. Provide curb ramps to connect the pedestrian access route at each pedestrian street crossing. Handrails are not required on curb ramps.
13. Curb ramps and landings shall be constructed and paid for in accordance with Item 531 "Sidewalks".
14. Place concrete at a minimum depth of 5" for ramps, flares and landings, unless otherwise directed.
15. Furnish and install No. 3 reinforcing steel bars at 18" o.c. both ways, unless otherwise directed.
16. Provide a smooth transition where the curb ramps connect to the street.
17. Curbs shown on sheet 1 within the limits of payment are considered part of the curb ramp for payment, whether it is concrete curb, gutter, or combined curb and gutter.
18. Existing features that comply with applicable standards may remain in place unless otherwise shown on the plans.

DETECTABLE WARNING MATERIAL


19. Curb ramps must contain a detectable warning surface that consists of raised truncated domes complying with PROWAG. The surface must contrast visually with adjoining surfaces, including side flares. Furnish and install an approved cast-in-place dark brown or dark red detectable warning surface material adjacent to uncolored concrete, unless specified elsewhere in the plans.
20. Detectable Warning Materials must meet TxDOT Departmental Materials Specification DMS 4350 and be listed on the Material Producer List. Install products in accordance with manufacturer's specifications.
21. Detectable warning surfaces must be firm, stable and slip resistant.
22. Detectable warning surfaces shall be a minimum of 24 inches in depth in the direction of pedestrian travel, and extend the full width of the curb ramp or landing where the pedestrian access route enters the street.
23. Detectable warning surfaces shall be located so that the edge nearest the curb line is at the back of curb and neither end of that edge is greater than 5 feet from the back of curb. Detectable warning surfaces may be curved along the corner radius.
24. Shaded areas on Sheet 1 of 4 indicate the approximate location for the detectable warning surface for each curb ramp type.

DETECTABLE WARNING PAVERS (IF USED)

25. Furnish detectable warning paver units meeting all requirements of ASTM C-936, C-33. Lay in a two by two unit basket weave pattern or as directed.
26. Lay full-size units first followed by closure units consisting of at least 25 percent (25%) of a full unit. Cut detectable warning paver units using a power saw.


SIDEWALKS

27. Provide clear ground space at operable parts, including pedestrian push buttons. Operable parts shall be placed within unobstructed reach range specified in PROWAG section R406.
28. Place traffic signal or illumination poles, ground boxes, controller boxes, signs, drainage facilities and other items so as not to obstruct the pedestrian access route or clear ground space.
29. Street grades and cross slopes shall be as shown elsewhere in the plans.
30. Changes in level greater than 1/4 inch are not permitted.
31. The least possible grade should be used to maximize accessibility. The running slope of sidewalks and crosswalks within the public right of way may follow the grade of the parallel roadway. Where a continuous grade greater than five percent (5%) must be provided, handrails may be desirable to improve accessibility. Handrails may also be needed to protect pedestrians from potentially hazardous conditions. If provided, handrails shall comply with PROWAG R409.
32. Handrail extensions shall not protrude into the usable landing area or into intersecting pedestrian routes.
33. Driveways and turnouts shall be constructed and paid for in accordance with Item "Intersections, Driveways and Turnouts". Sidewalks shall be constructed and paid for in accordance with Item, "Sidewalks".
34. Sidewalk details are shown elsewhere in the plans.




SECTION VIEW DETAIL
CURB RAMP AT DETECTIBLE WARNINGS


DETECTABLE WARNING SURFACE DETAILS



PARALLEL CURB RAMP
TYPICAL PLACEMENT OF DETECTABLE WARNING SURFACE ON LANDING AT STREET EDGE.



PERPENDICULAR CURB RAMP
TYPICAL PLACEMENT OF DETECTABLE WARNING SURFACE ON SLOPING RAMP RUN.



* NOTE:
 BOTH ENDS OF THE
 DETECTABLE WARNING SURFACE
 SHALL BE 5' OR LESS
 FROM BACK OF CURB.

DIRECTIONAL CURB RAMP
TYPICAL PLACEMENT OF DETECTABLE WARNING SURFACE ON SLOPING RAMP RUN.





SHEET 2 OF 4

Texas Department of Transportation		Design Division Standard	
PEDESTRIAN FACILITIES CURB RAMPS			
PED-18			
FILE: ped18	DN: TxDOT	DW: VP	CK: KM
© TxDOT: MARCH, 2002	CONT	SECT	JOB
REVISIONS	0069	07	116, ETC.
REVISOR: 08, 2009	DIST	COUNTY	SHEET NO.
REVISOR: 06, 2012	SJT	TOM GREEN	118
REVISOR: 01, 2018			


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



SIDEWALK TREATMENT AT DRIVEWAYS




NOTES:
 * WHERE DRIVEWAYS CROSS THE PEDESTRIAN ROUTE, SIDES SHALL BE FLARED AT 10% MAX SLOPE.
 * * IF CURB HEIGHT IS GREATER THAN 6 INCHES, USE GRADE LESS THAN OR EQUAL TO 5%. HANDRAIL AND DETECTABLE WARNING ARE NOT REQUIRED.



NOTE: IN PEDESTRIAN CIRCULATION AREA, MAXIMUM 4" PROJECTION FOR POST OR WALL MOUNTED OBJECTS BETWEEN 27" AND 80" ABOVE THE SURFACE.



NOTE: ITEMS NOT INTENDED FOR PUBLIC USE. MINIMUM 4' X 4' CLEAR GROUND SPACE REQUIRED AT PUBLIC USE FIXTURES.




SHEET 3 OF 4

		Design Division Standard	
PEDESTRIAN FACILITIES CURB RAMPS PED-18			
FILE: ped18	DN: TxDOT	DW: VP	CK: KM
© TxDOT: MARCH, 2002	CONT: 0069	SECT: 07	JOB: 116, ETC.
REVISIONS			US 87
REVISED 08, 2005			
REVISED 06, 2012			
REVISED 01, 2018			
	DIST: SJT	COUNTY: TOM GREEN	SHEET NO.: 119


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL CROSSING LAYOUTS
SEE SHEET 1 OF 4 FOR DETAILS AND DIMENSIONS




SKewed INTERSECTION WITH "LARGE" RADIUS





AT INTERSECTION
W/FREE RIGHT TURN & ISLAND



SKewed INTERSECTION WITH "SMALL" RADIUS



MID-BLOCK PLACEMENT
PERPENDICULAR RAMPS



NORMAL INTERSECTION WITH "SMALL" RADIUS

LEGEND:

SHOWS DOWNWARD SLOPE. →

DENOTES PREFERRED LOCATION OF PEDESTRIAN PUSH BUTTON (IF APPLICABLE). ☒

DENOTES PLANTING OR NON-WALKING SURFACE NOT PART OF PEDESTRIAN CIRCULATION PATH. ↙ ↘ ↙ ↘ ↙ ↘

SHEET 4 OF 4



PEDESTRIAN FACILITIES
CURB RAMPS


PED-18

FILE: ped18	DN: TxDOT	DW: VP	CK: KM	CK: PK & JG
© TxDOT: MARCH, 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
REVISED 08, 2009	DIST	COUNTY	SHEET NO.	
REVISED 06, 2012	SJT	TOM GREEN	120	
REVISED 01, 2018				


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




TY A (Shop Splices and Splice Joints only shown on one Type for clarity)




TY C (Shop Splices and Splice Joints only shown on one Type for clarity)

RECOMMENDED USAGE (9) (10)	
Dropoff Height/Condition	Recommended Rail Options
< 30" dropoff	TY A, TY B, TY C, or TY D
≥ 30" dropoff, or along Bike Path	TY E or TY F




SECTION A-A (Showing Handrail TY A) **SECTION B-B** (Showing Handrail TY B)



SECTION C-C (Showing Handrail TY C) **SECTION D-D** (Showing Handrail TY D)

- ① Parallel to ground.
- ② One shop splice per panel is permitted with minimum 85 percent penetration. The weld may be square groove or single vee groove. Grind smooth.
- ③ Shop splice is permitted with minimum 85 percent penetration. The weld may be square groove or single vee groove. Grind smooth.
- ④ See Ramp Details located elsewhere in plans for ramp slope and dimensions. Maximum ramp slope will not exceed 8.3 percent. Level landing required for each 30" rise if grade exceeds 5 percent.
- ⑤ 1 1/2" Dia. Standard Pipe (1.900" O.D., 0.145" wall thickness). Parallel to ramp / sidewalk. Provide holes as needed in 1 1/2" Dia. pipe for galvanizing drainage and venting.
- ⑥ 2 1/2" Dia. Standard Pipe (2.875" O.D., 0.203" wall thickness). See "Post Mount Detail" for crimping and trimming post to fit Dia. of top rail. Provide holes as needed in post for galvanizing drainage and venting. Plumb all posts.
- ⑦ See "Handrail Fabrication Details" for Splice Joints.
- ⑧ 5/8" Dia. Round Bar equal spacing at 4 1/2" Max. Plumb all pickets.
- ⑨ When needed for accessibility (grade > 5 percent) or as needed for pedestrian safety.
- ⑩ Not to be used on bridges.
- ⑪ See "General Notes" for anchor bolt information.

SHEET 1 OF 3








PEDESTRIAN HANDRAIL DETAILS

PRD-13

FILE: prd13.dgn	DNR TxDOT	CK: AM	DWR: JTR	CK: CGL
© TxDOT December 2006	CONT	SECT	JOB	HIGHWAY
REVISIONS	0069	07	116, ETC.	US 87
REVISED MAY, 2013 (VP)	DIST	COUNTY	SHEET NO.	
	SJT	TOM GREEN	121	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



- ① Parallel to ground.
- ② One shop splice per panel is permitted with minimum 85 percent penetration. The weld may be square groove or single vee groove. Grind smooth.
- ③ Shop splice is permitted with minimum 85 percent penetration. The weld may be square groove or single vee groove. Grind smooth.
- ④ See Ramp Details located elsewhere in plans for ramp slope and dimensions. Maximum ramp slope will not exceed 8.3 percent. Level landing required for each 30" rise if grade exceeds 5 percent.
- ⑤ 1 1/2" Dia. Standard Pipe (1.900" O.D., 0.145" wall thickness). Parallel to ramp / sidewalk. Provide holes as needed in 1 1/2" Dia. pipe for galvanizing drainage and venting.
- ⑥ 2 1/2" Dia. Standard Pipe (2.875" O.D., 0.203" wall thickness). See "Post Mount Detail" for crimping and trimming post to fit Dia. of top rail. Provide holes as needed in post for galvanizing drainage and venting. Plumb all posts.
- ⑦ See "Handrail Fabrication Details" for Splice Joints.
- ⑧ 5/8" Dia. Round Bar equal spacing at 4 1/2" Max. Plumb all pickets.
- ⑪ See "General Notes" for anchor bolt information.


SHEET 2 OF 3




**PEDESTRIAN HANDRAIL
DETAILS
PRD-13**

FILE: prd13.dgn	DWG: TxDOT	CHK: AM	DWG: JTR	CHK: CGL
© TxDOT December 2006	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
REVISED MAY, 2013 (VP)	DIST: SJT	COUNTY: TOM GREEN	SHEET NO. 122	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



HANDRAIL FABRICATION DETAILS



PLAN SHOWING RAIL AT RAMP CONDITIONS

GENERAL NOTES

Designed according to ADAAG, Texas Accessibility Standards, Uniform Building Code, and AASHTO LRFD Specifications.

Handrail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.

Pipe will conform to ASTM-A53 Grade B or A500 Grade B. Steel plates and steel bars will conform to ASTM-A36. Mechanical tubing (MT) will conform to ASTM A513 Grade 1015 or higher. Galvanize all steel components except reinforcing steel unless noted otherwise.

Concrete for foundations will be in accordance with Item 531 "Sidewalks". All reinforcing steel must be Grade 60. Bar laps, where required, will be as follows: Uncoated #4 = 1'-5" Epoxy coated #4 = 2'-1"

When the plans require painted steel, follow the requirements for painting galvanized steel in Item 446, "Cleaning and Painting Steel". Sleeve Members will receive galvanization and only get field painted after installation unless directed otherwise by Engineer.

Epoxy Anchor bolts for wall mount and post base plate will be 5/8 inch Dia. ASTM A36 threaded rods with one hex nut and one hardened steel washer at each bolt. 3/8 inch Dia. threaded rod embedment depth for wall mounts is 3 1/2 inches and embedment depth for post base plate is 5 inches.

Embed threaded rods into concrete with a Type III (Class C) epoxy meeting the requirements of DMS-6100, "Epoxyes and Adhesives". Mix and dispense adhesive with the manufacturer's static mixing nozzle/dual cartridge system. Core drill holes (percussion drilling not permitted).

At the contractor's option the post base plate anchor bolts may be cast with the Ramp/Sidewalk (See Cast-in-Place Anchor Bolt Options).

Optional cast-in-place anchor bolts will be 5/8 inch Dia ASTM A307 Grade A bolts (or A36 threaded rods with one tack welded hex nut each) with one hex nut and one hardened steel washer at each bolt. Embedment depth of cast-in-place bolt will be 8 inches for post base plate.

Handrails and any wall or other surface adjacent to them will be free of any sharp or abrasive elements.

Submit shop drawings to the Engineer unless otherwise noted. For curved handrail applications, fabricate the handrail to the curve if radius is less than 600 feet. Shop drawings are required when rail is fabricated to the curve.


For all handrails, erection drawings will be submitted to the Engineer for approval to ensure proper installation.

Drawings will show handrail mount locations with bolts setting, spacing, ramp slope, and/or splice joint locations, and handrail lengths with identification showing where each handrail goes on the layout.


Payment for concrete sidewalks or curb ramps will be paid for in accordance with Item 531 "Sidewalks".

Payment for all items shown is to be included in unit price bid in accordance with Item 450 "Railing" of the type specified.


All exposed edges will be rounded or chamfered to approximately 1/8 inch by grinding.



TYPICAL WALL MOUNT DETAILS




SECTION AT RAIL POST FOUNDATIONS




CAST-IN-PLACE ANCHOR BOLT OPTIONS
(Used for Post Base Plate only)


- (5) 1 1/2" Dia. Standard Pipe (1.900" O.D., 0.145" wall thickness). Parallel to ramp/sidewalk. Provide holes as needed in 1 1/2" Dia. pipe for galvanizing drainage and venting.
- (6) 2 1/2" Dia. Standard Pipe (2.875" O.D., 0.203" wall thickness). Plumb all posts. See "Post Mount Detail" for crimping and trimming post to fit the diameter of top rail. Provide holes as needed in post for galvanizing drainage and venting.
- (11) See "General Notes" for anchor bolt information.
- (12) Bars S(#3) spaced at 12" Max (Spaced 3" from outside edge of overall length of Ramp/Sidewalk).
- (13) Provide 1 1/2" end cover to Bars D(#4) from outside edge of overall length of Ramp/Sidewalk.



TYPICAL POST BASE PLATE DETAIL



POST MOUNT DETAILS



ELEVATION


PEDESTRIAN HANDRAIL DETAILS PRD-13

FILE: prd13.dgn	DWG: TxDOT	CHK: AM	DWG: JTR	CR: CGL
© TxDOT December 2006	CONT: 0069	SECT: 07	JOB: 116, ETC.	HIGHWAY: US 87
REVISIONS	DIST: SJT	COUNTY: TOM GREEN	SHEET NO. 123	


DATE: FILE:

GENERAL NOTES


1. Acceptable joint sealing compounds are listed on the Department's "Joint Sealers" Material/Producer List.
2. Joint filler boards shall conform to the requirements of DMS-6310, "Joint Sealants and Fillers."
3. Reinforcing steel shall conform to the requirements of Item 440, "Reinforcement for Concrete."
4. Curb and valley gutter shall have no contraction joints.
5. Construct sealed expansion joints in curb at points of curvature and at intervals no greater than 120 ft.
6. Reinforcing bars in curb and valley gutter shall be lapped a minimum of 15 in.
7. No. 4 steel reinforcing bars shall be used in concrete valley gutter. Synthetic fibers may not be used in lieu of steel reinforcing in concrete valley gutter.
8. Before final acceptance of the project, remove discoloration caused by tire marks, mud, asphalt, paint or other similar material to achieve a uniform color and texture of the finished surface exposed to view.
9. Synthetic fibers may not be used in lieu of steel reinforcing in concrete radius curb placed at roadway intersections.
10. See Standard Sheet CCCG for curb steel reinforcing details and additional information.
11. Unless otherwise shown in the plans, furnish and install 8 in. of flexible base beneath curb and gutter and valley gutter. Unless otherwise shown in the plans, Flexible base shall conform to the requirements of Item 247, "Flexible Base," Type A, Grade 5 (without minimum strengths or classification).
12. Drain slots are required where shown on the plans.




CONCRETE CURB AND GUTTER (TYPE I)




CONCRETE CURB AND GUTTER (TYPE II)




TRANSITION AT END OF CURB




CONCRETE VALLEY GUTTER




SECTION THRU CURB WITH DRAIN SLOT



FLEXIBLE BASE DETAILS



SEALED EXPANSION JOINT



ELEVATION OF CURB WITH DRAIN SLOT

PAY ITEMS

0529	6007	CONC CURB & GUTTER (TY I)	LF
0529	6008	CONC CURB & GUTTER (TY II)	LF
0529	6021	CONC CURB & GUTTER (SLOTTED)	LF
0529	6023	CONC CURB & GUTTER (VALLEY GUTTER) (36")	LF



Texas Department of Transportation San Angelo District

CURB DETAILS


SHEET 1 OF 1 NOT TO SCALE

0069	07	116, ETC.	US 87
11-19		TOM GREEN	124


DATE: 5/28/2024 1:34:27 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms38156\td10240091ch_sdet13.dgn

GENERAL NOTES

1. The work performed, materials furnished, equipment, labor, tools, and incidentals for flexible base, sealed expansion joints and earth backfill will not be measured or paid directly, but will be considered as included in payment for Item 531, "Sidewalks."
2. Acceptable joint sealing compounds are listed on the Department's "Joint Sealers" Material/Producer List.
3. Joint filler boards shall conform to the requirements of DMS-6310, "Joint Sealants and Fillers."
4. Reinforcing steel shall conform to the requirements of Item 440, "Reinforcement for Concrete."
5. Where earth backfill is required, place imported topsoil or suitable topsoil from adjacent excavations. Limits and extent of backfill vary. Adjust backfill as directed to avoid obstructions or to remain within right of way limits. Slopes of earth backfill used to patch adjacent to new sidewalk shall be 3:1 or less, unless otherwise directed.
6. Remove and/or relocate any existing irrigation system components, plant material, and other landscaping items that conflict with locations of proposed construction as directed. Unless otherwise identified on the plans, this will not be measured or paid directly, but will be considered as included in payment for Item 531, "Sidewalks."
7. Construct 1/4 in. radius transverse contraction (tooled) joints at intervals equal to the sidewalk width, unless otherwise directed.
8. Construct sealed expansion joints at intervals not to exceed 40 ft. and where new concrete sidewalk abuts curbs, driveways, storm drain inlets, and existing concrete or buildings.
9. Sidewalks crossing driveways shall conform to the driveway details as shown elsewhere in the plans.
10. Flexible base shall conform to the requirements of Item 247, "Flexible Base," Type A, Grade 5 (without minimum strengths or classification). Recycled asphalt pavement (RAP) may be incorporated into the flexible base or may be used in place of flexible base.
11. The use of synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber is listed on the Department's "Fibers for Class A and Class B Concrete Applications" Material/Producer List.
12. If used, reinforcing steel shall be No. 3 uncoated deformed bars, placed at the vertical mid-point of the sidewalk thickness. Securely tie reinforcing steel where bars lap, intersect, or cross. Equivalent welded wire reinforcement may be substituted.
13. Where obstructions to remain exist, sidewalk width may be decreased to 3 ft. for a distance not to exceed 200 ft. When approved, sidewalk width may be decreased at obstructions to 32 in. for a distance not to exceed 2 ft. provided that reduced width segments are separated by segments that are 4 ft. long minimum and 3 ft. wide minimum.
14. Concrete for pedestrian rail footing and edge curb protection will be measured and paid for as Item 420.
15. Construct concrete riprap flumes 5 in. thick. Flumes adjacent to curbs are not intended for use in urban areas or within sidewalks. Slope flumes to match surrounding grades.
16. Use details on sheet SIDEWALK RETAINING WALL DETAILS if pedestrian rail footing height exceeds 1'-6".




TYPICAL SECTION THROUGH SIDEWALK




SECTION THRU SIDEWALK WITH PEDESTRIAN RAIL FOOTING


Sidewalk Width	No. of Longitudinal Bars
3 ft.	3
4 ft.	4
5 ft.	5
6 ft.	6




SIDEWALK STEEL REINFORCING




SECTION THRU SIDEWALK WITH EDGE CURB PROTECTION




SEALED EXPANSION JOINT



JOINT LAYOUT AT OBSTRUCTION



PLAN OF CONCRETE RIPRAP FLUME ADJACENT TO SIDEWALK DRAIN



PLAN OF CONCRETE RIPRAP FLUME ADJACENT TO CURB

SIDEWALK EDGE PROTECTION GUIDANCE

HAZARD TYPE	EDGE PROTECTION
drop-off < 1/2" or drop-off beyond 2' from sidewalk edge	none required
drop-off between 1/2" and 10" within 2' from sidewalk edge	edge curb or handrail
drop-off > 10" within 2' from sidewalk edge and total drop-off > 30"	handrail

PAY ITEMS

0420 6012 CL B CONC (MISC)	CY
0432 6044 RIPRAP (CONC) (FLUME)	CY
0531 6001 CONC SIDEWALKS (4")	SY
0531 6002 CONC SIDEWALKS (5")	SY
0531 6003 CONC SIDEWALKS (6")	SY




SIDEWALK DETAILS

SHEET 1 OF 1		NOT TO SCALE	
CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
11-19		DIST	COUNTY
		SJT	TOM GREEN
		SHEET NO. 125	


DATE: 5/28/2024 1:34:43 PM
FILE: c:\pwworking\infreese-pw.bentley.com_freese-pw-01\dms381561td10240091ch_sdet17.dgn

GENERAL NOTES


- Concrete pads for utility adjustments in HMA/CP paved areas and unpaved areas shall conform to the requirements of Item 421, "Hydraulic Cement Concrete" Class C, Class P, or Class HES. If Class HES concrete is provided, the flexural strength shall be 425 psi in 16 hours.
- Concrete pads for utility adjustments in existing concrete shall conform to the thickness of the surrounding concrete.
- For Class HES concrete pads, do not allow traffic on concrete until the concrete is at least 8 hours old. This time may be extended by the Engineer if weather or other conditions require. The concrete may be opened to traffic after the concrete has been cured for at least 8 hours and has obtained a flexural strength of 275 psi.
- For Class C or Class P concrete pads, the concrete may be opened to traffic after the concrete has attained a flexural strength of 450 psi or a compressive strength of 2,800 psi.
- The manhole or water valve should be centered within the concrete pad.
- Reinforcing steel shall conform to the requirements of Item 440, "Reinforcement for Concrete." Provide a minimum of 3 in. clear cover for reinforcing.
- Existing conditions may vary from the details shown. Make field adjustments as required.
- Place sealed expansion joints where concrete pad is adjacent to concrete.




SEALED EXPANSION JOINT



MANHOLE ADJUSTMENT IN CONCRETE PAVEMENT



MANHOLE ADJUSTMENT DETAILS




PLAN
No. 3 bars 6 in. O.C.E.W.

MANHOLE ADJUSTMENT NOTES


- Clean and re-use existing ring and cover, unless new materials are furnished by owner.
- Top of ring and cover shall be in the plane of the concrete collar.
- For brick manhole, adjust with brick as required to achieve new roadway elevation, and grout brick on the inside with 1/2 in. of mortar.
- For precast manhole, adjust with concrete adjustment rings as required to achieve new roadway elevation, and grout brick on the inside with 1/2 in. of mortar.

WATER VALVE BOX ADJUSTMENT NOTES


- Clean and re-use existing lid, unless new materials are furnished by owner.
- Furnish and install valve box risers as required.
- Use similar details for adjustments of water meter box, monitor well box, electric box, irrigation box, and telephone box. Dimensions may vary.



WATER VALVE BOX ADJUSTMENT DETAILS



PLAN



WATER VALVE BOX ADJUSTMENT IN CONCRETE PAVEMENT

PAY ITEMS

0479	6001	ADJUSTING MANHOLES	EA
0479	6005	ADJUSTING MANHOLES (WATER VALVE BOX)	EA
0479	6008	ADJUSTING MANHOLES (WATER METER)	EA
0479	6009	ADJUSTING MANHOLES (MONITOR WELL BOX)	EA
0479	6010	ADJUSTING MANHOLES (ELECTRIC BOX)	EA
0479	6011	ADJUSTING MANHOLES (IRRIGATION BOX)	EA
0479	6012	ADJUSTING MANHOLES (TELEPHONE BOX)	EA



UTILITY ADJUSTMENT DETAILS

SHEET 1 OF 1		NOT TO SCALE	
CTxDOT 2024	CONT	SECT	JOB
SHEET ISSUED OR LAST REVISED	0069	07	116, ETC.
11-19	DIST	COUNTY	SHEET NO.
	SJT	TOM GREEN	126

DATE: 5/28/2024 1:34:59 PM
FILE: c:\pwworking\infreese-pw.bentley.com_freese-pw-01\dms381561\td10240091ch_sdet22.dgn

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For projects with less than one acre of soil disturbing activity and that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

0069-07-116

1.2 PROJECT LIMITS:

From: AT 23RD STREET

To: _____

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 31.4802966, (Long) -100.4565625

END: (Lat) 31.4800492, (Long) -100.4562373

1.4 TOTAL PROJECT AREA (Acres): < 1 ACRE

1.5 TOTAL AREA TO BE DISTURBED (Acres): < 1 ACRE

1.6 NATURE OF CONSTRUCTION ACTIVITY:

TRAFFIC SIGNAL INSTALLATION IMPROVEMENTS INCLUDING DRILL SHAFT INSTALLATION, RAMP/CONCRETE WORK, CABINET INSTALLATION, ETC.

1.7 MAJOR SOIL TYPES:

Soil Type	Description

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: _____
 Other: _____
 Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Discharges from concrete washout activities, runoff from concrete cutting activities, and other concrete related activities
- Other: _____
- Other: _____
- Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody

* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: _____
- Other: _____



STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
6	SEE TITLE SHEET			127
STATE	STATE DIST.	COUNTY		
TEXAS	SJT	TOM GREEN		
CONT.	SECT.	JOB	HIGHWAY NO.	
0069	07	116, ETC.	US 87	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: EROSION CONTROL LOGS
- Other: _____
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: _____
- Other: _____
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.10 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



5/28/2024
TEXAS REGISTERED ENGINEERING FIRM F-2144

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
6	SEE TITLE SHEET			128
STATE	STATE DIST.	COUNTY		
TEXAS	SJT	TOM GREEN		
CONT.	SECT.	JOB	HIGHWAY NO.	
0069	07	116, ETC.	US 87	

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or CGP required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator that may receive discharges from this project. The MS4 Operator may need to be notified prior to construction activities.

1. N/A
 NO ACTION REQUIRED ACTION REQUIRED

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post CSN with SW3P information on or near the site, accessible to the public and TCEO, EPA or other inspectors.
- When PSL's increase disturbed soil area to 5 acres or more, submit NOI to TCEO and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

Adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP#

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Required Actions: List waters of the U.S. that the permit applies to, the location in project, and check BMP's planned to control erosion, sedimentation and post-construction TSS.

1. N/A

III. CULTURAL RESOURCES

Refer to the Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- NO ACTION REQUIRED ACTION REQUIRED
 1. N/A

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical.

Adhere to specification requirements of Items 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- NO ACTION REQUIRED ACTION REQUIRED
 1. Only remove woody vegetation between October 1 and March 1.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

- NO ACTION REQUIRED ACTION REQUIRED

- The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit issued in accordance with the Act's policies and regulations. Migration patterns would not be affected by the proposed project. Remove non-active migratory bird nests from structures where work would be performed from September 1 through the end of February. Prevent migratory birds from building nests from March 1 to August 31. In the event that migratory birds are encountered on-site during project construction, avoid adverse impacts on protected birds, active nests, eggs, and/or young.

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site MSDS for all hazardous products used on the project, which may include, but are not limited to the following categories: paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act.

Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the TxDOT District spill coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- YES NO

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- YES NO

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site (hazardous materials or contamination issues specific to this project):

- NO ACTION REQUIRED ACTION REQUIRED

1. N/A

BEST MANAGEMENT PRACTICES

EROSION

- SEEDING OR SODDING
- MULCHING
- SOIL RETENTION BLANKETS
- BIODEGRADABLE EROSION CONTROL LOGS
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- TOPSOIL OR COMPOST
- FLEXIBLE CHANNEL LINERS
- GROUND COVER

SEDIMENTATION

- ROCK FILTER DAMS
- TEMPORARY SEDIMENT CONTROL FENCES
- TRIANGULAR FILTER DIKES
- TOPSOIL OR COMPOST
- BIODEGRADABLE EROSION CONTROL LOGS
- SEDIMENT BASINS
- SAND BAG BERMS
- STRAW BALE DIKES
- BRUSH BERMS
- STORM INLET SEDIMENT TRAPS

POST-CONSTRUCTION TSS

- VEGETATIVE FILTER STRIPS
- RETENTION/IRRIGATION SYSTEMS
- EXTENDED DETENTION BASINS
- CONSTRUCTED WETLANDS
- WET BASINS
- TOPSOIL OR COMPOST
- BIODEGRADABLE EROSION CONTROL LOGS
- VEGETATION LINED DITCHES
- SAND FILTER SYSTEMS
- GRASSY SWALES

ABBREVIATIONS USED

- | | |
|--|--|
| BMP - Best Management Practice | NOI - Notice of Intent |
| CGP - Construction General Permit | NWP - Nationwide Permit |
| CSN - Construction Site Notice | PCN - Pre-Construction Notification |
| DSHS - Texas Department of State Health Services | PSL - Project Specific Location |
| EPA - U.S. Environmental Protection Agency | SW3P - Storm Water Pollution Prevention Plan |
| MS4 - Municipal Separate Stormwater Sewer System | TCEO - Texas Commission on Environmental Quality |
| MSDS - Material Safety Data Sheet | TPDES - Texas Pollutant Discharge Elimination System |
| | TSS - Total Suspended Solids |
| | USACE - U.S. Army Corps of Engineers |

VII. OTHER ENVIRONMENTAL ISSUES

(Includes regional issues such as Edwards Aquifer District, etc.)

- NO ACTION REQUIRED ACTION REQUIRED

1. N/A

DATE: 5/28/2024 1:35:50 PM
 FILE: c:\pwworking\freese-pw.bentley.com\freese-pw-01\dms381621d10240091kd_epic00.dgn



5/28/2024
 TEXAS REGISTERED ENGINEERING FIRM F-2144



ENVIRONMENTAL PERMITS ISSUES AND COMMITMENTS

SHEET 1 OF 1 NOT TO SCALE

CONT	SECT	JOB	HIGHWAY
0069	07	116, ETC.	US 87
DIST	COUNTY	SHEET NO.	
SJT	TOM GREEN	129	