SEE SHEET NO. 2 FOR INDEX OF SHEETS

STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO. STP 2B24(521)HES


FM 1008 LIBERTY COUNTY CSJ 0952-01-064, ETC.

CSJ 0952-01-064 NET LENGTH OF ROADWAY = 1,214.00 FT.= 0.230 MI.
CSJ 0952-01-064 NET LENGTH OF BRIDGE = 90.00 FT.= 0.017 MI.
CSJ 0952-01-069 NET LENGTH OF ROADWAY = 1,282.00 FT.= 0.243 MI.
NET LENGTH OF PROJECT = 2,496.00 FT.= 0.473 MI.

CSJ 0952-01-064 LIMITS: FROM 0.02 MI SOUTH OF CR 631, SOUTH TO 0.05 MI SOUTH OF BOWIE CREEK CSJ 0952-01-069 LIMITS: 0.3 MI NORTH OF HILLCREST TO 0.1 MI NORTH OF HILLCREST

FOR THE CONSTRUCTION OF A HAZARD ELIMINATION & SAFETY PROJECT

CONSISTING OF INCREASE SUPERELEVATION AND INSTALL LED FLASHING CHEVRONS



EXCEPTIONS: NONE
EQUATIONS: NONE
RAILROAD CROSSINGS: NONE

©2024 BY TEXAS DEPARTMENT OF TRANSPORTATION ALL RIGHTS RESERVED. | STP 2824(521)HES | CONT | SECT | JOB | HIGHWAY | O952 | O1 | O64, etc | FM1008 | O157 | COUNTY | SHEET NO. | BMT | LIBERTY | 1

DESIGN SPEED = 40 MPH A.D.T. (2022)= 8,948 A.D.T. (2042)= 15,927

FINAL PLANS

LETTING DATE:	
DATE CONTRACTOR BEGAN WORK:	
DATE WORK WAS COMPLETED & ACCEPTED:	
FINAL CONTRACT COST: \$	
CONTRACTOR	

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".



Lisa Collins

TING: 6/27/2024

6/27/2024

-5C6C707937C24CE... OF TRANSPORTATION PLANNING AND DEVELOPMENT

DocuSigned by:

5CAE84E05D7F456...

:: 6/21/2024 4:55:13 PM c:\txdot\pw opline\txdot\5\aldot

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, SEPTEMBER 1, 2024 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023)

INDEX OF SHEETS

SHEET NO. **DESCRIPTION**

```
CENERAL
               TITLE SHEET
               INDEX OF SHEETS
    2
               TYPICAL SECTIONS
    3
    4-8
               GENERAL NOTES
    9-10
               ESTIMATE & QUANTITY
    11-12
               QUANTITY SUMMARY
               IRAFEIC CONTROL PLAN
               SEQUENCE OF WORK
     13
    14-25
               BC (1)-21 THRU BC (12)-21
.
               TCP (1-2)-18
    26
. .
    27
               TCP (2-2)-18
. .
    28
               TCP (3-1)-13
. .
    29
               TCP (3-3)-14
               WZ (STPM)-23
    30
. .
    31
               WZ(UL)-13
. .
    32
               WZ( RS) -22
               ROADWAY_DETAILS
    33-35
               ROADWAY LAYOUT
               SUPER ELEVATION DETAILS
     36
. .
    37
               RS (2)-23
. .
    38
               RS (4)-23
               HOT MIX LONGITUDINAL AND PAVEMENT EDGE JOINT DETAILS
    39
               DRIVEWAY SUMMARY AND DETAILS
    41
               CLEARING DETAIL
               GF(31)-19
    42
. .
               GF( 31) TRTL3-20
    43-44
..
    45
               GF(31)MS-19
= =
               GF(31)LS-19
    46
. .
    47
               BED-14
. .
    48
               SGT( 10S) 31-16
..
               SGT(11S)31-18
    49
..
    50
               SGT( 12S) 31-18
               IRAFFIC DETAILS
..
    51
               D& OM (1)-20
. .
    52
53
               D& OM (2) -20
. .
               D& OM (3) -20
. .
    54
               D& OM (4) -20
. .
    55
               D& OM (5) -20
. .
    56
               PM (1)-22
    57
               PM (2)-22
     58
               SOSS
    59
               SMALL SIGN DETAILS
               SMD (SLIP-1)-08
    60
. .
    61
               SMD (SLIP-2)-08
..
    62
               SMD (SLIP-3)-08
..
    63
               TSR (4)-13
. .
               TSR (5)-13
. .
    65
               RFBA-13
               SPRFBA(1)-13
    66
.
    67
               SPRFBA(2)-13
. .
    68
               SPRFBA(3)-13
```

ENVIRONMENTAL ISSUES

SWP3

EPIC

SW3P-B

EC (1)-16

EC (9)-16

69-70

73-75

71

76

. . 72

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED WITH A "**" HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.


INDEX OF SHEETS



THEA TEXAS	FEDERAL AID PROJECT NO.			
DIVISION				2
STATE	DISTRICT		COLATT	
TEXAS	20	L	IBERT	Υ
SONTROL	SECTION	,000	M Della	Y 40.
0952	01	064.E	TCI FM 1	008

7/3/2024

DATE



Highway: FM 1008 Control: 0952-01-064,ETC

GENERAL NOTES:

Contractor questions on this project are to be addressed to the following individual(s):

Name Roberto Rodriguez, P.E.

Email (Roberto.M.Rodriguez@txdot.gov)

Name Nyemb Nyemb, P.E.

Email (Nyemb.Nyemb@txdot.gov)

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 4 Scope of Work

Remove all vegetation from pavement edges, intersections and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

It is the contractors responsibility to mark the location of all existing striping and place proposed striping back in the same location or as shown in the plans.

Item 5 Control of the Work

Station the project before commencing work. Mark the stations every 100 feet. Maintain stationing throughout the duration of the project. Remove the station markings at the completion of the project. Consider this work to be subsidiary to the various bid items of the contract.

Verify all horizontal and vertical control, approach grades to structures and driveways before beginning work. Notify the Engineer immediately if discrepancies are discovered.

Item 6 Control of Materials

Flammable/combustible materials must be stored at a designated location as approved.

Do not store flammable/combustible materials under or adjacent to Bridge class structures. Daily removal of these materials will be considered incidental work.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit an original of the TXDOT Construction Material Buy America

County: Liberty Sheet: 4

Highway: FM 1008 Control: 0952-01-064,ETC

Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html for clarification on material categorization.

Item 7 Legal Relations and Responsibilities

Furnish all materials, labor and incidentals required to provide for traffic across the highway and for temporary ingress and egress to private property in accordance with article 7.2.4 of the standard specifications at no additional cost to the state. Always maintain ingress and egress to the adjacent property. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor will be completely responsible for the immediate removal of any material that gets upon any vehicle as a result of their operation.

State contract mowers will mow the right of way during the growing season. The Contractor will be notified by the Engineer one week in advance of the anticipated time when mowers will be in the limits of the project. Clean the right of way to such a condition that allows the mowing contractors to safely mow.

Personal vehicles of the contractor's employees will not be parked within the right of way at any time including any section closed to public traffic, unless the vehicle is being used for construction procedures. However, the Contractor's employees may park on the right of way at sites where the contractor has their office, equipment and materials storage yard.

The following significant traffic generator events have been identified in the project limits: Dayton Ole Tyme Days Festival in April 11-14, 2025

Item 8 Prosecution and Progress

Compute and charge working days in accordance with Section 8.3.1.4 Standard Workweek.

Adjoining projects may be in progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects, if applicable. Manage construction of all phases to minimize disruption to traffic.

Maintain one lane open to traffic during construction, unless otherwise approved. Schedule work so that all travel lanes are open during non-working hours, nights and weekends, unless otherwise approved.

General Notes Sheet A General Notes Sheet B

Highway: FM 1008 Control: 0952-01-064,ETC

Submit a work schedule to the Engineer at the preconstruction meeting indicating completion dates for each location, and the number of crews required for the completion of the contract within the contract time period. If at any time during the contract the work progress is behind the initial schedule, submit documentation indicating how the project will be accelerated to ensure project completion in the remaining contract time.

Work will not be permitted when impending bad weather or low temperatures may impair the quality of work.

Working days will be charged during the observed curing times, even if no other work is being performed.

Where road closures or detours around structures are necessary to accomplish proposed work, the removal of existing structures and/or cutting of existing pavement will not be permitted until all pre-cast members for the proposed structure have been cast, tested and approved for use.

HURRICANE

In the event of the declaration of a hurricane watch, warning, other severe weather warning or national or state emergency that requires the roadways in the vicinity be used as evacuation routes,

cease all work that requires the Contractor's, sub-contractors' or material suppliers' vehicles to enter the stream of traffic on these primary or secondary evacuation routes. This work includes material hauling and delivery, and mobilization or demobilization of equipment.

Item 100 Preparing Right of Way

When bridge demolition, tree trimming or tree/brush removal is required from February 15 to September 30, the contractor will provide a qualified biologist with a Bachelor's Degree in biology and demonstrated bird nest survey experience to conduct nesting surveys before work can begin and until vegetation work is completed to ensure compliance with the Migratory Bird Treaty Act (MBTA). See EPIC sheet for details.

Chipping and disposal on right of way of smaller debris will be allowed. Depth of the chipped material will not exceed 2 inches. Direct discharge of chipped material towards the right of way line in non-residential areas only. Chipping will not be allowed in front of residences.

Heavy equipment rutting will be graded to the existing terrain profile. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor's attention is directed to potential regulations against burning within the project limits. Abide by all local ordinances and county imposed burn bans. When burning is prohibited, dispose of material in accordance with regulations set forth by other regulatory agencies including the Texas Commission for Environmental Quality. The cost of burning disposal of any product is subsidiary to various bid items. During burn bans obtain written approval from the Commissioners Court before burning brush.

Do not burn trash, debris, etc. within the City limits.

County: Liberty Sheet: 5

Highway: FM 1008 Control: 0952-01-064,ETC

Item 132 Embankment:

It is the Contractor's responsibility to advise the Engineer of the location of the material source enough in advance to avoid delay due to testing requirements.

Embankment Type C will conform to the following specification requirements:

1.Liquid Limit – 40 maximum

- 2.Plasticity Index 21 maximum, 8 minimum
- 3.A cohesionless sand will not be permitted

Item 134 Backfilling Pavement Edges

Embankment quantity by station includes both sides of the roadway. No deduction in payment will be made when in the opinion of the Engineer only one side of a roadbed section requires backfilling.

Provide material conforming to the specifications for Item 132 Embankment Type C.

Item 168 Vegetative Watering

Equip water trucks with sprinkler systems capable of covering the entire area to be seeded or sodded from the roadway.

Water all newly placed sod or seeded areas the same day of installation. Thereafter, maintain the sod or seeded areas in a well-watered condition and at no time allow the areas to dry to the condition that water stress is evident.

Mechanical watering may not be required during periods of adequate moisture as determined.

Furnish and apply water at a rate of 6.788 Mega gallons per acre per cycle or as directed on the plans.

Comply with stabilization requirements for 70% grass coverage; uniform vegetative coverage is required. During this period, meter and operate water equipment under pumping pressure capable of delivering the required quantities of water necessary. For Permanent seeding each cycle will be executed weekly for 12 weeks, unless directed otherwise. For Temporary seeding each cycle will be executed weekly for 6 weeks, unless directed otherwise.

Provide a log book showing daily water usage and receipts of water applied, in addition to metering the water equipment.

Genera Notes Sheet C General Notes Sheet D

Highway: FM 1008 Control: 0952-01-064, ETC

Item 341 Dense Graded Hot Mix Asphalt (Exempt)

Prepare Mix Designs using the Superpave Gyratory compactor.

Provide a separate Laboratory space, building or testing area, large enough to accommodate TxDOT equipment and testing on site at the Hot Mix Plant near or within the area of Contractor's testing equipment. The contractor will provide the SGC" Superpave Gyratory Compactor" and

TGC "Texas Gyratory Compactor". All other equipment must be provided by TxDOT. TxDOT will be responsible for maintaining state provided equipment. The Contractor will provide TxDOT with the Calibration paperwork on the shared equipment that they provide.

Provide an all-weather parking area for the sole use of at least 2 State-owned vehicles. Situate the parking area near the Laboratory area at an acceptable location. Maintain the parking area until the project is completed and restore the area to a condition acceptable to the Engineer upon project completion.

Laboratory area shall have a roof, floor, doors, and screened windows. Ensure the floor is strong enough to support testing equipment and has an impervious floor covering. Ensure that the Laboratory area is tied down, weatherproof, piped for water and fuel, and electrically wired by personnel meeting the requirements of Article 7.18., "Electrical Requirements."

Provide secured and controlled access to the Laboratory area through security measures such as bars, locks, alarms, or security fencing for the Laboratory area.

Furnish and install adequate equipment, outlets, lighting, air-conditioning, heating, and ventilation for the Laboratory area. Heating and Air Conditioning shall maintain the Laboratory working area temperature within range of (68oF through 72oF).

Provide partitioned restroom furnished with restroom supplies, a lavatory, and a flush toilet connected to a sewer or septic tank within the Laboratory area.

Laboratory area will have the use of an internet service provider (ISP) that can provide more than one computer access to ISP account at one time. ISP provider must be able to supply a minimum 100 gigabyte download speed per account.

Required appurtenances within the Laboratory Area:

- 1. A 10lb ABC fire extinguisher with up-to-date inspection tag and a working smoke detector.
- 2. Additional workbench and tables at least 3 ft. wide, 6 ft. long, and 3 ft. high.
- 3. Minimum two chairs and one desk, filing cabinets, solar screen blinds or shades.
- 4. An operational telephone system.
- 5. Water fountain or bottled water fountain able to provide cold water and have cup dispenser and cups.
- 6. Water (for testing purposes) from an approved source

General Notes Sheet E

County: Liberty Sheet: 6

Highway: FM 1008 Control: 0952-01-064, ETC

7. Adequately power ventilate the room for the ignition oven. Provide a NEMA 6-50R (208/240 volt, 50 amp) outlet within 2.25 ft. of the ignition oven location and an independent exhaust outlet to the outside located a maximum of 8 ft. from the oven. Provide a level, sturdy and

- 8. fireproof surface for the ignition oven with a minimum of 6 in. clearance between the furnace and other vertical surfaces. Vent the ignition oven to the outside.
- 9. A minimum of 20 ft. of total work counter length at least 3 ft. wide and 3 ft. above the floor and strong enough to support required testing equipment.
- 10. A laboratory sink measuring 24×30 in. and 12 in. deep
- 11. Door openings for the Laboratory area must be 48-inches minimum width. If steps are required to gain access to the facility's then a landing dock will be provided with minimum dimensions of 60 inches wide by 60 inches deep. The strong floor and landing of the facility

shall support the weight of all equipment and personnel providing a stable, essentially zero deflection during testing operations acceptable to the Engineer.

• Provide multifunction color printer/fax/scanner/copier capable of reproducing 11 X 17

For the Laboratory area the work performed, materials furnished, utilities, and utility services (including phone and internet), appurtenances including office equipment testing

equipment, labor, tools, and incidentals will not be paid measured or paid for directly but will be subsidiary to pertinent items.

Use aggregate that meets the SAC requirement of class A for all surface mixes. RAP aggregate must meet the requirements of Table 1.

Aggregates used on shoulders and ramps are required to meet SAC requirements. Provide mix designs. Mix designs must be verified and approved.

Remove all vegetation from pavement edges, intersections, curbs and gutters and driveways before planning or ACP operations. This work will not be paid for directly but will be subsidiary to the various bid items.

Operate the spreading and finishing machine at a uniform forward speed consistent with the plant production rate, hauling capability, and roller train capacity to result in a continuous operation. The speed will be slow enough, so that stopping between trucks is not ordinarily required. If the Engineer determines sporadic delivery of material is adversely affecting the HMA placement, the Engineer may require paving operations to cease until acceptable methods are employed to minimize starting and stopping of the paver.

Station limits may be adjusted as directed to meet varying field conditions.

Item 351 Flexible Pavement Structure Repair

The repair areas will require full depth saw-cut when milling is not used. Consider this work to be subsidiary to the various bid items of the contract.

General Notes Sheet F

Highway: FM 1008 Control: 0952-01-064, ETC

Provide Flexible Pavement Repair with Item 341, Type B (PG 64-22) unless approved otherwise. Place Hot Mix with a constant longitudinal surface grade and tie in flush with the existing surface at each end and both sides of the repair area.

Unless otherwise directed, place new ASB with maximum 4" lifts. The minimum patch sizes will be 6' in width and 10' in length.

Match the existing cross slope in the repair areas, unless directed otherwise.

All repair locations must be filled the same day they are excavated. No open cut areas will be allowed overnight.

All excavated materials will be removed from the project daily.

Ordinary compaction will be used on this project.

Station limits may be adjusted as directed to meet varying field conditions.

For repair locations located in areas to be planed, perform flexible pavement repairs after planning operations.

Seal the perimeter of the repair areas with hot poured rubber in accordance with Item 712. Consider this work to be subsidiary to the various bid items of the contract.

Item 354 Planning and Texturing Pavement

Where the underlying flexible base is exposed during the planning operation, prime this area with an asphalt at a rate as directed and patch with an approved HMA material, at the end of the day's operation in which it occurs. These items of work will not be paid for directly but will be subsidiary to Item 354.

Complete planning operations in adjacent lanes and shoulders to the same point at the end of each day.

Cut the existing shoulder pavement to allow for drainage of water away from travel lanes which have been planned. This work will be subsidiary to various bid items.

Retain ownership of planed materials.

Schedule the work so that a seal coat or HMA is placed no more than two weeks after milling has been performed on any pavement surface, unless otherwise approved. The Engineer may require the seal coat to be placed sooner than two weeks in cases when base materials are exposed or when the pavement structure is showing signs of distress.

Item 502 Barricades, Signs, and Traffic Handling

County: Liberty Sheet: 7

Highway: FM 1008 Control: 0952-01-064, ETC

Construct all work zone signs, sign supports, and barricades from material other than wood unless approved otherwise. Metal posts, if used, are to be galvanized. Aluminum signs, if used, will meet the following minimum thickness requirements:

Square Feet	Minimum Thickness
Less than 7.5	0.080 inches
7.5 to 15	0.100 inches
Greater than 15	0.125 inches

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be used for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

If the Engineer approves placement of temporary stockpiles in the right of way, delineation of the stockpile must follow the detail shown on the BC(10) standard.

Arrange asphalt laydown schedule to meet plan striping requirements. Limit length of lane closures to 1 mile unless otherwise approved.

Use drums as channelizing devices.

Remove all traffic control devices from the right of way when they are not in use. Devices scheduled to be used within 3 days may be placed along the shoulder of the roadway or along the right of way when not in use, or stored in other approved areas on the project. Cover any construction signs that are not in effect and are installed in a fashion that will not allow them to be removed from the right of way easily.

Provide construction fencing as approved at all work locations to protect pedestrian or bicycle traffic. This material and its placement will be considered subsidiary to Item 502.

Arrange construction operations to prevent the hauling of materials through the completed pavement sections unless otherwise approved.

Provide all flaggers and pilot vehicle drivers with two-way radio communication capability. Provide flaggers at each side road intersection.

Item 505

Shadow vehicles with TMA and high intensity rotating, flashing, oscillating or strobe lights are required. Use one TMA preceding every stationary work zone and two TMA's for mobile operations.

General Notes Sheet G General Notes Sheet H

Highway: FM 1008 Control: 0952-01-064, ETC

Therefore, 3 total shadow vehicles with TMA will be required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project

Item 540 Metal Beam Guard Fence

Provide Type II galvanization metal beam rail elements.

Provide round timber posts.

At the close of work each day, protect the ends of metal beam guard fence in an approved manner.

Item 585 Ride Quality for Pavement Surfaces

Use Surface Test Type A to evaluate ride quality of travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

Item 644 Small Roadside Sign Assemblies

Erect Reference Marker signs at the same station as they were located before removal.

Item 658 Delineator and Object Marker Assemblies

Use Type A reflector unit (sheeting) on delineator assemblies attached to concrete barrier.

Use bolt-on attachment for delineator assemblies attached to guard fence.

Install delineators when directed. This may require installation of delineators on portions of guardrail and bridge rail that is not being repaired in order to maintain consistency with adjacent sections.

MBGF will receive GF2 delineators installed on 100' maximum spacing.

Type C delineators will be installed using Adhesive 795A manufactured by Davidson Traffic Control Products or an equivalent approved in writing.

Item 666 Retroreflectorized Pavement Markings

Furnish Type II drop-on glass beads.

General Notes Sheet I



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0952-01-064

DISTRICT Beaumont **HIGHWAY** FM 1008

COUNTY Liberty

Report Created On: Jul 17, 2024 10:14:46 AM

		CONTROL SECTION JOB		0952-01	L-064	0952-01	-069		
		PROJECT ID		A00184	1091	A00193	025	_	TOTAL
		С	OUNTY	Liberty		Liber	ty	TOTAL EST.	TOTAL FINAL
		HIC	GHWAY FM 1008		800	FM 1008			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	100-7002	PREPARING ROW	STA			20.000		20.000	
	104-7005	REMOV CONC (MOWSTRIP)	LF	206.000				206.000	
	134-7002	BACKFILL (TY B)	STA	6.000				6.000	
	164-7002	BROADCAST SEED (PERM_RURAL_CLAY)	SY	516.000				516.000	
	164-7005	BROADCAST SEED (TEMP_WARM)	SY	516.000				516.000	
	168-7001	VEGETATIVE WATERING	TGL	1.000				1.000	
	341-7046	D-GR HMA TY-D PG64-22 (LEVEL-UP)	TON	101.000				101.000	
	341-7082	TACK COAT	GAL	181.000				181.000	
	351-7007	FLEXIBLE PAVEMENT STRUCTURE REPAIR(8")	SY	300.000				300.000	
	432-7013	RIPRAP (MOW STRIP)(4 IN)	CY	40.000				40.000	
	500-7001	MOBILIZATION	LS	1.000				1.000	
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	2.000				2.000	
	503-7002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1.000				1.000	
	505-7001	TMA (STATIONARY)	DAY	27.000		11.000		38.000	
	505-7003	TMA (MOBILE OPERATION)	DAY	3.000				3.000	
	506-7044	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	200.000				200.000	
	506-7046	BIODEG EROSN CONT LOGS (REMOVE)	LF	200.000				200.000	
	530-7015	DRIVEWAYS (BASE)	SY	17.000				17.000	
	533-7002	MILL RUMBLE STRIPS (ASPH) (CENTERLINE)	LF	1,293.000				1,293.000	
	540-7001	MTL W-BEAM GD FEN (TIM POST)	LF	325.000				325.000	
	540-7005	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	4.000				4.000	
	542-7001	REMOVE METAL BEAM GUARD FENCE	LF	225.000				225.000	
	544-7001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000				4.000	
	544-7003	GUARDRAIL END TREATMENT (REMOVE)	EA	4.000				4.000	
	618-7030	CONDT (PVC) (SCH 40) (2")	LF			1,215.000		1,215.000	
	618-7031	CONDT (PVC) (SCH 40) (2") (BORE)	LF			40.000		40.000	
	620-7007	ELEC CONDR (NO.8) BARE	LF			1,255.000		1,255.000	
	620-7008	ELEC CONDR (NO.8) INSULATED	LF			2,510.000		2,510.000	
	624-7002	GROUND BOX TY A (122311)W/APRON	EA			1.000		1.000	
	628-7260	ELC SRV TY D 120/240 100(NS)SS(N)SP(U)	EA			1.000		1.000	
	644-7001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	8.000				8.000	
	644-7025	IN SM RD SN SUP&AM TYS80(1)SA(P)	EA			10.000		10.000	
	644-7073	REMOVE SM RD SN SUP&AM	EA	8.000		1.000		9.000	
	662-7114	WK ZN PAV MRK SHT TERM (TAB)TY Y-2	EA	97.000				97.000	
	666-7269	RE PROFILE PM TY I(Y)6"(SLD)(090MIL)	LF	2,584.000				2,584.000	
	666-7279	RE PROF PM (W)6"(SLD) RAISD PROF ONLY	LF	2,584.000				2,584.000	
	672-7004	REFL PAV MRKR TY II-A-A	EA	17.000				17.000	



DISTRICT	COUNTY	CCSJ	SHEET
Beaumont	Liberty	0952-01-064	9



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0952-01-064

DISTRICT Beaumont **HIGHWAY** FM 1008

COUNTY Liberty

Report Created On: Jul 17, 2024 10:14:46 AM

		CONTROL SECTIO	N JOB	0952-01-064		0952-0	L-069		
		PROJE	PROJECT ID		A00184091		A00193025		
	COUNTY		Liberty		Liberty		TOTAL EST.	TOTAL FINAL	
		HIG	HWAY	FM 1008		FM 1008			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL		
	6003-7001	LEAD LED CURVE SIGN	EA			2.000		2.000	
	6003-7002	LED CHEVRON	EA			8.000		8.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000				1.000	



DISTRICT	COUNTY	CCSJ	SHEET	
Beaumont	Liberty	0952-01-064	10	

ROADWAY ITEMS

	100	134	10	164		34	41	351
	7002	7002	7002	7005	7001	7046	7082	7007
	PREPARING ROW	BACKFILL (TY B)	BROADCAST SEED (PERM_RURAL_CL AY)	BROADCAST SEED (TEMP) (WARM)	VEGETATIVE WATERING	D-GR HMA TY-D PG64-22 (LEVEL-UP)	TACK COAT	FLEXIBLE PAVEMENT STRUCTURE REPAIR (8")
UNIT OF MEASURE	STA	STA.	SY	SY	AC	SY	SY	SY
0952-01-064	0	6	516	516	1	1367	1807	300
0952-01-069	20	0	0	0	0	0	0	0
TOTALS	20	6	516	516	1	1367	1807	300

^{*}FOR CONTRACTOR INFO ONLY, FOR PAY QUANTITY SEE BASIS OF ESTIMATE

ROADWAY ITEMS

	530	533
	7015	7002
	DRIVEWAY (BASE)	MILL RUMBLE STRIPS (ASPHALT) (CENTERLINE)
UNIT OF MEASURE	SY	LF
0952-01-064	17	1293
0952-01- 069	0	0
TOTALS	17	1293

^{*}FOR CONTRACTOR INFO ONLY, FOR PAY QUANTITY SEE BASIS OF ESTIMATE

SW3P ITEMS

	50	06
	7044	7046
	BIODEG EROSN CONT LOGS (INSTL)(12")	BIODEG EROSN CONT LOGS (REMOVE)
UNIT OF MEASURE	LF	LF
0952-01-064	200	200
0952-01-069	0	0
TOTALS	200	200

WORKZONE MARKING ITEMS


	503	50	05	662
	7002	7001	7003	7114
	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)	TMA (MOBILE OPERATION)	WK ZN PAV MRK SHT TERM (TAB) TY Y-2
UNIT OF MEASURE	EA	DAY	DAY	EA
0952-01-064	1	27	3	97
0952-01-069	0	11	0	0
TOTALS	1	38	3	97

BASIS OF ESTIMATE

ITEM	DESCRIPTION	RATE	# OF UNITS	UNIT	QUANTITY	UNIT
168-7001	VEGETATIVE WATERING	6.788 MG/AC/CYCLE (2 CYCLES)	1	AC	1.00	MG
341-7046	D-GR HMA TY-D PG64-22 (LEVEL-UP)	146.67 LBS/CF	1367	CF	101.00	TON
341-7082	TACK COAT	0.1 GALS/ SY	1807	SY	181.00	GAL

FM 1008 QUANTITY SUMMARY

SHEET 1 OF 2



2:32:07 PM

TRAFFIC ITEMS

	104	432	5	40	542	5.	44	6	18
	7005	7013	7001	7005	7001	7001	7003	7030	7031
	REMOV CONC (MOWSTRIP)	RIPRAP (MOW STRIP)(4 IN)	MTL W-BEAM GD FEN (TIM POST)	MTL BEAM GD FEN TRANS (THRIE-BEAM)	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL END TREATMENT (INSTALL)	GUARDRAIL END TREATMENT (REMOVE)	CONDT (PVC) (SCH 40) (2")	CONDT (PVC) (SCH 40) (2") (BORE)
UNIT OF MEASURE	LF	CY	LF	EA	LF	EA	EA	LF	LF
0952-01-064	206	40	325	4	225	4	4	0	0
0952-01-069	0	0	0	0	0	0	0	1215	40
TOTALS	206	40	325	4	225	4	4	1215	40

TRAFFIC ITEMS

IMALITETIEN	113										
		620	624	628		644			6003		
	7007	7008	7002	7260	7001	7025	7073	7001	7002		
	ELEC CONDR (NO.8) BARE	ELEC CONDR (NO.8) INSULATED	GROUND BOX TY A (122311) W/APRON	ELC SRV TY D 120/240 100(NS) SS(N)SP(U)	IN SM RD SN SUP & AM TY 10 BWG(1)SA(P)	IN SM RD SN SUP&AM TYS80(1)SA(P)	REMOVE SM RD SN SUP & AM	LEAD LED CURVE SIGN	LED CHEVRON		
UNIT OF MEASURE	LF	LF	EA	EA	EA	EA	EA	EA	EA		
0952-01-064	0	0	0	0	8	0	8	0	0		
0952-01-069	1255	2510	1	1	0	10	1	2	8		
TOTALS	1255	2510	1	1	8	10	9	2	8		

PAVEMENT MARKING ITEMS

	533	66	56	672
	7002	7269	7279	7004
	MILL RUMBLE STRIPS (ASPHALT) (CENTERLINE)	RE PROFILE PM TY I(Y)6"(SLD)(090MIL)		REFL PAV MRKR TY II-A-A
UNIT OF MEASURE	LF	LF	LF	EA
0952-01-064	1293	2584	2584	17
0952-01-069	0	0	0	0
TOTALS	1293	2584	2584	17



SHEET 1 OF 2



SEQUENCE OF WORK:

- 1. INSTALL CONSTRUCTION BARRICADES, SIGNS AND SWEP OR EROSION CONTROL ITEMS. MAINTAIN AS NECESSARY THOUGHOUT PROJECT DURATION.
- 2. PORTABLE CHANGEABLE MESSAGE BOARDS ARE TO BE PLACED 2 WEEKS PRIOR BEGINNING CONSTRUCTION OR AT THE DIRECTION OF ENGINEER
- 3. CONSTRUCT SUPER-ELEVATIONS INCREASE WITH TYPE D PG 64-22, AS SHOWN IN THE PLANS. BACKFILL PAVEMENT EGDES DAILY.
- 4. PLACE WORKZONE TABS IN ACCORDANCE WITH WZ(STPM)-23.
- 5. REMOVE METAL BEAM GUARD FENCE. INSTALL THE NEW METAL BEAM GUARD FENCE, AS SHOWN IN ROADWAY LAYOUT.
- 6. PERFORM DRIVEWAY WORK AS SHOWN.
- 7. PLACE FINAL PAVEMENT MARKINGS AS SHOWN IN THE PLANS AND IN ACCORDANCE WITH CURRENT PAVEMENT MARKING STANDARDS.
- 8. PERFORM SIGN UPGRADES IN ACCORDANCE WITH CURRENT STANDARDS.
- 9. CLEAN SITE AND REMOVE BARRICADES, SIGN AND SW3P ITEMS AFTER FINAL ACCEPTANCE.



FM 1008 SEQUENCE OF WORK



	_		
CONT	SECT	JOB	HIGHWAY
0952	01	064	FM1008
DIST		COUNTY	SHEET NO.
BMT		LIBERTY	13

NOTES:

- PERPARE THE BID ACCORDING TO THIS SEQUENCE OF WORK. THE ENGINEER MAY MAY APPROVE ADJUSTMENTS TO THE SCHEDULE OF WORK AFTER LETTING.
- REFER TO THE GENERAL NOTES AND PLAN SHEETS FOR ADDITIONAL DIRECTION.

ts/0952-01-064_FM 1008 Increese Super

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. The development and design of the Traffic Control Plan (TCP)is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- 6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travellanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD) DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) MATERIAL PRODUCER LIST (MPL) ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)" STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD) TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

Traffic Safety Division Standar



BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS


BC(1)-21

FILE:	bc-21.dgn	DN: T>	DOT	ck: TxDOT	DW:	TxDOT	ск: ТхDОТ
© TxD0T	November 2002	CONT	SECT	JOB		HIC	SHWAY
4-03	7-13	0952	01	064		FM	1008
9-07	8-14	DIST		COUNTY		6	SHEET NO.
5-10	5-21	ВМТ		LIBERT	Y		14

95

ROAD

CLOSED R11-2



- May be mounted on back of "ROAD WORK AHEAD"(CW20-1D) sign with approval of Engineer. (See note 2 below)
- 1. The typical minimum signing on a crossrood approach should be a "ROAD WORK AHEAD" (CW20-1D)sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
- 2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK"(G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
- 3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Slandard Sheets.
- 4. The "ROAD WORK NEXT X MILES"(G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
- 5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
- 6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

CW1-4

CW13-1P

Barricade or

devices

T-INTERSECTION WORK * *G20-9TP X XR20-5T DOUBLE * * R20-5aTP ROAD WORK <> NEXT X MALES * *C20-26T WORK ZONE G20-16TL INTERSECTED 1000'-1500' - Hwy 1 Block - City 1000'-1500' - Hwy ROADWAY 1 Block - City \Rightarrow G20-16TR ROAD WORK WORK ZONE G20-26T ** BEGIN G20-5T * * G20-9TP ZONE TRAFFIC G20-6T * * R20-5T FINES DOUBLE * * R20-5oTP ROAD WORK G20-2

CSJ LIMITS AT T-INTERSECTION

- 1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- 2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME"(G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow(G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR)" signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING


SPACING

	SIZE	
Sign Number or Series	Conventional Road	Expressway/ Freeway
CW20 ⁴ CW21 CW22 CW23 CW25	48" × 48"	48" × 48"
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36" 48'	' x 48"
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	8" × 48" 48'	' × 48"

- Posted Sign Speed Spacing Feet Apprx. 30 120 35 160 40 240 45 320 50 55 500 ² 60 600 ² 65 700 2 70 800 ² 75 900 ² 80 1000 2
- * For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.
- Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4.36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroods at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped worning sign sizes are indicated.
- . See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design



¥ ¥G20-9TP

XR20-5T

¥ ¥R20-5aTP

SPEED

-CSJ Limi

R2-1

CONTRACTOR

* *G20-5T

¥ ¥G20-6T

END ROAD WORK

G20-2 * *

ROAD

WORK

1/2 MILE

CW20-1E

ROAD

WORK

AHE AD

CW20-1D

ZONE

TRAFFIC

DOUBLE

FINES

SPEED R2-1

STAY ALERT

TALK OR TEXT LATER

G20-10T

OBEY

STATE LAW

➾

WORK ZONE G20-2bT *

R20-3T

to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES"(G20-5T)sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

- ☐ The "BEGIN WORK ZONE"(G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a port of the work zone lying outside the CSJ Limits where traffic fines may double workers are present.
- CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
- Area for placement of "ROAD WORK AHEAD" (CW20-1D)sign and other signs or devices as called for on the Traffic
- Contractor will install a regulatory speed limit sign at the end of the work zone.

	LEGEND
\blacksquare	Type 3 Barricade
000	Channelizing Devices
1	Sign
x	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION

BC(2)-21


7-13	5-21	BMT		LIBERT			15
9-07	8-14	DIST	_	COUNTY			SHEET NO.
	REVISIONS	0952	01	064		FM	1008
© TxD0T	November 2002	CONT	SECT JOB		HIGHWAY		
FILE:	bc-21.dgn	DN: T)	DOT	ск: ТхDОТ	DW:	TxDOT	ск: ТхD0

PROJECT LIMIT

7-13	5-21	ВМТ		LIBERT	Y		15
9-07	8-14	DIST		COUNTY		SHEET NO	
	REVISIONS	0952	01	064		FM1008	
© TxD0T	November 2002	CONT	SECT	JOB		HIG	HWAY
FILE:	bc-21.dgn	DN: T)	DOT	ck: TxDOT	DW:	TxDOT	ск: ТхД

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged povement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.


SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of traveland are normally posted for each direction of travel.
- 4. Frequency of work zone speed limit signs should be:
 - 40 mph and greater 0.2 to 2 miles
- - 35 mph and less
- 0.2 to 1 mile
- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- 6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form *1204 in the TxDOT e-form system.



Traffic Safety Division Standard





BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC(3)-21


7-13	J-21	BMT		LIBERT	Υ		16
9-07	5-1 4 5-21	DIST		COUNTY		8	SHEET NO.
0.07	REVISIONS 8-14	0952	01	064		FM	1008
TxD0T	November 2002	CONT	SECT	JOB		HIG	HWAY
E:	bc-21.dgn	DN: TxD)OT	ск: TxDOT	DW:	TxDOT	ск: ТхDОТ

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS










- * When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling
 - x x When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travellane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.




Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the spice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.


Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

> Nails shall NOT be allowed. Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by ony means. Wood supports shall not be extended or repaired by splicing or other means.

STOP/SLOW PADDLES

- 1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- 2. STOP/SLOW poddles shall be retroreflectorized when used at night. 3. STOP/SLOW poddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- 4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.





SHEETING REC	UIREMENTS	(WHEN USED AT NIGHT)
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without

SIDE ELEVATION

Wood

- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on croshworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be pointed white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, worn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been amitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the inspector's TxDOT diary and having both the inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

<u> DURATION OF WORK (as defined by the "Texas Manualon Uniform Traffic Control Devices" Part 61</u>

- The lypes of sign supports, sign mounting height,the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- b. Intermediate term stationary work that occupies a location more than one daylight period up to 3 days, or nighttime work losting more than one hour.
- c. Short-term stationary daytime work that occupies a location for more than 1 hour in a single daylight period.
- d. Short, duration work that occupies a location up to 1 hour.
- e. Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- 1. The boltom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the povement surface but no more than 2 feel above
- the ground.
 3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing
- 4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer. SIGN SUBSTRATES

- 1. The Controctor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT on approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the spice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- 3. Orange sheeting, meeting the requirements of DMS-8300 Type B or Type 🔓 , shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
 Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mill black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlan shall NOT be used to cover signs.
- 6. Duct tape or other adhesive material shall NOT be affixed to a sign face. Signs and anchor slubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.

 The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight
- 3. Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights.

 Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.

 Sandbags shall be made of a durable material that tears upon vehicular
- impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- with tubber buses may be used when shown in the Charles list.

 Sondbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandboas shall be placed along the length of the skids to weigh down the sign support. Sondbogs shall NOT be placed under the skid and shall not be used to level
- sion supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be arange or fluorescent red-arange in color. Flags shall not be allowed to cover any portion of the sign face. SHEET 4 OF 12



BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

Traffic Safety Division Standard

BC(4)-21

bc-21.dgr DN: TXDOT CK: TXDOT DW: TXDOT CK: TXDO TxDOT November 2002 0952 01 064 EM1008 9-07 8-14 7-13 5-21 LIBERTY 17



-9 sq. ft. or less-

10mm extruded

-1 3/4" x 1 3/4" x 11 foot

thinwall plastic

12 go post (DO NOT SPLICE)

13/4" galv. round with 5/16" holes

or 13/4" x 13/4"

pin at angle needed to motch sideslope

-2" x 2" x

12 go.

square tubing

Upright must

telescope to

weld -starts here

provide 7' height

above povement

48"


-Welds to start on

opposite sides going in opposite directions. Minimum

weld, do not

back fill puddle





WEDGE ANCHORS

Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

Ø 3/8 " X 3" gr.

5 bolt

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" log screws must be used on every joint for final
- No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
- . When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiory to Item 502.
 - See BC(4) for definition of "Work Duration."
 - Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - ☐ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12




Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

© TxD0T	November 2002	CONT SECT JOB		02 CONT SECT JOB HIGHW		HWAY	
100 1000	REVISIONS	0952	01	064		FM	1008
9-07	8-14	DIST		COUNTY		- 6	SHEET NO.
7-13	5-21	ВМТ		LIBERT	Y		18



PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- 2. Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR." "AT." etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP.
- 5. Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- 6. When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible
- 7. The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- 8. The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- 9. Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e.,
- keeping two lines of the message the same and changing the third line. 11. Do not use the word "Danger" in message.
- 12. Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the lext should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Rood A	CCS RD	Major MAJ	
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PK ING RD
CROSSING	XING	Road Right Lane	
Detour Route	DETOUR RTE	Saturday	RT LN SAT
Do Not	DONT	Service Road	SERV RD
East	E	Shoulder	SHLDR
Eastbound	(route) E	Slippery	SLIP
Emergency	EMER	South	S
Emergency Vehicle		Southbound	(route) S
Entrance, Enter	ENT	Speed	SPD
Express Lone	EXP LN	Street	ST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hozordous Driving	HAZ DRIVING	Travelers	TRVLRS
Hazardous Material	HAZMAT		TUES
High-Occupancy	HOV	Tuesday Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway	I THE I	Vehicles (s)	VEH, VEHS
Hour (s)	HR, HRS	Warning	WARN
Information	INFO	Wednesday	WED
I† Is	[TS	Weight Limit	WT L[M[T
Junction	JCT	West	M. CIWII
Left	LFT	Westbound	(route) W
Left Lane	LFT LN	Wet Pavement	WET PVMT
Lone Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL] L #111 NO!	#VIII I
Maintenance	MAINT		

Roadway designation • IH-number, US-number, SH-number, FM-number

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

oad/Lane/Ramp	Closure List	Other Condit	ion List
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT
xxxxxxx			

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS.
- 2. The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phose Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases. and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

Phase 2: Possible Component Lists

tion to Take/Effect on Travel List	Location List	Warning List	* AdvanceNotice List
MERGE FORM X LINES RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM- X PM
DETOUR NEXT X EXITS USE XXXXX RD EXIT	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX- XX X PM-X AM
USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
STAY ON US XXX SOUTH USE I-XX E TO I-XX N	PAST US XXX EXIT	ADVISORY SPEED XX MPH	BEGINS MAY XX
TRUCKS USE US XXX N WATCH FOR TRUCKS	XXXXXXX TO XXXXXXX	RIGHT LANE EXIT	MAY X-X XX PM - XX AM
WATCH EXPECT DELAYS TRUCKS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
EXPECT PREPARE TO STOP		DRIVE SAFELY	XX AM TO XX PM
REDUCE END SPEED SHOULDER XXX FT USE		DRIVE WITH CARE	NEXT TUE AUG XX
USE WATCH OTHER FOR ROUTES WORKERS			TONIGHT XX PM- XX AM
STAY IN LANE *	×× Se	ee Application Guidelines No	te 6.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate 2. Roadway designations IH, US, SH, FM and LP can be interchanged as
- 3. EAST, WEST, NORTH and SOUTH (or abbreviations E. W. N and S) can
- be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary.
- 7. FT and MI, MILE and MILES interchanged as appropriate
- 8. AT, BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


FULL MATRIX PCMS SIGNS

BLVD

CLOSED

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol"(CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above 3. When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute
- for, or replace that sign. 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the

SHEET 6 OF 12




Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC(6)-21


			_				
FILE:	bc-21.dgn	DN: T)	OOT	ск: ТхDОТ	DW:	TxDOT	ск: TxDOT
© TxD0T	November 2002	CONT	SECT	JOB		HIC	HWAY
	REVISIONS	0952	01	064		FM	1008
9-07	8-14	DIST		COUNTY			SHEET NO.
7-13	5-21	ВМТ		LIBERT	Y		19

- 1. Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address
- 2. Color of Barrier Reflectors shall be as specified in the TMUTCD. The



CONCRETE TRAFFIC BARRIER (CTB)

- 3. Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- 5. When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- 6. Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- 7. Maximum spacing of Barrier Reflectors is forty (40) feet.
- 8. Povement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- 9. Attachment of Barrier Reflectors to CTB shall be per manufacturer's
- 10.Missing or domaged Barrier Reflectors shall be replaced as directed by the Engineer
- 11. Single slope barriers shall be delineated as shown on the above detail.




IN WORK ZONES LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE

BARRIER (LPCB) USED

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the apppropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS

Type C Warning Light or approved substitute mounted on a

Warning reflector may be round

or square.Must have a yellow

30 square inches

reflective surface area of at least

drum adjacent to the travelway.

1. Warning lights shall meet the requirements of the TMUTCD.

2. Worning lights shall NOT be installed on barricades.

- 3. Type Á-Lów Intensity Floshing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B or C Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- 4. Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control
- devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB"
- 5. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices. 6. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will
- certify the warning lights meet the requirements of the lotest ITE Purchase Specifications for Floshing and Steady-Burn Warning Lights. 7. When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- 8. The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS

- 1. Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- 2. Type A random flashing warning lights are not intended for defineation and shall not be used in a series.
- 3. A series of sequential floshing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive floshing of the sequential worning lights should occur from the beginning of the toper to the end of the merging toper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- 4. Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travellane on detours on lane changes, on lane closures, and on other similar conditions.
- 5. Type Á, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- 6. Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- 7. The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.


WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- 1. A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- 2. The worning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed
- 3. The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- 4. Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- 5. Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it
- 6. The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- 7. When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- 8. The worning reflector should be mounted on the side of the handle nearest approaching traffic.
- 9. The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- 1. The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travellanes.

 2. Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions
- or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, borricades and/or other traffic control devices that should be used in conjunction with the Floshing Arrow Board.
- 4. The Floshing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- 6. The straight line coution display is NOT ALLOWED.
- The Floshing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage.
 The floshing rate of the lamps shall not be less than 25 nor more than 40 floshes per minute.
- 8. Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal

- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
 The sequential arrow display is NOT ALLOWED.
 The llashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during dayight operations.
 The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
 A flushing Arrow Board SHALL NOT BE USED to laterally shift traffic.
 A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
 Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.
- to bottom of panel.

REQUIREMENTS									
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE						
В	30 × 60	13	3/4 mile						
С	48 x 96	15	1 mile						

ATTENTION Flashina Arrow Boards shall be equipped with automatic dimmina devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

Traffic Safety Division Standar

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- 1. Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for
- Assessing Sofety Hordwore (MASH).

 2. Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- 3. Refer to the CWZTCD for a list of approved TMAs.
- 4. TMAs are required on freeways unless otherwise noted
- 5. A TMA should be used onytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- 6. The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS. WARNING LIGHTS & ATTENUATOR

BC(7)-21

FILE:	bc-21.dgn	DN: T)	(DOT	ck: TxDOT	DW:	TxDOT	ск: ТхD01
© TxD0T	November 2002	CONT	SECT	JOB		HIG	HWAY
27. 25.00	REVISIONS	0952	01	064		FM	1008
9-07	8-14	DIST		COUNTY		3	SHEET NO.
7-13	5-21	BMT		LIBERT	Y		20



- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace ony plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

GENERAL NOTES

Pre-qualified plastic drums shall meet the following requirements:


- Plostic drums shall be a two-piece design: the "body" of the drum shall be the top portion and the "bose" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by possing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Boses shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
 Plostic drums shall be constructed of ultra-violet slabilized, orange,
- high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballosted weight of 11 lbs.
 10.Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above povement surface may not exceed 12 inches.
- Boses with built-in ballast shall weigh between 40 lbs. and 50 lbs.
 Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck lire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballost shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to povement.






DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrions with visual disabilities normally use the closed sidewalk, a Detectable Pedestrion Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily defineate a pedestrian path.
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian apparent.
- Warning lights shall not be attached to detectable pedestrian borricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or shorp edges.



18" x 24" Sign (Maximum Sign Dimension) Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer

See Ballast



12" x 24"
Vertical Panel
mount with diagonals
sloping down towards
trovel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plostic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B or Type C Orange, sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lone.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12



Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

FILE: bc-21.dgn	DN: Tx	DOT	ск: TxDOT	DW:	TxDOT	ск: ТхDОТ
© TxDOT November 2002	CONT	SECT	JOB		HIC	HWAY
REVISIONS	0952	01	064		FM	1008
4-03 8-14 9-07 5-21	DIST		COUNTY			SHEET NO.
7-13	BMT		LIBERT	Y		21

8" to 12"

Bose

Surface.


PORTABLE

VP-1

Fixed Bose

w/ Approved

(Rigid or self-righting)



- 1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- 2. VP's may be used in daylime or nightlime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime defineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- 3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travellane.
- 4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- 5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List"
- 6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- 7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

VERTICAL PANELS (VPs)

- 1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the povement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- 2. The OTLD may be used in combination with 42" cones or VPs.
- 3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- 4. The OTLD shall be orange with a black nonreflective legend. Sheeting for the OTLD shall be retroreflective Type B or Type C conforming to Departmental Material Specification DMS-8300. unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)


mounted

Portable,

Fixed or

or may be

mounted




Fixed Bose w/ Approved Adhesive (Driveoble Base, or Flexible Support can be used)

- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the for side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B or Type C configrming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on topers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- 6. Povement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final povement surfaces, including povement surface discoloration or surface integrity. Driveable bases shall not be permitted on final povement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are croshworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travellanes.
- 6. LCDs used as barricodes placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballosted systems used as barriers shall not be used solely to channelize rood users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roodway speed and barrier application.
- 2. Water bollosted systems used to channelize vehicular traffic shall be supplemented with retroreflective defineation or channelizing devices to improve daytime/nightlime visibility. They may also be supplemented with povement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. Water ballosted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- 5. When water ballosted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flored to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballosted systems must have a continuous detectable bottom for users of long canes and the top the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	Minimum Desiroble Toper Lengths * *		Suggested Moximum Spocing of Channelizing Devices		
		10° Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	2	150'	165'	180'	30,	60'
35	L• <u>ws²</u>	205'	225'	245'	35'	70'
40] 60	265'	295'	320	40'	80'
45		450'	495'	540'	45'	90.
50	l	500'	550	600.	50'	100'
55	L-WS	550'	605'	660'	55'	110'
60	" " " " " " " " " " " " " " " " " " "	600'	660'	720'	60,	120'
65	l	650'	715'	780'	65'	130'
70	l	700'	770'	840'	70'	140'
75	l	750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

* * Toper lengths have been rounded of L-Length of Toper (FT.) W-Width of Offset (FT.)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



Traffic Safety Division Standard


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(9)-21


7-13	5-21	BMT		LIBERT			22
9-07	8-14	DIST		COUNTY			SHEET NO.
	REVISIONS	0952	01	064		FM	1008
© TxD0T	November 2002	CONT	SECT	JOB		HIG	HWAY
FILE:	bc-21.dgn	DN: T)	DOT	ck: TxDOT	DW:	TxDOT	ск: ТхDОТ

TYPE 3 BARRICADES

- 1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Borricodes.
- 2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- 3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- 4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- 6. Barricades shall not be placed parallel to traffic unless an adequate
- 7. Warning lights shall NOT be installed on barricades.
- 8. Where borricodes require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- 9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.


Alternote


TYPICAL PANEL DETAIL



TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION

Alternate





Two-Piece cones

‡ 3" min.

One-Piece cones

Tubular Marker

FOR SKID OR POST TYPE BARRICADES

Drums, vertical panels or 42" cones 50' 50 at 50' maximum spacing or 1 Type 3 or 1 Type 3 borricode barricade STOCKPILE On one-way roads Desirable downstream drums stockpile location Channelizing devices parallel to traffic or barricade may be is outside should be used when stockpile is omitted here clear zone.

TRAFFIC CONTROL FOR MATERIAL STOCKPILES


 \Diamond

➾

28" Cones shall have a minimum weight of 9 1/2 lbs.

42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

- 1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- 2. One piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base. or ballast, that is added to keep the device upright and in place.
- 3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to gid in retrieving the device.
- 4. Cones or tubular markers shall have white or white and arange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
- 5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 6. 42" two-piece cones, vertical panels or drums are suitable for all work zone
- 7. Cones or tubular markers used on each project should be of the same size and shape.





Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21

			8				
FILE:	bc-21.dgn	DN: T)	DOT	ck: TxDOT	DW:	TxDOT	ск: ТхD0
© TxD0T	November 2002	CONT	SECT	JOB		HIG	HWAY
	REVISIONS	0952	01	064		FM	1008
9-07	8-14	DIST		COUNTY		8	SHEET NO.
7-13	5-21	BMT		LIBERT	Υ	1	2.3

WORK ZONE PAVEMENT MARKINGS

- 1. The Contractor shall be responsible for maintaining work zone and existing povement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- 2. Color, polterns and dimensions shall be in conformance with the Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 3. Additional supplemental povement marking details may be found in the plans or specifications.
- 4. Povement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- 5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard povement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing
- 7. All work zone povement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns
- 2. All raised povement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- 1. Removable prefabricated povement markings shall meet the requirements
- 2. Non-removable prefabricated povement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- 1. The Contractor will be responsible for maintaining work zone payement markings within the work limits.
- 2. Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- 4. Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per

REMOVAL OF PAVEMENT MARKINGS

- 1. Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- 2. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- 3. Povement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Povement Markings and Markers".
- 4. The removal of povement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- 5. Subject to the approval of the Engineer, any method that proves to be successful on a particular type povement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised pavement markers shall be as directed by the
- 9. Removal of existing povement markings and markers will be paid for directly in occordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- 1. Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- 2. Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the
 - A Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - B. Select five (5) tobs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic povement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear lires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new povements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- 1. Raised povement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- 2. All temporary construction raised povement markers provided on a project shall be of the same manufacturer.
- 3. Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pod for all surfaces, or thermoplastic for concrete

Guidemarks shall be designated as: YELLOW - (two omber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of preguglified reflective raised povement markers. non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web oddress shown on BC(1).

SHEET 11 OF 12





Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21

02	8-14	BMT		LIBERT	Y		24
REVISIONS -98 9-07 5-21 02 7-13		DIST	COUNT		Y		SHEET NO.
		0952	01	064		FM	11008
1xT(OT February 1998	CONT	SECT	JOB		HIG	SHWAY
	be-21.dgn	DN: T)	DOT	ск: ТхDОТ	DW:	TxDOT	ск: ТхDОТ





	LEGEND								
	Type 3 Barricade	••	Channelizing Devices						
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)						
a	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)						
-	Sign	♡	Traffic Flow						
\Diamond	Flag	Ъ	Flagger						

Posted Speed	peed	Minimum Desiroble Toper Lengths x x		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance	
×		10° Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	B	
30	2	150'	165'	180'	30.	60'	120'	90'	200
35	L- <u>ws²</u>	205	225'	245'	35'	70'	160'	120'	250'
40	1 80	265	295	320	40'	80.	240'	155'	305'
45		450	495	540'	45'	90'	320'	195'	360'
50	1	500'	550	600	50'	100'	400	240'	425'
55	L·ws	550'	605'	660.	55'	110'	500	295	495
60] - "3	600.	660'	720'	60'	120'	600.	350'	570°
65		650	715'	780 ⁻	65 ⁻	130	700	410'	645'
70		700'	770'	840'	70'	140'	800.	475'	730
75	1	750°	825'	900.	75'	150	900.	540'	820'

- **▼** Conventional Roads Only
- * * Taper lengths have been rounded off.
- L-Length of Taper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

	TYPICAL USAGE								
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY								
4 4									

GENERAL NOTES

- 1. Flags attached to signs where shown are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4D "ONE LANE ROAD AHEAD" sign, but proper sign spacing shall be maintained.
- . Sign spacing may be increased or an additional CW20-1D "ROAD WORK AHEAD" sign may be used if advance worning ahead of the flagger or R1-2 "YIELD" sign is less than 1500 feet.
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- . Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect wider work spaces.

TCP (1-2a)

- 7. R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work spaces should be no longer than one half city block. In rural areas on roadways with less than 2000 ADT, work spaces should be no longer than 400 feet.
- B. R1-2 "YIELD" sign with R1-2aP "TO ONCOMING TRAFFIC" plaque shall be placed on a support at a 7 foot minimum mounting height.

TCP (1-2b)

- 9. Flaggers should use two-way radios or other methods of communication to control traffic.
- . Length of work space should be based on the ability of flaggers to communicate.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain adequate stopping sight distance to the flagge and a queue of stopped vehicles (see table above).
- . Channelizing devices on the center-line may be omitted when a pilot car is leading
- traffic and approved by the Engineer. 13. Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP(1-2)-18

1-97 2-18	ВМТ		LIBERT	Υ	2	26
2-94 2-12	DIST		COUNTY		S	HEET NO.
4-90 4-98	0952	01	064		FM	800
© TxD0T December 1985	CONT	SECT	JOB		HIGH	YAWH
FILE: tcp1-2-18.dgn	DN:		ск:	DW:		CK:



CW20-4 48" X 48 ONE LANE ROAD ROAD WORK CW3-4 XXX FT 48" X 48" AHEAD BE PREPARED CW20-1D 48" X 48" (Flags-See note 1) TO STOP CW20-7 XXX FEET ω END CW16-2P ROAD WORK 24" X 18" A G20-2 Except in 48" X 24" emergencies, flagger stations shall be illuminated at night Temporary 24" Stop Line (See Note 2) 100' Approx. Devices at 20' spacing Shodow Vehicle with TMA and high intensity rotating, floshing, oscillating or strobe lights. (See notes 6 & 7) CW20-7 48" X 48" Devices at 20' spacing on the Toper XXX FEET CW16-2P 24" X 18" ▲ Except in emergencies, flagger stations shall be BE PREPARED illuminated TO STOP CW3-4 48" X 48" Temporary (See note 2) 24" Stop Line (See Note 2) ONE LANE \Diamond ∣ ↔ ROAD XXX FT CW20-4 48" X 48" **END** ROAD ROAD WORK WORK G20-2 48" X 24" AHEAD CW20-1D 48" X 48" (Flags-See note 1) TCP (2-2b) 2-LANE ROADWAY WITHOUT PAVED SHOULDERS

> ONE LANE TWO-WAY CONTROL WITH FLAGGERS

	LEGEND								
~~~	_	Type 3 Barricade	• •	Channelizing Devices					
	Þ	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)					
Ê	Trailer Mounted Flashing Arrow Board			Portable Changeable Message Sign (PCMS)					
_		Sign	♡	Traffic Flow					
$\bigcirc$		Flag	9	Flagger					
-	Т	Minimum Suggested	Maximum	( , , , , , , , , , , , , , , , , , , ,					

V\							- 53-		<u> </u>
Posted Speed			Minimum Desirable Taper Lenglhs x x		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spocing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance
×		10" Offset	11" Offset	12° Offset	On a Taper	On a Tangent	Distance	B	
30	2	150'	165'	180'	30'	60'	120'	90,	200
35	L. <u>ws²</u>	205'	225	245'	35'	70'	160'	120'	250'
40	1 80	265'	295	320	40'	80.	240'	155'	305'
45		450	495'	540'	45'	90'	320'	195'	360'
50		500	550'	600.	50'	100'	400'	240 ⁻	425'
55	l.ws	550	605'	660'	55'	110'	500'	295'	495'
60	] - " -	600.	660'	720'	60'	120'	600,	350'	570'
65		650	715'	780'	65'	130'	700'	4 10'	645'
70		700 ⁻	770'	840'	70'	140'	800'	475'	730 ⁻
75		750'	825	900.	75'	150'	900.	540'	820'

- Conventional Roads Only
- * * Toper lengths have been rounded off.
  - L-Length of Toper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM STATIONARY STATIONARY								

# GENERAL NOTES

- I. Flags attached to signs where shown, are REQUIRED.
- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved
- 3. The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
- . Flaggers should use two-way radios or other methods of communication to control traffic.
- 5. Length of work space should be based on the ability of flaggers to communicate
- 5. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- . Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

# TCP (2-20)

- 8. The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roodways with less than 2000 ADT, work space should be no longer than 400 feet. 9. The R1-2oP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum
- mounting height.

# TCP (2-2b)

- 10.Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer
- 11.If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles.
- 12.Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situlations.



Traffic Operations Division Standard

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL


TCP(2-2)-18

FILE: tcp2-2-18.dgn	DN:		CK:	DW:		CK:
© TxDOT December 1985	CONT	SECT	JOB		HIGH	HWAY
REVISIONS 8-95 3-03	0952	01	064		FM	1008
1-97 2-12	DIST		COUNTY			SHEET NO.
4-98 2-18	ВМТ		LIBERT	Y	1	27

# X VEHICLE WORK OR CONVOY CONVOY CW21-10cT CW21-10aT 72" X 36" 60" X 36" ••••• X VEHICLE CONVOY


# TRAIL/SHADOW VEHICLE A


with RIGHT Directional display Flashing Arrow Board



TCP (3-1b)

# TWO-WAY ROADWAY WITH PAVED SHOULDERS





TRAIL/SHADOW VEHICLE B


with Flashing Arrow Board in CAUTION display

	LEGEND									
*	Trail Vehicle	ADDOW DOADD DISDLAY								
* *	Shadow Vehicle	ARROW BOARD DISPLAY								
* * *	Work Vehicle	RIGHT Directional								
	Heavy Work Vehicle	<b>F</b>	LEFT Directional							
	Truck Mounted Attenuator (TMA)	<b>#</b>	Double Arrow							
♦	Traffic Flow	CAUTION (Alternating Diamond or 4 Corner Flash)								

TYPICAL USAGE									
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM TERM STATIONARY STATIONARY								
4	1								

### **GENERAL NOTES**

- 1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD VEHICLE and/or TRAIL VEHICLE are required based on prevailing roadway conditions, traffic volume, and sight distance restrictions.
- 2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.
- 3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE ore required.
- 4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8300, Type A.
- 5. Flashing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- 6. Each vehicle shall have two-way radio communication capability.
- 7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shodow the other convoy vehicles.
- 8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they opproach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors.
- 9. "X VEHICLE CONVOY" (CW21-10cT) or "WORK CONVOY" (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" X 48" diamond shaped "WORK CONVOY"(CW21-10T) or "X VEHICLE CONVOY" (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation
  "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- 10. On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to poss the work convoy, a "DO NOT PASS" (R4-1) sign should be placed on the back of the rearmost protection vehicle.







# TRAFFIC CONTROL PLAN MOBILE OPERATIONS UNDIVIDED HIGHWAYS

TCP(3-1)-13

Traffic Operations Division Standard


1-97	2007	BMT		LIBERT	Υ		28
8-95 7-1		0952 01 064 FM1008  DIST COUNTY SHEET NO.					
2-94 4-9	REVISIONS R	0952	01	064		FM	1008
© TxD0T	December 1985	CONT	SECT	JOB		HIG	HWAY
FILE:	tcp3-1.dgn	DN: T)	DOT	ck: TxDOT	DW:	TxDOT	ск: ТхD0






# TRAIL/SHADOW VEHICLE A

with RIGHT Directional display





# TRAIL/SHADOW VEHICLE B

with Flashing Arrow Board in Caution Mode



ADVANCE WARNING VEHICLE





TYPICAL USAGE									
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY								
J	1								

# GENERAL NOTES

- 1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as illustrated. When a LEAD vehicle is not used on two way roads the WORK vehicle must have an arrow board. For divided roadways, the arrow board on the WORK vehicle is optional based on the type of work being performed. The Engineer will determine if the LEAD vehicle and/or TRAIL vehicle are required based on
- prevailing roadway conditions, traffic volume, and sight distance restrictions.

  2. The use of amber high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating, or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the amber beacons or strobe lights.

  The use of truck mounted attacked attacked as INAL as the SINAL with the side of the vehicle may be operated.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE, ADVANCE WARNING
- ond TRAIL VEHICLE ore required.

  4. Reflective sheeting on the reor of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION
- DMS 8300, Type A.
  Floshing arrow boards shall be Type B or Type C as per the Barricade and Construction (BC) standards. The board shall be controlled from inside the

- 6. Each vehicle shall have two-way radio communication capability.
  7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to shadow the other convoy vehicles.
  8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change
- should be oble to see the IRAL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and SHADOW VEHICLE and vehicle spacing between WORK VEHICLE and LEAD VEHICLE may vary according to terrain, work activity and other factors. 

  X VEHICLE CONVOY (CW21-10cT) or WORK CONVOY (CW21-10aT) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option 48" x 48" diamond shaped WORK CONVOY (CW21-10T) or X VEHICLE CONVOY (CW21-10bT) signs may be used where adequate mounting space exists. When used, the X VEHICLE CONVOY sign shall have the number of the convoy vehicles displayed on the sign in the number designation "X" location. The X VEHICLE CONVOY sign shall not be used on the SHADOW VEHICLE if a TRAIL VEHICLE is used.
- 10.For divided highways with two or three lanes in one direction, the appropriate
  LEFT LANE CLOSED (CW20-5bTL), RIGHT LANE CLOSED (CW20-5bTR), or CENTER LANE
  CLOSED (CW20-5dT) sign should be used on the Advance Warning Vehicle. As an option, a portable changeable message sign (PCMS) or truck mounted changeable message sign (TMCMS) with a minimum character height of 12", and displaying the same legend may be substituted for these signs. An appropriate directional arrow display, simulating the size and legibility of the flashing arrow board may be used in the second phase of the PCMS/TMCMS message. When this is done, the arrow board will not be required on the Advance Warning Vehicle.

  11.A double arrow shall not be displayed on the arrow board on the Advance Warning
- 12.For divided highways with three or four lanes in each direction, use TCP(3-2).
  13.Standard diamond shape versions of the CW20-5 series signs may be used as an
- option if the rectangular signs shown are not available.

  14.The Advance Warning Vehicle may straddle the edgeline when Shoulder width makes it necessory.
- 15.On two-lane two-way roadways, the work and protection vehicles should pull over periodically to allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a DO NOT PASS (R4-1) sign should be placed on the back of the rearmost protection vehicle.




Traffic Operations Division Standard

TRAFFIC CONTROL PLAN MOBILE OPERATIONS RAISED PAVEMENT MARKER INSTALLATION/ REMOVAL TCP(3-3)-14

1-97 7-14		ВМТ		LIBERT	Υ		29
8-95 7-13		DIST		COUNTY			SHEET NO.
REVISIONS 2-94 4-98		0952	01	064		FM	1008
©TxDOT Septe	mber 1987	CONT	SECT	JOB		HIGI	HWAY
FILE: tcp3	3.dgn	DN: Tx	DOT	ск: TxDOT	DW:	TxDOT	ск: TxD0


ATE: 6/21/2024




- Short term pavement markings may be prefabricated markings (stick down tape) or temporary flexible reflective roadway marker tabs unless otherwise specified elsewhere in plans.
- 2. Short term pavement markings shall NOT be used to simulate edge lines.
- 3. Dimensions indicated on this sheet are typical and approximate. Variations in size and height may occur between markers or devices made by manufacturers, by as much as 1/4 inch, unless otherwise noted.
- 4. Temporary flexible-reflective roadway marker tabs will require normal maintenance replacement when used on roadways with an ADT per lane of up to 7500 vehicles with no more than 10% truck mix. When roadways exceed these values, additional maintenance replacement of devices should be planned.
- 5. No segment of roadway open to traffic shall remain without permanent pavement markings for a period greater than 14 calendar days. The Contractor will be responsible for maintaining short term pavement markings until permanent pavement markings are in place. When the Contractor is responsible for placement of permanent pavement markings, no segment of roadway shall remain without permanent pavement markings for a period greater than 14 calendar days unless weather conditions prohibit placement. Permanent pavement markings shall be placed as soon as weather permits.
- 6. For two lane, two-way roadways, DO NOT PASS signs shall be erected to mark the beginning of sections where passing is prohibited and PASS WITH CARE signs shall be erected to mark the beginning of sections where passing is permitted. Signs shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and may be used to indicate the limits of no-passing zones for up to 14 calendar days. Permanent payement markings should then be placed.
- 7. For low volume two lane, two-way roadways of 4000 ADT or less, no-passing lines may be omitted when approved by the Engineer. DO NOT PASS and PASS WITH CARE signs shall be erected (see note 6).
- 8. For exit gores where a lane is being dropped place wide gore markings or retroreflective channelizing devices to guide motorist through the exit. If channelizing devices are to be used it should be noted elsewhere in the plans. One piece cones are not allowed for this purpose.

# TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS (TABS)

- 1. Temporary flexible-reflective roadway marker tabs detailed on this sheet will be designated Type Y-2 (two amber reflective surfaces with yellow body); Type Y (one amber reflective surface with yellow body); and Type W (one white or silver reflective surface with white body). Additional details may be found on BC(11).
- 2. Tabs shall meet requirements of Departmental Material Specification DMS-8242
- 3. When dry, tabs shall be visible for a minimum distance of 200 feet during normal daylight hours and when illuminated by automobile low-beam head light at night, unless sight distance is restricted by roadway geometrics.
- 4. No two consecutive tabs nor four tabs per 1000 feet of line shall be missing or fail to meet the visual performance requirements of Note 3.





If raised pavement markers are used to supplement REMOVABLE short term markings, the markers shall be applied to the top of the tape at the approximate mid length of the tape. This allows an easier removal of raised markers and tape.

# PREFABRICATED PAVEMENT MARKINGS

- 1. Temporary Removable Prefabricated Pavement Markings shall meet the requirements of DMS-8241
- Non-removable Prefabricated Pavement Markings shall meet the requirements of either DMS-8240 "Permanent Prefabricated Pavement Markings" or DMS-8243 "Temporary Costruction-Grade Prefabricated Pavement Markings."

# RAISED PAVEMENT MARKERS

 All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and DMS-4200.

# DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS) & MATERIAL PRODUCER LISTS (MPL)

1. DMSs referenced above can be found along with embedded links to their respective MPLs at the following website:

http://www.txdot.gov/business/contractors_consultants/material_specifications/default.htm



WORK ZONE SHORT TERM PAVEMENT MARKINGS

Traffic Safety Division Standard

WZ(STPM)-23

ILE:	WZ	stpm-23.dgn	DN:		CK:	DW:	CK:
) Txl	TOC	February 2023	CONT	SECT	JOB		HIGHWAY
	170 1074	REVISIONS	0952	01	064		FM1008
-92 -97	7-13 2-23		DIST		COUNTY		SHEET NO.
-03			BMT		LIBERT	Υ	30

DEPARTMENTAL MATERIAL SPECIFICATIONS					
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240				
TEMPORARY (REMOVABLE) PREFABRICATED PAVEMENT MARKINGS	DMS-8241				
SIGN FACE MATERIALS	DMS-8300				


COLOR	USAGE	SHEETING MATERIAL
ORANGE	BACKGROUND	TYPE B _{FL} OR TYPE C _{FL} SHEETING
BLACK	LEGEND & BORDERS	ACRYLIC NON-REFLECTIVE SHEETING

# GENERAL NOTES

- If spolling or holes occur, ROUGH ROAD (CW8-8) signs should be placed in advance of the condition and be repeated every two miles where the condition persists.
- UNEVEN LANES (CW8-11) signs shall be installed in advance of the
  condition and repeated every mile. Signs installed along the uneven
  lone condition may be supplemented with the NEXT XX MILES (CW7-3oP)
  plaque or Advisory Speed (CW13-1P) plaque.
- 3. NO CENTER LINE (CW8-12) signs and temporary pavement markings as per the WZ(STPM) standard shall be installed if yellow centerlines separating two way traffic are obscured or obliterated. Repeat NO CENTER LINE signs every two miles where the center line markings are not in place. The signs and markings shall remain in place until permanent pavement markings are installed.
- 4. Signs shall be spaced at the distances recommended as per BC standards.
- Additional signs may be required as directed by the Engineer. Signs shall remain in place until final surface is applied. Signs shall be considered subsidiary to Item 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING."
- Signs shall be fabricated and mounted on supports as shown on the BC standards and/or listed on the "Compliant Work Zone Traffic Control Devices" list
- 7. Short term markings shall not be used to simulate edge lines.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition.

	TABLE 1							
Edge Condition	Edge Height (D)	* Warning Devices						
0	Less than or equal to: 11/4" (maximum-planing) 11/2" (typical-overlay)	Sign: CW8-11						
	Distance "D" may be a maximum of 11/4 " for planing operations and 2" for overlay operations if uneven lanes with edge condition 1 are open to traffic after work operations cease.							
② >3 1 1 0 0	Less than or equal to 3"	Sign: CW8-11						
3 0" to 3/4" 7 0 12"	Distance "D" may be a maximum of 3" if uneven lanes with edge condition 2 or 3 are open to traffic after work operations cease. Uneven lanes should not be open to traffic when "D" is greater than 3".							
Notched Wedge Joint								

TRAFFIC CONTROL DURING PLANING, OVERLAY AND LEVELING OPERATIONS ARE SHOWN ELSEWHERE IN THE PLANS.



SIGNING FOR

Texas Department of Transportation


WZ(UL)-13

UNEVEN LANES

Traffic Operations Division Standard

FILE:		wzul-13.dgn	DN: T	OOT	ск: ТхDОТ	DW:	TxDOT	ск: ТхD0
© Tx	DOT	April 1992	CONT	SECT	JOB		HIG	HWAY
		REVISIONS	0952	01	064		FM	1008
8-95	2-98	7-13	DIST		COUNTY		8	SHEET NO.
1-97	3-03		ВМТ		LIBERT	Υ		.31

112



# GENERAL NOTES

- . Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- 2. The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- 4. Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- 10.Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

LEGEND							
	Type 3 Barricade	••	Channelizing Devices				
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)				
<b>(1)</b>	Trailer Mounted Floshing Arrow Panel		Portable Changeable Message Sign (PCMS)				
1	Sign	Ŷ	Traffic Flow				
$\Diamond$	Flag	Ф	Flagger				

Posted Speed	Formula	Desiroble		Spacir Channel		Minimum Sign Spacing	Suggested Longitudinal Buffer Space	
×		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	B
30	2	150'	165'	180'	30'	60'	120'	90 [,]
35	L. WS ²	205'	225'	245'	35'	70'	160'	120'
40	1 80	265'	295'	320'	40'	80.	240'	155'
45		450'	495	540	45'	90.	320'	195'
50		500'	550	600.	50'	100'	400'	240'
55	L-ws	550 ⁻	605	660'	55'	110'	500'	295'
60	] " " "	600.	660	720'	60'	120'	600,	350'
65		650	715	780'	65'	130'	700'	410'
70	]	700	770	840'	70'	140'	800.	475'
75		750 ⁻	825	900.	75'	150'	900'	540 [.]

- **▼** Conventional Roads Only
- x x Toper lengths have been rounded off. L-Length of Toper(FT) W-Width of Offset(FT) S-Posted Speed(MPH)

TYPICAL USAGE							
MOBILE	MOBILE SHORT SHORT TERM STATIONARY		INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY			
	1	1					

- Signs are for illustrative purposes only. Signs required may vary depending on the TCP,TMUTCD Typical Application, or project specific details for the project.
- For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.

TABLE 2							
Speed	Approximate distance between strips in an array						
< 40 MPH	10'						
> 40 MPH & <_55 MPH	15′						
= 60 MPH	20'						
≥ 65 MPH	* 35'+						





Traffic Safety Division Standard


# TEMPORARY RUMBLE STRIPS

WZ(RS)-22

4-10		BMT		LIBERT	Y		32	
2-14 ° 4-16	1-22	DIST		COUNTY		8	SHEET NO.	
0.44	REVISIONS	0952	01	064		FM	1008	
)TxD0T	November 2012	CONT	SECT	JOB		HIG	HWAY	
E:	wzrs22.dgn	DN: Txl	DOT	ск: ТхDОТ	DW:	TxDOT	ск: TxDOT	







**AXIS OF ROTATION** 

POINT OF INTERSECTION	167+55, 88
DEFELCTION ANGLE	39°49′ 32. 4" (LT)
DEGREE OF CURVE	07°34′24.9"
TANGENT DISTANCE	274. 05'
LENGTH	525. 85'
RADUIS	756. 52'
DESIGN SPEED	45
SUPER ELEVATION, Se	6%

SUPERELEVATION DIAGRAMS ARE NOT REPRESENTATIVE OF ACTUAL EXISTING CROSS-SECTIONS. THE DIAGRAMS ARE SHOWN FOR THE CONTRACTOR'S INFORMATION REGARDING THE METHOD OF ATTAINING SUPERELEVATION AND ILLUSTRATE THE STATION LIMITS OF EACH TRANSITIONS SEGMENT. QUANTITIES WERE DERIVED FROM SURVEYED CROSS-SECTIONS. PROPOSED SUPERELEVATIONS TRANSITION FROM EXISTING CROSS -SLOPE.

DASHED LINE REPRESENTS EXISTING CONDITION. SOLID LINE REPRESENTS PROPOSED SLOPE TO BE ATTAINED IN EACH STEP.

ARROWS INDICATE THE DIRECTION OF CHANGE.

** AT THIS PHASE THE DETAIL IS INDICATING A TRANSITION, NO MILLING IS REQUIRED



-50238C8D55F5470..


FM 1008
SUPER ELEVATION DETAILS
CURVE DATA



N.T.S.

2 01 064 FM1008

COUNTY SHEET NO
LIBERTY 36



## **GENERAL NOTES**


- Rumble strips and profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- Use Standard Sheet PM(2) and FPM(1) for positioning, dimensioning, and spacing
  of all reflective raised pavement markers, pavement markings, and profile
  markings.
- See the Shoulder Width Table below for determining what options may be used for edge line rumble strips.
- Breaks in edge line rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections, or driveways with high usage of large trucks when installed on conventional highways.
- Rumble strips shall not be placed across exit or entrance ramps, acceleration or deceleration lanes, crossovers, gore areas, or intersections with other roadways.
- Consideration should be given to noise levels when edgeline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these areas.
- 8. Consideration shall be given to bicyclists. See RS(6).

# WHEN INSTALLING MILLED DEPRESSION EDGE LINE RUMBLE STRIPS:

- 9. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
- 10. Pavement markings can be applied over milled shoulder rumble strips to create an edge line rumble strip.

# WHEN INSTALLING RAISED OR PROFILE EDGE LINE RUMBLE STRIPS:

- 11. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per the manufacturer's recommendations.
- 12. Non-reflective traffic buttons shall be placed adjacent to the pavement marking delineating the edge line when used as a rumble strip. The color of the button should match the color of the adjacent edge line marking (white or yellow). The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- 13. Non-reflective traffic buttons shall not be placed across exit or entrance ramps, acceleration and deceleration lanes, crossovers, gore areas or intersections with other roadways.
- 14. The minimum distance between the edge line and the buttons should be used if the shoulder is less than 8 feet in width.
- Raised profile thermoplastic markings used as edge lines may substitute for buttons.



24" ±1/2" **PROFILE VIEW** PROFILE VIEW PROFILE VIEW is standard is governed by the "Texas Engineering Practice Act". No warranty of any TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the convex to other formats or for incorrect results or damages resulting from its use. Non-reflective raised traffic **₩**0 Centerline or black) markings Centerline Centerline markings markings 0 0 .09 0 See Note 6 -See Note 6 RPM -See Note 6 RPM (reflectorized) 0 (reflectorized) (reflectorized) Non-reflective raised traffic buttons (black) 16" ±1/2" Preformed thermoplastic rumble strips ♦┃♦ PLAN VIEW PLAN VIEW PLAN VIEW OPTION 1 OPTION 2 OPTION 3 PROFILE CENTERLINE MARKINGS PREFORMED THERMOPLASTIC TWO LANE TWO-WAY MILLED CENTERLINE RAISED CENTERLINE

**RUMBLE STRIPS** 

**HIGHWAYS** 

**RUMBLE STRIPS** 

CENTERLINE RUMBLE STRIPS

## **GENERAL NOTES**

PROFILE VIEW

centerline markings

See Note 6 RPM

(reflectorized)

Preformed

PLAN VIEW

OPTION 4

**RUMBLE STRIPS** 

AND PREFORMED THERMOPLASTIC

**RUMBLE STRIPS** 

- 1. This standard sheet provides guidelines for installing centerline rumble strips on two-lane highways with or without shoulders.
- 2. Centerline and edge line rumble strips or profile markings shall not be placed on roadways with a posted speed limit of 45 MPH or less.
- 3. Milled rumble strips are preferred when adequate pavement depth is available. If pavement thickness is less than 2 inches, milled rumble strips shall not be used. Rumble strips shall not be milled or depressed into bridge decks.
- 4. See dimensions for milled rumble strips. Other shapes and dimensions may be used if approved by the Traffic Safety Division.
- 5. Breaks in milled centerline rumble strips shall occur at least 50 feet and no more than 150 feet in advance of bridges, railroad crossings, intersections or driveways with high usage of large trucks.
- 6. Use standard sheet PM(2) for positioning, dimensioning, and spacing of all reflective raised pavement markers, pavement markings and profile
- 7. Consideration should be given to noise levels when centerline rumble strips are to be installed near residential areas, schools, churches, etc. A 3/8 inch deep (minimum) milled rumble strip may be considered in these
- 8. Pavement markings must be applied over milled centerline rumble strips.

# WHEN INSTALLING CENTERLINE RUMBLE STRIPS

- 9. Raised rumble strips consisting of non-reflective raised traffic buttons may be used. Non-reflective raised traffic buttons can be affixed to asphalt or concrete with bitumen or adhesives, as per manufacturer's recommendations.
- 10. When using non-reflective raised traffic buttons as a centerline rumble strip, the button shall be placed adjacent to the pavement marking delineating the centerline. The buttons will be paid for under Item 672, "Raised Pavement Markers." Non-reflective traffic buttons must meet the requirements of DMS-4300.
- 11. The color of the button should be yellow for a continuous no passing roadway. Black buttons should be used in areas where passing is allowed.
- 12. Consideration shall be given to bicyclists. See RS(6).

WHEN INSTALLING EDGE LINE RUMBLE STRIPS WITH OR WITHOUT CENTERLINE RUMBLE STRIPS ON UNDIVIDED HIGHWAYS:

13. See standard sheet RS(2).



Traffic Safety Division Standard

**CENTERLINE RUMBLE STRIPS** ON TWO LANE TWO-WAY HIGHWAYS RS(4)-23

		\ /				
FILE: rs(4)-2	23.dgn	DN: Tx	DOT	ск: TxDOT	w: TxDOT	ск:TxDOT
C TxDOT	January 2023	CONT	SECT	JOB	HIG	HWAY
	EVISIONS	0952	01	064	FM	1008
10-13 1-23		DIST		COUNTY		SHEET NO.
		BMT		LIBERTY	1	38

** SEE LAYOUT SHEETS FOR DEPTH AND TYPE OF TOM.

LONGITUDINAL JOINTS SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL EXTEND BEYOND THE NORMAL LAND WIDTH. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVISE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. TACK COAT SHALL BE APPLIED TO THE IN-PLACE TAPER BEFORE THE ADJACENT MAT IS PLACED. FINAL DENSITY REQUIREMENTS FOR THE ENTIRE PAVEMENT, INCLUDING THE TAPER AREA, WILL REMAIN UNCHANGED.

PAVEMENT EDGES SHALL BE CONSTRUCTED BY TAPERING THE BITUMINOUS MAT. THE TAPERED PORTION SHALL BE PLACED WITHIN THE NORMAL LANE WIDTH UNLESS OTHERWISE SHOWN ON THE PLANS. THE TAPERED PORTION OF THE MAT SHALL BE CONSTRUCTED BY THE USE OF AN APPROVED SCREED ATTACHMENT WHICH WILL PRODUCE THE DESIRED SHAPE WITH THE MAIN SCREED. USE OF AN EXTERNAL STRIKE-OFF DEVICE TO MODIFY THE MAT SHAPE AFTER PASSING OF THE SCREED WILL NOT BE ALLOWED. COMPACTION OF THE PAVEMENT EDGE TAPER WILL BE REQUIRED TO AS NEAR TO FINAL DENSITY AS POSSIBLE.



-50238C8D55F5470..

7/3/2024

Texas Department of Transportation

HOT MIX

LONGITUDINAL

AND.


PAVEMENT EDGE

JOINT DETAILS


FED.RD. DIV.NO.				SHEET NO.
				39
STATE	DIST.		COUNTY	
TEXAS	BMT		LIBERT	Y
CONT.	SECT.	JOB	HIG	HWAY NO.
0952	0.1	064	FM	1008

NOTES:

# DRIVEWAY & PUBLIC ROADS OVERLAY TAPER



# **PLAN**



# OVERLAY TAPER NOTES:

**ELEVATION** 

1) - FOR COUNTY ROADS "L" EQUALS THE DISTANCE TO THE ROW. PLACE 1.5" HMA TY-D, SAC -A PG 76-22. THIS WILL BE PAID FOR UNDER ITEM 530.

2) - FOR RESIDENTIAL ACP/CONCRETE DRIVEWAYS "L" EQUALS 5' PLACE 1.5" HMA TY-D, SAC -A PG 76-22 AND TAPER TO EXISITNG SURFACE. HMA WILL BE PAID FOR UNDER ITEM 530.

3) - FOR RESIDENTIAL FLEX BASE DRIVEWAYS "L" EQUALS 5' PLACE 1.5" FLEXABLE BASE AND TAPER TO EXISTING SURFCE FLEX BASE WILL BE PAID FOR UNDER ITEM 530.

- 4) UNLESS OTHERWISE NOTED, PROVIDE MATERIALS MATCHING WHAT IS USED ELSEWHERE ON THE PROJECT.
- 5) PROVIDE SMOOTH TRANSITIONS TO EXISTING ROADWAY AND DRIVEWAYS.
- 6) SEE DRIVEWAY & PUBLIC ROAD SUMMARY SHEET FOR MORE INFORMATION

	DRIVEWAY & PUBLIC ROAD DATA SHEET													
				TYPE	,	PRIVATE	DUDI IC		P	ROP. DWY WORK		WIDTH	LENGTH	AREA
DWY#	STATION	LEFT	RIGHT			DRIVE		NAME	CUT & REST⊕R	CD AVELAY	FB OVERLAY		DENGTH	/ INE/
				ACP/CON GRAV./ F	GRASS				COT & RESTUR	SF WELHI	FB UVERLHI	FT	FT	SY
1	170+85		×	Х		Х				×		30	5	17



-DocuSigned by: 7/3/2024

50238C8D55F5470...

N.T.S.




DRIVEWAY & PUBLIC ROAD DETAILS


2024

CONT	SECT	JOB	HIGHWAY
0952	01	064	FM1008
DIST		COUNTY	SHEET NO.
BMT		LIBERTY	40

# INTERSECTING ROADWAY CLEARING




# TYPICAL CLEARING SECTION






# NOTES:

- 1. ALL TREE LIMBS EXTENDING INTO THE CLEARING LIMITS WILL BE REMOVED TO A MINIMUM HEIGHT OF SIXTEEN FEET (16') ABOVE THE ADJACENT PAVEMENT EDGE ELEVATION.
- 2. CLEARING OPERATIONS SHALL BE PERFORMED IN ACCORDANCE WITH ITEM 100, "PREPARING THE RIGHT OF WAY", EXCEPT THOSE SHOWN BY THESE DETAILS.
- 3. ALL STUMPS WITHIN THE CLEARING LIMITS SHALL BE REMOVED BY GRUBBING, EXCEPT IN AREAS NEAR UNDERGROUND UTILITIES.
- 4. WHERE CLEARING IS REQUIRED NEAR EXISING UNDERGROUND UTILITIES, TREES AND STUMPS ARE NOT TO BE GRUBBED. FOR THOSE CONDITIONS, THE RIGHT OF WAY SHALL BE PREPARED BY CUTTING AND GRINDING OF STUMPS AND ROOTS AS DIRECTED.
- 5. ON AREAS TO BE COVORED BY AT LEAST THREE (3) FEET OF EMBANKMENT, TREES AND STUMPS MAY BE CUT OFF AS CLOSE TO NATURAL GROUND AS PRACTICABLE.
- 6. WHERE STEEP SLOPES MAKE GRINDING OPERATIONS IMPRACTICAL, AND THE ENGINEER AGREES IN WRITING, THE CONTRACTOR MAY CUT STUMPS OFF EVEN WITH THE GROUND.
- 7. AT ALL INTERSECTING ROADWAYS, CLEARING SHALL EXTEND TO THE RIGHT OF WAY LINE FOR 200'.



# STUMP GRINDING DETAIL





CLE ARING DETAIL



NTS

MID-SPAN

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE

REQUIRED WITH 6'-3" POST SPACINGS.

RAIL SPLICE DETAIL

FBB01 - 11/4"

POST & BLOCK LENGTH

BUTTON HEAD BOLT NOTE: SEE GENERAL NOTE 3 FOR

SPLICE & POST BOLT DETAILS.

FBB02 - 2"

FBB03 - 10"

FBB04 - 18"

# GENERAL NOTES

- 1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER, STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
- 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAL ELEMENTS OF 25'- 0", OR 12'- 6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL
- 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 1/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
- 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445,"GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
- 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
- 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
- 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
- 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
- 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT, BACKFILL WITH COARSE AGGREGATE MATERIAL.
- 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
- 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
- 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPI MAY FURNISH COMPOSITE MATERIAL BLOCKS.
- 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
- 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL, WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

NOTE: TRANSISTIONS TO BRIDGE RAILS OR TRAFFIC BARRIERS. SEE GF(31)TL3 TR STANDARD FOR HIGH-SPEED TL-3 TRANSITIONS. SEE GF(31)TL2 TR STANDARD FOR LOW-SPEED TL-2 TRANSITIONS.

NOTE: TWO INSTALLATION OPTIONS.

(TYP)

1" X 1 1/2"

SLOTTED HOLES

CULVERT SLAB).

STEEL POST CONNECTION TO

CULVERT SLAB (USE WHEN THERE IS LESS THAN 36" COVER OVER

12"(TYP)

41/2 41/2

(TYP)

12"x 12"x 1/8"

ASTM A572 GR 50)TOP PLATE I" DIA. HOLES FORMED OR CORED IN CONCRETE

W6 X 9 OR W6 X 8.5

STEEL POST

**GUARDRAIL** 

BLOCK

BOLT-THROUGH OPTION: REQUIRES A 6" MIN. SLAB THICKNESS 1/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH . SLAB PLUS 2 1/4" MIN.

2. EPOXY ANCHOR OPTION: THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK, THREADED ANCHOR RODS MUST BE 1/4" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH, EMBED ANCHOR RODS 6" WITH HILTIHIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTIHIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA, FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS, EXTEND RODS 1/4" MIN. BEYOND NUT.


NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

Texas Department of Transportation

METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT

GF(31)-19


	BMT		LIBER	TY	42
	DIST		COUNT	Υ	SHEET NO.
REVISIONS	0952	01	064		FM1008
CTXDOT: NOVEMBER 2019	CONT	SECT	JOB		HIGHWAY
FILE: gf3119.dgn	DN: T×DOT		ск: КМ	ow:VP	ck: CGL/AG



DIRECTION OF TRAFFIC

(8) 3" X 1 4" BUTTON HEAD SPLICE

BOLTS WITH RECCESSED NUTS.



# **GENERAL NOTES**

- CONTACT THE DESIGN DIVISION FOR DRAINAGE CUT OUT OPTIONS NEEDED WITHIN THE CURB SECTION OF THE THRIE-BEAM TRANSITION. (512) 416-2678
- CONCRETE CURB MAY BE CAST-IN-PLACE OR PRECAST AS SHOWN ON THIS SHEET. WHEN USED IN CONJUNCTION WITH THE THRIE-BEAM TRANSITIONS, CURB SHALL BE TYPE II 15- 1/4"
  HEIGHT): SEE CURRENT CCCG STANDARD SHEET FOR FURTHER DETAILS IF OTHER CURB HEIGHTS
  ARE SHOWN IN THE PLANS IN CONJUNCTION WITH THE TRANSITION, THE CURB HEIGHT MAY BE FROM 4" TO 8" WITH A RELATIVELY VERTICAL FACE. CONCRETE CURB SHALL BE CONTINUOUS TO THE SEVENTH POST UNLESS OTHERWISE SHOWN IN THE PLANS. SEE GENERAL NOTE:17 FOR CIRCUMSTANCES WHERE CURB CONTINUES PAST POST 7.
- CONCRETE CURB TYPE II SUBSIDIARY TO "METAL BEAM GUARD FENCE TRANSITION". IF NO ADDITIONAL CURB IS INDICATED BEYOND THE TRANSITION, THEN ANY CURB HEIGHT GREATER THAN 4" WILL BE TAPERED DOWN BEGINNING AT THE LAST 7 FT. POST TO A MAXIMUM HEIGHT OF 4" AT POST 7. IF SHOWN ELSEWHERE IN THE PLANS, ADDITIONAL CURB UNDERNEATH
- 4. UNLESS OTHERWISE SHOWN IN THE PLANS, TRANSITIONS SHALL BE PLACED WITH THE BLOCKOUT FACE IN FRONT OF OR DIRECTLY ABOVE THE CURB FACE. SEE SECTION A-A.
- 5. FOR ROUND WOOD POST SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7  $^{1}\!\!/_{2}$ " DIA. MINIMUM THROUGHOUT THE THRIE-BEAM TRANSITION.
- THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. REFER TO GF(31) STANDARD SHEET.
- THE POST LENGTH SHALL BE MARKED ON ALL 7'- O" LONG POSTS BY THE MANUFACTURER. THE MARK SHALL BE LOCATED WITHIN THE TOP 1FT. REGION OF THE POST, AT LEAST %" IN HEIGHT, AND VISIBLE AFTER INSTALLATION. WOODEN POSTS SHALL BE MARKED WITH A BRAND, AND STEEL POSTS WITH A STENCIL BEFORE GALVANIZING.
- POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
- RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED ON THE PLANS. THE THRIE-BEAM TERMINAL CONNECTOR AND THE THRIE-BEAM TRANSITION TO W-BEAM SHALL BE OF THE SAME MATERIAL, BUT SHALL NOT BE LESS THAN 10 GAUGE. CONTRACTOR SHALL VERIFY THAT THE LOCATIONS OF BOLT HOLES MATCH THOSE IN THE THRIE-BEAM TERMINAL CONNECTOR PRIOR TO ORDERING MATERIALS.
- BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 56" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
- FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
- CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
- WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
- UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. TXDOT'S MATERIALS AND TESTS DIVISION MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE
- REFER TO GF(31)STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
- THE INSTALLATION OF THE TYPE II CURB IS CRITICAL FOR THE PERFORMANCE OF THE THRIE-BEAM TRANSITION SYSTEM. THE CURB PREVENTS (VEHICLE WHEEL SNAGGING) AT THE CONCRETE RAIL AND IS REQUIRED TO MEET MASH CRASH TEST CRITERIA.
- IF CURB EXTENDS BEYOND POST 7, 25' OF NESTED W-BEAM GUARDRAIL SHALL BE INSTALLED BEYOND THE PAY LIMITS OF THRE-BEAM TRANSITION SECTION, (SEE SHT.2). PAYMENT FOR THIS 25' SECTION WILL BE BY LINEAR FOOT, PAY ITEM "0540 6XXX MTL W-BEAM GD FEN (NESTED)(TIM POST)" OR "540 6XXX MTL W-BEAM GD FEN (NESTED)(STEEL POST)" AS APPLICABLE FOR POST TYPE, SEE SHT.2 FOR ADDITIONAL INFORMATION.

# HIGH-SPEED TRANSITION

SHEET 1 OF 2





METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT

GF(31)TR TL3-20

FILE: gf31trtl320.dgn	DN: Tx	DOT	ck: KM	pw:VP	ck: CGL/AG
©TXDOT: NOVEMBER 2020	CONT	SECT	JOB		HIGHWAY
REVISIONS	0952	01	064		FM1008
	DIST		COUNT	Y	SHEET NO.
	ВМТ		LIBERT	Y Y	43


REQUIRED ALTERNATIVE FOR CONTINUOUS CURB EXTENDING PAST POST 7 (SEE SHT. 1 GENERAL NOTE 17)





ELEVATION VIEW

SECTION D-D



# THRIE BEAM TRANSITION BLOCKOUT DETAILS

# HICH-SPEED TRANSITION

SHEET 2 OF 2




Division Standard

METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION TL-3 MASH COMPLIANT

GF(31)TR TL3-20

FILE: gf31trtl320.dgn	DN: Tx	DOT	ck: KM	DW: KM	ck:CGL/AG
©TXDOT: NOVEMBER 2020	CONT	SECT	JOB		HIGHWAY
REVISIONS	0952	01	064		FM1008
	DIST		COUNT	Υ	SHEET NO.
	ВМТ		LIBER1	ΓY	44

18" x 18" min. or



Minimum 1'-10" beyond

Note: See SGT standard sheets for


proper installation and length

Site conditions may exist where grading is required for the proper installation of metal quard fence and

Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.

# GENERAL NOTES

- This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard
- 2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprop." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
- 3. The leave-out behind the post shall be a minimum of 7".
- 4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
- 5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
- 7. The limits of payment for reinforced concrete will include leave-outs for the posts.
- 8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprop mow strip.





2'-0"


Design Division Standard

METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT

GF(31)MS-19

FILE: gf31ms19.dgn	DN: Tx	DOT	ck: KM	DW:VP	ck:CGL/AG	
©TXDOT: NOVEMBER 2019	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0952	01	064		FM1008	
	DIST		COUNT	Y	SHEET NO.	
	ВМТ		LIBERT	Υ	45	

NOTE: TOENAIL WITH ONE 16D GALV.



**GENERAL NOTES** 

End of Check for horizontal –Bridge Roil clearance protection Front Slope (See General Notes 4,5 & 6) 25' MBGF MBGF Transition SGT (25:1 Straight Toper) (See note 1) (See note 10) (See note 9) MBGF length of need (L) SGT plus 25' MBGF plus MBGF Transition is the minimum length of need (L) required. Begin or end structure MBGF length of need (L) MBGF Transition MBGF (6'- 3" Spacing) SGT (25:1 Straight Taper) (See Note 10) (See note 1) (See note 9) Front Slope Break TWO LANE (RURAL) HIGHWAYS Fnd of Note: SGT rail taper may be decreased or eliminated. (See SGT standard sheets) Bridge Rail End of Bridge Roil Front Slope Break **MBGF** Transition MBGF (6'- 3" Spacing) (See Note 10) SGT (25:1 Straight Taper) (See note 1) (See note 9) MBGF length of need (L) (Two or more lanes in each direction) -Begin or end structure DAT Terminal , 2'- 0" Typ. * See GF(31)DAT for minimum MBGF required. 9'-4 1/2" (See note 7) Front slope Check for horizontal Downstream Bridge Front Slope clearance protection MULTILANE UNDIVIDED (RURAL) HIGHWAYS End (See Detail A) See General Notes 4,5 & 6) End of TYPICAL CROSS SECTION -Front Slope Bridge Rail Break MBGF Transition SGT (25:1 Straight Taper) MBGF (6'- 3" Spacing) (See Note 10) (See note 1) (See note 9) MBGF length of need (L) Begin or end structure ONE WAY TRAFFIC number of lones) MBGF length of need (L) MBGF Transition SGT (25:1 Stroight Toper) MBGF (6'- 3" Spacing) (See Note 10) (See note 1) (See note 9) ONE WAY TRAFFIC ∠End of Front Slope Bridge Roil Break

# **GENERAL NOTES**


- 1. For more detail: See GF(31), SGT( )31, GF(31)TR, and GF(31)TL2 standard sheets.
- 2. Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
- 3. Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume
- 4. MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
- 5. Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
- 6. Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic.
  (This requires a minimum of three standard line posts plus the DAT terminal,
- 7. The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'- 0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
- 8. For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge location(s) shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft."maximum" offset from the shoulder edge in the approach direction.
- 9. Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
- 10. A minimum 25' length of MBGF will be required.

See GF(31) standard

for post types.

Edge of shoulder


AT MBGF



All rail elements shall be lapped in the direction of adjacent traffic.

DETAIL A

Showing Downstream Rail Attachment



	DMT		LIBERT	~		47
SEE (MEMO D414)	DIST		COUNTY			SHEET NO.
REVISIONS REVISED APRIL 2014	0952	01	064		FM	1008
CTxDOT: December 2011	CONT	SECT	JOB		HIG	HWAY
FILE: bed14.dgn	DN: Tx[	OT.	ck: AM	DW:	BD/VP	ск: CGL

NOTE: STEEL I-BEAM POST W6 X 8.5 (6'-0") PN:533G STANDARD WOOD BLOCKOUTS (6"X8"X14") PN:4076B %" X 10" HGR BOLT PN:3500G LINE AT THE BACK OF POST *2 THRU *8 FROM THE CENTERLINE OF POST(1) & POST(0) %" HGR NUT PN:3340G AT (POSTS 2 THRU 8) ANCHOR PADDLE ANGLE STRUT PN:15204A PN:15202G POST(8) POST(7) POST(6) POST(5) POST(4) POST(3) /POST(1) DO NOT BOLT SEE DETAL POST(0) PLAN VIEW BEGIN LENGTH OF NEED ANCHOR RAIL TO - POST (2) MASH TEST LEVEL 3 (TL-3) LENGTH OF SoftStop TERMINAL (50'-9 1/2") TRAFFIC FLOW 50'-9 1/2" STANDARD INSTALLATION LENGTH (MASH TL-3 SoftStop) END PAYMENT FOR SGT BEGIN STANDARD ANCHOR RAIL WITH SLOTS - (THREADED THRU HEAD)
SEE SoftStop MANUAL FOR COMPLETE DETAILS OUTSIDE SLOTS CUTOUT SoftStop FACE MBGF LAPPED IN DIRECTION OF TRAFFIC FLOW SEE GN(3) 25'-0" DOWNSTREAM W-BEAM GUARDRAIL PN:61G SoftStop ANCHOR RAIL (12GA) PN:15215G & NOTE:B 3-1/2"(-/-) **⊸** B ANCHOR PADDLE 6'-3" PN:15204A SEE MOTE:C END OF ANCHOR RAIL PN:15215G POST 32" DO NOT BOLT ANCHOR RAIL TO RAIL 25'-0" PN:61G RAIL 25'-0" PN:15215G SEE A HEIGHT SEE 2 POST(2) RAIL HEIGHT RAIL HEIGHT 13/16DIA. YIELDING 13/16 DIA. (8) %"x 1- 1/4" HGR BOLTS PN:3360G (8) %"* 1- 1/4" GR BOLTS PN:3360G YIELDING POST 40" DEPTH %" HEX NUTS PN:3340G %" HEX NUTS PN:3340G SEE 3 (TYP 1-8) 6-1% POST(2) 6'-0" (SYTP) POSTO POST(8) POST(7) POST(6) POST(5) POST(4) POST(3) 4'-9 1/2" SYTP PN: 15203G HARDWARE FOR POST(2) THRU POST(8) **ELEVATION VIEW** PN: 15000G (1) %"x 10" HGR BOLT PN:3500G (1) %" HGR HEX NUT PN:3340G ANGLE STRUT (1) 3/8" x 1 3/4" PN: 15202G NOTE: DO NOT BOLT ANCHOR RAIL PANEL TO POST(2) POST(0) HEX HD BOLT PN 3391G ALTERNATE BLOCKOUT PN: 152054 SEE GENERAL NOTE:6 (2) %" WASHERS 6" X 8" X 14" (1) 3/6" HEX NUT (1) 1/6" x 1- 1/2" HEX HD BOLT-GR-5 ANCHOR PLATE WASHER PN 4372G (1) %" HGR HEX NUT BLOCKOUT 1/2" THICK PN:15206G BLOCKOUT COMPOSITE ANCHOR KEEPER WOOD PN:105286 1" ROUND WASHER F463 PN:4902G PN:4076B PN 3340G PLATE (24 GA) (2) %6 PN:6777B NOTE: DO NOT BOLT ANCHOR RAIL TO ROUND WASHERS PN:15207G DETAIL 1 PN:3240G ALTERNATE BLOCKOUT (2) 1/6" x 2 1/2" HEX 6" X 8" X 14" SHOWN AT POST(1) POST(2) BLOCKOUT WOOD HD BOLT GR-5 W-BEAM RAIL NEAR GROUND PN:105285G 25'-0" BLOCKOUT WOOD W-BEAM RAIL DETAIL 2 GENERAL NOTE %" HGR NUT PN:3340G HGR POST BOLT SHOWN AT POST(1) (2) %6" ROUND WASHER HGR POST BOLT PN:3500G HGR POST BOLT (WIDE) PN:3240G PN:3500G %" HGR NUT PN:3340G %" HGR NUT PN:3340G -1" NUT PN:3908G SHALL BE SECURELY TIGHTENE POST 32" HEIGHT POST ANCHOR PADDLE -HEIGHT (2) %" HEX NUT A563 GR.DH 31" RAIL 31" RAIL PN: 15204A 13/6DIAMETER YIELDING HOLES AFTER FINAL ASSEMBLY, BUT NOT DEFORMING TH LOCATED IN FLANGES W-BEAM FLATTENED KEEPER PLATE. (4 PLIES) POST 17"- 1/2" SEE NOTE: A CHOLES APROXIMATELY CENTERED HEIGHT FINISHED PN: 15202G -FINISHED AT FINISHED GRADE) GRADE GRADE 13/6 DIA. (2) 3/4" x 2 1/2" HEX BOLT (TYP) PN:3717G YIELDING HOLES 4 - 9 1/2" POST(2) LINE POST (4) 34" FLAT WASHER (2) ¾" HEX NUT (TYP) PN:3704G POST(1) 6'- 1%" POST DEPTH ISOMETRIC VIEW SECTION VIEW B-B SECTION VIEW A-A (2) ANCHOR POST ANGLE PN:15201G POST(1 & 2) 6'-0" (W6 X 8.5) I-BEAM POST PN: 533G 6'-0" (W6 X 8.5) (SYTP) I-BEAM POST PN:15000G W6 X 8.5 I-BEAM POST SHOWING FRONT VIEW POST(1) STANDARD WOOD BLOCKOUT NOTE: DO NOT BOLT ANCHOR RAIL PANEL TO POST(2) 4'-9 1/2" (W6 X 8.5) (SYTP) I-BEAM POST PN:15203G NOTE: NO BLOCKOUT INSTALLED AT POST(1) NOTE: NO BLOCKOUT INSTALLED AT POST(1) DETAIL 3 AT POST(0) 2.-0.. 50' APPROACH GRADING APPROX 5'-10' 6'-5 ¾" (W6 X 15) STANDARD I-BEAM POST PN:15205A TRAFFIC FLOW APPROACH GRADING (1V:10H OR FLATTER)
SEE PRODUCT ASSEMBLY MANUAL EDGE OF PAVEMENT NOTE: ADJUST WIDTH ACCORDINGLY WHEN OFFSET IS USED. (OFFSET "OPTION" SHOWN) RAIL OFFSET FOR ADDITIONAL GUIDANCE. THIS STANDARD IS A BASIC REPRESENTATION OF THE SOILSTOP END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL. APPROACH GRADING AT GUARDRAIL END TREATMENTS

## GENERAL NOT

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374. 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
- 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207

  2. FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE:
  SOILStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN:620237B
- 3. APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS.
  OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- 4. FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- 5. HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE CALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
- 6. A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- 7. IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
- 8. POSTS SHALL NOT BE SET IN CONCRETE.
- 9. IT IS ACCEPTABLE TO INSTALL THE SOLISION IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
- 10. DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
- 11. UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
- 12. A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCROACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTE:A	THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.
NOTE:B	PART PN:58528 RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN:58518 LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)
NOTE:C	W-BEAM SPLICE LOCATED BETWEEN LINE POST(4)AND LINE POST(5) GUARDRAIL PANEL 25'-0" PN:61G ANCHOR RAIL 25'-0" PN:15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

		MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25'- 0")
15205A	1	POST *0 - ANCHOR POST (6'- 5 %")
15203G	1	POST *1 - (SYTP) (4'- 9 1/2")
15000G	1	POST *2 - (SYTP) (6'- 0")
533G	6	POST =3 THRU =8 - I-BEAM (W6 x 8.5) (6'- 0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" x 8" x 14")
67778	7	BLOCKOUT - COMPOSITE (4" x 7 1/2" x 14")
15204A	1	ANCHOR PADDLE
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER ( 1/2" THICK )
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT
		HARDWARE
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	¾" × 2 ½" HEX BOLT A325
3701G	4	¾" ROUND WASHER F436
3704G	2	¾" HEAVY HEX NUT AS63 GR.DH
3360G	16	%" x 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	%" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	%" x 10" HCR POST BOLT A307
3391G	1	%" × 1 ¾" HEX HD BOLT A325
4489G	1	%" x 9" HEX HD BOLT A325
4372G	4	%" WASHER F436
105285G	2	%6" × 2 1/2" HEX HD BOLT GR-5
105286G	1	%6" x 1 1/2" HEX HD BOLT GR-5
3240G	6	%" ROUND WASHER (WIDE)
3245G	3	% HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE:B
	15215G 61G 15205A 15205A 15200G 533G 40768 6777B 15204A 15207G 15206G 15201G 15202G 4902G 3908G 3717G 3701G 3704G 3360G 3340G 3500G 3590G 4489G 4372G 105285G 105285G 105286G 3240G	15215G 1 61G 1 15205A 1 15203G 1 15203G 1 15000G 1 533G 6 4076B 7 67778 7 15204A 1 15207G 1 152



Design Division Standard

TRINITY HIGHWAY
SOFTSTOP END TERMINAL
MASH - TL-3

SGT(10S)31-16

301	(103)	JI	- 10		
ILE: sgt10s3116	DN: TxE	OT	ck: KM	pw:VP	ck: MB/VP
CTxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY
REVISIONS	0952	01	064		FM1008
	DIST		COUNT	Y.	SHEET NO.
	BMT		LIBERT	ſΥ	48

# GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
- 2. FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MANMAX REV D (ECN 3516).
- 3. APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURE'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- 4. FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- 5. ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
- 6. SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
- 7. COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST(MPL)FOR CERTIFIED PRODUCERS.
- 8. REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
- 9. IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
- 10. POSTS SHALL NOT BE SET IN CONCRETE.
- 11. A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
- 12. MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
- 13. IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
- 14. THE SYSTEM IS SHOWN WITH 12"-6" MBGF PANELS, 25"-0" MBGF PANELS ARE ALSO ALLOWED.
- 15. A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM #	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FTGALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	%" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	¾" x 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	%" X 11/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	%" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	%" WASHER F436 STRUCTURAL MGAL	2
20	4001116	%" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	%" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25 W-BEAM GUARDRAIL PANEL,8-SPACE,12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1



Design Division Standard

MAX-TENSION END TERMINAL

MASH - TL-3

SGT(11S)31-18

ILE: sgt11s3118.dgn	DN: TxD	ОТ	ck: KM	DW: TxDOT	ck: CL
TxDOT: FEBRUARY 2018	CONT	SECT	JOB H		SHWAY
REVISIONS	0952	01	064	FI	W1008
	DIST		COUNT	Υ	SHEET NO.
	ВМТ		LIBER1	Y	49

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
- FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
- 3. APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- 4. FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- 5. HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
- 6. SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
- 7. A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- 8. IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBGF STANDARD FOR INSTALLATION GUIDANCE.
- 11. UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
- 12. A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCROACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
- 13. THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN THEIR PLACE.
- 14. A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.


ITEM	OTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
Α	1	MSKT IMPACT HEAD	MS3000
В	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
С	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
Ε	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
Н	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6x9 OR W6x8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
0	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
Ρ	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
		SMALL HARDWARE	
0	2	%6" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	%6" WASHER	W0516
C	2	%6" HEX NUT	N0516
d	25	%" Dio. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	%" Dio. x 9" HEX BOLT (GRD A449)	B580904A
f	3	%" WASHER	W050
9	33	%" Dia. H.G.R NUT	N050
h	1	¾" Dio. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	¾" Dio. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
Î	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
0	8	1 1/16" O.D. x 1/6" I.D. STRUCTURAL WASHERS	W012A
ρ	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	%" × 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151

Design Division Standard Texas Department of Transportation


SINGLE GUARDRAIL TERMINAL MSKT-MASH-TL-3

SGT(12S)31-18

	ВМТ		LIBERT	Υ Υ	50
	DIST		COUNT	Υ	SHEET NO.
REVISIONS	0952	01 064 FM100			FM1008
xDOT: APRIL 2018	CONT	SECT	JOB		HIGHWAY
: sgt12s3118.dgn	DN: Tx	DOT	CK: KM	DW:VP	CK: CL




20A



# MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS


		WITH ADVISORI	SPEEDS		
Г	Amount by which Advisory Speed	Curve Advisory Speed			
	is less than Posted Speed	Turn (30 MPH or less)	Curve (35 MPH or more)		
	5 MPH & 10 MPH	• RPMs	• RPMs		
1.	5 MPH & 20 MPH	<ul> <li>RPMs and One Direction Large Arrow sign</li> </ul>	<ul> <li>RPMs and Chevrons; or</li> <li>RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.</li> </ul>		
s resulting from its us	25 MPH & more	RPMs and Chevrons; or     RPMs and One Direction     Large Arrow sign where     geometric conditions or     roadside obstacles prevent     the installation of     chevrons	RPMs and Chevrons		

# SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



# SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES

approach lane.



# DELINEATOR AND CHEVRON **SPACING**

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN

	FEET						
Degree of Curve	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve			
		Α	2A	В			
1 5	730	225	450				
2	2865	160	320				
3	1910	130	260	200			
4	1433	110	220	160			
5	1146	100	200	160			
6	955	90	180	160			
7	819	85	170	160			
8	716	75	150	160			
9	637	75	150	120			
10	573	70	140	120			
11 :	521 65	13	0 120				
12	478	60	120	120			
13	441	60	120	20			
14	409	55	110	80			
15	382	55	110	80			
16	358	55	110	80			
19	302	50	100	80			
23	249	40	80	80			
29	198	35	70	40			
38	151	30	60	40			
57	101	20	40	40			

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

# DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN

Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	Α	2×A	В
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

# DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING		
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets		
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table		
Frwy/Exp.Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents  Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)		
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))		
Truck Escape Ramp	Single red delineators on both sides	50 feet		
Bridge Rail (steel or concrete)and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction  Single Delineators when multiple lanes each direction	Equal spacing (100'max) but not less than 3 delineators		
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max		
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100'max)		
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end  Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)		
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)		
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end  See D & OM (5)		
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)		
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)		
Pavement Narrowing (lane merge)on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet		

- 1. Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- 2. Barrier reflectors may be used to replace required delineators.
- 3. Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications


**LEGEND** Bi-directional Delineator  $\mathbf{x}$ Delineator Sign



**DELINEATOR &** OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20

FILE: d	om3-20.dgn	DN: TX[	TO	ck: TXDOT	DW: T	XDOT	ск: ТХДО
© TxD0T	August 2004	CONT	SECT	JOB		HIG	HWAY
	REVISIONS	0952	01	064		FM	1008
3-15 8-15		DIST	•	COUNTY			SHEET NO.
8-15 7-20	)	ВМТ		LIBERT	Y		53



## TWO-WAY, TWO LANE ROADWAY TWO-WAY, TWO LANE ROADWAY TWO-WAY, TWO LANE ROADWAY WITH REDUCED WIDTH APPROACH RAIL WITH METAL BEAM GUARD FENCE (MBGF) BRIDGE WITH NO APPROACH RAIL See Note 1 See Note 1 See Note 1 丛 出 LAMMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion is graded to the conversion of the conversion of the conversion of the conversion is use. 25 ft. 25 ft. 3- Type 出 3- Type D-SW D-SW delineators delineators spaced 25' spaced 25' 常 apart 出 出 MBGF Type D-SW Type D-SW delineators delineators $\stackrel{\wedge}{\mathbb{A}}$ \\ bidirectional bidirectional $\stackrel{\mathsf{A}}{\bowtie}$ One barrier One barrier reflector shall reflector shall be ploced $\stackrel{\wedge}{\bowtie}$ $\stackrel{\wedge}{\mathbb{A}}$ Steel or concrete be placed directly behind Bridge rail directly behind each OM-3. each OM-3. The others The others $\stackrel{\wedge}{\mathbb{A}}$ will have Steel or concrete will have equal spacing ₿ $\stackrel{\mathsf{H}}{\bowtie}$ Bridge rail equal spacing (100' max), but (100' max), but not less than 3 Bidirectional not less than 3 bidirectional Bidirectional white barrier bidirectional white barrier white barrier reflectors or white barrier Equal spacing reflectors reflectors or $\stackrel{\mathsf{H}}{\bowtie}$ delineators reflectors (100' max), but Equal spacing delineators (100' max), but not less than 3 bidirectional not less than 3 bidirectional white barrier reflectors or white barrier Equal $\stackrel{\mathsf{A}}{\bowtie}$ $\stackrel{\mathsf{A}}{\bowtie}$ $\stackrel{\mathsf{A}}{\bowtie}$ delineators Equal reflectors or spacing spacing delineators (100' max), (100' max), but not but not less than less than 3 total. 3- Type $\mathbf{x}$ $\mathbf{x}$ $\stackrel{\mathsf{H}}{\bowtie}$ $\stackrel{\mathsf{A}}{\bowtie}$ 3 total. 3- Type $\stackrel{\wedge}{\mathbb{A}}$ D-SW delineators MBGF delineators spaced 25' spaced 25' apar t $\mathbf{x}$ $\mathbf{x}$ apart $\stackrel{\wedge}{\mathbb{A}}$ Type D-SW $\mathbf{x}$ ਸ _ਾ Type D-SW délineators Shoulder delineators bidirectional $\stackrel{\mathsf{A}}{\triangleright}$ $\stackrel{\wedge}{\bowtie}$ MBGF **LEGEND** 25 ft. 25 ft. 25 ft. Texas Department of Transportation $\stackrel{\mathsf{A}}{\bowtie}$ Bidirectional Delineator **DELINEATOR &** $\mathbf{R}$ Delineator See Note **OBJECT MARKER** PLACEMENT DETAILS NOTE: NOTE: OM-2 D & OM(5)-201. Terminal ends require reflective 1. Terminal ends require reflective sheeting provided by manufacturer sheeting provided by manufacturer per D & OM (VIA) or a Type 3 per D & OM (VIA) or a Type 3 $\Box$ Terminal End TxDOT August 2015 Object Marker (OM-3) in front of Object Marker (OM-3) in front 0952 01 064 FM1008 the terminal end. of the terminal end. raffic Flow LIBERTY 55

# **GENERAL NOTES**

6" Solid Yellow Line

-6" Solid White Edge Line

ALLEY, PRIVATE ROAD

OR MINOR DRIVEWAY

' Solid

Edge Line

6" Solid

Yellow Line

 $\Diamond$ 

 $\Diamond$ 

♦

♦

3" to 12" + |+

being marked equal to or greater than 45 MPH.

YIELD LINES

For posted speed on road


being marked equal to or less than 40 MPH.

_

- 1. Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- 2. The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.

MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.




NOTE: Traveled way is exclusive of shoulder widths.

Refer to General Note 2 for additional details.


# GUIDE FOR PLACEMENT OF STOP LINES. EDGE LINE & CENTERLINE

Based on Traveled Way and Pavement Widths for Undivided Roadways


3-03 12-22




LIBERTY



# CENTERLINE FOR ALL TWO LANE TWO-WAY ROADWAYS




# CENTERLINE & LANE LINES FOR FOUR LANE TWO-WAY ROADWAYS




# Continuous two-way left turn lane Type II-A-A 40' 40' Type II-C

# CENTERLINE AND LANE LINES FOR TWO-WAY LEFT TURN LANE



# LANE LINES FOR ONE-WAY ROADWAY (NON-FREEWAY FACILITIES)

Raised povement markers Type II-C-R shall have clear face toward normal traffic and red face toward wrong-way traffic. See Note 3.




# **GENERAL NOTES**


- All raised pavement markers placed along broken lines shall be placed in line with and midway between the stripes.
- On concrete pavements, the raised pavement markers should be placed to one side of the longitudinal joints.
- Use raised povement marker Type I-C with undivided roadways, flush medians, and two way left turn lanes. Use raised povement marker Type II-C-R with divided highways and raised medians.

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
TRAFFIC PAINT	DMS-8200
HOT APPLIED THERMOPLASTIC	DMS-8220
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240

All povement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



Type I(Top View)



35° max25° min

Roadway Surface

SECTION A

RAISED PAVEMENT MARKERS



Traffic Safety Division Standard

POSITION GUIDANCE USING RAISED MARKERS REFLECTORIZED PROFILE MARKINGS PM(2)-22

FILE: pm2-22.dgn	DN:		ск:	DW:	CK:
© TxD0T December 2022	CONT	SECT	JOB		HIGHWAY
REVISIONS 4-77 8-00 6-20	0952	01	064		FM1008
4-92 2-10 12-22	DIST		COUNTY	1	SHEET NO.
5-00 2-12	ВМТ		LIBERT	Υ	57

22B

OF SMALL SUMMARY SIGNS SM RD SGN ASSM TY XXXXX BRIDGE £ £ MOUNT CLEARANCE POST TYPE POSTS ANCHOR TYPE MOUNTING DESIGNATION SIGNS SIGN SIGN PREFABRICATED | 1EXT or 2EXT = # of Ext UA=Universal Conc STA. DIMENSIONS (See SIGN NOMENCLATURE NO. FRP = Fiberglass UB•Universal Bolt Note 2) BM = Extruded Wind Beam TWT = Thin-Wall SA=Slipbose-Conc WC = 1.12 #/ft Wing P = "Plain" 1 or 2 TY = TYPE 10BWG = 10 BWG SB=Slipbase-Bolt T = "T" Channe I S80 = Sch 80 WS=Wedge Steel U = "U" EXAL = Extruded Alum Sign TY N WP=Wedge Plastic Panels TY S CSJ: 0952-01-069 SYMBOL-HORIZ CURVE LEFT 36 × 36 Р 65+50 W1-2L **S80** SA 67+40 2 W1-8L < CHEVRON LEFT>  $18 \times 24$ X S80 1 SA Р < CHEVRON RIGHT> W1-8R  $18 \times 24$ < CHEVRON LEFT> 18 × 24 S80 SA Р 68+60₁ W1-8L W1-8R < CHEVRON RIGHT>  $18 \times 24$ 69+80 < CHEVRON LEFT> 18 × 24 S80 SA D W1-8L W1-8R < CHEVRON RIGHT> 18 × 24 < CHEVRON LEFT> 71+00 W1-8L  $18 \times 24$ **S80** SA W1-8R < CHEVRON RIGHT>  $18 \times 24$ SA 72+20 W1-8L < CHEVRON LEFT>  $18 \times 24$ **S80** Р W1-8R < CHEVRON RIGHT>  $18 \times 24$ 73+40 W1-8L < CHEVRON LEFT>  $18 \times 24$ X **S80** SA Р < CHEVRON RIGHT> W1-8R  $18 \times 24$ <CHEVRON LEFT> Р 74+60 8 W1-8L  $18 \times 24$ **S80** 1 SA < CHEVRON RIGHT> W1-8R  $18 \times 24$ <CHEVRON LEFT> 18 × 24 75+80 9 W1-8L X **S80** SA Р W1-8R < CHEVRON RIGHT> 18 × 24 Р 77+70 10 W1-2R SYMBOL-HORIZ CURVE RIGHT 36 × 36 **S80** SA X 1 CSJ: 0952-01-064 163+21 30 × 18 SA Р 11 X 10BWG I - 3 BOWIE CREEK SA Р 164+22 12 I - 3 BOWIE CREEK  $30 \times 18$ X 1 ØBWG 1 166+10 13 18 × 24 SA Р < CHEVRON LEFT> Х 10BWG W1-8L 1 < CHEVRON RIGHT> W1-8R  $18 \times 24$ <CHEVRON LEFT> 18 × 24 10BWG SA Р 167+63 14 X W1-8L 1 W1-8R < CHEVRON RIGHT> 18 × 24 <CHEVRON LEFT> 169+33 15 W1-8L 18 × 24 SA Р X 10BWG 1 W1-8R <CHEVRON RIGHT> 18 × 24 170+00 16 D20-1TL COUNTY ROAD (631)  $24 \times 24$ 10BWG SA 1 171+55 17 M1-6F FARM ROAD 1008  $24 \times 24$ l x l SA Р 10BWG 1 D10-7aT REFERENCE MARKER < 4 5 0>  $3 \times 10$ W8-13aT BRIDGE MAY ICE IN COLD WEATHER 36 × 36 171+56 18 10BWG 1 SA Р

ALUMINUM SIGN BLANKS THICKNESS					
Square Feet	Minimum Thickness				
Less than 7.5	0.080"				
7.5 to 15	0.100"				
Greater than 15	0.125"				

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

http://www.txdot.gov/

# NOTE:

- 1. Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.
- 2. For installation of bridge mount clearance signs, see Bridge Mounted Clearance Sign Assembly (BMCS) Standard Sheet.
- 3. For Sign Support Descriptive Codes, see Sign Mounting Details Small Roadside Signs General Notes & Details SMD(GEN).

Texas Department of Transportation


Traffic Operations Division Standard


SUMMARY OF SMALL SIGNS


SOSS

FILE	sums 16. dgn	ON: TxC	OT	CK: TxDOT	DWs	TxDOT	ck: TxD0
© 1×DO1	May 1987	CONT	SECT	JOB		H	CHWAY
	REVISIONS	0952	01	064		FM	11008
4-16 8-16		DIST		COUNTY	9		SHEET NO.
0 10		BMT		LIBER	ΤΥ		58


18







FM 1008 SMALL SIGN DETAILS



CONT	SECT	JOB	HIGHWAY	
0952	01	064	FM1008	
DIST		COUNTY	SHEET NO.	
BMT		LIBERTY	50	


12" Dia

SM RD SGN ASSM TY XXXXX(X)SA(X-XXXX)

# NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

# CONCRETE ANCHOR



diometer stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxies and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psinormalweight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

Concrete anchor consists of 5/8"

# GENERAL NOTES:

- 1. Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- 2. Material used as post with this system shall conform to the following specifications:

10 BWG Tubing (2.875" outside diameter)

0.134" nominal wall thickness

Seamless or electric-resistance welded steel tubing or pipe

Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008

Other steels may be used if they meet the following:

55,000 PSI minimum yield strength

70,000 PSI minimum tensile strength

20% minimum elongation in 2"

Wall thickness (uncoated) shall be within the range of 0.122" to 0.138"

Outside diameter (uncooted) shall be within the range of 2.867" to 2.883" Galvanization per ASTM A123 or ASTM A653 G210. For precooted steel tubing (ASTM A653), recoot

tube outside diameter weld seam by metallizing with zinc wire per ASTM 8833.

Schedule 80 Pipe (2.875" outside diameter) 0.276" nominal wall thickness

Steel tubing per ASTM A500 Gr C

Other seamless or electric-resistance welded steel tubing or pipe with equivalent

outside diameter and wall thickness may be used if they meet the following:

46,000 PSI minimum yield strength

62,000 PSI minimum tensile strength

21% minimum elongation in 2"

Wall thickness (uncoated) shall be within the range of 0.248" to 0.304" Outside diameter (uncoated) shall be within the range of 2.855" to 2.895"

Galvanization per ASTM A123

3. See the Traffic Operations Division website for detailed drawings of sign clamps and Texas Universal Triangular Slipbase System components. The website address is:

http://www.txdot.gov/publications/traffic.htm

4. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

# ASSEMBLY PROCEDURE

- 1. Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- 2. The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable. motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- 3. Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- 4. Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- 5. The triangular slipbose system is multidirectional and is designed to release when struck from any


- 1. Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and
- 2. Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.



# SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-1)-08

© TxDOT July 2002	DN: TXI	тос	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08 REVISIONS	CONT	SECT	JOB	H	HIGHWAY
	0952	01	064 FM100		FM1008
	DIST		COUNTY	1	SHEET NO.
	ВМТ		LIBERTY	1	60



-.025"•.010"

Pipe O.D.

·.025"·.010"

Depth

Rolled Crimo to

engage pipe O.D.

SM RD SGN ASSM TY XXXXX(1)XX(T)

(* - See Note 12)

# GENERAL NOTES:

SIGN SUPPORT	• OF POSTS	MAX. SIGN AREA
10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1	32 SF
Sch 80	2	64 SF

- 2. The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- 3. Sign supports shall not be spliced except where shown.
- Sign support posts shall not be spliced.


  4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
- in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of
- greater height.

  7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign ponel. This will allow each support to act independently
- when impacted by an errant vehicle.

  8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.
- Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign ponel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- 10. Additional route markers may be added vertically, provided the total sign area does not exceed the maximum allowable amount per Note 1.
- 11. Additional sign clamp required on the "T-bracket" post for 24 inch height signs. Place the clamp 3 inches above bottom of sign when possible.

  12. Post open ends shall be fitted with Friction Caps.
- 13. Sign blanks shall be the sizes and shapes shown on the

	REQUIRED SUPPORT					
	SIGN DESCRIPTION SUPPORT					
	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)				
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)				
Regulatory	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)				
Regul	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)				
	48x60-inch signs	TY S80(1)XX(T)				
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)				
23000	48x60-inch signs	TY S80(1)XX(T)				
Warning	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)				
WC	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)				
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)				





# SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-2)-08

© TxDOT July 2002	DN: TXE	тос	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08 REVISIONS	CONT	SECT	JOB		HIGHWAY
	0952	01	01 064 FM1		FM1008
	DIST		COUNTY	e .	SHEET NO.
	BMT		LIBERT	Y	61

The depth shall be sufficient to give positive


protection against entrance of rainwater. They

shall be free of sharp creases or indentations and show no evidence of metal fracture.

B633 Closs FE/ZN 8.

Caps shall have an electrodeposited coating of

zinc in accordance with the requirements of ASTM



# GENERAL NOTES:

SIGN SUPPORT	OF POSTS	MAX. SIGN AREA
10 BWG	1	16 SF
10 BWG	2	32 SF
Sch 80	1 1	32 SF
Sch 80	2	64 SF

- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- 3. Sign supports shall not be spliced except where shown.
- Sign support posts shall not be spliced.

  4. Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. (t., 0.100 for signs 7.5 to 15 sq. (t., and 0.125 for signs greater than 15 sq. (t., 5.) Signs that require specific supports due to reasons
- in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- 6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brockets are used for signs of
- greater height.

  7. When two triongular slipbose supports are used to support a single sign, they shall not be "rigidly" connected to each other except through the sign panel. This will allow each support to act independently
- when impacted by an erront vehicle.


  8. Wing channelshall meet ASTM A 1011 SS Gr 50 and be galvanized per ASTM A 123.

  9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- 10. Sign blanks shall be the sizes and shapes shown on
- the plans.

  11. Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.

  12. Post open ends shall be fitted with Friction Cops.

	REQUIRED SUPPORT	
	SIGN DESCRIPTION	SUPPORT
	48-inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
eguiotoi y	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)
nego.	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)
	48x60-inch signs	TY S80(1)XX(T)
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)
	48x60-inch signs	TY \$80(1)XX(T)
Marning	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)
*	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)
	Lorge Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)



# SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD(SLIP-3)-08

© TxDOT July 2002	DN: TXI	тос	CK: TXDOT	DW: TXDOT	CK: TXDOT
9-08 REVISIONS	CONT	SECT	JOB		HIGHWAY
3 00	0952	01	064 FM1008		FM1008
	DIST		COUNTY		SHEET NO.
	BMT		LIBERTY		62








WRONG WAY

# REQUIREMENTS FOR FOUR SPECIFIC SIGNS ONLY

	SHEETING REQUIREMENTS					
USAGE	COLOR	SIGN FACE MATERIAL				
BACKGROUND	RED	TYPE B OR C SHEETING				
BACKGROUND	WHITE	TYPE B OR C SHEETING				
LEGEND & BORDERS	WHITE	TYPE B OR C SHEETING				
LEGEND	RED	TYPE B OR C SHEETING				

REQUIREMENTS FOR WARNING SIGNS





# TYPICAL EXAMPLES

SHEETING REQUIREMENTS						
USAGE	COLOR	SIGN FACE MATERIAL				
BACKGROUND	FLOURESCENT YELLOW	TYPE B _{FL} OR C _{FL} SHEETING				
LEGEND & BORDERS	BLACK	ACRYLIC NON-REFLECTIVE FILM				
LEGEND & SYMBOLS	ALL OTHER	TYPE B OR C SHEETING				

# REQUIREMENTS FOR WHITE BACKGROUND REGULATORY SIGNS

(EXCLUDING STOP, YIELD, DO NOT ENTER AND WRONG WAY SIGNS)





# TYPICAL EXAMPLES

SHEETING REQUIREMENTS						
USAGE	COLOR	SIGN FACE MATERIAL				
BACKGROUND	WHITE	TYPE A SHEETING				
BACKGROUND	ALL OTHERS	TYPE B OR C SHEETING				
LEGEND,BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM				
LEGEND,BORDERS AND SYMBOLS	ALL OTHER	TYPE B OR C SHEETING				

# REQUIREMENTS FOR SCHOOL SIGNS





# TYPICAL EXAMPLES

SHEETING REQUIREMENTS					
USAGE	COLOR	SIGN FACE MATERIAL			
BACKGROUND	WHITE	TYPE A SHEETING			
BACKGROUND	FLOURESCENT YELLOW GREEN	TYPE B _{FL} OR C _{FL} SHEETING			
LEGEND,BORDERS AND SYMBOLS	BLACK	ACRYLIC NON-REFLECTIVE FILM			
SYMBOLS	RED	TYPE B OR C SHEETING			

# **GENERAL NOTES**

- 1. Signs to be furnished shall be as detailed elsewhere in the plans and/or as shown on sign tobulation sheet. Standard sign designs and arrow dimensions can be found in the "Standard Highway Sign Designs for Texas" (SHSD).
- Sign legend shall use the Federal Highway Administration (FHWA) Standard Highway Alphabets (B, C, D, E, Emod or F).
- 3. Lateral spacing between letters and numerals shall conform with the SHSD, and any approved changes thereto. Lateral spacing of legend shall provide a balanced appearance when spacing is not shown.
- 4. Black legend and borders shall be applied by screening process or cut-out acrylic non-reflective black film to background sheeting, or combination
- 5. White legend and borders shall be applied by screening process with transparent colored ink, transparent colored overlay film to white background sheeting or cut-out white sheeting to colored background sheeting, or combination thereof.
- 6. Colored legend shall be applied by screening process with transparent colored ink, transparent colored overlay film or colored sheeting to background sheeting, or combination thereof.
- 7. Sign substrate shall be any material that meets the Departmental Material  $\,$ Specification requirements of DMS-7110 or approved alternative.
- 8. Mounting details for roadside mounted signs are shown in the "SMD series" Standard Plan Sheets.

ALUMINUM SIGN BL	ANKS THICKNESS
Square Feet	Minimum Thickness
Less than 7.5	0.080
7.5 to 15	0.100
Greater than 15	0.125

DEPARTMENTAL MATERIAL SPECIF	ICATIONS
ALUMINUM SIGN BLANKS	DMS-7110
SIGN FACE MATERIALS	DMS-8300

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

http://www.txdot.gov/



Traffic Operations Division Standard

# TYPICAL SIGN REQUIREMENTS

TSR(4)-13


FILE:	tsr4-13.dgn	DN: T	DOT	ck: TxDOT	DW:	TxDOT	ск: TxDOT
© TxD0T	October 2003	CONT	SECT	JOB		HIG	HWAY
REVISIONS		0952	01 064			FM1008	
12-03 7-13 9-08		DIST	COUNTY			SHEET NO.	
3 00		ВМТ		LIBERT	Y		53


# ARROW DETAILS


for Large Ground-Mounted and Overhead Guide Signs

# SIGN BLANK PUNCHING DETAILS FOR ATTACHMENTS WHEN SPECIFIED TO BE TYPE A ALUMINUM SIGNS (FOR MOUNTING TO GUIDE SIGN FACE)


"Y" NO. OF EQUAL SPACES












Down Arrow



U.S. ROUTE MARKERS

Sign Size


24×24

30×24

36×36

45×36 48×48

60×48



STATE ROUTE MARKERS

No. of Digits	W	Х
4	24	4
4	36	5
4	48	6
3	24	3
3	36	4
3	48	5

Type A

TYPE

A-2

A-3

B-1

B-2

B-3

CODE

E-3

E-4

Type B

USE

Single

Exits

Multiple

Exits

LETTER SIZE

10.67" U/L and 10" Caps

13.33" U/L and 12" Caps

16" & 20" U/L

10.67" U/L and 10" Caps

13.33" U/L and 12" Caps

16" & 20" U/L

USED ON SIGN NO.

E5-laT

E5-16T

E-3


Arrow dimensions are shown in the

"Standard Highway Sign Designs for

The Standard Highway Sign Designs for Texas (SHSD) can be found at the following website.

INTERSTATE ROUTE MARKERS

Α	С	D	Ε
36	21	15	11/2
48	28	20	13/4




# http://www.txdot.gov/

NOTE


# MOUNTING DETAILS OF ATTACHMENTS TO GUIDE SIGN FACE

# ("EXIT ONLY" AND "LEFT EXIT" PANELS, ROUTE MARKERS AND OTHER ATTACHMENTS)




# NOTE:

- 1. Sheeting for legend, symbols, and borders must be cut at panel joints.
- 2. Direct applied attachment signs will be subsidiary to "Aluminum Signs" or "Fiberglass Signs".



SCREW ATTACHMENT






# NOTE:

Furnish Type A aluminum sign attachments only when specified in the plans. These signs will be paid for under "Aluminum Signs".

# ARROW DETAILS

for Destination Signs (Type D)



# TYPICAL SIGN

Texas Department of Transportation


TSR(5)-13

REQUIREMENTS


							,	
LE:	tsr5-13.dgn	DN: Tx	OOT	ck: TxDOT pw:		TxDOT	ск: TxDOT	
) TxDOT	October 2003	CONT	CONT SECT JOB		HIGI	HIGHWAY		
REVISIONS		0952	01	01 064			FM1008	
2-03 7-13 9-08	-13	DIST		COUNTY		SHEET NO.		
9-00		BMT	LIBERTY			- 6	54	


# GENERAL NOTES:

- 1. Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
- 2. See Item 685, "Roodside Floshing Beacon Assemblies" for further requirements.
- 3. See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- 4. Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered flashing beacon assemblies.
- 5. When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- 6. Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on poles.
- 7. Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- 8. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- 9. Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening of connection.
- 10. Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL in the file "Roadway Illumination and Electrical Supplies." Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
- 11. Provide clearance as shown above the sidewalk or povement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
- 12. Make connections to ground rods according to NEC. Ground rod clamps shall be listed for their intended purpose.
- 13. Ensure height of conduit and ground rod is below top of anchor bolts.




NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS





**FRONT** 

SIDE



NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS EXPLODED VIEW



Traffic Operations Division Standard


# ROADSIDE FLASHING **BEACON ASSEMBLY**


RFBA-13

98	ВМТ		LIBERT	Υ		65
REVISIONS 93 12-04 93 3-13	DIST	DIST COUNTY			SHEET NO.	
	0952	01	064		FN	11008
TxDOT January 1992	CONT	SECT	JOB		HIS	GHWAY
: rfba-13.dgn	DN: Tx	DOT	ск: ТхDОТ	DW:	TxDOT	ck: TxD07


# 1. Details show a typical other arrangements

- Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
- See Item 685, "Roadside Flashing Beacon Assemblies" for further requirements.
- See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- 4. Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered flashing beacon assemblies.
- When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- Use materials specifically designed for attaching cabinets, beacon heads, solar panels, etc., to poles.
- Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on poles.
- Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening on connection.
- 10. Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL in the file "Roadway Illumination and Electrical Supplies." Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
- 11. Install the batteries in a battery box. Place the batteries on a  $\frac{3}{16}$ " thick plastic sheet and connect together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and  $\frac{3}{16}$ " plastic sheet are subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies." When required, install batteries in the flasher cobinet. Wire batteries according to manufacturers recommendations. Provide the number of batteries as required by the manufacturer.
- See standard sheet Electrical Details (ED) for additional requirements regarding the installation of ground boxes/battery boxes, conduit, and cabinets.
- 13. Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
- 14. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- 15. Orient solar panel for optimum exposure to sunlight (face to the south). Prior to installation, check the location to ensure there is no overhead obstruction that would block the solar panel from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- 16. Ensure height of conduit is below top of anchor bolts.





NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS



NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS
EXPLODED VIEW



SPRFBA(1)-13

DETAILS


75A


# GENERAL NOTES:

- Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the upper beacon.
- 2. See Item 685, "Roodside Floshing Beacon Assemblies" for further requirements.
- See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- 4. Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered floshing beacon assemblies.
- When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- 6. Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or pavement grade at the edge of the road.
- Provide 20' in length ANSI class 5 timber poles. Install pole as shown or at the edge of the right of way. The timber pole is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- Use materials specifically designed for attaching cabinets, beacon heads, solar panels, etc., to poles.
- Conduit in foundation and within 6 in, of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- 10. Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening on connection.
- Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hordware specifically designed for mounting beacon heads on poles.
- Install the Type LB conduit body attachment in the bottom third of the back of the cabinet. See Detail A.
- 13. Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL, in the file "Roadway Illumination and Electrical Supplies". Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse (slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).
- 14. Install the batteries in a battery box. Place the batteries on a 3/16" thick plastic sheet and connect together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strap. The batteries, bell jars, straps and 3/16" plastic sheet are subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies." When required, install batteries in the flasher cabinet. Wire batteries according to manufacturers recommendations. Provide the number of batteries as required by the manufacturer.
- See standard sheet Electrical Details (ED) for additional requirements regarding the installation of ground boxes/battery boxes, conduit, and cabinets.
- 16. Unless otherwise shown on the plans or recommended by the manufacturer, use the following table to determine the wire size from cabinet to beacons.


Distance from Cabinet to Beacons (ft.)	Minimum Required Wire Size (AWG)
0 - 35	•14
35 - 60	•12
60 - 100	•10
\ 100	

- 17. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- 18. Orient solar panel for optimum exposure to sunlight (face to the south). Prior to installation, check the location to ensure there is no overhead obstruction that would block the solar panel from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- 19. Ensure height of conduit is below top of anchor bolts







NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS




NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS
EXPLODED VIEW




# DETAIL A



# DETAIL B



# DETAIL C



DETAIL D



Traffic Operations Division Standard

# SOLAR POWERED ROADSIDE FLASHING BEACON ASSEMBLY DETAILS (TIMBER)

# SPRFBA(2)-13


3 13		ВМТ		LIBERT	Y		67
12-04 3-13		DIST	DIST COUNTY			5	SHEET NO.
REVISIONS		0952	01 064		FM1008		
© TxD0T	May 2003	CONT	SECT	JOB		HIG	HWAY
FILE:	spb2-13.dgn	DN: Tx	DOT	ск: ТхDОТ	DW:	TxDOT	ск: TxDC

# GENERAL NOTES:


- Details show a typical warning sign with two flashing beacon heads, other arrangements are possible. When only one beacon is required, install the
- 2. See Item 685, "Roodside Floshing Beacon Assemblies" for further requirements.
- 3. See SMD standard sheets for lateral and vertical clearances and sign mounting details. Install signs as shown on the sign layout sheets.
- 4. Use either a Screw-In Type Anchor Foundation or a Drilled Shaft Foundation as shown elsewhere in the plans. When plans require a Drilled Shaft Foundation, see standard sheet TS-FD. Install the Screw-In Type Anchor Foundation as per manufacturer's recommendations. On a slope, install one edge at ground level. Screw-In/Drilled Shaft Foundation is subsidiary to Item 685. Installation of a ground rod is not required for solar powered
- When used, provide Screw-In Type Anchor Foundations as shown on TxDOT's Material Producer List (MPL) in the file "Highway Traffic Signals".
- 6. Provide clearance as shown above the sidewalk or pavement grade at the edge of the road. When a bottom beacon is not used, mount the bottom of the sign at least 7 ft. above the sidewalk or povement grade at the edge of the road.
- 7. Use materials specifically designed for attaching cabinets, beacon heads, solar panels, etc., to poles,
- 8. Conduit in foundation and within 6 in. of foundation is subsidiary to the Item 685, "Roadside Flashing Beacon Assemblies."
- Per manufacturer's recommendations, engage all threads on the pedestal pole base and pipe unless the pipe is fully seated into base. In high winds, use a pole and base collar assembly to add strength and prevent loosening on
- 10. Install beacon heads as shown here, as shown elsewhere on the plans, or as directed. Use hardware specifically designed for mounting beacon heads on
- 11. Install the cable clamp in the bottom third of the back of the cabinet. See Detail A.
- 12. Provide single pole non-fused watertight breakaway electrical connectors for frangible pedestal pole bases, as shown on TxDOT's MPL in the file "Roadway Illumination and Electrical Supplies". Approved models are listed under Item 685. For ungrounded (hot) conductors, install a breakaway connector with a dummy fuse (slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy
- Install the batteries in a battery box. Place the batteries on a 3/16" thick plastic sheet and connect together. Place a plastic cover (battery bell jar) over the top of each battery and secure the battery bell jar to the battery with a strop. The batteries, bell jars, strops and 3/16 " plastic sheet are subsidiary to the Item 685, "Roadside Floshing Beacon Assemblies." When required, install batteries in the flasher cabinet. Wire batteries according to manufacturers recommendations. Provide the number of batteries as required
- 14. See standard sheet Electrical Details (ED) for additional requirements regarding the installation of ground boxes/battery boxes, conduit, and cabinets.
- 15. Unless otherwise shown on the plans or recommended by the manufacturer, use the following table to determine the wire size from cabinet to beacons.

2	
Distance from Cabinet	Minimum Required
to Beacons (ft.)	Wire Size (AWG)
0 - 35	-14
35 - 60	•12
60 - 100	•10
> 100	•8


- 16. Unless otherwise shown on the plans, pole shaft shall be one piece, Schedule 40 Aluminum pipe, ASTM B429 or B221 (Alloy 6061-T6 only). Aluminum conduit will not develop the necessary strength and will not be allowed.
- 17. Orient solar panel for optimum exposure to sunlight (face to the south). Prior to installation, check the location to ensure there is no overhead obstruction that would block the solar panel from receiving full sunlight. Unless specified elsewhere, mount a minimum of 14' above grade.
- 18. Ensure height of conduit is below top of anchor bolts.



DETAIL FOR SOLAR PANEL, CABINET, AND BATTERIES LOCATED OUT OF CLEAR ZONE ON SEPARATE ALUMINUM POLE ASSEMBLY



NON-FUSED BREAKAWAY ELECTRICAL CONNECTORS





Traffic Operations Division Standard

# SOLAR POWERED ROADSIDE FLASHING BEACON ASSEMBLY DETAILS (ALUMINUM)

SPRFBA(3)-13

• •		ВМТ		LIBERT	Υ		68
3-13		DIST		COUNTY	(	-	SHEET NO.
12-04	REVISIONS	0952	01	064		FM	1008
© TxD0T	May 2003	CONT	SECT	JOB		HIC	HWAY
FILE:	spb3-13.dgn	DN: Tx	DOT	ск: ТхDОТ	DW:	TxDOT	ck: TxDC



# STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with soil disturbing activity and for projects that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

# 1.0 SITE/PROJECT DESCRIPTION

# 1.1 PROJECT CONTROL SECTION JOB (CSJ): 0952-01-064

# 1.2 PROJECT LIMITS:

From: 0.02 MI SOUTH OF CR 631, SOUTH

To: 0.05 MI SOUTH OF BOWIE CREEK

# 1.3 PROJECT COORDINATES:

,(Long)-94.8621323 BEGIN: (Lat) 30.0835713

END: (Lat) 30.0807103 (Long) -94.8637874

# 1.4 TOTAL PROJECT AREA (Acres): 0.5

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.003

1.6 NATURE OF CONSTRUCTION ACTIVITY:

# 1.7 MAJOR SOIL TYPES:

Soil Type	Description

# 1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below: PSLs determined during preconstruction meeting

PSLs determined during construction

No PSLs planned for construction

Туре	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

# 1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

Mobilization

Install sediment and erosion controls

Blade existing topsoil into windrows, prep ROW, clear and grub

Remove existing pavement

Grading operations, excavation, and embankment

Excavate and prepare subgrade for proposed pavement widening

Remove existing culverts, safety end treatments (SETs)

Remove existing metal beam guard fence (MBGF), bridge rail

Install proposed pavement per plans

Install culverts, culvert extensions, SETs

Install mow strip, MBGF, bridge rail

Place flex base

Rework slopes, grade ditches

Blade windrowed material back across slopes

Revegetation of unpaved areas

Achieve site stabilization and remove sediment and

erosion control measures

Other:

Other:					

# 1.10 POTENTIAL POLLUTANTS AND SOURCES:

Sediment laden stormwater from stormwater conveyance over disturbed area

Fuels, oils, and lubricants from construction vehicles, equipment, and storage

Solvents, paints, adhesives, etc. from various construction

Transported soils from offsite vehicle tracking

Construction debris and waste from various construction

Contaminated water from excavation or dewatering pump-out

Sanitary waste from onsite restroom facilities

Trash from various construction activities/receptacles

Long-term stockpiles of material and waste

Other: _			

Other: _____

Other:

# 1.11 RECEIVING WATERS:

**Tributaries** 

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

**Classified Waterbody** 

SEGMENT ID 0808	TRINITY RIVER
SEGMENT NAME	LAKE LIVINSTON
* A   1 / 4 \ C	

# * Add (*) for impaired waterbodies with pollutant in ().

# 1.12 ROLES AND RESPONSIBILITIES: TxDOT

X Development of plans and specifications

X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)

X Post Construction Site Notice

X Submit NOI/CSN to local MS4

X Perform SWP3 inspections

X Maintain SWP3 records and update to reflect daily operations

X Complete and submit Notice of Termination to TCEQ

X Maintain SWP3 records for 3 years

Other:		
Other.		

Other:

# 1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

X Day To Day Operational Control

X Submit Notice of Intent (NOI) to TCEQ (≥5 acres)

X Post Construction Site Notice

X Submit NOI/CSN to local MS4

☐ Other:

X Maintain schedule of major construction activities

X Install, maintain and modify BMPs


X Complete and submit Notice of Termination to TCEQ

X Maintain SWP3 records for 3 years

Other:	 	

# 1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER **SYSTEM (MS4) OPERATOR COORDINATION:**

**MS4 Entity** 



# STORMWATER POLLUTION PREVENTION PLAN (SWP3)



* July 2023 Sheet 1 of 2

Texas Department of Transportation

FED. RD. DIV. NO.		PROJECT NO.	SHEET NO.
			69
STATE	STATE DIST.		COUNTY
TEXAS	20	LII	BERTY
CONT.	SECT.	JOB	HIGHWAY NO.
0952	01	064	FM1008

# STORMWATER POLLUTION PREVENTION PLAN (SWP3):

# 2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

# 2.1 EDOSION CONTROL AND SOIL

STABILIZATION BMPs:
T/P
□ □ Protection of Existing Vegetation
□ □ Vegetated Buffer Zones
□ □ Soil Retention Blankets
□ □ Geotextiles
□ □ Mulching/ Hydromulching
□ □ Soil Surface Treatments
□ □ Temporary Seeding
□ □ Permanent Planting, Sodding or Seeding
□ □ Biodegradable Erosion Control Logs
□ □ Rock Filter Dams/ Rock Check Dams
□ □ Vertical Tracking
□ □ Interceptor Swale
□ □ Riprap
□ □ Diversion Dike
□ □ Temporary Pipe Slope Drain
□ □ Embankment for Erosion Control
□ □ Paved Flumes
Other:
□ Other:
□ □ Other:
□ □ Other:

located in Attachment 1.2 of this SWP3

		Other.
2.2	2 S	EDIMENT CONTROL BMPs:
T ,	P	
		Biodegradable Erosion Control Logs
		Dewatering Controls
		Inlet Protection
		Rock Filter Dams/ Rock Check Dams
		Sandbag Berms
		Sediment Control Fence
		Stabilized Construction Exit
		Floating Turbidity Barrier
		Vegetated Buffer Zones
		Vegetated Filter Strips
		Other:

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

# T/P

□ □ Sediment Trap

<ul> <li>□ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area</li> <li>□ 3,600 cubic feet of storage per acre drained</li> </ul>
Sedimentation Basin
□ Not required (<10 acres disturbed)
□ Required (>10 acres) and implemented.
□ Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
$\hfill \hfill 3,600$ cubic feet of storage per acre drained
□ Required (>10 acres), but not feasible due to:
☐ Available area/Site geometry
☐ Site slope/Drainage patterns
☐ Site soils/Geotechnical factors
□ Public safety
□ Other:

# 2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Туре	Stationing				
	From	То			

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

# 2.4 OFFSITE VEHICLE TRACKING CONTROLS:

☐ Excess dirt/mud on road removed daily
□ Haul roads dampened for dust control
□ Loaded haul trucks to be covered with tarpaulin
□ Stabilized construction exit
□ Daily street sweeping
□ Other:
2.5 POLLUTION PREVENTION MEASURES:
□ Chemical Management
□ Concrete and Materials Waste Management
□ Debris and Trash Management
□ Dust Control
□ Sanitary Facilities
□ Other:
Other:
en se de deserción de la contraction de la contr

# **2.6 VEGETATED BUFFER ZONES:**

Other:

Other:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Statio	tioning	
From	To	
	From Station	

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

# 2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- X Fire hydrant flushings
- X Irrigation drainage
- X Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- X Potable water sources
- X Springs
- X Uncontaminated groundwater
- X Water used to wash vehicles or control dust
- X Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

# 2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.


# 2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

When dewatering activities are present, a daily inspection will be conducted once per day during those activities and documented in accordance with CGP and TxDOT requirements.

# 2.10 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.




# STORMWATER POLLUTION **PREVENTION PLAN (SWP3)**



* July 2023 Sheet 2 of 2

Texas Department of Transportation

FED. RD. DIV. NO.		PROJECT NO.					
STATE STATE COUNTY							
TEXA:	S	20	LIBERTY				
CONT.		SECT.	J0B	HIGHWAY NO.			
0952		01	064	FM100	)8		



# **NOTES**:

For projects disturbing 5 or more acres, place laminated copies of the TxDOT and Contractor Construction Site Notices and the TxDOT and Contractor Notices of Intent on the SW3P Notification Board.

For projects disturbing between 1 and 5 acres, place laminated copies of the TxDOT and Contractor Construction Site Notices on the SW3P Notification Board.

For projects with an Individual Permit with the US Army Corp of Engineer, place a laminated copy of the Permit Certificate on the Notification Board.

# Center all postings.

Notification Boards are to be constructed from chloroplast and placed at a location within the right-of-way but outside the clear zone as directed by the Engineer. This work will not be paid for directly, but will be considered subsidiary to other items.

CSN - Construction Site Notice, Large for projects greater than 5 acres, Small for projects greater than 1 and less than 5 acres.



BEAUMONT DISTRICT


SW3P

NOTIFICATION BOARD

DETAIL


(SW3P-B)

REVISIONS	FINA TEXAS	FEOCRAL A	SHEET NO.		
<b>©2022</b>	DIVISOR		v10		71
	STATE	DISTRICT		COUNTY	
	TEXAS	BMT	L	LIBERTY	
	CONTROL	SECTION	J08	нісніў А	r NO.
	0952	(A)	064	FMI	เดล



# TEMPORARY SEDIMENT CONTROL FENCE

SCF)—



# HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA.SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

# SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT . Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


# **LEGEND**

Sediment Control Fence



# GENERAL NOTES

- 1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
- 2. Perform vertical tracking on slopes to temporarily stabilize soil.
- 3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
- 4. Do not exceed 12" between track impressions.
- 5. Install continous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



VERTICAL TRACKING



TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING

EC(1)-16

	BMT		LIBERT	Y	72	
	DIST		COUNTY		SHEET NO.	
REVISIONS	0952	01	064		FM1008	
TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY	
LE: ec116	ри: TxD	0T	ck: KM	ow: VP	DN/CK: LS	

purpose * from its for any resulting "Texos Engineering Practice Act". No worranly of any kind is mode by TxDOT version of this standard to other formots or for incorrect results or damages

TEMP, EROSION FLOW CONTROL LOG ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE LOG ON DOWNHILL STAKE AS SIDE AT THE CENTER, DIRECTED AT EACH END, AND AT ADDITIONAL POINTS AS NEEDED TO SECURE LOG (4' MAX. SPACING), OR AS DIRECTED BY THE ENGINEER. PLAN VIEW

STAKE LOG ON DOWNHILL

SIDE AT THE CENTER,

AT EACH END, AND AT

ADDITIONAL POINTS AS

(4' MAX. SPACING), OR

AS DIRECTED BY THE

ENGINEER.

NEEDED TO SECURE LOG


ADDITIONAL UPSTREAM

STAKES FOR HEAVY


RUNOFF EVENTS

FLOW ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE AS DISTURBED AREA DIRECTED BACK OF CURB LIP OF GUTTER STAKE ON DOWNHILL SIDE OF TEMP. EROSION LOG AT 8' (ON CENTER) MAX. CONTROL LOG AS NEEDED TO SECURE LOG, OR AS DIRECTED BY THE ENGINEER.


PLAN VIEW



# PLAN VIEW



CL-ROW



EROSION CONTROL LOG AT BACK OF CURB

CL-BOC

EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

# 1/2" ±

REBAR STAKE DETAIL

# LEGEND

SECTION A-A

EROSION CONTROL LOG DAM

CL-D

EROSION CONTROL LOG DAM CL-D

TEMP. EROSION

CONTROL LOG

1' (TYP.)

COMPOST CRADLE

UNDER EROSION

CONTROL LOG

(CL-BOC) -EROSION CONTROL LOG AT BACK OF CURB

-EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY (CL-ROW)

EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING CL-SST

EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING CL-SSL

EROSION CONTROL LOG AT DROP INLET CL-DI

CL-CI EROSION CONTROL LOG AT CURB INLET

EROSION CONTROL LOG AT CURB & GRATE INLET CL-GI

# SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion controllog sediment trop may be used to filter sediment out of runoff draining from an unstabilized area.

Log Traps: The drainage area for a sediment trap should not exceed 5 acres. The trop capacity should be 1800 CF/Acre (0.5" over the drainage area).

Controllogs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets
- 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.

# BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.

RECOMMENDATIONS, OR AS DIRECTED BY THE

**GENERAL NOTES:** 

IN ACCORDANCE WITH MANFACTURER'S

ENGINEER.

- UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
- FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
- STAKES SHALL BE 2" X 2" WOOD OR *3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.
- DO NOT PLACE STAKES THROUGH CONTAINMENT
- COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
- SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
- TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE
- FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

DIAMETER MEASUREMENTS OF EROSION

CONTROL LOGS SPECIFIED IN PLANS


MINIMUM

COMPACTED DIAMETER

MINIMUM

DIAMETER

COMPACTED



TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES

**EROSION CONTROL LOG** 

EC(9)-16

	ВМТ		LIBERT	Y	73
	DIST		COUNTY		SHEET NO.
REVISIONS	0952	01	064 FM1		M1008
© TxDOT: JULY 2016	CONT	SECT	JOB	H	HIGHWAY
FILE: ec916	DN: TxD(	OT	ск: КМ	ow: LS/PT	ck: LS

6' BELOW TOP OF SLOPE SECURE END OF LOG TO STAKE AS DIRECTED DISTURBED AREA LOG SPACING (SEE EROSION CONTROL LOG SPACING TABLE BELOW) LOG SPACING (SEE EROSION CONTROL LOG SPACING TABLE BELOW) END SECTION RAP DETAIL EROSION CONTROL LOG - EROSION CONTROL LOG STAGGER JOINTS STAGGER JOINTS 5'-0" TO 10'-0" 5'-0" TO 10'-0" 5'-0" ABOVE TOE OF SLOPE 5'-0" ABOVE EROSION CONTROL LOG SPACING TABLE TOE OF SLOPE LOG DIAMETER SLOPE 12" 18" 6" 8" 1:1 OR STEEPER 20' 10' 15' TOE OF SLOPE TOE OF SLOPE 20' 40 2:1 10' 30' **EROSION CONTROL LOGS ON SLOPES EROSION CONTROL LOGS ON SLOPES** 3:1 15' 30' 45' 60' STAKE AND LASHING ANCHORING STAKE AND TRENCHING ANCHORING 20' 4:1 OR FLATTER 40' 60. 80. CL-SST . ADJUSTMENTS CAN BE MADE FOR SOIL TYPE: CL-SSL SOFT, LOAMY SOILS-ADJUST ROWS CLOSER TOGETHER: HARD, ROCKY SOILS- ADJUST ROWS FARTHER APART STAKE STAKE -2" x 2" WOOD or =3 REBAR, 2'TO 4'LONG. ROPE **EROSION CONTROL LOG** ROPE ADDITIONAL PLACE EXCAVATED MATERIAL ON UPHILL SIDE OF EROSION CONTROL LOG. **EROSION EROSION** STAKING IF CONTROL CONTROL NEEDED FOR LOG LOG HEAVY RUNOFF **EVENTS** NOTCH Typ EROSION CONTROL LOG 2' MINIMUM OVERLAP SLOPE NOTE: COMPACT EXCAVATED SOIL TO PREVENT UNDERCUTTING. 6" DIAMETER STAKE AND LASHING ANCHORING DETAIL CL-SSL SHEET 2 OF 3 STAKE AND TRENCHING ANCHORING DETAIL Design Division Standard Texas Department of Transportation CL-SST TEMPORARY EROSION. TRENCH DEPTH TABLE NOTCH SEDIMENT AND WATER LOG DIAMETER POLLUTION CONTROL MEASURES 2" STAKE NOTCH DETAIL 8" 3" **EROSION CONTROL LOG** 4" 12" EC(9)-16 18" 5" DN: TxDOT CK: KM DW: LS/PT CK: LS TXDOT: JULY 2016 0952 01 064 FM1008 ВМТ LIBERTY

TOP OF SLOPE

TOP OF SLOPE

6' BELOW TOP OF SLOPE

SECURE END OF LOG TO STAKE AS DIRECTED

TEMP. EROSION CONTROL LOG


FLOW



# CURB AND GRATE INLET

EROSION CONTROL LOG AT DROP INLET

CL-DI



SANDBAG

OVERLAP ENDS TIGHTLY 24" MINIMUM

COMPLETELY SURROUND DRAINAGE ACCESS TO AREA DRAIN INLETS WITH EROSION CONTROL LOG

FLOW

-Stake or use Sandbags on Downhill Side of log as Needed to Hold in Place (Typical)

# EROSION CONTROL LOG AT CURB & GRADE INLET

EROSION CONTROL LOG AT CURB INLET

CURB

TEMP. EROSION CONTROL LOG

SANDBAG

# EROSION CONTROL LOG AT CURB INLET

-2 SAND BAGS

CL-CI CL-CI

USE STAKES ON DOWNSTREAM SIDE OF LOGS, AT ENDS, MIDPOINT, & AS NEEDED OR SANDBAGS TO HOLD IN PLACE.


6" CURB-

ROADWAY

2 SAND BAGS

TEMP. EROSION CONTROL LOG

NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE TRAFFIC OR FLOOD THE ROADWAY OR WHEN THE STORM SEWER SYSTEM IS NOT FULLY FUNCTIONAL.



SHEET 3 OF 3



CURB INLET INLET EXTENSION

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES **EROSION CONTROL LOG** 

EC(9)-16

FILE: ec916	on: TxD	OT	ск: КМ	ow: LS/PT	ck: LS		
© TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY		
REVISIONS	0952	01	064		FM1008		
	DIST	COUNTY		ГҮ	SHEET NO.		
	ВМТ		LIBER	TY	75		

I. STORMWATER POLLUTION PR	EVENTION-CLEAN WATER A	CT SECTION 402	II. CULTURAL RESOURCES	VI. HAZARDOUS MATERIALS OR CO	
	Discharge Permit or Construction		☐ No Action Required	No Action Required	
disturbed soil must protect for er Item 506. List MS4 Operator(s) that may r They may need to be notified p	ore acres disturbed soil. Projects osion and sedimentation in accord eceive discharges from this proje rior to construction activities.	once with	Action No.  1. Refer to TxDOT Standard Specifications in the event historicalissues or archeological artifacts are found during construction. Upon dis-	General (applies to all projects): Comply with the Hazard Communication A hazardous materials by conducting safety making workers aware of potential hazards provided with personal protective equipment	
1. TxDOT - Beaumont District			covery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.	Obtain and keep on-site Material Safety D used on the project, which may include, b Paints, acids, solvents, asphalt products, cl compounds or additives. Provide protecte	
No Action Required	Required Action			products which may be hazardous. Maintai	
accordance with TPDES Pern	y controlling erosion and sediment nit TXR 150000 vise when necessary to controlpo		IV. VEGETATION RESOURCES  No Action Required  Required Action  Action No.	Maintain an adequate supply of on-site sp In the event of a spill, take actions to mi in accordance with safe work practices, a immediately. The Contractor shall be respo of all product spills.	
3. The project is estimated to in the event the project disthan one acre, the CGP is coordination with DEOC for Take measures to prevent not limited to wastewater (i)	involve less than one acre of so turbance acreage becomes equal to applicable. Contact TxDOT project in necessary action. construction materials and debris .e., cooling liquid, etc.) associated to ering any inlets, ditches, or waterwa	o or greater inspector for including, but with	1. No vegetation removalor trimming of any kind is allowed. Exceptions are allowed for mowed and maintained grass.	Contact the Engineer if any of the followin  Dead or distressed vegetation (not Trosh piles, drums, conister, barrels, Undesirable smells or odors Evidence of leaching or seepage of Any other evidence indicating possil	
II. WORK IN OR NEAR STREAM ACT SECTIONS 401 AND		ANDS CLEAN WATER		List below any bridge class structure replaced, rehabilitated, removed, exten or state "None", if applicable. If "None", then no further action is re	
water bodies, rivers, creeks, str The Contractor must adhere to	all of the terms and conditions, in	ncluding	V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.	for completing asbestos assessment/  Provide results below:  Structure Location PSN	
permit(s):	e of Texas, associated with the fo	ollowing			
No Permit Required			☐ No Action Required		
Nationwide Permit 14 - PCN wetlands affected)	not Required (less than 1/10th ac	re waters or	Action No.	If Asbestos is present, then TxDOT n to assist with the notification, develop	
☐ Nationwide Permit 14 - PCN☐ Individual 404 Permit Require	Required (1/10 to <1/2 acre, 1/3 ed: Permit •	in tidal waters)	If any animal enters the work area, do not harm, harass, or attempt to handle; let the animal leave on its own.  If coves or sinkholes are discovered on site, cease work in the	management activities as necessary.  If Asbestos is not present, then TxDO	
Other Nationwide Permit Rec	quired: NWP=		area and contact the TxDOT Inspector or DEQC for guidance.  3. Comply with "Wildlife: Regulatory Requirements and Best Management	prior to any scheduled demolition. In either case, the Contractor is resp activities and/or demolition with care	
	the US permit opplies to, location actices planned to control erosion,	•	Practices" section found in the Beaumont District Environmental Field Guide.  4. Contractor shall maintain compliance with the Migratory Bird Treaty Act (MBTA) and Texas Parks and Wildlife (TPW) Code Section 64.002. The full MBTA quidance may be found here: https://ftp.dot.state.tx.us/pub/ txdot-info/env/toolkit/350-01-gui.pdf	asbestos consultant in order to minim Hazardous Materials or Contamination	
1 Maintain a neat and clean worl	ksite next to the water and do no	t allow any		Action No.	
debris to fallinto the water.  2. Comply with "Work In or Near	Waters/Wetlands Regulatory Requ " section found in the Beaumont C	irements and	<ol> <li>Resource specific BMPs (Section I) and Pavement BMPs (Section II, F) from the 'Updated Best Management Practices (BMPs) for TxDOT Maintenance Activities' guidance under the TxDOT Maintenance Program EA shall be reviewed and implemented where appropriate. The maintenance EA BMPs may be found here: https://ftp.txdot.gov/pub/txdot-info/env/ 080-01-bmp.pdf</li> </ol>	Comply with TxDOT Standard     if evidence of hazardous     materials or contamination is     Notify TxDOT Inspector or Di     including fuel, hydraulic fluid,	
				VII. OTHER ENVIRONMENTAL ISSUE	
The elevation of the ordinary hi	gh water marks of any areas requ	iiring work		(includes regionalissues such as E	
to be performed in the waters permit can be found on the Brid	of the US requiring the use of a gge Loyouts.	nationwide		☐ No Action Required	
Best Management Practices:				Action No. 1. Comply with "General Constru	
Erosion	Sedimentation	Post-Construction TSS		District Environmental Field G	
☐ Temporary Vegetation	Silt Fence	Vegetative Filler Strips			
Blonkets/Molling	Rock Berm	Retention/Irrigation Systems			
Mulch	Triangular Filter Dike	Extended Detention Basin			
☐ Sodding	Sand Bag Berm	Constructed Wetlands	LIST OF ABBREVIATIONS		
Interceptor Swale	Strow Bale Dike	Wet Bosin	BMP: Best Management Practice SPCC: Spill Prevention Control and Countermeasure		
Diversion Dike	Brush Berms	Erosion Control Compost	COP: Construction General Permit SWDP: Storm Water Pollution Prevention Plan DSHS: Texas Department of State Health Services PON: Pre-Construction Notification		
Erosion Control Compost	Erosion Control Compost	Mulch Filler Berm and Socks	FHMA: Federal Highway Administration PSL: Project Specific Location		
Mulch Filter Berm and Socks	Mulch Filter Berm and Socks	Compost Filter Berm and Socks	MOA: Memorandum of Agreement TCEC: Texas Commission on Environmental Quality MOU: Memorandum of Understanding TPDES: Texas Pollutant Discharge Elimination System	Tarrod Tustica	
Compost Filter Berm and Socks	Compost Filter Berm and Socks	☐ Vegetation Lined Ditches	MS4: Municipal Separate Stormwater Sewer System TPWD: Texas Parks and Wildlife Department MBTA: Migratory Bird Treaty Act TxDOT: Texas Department of Transportation	Jerrod Justice 06/10/2	
	Stone Outlet Sediment Traps Sediment Basins	Sond Filler Systems	NOT: Notice of Termination T&E: Threatened and Endangered Species  NWP: Notice of Intent USACE: U.S. Army Corps of Engineers  NOT: Notice of Intent USFWS: U.S. Fish and Wildlife Service	DISTRICT ENVIRONMENTAL DEPARTMENT	

Required Action

ply with the Hazard Communication Act (the Act) for personnel who will be working with rdous materials by conducting safety meetings prior to beginning construction and ing workers aware of potential hazards in the workplace. Ensure that all workers are ided with personal protective equipment appropriate for any hazardous materials used.

in and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products on the project, which may include, but are not limited to the following categories: ts, acids, solvents, asphalt products, chemical additives, fuels and concrete curing pounds or additives. Provide protected storage, off bare ground and covered, for lucts which may be hozordous. Maintain product labelling as required by the Act. tain an adequate supply of on-site spill response materials, as indicated in the MSDS. ne event of a spill, take actions to mitigate the spill as indicated in the MSDS, ccordance with safe work practices, and contact the District Spill Coordinator ediately. The Contractor shall be responsible for the proper containment and cleanup

act the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
- Trash piles, drums, canister, barrels, etc.
- Undesirable smells or odors
- Evidence of leaching or seepage of substances
- Any other evidence indicating possible hazardous materials or contamination discovered on site.

List below any bridge class structure(s), not including box culverts, being replaced, rehabilitated, removed, extended or modified as part of this project, or state "None", if applicable.

If "None", then no further action is required. Otherwise TxDOT is responsible for completing asbestos assessment/inspection and evaluation for presence of lead.

# Provide results below:

Structure Location	PSN E	lement Leo	Asbesto:	

f Asbestos is present, then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary.

Asbestos is not present, then TxDOT is still required to notify DSHS prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Hazardous Materials or Contamination Issues Specific to this Project:

# Action No.

- 1. Comply with TxDOT Standard Specification 7.12 and Special Provision 006-012 if evidence of hozordous
- materials or contamination is noted during construction.
- 2. Notify TxDOT Inspector or DEQC of any hazardous materials spills including fuel, hydraulic fluid, etc.

# OTHER ENVIRONMENTAL ISSUES

(includes regionalissues such as Edwards Aquifer District, etc.)

Required Action

# Action No.

Comply with "General Construction" section found in the Beaumont District Environmental Field Guide.

Texas Department of Transportation

# ENVIRONMENTAL PERMITS. ISSUES AND COMMITMENTS

**EPIC** 

06/10/2024

DN: TxDOT CK: AM DW: VP © TxDOT February 2019 CONT SECT JOB 0952 01 064 FM1008 LIBERTY