Control	2121-06-054
Project	C 2121-6-54
Highway	IH 10
County	HUDSPETH

# ADDENDUM ACKNOWLEDGMENT

Each bidder is required to acknowledge receipt of an addendum issued for a specific project. This page is provided for the purpose of acknowledging an addendum.

FAILURE TO ACKNOWLEDGE RECEIPT OF AN ADDENDUM WILL RESULT IN THE BID NOT BEING READ.

In order to properly acknowledge an addendum place a mark in the box next to the respective addendum.



In addition, the bidder by affixing their signature to the signature page of the proposal is acknowledging that they have taken the addendum(s) into consideration when preparing their bid and that the information contained in the addendum will be included in the contract, if awarded by the Commission or other designees.

This page intentionally left blank.

Control	2121-06-054
Project	C 2121-6-54
Highway	IH 10
County	HUDSPETH

# PROPOSAL TO THE TEXAS TRANSPORTATION COMMISSION

#### **2014 SPECIFICATIONS**

#### WORK CONSISTING OF PREVENTIVE MAINTENANCE HUDSPETH COUNTY, TEXAS

The quantities in the proposal are approximate. The quantities of work and materials may be increased or decreased as considered necessary to complete the work as planned and contemplated.

This project is to be completed in 52 working days and will be accepted when fully completed and finished to the satisfaction of the Executive Director or designee.

Provide a proposal guaranty in the form of a Cashier's Check, Teller's Check (including an Official Check) or Bank Money Order on a State or National Bank or Savings and Loan Association, or State or Federally chartered Credit Union made payable to the Texas Transportation Commission in the following amount:

THIRTY THOUSAND (Dollars) ( \$30,000)

A bid bond may be used as the required proposal guaranty. The bond form may be detached from the proposal for completion. The proposal may not be disassembled to remove the bond form. The bond must be in accordance with Item 2 of the specifications.

Any addenda issued amending this proposal and/or the plans that have been acknowledged by the bidder, become part of this proposal.

By signing the proposal the bidder certifies:

- 1. the only persons or parties interested in this proposal are those named and the bidder has not directly or indirectly participated in collusion, entered into an agreement or otherwise taken any action in restraint of free competitive bidding in connection with the above captioned project.
- 2. in the event of the award of a contract, the organization represented will secure bonds for the full amount of the contract.
- 3. the signatory represents and warrants that they are an authorized signatory for the organization for which the bid is submitted and they have full and complete authority to submit this bid on behalf of their firm.
- 4. that the certifications and representations contained in the proposal are true and accurate and the bidder intends the proposal to be taken as a genuine government record.
- Signed: \*\*

(1)	_(2)	_(3)
Print Name:		
(1)	_(2)	_(3)
<b>Title:</b> (1)	_(2)	_(3)
Company: (1)	_(2)	_(3)

• Signatures to comply with Item 2 of the specifications.

\*\*Note: Complete (1) for single venture, through (2) for joint venture and through (3) for triple venture.

\* When the working days field contains an asterisk (\*) refer to the Special Provisions and General Notes.

# NOTICE TO CONTRACTORS

ANY CONTRACTORS INTENDING TO BID ON ANY WORK TO BE AWARDED BY THIS DEPARTMENT MUST SUBMIT A SATISFACTORY "AUDITED FINANCIAL STATEMENT" AND "EXPERIENCE QUESTIONNAIRE" AT LEAST TEN DAYS PRIOR TO THE LETTING DATE.

UNIT PRICES MUST BE SUBMITTED IN ACCORDANCE WITH ITEM 2 OF THE STANDARD SPECIFICATIONS OR SPECIAL PROVISION TO ITEM 2 FOR EACH ITEM LISTED IN THIS PROPOSAL.

		<b>BID BOND</b>	
KNOW ALL PERS	ONS BY THESE P	PRESENTS,	
That we, (Contracto	or Name)		
Hereinafter called th	ne Principal, and (S	urety Name)	
Surety, are held and the sum of not less t housand dollars, no displayed on the cov	firmly bound unto than two percent (2' of to exceed one hur ver of the proposal) l ourselves, our hein	transact surety business in the State of the Texas Department of Transportatio %) of the department's engineer's estimated thousand dollars (\$100,000) as a , the payment of which sum will and tr rs, executors, administrators, successor	n, hereinafter called the Oblig nate, rounded to the nearest of proposal guaranty (amount uly be made, the said Princip
WHEREAS, the pri	ncipal has submitte	d a bid for the following project identi	fied as:
	Control	2121-06-054	
	Project	C 2121-6-54	
	Highway County	IH 10 HUDSPETH	
NOW, THEREFOR the Contract in writi	ing with the Obliged t of failure of the Pr	all award the Contract to the Principal e in accordance with the terms of such incipal to execute such Contract in acc	bid, then this bond shall be nu cordance with the terms of suc
void. If in the event	ane the property of lated damages.	the Obligee, without recourse of the P	rincipal and/or Surety, not as
void. If in the event his bond shall beco penalty but as liquic	lated damages.	the Obligee, without recourse of the P Day of	
void. If in the event this bond shall beco penalty but as liquid Signed this	lated damages.	Day of	20
void. If in the event this bond shall beco penalty but as liquid Signed this	lated damages.		20
void. If in the event this bond shall beco penalty but as liquid Signed this By:	lated damages.	Day of (Contractor/Principal Name) d Title of Authorized Signatory for Contractor/	20
void. If in the event         this bond shall beco         penalty but as liquid         Signed this         By:	lated damages.	Day of (Contractor/Principal Name) d Title of Authorized Signatory for Contractor/ (Surety Name)	20
void. If in the event         this bond shall beco         penalty but as liquid         Signed this         By:	lated damages. (Signature and	Day of (Contractor/Principal Name) d Title of Authorized Signatory for Contractor/ (Surety Name) (Signature of Attorney-in-Fact)	20

This page intentionally left blank.

### **BIDDER'S CHECK RETURN**

#### **IMPORTANT**

The space provided for the return address must be completed to facilitate the return of your bidder's check. Care must be taken to provide a legible, accurate, and <u>complete</u> return address, including zip code. A copy of this sheet should be used for each different return address.

#### NOTE

#### Successful bidders will receive their guaranty checks with the executed contract.

RETURN BIDDERS CHECK TO (PLEASE PRINT):

Control	2121-06-054
Project	C 2121-6-54
Highway	IH 10
County	HUDSPETH

#### IMPORTANT

#### PLEASE RETURN THIS SHEET IN ITS ENTIRETY

Please acknowledge receipt of this check(s) at your earliest convenience by signing below in longhand, in ink, and returning this acknowledgement in the enclosed self addressed envelope.

Check Received By:	Date:
Title:	
For (Contractor's Name):	
Project	County

This page intentionally left blank.

# NOTICE TO THE BIDDER

In the space provided below, please enter your total bid amount for this project. Only this figure will be read publicly by the Department at the public bid opening.

It is understood and agreed by the bidder in signing this proposal that the total bid amount entered below is not binding on either the bidder or the Department. It is further agreed that **the official total bid amount for this proposal will be determined by multiplying** <u>the unit bid prices</u> **for each pay item by the respective estimated quantities** <u>shown in this proposal</u> and then totaling all of the extended amounts.

\$\_\_\_\_\_

**Total Bid Amount** 

Control0001-03-030ProjectSTP 2000(938)HESHighwaySH 20CountyEL PASO

ALT	ITEM	DESC	SP	Bid Item Description	Unit	Quantity	Bid Price	Amount	Seq
	104	509		REMOV CONC (SDWLK)	SY	266.400	\$10.000	\$2,664.00	1
						Total Bid Amo	unt\$2,6	64.00	-
Signe	d								

Signeu	
Title	
Date	

Additional Signature for Joint Venture:

Signed	
Title	
Date	

# EXAMPLE OF BID PRICES SUBMITTED BY COMPUTER PRINTOUT



This page intentionally left blank.

#### PROJECT C 2121-6-54 COUNTY HUDSPETH

Г

#### Proposal Sheet TxDOT FORM 234-B I-61-5M

	ITEM-CODE		DE					DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONI WRITTEN IN WORD	UNIT BID PRICE ONLY. WRITTEN IN WORDS		APPROX QUANTITIES	USE ONLY
	500	6001		MOBILIZATION		LS	1.000	1
					DOLLARS			
				and	CENTS			
	502	6001	008	BARRICADES, SIGNS AND TRAF	FIC HAN-	МО	3.000	2
					DOLLARS			
		6004		and	CENTS		05.040.000	2
	662	6004		WK ZN PAV MRK NON-REMOV (	W)4"(SLD) DOLLARS	LF	95,040.000	3
				and	CENTS			
	662	6005		WK ZN PAV MRK NON-REMOV (	W)6"(BRK) DOLLARS	LF	23,760.000	4
				and	CENTS			
	662	6034		WK ZN PAV MRK NON-REMOV (	· · · ·	LF	95,040.000	5
				and	DOLLARS CENTS			
	666	6161	007	RE PV MRK TY		LF	11,880.000	6
				I(BLACK)6"(SHADOW)(090MIL)				
					DOLLARS			
				and	CENTS			
	666	6302	007	RE PM W/RET REQ TY I (W)4"(SI	LD)(090MIL)	LF	47,520.000	7
					DOLLARS			
				and	CENTS			
	666	6305	007	RE PM W/RET REQ TY I (W)6"(BI	RK)(090MIL) DOLLARS	LF	11,880.000	8
				and	CENTS			
	666	6314	007	RE PM W/RET REQ TY I (Y)4"(SL		LF	47,520.000	9
	000	0514	007		DOLLARS	121	47,520.000	,
				and	CENTS			
-	672	6010		REFL PAV MRKR TY II-C-R		EA	594.000	10
				and	DOLLARS			
	<b>(7</b> )	60.01		and	CENTS		0.5.040.000	
	678	6001		PAV SURF PREP FOR MRK (4")		LF	95,040.000	11
				and	DOLLARS CENTS			

#### PROJECT C 2121-6-54 COUNTY HUDSPETH

#### Proposal Sheet TxDOT FORM 234-B I-61-5M

				T	-			1
	ITEM-CODE							DEPT
ALT	ITEM NO						APPROX QUANTITIES	USE ONLY
	678	6002		PAV SURF PREP FOR MRK (6")		LF	23,760.000	12
					DOLLARS			
				and	CENTS			
	3004	6001		CONTINUOUS DIAMOND GRIN	DING CONC	SY	122,355.000	13
				PVMT				
					DOLLARS			
				and	CENTS			
	3012	6002		NEXT GEN CONC SURF GRIND	OF CONC	SY	122,355.000	14
				PAV				
					DOLLARS			
				and	CENTS			
	6001	6002		PORTABLE CHANGEABLE MES	SAGE SIGN	EA	2.000	15
					DOLLARS			
				and	CENTS			
	6185	6002	002	TMA (STATIONARY)		DAY	32.000	16
					DOLLARS			
				and	CENTS			
	6185	6005	002	TMA (MOBILE OPERATION)		DAY	6.000	17
					DOLLARS			
				and	CENTS			

# CERTIFICATION OF INTEREST IN OTHER BID PROPOSALS FOR THIS WORK

By signing this proposal, the bidding firm and the signer certify that the following information, as indicated by checking "Yes" or "No" below, is true, accurate, and complete.

- A. Quotation(s) have been issued in this firm's name to other firm(s) interested in this work for consideration for performing a portion of this work.
  - \_\_\_\_\_ YES
- B. If this proposal is the low bid, the bidder agrees to provide the following information prior to award of the contract.
  - 1. Identify firms which bid as a prime contractor and from which the bidder received quotations for work on this project.
  - 2. Identify all the firms which bid as a prime contractor to which the bidder <u>gave quotations</u> for work on this project.

# **ENGINEER SEAL**

Control	2121-06-054
Project	C 2121-6-54
Highway	IH 10
County	HUDSPETH

The enclosed Texas Department of Transportation Specifications, Special Specifications, Special Provisions, General Notes and Specification Data in this document have been selected by me, or under my responsible supervision as being applicable to this project. Alteration of a sealed document without proper notification to the responsible engineer is an offense under the Texas Engineering Practice Act.



The seal appearing on this document was authorized by Maricruz Saenz, P.E. MAY 03, 2022

COUNTY: HUDSPETH COUNTY

HIGHWAY: IH 10

#### General Requirements

Maintain the entire project area in a neat and orderly manner throughout the duration of the work. Remove all construction litter and undesirable vegetation within the right of way inside the project limits. This work will be subsidiary to the various bid items.

General Project Description – This project consists of rehabilitation of existing road consisting of Diamond Grinding and Next Generation Concrete Surface Grinding (NGCS) and Pavement Markings.

### <u>Traffic</u>

Contact the Engineer or the City when construction operations are within 400 feet of a signalized intersection to determine/verify the location of loop detectors, conduit, ground-boxes, etc. Repair or replace any signal equipment damaged by construction operations. The method of repair or replacement shall be pre-approved and inspected. This work shall be completed at the Contractor's expense.

Inform the Engineer and the respective utility companies, when it becomes apparent that the utility lines will interfere with the work in progress.

Contractor questions on this project are to be addressed to the following individual(s):

East Area Office:

Monica Ruiz, P.E. District Construction Engineer, monica.ruiz@txdot.gov Aldo Madrid, P.E. Director of Construction Aldo.Madrid@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:

#### https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

#### <u>Traffic</u>

Contact the Department's El Paso District Signal Shop at <u>txdotelplocates@txdot.gov</u> to request all Department utility line locates within the project limits. The Signal Shop will locate one time

COUNTY: HUDSPETH COUNTY

#### HIGHWAY: IH 10

only. Record locates for the purpose of refreshing and maintaining all markings throughout the duration of the project.

Contact City of El Paso Streets and Maintenance Department at <u>linespots@elpasotexas.gov</u> and <u>pavementcut@elpasotexas.gov</u> to request all City of El Paso utility line locates within project limits. The City will locate one time only. Record locates for refreshing and maintaining all markings throughout the duration of the project.

#### Item 7 – Legal Relations and Responsibilities

Comply with all requirements of the Environmental Permits Issues and Commitments (EPIC) Sheet.

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

Occupational Safety & Health Administration (OSHA) regulations prohibit operations that bring people or equipment within 10 ft. of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all necessary adjustments to ensure the safety of workers near the energized line.

No significant traffic generator events identified.

#### Law Enforcement Personnel

Submit charge summary and invoices using the Department forms.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

No payment will be made for law enforcement personnel needed for moving equipment or payment for drive time to/from the event site.

#### Item 8 – Prosecution and Progress

Working days will be calculated in accordance with Section 8.3.1., "**Standard** Workweek." A bar chart schedule is required for this project conforming to Section 8.5.5.1, "Bar Chart." Provide updates as directed by the Engineer.

Prior to beginning operations, schedule and attend a preconstruction conference with the Engineer. Provide the Department a written outline of the proposed sequence of work (Bar Chart Schedule) and an estimated progress schedule.

COUNTY: HUDSPETH COUNTY

HIGHWAY: IH 10

#### Item 9 – Measurement and Payment

Monthly progress payments will be made for items of work completed by the 27<sup>th</sup> day of each month. Any work completed after the 27<sup>th</sup> will be included for payment in the subsequent monthly progress payment.

Submit Material on Hand (MOH) payment requests at least **three (3)** working days before the end of the month for payment consideration on that month's estimate.

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take "Safe and Effective Use of Law Enforcement Personnel in Work Zones" (Course #133119) which can be found online at the following site: <u>www.nhi.fhwa.dot.gov</u>

Certificates of completion should be available to all who finish the course. These should be kept by the officers in order to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case by case basis.

#### Item 502 – Barricades, Signs, and Traffic Handling

Prior to beginning construction, the Engineer will approve the routing of traffic and sequence of work.

Additional signs and barricades, placed as directed, will be considered subsidiary to this Item.

In accordance with Section 7.2.6.1, designate, in writing, a Contractor Responsible Person (CRP) and a CRP alternate to take full responsibility for the set-up, maintenance, and necessary corrective measures of the traffic control plan. The CRP or CRP alternate must be present at site and implement the initial set up of every traffic control phase/stage, at each location, and/or each call out, for the entire duration of the project.

COUNTY: HUDSPETH COUNTY

#### HIGHWAY: IH 10

At the written request of the Engineer, immediately remove the CRP or CRP alternate from the project if, in the opinion of the Engineer, is not competent, not present at initial TCP set-ups, or does not perform in a proper, skillful, or safe manner. These individuals shall not be reinstated without written consent of the Engineer.

CRP and CRP alternate must be trained using Department approved training. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table **1** for Department approved Training.

#### Table <mark>1</mark>

#### **Contractor Responsible Person and Alternate**

Provider	Course Number	Course Title	Duration	Notes
American Traffic Safety Services Association	TCS	Traffic Control Supervisor	2 days	
National Highway Institute	133112 133113	Design and Operation of Work Zone Traffic Control Work Zone Traffic Control for Maintenance Operations	1 day 1 day	Both courses are required to meet minimum required training.
Texas Engineering Extension Services	133112A	Design and Operation of Work Zone Traffic Control	3 days	
University of Texas Arlington Division for Enterprise Development	WKZ421	Traffic Control Supervisor	16 hours	Contact UTA for training needs.

All contractor workers involved with the traffic control implementation and maintenance must participate and complete a Department approved training course. Provide a copy of the certificate of completion to the Engineer for project records. Refer to Table 2 for Department approved training.

COUNTY: HUDSPETH COUNTY

HIGHWAY: IH 10

### Table <mark>2</mark>

### Other Work Zone Personnel

Provider	Course Number	Course Title	Duration	Notes	
American Traffic Safety Services Association	ТСТ	Traffic Control Technician	1 day		
Texas Engineering Extension Services	HWS002	Work Zone Traffic Control	16 hours	Identical to HWS-410. Counts for 3 year CRP requirement.	
National Highway Institute	133116	Maintenance of Traffic for Technicians	5 hours	Web based	
National Highway Institute	134109-I	Maintenance Training Series: Basics of Work Zone Traffic Control	1 hour	Free, Web based	
University of Texas at Arlington, Division for Enterprise Development	WKZ100	Work Zone Safety: Temporary Traffic Control	4 hours	Note name change. Free, Web based	
TxDOT/AGC Joint		Safe Workers Awareness	16 minutes	Videos available through	
Development	N/A	Highway Construction Work Zone Hazards	18 minutes	AGC of Texas offices. English & Spanish	
AGC America	N/A	Highway Work Zone Safety Training	1 day		
Texas Engineering Extension Service	HWS400	Temporary Traffic Control Worker	4 hours	Contact TEEX, if interested in course	
TxDOT/AGC Joint Development	N/A	Work Zone Fundamentals	10 minutes	Videos available through ACT of Texas offices. English & Spanish	

#### COUNTY: HUDSPETH COUNTY

#### HIGHWAY: IH 10

Contractor may choose to train workers involved with the traffic control implementation and maintenance with a contractor developed training in lieu of Department approved training. Contractor developed training must be equivalent to the Department approved training shown in Table 2. Provide the Engineer a copy of the course curriculum for pre-approval, prior to conducting the contractor developed training. Provide the Engineer a copy of the log of attendees after training completion for project records.

Existing regulatory signs, route marker auxiliaries, guide signs, and warning signs that must be removed due to widening shall be relocated temporarily and erected on approved supports at locations shown in the plans, or as directed. This work will not be paid for directly, but considered subsidiary to this Item.

Notify the Department officials when major traffic changes are to be made, such as detours. Coordinate with the Department on all traffic changes. Advance notification for the following week's work must be made by 5 P.M. on Wednesdays.

If Law Enforcement Personnel is required by the Engineer, coordinate with local law enforcement as directed or agreed. Complete the weekly tracking form provided by the Department and submit invoices with 5% allowance for Law Enforcement payments by Contractor that agree with the tracking form for payment at the end of each month where approved services were provided.

Provide access to intersecting side roads and driveways at all times, unless otherwise directed.

Any approved change to the sequence of work or TCP, must be signed and sealed by a Contractor's Licensed Professional Engineer assuming full responsibility for any additional barricade signs and devices needed.

Use striping operations to channelize traffic into the newly completed roadway, as directed. Maintain shoulders and median areas in a condition capable of serving as emergency paths, as approved. This work will be subsidiary to this Item.

Use portable changeable message signs (PCMS) to alert public of construction two weeks prior to construction.

Use flaggers when directed. Provide two-way radio communication for all flaggers.

Place and maintain sufficient additional warning signs, beacons, delineators, and barricades to warn and guide the public of all hazards through the construction zone at all times, and as directed.

Use flashing arrow boards on all tapers for each lane closure.

Some signs, barricades, and channelization devices may not be shown at the precise or measured position. Place the barricades, devices, or signs, with approval, in positions to meet field conditions.

COUNTY: HUDSPETH COUNTY

#### HIGHWAY: IH 10

Fill any holes left by barricade or sign supports and restore the area to its original condition.

Use Type A flashing warning lights or delineators to mark open excavation, footings, foundations, or other obstructions near lanes that may be open to traffic, as directed.

For additional information pertaining to channelization, signing, spacing details, and flagging procedures required to regulate, warn, and guide traffic through project, refer to the "Barricade and Construction Standards," BC(1)-21 and to the current *Texas Manual on Uniform Traffic Control Devices(TMUTCD).* 

Remove or cover signs that do not apply to current conditions at the end of each day's work.

Repair and/or replace all signs damaged by the public or due to weather events.

#### Safety Contingency

The contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancement, to improve the effectiveness of the TCP that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

#### Item 506 – Temporary Erosion, Sedimentation, and Environmental Controls

It is not anticipated that any erosion, sedimentation, or environmental control devices will be needed on this project. However, in the event that such controls are necessary, the Storm Water Pollution Prevention Plan (SWP3) for this project shall consist of the use of any temporary erosion control measures deemed necessary by the Engineer and as provided under this Item. Payment for the work will be determined in accordance with Article 9.7, "Payment for Extra Work and Force Account Method."

#### Item 662 – Work Zone Pavement Markings

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engine er as directed. Place final striping on these locations.

Remove and properly dispose of tabs upon completion of the final striping. This work is considered subsidiary to various bid items.

Place tabs as per the Department's Standard sheet WZ (STPM)-13. Place raised pavement markers in accordance with applicable standards and as directed.

COUNTY: HUDSPETH COUNTY

HIGHWAY: IH 10

#### Item 666 – Retroreflectorized Pavement Markings

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required as pavement surface preparation.

In those areas where existing pavement markings are to be covered or removed, field locate and record the existing pavement markings by survey or other approved method by the Engine er as directed. Place final striping on these locations.

#### Item 672 – Raised Pavement Markers

Use a pilot line for final striping and remove pilot line after all striping is complete. Removal will be in accordance with the methods specified in Item 677, "Eliminating Existing Pavement Markings and Markers," and will be subsidiary to this Item.

Air blasting is required for pavement surface preparation.

Furnish adhesives that conform to DMS-6100, "Epoxies and Adhesives," and DMS-6130, "Bituminous Adhesive for Pavement Markers," for this Item.

Do not place raised pavement markers when the pavement surface temperature is below 60 °F.

Removal of all existing raised pavement markers will be considered subsidiary to the various bid items.

#### Item 3004 Diamond Grinding and Grooving Pavement

Diamond grinding will be performed with a minimum of 3 pavement grinding machines to ensure the work is maximized within a shift and to complete all work in the required contract time. This method will be performed on travel lanes only omitting shoulder bridges and ramps. After completion of the surface grinding operation, measure the ride quality and correct areas not within tolerance in accordance with Item 585 "Ride Quality for Pavement Surfaces." Test Type A. Ride Quality will be subsidiary to Item 3004

#### Item 3012 Next Generation Concrete Surface Grinding

NGCS Grinding will be performed with 3 pavement grinding machines in a two-pass operation to ensure the work is maximized within a shift and to complete all work in the required contract time. The first pass will be to provide a flush surface, second pass will be to provide longitudinal grooves. Both steps will have to be performed during the same lane closure for a given length. Pavement shall not be opened to traffic prior to completing the two-pass operation. Before opening to traffic, verify that the full lane width has been grinded and grooved to avoid irregularities

COUNTY: HUDSPETH COUNTY

#### HIGHWAY: IH 10

on either of the wheel paths. Perform diamond grinding on the traveled lanes and shoulders only. Omit bridges and ramps. Cleaning and sealing existing joints and cracks will be incidental to this item.

#### Item 6185 – Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

All TMA Operators must participate in a TMA workshop to be conducted by the El Paso District Safety Office, on the proper use of TMAs, prior to working on Department Right of Way (ROW). A certificate of completion will be issued to TMA Operators that successfully complete the TMA workshop. The certificate of completion must be carried by TMA Operators at all times while working on Department right of way.

Acquire the TCP and TMA Operator's certificates of completion prior to the authorization to begin work. No time suspension will be granted and no traffic control work will be allowed without certificates of completion.

Up to 3 shadow vehicles with TMAs are required for this type of work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

The supporting vehicle for the TMA shall have a minimum gross (i.e., ballasted) vehicular weight of 19,000 pounds.

Basis of Estimate for Stationary TMAs				
Phase	Standard	Required	Additional	Total
Diamond Grinding	TCP (6-1)–12 thru TCP (6-4)-12	1	0	1
NGCS Grinding		1	0	1

Basis of Estimate for Mobile TMAs				
Phase	Standard	Required	Additional	Total
Pavement Markers	TCP (3-2)-13, TCP (3-3)-14	3	0	3
Pavement Markings		3	0	3

CONTROL : 2121-06-054 PROJECT : C 2121-6-54 HIGHWAY : IH 10 COUNTY : HUDSPETH

#### TEXAS DEPARTMENT OF TRANSPORTATION

#### GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION NOVEMBER 1, 2014. STANDARD SPECIFICATIONS ARE INCORPORATED INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS

- ITEM 500 MOBILIZATION
- ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING
- ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS <506>
- ITEM 662 WORK ZONE PAVEMENT MARKINGS (666) (668) (672) (677)
- ITEM 666 RETROREFLECTORIZED PAVEMENT MARKINGS (316)(502)(662)(677) (678)
- ITEM 672 RAISED PAVEMENT MARKERS (677)(678)
- ITEM 677 ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS (300) (302)(316)
- ITEM 678 PAVEMENT SURFACE PREPARATION FOR MARKINGS (677)

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE ----- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL PROVISIONS TO ITEM 5 (005---002)(005---003) SPECIAL PROVISIONS TO ITEM 6 (006---001)(006---012) SPECIAL PROVISIONS TO ITEM 7 (007 - - -004) (007 - - -008) (007 - - -010)(007 - - - 011)SPECIAL PROVISIONS TO ITEM 8 (008---030) (008---033) SPECIAL PROVISIONS TO ITEM 9 (009---010) (009---011) SPECIAL PROVISION TO ITEM 300 (300---020) SPECIAL PROVISION TO ITEM 302 (302---003) SPECIAL PROVISION TO ITEM 316 (316---002) SPECIAL PROVISION TO ITEM 502 (502---008) SPECIAL PROVISION TO ITEM 506 (506---002) SPECIAL PROVISION TO ITEM 666 (666---007) SPECIAL PROVISION TO SPECIAL SPECIFICATION ITEM 6185 (6185--002)

SPECIAL SPECIFICATIONS:

-----

ITEM 3004 DIAMOND GRINDING AND GROOVING PAVEMENT (585)(720)
ITEM 3012 NEXT GENERATION CONCRETE SURFACE (NGCS) GRINDING <3096>
ITEM 3096 ASPHALTS, OILS, AND EMULSIONS
ITEM 6001 PORTABLE CHANGEABLE MESSAGE SIGN
ITEM 6185 TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA)

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH ----- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-CATIONS FOR THIS PROJECT.

Control	2121-06-054
Project	C 2121-6-54
Highway	IH 10
County	HUDSPETH

### SMALL BUSINESS ENTERPRISE REQUIREMENTS

The following goal for small business enterprises is established:

**SBE** 0.0%

# **CHILD SUPPORT STATEMENT**

Under Section 231.006, Family Code, the vendor or applicant certifies that the individual or business entity named in this contract, bid, or application is not ineligible to receive the specified grant, loan, or payment and acknowledges that this contract may be terminated and payment may be withheld if this certification is inaccurate.

# CONFLICT OF INTEREST CERTIFICATION

Pursuant to Texas Government Code Section 2261.252(b), the Department is prohibited from entering into contracts in which Department officers and employees have a financial interest.

By signing the Contract, the Contractor certifies that it is not prohibited from entering into a Contract with the Department as a result of a financial interest as defined under Texas Government Code Section 2261.252(b), and that it will exercise reasonable care and diligence to prevent any actions or conditions that could result in a conflict of interest with the Department.

The Contractor also certifies that none of the following individuals, nor any of their family members within the second degree of affinity or consanguinity, owns 1% or more interest or has a financial interest as defined under Texas Government Code Section 2261.252(b) in the Contractor:

- Any member of the Texas Transportation Commission; and
- The Department's Executive Director, General Counsel, Chief of Procurement and Field Support Operations, Director of Procurement, and Director of Contract Services.

# **E-VERIFY CERTIFICATION**

Pursuant to Texas Transportation Code §223.051, all TxDOT contracts for construction, maintenance, or improvement of a highway must include a provision requiring Contractors and subcontractors to use the U.S. Department of Homeland Security's E-Verify system to determine employment eligibility. By signing the contract, the Contractor certifies that prior to the award of the Contract:

- the Contractor has registered with and will, to the extent permitted by law, utilize the United States Department of Homeland Security's E-Verify system during the term of the Contract to determine the eligibility of all persons hired to perform duties within Texas during the term of the agreement; and
- the Contractor will require that all subcontractors also register with and, to the extent permitted by law, utilize the United States Department of Homeland Security's E-Verify system during the term of the subcontract to determine the eligibility of all persons hired to perform duties within Texas during the term of the agreement.

Violation of this requirement constitutes a material breach of the Contract, subjects a subcontractor to removal from the Contract, and subjects the Contractor or subcontractors to possible sanctions in accordance with Title 43, Texas Administrative Code, Chapter 10, Subchapter F, "Sanctions and Suspension for Ethical Violations by Entities Doing Business with the Department."

### **Certification Regarding Disclosure of Public Information**

Pursuant to Subchapter J, Chapter 552, Texas Government Code, contractors executing a contract with a governmental body that results in the expenditure of at least \$1 million in public funds must:

- 1) preserve all contracting information\* as provided by the records retention requirements applicable to Texas Department of Transportation (TxDOT) for the duration of the contract,
- 2) on request of TxDOT, promptly provide any contracting information related to the contract that is in the custody or possession of the entity, and
- 3) on completion of the contract, either:
  - A. provide, at no cost to TxDOT, all contracting information related to the contract that is in the custody or possession of the entity, or
  - B. preserve the contracting information related to the contract as provided by the records retention requirements applicable to TxDOT

The requirements of Subchapter J, Chapter 552, Government Code, may apply to this contract, and the contractor or vendor agrees that the contract can be terminated if the contractor or vendor knowingly or intentionally fails to comply with a requirement of that subchapter.

By entering into Contract, the Contractor agrees to:

- provide, or make available, to TxDOT and any authorized governmental investigating or auditing agency all records, including electronic and payment records related to the contract, for the same period provided by the records retention schedule applicable to TxDOT, and
- ensure that all subcontracts include a clause requiring the same.

\* As defined in Government Code §552.003, "Contracting information" means the following information maintained by a governmental body or sent between a governmental body and a vendor, contractor, potential vendor, or potential contractor:

- 1) information in a voucher or contract relating to the receipt or expenditure of public funds by a governmental body;
- 2) solicitation or bid documents relating to a contract with a governmental body;
- 3) communications sent between a governmental body and a vendor, contractor, potential vendor, or potential contractor during the solicitation, evaluation, or negotiation of a contract;
- 4) documents, including bid tabulations, showing the criteria by which a governmental body evaluates each vendor, contractor, potential vendor, or potential contractor responding to a solicitation and, if applicable, an explanation of why the vendor or contractor was selected; and

5) communications and other information sent between a governmental body and a vendor or contractor related to the performance of a final contract with the governmental body or work performed on behalf of the governmental body.

# CERTIFICATION TO NOT BOYCOTT ISRAEL

Pursuant to Texas Government Code §2271.002, the Department must include a provision requiring a written verification affirming that the Contractor does not boycott Israel, as defined in Government Code §808.001, and will not boycott Israel during the term of the contract. This provision applies to a contract that:

- 1) is with a Contractor that is not a sole proprietorship,
- 2) is with a Contractor with 10 or more full-time employees, and
- 3) has a value of \$100,000 or more.

By signing the contract, the Contractor certifies that it does not boycott Israel and will not boycott Israel during the term of this contract. "Boycott" means refusing to deal with, terminating business activities with, or otherwise taking any action that is intended to penalize, inflict economic harm on, or limit commercial relations specifically with Israel, or with a person or entity doing business in Israel or in an Israeli-controlled territory, but does not include an action made for ordinary business purposes.

# CERTIFICATION TO NOT BOYCOTT ENERGY COMPANIES

Pursuant to Texas Government Code §2274.002, the Department must include a provision requiring a written verification affirming that the Contractor does not boycott energy companies, as defined in Government Code §809.001, and will not boycott energy companies during the term of the contract. This provision applies to a contract that:

- 1) is with a Contractor that is not a sole proprietorship,
- 2) is with a Contractor with 10 or more full-time employees, and
- 3) has a value of \$100,000 or more.

By signing the contract, the Contractor certifies that it does not boycott energy companies and will not boycott energy companies during the term of this contract. "Boycott" means taking any action that is intended to penalize, inflict economic harm on, or limit commercial relations with a company because the company: (1) engages in the exploration, production, utilization, transportation, sale, or manufacturing of fossil fuel-based energy and does not commit or pledge to meet environmental standards beyond applicable federal and state law; or (2) does business with a company described by (1).

### CERTIFICATION TO NOT DISCRIMINATE AGAINST FIREARM ENTITIES OR FIREARM TRADE ASSOCIATIONS

Pursuant to Texas Government Code §2274.002, the Department must include a provision requiring a written verification affirming that the Contractor:

- 1) does not have a practice, policy, guidance, or directive that discriminates against a firearm entity or firearm trade association, as defined in Government Code §2274.001, and
- 2) will not discriminate against a firearm entity or firearm trade association during the term of the contract.

This provision applies to a contract that:

- 1) is with a Contractor that is not a sole proprietorship,
- 2) is with a Contractor with 10 or more full-time employees, and
- 3) has a value of \$100,000 or more.

By signing the contract, the Contractor certifies that it does not discriminate against a firearm entity or firearm trade association as described and will not do so during the term of this contract. "Discriminate against a firearm entity or firearm trade association" means, with respect to the entity or association, to: (1) refuse to engage in the trade of any goods or services with the entity or association based solely on its status as a firearm entity or firearm trade association; (2) refrain from continuing an existing business relationship with the entity or association based solely on its status as a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association; or (3) terminate an existing business relationship with the entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association. "Discriminate against a firearm entity or platform that restrict or prohibit the listing or selling of ammunition, firearms, or firearm accessories; (2) a company's refusal to engage in the trade of any goods or services, decision to refrain from continuing an existing business relationship, or decision to terminate an existing business relationship to comply with federal, state, or local law, policy, or regulations or a directive by a regulatory agency, or

# PROHIBITION ON CERTAIN TELECOMMUNICATIONS EQUIPMENT OR SERVICES

The Federal Register Notice issued the Final Rule and states that the amendment to 2 CFR 200.216 is effective on August 13, 2020. The new 2 CFR 200.471 regulation provides clarity that the telecommunications and video surveillance costs associated with 2 CFR 200.216 are unallowable for services and equipment from these specific providers. OMB's Federal Register Notice includes the new 2 CFR 200.216 and 2 CFR 200.471 regulations.

https://www.federalregister.gov/documents/2020/08/13/2020-17468/guidance-for-grants-and-agreements

Per the Federal Law referenced above, use of services, systems, or services or systems that contain components produced by any of the following manufacturers is strictly prohibited for use on this project. Therefore, for any telecommunications, CCTV, or video surveillance equipment, services or systems cannot be manufactured by, or have components manufactured by:

- Huawei Technologies Company,
- ZTE Corporation (any subsidiary and affiliate of such entities),
- Hyatera Communications Corporation,
- Hangzhou Hikvision Digital Technology Company,
- Dahua Technology Company (any subsidiary and affiliate of such entities).

Violation of this prohibition will require replacement of the equipment at the contractor's expense.

# Special Provision to Item 000 Special Labor Provisions for State Projects



### 1. GENERAL

This is a "Public Works" Project, as provided under Government Code Title 10, Chapter 2258, "Prevailing Wage Rates," and is subject to the provisions of the Statute. No provisions in the Contract are intended to be in conflict with the provisions of the Statute.

The Texas Transportation Commission has ascertained and indicated in the special provisions the regular rate of per diem wages prevailing in each locality for each craft or type of worker. Apply the wage rates contained in the specifications as minimum wage rates for the Contract.

### 2. MINIMUM WAGES, HOURS AND CONDITIONS OF EMPLOYMENT

All workers necessary for the satisfactory completion of the work are within the purview of the Contract.

Whenever and wherever practical, give local citizens preference in the selection of labor.

Do not require any worker to lodge, board or trade at a particular place, or with a particular person as a condition of employment.

Do not charge or accept a fee of any from any person who obtains work on the project. Do not require any person who obtains work on the project to pay any fee to any other person or agency obtaining employment for the person on the project.

Do not charge for tools or equipment used in connection with the duties performed, except for loss or damage of property. Do not charge for necessary camp water.

Do not charge for any transportation furnished to any person employed on the project.

The provisions apply where work is performed by piece work, station work, etc. The minimum wage paid will be exclusive of equipment rental on any shipment which the worker or subcontractor may furnish in connection with his work.

Take responsibility for carrying out the requirements of this specification and ensure that each subcontractor working on the project complies with its provisions.

Any form of subterfuge, coercion or deduction designated to evade, reduce or discount the established minimum wage scales will be considered a violation of the Contract.

The Fair Labor Standards Acts (FLSA) established one and one-half (1-1/2) pay for overtime in excess of 40 hours worked in 1 week. Do not consider time consumed by the worker in going to and returning from the place of work as part of the hours of work. Do not require or permit any worker to work in excess of 40 hours in 1 week, unless the worker receives compensation at a rate not less than 1-1/2 times the basic rate of pay for all hours worked in excess of 40 hours in the workweek.

The general rates of per diem wages prevailing in this locality for each class and type of workers whose services are considered necessary to fulfill the Contract are indicated in the special provisions, and these rates govern as minimum wage rates on this Contract. A penalty of \$60.00 per calendar day or portion of a calendar day for each worker that is paid less than the stipulated general rates of per diem wages for any work done under the Contract will be deducted. The Department, upon receipt of a complaint by a worker,

will determine within 30 days whether good cause exists to believe that the Contractor or a subcontractor has violated wage rate requirements and notify the parties involved of the findings. Make every effort to resolve the alleged violation within 14 days after notification. The next alternative is submittal to binding arbitration in accordance with the provisions of the Texas General Arbitration Act (Art. 224 et seq., Revised Statutes).

Notwithstanding any other provision of the Contract, covenant and agree that the Contractor and its subcontractors will pay each of their employees and contract labor engaged in any way in work under the Contract, a wage not less than what is generally known as the "federal minimum wage" as set out in 29 U.S.C. 206 as that Statute may be amended from time to time.

Pay any worker employed whose position is not listed in the Contract, a wage not less than the per diem wage rate established in the Contract for a worker whose duties are most nearly comparable.

#### 3. RECORD AND INSPECTIONS

Keep copies of weekly payrolls for review. Require subcontractors to keep copies of weekly payrolls for review. Show the name, occupation, number of hours worked each day and per diem wage paid each worker together with a complete record of all deductions made from such wages. Keep records for a period of 3 years from the date of completion of the Contract.

Where the piece-work method is used, indicate on the payroll for each person involved:

- Quantity of piece work performed.
- Price paid per piece-work unit.
- Total hours employed.

The Engineer may require the Contractor to file an affidavit for each payroll certifying that payroll is a true and accurate report of the full wages due and paid to each person employed.

Post or make available to employees the prevailing wage rates from the Contract. Require subcontractors to post or make available to employees the prevailing wage rates from the Contract.

The wage rates listed herein are those predetermined by the Secretary of Labor and State Statue and listed in the United States Department of Labor's (USDOL) General Decisions dated **02-24-2022** and are the minimum wages to be paid accordingly for each specified classification. To determine the applicable wage rate zone, a list entitled "TEXAS COUNTIES IDENTIFIED BY WAGE RATE ZONES" is provided in the contract. Any wage rate that is not listed herein and not in the USDOL's general decision, must be submitted to the Engineer for approval. IMPORTANT NOTICE FOR STATE PROJECTS: only the controlling wage rate zone applies to the contract. Effective 02-24-2022.

CLASS. #	CLASSIFICATION DESCRIPTION	ZONE TX02 *(TX20220002)	ZONE TX03 *(TX20220003)	ZONE TX04 *(TX20220004)	ZONE TX05 *(TX20220005)	ZONE TX06 *(TX20220006)	ZONE TX07 *(TX20220007)	ZONE TX08 *(TX20220008)	ZONE TX24 *(TX20220024)	ZONE TX25 *(TX20220025)	ZONE TX27 *(TX20220027)	ZONE TX28 *(TX20220028)	ZONE TX29 *(TX20220029)	ZONE TX30 *(TX20220030)	ZONE TX37 *(TX20220037)	ZONE TX38 *(TX20220038)	ZONE TX42 *(TX20220042)
1428	Agricultural Tractor Operator						\$12.69					\$12.35			\$11.75		
1300	Asphalt Distributor Operator	\$14.87	\$13.48	\$13.88	\$15.72	\$15.58	\$15.55	\$15.72	\$13.28	\$15.32	\$15.62	\$14.36	\$14.25	\$14.03	\$13.75	\$14.06	\$14.40
1303	Asphalt Paving Machine Operator	\$13.40	\$12.25	\$12.35	\$13.87	\$14.05	\$14.36	\$14.20	\$13.26	\$13.99	\$14.68	\$12.92	\$13.44	\$12.53	\$14.00	\$14.32	\$12.99
1106	Asphalt Raker	\$12.28	\$10.61	\$12.02	\$14.21	\$11.65	\$12.12	\$11.64	\$11.44	\$12.69	\$12.05	\$11.34	\$11.67	\$11.40	\$12.59	\$12.36	\$11.78
1112	Batching Plant Operator, Asphalt																
1115	Batching Plant Operator, Concrete																
1214	Blaster																
1615	Boom Truck Operator						\$18.36										
1444	Boring Machine Operator																
1305	Broom or Sweeper Operator	\$11.21	\$10.33	\$10.08	\$11.99		\$11.04	\$11.62		\$11.74	\$11.41	\$10.30		\$10.23	\$10.60	\$12.68	\$11.05
1144	Communications Cable Installer																
1104	Concrete Finisher, Paving and Structures	¢10 55	¢10.46	¢10.46	¢10.05	¢10.64	¢10.50	¢40.77	¢10.44	¢14.40	¢12.04	¢10.00	¢10.64	¢10.00	¢10.70	¢10.00	¢10.00
1124	Concrete Pavement Finishing Machine	\$13.55	\$12.46	\$13.16	\$12.85	\$12.64	\$12.56	\$12.77	\$12.44	\$14.12	\$13.04	\$13.38	\$12.64	\$12.80	\$12.79	\$12.98	\$13.32
1318	Operator				\$16.05		\$15.48			\$16.05		\$19.31				\$13.07	
	Concrete Paving, Curing, Float, Texturing																
1315	Machine Operator											\$16.34				\$11.71	
1333	Concrete Saw Operator				\$14.67					\$14.48	\$17.33					\$13.99	
1399	Concrete/Gunite Pump Operator Crane Operator, Hydraulic 80 tons																
1344	or less				\$18.22		\$18.36			\$18.12	\$18.04	\$20.21			\$18.63	\$13.86	
	Crane Operator, Hydraulic Over				+					Ţ.Ţ.							
1345	80 Tons																
1342	Crane Operator, Lattice Boom 80 Tons or Less	\$16.82	\$14.39	\$13.85	\$17.27		\$15.87			\$17.27		\$14.67			\$16.42	\$14.97	\$13.87
1342	Crane Operator, Lattice Boom Over	φ10.02	ψ14.3 <del>3</del>	φ13.0J	ψ17.27		φ13.07			ψ17.27		φ14.07			ψ10. <del>4</del> 2	φ14.97	φ13.0 <i>1</i>
1343	80 Tons				\$20.52		\$19.38			\$20.52		\$17.49			\$25.13	\$15.80	
1306	Crawler Tractor Operator	\$13.96	\$16.63	\$13.62	\$14.26		\$15.67			\$14.07	\$13.15	\$13.38			\$14.60	\$13.68	\$13.50
1351	Crusher or Screen Plant Operator																
1446	Directional Drilling Locator						\$11.67										
1445	Directional Drilling Operator				\$20.32		\$17.24										
1139	Electrician	\$20.96		\$19.87	\$19.80		\$26.35		\$20.27	\$19.80		\$20.92				\$27.11	\$19.87
	Excavator Operator, 50,000									<b>•</b> • <b>•</b> • •							
1347	pounds or less Excavator Operator, Over 50,000	\$13.46	\$12.56	\$13.67	\$17.19		\$12.88	\$14.38	\$13.49	\$17.19		\$13.88			\$14.09	\$12.71	\$14.42
1348	pounds		\$15.23	\$13.52	\$17.04		\$17.71			\$16.99	\$18.80	\$16.22				\$14.53	\$13.52
1150	Flagger	\$9.30	\$9.10	\$8.50	\$10.28	\$8.81	\$9.45	\$8.70		\$10.06	\$9.71	\$9.03	\$8.81	\$9.08	\$9.90	\$10.33	\$8.10
	Form Builder/Setter, Structures	\$13.52	\$12.30	\$13.38	\$12.91	\$12.71	\$12.87	\$12.38	\$12.26	\$13.84	\$12.98	\$13.07	\$13.61	\$12.82	\$14.73	\$12.23	\$12.25
1160	Form Setter, Paving & Curb	\$12.36	\$12.16	\$13.93	\$11.83	\$10.71	\$12.94			\$13.16	\$12.54	\$11.33	\$10.69		\$13.33	\$12.34	\$13.93
	Foundation Drill Operator, Crawler																
1360	Mounted				\$17.99					\$17.99						\$17.43	
1363	Foundation Drill Operator, Truck Mounted		\$16.86	\$22.05	\$21.51		\$16.93			\$21.07	\$20.20	\$20.76		\$17.54	\$21.39	\$15.89	\$22.05
1000	Front End Loader Operator,		ψ10.00	ψ22.05	ψ <b>2</b> 1. <b>J</b> I		ψ10.95			ψ21.07	ψ20.20	ψ20.70		ψττ.34	Ψ <u>2</u> 1.09	ψ10.09	ψ22.00
1369	3 CY or Less	\$12.28	\$13.49	\$13.40	\$13.85		\$13.04	\$13.15	\$13.29	\$13.69	\$12.64	\$12.89			\$13.51	\$13.32	\$12.17
4070	Front End Loader Operator,	¢ 40	¢ 10.00	¢10.05	<b>6</b> 4 4 6 5		¢ 10.0 i	¢10.00	¢ 10 5-	<u> </u>	¢ 10	A10.00			<b>610</b> / 10	6 4 0 V -	¢10.05
-	Over 3 CY	\$12.77	\$13.69	\$12.33	\$14.96		\$13.21	\$12.86	\$13.57	\$14.72	\$13.75	\$12.32			\$13.19	\$13.17	\$13.02
1329	Joint Sealer	¢10.00	¢0.00	¢10.00	¢10 51	¢10 71	¢10 50	¢10.04	¢10 50	¢10.70	¢10.45	¢10.00	¢10.05	¢10.00	¢10 54	¢11.00	¢10.45
1172	Laborer, Common	\$10.30	\$9.86	\$10.08	\$10.51	\$10.71	\$10.50	\$10.24	\$10.58	\$10.72	\$10.45	\$10.30	\$10.25	\$10.03	\$10.54	\$11.02	\$10.15
1175	Laborer, Utility	\$11.80	\$11.53	\$12.70	\$12.17	\$11.81	\$12.27	\$12.11	\$11.33	\$12.32	\$11.80	\$11.53	\$11.23	\$11.50	\$11.95	\$11.73	\$12.37

CLASS. #	CLASSIFICATION DESCRIPTION	ZONE TX02 *(TX20220002)	ZONE TX03 *(TX20220003)	ZONE TX04 *(TX20220004)	ZONE TX05 *(TX20220005)	ZONE TX06 *(TX20220006)	ZONE TX07 *(TX20220007)	ZONE TX08 *(TX20220008)	ZONE TX24 *(TX20220024)	ZONE TX25 *(TX20220025)	ZONE TX27 *(TX20220027)	ZONE TX28 *(TX20220028)	ZONE TX29 *(TX20220029)	ZONE TX30 *(TX202220030)	ZONE TX37 *(TX20220037)	ZONE TX38 *(TX20220038)	ZONE TX42 *(TX20220042)
1346	Loader/Backhoe Operator	\$14.18	\$12.77	\$12.97	\$15.68		\$14.12			\$15.18	\$13.58	\$12.87		\$13.21	\$14.13	\$14.29	\$12.90
1187	Mechanic	\$20.14	\$15.47	\$17.47	\$17.74	\$17.00	\$17.10			\$17.68	\$18.94	\$18.58	\$17.00	\$16.61	\$18.46	\$16.96	\$17.47
1380	Milling Machine Operator	\$15.54	\$14.64	\$12.22	\$14.29		\$14.18			\$14.32	\$14.35	\$12.86			\$14.75	\$13.53	\$12.80
1390	Motor Grader Operator, Fine Grade	\$17.49	\$16.52	\$16.88	\$17.12	\$18.37	\$18.51	\$16.69	\$16.13	\$17.19	\$18.35	\$17.07	\$17.74	\$17.47	\$17.08	\$15.69	\$20.01
1393	Motor Grader Operator, Rough	\$16.15	\$14.62	\$15.83	\$16.20	\$17.07	\$14.63	\$18.50		\$16.02	\$16.44	\$15.12	\$16.85	\$14.47	\$17.39	\$14.23	\$15.53
1413	Off Road Hauler			\$10.08	\$12.26		\$11.88			\$12.25		\$12.23			\$13.00	\$14.60	
1196	Painter, Structures					\$21.29	\$18.34						\$21.29			\$18.62	
1396	Pavement Marking Machine Operator	\$16.42		¢12.10	\$13.55		¢10.47	¢10.01		\$13.63	\$14.60	\$13.17		\$16.65	\$10.54	\$11.18	¢12.10
	•	\$10.42		\$13.10	\$13.33		\$19.17	\$12.01		\$13.03	\$14.0U	\$I3.I <i>1</i>		¢10.01	\$10.54	\$II.IO	\$13.10
	Percussion or Rotary Drill Operator															\$14.95	i1
1202	Piledriver		\$11.87	\$14.64	\$13.17	\$11.17	\$12.79		\$11.37	\$13.24	¢10.66	\$13.24	\$11.17	\$11.67			¢14.64
1205	Pipelayer	\$12.85	\$11.87	\$14.64	\$13.17 \$11.90	\$11.17	\$12.79		\$11.37	\$13.24	\$12.66	\$13.24	\$11.17	\$11.67		\$12.12	\$14.64
	Reclaimer/Pulverizer Operator	\$12.85	¢14.07	¢17 50			\$12.88			\$11.01 \$16.18	¢10.74	\$10.46		¢17.10		\$15.15	¢47.70
1500	Reinforcing Steel Worker		\$14.07	\$17.53	\$16.17 \$13.29			¢44.04			\$12.74			\$17.10	¢44.74		\$17.72
1402	Roller Operator, Asphalt	\$10.95		\$11.96			\$12.78	\$11.61		\$13.08	\$12.36	\$11.68		¢40.04	\$11.71	\$11.95	\$11.50
	Roller Operator, Other	\$10.36	<b>0</b> 44.07	\$10.44	\$11.82		\$10.50	\$11.64	<b>*</b> 44.40	\$11.51	\$10.59	\$10.30		\$12.04	\$12.85	\$11.57	\$10.66
	Scraper Operator	\$10.61	\$11.07	\$10.85	\$12.88		\$12.27		\$11.12	\$12.96	\$11.88	\$12.43		\$11.22	\$13.95	\$13.47	\$10.89
	Self-Propelled Hammer Operator	¢10.00	¢40.04	¢44.44	¢44.74		¢44.54	<b>\$45.50</b>	¢40.44	¢44.50	¢44.04	¢40.00		¢40.40	¢40.70	¢40.07	611.11
	Servicer	\$13.98	\$12.34	\$14.11	\$14.74		\$14.51	\$15.56	\$13.44	\$14.58	\$14.31	\$13.83		\$12.43	\$13.72	\$13.97	\$14.11
1513	Sign Erector Slurry Seal or Micro-Surfacing Machine																<b>└────</b> ┤
1708	Operator																1
1341	Small Slipform Machine Operator									\$15.96							
1515	Spreader Box Operator	\$12.60		\$13.12	\$14.71		\$14.04			\$14.73	\$13.84	\$13.68		\$13.45	\$11.83	\$13.58	\$14.05
1705	Structural Steel Welder															\$12.85	
1509	Structural Steel Worker						\$19.29									\$14.39	
1339	Subgrade Trimmer																
1143	Telecommunication Technician																
1145	Traffic Signal/Light Pole Worker Trenching Machine Operator,						\$16.00										
1440	Heavy						\$18.48										1
	Trenching Machine Operator,																
1437	Light																
	Truck Driver Lowboy-Float	\$14.46	\$13.63	\$13.41	\$15.00	\$15.93	\$15.66			\$16.24	\$16.39	\$14.30	\$16.62	\$15.63	\$14.28	\$16.03	\$13.41
	Truck Driver Transit-Mix				\$14.14					\$14.14							L
1600	Truck Driver, Single Axle Truck Driver, Single or Tandem Axle	\$12.74	\$10.82	\$10.75	\$13.04	\$11.61	\$11.79	\$13.53	\$13.16	\$12.31	\$13.40	\$10.30	\$11.61		\$11.97	\$11.46	\$10.75
1606	Dump Truck	\$11.33	\$14.53	\$11.95	\$12.95		\$11.68		\$14.06	\$12.62	\$11.45	\$12.28		\$13.08	\$11.68	\$11.48	\$11.10
	Truck Driver, Tandem Axle Tractor with	φ11.00	φ1 <del>4</del> .00	Ş11.00	ψ12.00		ψ11.00		φ14.00	ψ12.02	ψι ιτυ	ψ12.20		ψ10.00	φ11.00	ψ11 <del>1</del> 0	φ11.10
1607	Semi Trailer	\$12.49	\$12.12	\$12.50	\$13.42		\$12.81	\$13.16		\$12.86	\$16.22	\$12.50			\$13.80	\$12.27	\$12.50
1441	Tunneling Machine Operator, Heavy																
1442	Tunneling Machine Operator, Light																
1706	Welder		\$14.02		\$14.86		\$15.97		\$13.74	\$14.84					\$13.78		
1520	Work Zone Barricade Servicer	\$10.30	\$12.88	\$11.46	\$11.70	\$11.57	\$11.85	\$10.77		\$11.68	\$12.20	\$11.22	\$11.51	\$12.96	\$10.54	\$11.67	\$11.76

Notes:

\*Represents the USDOL wage decision.

Any worker employed on this project shall be paid at the rate of one and one half (1-1/2) times the regular rate for every hour worked in excess of forty (40) hours per week.

For reference, the titles and descriptions for the classifications listed here are detailed further in the AGC of Texas' *Standard Job Classifications and Descriptions for Highway, Heavy, Utilities, and Industrial Construction in Texas* posted on the AGC's Web site for any contractor.

### TEXAS COUNTIES IDENTIFIED BY WAGE RATE ZONES: 2, 3, 4, 5, 6, 7, 8, 24, 25, 27, 28, 29, 30, 37, 38, 42

County Name	Zone	County Name	Zone	County Name	Zone	County Name	Zone
Anderson		Donley		Karnes		Reagan	37
Andrews		Duval		Kaufman		Real	37
Angelina		Eastland		Kendall	7	Red River	28
Aransas		Ector	2	Kenedy		Reeves	8
Archer		Edwards	8	Kent		Refugio	27
Armstrong	2	El Paso		Kerr	27	Roberts	37
Atascosa	7	Ellis		Kimble	37	Robertson	7
Austin		Erath		King		Rockwall	25
Bailey	-	Falls		Kinney	8	Runnels	37
Bandera	7	Fannin		Kleberg	27	Rusk	4
Bastrop	7	Fayette		Knox		Sabine	28
Baylor		Fisher		Lamar		San Augustine	28
Bee		Floyd		Lamb	37	San Jacinto	38
Bell	7	Foard		Lampasas	7	San Patricio	29
Bexar	7	Fort Bend		LaSalle		San Saba	37
Blanco		Franklin		Lavaca	27	Schleicher	37
Borden		Freestone		Lee	27	Scurry	37
Bosque	28	Frio		Leon		Shackelford	37
Bowie	4	Gaines		Liberty		Shelby	28
Brazoria	38	Galveston		Limestone	28	Sherman	37
Brazos	7	Garza	37	Lipscomb	37	Smith	4
Brewster	8	Gillespie		Live Oak	27	Somervell	28
Briscoe	37	Glasscock		Llano	27	Starr	30
Brooks	30	Goliad	29	Loving	37	Stephens	37
Brown	37	Gonzales	27	Lubbock	2	Sterling	37
Burleson	7	Gray	37	Lynn	37	Stonewall	37
Burnet	27	Grayson	25	Madison	28	Sutton	8
Caldwell	7	Gregg	4	Marion	28	Swisher	37
Calhoun	29	Grimes	28	Martin	37	Tarrant	25
Callahan	25	Guadalupe	7	Mason	27	Taylor	2
Cameron	3	Hale	37	Matagorda	27	Terrell	8
Camp	28	Hall		Maverick	30	Terry	37
Carson	2	Hamilton	28	McCulloch	37	Throckmorton	37
Cass	28	Hansford	37	McLennan	7	Titus	28
Castro	37	Hardeman	37	McMullen	30	Tom Green	2
Chambers		Hardin	38	Medina	7	Travis	7
Cherokee	28	Harris		Menard	37	Trinity	28
Childress		Harrison		Midland	2	Tyler	28
Clay	25	Hartley	37	Milam		Úpshur	4
Cochran		Haskell		Mills	37	Upton	37
Coke	37	Hays	7	Mitchell		Uvalde	30
Coleman		Hemphill	37	Montague		Val Verde	8
Collin		Henderson		Montgomery		Van Zandt	28
Collingsworth		Hidalgo		Moore		Victoria	6
Colorado		Hill		Morris		Walker	28
Comal		Hockley	-	Motley	-	Waller	38
Comanche		Hood		Nacogdoches		Ward	37
Concho	-	Hopkins		Navarro		Washington	28
Cooke		Houston		Newton		Webb	3
Coryell		Howard		Nolan		Wharton	27
Cottle		Hudspeth		Nueces		Wheeler	37
Crane		Hunt		Ochiltree		Wichita	5
Crockett		Hutchinson		Oldham		Wilbarger	37
Crosby	2	Irion	2	Orange		Willacy	30
Culberson	8	Jack		Palo Pinto		Williamson	7
Dallam		Jackson		Panola		Wilson	7
Dallas	25	Jasper		Parker		Winkler	37
Dawson		Jeff Davis		Parmer		Wise	25
Deaf Smith	37	Jefferson		Pecos	8	Wood	28
Delta	25	Jim Hogg		Polk		Yoakum	37
Denton		Jim Wells		Potter	2	Young	37
DeWitt	27	Johnson		Presidio		Zapata	30
Dickens	37	Jones	25	Rains		Zavala	30
Dimmit	30			Randall	2		

## Special Provision to Item 000 Nondiscrimination



### 1. DESCRIPTION

All recipients of federal financial assistance are required to comply with various nondiscrimination laws including Title VI of the Civil Rights Act of 1964, as amended, (Title VI). Title VI forbids discrimination against anyone in the United States on the grounds of race, color, or national origin by any agency receiving federal funds.

Texas Department of Transportation, as a recipient of Federal financial assistance, and under Title VI and related statutes, ensures that no person shall on the grounds of race, religion (where the primary objective of the financial assistance is to provide employment per 42 U.S.C. § 2000d-3), color, national origin, sex, age or disability be excluded from participation in, be denied the benefits of, or otherwise be subjected to discrimination under any Department programs or activities.

### 2. DEFINITION OF TERMS

Where the term "contractor" appears in the following six nondiscrimination clauses, the term "contractor" is understood to include all parties to contracts or agreements with the Texas Department of Transportation.

### 3. NONDISCRIMINATION PROVISIONS

During the performance of this contract, the contractor agrees as follows:

- 3.1. **Compliance with Regulations**. The Contractor shall comply with the Regulations relative to nondiscrimination in Federally-assisted programs of the Department of Transportation (hereinafter, "DOT") Title 49, Code of Federal Regulations, Part 21, as they may be amended from time to time, (hereinafter referred to as the Regulations), which are herein incorporated by reference and made a part of this contract.
- 3.2. **Nondiscrimination**. The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor shall not participate either directly or indirectly in the discrimination prohibited by section 21.5 of the Regulations, including employment practices when the contract covers a program set forth in Appendix B of the Regulations.
- 3.3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment: In all solicitations either by competitive bidding or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials or leases of equipment, each potential subcontractor or supplier shall be notified by the contractor of the contractor's obligations under this contract and the Regulations relative to nondiscrimination on the grounds of race, color, or national origin.
- 3.4. Information and Reports: The contractor shall provide all information and reports required by the Regulations or directives issued pursuant thereto, and shall permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Texas Department of Transportation to be pertinent to ascertain compliance with such Regulations, orders and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish this information the contractor shall so certify to the Recipient, or the Texas Department of Transportation as appropriate, and shall set forth what efforts it has made to obtain the information.

- 3.5. **Sanctions for Noncompliance**. In the event of the contractor's noncompliance with the nondiscrimination provisions of this contract, the Recipient shall impose such contract sanctions as it or the Texas Department of Transportation may determine to be appropriate, including, but not limited to:
  - withholding of payments to the contractor under the contract until the contractor complies, and/or
  - cancellation, termination or suspension of the contract, in whole or in part.
- 3.6. Incorporation of Provisions. The contractor shall include the provisions of paragraphs (1) through (6) in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Regulations, or directives issued pursuant thereto. The contractor shall take such action with respect to any subcontract or procurement as the Recipient or the Texas Department of Transportation may direct as a means of enforcing such provisions including sanctions for non-compliance: Provided, however, that, in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or supplier as a result of such direction, the contractor may request the Recipient to enter into such litigation to protect the interests of the Recipient, and, in addition, the contractor may request the United States to enter into such litigation to protect the interests of the United States.

# Special Provision to Item 000 Small Business Enterprise in State Funded Projects



### 1. DESCRIPTION

The purpose of this Special Provision is to carry out the Texas Department of Transportation's policy of ensuring that Small Business Enterprise (SBE) has an opportunity to participate in the performance of contracts. If the SBE goal is greater than zero, Article A of this Special Provision shall apply to this Contract; otherwise, Article B of this Special Provision applies. The percentage goal for SBE participation in the work to be performed under this contract will be shown in the proposal.

### 2. DEFINITIONS

Small Business Enterprise (SBE) is a firm (including affiliates) certified by the Department whose annual gross receipts do not exceed the U.S. Small Business Administration's size standards for 4 consecutive years. Firms certified as Historically Underutilized Businesses (HUBs) by the Texas Comptroller of Public Accounts and as Disadvantaged Business Enterprises (DBEs) by the Texas Uniform Certification Program automatically qualify as SBEs.

#### 2.1. Article A - SBE Goal is Greater than Zero.

- 2.1.1. **Policy**. The Department is committed to providing contracting opportunities for small businesses. In this regard, it is the Department's policy to develop and maintain a program in order to facilitate contracting opportunities for small businesses. Consequently, the requirements of the Department's Small Business Enterprise Program apply to this contract as follows:
- 2.1.1.1. The Contractor shall make a good faith effort to meet the SBE goal for this contract.
- 2.1.1.2. The Contractor and any Subcontractors shall not discriminate on the basis of race, color, national origin, age, disability or sex in the award and performance of this contract. These nondiscrimination requirements shall be incorporated into any subcontract and purchase order.
- 2.1.1.3. After a conditional award is made to the low bidder, the Department will determine the adequacy of a Contractor's efforts to meet the contract goal, as is outlined under Section 2, "Contractor's Responsibilities." If the requirements of Section 2 are met, the contract will be forwarded to the Contractor for execution.

The Contractor's performance, during the construction period of the contract in meeting the SBE goal, will be monitored by the Department.

- 2.1.2. **Contractor's Responsibilities**. These requirements must be satisfied by the Contractor. A SBE Contractor may satisfy the SBE requirements by performing at least 25% of the contract work with its own organization as defined elsewhere in the contract.
- 2.1.2.1. The Contractor shall submit a completed SBE Commitment Agreement Form for each SBE they intend to use to satisfy the SBE goal so as to arrive in the Department's Office of Civil Rights (OCR) in Austin, Texas not later than 5:00 p.m. on the 10th business day, excluding national holidays, after the conditional award of the contract. When requested, additional time, not to exceed 7 business days, excluding national holidays, may be granted based on documentation submitted by the Contractor.
- 2.1.2.2. A Contractor who cannot meet the contract goal, in whole or in part, shall document the good faith efforts taken to meet the SBE goal. The Department will consider as good faith efforts all documented explanations

that are submitted and that describe a Contractor's failure to meet a SBE goal or obtain SBE participation, including:

- 2.1.2.2.1. Advertising in general circulation, trade association, and/or minority/women focus media concerning subcontracting opportunities,
- 2.1.2.2.2. Dividing the contract work into reasonable portions in accordance with standard industry practices,
- 2.1.2.2.3. Documenting reasons for rejection or meeting with the rejected SBE to discuss the rejection,
- 2.1.2.2.4. Providing qualified SBEs with adequate information about bonding, insurance, plans, specifications, scope of work, and the requirements of the contract,
- 2.1.2.2.5. Negotiating in good faith with qualified SBEs, not rejecting qualified SBEs who are also the lowest responsive bidder, and;
- 2.1.2.2.6. Using the services of available minorities and women, community organizations, contractor groups, local, state and federal business assistance offices, and other organizations that provide support services to SBEs.
- 2.1.2.3. The good faith effort documentation is due at the time and place specified in Subarticle 2.(a). of this Special Provision. The Director of the DBE & SBE Programs Section will evaluate the Contractor's documentation. If it is determined that the Contractor has failed to meet the good faith effort requirements, the Contractor will be given an opportunity for reconsideration by the Department.
- 2.1.2.4. Should the bidder to whom the contract is conditionally awarded refuse, neglect or fail to meet the SBE goal and/or demonstrate to the Department's satisfaction sufficient efforts to obtain SBE participation, the proposal guaranty filed with the bid shall become the property of the State, not as a penalty, but as liquidated damages to the Department.
- 2.1.2.5. The Contractor must not terminate a SBE subcontractor submitted on a commitment agreement for a contract with an assigned goal without the prior written consent of the Department.
- 2.1.2.6. The Contractor shall designate a SBE contact person who will administer the Contractor's SBE program and who will be responsible for submitting reports, maintaining records, and documenting good faith efforts to use SBEs.
- 2.1.2.7. The Contractor must inform the Department of the representative's name, title and telephone number within 10 days of beginning work.
- 2.1.3. Eligibility of SBEs.
- 2.1.3.1. The Department certifies the eligibility of SBEs.
- 2.1.3.2. The Department maintains and makes available to interested parties a directory of certified SBEs.
- 2.1.3.3. Only firms certified at the time of letting or at the time the commitments are submitted are eligible to be used in the information furnished by the Contractor required under Section 2.(a) above.
- 2.1.3.4. Certified HUBs and DBEs are eligible as SBEs.
- 2.1.3.5. Small Business Size Regulations and Eligibility is referenced on e-CFR (Code of Federal Regulations), Title 13 – Business Credit and Assistance, Chapter 1 – Small Business Administration, Part 121 – Small Business Size Regulations, Subpart A – Size Eligibility Provisions and Standards.
- 2.1.4. **Determination of SBE Participation**. SBE participation shall be counted toward meeting the SBE goal in this contract in accordance with the following:

- 2.1.4.1. A Contractor will receive credit for all payments actually made to a SBE for work performed and costs incurred in accordance with the contract, including all subcontracted work.
- 2.1.4.2. A SBE Contractor or subcontractor may not subcontract more than 75% of a contract. The SBE shall perform not less than 25% of the value of the contract work with its own organization.
- 2.1.4.3. A SBE may lease equipment consistent with standard industry practice. A SBE may lease equipment from the prime contractor if a rental agreement, separate from the subcontract specifying the terms of the lease arrangement, is approved by the Department prior to the SBE starting the work in accordance with the following:
- 2.1.4.3.1. If the equipment is of a specialized nature, the lease may include the operator. If the practice is generally acceptable with the industry, the operator may remain on the lessor's payroll. The operator of the equipment shall be subject to the full control of the SBE, for a short term, and involve a specialized piece of heavy equipment readily available at the job site.
- 2.1.4.3.2. For equipment that is not specialized, the SBE shall provide the operator and be responsible for all payroll and labor compliance requirements.

#### 2.1.5. Records and Reports.

2.1.5.1. The Contractor shall submit monthly reports, after work begins, on SBE payments, (including payments to HUBs and DBEs). The monthly reports are to be sent to the Area Engineer's office. These reports will be due within 15 days after the end of a calendar month.

These reports will be required until all SBE subcontracting or supply activity is completed. The "SBE Progress Report" is to be used for monthly reporting. Upon completion of the contract and prior to receiving the final payment, the Contractor shall submit the "SBE Final Report" to the Office of Civil Rights and a copy to the Area Engineer. These forms may be obtained from the Office of Civil Rights and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by requesting, on a random basis, copies of invoices and cancelled checks paid to SBEs. When the SBE goal requirement is not met, documentation supporting Good Faith Efforts, as outlined in Section 2.(b) of this Special Provision, must be submitted with the Final Report.

- 2.1.5.2. SBE subcontractors and/or suppliers should be identified on the monthly report by SBE certification number, name and the amount of actual payment made to each during the monthly period. These reports are required regardless of whether or not SBE activity has occurred in the monthly reporting period.
- 2.1.5.3. All such records must be retained for a period of 3 years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the Department.
- 2.1.6. **Compliance of Contractor**. To ensure that SBE requirements of this contract are complied with, the Department will monitor the Contractor's efforts to involve SBEs during the performance of this contract. This will be accomplished by a review of monthly reports submitted by the Contractor indicating his progress in achieving the SBE contract goal and by compliance reviews conducted by the Department.

A Contractor's failure to comply with the requirements of this Special Provision shall constitute a material breach of this contract. In such a case, the Department reserves the right to employ remedies as the Department deems appropriate in the terms of the contract.

#### 2.2. Article B - No SBE Goal.

2.2.1. **Policy**. It is the policy of the Department that SBEs shall have an opportunity to participate in the performance of contracts. Consequently, the requirements of the Department's Small Business Enterprise Program apply to this contract as specified in Section 2-5 of this Article.

- 2.2.2. **Contractor's Responsibilities**. If there is no SBE goal, the Contractor will offer SBEs an opportunity to participate in the performance of contracts and subcontracts.
- 2.2.3. **Prohibit Discrimination**. The Contractor and any subcontractor shall not discriminate on the basis of race, color, national origin, religion, age, disability or sex in the award and performance of contracts. These nondiscrimination requirements shall be incorporated into any subcontract and purchase order.

#### 2.2.4. Records and Reports.

2.2.4.1. The Contractor shall submit reports on SBE (including HUB and DBE) payments. The reports are to be sent to the Area Engineer's office. These reports will be due annually by the 31<sup>st</sup> of August or at project completion, whichever comes first.

These reports will be required until all SBE subcontracting or supply activity is completed. The "SBE Progress Report" is to be used for reporting. Upon completion of the contract and prior to receiving the final payment, the Contractor shall submit the "SBE Final Report" to the Office of Civil Rights and a copy to the Area Engineer. These forms may be obtained from the Office of Civil Rights and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by requesting copies of invoices and cancelled checks paid to SBEs on a random basis.

- 2.2.4.2. SBE subcontractors and/or suppliers should be identified on the report by SBE Certification Number, name and the amount of actual payment made.
- 2.2.4.3. All such records must be retained for a period of 3 years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the Department.

## Special Provision 000 Certificate of Interested Parties (Form 1295)



Submit a notarized Form 1295, "Certificate of Interested Parties," in the following instances:

- at Contract execution for Contracts awarded by the Commission;
- at Contract execution for Contracts awarded by the District Engineer or Chief Engineer with an award amount of \$1,000,000 or more; at any time an existing Contract awarded by the District Engineer or Chief Engineer increases in value to \$1,000,000 or more due to changes in the Contract; at any time there is an increase of \$1,000,000 or more to an existing Contract (change orders, extensions, and renewals); or
- at any time there is a change to the information in Form 1295, when the form was filed for an existing Contract.

Form 1295 and instructions on completing and filing the form are available on the Texas Ethics Commission website.

# Special Provision to Item 000 Schedule of Liquidated Damages



Table 1 Schedule of Liquidated Damages							
For Dollar Amount	of Original Contract	Dollar Amount of Daily Contract					
From More Than	To and Including	Administration Liquidated Damages per Working Day					
0	100,000	570					
100,000	500,000	590					
500,000	1,000,000	610					
1,000,000	1,500,000	685					
1,500,000	3,000,000	785					
3,000,000	5,000,000	970					
5,000,000	10,000,000	1,125					
10,000,000	20,000,000	1,285					
20,000,000	Over 20,000,000	2,590					

In addition to the amount shown in Table 1, the Liquidated Damages will be increased by the amount shown in Item 8 of the General Notes for Road User Cost (RUC), when applicable.

# Special Provision 000 Notice of Contractor Performance Evaluations



### 1. GENERAL

In accordance with Texas Transportation Code §223.012, the Engineer will evaluate Contractor performance based on quality, safety, and timeliness of the project.

### 2. DEFINITIONS

2.1. **Project Recovery Plan (PRP)**—a formal, enforceable plan developed by the Contractor, in consultation with the District, that documents the cause of noted quality, safety, and timeliness issues and specifies how the Contractor proposes to correct project-specific performance deficiencies.

In accordance with Title 43, Texas Administrative Code (TAC), §9.23, the District will request a PRP if the Contractor's performance on a project is below the Department's acceptable standards and will monitor the Contractor's compliance with the established plan.

2.2. **Corrective Action Plan (CAP)**—a formal, enforceable plan developed by the Contractor, and proposed for adoption by the Construction or Maintenance Division, that documents the cause of noted quality, safety, and timeliness issues and specifies how the Contractor proposes to correct statewide performance deficiencies.

In accordance with 43 TAC §9.23, the Division will request a CAP if the average of the Contractor's statewide final evaluation scores falls below the Department's acceptable standards for the review period and will monitor the Contractor's compliance with the established plan.

### 3. CONTRACTOR EVALUATIONS

In accordance with Title 43, Texas Administrative Code (TAC) §9.23, the Engineer will schedule evaluations at the following intervals, at minimum:

- Interim evaluations—at or within 30 days after the anniversary of the notice to proceed, for Contracts extending beyond 1 yr., and
- Final evaluation—upon project closeout.

In case of a takeover agreement, neither the Surety nor its performing Contractor will be evaluated.

In addition to regularly scheduled evaluations, the Engineer may schedule an interim evaluation at any time to formally communicate issues with quality, safety, or timeliness. Upon request, work with the Engineer to develop a PRP to document expectations for correcting deficiencies.

Comply with the PRP as directed. Failure to comply with the PRP may result in additional remedial actions available to the Engineer under Item 5, "Control of the Work." Failure to meet a PRP to the Engineer's satisfaction may result in immediate referral to the Performance Review Committee for consideration of further action against the Contractor.

The Engineer will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards or comply with a PRP, including consideration of sufficient time.

Follow the escalation ladder if there is a disagreement regarding an evaluation or disposition of a PRP. The Contractor may submit additional documentation pertaining to the dispute. The District Engineer's decision

on a Contractor's evaluation score and recommendation of action required in a PRP or follow up for noncompliance is final.

#### 4. DIVISION OVERSIGHT

Upon request of the Construction or Maintenance Division, develop and submit for Division approval a proposed CAP to document expectations for correcting deficiencies in the performance of projects statewide.

Comply with the CAP as directed. The CAP may be modified at any time up to completion or resolution after written approval of the premise of change from the Division. Failure to meet an adopted or revised adopted CAP to the Division's satisfaction within 120 days will result in immediate referral to the Performance Review Committee for consideration of further action against the Contractor.

The Division will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards or comply with a CAP, including consideration of sufficient time and associated costs as appropriate.

#### 5. PERFORMANCE REVIEW COMMITTEE

The Performance Review Committee, in accordance with 43 TAC §9.24, will review at minimum all final evaluations, history of compliance with PRPs, any adopted CAPs including agreed modifications, any information about events outside a Contractor's control contributing to the Contractor's performance, and any documentation submitted by the Contractor and may recommend one or more of the following actions:

- take no action,
- reduce the Contractor's bidding capacity,
- prohibit the Contractor from bidding on one or more projects,
- immediately suspend the Contractor from bidding for a specified period of time, by reducing the Contractor's bidding capacity to zero, or
- prohibit the Contractor from being awarded a Contract on which they are the apparent low bidder.

The Deputy Executive Director will determine any further action against the Contractor.

#### 6. APPEALS PROCESS

In accordance with 43 TAC §9.25, the Contractor may appeal remedial actions determined by the Deputy Executive Director.

### Special Provision to Item 2 Instructions to Bidders



Item 2, "Instructions to Bidders," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

#### Article 2.3., "Issuing Proposal Forms," is supplemented by the following:

the Bidder or affiliate of the Bidder that was originally determined as the apparent low Bidder on a project, but was deemed nonresponsive for failure to register or participate in the Department of Homeland Security's (DHS) E-Verify system as specified in Article 2.15., "Department of Homeland Security (DHS) E-Verify System," is prohibited from rebidding that specific project.

#### Article 2.7., "Nonresponsive Bid," is supplemented by the following:

the Bidder failed to participate in the Department of Homeland Security's (DHS) as specified in Article 2.15., "Department of Homeland Security (DHS) E-Verify System."

#### Article 2.15., "Department of Homeland Security (DHS) E-Verify System," is added.

The Department will not award a Contract to a Contractor that is not registered in the DHS E-Verify system. Remain active in E=Verify throughout the life of the contract. In addition, in accordance with paragraph six of Article 8.2, "Subcontracting," include this requirement in all subcontracts and require that subcontractors remain active in E-Verify until their work is completed.

If the apparent low Bidder does not appear on the DHS E-Verify system prior to award, the Department will notify the Contractor that they must submit documentation showing that they are compliant within 5-business days after the date the notification was sent. A Contractor who fails to comply or respond within the deadline will be declared non-responsive and the Department will execute the proposal guaranty. The proposal guaranty will become the property of the State, not as a penalty, but as liquidated damages. The Bidder forfeiting the proposal guaranty will not be considered in future proposals for the same work unless there has been a substantial change in the scope of the work.

The Department may recommend that the Commission:

- reject all bids, or
- award the Contract to the new apparent low Bidder, if the Department is able to verify the Bidder's participation in the DHS E-verify system. For the Bidder who is not registered in E-Verify, the Department will allow for one business day after notification to provide proof of registration.

If the Department is unable to verify the new apparent low Bidder's participation in the DHS E-Verify system within one calendar day:

- the new apparent low Bidder will not be deemed nonresponsive,
- the new apparent low Bidder's guaranty will not be forfeited,
- the Department will reject all bids, and
- the new apparent low Bidder will remain eligible to receive future proposals for the same project.

## Special Provision to Item 2 Instructions to Bidders



Item 2, "Instructions to Bidders" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 3., "Issuing Proposal Forms," is supplemented by the following:

The Electronic State Business Daily (ESBD), the Integrated Contractor Exchange (iCX) system, and the project proposal are the official sources of advertisement and bidding information for the State and Local Lettings. Bidders should bid the project using the information found therein, including any addenda. These sources take precedence over information from other sources, including TxDOT webpages, which are unofficial and intended for informational purposes only.

## Special Provision to Item 3 Award and Execution Contract



Item 3, Award and Execution of Contract," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 4.3, "Insurance." The first sentence is voided and replaced by the following:

For construction and building Contracts, submit a certificate of insurance showing coverages in accordance with Contract requirements. For routine maintenance Contracts, refer to Article 8, "Beginning of Work."

Article 8, "Beginning of Work." The first sentence is supplemented by the following:

For a routine maintenance Contract, do not begin work until a certificate of insurance showing coverages in accordance with the Contract requirements is provided and accepted.

## Special Provision to Item 3 Award and Execution of Contract



Item 3, "Award and Execution of Contract" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

#### Section 4.3 "Insurance" is being amended by the following:

Table 2 Insurance Requirements						
Type of Insurance	Amount of Coverage					
Commercial General Liability Insurance	Not Less Than:					
	\$600,000 each occurrence					
Business Automobile Policy	Not Less Than:					
	\$600,000 combined single limit					
Workers' Compensation	Not Less Than:					
	Statutory					
All Risk Builder's Risk Insurance	100% of Contract Price					
(For building-facilities contracts only)						

# Special Provision to Item 5 Control of the Work



Item 5, "Control of the Work," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 5.1, "Authority of Engineer," is voided and replaced by the following.

The Engineer has the authority to observe, test, inspect, approve, and accept the work. The Engineer decides all questions about the quality and acceptability of materials, work performed, work progress, Contract interpretations, and acceptable Contract fulfillment. The Engineer has the authority to enforce and make effective these decisions.

The Engineer acts as a referee in all questions arising under the terms of the Contract. The Engineer's decisions will be final and binding.

The Engineer will pursue and document actions against the Contractor as warranted to address Contract performance issues. Contract remedies include, but are not limited to, the following:

- conducting interim performance evaluations requiring a Project Recovery Plan, in accordance with Title 43, Texas Administrative Code (TAC) §9.23,
- requiring the Contractor to remove and replace defective work, or reducing payment for defective work,
- removing an individual from the project,
- suspending the work without suspending working day charges,
- assessing standard liquidated damages to recover the Department's administrative costs, including additional projectspecific liquidated damages when specified in the Contract in accordance with 43 TAC §9.22,
- withholding estimates,
- declaring the Contractor to be in default of the Contract, and
- in case of a Contractor's failure to meet a Project Recovery Plan, referring the issue directly to the Performance Review Committee for consideration of further action against the Contractor in accordance with 43 TAC §9.24.

The Engineer will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards, including consideration of sufficient time.

Follow the issue escalation ladder if there is disagreement regarding the application of Contract remedies.

## Special Provision to Item 5 Control of the Work



Item 5, "Control of the Work" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

# Article 5.4, "Coordination of Plans, Specifications, and Special Provisions," the last sentence of the last paragraph is replaced by the following:

Failure to promptly notify the Engineer will constitute a waiver of all contract claims against the Department for misunderstandings or ambiguities that result from the errors, omissions, or discrepancies.

### Special Provision to Item 6 Control of Materials



For this project, Item 6, "Control of Materials," of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 4., "Sampling, Testing, and Inspection," is supplemented by the following:

Meet with the Engineer and choose either the Department or a Department-selected Commercial Lab (CL) for conducting the subset of project-level sampling and testing shown in Table 1, "Select Guide Schedule Sampling and Testing." Selection may be made on a test by test basis. CLs will meet the testing turnaround times shown (includes test time and time for travel/sampling and reporting) and in all cases issue test reports as soon as possible.

If the Contractor chooses a Department-selected CL for any Table 1 sampling and testing:

- notify the Engineer, District Lab, and the CL of project scheduling that may require CL testing;
- provide the Engineer, District Lab, and CL at least 24 hours' notice by phone and e-mail;
- reimburse the Department for CL Table 1 testing using the contract fee schedule for the CL (including mileage and travel/standby time) at the minimum guide schedule testing frequencies;
- reimburse the Department for CL Table 1 testing above the minimum guide schedule frequencies for retesting when minimum frequency testing results in failures to meet specification limits;
- agree with the Engineer and CL upon a policy regarding notification for testing services;
- give any cancellation notice to the Engineer, District Lab, and CL by phone and e-mail;
- reimburse the Department a \$150 cancellation fee to cover technician time and mileage charges for previously scheduled work cancelled without adequate notice, which resulted in mobilization of technician and/or equipment by the CL; and
- all CL charges will be reimbursed to the Department by a deduction from the Contractor's monthly pay estimate.

If the CL does not meet the Table 1 turnaround times, testing charge to the Contractor will be reduced by 50% for the first late day and an additional 5% for each succeeding late day.

Approved CL project testing above the minimum testing frequencies in the Guide Schedule of Sampling and Testing, and not as the result of failing tests, will be paid by the Department.

Other project-level Guide Schedule sampling and testing not shown on Table 1 will be the responsibility of the Department.

 Table 1

 Select Guide Schedule Sampling and Testing (Note 1)

TxDOT Test	Test Description	Turn- Around Time (Calendar days)
	SOILS/BASE	
Tex-101-E	Preparation of Soil and Flexible Base Materials for Testing (included in other tests)	
Tex-104-E	Liquid Limit of Soils (included in 106-E)	
Tex-105-E	Plastic Limit of Soils (included in 106-E)	
Tex-106-E	Calculating the Plasticity Index of Soils	7
Tex-110-E	Particle Size Analysis of Soils	6
Tex-113-E	Moisture-Density Relationship of Base Materials	7
Tex-114-E	Moisture-Density Relationship of Subgrade and Embankment Soil	7
Tex-115-E	Field Method for In-Place Density of Soils and Base Materials	2
Tex-116-E	Ball Mill Method for the Disintegration of Flexible Base Material	5
Tex-117-E, Part II	Triaxial Compression Tests For Disturbed Soils and Base Materials (Part II)	6
Tex-113-E w/ Tex-117-E	Moisture-Density Relationship of Base Materials with Triaxial Compression Tests For Disturbed Soils and Base Materials (Part II)	10
Tex-140-E	Measuring Thickness of Pavement Layer	2
Tex-145-E	Determining Sulfate Content in Soils - Colorimetric Method	4
	HOT MIX ASPHALT	
Tex-200-F	Sieve Analysis of Fine and Coarse Aggregate (dry, from ignition oven with known correction factors)	1 (Note 2)
Tex-203-F	Sand Equivalent Test	3
Tex-206-F, w/ Tex-207-F, Part I, w/ Tex-227-F	(Lab-Molded Density of Production Mixture – Texas Gyratory) Method of Compacting Test Specimens of Bituminous Mixtures with Density of Compacted Bituminous Mixtures, Part I - Bulk Specific Gravity of Compacted Bituminous Mixtures, with Theoretical Maximum Specific Gravity of Bituminous Mixtures	1 (Note 2)
Tex-207-F, Part I <b>&amp;/or</b> Part VI	(In-Place Air Voids of Roadway Cores) Density of Compacted Bituminous Mixtures, Part I- Bulk Specific Gravity of Compacted Bituminous Mixtures <b>&amp;/or</b> Part VI - Bulk Specific Gravity of Compacted Bituminous Mixtures Using the Vacuum Method	1 (Note 2)
Tex-207-F, Part V	Density of Compacted Bituminous Mixtures, Part V- Determining Mat Segregation using a Density-Testing Gauge	3
Tex-207-F, Part VII	Density of Compacted Bituminous Mixtures, Part VII - Determining Longitudinal Joint Density using a Density-Testing Gauge	4
Tex-212-F	Moisture Content of Bituminous Mixtures	3
Tex-217-F	Deleterious Material and Decantation Test for Coarse Aggregate	4
Tex-221-F	Sampling Aggregate for Bituminous Mixtures, Surface Treatments, and LRA (included in other tests)	
Tex-222-F	Sampling Bituminous Mixtures (included in other tests)	
Tex-224-F	Determination of Flakiness Index	3
Tex-226-F	Indirect Tensile Strength Test (production mix)	4
Tex-235-F	Determining Draindown Characteristics in Bituminous Materials	3
Tex-236-F (Correction Factors)	Asphalt Content from Asphalt Paving Mixtures by the Ignition Method (Determining Correction Factors)	4
Tex-236-F	Asphalt Content from Asphalt Paving Mixtures by the Ignition Method (Production Mixture)	1 (Note 2)
Tex-241-F w/ Tex-207-F, Part I, w/ Tex-227-F	(Lab-Molded Density of Production Mixture – Superpave Gyratory) Superpave Gyratory Compacting of Specimens of Bituminous Mixtures (production mixture) with Density of Compacted Bituminous Mixtures, Part I - Part I - Bulk Specific Gravity of Compacted Bituminous Mixtures, with Theoretical Maximum Specific Gravity of Bituminous Mixtures	1 (Note 2)
Tex-242-F	Hamburg Wheel-Tracking Test (production mix, molded samples)	3
Tex-244-F	Thermal Profile of Hot Mix Asphalt	1
Tex-246-F	Permeability of Water Flow of Hot Mix Asphalt	3
Tex-280-F	Flat and Elongated Particles	3
Tex-530-C	Effect of Water on Bituminous Paving Mixtures (production mix)	4

AGGREGATES						
Tex-400-A Sampling Flexible Base, Stone, Gravel, Sand, and Mineral Aggregates						
Tex-410-A Abrasion of Coarse Aggregate Using the Los Angeles Machine						
Tex-411-A Soundness of Aggregate by Use of Sodium Sulfate or Magnesium Sulfate 12						
Tex-461-A Degradation of Coarse Aggregate by Micro-Deval Abrasion						
	CHEMICAL					
Tex-612-J	Acid Insoluble Residue for Fine Aggregate	4				
	GENERAL					
HMA Production Sp	HMA Production Specialist [TxAPA – Level 1-A] (\$/hr)					
HMA Roadway Spec	HMA Roadway Specialist [TxAPA – Level 1-B] (\$/hr)					
Technician Travel/S	Technician Travel/Standby Time (\$/hr)					
Per Diem (\$/day - m	Per Diem (\$/day – meals and lodging)					
Mileage Rate (\$/mile	Mileage Rate (\$/mile from closest CL location)					
Note 1– Turn-Arou	Note 1– Turn-Around Time includes test time and time for travel/sampling and reporting.					

Note 1 – run-Around time includes test time and time for travel/sampling and reporting. Note 2 – These tests require turn-around times meeting the governing specifications. Provide test results within the stated turn-around time. CL is allowed one additional day to provide the signed and sealed report.

# Special Provision to Item 6 Control of Materials



Item 6, "Control of Materials" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 6.10., "Hazardous Materials," is voided and replaced by the following:

Comply with the requirements of Article 7.12., "Responsibility for Hazardous Materials."

Notify the Engineer immediately when a visual observation or odor indicates that materials on sites owned or controlled by the Department may contain hazardous materials. Except as noted herein, the Department is responsible for testing, removing, and disposing of hazardous materials not introduced by the Contractor. The Engineer may suspend work wholly or in part during the testing, removing, or disposing of hazardous materials, except in the case where hazardous materials are introduced by the Contractor.

Use materials that are free of hazardous materials. Notify the Engineer immediately if materials are suspected to contain hazardous materials. If materials delivered to the project by the Contractor are suspected to contain hazardous materials, have an approved commercial laboratory test the materials for the presence of hazardous materials as approved. Remove, remediate, and dispose of any of these materials found to contain hazardous materials. The work required to comply with this section will be at the Contractor's expense if materials are found to contain hazardous materials. Working day charges will not be suspended and extensions of working days will not be granted for activities related to handling hazardous material introduced by the Contractor. If suspected materials are not found to contain hazardous materials, the Department will reimburse the Contractor for hazardous materials testing and will adjust working day charges if the Contractor can show that this work impacted the critical path.

**10.1. Painted Steel Requirements**. Coatings on existing steel contain hazardous materials unless otherwise shown on the plans. Remove paint and dispose of steel coated with paint containing hazardous materials is in accordance with the following:

**10.1.1. Removing Paint From Steel** For contracts that are specifically for painting steel, Item 446, "Field Cleaning and Painting Steel" will be included as a pay item. Perform work in accordance with that item.

For projects where paint must be removed to allow for the dismantling of steel or to perform other work, the Department will provide for a separate contractor (third party) to remove paint containing hazardous materials prior to or during the Contract. Remove paint covering existing steel shown not to contain hazardous materials in accordance with Item 446, "Field Cleaning and Painting Steel."

**10.1.2. Removal and Disposal of Painted Steel.** For steel able to be dismantled by unbolting, paint removal will not be performed by the Department. The Department will remove paint, at locations shown on the plans or as agreed, for the Contractor's cutting and dismantling purposes. Utilize Department cleaned locations for dismantling when provided or provide own means of dismantling at other locations.

Painted steel to be retained by the Department will be shown on the plans. For painted steel that contains hazardous materials, dispose of the painted steel at a steel recycling or smelting facility unless otherwise shown on the plans. Maintain and make available to the Engineer invoices and other records obtained from the facility showing the received weight of the steel and the facility name. Dispose of steel that does not contain hazardous material coatings in accordance with federal, state and local regulations.

**10.2.** Asbestos Requirements. The plans will indicate locations or elements where asbestos containing materials (ACM) are known to be present. Where ACM is known to exist or where previously unknown ACM has been found, the Department will arrange for abatement by a separate contractor prior to or during the Contract. Notify the Engineer of proposed dates of demolition or removal of structural elements with ACM at least 60 days before beginning work to allow the Department sufficient time for abatement.

The Department of State Health Services (DSHS), Asbestos Programs Branch, is responsible for administering the requirements of the National Emissions Standards for Hazardous Air Pollutants, 40 CFR Part 61, Subpart M and the Texas Asbestos Health Protection Rules (TAHPR). Based on EPA guidance and regulatory background information, bridges are considered to be a regulated "facility" under NESHAP. Therefore, federal standards for demolition and renovation apply.

The Department is required to notify the DSHS at least 10 working days (by postmarked date) before initiating demolition or renovation of each structure or load bearing member shown on the plans. If the actual demolition or renovation date is changed or delayed, notify the Engineer in writing of the revised dates in sufficient time to allow for the Department's notification to DSHS to be postmarked at least 10 days in advance of the actual work.

Failure to provide the above information may require the temporary suspension of work under Article 8.4., "Temporary Suspension of Work or Working Day Charges," due to reasons under the control of the Contractor. The Department retains the right to determine the actual advance notice needed for the change in date to address post office business days and staff availability.

**10.3. Lead Abatement.** Provide traffic control as shown on the plans, and coordinate and cooperate with the third party and the Department for managing or removing hazardous materials. Work for the traffic control shown on the plans and coordination work will not be paid for directly but will be subsidiary to pertinent Items.

# Special Provision to Item 7 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 7.7.2., "Texas Pollutant Discharge Elimination System (TPDES) Permits and Storm Water Pollution Prevention Plans (SWP3)," is voided and replaced by the following:

- 7.2. Texas Pollution Discharge Elimination System (TPDES) Permits and Storm Water Pollution Prevention Plans (SWP3).
- 7.2.1. Projects with less than one acre of soil disturbance including required associated project specific locations (PSL's) per TPDES GP TXR 150000.

No posting or filing will be required for soil disturbances within the right of way. Adhere to the requirements of the SWP3.

7.2.2. Projects with one acre but less than five acres of soil disturbance including required associated PSL's per TPDES GP TXR 150000.

The Department will be considered a primary operator for <u>Operational Control Over Plans and Specifications</u> as defined in TPDES GP TXR 150000 for construction activity in the right of way. The Department will post a small site notice along with other requirements as defined in TPDES GP TXR 150000 as the entity of having operational control over plans and specifications for work shown on the plans in the right of way.

The Contractor will be considered a Primary Operator for <u>Day-to-Day Operational Control</u> as defined in TPDES GP TXR 150000 for construction activity in the right of way. In addition to the Department's actions, the Contractor will post a small site notice along with other requirements as defined in TPDES GP TXR 150000 as the entity of having day-to-day operational control of the work shown on the plans in the right of way. This is in addition to the Contractor being responsible for TPDES GP TXR 150000 requirements for on- right of way and off- right of way PSL's. Adhere to all requirements of the SWP3 as shown on the plans. The Contractor will be responsible for Implement the SWP3 for the project site in accordance with the plans and specifications, TPDES General Permit TXR150000, and as directed.

# 7.2.3. Projects with 5 acres or more of soil disturbance including required associated PSL's per TPDES GP TXR 150000.

The Department will be considered a primary operator for <u>Operational Control Over Plans and Specifications</u> as defined in TPDES GP TXR 150000 for construction activities in the right of way. The Department will post a large site notice, file a notice of intent (NOI), notice of change (NOC), if applicable, and a notice of termination (NOT) along with other requirements per TPDES GP TXR 150000 as the entity having operational control over plans and specifications for work shown on the plans in the right of way.

The Contractor will be considered a primary operator for <u>Day-to-Day Operational Control</u> as defined in TPDES GP TXR 150000 for construction activities in the right of way. In addition to the Department's actions, the Contractor shall file a NOI, NOC, if applicable, and NOT and post a large site notice along with other requirements as the entity of having day-to-day operational control of the work shown on the plans in the right of way. This is in addition to the Contractor

being responsible for TPDES GP TXR 150000 requirements for on- right of way and off- right of way PSL's. Adhere to all requirements of the SWP3 as shown on the plans.

# Special Provision to Item 7 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 19.1., Minimum Wage Requirements for Federally Funded Contracts. The second paragraph is voided and replaced by the following:

Submit electronic payroll records to the Engineer using the Department's payroll system.

Section 19.2., Minimum Wage Requirements for State Funded Contracts. The second paragraph is voided and replaced by the following:

Submit electronic payroll records to the Engineer using the Department's payroll system.

## Special Provision to Item 7 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 7.2.4., "Public Safety and Convenience." The first paragraph is deleted and replaced by the following.

Ensure the safety and convenience of the public and property as provided in the Contract and as directed. Keep existing roadways open to traffic or construct and maintain detours and temporary structures for safe public travel. Manage construction to minimize disruption to traffic. Maintain the roadway in a good and passable condition, including proper drainage and provide for ingress and egress to adjacent property.

If the construction of the project requires the closing of a highway, as directed, coordinate the closure with the Engineer and work to ensure all lanes and ramps possible are available during peak traffic periods before, during, and after significant traffic generator events to avoid any adverse economic impact on the municipalities during:

- dates or events as shown on the plans, and
- other dates as directed.

## Special Provision to Item 007 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below.

Section 2.6., "Barricades, Signs, and Traffic Handling," the first paragraph is voided and replaced by the following:

2.6. **Barricades, Signs, and Traffic Handling.** Comply with the requirements of Item 502 "Barricades, Signs, and Traffic Handling," and as directed. Provide traffic control devices that conform to the details shown on the plans, the TMUTCD, and the Department's Compliant Work Zone Traffic Control Device List maintained by the Traffic Safety Division. When authorized or directed, provide additional signs or traffic control devices not required by the plans.

Section 2.6.1., "Contractor Responsible Person and Alternative," is voided and replaced by the following:

2.6.1. **Contractor Responsible Person and Alternative.** Designate in writing, a Contractor's Responsible Person (CRP) and an alternate to be the representative of the Contractor who is responsible for taking or directing corrective measures regarding the traffic control. The CRP or alternate must be accessible by phone 24 hr. per day and able to respond when notified. The CRP and alternate must comply with the requirements of Section 2.6.5., "Training."

Section 2.6.2, "Flaggers," the first paragraph is voided and replaced by the following:

2.6.2. **Flaggers.** Designate in writing, a flagger instructor who will serve as a flagging supervisor and is responsible for training and assuring that all flaggers are qualified to perform flagging duties. Certify to the Engineer that all flaggers will be trained and make available upon request a list of flaggers trained to perform flagging duties.

Section 2.6.5, "Training," is voided and replaced by the following:

2.6.5. **Training.** Train workers involved with the traffic control using Department-approved training as shown on the "Traffic Control Training" Material Producer List.

> Coordinate enrollment, pay associated fees, and successfully complete Department-approved training or Contractor-developed training. Training is valid for the period prescribed by the provider. Except for law enforcement personnel training, refresher training is required every 4 yr. from the date of completion unless otherwise specified by the course provider. The Engineer may require training at a frequency instead of the period prescribed based on the Department's needs. Training and associated fees will not be measured or paid for directly but are considered subsidiary to pertinent Items.

> Certify to the Engineer that workers involved in traffic control and other work zone personnel have been trained and make available upon request a copy of the certification of completion to the Engineer. Ensure the following is included in the certification of completion:

- name of provider and course title,
- name of participant,
- date of completion, and
- date of expiration.

Where Contractor-developed training or a Department-approved training course does not produce a certification, maintain a log of attendees. Make the log available upon request. Ensure the log is legible and includes the following:

- printed name and signature of participant,
- name and title of trainer, and
- date of training.
- 2.6.5.1. **Contractor-developed Training.** Develop and deliver Contractor-developed training meeting the minimum requirements established by the Department. The outline for this training must be submitted to the Engineer for approval at the preconstruction meeting. The CRP or designated alternate may deliver the training instead of the Department-approved training. The work performed and materials furnished to develop and deliver the training will not be measured or paid for directly but will be considered subsidiary to pertinent Items.
- 2.6.5.1.1. Flagger Training Minimum Requirements. A Contractor's certified flagging instructor is permitted to train other flaggers.
- 2.6.5.1.2. **Optional Contractor-developed Training for Other Work Zone Personnel.** For other work zone personnel, the Contractor may provide training meeting the curriculum shown below instead of Department-approved training.

Minimum curriculum for Contractor-provided training is as follows:

Contractor-developed training must provide information on the use of personnel protection equipment, occupational hazards and health risks, and other pertinent topics related to traffic management. The type and amount of training will depend on the job duties and responsibilities. Develop training applicable to the work being performed. Develop training to include the following topics.

- The Life You Save May Be Your Own (or other similar company safety motto).
- Purpose of the training.
  - It's the Law.
  - To make work zones safer for workers and motorist.
  - To understand what is needed for traffic control.
  - To save lives including your own.
- Personal and Co-Worker Safety.
  - High Visibility Safety Apparel. Discuss compliant requirements; inspect regularly for fading and reduced reflective properties; if night operations are required, discuss the additional and appropriate required apparel in addition to special night work risks; if moving operations are underway, discuss appropriate safety measures specific to the situation and traffic control plan.
  - Blind Areas. A blind area is the area around a vehicle or piece of construction equipment not
    visible to the operators, either by line of sight or indirectly by mirrors. Discuss the "Circle of Safety"
    around equipment and vehicles; use of spotters; maintain eye contact with equipment operators;
    and use of hand signals.
  - Runovers and Backovers. Remain alert at all times; keep a safe distance from traffic; avoid turning your back to traffic and if you must then use a spotter; and stay behind protective barriers, whenever possible. Note: It is not safe to sit on or lean against a concrete barrier, these barriers can deflect four plus feet when struck by a vehicle.
  - Look out for each other, warn co-workers.
  - Be courteous to motorists.
  - Do not run across active roadways.
  - Workers must obey traffic laws and drive courteously while operating vehicles in the work zones.
  - Workers must be made aware of company distracted driving policies.
- Night Time Operations. Focus should be placed on projects with a nighttime element.

- **Traffic Control Training.** Basics of Traffic Control.
  - Identify work zone traffic control supervisor and other appropriate persons to report issues to when they arise.
  - Emphasize that work zone traffic control devices must be in clean and in undamaged condition. If devices have been hit but not damaged, put back in their correct place and report to traffic control supervisor. If devices have been damaged, replace with new one and report to traffic control supervisor. If devices are dirty, faded or have missing or damaged reflective tape clean or replace and report to traffic control supervisor. Show examples of non-acceptable device conditions. Discuss various types of traffic control devices to be used and where spacing requirements can be found.
  - **Channelizing Devices and Barricades with Slanted Stripes.** Stripes are to slant in the direction you want traffic to stay or move to; demonstrate this with a device.
  - Traffic Queuing. Workers must be made aware of traffic queuing and the dangers created by it. Workers must be instructed to immediately notify the traffic control supervisor and other supervisory personnel if traffic is queuing beyond advance warning sign and devices or construction limits.
  - Signs. Signs must be straight and not leaning. Report problems to the traffic control supervisor or other as designated for immediate repair. Covered signs must be fully covered. If covers are damaged or out of place, report to traffic control supervisor or other as designated.

# Special Provision to Item 8 Prosecution and Progress



Item 8, "Prosecution and Progress" of the Standard Specification is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 8.2., "Subcontracting," is supplemented by the following paragraph, which is added as paragraph six to this article:

The Contractor certifies by signing the Contract that the Contractor will not enter into any subcontract with a subcontractor that is not registered in the Department of Homeland Security's (DHS) E-Verify system. Require that all subcontractors working on the project register and require that all subcontractors remain active in the DHS E-Verify system until their work is complete on the project.

# Special Provision to Item 8 Prosecution and Progress



Item 8, "Prosecution and Progress" of the Standard Specifications is amended with respect to the clause cited below. No other clauses or requirements of this Item are waived or changed.

Article 8.7.2., "Wrongful Default," is revised and replaced by the following:

If it is determined after the Contractor is declared in default, that the Contractor was not in default, the rights and obligations of all parties will be the same as if termination had been issued for the convenience of the public as provided in Article 8.8 "Termination of Contract."

# Special Provision to Item 009 Measurement and Payment



Item 009 "Measurement and Payment" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

#### Article 9.5., "PROGRESS PAYMENTS" is supplemented with the following:

It is the Department's desire to pay a Contractor for work through the last working day of the month; however, the use of early cut-off dates for monthly estimates and MOH is a project management practice to manage workload at the Area Office level. Approval for using early cut-off dates is at the District's discretion. The earliest cut-off date for estimates is the 25<sup>th</sup> of the month.

#### Article 9.6., "PAYMENT FOR MATERIAL ON HAND (MOH)" first paragraph is amended as follows:

If payment for MOH is desired, request compensation for the invoice cost of acceptable nonperishable materials that have not been used in the work before the request, and that have been delivered to the work location or are in acceptable storage places. Nonperishable materials are those that do not have a shelf life or whose characteristics do not materially change when exposed to the elements. Include only materials that have been sampled, tested, approved, or certified, and are ready for incorporation into the work. Only materials which are completely constructed or fabricated on the Contractor's order for a specific Contract and are so marked and on which an approved test report has been issued are eligible. Payment for MOH may include the following types of items: concrete traffic barrier, precast concrete box culverts, concrete piling, reinforced concrete pipe, and illumination poles. Any repairs required after fabricated materials have been approved for storage will require approval of the Engineer before being made and will be made at the Contractor's expense. Include only those materials and products, when cumulated under an individual item or similar bid items, that have an invoice cost of at least \$1,000 in the request for MOH payment (e.g. For MOH eligibility, various sizes of conductor are considered similar bid items and may be cumulated to meet the threshold; for small roadside signs, the sign supports, mounting bolts, and the sign face is considered one bid item or similar bid items for more than one pay item for sign supports.) Requests for MOH are to be submitted at least two days before but not later than the estimate cutoff date unless otherwise agreed. If there is a need to request MOH after the established cut-off date, the district can make accommodation as the need arises. This needed accommodation is to be the exception, though, and not the rule.

### Special Provision to Item 9 Measurement and Payment



Item 9, "Measurement and Payment" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 9.7.1.4.3., "Standby Equipment Costs," is voided and replaced by the following:

7.1.4.3. **Standby Equipment Costs.** Payment for standby equipment will be made in accordance with Section 9.7.1.4., "Equipment," except that the 15% markup will not be allowed and that:

Section 7.1.4.3.1., "Contractor-Owned Equipment," is voided and replaced by the following:

- 7.1.4.3.1. Contractor-Owned Equipment. For Contractor-owned equipment:
  - Standby will be paid at 50% of the monthly Equipment Watch rate after the regional and age adjustment factors have been applied. Operating costs will not be allowed. Calculate the standby rate as follows.

Standby rate = (FHWA hourly rate - operating costs) × 50%

- If an hourly rate is needed, divide the monthly *Equipment Watch* rate by 176.
- No more than 8 hr. of standby will be paid during a 24-hr. day period, nor more than 40 hr. per week.
- Standby costs will not be allowed during periods when the equipment would have otherwise been idle.

## Special Provision to Item 300 Asphalt, Oils, and Emulsions



Item 300, "Asphalt, Oils, and Emulsions" of the Standard Specifications is replaced by Special Specification <u>3096</u>, "Asphalts, Oils, and Emulsions." All Item 300 Special Provisions are no longer available, beginning with the April 2022 letting.

## Special Provision to Item 302 Aggregates for Surface Treatments



Item 302, "Aggregates for Seal Coats," of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Section 2.1., "Aggregate.	" Tables 2 and 3 are voided and r	replaced by the following.
---------------------------	-----------------------------------	----------------------------

		Aggree	gate Grad		ible 2 ments (Cumul	ative % F	Retained <sup>1</sup> )	)	
					Grade				
Sieve	1	2	3S <sup>2</sup>		3	4S <sup>2</sup>	4	5S <sup>2</sup>	5
Sieve				Non- Lightweight	Lightweight				
1"	-	-	-	-	-	-	-	-	-
7/8"	0–2	0	-	-	-	-	-	-	-
3/4"	20–35	0–2	0	0	0	-	-	-	-
5/8"	85–100	20–40	0–5	0–5	0–2	0	0	-	-
1/2"	-	80–100	55–85	20–40	10–25	0–5	0–5	0	0
3/8"	95–100	95–100	95–100	80–100	60–80	60–85	20–40	0–5	0–5
1/4"	-	-	-	95–100	95–100	-	-	65–85	-
#4	-	-	-	-	-	95–100	95–100	95–100	50-80
#8	99–100	99–100	99–100	98–100	98–100	98–100	98–100	98–100	98–100

Round test results to the nearest whole number.

2. Single-size gradation.

	T (M () )	Requir	rement <sup>1</sup>
Property	Test Method	Minimum           QMP         As shown o           7-F, Part I         -           406-A         -           -224-F         -           0-F, Part I         Table 2 Red           411-A         -           461-A         Note           2-A, Part I         85           rements for Lightweight Aggregate           404-A         35           431-A         -           432-A         -	Maximum
SAC	AQMP	As shown of	on the plans
Deleterious Material <sup>2</sup> , %	<u>Tex-217-F</u> , Part I	-	2.0
Decantation, %	<u>Tex-406-A</u>	-	1.5
Flakiness Index, %	<u>Tex-224-F</u>	-	17
Gradation	<u>Tex-200-F</u> , Part I	Table 2 Re	equirements
Los Angeles Abrasion, %	<u>Tex-410-A</u>	-	35
Magnesium Sulfate Soundness, 5 Cycle, %	<u>Tex-411-A</u>	-	25
Micro-Deval Abrasion, %	<u>Tex-461-A</u>	No	te 3
Coarse Aggregate Angularity <sup>4</sup> , 2 Crushed Faces, %	<u>Tex-460-A</u> , Part I	85	-
Additic	onal Requirements for L	ightweight Aggregate	
Dry Loose Unit Wt., Ib./cu. ft.	<u>Tex-404-A</u>	35	60
Pressure Slaking, %	<u>Tex-431-A</u>	-	6.0
Freeze-Thaw Loss, %	<u>Tex-432-A</u>	-	10.0
Water Absorption, 24hr., %	Tex-433-A	-	12.0

### Table 3 Aggregate Quality Requirements

1. Material requirements are listed below, unless otherwise shown on the plans.

2. Not required for lightweight aggregate.

3. Used to estimate the magnesium sulfate soundness loss in accordance with Section 2.1.1.

4. Only required for crushed gravel.

#### Section 2.1.1., "Micro-Deval Abrasion," is added.

The Engineer will perform a minimum of one Micro-Deval abrasion test in accordance with <u>Tex-461-A</u> for each coarse aggregate source per project that has a Rated Source Soundness Magnesium (RSSM) loss value greater than 15 as listed in the BRSQC. The Engineer may waive all Micro-Deval testing based on a satisfactory test history of the same aggregate source.

The Engineer will estimate the magnesium sulfate soundness loss for each coarse aggregate source, when tested, using the following formula.

Mg<sub>est.</sub> = (RSSM)(MD<sub>act</sub>/RSMD)

where:  $Mg_{est}$  = magnesium sulfate soundness loss  $MD_{act}$  = actual Micro-Deval percent loss RSMD = Rated Source Micro-Deval

When the estimated magnesium sulfate soundness loss is greater than the maximum magnesium sulfate soundness loss specified, the coarse aggregate source will not be allowed for use unless otherwise approved by the Engineer. The Engineer may require additional testing before granting approval.

Section 2.2., "Precoating." The third paragraph is voided and replaced by the following.

The Engineer retains the right to remove precoat material from aggregate samples in accordance with <u>Tex-210-F</u>, or as recommended by the Construction Division, and test the aggregate to verify compliance with Table 2 and Table 3 requirements. Gradation testing may be performed with precoat intact.

#### Section 2.3., "Sampling," is added.

Personnel who conduct sampling and witnessing of sampling must be certified by the Department-approved certification program. Supply the Engineer with a list of certified personnel and copies of their current certificates before beginning construction and when personnel changes are made. At any time during the project, the Engineer may perform production tests as deemed necessary in accordance with Item 5, "Control of the Work."

The Engineer will sample aggregate from stockpiles located at the production site, intermediate distribution site, or project location in accordance with <u>Tex-221-F</u>, Section 3.2.3. The Engineer will split each sample into 2 equal portions in accordance with <u>Tex-200-F</u>, Section 3.3, and label these portions "Engineer" and "Contractor" or "Supplier." Witness the sampling and splitting, and take immediate possession of the samples labeled "Contractor" or "Supplier".

#### Section 2.4., "Reporting and Responsibilities," is added.

The Engineer will provide test results to the Contractor and Supplier within 10 working days from the date the stockpile was sampled for sources listed on the Department's Bituminous Rated Source Quality Catalog (BRSQC), unless otherwise directed. The Engineer will provide test results for the LA Abrasion (<u>Tex-410-A</u>) and Magnesium Sulfate Soundness (<u>Tex-411-A</u>) tests within 30 calendar days for sources not listed on the BRSQC, or for sources not meeting the requirements of Section 2.1.1., "Micro-Deval Abrasion." The Engineer will report to the other party within 24 hours when any test result does not meet the requirements listed in Table 2 or Table 3.

### Special Provision to Item 316 Seal Coat



Item 316, "Seal Coat" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 4.8, "Asphalt Placement" is supplemented by the following:

4.8.5. Collect all samples in accordance with Tex-500-C, "Sampling Bituminous Materials, Pre-Molded Joint Fillers, and Joint Sealers" from the distributor and with witness by the Engineer.

At least once per project, collect split samples of each binder grade and source used. The Engineer will submit one split sample to MTD for testing and retain the other split sample.

In addition, collect one sample of each binder grade and source used on the project for each production day. The Engineer will retain these samples.

The Engineer will keep all retained samples for one yr., for hot-applied binders and cutback asphalts; or for two mo., for emulsified asphalts. The Engineer may submit retained samples to MTD for testing as necessary or as requested by MTD.

### Special Provision to Item 502 Barricades, Signs and Traffic Handling



Item 502, "Barricades, Signs and Traffic Handling" of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 502.1., "Description," is supplemented by the following:

Temporary work-zone (TWZ) traffic control devices manufactured after December 31, 2019, must have been successfully tested to the crashworthiness requirements of the 2016 edition of the Manual for Assessing Safety Hardware (MASH). Such devices manufactured on or before this date and successfully tested to NCHRP Report 350 or the 2009 edition of MASH may continue to be used throughout their normal service lives. An exception to the manufacture date applies when, based on the project's date of letting, a category of MASH-2016 compliant TWZ traffic control devices are not approved, or are not self-certified after the December 31, 2019, date. In such case, devices that meet NCHRP-350 or MASH-2009 may be used regardless of the manufacture date.

Such TWZ traffic control devices include: portable sign supports, barricades, portable traffic barriers designated exclusively for use in temporary work zones, crash cushions designated exclusively for use in temporary work zones, longitudinal channelizers, truck and trailer mounted attenuators. Category I Devices (i.e., lightweight devices) such as cones, tubular markers and drums without lights or signs attached however, may be self-certified by the vendor or provider, with documentation provided to Department or as are shown on Department's Compliant Work Zone Traffic Control Device List.

Article 502.4., "Payment," is supplemented by the following:

Truck mounted attenuators and trailer attenuators will be paid for under Special Specification, "Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)." Portable Changeable Message Signs will be paid for under Special Specification, "Portable Changeable Message Sign." Portable Traffic Signals will be paid for under Special Specification, "Portable Traffic Signals."

### Special Provision to Item 506 Temporary Erosion, Sedimentation, and Environmental Controls



For this project, Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls," of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 506.1., "Description," is voided and replaced by the following:

Install, maintain, and remove erosion, sedimentation, and environmental control measures to prevent or reduce the discharge of pollutants in accordance with the Storm Water Pollution Prevention Plan (SWP3) or as directed. Ensure the installation and maintenance of control measures is performed in accordance with the manufacturer's or designer's specifications. Erosion and sediment control devices must be selected from the "Erosion Control Approved Products" or "Sediment Control Approved Products" lists. Perform work in a manner to prevent degradation of receiving waters, facilitate project construction, and comply with applicable federal, state, and local regulations.

Article 506.3., "Qualifications, Training, and Employee Requirements," is voided and not replaced.

Section 506.4.1., "Contractor Responsibilities," Section 506.4.2., "Implementation," and Section 506.4.3., "General," are voided and replaced by the following:

- 4.1. **Contractor Responsibilities**. Implement the SWP3 for the project site in accordance with the plans and specifications, and as directed. Coordinate storm water management with all other work on the project. Develop and implement an SWP3 for project-specific material supply plants within and outside of the Department's right of way in accordance with the specific or general storm water permit requirements. Prevent water pollution from storm water associated with construction activity from entering any surface water or private property on or adjacent to the project site.
- 4.2. Implementation.
- 4.2.1. **Commencement**. Implement the SWP3 as shown and as directed. Contractor proposed recommendations for changes will be allowed as approved. Do not implement changes until approval has been received and changes have been incorporated into the plans by the Engineer. Minor adjustments to meet field conditions are allowed and will be recorded by the Engineer in the SWP3.

Implement control measures before the commencement of activities that result in soil disturbance. Phase and minimize the soil disturbance to the areas shown on the plans. Coordinate temporary control measures with permanent control measures and all other work activities on the project to assure economical, effective, safe, continuous water pollution prevention. Provide control measures that are appropriate to the construction means, methods, and sequencing allowed by the Contract.

Do not prolong final grading and shaping. Preserve vegetation where possible throughout the project and minimize clearing, grubbing, and excavation within stream banks, bed, and approach sections.

- 4.3. General.
- 4.3.1. **Temporary Alterations or Control Measure Removal**. Altering or removal of control measures is allowed when control measures are restored within the same working day.

- 4.3.2. **Stabilization**. Initiate stabilization for disturbed areas no more than 14 days after the construction activities in that portion of the site has temporarily or permanently ceased. Establish a uniform vegetative cover or use another stabilization practice as approved.
- 4.3.3. Finished Work. Upon the Engineer's acceptance of vegetative cover or other stabilization practice, remove and dispose of all temporary control measures unless otherwise directed. Complete soil disturbing activities and establish a uniform perennial vegetative cover. A project will not be considered for acceptance until a vegetative cover of 70% density of existing adjacent undisturbed areas is obtained or equivalent permanent stabilization is obtained as approved.
- 4.3.4. **Restricted Activities and Required Precautions**. Do not discharge onto the ground or surface waters any pollutants such as chemicals, raw sewage, fuels, lubricants, coolants, hydraulic fluids, bitumens, or any other petroleum product. Operate and maintain equipment on site in a manner as to prevent actual or potential water pollution. Manage, control, and dispose of litter on site such that no adverse impacts to water quality occur. Prevent dust from creating a potential or actual unsafe condition, public nuisance, or condition endangering the value, utility, or appearance of any property. Wash out concrete trucks only in approved contained areas. Use appropriate controls to minimize the offsite transport of suspended sediments and other pollutants if it is necessary to pump or channel standing water (i.e. dewatering). Prevent discharges that would contribute to a violation of Edwards Aquifer Rules, water quality standards, the impairment of a listed water body, or other state or federal law.

Section 506.4.4., "Installation, Maintenance, and Removal Work." The first paragraph is voided and replaced by the following.

Perform work in accordance with the SWP3, and according to the manufacturers' guidelines. Install and maintain the integrity of temporary erosion and sedimentation control devices to accumulate silt and debris until soil disturbing activities are completed and permanent erosion control features are in place or the disturbed area has been adequately stabilized as determined by the Engineer.

Section 506.4.5., "Monitoring and Documentation," is voided and not replaced.

Section 506.6.5.2., "Maintenance Earthwork for Erosion and Sediment Control for Cleaning and/or Restoring Control Measures," is voided and replaced by the following:

Earthwork needed to remove and obliterate of erosion-control features will not be paid for directly but is subsidiary to pertinent Items unless otherwise shown on the plans.

Sprinkling and rolling required by this Item will not be paid for directly but will be subsidiary to this Item.

## Special Provision to Item 666 Retroreflectorized Pavement Markings



Item 666, "Retroreflectorized Pavement Markings," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 2.3., "Glass Traffic Beads." The first paragraph is voided and replaced by the following:

Furnish drop-on glass beads in accordance with DMS-8290, "Glass Traffic Beads," or as approved. Furnish a double-drop of Type II and Type III drop-on glass beads for longitudinal pavement markings where each type bead is applied separately in equal portions (by weight), unless otherwise approved. Apply the Type III beads before applying the Type II beads. Furnish Type II beads for work zone pavement markings and transverse markings or symbols.

Section 4.3.1., "Type I Markings.," is supplemented by the following:

**4.3.1.3. Spot Striping.** Perform spot striping on a callout basis with a minimum callout quantity as shown on the plans.

Section 4.3.2., "Type II Markings.," is supplemented by the following:

**4.3.2.1. Spot Striping.** Perform spot striping on a callout basis with a minimum callout quantity as shown on the plans.

Section 4.4., "Retroreflectivity Requirements.," is voided and replaced by the following.

Type I markings for Contracts totaling more than 20,000 ft. of pavement markings must meet the following minimum retroreflectivity values for all longitudinal edgeline, centerline or no passing barrier-line, and lane line markings when measured any time after 3 days, but not later than 10 days after application.

- White markings: 250 millicandelas per square meter per lux (mcd/m<sup>2</sup>/lx)
- Yellow markings: 175 mcd/m<sup>2</sup>/lx

Retroreflectivity requirements for Type I markings are not required for Contracts with less than 20,000 ft. of pavement markings or Contracts with callout work, unless otherwise shown on the plans.

Section 4.5., "Retroreflectivity Measurements.," is voided and replaced by the following:

Use a mobile retroreflectometer to measure retroreflectivity for Contracts totaling more than 50,000 ft. of pavement markings, unless otherwise shown on the plans. For Contracts with less than 50,000 ft. of pavement markings, mobile or portable retroreflectometers may be used at the Contractor's discretion. Coordinate with and obtain authorization from the Engineer before starting any retroreflectivity data collection.

Section 4.5.1., "Mobile Retroreflectometer Measurements." The last paragraph is voided and replaced by the following.

Restripe again at the Contractor's expense with a minimum of 0.060 in. (60 mils) of Type I marking material if the average of these measurements falls below the minimum retroreflectivity requirements. Take measurements every 0.1 miles a minimum of 10 days after this third application within that mile segment for that series of markings. If the markings do not meet minimum retroreflectivity after this third application, the Engineer may require removal of all existing markings, a new application as initially specified, and a repeat of the application process until minimum retroreflectivity requirements are met.

Section 4.5.2., "Portable Retroreflectometer Measurements." The first and second paragraphs are voided and replaced by the following.

Provide portable measurement averages for every 1.0 mile unless otherwise specified or approved. Take a minimum of 20 measurements for each 1-mi. section of roadway for each series of markings (e.g., edgeline, center skip line, each line of a double line) and direction of traffic flow when using a portable reflectometer. Measure each line in both directions for centerlines on two-way roadways (i.e., measure both double solid lines in both directions and measure all center skip lines in both directions). The spacing between each measurement must be at least 100 ft. The Engineer may decrease the mileage frequency for measurements if the previous measurements provide satisfactory results. The Engineer may require the original number of measurements if concerns arise.

Restripe at the Contractor's expense with a minimum of 0.060 in. (60 mils) of Type I marking material if the averages of these measurements fail. Take a minimum of 10 more measurements after 10 days of this second application within that mile segment for that series of markings. Restripe again at the Contractor's expense with a minimum of 0.060 in. (60 mils) of Type I marking material if the average of these measurements falls below the minimum retroreflectivity requirements. If the markings do not meet minimum retroreflectivity after this third application, the Engineer may require removal of all existing markings, a new application as initially specified, and a repeat of the application process until minimum retroreflectivity requirements are met.

Section 4.6. "Performance Period." The first sentence is voided and replaced by the following:

All longitudinal markings must meet the minimum retroreflectivity requirements within the time frame specified. All markings must meet all other performance requirements of this specification for at least 30 calendar days after installation.

Article 6. "Payment." The first two paragraphs are voided and replaced by the following.

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Pavement Sealer" of the size specified; "Retroreflectorized Pavement Markings" of the type and color specified and the shape, width, size, and thickness (Type I markings only) specified, as applicable; "Retroreflectorized Pavement Markings with Retroreflective Requirements" of the types, colors, sizes, widths, and thicknesses specified; "Retroreflectorized Profile Pavement Markings" of the various types, colors, shapes, sizes, and widths specified; or "Reflectorized Pavement Marking (Call Out)" of the shape, width, size, and thickness (Type I markings only) specified, as applicable; or "Pavement Sealer (Call Out)" of the size specified.

This price is full compensation for materials, application of pavement markings, equipment, labor, tools, and incidentals.

### Special Provision to Special Specification 6185 Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)



Item 6185, "Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)" of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 4. "Measurement", is voided and replaced by the following:

- 4.1. **Truck Mounted Attenuator/Trailer Attenuator (Stationary).** This Item will be measured by the day. TMA/TAs must be set up in a work area and operational before a calendar day can be considered measureable. A day will be measured for each TMA/TA set up and operational on the worksite.
- 4.2. **Truck Mounted Attenuator/Trailer Attenuator (Mobile Operation).** This Item will be measured by the hour or by the day. The time begins once the TMA/TA is ready for operation at the predetermined site and stops when notified by the Engineer. When measurement by the hour is specified, a minimum of 4 hr. will be paid each day for each operating TMA/TA used in a mobile operation. When measurement by the day is specified, a day will be measured for each TMA/TA set up and operational on the worksite.

# Special Specification 3004 Diamond Grinding and Grooving Pavement



### 1. DESCRIPTION

Diamond grind and/or groove existing pavement surfaces and remove resulting residue at locations shown on the plans or as directed.

### EQUIPMENT

2.

Provide machinery, tools, and equipment necessary for proper execution of the work. Do not use flailing devices. Use machines that:

- have a self-propelled machine built for grinding and/or grooving pavements;
- provide enough power, traction, and stability to maintain specified depth of cut and cross slope; and
- are able to achieve a uniform depth of cut, flush to all inlets, manholes, bridge joints, and other appurtenances within the paved area.

In addition, for continuous operations, use machines that:

- have 50 to 60 diamond blades per foot, mounted on a multi-blade arbor;
- have dual longitudinal controls capable of operating on both sides automatically from any longitudinal grade reference, which includes string line, ski, mobile string line, or matching shoe; and
- have transverse controls to control cross slope at a given rate.Table1

### 3. CONSTRUCTION

Demonstrate grinding and/or grooving work to receive approval of the operation procedure and the use of grinding and/or grooving and residue removing equipment.

3.1. **Grinding**. Perform grinding in a longitudinal direction beginning and ending at lines perpendicular to the pavement lane lines. Start grinding at the outside edge of the pavement, and continue across the lane surface to the opposite outer edge of the traffic lane or pavement. Grind surfaces on both sides of transverse joints or cracks, and finish the surfaces in essentially the same plane.

The finished cross slope shall mirror the pre-grind cross slope and shall have no depressions or misalignment of slope greater than 1/4 inch (6.35 millimeters) in 12 feet (3.66 meters) when measured with a 12-foot (3.66 meter) straightedge placed perpendicular to the centerline. The straightedge shall also be used perpendicular to the centerline to ensure the contractor is not grinding a "W" into the roadway surface when grinding wheel-rutted surfaces. Areas of deviation shall be reground. Straightedge requirements will not apply across longitudinal joints or outside the ground area.

Transition auxiliary and ramp lane grinding from the mainlane edge as directed. Terminate grinding at bridge joints.

Produce a uniform surface with a longitudinal corduroy-type texture that eliminates joint and crack faults. Provide positive lateral surface drainage by maintaining a constant cross-slope across each lane.

3.2. **Grooving**. Groove 0.10–0.16 in. wide with a land area 0.70–0.80 in. between the grooves. Groove 0.19 in. deep unless otherwise as shown on the plans. Meet the groove tolerances  $\pm$  0.02 in. for width and  $\pm$  0.06 in. for depth under normal pavement conditions unless otherwise directed. Do not groove ground asphaltic pavement unless otherwise shown on the plans.

- 3.3. **Repairs**. As directed, perform repairs in accordance with Item 720, "Repair of Spalling in Concrete Pavement," if spalls are 0.25–3 in. in depth.
- 3.4. **Ride Quality**. Unless otherwise shown on the plans, measure ride quality in accordance with Item 585, "Ride Quality for Pavement Surfaces," Surface Test Type A, after completion of grinding and/or grooving and residue removal operations.
- 3.5. **Removal of Residue**. Immediately and continuously, remove the slurry or residue resulting from the grinding operation. Keep pavement in a washed clean condition, free of slipperiness from the slurry, etc. Do not permit the residue to flow across shoulders or lanes occupied by traffic or into gutters or other drainage facilities.

#### 4. MEASUREMENT

- 4.1. Continuous Diamond Grinding of Concrete Pavement. Continuous diamond grinding of concrete pavement will be measured by the square yard of surface area ground and accepted, within the limits shown on the plans.
- 4.2. **Spot Diamond Grinding of Concrete Pavement.** Spot diamond grinding of concrete pavement will be measured in place at locations determined by the Engineer.
- 4.3. Continuous Diamond Grinding of Asphaltic Pavement. Continuous diamond grinding of asphaltic pavement will be measured by the square yard of surface area ground and accepted, within the limits shown on the plans.
- 4.4. **Spot Diamond Grinding of Asphaltic Pavement.** Spot diamond grinding of asphaltic pavement will be measured in place at locations determined by the Engineer.
- 4.5. **Continuous Diamond Grooving of Concrete Pavement.** Continuous diamond grooving of concrete pavement will be measured by the square yard of surface area grooved and accepted, within the limits shown on the plans.
- 4.6. **Spot Diamond Grooving of Concrete Pavement.** Spot diamond grooving of concrete pavement will be measured in place at locations determined by the Engineer.

### 5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Continuous Diamond Grinding of Concrete Pavement," "Spot Diamond Grinding of Concrete Pavement," "Continuous Diamond Grinding of Asphaltic Pavement," "Spot Diamond Grinding of Asphaltic Pavement," "Continuous Diamond Grooving of Concrete Pavement," or "Spot Diamond Grinding of Concrete Pavement." This price is full compensation for grinding the pavement surface; repairing of concrete pavement damaged during grinding and/or grooving operations, including spalls or partial depth failures; loading, hauling, and disposing of the residue material; labor; tools; equipment; and incidentals. Demonstration work to receive approval for use of equipment will not be paid for unless work is performed in accordance with the Contract and is accepted.

Repairs to existing pavement necessary due to the Contractor's failure to comply with contract requirements will not be paid for directly. Repairs to existing pavement due to other causes will be paid for in accordance with pertinent items or under Force Account as directed by the Engineer.

### Special Specification 3012 Next Generation Concrete Surface (NGCS) Grinding



### 1. DESCRIPTION

Construct Next Generation Concrete Surface (NGCS) using diamond grinding and grooving techniques on existing and new pavement surfaces. Remove resulting residue at locations shown on the plans or as directed.

### 2. EQUIPMENT

2.1

Provide machinery, tools, and equipment necessary for proper execution of the work.

#### Diamond Grinding Equipment. Utilize diamond grinding equipment that:

- has diamond blades mounted on a self-propelled machine designed for grinding and texturing pavement;
- weighs a minimum 35,000 lbs. (grinding head included);
- has sufficient size to grind a strip at least 4 ft. wide, and can produce overlapping match lines out of the wheel path;
- will not cause ravels, aggregate fractures, spalls, or disturbance to the transverse or longitudinal joints; and
- has a positive means of vacuuming the grinding residue from the pavement surface and will leave the pavement in a clean, near-dry condition.

### 3. CONSTRUCTION

Perform and schedule construction operations to produce a neat, uniform finished surface. Transition auxiliary or ramp lane grinding from the edge of the mainline as required to provide drainage and an acceptable riding surface. Complete pavement repair operations, if required, before performing any grinding. Complete joint sealing subsequent to the diamond grinding operations and install joint sealing in a recessed condition.

Construct a single lane NGCS test grind 500 ft. in length.

Demonstrate that the equipment and operation procedures used are capable of attaining the desired surface texture and smoothness requirements.

Work will not be allowed to proceed until test grind has been approved by the Engineer.

3.1. **Grinding**. Perform grinding in a longitudinal direction beginning and ending at lines perpendicular to the pavement lane lines.

Do not overlap passes of the grinding head more than 1 in. No unground surface area between passes will be permitted. Grind to a depth sufficient to remove the existing transverse tining but not exceeding 0.25 in.

3.2. **Two-Pass NGCS Operation.** Perform two separate operations to construct the NGCS section. The first operation will create a flush ground surface. Mount the blades that are used to flush grind, onto a 4 ft. grinding head, stacked with 0.125 in. wide blades separated by the 0.035 +/-0.005 in. wide spacers. Produce the flush ground surface using blades that are flat across their contact surface and in the same plane with the

other flush ground blades when mounted. Ensure the complete head, when stacked with the blades, is straight across in length without bowing when mounted on the diamond grinding machine.

No unground surface area between passes will be permitted.

Attain and measure the smoothness level stated to the satisfaction of the Engineer before starting the second operation.

The second operation will provide the longitudinal grooves.

3.3. **Final Surface Finish.** Produce a pavement surface that is true to grade and uniform in appearance with a longitudinal grooved texture. Cut the line-type texture with corrugations that are:

- 0.125 in. wide
- 0.125 in. to 0.1875 in. deep
- Spaced on 0.5 in. to 0.625 in. centers
- Parallel to Centerline
- Use a guide to ensure proper alignment of the grooves to centerline.
- Provide a flush ground surface that appears smooth and contains no ridges that exceed 0.03 in. At a minimum, texture 98% of the pavement surface with both the flush ground and grooved surface.
- 3.4. Repairs. As directed, perform repairs in accordance with Item 720, "Repair of Spalling in Concrete Pavement," if spalls are 0.25 3 in. in depth. As directed, clean and seal existing joints in accordance with Item 438, "Cleaning and Sealing Joints."
- 3.5. Smoothness Requirements. Produce a finished NGCS final profile that has an average International Roughness Index (IRI) of 50 in./mi. or less when measured in accordance with Tex-1001-S. See Table 1 for Pay Adjustment Schedule.

Measure surfaces for smoothness acceptance following the flush grinding operation and before the longitudinal grooving operation.

Generate the smoothness profile using inertial profile equipment on the Department's approved list of Inertial Profilers with equipment shown to have line lasers. Provide operators from the approved list of Inertial Profile Operators.

Depressed pavement areas due to subsidence or other localized causes are excluded from the smoothness requirements. These areas will be reviewed and approved by the Engineer.

Bumps exceeding 0.3 in. per 25 ft. will not be allowed in the finished ground surface.

3.6 **Slurry Removal.** Remove and dispose of residue from the pavement surface in a manner to satisfy environmental regulations. Immediately and continuously, remove the slurry or residue resulting from the grinding operation. Keep pavement in a washed clean condition, free of slipperiness from the slurry, etc. Do not permit the residue to flow across shoulders or lanes occupied by traffic or into gutters or other drainage facilities.

### 4. MEASUREMENT

- 4.1 **Grinding.** Diamond grinding of concrete pavement will be measured by the square yard of surface area ground.
- 4.2 Next Generation Concrete Surface Grinding of Concrete Pavement. NGCS Diamond grinding of concrete pavement will be measured by the square yard of surface area ground and accepted, regardless of the number of passes required to achieve acceptable results.

### PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Grinding" or "Next Generation Concrete Surface Grinding of Concrete Pavement." This price is full compensation for grinding the pavement surface; loading, hauling, and disposing of the residue material; labor; tools; equipment; and incidentals. Demonstration work to receive approval for use of equipment will not be paid for unless work is performed in accordance with the contract and is accepted.

Cleaning and sealing existing joints and cracks will be incidental to the Item "Next Generation Concrete Surface Grinding of Concrete Pavement."

Pay Adjust	ment Schedule
Average IRI for each 0.10 mi. of Traffic Lane	Pay Adjustment
(in./mi.)	(\$/0.10 mi. of Traffic Lane)
0-35	704
35.1-45	-69.703(IRI)+3143.6
45.1-50	0.00
>50	Corrective Action

Table 1Pay Adjustment Schedule

# Special Specification 3096 Asphalts, Oils, and Emulsions



### 1. DESCRIPTION

Provide asphalt cements, cutback and emulsified asphalts, performance-graded asphalt binders, and other miscellaneous asphalt materials as specified on the plans.

### 2. MATERIALS

Provide asphalt materials that meet the stated requirements when tested in conformance with the referenced Department, AASHTO, and ASTM test methods. Use asphalt containing recycled materials only if the recycled components meet the requirements of Article 6.9., "Recycled Materials." Provide asphalt materials that the Department has preapproved for use in accordance with <u>Tex-545-C</u>, "Asphalt Binder Quality Program."

Inform the Department of all additives or modifiers included in the asphalt binder as part of the facility quality plan, as required by <u>Tex-545-C</u>, "Asphalt Binder Quality Program," and provide that information to Department personnel. The Department reserves the right to prohibit the use of any asphalt additive or modifier.

Limit the use of polyphosphoric acid to no more than 0.5% by weight of the asphalt binder.

The use of re-refined engine oil bottoms is prohibited.

Acronyms used in this Item are defined in Table 1.

	Table1
٨	

	Acronyms								
Acronym	Definition								
	Test Procedure Designations								
Tex	Department								
T or R	AASHTO								
D	ASTM								
	Polymer Modifier Designations								
Р	polymer-modified								
SBR or L	styrene-butadiene rubber (latex)								
SBS	styrene-butadiene-styrene block co-polymer								
TR	tire rubber (from ambient temperature grinding of truck and								
	passenger tires)								
AC	asphalt cement								
AE	asphalt emulsion								
AE-P	asphalt emulsion prime								
A-R	asphalt-rubber								
С	cationic								
EAP&T	emulsified asphalt prime and tack								
EBL	emulsified bonding layer								
FDR	full depth reclamation								
H-suffix	harder residue (lower penetration)								
HF	high float								
HY	high yield								
MC	medium-curing								
MS	medium-setting								
PCE	prime, cure, and erosion control								
PG	performance grade								
RC	rapid-curing								
RS	rapid-setting								
S-suffix	stockpile usage								
SCM	special cutback material								
SS	slow-setting								
SY	standard vield								
TRAIL	tracking resistant asphalt interlayer								

2.1. **Asphalt Cement**. Provide asphalt cement that is homogeneous, water-free, and nonfoaming when heated to 347°F, and meets the requirements in Table 2.

		As	sphalt	Cemer	t							
	Test	Viscosity Grade										
Property	Test	AC	0.6	AC-1.5		AC-3		AC-5		AC-10		
	Procedure	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	
Viscosity	T 202											
140°F, poise		40	80	100	200	250	350	400	600	800	1,200	
275°F, poise		0.4	-	0.7	-	1.1	-	1.4	-	1.9	-	
Penetration, 77°F, 100g, 5 sec.	T 49	350	_	250	_	210	_	135	-	85	_	
Flash point, C.O.C., °F	T 48	425	-	425	-	425	-	425	-	450	-	
Solubility in trichloroethylene, %	T 44	99.0	_	99.0	_	99.0	_	99.0	-	99.0	_	
Spot test	Tex-509-C	Ne	eg.	Ne	eg.	Ne	eg.	Ne	eg.	Ne	eg.	
Tests on residue from RTFOT:	T 240											
Viscosity, 140°F, poise	T 202	-	180	-	450	-	900	-	1,500	-	3,000	
Ductility, <sup>1</sup> 77°F 5 cm/min., cm	T 51	100	-	100	-	100	-	100	-	100	-	

Table 2 sphalt Ceme

 If AC-0.6 or AC-1.5 ductility at 77°F is less than 100 cm, material is acceptable if ductility at 60°F is more than 100 cm.

3096

2.2.

**Polymer-Modified Asphalt Cement**. Provide polymer-modified asphalt cement that is smooth, homogeneous, and meets the requirements Table 3. Supply samples of the base asphalt cement and polymer additives if requested.

Property	Test	Polymer-Modified Viscosity Grade											
	Procedure	AC-12	2-5TR	NT-	HA <sup>1</sup>	AC-		AC-2		AC-10	-2TR	AC-20	-5TR
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Polymer		TI	۲	-	-	SE	3S	SB	IS	TF	२	TF	२
Polymer content, %	<u>Tex-533-C</u>	5.0	-	-	-	3.0	-	-	-	2.0	-	5.0	-
(solids basis)	or <u>Tex-553-C</u>												
Dynamic shear,	T 315			1.0	-								
G*/sinδ, 82°C,													
10 rad/s, kPa													
Dynamic shear,	T 315	-	-	-	-	-	-	1.0	-	-	-	1.0	-
G*/sinδ, 64°C,													
10 rad/s, kPa													
Dynamic shear,	T 315	1.0	-	-	-	-	-	-	-	1.0	-	-	-
G*/sinδ, 58°C,													
10 rad/s, kPa													
Viscosity													
140°F, poise	T 202	1,200	-			1,500	-	2,000	-	1,000	-	2,000	-
275°F, poise	T 202			-	4,000	-	8.0	-	-	-	8.0	-	10.0
Penetration, 77°F,	T 49	110	150	-	25	100	150	75	115	95	130	75	115
100 g, 5 sec.													
Ductility, 5cm/min.,	T 51					-	-	-	-	-	-	-	-
39.2°F, cm													
Elastic recovery,	<u>Tex-539-C</u>	55	-			55	-	55	-	30	-	55	-
50°F, %													
Softening point, °F	T 53	113	-	170	-	-	-	120	-	110	-	120	-
Polymer separation,	<u>Tex-540-C</u>	No	ne			No	ne	No	ne	Noi	ne	No	ne
5 hr.							-						-
Flash point, C.O.C.,	T 48	425	-	425	-	425	-	425	-	425	-	425	-
°F													
Tests on residue	T 240												
from RTFOT aging	and R 28												
and pressure aging:													
Creep stiffness	T 313												
S, -18°C, MPa		-	300	-	-	-	300	-	300	-	300	-	300
m-value, -18°C		0.300	-	-	-	0.300	-	0.300	-	0.300	-	0.300	-

Table 3
Polymer-Modified Asphalt Cement
Delumer Medifi

1. Non-Tracking Hot Applied Tack Coat - TRAIL product

2.3.

**Cutback Asphalt**. Provide cutback asphalt that meets the requirements of Tables 4, 5, and 6, for the specified type and grade. Supply samples of the base asphalt cement and polymer additives if requested.

Property	Test Procedure	Type–Grade							
		RC-250		RC	-800	RC-3000			
		Min	Max	Min	Max	Min	Max		
Kinematic viscosity, 140°F, cSt	T 201	250	400	800	1,600	3,000	6,000		
Water, %	D95	_	0.2	_	0.2	_	0.2		
Flash point, T.O.C., °F	T 79	80	-	80	-	80	-		
Distillation test:	T 78								
Distillate, percentage by volume of total									
distillate to 680°F									
to 437°F		40	75	35	70	20	55		
to 500°F		65	90	55	85	45	75		
to 600°F		85	-	80	-	70	-		
Residue from distillation, volume %		70	-	75	-	82	-		
Tests on distillation residue:									
Viscosity, 140°F, poise	T 202	600	2,400	600	2,400	600	2,400		
Ductility, 5 cm/min., 77°F, cm	T 51	100	-	100	-	100	-		
Solubility in trichloroethylene, %	T 44	99.0	-	99.0	-	99.0	-		
Spot test	Tex-509-C	N	eg.	Ne	eg.	Ne	eg.		

Table 4 Rapid-Curing Cutback Asphalt

Medium-Curing Cutback Asphalt											
Property	Test				Тур	e–Grade					
	Procedure	MC	C-30	MC	250	MC-	800	MC-	3000		
		Min	Max	Min	Max	Min	Max	Min	Max		
Kinematic viscosity, 140°F, cSt	T 201	30	60	250	500	800	1,600	3,000	6,000		
Water, %	D95	-	0.2	-	0.2	-	0.2	-	0.2		
Flash point, T.O.C., °F	T 79	95	-	122	-	140	-	149	-		
Distillation test: Distillate, percentage by volume of total distillate to 680°F to 437°F to 500°F to 600°F Residue from distillation, volume %	T 78	- 30 75 50	35 75 95 –	- 5 60 67	20 55 90 –	- - 45 75	- 40 85 -	- - 15 80	- 15 75 -		
Tests on distillation residue: Viscosity, 140°F, poise Ductility, 5 cm/min., 77°F, cm Solubility in	T 202 T 51 T 44	300 100 99.0	1,200 - -	300 100 99.0	1,200 _ _	300 100 99.0	1,200 _ _	300 100 99.0	1,200 - -		
trichloroethylene, % Spot test	<u>Tex-509-C</u>	N	eg.	Ne	eg.	Ne	g.	Ne	eg.		

Table 5

Special-Use Cutback Asphalt												
Property	Test	Type–Grade										
	Procedure	MC-2	MC-2400L		CMI	SCM II						
		Min	Max	Min	Max	Min	Max					
Kinematic viscosity, 140°F, cSt	T 201	2,400	4,800	500	1,000	1,000	2,000					
Water, %	D95	-	0.2	-	0.2	-	0.2					
Flash point, T.O.C., °F	T 79	150	-	175	-	175	_					
Distillation test:	T 78											
Distillate, percentage by volume of												
total distillate to 680°F												
to 437°F		-	-	-	-	-	-					
to 500°F		-	35	-	0.5	-	0.5					
to 600°F		35	80	20	60	15	50					
Residue from distillation, volume %		78	-	76	-	82	-					
Tests on distillation residue:												
Polymer		SE	BR		-		-					
Polymer content, % (solids basis)	<u>Tex-533-C</u>	2.0	-	-	-	-	-					
Penetration, 100 g, 5 sec., 77°F	T 49	150	300	180	-	180	-					
Ductility, 5 cm/min., 39.2°F, cm	T 51	50	-	-	-	-	-					
Solubility in trichloroethylene, %	T 44	99.0		99.0		99.0	_					

Table 6

2.4.

**Emulsified Asphalt**. Provide emulsified asphalt that is homogeneous, does not separate after thorough mixing, and meets the requirements for the specified type and grade in Tables 7, 8, 9, 10, and 10A-C.

Data a carta	Test		Emuis	ified Asp	nait	Turne	) un al a				
Property	Procedure	Rapid-S	Sotting		Mediun	Type–G n-Settina	brade		Slow	Setting	
	Tiocedule	HFR	<u> </u>	M			-300	SS-1			-1H
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72	WIIII	Max	WIIII	Max		Max		max		Max
77°F. sec.	172	_	_	_	_	75	400	20	100	20	100
122°F, sec.		150	400	100	300	-	-		-	_	-
Sieve test, %	T 59	-	0.1	-	0.1	-	0.1	_	0.1	-	0.1
Miscibility	T 59	_	0.1	-	-	_		Pa	ass	Pa	ISS
Cement mixing, %	T 59	_	_	_	_	_	_	-	2.0	-	2.0
Coating ability and water	T 59								2.0		2.0
resistance:											
Dry aggregate/after spray		_		-	-	Good/	Fair	-	-	-	-
Wet aggregate/after spray		_			_	Fair/	Fair	-	-	-	-
Demulsibility, 35 mL of 0.02	T 59	50	-	-	30	-	-	-	-	-	-
N CaCl <sub>2</sub> , %											
Storage stability, 1 day, %	T 59	-	1	-	1	-	1	-	1	-	1
Freezing test, 3 cycles <sup>1</sup>	T 59	_		Pa	ISS	_		Pa	ISS	Pa	ISS
Distillation test:	T 59										
Residue by distillation, %		65	-	65	-	65	-	60	-	60	-
by wt.											
Oil distillate, % by volume		-	0.5	-	0.5	-	5	-	0.5	-	0.5
of emulsion											
Tests on residue from											
distillation:											
Penetration, 77°F, 100 g,	T 49	100	140	120	160	300	-	120	160	70	100
5 sec.											
Solubility in	Т 44	97.5	-	97.5	-	97.5	-	97.5	-	97.5	-
trichloroethylene, %	T 64	400		100				400			
Ductility, 77°F, 5 cm/min.,	T 51	100	-	100	-	-	-	100	-	80	-
CM Float toat 140°E and	T 50	1.200				1.200					
Float test, 140°F, sec.		1	-	-	-	1,200	-	-	-	-	-

Table 7 Emulsified Asphalt

1. Applies only when the Engineer designates material for winter use.

#### Table 8 Cationic Emulsified Asphalt

Property	Test						Тур	e-Grade					
	Procedure		Rapid-	Setting			Medium	-Setting			Slow-S	Setting	
		CF	RS-2	CRS	S-2H	CM	IS-2	CMS	S-2S	CSS	S-1	CSS	-1H
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72												
77°F, sec.		-	-	-	-	-	-	-	-	20	100	20	100
122°F, sec.		150	400	150	400	100	300	100	300	-	-	-	-
Sieve test, %	T 59	-	0.1	-	0.1	-	0.1	-	0.1	-	0.1	-	0.1
Cement mixing, %	T 59	-	-	-	-	-	-	-	-	-	2.0	-	2.0
Coating ability and water resistance:	T 59												
Dry aggregate/after spray			-	-	-	Good	d/Fair	Good	d/Fair	-		-	-
Wet aggregate/after spray			-	-	-	Fair	/Fair	Fair	/Fair	-		-	
Demulsibility, 35 mL of 0.8%	T 59	70	-	70	-	-	-	-	-	-	-	-	-
Sodium dioctyl sulfosuccinate, %													
Storage stability, 1 day, %	T 59	-	1	-	1	-	1	-	1	-	1	-	1
Particle charge	T 59	Pos	sitive	Pos	itive	Pos	sitive	Pos	itive	Posi	tive	Posi	tive
Distillation test:													
Residue by distillation, % by wt.	T 59	65	-	65	-	65	-	65	-	60	-	60	-
Oil distillate, % by volume of	1 55	-	0.5	-	0.5	-	7	-	5	-	0.5	-	0.5
emulsion													
Tests on residue from distillation:													
Penetration, 77°F, 100 g, 5 sec.	T 49	120	160	70	110	120	200	300	-	120	160	70	110
Solubility in trichloroethylene, %	T 44	97.5	-	97.5	-	97.5	-	97.5	-	97.5	-	97.5	-
Ductility, 77°F, 5 cm/min., cm	T 51	100	-	80	-	100	-		-	100	-	80	-

Property	Test					Тур	e-Grade				
	Procedure	Rapid-	Setting		Medium	-Setting			Slow	Setting	
		HFR	S-2P	AES	150P	AES	300P	AES-3	300S	SS-1P	
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72										
77°F, sec.		-	-	75	400	75	400	75	400	30	100
122°F, sec.		150	400					-	-	-	-
Sieve test, %	T 59	-	0.1	-	0.1	-	0.1	-	0.1	-	0.1
Miscibility	T 59		_	-	-	-	-	-		F	ass
Coating ability and water resistance:											
Dry aggregate/after spray	T 59		-	Good	d/Fair	Good	d/Fair	Good/F	air		_
Wet aggregate/after spray			-	Fair	/Fair	Fair	/Fair	Fair/F	air		-
Demulsibility, 35 mL of 0.02 N CaCl <sub>2</sub> ,	T 59	50	-	-	-	-	-	-	-	-	-
%											
Storage stability, 1 day, %	T 59	-	1	-	1	-	1	I	1	-	1
Breaking index, g	<u>Tex-542-C</u>	-	-								
Distillation test:1	T 59										
Residue by distillation, % by wt.		65	-	65	-	65	-	65	-	60	-
Oil distillate, % by volume of		-	0.5	-	3	-	5	-	7	-	0.5
emulsion											
Tests on residue from distillation:											
Polymer content, wt. % (solids	<u>Tex-533-C</u>	3.0	-	-	-	-	-	-	-	3.0	-
basis)											
Penetration, 77°F, 100 g, 5 sec.	T 49	90	140	150	300	300	-	300	-	100	140
Solubility in trichloroethylene, %	T 44	97.0	-	97.0	-	97.0	-	97.0	-	97.0	-
Viscosity, 140°F, poise	T 202	1,500	-	-	-	-	-	-	-	1,300	-
Float test, 140°F, sec	T 50	1,200	-	1,200	-	1,200	-	1,200	-	-	-
Ductility, <sup>2</sup> 39.2°F, 5 cm/min., cm	T 51	50	-	-	-	-	-	-	-	50	-
Elastic recovery,2 50°F, %	<u>Tex-539-C</u>	55	-	-	-	-	-	-	-	-	-
Tests on RTFO curing of distillation	T 240										
	Tev 526.0			50		50		20			
Elastic recovery, 50°F, %	<u>Tex-536-C</u>	-	—	50	-	50	-	30	-	-	-

Table 9 Polymer-Modified Emulsified Asphalt

Exception to T 59: Bring the temperature on the lower thermometer slowly to 350°F ±10°F. Maintain at this temperature for 20 min. Complete total distillation in 60 min. (±5 min.) from the first application of heat.
 HFRS-2P must meet one of either the ductility or elastic recovery requirements.

Table 10	
Polymer-Modified Cationic Emulsified Asphal	t

Property	Test	Polyme	-iviouini	ed Cationi	CEIIIUISI		III Type–G	rade					
rioperty	Procedure			Rapid-S	ottina		Type=0	laue	Medium	Setting	1	Slow	Setting
	Trocedure	CRS	.2P	CHFR		CRS-	2TR	CMS	S-1P <sup>3</sup>		1 S-2P <sup>3</sup>		Setting S 1P
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72												
77°F, sec.		_	_	_	_	_	_	10	100	_	_	20	100
122°F, sec.		150	400	100	400	150	500	_	_	50	400	_	_
Sieve test. %	T 59	-	0.1	-	0.1	-	0.1	_	0.1	-	0.1	_	0.1
Demulsibility, 35 ml of 0.8% sodium	T 59	70	-	60	-	40	-	_	-	_	-	-	-
dioctyl sulfosuccinate, %	1.00	10		00		10							
Storage stability, 1 day, %	T 59	-	1	-	1	-	1	-	1	-	1	-	1
Breaking index, g	Tex-542-C	-	-	-	-	-	-	-	-	-	-	-	-
Particle charge	T 59	Posi	tive	Posi	tive	Posit	ive	Pos	sitive	Po	sitive	Po	sitive
Distillation test1:	T 59												
Residue by distillation, % by weight		65	-	65	-	65	-	30	-	60	-	62	-
Oil distillate, % by volume of emulsion		-	0.5	-	0.5	-	3	-	0.5	-	0.5	-	0.5
Tests on residue from distillation:													
Polymer content, wt. % (solids basis)	Tex-533-C	3.0	-	3.0	-	5.07	-	-	-	-	-	3.0	-
Penetration, 77°F, 100 g, 5 sec.	T 49	90	150	80	130	90	150	30	-	30	-	55	90
Viscosity, 140°F, poise	T 202	1,300	-	1,300	-	1,000	-	-	-	-	-	-	-
Solubility in trichloroethylene, %	T44	97.0	-	95.0	-	98	-	-	-	-	-	97.0	-
Softening point, °F	T 53	-	-	-	-	-	-	-	-	-	-	135	-
Ductility, 77°F, 5 cm/min., cm	T 51	-	-	-	-	40	-	-	-	-	-	70	-
Float test, 140°F, sec.	T 50	-	-	1,800	-	-	-	-	-	-	-	-	-
Ductility, <sup>2</sup> 39.2°F, 5 cm/min., cm	T 51	50	-	-	-	-	-	-	-	-	-	-	-
Elastic recovery, <sup>2</sup> 50°F, %	Tex-539-C	55	-	55	-	-	-	-	-	-	-	-	-
Tests on residue from evaporative	R 78,												
recovery:	Procedure												
	В												
Nonrecoverable creep compliance of	T 350	-	-	-	-	-	-	-	2.0	-	4.0	-	-
residue, 3.2 kPa, 52°C, kPa-1													
Tests on rejuvenating agent:													
Viscosity, 140°F, cSt	T 201	-	-	-	-	-	-	50	175	50	175	-	-
Flash point, C.O.C., °F	T 48	-	-	-	-	-	-	380	-	380	-	-	-
Saturates, % by weight	D 2007	-	-	-	-	-	-	-	30	-	30	-	-
Solubility in n-pentane, % by weight	D 2007	-	-	-	-	-	-	99	-	99	-	-	-
Tests on rejuvenating agent after RTFO	T 240												
Weight Change, %		-	-	-	-	-	-	-	6.5	-	6.5	-	-
Viscosity Ratio		-	-	-	-	-	-	-	3.0	-	3.0	-	-
Tests on latex4:													
Tensile strength, die C dumbbell, psi	D 412 <sup>5</sup>	-	-	-	-	-	-	800	-	800	-	-	-
Change in mass after immersion in	D 471	-	-	-	-	-	-	-	406	-	406	-	-
rejuvenating agent, %													

1. Exception to T 59: Bring the temperature on the lower thermometer slowly to 350°F (±0°F). Maintain at this temperature for 20 min. Complete total distillation in 60 min. (±5 min.) from the first application of heat.

2. CRS-2P must meet one of either the ductility or elastic recovery requirements.

With all precertification samples of CMS-1P or CMS-2P, submit certified test reports showing that the rejuvenating agent and latex meet the stated requirements. Submit samples of these raw materials if requested by the Engineer.

4. Preparation of latex specimens: use any substrate and recovery method which produces specimens of uniform dimensions and which delivers enough material to achieve desired residual thickness.

5. Cut samples for tensile strength determination using a crosshead speed of 20 in. per minute.

6. Specimen must remain intact after exposure and removal of excess rejuvenating agent.

7. Modifier type is tire rubber.

Property	Test Procedure	NT-	HRE	NT-RR	E	NT-	SRE
		Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72	15	-	15	-	10	100
77° F, sec.							
Storage stability, 1 Day, %	T 59	-	1	-	1	-	1
Settlement, 5-day, %	T 59	-	5	-	5	-	5
Sieve test, %	T 59	-	0.30	-	0.30	-	0.1
Distillation test:2	T 59						
Residue by distillation, % by wt.		50	-	58	-	50	-
Oil distillate, by volume of emulsion		-	1.0	-	1.0	-	1.0
Test on residue from distillation:							
Penetration, 77°F, 100 g, 5 sec.	T 49	-	20	15	45	40	90
Solubility in trichloroethylene, %	T 44	97.5	-	97.5	-	97.5	-
Softening point, °F	T 53	150	-	-	-	-	-
Dynamic shear, G*/sin(δ), 82°C, 10 rad/s, kPa	T 315	1.0	-	-	-	-	-

Table 10A
Non-Tracking Tack Coat Emulsion <sup>1</sup>

1. Due to the hardness of the residue, these emulsions should be heated to 120-140°F before thoroughly mixing as the emulsion is being prepared for testing.

 Exception to T 59: Bring the temperature on the lower thermometer slowly to 350°F ± 10°F. Maintain at this temperature for 20 min. Complete total distillation in 60 ± 5 min. from first application of heat.

Spray Applied Underseal Memo	brane Polymer-Modified	Emuisions (Eb	3L)
Property	Test Procedure	Min	Max
Viscosity @ 77°F, SSF	T 72	20	100
Storage Stability <sup>1</sup> , %	T 59	-	1
Demulsibility <sup>2</sup>	T 59	55	-
Anionic emulsions – 35 mL of 0.02 N CaCl2, %			
Cationic emulsions – 35 mL of 0.8% sodium			
dioctyl sulfosuccinate, %			
Sieve Test <sup>3</sup> , %	T 59	-	0.05
Distillation Test <sup>4</sup>	T 59		
Residue by distillation, % by wt.		63	
Oil portion of distillate, % by vol.			0.5
Test on Residue from Distillation			
Elastic Recovery @ 50°F, 50 mm/min., %	Tex-539-C	60	-
Penetration @ 77°F, 100 g, 5 sec., 0.1 mm	T 49	80	130
4 46 7 8 8 8 1 1 1 6 6 4 1 8 1			

Table10B Spray Applied Underseal Membrane Polymer-Modified Emulsions (EBL)

1. After standing undisturbed for 24 hr., the surface must be smooth, must not exhibit a white or milky colored substance, and must be a homogeneous color throughout.

2. Material must meet demulsibility test for emulsions.

3. May be required by the Engineer only when the emulsion cannot be easily applied in the field.

4. The temperature on the lower thermometer should be brought slowly to 350°F ± 10°F and maintained at this temperature for 20 min. The total distillation should be completed in 60 ± 5 min. from the first application of heat.

Property	Test Procedure	Standard	Yield (SY)	High	Yield (HY)
		Min	Max	Min	Max
Sieve test, %	T 59	-	0.1	-	0.1
Viscosity Saybolt Furol @ 77°F, sec.	T 59	20	100	20	100
Distillation test1:	T 59				
Residue by distillation, % by wt.		60	-	63	-
Oil portion of distillate, % by vol.		-	0.5	-	0.5
Test on residue from distillation:	T 49				
Penetration @ 77°F, dmm		55	95	120	-
Test on rejuvenating agent:					
BWOA, % <sup>2</sup>	***	-	-	2	-
Viscosity @ 140°F, cSt	T 201	-	-	50	175
Flash Point, COC, °F	T 48	-	-	380	-
Solubility in n-pentane, % by wt.	D2007	-	-	99	-

Table 10C	
Full-Depth Reclamation Emulsion (	FDR EM)

 The temperature on the lower thermometer should be brought slowly to 350°F ±10°F and maintained at this temperature for 20 min. The total distillation should be completed in 60 ± 5 min. from the first application of heat.

2. BWOA = By weight of asphalt. Provide a manufacturer's certificate of analysis (COA) with the percent of rejuvenator added.

2.5.

**Specialty Emulsions.** Provide specialty emulsion that is either asphalt-based or resin-based and meets the requirements of Table 11 or Table 11A.

Specialty Emulsions									
Property	Test Procedure			Type-0	Grade				
			Medium-	Setting		Slow-	Setting		
		AE	·P	EA	P&T	P			
		Min	Max	Min	Max	Min	Max		
Viscosity, Saybolt Furol	T 72								
77°F, sec.		-	-	-	-	10	100		
122°F, sec.		15	150	-	-	-	-		
Sieve test, %	T 59	-	0.1	-	0.1	-	0.1		
Miscibility <sup>2</sup>	T 59	-		Pass		Pass			
Demulsibility, 35 mL of 0.10 N CaCl <sup>2</sup> , %	T 59	-	70	-	-	-	-		
Storage stability, 1 day, %	T 59	-	1	-	1	-	-		
Particle size, <sup>5</sup> % by volume < 2.5 μm	<u>Tex-238-F<sup>3</sup></u>	-	-	90	-	90	-		
Asphalt emulsion distillation to 500°F									
followed by Cutback asphalt distillation of	T 59 & T 78								
residue to 680°F:									
Residue after both distillations, % by wt.		40	-	-	-	-	-		
Total oil distillate from both distillations, %		25	40	-	-	-	-		
by volume of emulsion									
Residue by distillation, % by wt.	T 59	-	-	60	-	-	-		
Residue by evaporation, <sup>4</sup> % by wt.	T 59	-	-	-	-	60	-		
Tests on residue after all distillations:									
Viscosity, 140°F, poise	T 202	-	-	800	-	-	-		
Kinematic viscosity, <sup>5</sup> 140°F, cSt	T 201	-	-	-	-	100	350		
Flash point C.O.C., °F	T 48	-	-	-	-	400	-		
Solubility in trichloroethylene, %	T 44	97.5	-	-	-	-	-		
Float test, 122°F, sec.	T 50	50	200	-	-	-	-		

Table 11 Specialty Emulsio

1. Supply with each shipment of PCE:

 a copy of a lab report from an approved analytical lab, signed by a lab official, indicating the PCE formulation does not meet any characteristics of a Resource Conservation Recovery Act (RCRA) hazardous waste;

a certification from the producer that the formulation supplied does not differ from the one tested and that no listed RCRA hazardous wastes or Polychlorinated Biphenyls (PCBs) have been mixed with the product; and

a Safety Data Sheet.

3.

2. Exception to T 59: In dilution, use 350 mL of distilled or deionized water and a 1,000-mL beaker.

Use <u>Tex-238-F</u>, beginning at "Particle Size Analysis by Laser Diffraction," with distilled or deionized water as a medium and no dispersant, or use another approved method.

4. Exception to T 59: Leave sample in the oven until foaming ceases, then cool and weigh.

5. PCE must meet either the kinematic viscosity requirement or the particle size requirement.

Hard Residue Surface Sealant									
Property	Test	Min	Max						
	Procedure								
Viscosity, Krebs unit, 77°F, Krebs units	D 562	45	75						
Softening point, °F	Tex-505-C <sup>1</sup>	250	Ι						
Uniformity	D 2939	Pa	SS <sup>2</sup>						
Resistance to heat	D 2939	Pa	SS <sup>3</sup>						
Resistance to water	D 2939	Pa	SS <sup>4</sup>						
Wet flow, mm	D 2939	-	0						
Resistance to Kerosene (optional) <sup>5</sup>	D 2939	Pass <sup>6</sup>							
Ultraviolet exposure, UVA-340, 0.77 W/m <sup>2</sup> ,	G 154	Pa	SS <sup>8</sup>						
50°C chamber, 8 hr. UV lamp, 5 min. spray,									
3 hr. 55 min. condensation, 1,000 hr. total									
exposure <sup>7</sup>									
Abrasion loss, 1.6 mm thickness, liquid only, %	ISSA TB-100	Ι	1.0						
Residue by evaporation, % by weight	D 2939	33	-						
Tests on residue from evaporation:									
Penetration, 77°F, 100 g, 5 sec.	T 49	15	30						
Flash point, Cleveland open cup, °F	T 48								
Tests on base asphalt before emulsification									
Solubility in trichloroethylene, %	T 44	98	-						

Table 11A Hard Residue Surface Sealant

1. Cure the emulsion in the softening point ring in a 200°F  $\pm$  5°F oven for 2 hr.

2. Product must be homogenous and show no separation or coagulation that cannot be overcome by moderate stirring.

3. No sagging or slippage of film beyond the initial reference line.

4. No blistering or re-emulsification.

5. Recommended for airport applications or where fuel resistance is desired.

- 6. No absorption of Kerosene into the clay tile past the sealer film. Note sealer surface condition and loss of adhesion.
- 7. Other exposure cycles with similar levels of irradiation and conditions may be used with Department approval.
- 8. No cracking, chipping, surface distortion, or loss of adhesion. No color fading or lightening.
- 2.6. **Recycling Agent**. Recycling agent and emulsified recycling agent must meet the requirements in Table 12. Additionally, recycling agent and residue from emulsified recycling agent, when added in the specified proportions to the recycled asphalt, must meet the properties specified on the plans.

Recy	cling Agent ar	nd Emulsif	ied Recycl	ing Agent			
Property	Test Procedure				Emulsified Recycling Agent (ARA-1)		Modified sified ng Agent A-1P)
		Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol, 77°F, sec.	T 72	-	-	15	100	15	110
Sieve test, %	T 59	-	-	-	0.1	-	0.1
Miscibility <sup>1</sup>	T 59	<ul> <li>– No coagulation</li> </ul>		gulation			
Residue by evaporation, <sup>2</sup> % by wt.	T 59	_	-	60	-	I	_
Distillation test:	T 59						
Residue by distillation, % by wt.						60	65
Oil distillate, % by volume of emulsion						-	2
Penetration of Distillation Residue at	T 49					110	190
39.2°F, 100 g, 5 sec.							
Tests on recycling agent or residue from							
evaporation:							
Flash point, C.O.C., °F	T 48	400	-	400	-	400	-
Kinematic viscosity,	T 201						
140°F, cSt		75	200	75	200		
275°F, cSt		-	10.0	-	10.0		

Table 12

Exception to T 59: Use 0.02 N CaCl2 solution in place of water. 1.

Exception to T 59: Maintain sample at 300°F until foaming ceases, then cool and weigh. 2.

2.7. Crumb Rubber Modifier. Crumb rubber modifier (CRM) consists of automobile and truck tires processed by ambient temperature grinding.

CRM must be:

- free from contaminants including fabric, metal, and mineral and other nonrubber substances;
- free-flowing; and
- nonfoaming when added to hot asphalt binder.

Ensure rubber gradation meets the requirements of the grades in Table 13 when tested in accordance with Tex-200-F, Part I, using a 50-g sample.

Table 13

				CRM Grad	ations			
Sieve Size	Grad	e A	Grade B Grade C		Grade D	Grade E		
(% Passing)	Min	Max	Min	Max	Min	Max		
#8	100	-	-	-	-	-	As shown on the plans	
#10	95	100	100	-	-	-		
#16	-	-	70	100	100	-		As approved
#30	-	-	25	60	90	100		As approved
#40	-	-	-	-	45	100		
#50	0	10	-	-	-	-		
#200	-	-	0	5	-	-		

2.8.

Crack Sealer. Provide polymer-modified asphalt-emulsion crack sealer meeting the requirements of Table 14. Provide rubber-asphalt crack sealer meeting the requirements of Table 15.

r orymer-woulded Asphalt-Emulsion orack dealer							
Property	Test Procedure	Min	Max				
Rotational viscosity, 77°F, cP	D 2196, Method A	10,000	25,000				
Sieve test, %	T 59	-	0.1				
Storage stability, 1 day, %	T 59	-	1				
Evaporation	<u>Tex-543-C</u>						
Residue by evaporation, % by wt.		65	-				
Tests on residue from evaporation:							
Penetration, 77°F, 100 g, 5 sec.	Т 49	35	75				
Softening point, °F	T 53	140	-				
Ductility, 39.2°F, 5 cm/min., cm	T 51	100	-				

Table 14 Polymer-Modified Asphalt-Emulsion Crack Sealer

Table 15 Rubber-Asphalt Crack Sealer

Property	Test	Cla	ss A	Class B				
	Procedure	Min	Max	Min	Max			
CRM content, Grade A or B, % by wt.	<u>Tex-544-C</u>	22	26	-	_			
CRM content, Grade B, % by wt.	<u>Tex-544-C</u>	-	-	13	17			
Virgin rubber content, <sup>1</sup> % by wt.		-	-	2	-			
Flash point, <sup>2</sup> C.O.C., °F	T 48	400	-	400	_			
Penetration, <sup>3</sup> 77°F, 150 g, 5 sec.	T 49	30	50	30	50			
Penetration, <sup>3</sup> 32°F, 200 g, 60 sec.	T 49	12	-	12	_			
Softening point, °F	T 53	-	-	170	_			
Bond Test, non-immersed, 0.5 in specimen,								
50% extension, 20°F <sup>4</sup>	D5329	.	-	Pa	ISS			
A Description and the attent that the Mire 0/ structures	أسوادا والمتعادين والماري							

1. Provide certification that the Min % virgin rubber was added.

2. Agitate the sealing compound with a 3/8- to 1/2 in. (9.5- to 12.7 mm) wide, square-end metal spatula to bring the material on the bottom of the cup to the surface (i.e., turn the material over) before passing the test flame over the cup. Start at one side of the thermometer, move around to the other, and then return to the starting point using 8 to 10 rapid circular strokes. Accomplish agitation in 3 to 4 sec. Pass the test flame over the cup immediately after stirring is completed.

3. Exception to T 49: Substitute the cone specified in D 217 for the penetration needle.

4. Allow no crack in the crack sealing materials or break in the bond between the sealer and the mortar blocks over 1/4 in. deep for any specimen after completion of the test.

2.9. Asphalt-Rubber Binders. Provide asphalt-rubber (A-R) binders that are mixtures of asphalt binder and CRM, which have been reacted at elevated temperatures. Provide A-R binders meeting D6114 and containing a minimum of 15% CRM by weight. Provide Types I or II, containing CRM Grade C, for use in hot-mixed aggregate mixtures. Provide Types II or III, containing CRM Grade B, for use in surface treatment binder. Ensure binder properties meet the requirements of Table 16.

15

130

20

450

75

25

125

10

450

75

-

\_

\_

\_

\_

-

\_

\_

\_

\_

2.10.

**Performance-Graded Binders**. Provide PG binders that are smooth and homogeneous, show no separation when tested in accordance with <u>Tex-540-C</u>, and meet the requirements of Table 17.

10

135

25

450

75

-

\_

\_

\_

\_

T 49

T 53

D5329

T 48

T 179

T 49

Separation testing is not required if:

Property

Apparent viscosity, 347°F, cP

Penetration, 77°F, 100 g, 5 sec.

Tests on residue from Thin-Film

200 g, 60 sec., % of original

Retained penetration ratio, 39.2°F,

Softening point, °F

Resilience, 77°F, %

Oven Test:

Flash point, C.O.C., °F

Penetration, 39.2°F, 200 g, 60 sec.

- a modifier is introduced separately at the mix plant either by injection in the asphalt line or mixer,
- the binder is blended on site in continuously agitated tanks, or
- binder acceptance is based on field samples taken from an in-line sampling port at the hot-mix plant after the addition of modifiers.

#### Table 17 Performance-Graded Binders

					Pe	rtorma	nce-Gra											
Property and Test Method								Pe		nce Grad	е							
	PG 58				PG 64			PG 70			PG 76			PG 82				
	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28
Average 7-day max pavement design temperature, °C1		58				64			-	70			7	6			82	
Min pavement design temperature, °C1	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28
						Ori	ginal Bin	der										
Flash point, T 48, Min, °C									23	30								
Viscosity, T 316 <sup>2, 3</sup> :									11	35								
Max, 3.0 Pas, test temperature, °C									1.	50								
Dynamic shear, T 3154:																		
Ğ*/sin(δ), Min, 1.00 kPa, Max, 2.00 kPa²,		58				64			-	70			7	6			82	
Test temperature @ 10 rad/sec., °C																		
Elastic recovery, D6084, 50°F, % Min <sup>8</sup>	-	-	30	-	-	30	50	-	30	50	60	30	50	60	70	50	60	70
					Rollin	g Thin-	Film Ove	n ( <u>Tex-5(</u>	) <mark>6-C</mark> )									
Mass change, T 240, Max, %									1	.0								
Dynamic shear, T 315:																		
Ġ*/sin(δ), Min, 2.20 kPa, Max, 5.00 kPa <sup>7</sup> ,		58				64			-	70			7	6			82	
Test temperature @ 10 rad/sec., °C																		
MSCR, T350, Recovery, 0.1 kPa, High Temperature, % Min <sup>8</sup>	-	-	20	-	-	20	30	-	20	30	40	20	30	40	50	30	40	50
				Pre	essure A	Aging V	essel (PA	V) Resid	lue (R 2	8)								
PAV aging temperature, °C									1(	00								
Dynamic shear, T 315:																		
G <sup>*</sup> sin(δ), Max, 5,000 kPa	25	22	19	28	25	22	19	28	25	22	19	28	25	22	19	28	25	22
Test temperature @ 10 rad/sec., °C																		
Creep stiffness, T 313 <sup>5, 6</sup> :																		
S, max, 300 MPa,	10	-18	04	<u> </u>	10	-18	04	<u> </u>	10	10	04	<u> </u>	-12	-18	24	~	10	10
<i>m</i> -value, Min, 0.300	-12	-1ŏ	-24	-6	-12	-10	-24	-6	-12	-18	-24	-6	-12	-1ŏ	-24	-6	-12	-18
Test temperature @ 60 sec., °C																		
Direct tension, T 3146:																		
Failure strain, min, 1.0% Test temperature @ 1.0 mm/min., °C	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18

1. Pavement temperatures are estimated from air temperatures and using an algorithm contained in a Department-supplied computer program, may be provided by the Department, or by following the procedures outlined in AASHTO MP 2 and PP 28.

 This requirement may be waived at the Department's discretion if the supplier warrants that the asphalt binder can be adequately pumped, mixed, and compacted at temperatures that meet all applicable safety, environmental, and constructability requirements. At test temperatures where the binder is a Newtonian fluid, any suitable standard means of viscosity measurement may be used, including capillary (T 201 or T 202) or rotational viscometry (T 316).

3. Viscosity at 135°C is an indicator of mixing and compaction temperatures that can be expected in the lab and field. High values may indicate high mixing and compaction temperatures. Additionally, significant variation can occur from batch to batch. Contractors should be aware that variation could significantly impact their mixing and compaction operations. Contractors are therefore responsible for addressing any constructability issues that may arise.

4. For quality control of unmodified asphalt binder production, measurement of the viscosity of the original asphalt binder may be substituted for dynamic shear measurements of G\*/sin(δ) at test temperatures where the asphalt is a Newtonian fluid. Any suitable standard means of viscosity measurement may be used, including capillary (T 201 or T 202) or rotational viscometry (T 316).

5. Silicone beam molds, as described in AASHTO TP 1-93, are acceptable for use.

6. If creep stiffness is below 300 MPa, direct tension test is not required. If creep stiffness is between 300 and 600 MPa, the direct tension failure strain requirement can be used instead of the creep stiffness requirement. The m value requirement must be satisfied in both cases.

7. Maximum values for unaged and RTFO aged dynamic shear apply only to materials used as substitute binders, as described in Item 340, "Dense-Graded Hot-Mix Asphalt (Small Quantity)", Item 341, "Dense-Graded Hot-Mix Asphalt, and Item 344, "Superpave Mixtures."

8. Elastic Recovery (ASTM D6084) is not required unless MSCR (AASHTO T 350) is less than the minimum % recovery. Elastic Recovery must be used for the acceptance criteria in this instance.

### EQUIPMENT

3.

Provide all equipment necessary to transport, store, sample, heat, apply, and incorporate asphalts, oils, and emulsions.

4.

### CONSTRUCTION

**Typical Material Use.** Use materials shown in Table 18, unless otherwise determined by the Engineer.

Table18						
Typical Material Use						
Material Application	Typically Used Materials					
Hot-mixed, hot-laid asphalt mixtures	PG binders, A-R binders Types I and II					
Surface treatment	AC-5, AC-10, AC-15P, AC-20XP, AC-10-2TR, AC-20-5TR, HFRS-2, MS-2, CRS-2, CRS-2H, CRS-2TR, CMS-2P HFRS-2P, CRS-2P, CHFRS-2P, A-R binders Types II and III					
Surface treatment (cool weather)	AC12-5TR, RC-250, RC-800, RC-3000, MC-250, MC-800, MC-3000, MC-2400L, CMS-2P					
Precoating	AC-5, AC-10, PG 64-22, SS-1, SS-1H, CSS-1, CSS-1H					
Tack coat	PG Binders, SS-1H, CSS-1H, EAP&T, TRAIL, EBL					
Fog seal	SS-1, SS-1H, CSS-1, CSS-1H, CMS-1P					
Hot-mixed, cold-laid asphalt mixtures	AC-0.6, AC-1.5, AC-3, AES-300, AES-300P, CMS-2, CMS-2S					
Patching mix	MC-800, SCM I, SCM II, AES-300S					
Recycling	AC-0.6, AC-1.5, AC-3, AES-150P, AES-300P, recycling agent, emulsified recycling agent					
Crack sealing	SS-1P, polymer mod AE crack sealant, rubber asphalt crack sealers (Class A, Class B)					
Microsurfacing	CSS-1P					
Prime	MC-30, AE-P, EAP&T, PCE					
Curing membrane	SS-1, SS-1H, CSS-1, CSS-1H, PCE					
Erosion control	SS-1, SS-1H, CSS-1, CSS-1H, PCE					
FDR -Foaming	PG 64-22, FDR EM-SY, FDR EM-HY					

4.1. **Storage and Application Temperatures**. Use storage and application temperatures in accordance with Table 19. Store and apply materials at the lowest temperature yielding satisfactory results. Follow the manufacturer's instructions for any agitation requirements in storage. Manufacturer's instructions regarding recommended application and storage temperatures supersede those of Table 19.

Storage	and Application Temperature			
	Applicat	Storage		
Type-Grade	Recommended Range (°F)	Max Allowable (°F)	Max (°F)	
AC-0.6, AC-1.5, AC-3	200–300	350	350	
AC-5, AC-10	275–350	350	350	
AC-15P, AC-20-5TR, AC12-5TR and AC10-2TR	300–375	375	360	
RC-250	125–180	200	200	
RC-800	170–230	260	260	
RC-3000	215–275	285	285	
MC-30, AE-P	70–150	175	175	
MC-250	125–210	240	240	
MC-800, SCM I, SCM II	175–260	275	275	
MC-3000, MC-2400L	225–275	290	290	
HFRS-2, MS-2, CRS-2, CRS-2H, HFRS-2P, CRS-2P, CMS-2, CMS-2S, AES-300, AES-300S, AES-150P, AES-300P, CRS-2TR	120–160	180	180	
SS-1, SS-1H, CSS-1, CSS-1H, PCE, EAP&T, SS-1P, RS-1P, CRS-1P, CSS-1P, recycling agent, emulsified recycling agent, polymer mod AE crack sealant	50–130	140	140	
PG binders	275–350	350	350	
Rubber asphalt crack sealers (Class A, Class B)	350–375	400	-	
A-R binders Types I, II, and III	325-425	425	425	

Table19 Storage and Application Temperatures

### 5. MEASUREMENT AND PAYMENT

The work performed, materials furnished, equipment, labor, tools, and incidentals will not be measured or paid for directly but is subsidiary or is included in payment for other pertinent Items.

### Special Specification 6001 Portable Changeable Message Sign



### 1. DESCRIPTION

Furnish, operate, and maintain portable trailer mounted changeable message sign (PCMS) units.

### 2. MATERIALS

Furnish new or used material in accordance with the requirements of this Item and the details shown on the plans. Provide a self-contained PCMS unit with the following:

- Sign controller
- Changeable Message Sign
- Trailer
- Power source

Paint the exterior surfaces of the power supply housing, supports, trailer, and sign with Federal Orange No. 22246 or Federal Yellow No. 13538 of Federal Standard 595C, except paint the sign face assembly flat black.

- 2.1. **Sign Controller**. Provide a controller with permanent storage of a minimum of 75 pre-programmed messages. Provide an external input device for random programming and storage of a minimum of 75 additional messages. Provide a controller capable of displaying up to 3 messages sequentially. Provide a controller with adjustable display rates. Enclose sign controller equipment in a lockable enclosure.
- 2.2. **Changeable Message Sign**. Provide a sign capable of being elevated to at least 7 ft. above the roadway surface from the bottom of the sign. Provide a sign capable of being rotated 360° and secured against movement in any position.

Provide a sign with 3 separate lines of text and 8 characters per line minimum. Provide a minimum 18 in. character height. Provide a 5 × 7 character pixel matrix. Provide a message legibility distance of 600 ft. for nighttime conditions and 800 ft. for normal daylight conditions. Provide for manual and automatic dimming light sources.

The following are descriptions for 3 screen types of PCMS:

- Character Modular Matrix. This screen type comprises of character blocks.
- **Continuous Line Matrix**. This screen type uses proportionally spaced fonts for each line of text.
- Full Matrix. This screen type uses proportionally spaced fonts, varies the height of characters, and displays simple graphics on the entire sign.
- 2.3. **Trailer**. Provide a 2 wheel trailer with square top fenders, 4 leveling jacks, and trailer lights. Do not exceed an overall trailer width of 96 in. Shock mount the electronics and sign assembly.
- 2.4. **Power Source**. Provide a diesel generator, solar powered power source, or both. Provide a backup power source as necessary.
- 2.5. **Cellular Telephone**. When shown on the plans, provide a cellular telephone connection to communicate with the PCMS unit remotely.

### 3. CONSTRUCTION

Place or relocate PCMS units as shown on the plans or as directed. The plans will show the number of PCMS units needed, for how many days, and for which construction phases.

Maintain the PCMS units in good working condition. Repair damaged or malfunctioning PCMS units as soon as possible. PCMS units will remain the property of the Contractor.

### 4. MEASUREMENT

This Item will be measured by each PCMS or by the day used. All PCMS units must be set up on a work area and operational before a calendar day can be considered measurable. When measurement by the day is specified, a day will be measured for each PCMS set up and operational on the worksite.

### 5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Portable Changeable Message Sign." This price is full compensation for PCMS units; set up; relocating; removing; replacement parts; batteries (when required); fuel, oil, and oil filters (when required); cellular telephone charges (when required); software; and equipment, materials, tools, labor, and incidentals.

### **Special Specification 6185**

# Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)



### 1. DESCRIPTION

Furnish, operate, maintain and remove upon completion of work, Truck Mounted Attenuator (TMA) or Trailer Attenuator (TA).

### 2. MATERIALS

Furnish, operate and maintain new or used TMAs or TAs. Assure used attenuators are in good working condition and are approved for use. A list of approved TMA/TA units can be found in the Department's Compliant Work Zone Traffic Control Devices List. The host vehicle for the TMA and TA must weigh a minimum of 19,000 lbs. Host vehicles may be ballasted to achieve the required weight. Any weight added to the host vehicle must be properly attached or contained within it so that it does not present a hazard and that proper energy dissipation occurs if the attenuator is impacted from behind by a large truck. The weight of a TA will not be considered in the weight of the host vehicle but the weight of a TMA may be included in the weight of the host vehicle. Upon request, provide either a manufacturer's curb weight or a certified scales weight ticket to the Engineer.

#### 3. CONSTRUCTION

Place or relocate TMA/TAs as shown on the plans or as directed. The plans will show the number of TMA/TAs needed, for how many days or hours, and for which construction phases.

Maintain the TMA/TAs in good working condition. Replace damaged TMA/TAs as soon as possible.

#### 4. MEASUREMENT

- 4.1. **Truck Mounted Attenuator/Trailer Attenuator (Stationary).** This Item will be measured by the each or by the day. TMA/TAs must be set up in a work area and operational before a calendar day can be considered measurable. When measurement by the day is specified, a day will be measured for each TMA/TA set up and operational on the worksite.
- 4.2. **Truck Mounted Attenuator/Trailer Attenuator (Mobile Operation).** This Item will be measured by the hour. The time begins once the TMA/TA is ready for operation at the predetermined site and stops when notified by the Engineer. A minimum of 4 hr. will be paid each day for each operating TMA/TA used in a mobile operation.

### 5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Truck Mounted Attenuators/Trailer Attenuators (Stationary)," or "Truck Mounted Attenuators/Trailer Attenuators (Mobile Operation)." This price is full compensation for furnishing TMA/TA: set up; relocating; removing; operating; fuel; and equipment, materials, tools, labor, and incidentals.

This page intentionally left blank.