

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: F 2023(167)

CONTROL: 0047-04-031

COUNTY: COLLIN

LETTING: 12/02/2022

REFERENCE NO: 1118

PROPOSAL ADDENDUMS

___ PROPOSAL COVER

X BID INSERTS (SH. NO.: ALL)

X GENERAL NOTES (SH. NO.: ALL)

___ SPEC LIST (SH. NO.:)

___ SPECIAL PROVISIONS:)

ADDED:

DELETED:

___ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: PLAN SHEET AND OTHER CHANGES

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

***** BID INSERTS *****

REVISED QUANTITIES FOR THE FOLLOWING BID ITEMS:

423-6004, 464-6008, 464-6009, 512-6049, 512-6057, 512-6058

450-6103, 260-6012, 400-6005

***** GENERAL NOTES *****

TABLE 2 ITEM 260 RATE REVISED

***** PLAN SHEETS *****

SHEET 0015, 0015A-0015K, 0016, 0016A-0016F, 0017, 0022, 0023, 0024,

0025, 0042, 0043, 0109 ARE REVISED

INDEX OF SHEETS

SHEET NO. DESCRIPTION

SHEET NO. DESCRIPTION

SHEET NO. DESCRIPTION

I. GENERAL

| | |
|---------------|---|
| 1 | TITLE SHEET |
| 2 - 3 | INDEX OF SHEETS |
| 4 - 8 | PROJECT LAYOUT |
| 9 - 10 | EXISTING TYPICAL SECTIONS |
| 11 - 14A | PROPOSED TYPICAL SECTIONS |
| 15, 15A - 15K | GENERAL NOTES |
| 16, 16A - 16F | ESTIMATE & QUANTITY SHEETS |
| 17 - 18 | SUMMARY OF TRAFFIC CONTROL QUANTITIES |
| 19 - 20 | SUMMARY OF EARTHWORK QUANTITIES |
| 21 | SUMMARY OF REMOVAL QUANTITIES |
| 22 | SUMMARY OF ROADWAY QUANTITIES |
| 23 | SUMMARY OF RETAINING WALL QUANTITIES |
| 24 - 28 | SUMMARY OF DRAINAGE QUANTITIES |
| 29 | SUMMARY OF TEMPORARY SIGNAL QUANTITIES |
| 30 | SUMMARY OF PERMANENT TRAFFIC SIGNAL QUANTITIES |
| 31 - 32 | SUMMARY OF SIGNING AND PAVEMENT MARKINGS QUANTITIES |
| 33 - 36A | SUMMARY OF SMALL SIGNS |
| 37 | SUMMARY OF SW3P QUANTITIES |

II. TRAFFIC CONTROL PLAN

| | |
|---------|---|
| 38 | TRAFFIC CONTROL PLAN NARRATIVE |
| 39 - 40 | TRAFFIC CONTROL PLAN ADVANCED WARNING SIGNS |
| 41 | TRAFFIC CONTROL PLAN ADVANCED WARNING SIGNS CROSS STREETS |
| 42 - 43 | TRAFFIC CONTROL PLAN TYPICAL SECTIONS |
| 44 - 53 | TRAFFIC CONTROL PLAN PHASE 1 LAYOUT |
| 54 - 56 | TRAFFIC CONTROL PLAN PHASE 1 LAYOUT AT E MELISSA RD |
| 57 - 58 | TRAFFIC CONTROL PLAN PHASE 1 LAYOUT AT W FANNIN RD |
| 59 - 60 | TRAFFIC CONTROL PLAN PHASE 1 LAYOUT AT COLLIN COUNTY OUTER LP |
| 61 - 70 | TRAFFIC CONTROL PLAN PHASE 2 LAYOUT |
| 71 - 73 | TRAFFIC CONTROL PLAN PHASE 2 LAYOUT AT E MELISSA RD |
| 74 - 76 | TRAFFIC CONTROL PLAN PHASE 2 LAYOUT AT PENNSYLVANIA AVE |
| 77 - 80 | TRAFFIC CONTROL PLAN PHASE 2 LAYOUT AT THROCKMORTON RD |
| 81 | TRAFFIC CONTROL PLAN TEMPORARY PAVEMENT MARKINGS ON NEW ROADWAYS |
| 82 | TRAFFIC CONTROL PLAN PHASE 1 & 2 DETOUR LAYOUT W FANNIN RD |
| 83 | TRAFFIC CONTROL PLAN PHASE 1 DETOUR LAYOUT HIGHLAND RD |
| 84 | TRAFFIC CONTROL PLAN PHASE 2 DETOUR LAYOUT HIGHLAND RD/N CENTRAL ST |
| 85 | TRAFFIC CONTROL PLAN PHASE 2 DETOUR LAYOUT COLLIN COUNTY OUTER LP |
| 86 | TYPICAL MINOR STREET & DRIVEWAY TCP PHASING DETAIL |
| 87 | TWO-WAY MINOR STREET & DRIVEWAY TCP PHASING DETAIL |

STANDARDS

| | |
|---------------|-----------------------------|
| *** 88 - 99 | BC(1)-21 THRU BC(12)-21 |
| *** 100 - 101 | LPCB-13 |
| *** 102 | TCP(2-1)-18 |
| *** 103 | TCP(2-3)-18 |
| *** 104 | WZ(BRK)-13 |
| *** 105 - 106 | WZ(BTS-1)-13 & WZ(BTS-2)-13 |
| *** 107 | WZ(RCD)-13 |
| *** 108 | WZ(STPM)-13 |
| *** 109 | CCSS |
| *** 110 - 111 | SSCB(2)-10 |
| *** 112 | ABSORB(M)-19 |
| *** 113 | OMIT |

III. ROADWAY DETAILS

| | |
|------------|---|
| 114 | SURVEY CONTROL INDEX |
| 115 | HORIZONTAL AND VERTICAL CONTROL SHEET |
| 116 - 119 | SOIL BORING LOGS |
| 120 - 133 | HORIZONTAL ALIGNMENT DATA |
| 134 - 142 | REMOVAL PLAN |
| 143 - 159 | ROADWAY PLAN AND PROFILE |
| 160 | E. MELISSA RD. PLAN AND PROFILE |
| 161 | N. CENTRAL ST. PLAN AND PROFILE |
| 162 | HIGHLAND RD. PLAN AND PROFILE |
| 163 | THROCKMORTON RD. PLAN AND PROFILE |
| 164 | COLLIN COUNTY OUTER LOOP PLAN AND PROFILE |
| 165 - 169 | INTERSECTION LAYOUT |
| 170 - 177 | MINOR CROSS STREET PLAN AND PROFILE |
| 178 - 207A | DRIVEWAY DETAILS |
| 208 - 211 | MISCELLANEOUS ROADWAY DETAILS |

STANDARDS

| | |
|-------------|------------------------|
| * 212 | CCCG-22 |
| * 213 | JS-14 |
| * 214 - 215 | CRCP(1)-20 |
| * 216 - 219 | PED-18 |
| * 220 - 221 | MBP(1)-22 & MBP(2)-22 |
| * 222 - 225 | MB(1)-21 THRU MB(4)-21 |
| 226 | OMIT |
| * 227 | TE(HMAC)-11 |
| * 228 | LJD(1-1)-07 (DAL) |
| * 229 - 230 | PR11 |

IV. RETAINING WALL DETAILS

| | |
|-----|-----------------------|
| 231 | RETAINING WALL LAYOUT |
|-----|-----------------------|

STANDARDS


| | |
|-------|--------|
| * 232 | RW(CB) |
|-------|--------|

V. DRAINAGE DETAILS

| | |
|-----------|--|
| 233 - 234 | OVERALL DRAINAGE AREA MAP |
| 235 - 251 | DRAINAGE AREA MAP |
| 252 - 254 | RUNOFF COMPUTATIONS |
| 255 - 268 | INLET COMPUTATIONS |
| 269 - 283 | STORM SEWER COMPUTATIONS |
| 284 | CULVERT SUMMARY DATA |
| 285 - 286 | CULVERT LAYOUT |
| 287 - 303 | NB DRAINAGE PLAN AND PROFILE |
| 304 - 320 | SB DRAINAGE PLAN AND PROFILE |
| 321 | N. CENTRAL ST. DRAINAGE PLAN AND PROFILE |
| 322 | HIGHLAND RD. DRAINAGE PLAN AND PROFILE |
| 323 - 325 | NB DRAINAGE LATERALS |
| 326 - 328 | SB DRAINAGE LATERALS |
| 329 | SPECIAL JUNCTION BOX A6-OUT |
| 330 | SPECIAL JUNCTION BOX A7-OUT |
| 330A | EXCAVATION AND BACKFILL DIAGRAMS |

STANDARDS

| | |
|---------------|---------|
| * 331 | BCS |
| * 332 - 333 | SCC-3&4 |
| * 334 - 335 | SCC-5&6 |
| * 335A - 335B | SCC-8 |
| * 336 | SCC-MD |
| * 337 | SCP-3 |
| * 338 | SCP-4 |
| * 339 | SCP-5 |
| * 340 | SCP-6 |
| * 340A | SCP-8 |
| * 341 | SCP-MD |
| * 342 | ECD |
| * 343 | PW |
| * 344 | PB |
| * 345 | PBGC |
| * 346 | PJB |
| * 347 | PDD |
| * 348 - 349 | PCO |
| * 350 | CGT-PCO |
| * 351 - 352 | PSL |
| * 353 - 354 | SETP-CD |
| * 355 | SETP-PD |
| * 356 | PSET-SC |
| * 357 | PSET-RC |
| * 358 | PSET-SP |
| * 359 | PSET-RP |
| * 359A - 359B | PCU |
| * 359C | CGT-PCU |



* THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Paul M. Baxter, P.E. 11/15/2022
SIGNATURE OF REGISTRANT & DATE



*** THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

Chansothi Oum, P.E. 10/26/2022
SIGNATURE OF REGISTRANT & DATE

CivilTech Engineering, Inc. 11821 Telge Road
Cypress, Texas 77429
PH: (281) 304-0200 - FX: (281) 304-0210
Firm Registration No. F-382



SH 5

INDEX OF SHEETS

SHEET 1 OF 2

| | | | | |
|-----------|---------------------|-----------------------------|---------------|------------------|
| DSN: DC | FED. RD. DIV. NO. 6 | PROJECT NO. SEE TITLE SHEET | | SHEET NO. 2 |
| DRN: DA | STATE TEXAS | DIST. 18 | COUNTY COLLIN | |
| APPVD: PB | CON. 0047 | SECT. 04 | JOB 031 | HIGHWAY NO. SH 5 |

ADDENDUM #1, 11/15/22, REPLACE SHEET

10/26/2022 1:26:05 PM c:\pwworking\tdgdl\civiltech\civiltech\civiltech\dms06064\SEG1_GNIS_01.dgn

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

SPECIFICATION DATA

| Table 1: Soil Constants Requirements | | | | |
|--------------------------------------|---------------------------------|------------------|-----|------|
| Item | Description | Plasticity Index | | Note |
| | | Max | Min | |
| 132 | EMBANKMENT (FINAL) (XX) (TY C1) | 40 | 8 | 1 |
| 132 | EMBANKMENT (FINAL) (XX) (TY C2) | 25 | 8 | 2 |

Note 1: Material excavated from the project must meet the PI requirements when used in the top 10 feet of embankment that supports the pavement structure or other locations shown in the plans. Do not use shale and obtain approval to incorporate shaley clay produced by the construction project.

Note 2: Use as a non-select embankment backfill as defined under Item 423.2.4.1. Use as an embankment to backfill behind abutments to the extent of the approach slab or to backfill areas enclosed by an abutment and / or retaining walls or other locations as shown in the plans.

| Table 2: Basis of Estimate for Permanent Construction | | | | | |
|---|--|-----------|--------------------|------------|------------|
| Item | Description | Thickness | Rate | | Quantity |
| 162 | Block Sod | N/A | See Specifications | | 52,633 SY |
| 164 | Drill Seed (Perm) (R) (C/S) | N/A | See Specifications | | 51,343 SY |
| 166 * | Fertilizer (12-6-6) | N/A | 500 | Lbs./Ac | 5.37 Ton |
| 168 | Vegetative Watering (Warm)** | N/A | 12 | MG/Ac/Day | 15,474 MG |
| 260 | Hydrated Lime (slurry) | | | 4% by wt. | 1,898 Ton |
| 260 | Commercial Lime Slurry | | | | |
| 260 | Quick Lime (slurry) | | | | |
| 3077 | SP MIXESSP-BPG64-22 | See Plans | 110 | Lbs./SY/In | 35,264 Ton |
| | SP MIXESSP-CPG64-22 | See Plans | 110 | Lbs./SY/In | 4,466 Ton |
| 3077 | Tack Coat (Undiluted Application Rate) | | 0.12 | Gal/SY | 963 Gal |

General Notes

Sheet A

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

*For contractor's information only
 **Use Summer rate for calculation, adjust for actual field conditions/temperatures as necessary. See Vegetation Establishment Plan Sheet for estimated daily rates.
 ***Portland Concrete Cement

Note: (1) Base material weight based on 1.50 Ton/CY (dry- compacted)
 (2) Asphalt weight based on 110 Lbs./SY/In
 (3) Subgrade weight based on 1.35 Ton/CY (dry-compacted)

| Table 3: Basis of Estimate for Temporary Erosion Control Items | | | | |
|--|-------------------------------------|--------------------|-----------|-----------|
| Item | Description | Rate | | Quantity |
| 164 | Drill Seeding (Temp) (Warm or Cool) | See Specifications | | 51,343 SY |
| 166* | Fertilizer (12-6-6) | 500 | Lb/Ac | 2.65 Ton |
| 168 | Vegetative Watering (Warm)** | 12 | MG/Ac/Day | 7,631 MG |

*For Contractor's Information Only.
 **Use Summer rate for calculation, adjust for Actual Field Conditions/Temperatures as Necessary. See Vegetation Establishment Sheet for estimated daily rates.

GENERAL

The construction, operation and maintenance of the proposed project will be consistent with the state implementation plan as prepared by the Texas Commission on Environmental Quality.

The disturbed area for this project, as shown on the plans is 63.08 acres. However, the Total Disturbed Area (TDA) will establish the required authorization for storm water discharges. The TDA of this project will be determined by the sum of the disturbed area in all project locations in the contract, and all disturbed area on all Project-Specific Locations (PSL) located in the project limits and/or within 1 mile of the project limits. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction site as shown on the plans, according to the TDA of the project. The contractor will obtain any required authorization from the TCEQ for the discharge of storm water from any PSL for construction support activities on or off of the project row according to the TDA of the project. When the TDA for the project exceeds 1 acre, provide a copy of the appropriate application of permit (NOI, or Construction Site Notice) to the engineer, for any PSL located in the project limits or within 1 mile of the project limits. Follow the directives and adhere to all requirements set forth in the TCEQ, Texas Pollution Discharge Elimination System, Construction General Permit (TPDES, CGP).

This project required permits with environmental resources agencies as outlined in the plan set Environmental Permits, Issues and Commitments (EPIC) Sheet. There is a high probability that an environmentally sensitive area could be encountered on the contractor designated Project-Specific Locations (PSL) for this project (haul roads, equipment staging areas, borrow pits,

General Notes

Sheet B

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

disposal sites, field offices, storage areas, parking areas, etc.). Item 7.6 "Project-Specific Locations", provides a listing of regulatory agencies that may need to be contacted regarding this project.

Leave all right of way areas undisturbed until actual construction is to be performed in said areas.

Contractor questions on this project are to be addressed to the following individual(s):

Jennifer Vorster Jennifer.Vorster@txdot.gov
Gerald Waltman Gerald.Waltman@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individuals.

All contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following Address:
<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Paper copies of cross-sections may be produced by using the provided .pdf file located on the above FTP Website at the bidders' expense and at copying companies. This data is for non-construction purposes only and it is the responsibility of the prospective bidder to validate the enclosed data with appropriate plans, specifications and estimate for the project(s).

The following standard detail sheets have been modified:
TS-FD-12(MOD)

Item 2:

This project will use A+B bidding.

Item 5:

Place survey monuments, provided by the department, at points indicated and as detailed in the plans or as directed. Furnish surface coordinates and the elevation of the set monument and an azimuth from the monument to some prominent physical feature, preferably another survey monument on the project. This work will not be paid for directly, but will be considered subsidiary to the various bid items.

Underground utilities owned by the Texas Department of Transportation may be present within the Right-Of-Way on this project. For signal, illumination, surveillance, and communications & control maintained by TxDOT, call the TxDOT Traffic Signal Office (214-320-6682) for locates a minimum of 48 hours in advance of excavation. For irrigation systems, call TxDOT Landscape Office (214-320-6205) for locates a minimum of 48 hours in advance of excavation. If city or town owned irrigation facilities are present, call the appropriate department of the local city or town a

General Notes

Sheet C

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

minimum of 48 hours in advance of excavation. The Contractor is liable for all damages when utilities are damaged due to Contractor's negligence including, but not limited to, repair or replacement at the Contractor's expense.

For the project to be deemed complete, permanently stabilize all unpaved disturbed areas of the project with a vegetative cover at a minimum of 70% density for the control of erosion.

Place construction stakes/station markings at intervals of no more than 100 feet or as directed by the Engineer. Place stakes and markings so as not to interfere with normal construction operations.

ITEM 6: CONTROL OF MATERIALS

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Buy America material classification sheet

The Buy America material classification sheet categorizes materials as iron and steel, construction material, or manufactured product on a per item basis.

Item 7:

Repair or replace any structures and utilities that might have been damaged by negligence or a failure to have utility locates performed.

Perform all electrical work in accordance with the National Electrical Code and Texas Department of Transportation Specifications.

Consult with appropriate electric company representatives according to their respective area to coordinate electrical services installations.

Holiday restrictions – The Engineer may decide that no lane closures or construction operations shall be allowed during the restricted periods listed in the following holiday schedule. TxDOT has the right to lengthen, shorten, or otherwise modify these restricted periods as actual, or expected, traffic conditions may warrant. Working days will not be charged for these restricted periods. No additional compensation will be allowed for these closures (i.e., overhead, delays, stand-by, barricades or any other associated cost impacts).

General Notes

Sheet D

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

- New Year's Eve and Day (5 am on December 31 thru 10:00 pm January 1)
- Easter Holiday weekend (5 am on Friday thru 10:00 pm Sunday)
- Memorial Day weekend (5 am on Friday thru 10:00pm Monday)
- Independence Day (5 am on July 3 thru 10:00 pm on July 5)
- Labor Day weekend (5 am on Friday thru 10:00 pm Monday)
- Thanksgiving Holiday (5 am on Wednesday thru 10:00 pm Sunday)
- Christmas Holiday (5 am on December 23 thru 10:00 pm December 26)

No significant traffic generator events identified.

Item 8:

This Project will be a Six-Day Workweek in accordance with Article 8.3.1.2.

Critical Path Method (CPM) schedule in P6 format will be required for this project. Submit baseline schedule and obtain approval prior to beginning construction. The Estimate will be held if monthly schedule update is not submitted.

The minimum number of working days allowable for bid (B part) is 624.

The maximum number of working days is 780 days was calculated using a conceptual time determination schedule that assumed generic resources, production rates, sequence of construction and average weather conditions. The time determination schedule is provided for informational use only and is not intended for bidding or construction purposes.

Substantial completion of the contract is defined as the point in time at which the roadway and the cross streets are in their final geometric configuration and traffic is following the lane arrangement as shown in the plans for the finished roadway. All pavement construction is complete with traffic control devices and pavement markings in their final position.

The daily road-user cost incentive/disincentive for substantial completion of the project is \$5,000 per day. The road user cost disincentive shall be limited to a maximum of 365 working days of damages charged to the contractor. The early substantial completion of work incentive shall be limited to a maximum of 120 calendar days. The road-user cost disincentive deductions will be in addition to any contract administration liquidated damages. The number of days for final completion, excluding vegetation and landscaping maintenance, will be 28 calendar days after the substantial completion of the project.

Item 100:

Remove the existing roadway small signs, delineators and object markers as shown on the plans, or as directed, during construction within the right of way. Small sign, delineator and object marker removals are subsidiary to this Item.

General Notes

Sheet E

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

The limits of preparing right of way will be measured from Sta. 118+82.75 to Sta. 286+00.00 along the centerline of construction.

Item 104:

In those areas where the pavement is not to be overlaid, provide a smooth surface after the curb removal. Planing or grinding is considered an acceptable method at these locations. Measurement and payment is in accordance with this item.

Sawing of concrete is not paid for directly, but is considered subsidiary to this item.

Items 105:

Saw existing asphalt along neat lines where portions are to be left in place temporarily or permanently. Sawing is not paid for directly, but is subsidiary to this item.

Take possession of recycled asphalt pavement from the project and recycle the material.

Properly dispose of unsalvageable material at your own expense.

Item 110:

Excavated shale is not an acceptable material for embankment.

Items 110 and 132:

Scarify and loosen the excavated areas, unpaved surface areas, except rock, to a depth of at least 8 inches and compact in accordance with the specifications.

Excavation and embankment for driveways, sleeper slabs, alleys and intersections will not be paid for directly, but will be considered subsidiary to these items.

Item 132:

Excavated material from the project site has not been determined to be suitable for embankment. The bidder assumes all risk for the use of excavated materials for embankment and is expected to meet all material requirements for embankment regardless of the source.

Perform Tex-106-E (Plasticity Index) by an approved laboratory on excavated soils from sources outside right of way when used in roadway embankment. Provide the test results at no expense to the department. The engineer will sample and test soils produced by the construction project for specification requirements or material sources specified in the plans.

Earth embankment Type C1 and C2, are mainly composed of material other than shale. Furnish material that is free from vegetation or other objectionable material and that conforms to the requirements of Table 1 (Sheet A). If necessary, treat material with lime slurry in accordance with Item 260, "Lime Treatment (Road-Mixed)" in order to meet these requirements. Use Tex-121-E, figure 1, page 4 to calculate the amount of lime required. When lime treated subgrade is specified, 3000 PPM is the maximum allowed sulfate content in the top 3 feet when material comes from borrow source. Follow recommendations of 260.4.4 for mixing and mellowing. The engineer will test material placed or excavated to a depth of one foot below and

General Notes

Sheet F

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

laterally to one foot outside the proposed treatment limit. Lime treatment of this material will not be paid for directly, but will be considered subsidiary to this item.

Do not use shaley clays in embankment unless approved in writing.

Use embankment material Type C2 described in Table 1 "Soil Constants Requirements" for embankments behind bridge abutments to the extent of the bridge approach slabs, and other embankments enclosed by an abutment and / or retaining walls.

Item 160:

Sequence construction operations to salvage topsoil from one location and spread on areas ready to receive topsoil. Keep stockpiling of topsoil to a minimum.

Use fertile clay or loam from the project site not more than six inches below natural grade as topsoil.

Item 161:

Provide tickets representing quantity of compost delivered to site.

Item 260:

Furnish and distribute MS-2 smoothly and evenly at the rate of 0.20 gallons per square yard to cure lime, as directed.

Provide Commercial Lime Slurry, Hydrated Lime, or Quicklime and apply lime by slurry placement method.

Item 301:

Provide liquid antistripping agents unless otherwise directed. Add the minimum dosage determined by the manufacturer or higher dosage determined by design requirement and try subsequent trials at 0.25% increments.

Item 320:

The use of windrow pick-up equipment is allowed except on the first course of roadway material placed over the subgrade.

Item 360:

Use of multiple piece tiebars will be required. Provide chairs for multiple piece tiebars, threaded connectors or other adequate devices, used in concrete paving, or tie them to the pavement reinforcing steel. If approved by the engineer for specific areas, in lieu of multiple piece tiebars, drill holes into the pavement and grout straight tiebars in place with epoxy. Use a non-impact, rotary core drill to prevent damage to the pavement unless otherwise directed. Clean the drill holes and then completely fill with epoxy before inserting the tiebar. Do not bend the tiebars or insert them into plastic concrete without the approval of the engineer.

Provide curbs monolithically constructed with the concrete pavement. If continuous monolithic curb has to be temporarily omitted for any reason, provide dowelled curbs in the proposed areas, as detailed in the plans, and apply an approved epoxy resin to the pavement to receive

General Notes

Sheet G

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

the curb as directed. This work and materials will not be paid for directly, but is considered subsidiary to this item.

If asphalt curing is used, cure the concrete pavement with MS-2.

Stockpile the concrete aggregates at the plant site.

Provide pavement widening joints, as detailed in the plans, at all locations where concrete pavement is placed adjacent to existing concrete pavement. Installation of these joints is not paid for directly, but is considered subsidiary to this item.

Payment for furnishing and installing the pre-molded expansion joint material between the retaining walls and concrete pavement is not paid for directly, but is considered subsidiary to this item.

Provide a curing machine equipped with rubber tires, or other acceptable arrangement, so that the machine will span the pavement and monolithic curb.

Curb transition is paid for as Type II curb.

The installation of curb openings is not paid for directly, but is considered subsidiary to this item.

Place construction, sawed and contraction joints in accordance with the pavement detail sheet and as directed. Joint locations, other than as shown on the plans, are subject to approval.

Pavement leave outs are required on this project as necessary to provide for traffic at driveways and side streets as shown in the plans or as directed. The cost of providing these leaveouts, including the construction of a suitable crossover connection at each site, is not paid for directly but is considered subsidiary to this item.

If a traveling form paver is used, provide one equipped with an electronically operated horizontal control device.

Use "mechanical steel placing equipment" at the discretion of the engineer.

Provide Class HES concrete at the locations shown on the plans. Design Class HES to meet the requirements of Class P and a minimum average flexural strength of 450 psi or minimum average compressive strength of 3200 psi in 24 hr.

Supply the Engineer with a list of certified personnel and copies of their current ACI certificates before beginning production and when personnel changes are made. Supply hard copies of calibration reports for testing equipment when required by the Engineer.

If more than 30% of an area in any 1000-Ft section of roadway requires grinding, action will be taken by the Contractor to make that 1000-Ft full width section uniform without changing ride quality, compromising quality of pavement and decreasing skid resistance. Approved blasting method or other method approved by the Engineer will be performed at the Contractor's expense.

General Notes

Sheet H

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Item 400:

Structural Excavation is not paid for directly but is considered subsidiary to pertinent Items.

When placing concrete storm drain pipe on slopes of greater than 10 percent, provide cement stabilized backfill to a depth shown on the plans.

Item 416:

Provide a minimum of one core per bent, regardless of placement method.

Drilled shafts shall be drilled and poured on the same day unless directed by the engineer.

Provide a formed smooth finish for all portions of drill shafts extending above proposed ground. Include cost for this work in the unit bid price for this item.

Traffic signal pole foundations will be paid for once regardless of extra work caused by obstructions.

Concrete removal required for installation of drilled shafts will be subsidiary to Item 416.

Item 421:

Furnish mix designs to the Engineer in a format compatible to the latest version of the Department's Construction Management System (SiteManager). Mix Design templates will be provided by the Engineer.

Provide sulfate resistant concrete for all drilled shafts.

Item 423:

For concrete block retaining walls, provide a system from one of the following approved suppliers:

The following Concrete Block Retaining Wall systems are approved for unrestricted use on TxDOT projects:

| Name | Manufacturer | Phone |
|-----------------------------|---|----------------|
| Allan Block Retaining Walls | Jewell Concrete 400 Jewell Drive Waco, TX 76712 | (254) 772-3440 |

General Notes

Sheet I

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

| Name | Manufacturer | Phone |
|---|---|----------------|
| Anchor Wall System (Diamond Pro, Diamond Pro PS, Vertica) | Jewell Concrete Products, Inc 2561 Southwest Grapevine Parkway, #200 Grapevine, TX 75061 | (817) 235-2914 |
| Keystone Hardscapes (Compac III, Regal Stone Pro) | Pavestone Company P.O. Box 1868 Grapevine, TX 76051 | (817) 481-5802 |
| Mesa Retaining Wall System | Tensar International Corporation 2500 Northwinds Parkway, Suite 500 Alpharetta, GA 30009 | (770) 344-2090 |
| Redi-Rock Retaining Walls | Redi-Rock International, LLC 05481 US 31 S. Charlevoix, MI 49720 | (866) 222-8400 |
| Stone Strong Systems | Stone Strong, LLC 13460 Chandler Road, Suite 100 Omaha, NE 68138 | (877) 501-5652 |

Restricted Status (Phase One)

The following Concrete Block Retaining Wall systems are on restricted status*:

| Name | Manufacturer | Phone |
|--------------------|--|----------------|
| ReCon Wall Systems | ReCon Wall Systems, Inc. 7600 W. 27th St., #229 St. Louis Park, MN 55426 | (952) 922-0027 |

*Systems on restricted status have been reviewed and approved by TxDOT, but have not yet been approved for unrestricted status according to [DMS-4800](#). These systems are expected to perform acceptably and should be considered for use on projects.

General Notes

Sheet J

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Note: TxDOT policy does not allow the use of restricted systems on projects with:

- over 50,000 square feet of retaining wall,
- walls over 25 feet tall, or
- walls supporting or immediately adjacent to interstate highways.

Contact Us

TxDOT Bridge Division
(512) 416-2359

All retaining walls will have a uniform texture and appearance.

Unless otherwise noted in the plans, the top of the leveling pad is located 2 feet below the proposed ground.

Square foot surface area of retaining wall is measured from the top of retaining wall to the top of the leveling pad. Footing adjustments made to accommodate the available optional retaining walls are not measured.

Unless otherwise shown on the plans, provide Type AS backfill as defined under this item for permanent MSE or concrete block (CB) walls not subject to inundation. Unless otherwise shown on the plans, provide type DS backfill as defined under this item for permanent MSE or CB walls subject to inundation.

Supply drainage aggregate meeting the requirements of this item for use as filter material with the retaining wall.

Cement-Stabilized Backfill (CSB) is not permitted.

Unless otherwise noted on the plans, provide flowable backfill meeting the requirements of Item 401 between the back of panels and inlets or drainage pipes where the required compaction can not be achieved. Flowable backfill used for this purpose is subsidiary to this item.

Provide earth reinforcements with a minimum length of 8' or longer as required by RW(MSE)-DD. Earth reinforcement length is measured perpendicular to the wall. Adjust skewed earth reinforcements as necessary to obtain required length.

Submit design calculations supporting the details necessary to incorporate coping, railing, inlets, drainage, electrical conduits and any additional necessary features.

The contractor has the option of constructing any of the types of retaining walls for which details and specifications are included in the plans. Footing adjustments made to accommodate the available optional retaining walls are not measured. Regardless of option or options chosen, use the same fascia pattern throughout the entire project, including cast in place full height retaining walls or retaining wall type abutments.

General Notes

Sheet K

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Submit detailed drawings depicting the patterns and matching of precast with cast-in-place for approval.

Unless otherwise shown on the plans, form the map of Texas emblem into a wall panel next to each bridge abutment. Engineer approval of the exact location of each emblem is required. The cost of forming emblems is considered subsidiary to this item. Inset the map of Texas a minimum of 3/4 inch into the face of the panel, and provide a smooth finish with an engineer approved contrasting color.

At contractor's expense, repair all damage to the precast units (such as chips) as required to match the fascia pattern.

Use Embankment Type C2 as non-select embankment backfill as defined under Item 423.2.4.1. For non-select embankment fill behind retaining walls provide and install fill in accordance with Item 132, Type C2.

For cut walls, the backfill between the select fill zone and the existing ground shall be either select material as required for the select fill zone or backfill meeting or exceeding the requirements of Item 132, type C2. Place material in accordance with Item 132, Type C2 requirements. If existing ground is laid back (i.e. not vertical), the lay back shall be done as a series of equal height benches so as to prevent the formation of a smooth surface at the material interface.

Avoid distinct vertical joints between select backfill and embankment (Non-Select) backfill as required by Section 423.3.4. This may be conveniently done by providing a zone of material behind the strap zone (1' min width) in which alternating lifts of select and non-select materials are interlaced.

Items 440:

Fiber Reinforced Concrete (FRC) can be used as a substitute for Non-Structural Class Reinforced Concrete in Mow-Strip and Rip Rap Items as approved. FRC may also be used for other Non-Structural Class Reinforced Concrete Items as approved.

Item 449:

Use Thomas & Betts Kopr-Shield, MG Chemicals #846, MG Chemicals #8463, NYOGEL #756G, Pro-Shield #7308, Cho-Lube #4220, or other approved electrically conducting lubricant compound.

Item 464:

The concrete collars and the connections of pipes to existing or proposed concrete boxes or pipe will not be paid for directly but will be considered subsidiary to the various bid items.

At locations where storm drains dead-end, plug with a concrete plug of a thickness equal to 1 1/2 inches per foot of diameter of pipe with a minimum thickness of 3 inches. The cost of the plugs shall be included in the unit price bid per foot of the various storm drain pipes.

Item 465:

All manholes, junction boxes and inlets will require inverts unless otherwise directed.

General Notes

Sheet L

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Item 496:

Concrete pavement removed as a result of removing the inlets will not be paid for directly but will be considered as subsidiary to Item 496.

Inlet grates and manhole covers become the property of the contractor for disposal.

Item 500:

Material On Hand (MOH) will not be used in calculating partial payments for Mobilization.

Item 502:

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Access will be provided to all business and residences at all times. Where turning radii are limited during phased construction at intersections, provide all weather surfaces such as RAP or base in turning movements to accommodate and to protect the traffic from edge drop-offs. Materials, labor, maintenance and removal for these temporary accesses and radii will not be paid for directly but will be considered subsidiary to the various bid items.

Provide written proposed lane closure information by 1:00 pm on the business day prior to the proposed closures. Do not close lanes when this requirement is not met.

When excavation is required next to a pavement lane carrying traffic and the widening is not completed by the end of the work day, backfill against the edge of the pavement with at least a 3:1 slope using an acceptable material to support vehicular traffic. Carefully remove and dispose of this material when work resumes. Backfilling pavement edges, and the materials required for the work will be subsidiary to this item.

Place barricades and signs in locations that do not obstruct the sight distance of drivers entering the highway from driveways or side streets.

Provide rectangular shape (CW12-2P) Temporary Clearance Signs on all bridges where the existing vertical clearance has changed. Install Signs to the satisfaction of the Engineer prior to opening to traffic. Plywood sign blanks will have minimum dimensions of 84" X 12". Work performed and materials are subsidiary to this item.

Do not commence work on the road before sunrise. Do not operate or park any equipment/machinery closer than 30 feet from the traveled roadway after sunset unless authorized by the engineer.

When moving unlicensed equipment on or across any pavement or public highways, protect the pavement from all damage using an acceptable method.

General Notes

Sheet M

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

As approved by the Engineer, provide uniformed off duty police officers and squad cars during lane or ramp closures, night time work or other situations that indicate a need for additional traffic control to protect the traveling public or the construction workforce. Provide documentation such as payroll, log sheets with signatures and badge number, or invoices from the government entity providing the officers for reimbursement. Complete the weekly tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Reimbursement will not be made for coordination fees charged by any party.

Limit lane closures along SH 5 to the hours between 9:00 am and 3:30 pm. Work in other areas of the project is not restricted to this time frame.

Traffic Control Plans with Lane Closures causing backups of 20 minutes or greater in duration will be modified by the Engineer up to and including removal of the lane closure and adjustment of lane closure times.

Work in other areas of the project is not restricted to this time frame.

Additional lanes may be closed, started earlier, or extended later with written permission of the Engineer.

Item 506:

Take all practicable precautions to prevent debris from being discharged into the Waters of Texas or a designated wetland. Install Best Management Practices before demolition begins and maintain them during the demolition. Remove any debris or construction material that escapes containment devices and are discharged into the restricted areas, before the next rain event or within 24 hours of the discharge.

If temporary construction stream crossings are allowed under a Nationwide Permit, submit in writing for approval the type and location of each temporary stream crossing. Use temporary bridges, timber mats, or other structurally sound and non-eroding material for temporary stream crossings. A temporary culvert crossing will consist of storm sewer pipes and 4- to 8-inch nominal size rock. Temporary stream crossings must not cause more than minimal changes to the hydraulic flow characteristics of the stream, increase flooding, or cause more than minimal degradation of water quality. Remove the temporary stream crossings in their entirety and return the affected areas to their pre-existing elevation. All work and materials use for temporary construction stream crossings will not be paid for directly but are subsidiary to pertinent Items.

Provide SW3P Signs. Obtain from the Engineer a copy of the project's completed TPDES Storm Water Program Construction Site Notice and Contractor Site Notice. Laminate the sheets and bond with adhesive to 36" X 36" plywood sign blanks. Ensure the sheets remain dry. Apply Type C Blue reflective sheeting as the background and add the text "SW3P" in 5" white lettering, centered at the top. Attach the signs to approved temporary mounts and locate at each of the project limits just inside the right of way line at a readable height or as directed by the Engineer. If the sign cannot be placed outside the clear zone, it must adhere to the TMUTCD. SW3P

General Notes

Sheet N

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

signs, maintenance, and reposting (for replacement or as needed to ensure readability) will be subsidiary to Item 502.

Concrete Washouts are required per the CGP. The Concrete Washout Area(s) structural controls must consist of temporary berms, temporary shallow pits, and/or temporary storage tanks to prevent contaminated runoff and must be lined as to prevent contamination of underlying soil. Ensure pits properly maintained including removal of concrete as not to allow over flow. The location(s) of washout area will be approved by the Engineer. When washout pits are no longer needed, they will be removed and area will be restored to original condition. This work, materials and labor will not be measured or paid for directly but will be subsidiary to Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls."

Item 508:

Testing of materials used in the construction of a temporary detour may be waived when approved by the Engineer.

Item 529:

Provide grooved joints at 10-foot intervals and 3/4 inch expansion joint material for doweled curb at the same locations as on the existing pavement.

For Curb and Gutter sections, provide grooved joints at 10-foot intervals and 3/4 inch expansion joint material at a maximum of 50-foot centers and at all radius points and inlets.

Curb and Gutter transitions will be paid for by the foot at the unit price for the corresponding curb or curb and gutter section.

Saw joints at the same location as on the existing pavement.

Item 531:

Joint sealant is required when shown in the plans. This work will not be paid for directly but will be considered subsidiary to this Item.

Item 556:

The unit price bid per linear foot of "pipe underdrain" shall include the cost of making connections to storm sewer lines.

Place bell and spigot type pipe with an open joint of approximately 3/4 inch.

In the event that Type 5 Underdrain Pipe is bid, make the connection as shown in the plans. The cost of making the connection will be considered subsidiary to this item.

The requirements for decantation of filter material are deleted for this project.

Item 585:

Use Surface Test Type A on all intersections and driveways.

Use Surface Test Type B pay adjustment schedule 2 on the travel lanes.

General Notes

Sheet O

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Item 618:

Place conduit under railroad tracks to maintain a minimum of 42" below the bottom of the ties.

The location of conduits and ground boxes are diagrammatic only and may be shifted to accommodate field conditions as directed.

Secure permission and approval from the proper authority prior to cutting into or removing any sidewalks or curbs for installation of this Item.

When holes are drilled through concrete structures, use a coring device. Do not use masonry or concrete drills.

Place conduit under existing pavement by an approved boring method. Do not place boring pits closer than 2 feet from the edge of the pavement unless otherwise directed. Do not use water jetting. When conduits are bored, do not exceed 18 inches in the vertical and horizontal tolerances as measured from the intended target point.

Do not use a pneumatically driven device for punching holes beneath the pavement (commonly known as a "missile").

Furnish and install a flat, high tensile strength polyester fiber pull tape in conduit runs in excess of 50 feet or for future use and protected with standard weather-tight conduit caps, as approved. Acceptable products include Garvin # PT-1250-3K, ComStar PUL 1250P3K, Ideal Part No. 31-315 or equal as approved by the Engineer. This work will not be paid for directly, but is subsidiary to this Item.

Use a colored cleaner-primer on all PVC to PVC joints before application of PVC cement.

Seal all conduit ends with a permanently soft, non-toxic duct seal. Use a duct seal that does not adversely affect other plastic materials or corrode metals.

Where sidewalk is removed to install trenched conduit, replace sidewalk to match existing material. This work will be subsidiary to Item 618 except where shown otherwise in the plans.

2" Schedule 80 PVC will be used at the power pole to supply electricity to underground services.

Item 620:

The equipment grounding conductor shall be identified by a continuous green colored jacket insulation or bare wire. Grounded conductors (Neutral) shall be identified by a continuous white colored jacket. Ungrounded conductors (Hot) in a 120/240v system shall be identified by each pole or leg. For 240-volt branch circuit fed from 120/240 source, ensure one leg is identified by a continuous black colored jacket and the other leg by a continuous red colored jacket.

Item 624:

Slack conductors required by Standard Sheet ED(3)-14 will be subsidiary to Item 624.

General Notes

Sheet P

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Concrete removal required for installation of ground boxes will be subsidiary to Item 624.

Item 627:

Use the timber pole heights, as shown on the plans and in the material summary, for bidding purposes only. Coordinate pole locations, and make field measurements before construction to ensure a vertical clearance of 17 to 19 feet from the highest point on the roadway surface to the span. Except for supplemental nearside signal heads, all signal heads must be installed at least 40' from the stop line. If field adjustments result in the nearest signal head being more than 180' from the stop line, install a supplemental nearside signal head as directed by the engineer. Determine the field measurements and elevations from the actual field location of the poles, considering all above and below ground utilities and existing roadway elevations.

Item 628:

Contact the appropriate utility company during the first three weeks of the project lead-time period to allow adequate time for any necessary utility adjustments, transformer installation, etc.

For new Oncor supplied electrical services the Contractor shall submit an online request at ONCOR.com by following the steps below:

Select Construction and Development tab at top of screen.

Scroll down to New Construction and select Learn More.

Select the Start Request icon under the Commercial and Industrial project type.

Select the One Single Building Facility tab and fill in all required information.

Submit the request. An ONCOR representative will contact you within a few days.

The Meter Base shall be mounted facing the roadway and the service enclosure shall be mounted on the opposite side of the service pole or pedestal.

The Contractor shall obtain the street address of the new electrical service directly from the applicable City.

Label the service enclosures indicating service address as well as all required information as shown on the Electrical Detail (ED) standard sheets. Labeling shall be silk screening or other acceptable method. This work will not be paid for directly, but is subsidiary to this Item.

A Licensed Master Electrician shall oversee the installation of all electrical services.

Bill the electrical service power usage to the Texas Department of Transportation.

On the outside lower front of each electrical service meter base cover, install a 12 gauge minimum thickness stainless steel, aluminum or brass placard. The placard shall be engraved or stamped with the numeric portion of the street address and permanently affixed to the cover with exterior rated adhesive so as not to interfere with the operation of the latch. This work will not be paid for directly, but is subsidiary to this Item.

General Notes

Sheet Q

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Items 644:

Provide two (2) sets of shop drawings for signs. The shop drawings shall conform to the details shown on the plans. The shop drawings shall show the details of the panels, wind beams, stiffeners, joint backing plates, splices, fasteners, brackets, and sign support connections. The shop drawings shall show letter types and sizes, interline spacing and message arrangements.

Affix a sign identification decal to the back of all signs in accordance with Item 643.

Prior to taking elevations to determine lengths for fabrication of sign posts and/or sign support towers, obtain verification of all proposed locations.

All sign mounts shall have a clamp base system for all small roadside sign assemblies.

Item 662 and 672:

Black adhesive will be used on asphalt pavements and white adhesive will be used on concrete pavements.

Item 677:

A water blasting method approved by the Engineer will be the only method allowed for the removal of permanent and temporary pavement markings except on a sealcoat surface. A 2 foot wide sealcoat will be required on sealcoat surfaces to eliminate permanent and temporary pavement markings.

Item 680:

Requirements for this Item include the following work, all of which are subsidiary to this Item:

1. Notify the Traffic Projects Office at DAL_TPO@txdot.gov one week before beginning any work involving traffic signals. Supplement email correspondence with the District Signal Maintenance Office at (214)320-6682 and Construction Office at (214)319-6406.
2. Provide submittal literature for all traffic signal equipment before installation.
3. Furnish and install a new controller (eight phase NEMA TS 2 Type 1) and cabinet (NEMA TS 2 Size 6, 16 position load bay), meeting the requirements of Departmental Materials Specifications DMS-11170. Provide detector panel toggle switches that additionally permit the user to disconnect the detector. Provide new MMU with Ethernet port.
4. Deliver the cabinet, controller, and accessories (with all cabinet components completely connected and securely strapped down) to the District Signal Shop, 4777 E Hwy 80, Mesquite, for testing. Notify the District Signal Shop two working days before delivery at (214)320-6682.
5. Install the controller cabinet in an orientation as directed.
6. Connect all field wiring to the controller assembly. The District will assist in determining how the detection cables are to be connected, and will also program the controller for operation, hook up the malfunction management unit (MMU) or conflict monitor, detector units, and other equipment, and turn on the controller. Pick up the signal cabinet from the District Signal Shop.

General Notes

Sheet R

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

- Have a qualified technician and a representative from the controller supplier on the project site to place the traffic signals in operation.
7. Furnish and install all sign panels for mounting on signal poles, mast arms, and span wires. Fabricate the sign panels in accordance with Item 636, and mount with Astro-Sign Brac, Signfix aluminum channel, or equal as approved by the Engineer. Submit five (5) sets of shop drawings for street name signs. Install the sign panels supplied for mounting on signal poles, mast arms, and span wires. Furnish and install all other signs in accordance to Item 636. Furnish all mounting hardware for all signs. Mount signs with Astro-Sign Brac, Signfix aluminum channel, or equal as approved by the Engineer.
 8. Provide 250W Equivalent LED Fixtures with 240 volt electronic LED drivers as shown on the Material Producers List.
 9. Remove the existing stop sign panels (or assemblies) after the traffic signals are in operation.
 10. Install the emergency vehicle preemption equipment supplied by the City of Melissa and the City of Anna.
 11. Have a qualified technician on the project site to place the traffic signal in operation.
 12. Use qualified personnel to respond to and diagnose all trouble calls during the thirty-day test period. Repair any malfunction to Contractor-supplied signal equipment. Provide to the Engineer a local telephone number, not subject to frequent changes and available on a 24-hour basis, for reporting trouble calls. Response time to reported calls must be less than 2 hours. Make appropriate repairs within 24 hours. Place a logbook in the controller cabinet and keep a record of each trouble call reported. Notify the Engineer of each trouble call. Do not clear the error log in the conflict monitor or MMU during the thirty-day test period without approval.
 13. Furnish a spare controller (eight-phase NEMA TS 2 Type 1) and base-mount (or pole-mount) cabinet (NEMA TS 2 Size 6, 16 position load bay), meeting the requirements of Departmental Materials Specifications DMS-11170. Provide detector panel toggle switches that additionally permit the user to disconnect the detector. Provide new MMU with Ethernet port. Provide three mounting brackets for a pole-mount controller cabinet.
 14. When the work required by this contract has been satisfactorily completed on any individual or inter-connected system of signalized intersections, final clean-up has been performed, and the traffic signal equipment supplied has operated continuously and satisfactorily for at least 30 days, release from further maintenance on that particular intersection is authorized. This partial acceptance, made in writing, does not void or alter any of the terms of the contract.
 15. Prevent any damage to property owner's poles, fences, shrubs, mailboxes, etc. Protect all underground and overhead utilities and repair any damage. Provide access to all driveways during construction.
 16. Integrate the proposed traffic signal(s) into the existing closed loop system as shown on the plans. –CENTRACS closed loop software, which utilizes Econolite Cobalt controllers, is currently in use in the Dallas District. Provide controllers on this project that fully communicate with the existing closed loop system.
 17. The concrete foundation for the controller as shown on standard TS-CF is diagrammatic and the dimensions will be adjusted in the field to fit existing conditions.
 18. A 3 inch strip of red prismatic conformable sheeting shall be placed on all Do Not Enter sign assemblies. This sheeting shall be placed directly below the Do Not Enter sign for the entire length of the sign post facing wrong way traffic.
 19. Salvage the existing traffic signals at SH 5 & FANNIN RD, SH 5 & HIGHLAND RD/PENNSYLVANIA AVE, SH 5 AT THROCKMORTON RD, AND SH 5 & COLLIN COUNTY

General Notes

Sheet S

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

- OUTER LOOP, etc. as shown on the plans. Salvage poles, cabinets, service poles and equipment, exposed conduit, and any other equipment as directed. This equipment remains the property of the Texas Department of Transportation. The material listed above is to be stockpiled at the TxDOT District Signal Shop, 4777 E Hwy 80, Building N, Mesquite, TX 75150, as directed. Contact the District Signal Shop at 214-320-6682 48 hours in advance of delivery. All other material removed in this project will become the property of the Contractor. Dispose of material off the right of way in accordance with federal, state, and local regulations. Maintain the operation of the existing traffic signal until directed to remove it.
20. Completely remove timber poles not set in concrete without cutting off the pole. Timber poles set in concrete are considered unsalvageable.

Item 681:

Requirements for this Item include the following work, all of which are subsidiary to this Item:

1. Re-guy signal heads and re-strap the cable after making adjustments to head locations. Accomplish relocation of signal heads for a phase change during the same day.
2. Bottom tether cable for signal heads and signs will be required.
3. Provide submittal literature for all traffic signal equipment before installation.
4. Furnish and install a controller (eight phase NEMA TS 2 Type 1) and cabinet (NEMA TS 2 Size 6, 16 position load bay), meeting the requirements of Departmental Materials Specifications DMS-11170. Provide detector panel toggle switches that additionally permit the user to disconnect the detector. Provide MMU with Ethernet port. Provide a pole-mounted cabinet that has three brackets for pole mounting and install a 5' x 5' x 4" Class A concrete pad under the cabinet in accordance to Items 420 and 421. .
5. Operate and maintain the temporary signal. Provide a telephone number to the District for trouble calls. Check the signal equipment at least monthly, and within 24 hours in response to complaints, and immediately repair or replace any malfunctioning Contractor-supplied equipment. Notify the Department immediately upon finding malfunctioning Department-supplied equipment or a problem with the signal timing. If the controller is supplied by the Contractor, provide a reliable technical support person and phone number for the manufacturer of the controller. If the vehicle detection is Department-supplied, notify the TxDOT Dallas District Signal Shop one week prior to traffic switches to reprogram and re-aim the detectors.
6. CENTRACS closed loop software, which utilizes Econolite Cobalt controllers, is currently in use in the Dallas District. Provide controllers on this project that fully communicate with the existing closed loop system.
7. Relocate existing emergency vehicle preemption equipment to temporary signals.
8. Install pole-mounted BBU on the opposite side of the pole from the controller cabinet.

Item 682:

Install signal head attachments so that the wiring to each signal head passes from the mast arm through the attachment hardware to the signal head. Do not leave cable or wiring exposed.

Provide signal head attachments that allow for adjustment about the horizontal and vertical axis.

General Notes

Sheet T

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

Provide aluminum pedestrian and vehicle signal heads in the following color: Federal Yellow #13538 of Federal Standard 595. Provide non-painted aluminum tubing. Provide back plates, louvers, and the inside of visors with a flat black finish. Provide aluminum vented back plates for all traffic signal heads.

Turn down signal heads or cover with burlap or other material, as approved, until traffic signal is placed in operation.

Mount signal heads level and plumb and aim as directed.

Item 684:

Provide stranded 14 AWG Type A signal cables for LED signal heads and stranded 12 AWG Type C cables for APS units.

Provide a separate multi-conductor signal cable (14 AWG) inside pedestal poles and signal poles from the terminal strip to each signal head as shown on the plans.

Identify each cable as shown on the plans (cable 1, etc.) with permanent marking labels (Panduit Type PLM standard single marker tie, Thomas&Betts Type 548M, or equal) at each ground box, pole base, and controller.

Item 686:

Provide 12 circuit Buchanan Type 112SN, Kulka Type 985-GP-12 CU, or equal terminal strips in the signal pole access compartment. Provide additional terminal strips of 8 circuits each when more than 12 circuits are required. The conductors for the line and load side of the terminal strip shall be identified with a plastic label with two straps per tag. The load side shall have each signal head and ped head identified on the tag.

Mark pole shafts and mast arms with the identification numbers from the plans to facilitate field-assembly. Identify pole shafts and mast arms by intersection for projects with multiple intersections.

Provide nuts on top and bottom (double nuts) of the base plate as shown on the plans.

Set anchor bolts for mast arm signal poles and strain poles so that two are in tension and two are in compression. Obtain approval of anchor bolt placement before placing concrete.

Provide vertical clearance of 17 to 19 feet from the roadway to the lowest point of the signal head or mast arm. Except for supplemental nearside signal heads, all signal heads must be installed at least 40' from the stop line. If field adjustments result in the nearest signal head being more than 180' from the stop line, install a supplemental nearside signal head as directed by the engineer. Determine the field measurements and elevations from the actual field location of the poles, considering all above and below ground utilities and existing roadway elevations.

Provide vibration dampers for mast arms 28 feet to 48 feet in length. Install as shown on MA-DPD.

General Notes

Sheet U

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

For mast arm poles designated with an ILSN bid code, the ILSN arm, clamps, bolts, and washers will be considered part of the complete pole assembly. The ILSN signs and mounting hardware will be furnished by the applicable City.

Powder coating for signal poles will be considered subsidiary to this item and must meet the requirements of the City.

Item 687:

Powder coating for pedestal poles will be considered subsidiary to this item and must meet the requirements of the City.

Item 688:

Verify the location of the APS units and the direction of the arrows on the signs prior to installation.

Contractor shall provide a digital copy of the APS messages to TxDOT for all new APS Units on the project.

APS Units shall operate with hardwired connections for the communications path between the APS Units and the APS controller.

Item 730:

At the discretion of the Engineer, mow non-paved areas within the project prior to placement of permanent vegetation. Mow up to three (3) cycles per growing season.

Item 3077:

Use aggregate that meets the Surface Aggregate Classification (SAC) requirement of Class B.

Superpave Mixtures used as concrete pavement underlayment is deemed as "Exempt Production".

Provide PG binder 64-22 in Type SP-B & SP-C mixture.

Item 6058:

The BBU will be installed with the controller on the concrete pad paid for under Item 680. If a larger pad is needed to accommodate the BBU, the additional labor and material will be subsidiary to this item.

Item 6185:

The total number of truck mounted attenuators (TMAs) or trailer attenuators (TAs) required when utilizing the traffic control standards are shown in the tables below.

General Notes

Sheet V

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

| TCP 2 Series | Scenario | Required TMA/TA | |
|--------------|----------|-----------------|---|
| (2-1)-18 | All | 1 | |
| (2-3)-18 | A B | 1 | 2 |

| WZ (BTS) Series | Scenario | Required TMA/TA |
|-----------------|------------------------|-----------------|
| (BTS-1)-13 | Near Side Lane Closure | 1 |

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed for the project. Additional TMAs/TAs used that are not specified in the plans in which the contractor expects compensation will require prior approval from the Engineer.

Item 6292:

All additional items such as poles, conduit, cable, etc. required to achieve the detection specified in the plans will not be paid for separately, but will be considered subsidiary to this item.

The list of material below is for the Contractor's information only.
It is the responsibility of the Contractor to verify all items and quantities listed below.

LIST OF MATERIAL/LABOR
SUBSIDIARY TO ITEM 680

| DESCRIPTION | UNIT | QUANTITY |
|--|------|----------|
| 5/8" X 8' COPPERCLAD GROUND ROD W/CLAMP | EA | 5 |
| 250W EQ LED LUMINAIRE | EA | 19 |
| 8 PHASE NEMA CONTROLLER COMPLETE W/ CABINET AND ACCESSORIES | EA | 5 |
| TRAFFIC SIGNAL CONTROLLER BASE | EA | 5 |
| INSTALL OPTICOM EQUIPMENT (INTERSECTION) | LS | 5 |
| REGULATORY SIGN PANEL (R10-12,ETC) | EA | 26 |

General Notes

Sheet W

CSJ: 0047-04-031

County: COLLIN

Highway: SH 5

| | | |
|---|----|-----|
| INSTALL CITY SUPPLIED ILSN SIGNS | EA | 19 |
| REMOVE EXISTING STOP SIGN PANEL | EA | 2 |
| CONCRETE FOUNDATION (8' X 9' X 6", CLASS B) | CY | 6.5 |

LIST OF MATERIAL/LABOR
SUBSIDIARY TO ITEM 681

See summary of temporary traffic signal quantities.

General Notes

Sheet X



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|---|------|-------------|-------|-------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 100-6002 | PREPARING ROW | STA | 174.170 | | 174.170 | |
| | 104-6001 | REMOVING CONC (PAV) | SY | 40,458.000 | | 40,458.000 | |
| | 104-6011 | REMOVING CONC (MEDIANS) | SY | 34.000 | | 34.000 | |
| | 104-6013 | REMOVING CONC (FOUNDATIONS) | SY | 185.000 | | 185.000 | |
| | 104-6015 | REMOVING CONC (SIDEWALKS) | SY | 1,638.000 | | 1,638.000 | |
| | 104-6017 | REMOVING CONC (DRIVEWAYS) | SY | 2,801.000 | | 2,801.000 | |
| | 104-6021 | REMOVING CONC (CURB) | LF | 810.000 | | 810.000 | |
| | 104-6022 | REMOVING CONC (CURB AND GUTTER) | LF | 649.000 | | 649.000 | |
| | 104-6024 | REMOVING CONC (RETAINING WALLS) | SY | 13.000 | | 13.000 | |
| | 104-6036 | REMOVING CONC (SIDEWALK OR RAMP) | SY | 90.000 | | 90.000 | |
| | 105-6011 | REMOVING STAB BASE AND ASPH PAV (2"-6") | SY | 5,823.000 | | 5,823.000 | |
| | 105-6077 | REMOVING STAB BASE & ASPH PAV (8") | SY | 39,097.000 | | 39,097.000 | |
| | 105-6096 | REMOV STAB BASE AND ASPH PAV (0"-12") | SY | 58,166.000 | | 58,166.000 | |
| | 110-6001 | EXCAVATION (ROADWAY) | CY | 45,660.000 | | 45,660.000 | |
| | 132-6025 | EMBANKMENT (FINAL) (DENS CONT) (TY C1) | CY | 56,147.000 | | 56,147.000 | |
| | 132-6026 | EMBANKMENT (FINAL) (DENS CONT) (TY C2) | CY | 9.000 | | 9.000 | |
| | 161-6017 | COMPOST MANUF TOPSOIL (4") | SY | 103,976.000 | | 103,976.000 | |
| | 162-6002 | BLOCK SODDING | SY | 52,633.000 | | 52,633.000 | |
| | 164-6051 | DRILL SEED (TEMP)(WARM OR COOL) | SY | 51,343.000 | | 51,343.000 | |
| | 164-6066 | DRILL SEEDING (PERM)(WARM OR COOL) | SY | 51,343.000 | | 51,343.000 | |
| | 168-6001 | VEGETATIVE WATERING | MG | 23,105.000 | | 23,105.000 | |
| | 260-6012 | LIME(HYD,COM OR QK)(SLRY)OR QK(DRY) | TON | 1,898.000 | | 1,898.000 | |
| | 260-6027 | LIME TRT (EXST MATL)(8") | SY | 168,314.000 | | 168,314.000 | |
| | 360-6005 | CONC PVMT (CONT REINF - CRCP) (11") | SY | 143,623.000 | | 143,623.000 | |
| | 360-6058 | CONC PVMT (CONT REINF-CRCP) (HES) (11") | SY | 1,487.000 | | 1,487.000 | |
| | 402-6001 | TRENCH EXCAVATION PROTECTION | LF | 28,182.000 | | 28,182.000 | |
| | 416-6032 | DRILL SHAFT (TRF SIG POLE) (36 IN) | LF | 78.000 | | 78.000 | |
| | 416-6034 | DRILL SHAFT (TRF SIG POLE) (48 IN) | LF | 286.000 | | 286.000 | |
| | 423-6004 | RETAINING WALL (CONC BLOCK) | SF | 302.000 | | 302.000 | |
| | 432-6002 | RIPRAP (CONC)(5 IN) | CY | 154.000 | | 154.000 | |
| | 432-6044 | RIPRAP (CONC)(FLUME) | CY | 4.000 | | 4.000 | |
| | 450-6103 | RAIL (TY PR11) | LF | 3,114.000 | | 3,114.000 | |
| | 462-6001 | CONC BOX CULV (3 FT X 2 FT) | LF | 3,842.000 | | 3,842.000 | |
| | 462-6003 | CONC BOX CULV (4 FT X 2 FT) | LF | 1,275.000 | | 1,275.000 | |
| | 462-6004 | CONC BOX CULV (4 FT X 3 FT) | LF | 822.000 | | 822.000 | |
| | 462-6005 | CONC BOX CULV (4 FT X 4 FT) | LF | 415.000 | | 415.000 | |
| | 462-6006 | CONC BOX CULV (5 FT X 2 FT) | LF | 533.000 | | 533.000 | |

1 ADDENDUM #1 , 11/15/22 , REPLACE SHEET

| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16 |



CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

Estimate & Quantity Sheet

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|---|------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 462-6008 | CONC BOX CULV (5 FT X 4 FT) | LF | 436.000 | | 436.000 | |
| | 462-6010 | CONC BOX CULV (6 FT X 3 FT) | LF | 183.000 | | 183.000 | |
| | 462-6019 | CONC BOX CULV (8 FT X 4 FT) | LF | 132.000 | | 132.000 | |
| | 464-6003 | RC PIPE (CL III)(18 IN) | LF | 615.000 | | 615.000 | |
| | 464-6005 | RC PIPE (CL III)(24 IN) | LF | 16,755.000 | | 16,755.000 | |
| | 464-6007 | RC PIPE (CL III)(30 IN) | LF | 3,050.000 | | 3,050.000 | |
| | 464-6008 | RC PIPE (CL III)(36 IN) | LF | 1,237.000 | | 1,237.000 | |
| | 464-6009 | RC PIPE (CL III)(42 IN) | LF | 565.000 | | 565.000 | |
| | 464-6010 | RC PIPE (CL III)(48 IN) | LF | 191.000 | | 191.000 | |
| | 465-6005 | JCTBOX(COMPL)(PJB)(3FTX3FT) | EA | 2.000 | | 2.000 | |
| | 465-6006 | JCTBOX(COMPL)(PJB)(4FTX4FT) | EA | 3.000 | | 3.000 | |
| | 465-6011 | JCTBOX(COMPL)(PJB)(6FTX6FT) | EA | 1.000 | | 1.000 | |
| | 465-6012 | JCTBOX(COMPL)(PJB)(8FTX8FT) | EA | 2.000 | | 2.000 | |
| | 465-6013 | INLET (COMPL)(PCO)(3FT)(NONE) | EA | 5.000 | | 5.000 | |
| | 465-6014 | INLET (COMPL)(PCO)(3FT)(LEFT) | EA | 41.000 | | 41.000 | |
| | 465-6015 | INLET (COMPL)(PCO)(3FT)(RIGHT) | EA | 26.000 | | 26.000 | |
| | 465-6016 | INLET (COMPL)(PCO)(3FT)(BOTH) | EA | 15.000 | | 15.000 | |
| | 465-6017 | INLET (COMPL)(PCO)(4FT)(NONE) | EA | 1.000 | | 1.000 | |
| | 465-6018 | INLET (COMPL)(PCO)(4FT)(LEFT) | EA | 16.000 | | 16.000 | |
| | 465-6019 | INLET (COMPL)(PCO)(4FT)(RIGHT) | EA | 19.000 | | 19.000 | |
| | 465-6020 | INLET (COMPL)(PCO)(4FT)(BOTH) | EA | 1.000 | | 1.000 | |
| | 465-6023 | INLET (COMPL)(PCO)(5FT)(RIGHT) | EA | 4.000 | | 4.000 | |
| | 465-6024 | INLET (COMPL)(PCO)(5FT)(BOTH) | EA | 1.000 | | 1.000 | |
| | 465-6025 | INLET (COMPL)(PCO)(6FT)(NONE) | EA | 6.000 | | 6.000 | |
| | 465-6026 | INLET (COMPL)(PCO)(6FT)(LEFT) | EA | 7.000 | | 7.000 | |
| | 465-6027 | INLET (COMPL)(PCO)(6FT)(RIGHT) | EA | 5.000 | | 5.000 | |
| | 465-6035 | INLET (COMPL)(PCU)(4FT)(RIGHT) | EA | 2.000 | | 2.000 | |
| | 465-6036 | INLET (COMPL)(PCU)(4FT)(BOTH) | EA | 2.000 | | 2.000 | |
| | 465-6039 | INLET (COMPL)(PCU)(5FT)(RIGHT) | EA | 2.000 | | 2.000 | |
| | 465-6070 | INLET (COMPL)(PSL)(RC)(3FTX3FT) | EA | 3.000 | | 3.000 | |
| | 465-6076 | INLET (COMPL)(PSL)(RC)(6FTX6FT) | EA | 1.000 | | 1.000 | |
| | 465-6077 | INLET (COMPL)(PSL)(RC)(8FTX8FT) | EA | 1.000 | | 1.000 | |
| | 465-6126 | INLET (COMPL)(PSL)(FG)(3FTX3FT-3FTX3FT) | EA | 57.000 | | 57.000 | |
| | 465-6130 | INLET (COMPL)(PSL)(FG)(3FTX5FT-3FTX5FT) | EA | 1.000 | | 1.000 | |
| | 465-6225 | JCT BOX (COMPL)(SPL) | EA | 2.000 | | 2.000 | |
| | 466-6180 | WINGWALL (PW - 1) (HW=5 FT) | EA | 1.000 | | 1.000 | |
| | 466-6181 | WINGWALL (PW - 1) (HW=6 FT) | EA | 3.000 | | 3.000 | |

1 ADDENDUM #1 , 11/15/22 , REPLACE SHEET



| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16A |



CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

Estimate & Quantity Sheet

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|--|------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 467-6356 | SET (TY II) (18 IN) (RCP) (3: 1) (C) | EA | 2.000 | | 2.000 | |
| | 467-6388 | SET (TY II) (24 IN) (RCP) (3: 1) (C) | EA | 2.000 | | 2.000 | |
| | 467-6390 | SET (TY II) (24 IN) (RCP) (4: 1) (C) | EA | 3.000 | | 3.000 | |
| | 467-6395 | SET (TY II) (24 IN) (RCP) (6: 1) (P) | EA | 2.000 | | 2.000 | |
| | 467-6468 | SET (TY II) (48 IN) (CMP) (4: 1) (C) | EA | 1.000 | | 1.000 | |
| | 496-6002 | REMOV STR (INLET) | EA | 3.000 | | 3.000 | |
| | 496-6003 | REMOV STR (MANHOLE) | EA | 2.000 | | 2.000 | |
| | 496-6004 | REMOV STR (SET) | EA | 66.000 | | 66.000 | |
| | 496-6005 | REMOV STR (WINGWALL) | EA | 20.000 | | 20.000 | |
| | 496-6006 | REMOV STR (HEADWALL) | EA | 12.000 | | 12.000 | |
| | 496-6007 | REMOV STR (PIPE) | LF | 3,676.000 | | 3,676.000 | |
| | 496-6008 | REMOV STR (BOX CULVERT) | LF | 511.000 | | 511.000 | |
| | 496-6043 | REMOV STR (SMALL FENCE) | LF | 586.000 | | 586.000 | |
| | 496-6072 | REMOVING ROCK RIPRAP | LF | 84.000 | | 84.000 | |
| | 500-6001 | MOBILIZATION | LS | 1.000 | | 1.000 | |
| | 502-6001 | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO | 30.000 | | 30.000 | |
| | 506-6001 | ROCK FILTER DAMS (INSTALL) (TY 1) | LF | 351.000 | | 351.000 | |
| | 506-6002 | ROCK FILTER DAMS (INSTALL) (TY 2) | LF | 501.000 | | 501.000 | |
| | 506-6003 | ROCK FILTER DAMS (INSTALL) (TY 3) | LF | 114.000 | | 114.000 | |
| | 506-6011 | ROCK FILTER DAMS (REMOVE) | LF | 966.000 | | 966.000 | |
| | 506-6020 | CONSTRUCTION EXITS (INSTALL) (TY 1) | SY | 354.000 | | 354.000 | |
| | 506-6024 | CONSTRUCTION EXITS (REMOVE) | SY | 354.000 | | 354.000 | |
| | 506-6038 | TEMP SEDMT CONT FENCE (INSTALL) | LF | 17,779.000 | | 17,779.000 | |
| | 506-6039 | TEMP SEDMT CONT FENCE (REMOVE) | LF | 17,779.000 | | 17,779.000 | |
| | 506-6041 | BIODEG EROSN CONT LOGS (INSTL) (12") | LF | 3,680.000 | | 3,680.000 | |
| | 506-6043 | BIODEG EROSN CONT LOGS (REMOVE) | LF | 3,680.000 | | 3,680.000 | |
| | 508-6001 | CONSTRUCTING DETOURS | SY | 19,041.000 | | 19,041.000 | |
| | 512-6001 | PORT CTB (FUR & INST)(SGL SLOPE)(TY 1) | LF | 2,440.000 | | 2,440.000 | |
| | 512-6009 | PORT CTB (FUR & INST)(LOW PROF)(TY 1) | LF | 6,320.000 | | 6,320.000 | |
| | 512-6010 | PORT CTB (FUR & INST)(LOW PROF)(TY 2) | LF | 1,200.000 | | 1,200.000 | |
| | 512-6025 | PORT CTB (MOVE)(SGL SLP)(TY 1) | LF | 2,080.000 | | 2,080.000 | |
| | 512-6033 | PORT CTB (MOVE)(LOW PROF)(TY 1) | LF | 1,260.000 | | 1,260.000 | |
| | 512-6034 | PORT CTB (MOVE)(LOW PROF)(TY 2) | LF | 400.000 | | 400.000 | |
| | 512-6049 | PORT CTB (REMOVE)(SGL SLP)(TY 1) | LF | 2,440.000 | | 2,440.000 | |
| | 512-6057 | PORT CTB (REMOVE)(LOW PROF)(TY 1) | LF | 6,320.000 | | 6,320.000 | |
| | 512-6058 | PORT CTB (REMOVE)(LOW PROF)(TY 2) | LF | 1,200.000 | | 1,200.000 | |
| | 529-6005 | CONC CURB (MONO) (TY II) | LF | 64,544.000 | | 64,544.000 | |

1 ADDENDUM #1 , 11/15/22 , REPLACE SHEET

| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16B |



CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

Estimate & Quantity Sheet

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|--|------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 530-6004 | DRIVEWAYS (CONC) | SY | 3,299.000 | | 3,299.000 | |
| | 530-6017 | DRIVEWAYS (CONC) (HES) | SY | 2,791.000 | | 2,791.000 | |
| | 531-6001 | CONC SIDEWALKS (4") | SY | 17,209.000 | | 17,209.000 | |
| | 531-6004 | CURB RAMPS (TY 1) | EA | 6.000 | | 6.000 | |
| | 531-6005 | CURB RAMPS (TY 2) | EA | 3.000 | | 3.000 | |
| | 531-6010 | CURB RAMPS (TY 7) | EA | 36.000 | | 36.000 | |
| | 531-6013 | CURB RAMPS (TY 10) | EA | 19.000 | | 19.000 | |
| | 536-6002 | CONC MEDIAN | SY | 654.000 | | 654.000 | |
| | 536-6005 | CONCRETE MEDIAN (NOSE) | SY | 87.000 | | 87.000 | |
| | 542-6001 | REMOVE METAL BEAM GUARD FENCE | LF | 533.000 | | 533.000 | |
| | 544-6003 | GUARDRAIL END TREATMENT (REMOVE) | EA | 6.000 | | 6.000 | |
| | 545-6003 | CRASH CUSH ATTEN (MOVE & RESET) | EA | 6.000 | | 6.000 | |
| | 545-6005 | CRASH CUSH ATTEN (REMOVE) | EA | 12.000 | | 12.000 | |
| | 545-6019 | CRASH CUSH ATTEN (INSTL)(S)(N)(TL3) | EA | 6.000 | | 6.000 | |
| | 550-6003 | CHAIN LINK FENCE (REMOVE) | LF | 2,600.000 | | 2,600.000 | |
| | 550-6006 | GATE (REMOVE) | EA | 2.000 | | 2.000 | |
| | 560-6001 | MAILBOX INSTALL-S (TWG-POST) TY 1 | EA | 29.000 | | 29.000 | |
| | 560-6002 | MAILBOX INSTALL-D (TWG-POST) TY 1 | EA | 5.000 | | 5.000 | |
| | 560-6003 | MAILBOX INSTALL-M (TWG-POST) TY 1 | EA | 3.000 | | 3.000 | |
| | 618-6023 | CONDT (PVC) (SCH 40) (2") | LF | 16,235.000 | | 16,235.000 | |
| | 618-6029 | CONDT (PVC) (SCH 40) (3") | LF | 420.000 | | 420.000 | |
| | 618-6033 | CONDT (PVC) (SCH 40) (4") | LF | 345.000 | | 345.000 | |
| | 618-6034 | CONDT (PVC) (SCH 40) (4") (BORE) | LF | 2,305.000 | | 2,305.000 | |
| | 618-6046 | CONDT (PVC) (SCH 80) (2") | LF | 225.000 | | 225.000 | |
| | 620-6004 | ELEC CONDR (NO.12) INSULATED | LF | 1,520.000 | | 1,520.000 | |
| | 620-6007 | ELEC CONDR (NO.8) BARE | LF | 2,545.000 | | 2,545.000 | |
| | 620-6008 | ELEC CONDR (NO.8) INSULATED | LF | 5,590.000 | | 5,590.000 | |
| | 620-6009 | ELEC CONDR (NO.6) BARE | LF | 305.000 | | 305.000 | |
| | 620-6010 | ELEC CONDR (NO.6) INSULATED | LF | 610.000 | | 610.000 | |
| | 621-6002 | TRAY CABLE (3 CONDR) (12 AWG) | LF | 4,576.000 | | 4,576.000 | |
| | 624-6001 | GROUND BOX TY A (122311) | EA | 5.000 | | 5.000 | |
| | 624-6002 | GROUND BOX TY A (122311)W/APRON | EA | 46.000 | | 46.000 | |
| | 624-6008 | GROUND BOX TY C (162911)W/APRON | EA | 26.000 | | 26.000 | |
| | 628-6185 | ELC SRV TY D 120/240 070(NS)SS(E)GC(O) | EA | 1.000 | | 1.000 | |
| | 628-6187 | ELC SRV TY D 120/240 070(NS)SS(E)PS(U) | EA | 4.000 | | 4.000 | |
| | 644-6001 | IN SM RD SN SUP&AM TY10BWG(1)SA(P) | EA | 46.000 | | 46.000 | |
| | 644-6004 | IN SM RD SN SUP&AM TY10BWG(1)SA(T) | EA | 51.000 | | 51.000 | |

1 ADDENDUM #1 , 11/15/22 , REPLACE SHEET

| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16C |



CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

Estimate & Quantity Sheet

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|---|------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 644-6007 | IN SM RD SN SUP&AM TY10BWG(1)SA(U) | EA | 1.000 | | 1.000 | |
| | 644-6027 | IN SM RD SN SUP&AM TYS80(1)SA(P) | EA | 2.000 | | 2.000 | |
| | 644-6036 | IN SM RD SN SUP&AM TYS80(1)SA(U-BM) | EA | 2.000 | | 2.000 | |
| | 658-6047 | INSTL OM ASSM (OM-2Y)(WC)GND | EA | 8.000 | | 8.000 | |
| | 662-6060 | WK ZN PAV MRK REMOV (W)4"(BRK) | LF | 1,442.000 | | 1,442.000 | |
| | 662-6063 | WK ZN PAV MRK REMOV (W)4"(SLD) | LF | 45,932.000 | | 45,932.000 | |
| | 662-6071 | WK ZN PAV MRK REMOV (W)8"(SLD) | LF | 2,577.000 | | 2,577.000 | |
| | 662-6075 | WK ZN PAV MRK REMOV (W)24"(SLD) | LF | 2,772.000 | | 2,772.000 | |
| | 662-6080 | WK ZN PAV MRK REMOV (W)(ARROW) | EA | 32.000 | | 32.000 | |
| | 662-6086 | WK ZN PAV MRK REMOV (W)(RR XING) | EA | 15.000 | | 15.000 | |
| | 662-6090 | WK ZN PAV MRK REMOV (W)(WORD) | EA | 32.000 | | 32.000 | |
| | 662-6095 | WK ZN PAV MRK REMOV (Y)4"(SLD) | LF | 70,170.000 | | 70,170.000 | |
| | 662-6102 | WK ZN PAV MRK REMOV (Y)24"(SLD) | LF | 1,092.000 | | 1,092.000 | |
| | 666-6006 | REFL PAV MRK TY I (W)4"(DOT)(100MIL) | LF | 1,014.000 | | 1,014.000 | |
| | 666-6036 | REFL PAV MRK TY I (W)8"(SLD)(100MIL) | LF | 16,664.000 | | 16,664.000 | |
| | 666-6042 | REFL PAV MRK TY I (W)12"(SLD)(100MIL) | LF | 6,649.000 | | 6,649.000 | |
| | 666-6045 | REFL PAV MRK TY I (W)18"(SLD)(100MIL) | LF | 139.000 | | 139.000 | |
| | 666-6048 | REFL PAV MRK TY I (W)24"(SLD)(100MIL) | LF | 3,161.000 | | 3,161.000 | |
| | 666-6141 | REFL PAV MRK TY I (Y)12"(SLD)(100MIL) | LF | 680.000 | | 680.000 | |
| | 666-6224 | PAVEMENT SEALER 4" | LF | 89,848.000 | | 89,848.000 | |
| | 666-6226 | PAVEMENT SEALER 8" | LF | 16,664.000 | | 16,664.000 | |
| | 666-6228 | PAVEMENT SEALER 12" | LF | 7,329.000 | | 7,329.000 | |
| | 666-6229 | PAVEMENT SEALER 18" | LF | 139.000 | | 139.000 | |
| | 666-6230 | PAVEMENT SEALER 24" | LF | 3,161.000 | | 3,161.000 | |
| | 666-6231 | PAVEMENT SEALER (ARROW) | EA | 56.000 | | 56.000 | |
| | 666-6232 | PAVEMENT SEALER (WORD) | EA | 56.000 | | 56.000 | |
| | 666-6237 | PAVEMENT SEALER (LNDP ARROW) | EA | 4.000 | | 4.000 | |
| | 666-6242 | PAVEMENT SEALER (RR XING) | EA | 9.000 | | 9.000 | |
| | 666-6300 | RE PM W/RET REQ TY I (W)4"(BRK)(100MIL) | LF | 8,760.000 | | 8,760.000 | |
| | 666-6303 | RE PM W/RET REQ TY I (W)4"(SLD)(100MIL) | LF | 37,582.000 | | 37,582.000 | |
| | 666-6315 | RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL) | LF | 44,420.000 | | 44,420.000 | |
| | 668-6077 | PREFAB PAV MRK TY C (W) (ARROW) | EA | 56.000 | | 56.000 | |
| | 668-6083 | PREFAB PAV MRK TY C (W) (LNDP ARROW) | EA | 4.000 | | 4.000 | |
| | 668-6085 | PREFAB PAV MRK TY C (W) (WORD) | EA | 56.000 | | 56.000 | |
| | 668-6089 | PREFAB PAV MRK TY C (W) (RR XING) | EA | 9.000 | | 9.000 | |
| | 672-6007 | REFL PAV MRKR TY I-C | EA | 793.000 | | 793.000 | |
| | 672-6009 | REFL PAV MRKR TY II-A-A | EA | 234.000 | | 234.000 | |

1 ADDENDUM #1 , 11/15/22 , REPLACE SHEET

| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16D |



CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

Estimate & Quantity Sheet

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|----------|--|------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 672-6010 | REFL PAV MRKR TY II-C-R | EA | 435.000 | | 435.000 | |
| | 677-6001 | ELIM EXT PAV MRK & MRKS (4") | LF | 28,715.000 | | 28,715.000 | |
| | 678-6001 | PAV SURF PREP FOR MRK (4") | LF | 91,776.000 | | 91,776.000 | |
| | 678-6004 | PAV SURF PREP FOR MRK (8") | LF | 16,664.000 | | 16,664.000 | |
| | 678-6006 | PAV SURF PREP FOR MRK (12") | LF | 7,329.000 | | 7,329.000 | |
| | 678-6007 | PAV SURF PREP FOR MRK (18") | LF | 139.000 | | 139.000 | |
| | 678-6008 | PAV SURF PREP FOR MRK (24") | LF | 2,855.000 | | 2,855.000 | |
| | 678-6009 | PAV SURF PREP FOR MRK (ARROW) | EA | 58.000 | | 58.000 | |
| | 678-6016 | PAV SURF PREP FOR MRK (WORD) | EA | 56.000 | | 56.000 | |
| | 678-6020 | PAV SURF PREP FOR MRK (RR XING) | EA | 9.000 | | 9.000 | |
| | 680-6002 | INSTALL HWY TRF SIG (ISOLATED) | EA | 5.000 | | 5.000 | |
| | 680-6004 | REMOVING TRAFFIC SIGNALS | EA | 4.000 | | 4.000 | |
| | 681-6001 | TEMP TRAF SIGNALS | EA | 4.000 | | 4.000 | |
| | 682-6001 | VEH SIG SEC (12")LED(GRN) | EA | 43.000 | | 43.000 | |
| | 682-6002 | VEH SIG SEC (12")LED(GRN ARW) | EA | 15.000 | | 15.000 | |
| | 682-6003 | VEH SIG SEC (12")LED(YEL) | EA | 43.000 | | 43.000 | |
| | 682-6004 | VEH SIG SEC (12")LED(YEL ARW) | EA | 30.000 | | 30.000 | |
| | 682-6005 | VEH SIG SEC (12")LED(RED) | EA | 43.000 | | 43.000 | |
| | 682-6006 | VEH SIG SEC (12")LED(RED ARW) | EA | 34.000 | | 34.000 | |
| | 682-6018 | PED SIG SEC (LED)(COUNTDOWN) | EA | 34.000 | | 34.000 | |
| | 682-6054 | BACKPLATE W/REF BRDR(3 SEC)(VENT)ALUM | EA | 41.000 | | 41.000 | |
| | 682-6055 | BACKPLATE W/REF BRDR(4 SEC)(VENT)ALUM | EA | 10.000 | | 10.000 | |
| | 682-6056 | BACKPLATE W/REF BRDR(5 SEC)(VENT)ALUM | EA | 9.000 | | 9.000 | |
| | 684-6031 | TRF SIG CBL (TY A)(14 AWG)(5 CONDR) | LF | 5,618.000 | | 5,618.000 | |
| | 684-6033 | TRF SIG CBL (TY A)(14 AWG)(7 CONDR) | LF | 705.000 | | 705.000 | |
| | 684-6042 | TRF SIG CBL (TY A)(14 AWG)(16 CONDR) | LF | 3,780.000 | | 3,780.000 | |
| | 684-6079 | TRF SIG CBL (TY C)(12 AWG)(2 CONDR) | LF | 5,297.000 | | 5,297.000 | |
| | 685-6004 | INSTL RDSO FLSH BCN ASSM (SOLAR PWRD) | EA | 2.000 | | 2.000 | |
| | 686-6036 | INS TRF SIG PL AM(S)1 ARM(32')LUM&ILSN | EA | 2.000 | | 2.000 | |
| | 686-6044 | INS TRF SIG PL AM(S)1 ARM(40')LUM&ILSN | EA | 1.000 | | 1.000 | |
| | 686-6048 | INS TRF SIG PL AM(S)1 ARM(44')LUM&ILSN | EA | 1.000 | | 1.000 | |
| | 686-6052 | INS TRF SIG PL AM(S)1 ARM(48')LUM&ILSN | EA | 2.000 | | 2.000 | |
| | 686-6060 | INS TRF SIG PL AM(S)1 ARM(55')LUM&ILSN | EA | 4.000 | | 4.000 | |
| | 686-6064 | INS TRF SIG PL AM(S)1 ARM(60')LUM&ILSN | EA | 4.000 | | 4.000 | |
| | 686-6068 | INS TRF SIG PL AM(S)1 ARM(65')LUM&ILSN | EA | 5.000 | | 5.000 | |
| | 687-6001 | PED POLE ASSEMBLY | EA | 19.000 | | 19.000 | |
| | 688-6001 | PED DETECT PUSH BUTTON (APS) | EA | 34.000 | | 34.000 | |

1 ADDENDUM #1 , 1/15/22 , REPLACE SHEET



| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16E |



CONTROLLING PROJECT ID 0047-04-031

DISTRICT Dallas
HIGHWAY SH 5

COUNTY Collin

Estimate & Quantity Sheet

| CONTROL SECTION JOB | | | | 0047-04-031 | | TOTAL EST. | TOTAL FINAL |
|---------------------|-----------|---|------|-------------|-------|------------|-------------|
| PROJECT ID | | | | A00129571 | | | |
| COUNTY | | | | Collin | | | |
| HIGHWAY | | | | SH 5 | | | |
| ALT | BID CODE | DESCRIPTION | UNIT | EST. | FINAL | | |
| | 688-6003 | PED DETECTOR CONTROLLER UNIT | EA | 5.000 | | 5.000 | |
| | 730-6107 | FULL - WIDTH MOWING | CYC | 6.000 | | 6.000 | |
| | 3077-6001 | SP MIXESSP-BPG64-22 | TON | 35,264.000 | | 35,264.000 | |
| | 3077-6011 | SP MIXESSP-CPG64-22 | TON | 4,466.000 | | 4,466.000 | |
| | 3077-6075 | TACK COAT | GAL | 963.000 | | 963.000 | |
| | 6001-6002 | PORTABLE CHANGEABLE MESSAGE SIGN | EA | 2.000 | | 2.000 | |
| | 6058-6001 | BBU SYSTEM (EXTERNAL BATT CABINET) | EA | 5.000 | | 5.000 | |
| | 6185-6002 | TMA (STATIONARY) | DAY | 1,196.000 | | 1,196.000 | |
| | 6185-6003 | TMA (MOBILE OPERATION) | HR | 256.000 | | 256.000 | |
| | 6292-6001 | RVDS(PRESENCE DETECTION ONLY) | EA | 9.000 | | 9.000 | |
| | 6292-6003 | RVDS(PRESENCE AND ADVANCE DET) | EA | 10.000 | | 10.000 | |
| | 6306-6006 | VIVDS TEMPORARY | EA | 4.000 | | 4.000 | |
| | 18 | LAW ENFORCEMENT: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | 1.000 | | 1.000 | |
| | | SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING) | LS | 1.000 | | 1.000 | |
| | | EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART) | LS | 1.000 | | 1.000 | |

1 ADDENDUM #1 , 11/15/22 , REPLACE SHEET

| | | | |
|----------|--------|-------------|-------|
| DISTRICT | COUNTY | CCSJ | SHEET |
| Dallas | Collin | 0047-04-031 | 16F |

SUMMARY OF TRAFFIC CONTROL QUANTITIES

| LOCATION | 508 | 512 | 512 | 512 | 512 | 512 | 512 | 512 | 512 | 512 | 545 | 545 | 545 | 662 | 662 | 662 |
|-----------------------------|-------------------------|--|--|--|--|---|---|--|---|---|---------------------------------------|---------------------------------|---|--|--|--|
| | 6001 | 6001 | 6009 | 6010 | 6025 | 6033 | 6034 | 6049 | 6057 | 6058 | 6003 | 6005 | 6019 | 6060 | 6063 | 6071 |
| | CONSTRUCTING DETOURS | PORT CTB (FUR & INST) (SGL SLOPE) (TY 1) | PORT CTB (FUR & INST) (LOW PROF) (TY 1) | PORT CTB (FUR & INST) (LOW PROF) (TY 2) | PORT CTB (MOVE) (SGL SLP) (TY 1) | PORT CTB (MOVE) (LOW PROF) (TY 1) | PORT CTB (MOVE) (LOW PROF) (TY 2) | PORT CTB (REMOVE) (S GL SLP) (TY 1) | PORT CTB (REMOVE) (LOW PROF) (TY 1) | PORT CTB (REMOVE) (LOW PROF) (TY 2) | CRASH CUSH ATTEN (MOVE & RESET) | CRASH CUSH ATTEN (REMOVE) | CRASH CUSH ATTEN (INSTL) (S) (N) (TL3) | WK ZN PAV MRK REMOV (W) 4" (BRK) | WK ZN PAV MRK REMOV (W) 4" (SLD) | WK ZN PAV MRK REMOV (W) 8" (SLD) |
| | SY | LF | LF | LF | LF | LF | LF | LF | LF | LF | EA | EA | EA | LF | LF | LF |
| PHASE 1 | | | | | | | | | | | | | | | | |
| SHEET 1 OF 10 | | | | | | | | | | | | | | | | 281 |
| SHEET 2 OF 10 | 2,040 | | 1,640 | 100 | | | | | | | | | | | | 3,103 |
| SHEET 3 OF 10 | 2,435 | | 940 | 120 | | | | | | | | | | | | 4,030 |
| SHEET 4 OF 10 | 2,780 | | 1,000 | 220 | | | | | | | | | | | | 4,254 |
| SHEET 5 OF 10 | 1,893 | | 1,320 | 300 | | | | | | | | | | | | 4,433 |
| SHEET 6 OF 10 | 152 | | 140 | 60 | | | | | | | | | | | | 401 |
| SHEET 7 OF 10 | 192 | | | | | | | | | | | | | | | |
| SHEET 8 OF 10 | 87 | 800 | | | | | | | | | | | 1 | | | |
| SHEET 9 OF 10 | 358 | 200 | | | | | | | | | | | 3 | | | |
| SHEET 10 OF 10 | 2,711 | 1,440 | | | | | | | | | | | 2 | | 2,200 | |
| PHASE 1 INTERSECTIONS | | | | | | | | | | | | | | | | |
| E MELISSA RD | | | | | | | | | | | | | | | | |
| PHASE 1 STEP 1A | 90 | | 260 | 60 | | | | | | | | | | | | 377 |
| PHASE 1 STEP 1B | | | | | | 160 | 40 | | 100 | 20 | | | | | | 907 |
| PHASE 1 STEP 1C | | | | | | | | | 160 | 40 | | | | 147 | 269 | 395 |
| FANNIN RD | | | | | | | | | | | | | | | | |
| PHASE 1 STEP 1A | | | 80 | 60 | | | | | | | | | | | | 154 |
| PHASE 1 STEP 1B | | | 20 | | | 80 | 60 | | | | | | | | | 65 |
| PHASE 1 STEP 1C | | | | | | | | | 100 | 60 | | | | | | 465 |
| COLLIN COUNTY OUTER LOOP | | | | | | | | | | | | | | | | |
| PHASE 1 STEP 1A | 53 | | 180 | 60 | | | | | | | | | | | | 1,121 |
| PHASE 1 STEP 1B | | | | | | 160 | 60 | | 20 | | | | | | | 912 |
| PHASE 1 STEP 1C | | | | | | | | | 160 | 60 | | | | | | 1,606 |
| PHASE 1 SUBTOTAL | 12,791 | 2,440 | 5,580 | 980 | 0 | 400 | 160 | 0 | 540 | 180 | 0 | 0 | 6 | 147 | 24,576 | 1,364 |

| | | | | | | | | | | | | | | | | |
|--------------------------|-------|---|-----|-----|-------|-----|-----|-------|-------|-------|---|---|----|-------|--------|-------|
| PHASE 2 | | | | | | | | | | | | | | | | |
| SHEET 1 OF 10 | | | | | | | | | | | | | | | | 210 |
| SHEET 2 OF 10 | 847 | | | | | 100 | 40 | | 1,540 | 60 | | | | | | 2,206 |
| SHEET 3 OF 10 | 2,017 | | | | | | | | 940 | 120 | | | | | | 92 |
| SHEET 4 OF 10 | 1,759 | | | | | | | | 1,000 | 220 | | | | | | 1,632 |
| SHEET 5 OF 10 | 1,331 | | | | 380 | | | | 1,320 | 300 | 1 | | | | | 1,560 |
| SHEET 6 OF 10 | 296 | | | | | 80 | 40 | | 60 | 20 | 1 | | | | | 351 |
| SHEET 7 OF 10 | | | | | | | | | | | | | | | | |
| SHEET 8 OF 10 | | | | | 440 | | | | | | 1 | | | 267 | 495 | 321 |
| SHEET 9 OF 10 | | | | | 660 | | | | | | 2 | | 0 | 623 | 1,381 | 660 |
| SHEET 10 OF 10 | | | | | 600 | | | 2,440 | 180 | 80 | 1 | 6 | | | 2,082 | |
| PHASE 2 INTERSECTIONS | | | | | | | | | | | | | | | | |
| E MELISSA RD | | | | | | | | | | | | | | | | |
| PHASE 2 STEP 1A | | | 360 | 80 | | | | | | | | | | | | 681 |
| PHASE 2 STEP 1B | | | | | | 320 | 40 | | 40 | 40 | | | 56 | | | 791 |
| PHASE 2 STEP 1C | | | | | | | | | 320 | 40 | | | | | | 788 |
| PENNSYLVANIA AVE | | | | | | | | | | | | | | | | |
| PHASE 2 STEP 1A | | | 120 | 40 | | | | | | | | | | | | 1,256 |
| PHASE 2 STEP 1B | | | | | | 80 | 40 | | 40 | 40 | | | | | | 1,784 |
| PHASE 2 STEP 1C | | | | | | | | | 80 | 40 | | | | | | 1,417 |
| THROCKMORTON RD | | | | | | | | | | | | | | | | |
| PHASE 2 STEP 1A | | | 80 | 40 | | | | | | | | | | | | 1,165 |
| PHASE 2 STEP 1B | | | 180 | 60 | | | 80 | 40 | | | | | | | | 1,052 |
| PHASE 2 STEP 1C | | | | | | 200 | 40 | | 60 | 60 | | | | | | 1,468 |
| PHASE 2 STEP 1D | | | | | | | | | 200 | 40 | | | | 349 | 945 | |
| TEMP PAV MARK LAYOUT | | | | | | | | | | | | | | | 285 | 250 |
| PHASE 2 SUBTOTAL | 6,250 | 0 | 740 | 220 | 2,080 | 860 | 240 | 2,440 | 5,780 | 1,020 | 6 | 6 | 0 | 1,295 | 21,356 | 1,212 |

| | | | | | | | | | | | | | | | | |
|-------------------|--------|-------|-------|-------|-------|-------|-----|-------|-------|-------|---|---|---|-------|--------|-------|
| PROJECT TOTALS | 19,041 | 2,440 | 6,320 | 1,200 | 2,080 | 1,260 | 400 | 2,440 | 6,320 | 1,200 | 6 | 6 | 6 | 1,442 | 45,932 | 2,577 |
|-------------------|--------|-------|-------|-------|-------|-------|-----|-------|-------|-------|---|---|---|-------|--------|-------|

| REV. NO. | DATE | BY | REVISION |
|----------|------|----|----------|
| | | | |

AECOM 19219 KATY FREEWAY
SUITE 100
AECOM Technical Services Inc.- 3580 HOUSTON, TX 77094



SH 5

SUMMARY OF
TRAFFIC CONTROL
QUANTITIES

SHEET 1 OF 2

| | | | |
|-----------|----------------------|-----------------|--------------|
| DSN: CC | FED. RD. DIV. NO. | PROJECT NO. | SHEET NO. |
| CK: CO | 6 | SEE TITLE SHEET | 17 |
| DRN: JM | STATE | DIST. | COUNTY |
| APPVD: DH | TEXAS | 18 | COLLIN |
| CONT. | SECT. | JOB | HIGHWAY NO. |
| 0047 | 04 | 031 | SH 5 |

ADDENDUM #1, 11/15/22, REPLACE SHEET

11/15/2022 9:07:36 AM c:\pwworking\ngdlr\khu\an_bazar\vaani@aecom.com\dms0527\SEG1_ICP_QTY_01.dgn

| SUMMARY OF ROADWAY QUANTITIES | | | | | | | | | | | | | |
|-------------------------------|--|---------------------------|-------------------------------------|---|----------------|--------------------------|------------------|------------------------|---------------------|-------------------|-------------------|-------------------|--------------------|
| LOCATION | 260 | 260 | 360 | 360 | 450 | 529 | 530 | 530 | 531 | 531 | 531 | 531 | 531 |
| | 6012 | 6027 | 6005 | 6058 | 6103 | 6005 | 6004 | 6017 | 6001 | 6004 | 6005 | 6010 | 6013 |
| | LIME (HYD, COM OR QK) (SLRY) OR QK (DRY) | LIME TRT (EXST MATL) (8") | CONC PVMT (CONT REINF - CRCP) (11") | CONC PVMT (CONT REINF - CRCP) (HES) (11") | RAIL (TY PR11) | CONC CURB (MONO) (TY 11) | DRIVEWAYS (CONC) | DRIVEWAYS (CONC) (HES) | CONC SIDEWALKS (4") | CURB RAMPS (TY 1) | CURB RAMPS (TY 2) | CURB RAMPS (TY 7) | CURB RAMPS (TY 10) |
| | TON | SY | SY | SY | LF | LF | SY | SY | SY | EA | EA | EA | EA |
| BEGIN TO STA 125+00 | 49 | 4,360 | 3,853 | | | 2,336 | | 73 | 667 | | | | |
| STA 125+00 TO STA 136+00 | 106 | 9,421 | 8,240 | | | 4,232 | 370 | | 1,117 | | | 1 | |
| STA 136+00 TO STA 147+00 | 120 | 10,677 | 9,583 | | | 4,125 | 723 | 146 | 1,034 | | | 1 | |
| STA 147+00 TO STA 158+00 | 157 | 13,923 | 12,848 | | 59 | 4,224 | 695 | 559 | 1,014 | | 2 | 6 | |
| STA 158+00 TO STA 169+00 | 141 | 12,543 | 11,471 | | | 4,315 | | 513 | 864 | | 1 | 8 | 7 |
| STA 169+00 TO STA 180+00 | 133 | 11,809 | 10,694 | | 469 | 4,065 | 519 | 565 | 956 | | | | 7 |
| STA 180+00 TO STA 191+00 | 125 | 11,066 | 9,988 | 448 | | 3,896 | 258 | 301 | 1,079 | 4 | | | 5 |
| STA 191+00 TO STA 202+00 | 134 | 11,859 | 10,741 | | | 4,094 | 127 | 166 | 1,105 | | | 8 | |
| STA 202+00 TO STA 213+00 | 92 | 8,112 | 6,904 | | 280 | 4,320 | 146 | 129 | 1,192 | | | | |
| STA 213+00 TO STA 224+00 | 91 | 8,067 | 7,089 | | | 4,399 | | 78 | 1,201 | | | | |
| STA 224+00 TO STA 235+00 | 91 | 8,065 | 7,087 | | | 4,409 | | 69 | 1,199 | | | | |
| STA 235+00 TO STA 246+00 | 93 | 8,275 | 7,175 | | 755 | 4,517 | | 132 | 1,205 | | | | |
| STA 246+00 TO STA 257+00 | 100 | 8,857 | 7,875 | 1,039 | 250 | 4,113 | 461 | | 1,085 | | | 2 | |
| STA 257+00 TO STA 268+00 | 131 | 11,657 | 10,548 | | 1,301 | 3,825 | | | 1,114 | | | 2 | |
| STA 268+00 TO STA 277+00 | 93 | 8,225 | 7,227 | | | 3,622 | | 60 | 983 | | | | |
| STA 277+00 TO STA 288+00 | 159 | 14,148 | 10,877 | | | 3,224 | | | 890 | | | 8 | |
| STA 288+00 TO END | 46 | 4,011 | | | | | | | | | | | |
| N. CENTRAL ST. | 18 | 1,604 | 1,423 | | | 828 | | | 504 | 2 | | | |
| HIGHLAND RD. | 19 | 1,635 | | | | | | | | | | | |
| PROJECT TOTALS | 1,898 | 168,314 | 143,623 | 1,487 | 3,114 | 64,544 | 3,299 | 2,791 | 17,209 | 6 | 3 | 36 | 19 |

| SUMMARY OF ROADWAY QUANTITIES | | | | | | | | |
|-------------------------------|-------------|--------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------|-----------------------|-----------|
| LOCATION | 536 | 536 | 560 | 560 | 560 | 3077 | 3077 | 3077 |
| | 6002 | 6005 | 6001 | 6002 | 6003 | 6001 | 6011 | 6075 |
| | CONC MEDIAN | CONC MEDIAN (NOSE) | MAILBOX INSTALL-S (TWG-POST) TY 1 | MAILBOX INSTALL-D (TWG-POST) TY 1 | MAILBOX INSTALL-M (TWG-POST) TY 1 | SP MIXES SP-B PG64-22 | SP MIXES SP-C PG64-22 | TACK COAT |
| | SY | SY | EA | EA | EA | TON | TON | GAL |
| BEGIN TO STA 125+00 | 39 | | | 1 | | 959 | | |
| STA 125+00 TO STA 136+00 | | 3 | 1 | 1 | | 2,073 | | |
| STA 136+00 TO STA 147+00 | | 21 | 3 | | | 2,349 | | |
| STA 147+00 TO STA 158+00 | | 8 | 4 | | 1 | 3,063 | | |
| STA 158+00 TO STA 169+00 | | 6 | 4 | | | 2,759 | | |
| STA 169+00 TO STA 180+00 | | 6 | 5 | 2 | | 2,598 | | |
| STA 180+00 TO STA 191+00 | 226 | 3 | 6 | 1 | | 2,435 | | |
| STA 191+00 TO STA 202+00 | 389 | 3 | 3 | | | 2,609 | | |
| STA 202+00 TO STA 213+00 | | | 2 | | | 1,785 | | |
| STA 213+00 TO STA 224+00 | | 10 | | | 1 | 1,775 | | |
| STA 224+00 TO STA 235+00 | | | | | | 1,774 | | |
| STA 235+00 TO STA 246+00 | | | | | | 1,821 | | |
| STA 246+00 TO STA 257+00 | | 10 | 1 | | 1 | 1,949 | | |
| STA 257+00 TO STA 268+00 | | 11 | | | | 2,565 | | |
| STA 268+00 TO STA 277+00 | | | | | | 1,810 | | |
| STA 277+00 TO STA 288+00 | | 6 | | | | 2,590 | 1,176 | 285 |
| STA 288+00 TO END | | | | | | | 2,481 | 481 |
| N. CENTRAL ST. | | | | | | 353 | | |
| HIGHLAND RD. | | | | | | | 809 | 196 |
| PROJECT TOTALS | 654 | 87 | 29 | 5 | 3 | 35,264 | 4,466 | 963 |

| REV. NO. | DATE | BY | REVISION |
|----------|------|----|----------|
| | | | |

CivilTech Engineering, Inc. 11821 Telge Road
Cypress, Texas 77429
PH: (281) 304-0200 - FX: (281) 304-0210
Firm Registration No. F-382



SH 5
SUMMARY OF ROADWAY QUANTITIES

SHEET 1 OF 1

| DSN: | DC | FED. RD. DIV. NO. | PROJECT NO. | SHEET NO. |
|--------|-------|-------------------|-----------------|-----------|
| CK: | CW | 6 | SEE TITLE SHEET | 22 |
| DRN: | DA | STATE | DIST. | COUNTY |
| APPVD: | PB | TEXAS | 18 | COLLIN |
| CONT. | SECT. | JOB | HIGHWAY NO. | |
| 0047 | 04 | 031 | SH 5 | |

ADDENDUM #1, 11/15/22, REPLACE SHEET

11/15/2022 11:57:55 AM c:\pw\work\ingdir\cwn\itec\civil\techeng.com\dms06068\SEG1_GNSR_01.dgn

| SUMMARY OF DRAINAGE QUANTITIES | | | | | | | | | | | |
|---------------------------------------|-----------------|-----------------------|------------------------------------|----------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|
| LOCATION | *400 6001 | 400 6005 | 402 6001 | 432 6002 | 462 6001 | 462 6003 | 462 6004 | 462 6005 | 462 6006 | 462 6008 | 462 6010 |
| | STRUCT EXCAV | CEM STABIL BKFL | TRENCH EXCAVATION PROTECTION | RIPRAP (CONC) (5 IN) | CONC BOX CULV (3 FT X 2 FT) | CONC BOX CULV (4 FT X 2 FT) | CONC BOX CULV (4 FT X 3 FT) | CONC BOX CULV (4 FT X 4 FT) | CONC BOX CULV (5 FT X 2 FT) | CONC BOX CULV (5 FT X 4 FT) | CONC BOX CULV (6 FT X 3 FT) |
| | CY | CY | LF | CY | LF | LF | LF | LF | LF | LF | LF |
| NB DRAINAGE PLAN & PROFILE | | | | | | | | | | | |
| BEGIN TO STA 125+00 | 261 | | 133 | | | | | | | | |
| STA 125+00 TO STA 136+00 | 1,226 | | 1,117 | | | | | | | | |
| STA 136+00 TO STA 147+00 | 381 | | 451 | | | | | | | | |
| STA 147+00 TO STA 158+00 | 1,308 | | 1,088 | | | | | | | | |
| STA 158+00 TO STA 169+00 | 1,229 | | 1,151 | | | | | | | | |
| STA 169+00 TO STA 180+00 | 1,140 | | 948 | | | | | | | | 74 |
| STA 180+00 TO STA 191+00 | 1,420 | | 1,160 | | | | | | | | |
| STA 191+00 TO STA 202+00 | 609 | | 757 | | | | | | | | |
| STA 202+00 TO STA 213+00 | 1,343 | | 1,142 | | | | | | | | |
| STA 213+00 TO STA 224+00 | 1,108 | | 1,100 | | | | | | | | |
| STA 224+00 TO STA 235+00 | 407 | | | | | | | | | | |
| STA 235+00 TO STA 246+00 | 898 | | 928 | | | | | | | | |
| STA 246+00 TO STA 257+00 | 880 | | 940 | | | | | | | | |
| STA 257+00 TO STA 268+00 | 1,710 | | 1,124 | | 913 | | | | | | |
| STA 268+00 TO STA 277+00 | 1,055 | | 915 | | 195 | | | | | | |
| STA 277+00 TO STA 288+00 | 663 | | 640 | | | | | | | | |
| STA 288+00 TO END | | | | | | | | | | | |
| SB DRAINAGE PLAN & PROFILE | | | | | | | | | | | |
| BEGIN TO STA 125+00 | 355 | | 150 | | | | | | | | |
| STA 125+00 TO STA 136+00 | 1,104 | | 1,150 | | | | | | | | |
| STA 136+00 TO STA 147+00 | 720 | | 721 | | | | | | | | |
| STA 147+00 TO STA 158+00 | 2,590 | | 1,315 | | | | 415 | | 436 | | |
| STA 158+00 TO STA 169+00 | 1,654 | | 1,204 | | | | | | | | |
| STA 169+00 TO STA 180+00 | 1,627 | | 1,010 | 31 | | | 781 | | | | 109 |
| STA 180+00 TO STA 191+00 | 1,324 | | 1,144 | | | | 41 | | | | |
| STA 191+00 TO STA 202+00 | 828 | | 740 | | | | | | | | |
| STA 202+00 TO STA 213+00 | 1,129 | | 1,132 | | | | | | 249 | | |
| STA 213+00 TO STA 224+00 | 1,090 | | 1,100 | | 590 | 171 | | | 284 | | |
| STA 224+00 TO STA 235+00 | 601 | | 575 | | | | | | | | |
| STA 235+00 TO STA 246+00 | 346 | | 233 | | | | | | | | |
| STA 246+00 TO STA 257+00 | 1,052 | | 925 | | 416 | | | | | | |
| STA 257+00 TO STA 268+00 | 1,406 | | 1,100 | | 258 | 814 | | | | | |
| STA 268+00 TO STA 277+00 | 1,092 | | 900 | | 880 | | | | | | |
| STA 277+00 TO STA 288+00 | 831 | | 608 | | 590 | | | | | | |
| STA 288+00 TO END | | | | | | | | | | | |
| N. CENTRAL ST. | | | | | | | | | | | |
| | 444 | | 291 | | | | | | | | |
| CULVERT C4 LAYOUT | | | | | | | | | | | |
| | 313 | | 131 | 55 | | | | | | | |
| CULVERT C6 LAYOUT | | | | | | | | | | | |
| | 251 | | 159 | 68 | | 290 | | | | | |
| PROJECT TOTALS | | | | | | | | | | | |
| | 34,395 | 0 | 28,182 | 154 | 3,842 | 1,275 | 822 | 415 | 533 | 436 | 183 |

* FOR CONTRACTOR'S INFORMATION ONLY

| REV. NO. | DATE | BY | REVISION |
|----------|------|----|----------|
| | | | |
| | | | |

CivilTech Engineering, Inc. 11821 Telge Road
Cypress, Texas 77429
PH: (281) 304-0200 - FX: (281) 304-0210
Firm Registration No. F-382



SH 5
SUMMARY OF DRAINAGE QUANTITIES

SHEET 1 OF 5

| | | | | |
|------------|---------------------|-----------------------------|------------------|--------------|
| DSN: DC | FED. RD. DIV. NO. 6 | PROJECT NO. SEE TITLE SHEET | | SHEET NO. 24 |
| CK: CW | STATE DA | DIST. 18 | COUNTY COLLIN | |
| APPVD: PB | TEXAS | JOB 0047 | HIGHWAY NO. SH 5 | |
| CONT. 0047 | SECT. 04 | JOB 031 | HIGHWAY NO. SH 5 | |

ADDENDUM #1, 11/15/22, REPLACE SHEET

11/21/2022 1:08:59 PM c:\pw\work\ingdi\cwin\itec\civil\techeng.com\dms06068\SEG1_GNDR_01.dgn

11/15/2022 11:58:29 AM
 c:\pw\work\ingdi\cwin\itec\civil\techeng.com\dms06068\SEG1_GNDR_02.dgn

| SUMMARY OF DRAINAGE QUANTITIES | | | | | | | | | | | |
|---------------------------------------|-----------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------------|--------------------------------------|--------------------------------------|--------------------------------------|
| LOCATION | 462 | 464 | 464 | 464 | 464 | 464 | 464 | 465 | 465 | 465 | 465 |
| | 6019 | 6003 | 6005 | 6007 | 6008 | 6009 | 6010 | 6005 | 6006 | 6011 | 6012 |
| | CONC BOX CULV (8 FT X 4 FT) | RC PIPE (CL III) (18 IN) | RC PIPE (CL III) (24 IN) | RC PIPE (CL III) (30 IN) | RC PIPE (CL III) (36 IN) | RC PIPE (CL III) (42 IN) | RC PIPE (CL III) (48 IN) | JCTBOX (COMPL) (PJB) (3FTX3FT) | JCTBOX (COMPL) (PJB) (4FTX4FT) | JCTBOX (COMPL) (PJB) (6FTX6FT) | JCTBOX (COMPL) (PJB) (8FTX8FT) |
| | LF | LF | LF | LF | LF | LF | LF | EA | EA | EA | EA |
| NB DRAINAGE PLAN & PROFILE | | | | | | | | | | | |
| BEGIN TO STA 125+00 | | | 376 | | | | | | | | |
| STA 125+00 TO STA 136+00 | | 12 | 1076 | | | | | | | | |
| STA 136+00 TO STA 147+00 | | 12 | 418 | | | | | | | | |
| STA 147+00 TO STA 158+00 | | 45 | 556 | 505 | | | | 1 | | | |
| STA 158+00 TO STA 169+00 | | 7 | 1097 | | | | | | | | |
| STA 169+00 TO STA 180+00 | | 157 | 179 | 263 | 518 | | | | | | |
| STA 180+00 TO STA 191+00 | | | 723 | 376 | | | | 1 | | | |
| STA 191+00 TO STA 202+00 | | 153 | 570 | | | | | | | | |
| STA 202+00 TO STA 213+00 | | 15 | 275 | 821 | | | | | | | |
| STA 213+00 TO STA 224+00 | | | 789 | 285 | | | | | | | |
| STA 224+00 TO STA 235+00 | | | 580 | | | | | | | | |
| STA 235+00 TO STA 246+00 | | | 906 | | | | | | | | |
| STA 246+00 TO STA 257+00 | | | 913 | | | | | | | | |
| STA 257+00 TO STA 268+00 | | 18 | 160 | | | | | | | | |
| STA 268+00 TO STA 277+00 | | 10 | 685 | | | | | | | | |
| STA 277+00 TO STA 288+00 | | 20 | 601 | | | | | | | | |
| STA 288+00 TO END | | | | | | | | | | | |
| SB DRAINAGE PLAN & PROFILE | | | | | | | | | | | |
| BEGIN TO STA 125+00 | | | 378 | | | | | | | | |
| STA 125+00 TO STA 136+00 | | 14 | 1096 | | | | | | | | |
| STA 136+00 TO STA 147+00 | | | 372 | 102 | 176 | 35 | | | | | |
| STA 147+00 TO STA 158+00 | | | 36 | | | 300 | 191 | | | | 2 |
| STA 158+00 TO STA 169+00 | | 35 | 203 | 173 | 543 | 230 | | | 2 | | |
| STA 169+00 TO STA 180+00 | | 65 | 76 | | | | | | | | |
| STA 180+00 TO STA 191+00 | | | 1065 | | | | | | | 1 | |
| STA 191+00 TO STA 202+00 | | 29 | 825 | | | | | | | | |
| STA 202+00 TO STA 213+00 | | | 390 | 525 | | | | | | | |
| STA 213+00 TO STA 224+00 | | | 52 | | | | | | | | |
| STA 224+00 TO STA 235+00 | | | 564 | | | | | | | | |
| STA 235+00 TO STA 246+00 | | | 1010 | | | | | | | | |
| STA 246+00 TO STA 257+00 | | | 483 | | | | | | | | |
| STA 257+00 TO STA 268+00 | | | | | | | | | | | |
| STA 268+00 TO STA 277+00 | | | | | | | | | | | |
| STA 277+00 TO STA 288+00 | | 23 | 34 | | | | | | 1 | | |
| STA 288+00 TO END | | | | | | | | | | | |
| N. CENTRAL ST. | | | | | | | | | | | |
| CULVERT C4 LAYOUT | 132 | | | | | | | | | | |
| CULVERT C6 LAYOUT | | | | | | | | | | | |
| PROJECT TOTALS | 132 | 615 | 16,755 | 3,050 | 1,237 | 565 | 191 | 2 | 3 | 1 | 2 |

| REV. NO. | DATE | BY | REVISION |
|----------|------|----|----------|
| | | | |
| | | | |
| | | | |

CivilTech Engineering, Inc. 11821 Telge Road
 Cypress, Texas 77429
 PH: (281) 304-0200 - FX: (281) 304-0210
 Firm Registration No. F-382



SH 5


SUMMARY OF DRAINAGE QUANTITIES

SHEET 2 OF 5


| | | | | |
|------------|---------------------|-----------------------------|------------------|--------------|
| DSN: DC | FED. RD. DIV. NO. 6 | PROJECT NO. SEE TITLE SHEET | | SHEET NO. 25 |
| CK: CW | STATE DA | DIST. 18 | COUNTY COLLIN | |
| APPVD: PB | TEXAS | 18 | COLLIN | |
| CONT. 0047 | SECT. 04 | JOB 031 | HIGHWAY NO. SH 5 | |

ADDENDUM #1, 11/15/22, REPLACE SHEET


- LEGEND:**
- CONSTRUCTION ZONE THIS PHASE
 - FAST TRACK PAVEMENT CONSTRUCTION
 - PAVEMENT CONSTRUCTION THIS PHASE
 - PAVEMENT CONSTRUCTED PREVIOUS PHASE
 - TEMPORARY PAVEMENT CONSTRUCTION
 - CHANNELIZING DRUMS @ 45' C-C
 - LOW PROFILE CONCRETE BARRIER
 - WK ZN PAV MRK REMOV (W) 4" (SLD)
 - WK ZN PAV MRK REMOV (Y) 4" (SLD) (DBL)



2 YEAR TEMPORARY FLEXIBLE PAVEMENT
5" SP-C PG64-22 SAC B
8" LTS @ 4% LIME/SUBGRADE




| REV NO. | DATE | BY | REVISION |
|---------|------|----|----------|
| | | | |



Chansothi
11/15/2022

AECOM 19219 KATY FREEWAY
SUITE 100
AECOM Technical Services Inc. 3580 HOUSTON, TX 77094



SH 5










TRAFFIC CONTROL PLAN
TYPICAL SECTIONS


SHEET 1 OF 2

| | | | | |
|------------|---------------------|-----------------|------------------|--------------|
| DSN: CC | FED. RD. DIV. NO. 6 | PROJECT NO. | | SHEET NO. 42 |
| CK: CO | | SEE TITLE SHEET | | |
| DRN: JM | STATE | DIST. | COUNTY | |
| APPVD: DH | TEXAS | 18 | COLLIN | |
| CONT. 0047 | SECT. 04 | JOB 031 | HIGHWAY NO. SH 5 | |

ADDENDUM #1, 11/15/22, REPLACE SHEET


11/15/2022 9:09:04 AM c:\pw\work\ingdi\1\khu\an_bazar\vaani@aecom.com\dms05527\SEG1_TCP_TYP_01.DGN

- LEGEND:**
-  CONSTRUCTION ZONE THIS PHASE
 -  FAST TRACK PAVEMENT CONSTRUCTION
 -  PAVEMENT CONSTRUCTION THIS PHASE
 -  PAVEMENT CONSTRUCTED PREVIOUS PHASE
 -  TEMPORARY PAVEMENT CONSTRUCTION
 -  CHANNELIZING DRUMS @ 45' C-C
 -  LOW PROFILE CONCRETE BARRIER
 -  WK ZN PAV MRK REMOV (W) 4" (SLD)
 -  WK ZN PAV MRK REMOV (Y) 4" (SLD) (DBL)




2 YEAR TEMPORARY FLEXIBLE PAVEMENT
 5" SP-C PG64-22 SAC B
 8" LTS @ 4% LIME/SUBGRADE

| REV. NO. | DATE | BY | REVISION |
|----------|------|----|----------|
| | | | |




Chansothi

11/15/2022



19219 KATY FREEWAY
 SUITE 100
 HOUSTON, TX 77094




Texas Department
 of Transportation

SH 5

TRAFFIC CONTROL PLAN
 TYPICAL SECTIONS

SHEET 2 OF 2

| | | | |
|------------|---------------------|-----------------|------------------|
| DSN: CC | FED. RD. DIV. NO. 6 | PROJECT NO. | SHEET NO. 43 |
| CK: CO | STATE | SEE TITLE SHEET | |
| DRN: JM | TEXAS | DIST. 18 | COUNTY COLLIN |
| APPVD: DH | | JOB 031 | HIGHWAY NO. SH 5 |
| CONT. 0047 | SECT. 04 | | |

 ADDENDUM #1, 11/15/22, REPLACE SHEET

11/15/2022 9:09:10 AM
 c:\p_w\work\ingdi\1\khu\an_bazar\vaani@aecom.com\dms05527\SEG1_TCP_TYP_04.DGN

REINFORCED CONCRETE PIPE


EXCAVATION AND BACKFILL QUANTITIES

| PIPE DIA. IN. | T FT. | CULVERT OR SEWER EXCAVATION IN A PAVED OR GRADED AREA | CEMENT STABILIZED BACKFILL IN A PAVED OR GRADED AREA |
|------------------|----------|---|--|
| | | C.Y.PER L.F.PER FT.OF DEPTH | C.Y.PER L.F. OF PIPE |
| 18 | 0.19 | 0.144 | 0.383 |
| 24 | 0.23 | 0.165 | 0.478 |
| 30 | 0.29 | 0.188 | 0.586 |
| 36 | 0.33 | 0.210 | 0.692 |
| 42 | 0.38 | 0.231 | 0.808 |
| 48 | 0.42 | 0.327 | 1.394 |
| 54 | 0.46 | 0.349 | 1.560 |
| 60 | 0.50 | 0.370 | 1.731 |
| 66 | 0.54 | 0.392 | 1.907 |
| 72 | 0.58 | 0.414 | 2.088 |
| 78 | 0.62 | 0.435 | 2.275 |
| 84 | 0.67 | 0.457 | 2.474 |


MONOLITHIC PIPE

EXCAVATION QUANTITIES


| PIPE DIA. IN. | T FT. | EXCAVATION | |
|------------------|----------|-----------------------------|----------------------|
| | | C.Y.PER L.F.PER FT.OF DEPTH | C.Y.PER L.F. OF PIPE |
| 36 | 0.417 | 0.142 | |
| 42 | 0.458 | 0.164 | |
| 48 | 0.458 | 0.182 | |
| 54 | 0.500 | 0.204 | |
| 60 | 0.583 | 0.228 | |
| 66 | 0.583 | 0.247 | |
| 72 | 0.625 | 0.269 | |
| 78 | 0.625 | 0.287 | |
| 84 | 0.625 | 0.306 | |



EXCAVATION DETAIL
MONOLITHIC PIPE
IN A PAVED OR GRADED AREA



BACKFILL DETAIL
BOX CULVERTS
IN A GRADED OR PAVED AREA
INCLUDING DETOURS *



EXCAVATION DETAIL
BOX CULVERTS
IN A GRADED AREA

NOTE:
Cement stabilized backfill may be omitted in private driveways as indicated elsewhere in the plans.
Rubber gaskets shall be required for all joints on proposed cross drainage, pipe culverts and proposed storm sewer systems, unless otherwise shown in the plans.
Backfill with cement stabilized material will be required for all structures under detours unless noted otherwise in the General Notes.


SHEET 1 OF 1

Texas Department of Transportation


EXCAVATION AND BACKFILL DIAGRAMS

E&BD

| | | | | |
|---|-----------|-----------|-----------------------------|------------|
| FILE: STDE1.DGN | DW: TxDot | CK: TxDot | DW: TxDot | CK: TxDot |
| © TxDOT FEB 2010 | DIST 18 | FED REG 6 | PROJECT NO. SEE TITLE SHEET | SHEET 330A |
| REVISIONS | COUNTY | CONTROL | SECT | JOB |
| REVIS 11/15/22 | COLLIN | 0047 | 04 | 031 |
| REVIS 2/2010 Added note to Table 1, Sht 2 of 2. | | | | |
| REVIS 6/12 | | | | |
| REVIS 9/14 | | | | |



EXCAVATION & BACKFILL DETAIL
REINFORCED CONCRETE PIPE
IN A GRADED OR PAVED AREA
INCLUDING DETOURS



BACKFILL DETAIL
AT MANHOLE, INLET OR JUNCTION BOX

STATE OF TEXAS
CURTIS W. WHITE
113382
LICENSED PROFESSIONAL ENGINEER
Curtis W. White
11/15/2022

ADDENDUM #1, 11/15/22, NEW SHEET

D = Depth
H = Height
T = Thickness
R = Radius
Dia = Diameter