```
SUBJECT: PLANS AND PROPOSAL ADDENDUMS
      PROJECT: BR 2023 (404) CONTROL: 0035-04-039
      COUNTY: CONCHO
       LETTING: 02/01/2023
      REFERENCE NO: 0131
                         PROPOSAL ADDENDUMS
   PROPOSAL COVER
X BID INSERTS (SH. NO.: 1 - 4
_ GENERAL NOTES (SH. NO.:
X SPEC LIST
              (SH. NO.: 1 - 3
  SPECIAL PROVISIONS:
  ADDED:
      DELETED:
  SPECIAL SPECIFICATIONS:
  ADDED:
      DELETED:
X OTHER: PLAN SHEETS AND OTHER CHANGES
DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)
***** BID INSERTS *****
ADDED THE FOLLOWING BID ITEMS: 428-6001, 429-6002, 483-6006, 512-6001,
512-6049, 545-6005
DELETED THE FOLLOWING BID ITEMS: 427-6007, 483-6012, 495-6001, 512-6013,
512-6037, 545-6004
***** SPECIFICATION LIST *****
ADDED THE FOLLOWING PAY ITEMS: 428
DELETED THE FOLLOWING PAY ITEMS: 427, 495
***** PLAN SHEETS *****
SHEET 2: REMOVED SHEET 38
DESCRIPTION OF ABOVE CHANGES
                                                               (CONTINUED)
```

)

(INCLUDING PLANS SHEET CHANGES)

SHEET 4: QUANTITIES REVISED DUE TO ABOVE CHANGES

SHEET 5, 7: REVISED TRAFFIC CONTROL PLAN

SHEET 25: REVISED RAIL REPAIR DETAILS

SHEET 26: REVISED SUBSTRUCTURE REPAIR DETAILS

SHEET 30: REVISED JOINT DETAILS

SHEET 36-37: RAIL RETROFIT SHEETS REMOVED AND REPLACED WITH T203

STANDARDS

SHEET 38: SHEET OMITTED

GENERAL

TITLE SHEET INDEX OF SHEETS

PROJECT LOCATION MAP 3A-3C GENERAL NOTES

SUMMARY OF BRIDGE QUANTITIE

TRAFFIC CONTROL PLAN TRAFFIC CONTROL PLAN TYPICAL SECTION ADVANCED WARNING SIGNS TRAFFIC CONTROL PLAN NARRATIVE 2

TRAFFIC CONTROL PLAN STANDARDS

ABSORB (M) -19 ## 8 BC(1)-21 ## 9 BC(2)-21 ## 10 ## 11 BC(3)-21 BC(4)-21 ## 12 BC(5)-21 ## 13 BC(6)-21 ## 14 ## 15 BC(7)-21 ## 16 BC(8)-21 ## 17 BC (9) -21 ## 18 BC(10)-21 ## 19 BC(11)-21 BC(12)-21 ## 20 ## 21 TCP(2-5)-18 ## 22 TCP (SC-3)-21 **##** 23 SLED-19 ## 24 SLEDMINI-19

> BRIDGE-ROADWAY LOCATION O1 REPAIR LAYOUT LOCATION O1 SUBSTRUCTURE REPAIR

> > ROADWAY STANDARDS

27-28 CRCP(1)-20

£25

} 26

31-34

BRIDGE DETAILS BRIDGE SPALL REPAIR DETAILS {30 BRIDGE TYPE A JOINT REPAIR DETAILS

BRIDGE STANDARDS

C-RAIL-R SEJ-M 36-37 TYPE T203 OMITTED 38

PAVEMENT MARKING PAVEMENT MARKING LAYOUT

39

PAVEMENT MARKING STANDARD

40-42 PM(1)-20 THRU PM(3)-20 PM(4)-22

ENVIRONMENTAL ISSUES 44

SW3P LAYOUT 45 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

ENVIRONMENTAL ISSUES STANDARDS

*** 46 EC (1)-16

*** 47-49 EC (9)-16



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET ## HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

ALFONSO D. PEREZ 1/31/2023 NAME DATE



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET *** HAVE BEEN ISSUED BY ME AND ARE APPLICABLE TO THIS PROJECT.

1/31/2023 KENNETH E. GOTTLEABER DATE NAME





Texas Department of Transportation

US 83

INDEX OF SHEETS

HARDIN CREEK 07-048-0-0035-04-016

ID. 10.	STATE	F.E.	DERAL AID	PROJECT	SHEET NO.	.04
	TEXAS	В	R 2023(4	04)	2	X 1 Z
E ICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.	3024
Г	CONCHO	0035	04	039	US 83	D18

	SUMMARY OF BRIDGE ITEMS									
	361	428	429	429	438	439	454 V	483	483	778
	6079	6001	6002	6007	6004	6016	6021	6006 <	6017	6015
LOCATION	FULL-DEPTH REPAIR CRCP (12"-14")	PENETRATING CONCRETE SURFACE TREATMENT	CONC STR REPAIR (EPOXY MORTAR)	CONC STR REPAIR (VERTICAL & OVERHEAD)	CLEANING AND SEALING EXIST JOINTS (CL 7)	CL CO CONC OVRLY(STL FBR REIN)(5 1/2IN)	TYPE A JOINT	HYDRO- DEMOLITION < (1 1/2 IN) <	MILLING CONCRETE SLAB (3IN)	CONCRETE RAIL REPLACEMENT (TYPE 203)
	SY	SY	SF	SF	LF	SY	LF	SY <	SY	LF
CSJ: 0035-04-039	167	889	20	40	220	962	348	962 <	962	100
PROJECT TOTALS	167	889	20	40	220	962	348	962	962	100

			SUMM	ARY OF PAVEMENT	MARKINGS ITEMS					
	666 6167	666 6205	666 6207	666 6300	666 6312	666 6315	672 6007	672 6009	678 6001	678 6033
LOCATION	REFL PAV MRK TY II (W) 4" (BRK)	REFL PAV MRK TY II (Y) 4" (BRK)	REFL PAV MRK TY II (Y) 4" (SLD)	RE PM W/RET REQ TY I (W)4"(BRK)(10 ØMIL)	RE PM W/RET REQ TY I (Y)4"(BRK)(10 ØMIL)	RE PM W/RET REQ TY I (Y)4"(SLD)(10 ØMIL)	REFL PAV MRKR TY I-C	REFL PAV MRKR TY II-A-A	PAV SURF PREP FOR MRK (4")	PAV SURF PREP FOR MRK (RPM)
	LF	LF	LF	LF	LF	LF	EA	EA	LF	EA
CSJ: 0035-04-039	200	200	200	200	200	200	10	10	1200	20
PROJECT TOTALS	200	200	200	200	200	200	10	10	1200	20

	SUMMARY OF EROSION CONTROL ITEMS							
	506 6021	506 6024	506 6035	506 6038	506 6039	506 6040	506 6043	
LOCATION	CONSTRUCTION EXITS (INSTALL) (TY 2)	CONSTRUCTION EXITS (REMOVE)	SANDBAGS FOR EROSION CONTROL	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)	BIODEG EROSN CONT LOGS (INSTL) (8")	BIODEG EROSN CONT LOGS (REMOVE)	
	SY	SY	EA	LF	LF	LF	LF	
CSJ: 0035-04-039	78	78	76	300	300	400	400	
PROJECT TOTALS	78	78	76	300	300	400	400	

Δ	1/18/2023 1/27/2023		AP
NO.	DATE	REVISION	APPROV.
		conso	r




US 83

SUMMARY OF QUANTITIES

HARDIN CREEK 07-048-0-0035-04-016 SHEET 1 OF 1

				JIILLI I	01 1	1
FED.RD. DIV.NO.	STATE	F.E.	DERAL AID	PROJECT	SHEET NO.	.04
6	TEXAS	Ві	R 2023(4)	04)	4	XLL
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.	3024
SJT	CONCHO	0035	04	039	US 83	D18
n Files\0	l general\02.	HARDIN C	REEK\C (016 S Quantit	v Summarv.dar	í



LOCATION	DIRECTION	FACILITY CROSSED	NBI =	LAT/LONG	PROPOSED WORK	TCP NARRATIVE	PROPOSED TCP STANDARD
Ø1	US 83 NB & SB LANES	HARDIN CREEK	07-048-0-0035-04-016	LAT: 31.20743 LONG:-99.84531	(-REMOVE DCO BY MILLING & (HYDRODEMOLITION. INSTALL NEW CL.)CO OVRLY (STL FBR REIN)(5 1/2 IN). AND TYPE A JOINTS. CLEAN AND (SEAL EXISTING DECK JOINTS. (REMOVE PORTIONS EXISTING (RAILING, PLACE NEW T203)RAILING, AND REPAIR CONC SPALLS. CRCP FULL (DEPTH REPAIR.	-COMPLETE WORK ON CENTER TURNING LANE AND INSIDE LANES ON PHASE 1. COMPLETE WORK ON OUTSIDE LANES ON PHASE 2.USE PCB AT THIS LOCATION AS SHOWN ON STANDARD FOR LANE CLOSURE.	TCP (SC-3a) CENTER LANES CLOSED CONTROL W/ PCTB & TCP (2-5a) TRAFFIC ONE LANE CLOSED.
)	

LEGEND

WORK ZONE

PROPOSED TRAFFIC

NOTES

1.APPLY TRAFFIC CONTROL PLAN SETUP AS DESCRIBED IN THE TCP TABLE UNLESS OTHERWISE DIRECTED BY THE ENGINEER. 2.PROVIDE AND MAINTAIN ALL BARRICADES, WARNING SIGNS AND TRAFFIC CONTROL DEVICES IN CONFORMANCE WITH TXDOT BC AND TCP STANDARDS, AND PART VI OF THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

SCALE: NTS







Texas Department of Transportation

US 83 TRAFFIC CONTROL PLAN TYPICAL SECTIONS

HARDIN CREEK 07-048-0-0035-04-016

SHEET 1 OF 1 STATE FEDERAL AID PROJECT TEXAS
 DISTRICT
 COUNTY
 NO.
 NO.
 NO.

 SJT
 CONCHO
 0035
 04
 039

GENERAL:

1. TRAFFIC MUST BE HANDLED THROUGHOUT THE PROJECT DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SAFE AND COMFORTABLE PASSAGE FOR VEHICULAR TRAFFIC WITH MINIMAL INCONVENIENCE TO THE PUBLIC, AS SHOWN IN THE PLANS OR AS DIRECTED AND APPROVED BY THE ENGINEER.

2. THE CONTRACTOR MAY PROPOSE OR RECOMMEND MODIFICATIONS TO THE SEQUENCE OF CONSTRUCTION FOR CONSIDERATION BY THE ENGINEER, ANY MAJOR RECOMMENDED MODIFICATION BY THE CONTRACTOR SHALL INCLUDE ANY CHANGES TO THE VARIOUS BID ITEMS, IMPACT TO TRAFFIC, AND EFFECT OF OVERALL PROJECT IN TIME AND COST. IF THIS PROPOSAL IS IMPLEMENTED, THE CONTRACTOR WILL BE RESPONSIBLE FOR DEVELOPING DETAILED PLAN SHEETS TO BE SEALED BY A LICENSED PROFESSIONAL ENGINEER FOR INCLUSION WITH THE CHANGE ORDER. THE CONTRACTOR CANNOT PROCEED WITH ANY CONSTRUCTION OPERATIONS BASED ON A REVISED PHASE OR SEQUENCE UNTIL WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER. IF AT ANY TIME, DURING CONSTRUCTION, THE CONTRACTOR'S PROPOSED PLAN OF OPERATION FOR HANDLING TRAFFIC DOES NOT PROVIDE FOR SAFE AND COMFORTABLE MOVEMENT, THE CONTRACTOR WILL IMMEDIATELY CHANGE THEIR OPERATION TO CORRECT THE UNSATISFACTORY CONDITION.

3. TEMPORARY DRAINAGE IS THE RESPONSIBILITY OF THE CONTRACTOR. ENSURE ADEQUATE POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.

4. DO NOT STORE ANY CONSTRUCTION MATERIAL OR EQUIPMENT AT ANY LOCATION THAT WILL CONSTITUTE A HAZARD AND WILL ENDANGER TRAFFIC.

5. THE CONTRACTOR WILL NOTIFY THE ENGINEER IN WRITING OF UPCOMING LANE CLOSURES 10 BUSINESS DAYS IN ADVANCE FOR ALL TEMPORARY CLOSURES OR DETOURS.

6. ACCESS TO ADJOINING PROPERTY MUST BE MAINTAINED AT ALL TIMES.

7. NO EQUIPMENT WILL BE LEFT WITHIN 30 FEET OF TRAVEL WAY AFTER WORKING HOURS UNLESS LOCATED BEHIND TRAFFIC BARRIER.

8. REMOVAL AND DISPOSAL OF EXISTING ABANDONED UTILITIES (EITHER PREVIOUSLY ABANDONED OR ABANDONED DURING THIS PROJECT) REQUIRED TO SUPPORT THIS PROJECT'S CONSTRUCTION WILL BE PERFORMED UNDER THE OVERALL PREPARING RIGHT OR WAY ITEM (ITEM 100).

9. COVER PERMANENT SIGNS IF NOT USED. PAYMENT WILL BE CONSIDERED SUBSIDIARY TO ITEM 502.

10.SEE BC STANDARDS AND THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) FOR SIGN SPACING AND LOCATION REQUIREMENTS NOT SHOWN IN THE PLANS.

11.SEE THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) FOR CHANNELIZING DEVICE SPACING REQUIREMENTS NOT SHOWN IN THE PLANS.

12.WORK ZONE PAVEMENT MARKINGS WILL BE RAISED PAVEMENT MARKERS ON THE NEW BRIDGE AND WILL BE PAID FOR UNDER ITEM 672.

13.THE CONTRACTOR WILL PROVIDE, CONSTRUCT, AND MAINTAIN ALL BARRICADES AND SIGNS IN ACCORDANCE WITH STATE STANDARDS. ANY SIGNS REQUIRED THAT ARE NOT DETAILED IN THE STANDARD SHEETS SHALL BE IN CONFORMANCE WITH THE LATEST TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD) AND THE STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS.

14.BARRICADES AND WARNING SIGNS SHALL BE PLACED AS SHOWN ON THE PLANS. THIS SHALL BE CONSIDERED THE MINIMUM REQUIRED TO PROVIDE FOR THE SAFETY OF TRAFFIC DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN OTHER SUCH BARRICADES AND SIGNS DEEMED NECESSARY BY THE ENGINEER OR AS DIRECTED BY FIELD CONDITIONS TO PROVIDE FOR THE SAFE PASSAGE OF TRAFFIC AT ALL TIMES.

15.THE CONTRACTOR SHALL PROVIDE AND MAINTAIN FLAGGERS AS DIRECTED AND APPROVED BY THE ENGINEER, AT SUCH POINTS, AND FOR SUCH PERIODS OR TIME AS MAY BE REQUIRED, TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC AND THE CONTRACTOR'S PERSONNEL.

16.THE CONTRACTOR SHALL KEEP THE ROADWAY CLEAN AND FREE OF DIRT OR OTHER MATERIALS DURING HAULING OPERATIONS. IF THE CONTRACTOR DOES NOT MAINTAIN A CLEAN ROADWAY, THEY SHALL CEASE ALL CONSTRUCTION OPERATIONS, WHEN DIRECTED BY THE ENGINEER, TO CLEAN THE ROADWAY TO THE SATISFACTION OF THE ENGINEER.

17.THE USE OF RUBBER-TIRED EQUIPMENT WILL BE REQUIRED FOR MOVING DIRT OR OTHER MATERIALS ALONG OR ACROSS PAVEMENT SURFACES. WHERE THE CONTRACTOR DESIRES TO MOVE ANY EQUIPMENT NOT LICENSED FOR OPERATION ON PUBLIC HIGHWAYS, ON OR ACROSS PAVEMENT, THEY SHALL PROTECT THE PAVEMENT FROM DAMAGE AS DIRECTED AND APPROVED BY THE ENGINEER.

18.THROUGHOUT CONSTRUCTION OPERATIONS, THE CONTRACTOR WILL BE REQUIRED TO CONDUCT THEIR HAULING OPERATIONS IN A MANNER SUCH THAT VEHICLES WILL NOT HAUL OVER PERVIOUSLY RE-COMPACTED SUBGRADE OR COMPACTED BASE MATERIAL, EXCEPT IN SHORT SECTIONS FOR DUMPING MANIPULATIONS.

19,UPON COMPLETION OF THE WORK AND BEFORE FINAL ACCEPTANCE AND FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL CLEAR AND REMOVE FROM THE SITE ALL SURPLUS AND DISCARDED MATERIALS AND DEBRIS OF EVERY KIND LEAVING THE ENTIRE PROJECT IN A SMOOTH, NEAT, AND SIGHTLY CONDITION.

20.ALL BARRICADES, SIGNS, AND FLAGGERS WILL BE PAID UNDER ITEM 502 "BARRICADES, SIGNS, AND TRAFFIC HANDLING". ALL EROSION AND SEDIMENT CONTROL DEVICES WILL BE PAID UNDER ITEM 506 "TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS". ALL WORK ZONE PAVEMENT MARKINGS WILL BE PAID UNDER ITEM 662 "WORK ZONE PAVEMENT MARKINGS" UNLESS OTHERWISE NOTED. ALL OTHER WORK AND MATERIALS WILL BE CONSIDERED SUBSIDIARY TO THE VARIOUS BID ITEMS UNLESS OTHERWISE INDICATED IN THE PLANS.

SEQUENCE OF CONSTRUCTION:

1. PREPARING RIGHT OF WAY AND REMOVAL OF EXISTING ITEMS TO BE DONE ONLY IN AREAS WHERE CONSTRUCTION IS OCCURING, AS PER THE PHASES NOTED BELOW.

2. PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS), PER TMUTCD, SHALL BE PLACED 7 CALENDAR DAYS IN ADVANCE OF LANE CLOSURES AND CHANGES IN TRAFFIC PATTERNS. THE ENGINEER SHALL APPROVE THE LOCATION OF PCMS PRIOR TO PLACEMENT AND/OR RELOCATION. THE ENGINEER SHALL APPROVE THE WORDING OF THE PCMS.

PHASE 1:

- 1. INSTALL ADVANCE WARNING SIGNS ACCORDING TO THE BC STANDARDS AND THE LATEST TMUTCD.
- 2. FURNISH AND PLACE PCMS IN AN UNOBSCURED LOCATION AT PROJECT LIMITS TO ALERT MOTORISTS OF UPCOMING CHANGES IN TRAFFIC PATTERN AS DIRECTED BY THE ENGINEER.
- 3. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS.

4.INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS, TYPICAL SECTIONS, AND APPLICABLE TCP STANDARDS.

5. INSTALL PCTBs ONLY TO THE LIMITS OF BRIDGE AND BUFFER DISTANCE ALL OTHER CHANNELIZING DEVICES SHALL BE PLASTIC DRUMS.

6. PREPARE ROW IN ACCORDANCE WITH THE PLANS.

7. REMOVE DCO AS SHOWN ON PLANS, INSTALL NEW CL CO OVRLY (STL FBR REIN) (5 1/2 IN) AND TYPE A JOINT, REPAIR SPALLS AND INSTALL PAVEMENT MARKINGS FOR THE LIMITS ALONG THE SB LANES.

PHASE 2:

1. FURNISH AND PLACE PCMS IN AN UNOBSCURED LOCATION AT PROJECT LIMITS TO ALERT MOTORISTS OF UPCOMING CHANGES IN TRAFFIC PATTERN AS DIRECTED BY THE ENGINEER.

2. INSTALL TEMPORARY EROSION CONTROL IN ACCORDANCE WITH THE PLANS.

3. INSTALL SHOULDER WORK TRAFFIC CONTROL AND SET UP TRAFFIC CONTROL IN ACCORDANCE WITH THE TCP LAYOUTS. TYPICAL SECTIONS, AND APPLICABLE TCP STANDARDS.

5. INSTALL PCTBs ONLY TO THE LIMITS OF BRIDGE AND BUFFER DISTANCE, ALL OTHER CHANNELIZING DEVICES SHALL BE PLASTIC DRUMS.

6. PREPARE ROW IN ACCORDANCE WITH THE PLANS.

7. CLEAN AND SEAL EXISTING JOINTS. REMOVE/REPLACE T203 RAIL. CRCP FULL DEPTH REPAIR.

PHASE 3:

1. REMOVE ANY TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THE PLANS.

SCALE: NTS



1/27/2023 TRAFFIC CONTROL PLAN NARRATIVE REVISED AP

NO. DATE REVISION APPRO






US 83
TRAFFIC CONTROL PLAN
NARRATIVE


HARDIN CREEK 07-048-0-0035-04-016 SHEET 1 OF 1

			_	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	٠, ١	1
FED.RD. DIV.NO.	STATE	F.E.	DERAL AID	PROJECT	SHEET NO.	.04
6	TEXAS	В	R 2023(4	04)	7	71X
STATE DISTRICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.	3024
SJT	CONCHO	0035	04	039	US 83	916

VITTO NTO SELES NA 2013 NA 1902-11 NAM-YI_DESIGN COOLCADD NGIN OF PESSIGN THES NATHREN EN WE. HANDIN CALEAN NEUTO_FITTO TO SELEMENT OF PM.



NO. NO. NO. NO. 0035 04 039





BENT 5 LOOKING NORTH





REPAIR TYPE DESCRIPTION

(A1) MINOR SPALL

CONTRACTOR SHALL COORDINATE
WITH FIELD ENGINEER FOR THE
REMOVAL OF LEAD BEARING SHEETS
UNDERNEATH ALL ORIGINAL T-BEAMS
LOCATIONS. THIS SHALL BE SUBSIDIARY
TO ITEM 429 6007 "CONC STR REPAIR
(VERTICAL & OVERHEAD)"

BEARING SHEET PLATES SHALL BE SUBSIDIARY TO FFEM 495 "RAISING EXISTING STRUCTURE"

SEE "BRIDGE SPALL REPAIR DETAILS" SHEETS FOR REPAIR NOTES, DETAILS AND ADDITIONAL INFORMATION.


ALL CONCRETE ELEMENTS IN SUBSTRUCTURE SHALL BE ITEM 428 6001 "PENETRATING SURFACE TREATMENT."

SCALE: NTS



1/27/2023






Texas Department of Transportation

US 83

LOCATION 01 SUBSTRUCTURE REPAIR HARDIN CREEK 07-048-0-0035-04-016

SHEET 1 OF 1


NO.	STATE	FEI	DERAL AID	PROJECT	NO.	Ò
	TEXAS	BF	2023(40	04)	26	X 1 Z
TE RICT	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.	3024
Τ	CONCHO	0035	04	039	US 83	DIG
1100	DOLL CREEK I	AVOUTC) C	01C C C			•




			BRIDGE QUANTITIES		
^	ITEM	CODE	DESCRIPTION	UNIT	QTY
$\sqrt{2}$	427	6007	FPOXY WATERPROOF FINISH (TY X)	SF	8000
8	428	6001	PENETRATING CONCRETE SURFACE TREATMENT	SY	889
8	429	6002	CONC STR REPAIR (EPOXY MORTAR)	SF	20
^	429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	SF	10
$\sqrt{2}$	495	6001	RAISING EXIST STRUCT	LS	1

 $\overline{A1}$

PM04\1_Design\500_CADD\dgn\01 Master Design Files\Prime\02. HARDIN CREEK LAYOUT5\C_016_S_Section Views Location 02.dgn



JOINT WITH
SILICONE SEAL
(USED WITHOUT ACP OVERLAY)




- 9 USE CLASS 7 SILICONE SEALANT. PREPARE JOINT AND SEAL IN ACCORDANCE WITH ITEM 438 "CLEANING AND SEALING JOINTS."
- BACKER ROD MUST BE 25% LARGER THAN JOINT OPENING AND MUST BE COMPATIBLE WITH THE SEALANT.

PROCEDURE FOR CLEANING AND SEALING EXISTING CONCRETE GIRDER JOINT WITH SILICONE SEAL:

- 1) CLEAN JOINT OPENING OF ALL OLD EXPANSION MATERIALS/DEVICES, DIRT, AND ALL OTHER DELETERIOUS MATERIALS IN ACCORDANCE WITH ITEM 438, "CLEANING AND SEALING JOINTS." CLEAN JOINT OUT FULL DEPTH OF THE JOINT.
- 2) OBTAIN APPROVAL OF CLEANED JOINT PRIOR TO
- 3) PLACE BACKER ROD INTO JOINT OPENING 1"
 BELOW THE TOP OF CONCRETE. THE BACKER ROD
 BUILT DE 150% ADDED THAN THE JOINT OPENING
- 4) SEAL THE JOINT OPENING WITH A CLASS 7 SILICONE. RECESS SEAL ½" BELOW TOP OF CONCRETE IN TRAVEL LANES AND ½" BELOW TOP OF CONCRETE IN SHOULDERS.

CLEANING AND SEALING EXISTING JOINTS



GENERAL NOTES

1 1/4" BACKER ROD MUST BE COMPATIBLE WITH JOINT SEALANT.
USE OF MULTIPLE PIECES TO CREATE A BACKER ROD CROSS
SECTION IS NOT PERMITTED. TOP OF BACKER ROD MUST BE
CONVEX AS SHOWN.

2 IF DAMAGED REINFORCEMENT IS ENCOUNTER DURING DEMOLITION ACTIVITIES, THE CONTRACTOR MUST CLEAN AND STRAIGHTEN EXISTING REINFORCEMENT. REPLACE REINFORCEMENT IF REQUIRED AND DIRECTED BY THE ENGINEER.


(3) CLASS 7 SILICONE SEALANT THAT CONFORMS TO DMS-6310. INSTALL WHEN AMBIENT TEMPERATURE IS BETWEEN (55°F AND 85°F AND RISING.

(4) SEAL JOINT IN ACCORDANCE WITH ITEM 438, CLEANING AND SEALING EXISTING BRIDGE JOINT DETAILS.

(5) NEW CL CO CONC OVRLY (STL FBR REIN) (5 1/21N) SHALL MATCH EXISTING DECK ELEVATION. USE 40LBS/CY OF STEEL FIBER REINFORCEMENT SIZE=2 ½" LONG.

(6) REMOVE EXISTING 2" THICK DCO AND 1" OF EXISTING CONCRETE GIRDER TOP SLAB BY CONCRETE MILLING. USE CONCRETE MILLING EQUIPMENT CAPABLE OF MAINTAINING CONSTANT DEPTH OF CUT SPECIFIED. EQUIPMENT MACHINE WITH AUTOMATED DEBRIS COLLECTION SYSTEM.

(TREMOVE DAMAGE AND LOOSE CONCRETE BY HYDRODEMOLITION UNTIL SOUND CONCRETE IS REACHED. AVOID DAMMAGE TO SOUND CONCRETE.



ABUTMENT JOINT REPAIR 📵

INTERIOR BENT JOINT REPAIR 📵

SCALE: NTS



 ▲
 1/18/2023
 JOINT REVISED

 ▲
 1/18/2023
 DCO. MILLING AND HYDRO-DEMOLITION REVISED

 NO.
 DATE
 REVISION
 A.

CONSOR

© 2023

Texas Department of Transportation

BRIDGE TYPE A JOINT
REPAIR DETAILS

HARDIN CREEK 07-048-0-0035-04-016 SHEET 1 OF

F:_v=1 PD\rf0jetts\ 6:12:14 PM 1/27/2023

