

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: STP 2023 (512) TP

CONTROL: 0314-02-054

COUNTY: PALO PINTO

LETTING: 03/08/2023

REFERENCE NO: 0213

PROPOSAL ADDENDUMS

PROPOSAL COVER

BID INSERTS (SH. NO.:

GENERAL NOTES (SH. NO.:

SPEC LIST (SH. NO.:

SPECIAL PROVISIONS:

ADDED:

DELETED:

SPECIAL SPECIFICATIONS:

ADDED:


DELETED:

X OTHER: See Changes Below



DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

PLAN SHEETS: Sheets 4B, 5 and 5A replaced due to previous changes that were made to the plans estimate/quantities sheet and engineer's estimate.



PALO PINTO COUNTY												
IH20	247 6061	275 6001	275 6010	310 6001	416 6026	416 6029	432 6009	512 6017	540 6001	542 6001	544 6001	3076 6029
	FL BS (CMP IN PLC)(TYA GR1-2) (6")	CEMENT	CEMENT TREAT (SUBGRADE) (8")	PRIME COAT (MULTI OPTION)	DRILL SHAFT (HIGH MAST POLE) (60 IN)	DRILL SHAFT (RDWY ILL POLE) (30 IN)	RIPRAP (CONC) (CL B) (4")	PORT CTB (DES SOURCE)(F -SHAPE)(TY 1)	MTL W-BEAM GD FEN (TIM POST)	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL END TREATMENT (INSTALL)	D-GR HMA TY-C SAC-B PG70-28
	SY	TON	SY	GAL	LF	LF	CY	LF	LF	LF	EA	TON
Quantity	28640	382	28640	2864	80	60	7.22	950	994	994	2	6300
PROJECT TOTALS	28640	382	28640	2864	80	60	7.22	950	994	994	2	6300



Revision #1 - 2/10/2023

ESTIMATE & QUANTITIES				
	FED.RD. DIV.NO.	STATE PROJECT NO.		SHEET NO.
	6	SEE TITLE SHEET		4B
REVISIONS	STATE	DISTRICT	COUNTY	
	TEXAS	FTW	PALO PINTO	
	CONTROL	SECTION	JOB	HIGHWAY NO.
	0314	02	054	IH-20



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0314-02-054

DISTRICT Fort Worth
HIGHWAY IH 20

COUNTY Palo Pinto

CONTROL SECTION JOB				0314-02-054		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00190799			
COUNTY				Palo Pinto			
HIGHWAY				IH 20			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6001	PREPARING ROW	AC	12.430		12.430	
	100-6003	PREPARING ROW(TREE)(5" TO 12" DIA)	EA	23.000		23.000	
	100-6004	PREPARING ROW(TREE)(12" TO 24" DIA)	EA	25.000		25.000	
	100-6007	PREP ROW (TREE)(GREATER THAN 24" DIA)	EA	25.000		25.000	
	104-6015	REMOVING CONC (SIDEWALKS)	SY	656.670		656.670	
	105-6030	REMOVING STAB BASE & ASPH PAV (8"-14")	SY	12,146.000		12,146.000	
	110-6001	EXCAVATION (ROADWAY)	CY	2,694.480		2,694.480	
	247-6061	FL BS (CMP IN PLC)(TYA GR1-2) (6")	SY	28,640.000		28,640.000	
	275-6001	CEMENT	TON	382.000		382.000	
	275-6010	CEMENT TREAT (SUBGRADE) (8")	SY	28,640.000		28,640.000	
	310-6001	PRIME COAT (MULTI OPTION)	GAL	2,864.000		2,864.000	
	416-6026	DRILL SHAFT (HIGH MAST POLE) (60 IN)	LF	80.000		80.000	
	416-6029	DRILL SHAFT (RDWY ILL POLE) (30 IN)	LF	60.000		60.000	
	432-6009	RIPRAP (CONC) (CL B) (4")	CY	7.220		7.220	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		5.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	1,500.000		1,500.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	1,500.000		1,500.000	
	506-6041	BIODEG EROSN CONT LOGS (INSTL) (12")	LF	1,500.000		1,500.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	1,500.000		1,500.000	
	512-6017	PORT CTB (DES SOURCE)(F-SHAPE)(TY 1)	LF	950.000		950.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	994.000		994.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	994.000		994.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	2.000		2.000	
	610-6009	REMOVE RD IL ASM (TRANS-BASE)	EA	7.000		7.000	
	610-6214	IN RD IL (TY SA) 40T-8 (250W EQ) LED	EA	6.000		6.000	
	613-6005	HI MST IL POLE (150 FT)(80 MPH)	EA	2.000		2.000	
	618-6023	CONDT (PVC) (SCH 40) (2")	LF	3,207.000		3,207.000	
	618-6047	CONDT (PVC) (SCH 80) (2") (BORE)	LF	289.000		289.000	
	620-6007	ELEC CONDR (NO.8) BARE	LF	3,568.000		3,568.000	
	620-6008	ELEC CONDR (NO.8) INSULATED	LF	9,948.000		9,948.000	
	624-6010	GROUND BOX TY D (162922)W/APRON	EA	6.000		6.000	
	628-6045	ELC SRV TY A 240/480 060(NS)SS(E)SP(O)	EA	1.000		1.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	476.000		476.000	
	666-6042	REFL PAV MRK TY I (W)12"(SLD)(100MIL)	LF	200.000		200.000	
	666-6174	REFL PAV MRK TY II (W) 6" (SLD)	LF	7,222.000		7,222.000	
	666-6210	REFL PAV MRK TY II (Y) 6" (SLD)	LF	444.000		444.000	



Addendum #1- Revision 2/10/23

DISTRICT	COUNTY	CCSJ	SHEET
Fort Worth	Palo Pinto	0314-02-054	5



Estimate & Quantity Sheet


CONTROLLING PROJECT ID 0314-02-054

DISTRICT Fort Worth

COUNTY Palo Pinto

HIGHWAY IH 20

CONTROL SECTION JOB				0314-02-054		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00190799			
COUNTY				Palo Pinto			
HIGHWAY				IH 20			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	3076-6029	D-GR HMA TY-C SAC-B PG70-28	TON	6,300.000		6,300.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	6156-6001	LED HI MST IL ASM (6 FIXT)(SYM)(TY S)	EA	2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY	120.000		120.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000		1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000		1.000	



Addendum #1-revision 2/10/23