Control	0908-12-027
Project	C 908-12-27
Highway	VA
County	HOWARD

ADDENDUM ACKNOWLEDGMENT

Each bidder is required to acknowledge receipt of an addendum issued for a specific project. This page is provided for the purpose of acknowledging an addendum.

FAILURE TO ACKNOWLEDGE RECEIPT OF AN ADDENDUM WILL RESULT IN THE BID NOT BEING READ.

In order to properly acknowledge an addendum place a mark in the box next to the respective addendum.

ADDENDUM NO. 1	
ADDENDUM NO. 2	
ADDENDUM NO. 3	
ADDENDUM NO. 4	
ADDENDUM NO. 5	

In addition, the bidder by affixing their signature to the signature page of the proposal is acknowledging that they have taken the addendum(s) into consideration when preparing their bid and that the information contained in the addendum will be included in the contract, if awarded by the Commission or other designees.



Control	0908-12-027
Project	C 908-12-27
Highway	VA
County	HOWARD

PROPOSAL TO THE TEXAS TRANSPORTATION COMMISSION

2014 SPECIFICATIONS WORK CONSISTING OF STATE PARK IMPROVEMENTS HOWARD COUNTY, TEXAS

The quantities in the proposal are approximate. The quantities of work and materials may be increased or decreased as considered necessary to complete the work as planned and contemplated.

This project is to be completed in 37 working days and will be accepted when fully completed and finished to the satisfaction of the Executive Director or designee.

Provide a proposal guaranty in the form of a Cashier's Check, Teller's Check (including an Official Check) or Bank Money Order on a State or National Bank or Savings and Loan Association, or State or Federally chartered Credit Union made payable to the Texas Transportation Commission in the following amount:

SEVEN THOUSAND (Dollars) (\$7,000)

A bid bond may be used as the required proposal guaranty. The bond form may be detached from the proposal for completion. The proposal may not be disassembled to remove the bond form. The bond must be in accordance with Item 2 of the specifications.

Any addenda issued amending this proposal and/or the plans that have been acknowledged by the bidder, become part of this proposal.

By signing the proposal the bidder certifies:

- 1. the only persons or parties interested in this proposal are those named and the bidder has not directly or indirectly participated in collusion, entered into an agreement or otherwise taken any action in restraint of free competitive bidding in connection with the above captioned project.
- 2. in the event of the award of a contract, the organization represented will secure bonds for the full amount of the contract.
- 3. the signatory represents and warrants that they are an authorized signatory for the organization for which the bid is submitted and they have full and complete authority to submit this bid on behalf of their firm.
- 4. that the certifications and representations contained in the proposal are true and accurate and the bidder intends the proposal to be taken as a genuine government record.

• Signed: **			
(1)	(2)	(3)	
Print Name:			
(1)	(2)	(3)	
Title: (1)	(2)	(3)	
Company: (1)	(2)	(3)	

• Signatures to comply with Item 2 of the specifications.

^{**}Note: Complete (1) for single venture, through (2) for joint venture and through (3) for triple venture.

^{*} When the working days field contains an asterisk (*) refer to the Special Provisions and General Notes.

NOTICE TO CONTRACTORS

ANY CONTRACTORS INTENDING TO BID ON ANY WORK TO BE AWARDED BY THIS DEPARTMENT MUST SUBMIT A SATISFACTORY "AUDITED FINANCIAL STATEMENT" AND "EXPERIENCE QUESTIONNAIRE" AT LEAST TEN DAYS PRIOR TO THE LETTING DATE.

UNIT PRICES MUST BE SUBMITTED IN ACCORDANCE WITH ITEM 2 OF THE STANDARD SPECIFICATIONS OR SPECIAL PROVISION TO ITEM 2 FOR EACH ITEM LISTED IN THIS PROPOSAL.

TEXAS DEPARTMENT OF TRANSPORTATION

		BID BOND	
KNOW ALL PERSON	NS BY THESE F	PRESENTS,	
That we, (Contractor I	Name)		
Hereinafter called the	Principal, and (S	urety Name)	
Surety, are held and fir the sum of not less that thousand dollars, not to displayed on the cover	mly bound unto n two percent (2' o exceed one hur of the proposal) urselves, our heir	o transact surety business in the State of the Texas Department of Transportatio %) of the department's engineer's estimated thousand dollars (\$100,000) as a to the payment of which sum will and transfer, executors, administrators, successor	on, hereinafter called the Oblige mate, rounded to the nearest on proposal guaranty (amount ruly be made, the said Principal
WHEREAS, the princi	pal has submitte	ed a bid for the following project identi	fied as:
	Control	0908-12-027	
	Project	C 908-12-27	
	Highway	VA	
	County	HOWARD	
the Contract in writing void. If in the event of	with the Obliged failure of the Prette the property of	nall award the Contract to the Principal e in accordance with the terms of such incipal to execute such Contract in acc the Obligee, without recourse of the P	bid, then this bond shall be null cordance with the terms of such
Signed this		Day of	20
Ву:		(Contractor/Principal Name)	
	(Signature an	d Title of Authorized Signatory for Contractor/	Principal)
*By:	_		i inicipai)
•		(Surety Name)	
*Attach Power of attor		(Signature of Attorney-in-Fact) Attorney-in-Fact	Impressed Surety Seal Only
	This for	m may be removed from the prop	oosal.

1-1



BIDDER'S CHECK RETURN

IMPORTANT

The space provided for the return address must be completed to facilitate the return of your bidder's check. Care must be taken to provide a legible, accurate, and <u>complete</u> return address, including zip code. A copy of this sheet should be used for each different return address.

NOTE

Successful bidders will receive their guaranty checks with the executed contract.

RETURN BID	DDERS CHECK TO (PLEASE PRINT):	
	Control	0908-12-027	
	Project	C 908-12-27	
	Highway	VA	
	County	HOWARD	
		IMPORTAN	Т
	PLEASE RI	ETURN THIS SHEE	Γ IN ITS ENTIRETY
Please acknow ink, and return	rledge receipt of this cling this acknowledge	check(s) at your earliest ement in the enclosed sel	convenience by signing below in longhand, in f addressed envelope.
Check Receive	ed By:		Date:
Title:			
For (Contracto	or's Name):		
Project			County



NOTICE TO THE BIDDER

In the space provided below, please enter your total bid amount for this project. Only this figure will be read publicly by the Department at the public bid opening.

It is understood and agreed by the bidder in signing this proposal that the total bid amount entered below is not binding on either the bidder or the Department. It is further agreed that **the official total bid amount** for this proposal will be determined by multiplying the unit bid prices for each pay item by the respective estimated quantities shown in this proposal and then totaling all of the extended amounts.

\$_____ Total Bid Amount

ALT	ITEM	DESC	SP	Bid Item Description	Unit	Quantity	Bid Price	Amount	Seq
	104	509	REM	MOV CONC (SDWLK)	SY	266.400	\$10.000	\$2,664.00	1
						Total Bid Amount	\$2,6	564.00	-
Signed	<u> </u>								
Title									
Date									
Additio	onal Sig	nature f	or Joint Ver	iture:					
Signed	L								
Title									
Date									

Control

Project

0001-03-030

STP 2000(938)HES

EXAMPLE OF BID PRICES SUBMITTED BY COMPUTER PRINTOUT





	ITEM-CODE							DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS		UNIT	APPROX QUANTITIES	USE ONLY
	100	6002		PREPARING ROW		STA	5.500	1
				and	DOLLARS CENTS			
	110	6001		EXCAVATION (ROADWAY) and	DOLLARS CENTS	CY	1,802.000	2
	132	6004		EMBANKMENT (FINAL)(DEN	DOLLARS CENTS	CY	681.000	3
	160	6003		FURNISHING AND PLACING T	TOPSOIL (4") DOLLARS CENTS	SY	3,684.000	4
	164	6057		CELL FBR MLCH SEED(PERM MIX))(SPECIAL DOLLARS CENTS	SY	3,684.000	5
	168	6001		VEGETATIVE WATERING and	DOLLARS CENTS	MG	32.000	6
	169	6002		SOIL RETENTION BLANKETS and	(CL 1) (TY B) DOLLARS CENTS	SY	3,684.000	7
	247	6041	003	FL BS (CMP IN PLC)(TYA GR1	-2)(FNAL POS) DOLLARS CENTS	CY	261.000	8
	310	6009		PRIME COAT (MC-30) and	DOLLARS CENTS	GAL	330.000	9
	316	6017	002	ASPH (AC-20-5TR) and	DOLLARS CENTS	GAL	948.000	10
	316	6175	002	AGGR(TY-B GR-4 SAC-B) and	DOLLARS CENTS	CY	22.000	11

	ITEM-CODE							DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS		UNIT	APPROX QUANTITIES	USE ONLY
	432	6003		RIPRAP (CONC)(6 IN)		CY	49.000	12
					DOLLARS			
				and	CENTS			
	464	6026	001	RC PIPE (CL V)(24 IN)		LF	28.000	13
				1	DOLLARS			
	4.67	6200		and	CENTS	F.4	2 000	1.4
	467	6390		SET (TY II) (24 IN) (RCP) (4:	DOLLARS	EA	2.000	14
				and	CENTS			
	500	6001		MOBILIZATION	CLIVIS	LS	1.000	15
	300	0001		MODIEIZMIOIV	DOLLARS	LS	1.000	13
				and	CENTS			
	502	6001	008	BARRICADES, SIGNS AND	TRAFFIC HAN-	MO	3.000	16
				DLING				
					DOLLARS			
				and	CENTS			
	506	6002	005	ROCK FILTER DAMS (INST	* * *	LF	25.000	17
					DOLLARS			
	5 0.5	5011	005	and	CENTS		25.000	10
	506	6011	005	ROCK FILTER DAMS (REM	<i>'</i>	LF	25.000	18
				and	DOLLARS CENTS			
	506	6041	005	BIODEG EROSN CONT LOC		LF	380.000	19
	300	0041	003	BIODEO ENOSIV CONT LOC	DOLLARS	Li	380.000	1)
				and	CENTS			
	506	6043	005	BIODEG EROSN CONT LOC	GS (REMOVE)	LF	380.000	20
					DOLLARS			
				and	CENTS			
	552	6009		GATE (SPECIAL)		EA	1.000	21
					DOLLARS			
				and	CENTS			
	644	6001		IN SM RD SN SUP&AM TY1	` ' ` '	EA	5.000	22
				1	DOLLARS			
	C11	6002		and	CENTS	EA	1 000	22
	644	6002		IN SM RD SN SUP&AM TY1 BM)	UD W U(1)SA(P-	EA	1.000	23
				<i>D</i>)	DOLLARS			
				and	CENTS			

	ITEM-CODE							DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS		UNIT	APPROX QUANTITIES	USE ONLY
	658	6073		INSTL OM ASSM (OM-2Y)(WC)G	ND(BI) DOLLARS CENTS	EA	2.000	24
	666	6224	007	PAVEMENT SEALER 4" and	DOLLARS CENTS	LF	130.000	25
	666	6232	007	PAVEMENT SEALER (WORD) and	DOLLARS CENTS	EA	2.000	26
	666	6241	007	PAVEMENT SEALER (SYMBOL) and	DOLLARS CENTS	EA	1.000	27
	666	6303	007	RE PM W/RET REQ TY I (W)4"(SI and	D)(100MIL) DOLLARS CENTS	LF	646.000	28
	668	6077		PREFAB PAV MRK TY C (W) (AR)	ROW) DOLLARS CENTS	EA	1.000	29
	668	6085		PREFAB PAV MRK TY C (W) (WO and	PRD) DOLLARS CENTS	EA	3.000	30
	668	6091		PREFAB PAV MRK TY C (W) (18") and)(YLD TRI) DOLLARS CENTS	EA	8.000	31
	668	6114		PRE PM TY C(ACC PRK)(BL&WF BORDR)SM and	H)(W/ DOLLARS CENTS	EA	1.000	32
	678	6001		PAV SURF PREP FOR MRK (4") and	DOLLARS CENTS	LF	130.000	33
	678	6016		PAV SURF PREP FOR MRK (WOR	D) DOLLARS CENTS	EA	2.000	34
	678	6021		PAV SURF PREP FOR MRK (SYM) and	BOL) DOLLARS CENTS	EA	1.000	35

PROJECT C 908-12-27 COUNTY HOWARD Proposal Sheet TxDOT FORM 234-B I-61-5M

	ITEM-CODE		ЭE				DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	USE ONLY
	5008	6001		WHEEL STOPS	EA	20.000	36
				DOLLARS			
				and CENTS			

CERTIFICATION OF INTEREST IN OTHER BID PROPOSALS FOR THIS WORK

By signing this proposal, the bidding firm and the signer certify that the following information, as indicated by checking "Yes" or "No" below, is true, accurate, and complete.

A.	Quotation(s) have been issued in this firm's name to other firm(s) interested in this work for consideration for performing a portion of this work.
	YES
	NO

- B. If this proposal is the low bid, the bidder agrees to provide the following information prior to award of the contract.
 - 1. Identify firms which bid as a prime contractor and from which the bidder received quotations for work on this project.
 - 2. Identify all the firms which bid as a prime contractor to which the bidder gave quotations for work on this project.

ENGINEER SEAL

Control 0908-12-027

Project C 908-12-27

Highway VA

County HOWARD

The enclosed Texas Department of Transportation Specifications, Special Specifications, Special Provisions, General Notes and Specification Data in this document have been selected by me, or under my responsible supervision as being applicable to this project. Alteration of a sealed document without proper notification to the responsible engineer is an offense under the Texas Engineering Practice Act.



The seal appearing on this document was authorized by Stephen T. Jones, P.E. FEBRUARY 02, 2023

ABILENE DISTRICT GENERAL NOTES 2014 SPECIFICATIONS

General

Contractor questions on this project are to be addressed to the following individual(s):

Ryan R. Sayles, P.E. / Phone: 432-263-4768 / Ryan.Sayles@txdot.gov (Big Spring Area Office)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

For Q&A's on Proposals navigate to

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

Use the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

All relevant project documentation including contract time, cross sections, etc will be posted on the districts FTP website. https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/

Failure to make necessary corrections to SW3P based on SW3P inspections will be cause for withholding the monthly estimate until such corrections have been made.

Failure to make necessary corrections to traffic control items based on barricade inspections will be cause for withholding the monthly estimate until such corrections have been made.

Provide ingress/egress to the adjacent properties in areas under construction. Phased construction of driveways and streets shall be required to provide uninterrupted access to adjacent properties. Coordinate work with the property owners before beginning any construction in the vicinity of the drive.

Cut neat, straight lines with vertical faces along pavement edges or along joints between existing asphalt or concrete pavement and new pavement perpendicular or parallel to the direction of traffic by methods described in applicable bid items, or as directed. Provide clean edges or joints without jagged appearance or chunks broken out. This work is considered subsidiary to various bid items.

General Notes

Sheet A

The Contractor is required to coordinate with the Texas Parks and Wildlife Department (TPWD) and adjust construction efforts with the daily operations of the park. Establishment of any material and/or equipment staging or storage areas other than those shown on the plans must be approved by the engineer and the park superintendent prior to the start of work and thereafter if a change of location becomes necessary. As part of this coordination the contractor will be required to:

- 1. Hold a weekly meeting with a TxDOT representative, the park superintendent, and the contractor's superintendent to review and discuss the construction work and traffic control procedures planned for the following two week period.
- 2. Prior to the start of construction, delineate the limits of the work area with stakes and flagging to identify where non-work areas begin so that damage to adjacent park property by construction equipment and other vehicles is avoided.
- 3. Not be authorized to work on weekends or major holidays without prior written approval of both the engineer and the park superintendent.
- 4. Mitigate or replace unnecessary damage to trees or shrubs within and adjacent to the limits of construction. The contractor shall replace or mitigate damaged trees or shrubs with like size and types of trees or shrubs damaged. Final determination of the replacement or mitigation requirements will be determined by the TxDOT Landscape Architect. All cost associated with the replacement or mitigation cost will be the responsibility of the contractor.
- 5. Repair or replace any unnecessary damage to arbors or utilities within and adjacent to the limits of construction. Any replacement cost will be the responsibility of the contractor.
- 6. Archeological monitoring will be provided by TPWD during construction activities in the flagged areas. As such the contractor will be required to notify TPWD's archeological monitor (Tim Roberts, 432-557-0130) before any ground disturbing work can be performed on any phase of the project within that area. Lead time for the notification should take place at the weekly meeting but not less than two weeks in advance.

Environmental

Endangered and Protected Species

- 1. Migratory Birds
 - a. Bird nesting season is typically 15Feb through 15Sep annually.
 - b. The Contractor will avoid disturbing, destroying, removing, or relocating migratory birds and active nests found in trees, culverts, bridges, on the ground, or anywhere they are encountered.
 - c. Perform all tree trimming and other vegetation clearing activities during the non-breeding season (typically 15Sep-15Feb annually). Perform any inactive nest removal and bird exclusion methods to prevent birds from establishing nests. Phasing of work during construction may be necessary to stay in compliance.

- d. When active nests are unexpectedly encountered on-site during construction, the Contractor will stop work and immediately notify the Engineer. Take measures to avoid disturbance of these birds, their occupied nest, eggs, and/or young, in accordance with the Migratory Bird Treaty Act, Texas Parks and Wildlife Code, and TxDOT policy.
- e. The Engineer will notify the Contractor when work may resume.
- f. The Contractor should be prepared to prevent migratory birds from building nests by utilizing nest prevention methods, such as bird-deterrent netting and bird-repelling sprays and/or gels, between 15Feb and 15Sep. The Contractor can discuss other preventative measures with the Engineer and/or District Environmental Staff.

Best Management Practices

1. Bird BMPs

- a. Not disturbing, destroying, or removing active nests, including ground nesting birds, during the nesting season.
- b. Avoiding the removal of unoccupied, inactive nests, as practicable.
- c. Preventing the establishment of active nests during the nesting season on TxDOT owned and operated facilities and structures proposed for replacement or repair.
- d. Not collecting, capturing, relocating, or transporting birds, eggs, young, or active nests without a permit.

Item 5, "Control of Work"

Use Method C for construction surveying.

Make necessary arrangements with utility owners regarding temporary protections such as bracing power poles, and de-energizing power lines. The Department will not reimburse the cost of such temporary protections to the Contractor, unless the Engineer determines that inadequate information was available at the time the project was bid. "Call Before You Dig" "Call 811"

Excavation areas must be staked prior to the notification so that the underground utilities can be located in relationship to the proposed work. Preserve and document the marked utility locations to prevent unnecessary secondary notifications. Notify the Engineer of conflicts between proposed work and underground utilities.

Prior to construction, delineate the limits of the work area with stakes and flagging to identify where non-work areas begin so that damage to adjacent park property by construction equipment and other vehicles is avoided.

Item 7, "Legal Relations and Responsibilities"

The total area disturbed for this project is 1.0 acres. The disturbed area in this project, all project locations in the Contract, and the Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain required authorization from the TCEQ for Contractor PSLs for construction support activities on or off the ROW. When the total area disturbed in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer and to the government that operates a separate storm sewer system.

Provide one SW3P Notification Board for this project. Notification Boards are to be placed at locations within the right-of-way but outside the clear zone as directed by the Engineer. Consider this work to be subsidiary to the various bid items of the contract.

The Contractor's attention is directed to the Texas Aggregate Quarry Pit Safety Act. Any pit or quarry meeting the definition of an unacceptable unsafe location as defined in the Act is subject to regulations set forth in this Act. A copy of the Texas Administrative Code, Title 43, Part, 1, Chapter 21, Subchapter M may be viewed at

 $\frac{https://texreg.sos.state.tx.us/public/readtac\$ext.ViewTAC?tac_view=5\&ti=43\&pt=1\&ch=21\&sc_h=M\&rl=Y$

No significant traffic generator events identified

Hard hats are required at all times during construction when construction personnel are in TxDOT Right-of-Way.

Patrol vehicles must be clearly marked to correspond with the officer's agency and equipped with appropriate lights to identify them as law enforcement. For patrol vehicles not owned by a law enforcement agency, markings will be retroreflective and legible from 100 ft. from both sides and the rear of the vehicle. Lights will be high intensity and visible from all angles.

<u>LIGHTING STANDARDS FOR HIGHWAY MAINTENANCE OR CONSTRUCTION</u> <u>VEHICLES AND SERVICE VEHICLES</u>

VEHICLE LIGHTING SUMMARY

Vehicle Color of Flashing Lights Transportation Code Police Vehicles Red/Blue/White/Amber 547.305 & 547.702 Fire/EMS Vehicles Red/Blue/White/Amber 547.305 & 547.702 Volunteer Fire/EMS Red/Blue/White/Amber 547.305 & 547.702 School Bus Red/White (rooftop)/Amber 547.305 & 547.701

Highway Maintenance or Construction Vehicles1 and Service Vehicles2 Amber/Blue 547.105 & TxDOT

Item 8 "Prosecution and Progress"

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process and/or execute all contracts at the same time.

Coordinate and update the work schedule with the project inspector daily. Give a minimum of 24 hours of notice to project inspector if work requiring inspection or testing is to be performed. Failure to do so may cause that work to be delayed or postponed if TxDOT personnel are not available. Work performed without suitable inspection, as determined by the Engineer, may be ordered removed and replaced at Contractor's expense.

Prepare the progress schedule as a Critical Path Method (CPM).

Item 9, "Measurement and Payment"

The progress payment period shall end on the 25th of each month, unless directed by the Area Office Engineer. Material on Hand (MOH) is due two business days before estimate cut off.

Item 100, "Preparing Right of Way"

The Contractor's attention is directed to potential regulations against burning within the project limits. Abide by all local ordinances and county imposed burn bans. When burning is prohibited, dispose of material in accordance with regulations set forth by other regulatory agencies including the Texas Commission for Environmental Quality. The cost of burning or disposal of any product is subsidiary to various bid items.

TPWD shall identify 3 rocks (approx. 3'x3' in size) to be removed and stockpiled. Contractor shall remove and stockpile rocks as approved by TPWD within the limits of Big Spring State Park. Removal and stockpile work shall be subsidiary to Item 100.

Item 160, "Topsoil"

Topsoil source must be approved by TPWD prior to acquisition and placement.

Item 164, "Seeding for Erosion Control"

Quantities shown are approximate; limits of the permanent seeding will be determined during construction.

The following seeding mix shall be used unless otherwise approved by TPWD:

Common Name	Scientific Name	Pounds per acre of Pure Live Seed (PLS)
Bristlegrass	Setaria leucopila	3
Blue grama (Hachita germoplasm)	Bouteloua gracilis	2
Sideoats grama	Bouteloua curtipendula	5
Arizona cottontop	Digitaria californica	4
Green sprangletop (Van Horn germoplasm)	Leptochloa dubia	2

Item 168, "Vegetative Watering"

Water rate for this project shall be 1/4" of water per acre every two weeks for a 3-month period.

Item 421, "Hydraulic Cement Concrete"

Use a cement meeting the requirements of Ty II when Mix Design Option 7 is selected for cast in place concrete.

Class C fly ash and Type I cement will not be allowed for any mix unless approved by the Engineer.

As a minimum, curing facility includes concrete curing tank, heater and a concrete recording thermometer. Provide a recorder with the capability to chart temperatures for 24 hours, 7 days and 30 day periods of time.

Air Entrainment requirements are waived with exception to bridge deck concrete, and rails, top slabs of direct traffic culverts and approach slabs. Air Entrainment is required for all slip formed concrete (bridge rail, concrete traffic barrier, pavement, etc.).

Item 432, "Riprap"

Provide conventionally reinforced concrete in areas shown in the plans.

When using conventional reinforcement, meet all requirements in accordance with Article 432.3.1. Concrete Riprap with exception that Class A Concrete is required.

Finish the surface with broom finish.

Item 502, "Barricades, Signs and Traffic Handling"

Provide the Engineer with written notification seven (7) days in advance of major traffic changes. A major traffic change is defined as the temporary (greater than one day) or permanent relocation of traffic lanes typically in an urban setting. The notice will, at a minimum, include the expected date, time and scope of the traffic change. The Department will utilize the information provided to inform the traveling public of the changes. Failure to provide advance notice, or to provide accurate information, will result in delaying the work until such time that the public has been notified.

Additional signs, barricades and traffic handling may be necessary to complete the work shown herein and will be provided by the contractor as required and will be considered subsidiary to this item.

Provide separate attenuators for each work area within a common lane closure as approved or directed by the Engineer.

In sections where traffic is restricted to one lane, two-way traffic, flaggers will be stationed at each end of that section with two-way communication devices and a pilot car will control operations.

All safety appurtenances such as signs, delineators, object markers and route markers will be in place prior to opening each phase of the construction to traffic, unless otherwise directed.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The Contractor's person responsible for TCP compliance must be available by local telephone and have a response time within 45 minutes.

Equip all work vehicles within 30 feet of the traveled way with a functioning amber strobe light or rotating beacon visible from all directions.

Repair barricades within the timeline shown on the barricade inspection report. Failure to comply will cease all work until barricades are repaired to the satisfaction of the Department.

Replace all damaged traffic control devices immediately. Remove any damaged traffic control devices from the project within 24 hours.

Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls"

On site concrete washout shall not be allowed on this project.

Item 644, "Small Roadside Sign Supports and Assemblies"

Use the latest edition of the "Standard Highway Sign Designs for Texas" for Sign types for which design details are not shown on the plans.

Sign placement shall be in accordance with the latest edition of the TMUTCD & TxDOT's Sign Crew Field Book located at the following addresses.

TMUTCD - https://www.txdot.gov/business/resources/signage/tmutcd.html
TxDOT's Sign Crew Field Book - http://onlinemanuals.txdot.gov/txdotmanuals/sfb/index.htm

Before final sign installation, stake all sign locations for approval by the engineer.

All triangle slip base small sign mounts installed under this item shall utilize clamp type bases.

Item 658, "Delineator and Object Marker Assemblies"

Delineators and object marker assemblies will use winged channel posts. The winged channel posts will be 1.12 lb/ft and 6.5 ft in length.

Item 666, "Retro reflectorized Pavement Markings"

All longitudinal pavement markings (including profile pavement markings) must meet minimum retro reflectivity requirements.

Establish a true and correct alignment with a method approved by the Engineer. This work will be considered subsidiary.

Contractor is responsible for re-establishing location and alignment for new pavement markings matching pavement marking alignment prior to construction activities. This work will be considered subsidiary.

Item 6185, "Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)"

Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA) will not be considered a major item of work on this project.

TMAs will only be paid while workers are present or to protect a blunt object.

BASIS OF ESTIMATE FOR STATIONARY TMAS						
		TMA (Stationary)				
Phase	Standard	Required	Additional	TOTAL		
Phase 1,	TCP (2-1)-18	1	-	1		
Phase 2						

The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project. The Contractor must get approval from the Engineer for any changes in the number of TMA as shown in the plans.

If a TMA is used for both mobile and stationary traffic control on the same day, it will be paid for as stationary for that day.

CONTROL: 0908-12-027 PROJECT: C 908-12-27

HIGHWAY : VA COUNTY : HOWARD

TEXAS DEPARTMENT OF TRANSPORTATION

GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF ----- TRANSPORTATION NOVEMBER 1, 2014.

STANDARD SPECIFICATIONS ARE INCORPORATED

INTO THE CONTRACT BY REFERENCE.

- ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS
- ITEM 100 PREPARING RIGHT OF WAY (103)
- ITEM 110 EXCAVATION (132)
- ITEM 132 EMBANKMENT (100) (160) (204) (210) (216) (260) (400)
- ITEM 160 TOPSOIL (168)
- ITEM 164 SEEDING FOR EROSION CONTROL (162)(166)(168)
- ITEM 168 VEGETATIVE WATERING
- ITEM 169 SOIL RETENTION BLANKETS
- ITEM 247 FLEXIBLE BASE (105) (204) (210) (216) (520)
- ITEM 310 PRIME COAT (300)(316)<3096>
- ITEM 316 SEAL COAT (210)(300)(302)(340)(520)<3096>
- ITEM 400 EXCAVATION AND BACKFILL FOR STRUCTURES (110)(132)(401) (402) (403) (416) (420) (421) (423)
- ITEM 432 RIPRAP (247) (420) (421) (431) (440)
- ITEM 460 CORRUGATED METAL PIPE (400) (402) (403) (445) (467) (476)
- ITEM 464 REINFORCED CONCRETE PIPE (400)(402)(403)(467)(476)
- ITEM 467 SAFETY END TREATMENT (400)(420)(421)(432)(440)(442)(445) (460)(464)
- ITEM 500 MOBILIZATION
- ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING
- ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS (161) (432) (556)
- ITEM 552 WIRE FENCE (445)(492)
- ITEM 644 SMALL ROADSIDE SIGN ASSEMBLIES (421) (440) (441) (442) (445) (636) (643) (656)
- ITEM 658 DELINEATOR AND OBJECT MARKER ASSEMBLIES (445)
- ITEM 666 RETROREFLECTORIZED PAVEMENT MARKINGS (316)(502)(662)(677)
- ITEM 668 PREFABRICATED PAVEMENT MARKINGS (678)
- ITEM 678 PAVEMENT SURFACE PREPARATION FOR MARKINGS (677)

```
PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED
_____
                     HEREON WHEREVER IN CONFLICT THEREWITH.
SPECIAL LABOR PROVISIONS FOR STATE PROJECTS (000---008)
WAGE RATES
SPECIAL PROVISION "NONDISCRIMINATION" (000---002)
SPECIAL PROVISION "SMALL BUSINESS ENTERPRISE IN STATE FUNDED PROJECTS
                   " (000---009)
SPECIAL PROVISION "CERTIFICATE OF INTERESTED PARTIES (FORM 1295)"
                     (000 - -1019)
SPECIAL PROVISION "SCHEDULE OF LIQUIDATED DAMAGES" (000--1243)
SPECIAL PROVISION "NOTICE OF CONTRACTOR PERFORMANCE EVALUATIONS"
                     (000 - - -659)
SPECIAL PROVISIONS TO ITEM 2 (002---011)(002---013)
SPECIAL PROVISIONS TO ITEM
                              3 (003---011) (003---013)
SPECIAL PROVISIONS TO ITEM
                             5 (005---002)(005---003)
                              6 (006---001)(006---012)
SPECIAL PROVISIONS TO ITEM
SPECIAL PROVISIONS TO ITEM
                              7 (007---004) (007---008) (007---010)
                                  (007 - - - 011)

        SPECIAL PROVISIONS TO ITEM
        8 (008---030)(008---033)

        SPECIAL PROVISIONS TO ITEM
        9 (009---010)(009---011)

SPECIAL PROVISION TO ITEM 247 (247---003)
SPECIAL PROVISION TO ITEM 300 (300---020)
SPECIAL PROVISION TO ITEM 302
                                 (302 - - - 003)
SPECIAL PROVISION TO ITEM 316
                                 (316---002)
SPECIAL PROVISION TO ITEM 340 (340---004)
SPECIAL PROVISION TO ITEM 420 (420---001)
SPECIAL PROVISION TO ITEM 421 (421---010)
SPECIAL PROVISION TO ITEM 440 (440---004)
SPECIAL PROVISION TO ITEM 441 (441---004)
SPECIAL PROVISION TO ITEM 442 (442---001)
SPECIAL PROVISION TO ITEM 464
                                  (464---001)
SPECIAL PROVISION TO ITEM 502 (502---008)
SPECIAL PROVISION TO ITEM 506 (506---005)
SPECIAL PROVISION TO ITEM 520 (520---002)
SPECIAL PROVISION TO ITEM 636 (636---001)
SPECIAL PROVISION TO ITEM 643 (643---001)
SPECIAL PROVISION TO ITEM 656 (656---001)
SPECIAL PROVISION TO ITEM 666 (666---007)
SPECIAL SPECIFICATIONS:
______
```

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH

PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER

ITEM 3096 ASPHALTS, OILS, AND EMULSIONS ITEM 5008 PRECAST CONCRETE WHEEL STOPS

PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFICATIONS FOR THIS PROJECT.

Control 0908-12-027

Project C 908-12-27

Highway VA

County HOWARD

SMALL BUSINESS ENTERPRISE REQUIREMENTS

The following goal for small business enterprises is established:

SBE 0.0%

CHILD SUPPORT STATEMENT

Under Section 231.006, Family Code, the vendor or applicant certifies that the individual or business entity named in this contract, bid, or application is not ineligible to receive the specified grant, loan, or payment and acknowledges that this contract may be terminated and payment may be withheld if this certification is inaccurate.

CONFLICT OF INTEREST CERTIFICATION

Pursuant to Texas Government Code Section 2261.252(b), the Department is prohibited from entering into contracts in which Department officers and employees have a financial interest.

By signing the Contract, the Contractor certifies that it is not prohibited from entering into a Contract with the Department as a result of a financial interest as defined under Texas Government Code Section 2261.252(b), and that it will exercise reasonable care and diligence to prevent any actions or conditions that could result in a conflict of interest with the Department.

The Contractor also certifies that none of the following individuals, nor any of their family members within the second degree of affinity or consanguinity, owns 1% or more interest or has a financial interest as defined under Texas Government Code Section 2261.252(b) in the Contractor:

- Any member of the Texas Transportation Commission; and
- The Department's Executive Director, General Counsel, Chief of Procurement and Field Support Operations, Director of Procurement, and Director of Contract Services.

Violation of this certification may result in action by the Department.

E-VERIFY CERTIFICATION

Pursuant to Texas Transportation Code §223.051, all TxDOT contracts for construction, maintenance, or improvement of a highway must include a provision requiring Contractors and subcontractors to use the U.S. Department of Homeland Security's E-Verify system to determine employment eligibility. By signing the contract, the Contractor certifies that prior to the award of the Contract:

- the Contractor has registered with and will, to the extent permitted by law, utilize the United States Department of Homeland Security's E-Verify system during the term of the Contract to determine the eligibility of all persons hired to perform duties within Texas during the term of the agreement; and
- the Contractor will require that all subcontractors also register with and, to the extent permitted by law, utilize the United States Department of Homeland Security's E-Verify system during the term of the subcontract to determine the eligibility of all persons hired to perform duties within Texas during the term of the agreement.

Violation of this requirement constitutes a material breach of the Contract, subjects a subcontractor to removal from the Contract, and subjects the Contractor or subcontractors to possible sanctions in accordance with Title 43, Texas Administrative Code, Chapter 10, Subchapter F, "Sanctions and Suspension for Ethical Violations by Entities Doing Business with the Department."

Certification Regarding Disclosure of Public Information

Pursuant to Subchapter J, Chapter 552, Texas Government Code, contractors executing a contract with a governmental body that results in the expenditure of at least \$1 million in public funds must:

- 1) preserve all contracting information* as provided by the records retention requirements applicable to Texas Department of Transportation (TxDOT) for the duration of the contract,
- 2) on request of TxDOT, promptly provide any contracting information related to the contract that is in the custody or possession of the entity, and
- 3) on completion of the contract, either:
 - A. provide, at no cost to TxDOT, all contracting information related to the contract that is in the custody or possession of the entity, or
 - B. preserve the contracting information related to the contract as provided by the records retention requirements applicable to TxDOT

The requirements of Subchapter J, Chapter 552, Government Code, may apply to this contract, and the contractor or vendor agrees that the contract can be terminated if the contractor or vendor knowingly or intentionally fails to comply with a requirement of that subchapter.

By entering into Contract, the Contractor agrees to:

- provide, or make available, to TxDOT and any authorized governmental investigating or auditing agency all
 records, including electronic and payment records related to the contract, for the same period provided by the
 records retention schedule applicable to TxDOT, and
- ensure that all subcontracts include a clause requiring the same.
- * As defined in Government Code §552.003, "Contracting information" means the following information maintained by a governmental body or sent between a governmental body and a vendor, contractor, potential vendor, or potential contractor:
 - 1) information in a voucher or contract relating to the receipt or expenditure of public funds by a governmental body;
 - 2) solicitation or bid documents relating to a contract with a governmental body;
 - 3) communications sent between a governmental body and a vendor, contractor, potential vendor, or potential contractor during the solicitation, evaluation, or negotiation of a contract;
 - 4) documents, including bid tabulations, showing the criteria by which a governmental body evaluates each vendor, contractor, potential vendor, or potential contractor responding to a solicitation and, if applicable, an explanation of why the vendor or contractor was selected; and
 - 5) communications and other information sent between a governmental body and a vendor or contractor related to the performance of a final contract with the governmental body or work performed on behalf of the governmental body.

CERTIFICATION TO NOT BOYCOTT ISRAEL

Pursuant to Texas Government Code §2271.002, the Department must include a provision requiring a written verification affirming that the Contractor does not boycott Israel, as defined in Government Code §808.001, and will not boycott Israel during the term of the contract. This provision applies to a contract that:

- 1) is with a Contractor that is not a sole proprietorship,
- 2) is with a Contractor with 10 or more full-time employees, and
- 3) has a value of \$100,000 or more.

By signing the contract, the Contractor certifies that it does not boycott Israel and will not boycott Israel during the term of this contract. "Boycott" means refusing to deal with, terminating business activities with, or otherwise taking any action that is intended to penalize, inflict economic harm on, or limit commercial relations specifically with Israel, or with a person or entity doing business in Israel or in an Israeli-controlled territory, but does not include an action made for ordinary business purposes.

Violation of this certification may result in action by the Department.

CERTIFICATION TO NOT BOYCOTT ENERGY COMPANIES

Pursuant to Texas Government Code §2274.002, the Department must include a provision requiring a written verification affirming that the Contractor does not boycott energy companies, as defined in Government Code §809.001, and will not boycott energy companies during the term of the contract. This provision applies to a contract that:

- 1) is with a Contractor that is not a sole proprietorship,
- 2) is with a Contractor with 10 or more full-time employees, and
- 3) has a value of \$100,000 or more.

By signing the contract, the Contractor certifies that it does not boycott energy companies and will not boycott energy companies during the term of this contract. "Boycott" means taking any action that is intended to penalize, inflict economic harm on, or limit commercial relations with a company because the company: (1) engages in the exploration, production, utilization, transportation, sale, or manufacturing of fossil fuel-based energy and does not commit or pledge to meet environmental standards beyond applicable federal and state law; or (2) does business with a company described by (1).

Violation of this certification may result in action by the Department.

CERTIFICATION TO NOT DISCRIMINATE AGAINST FIREARM ENTITIES OR FIREARM TRADE ASSOCIATIONS

Pursuant to Texas Government Code §2274.002, the Department must include a provision requiring a written verification affirming that the Contractor:

- does not have a practice, policy, guidance, or directive that discriminates against a firearm entity or firearm trade association, as defined in Government Code §2274.001, and
- 2) will not discriminate against a firearm entity or firearm trade association during the term of the contract.

This provision applies to a contract that:

- 1) is with a Contractor that is not a sole proprietorship,
- 2) is with a Contractor with 10 or more full-time employees, and
- 3) has a value of \$100,000 or more.

By signing the contract, the Contractor certifies that it does not discriminate against a firearm entity or firearm trade association as described and will not do so during the term of this contract. "Discriminate against a firearm entity or firearm trade association" means, with respect to the entity or association, to: (1) refuse to engage in the trade of any goods or services with the entity or association based solely on its status as a firearm entity or firearm trade association; (2) refrain from continuing an existing business relationship with the entity or association based solely on its status as a firearm entity or firearm trade association; or (3) terminate an existing business relationship with the entity or association based solely on its status as a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association" does not include: (1) the established policies of a merchant, retail seller, or platform that restrict or prohibit the listing or selling of ammunition, firearms, or firearm accessories; (2) a company's refusal to engage in the trade of any goods or services, decision to refrain from continuing an existing business relationship, or decision to terminate an existing business relationship to comply with federal, state, or local law, policy, or regulations or a directive by a regulatory agency, or for any traditional business reason that is specific to the customer or potential customer and not based solely on an entity 's or association's status as a firearm entity or firearm trade association.

Violation of this certification may result in action by the Department.

PROHIBITION ON CERTAIN TELECOMMUNICATIONS EQUIPMENT OR SERVICES

The Federal Register Notice issued the Final Rule and states that the amendment to 2 CFR 200.216 is effective on August 13, 2020. The new 2 CFR 200.471 regulation provides clarity that the telecommunications and video surveillance costs associated with 2 CFR 200.216 are unallowable for services and equipment from these specific providers. OMB's Federal Register Notice includes the new 2 CFR 200.216 and 2 CFR 200.471 regulations.

https://www.federal register.gov/documents/2020/08/13/2020-17468/guidance-for-grants-and-agreements

Per the Federal Law referenced above, use of services, systems, or services or systems that contain components produced by any of the following manufacturers is strictly prohibited for use on this project. Therefore, for any telecommunications, CCTV, or video surveillance equipment, services or systems cannot be manufactured by, or have components manufactured by:

- Huawei Technologies Company,
- ZTE Corporation (any subsidiary and affiliate of such entities),
- Hyatera Communications Corporation,
- Hangzhou Hikvision Digital Technology Company,
- Dahua Technology Company (any subsidiary and affiliate of such entities).

Violation of this prohibition will require replacement of the equipment at the contractor's expense.

1-1

BPSDocName

Special Provision to Item 000 Special Labor Provisions for State Projects



1. **GENERAL**

This is a "Public Works" Project, as provided under Government Code Title 10, Chapter 2258, "Prevailing Wage Rates," and is subject to the provisions of the Statute. No provisions in the Contract are intended to be in conflict with the provisions of the Statute.

The Texas Transportation Commission has ascertained and indicated in the special provisions the regular rate of per diem wages prevailing in each locality for each craft or type of worker. Apply the wage rates contained in the specifications as minimum wage rates for the Contract.

2. MINIMUM WAGES, HOURS AND CONDITIONS OF EMPLOYMENT

All workers necessary for the satisfactory completion of the work are within the purview of the Contract.

Whenever and wherever practical, give local citizens preference in the selection of labor.

Do not require any worker to lodge, board or trade at a particular place, or with a particular person as a condition of employment.

Do not charge or accept a fee of any from any person who obtains work on the project. Do not require any person who obtains work on the project to pay any fee to any other person or agency obtaining employment for the person on the project.

Do not charge for tools or equipment used in connection with the duties performed, except for loss or damage of property. Do not charge for necessary camp water.

Do not charge for any transportation furnished to any person employed on the project.

The provisions apply where work is performed by piece work, station work, etc. The minimum wage paid will be exclusive of equipment rental on any shipment which the worker or subcontractor may furnish in connection with his work.

Take responsibility for carrying out the requirements of this specification and ensure that each subcontractor working on the project complies with its provisions.

Any form of subterfuge, coercion or deduction designated to evade, reduce or discount the established minimum wage scales will be considered a violation of the Contract.

The Fair Labor Standards Acts (FLSA) established one and one-half (1-1/2) pay for overtime in excess of 40 hours worked in 1 week. Do not consider time consumed by the worker in going to and returning from the place of work as part of the hours of work. Do not require or permit any worker to work in excess of 40 hours in 1 week, unless the worker receives compensation at a rate not less than 1-1/2 times the basic rate of pay for all hours worked in excess of 40 hours in the workweek.

The general rates of per diem wages prevailing in this locality for each class and type of workers whose services are considered necessary to fulfill the Contract are indicated in the special provisions, and these rates govern as minimum wage rates on this Contract. A penalty of \$60.00 per calendar day or portion of a calendar day for each worker that is paid less than the stipulated general rates of per diem wages for any work done under the Contract will be deducted. The Department, upon receipt of a complaint by a worker,

1

09-14

will determine within 30 days whether good cause exists to believe that the Contractor or a subcontractor has violated wage rate requirements and notify the parties involved of the findings. Make every effort to resolve the alleged violation within 14 days after notification. The next alternative is submittal to binding arbitration in accordance with the provisions of the Texas General Arbitration Act (Art. 224 et seq., Revised Statutes).

Notwithstanding any other provision of the Contract, covenant and agree that the Contractor and its subcontractors will pay each of their employees and contract labor engaged in any way in work under the Contract, a wage not less than what is generally known as the "federal minimum wage" as set out in 29 U.S.C. 206 as that Statute may be amended from time to time.

Pay any worker employed whose position is not listed in the Contract, a wage not less than the per diem wage rate established in the Contract for a worker whose duties are most nearly comparable.

3. RECORD AND INSPECTIONS

Keep copies of weekly payrolls for review. Require subcontractors to keep copies of weekly payrolls for review. Show the name, occupation, number of hours worked each day and per diem wage paid each worker together with a complete record of all deductions made from such wages. Keep records for a period of 3 years from the date of completion of the Contract.

Where the piece-work method is used, indicate on the payroll for each person involved:

- Quantity of piece work performed.
- Price paid per piece-work unit.
- Total hours employed.

The Engineer may require the Contractor to file an affidavit for each payroll certifying that payroll is a true and accurate report of the full wages due and paid to each person employed.

Post or make available to employees the prevailing wage rates from the Contract. Require subcontractors to post or make available to employees the prevailing wage rates from the Contract.

2 09-14 Statewide The wage rates listed herein are those predetermined by the Secretary of Labor and State Statue and listed in the United States Department of Labor's (USDOL) General Decisions dated **01-06-2023** and are the minimum wages to be paid accordingly for each specified classification. To determine the applicable wage rate zone, a list entitled "TEXAS COUNTIES IDENTIFIED BY WAGE RATE ZONES" is provided in the contract. Any wage rate that is not listed herein and not in the USDOL's general decision, must be submitted to the Engineer for approval. IMPORTANT NOTICE FOR STATE PROJECTS: only the controlling wage rate zone applies to the contract. Effective 01-06-2023.

CLASS.#	CLASSIFICATION DESCRIPTION	ZONE TX02 *(TX20230002)	ZONE TX03 *(TX20230003)	ZONE TX04 *(TX20230004)	ZONE TX05 *(TX20230005)	ZONE TX06 *(TX20230006)	ZONE TX07 *(TX20230007)	ZONE TX08 *(TX20230008)	ZONE TX24 *(TX20230024)	ZONE TX25 *(TX20230025)	ZONE TX27 *(TX20230027)	ZONE TX28 *(TX20230028)	ZONE TX29 *(TX20230029)	ZONE TX30 *(TX20230030)	ZONE TX37 *(TX20230037)	ZONE TX38 *(TX20230038)	ZONE TX42 *(TX20230042)
1428	Agricultural Tractor Operator						\$12.69					\$12.35			\$11.75		
1300	Asphalt Distributor Operator	\$14.87	\$13.48	\$13.88	\$15.72	\$15.58	\$15.55	\$15.72	\$13.28	\$15.32	\$15.62	\$14.36	\$14.25	\$14.03	\$13.75	\$14.06	\$14.40
1303	Asphalt Paving Machine Operator	\$13.40	\$12.25	\$12.35	\$13.87	\$14.05	\$14.36	\$14.20	\$13.26	\$13.99	\$14.68	\$12.92	\$13.44	\$12.53	\$14.00	\$14.32	\$12.99
1106	Asphalt Raker	\$12.28	\$10.61	\$12.02	\$14.21	\$11.65	\$12.12	\$11.64	\$11.44	\$12.69	\$12.05	\$11.34	\$11.67	\$11.40	\$12.59	\$12.36	\$11.78
1112	Batching Plant Operator, Asphalt																
1115	Batching Plant Operator, Concrete																
1214	Blaster																
1615	Boom Truck Operator						\$18.36										
1444	Boring Machine Operator																
1305	Broom or Sweeper Operator	\$11.21	\$10.33	\$10.08	\$11.99		\$11.04	\$11.62		\$11.74	\$11.41	\$10.30		\$10.23	\$10.60	\$12.68	\$11.05
1144	Communications Cable Installer																
4404	Concrete Finisher, Paving and	040.55	240.40	010.10	040.05	040.04	010.50	040.77	212.11	04440	040.04	240.00	0.10.01	240.00	040.70	* 40.00	240.00
1124	Structures Concrete Pavement Finishing	\$13.55	\$12.46	\$13.16	\$12.85	\$12.64	\$12.56	\$12.77	\$12.44	\$14.12	\$13.04	\$13.38	\$12.64	\$12.80	\$12.79	\$12.98	\$13.32
1318	Machine Operator				\$16.05		\$15.48			\$16.05		\$19.31				\$13.07	
1315	Concrete Paving, Curing, Float, Texturing Machine Operator											\$16.34				\$11.71	
1333	Concrete Saw Operator				\$14.67					\$14.48	\$17.33					\$13.99	
1399	Concrete/Gunite Pump Operator																
1344	Crane Operator, Hydraulic 80 tons or less				\$18.22		\$18.36			\$18.12	\$18.04	\$20.21			\$18.63	\$13.86	
	Crane Operator, Hydraulic Over																
1345	80 Tons Crane Operator, Lattice Boom 80																
	Tons																'
1342	or Less	\$16.82	\$14.39	\$13.85	\$17.27		\$15.87			\$17.27		\$14.67			\$16.42	\$14.97	\$13.87
1343	Crane Operator, Lattice Boom Over 80 Tons				\$20.52		\$19.38			\$20.52		\$17.49			\$25.13	\$15.80	
1306	Crawler Tractor Operator	\$13.96	\$16.63	\$13.62	\$14.26		\$15.67			\$14.07	\$13.15	\$13.38			\$14.60	\$13.68	\$13.50
1351	Crusher or Screen Plant Operator																
1446	Directional Drilling Locator						\$11.67										
1445	Directional Drilling Operator				\$20.32		\$17.24										
1139	Electrician	\$20.96		\$19.87	\$19.80		\$26.35		\$20.27	\$19.80		\$20.92				\$27.11	\$19.87
	Excavator Operator, 50,000																
1347	pounds or less Excavator Operator, Over 50,000	\$13.46	\$12.56	\$13.67	\$17.19		\$12.88	\$14.38	\$13.49	\$17.19		\$13.88		_	\$14.09	\$12.71	\$14.42
1348	pounds		\$15.23	\$13.52	\$17.04		\$17.71			\$16.99	\$18.80	\$16.22		1	1	\$14.53	\$13.52
1150	Flagger	\$9.30	\$9.10	\$8.50	\$10.28	\$8.81	\$9.45	\$8.70		\$10.06	\$9.71	\$9.03	\$8.81	\$9.08	\$9.90	\$10.33	\$8.10
1151	Form Builder/Setter, Structures	\$13.52	\$12.30	\$13.38	\$12.91	\$12.71	\$12.87	\$12.38	\$12.26	\$13.84	\$12.98	\$13.07	\$13.61	\$12.82	\$14.73	\$12.23	\$12.25
1160	Form Setter, Paving & Curb	\$12.36	\$12.16	\$13.93	\$11.83	\$10.71	\$12.94			\$13.16	\$12.54	\$11.33	\$10.69		\$13.33	\$12.34	\$13.93
1360	Foundation Drill Operator, Crawler Mounted		, , , , , ,		\$17.99					\$17.99		,				\$17.43	
1363	Foundation Drill Operator, Truck Mounted		\$16.86	\$22.05	\$21.51		\$16.93			\$21.07	\$20.20	\$20.76		\$17.54	\$21.39	\$15.89	\$22.05
1369	Front End Loader Operator, 3 CY or Less	\$12.28	\$13.49	\$13.40	\$13.85		\$13.04	\$13.15	\$13.29	\$13.69	\$12.64	\$12.89		Ţ <u>.</u>	\$13.51	\$13.32	\$12.17
1372	Front End Loader Operator, Over 3 CY	\$12.77	\$13.69	\$12.33	\$14.96		\$13.21	\$12.86	\$13.57	\$14.72	\$13.75	\$12.32			\$13.19	\$13.17	\$13.02
1329	Joint Sealer	Ų.L.//	Ų.U.UU	Ç.2.00	ψ. 7.50		Ų.J.Z1	ψ.2.00	Ç.3.07	Ψ.1.12	\$.5.70	Ų.2.0 <u>2</u>			\$13.10	ψ.σ.17	+
1172	Laborer, Common	\$10.30	\$9.86	\$10.08	\$10.51	\$10.71	\$10.50	\$10.24	\$10.58	\$10.72	\$10.45	\$10.30	\$10.25	\$10.03	\$10.54	\$11.02	\$10.15
1175	Laborer, Utility	\$11.80	\$11.53	\$12.70	\$12.17	\$11.81	\$12.27	\$12.11	\$11.33	\$12.32	\$11.80	\$11.53	\$11.23	\$11.50	\$11.95	\$11.73	\$12.37
1346	Loader/Backhoe Operator	\$14.18	\$12.77	\$12.97	\$15.68	ψ. γ. σ	\$14.12	Ψ.2.11	Çoo	\$15.18	\$13.58	\$12.87	ψ.1.20	\$13.21	\$14.13	\$14.29	\$12.90
1187	Mechanic	\$20.14	\$15.47	\$17.47	\$17.74	\$17.00	\$17.10			\$17.68	\$18.94	\$18.58	\$17.00	\$16.61	\$18.46	\$16.96	\$17.47
1380	Milling Machine Operator	\$15.54	\$14.64	\$12.22	\$14.29	ψ17.00	\$14.18			\$14.32	\$14.35	\$12.86	ψ17.00	\$10.01	\$14.75	\$13.53	
1300	wining machine Operator	\$15.54	φ14.04	\$12.2Z	\$14.29		ş14.18			\$14.32	\$14.35	\$12.80			\$14.75	\$13.53	\$12.8

CLASS.#	CLASSIFICATION DESCRIPTION	ZONE TX02 *(TX20230002)	ZONE TX03 *(TX20230003)	ZONE TX04 *(TX20230004)	ZONE TX05 *(TX20230005)	ZONE TX06 *(TX20230006)	ZONE TX07 *(TX20230007)	ZONE TX08 *(TX20230008)	ZONE TX24 *(TX20230024)	ZONE TX25 *(TX20230025)	ZONE TX27 *(TX20230027)	ZONE TX28 *(TX20230028)	ZONE TX29 *(TX20230029)	ZONE TX30 *(TX20230030)	ZONE TX37 *(TX20230037)	ZONE TX38 *(TX20230038)	ZONE TX42 *(TX20230042)
1390	Motor Grader Operator, Fine Grade	\$17.49	¢16.50	\$16.88	\$17.12	\$18.37	\$18.51	\$16.69	\$16.13	\$17.19	\$18.35	\$17.07	\$17.74	\$17.47	\$17.08	\$15.69	\$20.01
1393		\$17.49 \$16.15	\$16.52 \$14.62	\$15.83	\$17.12	\$10.37	\$16.51	\$18.50	\$10.13	\$17.19	\$16.33	\$17.07	\$17.74 \$16.85	\$17.47	\$17.00	\$15.69	\$20.01
1413	Motor Grader Operator, Rough Off Road Hauler	\$10.15	\$14.02	\$10.03	\$10.20	\$17.07	\$14.63	\$10.50		\$10.02	\$10.44	\$13.12	\$10.00	\$14.47	\$17.39		
				\$10.06	\$12.20	£04.00	\$11.00			\$12.25		\$12.23	\$21.29		\$13.00	\$14.60	
1196	Painter, Structures Pavement Marking Machine					\$21.29	\$18.34						\$21.29			\$18.62	
1396	Operator	\$16.42		\$13.10	\$13.55		\$19.17	\$12.01		\$13.63	\$14.60	\$13.17		\$16.65	\$10.54	\$11.18	\$13.10
1443	Percussion or Rotary Drill Operator																
1202	Piledriver															\$14.95	
1205	Pipelayer		\$11.87	\$14.64	\$13.17	\$11.17	\$12.79		\$11.37	\$13.24	\$12.66	\$13.24	\$11.17	\$11.67		\$12.12	\$14.64
1384	Reclaimer/Pulverizer Operator	\$12.85			\$11.90		\$12.88			\$11.01		\$10.46					
1500	Reinforcing Steel Worker	\$13.50	\$14.07	\$17.53	\$16.17		\$14.00			\$16.18	\$12.74	\$15.83		\$17.10		\$15.15	\$17.72
1402	Roller Operator, Asphalt	\$10.95		\$11.96	\$13.29		\$12.78	\$11.61		\$13.08	\$12.36	\$11.68			\$11.71	\$11.95	\$11.50
1405	Roller Operator, Other	\$10.36		\$10.44	\$11.82		\$10.50	\$11.64		\$11.51	\$10.59	\$10.30		\$12.04	\$12.85	\$11.57	\$10.66
1411	Scraper Operator	\$10.61	\$11.07	\$10.85	\$12.88		\$12.27		\$11.12	\$12.96	\$11.88	\$12.43		\$11.22	\$13.95	\$13.47	\$10.89
1417	Self-Propelled Hammer Operator																
1194	Servicer	\$13.98	\$12.34	\$14.11	\$14.74		\$14.51	\$15.56	\$13.44	\$14.58	\$14.31	\$13.83		\$12.43	\$13.72	\$13.97	\$14.11
1513 1708	Sign Erector Slurry Seal or Micro-Surfacing Machine Operator																
1341	Small Slipform Machine Operator									\$15.96							
1515	Spreader Box Operator	\$12.60		\$13.12	\$14.71		\$14.04			\$14.73	\$13.84	\$13.68		\$13.45	\$11.83	\$13.58	\$14.05
1705	Structural Steel Welder	Ų 12.00		ψ10.12	Ų		\$11.01			ψσ	Ç10.01	ψ10.00		Ų.0.10	\$11.55	\$12.85	
1509	Structural Steel Worker						\$19.29									\$14.39	
1339	Subgrade Trimmer						Ţ101 <u>2</u> 0									******	
1143	Telecommunication Technician																
1145	Traffic Signal/Light Pole Worker						\$16.00										
	Trenching Machine Operator,						\$10.00										1
1440	Heavy						\$18.48										
1437	Trenching Machine Operator, Light																
1609	Truck Driver Lowboy-Float	\$14.46	\$13.63	\$13.41	\$15.00	\$15.93	\$15.66			\$16.24	\$16.39	\$14.30	\$16.62	\$15.63	\$14.28	\$16.03	\$13.41
1612	Truck Driver Transit-Mix	ψ14.40	ψ10.00	ψ10. 4 1	\$14.14	Ψ10.50	ψ10.00			\$14.14	ψ10.00	ψ14.00	Ψ10.02	ψ10.00	ψ14.20	ψ10.00	\$10.41
1600	Truck Driver, Single Axle	\$12.74	\$10.82	\$10.75	\$13.04	\$11.61	\$11.79	\$13.53	\$13.16	\$12.31	\$13.40	\$10.30	\$11.61	-	\$11.97	\$11.46	\$10.75
1000	Truck Driver, Single or Tandem Axle	ψ12.74	ψ10.02	\$10.75	ψ10.04	Ψ11.01	Ψ11.79	ψ13.33	ψ13.10	Ψ12.51	ψ13.40	ψ10.30	Ψ11.01		\$11.97	\$11.40	\$10.73
1606	Dump Truck Truck Driver, Tandem Axle Tractor	\$11.33	\$14.53	\$11.95	\$12.95		\$11.68		\$14.06	\$12.62	\$11.45	\$12.28		\$13.08	\$11.68	\$11.48	\$11.10
1607	with Semi Trailer	\$12.49	\$12.12	\$12.50	\$13.42		\$12.81	\$13.16		\$12.86	\$16.22	\$12.50			\$13.80	\$12.27	\$12.50
1441	Tunneling Machine Operator, Heavy																
1442	Tunneling Machine Operator, Light																<u> </u>
1706	Welder		\$14.02		\$14.86		\$15.97		\$13.74	\$14.84					\$13.78	 	
1520 Notes:	Work Zone Barricade Servicer	\$10.30	\$12.88	\$11.46	\$11.70	\$11.57	\$11.85	\$10.77		\$11.68	\$12.20	\$11.22	\$11.51	\$12.96	\$10.54	\$11.67	\$11.76

Notes:

Any worker employed on this project shall be paid at the rate of one and one half (1-1/2) times the regular rate for every hour worked in excess of forty (40) hours per week.

For reference, the titles and descriptions for the classifications listed here are detailed further in the AGC of Texas' Standard Job Classifications and Descriptions for Highway, Heavy, Utilities, and Industrial Construction in Texas posted on the AGC's Web site for any contractor.

^{*}Represents the USDOL wage decision.

TEXAS COUNTIES IDENTIFIED BY WAGE RATE ZONES: 2, 3, 4, 5, 6, 7, 8, 24, 25, 27, 28, 29, 30, 37, 38, 42

County Name	Zone	County Name	Zone	County Name	Zone	County Name	Zone
Anderson		Donley		Karnes		Reagan	37
Andrews				Kaufman		Real	37
Angelina		Eastland	37	Kendall	7	Red River	28
Aransas	29	Ector	2	Kenedy		Reeves	8
Archer			8	Kent		Refugio	27
Armstrong	2	El Paso	24			Roberts	37
Atascosa	7	Ellis	25	Kimble		Robertson	7
Austin	38	Erath	28	King	37	Rockwall	25
Bailey	37	Falls		Kinney	8	Runnels	37
Bandera	7	Fannin	28	Kleberg		Rusk	4
Bastrop	7	Fayette	27	Knox		Sabine	28
Baylor	37	Fisher	37	Lamar		San Augustine	28
Bee	27	Floyd		Lamb	37	San Jacinto	38
Bell	7	Foard	37	Lampasas	7	San Patricio	29
Bexar	7	Fort Bend	38	LaSalle		San Saba	37
Blanco	27	Franklin		Lavaca	27	Schleicher	37
Borden	37	Freestone	28	Lee	27	Scurry	37
Bosque	28	Frio	27	Leon	28	Shackelford	37
Bowie	4	Gaines	37	Liberty	38	Shelby	28
Brazoria	38	Galveston	38	Limestone	28	Sherman	37
Brazos	7	Garza	37	Lipscomb	37	Smith	4
Brewster	8	Gillespie	27	Live Oak	27	Somervell	28
Briscoe	37	Glasscock	37	Llano	27	Starr	30
Brooks	30	Goliad	29	Loving	37	Stephens	37
Brown	37	Gonzales	27	Lubbock	2	Sterling	37
Burleson	7	Gray	37	Lynn		Stonewall	37
Burnet	27	Grayson		Madison		Sutton	8
Caldwell	7	Gregg	4	Marion	_	Swisher	37
Calhoun	29	Grimes		Martin		Tarrant	25
Callahan	25	Guadalupe	7	Mason		Taylor	2
Cameron	3	Hale	37	Matagorda		Terrell	8
Camp	28		37	•		Terry	37
Carson	2	Hamilton		McCulloch		Throckmorton	37
Cass	28	Hansford	37	McLennan	7	Titus	28
Castro	37	Hardeman	37	McMullen		Tom Green	2
Chambers		Hardin		Medina	7	Travis	7
Cherokee		Harris		Menard		Trinity	28
Childress	37	Harrison	42	Midland	2	Tyler	28
Clay	_	Hartley		Milam		Upshur	4
Cochran	37			Mills		Upton	37
Coke	-	Hays		Mitchell		Uvalde	30
Coleman		Hemphill		Montague		Val Verde	8
Collin		Henderson		Montgomery		Van Zandt	28
Collingsworth	37		3	Moore		Victoria	6
Colorado	-	Hill		Morris		Walker	28
Comal	7	Hockley		Motley		Waller	38
Comanche		Hood		Nacogdoches		Ward	37
Concho				Navarro		Washington	28
Cooke		Houston		Newton		Webb	3
Coryell	7	Howard		Nolan		Wharton	27
Cottle	37	Hudspeth	8	Nueces		Wheeler	37
Crane	37			Ochiltree		Wichita	5
Crockett	8	Hutchinson		Oldham		Wilbarger	37
Crosby	2	Irion	2	Orange		Willacy	30
Culberson	8	Jack		Palo Pinto		Williamson	7
Dallam	37	Jackson		Panola		Wilson	7
Dallas		Jasper		Parker		Winkler	37
	25 37	Jasper Jeff Davis	28 8			Wise	37 25
Dawson	_			Parmer			
Deaf Smith	37	Jefferson		Pecos		Wood	28
Delta	25	00		Polk		Yoakum	37
Denton	25				2	Young	37
DeWitt	27	Johnson		Presidio	8	Zapata	30
Dickens	37	Jones	25	Rains		Zavala	30
Dimmit	30			Randall	2		

Special Provision to Item 000 Nondiscrimination



1. DESCRIPTION

All recipients of federal financial assistance are required to comply with various nondiscrimination laws including Title VI of the Civil Rights Act of 1964, as amended, (Title VI). Title VI forbids discrimination against anyone in the United States on the grounds of race, color, or national origin by any agency receiving federal funds.

Texas Department of Transportation, as a recipient of Federal financial assistance, and under Title VI and related statutes, ensures that no person shall on the grounds of race, religion (where the primary objective of the financial assistance is to provide employment per 42 U.S.C. § 2000d-3), color, national origin, sex, age or disability be excluded from participation in, be denied the benefits of, or otherwise be subjected to discrimination under any Department programs or activities.

2. DEFINITION OF TERMS

Where the term "contractor" appears in the following six nondiscrimination clauses, the term "contractor" is understood to include all parties to contracts or agreements with the Texas Department of Transportation.

3. NONDISCRIMINATION PROVISIONS

During the performance of this contract, the contractor agrees as follows:

- 3.1. **Compliance with Regulations**. The Contractor shall comply with the Regulations relative to nondiscrimination in Federally-assisted programs of the Department of Transportation (hereinafter, "DOT") Title 49, Code of Federal Regulations, Part 21, as they may be amended from time to time, (hereinafter referred to as the Regulations), which are herein incorporated by reference and made a part of this contract.
- 3.2. **Nondiscrimination**. The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor shall not participate either directly or indirectly in the discrimination prohibited by section 21.5 of the Regulations, including employment practices when the contract covers a program set forth in Appendix B of the Regulations.
- 3.3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment: In all solicitations either by competitive bidding or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials or leases of equipment, each potential subcontractor or supplier shall be notified by the contractor of the contractor's obligations under this contract and the Regulations relative to nondiscrimination on the grounds of race, color, or national origin.
- 3.4. Information and Reports: The contractor shall provide all information and reports required by the Regulations or directives issued pursuant thereto, and shall permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Texas Department of Transportation to be pertinent to ascertain compliance with such Regulations, orders and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish this information the contractor shall so certify to the Recipient, or the Texas Department of Transportation as appropriate, and shall set forth what efforts it has made to obtain the information.

- 3.5. **Sanctions for Noncompliance**. In the event of the contractor's noncompliance with the nondiscrimination provisions of this contract, the Recipient shall impose such contract sanctions as it or the Texas Department of Transportation may determine to be appropriate, including, but not limited to:
 - withholding of payments to the contractor under the contract until the contractor complies, and/or
 - cancellation, termination or suspension of the contract, in whole or in part.
- 3.6. Incorporation of Provisions. The contractor shall include the provisions of paragraphs (1) through (6) in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Regulations, or directives issued pursuant thereto. The contractor shall take such action with respect to any subcontract or procurement as the Recipient or the Texas Department of Transportation may direct as a means of enforcing such provisions including sanctions for non-compliance: Provided, however, that, in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or supplier as a result of such direction, the contractor may request the Recipient to enter into such litigation to protect the interests of the Recipient, and, in addition, the contractor may request the United States to enter into such litigation to protect the interests of the United States.

2

09-14 Statewide

Special Provision to Item 000 Small Business Enterprise in State Funded Projects



1. DESCRIPTION

The purpose of this Special Provision is to carry out the Texas Department of Transportation's policy of ensuring that Small Business Enterprise (SBE) has an opportunity to participate in the performance of contracts. If the SBE goal is greater than zero, Article A of this Special Provision shall apply to this Contract; otherwise, Article B of this Special Provision applies. The percentage goal for SBE participation in the work to be performed under this contract will be shown in the proposal.

2. DEFINITIONS

Small Business Enterprise (SBE) is a firm (including affiliates) certified by the Department whose annual gross receipts do not exceed the U.S. Small Business Administration's size standards for 4 consecutive years. Firms certified as Historically Underutilized Businesses (HUBs) by the Texas Comptroller of Public Accounts and as Disadvantaged Business Enterprises (DBEs) by the Texas Uniform Certification Program automatically qualify as SBEs.

- 2.1. Article A SBE Goal is Greater than Zero.
- 2.1.1. Policy. The Department is committed to providing contracting opportunities for small businesses. In this regard, it is the Department's policy to develop and maintain a program in order to facilitate contracting opportunities for small businesses. Consequently, the requirements of the Department's Small Business Enterprise Program apply to this contract as follows:
- 2.1.1.1. The Contractor shall make a good faith effort to meet the SBE goal for this contract.
- 2.1.1.2. The Contractor and any Subcontractors shall not discriminate on the basis of race, color, national origin, age, disability or sex in the award and performance of this contract. These nondiscrimination requirements shall be incorporated into any subcontract and purchase order.
- 2.1.1.3. After a conditional award is made to the low bidder, the Department will determine the adequacy of a Contractor's efforts to meet the contract goal, as is outlined under Section 2, "Contractor's Responsibilities." If the requirements of Section 2 are met, the contract will be forwarded to the Contractor for execution.

The Contractor's performance, during the construction period of the contract in meeting the SBE goal, will be monitored by the Department.

- 2.1.2. Contractor's Responsibilities. These requirements must be satisfied by the Contractor. A SBE Contractor may satisfy the SBE requirements by performing at least 25% of the contract work with its own organization as defined elsewhere in the contract.
- 2.1.2.1. The Contractor shall submit a completed SBE Commitment Agreement Form for each SBE they intend to use to satisfy the SBE goal so as to arrive in the Department's Office of Civil Rights (OCR) in Austin, Texas not later than 5:00 p.m. on the 10th business day, excluding national holidays, after the conditional award of the contract. When requested, additional time, not to exceed 7 business days, excluding national holidays, may be granted based on documentation submitted by the Contractor.
- 2.1.2.2. A Contractor who cannot meet the contract goal, in whole or in part, shall document the good faith efforts taken to meet the SBE goal. The Department will consider as good faith efforts all documented explanations

1 09-14 Statewide

	that are submitted and that describe a Contractor's failure to meet a SBE goal or obtain SBE participation, including:
2.1.2.2.1.	Advertising in general circulation, trade association, and/or minority/women focus media concerning subcontracting opportunities,

- 2.1.2.2.2. Dividing the contract work into reasonable portions in accordance with standard industry practices,
- 2.1.2.2.3. Documenting reasons for rejection or meeting with the rejected SBE to discuss the rejection,
- 2.1.2.2.4. Providing qualified SBEs with adequate information about bonding, insurance, plans, specifications, scope of work, and the requirements of the contract,
- 2.1.2.2.5. Negotiating in good faith with qualified SBEs, not rejecting qualified SBEs who are also the lowest responsive bidder, and;
- 2.1.2.2.6. Using the services of available minorities and women, community organizations, contractor groups, local, state and federal business assistance offices, and other organizations that provide support services to SBEs.
- 2.1.2.3. The good faith effort documentation is due at the time and place specified in Subarticle 2.(a). of this Special Provision. The Director of the DBE & SBE Programs Section will evaluate the Contractor's documentation. If it is determined that the Contractor has failed to meet the good faith effort requirements, the Contractor will be given an opportunity for reconsideration by the Department.
- 2.1.2.4. Should the bidder to whom the contract is conditionally awarded refuse, neglect or fail to meet the SBE goal and/or demonstrate to the Department's satisfaction sufficient efforts to obtain SBE participation, the proposal guaranty filed with the bid shall become the property of the State, not as a penalty, but as liquidated damages to the Department.
- 2.1.2.5. The Contractor must not terminate a SBE subcontractor submitted on a commitment agreement for a contract with an assigned goal without the prior written consent of the Department.
- 2.1.2.6. The Contractor shall designate a SBE contact person who will administer the Contractor's SBE program and who will be responsible for submitting reports, maintaining records, and documenting good faith efforts to use SBEs.
- 2.1.2.7. The Contractor must inform the Department of the representative's name, title and telephone number within 10 days of beginning work.
- 2.1.3. Eligibility of SBEs.
- 2.1.3.1. The Department certifies the eligibility of SBEs.
- 2.1.3.2. The Department maintains and makes available to interested parties a directory of certified SBEs.
- 2.1.3.3. Only firms certified at the time of letting or at the time the commitments are submitted are eligible to be used in the information furnished by the Contractor required under Section 2.(a) above.
- 2.1.3.4. Certified HUBs and DBEs are eligible as SBEs.
- 2.1.3.5. Small Business Size Regulations and Eligibility is referenced on e-CFR (Code of Federal Regulations), Title 13 Business Credit and Assistance, Chapter 1 Small Business Administration, Part 121 Small Business Size Regulations, Subpart A Size Eligibility Provisions and Standards.
- 2.1.4. **Determination of SBE Participation**. SBE participation shall be counted toward meeting the SBE goal in this contract in accordance with the following:

2 09-14 Statewide

- 2.1.4.1. A Contractor will receive credit for all payments actually made to a SBE for work performed and costs incurred in accordance with the contract, including all subcontracted work.
- 2.1.4.2. A SBE Contractor or subcontractor may not subcontract more than 75% of a contract. The SBE shall perform not less than 25% of the value of the contract work with its own organization.
- 2.1.4.3. A SBE may lease equipment consistent with standard industry practice. A SBE may lease equipment from the prime contractor if a rental agreement, separate from the subcontract specifying the terms of the lease arrangement, is approved by the Department prior to the SBE starting the work in accordance with the following:
- 2.1.4.3.1. If the equipment is of a specialized nature, the lease may include the operator. If the practice is generally acceptable with the industry, the operator may remain on the lessor's payroll. The operator of the equipment shall be subject to the full control of the SBE, for a short term, and involve a specialized piece of heavy equipment readily available at the job site.
- 2.1.4.3.2. For equipment that is not specialized, the SBE shall provide the operator and be responsible for all payroll and labor compliance requirements.

2.1.5. Records and Reports.

2.1.5.1. The Contractor shall submit monthly reports, after work begins, on SBE payments, (including payments to HUBs and DBEs). The monthly reports are to be sent to the Area Engineer's office. These reports will be due within 15 days after the end of a calendar month.

> These reports will be required until all SBE subcontracting or supply activity is completed. The "SBE Progress Report" is to be used for monthly reporting. Upon completion of the contract and prior to receiving the final payment, the Contractor shall submit the "SBE Final Report" to the Office of Civil Rights and a copy to the Area Engineer. These forms may be obtained from the Office of Civil Rights and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by requesting, on a random basis, copies of invoices and cancelled checks paid to SBEs. When the SBE goal requirement is not met, documentation supporting Good Faith Efforts, as outlined in Section 2.(b) of this Special Provision, must be submitted with the Final Report.

- 2.1.5.2. SBE subcontractors and/or suppliers should be identified on the monthly report by SBE certification number. name and the amount of actual payment made to each during the monthly period. These reports are required regardless of whether or not SBE activity has occurred in the monthly reporting period.
- 2.1.5.3. All such records must be retained for a period of 3 years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the Department.
- 2.1.6. Compliance of Contractor. To ensure that SBE requirements of this contract are complied with, the Department will monitor the Contractor's efforts to involve SBEs during the performance of this contract. This will be accomplished by a review of monthly reports submitted by the Contractor indicating his progress in achieving the SBE contract goal and by compliance reviews conducted by the Department.

A Contractor's failure to comply with the requirements of this Special Provision shall constitute a material breach of this contract. In such a case, the Department reserves the right to employ remedies as the Department deems appropriate in the terms of the contract.

2.2. Article B - No SBE Goal.

2.2.1. Policy. It is the policy of the Department that SBEs shall have an opportunity to participate in the performance of contracts. Consequently, the requirements of the Department's Small Business Enterprise Program apply to this contract as specified in Section 2-5 of this Article.

> 3 09-14

- 2.2.2. **Contractor's Responsibilities**. If there is no SBE goal, the Contractor will offer SBEs an opportunity to participate in the performance of contracts and subcontracts.
- 2.2.3. **Prohibit Discrimination**. The Contractor and any subcontractor shall not discriminate on the basis of race, color, national origin, religion, age, disability or sex in the award and performance of contracts. These nondiscrimination requirements shall be incorporated into any subcontract and purchase order.
- 2.2.4. Records and Reports.
- 2.2.4.1. The Contractor shall submit reports on SBE (including HUB and DBE) payments. The reports are to be sent to the Area Engineer's office. These reports will be due annually by the 31st of August or at project completion, whichever comes first.

These reports will be required until all SBE subcontracting or supply activity is completed. The "SBE Progress Report" is to be used for reporting. Upon completion of the contract and prior to receiving the final payment, the Contractor shall submit the "SBE Final Report" to the Office of Civil Rights and a copy to the Area Engineer. These forms may be obtained from the Office of Civil Rights and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by requesting copies of invoices and cancelled checks paid to SBEs on a random basis.

- 2.2.4.2. SBE subcontractors and/or suppliers should be identified on the report by SBE Certification Number, name and the amount of actual payment made.
- 2.2.4.3. All such records must be retained for a period of 3 years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the Department.

4 09-14 Statewide

Special Provision 000 Certificate of Interested Parties (Form 1295)



Submit a notarized Form 1295, "Certificate of Interested Parties," in the following instances:

- at Contract execution for Contracts awarded by the Commission;
- at Contract execution for Contracts awarded by the District Engineer or Chief Engineer with an award amount of \$1,000,000 or more; at any time an existing Contract awarded by the District Engineer or Chief Engineer increases in value to \$1,000,000 or more due to changes in the Contract; at any time there is an increase of \$1,000,000 or more to an existing Contract (change orders, extensions, and renewals); or
- at any time there is a change to the information in Form 1295, when the form was filed for an existing Contract.

Form 1295 and instructions on completing and filing the form are available on the Texas Ethics Commission website.

Special Provision 000 Important Notice to Contractors



For Dollar Amoun	t of Original Contract	Dollar Amount of Daily Contract Administration Liquidated		
From More Than	To and including	Damages per Working Day		
0	1,000,000	618		
1,000,000	3,000,000	832		
3,000,000	5,000,000	940		
5,000,000	15,000,000	1317		
15,000,000	25,000,000	1718		
25,000,000	50,000,000	2411		
50,000,000	Over 50,000,000	4265		

In addition to the amount shown in Table 1, the Liquidated Damages will be increased by the amount shown in Item 8 of the General Notes for Road User Cost (RUC), when applicable.

Special Provision 000 Notice of Contractor Performance Evaluations



1. GENERAL

In accordance with Texas Transportation Code §223.012, the Engineer will evaluate Contractor performance based on quality, safety, and timeliness of the project.

2. DEFINITIONS

2.1. **Project Recovery Plan (PRP)**—a formal, enforceable plan developed by the Contractor, in consultation with the District, that documents the cause of noted quality, safety, and timeliness issues and specifies how the Contractor proposes to correct project-specific performance deficiencies.

In accordance with Title 43, Texas Administrative Code (TAC), §9.23, the District will request a PRP if the Contractor's performance on a project is below the Department's acceptable standards and will monitor the Contractor's compliance with the established plan.

2.2. **Corrective Action Plan (CAP)**—a formal, enforceable plan developed by the Contractor, and proposed for adoption by the Construction or Maintenance Division, that documents the cause of noted quality, safety, and timeliness issues and specifies how the Contractor proposes to correct statewide performance deficiencies.

In accordance with 43 TAC §9.23, the Division will request a CAP if the average of the Contractor's statewide final evaluation scores falls below the Department's acceptable standards for the review period and will monitor the Contractor's compliance with the established plan.

3. CONTRACTOR EVALUATIONS

In accordance with Title 43, Texas Administrative Code (TAC) §9.23, the Engineer will schedule evaluations at the following intervals, at minimum:

- Interim evaluations—at or within 30 days after the anniversary of the notice to proceed, for Contracts extending beyond 1 yr., and
- Final evaluation—upon project closeout.

In case of a takeover agreement, neither the Surety nor its performing Contractor will be evaluated.

In addition to regularly scheduled evaluations, the Engineer may schedule an interim evaluation at any time to formally communicate issues with quality, safety, or timeliness. Upon request, work with the Engineer to develop a PRP to document expectations for correcting deficiencies.

Comply with the PRP as directed. Failure to comply with the PRP may result in additional remedial actions available to the Engineer under Item 5, "Control of the Work." Failure to meet a PRP to the Engineer's satisfaction may result in immediate referral to the Performance Review Committee for consideration of further action against the Contractor.

The Engineer will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards or comply with a PRP, including consideration of sufficient time.

Follow the escalation ladder if there is a disagreement regarding an evaluation or disposition of a PRP. The Contractor may submit additional documentation pertaining to the dispute. The District Engineer's decision

on a Contractor's evaluation score and recommendation of action required in a PRP or follow up for non-compliance is final.

4. DIVISION OVERSIGHT

Upon request of the Construction or Maintenance Division, develop and submit for Division approval a proposed CAP to document expectations for correcting deficiencies in the performance of projects statewide.

Comply with the CAP as directed. The CAP may be modified at any time up to completion or resolution after written approval of the premise of change from the Division. Failure to meet an adopted or revised adopted CAP to the Division's satisfaction within 120 days will result in immediate referral to the Performance Review Committee for consideration of further action against the Contractor.

The Division will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards or comply with a CAP, including consideration of sufficient time and associated costs as appropriate.

5. PERFORMANCE REVIEW COMMITTEE

The Performance Review Committee, in accordance with 43 TAC §9.24, will review at minimum all final evaluations, history of compliance with PRPs, any adopted CAPs including agreed modifications, any information about events outside a Contractor's control contributing to the Contractor's performance, and any documentation submitted by the Contractor and may recommend one or more of the following actions:

- take no action.
- reduce the Contractor's bidding capacity,
- prohibit the Contractor from bidding on one or more projects,
- immediately suspend the Contractor from bidding for a specified period of time, by reducing the Contractor's bidding capacity to zero, or
- prohibit the Contractor from being awarded a Contract on which they are the apparent low bidder.

The Deputy Executive Director will determine any further action against the Contractor.

6. APPEALS PROCESS

In accordance with 43 TAC §9.25, the Contractor may appeal remedial actions determined by the Deputy Executive Director.

Special Provision to Item 2 Instructions to Bidders



Item 2, "Instructions to Bidders," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 2.3., "Issuing Proposal Forms," is supplemented by the following:

■ the Bidder or affiliate of the Bidder that was originally determined as the apparent low Bidder on a project, but was deemed nonresponsive for failure to register or participate in the Department of Homeland Security's (DHS) E-Verify system as specified in Article 2.15., "Department of Homeland Security (DHS) E-Verify System," is prohibited from rebidding that specific project.

Article 2.7., "Nonresponsive Bid," is supplemented by the following:

■ the Bidder failed to participate in the Department of Homeland Security's (DHS) as specified in Article 2.15., "Department of Homeland Security (DHS) E-Verify System."

Article 2.15., "Department of Homeland Security (DHS) E-Verify System," is added.

The Department will not award a Contract to a Contractor that is not registered in the DHS E-Verify system. Remain active in E=Verify throughout the life of the contract. In addition, in accordance with paragraph six of Article 8.2, "Subcontracting," include this requirement in all subcontracts and require that subcontractors remain active in E-Verify until their work is completed.

If the apparent low Bidder does not appear on the DHS E-Verify system prior to award, the Department will notify the Contractor that they must submit documentation showing that they are compliant within 5-business days after the date the notification was sent. A Contractor who fails to comply or respond within the deadline will be declared non-responsive and the Department will execute the proposal guaranty. The proposal guaranty will become the property of the State, not as a penalty, but as liquidated damages. The Bidder forfeiting the proposal guaranty will not be considered in future proposals for the same work unless there has been a substantial change in the scope of the work.

The Department may recommend that the Commission:

- reject all bids, or
- award the Contract to the new apparent low Bidder, if the Department is able to verify the Bidder's participation in the DHS E-verify system. For the Bidder who is not registered in E-Verify, the Department will allow for one business day after notification to provide proof of registration.

If the Department is unable to verify the new apparent low Bidder's participation in the DHS E-Verify system within one calendar day:

- the new apparent low Bidder will not be deemed nonresponsive,
- the new apparent low Bidder's guaranty will not be forfeited,
- the Department will reject all bids, and
- the new apparent low Bidder will remain eligible to receive future proposals for the same project.

Special Provision to Item 2 Instructions to Bidders



Item 2, "Instructions to Bidders" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 3., "Issuing Proposal Forms," is supplemented by the following:

The Electronic State Business Daily (ESBD), the Integrated Contractor Exchange (iCX) system, and the project proposal are the official sources of advertisement and bidding information for the State and Local Lettings. Bidders should bid the project using the information found therein, including any addenda. These sources take precedence over information from other sources, including TxDOT webpages, which are unofficial and intended for informational purposes only.

Special Provision to Item 3 Award and Execution Contract



Item 3, Award and Execution of Contract," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 4.3, "**Insurance**." The first sentence is voided and replaced by the following:

For construction and building Contracts, submit a certificate of insurance showing coverages in accordance with Contract requirements. For routine maintenance Contracts, refer to Article 8, "Beginning of Work."

Article 8, "Beginning of Work." The first sentence is supplemented by the following:

For a routine maintenance Contract, do not begin work until a certificate of insurance showing coverages in accordance with the Contract requirements is provided and accepted.

Special Provision to Item 3 Award and Execution of Contract



Item 3, "Award and Execution of Contract" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 4.3 "Insurance" is being amended by the following:

Table 2
Insurance Requirements

modranoc requirements					
Type of Insurance	Amount of Coverage				
Commercial General Liability Insurance	Not Less Than:				
•	\$600,000 each occurrence				
Business Automobile Policy	Not Less Than:				
•	\$600,000 combined single limit				
Workers' Compensation	Not Less Than:				
7	Statutory				
All Risk Builder's Risk Insurance	100% of Contract Price				
(For building-facilities contracts only)					

Special Provision to Item 5 Control of the Work



Item 5, "Control of the Work," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 5.1, "Authority of Engineer," is voided and replaced by the following.

The Engineer has the authority to observe, test, inspect, approve, and accept the work. The Engineer decides all guestions about the quality and acceptability of materials, work performed, work progress, Contract interpretations, and acceptable Contract fulfillment. The Engineer has the authority to enforce and make effective these decisions.

The Engineer acts as a referee in all questions arising under the terms of the Contract. The Engineer's decisions will be final and binding.

The Engineer will pursue and document actions against the Contractor as warranted to address Contract performance issues. Contract remedies include, but are not limited to, the following:

- conducting interim performance evaluations requiring a Project Recovery Plan, in accordance with Title 43, Texas Administrative Code (TAC) §9.23,
- requiring the Contractor to remove and replace defective work, or reducing payment for defective work,
- removing an individual from the project,
- suspending the work without suspending working day charges,
- assessing standard liquidated damages to recover the Department's administrative costs, including additional projectspecific liquidated damages when specified in the Contract in accordance with 43 TAC §9.22,
- withholding estimates,
- declaring the Contractor to be in default of the Contract, and
- in case of a Contractor's failure to meet a Project Recovery Plan, referring the issue directly to the Performance Review Committee for consideration of further action against the Contractor in accordance with 43 TAC §9.24.

The Engineer will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards, including consideration of sufficient time.

Follow the issue escalation ladder if there is disagreement regarding the application of Contract remedies.

Special Provision to Item 5 Control of the Work



Item 5, "Control of the Work" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 5.4, "Coordination of Plans, Specifications, and Special Provisions," the last sentence of the last paragraph is replaced by the following:

Failure to promptly notify the Engineer will constitute a waiver of all contract claims against the Department for misunderstandings or ambiguities that result from the errors, omissions, or discrepancies.

Special Provision to Item 6 Control of Materials



For this project, Item 6, "Control of Materials," of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 4., "Sampling, Testing, and Inspection," is supplemented by the following:

Meet with the Engineer and choose either the Department or a Department-selected Commercial Lab (CL) for conducting the subset of project-level sampling and testing shown in Table 1, "Select Guide Schedule Sampling and Testing." Selection may be made on a test by test basis. CLs will meet the testing turnaround times shown (includes test time and time for travel/sampling and reporting) and in all cases issue test reports as soon as possible.

If the Contractor chooses a Department-selected CL for any Table 1 sampling and testing:

- notify the Engineer, District Lab, and the CL of project scheduling that may require CL testing;
- provide the Engineer, District Lab, and CL at least 24 hours' notice by phone and e-mail;
- reimburse the Department for CL Table 1 testing using the contract fee schedule for the CL (including mileage and travel/standby time) at the minimum guide schedule testing frequencies;
- reimburse the Department for CL Table 1 testing above the minimum guide schedule frequencies for retesting when minimum frequency testing results in failures to meet specification limits;
- agree with the Engineer and CL upon a policy regarding notification for testing services;
- give any cancellation notice to the Engineer, District Lab, and CL by phone and e-mail;
- reimburse the Department a \$150 cancellation fee to cover technician time and mileage charges for previously scheduled work cancelled without adequate notice, which resulted in mobilization of technician and/or equipment by the CL; and
- all CL charges will be reimbursed to the Department by a deduction from the Contractor's monthly pay estimate.

If the CL does not meet the Table 1 turnaround times, testing charge to the Contractor will be reduced by 50% for the first late day and an additional 5% for each succeeding late day.

Approved CL project testing above the minimum testing frequencies in the Guide Schedule of Sampling and Testing, and not as the result of failing tests, will be paid by the Department.

Other project-level Guide Schedule sampling and testing not shown on Table 1 will be the responsibility of the Department.

1

09-14 Statewide

Table 1
Select Guide Schedule Sampling and Testing (Note 1)

TxDOT Test	Test Description	Turn- Around Time (Calendar days)
	SOILS/BASE	
Tex-101-E	Preparation of Soil and Flexible Base Materials for Testing (included in other tests)	
Tex-104-E	Liquid Limit of Soils (included in 106-E)	
Tex-105-E	Plastic Limit of Soils (included in 106-E)	
Tex-106-E	Calculating the Plasticity Index of Soils	7
Tex-110-E	Particle Size Analysis of Soils	6
Tex-113-E	Moisture-Density Relationship of Base Materials	7
Tex-114-E	Moisture-Density Relationship of Subgrade and Embankment Soil	7
Tex-115-E	Field Method for In-Place Density of Soils and Base Materials	2
Tex-116-E	Ball Mill Method for the Disintegration of Flexible Base Material	5
Tex-117-E, Part II	Triaxial Compression Tests For Disturbed Soils and Base Materials (Part II)	6
Tex-113-E w/ Tex-117-E	Moisture-Density Relationship of Base Materials with Triaxial Compression Tests For Disturbed Soils and Base Materials (Part II)	10
Tex-140-E	Measuring Thickness of Pavement Layer	2
Tex-145-E	Determining Sulfate Content in Soils - Colorimetric Method	4
	HOT MIX ASPHALT	
Tex-200-F	Sieve Analysis of Fine and Coarse Aggregate (dry, from ignition oven with known correction factors)	1 (Note 2)
Tex-203-F	Sand Equivalent Test	3
Tex-206-F, w/ Tex-207-F, Part I, w/ Tex-227-F	(Lab-Molded Density of Production Mixture – Texas Gyratory) Method of Compacting Test Specimens of Bituminous Mixtures with Density of Compacted Bituminous Mixtures, Part I - Bulk Specific Gravity of Compacted Bituminous Mixtures, with Theoretical Maximum Specific Gravity of Bituminous Mixtures	1 (Note 2)
Tex-207-F, Part I &/or Part VI	(In-Place Air Voids of Roadway Cores) Density of Compacted Bituminous Mixtures, Part I- Bulk Specific Gravity of Compacted Bituminous Mixtures &/or Part VI - Bulk Specific Gravity of Compacted Bituminous Mixtures Using the Vacuum Method	1 (Note 2)
Tex-207-F, Part V	Density of Compacted Bituminous Mixtures, Part V- Determining Mat Segregation using a Density-Testing Gauge	3
Tex-207-F, Part VII	Density of Compacted Bituminous Mixtures, Part VII - Determining Longitudinal Joint Density using a Density-Testing Gauge	4
Tex-212-F	Moisture Content of Bituminous Mixtures	3
Tex-217-F	Deleterious Material and Decantation Test for Coarse Aggregate	4
Tex-221-F	Sampling Aggregate for Bituminous Mixtures, Surface Treatments, and LRA (included in other tests)	
Tex-222-F	Sampling Bituminous Mixtures (included in other tests)	
Tex-224-F	Determination of Flakiness Index	3
Tex-226-F	Indirect Tensile Strength Test (production mix)	4
Tex-235-F	Determining Draindown Characteristics in Bituminous Materials	3
Tex-236-F (Correction Factors)	Asphalt Content from Asphalt Paving Mixtures by the Ignition Method (Determining Correction Factors)	4
Tex-236-F	Asphalt Content from Asphalt Paving Mixtures by the Ignition Method (Production Mixture)	1 (Note 2)
Tex-241-F w/ Tex-207-F, Part I, w/ Tex-227-F	(Lab-Molded Density of Production Mixture – Superpave Gyratory) Superpave Gyratory Compacting of Specimens of Bituminous Mixtures (production mixture) with Density of Compacted Bituminous Mixtures, Part I - Part I - Bulk Specific Gravity of Compacted Bituminous Mixtures, with Theoretical Maximum Specific Gravity of Bituminous Mixtures	1 (Note 2)
Tex-242-F	Hamburg Wheel-Tracking Test (production mix, molded samples)	3
Tex-244-F	Thermal Profile of Hot Mix Asphalt	1
Tex-246-F	Permeability of Water Flow of Hot Mix Asphalt	3
Tex-280-F	Flat and Elongated Particles	3
Tex-530-C	Effect of Water on Bituminous Paving Mixtures (production mix)	4

Sampling Flexible Base, Stone, Gravel, Sand, and Mineral Aggregates					
Sampling Flexible base, Storie, Graver, Sand, and Milleral Aggregates	3				
Tex-410-A Abrasion of Coarse Aggregate Using the Los Angeles Machine					
Soundness of Aggregate by Use of Sodium Sulfate or Magnesium Sulfate	12				
Degradation of Coarse Aggregate by Micro-Deval Abrasion	5				
CHEMICAL					
Acid Insoluble Residue for Fine Aggregate	4				
GENERAL					
HMA Production Specialist [TxAPA – Level 1-A] (\$/hr)					
HMA Roadway Specialist [TxAPA – Level 1-B] (\$/hr)					
Technician Travel/Standby Time (\$/hr)					
Per Diem (\$/day – meals and lodging)					
fileage Rate (\$/mile from closest CL location)					
d	Abrasion of Coarse Aggregate Using the Los Angeles Machine Soundness of Aggregate by Use of Sodium Sulfate or Magnesium Sulfate Degradation of Coarse Aggregate by Micro-Deval Abrasion CHEMICAL Acid Insoluble Residue for Fine Aggregate GENERAL dist [TxAPA – Level 1-A] (\$/hr) st [TxAPA – Level 1-B] (\$/hr) by Time (\$/hr) s and lodging)				

3 09-14 Statewide

Note 1– Turn-Around Time includes test time and time for travel/sampling and reporting.

Note 2 – These tests require turn-around times meeting the governing specifications. Provide test results within the stated turn-around time.

CL is allowed one additional day to provide the signed and sealed report.

Special Provision to Item 6 **Control of Materials**



Item 6, "Control of Materials" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 6.10., "Hazardous Materials," is voided and replaced by the following:

Comply with the requirements of Article 7.12., "Responsibility for Hazardous Materials."

Notify the Engineer immediately when a visual observation or odor indicates that materials on sites owned or controlled by the Department may contain hazardous materials. Except as noted herein, the Department is responsible for testing, removing, and disposing of hazardous materials not introduced by the Contractor. The Engineer may suspend work wholly or in part during the testing, removing, or disposing of hazardous materials, except in the case where hazardous materials are introduced by the Contractor.

Use materials that are free of hazardous materials. Notify the Engineer immediately if materials are suspected to contain hazardous materials. If materials delivered to the project by the Contractor are suspected to contain hazardous materials, have an approved commercial laboratory test the materials for the presence of hazardous materials as approved. Remove, remediate, and dispose of any of these materials found to contain hazardous materials. The work required to comply with this section will be at the Contractor's expense if materials are found to contain hazardous materials. Working day charges will not be suspended and extensions of working days will not be granted for activities related to handling hazardous material introduced by the Contractor. If suspected materials are not found to contain hazardous materials, the Department will reimburse the Contractor for hazardous materials testing and will adjust working day charges if the Contractor can show that this work impacted the critical path.

- 10.1. Painted Steel Requirements. Coatings on existing steel contain hazardous materials unless otherwise shown on the plans. Remove paint and dispose of steel coated with paint containing hazardous materials is in accordance with the following:
- 10.1.1. Removing Paint From Steel For contracts that are specifically for painting steel, Item 446, "Field Cleaning and Painting Steel" will be included as a pay item. Perform work in accordance with that item.

For projects where paint must be removed to allow for the dismantling of steel or to perform other work, the Department will provide for a separate contractor (third party) to remove paint containing hazardous materials prior to or during the Contract. Remove paint covering existing steel shown not to contain hazardous materials in accordance with Item 446, "Field Cleaning and Painting Steel."

10.1.2. Removal and Disposal of Painted Steel. For steel able to be dismantled by unbolting, paint removal will not be performed by the Department. The Department will remove paint, at locations shown on the plans or as agreed, for the Contractor's cutting and dismantling purposes. Utilize Department cleaned locations for dismantling when provided or provide own means of dismantling at other locations.

Painted steel to be retained by the Department will be shown on the plans. For painted steel that contains hazardous materials, dispose of the painted steel at a steel recycling or smelting facility unless otherwise shown on the plans. Maintain and make available to the Engineer invoices and other records obtained from the facility showing the received weight of the steel and the facility name. Dispose of steel that does not contain hazardous material coatings in accordance with federal, state and local regulations.

10.2. Asbestos Requirements. The plans will indicate locations or elements where asbestos containing materials (ACM) are known to be present. Where ACM is known to exist or where previously unknown ACM has been found, the Department will arrange for abatement by a separate contractor prior to or during the Contract. Notify the Engineer of proposed dates of demolition or removal of structural elements with ACM at least 60 days before beginning work to allow the Department sufficient time for abatement.

The Department of State Health Services (DSHS), Asbestos Programs Branch, is responsible for administering the requirements of the National Emissions Standards for Hazardous Air Pollutants, 40 CFR Part 61, Subpart M and the Texas Asbestos Health Protection Rules (TAHPR). Based on EPA guidance and regulatory background information, bridges are considered to be a regulated "facility" under NESHAP. Therefore, federal standards for demolition and renovation apply.

The Department is required to notify the DSHS at least 10 working days (by postmarked date) before initiating demolition or renovation of each structure or load bearing member shown on the plans. If the actual demolition or renovation date is changed or delayed, notify the Engineer in writing of the revised dates in sufficient time to allow for the Department's notification to DSHS to be postmarked at least 10 days in advance of the actual work.

Failure to provide the above information may require the temporary suspension of work under Article 8.4., "Temporary Suspension of Work or Working Day Charges," due to reasons under the control of the Contractor. The Department retains the right to determine the actual advance notice needed for the change in date to address post office business days and staff availability.

10.3. Lead Abatement. Provide traffic control as shown on the plans, and coordinate and cooperate with the third party and the Department for managing or removing hazardous materials. Work for the traffic control shown on the plans and coordination work will not be paid for directly but will be subsidiary to pertinent Items.

2 - 2 02-18 Statewide

Special Provision to Item 7 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 7.7.2., "Texas Pollutant Discharge Elimination System (TPDES) Permits and Storm Water Pollution Prevention **Plans (SWP3),"** is voided and replaced by the following:

- 7.2. Texas Pollution Discharge Elimination System (TPDES) Permits and Storm Water Pollution Prevention Plans (SWP3).
- 7.2.1. Projects with less than one acre of soil disturbance including required associated project specific locations (PSL's) per TPDES GP TXR 150000.

No posting or filing will be required for soil disturbances within the right of way. Adhere to the requirements of the

7.2.2. Projects with one acre but less than five acres of soil disturbance including required associated PSL's per TPDES GP TXR 150000.

The Department will be considered a primary operator for Operational Control Over Plans and Specifications as defined in TPDES GP TXR 150000 for construction activity in the right of way. The Department will post a small site notice along with other requirements as defined in TPDES GP TXR 150000 as the entity of having operational control over plans and specifications for work shown on the plans in the right of way.

The Contractor will be considered a Primary Operator for Day-to-Day Operational Control as defined in TPDES GP TXR 150000 for construction activity in the right of way. In addition to the Department's actions, the Contractor will post a small site notice along with other requirements as defined in TPDES GP TXR 150000 as the entity of having day-to-day operational control of the work shown on the plans in the right of way. This is in addition to the Contractor being responsible for TPDES GP TXR 150000 requirements for on-right of way and off-right of way PSL's. Adhere to all requirements of the SWP3 as shown on the plans. The Contractor will be responsible for Implement the SWP3 for the project site in accordance with the plans and specifications, TPDES General Permit TXR150000, and as directed.

7.2.3. Projects with 5 acres or more of soil disturbance including required associated PSL's per TPDES GP TXR 150000.

The Department will be considered a primary operator for Operational Control Over Plans and Specifications as defined in TPDES GP TXR 150000 for construction activities in the right of way. The Department will post a large site notice, file a notice of intent (NOI), notice of change (NOC), if applicable, and a notice of termination (NOT) along with other requirements per TPDES GP TXR 150000 as the entity having operational control over plans and specifications for work shown on the plans in the right of way.

The Contractor will be considered a primary operator for <u>Day-to-Day Operational Control</u> as defined in TPDES GP TXR 150000 for construction activities in the right of way. In addition to the Department's actions, the Contractor shall file a NOI, NOC, if applicable, and NOT and post a large site notice along with other requirements as the entity of having day-to-day operational control of the work shown on the plans in the right of way. This is in addition to the Contractor

being responsible for TPDES GP TXR 150000 requirements for on- right of way and off- right of way PSL's. Adhere to all requirements of the SWP3 as shown on the plans.

Special Provision to Item 7 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 19.1., Minimum Wage Requirements for Federally Funded Contracts. The second paragraph is voided and replaced by the following:

Submit electronic payroll records to the Engineer using the Department's payroll system.

Section 19.2., Minimum Wage Requirements for State Funded Contracts. The second paragraph is voided and replaced by the following:

Submit electronic payroll records to the Engineer using the Department's payroll system.

Special Provision to Item 7 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 7.2.4., "Public Safety and Convenience." The first paragraph is deleted and replaced by the following.

Ensure the safety and convenience of the public and property as provided in the Contract and as directed. Keep existing roadways open to traffic or construct and maintain detours and temporary structures for safe public travel. Manage construction to minimize disruption to traffic. Maintain the roadway in a good and passable condition, including proper drainage and provide for ingress and egress to adjacent property.

If the construction of the project requires the closing of a highway, as directed, coordinate the closure with the Engineer and work to ensure all lanes and ramps possible are available during peak traffic periods before, during, and after significant traffic generator events to avoid any adverse economic impact on the municipalities during:

- dates or events as shown on the plans, and
- other dates as directed.

Special Provision to Item 007 Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below.

Section 2.6., "Barricades, Signs, and Traffic Handling," the first paragraph is voided and replaced by the following:

2.6. Barricades, Signs, and Traffic Handling. Comply with the requirements of Item 502 "Barricades, Signs, and Traffic Handling," and as directed. Provide traffic control devices that conform to the details shown on the plans, the TMUTCD, and the Department's Compliant Work Zone Traffic Control Device List maintained by the Traffic Safety Division. When authorized or directed, provide additional signs or traffic control devices not required by the plans.

Section 2.6.1., "Contractor Responsible Person and Alternative," is voided and replaced by the following:

2.6.1. Contractor Responsible Person and Alternative. Designate in writing, a Contractor's Responsible Person (CRP) and an alternate to be the representative of the Contractor who is responsible for taking or directing corrective measures regarding the traffic control. The CRP or alternate must be accessible by phone 24 hr. per day and able to respond when notified. The CRP and alternate must comply with the requirements of Section 2.6.5., "Training."

Section 2.6.2, "Flaggers," the first paragraph is voided and replaced by the following:

2.6.2. Flaggers. Designate in writing, a flagger instructor who will serve as a flagging supervisor and is responsible for training and assuring that all flaggers are qualified to perform flagging duties. Certify to the Engineer that all flaggers will be trained and make available upon request a list of flaggers trained to perform flagging duties.

Section 2.6.5, "Training," is voided and replaced by the following:

2.6.5. Training. Train workers involved with the traffic control using Department-approved training as shown on the "Traffic Control Training" Material Producer List.

> Coordinate enrollment, pay associated fees, and successfully complete Department-approved training or Contractor-developed training. Training is valid for the period prescribed by the provider. Except for law enforcement personnel training, refresher training is required every 4 yr. from the date of completion unless otherwise specified by the course provider. The Engineer may require training at a frequency instead of the period prescribed based on the Department's needs. Training and associated fees will not be measured or paid for directly but are considered subsidiary to pertinent Items.

Certify to the Engineer that workers involved in traffic control and other work zone personnel have been trained and make available upon request a copy of the certification of completion to the Engineer. Ensure the following is included in the certification of completion:

- name of provider and course title,
- name of participant,
- date of completion, and
- date of expiration.

Where Contractor-developed training or a Department-approved training course does not produce a certification, maintain a log of attendees. Make the log available upon request. Ensure the log is legible and includes the following:

- printed name and signature of participant,
- name and title of trainer, and
- date of training.
- 2.6.5.1. Contractor-developed Training. Develop and deliver Contractor-developed training meeting the minimum requirements established by the Department. The outline for this training must be submitted to the Engineer for approval at the preconstruction meeting. The CRP or designated alternate may deliver the training instead of the Department-approved training. The work performed and materials furnished to develop and deliver the training will not be measured or paid for directly but will be considered subsidiary to pertinent Items.
- 2.6.5.1.1. **Flagger Training Minimum Requirements.** A Contractor's certified flagging instructor is permitted to train other flaggers.
- 2.6.5.1.2. **Optional Contractor-developed Training for Other Work Zone Personnel.** For other work zone personnel, the Contractor may provide training meeting the curriculum shown below instead of Department-approved training.

Minimum curriculum for Contractor-provided training is as follows:

Contractor-developed training must provide information on the use of personnel protection equipment, occupational hazards and health risks, and other pertinent topics related to traffic management. The type and amount of training will depend on the job duties and responsibilities. Develop training applicable to the work being performed. Develop training to include the following topics.

- The Life You Save May Be Your Own (or other similar company safety motto).
- Purpose of the training.
 - It's the Law.
 - To make work zones safer for workers and motorist.
 - To understand what is needed for traffic control.
 - To save lives including your own.
- Personal and Co-Worker Safety.
 - High Visibility Safety Apparel. Discuss compliant requirements; inspect regularly for fading and
 reduced reflective properties; if night operations are required, discuss the additional and
 appropriate required apparel in addition to special night work risks; if moving operations are
 underway, discuss appropriate safety measures specific to the situation and traffic control plan.
 - Blind Areas. A blind area is the area around a vehicle or piece of construction equipment not
 visible to the operators, either by line of sight or indirectly by mirrors. Discuss the "Circle of Safety"
 around equipment and vehicles; use of spotters; maintain eye contact with equipment operators;
 and use of hand signals.
 - Runovers and Backovers. Remain alert at all times; keep a safe distance from traffic; avoid turning your back to traffic and if you must then use a spotter; and stay behind protective barriers, whenever possible. Note: It is not safe to sit on or lean against a concrete barrier, these barriers can deflect four plus feet when struck by a vehicle.
 - Look out for each other, warn co-workers.
 - Be courteous to motorists.
 - Do not run across active roadways.
 - Workers must obey traffic laws and drive courteously while operating vehicles in the work zones.
 - Workers must be made aware of company distracted driving policies.
- Night Time Operations. Focus should be placed on projects with a nighttime element.

- Traffic Control Training. Basics of Traffic Control.
 - Identify work zone traffic control supervisor and other appropriate persons to report issues to when they arise.
 - Emphasize that work zone traffic control devices must be in clean and in undamaged condition. If devices have been hit but not damaged, put back in their correct place and report to traffic control supervisor. If devices have been damaged, replace with new one and report to traffic control supervisor. If devices are dirty, faded or have missing or damaged reflective tape clean or replace and report to traffic control supervisor. Show examples of non-acceptable device conditions. Discuss various types of traffic control devices to be used and where spacing requirements can be found.
 - Channelizing Devices and Barricades with Slanted Stripes. Stripes are to slant in the direction
 you want traffic to stay or move to; demonstrate this with a device.
 - Traffic Queuing. Workers must be made aware of traffic queuing and the dangers created by it.
 Workers must be instructed to immediately notify the traffic control supervisor and other supervisory personnel if traffic is queuing beyond advance warning sign and devices or construction limits.
 - Signs. Signs must be straight and not leaning. Report problems to the traffic control supervisor or other as designated for immediate repair. Covered signs must be fully covered. If covers are damaged or out of place, report to traffic control supervisor or other as designated.

3 - 3 11-20 Statewide

Special Provision to Item 8 Prosecution and Progress



Item 8, "Prosecution and Progress" of the Standard Specification is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 8.2., "Subcontracting," is supplemented by the following paragraph, which is added as paragraph six to this article:

The Contractor certifies by signing the Contract that the Contractor will not enter into any subcontract with a subcontractor that is not registered in the Department of Homeland Security's (DHS) E-Verify system. Require that all subcontractors working on the project register and require that all subcontractors remain active in the DHS E-Verify system until their work is complete on the project.

Special Provision to Item 8 Prosecution and Progress



Item 8, "Prosecution and Progress" of the Standard Specifications is amended with respect to the clause cited below. No other clauses or requirements of this Item are waived or changed.

Article 8.7.2., "Wrongful Default," is revised and replaced by the following:

If it is determined after the Contractor is declared in default, that the Contractor was not in default, the rights and obligations of all parties will be the same as if termination had been issued for the convenience of the public as provided in Article 8.8 "Termination of Contract."

Special Provision to Item 009 Measurement and Payment



Item 009 "Measurement and Payment" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 9.5., "PROGRESS PAYMENTS" is supplemented with the following:

It is the Department's desire to pay a Contractor for work through the last working day of the month; however, the use of early cut-off dates for monthly estimates and MOH is a project management practice to manage workload at the Area Office level. Approval for using early cut-off dates is at the District's discretion. The earliest cut-off date for estimates is the 25th of the month.

Article 9.6., "PAYMENT FOR MATERIAL ON HAND (MOH)" first paragraph is amended as follows:

If payment for MOH is desired, request compensation for the invoice cost of acceptable nonperishable materials that have not been used in the work before the request, and that have been delivered to the work location or are in acceptable storage places. Nonperishable materials are those that do not have a shelf life or whose characteristics do not materially change when exposed to the elements. Include only materials that have been sampled, tested, approved, or certified, and are ready for incorporation into the work. Only materials which are completely constructed or fabricated on the Contractor's order for a specific Contract and are so marked and on which an approved test report has been issued are eligible. Payment for MOH may include the following types of items: concrete traffic barrier, precast concrete box culverts, concrete piling, reinforced concrete pipe, and illumination poles. Any repairs required after fabricated materials have been approved for storage will require approval of the Engineer before being made and will be made at the Contractor's expense. Include only those materials and products, when cumulated under an individual item or similar bid items, that have an invoice cost of at least \$1,000 in the request for MOH payment (e.g. For MOH eligibility, various sizes of conductor are considered similar bid items and may be cumulated to meet the threshold; for small roadside signs, the sign supports, mounting bolts, and the sign face is considered one bid item or similar bid items for more than one pay item for sign supports.) Requests for MOH are to be submitted at least two days before but not later than the estimate cutoff date unless otherwise agreed. If there is a need to request MOH after the established cut-off date, the district can make accommodation as the need arises. This needed accommodation is to be the exception, though, and not the rule.

Special Provision to Item 9 Measurement and Payment



Item 9, "Measurement and Payment" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 9.7.1.4.3., "Standby Equipment Costs," is voided and replaced by the following:

7.1.4.3. Standby Equipment Costs. Payment for standby equipment will be made in accordance with Section 9.7.1.4., "Equipment," except that the 15% markup will not be allowed and that:

Section 7.1.4.3.1., "Contractor-Owned Equipment," is voided and replaced by the following:

- 7.1.4.3.1. **Contractor-Owned Equipment**. For Contractor-owned equipment:
 - Standby will be paid at 50% of the monthly Equipment Watch rate after the regional and age adjustment factors have been applied. Operating costs will not be allowed. Calculate the standby rate as follows.

Standby rate = (FHWA hourly rate - operating costs) × 50%

- If an hourly rate is needed, divide the monthly *Equipment Watch* rate by 176.
- No more than 8 hr. of standby will be paid during a 24-hr. day period, nor more than 40 hr. per week.
- Standby costs will not be allowed during periods when the equipment would have otherwise been idle.

Special Provision to Item 247 Flexible Base



Item 247, "Flexible Base" of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Section 2.4., "Certification." This section is added.

Personnel certified by the Department-approved soils and base certification program must conduct all sampling, field testing, and laboratory testing required by the following:

- Section 2.1, "Aggregate,"
- Section 2.1.3.2, "Recycled Material (Including Crushed Concrete) Requirements,"
- Section 4.3, "Compaction," for measuring flexible base depth, and
- Section 4.3.2, "Density Control," for determining the roadway density and moisture content.

Supply the Engineer with a list of certified personnel and copies of their current certificates before laboratory and field testing is performed and when personnel changes are made. At any time during the project, the Engineer may perform production tests as deemed necessary in accordance with Item 5, "Control of the Work."

Section 2.5., "Reporting and Responsibilities." This section is added.

Use Department-provided templates to record and calculate all test data. Obtain the current version of the templates at http://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/forms/site-manager.html or from the Engineer. The Engineer and the Contractor will provide any available test results to the other party when requested. Record and electronically submit all test results and pertinent information on Department-provided templates.

Section 2.6., "Sampling." This section is added.

The Engineer will sample flexible base from stockpiles located at the production site or at the project location in accordance with Tex-400-A, Section 5.3. The Engineer will label the sample containers as "Engineer," "Contractor" or "Supplier," and "CST/M&P." Witness the sampling and take immediate possession of the sample containers labeled "Contractor" or "Supplier." The Engineer will maintain custody of the samples labeled "CST/M&P" until testing and reporting is completed.

Section 2.7., "Referee Testing." This section is added.

CST/M&P is the referee laboratory. The Contractor may request referee testing when the Engineer's test results fail to meet any of the material requirements listed in Table 1. Make the request via email within 5 working days after receiving test results from the Engineer. Submit test reports signed and sealed by a licensed professional engineer from a commercial laboratory listed on the Department's Material Producer List (MPL) of laboratories approved to perform compaction and triaxial compression testing located at http://ftp.dot.state.tx.us/pub/txdot-info/cmd/mpl/complabs.pdf. Submit completed test reports electronically on Department-provided templates in their original format. The referee laboratory will report test results to the Engineer within the allowable number of working days listed in Table 2 from the time the referee laboratory receives the samples. It is at the discretion of the Engineer or the referee laboratory to deny a referee request upon review of the test reports provided by the Contractor.

1

Table 2
Number of Allowable Working Days to Report Referee Test Results

Material Property	Test Method	Working Days
Gradation	Tex-110-E, Part I	5
Liquid Limit (Multi-Point Method)	Tex-104-E, Part I	5
Plasticity Index	Tex-106-E	5
Wet Ball Mill Value	Tex-116-E,	E
Wet Ball Mill, % Increase passing #40 sieve	Parts I and II	5
Compressive Strength ¹	Tex-117-E, Part II	6
Compressive Strength ²	Tex-117-E	12

- 1. Moisture-Density curve provided by the District
- 2. Moisture-Density curve determined by the referee laboratory

Section 4.6., "Ride Quality." This section is voided and replaced by the following.

Measurement of ride quality only applies to the final travel lanes that receive a 1- or 2-course surface treatment for the final riding surface, unless otherwise shown on the plans. Measure the ride quality of the base course either before or after the application of the prime coat, as directed, and before placement of the surface treatment. Use a certified profiler operator from the Department's MPL. When requested, furnish the Engineer documentation for the person certified to operate the profiler.

Provide all profile data to the Engineer in electronic data files within 3 days of measuring the ride quality using the format specified in <u>Tex-1001-S</u>. The Engineer will use Department software to evaluate longitudinal profiles to determine areas requiring corrective action. Correct 0.1-mi.sections for each wheel path having an average international roughness index (IRI) value greater than 100 in. per mile to an IRI value of 100 in. per mile or less, unless otherwise shown on the plans.

Re-profile and correct sections that fail to maintain ride quality, as directed. Correct re-profiled sections until specification requirements are met, as approved. Perform this work at no additional expense to the Department.

2

Special Provision to Item 300 Asphalt, Oils, and Emulsions



Item 300, "Asphalt, Oils, and Emulsions" of the Standard Specifications is replaced by Special Specification 3096, "Asphalts, Oils, and Emulsions." All Item 300 Special Provisions are no longer available, beginning with the April 2022 letting.

Special Provision to Item 302 Aggregates for Surface Treatments



Item 302, "Aggregates for Seal Coats," of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Section 2.1., "Aggregate." Tables 2 and 3 are voided and replaced by the following.

Aggregate Gradation Requirements (Cumulative % Retained¹)

					Grade				
Sieve	1	2	3S ²		3	4S ²	4	5S ²	5
Sieve				Non- Lightweight	Lightweight				
1"	-	-	-	-	-	-	-	-	-
7/8"	0–2	0	-	-	-	-	-	1	-
3/4"	20–35	0–2	0	0	0	-	1	1	-
5/8"	85–100	20–40	0–5	0–5	0–2	0	0	1	-
1/2"	-	80–100	55–85	20–40	10–25	0–5	0–5	0	0
3/8"	95–100	95–100	95–100	80–100	60–80	60–85	20–40	0–5	0–5
1/4"	1	1	1	95–100	95–100	1	ı	65–85	-
#4	-	-	-	-	-	95–100	95–100	95–100	50–80
#8	99–100	99–100	99–100	98–100	98–100	98–100	98–100	98–100	98–100

- Round test results to the nearest whole number.
- Single-size gradation.

Table 3
Aggregate Quality Requirements

Duran anta	To at Mathead	Requi	rement1		
Property	Test Method	Minimum	Maximum		
SAC	<u>AQMP</u>	As shown	on the plans		
Deleterious Material ² , %	Tex-217-F, Part I	-	2.0		
Decantation, %	<u>Tex-406-A</u>	-	1.5		
Flakiness Index, %	<u>Tex-224-F</u>	-	17		
Gradation	Tex-200-F, Part I	Table 2 R	equirements		
Los Angeles Abrasion, %	<u>Tex-410-A</u>	-	35		
Magnesium Sulfate Soundness, 5 Cycle, %	<u>Tex-411-A</u>	- 25			
Micro-Deval Abrasion, %	<u>Tex-461-A</u>	No	ote 3		
Coarse Aggregate Angularity ⁴ , 2 Crushed Faces, %	<u>Tex-460-A</u> , Part I	85	-		
Additio	onal Requirements for	Lightweight Aggregate			
Dry Loose Unit Wt., lb./cu. ft.	<u>Tex-404-A</u>	35	60		
Pressure Slaking, %	<u>Tex-431-A</u>	-	6.0		
Freeze-Thaw Loss, %	<u>Tex-432-A</u>	-	10.0		
Water Absorption, 24hr., %	<u>Tex-433-A</u>	-	12.0		

- 1. Material requirements are listed below, unless otherwise shown on the plans.
- Not required for lightweight aggregate.
- 3. Used to estimate the magnesium sulfate soundness loss in accordance with Section 2.1.1.
- Only required for crushed gravel.

Section 2.1.1., "Micro-Deval Abrasion," is added.

The Engineer will perform a minimum of one Micro-Deval abrasion test in accordance with <u>Tex-461-A</u> for each coarse aggregate source per project that has a Rated Source Soundness Magnesium (RSSM) loss value greater than 15 as listed in the BRSQC. The Engineer may waive all Micro-Deval testing based on a satisfactory test history of the same aggregate source.

The Engineer will estimate the magnesium sulfate soundness loss for each coarse aggregate source, when tested, using the following formula.

 $Mg_{est.} = (RSSM)(MD_{act.}/RSMD)$

where:

Mgest. = magnesium sulfate soundness loss MDact. = actual Micro-Deval percent loss RSMD = Rated Source Micro-Deval

When the estimated magnesium sulfate soundness loss is greater than the maximum magnesium sulfate soundness loss specified, the coarse aggregate source will not be allowed for use unless otherwise approved by the Engineer. The Engineer may require additional testing before granting approval.

Section 2.2., "Precoating." The third paragraph is voided and replaced by the following.

The Engineer retains the right to remove precoat material from aggregate samples in accordance with <u>Tex-210-F</u>, or as recommended by the Construction Division, and test the aggregate to verify compliance with Table 2 and Table 3 requirements. Gradation testing may be performed with precoat intact.

Section 2.3., "Sampling," is added.

Personnel who conduct sampling and witnessing of sampling must be certified by the Department-approved certification program. Supply the Engineer with a list of certified personnel and copies of their current certificates before beginning construction and when personnel changes are made. At any time during the project, the Engineer may perform production tests as deemed necessary in accordance with Item 5, "Control of the Work."

The Engineer will sample aggregate from stockpiles located at the production site, intermediate distribution site, or project location in accordance with <u>Tex-221-F</u>, Section 3.2.3. The Engineer will split each sample into 2 equal portions in accordance with <u>Tex-200-F</u>, Section 3.3, and label these portions "Engineer" and "Contractor" or "Supplier." Witness the sampling and splitting, and take immediate possession of the samples labeled "Contractor" or "Supplier".

Section 2.4., "Reporting and Responsibilities," is added.

The Engineer will provide test results to the Contractor and Supplier within 10 working days from the date the stockpile was sampled for sources listed on the Department's Bituminous Rated Source Quality Catalog (BRSQC), unless otherwise directed. The Engineer will provide test results for the LA Abrasion (Tex-410-A) and Magnesium Sulfate Soundness (Tex-411-A) tests within 30 calendar days for sources not listed on the BRSQC, or for sources not meeting the requirements of Section 2.1.1., "Micro-Deval Abrasion." The Engineer will report to the other party within 24 hours when any test result does not meet the requirements listed in Table 2 or Table 3.

2 06-18 Statewide

Special Provision to Item 316 Seal Coat



Item 316, "Seal Coat" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 4.8, "Asphalt Placement" is supplemented by the following:

4.8.5. Collect all samples in accordance with Tex-500-C, "Sampling Bituminous Materials, Pre-Molded Joint Fillers, and Joint Sealers" from the distributor and with witness by the Engineer.

At least once per project, collect split samples of each binder grade and source used. The Engineer will submit one split sample to MTD for testing and retain the other split sample.

In addition, collect one sample of each binder grade and source used on the project for each production day. The Engineer will retain these samples.

The Engineer will keep all retained samples for one yr., for hot-applied binders and cutback asphalts; or for two mo., for emulsified asphalts. The Engineer may submit retained samples to MTD for testing as necessary or as requested by MTD.

Special Provision to Item 340 Dense-Graded Hot-Mix (Small Quantity)



Item 340, "Dense-Graded Hot-Mix (Small Quantity)" of the Standard Specifications is replaced by Special Specification 3076, "Dense-Graded Hot-Mix Asphalt," Section 4.9.4., "Exempt Production." All Item 340 Special Provisions and bid codes are no longer available, beginning with the February 2022 letting.

Special Provision to Item 420 Concrete Substructure



Item 420, "Concrete Substructures" of the Standard Specifications is amended with respect to the clause cited below. No other clauses or requirements of this Item are waived or changed.

Article 420.6., "Payment." The first paragraph is replaced by the following:

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for the class of concrete and element identified and by the special designation when appropriate. This price is full compensation for furnishing, hauling, and mixing concrete materials; furnishing, bending, fabricating, splicing, welding and placing the required reinforcement; clips, blocks, metal spacers, ties, wire, or other materials used for fastening reinforcement in place; placing, finishing, and curing concrete; mass placement controls; applying ordinary surface finish; furnishing and placing drains, metal flashing strips, and expansion-joint material; excavation, subgrade preparation; and forms and falsework, equipment, labor, tools, and incidentals.

Special Provision to Item 421 Hydraulic Cement Concrete



Item 421, "Hydraulic Cement Concrete" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 421.2., "Materials," the second sentence of the first paragraph is voided and replaced by the following.

Provide aggregates from sources listed in the Department's Concrete Rated Source Quality Catalog (CRSQC).

Article 421.2.2., Supplementary Cementing Materials (SCM), is voided and replaced with the following.

Supplementary Cementing Materials (SCM).

- Fly Ash. Furnish fly ash, Modified fly ash (MFA), and Ground Bottom Ash (GBA) conforming to DMS-4610, "Fly Ash."
- Slag Cement. Furnish Slag Cement conforming to DMS-4620, "Slag Cement."
- Silica Fume. Furnish silica fume conforming to DMS-4630, "Silica Fume."
- Metakaolin. Furnish metakaolin conforming to DMS-4635, "Metakaolin."

Article 421.3.1.3., "Agitators and Truck and Stationary Mixers," the first paragraph is voided and replaced by the following.

Provide stationary and truck mixers capable of combining the ingredients of the concrete into a thoroughly mixed and uniform mass and capable of discharging the concrete so that the requirements of <u>Tex-472-A</u> are met.

Article 421.3.1.3., "Agitators and Truck and Stationary Mixers," is supplemented with the following.

Truck mixers with automated water and chemical admixture measurement and slump and slump flow monitoring equipment meeting the requirement of ASTM C 94 will be allowed. Provide data every 6 mo. substantiating the accuracy of slump, slump flow, temperature, water, and chemical admixture measurements. The slump measured by the automated system must be within 1 in. of the slump measured in accordance with Tex-415-A. The concrete temperature measured by the automated system must be within 1°F of concrete temperature measured in accordance with Tex-422-A. The Engineer will not use the automated measurements for acceptance.

Article 421.4.2, "Mix Design Proportioning," Table 8 is voided and replaced by the following.

Table 8
Concrete Classes

Concrete Classes										
Class of Concrete	Design Strength,¹ Min f'c (psi)	Max w/cm Ratio	Coarse Aggregate Grades ^{2,3,4}	Cement Types	Mix Design Options	Exceptions to Mix Design Options	General Usage ^s			
A	3,000	0.60	1–4, 8	I, II, I/II, IL, IP, IS, IT, V	1, 2, 4, & 7	When the cementitious material content does not exceed 520 lb./cu. yd., any fly ash listed in the MPL may be used at a cement replacement of 20% to	Curb, gutter, curb & gutter, conc. retards, sidewalks, driveways, back-up walls, anchors, non-reinforced drilled shafts			
В	2,000	0.60	2–7			50%.	Riprap, traffic signal controller foundations, small roadside signs, and anchors			
C ₆	3,600	0.45	1–6	I, II, I/II, IP, IL, IS, IT, V	1–8		Drilled shafts, bridge substructure, traffic rail, culverts except top slab of direct traffic culverts, headwalls, wing walls, inlets, manholes, traffic barrier			
E	3,000	0.50	2–5	I, II, I/II, IL, IP, IS, IT, V	1–8	When the cementitious material content does not exceed 520 lb./cu. yd., any fly ash listed in the MPL may be used at a cement replacement of 20% to 50%.	Seal concrete			
F ⁶	Note ⁷	0.45	2–5	I, II, I/II, IP, IL, IS, IT, V			Railroad structures; occasionally for bridge piers, columns, bents, post-tension members			
He	Note ⁷	0.45	3–6	I, II, I/II, III, IP, IL, IS, IT, V	1–4, 8	Mix design options 1-8 allowed for cast-in-place concrete and the following precast elements unless otherwise stated in the plans: ■ Bridge Deck Panels, ■ Retaining Wall Systems, ■ Coping, ■ Sound Walls, ■ Wall Columns, ■ Traffic Rail, ■ Traffic Barrier, ■ Long/Arch Span Culverts, and ■ precast concrete products included in Items 462, 464, and 465. Do not use Type III cement in mass placement concrete. Up to 20% of blended cement may be replaced with listed SCMs when Option 4 is used for precast concrete. Options 6, & 7 allowed for cast-in-place Class H concrete.	Precast concrete, post-tension members			
S ⁶	4,000	0.45	2–5	I, II, I/II, IP, IL, IS, IT, V	1–8	,	Bridge slabs, top slabs of direct traffic culverts, approach slabs			
Р	See Item 360, "Concrete Pavement."	0.50	2–3	I, II, I/II, IL, IP, IS, IT, V	1–8	When the cementitious material content does not exceed 520 lb./cu. yd., any fly ash listed in the MPL may be used at a cement replacement of 20% to 50%.	Concrete pavement			

Class of Concrete	Design Strength,¹ Min f'c (psi)	Max w/cm Ratio	Coarse Aggregate Grades ^{2,3,4}	Cement Types	Mix Design Options	Exceptions to Mix Design Options	General Usage⁵
CO ₆	4,600	0.40	6		4.0		Bridge deck concrete overlay
LMC ⁶	4,000	0.40	6–8		1–8		Latex-modified concrete overlay
SS ⁶	3,600	0.45	4–6	I, II, I/II, IP, IL, IS, IT, V	1-8	Use a minimum cementitious material content of 658 lb./cu. yd. of concrete. Limit the alkali loading to 4.0 lbs./cu. yd. or less when using option 7.	Slurry displacement shafts, underwater drilled shafts
K^6	Note ⁷	0.40	Note ⁷	I, II, I/II, III IP, IL, IS, IT, V	1-8		Note ⁷
HES	Note ⁷	0.45	Note ⁷	I, IL, II, I/II,		Mix design options do not apply. 700 lb. of cementitious material per cubic yard limit does not apply.	Concrete pavement, concrete pavement repair
"X" (HPC) _{6,8,9}	Note ¹⁰	0.45	Note ¹⁰	I, II, I/II, III IP, IL, IS, IT, V	1–4, & 8	Maximum fly ash replacement for Option 3 may be increased to 50%. Up to 20% of a blended cement may be replaced with listed SCMs for Option 4. Do not use Option 8 for precast concrete.	
"X" (SRC) 6.8. 9	Note ¹⁰	0.45	Note ¹⁰	I/II, II, IP, IL, IS, IT, V	1–4, & 7	When using fly ash, only use fly ashes allowed for SRC as listed in the Fly Ash MPL. Type III-MS may be used where allowed. Type I and Type III cements may be use when fly ashes allowed for SRC as listed in the Fly Ash MPL are used, and with a maximum w/cm of 0.40. Up to 20% of blended cement may be replaced with listed SCMs when Option 4 is used for precast concrete. Use Option 7 for precast concrete where allowed.	

- 1. Design strength must be attained within 56 days.
- 2. Do not use Grade 1 coarse aggregate except in massive foundations with 4 in. minimum clear spacing between reinforcing steel bars, unless otherwise permitted. Do not use Grade 1 aggregate in drilled shafts.
- 3. Use Grade 8 aggregate in extruded curbs unless otherwise approved.
- 4. Other grades of coarse aggregate maybe used in non-structural concrete classes when allowed by the Engineer.
- 5. For information only.
- 6. Structural concrete classes.
- 7. As shown on the plans or specified.
- 8. "X" denotes class of concrete shown on the plans or specified.
- 9. (HPC): High Performance Concrete, (SRC): Sulfate Resistant Concrete.
- 10. Same as class of concrete shown on the plans.

Article 421.4.2.2., "Aggregates," is supplemented by the following.

Use the following equation to determine if the aggregate combination meets the sand equivalency requirement when blending fine aggregate or using an intermediate aggregate:

$$\frac{(SE_{1} \times P_{1}) + (SE_{2} \times P_{2}) + (SE_{ia} \times P_{ia})}{100} \ge 80\%$$

where:

 SE_1 = sand equivalency (%) of fine aggregate 1

 SE_2 = sand equivalency (%) of fine aggregate 2

 SE_{ia} = sand equivalency (%) of intermediate aggregate passing the 3/8 in. sieve

 P_1 = percent by weight of fine aggregate 1 of the fine aggregate blend

 P_2 = percent by weight of fine aggregate 2 of the fine aggregate blend

 P_{ia} = percent by weight of intermediate aggregate passing the 3/8 in. sieve

Article 421.4.2.3., Chemical Admixtures," the second paragraph is voided and replaced with the following.

Use a 30% calcium nitrite solution when a corrosion-inhibiting admixture is required. Dose the admixture at the rate of gallons of admixture per cubic yard of concrete shown on the plans. Use set retarding admixtures, as needed, to control setting time to ensure concrete containing corrosion inhibiting admixtures remain workable for the entire duration of the concrete placement. Perform setting time testing and slump loss testing during trial batch testing.

Article 421.4.2.5., "Slump," the second paragraph is voided and not replaced. Table 9 is voided and replaced with below:

Table 9 Placement Slump Requirements

General Usage	Placement Slump Range, ^{1,2} in.
Walls (over 9 in. thick), caps, columns, piers	3 to 7
Bridge slabs, top slabs of direct traffic culverts, approach slabs, concrete overlays, latex- modified concrete for bridge deck overlays	3 to 6
Inlets, manholes, walls (less than 9 in. thick), bridge railing, culverts, concrete traffic barrier, concrete pavement (formed)	4 to 6
Precast concrete	4 to 9
Underwater concrete placements	6 to 8-1/2
Drilled shafts, slurry displaced and underwater drilled shafts	See Item 416, "Drilled Shaft Foundations."
Curb, gutter, curb and gutter, concrete retards, sidewalk, driveways, seal concrete, anchors, riprap, small roadside sign foundations, concrete pavement repair, concrete repair	As approved

Maximum slump values may be increase above these values shown using chemical admixtures, provided the admixture treated concrete has the same or lower water-to-cementitious ratio and does not exhibit segregation or excessive bleeding. Request approval to increase slump limits in advance for proper evaluation by the Engineer.

For fiber reinforced concrete, perform slump before addition of fibers.

Article 421.4.2.6., "Mix Design Options", is voided and replaced with the following.

Option 1. Replace cement with at least the minimum dosage listed in the Fly Ash MPL for the fly ash used in the mixture. Do not replace more than 50% of the cement with fly ash.

Option 2. Replace 35% to 50% of the cement with slag cement.

Option 3. Replace 35% to 50% of the cement with a combination of fly ash, slag cement, MFA, metakaolin, or at least 3% silica fume; however, no more than 35% may be fly ash, and no more than 10% may be silica fume.

Option 4. Use Type IP, Type IS, or Type IT cement as allowed in Table 8 for each class of concrete. Up to 10% of a Type IP, Type IS, or Type IT cement may be replaced with fly ash, slag cement, or silica fume. Use no more than 10% silica fume in the final cementitious material mixture if the Type IT cement contains silica fume, and silica fume is used to replace the cement.

Option 5. Option 5 is left intentionally blank.

Option 6. Use a lithium nitrate admixture at a minimum dosage determined by testing conducted in accordance with Tex-471-A. Before use of the mix, provide an annual certified test report signed and sealed by a licensed professional engineer, from a laboratory on the Department's MPL, certified by the Construction Division as being capable of testing according to Tex-471-A.

Option 7. Ensure the total alkali contribution from the cement in the concrete does not exceed 3.5 lb. per cubic yard of concrete when using hydraulic cement not containing SCMs calculated as follows:

lb. alkali per cu. yd. =
$$\frac{\left(\text{lb.cement per cu. yd.}\right) \times \left(\% \text{ Na}_{2} \text{O equivalent in cement}\right)}{100}$$

In the above calculation, use the maximum cement alkali content reported on the cement mill certificate.

Option 8. Use Table 10 when deviating from Options 1–3 or when required by the Fly Ash MPL. Perform required testing annually and submit results to the Engineer. Laboratories performing ASTM C1260, ASTM C1567, and ASTM C1293 testing must be listed on the Department's MPL. Before use of the mix, provide a certified test report signed and sealed by a licensed professional engineer demonstrating the proposed mixture conforms to the requirements of Table 10.

Provide a certified test report signed and sealed by a licensed professional engineer, when HPC is required, and less than 20% of the cement is replaced with SCMs, demonstrating ASTM C1202 test results indicate the permeability of the concrete is less than 1,500 coulombs tested immediately after either of the following curing schedules:

- Moisture cure specimens 56 days at 73°F.
- Moisture cure specimens 7 days at 73°F followed by 21 days at 100°F.

Table 10
Option 8 Testing and Mix Design Requirements

	ı		Totally and mix Beelgh Requirements						
Scenario	ASTM C	1260 Result	Testing Requirements for Mix Design Materials						
Scer	Mix Design Fine Aggregate	Mix Design Coarse Aggregate	or Prescriptive Mix Design Options						
A	> 0.10%	> 0.10%	Determine the dosage of SCMs needed to limit the 14-day expansion of each aggregate 1 to 0.10% when tested individually in accordance with ASTM C1567.						
В	≤ 0.10%	Use the minimum replacement listed in the Fly Ash MPL, or When Option 8 is listed on the MPL, use a minimum of 40% fly ash with a maximum CaO² content of 25%, or Use any ternary combination which replaces 35% to 50% of cement.							
	≤ 0.10%	ASTM C1293 1 yr. Expansion ≤ 0.04%	Use a minimum of 20% of any fly ash; or Use any ternary combination which replaces 20% to 50% of cement.						
С	≤ 0.10%	> 0.10%	Determine the dosage of SCMs needed to limit the 14-day expansion of coarse and intermediate ¹ aggregate to 0.10% when tested individually in accordance with ASTM C1567.						
D	> 0.10%	≤ 0.10%	Use the minimum replacement listed in the Fly Ash MPL, or When Option 8 is listed on the MPL, use a minimum of 40% fly ash with a maximum CaO² content of 25%, or Use any ternary combination which replaces 35% to 50% of cement.						
	> 0.10%	ASTM C1293 1 yr. Expansion ≤ 0.04%	Determine the dosage of SCMs needed to limit the 14-day expansion o each fine aggregate to 0.10% when individually tested in accordance with ASTM C1567.						

- 1. Intermediate size aggregates will fall under the requirements of mix design coarse aggregate.
- 2. Average the CaO content from the previous ten values as listed on the test certificate.

Article 421.4.2.7., "Optimized Aggregate Gradation (OAG) Concrete," the first sentence of the first paragraph is voided and replaced by the following.

5 - 6 03-22 Statewide The gradations requirements in Table 4 and Table 6 do not apply when OAG concrete is specified or used by the Contractor unless otherwise shown on the plans.

The fineness modulus for fine aggregate listed in Table 5, does not apply when OAG Concrete is used,

Article 421.4.6.2., Delivering Concrete," the third paragraph is supplemented by the following.

When truck mixers are equipped with automated water or chemical admixture measurement and slump or slump flow monitoring equipment, the addition of water or chemical admixtures during transit is allowed. Reports generated by this equipment must be submitted to the Engineer daily.

Article 421.4.6.2., "Delivering Concrete," the fifth paragraph is voided and replaced with the following. Begin the discharge of concrete delivered in truck mixers within the times listed in Table 14. Concrete delivered after these times, and concrete that has not begun to discharge within these times will be rejected

Article 421.4.8.3., "Testing of Fresh Concrete," is voided and replaced with the following.

Testing Concrete. The Engineer, unless specified in other Items or shown on the plans, will test the fresh and hardened concrete in accordance with the following methods:

- Slump. Tex-415-A;
- Air Content. Tex-414-A or Tex-416-A;
- Temperature. Tex-422-A;
- Making and Curing Strength Specimens. Tex-447-A;
- Compressive Strength. Tex-418-A;
- Flexural Strength. Tex-448-A; and
- Maturity. Tex-426-A.

Flexural strength and maturity specimens will not be made unless specified in other items or shown on the plans.

Concrete with slump less than minimum required after all addition of water withheld will be rejected, unless otherwise allowed by the Engineer. Concrete with slump exceeding maximum allowed may be used at the contractor's option. If used, Engineer will make, test, and evaluate strength specimens as specified in Article 421.5., "Acceptance of Concrete." Acceptance of concrete not meeting air content or temperature requirements will be determined by Engineer. Fresh concrete exhibiting segregation and excessive bleeding will be rejected.

Article 421.4.8.3.1. "Job-Control Testing," is voided and not replaced.

Special Provision to Item 440 Reinforcement for Concrete



Item 440, "Standard Specification Title" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 440.2., "Materials" is supplemented with the following:

- 2.14. Provide zinc-coated, hot-dip galvanized Class I or II steel reinforcement conforming to ASTM A767, Grades 60 or 75 when shown on the plans and as allowed.
- 2.15. Provide continuously hot-dip galvanized reinforcement (CGR) conforming to ASTM A1094 steel reinforcement, Grades 60 or 75 when shown on the plans and as allowed.

Article 440.2.5., "Weldable Reinforcing Steel" is supplemented with the following:

All welding operations must be performed prior to hot-dip galvanizing.

Article 440.2.8., "Mechanical Couplers" is supplemented with the following:

Provide hot-dipped or mechanically galvanized couplers when splicing galvanized reinforcing or continuously galvanized reinforcing.

Article 440.2.11., "Low-Carbon, Chromium Reinforcing Steel." The first sentence is voided and replaced by the following:

Provide deformed steel bars conforming to ASTM A1035, Grade 100, Type CS when low-carbon, chromium reinforcing steel is required on the plans. Type CM will only be permitted if specified on the plans.

Article 440.3.1., "Bending" is supplemented with the following:

Do not bend hot-dip galvanized reinforcement. Only minor positioning adjustments are permitted.

Bending of continuously galvanized reinforcement is permitted after galvanizing.

Article 440.3.5, "Placing" the following will be added to paragraph four.

Use Class 1 or 1A supports with continuously galvanized reinforcing. Provide epoxy or plastic-coated tie wires and clips for use with epoxy coated reinforcing steel.

Article 440.3.6.3., "Repairing Coating" is supplemented with the following:

Repair damaged galvanized surfaces in accordance with Article 445.3.5.2. "Repair Processes."

Special Provision to Item 441 Steel Structures



Item 441, "Steel Structures" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 441.2.2.. Approved Electrodes and Flux-Electrode Combinations," is voided and replaced with the following:

Use only electrodes and flux-electrode combinations conforming to AWS A5 specifications, and pertinent classifications for the applicable welding processes. When requested, submit a current Certificate of Conformance (COC) containing all test results as required by the applicable AWS A5 specification and welding code. Provide proof of Buy America compliance for welding consumables when requested. For bridge main member fabrication, submit the COC annually.

Section 441.2.3., "High-Strength Bolts," is revised and replaced by the following:

Use fasteners that meet Item 447, "Structural Bolting." Use galvanized fasteners on field connections of bridge members when ASTM F3125-Grade A325 bolts are specified, and steel is painted.

Section 441.3.1.51., "Plants," The second and third paragraphs are voided and replaced with the following:

Fabrication plants that produce the following non-bridge steel members must be approved in accordance with DMS-7380, "Steel Non-Bridge Member Fabrication Plant Qualification."

- Item 610, "Roadway Illumination Poles"
- Item 613, "High Mast Illumination Poles"
- Item 614, "High Mast Rings and Support Assemblies"
- Item 650, "Overhead Sign Support Structures"
- Item 654, "Sign Walkways"
- Item 686, "Traffic Signal Poles"
- Special Specification 6064, "Intelligent Transportation System (ITS) Poles."

The Materials and Tests Division (MTD) maintains a list of approved non-bridge fabrication plants on the Department MPL that produce these members.

Section 441.3.1.6.1., "Erection Drawings," the third paragraph is voided and replaced with the following:

Perform erection engineering evaluation of the structural adequacy and stability of constructing the bridge system for each step of the steel erection.

Section 441.3.1.5.3., "Nondestructive Testing (NDT)," is voided and replaced with the following:

Personnel performing NDT must be qualified in accordance with the applicable AWS code and the employer's Written Practice. Level III personnel who qualifies Level I and Level II technicians must be certified by ASNT for which the NDT Level III is qualified. In addition, NDT technicians must pass hands-on tests that MTD administers. This will remain current provided they continue to perform testing on Department materials as evidenced by test reports requiring their signature. A technician who fails any of the hands-on tests must wait 3 mo. or as approved otherwise before retesting. Qualification to perform NDT will be revoked when the technician's employment is terminated or when the technician goes 6 mo. without performing a test on a Department project. The technician must pass a new hands-on test to be re-certified. Testing of similar weld joints for non-Department projects may be considered by the Engineer instead of re-testing provided enough documentation is submitted with the signature of the project's Engineer. These requirements also apply to testing agencies, and individual third-party contractors.

1 - 2 01-22 Statewide Section 441.3.1.5.4., "Welding Procedure Specification Qualification Testing," is voided and replaced by the following:

For Fabricators qualified in accordance with DMS-7370, DMS-7380, or DMS-7395, laboratories performing procedure qualification testing for welding procedure specifications (WPSs) must be accredited by a nationally recognized agency that performs testing in accordance with ISO/International Electrotechnical Commission (IEC) 17025 in the mechanical field of testing.

Section 441.3.1.9., "Material Identification," is amended to include the following paragraph:

Low-stress stencil marks must have a radius instead of a sharp point. Acceptable stencils include dot, vibration, and rounded-V stencils. Label these stencils so that they are easily distinguishable from other stencils that are not lowstress.

Section 441.3.2.4.1., "Flange Tilt," the last sentence is voided and replaced with the following:

Minor jacking that does not deform the material will be permitted.

Section 441.3.2.5.3., "Magnetic Particle Testing," is voided and replaced with the following:

Use alternating current (AC) when using the yoke method unless otherwise approved. Welds may be further evaluated with halfwave rectified DC for subsurface indications. Centerline cracking may be detected with aluminum prod method when approved.

Section 441.3.5.8., "Hammering," is added to state the following:

Do not perform hammering on any portion of the member that causes the material to permanently deform. Avoid damage to the material by measures such as use of brass or aluminum hammers or by padding the area to be hammered.

Section 441.3.8.1., "Shop Painting," is amended to include with the following paragraph:

Measure the anchor profile after blast cleaning at random locations along the thermal cut surfaces. If specified anchor profile is not achieved over the entire flame cut surface, grind the edges and re-blast to achieve the required anchor pattern.

Section 441.3.9., "Handling and Storage of Materials," The second sentence of the second paragraph is replaced by the following:

Keep materials clean and avoid damaging of the applied coating.

Special Provision to Item 442 Metal for Structures



Item 442, "Metal for Structures" of the Standard Specifications is amended with respect to the clause cited below. No other clauses or requirements of this Item are waived or changed.

Section 442.2.1.3.3., "Fasteners." The first sentence of the first paragraph is replaced by the following:

Fasteners. Provide high-strength bolts that meet ASTM F3125-Grade A325 unless otherwise shown on the plans.

Section 442.2.1.3.3., "Fasteners." The third paragraph is deleted and not replaced.

Special Provision to Item 464 Reinforced Concrete Pipe



Item 464, "Reinforced Concrete Pipe," of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Section 2.1., "Fabrication." The section is voided and replaced with the following.

Fabrication plants must be approved by the Materials and Tests Division in accordance with DMS-7305, "Fabrication and Qualification Procedure for Multi-Project Fabrication Plants of Precast Concrete Drainage Structures," before furnishing precast reinforced concrete pipe for Departmental projects. The Department's MPL has a list of approved reinforced concrete pipe plants.

Furnish material and fabricate reinforced concrete pipe in accordance with DMS-7305, "Fabrication and Qualification Procedure for Multi-Project Fabrication Plants of Precast Concrete Drainage Structures."

Section 2.3., "Marking." The first paragraph is voided and replaced with the following.

Furnish each section of reinforced concrete pipe marked with the following information specified in DMS-7305, "Fabrication and Qualification Procedure for Multi-Project Fabrication Plants of Precast Concrete Drainage Structures."

- Class or D-Load of pipe,
- ASTM designation,
- Date of manufacture,
- Pipe size.
- Name or trademark of fabricator and plant location,
- Designation "TX" for precast units fabricated per DMS-7305;
- Designated fabricator's approval stamp for each approved unit,
- Pipe to be used for jacking and boring (when applicable), and
- Designation "SR" for pipe meeting sulfate-resistant concrete plan requirements (when applicable).

Section 2.5., "Causes for Rejection." The section is voided and replaced with the following.

Individual sections of pipe may be rejected for any of the conditions stated in the Annex of DMS-7305, "Fabrication and Qualification Procedure for Multi-Project Fabrication Plants of Precast Concrete Drainage Structures."

Section 2.6., "Repairs." The section is voided and replaced with the following:

Make repairs, if necessary, as stated in the Annex of DMS-7305, "Fabrication and Qualification Procedure for Multi-Project Fabrication Plants of Precast Concrete Drainage Structures."

Special Provision to Item 502 Barricades, Signs and Traffic Handling



Item 502, "Barricades, Signs and Traffic Handling" of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 502.1., "Description," is supplemented by the following:

Temporary work-zone (TWZ) traffic control devices manufactured after December 31, 2019, must have been successfully tested to the crashworthiness requirements of the 2016 edition of the Manual for Assessing Safety Hardware (MASH). Such devices manufactured on or before this date and successfully tested to NCHRP Report 350 or the 2009 edition of MASH may continue to be used throughout their normal service lives. An exception to the manufacture date applies when, based on the project's date of letting, a category of MASH-2016 compliant TWZ traffic control devices are not approved, or are not self-certified after the December 31, 2019, date. In such case, devices that meet NCHRP-350 or MASH-2009 may be used regardless of the manufacture date.

Such TWZ traffic control devices include: portable sign supports, barricades, portable traffic barriers designated exclusively for use in temporary work zones, crash cushions designated exclusively for use in temporary work zones, longitudinal channelizers, truck and trailer mounted attenuators. Category I Devices (i.e., lightweight devices) such as cones, tubular markers and drums without lights or signs attached however, may be self-certified by the vendor or provider, with documentation provided to Department or as are shown on Department's Compliant Work Zone Traffic Control Device List.

Article 502.4., "Payment," is supplemented by the following:

Truck mounted attenuators and trailer attenuators will be paid for under Special Specification, "Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)." Portable Changeable Message Signs will be paid for under Special Specification, "Portable Changeable Message Sign." Portable Traffic Signals will be paid for under Special Specification, "Portable Traffic Signals."

Special Provision to Item 506



Temporary Erosion, Sedimentation, and Environmental Controls

Item 506, "Temporary Erosion, Sedimentation, and Environmental Controls," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 506.1., "Description." The second paragraph is voided and replaced by the following.

Contractor is considered primary operator to have day-to-day operational control as defined in TPDES GP TXR150000.

- 1.1. For projects with soil disturbance of less than 1 acre, no submittal to TCEQ will be required but Contractor will follow SWP3. For projects with soil disturbance of 1 acre to less than 5 acres a small site notice will be posted at the site. For projects with soil disturbance of 5 acres or more a Notice of Intent (NOI) is required and a large site notice posted at site. Postings will be in accordance with TPDES GP TXR150000. Postings not associated with project specific locations will be in same location as Department's postings.
- 1.2. Notice of Intent (NOI). Submit a NOI, if applicable, with the TCEQ under the TPDES GP TXR150000 at least 7 days prior to commencement of construction activities at the project site. Provide a signed copy to the Engineer and any other MS4 operators at the time of submittal. The Department will submit their NOI prior to contractor submission and will provide a copy for Contractor's use in completing the Contractor's NOI form.
- **1.3. Notice of Change (NOC).** Upon concurrence of the Engineer, submit a NOC, if applicable, to the TCEQ within 14 days of discovery of a change or revision to the NOI as required by the TPDES GP TXR150000. Provide a signed copy of the NOC to the Engineer and any other MS4 operators at the time of submittal.
- **1.4. Notice of Termination (NOT).** Upon concurrence of the Engineer, submit a NOT, if applicable, to the TCEQ within 30 days of the Engineer's approval that 70% native background vegetative cover is met or equivalent permanent stabilization have been employed in accordance with the TPDES GP TXR 150000. Provide a signed copy of the NOT to the Engineer and any other MS4 operators at the time of submittal.

Section 506.3.1, "Contractor Responsible Person Environmental (CRPE) Qualifications and Responsibilities," is supplemented by the following:

3.1. Contractor Responsible Person Environmental (CRPE) Qualifications and Responsibilities. Provide and designate in writing at the preconstruction conference a CRPE and alternate CRPE who have overall responsibility for the storm water management program. The CRPE will implement stormwater and erosion control practices; will oversee and observe stormwater control measure monitoring and management; will monitor the project site daily and produce daily monitoring reports as long as there are BMPs in place or soil disturbing activities are evident to ensure compliance with the SWP3 and TPDES General Permit TXR150000. Daily monitor reports shall be maintained and made available upon request. During time suspensions when work is not occurring or on contract non-work days, daily inspections are not required unless a rain event has occurred. The CRPE will provide recommendations on how to improve the effectiveness of control measures. Attend the Department's preconstruction conference for the project. Ensure training is completed as identified in Section 506.3.3., "Training," by all applicable personnel before employees work on the project. Document and maintain and make available upon request, a list, signed by the CRPE, of all applicable Contractor and subcontractor employees who have completed the training. Include the employee's name, the training course name, and date the employee completed the training.

Section 506.3.3., "Training," is supplemented by the following:

Training is provided by the Department at no cost to the Contractor and is valid for 3 yr. from the date of completion. The Engineer may require the following training at a frequency less than 3 yr. based on environmental needs:

- "Environmental Management System: Awareness Training for the Contractor" (English and Spanish) (Approximate running time 20 min.), and
- "Storm Water: Environmental Requirements During Construction" (English and Spanish) (Approximate running time 20 min.).

The Contractor responsible person environmental (CRPE), alternate CRPE designated for emergencies, Contractor's superintendent, Contractor, and subcontractor lead personnel involved in soil disturbing or SWP3 activities must enroll in and complete the training listed below and maintain and make available upon request the certificate of completion. Training is provided by a third party and is valid for 3 yr. from the date shown on the Certificate of Completion. Coordinate enrollment as prescribed by the Department and pay associated fees for the following training:

- "Revegetation During Construction,"
- "Construction General Permit Compliance," and
- "Construction Stage Gate Checklist (CSGC)."

Training and associated fee will not be measured or paid for directly but are subsidiary to this Item.

Special Provision to Item 520 Weighing and Measuring Equipment



Item 520, "Weighing and Measuring Equipment" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 520.2., "Equipment." The third paragraph is voided and replaced by the following.

Calibrate truck scales using weights certified by the Texas Department of Agriculture (TDA) or an equivalent agency as approved. Provide a written calibration report from a scale mechanic for truck scale calibrations. Cease plant operations during the checking operation. Do not use inaccurate or inadequate scales. Bring performance errors as close to zero as practicable when adjusting equipment.

Article 520.2., "Equipment." The fourth paragraph is amended to include the following:

At the Contractors option, an electronic ticket delivery system (e-ticketing) may be used instead of printed tickets. The use of eticketing will require written approval of the Engineer. At a minimum, the approved system will:

- Provide electronic, real-time e-tickets meeting the requirements of the applicable bid items;
- Automatically generate e-tickets using software and hardware fully integrated with the automated scale system used to weigh the material, and be designed in such a way that data input cannot be altered by the Contractor or the Engineer;
- Provide the Engineer access to the e-ticketing data in real-time with a web-based or app-based system compatible with iOS;
- Provide offline capabilities to prevent data loss if power or connectivity is lost;
- Require both the Contractor and the Engineer to accept or reject the e-ticket and provide the ability to record the information required by the applicable bid items, as well as any comments. Record the time of the approval/rejection and include it in the summary spreadsheet described below. Provide each party the capability to edit their respective actions and any entered information;

The Contractor may discontinue use of the e-ticket system and provide printed tickets as needed to meet the requirements of the applicable bid items.

Special Provision to Item 636 Signs



Item 636, "Signs" of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Section 636.3.1, "Fabrication." is deleted.

Section 636.3.1.2, "Sheeting Application." The last sentence of the fourth paragraph is voided and replaced by the following.

Do not splice sheeting or overlay films for signs fabricated with ink or with colored transparent films.

Special Provision to Item 643 Sign Identification Decals



Item 643, "Sign Identification Decals," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 2. "Materials." The sign identification decal design shown in Figure 1 and the description for each row in Table 1 are supplemented by the following.

	Texas Department of Transportation												
С				Fal	oricat	ion D	ate				T	1	
J	F	М	Α	М	J	J	Α	S	0	N	D	2	
	20		20)2	20	03	20)4	20)5		3	
	0	1	2	3	4	5	6	7	8	9		4	
Sheeting MFR - Substrate													
Α	В	С	D	Ε	F	G	Н	J	K	L	М	5	
					Film	MFR							
Α	В	С	D	Ε	F	G	Н	J	K	L	М	6	
			S	heeti	ng MI	FR - L	egen	d					
Α	В	С	D	Е	F	G	Н	J	K	L	М	7	
			1	Ins	tallat	ion D	ate						
				0	1	2	3					8	
	0	1	2	3	4	5	6	7	8	9		9	
J	F	М	Α	М	J	J	Α	S	0	N	D	10	
	20)1	20)2	20	03	204		205			11	
	0	1	2	3	4	5	6	7	8	9		12	
	Name of Sign Fabricator Physical Address City, State, Zip Code											13	

Figure 1
Decal Design (Row numbers explained in Table 1)

Table 1 Decal Description

Row Explanation							
1 – Sign fabricator							
2 – Month fabricated							
3 – First 3 digits of year fabricated							
4 – Last digit of year fabricated							
5 – Manufacturer of the sheeting applied to the substrate							
6 – Film (colored transparent or non-reflective black) manufacturer							
7 – Manufacturer of the sheeting for the legend							
8 – Tens digit of date installed							
9 - Ones digit of date installed							
10 – Month installed							
11 – First 3 digits of year installed							
12 – Last digit of year installed							
13 – Name of sign fabricator and physical location of sign shop							

Special Provision to Item 656 Foundations for Traffic Control Devices



Item 656, "Foundations for Traffic Control Devices" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 3. "Construction.," the first paragraph is supplemented by the following:

Ensure the top of the foundation and anchor bolts meet specified requirements in relation to the final grade.

Special Provision to Item 666 **Retroreflectorized Pavement Markings**



Item 666, "Retroreflectorized Pavement Markings," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 2.3., "Glass Traffic Beads." The first paragraph is voided and replaced by the following:

Furnish drop-on glass beads in accordance with DMS-8290, "Glass Traffic Beads," or as approved. Furnish a double-drop of Type II and Type III drop-on glass beads for longitudinal pavement markings where each type bead is applied separately in equal portions (by weight), unless otherwise approved. Apply the Type III beads before applying the Type II beads. Furnish Type II beads for work zone pavement markings and transverse markings or symbols.

Section 4.3.1., "Type I Markings.," is supplemented by the following:

4.3.1.3. Spot Striping. Perform spot striping on a callout basis with a minimum callout quantity as shown on the plans.

Section 4.3.2., "Type II Markings.," is supplemented by the following:

4.3.2.1. Spot Striping. Perform spot striping on a callout basis with a minimum callout quantity as shown on the plans.

Section 4.4., "Retroreflectivity Requirements.," is voided and replaced by the following.

Type I markings for Contracts totaling more than 20,000 ft. of pavement markings must meet the following minimum retroreflectivity values for all longitudinal edgeline, centerline or no passing barrier-line, and lane line markings when measured any time after 3 days, but not later than 10 days after application.

- White markings: 250 millicandelas per square meter per lux (mcd/m²/lx)
- Yellow markings: 175 mcd/m²/lx

Retroreflectivity requirements for Type I markings are not required for Contracts with less than 20,000 ft. of pavement markings or Contracts with callout work, unless otherwise shown on the plans.

Section 4.5., "Retroreflectivity Measurements.," is voided and replaced by the following:

Use a mobile retroreflectometer to measure retroreflectivity for Contracts totaling more than 50,000 ft. of pavement markings, unless otherwise shown on the plans. For Contracts with less than 50,000 ft. of pavement markings, mobile or portable retroreflectometers may be used at the Contractor's discretion. Coordinate with and obtain authorization from the Engineer before starting any retroreflectivity data collection.

Section 4.5.1., "Mobile Retroreflectometer Measurements." The last paragraph is voided and replaced by the following.

Restripe again at the Contractor's expense with a minimum of 0.060 in. (60 mils) of Type I marking material if the average of these measurements falls below the minimum retroreflectivity requirements. Take measurements every 0.1 miles a minimum of 10 days after this third application within that mile segment for that series of markings. If the markings do not meet minimum retroreflectivity after this third application, the Engineer may require removal of all existing markings, a new application as initially specified, and a repeat of the application process until minimum retroreflectivity requirements are met.

Section 4.5.2., "Portable Retroreflectometer Measurements." The first and second paragraphs are voided and replaced by the following.

Provide portable measurement averages for every 1.0 mile unless otherwise specified or approved. Take a minimum of 20 measurements for each 1-mi. section of roadway for each series of markings (e.g., edgeline, center skip line, each line of a double line) and direction of traffic flow when using a portable reflectometer. Measure each line in both directions for centerlines on two-way roadways (i.e., measure both double solid lines in both directions and measure all center skip lines in both directions). The spacing between each measurement must be at least 100 ft. The Engineer may decrease the mileage frequency for measurements if the previous measurements provide satisfactory results. The Engineer may require the original number of measurements if concerns arise.

Restripe at the Contractor's expense with a minimum of 0.060 in. (60 mils) of Type I marking material if the averages of these measurements fail. Take a minimum of 10 more measurements after 10 days of this second application within that mile segment for that series of markings. Restripe again at the Contractor's expense with a minimum of 0.060 in. (60 mils) of Type I marking material if the average of these measurements falls below the minimum retroreflectivity requirements. If the markings do not meet minimum retroreflectivity after this third application, the Engineer may require removal of all existing markings, a new application as initially specified, and a repeat of the application process until minimum retroreflectivity requirements are met.

Section 4.6. "Performance Period." The first sentence is voided and replaced by the following:

All longitudinal markings must meet the minimum retroreflectivity requirements within the time frame specified. All markings must meet all other performance requirements of this specification for at least 30 calendar days after installation.

Article 6. "Payment." The first two paragraphs are voided and replaced by the following.

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Pavement Sealer" of the size specified; "Retroreflectorized Pavement Markings" of the type and color specified and the shape, width, size, and thickness (Type I markings only) specified, as applicable: "Retroreflectorized Pavement Markings with Retroreflective Requirements" of the types, colors, sizes, widths, and thicknesses specified; "Retroreflectorized Profile Pavement Markings" of the various types, colors, shapes, sizes, and widths specified; or "Reflectorized Pavement Marking (Call Out)" of the shape, width, size, and thickness (Type I markings only) specified, as applicable; or "Pavement Sealer (Call Out)" of the size specified.

This price is full compensation for materials, application of pavement markings, equipment, labor, tools, and incidentals.

Special Specification 3096 Asphalts, Oils, and Emulsions



1. DESCRIPTION

Provide asphalt cements, cutback and emulsified asphalts, performance-graded asphalt binders, and other miscellaneous asphalt materials as specified on the plans.

2. MATERIALS

Provide asphalt materials that meet the stated requirements when tested in conformance with the referenced Department, AASHTO, and ASTM test methods. Use asphalt containing recycled materials only if the recycled components meet the requirements of Article 6.9., "Recycled Materials." Provide asphalt materials that the Department has preapproved for use in accordance with Tex-545-C, "Asphalt Binder Quality Program."

Inform the Department of all additives or modifiers included in the asphalt binder as part of the facility quality plan, as required by Tex-545-C, "Asphalt Binder Quality Program," and provide that information to Department personnel. The Department reserves the right to prohibit the use of any asphalt additive or modifier.

Limit the use of polyphosphoric acid to no more than 0.5% by weight of the asphalt binder.

The use of re-refined engine oil bottoms is prohibited.

Acronyms used in this Item are defined in Table 1.

Table1 Acronyms

Acronym	Acronyms Definition
Autonym	Test Procedure Designations
Tex	Department Designations
TorR	AASHTO
D	ASTM
5	Polymer Modifier Designations
P	polymer-modified
SBR or L	styrene-butadiene rubber (latex)
SBS	styrene-butadiene-styrene block co-polymer
TR	tire rubber (from ambient temperature grinding of truck and
	passenger tires)
AC	asphalt cement
AE	asphalt emulsion
AE-P	asphalt emulsion prime
A-R	asphalt-rubber
С	cationic
EAP&T	emulsified asphalt prime and tack
EBL	emulsified bonding layer
FDR	full depth reclamation
H-suffix	harder residue (lower penetration)
HF	high float
HY	high yield
MC	medium-curing
MS	medium-setting
PCE	prime, cure, and erosion control
PG	performance grade
RC	rapid-curing
RS	rapid-setting
S-suffix	stockpile usage
SCM	special cutback material
SS	slow-setting
SY	standard yield
TRAIL	tracking resistant asphalt interlayer

2.1. **Asphalt Cement**. Provide asphalt cement that is homogeneous, water-free, and nonfoaming when heated to 347°F, and meets the requirements in Table 2.

Table 2
Asphalt Cement

			priait	Celliel	ιι.						
	T4	Viscosity Grade									
Property	Test	AC-	AC-0.6		-1.5	AC	2-3	AC	C-5	AC	-10
	Procedure	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity	T 202										
140°F, poise		40	80	100	200	250	350	400	600	800	1,200
275°F, poise		0.4	-	0.7	-	1.1	-	1.4	-	1.9	-
Penetration, 77°F, 100g,	T 49	350		250		210		135		85	
5 sec.	1 43	330	_	230	_	210	-	155	-	00	_
Flash point, C.O.C., °F	T 48	425	-	425	-	425	-	425	_	450	-
Solubility in	T 44	99.0	_	99.0	_	99.0	_	99.0	_	99.0	_
trichloroethylene, %	1 77	33.0		33.0		33.0		33.0		33.0	
Spot test	<u>Tex-509-C</u>	Ne	eg.	Ne	eg.	Ne	eg.	Ne	eg.	Ne	eg.
Tests on residue from											
RTFOT:	T 240										
Viscosity, 140°F, poise	T 202	-	180	-	450	_	900	_	1,500	-	3,000
Ductility, ¹ 77°F	T 51	100	_	100	_	100	_	100	_	100	_
5 cm/min., cm	1 31	100	_	100	_	100	_	100	_	100	_

1. If AC-0.6 or AC-1.5 ductility at 77°F is less than 100 cm, material is acceptable if ductility at 60°F is more than 100 cm.

2.2. **Polymer-Modified Asphalt Cement**. Provide polymer-modified asphalt cement that is smooth, homogeneous, and meets the requirements Table 3. Supply samples of the base asphalt cement and polymer additives if requested.

Table 3
Polymer-Modified Asphalt Cement

Property	Test			Olymor-III	loaifiea A			Viscosity	Grade				
	Procedure	AC-12	-5TR	NT-	HA ¹	AC-		AC-2		AC-10	-2TR	AC-20	-5TR
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Polymer		TF	7		_	SE	3S	SB	S	TF	₹	TF	₹
Polymer content, % (solids basis)	<u>Tex-533-C</u> or <u>Tex-553-C</u>	5.0	-	-	_	3.0	-	-	-	2.0	-	5.0	1
Dynamic shear, G*/sinδ, 82°C, 10 rad/s, kPa	T 315			1.0	-								
Dynamic shear, G*/sinδ, 64°C, 10 rad/s, kPa	T 315	-	-	-	-	1	-	1.0	-	-	-	1.0	-
Dynamic shear, G*/sinδ, 58°C, 10 rad/s, kPa	T 315	1.0	-	-	-	-	-	-	-	1.0	-	-	-
Viscosity 140°F, poise 275°F, poise	T 202 T 202	1,200	-	ı	4,000	1,500 –	_ 8.0	2,000 –	1 1	1,000 –	- 8.0	2,000	- 10.0
Penetration, 77°F, 100 g, 5 sec.	T 49	110	150	-	25	100	150	75	115	95	130	75	115
Ductility, 5cm/min., 39.2°F, cm	T 51					-	-	-	-	_	-	_	1
Elastic recovery, 50°F, %	<u>Tex-539-C</u>	55	-			55	_	55	-	30	-	55	1
Softening point, °F	T 53	113	_	170	_	_	_	120	_	110	_	120	-
Polymer separation, 5 hr.	<u>Tex-540-C</u>	No	ne			No	one	Nor	ne	Nor	ne	Nor	ne
Flash point, C.O.C., °F	T 48	425	-	425	_	425	-	425	1	425	1	425	1
Tests on residue from RTFOT aging and pressure aging:	T 240 and R 28												
Creep stiffness S, -18°C, MPa m-value, -18°C	T 313	- 0.300	300 -	- -	- -	- 0.300	300 -	- 0.300	300 -	- 0.300	300 -	- 0.300	300 -

^{1.} Non-Tracking Hot Applied Tack Coat - TRAIL product

2.3. **Cutback Asphalt**. Provide cutback asphalt that meets the requirements of Tables 4, 5, and 6, for the specified type and grade. Supply samples of the base asphalt cement and polymer additives if requested.

Table 4
Rapid-Curing Cutback Asphalt

Property	Test Procedure	Type–Grade						
		RC	-250	RC-800		RC-	3000	
		Min	Max	Min	Max	Min	Max	
Kinematic viscosity, 140°F, cSt	T 201	250	400	800	1,600	3,000	6,000	
Water, %	D95	_	0.2	_	0.2	_	0.2	
Flash point, T.O.C., °F	T 79	80	1	80	_	80	_	
Distillation test:	T 78							
Distillate, percentage by volume of total								
distillate to 680°F								
to 437°F		40	75	35	70	20	55	
to 500°F		65	90	55	85	45	75	
to 600°F		85	-	80	_	70	-	
Residue from distillation, volume %		70	-	75	-	82	-	
Tests on distillation residue:								
Viscosity, 140°F, poise	T 202	600	2,400	600	2,400	600	2,400	
Ductility, 5 cm/min., 77°F, cm	T 51	100	_	100	_	100	_	
Solubility in trichloroethylene, %	T 44	99.0	-	99.0	_	99.0	-	
Spot test	<u>Tex-509-C</u>	N	Neg. Neg.			Ne	eg.	

Table 5 Medium-Curing Cutback Asphalt

Property	Test		-curing c			e-Grade			
, ,	Procedure	MC	C-30	MC-	-250	MC-	800	MC-	3000
		Min	Max	Min	Max	Min	Max	Min	Max
Kinematic viscosity, 140°F, cSt	T 201	30	60	250	500	800	1,600	3,000	6,000
Water, %	D95	_	0.2	_	0.2	_	0.2	-	0.2
Flash point, T.O.C., °F	T 79	95	_	122	-	140	_	149	-
Distillation test: Distillate, percentage by volume of total distillate to 680°F to 437°F to 500°F to 600°F Residue from distillation, volume %	Т 78	- 30 75 50	35 75 95 –	- 5 60 67	20 55 90 –	- - 45 75	– 40 85 –	- - 15 80	- 15 75 -
Tests on distillation residue: Viscosity, 140°F, poise Ductility, 5 cm/min., 77°F, cm Solubility in	T 202 T 51 T 44	300 100 99.0	1,200 - -	300 100 99.0	1,200 - -	300 100 99.0	1,200 - -	300 100 99.0	1,200 - -
trichloroethylene, % Spot test	<u>Tex-509-C</u>	l Neg.		Ne	l Neg.		I g.	Neg.	

Table 6 Special-Use Cutback Asphalt

Property	Test	Type-Grade					
	Procedure	MC-2	2400L	SC	CM I	SC	CM II
		Min	Max	Min	Max	Min	Max
Kinematic viscosity, 140°F, cSt	T 201	2,400	4,800	500	1,000	1,000	2,000
Water, %	D95	_	0.2	-	0.2	_	0.2
Flash point, T.O.C., °F	T 79	150	_	175	_	175	_
Distillation test:	T 78						
Distillate, percentage by volume of							
total distillate to 680°F							
to 437°F		_	_	_	_	_	_
to 500°F		_	35	_	0.5	_	0.5
to 600°F		35	80	20	60	15	50
Residue from distillation, volume %		78	_	76	_	82	_
Tests on distillation residue:							
Polymer		SE	3R		_		_
Polymer content, % (solids basis)	Tex-533-C	2.0	_	_	_	_	_
Penetration, 100 g, 5 sec., 77°F	T 49	150	300	180	_	180	_
Ductility, 5 cm/min., 39.2°F, cm	T 51	50	_	_	_	_	_
Solubility in trichloroethylene, %	T 44	99.0	_	99.0	_	99.0	_

2.4. **Emulsified Asphalt**. Provide emulsified asphalt that is homogeneous, does not separate after thorough mixing, and meets the requirements for the specified type and grade in Tables 7, 8, 9, 10, and 10A-C.

Table 7 Emulsified Asphalt

Property	Test			inea Asp		Type-G	rade				
, ,	Procedure	Rapid-S	Setting		Mediun	n-Setting			Slow-S	Setting	
		HFR	S-2	MS	S-2	AES-300		SS-1		SS-1H	
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72										
77°F, sec.		-	_	_	-	75	400	20	100	20	100
122°F, sec.		150	400	100	300	-	_	-	-	-	_
Sieve test, %	T 59	-	0.1	_	0.1	-	0.1	-	0.1	_	0.1
Miscibility	T 59	_			-	_		Pa	ass	Pa	ass
Cement mixing, %	T 59	-	-	-	-	-	-	-	2.0	-	2.0
Coating ability and water	T 59										
resistance:											
Dry aggregate/after spray		_		-	-	Good/		-	-	-	-
Wet aggregate/after spray		_			_	Fair/	Fair	-	-	-	-
Demulsibility, 35 mL of 0.02	T 59	50	-	-	30	-	-	-	-	_	_
N CaCl ₂ , %											
Storage stability, 1 day, %	T 59	_	1	_	1	-	1	1	1	_	1
Freezing test, 3 cycles ¹	T 59	_		Pa	ISS	-		Pa	ass	Pa	ass
Distillation test:	T 59										
Residue by distillation, %		65	_	65	-	65	_	60	_	60	-
by wt.											
Oil distillate, % by volume		-	0.5	_	0.5	-	5	-	0.5	_	0.5
of emulsion											
Tests on residue from											
distillation:											
Penetration, 77°F, 100 g,	T 49	100	140	120	160	300	_	120	160	70	100
5 sec.											
Solubility in	T 44	97.5	-	97.5	-	97.5	-	97.5	-	97.5	_
trichloroethylene, %											
Ductility, 77°F, 5 cm/min.,	T 51	100	_	100	-	_	_	100	-	80	_
cm											
Float test, 140°F, sec.	T 50	1,200	_	-	-	1,200	_	-	-	-	-

Applies only when the Engineer designates material for winter use.

Table 8
Cationic Emulsified Asphalt

Property	Test						Тур	e-Grade	1				
	Procedure		Rapid-	Setting			Medium	-Setting			Slow-S	Setting	
		CF	RS-2	CRS	S-2H	CN	CMS-2 CMS-2S		CSS-1		CSS-1H		
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72												
77°F, sec.		_	_	_	_	_	_	_	_	20	100	20	100
122°F, sec.		150	400	150	400	100	300	100	300	-	_	ı	_
Sieve test, %	T 59	_	0.1	-	0.1	_	0.1	_	0.1	-	0.1	ı	0.1
Cement mixing, %	T 59	_	-	-	_	_	_	_	_	-	2.0	ı	2.0
Coating ability and water resistance:	T 59												
Dry aggregate/after spray			-	-	_	Good	d/Fair	Good	d/Fair	_		_	
Wet aggregate/after spray			-	-	-	Fair	/Fair	Fair	/Fair	_		-	
Demulsibility, 35 mL of 0.8%	T 59	70	_	70	-	_	_	_	_	-	_	-	-
Sodium dioctyl sulfosuccinate, %													
Storage stability, 1 day, %	T 59	-	1	-	1	_	1	_	1	-	1	-	1
Particle charge	T 59	Pos	sitive	Pos	itive	Pos	itive	Pos	itive	Posi	tive	Posi	tive
Distillation test:													
Residue by distillation, % by wt.	T 59	65	_	65	_	65	_	65	_	60	_	60	-
Oil distillate, % by volume of	1 39	_	0.5	_	0.5	_	7	-	5	-	0.5	-	0.5
emulsion													
Tests on residue from distillation:													
Penetration, 77°F, 100 g, 5 sec.	T 49	120	160	70	110	120	200	300	_	120	160	70	110
Solubility in trichloroethylene, %	T 44	97.5	-	97.5	_	97.5	_	97.5	_	97.5	-	97.5	-
Ductility, 77°F, 5 cm/min., cm	T 51	100	-	80	_	100	_		-	100	_	80	_

Table 9 Polymer-Modified Emulsified Asphalt

Property	Test		.y	ullied Elliu	1011104 710		e-Grade				
. ,	Procedure	Rapid-	Setting		Medium	n-Setting			Slow-	-Setting	
		HFR	S-2P	AES-	150P	AES-	300P	AES-3	300S	S	S-1P
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72										
77°F, sec.		_	-	75	400	75	400	75	400	30	100
122°F, sec.		150	400					_	-	_	_
Sieve test, %	T 59	_	0.1	-	0.1	-	0.1	-	0.1	-	0.1
Miscibility	T 59		_	-	_		_	-		F	ass
Coating ability and water resistance:											
Dry aggregate/after spray	T 59		_	Good	d/Fair	Good	d/Fair	Good/F	air		_
Wet aggregate/after spray			_	Fair	/Fair	Fair	/Fair	Fair/F	air		_
Demulsibility, 35 mL of 0.02 N CaCl ₂ ,	T 59	50	-	-	-	-	-	-	-	-	-
%											
Storage stability, 1 day, %	T 59	-	1	-	1	-	1	-	1	-	1
Breaking index, g	<u>Tex-542-C</u>	-	-								
Distillation test:1	T 59										
Residue by distillation, % by wt.		65	-	65	-	65	-	65	-	60	_
Oil distillate, % by volume of		-	0.5	-	3	-	5	_	7	-	0.5
emulsion											
Tests on residue from distillation:											
Polymer content, wt. % (solids	<u>Tex-533-C</u>	3.0	-	-	-	-	-	_	-	3.0	_
basis)											
Penetration, 77°F, 100 g, 5 sec.	T 49	90	140	150	300	300	-	300	-	100	140
Solubility in trichloroethylene, %	T 44	97.0	-	97.0	-	97.0	-	97.0	-	97.0	-
Viscosity, 140°F, poise	T 202	1,500	-	-	-	-	-	-	-	1,300	_
Float test, 140°F, sec	T 50	1,200	-	1,200	-	1,200	_	1,200	_	-	_
Ductility, ² 39.2°F, 5 cm/min., cm	T 51	50	-	_	_	_	_	_	_	50	-
Elastic recovery, 2 50°F, %	<u>Tex-539-C</u>	55	_	_	_	-	_	-	_	_	-
Tests on RTFO curing of distillation residue	T 240										
100.000	Tov 526 C			50		50		20			
Elastic recovery, 50°F, %	<u>Tex-536-C</u>	_	-	50	-	50	-	30	-	-	-

Exception to T 59: Bring the temperature on the lower thermometer slowly to 350°F ±10°F. Maintain at this temperature for 20 min. Complete total distillation in 60 min. (±5 min.) from the first application of heat.

 HFRS-2P must meet one of either the ductility or elastic recovery requirements.

Table 10 Polymer-Modified Cationic Emulsified Asphalt

Property	Test	. o.yc	· · · · · · · · · · · · · · · · · · ·	eu Calloni	o Elliaioi		Type-G	rade					
	Procedure			Rapid-S	etting				Medium	-Setting	1	Slow-	Setting
		CRS-	-2P	CHFR	S-2P	CRS-2	2TR	CMS	S-1P3	CM	S-2P ³	CS	S 1P
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72												
77°F, sec.		-	_	_	_	-	_	10	100	-	_	20	100
122°F, sec.		150	400	100	400	150	500	_	_	50	400	_	-
Sieve test, %	T 59	-	0.1	-	0.1	_	0.1	_	0.1	_	0.1	-	0.1
Demulsibility, 35 ml of 0.8% sodium	T 59	70	-	60	_	40	-	-	_	-	-	_	-
dioctyl sulfosuccinate, %													
Storage stability, 1 day, %	T 59	-	1	-	1	-	1	-	1	_	1	-	1
Breaking index, g	<u>Tex-542-C</u>	-	_	-	-	-	-	-	_	_	_	-	-
Particle charge	T 59	Posit	tive	Posi	tive	Posit	ive	Pos	sitive	Po	sitive	Po	sitive
Distillation test1:	T 59												
Residue by distillation, % by weight		65	_	65	_	65	-	30	_	60	-	62	-
Oil distillate, % by volume of emulsion		-	0.5	-	0.5	-	3	-	0.5	_	0.5	-	0.5
Tests on residue from distillation:													
Polymer content, wt. % (solids basis)	<u>Tex-533-C</u>	3.0	_	3.0	-	5.07	-	_	-	_	_	3.0	-
Penetration, 77°F, 100 g, 5 sec.	T 49	90	150	80	130	90	150	30	_	30	_	55	90
Viscosity, 140°F, poise	T 202	1,300	_	1,300	_	1,000	-	_	_	-	_		-
Solubility in trichloroethylene, %	T44	97.0	_	95.0	_	98	-	_	_	-	-	97.0	-
Softening point, °F	T 53	-	_	-	-	-	_	_	_	_	_	135	-
Ductility, 77°F, 5 cm/min., cm	T 51	-	_	-	-	40	-	_	_	_	_	70	-
Float test, 140°F, sec.	T 50	-	_	1,800	-	_	_	_	_	_	_	_	-
Ductility, ² 39.2°F, 5 cm/min., cm	T 51	50 55	_	- 55	_	_	_	_	_	_	_	_	-
Elastic recovery, 2 50°F, %	<u>Tex-539-C</u> R 78.	55	_	55	-	_		_	_	-		_	-
Tests on residue from evaporative	Procedure												
recovery:	B												
Nonrecoverable creep compliance of	T 350	_	_		_	_	_	_	2.0	_	4.0	_	_
residue, 3.2 kPa, 52°C, kPa-1	1 330	_	_	_	_	_	_	_	2.0	_	4.0	_	_
Tests on rejuvenating agent:													
Viscosity, 140°F, cSt	T 201	_	_	_	_	_	_	50	175	50	175	_	_
Flash point, C.O.C., °F	T 48	_	_	_	_	_	_	380	_	380	_	_	_
Saturates, % by weight	D 2007	_	_	_	_	_	_	_	30	_	30	_	_
Solubility in n-pentane, % by weight	D 2007	-	_	_	_	_	_	99	_	99	_	_	_
Tests on rejuvenating agent after RTFO	T 240												
Weight Change, %		-	_	_	_	_	-	_	6.5	-	6.5	_	-
Viscosity Ratio		-	_	_	_	_	-	_	3.0	-	3.0	-	
Tests on latex4:													
Tensile strength, die C dumbbell, psi	D 412 ⁵	-	_	_	_	_	-	800	_	800	-	_	-
Change in mass after immersion in	D 471	-	_	_	_	_	_	_	406	-	406	_	-
rejuvenating agent, %													

- Exception to T 59: Bring the temperature on the lower thermometer slowly to 350°F (±0°F). Maintain at this temperature for 20 min. Complete total distillation in 60 min. (±5 min.) from the first application of heat.
- CRS-2P must meet one of either the ductility or elastic recovery requirements.
- With all precertification samples of CMS-1P or CMS-2P, submit certified test reports showing that the rejuvenating agent and latex meet the stated 3. requirements. Submit samples of these raw materials if requested by the Engineer.
- Preparation of latex specimens: use any substrate and recovery method which produces specimens of uniform dimensions and which delivers enough material to achieve desired residual thickness.
- Cut samples for tensile strength determination using a crosshead speed of 20 in. per minute.
- Specimen must remain intact after exposure and removal of excess rejuvenating agent. 6.
- Modifier type is tire rubber.

Table 10A
Non-Tracking Tack Coat Emulsion¹

Property	Test Procedure	NT-	HRE	NT-RR	E	NT-	SRE
		Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72	15	-	15	-	10	100
77° F, sec.							
Storage stability, 1 Day, %	T 59	-	1	-	1	-	1
Settlement, 5-day, %	T 59	-	5	-	5	-	5
Sieve test, %	T 59	-	0.30	-	0.30	-	0.1
Distillation test:2	T 59						
Residue by distillation, % by wt.		50	_	58	_	50	_
Oil distillate, by volume of emulsion		_	1.0	_	1.0	_	1.0
Test on residue from distillation:							
Penetration, 77°F, 100 g, 5 sec.	T 49	_	20	15	45	40	90
Solubility in trichloroethylene, %	T 44	97.5	_	97.5	_	97.5	_
Softening point, °F	T 53	150	_	_	-	_	_
Dynamic shear, G*/sin(δ), 82°C, 10	T 315	1.0	_	_	-	_	_
rad/s, kPa							

- 1. Due to the hardness of the residue, these emulsions should be heated to 120-140°F before thoroughly mixing as the emulsion is being prepared for testing.
- 2. Exception to T 59: Bring the temperature on the lower thermometer slowly to 350°F ± 10°F. Maintain at this temperature for 20 min. Complete total distillation in 60 ± 5 min. from first application of heat.

Table10B
Spray Applied Underseal Membrane Polymer-Modified Emulsions (EBL)

Property	Test Procedure	Min	Max
Viscosity @ 77°F, SSF	T 72	20	100
Storage Stability ¹ , %	T 59	_	1
Demulsibility ²	T 59	55	-
Anionic emulsions – 35 mL of 0.02 N CaCl2, %			
Cationic emulsions – 35 mL of 0.8% sodium			
dioctyl sulfosuccinate, %			
Sieve Test ³ , %	T 59	_	0.05
Distillation Test ⁴	T 59		
Residue by distillation, % by wt.		63	
Oil portion of distillate, % by vol.			0.5
Test on Residue from Distillation			
Elastic Recovery @ 50°F, 50 mm/min., %	<u>Tex-539-C</u>	60	_
Penetration @ 77°F, 100 g, 5 sec., 0.1 mm	T 49	80	130

- After standing undisturbed for 24 hr., the surface must be smooth, must not exhibit a white or milky colored substance, and must be a homogeneous color throughout.
- 2. Material must meet demulsibility test for emulsions.
- 3. May be required by the Engineer only when the emulsion cannot be easily applied in the field.
- 4. The temperature on the lower thermometer should be brought slowly to 350°F ± 10°F and maintained at this temperature for 20 min. The total distillation should be completed in 60 ± 5 min. from the first application of heat.

Table 10C Full-Depth Reclamation Emulsion (FDR EM)

Property	Test Procedure	Standard	Yield (SY)	High	Yield (HY)
		Min	Max	Min	Max
Sieve test, %	T 59	_	0.1	_	0.1
Viscosity Saybolt Furol @ 77°F, sec.	T 59	20	100	20	100
Distillation test1:	T 59				
Residue by distillation, % by wt.		60	_	63	_
Oil portion of distillate, % by vol.		-	0.5	-	0.5
Test on residue from distillation:	T 49				
Penetration @ 77°F, dmm		55	95	120	_
Test on rejuvenating agent:					
BWOA, % ²	***	_	_	2	_
Viscosity @ 140°F, cSt	T 201	_	_	50	175
Flash Point, COC, °F	T 48	_	_	380	_
Solubility in n-pentane, % by wt.	D2007	_	_	99	_

- The temperature on the lower thermometer should be brought slowly to 350°F ±10°F and maintained at this temperature for 20 min. The total distillation should be completed in 60 ± 5 min. from the first application of heat.
- 2. BWOA = By weight of asphalt. Provide a manufacturer's certificate of analysis (COA) with the percent of rejuvenator added.

2.5. **Specialty Emulsions.** Provide specialty emulsion that is either asphalt-based or resin-based and meets the requirements of Table 11 or Table 11A.

Table 11
Specialty Emulsions

Property	Test Procedure			Type-0	Grade		
			Medium-	Setting		Slow-	Setting
		AE-	P	EA	P&T	P	CE ¹
		Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol	T 72						
77°F, sec.		_	_	_	_	10	100
122°F, sec.		15	150	_	-	_	-
Sieve test, %	T 59	_	0.1	_	0.1	_	0.1
Miscibility ²	T 59	-		Pass		Pass	
Demulsibility, 35 mL of 0.10 N CaCl ² , %	T 59	-	70	_	_	_	-
Storage stability, 1 day, %	T 59	-	1	_	1	_	-
Particle size, ⁵ % by volume < 2.5 μm	<u>Tex-238-F</u> ³	-	-	90	_	90	-
Asphalt emulsion distillation to 500°F							
followed by Cutback asphalt distillation of	T 59 & T 78						
residue to 680°F:							
Residue after both distillations, % by wt.		40	_	_	_	_	-
Total oil distillate from both distillations, %		25	40	_	_	_	-
by volume of emulsion							
Residue by distillation, % by wt.	T 59	-	-	60	-	_	-
Residue by evaporation, ⁴ % by wt.	T 59	-	_	_	-	60	-
Tests on residue after all distillations:							
Viscosity, 140°F, poise	T 202	_	_	800	_	_	-
Kinematic viscosity,5 140°F, cSt	T 201	-	_	_	_	100	350
Flash point C.O.C., °F	T 48	_	_	_	_	400	-
Solubility in trichloroethylene, %	T 44	97.5	_	_	_	_	-
Float test, 122°F, sec.	T 50	50	200	_	_	_	-

- 1. Supply with each shipment of PCE:
 - a copy of a lab report from an approved analytical lab, signed by a lab official, indicating the PCE formulation does not meet any characteristics of a Resource Conservation Recovery Act (RCRA) hazardous waste;
 - a certification from the producer that the formulation supplied does not differ from the one tested and that no listed RCRA hazardous wastes or Polychlorinated Biphenyls (PCBs) have been mixed with the product; and
 - a Safety Data Sheet.
 - 2. Exception to T 59: In dilution, use 350 mL of distilled or deionized water and a 1,000-mL beaker.
 - 3. Use <u>Tex-238-F</u>, beginning at "Particle Size Analysis by Laser Diffraction," with distilled or deionized water as a medium and no dispersant, or use another approved method.
 - 4. Exception to T 59: Leave sample in the oven until foaming ceases, then cool and weigh.
 - 5. PCE must meet either the kinematic viscosity requirement or the particle size requirement.

Table 11A Hard Residue Surface Sealant

Property	Test	Min	Max
. ,	Procedure		
Viscosity, Krebs unit, 77°F, Krebs units	D 562	45	75
Softening point, °F	Tex-505-C ¹	250	-
Uniformity	D 2939	Pa	SS ²
Resistance to heat	D 2939	Pa	SS ³
Resistance to water	D 2939	Pa	ss ⁴
Wet flow, mm	D 2939	_	0
Resistance to Kerosene (optional) ⁵	D 2939	Pa	SS ⁶
Ultraviolet exposure, UVA-340, 0.77 W/m ² ,	G 154	Pa	SS ⁸
50°C chamber, 8 hr. UV lamp, 5 min. spray,			
3 hr. 55 min. condensation, 1,000 hr. total			
exposure ⁷			
Abrasion loss, 1.6 mm thickness, liquid only, %	ISSA TB-100	-	1.0
Residue by evaporation, % by weight	D 2939	33	-
Tests on residue from evaporation:			
Penetration, 77°F, 100 g, 5 sec.	T 49	15	30
Flash point, Cleveland open cup, °F	T 48	500	
Tests on base asphalt before emulsification			
Solubility in trichloroethylene, %	T 44	98	_

- 1. Cure the emulsion in the softening point ring in a 200°F \pm 5°F oven for 2 hr.
- 2. Product must be homogenous and show no separation or coagulation that cannot be overcome by moderate stirring.
- 3. No sagging or slippage of film beyond the initial reference line.
- 4. No blistering or re-emulsification.
- 5. Recommended for airport applications or where fuel resistance is desired.
- 6. No absorption of Kerosene into the clay tile past the sealer film. Note sealer surface condition and loss of adhesion.
- 7. Other exposure cycles with similar levels of irradiation and conditions may be used with Department approval.
- 8. No cracking, chipping, surface distortion, or loss of adhesion. No color fading or lightening.
- 2.6. **Recycling Agent**. Recycling agent and emulsified recycling agent must meet the requirements in Table 12. Additionally, recycling agent and residue from emulsified recycling agent, when added in the specified proportions to the recycled asphalt, must meet the properties specified on the plans.

11 - 17 12-21

Table 12 Recycling Agent and Emulsified Recycling Agent

Property	Test Procedure	Recyclin	ng Agent	Emulsified Recycling Agent (ARA-1)		Emul Recyclir	Modified sified ng Agent A-1P)
		Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol, 77°F, sec.	T 72	-	-	15	100	15	110
Sieve test, %	T 59	-	-	1	0.1	_	0.1
Miscibility ¹	T 59			No coa	gulation		
Residue by evaporation, ² % by wt.	T 59	-	-	60	-	_	-
Distillation test: Residue by distillation, % by wt. Oil distillate, % by volume of emulsion	T 59					60 -	65 2
Penetration of Distillation Residue at 39.2°F, 100 g, 5 sec.	T 49					110	190
Tests on recycling agent or residue from evaporation: Flash point, C.O.C., °F Kinematic viscosity,	T 48 T 201	400	-	400	_	400	-
140°F, cSt 275°F, cSt	. 201	75 –	200 10.0	75 -	200 10.0		

- Exception to T 59: Use 0.02 N CaCl2 solution in place of water.
- Exception to T 59: Maintain sample at 300°F until foaming ceases, then cool and weigh.
- 2.7. Crumb Rubber Modifier. Crumb rubber modifier (CRM) consists of automobile and truck tires processed by ambient temperature grinding.

CRM must be:

- free from contaminants including fabric, metal, and mineral and other nonrubber substances;
- free-flowing; and
- nonfoaming when added to hot asphalt binder.

Ensure rubber gradation meets the requirements of the grades in Table 13 when tested in accordance with Tex-200-F, Part I, using a 50-g sample.

Table 13 **CRM Gradations**

Sieve Size	Grad	e A	Gra	de B	Grade C		Grade D	Grade E
(% Passing)	Min	Max	Min	Max	Min	Max		
#8	100	_	_	_	_	_		
#10	95	100	100	_	-	_		
#16	_	_	70	100	100	_	As shown on the plans	As approved
#30	-	-	25	60	90	100		As approved
#40	-	-	-	-	45	100		
#50	0	10	_	_	_	_		
#200	-	_	0	5	_	_		

2.8. Crack Sealer. Provide polymer-modified asphalt-emulsion crack sealer meeting the requirements of Table 14. Provide rubber-asphalt crack sealer meeting the requirements of Table 15.

Table 14 Polymer-Modified Asphalt-Emulsion Crack Sealer

1 orymer meanica repriate Emaision Grack Gealer									
Property	Test Procedure	Min	Max						
Rotational viscosity, 77°F, cP	D 2196, Method A	10,000	25,000						
Sieve test, %	T 59	_	0.1						
Storage stability, 1 day, %	T 59	-	1						
Evaporation	<u>Tex-543-C</u>								
Residue by evaporation, % by wt.		65	-						
Tests on residue from evaporation:									
Penetration, 77°F, 100 g, 5 sec.	T 49	35	75						
Softening point, °F	T 53	140	_						
Ductility, 39.2°F, 5 cm/min., cm	T 51	100	_						

Table 15 Rubber-Asphalt Crack Sealer

Property	Test	Clas	ss A	Clas	ss B
	Procedure	Min	Max	Min	Max
CRM content, Grade A or B, % by wt.	<u>Tex-544-C</u>	22	26	_	_
CRM content, Grade B, % by wt.	<u>Tex-544-C</u>	_	-	13	17
Virgin rubber content,1 % by wt.		_	-	2	_
Flash point, ² C.O.C., °F	T 48	400	-	400	_
Penetration, ³ 77°F, 150 g, 5 sec.	T 49	30	50	30	50
Penetration, ³ 32°F, 200 g, 60 sec.	T 49	12	-	12	_
Softening point, °F	T 53	ı	-	170	-
Bond Test, non-immersed, 0.5 in specimen,					
50% extension, 20°F4	D5329	-	-	Pa	iss

- Provide certification that the Min % virgin rubber was added.
- Agitate the sealing compound with a 3/8- to 1/2 in. (9.5- to 12.7 mm) wide, square-end metal spatula to bring the material on the bottom of the cup to the surface (i.e., turn the material over) before passing the test flame over the cup. Start at one side of the thermometer, move around to the other, and then return to the starting point using 8 to 10 rapid circular strokes. Accomplish agitation in 3 to 4 sec. Pass the test flame over the cup immediately after stirring is completed.
- Exception to T 49: Substitute the cone specified in D 217 for the penetration needle.
- Allow no crack in the crack sealing materials or break in the bond between the sealer and the mortar blocks over 1/4 in. deep for any specimen after completion of the test.
- 2.9. Asphalt-Rubber Binders. Provide asphalt-rubber (A-R) binders that are mixtures of asphalt binder and CRM, which have been reacted at elevated temperatures. Provide A-R binders meeting D6114 and containing a minimum of 15% CRM by weight. Provide Types I or II, containing CRM Grade C, for use in hotmixed aggregate mixtures. Provide Types II or III, containing CRM Grade B, for use in surface treatment binder. Ensure binder properties meet the requirements of Table 16.

Table 16 A-R Binders

Property	Test	Binder Type						
	Procedure	Type I		Тур	e II	Type III		
		Min	Max	Min	Max	Min	Max	
Apparent viscosity, 347°F, cP	D2196,	1,500	5,000	1,500	5,000	1,500	5,000	
	Method A							
Penetration, 77°F, 100 g, 5 sec.	T 49	25	75	25	75	50	100	
Penetration, 39.2°F, 200 g, 60 sec.	T 49	10	_	15	_	25	_	
Softening point, °F	T 53	135	_	130	_	125	_	
Resilience, 77°F, %	D5329	25	_	20	_	10	_	
Flash point, C.O.C., °F	T 48	450	_	450	_	450	_	
Tests on residue from Thin-Film	T 179							
Oven Test:								
Retained penetration ratio, 39.2°F, 200 g, 60 sec., % of original	T 49	75	_	75	_	75	_	

2.10. Performance-Graded Binders. Provide PG binders that are smooth and homogeneous, show no separation when tested in accordance with <u>Tex-540-C</u>, and meet the requirements of Table 17.

Separation testing is not required if:

- a modifier is introduced separately at the mix plant either by injection in the asphalt line or mixer,
- the binder is blended on site in continuously agitated tanks, or
- binder acceptance is based on field samples taken from an in-line sampling port at the hot-mix plant after the addition of modifiers.

Table 17 Performance-Graded Binders

Property and Test Method	Performance Grade																	
. ,		PG 58 PG 64 PG 70					PG	76		PG 82								
	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28
Average 7-day max pavement design temperature, °C1		58				64			7	70			7	'6			82	
Min pavement design temperature, °C1	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28
			!			Ori	ginal Bin	der	u .	ļ.					u .	!	u .	!
Flash point, T 48, Min, °C							_		23	30								
Viscosity, T 316 ^{2, 3} :									13	0.5								
Max, 3.0 Pa s, test temperature, °C									13	55								
Dynamic shear, T 3154:																		
G*/sin(δ), Min, 1.00 kPa, Max, 2.00		58				C 4			-	70			7	'6			00	
kPa ⁷ ,		58				64				70			,	О		82		
Test temperature @ 10 rad/sec., °C																		
Elastic recovery, D6084, 50°F, % Min8	_	_	30	_	_	30	50	_	30	50	60	30	50	60	70	50	60	70
•		•			Rollin	g Thin-	Film Ove	n (Tex-50	06-C)			•	•	•				
Mass change, T 240, Max, %								•	1.	.0								
Dynamic shear, T 315:																		
G*/sin(δ), Min, 2.20 kPa, Max, 5.00 kPa ⁷ ,		58				64		70			76			82				
Test temperature @ 10 rad/sec., °C																		
MSCR, T350, Recovery, 0.1 kPa, High			20			20	30		20	30	40	20	30	40	50	30	40	50
Temperature, % Min ⁸	_	_	20	_	_	20	30	_	20	30	40	20	30	40	50	30	40	50
•				Pre	ssure /	Aging V	essel (PA	V) Resid	lue (R 2	8)		•	•					
PAV aging temperature, °C									10	00								
Dynamic shear, T 315:																		
G*sin(δ), Max, 5,000 kPa	25	22	19	28	25	22	19	28	25	22	19	28	25	22	19	28	25	22
Test temperature @ 10 rad/sec., °C																		
Creep stiffness, T 313 ^{5, 6} :																		
S, max, 300 MPa,	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18
<i>m</i> -value, Min, 0.300	-12	-10	-24	-0	-12	-10	-24	-0	-12	-10	-24	-0	-12	-10	-24	-0	-12	-10
Test temperature @ 60 sec., °C																		
Direct tension, T 3146:																		
Failure strain, min, 1.0%	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18
Test temperature @ 1.0 mm/min., °C								hm cont										

- Pavement temperatures are estimated from air temperatures and using an algorithm contained in a Department-supplied computer program, may be provided by the Department, or by following the procedures outlined in AASHTO MP 2 and PP 28.
- This requirement may be waived at the Department's discretion if the supplier warrants that the asphalt binder can be adequately pumped, mixed, and compacted at temperatures that meet all applicable safety, environmental, and constructability requirements. At test temperatures where the binder is a Newtonian fluid, any suitable standard means of viscosity measurement may be used, including capillary (T 201 or T 202) or rotational viscometry (T 316).
- Viscosity at 135°C is an indicator of mixing and compaction temperatures that can be expected in the lab and field. High values may indicate high mixing and compaction temperatures. Additionally, significant variation can occur from batch to batch. Contractors should be aware that variation could significantly impact their mixing and compaction operations. Contractors are therefore responsible for addressing any constructability issues that may arise.
- For quality control of unmodified asphalt binder production, measurement of the viscosity of the original asphalt binder may be substituted for dynamic shear measurements of G*/sin(δ) at test temperatures where the asphalt is a Newtonian fluid. Any suitable standard means of viscosity measurement may be used. including capillary (T 201 or T 202) or rotational viscometry (T 316).
- Silicone beam molds, as described in AASHTO TP 1-93, are acceptable for use.
- If creep stiffness is below 300 MPa, direct tension test is not required. If creep stiffness is between 300 and 600 MPa, the direct tension failure strain requirement can be used instead of the creep stiffness requirement. The m value requirement must be satisfied in both cases.
- Maximum values for unaged and RTFO aged dynamic shear apply only to materials used as substitute binders, as described in Item 340, "Dense-Graded Hot-Mix Asphalt (Small Quantity)", Item 341, "Dense-Graded Hot-Mix Asphalt, and Item 344, "Superpave Mixtures."
- Elastic Recovery (ASTM D6084) is not required unless MSCR (AASHTO T 350) is less than the minimum % recovery. Elastic Recovery must be used for the acceptance criteria in this instance.

3. **EQUIPMENT**

Provide all equipment necessary to transport, store, sample, heat, apply, and incorporate asphalts, oils, and emulsions.

4. CONSTRUCTION

Typical Material Use. Use materials shown in Table 18, unless otherwise determined by the Engineer.

Table18
Typical Material Use

Material Application	Typical Material Use Typically Used Materials				
Hot-mixed, hot-laid asphalt mixtures	PG binders, A-R binders Types I and II				
	AC-5, AC-10, AC-15P, AC-20XP, AC-10-2TR, AC-20-5TR,				
Surface treatment	HFRS-2, MS-2, CRS-2, CRS-2H, CRS-2TR, CMS-2P HFRS-2P,				
	CRS-2P, CHFRS-2P, A-R binders Types II and III				
Surface treatment (cool weather)	AC12-5TR, RC-250, RC-800, RC-3000, MC-250, MC-800,				
Surface treatment (coor weather)	MC-3000, MC-2400L, CMS-2P				
Precoating	AC-5, AC-10, PG 64-22, SS-1, SS-1H, CSS-1, CSS-1H				
Tack coat	PG Binders, SS-1H, CSS-1H, EAP&T, TRAIL, EBL				
Fog seal	SS-1, SS-1H, CSS-1, CSS-1H, CMS-1P				
Hot-mixed, cold-laid asphalt	AC-0.6, AC-1.5, AC-3, AES-300, AES-300P, CMS-2, CMS-2S				
mixtures	AC-0.0, AC-1.0, AC-0, ALO-000, ALO-000F, CIVIO-2, CIVIO-20				
Patching mix	MC-800, SCM I, SCM II, AES-300S				
Recycling	AC-0.6, AC-1.5, AC-3, AES-150P, AES-300P, recycling agent,				
recycling	emulsified recycling agent				
Crack sealing	SS-1P, polymer mod AE crack sealant, rubber asphalt crack				
	sealers (Class A, Class B)				
Microsurfacing	CSS-1P				
Prime	MC-30, AE-P, EAP&T, PCE				
Curing membrane	SS-1, SS-1H, CSS-1, CSS-1H, PCE				
Erosion control	SS-1, SS-1H, CSS-1, CSS-1H, PCE				
FDR -Foaming	PG 64-22, FDR EM-SY, FDR EM-HY				

4.1. **Storage and Application Temperatures**. Use storage and application temperatures in accordance with Table 19. Store and apply materials at the lowest temperature yielding satisfactory results. Follow the manufacturer's instructions for any agitation requirements in storage. Manufacturer's instructions regarding recommended application and storage temperatures supersede those of Table 19.

Table19 **Storage and Application Temperatures**

	Applica	Storage	
Type-Grade	Recommended Range (°F)	Max Allowable (°F)	Max (°F)
AC-0.6, AC-1.5, AC-3	200–300	350	350
AC-5, AC-10	275–350	350	350
AC-15P, AC-20-5TR, AC12-5TR and AC10-2TR	300–375	375	360
RC-250	125–180	200	200
RC-800	170–230	260	260
RC-3000	215–275	285	285
MC-30, AE-P	70–150	175	175
MC-250	125–210	240	240
MC-800, SCM I, SCM II	175–260	275	275
MC-3000, MC-2400L	225–275	290	290
HFRS-2, MS-2, CRS-2, CRS-2H, HFRS-2P, CRS-2P, CMS-2, CMS-2S, AES-300, AES-300S, AES-150P, AES-300P, CRS-2TR	120–160	180	180
SS-1, SS-1H, CSS-1, CSS-1H, PCE, EAP&T, SS-1P, RS-1P, CRS-1P, CSS-1P, recycling agent, emulsified recycling agent, polymer mod AE crack sealant	50–130	140	140
PG binders	275–350	350	350
Rubber asphalt crack sealers (Class A, Class B)	350–375	400	_
A-R binders Types I, II, and III	325–425	425	425

5. **MEASUREMENT AND PAYMENT**

The work performed, materials furnished, equipment, labor, tools, and incidentals will not be measured or paid for directly but is subsidiary or is included in payment for other pertinent Items.

Special Specification 5008 Precast Concrete Wheel Stops



1. DESCRIPTION

Furnish and install precast concrete wheel stops.

2. MATERIALS

Provide 6 ft. length minimum wheel stops unless otherwise shown on the plans or as approved.

Hydraulic Concrete. Use Class A concrete conforming to Item 421, "Hydraulic Cement Concrete."

Reinforcing Steel. Use reinforcing steel conforming to Item 440, "Reinforcement for Concrete." Minimum reinforcing is two No. 4 or No. 3 bars placed longitudinally.

Precast. Submit commercially available wheel stop designs for approval.

3. CONSTRUCTION

Use an anchoring method and anchor rod type as shown on the plans or as approved.

4. MEASUREMENT

This Item will be measured by each wheel stop.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Precast Concrete Wheel Stops." This price is full compensation for furnishing, preparing, hauling and placing materials, and for labor, tools, equipment, and incidentals.

1 01-16 OTU