

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: BR 2022(355)

CONTROL: 0909-29-046

COUNTY: HAMILTON

LETTING: 05/05/2023

REFERENCE NO: 0425

PROPOSAL ADDENDUMS

-
- PROPOSAL COVER
 - BID INSERTS (SH. NO.: 2-4)
 - GENERAL NOTES (SH. NO.:)
 - SPEC LIST (SH. NO.:)
 - SPECIAL PROVISIONS:)
 - ADDED:
 -
 - DELETED:
 -
 - SPECIAL SPECIFICATIONS:
 - ADDED:
 -
 - DELETED:
 -
 - OTHER: PLANS

DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)

*****BID INSERTS*****

REVISED QTY FOR ITEM 500-6001

*****PLANS*****

SHEET 5: SEE CHANGES ABOVE



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0909-29-046

DISTRICT Waco
HIGHWAY CR 207

COUNTY Hamilton

CONTROL SECTION JOB				0909-29-046		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00140255			
COUNTY				Hamilton			
HIGHWAY				CR 207			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-6002	PREPARING ROW	STA	5.300		5.300	
	110-6001	EXCAVATION (ROADWAY)	CY	312.000		312.000	
	110-6002	EXCAVATION (CHANNEL)	CY	630.000		630.000	
	132-6004	EMBANKMENT (FINAL)(DENS CONT)(TY B)	CY	890.000		890.000	
	160-6003	FURNISHING AND PLACING TOPSOIL (4")	SY	1,362.000		1,362.000	
	164-6001	BROADCAST SEED (PERM) (RURAL) (SANDY)	SY	1,362.000		1,362.000	
	164-6071	BROADCAST SEED (TEMP)(WARM OR COOL)	SY	1,362.000		1,362.000	
	168-6001	VEGETATIVE WATERING	MG	23.000		23.000	
	169-6002	SOIL RETENTION BLANKETS (CL 1) (TY B)	SY	1,362.000		1,362.000	
	247-6053	FL BS (CMP IN PLC)(TYD GR1-2)(FNAL POS)	CY	194.000		194.000	
	400-6005	CEM STABIL BKFL	CY	105.000		105.000	
	416-6004	DRILL SHAFT (36 IN)	LF	147.000		147.000	
	420-6013	CL C CONC (ABUT)	CY	38.600		38.600	
	420-6029	CL C CONC (CAP)	CY	11.500		11.500	
	420-6037	CL C CONC (COLUMN)	CY	12.000		12.000	
	422-6001	REINF CONC SLAB	SF	3,640.000		3,640.000	
	425-6035	PRESTR CONC GIRDER (TX28)	LF	555.920		555.920	
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	862.000		862.000	
	450-6054	RAIL (TY SSTR) (W/DRAIN SLOTS)	LF	328.000		328.000	
	454-6004	ARMOR JOINT (SEALED)	LF	46.000		46.000	
	496-6009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000		1.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	1
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	5.000		5.000	
	506-6001	ROCK FILTER DAMS (INSTALL) (TY 1)	LF	176.000		176.000	
	506-6011	ROCK FILTER DAMS (REMOVE)	LF	176.000		176.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	1,036.000		1,036.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	1,036.000		1,036.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	100.000		100.000	
	540-6007	MTL BEAM GD FEN TRANS (TL2)	EA	2.000		2.000	
	540-6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	2.000		2.000	
	540-6018	MTL BM GD FEN TRANS (NON - SYM)	EA	2.000		2.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	2.000		2.000	
	552-6003	WIRE FENCE (TY C)	LF	100.000		100.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	3.000		3.000	
	658-6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	6.000		6.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	4.000		4.000	
08		CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS	1.000		1.000	

 = Revised By Addendum #1 - 04/25/23



DISTRICT	COUNTY	CCSJ	SHEET
Waco	Hamilton	0909-29-046	5