

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: C 441-7-74

CONTROL: 0441-07-074

COUNTY: PECOS

LETTING: 03/05/2024

REFERENCE NO: 0223

PROPOSAL ADDENDUMS

PROPOSAL COVER

BID INSERTS (SH. NO.: ALL)

GENERAL NOTES (SH. NO.: B)

SPEC LIST (SH. NO.: ALL)

SPECIAL PROVISIONS:

ADDED: SP008-006

DELETED:

SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

OTHER: PLAN SHEETS AND OTHER CHANGES

DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)

***** Bid Insert *****

ALL BID INSERT PROPOSAL SHEETS AND E&Q SHEETS 5,5A ARE REPLACED
AS PART OF THIS ADDENDUM

ADDED THE FOLLOWING BID ITEMS:

105-6069

DELETED THE FOLLOWING BID ITEMS:

105-6044

***** General Notes *****

GENERAL NOTES PROPOSAL SHEET B AND PLAN SHEET 004 ARE REPLACED AS PART OF
THIS ADDENDUM

SHEET B ITEM 8: ADDED NOTE

***** Spec List *****

DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)

(CONTINUED)

ADDED SPECIAL PROVISION SP008-006

***** Plan Sheets *****

SHEET 4 (GENERAL NOTES): REFER TO GENERAL NOTES CHANGED AS NOTED ABOVE

SHEETS 5, 5A (ESTIMATE & QUANTITY): REFER TO BID INSERT CHANGES AS NOTED ABOVE. ALSO REPLACED SHEET 5A

SHEET 6: REVISED ITEM

Contractor questions on this project are to be addressed to the following individual(s):
ODA-PreLettingQuestions@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Item 5: Control of the Work

For any structures containing bird nests, schedule all work to complete the demolition of the existing structures identified in the plans between September 15, 2023 and March 15, 2025. Failure to complete this work during the specified timeframe may cause construction delays due to environmental regulations.

The existing alignment is the control for the Contractor staking. Establish reference points for the control prior to removing the existing surface.

Use Method C for construction surveying.

In the event the finished surface does not conform to the typical sections or does not meet the required IRI, rework the non-conforming area to the limits necessary and employ additional survey control as directed.

Item 6: Control of Materials

Restrict storage of equipment and materials to approved areas. The Engineer will not approve storage in any TxDOT yard.

Promptly and properly dispose of any waste generated from servicing equipment on the project.

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit a notarized original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

Item 7: Legal Relations and Responsibilities

If access to the project is required through a new or unapproved driveway (i.e. Material source, stockpile location, field office, etc.), obtain an approved "Permit to Construct Access Driveway Facilities on Highway Right Of Way" (TxDOT Form 1058) before beginning any construction operations.

Utilities (public, private and TxDOT) exist throughout the project. Prior to any excavation, investigate to determine the utility locations within the project right of way. Contact the TxDOT Odessa Traffic Operations shop at 432-498-4690 to investigate and determine the location of any TxDOT utility that may exist within the project right of way. Exercise caution when excavating in areas where investigations have determined that utilities exist. The contractor is responsible for maintaining utility markings

No significant traffic generator events identified.

As an element of ensuring public safety and convenience under Article 7.2.4, the Contractor is hereby directed to open all closed lanes and shoulder and remove all traffic control devices from any areas where work is not being actively performed unless overnight traffic control is required and approved by the engineer. Removed devices must be stored outside of the clear zones near the right of way line or removed from the right of way line entirely.

At any time during construction that a previously installed crash cushion is damaged by the traveling public and is requested to be repaired by the Engineer, the repair will be paid at the same unit cost as the original installation.


Item 8: Prosecution and Progress

The following portions of the plans may affect the Contractor's planned construction sequencing. The Contractor's attention is directed to the appropriate plan sheet or standard sheet.

- Traffic Control Plan
- Storm Water Pollution Prevention Plan
- Environmental Permit, Issues And Commitments (EPIC)

Maintain ingress and egress to the frontage roads at all times.

Working days will be computed and charged in accordance with Article 8. 3.1.4. "Standard Workweek."

 Incentive for early contract completion shall be based on contract administrative liquidated damage rates. Incentive for early contract completion shall be maxed out at 30 days.

The road-user cost liquidated damages for 0441-07-074 are \$ 1,943 per day.

 Revised per Addendum 1 02/22/24



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0441-07-074

DISTRICT Odessa

COUNTY Pecos

HIGHWAY IH 10

CONTROL SECTION JOB				0441-07-074		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00180189			
COUNTY				Pecos			
HIGHWAY				IH 10			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
⚠	105-6069	REMOVING STAB BASE & ASPH PAV (4" - 6")	SY	119,188.000		119,188.000	
	134-6002	BACKFILL (TY B)	STA	410.000		410.000	
	150-6002	BLADING	HR	50.000		50.000	
	216-6001	PROOF ROLLING	HR	50.000		50.000	
	251-6079	REWORK BS MTL (TY D)(SURF)(ORD COMP)	SY	119,188.000		119,188.000	
	310-6005	PRIME COAT (AE-P)	GAL	23,838.000		23,838.000	
	315-6004	FOG SEAL (CSS-1H)	GAL	23,838.000		23,838.000	
	316-6017	ASPH (AC-20-5TR)	GAL	45,291.000		45,291.000	
	316-6126	AGGR(TY-PB GR-4 SAC-A)	CY	1,539.000		1,539.000	
	351-6013	FLEXIBLE PAVEMENT STRUCTURE REPAIR(4")	SY	4,500.000		4,500.000	
	354-6021	PLANE ASPH CONC PAV(0" TO 2")	SY	11,910.000		11,910.000	
	416-6016	DRILL SHAFT (SIGN MTS) (12 IN)	LF	40.000		40.000	
	416-6018	DRILL SHAFT (SIGN MTS) (24 IN)	LF	36.000		36.000	
	420-6136	CL C CONC (RAC-R)	CY	274.000		274.000	
	432-6045	RIPRAP (MOW STRIP)(4 IN)	CY	156.000		156.000	
	451-6024	RETROFIT RAIL (TY SSTR)	LF	3,532.000		3,532.000	
	500-6001	MOBILIZATION	LS	1.000		1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	10.000		10.000	
	506-6042	BIODEG EROSN CONT LOGS (INSTL) (18")	LF	2,500.000		2,500.000	
	506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF	2,500.000		2,500.000	
	533-6001	RUMBLE STRIPS (SHOULDER)	LF	75,228.000		75,228.000	
	540-6002	MTL W-BEAM GD FEN (STEEL POST)	LF	3,532.000		3,532.000	
	540-6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	24.000		24.000	
	542-6001	REMOVE METAL BEAM GUARD FENCE	LF	3,444.000		3,444.000	
	542-6002	REMOVE TERMINAL ANCHOR SECTION	EA	24.000		24.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	24.000		24.000	
	544-6003	GUARDRAIL END TREATMENT (REMOVE)	EA	24.000		24.000	
	636-6002	ALUMINUM SIGNS (TY G)	SF	406.000		406.000	
	644-6001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	13.000		13.000	
	644-6004	IN SM RD SN SUP&AM TY10BWG(1)SA(T)	EA	9.000		9.000	
	644-6076	REMOVE SM RD SN SUP&AM	EA	22.000		22.000	
	647-6001	INSTALL LRSS (STRUCT STEEL)	LB	3,259.000		3,259.000	
	647-6003	REMOVE LRSA	EA	8.000		8.000	
	658-6015	INSTL DEL ASSM (D-SW)SZ (BRF)GF1	EA	21.000		21.000	
	658-6026	INSTL DEL ASSM (D-SY)SZ (BRF)CTB	EA	14.000		14.000	
	658-6028	INSTL DEL ASSM (D-SY)SZ (BRF)GF1	EA	4.000		4.000	
	658-6060	REMOVE DELIN & OBJECT MARKER ASSMS	EA	182.000		182.000	



⚠ REVISED PER ADDENDUM 1 02/26/24

Report Generated By: txdotconnect_internal_ext

Report Created On: Feb 26, 2024 3:03:41 PM

DISTRICT	COUNTY	CCSJ	SHEET
Odessa	Pecos	0441-07-074	005



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0441-07-074

DISTRICT Odessa
HIGHWAY IH 10

COUNTY Pecos

CONTROL SECTION JOB				0441-07-074		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00180189			
COUNTY				Pecos			
HIGHWAY				IH 10			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	658-6080	INSTL DEL ASSM (D-SW)SZ 1(WFLX)GND	EA	30.000		30.000	
	658-6086	INSTL DEL ASSM (D-SY)SZ 1(YFLX)GND	EA	83.000		83.000	
	658-6099	INSTL OM ASSM (OM-2Z)(WFLX)GND	EA	30.000		30.000	
	662-6005	WK ZN PAV MRK NON-REMOV (W)6"(BRK)	LF	9,412.000		9,412.000	
	662-6008	WK ZN PAV MRK NON-REMOV (W)6"(SLD)	LF	40,950.000		40,950.000	
	662-6037	WK ZN PAV MRK NON-REMOV (Y)6"(SLD)	LF	41,339.000		41,339.000	
	662-6109	WK ZN PAV MRK SHT TERM (TAB)TY W	EA	2,792.000		2,792.000	
	666-6036	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	2,526.000		2,526.000	
	666-6042	REFL PAV MRK TY I (W)12"(SLD)(100MIL)	LF	200.000		200.000	
	666-6306	RE PM W/RET REQ TY I (W)6"(BRK)(100MIL)	LF	9,412.000		9,412.000	
	666-6309	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL)	LF	40,950.000		40,950.000	
	666-6321	RE PM W/RET REQ TY I (Y)6"(SLD)(100MIL)	LF	41,339.000		41,339.000	
	668-6084	PREFAB PAV MRK TY C (W) (NUMBER)	EA	6.000		6.000	
	672-6010	REFL PAV MRKR TY II-C-R	EA	557.000		557.000	
	3077-6007	SP MIXES SP-B SAC-B PG70-22	TON	36,056.000		36,056.000	
	3077-6075	TACK COAT	GAL	11,919.000		11,919.000	
	3080-6021	STONE-MTRX-ASPH SMAR-F SAC-A	TON	13,971.000		13,971.000	
	3084-6001	BONDING COURSE	GAL	13,547.000		13,547.000	
	6001-6002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	6079-6002	AUTO PORT SMRT TRF MONITOR SYS (PLAN 1)	DAY	328.000		328.000	
	6158-6001	TMSP RADAR SPEED CONTROL MONITOR	EA	2.000		2.000	
	6185-6002	TMA (STATIONARY)	DAY	328.000		328.000	
	6185-6005	TMA (MOBILE OPERATION)	DAY	328.000		328.000	
	08	CONTRACTOR FORCE ACCOUNT SAFETY CONTINGENCY (NON-PARTICIPATING)	LS	1.000		1.000	
		CONTRACTOR FORCE ACCOUNT EROSION CONTROL MAINTENANCE (NON-PARTICIPATING)	LS	1.000		1.000	

1

1 Revised per Addendum 1 02/22/24

DISTRICT	COUNTY	CCSJ	SHEET
Odessa	Pecos	0441-07-074	005A

ROADWAY ITEMS



DESCRIPTION	STA	to	STA	LENGTH (FT)	WIDTH (FT) (MAINLANES)	FULL WIDTH (FT)	SURFACE AREA (SY) (MAINLANES)	FULL WIDTH AREA (SY)	0105 6069	0134 6002	0150 6002	0216 6001	0251 6079	0310 6005	0315 6004	
									REMOVING STAB BASE & ASPH PAV (4" - 6")	BACKFILL (TY B)	BLADING	PROOF ROLLING	REWORK BS MTL (TY D) (SURF) (ORD COMP)	PRIME COAT (AE-P)	FOG SEAL (CSS-1H)	
									SY	STA	HR	HR	SY	GAL	GAL	
IH 10 WB	989+95		59+28	18,807	26	38	54,331	79,407	54,331	188				54,331	10,866	10,866
IH 10 EB	989+95		59+28	18,807	26	38	54,331	79,407	54,331	188	50	50		54,331	10,866	10,866
KENNEDY RAMP ON/OFF				3,383	28		10,525		10,525	34				10,525	2,105	2,105
PROJECT TOTALS									119,188	410	50	50	119,188	23,838	23,838	

DESCRIPTION	STA	to	STA	LENGTH (FT)	WIDTH (FT) MAINLANES	FULL WIDTH (FT)	SURFACE AREA (SY)	FULL WIDTH AREA (SY)	316 6017	316 6126	3077 6007	3077 6075	3080 6021
									ASPH (AC-20-5TR)	AGGR (TY-PB GR-4 SAC-A)	SP MIXES SP-B SAC-B PG70-22	TACK COAT	STONE-MTRX-ASPH SMAR-F SAC-A
									GAL	SY/CY	5.5 IN	GAL/SY	1.5 IN
IH 10 WB (MAINLANES)	989+95		59+28	18,807	26	38	54,331	79,407	20,646	722	16,436	5,433	6,551
IH 10 EB (MAINLANES)	989+95		59+28	18,807	26	38	54,331	79,407	20,646	722	16,436	5,433	6,551
KENNEDY RAMP ON/OFF				3,383	28		10,525		3,999	96	3,184	1,052	868
PROJECT TOTALS									45,291	1,539	36,056	11,919	13,971

Revised per Addendum 1 02/22/24

CONSOLIDATED SUMMARY

SHEET 1 OF 4



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
6	SEE TITLE SHEET			6
STATE	STATE DIST.	COUNTY		
TEXAS	ODA	PECOS		
CONT.	SECT.	JOB	HIGHWAY NO.	
0140	03	052	IH 10	