

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: BR 2B23 (212)

CONTROL: 0913-09-119

COUNTY: WHARTON

LETTING: 08/02/2024

REFERENCE NO: 0722

**PROPOSAL ADDENDUMS**

-----

- PROPOSAL COVER
- BID INSERTS (SH. NO.: ALL )
- GENERAL NOTES (SH. NO.: )

- SPEC LIST (SH. NO.: )
- SPECIAL PROVISIONS: )
- ADDED:

DELETED:

- SPECIAL SPECIFICATIONS:
- ADDED:

DELETED:

OTHER: PLAN SHEET AND OTHER CHANGES

DESCRIPTION OF ABOVE CHANGES  
(INCLUDING PLANS SHEET CHANGES)

\*\*\*\*\*BID INSERT\*\*\*\*\*

REVISED QUANTITY FOR THE FOLLOWING BID ITEM:425-6009

ADDED BID ITEM: 425-6011

\*\*\*\*\*PLAN SHEETS\*\*\*\*\*

SHEET 5&5A (ESTIMATE AND QUANTITY SHEET): REVISED QUANTITY FOR 425-6009  
ADDED ITEM 425-6011



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0913-09-119

DISTRICT Yoakum

COUNTY Wharton

HIGHWAY COUNTY ROAD 315, COUNTY ROAD 403, COUNTY ROAD 424

CONTROL SECTION JOB				0913-09-119		0913-09-121		0913-09-122		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00194199		A00194206		A00194209			
COUNTY				Wharton		Wharton		Wharton			
HIGHWAY				COUNTY ROAD 424		COUNTY ROAD 403		COUNTY ROAD 315			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	100-6002	PREPARING ROW	STA	3.580		3.860		4.080		11.520	
	110-6001	EXCAVATION (ROADWAY)	CY	408.000		259.000		394.000		1,061.000	
	110-6002	EXCAVATION (CHANNEL)	CY	98.000		176.000		570.000		844.000	
	132-6005	EMBANKMENT (FINAL)(ORD COMP)(TY C)	CY	50.000		437.000		204.000		691.000	
	150-6002	BLADING	HR	8.000		8.000		8.000		24.000	
	164-6003	BROADCAST SEED (PERM) (RURAL) (CLAY)	SY	991.000		933.000		1,166.000		3,090.000	
	164-6009	BROADCAST SEED (TEMP) (WARM)	SY	249.000		234.000		293.000		776.000	
	164-6011	BROADCAST SEED (TEMP) (COOL)	SY	249.000		234.000		293.000		776.000	
	168-6001	VEGETATIVE WATERING	MG	8.400		7.900		9.900		26.200	
	247-6370	FL BS (CMP IN PLC)(TY E GR 5)(FNL POS)	CY	361.000		291.000		288.000		940.000	
	316-6029	ASPH (RC-250)	GAL	246.000		249.000		246.000		741.000	
	316-6202	AGGR(TY-E GR-5 SAC-B)	CY	10.000		10.000		10.000		30.000	
	316-6249	AGGR(TY-PE GR-4 SAC-B)	CY	10.000		10.000		10.000		30.000	
	316-6542	ASPH (AC 20-5TR OR AC-20XP OR CRS-2P)	GAL	419.000		422.000		418.000		1,259.000	
	400-6005	CEM STABIL BKFL	CY	38.000		38.000		38.000		114.000	
	402-6001	TRENCH EXCAVATION PROTECTION	LF			4.000				4.000	
	416-6002	DRILL SHAFT (24 IN)	LF	189.000		273.000		318.000		780.000	
	420-6013	CL C CONC (ABUT)	CY	25.000		25.300		25.300		75.600	
	420-6029	CL C CONC (CAP)	CY			8.300		8.300		16.600	
	420-6037	CL C CONC (COLUMN)	CY			2.800		2.800		5.600	
	422-6001	REINF CONC SLAB	SF	1,285.000		2,088.000		2,891.000		6,264.000	
	425-6009	PRESTR CONC SLAB BEAM (4SB12)	LF	315.860		496.930				812.790	⚠
	425-6011	PRESTR CONC SLAB BEAM (4SB15)	LF					711.860		711.860	⚠
	432-6033	RIPRAP (STONE PROTECTION)(18 IN)	CY	171.000		340.000		719.000		1,230.000	
	450-6006	RAIL (TY T223)	LF	104.000		154.000		204.000		462.000	
	454-6004	ARMOR JOINT (SEALED)	LF	58.000		58.000		58.000		174.000	
	464-6005	RC PIPE (CL III)(24 IN)	LF			342.000				342.000	
	467-6395	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA			2.000				2.000	
	496-6009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000		1.000		1.000		3.000	
	500-6001	MOBILIZATION	LS	1.000						1.000	
	502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4.000		6.000		6.000		16.000	
	506-6038	TEMP SEDMT CONT FENCE (INSTALL)	LF	791.000		623.000		569.000		1,983.000	
	506-6039	TEMP SEDMT CONT FENCE (REMOVE)	LF	791.000		623.000		569.000		1,983.000	
	530-6006	DRIVEWAYS (SURF TREAT)	SY					59.000		59.000	
	540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	100.000		100.000		75.000		275.000	
	540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	4.000		4.000		3.000		11.000	
	544-6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000		3.000		11.000	

REVISION 07/22/2024

DISTRICT	COUNTY	CCSJ	SHEET
Yoakum	Wharton	0913-09-119, Etc.	5



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0913-09-119

DISTRICT Yoakum

COUNTY Wharton

HIGHWAY COUNTY ROAD 315, COUNTY ROAD 403, COUNTY ROAD 424

CONTROL SECTION JOB				0913-09-119		0913-09-121		0913-09-122		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00194199		A00194206		A00194209			
COUNTY				Wharton		Wharton		Wharton			
HIGHWAY				COUNTY ROAD 424		COUNTY ROAD 403		COUNTY ROAD 315			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	545-6006	CRASH CUSH ATTEN (INSTL)(L)(N)(TL2)	EA					1.000		1.000	
	658-6014	INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BI)	EA	2.000		2.000		3.000		7.000	
	658-6062	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	4.000		4.000		3.000		11.000	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000						1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PARTICIPATING)	LS	1.000							1.000

REVISION 07/22/2024



DISTRICT	COUNTY	CCSJ	SHEET
Yoakum	Wharton	0913-09-119, Etc.	5A