

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: BR 2B24(487)

CONTROL: 2279-02-023

COUNTY: CROCKETT

LETTING: 09/05/2024

REFERENCE NO: 0828

PROPOSAL ADDENDUMS

X PROPOSAL COVER

X BID INSERTS (SH. NO.: 3

_ GENERAL NOTES (SH. NO.:

_ SPEC LIST (SH. NO.:

_ SPECIAL PROVISIONS:

ADDED:

DELETED:

_ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: PLAN SHEETS AND OTHER CHANGES

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

***** PROPOSAL COVER *****

REVISED CONTRACT TO 298 WORKING DAYS

***** BID INSERTS *****

BID INSERT PROPOSAL SHEET 3 AND E&Q PLAN SHEET 5 ARE REPLACED AS PART OF THIS ADDENDUM.

REVISED QUANTITIES FOR THE FOLLOWING BID ITEMS: 502-7001.

***** PLAN SHEETS *****

PLAN SHEET 5 (ESTIMATE & QUANTITY SHEET) -

REVISED SHEET AS DESCRIBED ABOVE IN THE BID INSERTS OF THE PROPOSAL.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 2279-02-023

DISTRICT San Angelo
HIGHWAY US 190

COUNTY Crockett

CONTROL SECTION JOB				2279-02-023		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00188549			
COUNTY				Crockett			
HIGHWAY				US 190			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	100-7002	PREPARING ROW	STA	15.700		15.700	
	100-7003	PREP ROW (TREE REMOVE) (0"-12" DIA)	EA	267.000		267.000	
	100-7004	PREP ROW (TREE REMOVE) (12"-24" DIA)	EA	46.000		46.000	
	100-7005	PREP ROW (TREE REMOVE) (24"-36" DIA)	EA	10.000		10.000	
	100-7006	PREP ROW (TREE REMOVE) (36"-48" DIA)	EA	2.000		2.000	
	104-7006	REMOV CONC (RIPRAP)	SY	782.000		782.000	
	105-7011	RMV (11"-15") TRT/UNTRT BASE & ASPH PAV	SY	4,235.000		4,235.000	
	110-7001	EXCAV (ROADWAY)	CY	7,783.000		7,783.000	
	132-7004	EMBANK (FNL)(DC)(TY B)	CY	13,877.000		13,877.000	
	164-7010	DRILL SEED (PERM_RURAL_CLAY)	SY	3,978.000		3,978.000	
	164-7015	DRILL SEED (TEMP_WARM_COOL)	SY	3,978.000		3,978.000	
	169-7002	SOIL RET BLKT(SL_MOD_CLAY_LONG)	SY	1,750.000		1,750.000	
	247-7176	FL BS (CMP IN PLC)(TYA GR1-2)(FNAL POS)	CY	2,096.000		2,096.000	
	310-7004	PRIME COAT (MC-30)	GAL	1,077.000		1,077.000	
	316-7007	ASPH (AC-20-5TR)	GAL	4,366.000		4,366.000	
	316-7208	AGGR (TY-PB, GR-3)(SAC-B)	CY	49.000		49.000	
	316-7211	AGGR (TY-PB, GR-4)(SAC-B)	CY	42.000		42.000	
	400-7010	CEM STABIL BKFL	CY	126.000		126.000	
	403-7001	TEMPORARY SPL SHORING	SF	132.000		132.000	
	416-7006	DRILL SHAFT (36 IN)	LF	1,070.000		1,070.000	
	420-7012	CL C CONC (ABUT)	CY	57.200		57.200	
	420-7022	CL C CONC (CAP)	CY	85.700		85.700	
	420-7038	CL C CONC (COLUMN)	CY	65.600		65.600	
	422-7001	REINF CONC SLAB	SF	19,741.000		19,741.000	
	422-7013	APPROACH SLAB	CY	72.200		72.200	
	425-7003	PRESTR CONC GIRDER (TX40)	LF	2,704.000		2,704.000	
	432-7013	RIPRAP (MOW STRIP)(4 IN)	CY	92.000		92.000	
	432-7030	RIPRAP (STONE COMMON)(DRY)(8 IN)	CY	2,836.000		2,836.000	
	432-7043	RIPRAP (STONE PROTECTION)(18 IN)	CY	958.000		958.000	
	450-7024	RAIL (TY SSTR)	LF	880.000		880.000	
	454-7004	SEALED EXPANSION JOINT (4 IN) (SEJ - M)	LF	141.000		141.000	
	496-7010	REMOV STR (BRIDGE 100 - 499 FT LENGTH)	EA	1.000		1.000	
	500-7001	MOBILIZATION	LS	1.000		1.000	
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	17.000		17.000	1
	503-7002	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2.000		2.000	
	505-7002	TMA (MOBILE OPERATION)	HR	40.000		40.000	
	506-7020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	156.000		156.000	

1

1 REVISED 08/28/24