


INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2A - 2C	SPECIFICATION DATA AND GENERAL NOTES
3	ESTIMATE AND QUANTITY SUMMARY
4 - 9	UPGRADE SUMMARY
10 - 21	BCH/2/2/2/2/2/2
22	BCD-14
23	BCD2B-19
24 - 29	D&OMI-6A-20
30	D&OMI/A-20
31	CASSTL-14-4
32	GBL/RTL-14-4
33	GBL/3/10/AT-19
34	GF/3/1-19
35	IBGF-19
36	IBGFSR-19
37	IBGFTTR-19
38	OGELTE/MO(M)-20
39	RAIL-ADVA-19
40	RAIL-ADVB-19
41	SG/10S/3-16
42	SG/11S/3-16
43	SG/12S/3-16
44	SG/13S/3-20
45	TCR-1-16
46	TCR-3-18
47	TCR-4-18
48	TCR-5-18
49	TCR-6-18
50	TCR-7-18
51	TCR-8-18
52	TCR-9-18
53	TCR-10-18
54	TCR-11-18
55	TCR-12-18
56	TCR-13-18
57	TCR-14-18
58	TCR-15-18
59	TCR-16-18
60	TCR-17-18
61	TCR-18-18

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION
PLANS OF PROPOSED
ROUTINE MAINTENANCE CONTRACT

TYPE OF WORK:
ON-CALL GUARDRAIL & CABLE BARRIER INSTALLATION, UPGRADE, REPLACEMENT AND REPAIR
PROJECT NO.: RMC 646981001
CS-J-6469-81-001
HIGHWAY: VARIOUS
LIMITS OF WORK: PLAINVIEW AREA



PLAINVIEW AREA

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE
HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE
SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



Michael P. Stroop, P.E.
Date

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF
TRANSPORTATION SHALL GOVERN OVER ANY
LISTED AND DATED AS FOLLOWS SHALL GOVERN ON THIS
PROJECT.

© 2024 Texas Department of Transportation	
PROJECT NO.	SHEET NO.
RMC 646981001	646981001
STATE	DIST.
TEXAS	103
COUNTY	FILE NAME
SWISHER	646981001
CITY	DATE
	8/29/2024



SUBMITTED FOR LETTING: 8/29/2024
DocuSigned by: Michael Stroop, P.E.
COC6960262CADD

RECOMMENDED FOR LETTING: 8/29/2024
DocuSigned by: Heath C. Boyman, P.E.
A840CC12E64CE3

APPROVED FOR LETTING: 8/29/2024
DocuSigned by: Michael Stroop, P.E.
COC6960262CADD

NO SCALE
NO EQUATIONS
NO EXCEPTIONS
NO RAILROAD CROSSINGS

© 2024 Texas Department of Transportation
all rights reserved.

RMC 646981001

Project Number: RMC 646981001

County: Hale, Etc.

Highway: Various

GENERAL NOTES:

Contractor questions on this project are to be addressed to the following individual(s):

Michael P. Stroope, P.E. – mike.stroope@txdot.gov

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address: <https://tableau.txdot.gov/views/ProtectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

General Requirements and Covenants - Items 1 thru 9

Project Description – This project consists of On-Call guardrail installation, upgrade, replacement and/or repair and median cable barrier repair for the Plainview Area Office consisting of Castro, Swisher, Hale, Floyd and Crosby Counties. Items and quantities shown on E&Q sheet are for bidding purposes only. Engineer may overrun or underrun items as needed to complete required work.

Plainview Area Engineer

Heath Bozeman, P.E.
3900 S B LP IH 27
Plainview, TX 79072
PH (806) 293-5484

Castro County Maintenance Supervisor

German Vasquez
1544 S US 385
Dimmitt, TX 79027
PH (806) 647-3361

Swisher County Maintenance Supervisor

Chris Wadlow
7500 E SH 86
Tulua, TX 79088
PH (806) 995-3009

General Notes

Sheet A

General Notes

Sheet B

Project Number: RMC 646981001

County: Hale, Etc.

Highway: Various

Hale County Maintenance Supervisor

Ruben Ramirez
3900 S B LP IH 27
Plainview, TX 79072
PH (806) 293-5101

Floyd County Maintenance Supervisor

Adolfo Chavarria
708 N 2nd
Floydada, TX 79235
PH (806) 983-3320

Crosby County Maintenance Supervisor

Ben Kautz
100 Avenue E
Ralls, TX 79357
PH (806) 253-2575

Designate in writing the "On the Job Superintendent" authorized to act on behalf of the Contractor. Perform contract work only when the "On the Job Superintendent" is on the job site.

This contract is a work order contract. The Engineer will notify the Contractor through a written work order on approximate quantities of damaged guard fence or end treatments.

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Notify the responsible TxDOT office by telephone by 9:00 A.M. each morning that work is scheduled. Provide work location and time of arrival or reason for not working that day.

Restore surrounding site features which are damaged during construction operations to a condition as good as or better than that which previously existed. This work is at the Contractor's expense.

Minimize vehicles and equipment in construction areas to lessen the impact on existing vegetation. The intent of the plans is to prepare only that portion of the right-of-way necessary for construction. Excess damage to the vegetation in the right-of-way will be repaired at the Contractor's expense as directed.

Provide materials from approved sources.

Project Number: RMC 646981001
County: Hale, Etc.
Highway: Various

Project Number: RMC 646981001
County: Hale, Etc.
Highway: Various

Sheet 2

Control: 6469-81-001

Control: 6469-81-001

Sheet 2

Item 2 – Instructions to Bidders

View the plans on-line or download from the web at:
<http://www.dot.state.tx.us/business/plansonline/agreement.htm>
Choose "I Agree" then, "Click here"; then "State-Let-Construction", pick the letting month, then "Plans" and then choose the plans set.

Order plans from any of the plan reproduction companies shown on the web at:
http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm

By signing this proposal, a bidder acknowledges that he/she has a copy of the "Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges", adopted by the Texas Department of Transportation, November 1, 2014. This specification book may be purchased from the Department or downloaded at:
<http://www.txdot.gov/business/resources/txdot-specifications.html>

Item 4 Scope of Work

If agreed upon in writing by both parties to the contract, the contract may be extended for an additional period of time not to exceed the original contract time period. The extended contract will be for the original bid quantities, terms and conditions plus any applicable change orders. This contract includes non-site specific work. Multiple concurrent work orders will be issued to procure work of the type identified in the contract at locations that have not yet been determined.

For each repair, the Engineer will determine the work to be done and specify this on the work order issued to the Contractor. This includes determining whether the guardrail and associated elements will be upgraded to current standards or not.

Provide a minimum of twenty-four (24) hour notice prior to performing work to the requesting Maintenance Section or appropriate contact person. Failure to provide prior notification may result in nonpayment of work performed.

Work orders will be classified as Emergency or Routine. Emergency work orders will be issued as needed and will take precedence over the routine work orders as determined by the Engineer.

Emergency Work Orders:

Contractor shall be available to make repairs Monday through Friday. Begin work within three (3) working days after notification. If Contractor has not begun within three (3) working days of notification the Contractor will be charged liquidated damages at the rate set forth by this contract per day until the Contractor begins work. Once the Contractor begins work on a work

order the work shall be continuously performed until the work order is completed. Liquidated damages will begin if the Contractor begins the work and leaves before the work order is completed and accepted by the Engineer.

Emergency work will be defined as:

All GET or end treatment repair or replacement
Any disconnect of steel rail element
Any other repairs not listed above as determined by the Engineer to be an emergency

Routine Work Orders:

Contractor shall be available to make repairs Monday through Friday and weekends if directed by the Engineer. Work on Routine Work Orders shall begin within seven (7) calendar days after notification. If Contractor has not begun within seven (7) days of notification the Contractor will be charged liquidated damages at the rate set forth by this contract per day until the Contractor begins work. Once the Contractor begins work on a work order the work shall be continuously performed until the work order is completed. Liquidated damages will begin if the Contractor begins the work and leaves before the work order is completed and accepted by the Engineer.

Item 7. Legal Relations and Responsibilities

Restrict storage of equipment and materials to approved areas. The Engineer will not approve storage in any TxDOT yard.

Dispose of waste generated from servicing equipment on the project properly.

Existing utilities (public, private and TxDOT) are present throughout the project. Investigate to determine the utility locations and use caution when excavating in those areas.

Item 8 Prosecution and Progress

The Engineer will provide an Authorization To Begin Work letter to begin the project charge days.

Maintain ingress and egress to side streets and private property at all times.

This project is to be completed in 365 calendar days in accordance with Section 8.3.1.5, "Calendar Day."

Do not begin work before sunrise or end work after sunset unless authorized by the Engineer, and remove all equipment from the roadway before sundown.

General Notes

General Notes

Sheet D

Sheet C

Project Number: RMC 646981001

County: Hale, Etc.

Highway: Various

Sheet 2

Control: 6469-81-001

Item 9 Measurement and Payment

Material-on-hand will not be paid on this contract.

Item 500 Mobilization

Mobilization shall be paid for as Mobilization (Callout) or Mobilization (Emergency) as designated by work order.

Item 502 - Barricades, Signs and Traffic Handling

For this project, Barricades, Signs, and Traffic Handling shall be subsidiary to the various bid items.

Furnish and install all signs, barricades and other incidentals necessary for proper traffic control in accordance with part VI of the "Texas Manual on Uniform Traffic Control Devices for Streets and Highways" and barricade and construction standard sheets. Additional signs and barricades as directed by the Engineer will be considered subsidiary to various bid items.

Metal Beam Guard Fence installation, replacement or repair operations on multilane conventional roads, divided highways or controlled access facilities and service roads shall require the closure of the adjacent shoulder and travel lane per the appropriate TCP Standard.

The use of Temporary Rumble Strips in accordance with WZ (RS)-16 shall be used for travel lane closures.

Item 540 Metal Beam Guard Fence

For this project, use composite block outs.

Use a concrete saw to cut existing riprap in order to place metal beam guard fence post(s). This work is considered subsidiary to various bid items.

Use low fill culvert posts when there is less than 44" cover over culvert slab or as directed.

Item 540 shall only be used for the installation of new MBGF or the upgrade of undamaged MBGF.

Item 542 Removing Metal Beam Guard Fence

Items are to be used for the removal of MBGF at the direction of the Engineer that is no longer required or for undamaged MBGF that is being upgraded.

General Notes

Sheet E

Project Number: RMC 646981001

County: Hale, Etc.

Highway: Various

Sheet 2

Control: 6469-81-001

All materials removed become the property of the Contractor. Remove the materials from the project site.

Item 544 Guardrail End Treatments

Reusing parts of damaged GET's will not be allowed, and the damaged GET will be completely removed and replaced with a new unit.

All materials removed become the property of the Contractor. Remove the materials from the project site.

Item 658 Delineator and Object Marker Assemblies

All new installations and repairs will require GF2 post mounted reflectors to be installed in accordance with D&OM standard sheets. Removal of existing GF1 reflectors shall be subsidiary to the installation of new GF2 reflectors.

Item 770 Guard Fence Repair

When repairing damaged metal beam guard fence, post material used will be of the same material that exists at that location. Mixing of steel and wooden posts will not be allowed.

Item 771 Repair Cable Barrier System

The Contractor shall repair/replace cable barrier system components that match existing manufacturer and place in accordance with manufacture recommendations.

The Contractor shall provide a tension meter and use it to verify that repaired or replaced cables are properly tensioned per manufacture specifications. Re-tension the cable(s) when needed. This work will be considered subsidiary to the various bid items.

Item 771-7018 "Check/Re-Tension Cable" shall only be utilized and paid when no other cable barrier repair is required.

For posts not being replaced, straightening of the posts, new spacers and re-threading the cable will be considered subsidiary to the various bid items.

Reflector caps or spacers shall be replaced where required per the manufacturer specifications. Placement of these reflectors shall be considered subsidiary to various bid items.

General Notes

Sheet F

Project Number: RMC 646981001

Control: 6469-81-001

County: Hale, Etc.

Highway: Various

County	Control Section	Hwy	Limits		System	Type
Hale	0067-04	IH 27	Swisher CL	Plainview	Gibraltar	TL-4
	0067-05	IH 27	Hale Center	Plainview	Trinity	TL-4
	0067-06	IH 27	Lubbock CL	Hale Center	Trinity	TL-4
Floyd	0145-05**	US 70	Plainview	Floyd CL	Gibraltar	TL-4
	0145-06**	US 70	Hale CL	Floydada	Gibraltar	TL-4
	0145-07**	US 62	Floydada	FM 651	Gibraltar	TL-4
Crosby	0131-02/03**	US 62/82	FM 789 (LBB County)	CR 179	Gibraltar	TL-4
	0131-04**	US 82	CR 179	FM 2591	Gibraltar	TL-4
	0131-05**	US 82	FM 2591	Dickens CL	Gibraltar	TL-4
Swisher	0067-02	IH 27	Tulia	Randall CL	Gibraltar	TL-4
	0067-03	IH 27	Hale CL	Tulia	Gibraltar	TL-4

** Cable Barrier to be installed on future projects.

ESTIMATE SUMMARY

PROJECT NUMBER RMC 64698 1001 CSJ 6469-81-001																
EST.		FINAL		EST.		FINAL		EST.		FINAL		DESCRIPTION ALL BID ITEMS				
												EST.	FINAL			
EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	ITEM CODE	DESCRIPTION			
												UNIT	TOTAL			
												104	7006	REMOVING CONC (RIPRAP)	SY	34.000
												134	7006	BACKFILL (TYA/VEH)	CY	78.000
												432	7009	RIPRAP (CONC)(CL B)(6")	LF	12.000
												500	7002	MOBILIZATION (CALLOUT)	EA	12.000
												500	7033	MOBILIZATION (EMERGENCY)	EA	12.000
												505	7001	TMA (STATIONARY)	DAY	200.000
												540	7002	MTL W-BEAM GD FEN (STEEL POST)	LF	50000.000
												540	7005	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	115.000
												540	7006	MTL BEAM GD FEN TRANS (TL-2)	EA	4.000
												540	7015	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	50.000
												540	7016	MTL BM GD FEN TRANS (NON-SYM)	EA	14.000
												540	7018	MTL W-BEAM GD FEN (LOW FILL CULVERT)	LF	50.000
												540	7028	MTL BM GD FEN TRANS (31"-28")	EA	20.000
												540	7029	MTL BM GD FEN TRANS (ANCHOR PLATE)	EA	30.000
												540	7038	MTL W-BEAM GD FEN (NESTED)(STEEL POST)	LF	75.000
												540	7039	TL-3 31" SHORT RADIUS (COMPLETE)	EA	4.000
												540	7040	MBGF (W-BEAM)(MED BAR)	LF	1425.000
												542	7001	REMOVE METAL BEAM GUARD FENCE	LF	50000.000
												542	7002	REMOVE TERMINAL ANCHOR SECTION	EA	60.000
												542	7004	RM MTL BM GD FENCE TRANS (THRIE-BEAM)	EA	2.000
												544	7001	GUARDRAIL END TREATMENT (INSTALL)	EA	250.000
												544	7002	GUARDRAIL END TREATMENT (MOVE & RESET)	EA	25.000
												544	7003	GUARDRAIL END TREATMENT (REMOVE)	EA	250.000
												545	7004	CRASH CUSH ATTN (REMOVE)	EA	2.000
												545	7006	CRASH CUSH ATTEN (INSTL)(N)(TL3)	EA	2.000
												658	7018	INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2	EA	450.000
												658	7019	INSTL DEL ASSM (D-SW) SZ 1 (BRF) GF2 (BI)	EA	600.000
												658	7036	INSTL DEL ASSM (D-SY) SZ 1 (BRF) GF2	EA	300.000
												658	7037	INSTL DEL ASSM (D-SY) SZ 1 (BRF) GF2 (BI)	EA	100.000
												770	7001	REPLACE RAIL ELEMENT (W-BEAM)	LF	2000.000
												770	7006	REPLACE TIMBER POST W/O CONC FND	EA	250.000
												770	7007	REPLACE STEEL POST W/O CONC FND	EA	250.000
												770	7008	REPLACE TIMBER POST W/ CONC FND	EA	250.000
												770	7009	REPLACE STEEL POST W/ CONC FND	EA	250.000
												770	7010	REALIGN POSTS	EA	100.000
												770	7018	REPLACE BLOCKOUT	EA	100.000
												770	7019	REPAIR STEEL POST WITH BASE PLATE	EA	10.000
												770	7020	RESET SGT IMPACT HEAD	EA	10.000
												770	7021	REPLACE SGT OBJECT MARKER	EA	10.000
												771	7005	REPLACE POSTS (TL-4) (GILBRAL TAR)	EA	50.000
												771	7007	REPLACE POSTS (TL-4) (TRINITY)	EA	50.000
												771	7010	CABLE SPLICE / TURNBUCKLE (TL-4)	EA	5.000
												771	7012	REPAIR CONCRETE FOUNDATION (TL-4)	EA	5.000
												771	7014	REPR OR REPLC CABLE BARR TERM SEC (TL-4)	EA	5.000
												771	7016	REPLACE CABLE (TL-4)	LF	1000.000
												771	7018	CHECK/FIRE-TENSION CABLE	EA	25.000
												771	7020	REPLACE POST HARDWARE (TL-4)	EA	25.000

ESTIMATE & QUANTITY SHEET

STATE DIST. NO. 5	COUNTY HALE
PROJECT NO. RMC 6469-81-001	SHEET NO. 3

ROADWAY	REMOVING CONC (BR/SP)	134-7006	432-7009	540-7002	540-7005	540-7006	540-7008	540-7015	540-7016	540-7018	540-7019	540-7020	542-7002	542-7004	544-7001	544-7002	544-7003	545-7004	545-7006	688-7018	688-7019	688-7036			
		REINFORCING (Y/A) (USA)	RRAP (CONC) (LB) (G) (FEM) (STEEL) (POST)	MTL W-BEAM (THREE BEAM) (TUB)	MTL BEAM (G) (FEM) (STEEL) (THREE BEAM) (TUB)	MTL BEAM (G) (FEM) (STEEL) (THREE BEAM) (TUB)	TL 3 31" (COMPLETE) (RADIUS)	DOWNSTREA (FOR FEMINOR SECTION)	MTL W-BEAM (G) (FEM) (STEEL) (NON-STR)	MTL W-BEAM (G) (FEM) (STEEL) (LOW RILL CLOSURE)	MTL W-BEAM (G) (FEM) (STEEL) (NON-STR) (PLATE)	MTL W-BEAM (G) (FEM) (STEEL) (POST)	REMOVE METAL BEAM GUARD FENCE	REMOVE METAL BEAM GUARD FENCE	GUARDRAIL TREATMENT (INSTALL)	GUARDRAIL TREATMENT (REMOVE & RESET)	GUARDRAIL TREATMENT (REMOVE)	CRASH CURB ATTN (INSTALL) (REMOVE)	CRASH CURB ATTN (INSTALL) (REMOVE)	ASPH (L-SW) (S-L) (BR/SP) (S-L) (BR/SP)	INSTL DEL BI	INSTL DEL BI	INSTL DEL ASSM (D-SY) (S-L) (BR/SP)		
		SY	CY	CY	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA			
IH 27 - Parking Garage South of 141st Loop	IB Lamp	20.6																							
IH 27 at 141st	IB Main Lanes - Upstream	20.9																							
IH 27 at Main St	IB Main Lanes - Downstream	21.5																							
IH 27 at Loop 369	IB Main Lanes - Upstream	23.1																							
IH 27 at FM 54	IB Main Lanes - Downstream	24.8																							
IH 27 at CR 275	IB Main Lanes - Upstream	27.8																							
CR 275 Overpass	IB Main Lanes - Downstream	31.8																							
IH 27 at FM 137 - South	IB Main Lanes - Upstream	32.8																							
FM 137 - South Overpass	IB Main Lanes - Downstream	33.8																							
IH 27 at FM 137 - North	IB Main Lanes - Upstream	34.8																							
FM 137 - North Overpass	IB Main Lanes - Downstream	35.8																							
Sheet Totals		0	0	2	9750	25	0	0	11	5	25	0	0	0	975	10900	16	1	1	35	9	36	58	93	79



Designed by:
 Heath C. Rozeaman, P.E.
 8/29/2024

Date

UPGRADE SUMMARY
 Hale County - Abernathy
 Texas Department of Transportation

© 2024

REF. NO. DIV. NO.	MAINTENANCE PROJECT NO.	SHEET NO.
5	RMC 646981001	4
STATE	DISTRICT	COUNTY
TEXAS	LBB	HALE
CONTROL	SECTION	JOB
6469	81	001
		HIGHWAY NO.
		IHO027

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects about, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety hardware (MASH).


THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS



**BARRICADE AND CONSTRUCTION
GENERAL NOTES
AND REQUIREMENTS**

FILE	BC-21.dgn	DATE	November 2002	PROJECT	449	SECTION	01	SHEET NO.	10
TxDOT	4-03	7-15-03	01	001	001	001	001	001	001
	9-07	8-14							
	5-10	5-21							


TYPICAL LOCATION OF CROSSROAD SIGNS



May be mounted on back of "ROAD WORK AHEAD" (CW20-10) sign with approval of Engineer.

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-10) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" "ROAD WORK AHEAD" (CW20-10) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Roadway Signs" sign design manual for details. The Engineer may also use the advance warning signs on low volume roads (see Note 5 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Roadway Signs" sign design manual for details. The Engineer may also use the advance warning signs on low volume roads (see Note 5 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Roadway Signs" sign design manual for details.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Plans. The "ROAD WORK NEXT X MILES" (G20-10) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
4. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
5. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.


T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION


1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger, and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricade for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" (left arrow G20-10T) and "ROAD WORK NEXT X MILES" (right arrow G20-10T) signs shall be replaced by the detour signing called for in the plans.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between multiple work areas, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-10) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TSP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING

SIZE		SPACING	
Sign Number or Series	Conventional Road	Expressway/Freeway	Posted Speed Spacing X
CW20-4			Feet (Approx.)
CW21	48" x 48"	48" x 48"	30 120
CW22			35 160
CW25			40 240
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	45 320
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	55 500 ²
			65 700 ²
			70 800 ²
			75 900 ²
			80 1000 ²
			* * * 3

* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TSP Standard Sheets.

△ Minimum distances from work area to first advance warning sign nearest the work area and/or distance between each additional sign.


GENERAL NOTES

1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-10) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix for the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

LEGEND

—	Type 3 Barricade
○ ○ ○ ○	Channelizing Devices
⬇	Sign
X	See Typical Construction Warning Sign Size and Spacing for the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21

FILE: BC-21.dgn	REV: 11/01/02	DATE: 11/01/02	BY: JLD
PROJECT: 9-07	REVISION: 8-14	COUNTY: BELL	PROJECT NO: 11
DATE: 9-07	BY: JLD	COUNTY: BELL	SHEET NO: 11

NOTES

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) signs for each specific project. This distance shall replace the "X" and shall be rounded to the nearest 5 feet. No decimals shall be used.

The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2B1) shall be used as shown on the sample layout when advance warning signs are placed in advance of the work zone. The motorist of entering or leaving a part of the work zone the lying outside the CSJ limits where traffic fines may double if workers are present.

CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.


Area for placement of "ROAD WORK AHEAD" (CW20-10) signs and other signs or devices as called for on the Traffic Control Plan.

Contractor will install a regulatory speed limit sign at the end of the work zone.

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS
 This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

LONG/INTERMEDIATE TERM Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:
 a) rough road or damaged pavement surface
 b) substantial alteration of roadway geometrics (diversions)
 c) construction detours
 d) grade
 e) width
 f) other conditions readily apparent to the driver
 As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.
 Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered.
 (See Removing or Covering on BC(4)).

GENERAL NOTES

1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
4. Frequency of work zone speed limit signs should be:
 40 mph and greater 0.2 to 2 miles
 35 mph and less 0.2 to 1 mile
5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5p) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
8. Techniques that may help reduce traffic speeds include but are not limited to:
 A. Law enforcement.
 B. Flagger stationed next to sign.
 C. Portable changeable message sign (PCMS).
 D. Low-power (anemol) radar transmitter.
 E. Speed monitor trailers or signs.
9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.


Texas Department of Transportation

BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC (3) - 21

FILE#	DC-21.dgn	DR#	TxDOT	CR#	TxDOT	DR#	TxDOT	CR#	TxDOT
DATE	November 2002	COM#	8449	SECT	001	JOB	001	DIST	001
REVISIONS	9-07	BY	8-5	DATE	7-13	COUNTY		MILE	12

TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



ATTACHMENT FOR SIGN SUPPORTS




CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of cultural information. Drivers proceeding through a work zone need the same, if not better, route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the IS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- When signs are relocated on a project, they shall be attached to a sturdy base such as the SMO Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMO Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC Standard sheets, TLR Standard sheets or the CAZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMO Standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 500.

STOP/SLOW PADDLES

- STOP/SLOW paddles use the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles may be retroreflected when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6" to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 61.03 Hand Signaling Devices in the MUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)	
USAGE	SION FACE MATERIAL
BACKGROUND	RED
BACKGROUND	TYPE B OR C SHEETING
LEGEND & BORDER	TYPE B ₁ OR C ₁ SHEETING
LEGEND & BORDER	BLACK
LEGEND & BORDER	ACRYLIC NON-REFLECTIVE FILM

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Signs shall be installed in accordance with the plans.
- All signs shall be installed in accordance with the plans.
- The Contractor may require the Contractor to furnish other work zone signs that are shown in the MUTCD but may have been omitted from the plans. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's T400T diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CAZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) Standard Sheets. The Contractor shall install the sign supports in accordance with the manufacturer's recommendations. If there is a question as to the correct procedure, the Contractor shall consult with the Engineer. Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used on the back of the sign shall not exceed 10% of the sign height.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK LOS DEFINED BY THE "Texas Manual on Uniform Traffic Control Devices" (Part 6)

- The types of work loss defined by the "Texas Manual on Uniform Traffic Control Devices" (Part 6) are based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crush-resistance and duration of work requirements.
- Long-term stationary - work that occupies a location more than 3 days.
- Intermediate-term stationary - work that occupies a location more than one day/night period up to 3 days, or nighttime work lasting more than 3 days.
- Short-term stationary - work that occupies a location for more than 1 hour in a single daylight period.
- Mobile - work that moves continuously or intermittently stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-Term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except where applicable. Signs mounted below these heights shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- The bottom of Short-Term/Stationary signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-Term/Intermediate-term signs may be used in lieu of Short-Term/Stationary signs during daylight and shall be removed at the end of the workday or rolled to the appropriate Long-Term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CAZTCD lists each substrate that can be used on the different types and models of sign supports.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleats, 1/2" thick by 6" wide, spaced at 24" intervals along the length of the sign panels. The cleats shall be placed on both sides of the splice and spaced at 6 inches from the ends of the sign panels.
- Sign supports shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B₁ or Type C₁, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- Sign letters shall be clear and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and shall be the "Standard Sign" type as specified in the Standard Manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Bur-lap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and/or other studs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- Where sign supports require the use of weights to keep from turning over, the use of weights shall be in accordance with the following:
 - The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
 - Rock, concrete, iron, steel or other solid objects shall not be permitted.
 - Sandbags shall weigh a minimum of 35 lbs and a maximum of 50 lbs.
 - Sandbags should be made of a durable material that tears upon vehicular impact. Rubber (such as fire inner tubes) shall NOT be used.
 - Sign supports shall be placed on a level surface. The sign supports shall be placed on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CAZTCD list.
 - Sandbags shall only be placed along or laid over the base supports of the sign. They shall not be placed along or laid over the base supports of the sign along with wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
 - Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on a slope.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent orange-red in color. A flag shall not be used to cover any portion of the sign face.




Texas Department of Transportation

BARRICADE AND CONSTRUCTION

TEMPORARY SIGN NOTES

BC (4) - 21




FILE#	BC-21-091	REV#	001	DATE	07-13-01
PROJECT	November 2002	REVISION#	001	DATE	7-13-01
COUNTY	001	DIST	001	SHEET NO.	13
DATE		SHEET NO.		13	



SKID MOUNTED WOOD SIGN SUPPORTS


* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

Refer to the CWZTCO and the manufacturer's installation procedure for each type sign support.
The maximum sign square footage shall adhere to the manufacturer's recommendation.
Two post installations can be used for larger signs.



PERFORMED SQUARE METAL TUBING

WING CHANNEL



WEDGE ANCHORS

Both steel and plastic anchors, as shown on the SMO Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils. They are to be used in accordance with the manufacturer's instructions for "Traffic Engineering Standard Sheets" on BC(11).

OTHER DESIGNS

MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCO LIST. SEE BC(1) FOR WEBSITE LOCATION.

GENERAL NOTES

- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a CWZTCO List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCO for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT





BC (5) - 21

FILE#	DC-21.dgn	DR#	TxDOT	CR#	TxDOT	DR#	TxDOT
DATE	NOVEMBER 2002	DATE	NOVEMBER 2002	DATE	NOVEMBER 2002	DATE	NOVEMBER 2002
BY	9-07	BY	8-14	BY	8-14	BY	8-14
CHECKED	7-13	CHECKED	5-21	CHECKED	5-21	CHECKED	5-21
SCALE		SCALE		SCALE		SCALE	
SHEET NO.	14	SHEET NO.	14	SHEET NO.	14	SHEET NO.	14

SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

Refer to the CWZTCO and the manufacturer's installation procedure for each type sign support.
The maximum sign square footage shall adhere to the manufacturer's recommendation.
Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purposes whatsoever. TxDOT assumes no responsibility for the consequences of this standard to other formats or for incorrect results or damages resulting from its use.

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS). No more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by the driver.
- Use the word "EXIT" to refer to an exit ramp on a freeway, i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 1 foot above the roadway, where possible.
- Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed in a separate message or included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message, i.e., keeping two lines of the message the same and changing the third line. Do not use the word "DANGER" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be used. PCMS character height should be at least 18 inches for trailer-mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck-mounted units must have a character height of 10 inches or more. Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS is inoperative. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List	Other Condition List	Action to Take/Effect on Travel List	Location List	Warning List	** Advance Notice List
FREWAY CLOSED X MILE	ROADWORK XXX FT	MERGE RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM-X PM
ROAD CLOSED	FLAGGER XXXX FT	DETOUR NEXT X EXITS	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX-XX PM-X AM
ROAD CLOSED AT SH XXX	RIGHT LN NARROWS XXXX FT	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
ROAD CLOSED	MERGING TRAFFIC XXXX FT	STAY ON US XXX SOUTH	PAST X MILES	ADVISORY XX MPH	BEGINS MAY XX
LANES CLOSED	LOOSE LANE GRAVEL XXXX FT	TRUCKS FOR TRUCKS	XXXXXX TO XXXXX	RIGHT LANE EXIT	MAY X-X XX PM-X AM
NIGHT LANE CLOSED	DETOUR X MILE	WATCH FOR DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
VARIOUS LANES CLOSED	ROADWORK PAST SH XXXX	EXPECT DELAYS	XXXXXX TO XXXXX	DRIVE SAFELY	XX AM TO XX PM
EXIT CLOSED	RIGHT LN TO BE CLOSED	REDUCE SPEED XXX FT	US XXX TO FM XXXX	DRIVE WITH CARE	NEXT TUE AUG XX
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	USE OTHER ROUTES	XXXXXX TO XXXXX	TONIGHT XX PM-XX AM	
XXXXXXX BLVD CLOSED		STAY IN LANE			

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

** See Application Guide Lines Note 6.

Phase 2: Possible Component Lists

Road/Lane/Ramp Closure List	Other Condition List	Action to Take/Effect on Travel List	Location List	Warning List	** Advance Notice List
FREWAY CLOSED X MILE	ROADWORK XXX FT	MERGE RIGHT	AT FM XXXX	SPEED LIMIT XX MPH	TUE-FRI XX AM-X PM
ROAD CLOSED	FLAGGER XXXX FT	DETOUR NEXT X EXITS	BEFORE RAILROAD CROSSING	MAXIMUM SPEED XX MPH	APR XX-XX PM-X AM
ROAD CLOSED AT SH XXX	RIGHT LN NARROWS XXXX FT	USE EXIT I-XX NORTH	NEXT X MILES	MINIMUM SPEED XX MPH	BEGINS MONDAY
ROAD CLOSED	MERGING TRAFFIC XXXX FT	STAY ON US XXX SOUTH	PAST X MILES	ADVISORY XX MPH	BEGINS MAY XX
LANES CLOSED	LOOSE LANE GRAVEL XXXX FT	TRUCKS FOR TRUCKS	XXXXXX TO XXXXX	RIGHT LANE EXIT	MAY X-X XX PM-X AM
NIGHT LANE CLOSED	DETOUR X MILE	WATCH FOR DELAYS	US XXX TO FM XXXX	USE CAUTION	NEXT FRI-SUN
VARIOUS LANES CLOSED	ROADWORK PAST SH XXXX	EXPECT DELAYS	XXXXXX TO XXXXX	DRIVE SAFELY	XX AM TO XX PM
EXIT CLOSED	RIGHT LN TO BE CLOSED	REDUCE SPEED XXX FT	US XXX TO FM XXXX	DRIVE WITH CARE	NEXT TUE AUG XX
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	USE OTHER ROUTES	XXXXXX TO XXXXX	TONIGHT XX PM-XX AM	
XXXXXXX BLVD CLOSED		STAY IN LANE			

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

** See Application Guide Lines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice" Phase Lists.
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice" Phase Lists.
- A Location Phase is necessary only if a distance or location is not used in the first phase selected.
- When PCMS are used, they should be spaced by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate. NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- EAST and WEST can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- FIELD may be used instead of distance if necessary.
- ADVISORY may be used instead of advisory as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R. O. W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (M20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirements listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for the static sign.
- All Full Matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE#	BC-21-091	DATE	10/07	REV	1.0001
PROJECT	November 2002	DATE	10/07	REV	1.0001
REVISIONS		DATE		REV	
9-07	8-14	DATE		REV	
7-13	9-21	DATE		REV	
05	05	DATE		REV	
06	06	DATE		REV	
07	07	DATE		REV	
08	08	DATE		REV	
09	09	DATE		REV	
10	10	DATE		REV	

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. The user of this standard for any purpose other than that intended by the Texas Department of Transportation is at their own risk. No warranty of any kind is made by the Texas Department of Transportation. A pattern such as a series of horizontal solid bars is appropriate.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address.
- Color of Barrier Reflectors shall be as specified in the TxDOT. The cost of Barrier Reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)


- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in a staggered fashion on the side of the CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the CTB. CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. (BI-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in Figure 1.
- Where CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Where CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edge line being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Barrier Reflector units shall be pre-qualified and meet the color and reflectivity requirements of DMS-8600.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.

See D & OM (VIA)


LOW PROFILE CONCRETE BARRIER (LPCB)

LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zones, including those posted with speed 45 mph or less. See Standard Roadway Standard Sheet LPCB.



Max. spacing of barrier reflectors is 20 feet. Attach the reflectors as per manufacturer's recommendations.




DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZCD List for approved end treatments and manufacturers.

Arrow Boards may be located behind channelizing devices in place for a shoulder or travel lane. Arrow Boards shall be channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow lane closures, or lane closures on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the flashing arrow board.
- The Flashing Arrow Board should be able to display the following symbols:



ALTERNATING DIAMOND CAUTION

4. CORNER CAUTION

RIGHT/LEFT ARROW
(right arrow shown; left is similar)

DOUBLE ARROW

RIGHT/LEFT SEQUENTIAL CHEVRON
(right chevron shown; left is similar)

- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond display.
- The "CORNER CAUTION" display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage.
- The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- The flashing rate shall be adjustable in intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during night operations.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- The height of trailer mounted arrow boards should be 7 feet from roadway to bottom of panel.

TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD ON THE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 21

FILED	DC-21, sign	DATE	NOVEMBER 2002	PROJECT	TXDOT
REVISIONS	NOVEMBER 2002	BY	001	DESIGN	001
	9-07		7-13	COUNTY	16
	7-13		8-21	INCHES	16

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Standard Specifications for Construction Materials.
- Refer to the CWZCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- TMAs should be used on all work areas that require a work area to be spread over the roadway and the work crew is on extended distance from the TMA.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMDOT.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "EL". The Type A Warning Lights shall not be used with signs manufactured with Type B₁ or C₁ Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. The Contractor shall specify the location and type of warning lights to be installed on the traffic control devices. The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices. When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification, the warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- The maximum spacing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes, changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light if the warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it is not facing approaching traffic.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches.

DISCLAIMER: This standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device. They may be used in conjunction with plastic cones. Plastic cones shall be used in all other locations, except in the vicinity of work zones on freeways. In all other locations, one-piece cones may be used with the approval of the Engineer, but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short-term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapered, transition and tangent areas by the Engineer. One-piece cones or one-piece cones as approved by the Engineer are acceptable.
- Current and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZCDL).
- Drums, bases, and related materials shall exhibit good workmanship and affect their appearance or acceptability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS




- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design: the "body" of the drum shall be attached to the base on the bottom.
 - The body shall be a two-piece design in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
 - Plastic drums shall be constructed of lightweight flexible, and noncombustible materials. The Contractor shall NOT use metal drums or drums with metal components.
 - Drums shall be constructed of a material that is a minimum of 18 inches in diameter and shall be constructed of a material that is a minimum of 18 inches in diameter drum unit body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
 - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall be attached to the drum in such a manner that it will not allow attachment of a warning light, warning reflector unit or approved condition sign.
 - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflective area shall have a maximum width of 2 inches. Any non-reflective area shall have only two adjacent stripes shall not exceed 2 inches in length.
 - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footcandles of sufficient size to allow base to be held down while separating the drum body from the base.
 - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
 - Drum body shall have a maximum unballasted weight of 11 lbs.
 - Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B retroreflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum body. The sheeting shall be applied in such a manner that it will not generate in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs. (minimum) and 50 lbs. (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of ballast material shall not exceed 12 inches above pavement surface.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewall is acceptable for ballast on drums approved for use in the State of Texas.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall be placed in a secure base of drums.
- Adhesives may be used to secure base of drums to pavement.



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the GFD/CD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B1 or Type C1, orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended travel lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nut/bolt) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used of each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12

Texas Department of Transportation




Traffic Safety Division Standards

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21




FILE#	BC-21-sign	REV	1X00T	CHK	1X00T	DATE	1X00T
PROJECT	November 2002	CONTR	807	DESIGN	807	PROJECT	HOUSLEY
SECTION	4-03	REV	8-14	DATE	8-14	SECTION	HOUSLEY
COUNTY	9-07	DATE	5-21	DATE	5-21	COUNTY	HOUSLEY
SCALE	7-13	SCALE		SCALE		SHEET NO.	17

DISCLAIMER: This standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purposes whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE
(Rigid or self-righting)

VERTICAL PANELS (VPS)

- Opposing Traffic Lane Dividers (OTLD) are destination devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of travel. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPS.
- Spacing between the OTLD shall not exceed 500 feet. The OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective top. The OTLD's shall be retroreflective Type B₁ or Type C₁ conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

- The chevrons shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevron sets intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with the roadway centerline. The chevron set always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B₁ or Type C₁ conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapered or transitions on freeways and divided highways, plastic drums but not to replace plastic drums.

GENERAL NOTES

- Work zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUDCD).
- Channelizing devices shown on this sheet may have a drivable, fixed or portable base. The Engineer/Inspector shall specify the type of device to be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUDCD and the requirements of DMS-8300.
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs. that ensures proper bonding to the pavement surface. The Contractor shall ensure proper bonding of the adhesive, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface cracking or surface damage. The Contractor shall not be held responsible for any damage to the pavement surface. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

CHEVRONS




1. The chevrons shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevron sets intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with the roadway centerline. The chevron set always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B₁ or Type C₁ conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapered or transitions on freeways and divided highways, plastic drums but not to replace plastic drums.

GENERAL NOTES

- Work zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUDCD).
- Channelizing devices shown on this sheet may have a drivable, fixed or portable base. The Engineer/Inspector shall specify the type of device to be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUDCD and the requirements of DMS-8300.
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs. that ensures proper bonding to the pavement surface. The Contractor shall ensure proper bonding of the adhesive, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface cracking or surface damage. The Contractor shall not be held responsible for any damage to the pavement surface. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricodes placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rolls as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.



WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MSHA) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used as barriers shall be placed in accordance with delineation requirements for channelizing devices used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the TMUDCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) applications. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) applications.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long cones and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

Posted Speed	Formula	Minimum Desirable Taper Lengths x x x	Suggested Maximum Channelizing Devices
30	$L = MS^2$	10' 11" 12"	On a Taper: 30' 60'
35	$L = 60$	150' 165' 180'	30' 60'
40	$L = 60$	205' 225' 245'	35' 70'
45	$L = 60$	265' 295' 320'	40' 80'
50	$L = WS$	450' 495' 540'	45' 90'
55	$L = WS$	550' 605' 660'	55' 110'
60	$L = WS$	600' 660' 720'	60' 120'
65	$L = WS$	650' 715' 780'	65' 130'
70	$L = WS$	700' 770' 840'	70' 140'
75	$L = WS$	750' 825' 900'	75' 150'
80	$L = WS$	800' 880' 960'	80' 160'

XX Taper lengths have been rounded off.
L=Length of Taper (ft.) W=Width of Offset (ft.)
S=Posted Speed (mph)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESTRIBLE TAPER LENGTHS



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

FILED	DC-21, sign	DATE	NOV 2002	PROJECT	HOUSTON	SHEET NO.	18
PROJECT	NOVEMBER 2002	CONTRACT	6469	JOB	HOUSTON	DATE	11-13-02
DESIGNER	7-13-02	CHECKED		DATE		SCALE	

TYPE 3 BARRICADES

- Refer to the Compliant Mark Zone Traffic Control Devices List (CMZTCD) for a complete list of all materials used in the construction of Type 3 Barricades.
- Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
- Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn. Barricades should be placed in both directions from the center of the roadway. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
- Striping of rails, for the right side of the roadway, should slope downward to the right. Striping on the left side of the roadway, should slope downward to the left.
- Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
- Identification panels placed parallel to traffic unless an adequate clearance is provided.
- Warning lights shall NOT be installed on barricades. The use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to keep the sandbags from blowing away in the wind. The sandbags should be placed in a manner that covers any portion of a barricade rail's reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon impact. Sandbags shall only be placed along or upon the base of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
- Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.


Barricades shall NOT be used as a sign support.



TYPICAL STRIPING DETAIL FOR BARRICADE RAIL


Stiffener may be inside or outside of support, but no more than 2 stiffeners shall be allowed on one barricade.

TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES



TRAFFIC CONTROL FOR MATERIAL STOCKPILES

Each roadway of a divided highway shall be barricaded in the same manner.





PERSPECTIVE VIEW

The three coils on Type 3 barricades shall be reflective and orange. Reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

- Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
- Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION

PLAN VIEW



PERSPECTIVE VIEW


These drums are not required on one-way roadway.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary, minimum of 2 and maximum of 4 drums.

- Where positive redirection capability is provided, drums may be omitted.
- Plastic construction fencing may be used with drums for safety as required in the plans.
- Vertical posts or flexible support posts are not required if the shoulder width is less than 4 feet.
- When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
- Drums must extend the length of the culvert widening.


PLAN VIEW



A minimum of two drums shall be used across the work area.

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS


CONES



Two-Piece cones

28" cones shall have a minimum weight of 9 1/2 lbs. 42" 2-piece cones shall have a minimum weight of 30 lbs, including base.

One-Piece cones



Tubular Marker

- Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
- One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
- Cones shall be placed in a staggered pattern to 8' above the minimum height shown, in order to aid in retrieving the devices.
- Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed surface. The reflective bands shall be of Departmental Material Specification DMS-8300 Type A or Type B.
- 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
- 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
- Cones, tubular markers used on each project should be of the same size and shape.



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE#	DC-21, sign	DR#	TxDOT	CR#	TxDOT	EX#	TxDOT
DATE	November 2002	COM#	BCT	JOB#			
PROJECT	9-07	SECTION	649	BI	001		
DATE	7-13	DIST	05	COUNTY			
DATE	7-13	SCALE					
SHEET NO.	10						
TOTAL SHEETS	19						

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and markings in accordance with the specifications and special provisions on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the Texas Manual on Uniform Traffic Control Devices (TMUCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUCD, the plans and details as shown on the Standard Plan Sheet WZ(SPM).
- When standard pavement markings are not in place and the roadway is to be opened to traffic, the Contractor shall install and maintain PASS WITH CARE signs at the beginning of sections where passing is prohibited and is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 395.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or are otherwise not needed, shall be removed or obliterated before the roadway is opened to traffic. The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to confine the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernible marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers."
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blot cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers shall be paid for by the Contractor. The Contractor shall submit an EXISTING PAVEMENT MARKINGS AND MARKERS, unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



Height of sheeting is usually more than 1/4" and less than 1".

STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" above may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line, using a medium size passenger vehicle or pickup truck. Drive the vehicle over the tabs at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
 - Small design variances may be noted between tab manufacturers.
 - See Standard Sheet WZ(SPM) for tab placement on new pavements. See Standard Sheet TOP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or burl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS

PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(11).




BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS

BC(11)-21


FILE#	BC-21.dgn	DATE	1/2007	BY	1/2007	CHK	1/2007	APP	1/2007
PROJECT	February 1998	COM	ECT	JOB					
DESIGNER	2-98	DIST	81	COUNTY	001				
DRAWN	1-02	DIST	8-14	COUNTY	001				
CHECKED	11-02	DIST	8-14	COUNTY	001				
DATE	11-02	DIST	8-14	COUNTY	001				

PAVEMENT MARKING PATTERNS



Pattern A is the TxDOT Standard, however, Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.


CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.


EDGE & LANE LINES FOR DIVIDED HIGHWAY



REFLECTORIZED PAVEMENT MARKINGS





Prefabricated markings may be substituted for reflectorized pavement markings.

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.









EDGE & LANE LINES FOR DIVIDED HIGHWAY



RAISED PAVEMENT MARKERS

Prefabricated markings may be substituted for reflectorized pavement markings.

STANDARD WORK ZONE PAVEMENT MARKING DETAILS



Centerline only - not to be used on edge lines

SHEET 12 OF 12

Texas Department of Transportation
Traffic Safety Division Standards

BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS






BC (12) - 21

FILED	DC-21.dgn	DATE	11-02-8-14
PROJECT	1-97 9-07 3-20	DATE	11-02-8-14
CONTRACT	6409 B1	COUNTY	DADE
SECTION	001	SHEET NO.	21
DATE	11-02-8-14	SCALE	

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 'RAISED PAVEMENT MARKERS.'

DISCLAIMER
 TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.
 The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever.

- GENERAL NOTES**
- For more detail: See GF (31), SGT (31), GF (31)TR, and GF (31)TL2 standard sheets.
 - Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
 - Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
 - MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
 - Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
 - Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal. See Detail A)
 - The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is deemed to be adequate roadway. This does not apply to retrofits of existing roadway where existing roadway crown width is to be retained. (See Typical Cross Section of MBGF).
 - For restrictive bridge widths: The MBGF should be properly transitioned from the bridge to the standard rail. The MBGF should be placed on the flared end of the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
 - Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
 - A minimum 25' length of MBGF will be required.



 Texas Department of Transportation Design Division Standard	FILE: bed14.dgn	CR: AM	LINE: B0/VP	EXT: COL
	DATE: December 2011	DATE: 6/4/09	DATE: 8/1	DATE: 10/07
REVISIONS	BY: 6409	BY: 81	BY: 001	BY: 10007
	DATE: 05	DATE:	DATE:	DATE:
	COUNTY:	COUNTY:	COUNTY:	COUNTY:
	TITLE:	TITLE:	TITLE:	TITLE:
	SHEET NO.:	SHEET NO.:	SHEET NO.:	SHEET NO.:
	22	22	22	22

BRIDGE END DETAILS
 (METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)

BED-14

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS

SIZE 1	SIZE 2	SIZE 3	SIZE 4
DEVICE	DEVICE	DEVICE	DEVICE

SINGLE		DOUBLE	
1-Size 2 reflector unit	1-Size 1 reflector unit	2-Size 2 reflector units	2-Size 1 reflector units

DELINEATORS

D & OM DESCRIPTIVE CODES

INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX)

NUMBER OF REFLECTORS
 D = Double
 S = Single

COLOR OF REFLECTORS
 W = White
 Y = Yellow
 R = Red

REFLECTOR UNIT SIZE
 1 = 1-Size
 2 = 2-Size

TYPE OF POST OR DELINEATOR
 YFLX = Yellow Flexible Post
 WFLX = White Flexible Post
 SRF = Surface Mount

TYPE OF MOUNT
 GND = Embedded (drivable or set in concrete)
 CTB = Concrete Barrier Mount
 WFLX = Yellow Flexible Post
 SRF = Surface Mount

DIRECTION
 BI = Bi-Directional
 BR = Bi-Directional with red on back

INSTL OM ASSM (OM-XX)XXX (XX)

TYPE OF OBJECT MARKER
 1, 2, 3, or 4

NUMBER OF REFLECTORS OR DIRECTION
 X = 3-Size 2 reflector unit (Type 2 only)
 Y = 1-Size 2 reflector unit (Type 2 only)
 Z = 3-Size 1 or 1-Size 4 reflector unit (Type 2 only)
 R = Right Side (Type 3 Object Marker only)
 C = Center (Type 3 Object Marker only)

TYPE OF POST
 MC = Ring Channel Post
 WFLX = White Flexible Post
 TWT = Thin Walled Tubing

TYPE OF MOUNT
 GND = Embedded (drivable)
 WAS = Wedge Anchor Steel
 WAP = Wedge Anchor Plastic

DIRECTION
 BI = Bi-Directional

SHEETING Yellow, White or Red Type B or C reflective sheeting

NOTE
 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (FIX).
 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.

OBJECT MARKERS

Type 1 (OM-1)		Type 2 (OM-2)		Type 3 (OM-3)		Type 4 (OM-4)	
OM-1	OM-2X 3-Size 2 reflector units	OM-2Y 1-Size 3 reflector unit	OM-2Z 3-Size 1 reflector units or 1-Size 4 reflector unit	OM-3L 12" x 36" x 6"	OM-3R 12" x 36" x 6"	OM-3C 12" x 36" x 6"	OM-4
Yellow-Type B _{FL} or C _{FL} Sheeting	Yellow - Type B or C Sheeting	Yellow - Type B or C Sheeting	Yellow - Type B _{FL} or C _{FL} Sheeting	Alternating acrylic black and reflective yellow - Type B _{FL} or C _{FL} Sheeting	Alternating acrylic black and reflective yellow - Type B _{FL} or C _{FL} Sheeting	Red -Type B _{FL} or C _{FL} Sheeting	Red -Type B _{FL} or C _{FL} Sheeting
POST TYPE TWT WAS, WAP	WC GND	WC GND	WFLX GND, SRF	TWT WAS, WAP	TWT WAS, WAP	TWT WAS, WAP	TWT WAS, WAP

BARRIER REFLECTORS (BRP)

Type 1 (OM-1)		Type 2 (OM-2)	
GF1	GF2	GF3	GF4
DEVICE	DEVICE	DEVICE	DEVICE
1. Barrier reflectors shall meet the requirements of DMS 8600.	1. Barrier reflectors shall meet the requirements of DMS 8600.	2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.	1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.
Yellow, White, Red	Yellow, White, Red	Yellow, White, Red	Yellow, White, Red

CHEVRONS

Type 1 (OM-1)		Type 2 (OM-2)	
OM-1	OM-2	OM-3	OM-4
Yellow-Type B _{FL} or C _{FL} Sheeting	Yellow - Type B or C Sheeting	Yellow - Type B _{FL} or C _{FL} Sheeting	Yellow - Type B _{FL} or C _{FL} Sheeting
POST TYPE TWT WAS, WAP	WC GND	WFLX GND, SRF	TWT WAS, WAP

ONE DIRECTION LARGE ARROW

Type 1 (OM-1)		Type 2 (OM-2)	
OM-1	OM-2	OM-3	OM-4
Yellow-Type B _{FL} or C _{FL} Sheeting	Yellow - Type B or C Sheeting	Yellow - Type B _{FL} or C _{FL} Sheeting	Yellow - Type B _{FL} or C _{FL} Sheeting
POST TYPE TWT WAS, WAP	WC GND	WFLX GND, SRF	TWT WAS, WAP

NOTE:
 Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.

Texas Department of Transportation
 Traffic Safety Division
 Standard

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION
D & OM(1) -20

FILE: dms-20.dgn
 DATE: August 2004
 REVISIONS: 6/60 JS, 10/09 JS, 4/10 JES
 DRAWN BY: JES
 CHECKED BY: JES
 SCALE: FULL
 SHEET NO. 24

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

POST TYPE AND SUPPORT FOUNDATION DETAILS			
FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS	
WING CHANNEL (WC)	GND	SRF	WAS
<p>NOTES</p> <ol style="list-style-type: none"> Embedded Wing Channel (WC) post option may be used for delineator markers and delineators only. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499. 	<p>EMBEDDED</p>	<p>SURFACE MOUNT</p> <p>NOTES</p> <ol style="list-style-type: none"> See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. Install per manufacturer's recommendations. Post length may vary to meet field conditions. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow. 	<p>STEEL</p> <p>NOTE</p> <ol style="list-style-type: none"> Install per manufacturer's recommendations.
<p>DELINEATORS AND TYPE 2 OBJECT MARKERS</p>			
<p>NOTE</p> <p>Mounting of 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller).</p>	<p>NOTE</p> <p>Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-91) shall be installed per standard sheets and paid under item 644.</p>	<p>NOTE</p> <p>2'-0" to 8'-0" or in front of object being marked</p> <p>See general notes 1, 2 and 3.</p>	<p>DELINEATORS AND TYPE 2 OBJECT MARKERS</p>
<p>TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS</p>			
<p>CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN</p>			
<p>DELINEATORS AND TYPE 2 OBJECT MARKERS</p>			
<p>GENERAL NOTES</p> <ol style="list-style-type: none"> Place delineators on a section of roadway at a consistent distance from the edge of pavement. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane. 			
<p>CONCRETE TRAFFIC BARRIER (CTB)</p> <p>Place Barrier Reflector on top or on side(s) of CTB.</p>			
<p>TYPE OF BARRIER MOUNTS</p>			
<p>GUARD FENCE ATTACHMENT</p>		<p>GF2</p> <p>Attached to Post or Block</p>	
<p>GF1</p> <p>Centerline of MBF</p>		<p>GF2</p> <p>Attached to Post or Block</p>	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Texas Department of Transportation
 Traffic Safety Division
 Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20


FILE: 0802-20.dgn	DR: TxDOT	CR: TxDOT	DR: TxDOT	EXT: TxDOT
DATE: August 2004	COM: SECT	JOB	REV: 001	THROW: 000000
10-09 3-15	REVISIONS	16/09 SI	001	
4-10 7-20	DATE	COUNTY	DIST	SCALE

SHEET NO. **25**
 OF **25**

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS


Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed (35 MPH or more)	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	<ul style="list-style-type: none"> • RPMs 	<ul style="list-style-type: none"> • RPMs
15 MPH & 20 MPH	<ul style="list-style-type: none"> • RPMs and One Direction Large Arrow sign 	<ul style="list-style-type: none"> • RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstructions prevent the installation of chevrons.
25 MPH & more	<ul style="list-style-type: none"> • RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign, where geometric conditions or roadside obstructions prevent the installation of chevrons 	<ul style="list-style-type: none"> • RPMs and Chevrons

SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE
ONE DIRECTION LARGE ARROW (W-6) sign should be located at approximately and perpendicular to the extension of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE
At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

Degree of Curve	WHEN DEGREE OF CURVE OR RADIUS IS KNOWN		Chevron Spacing in Curve
	Radius of Curve	Spacing in Curve	
1	5730	225	450
2	2865	160	320
3	1910	130	260
4	1433	110	220
5	1146	100	200
6	955	90	180
7	819	85	170
8	716	75	150
9	637	75	150
10	573	70	140
11	521	65	130
12	478	60	120
13	441	60	120
14	409	55	110
15	382	55	110
16	358	55	110
19	302	50	100
23	249	40	80
29	198	35	70
38	151	30	60
57	101	20	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

Advisory Speed (MPH)	WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN		Chevron Spacing in Curve
	Spacing in Curve	Spacing in Straightway	
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use its delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Fwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Fwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Fwy./Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (V14) or D & OM (V14) or Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (V14) or Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (Underpass) on Freeways/Expressway	Single delineators adjacent to edge of transition length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation
Traffic Safety Division
Standard


DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM (3) - 20

FILE: dmt-20-09n
DATE: August 2004
REVISED: 8-15-05
8-15-05
COUNTY: BIST
STATE: TX


DATE: 11/11/07
SHEET NO. 26

CROSSOVERS




DETAIL 1

FOR CULVERTS WITHOUT MBGF




DETAIL 2

FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES




DETAIL 3

TYPICAL APPLICATION OF DEAD END BARRICADE



DETAIL 4

TYPICAL DEAD END BARRICADE INSTALLATION



NOTES

1. Barricade striping shall be red and white reflective sheeting for all permanent road closures.
2. Barricade striping is red and white sloping toward the center of the roadway.
3. Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Mark Zone Traffic Control Devices List, section D.2.F and D.2.G.

DETAIL 5

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Sign
	OM-2
	Double Delineator

Texas Department of Transportation
Traffic Safety Division Standard


DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(4) - 20

FILE: D&OM-20.dgn	Rev: TXDOT	Ch: TXDOT	Rev: TXDOT	Ext: TXDOT
1-15	AUGUST 2004	COM: BCT	JOB: H00000	PROJECT: H00000
3-15	REVISIONS	6/09	8/1	001
7-20		DIST: 05	COUNTY: 05	STATE: 05
				SHEET NO. 27


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**




NOTE:
1. Terminal ends require reflective sheeting as used by manufacturer of D & OM (5) -20 Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:
1. Terminal ends require reflective sheeting as used by manufacturer of D & OM (5) -20 Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND	
	Bidirectional Delimiter
	Delimiter
	OM-3
	OM-2
	Terminal End
	Traffic Flow


Texas Department of Transportation		Traffic Safety Division Standard	
DELINEATOR & OBJECT MARKER PLACEMENT DETAILS			
D & OM (5) -20			
FILE:	dm5-20.dgn	DATE:	08/14/07
PROJECT:	August 2015	DESIGNER:	081
REVISIONS:		CHECKER:	081
DATE:	7-20	DRAWN:	081
COUNTY:		SCALE:	
SHEET NO.:		TOTAL:	28

CONTINUOUS CONCRETE OR STEEL BARRIER




Equal spacing white barrier reflectors (either bidirectional on top or single direction on each side). 100' max.


MULTI-LANE UNDIVIDED, TWO-WAY ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



DIVIDED ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



EMERGENCY CROSSOVER



Texas Department of Transportation
Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM (6) - 20








FILE:	dm6-20.dgn	REV:	1x001	DATE:	1/001	BY:	1/001
PROJECT:	August 2015	REVISED:	6/10	BY:	001	DATE:	11/007
REVISIONS:	7-20	DATE:	05	BY:	001	DATE:	09

LEGEND



	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow

- NOTES**
- Equal spacing (100' max), but not less than 3 single directional white barrier reflectors or delimiters, on Continuous Barrier, equal spacing (100' max.)
 - Equal spacing (100' max), but not less than 3 single directional yellow barrier reflectors or delimiters.
 - Terminal ends require reflective sheeting provided by manufacturer per D & OM (1)A of a Type 3 Object Marker (OM-3) in front of the terminal end.



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



* Adjust to fit attenuator per manufacturer's recommendations as directed by the Engineer.




OBJECT MARKERS SMALLER THAN 3 FT²



Variable to match width of exit gore sign.

NOTES

- Spacing should be adjusted to attach through center line of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- Mounting should be flush with top of attenuator. Minimum size 96" x 24".











NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color requirements of the Manual of Uniform Traffic Control Devices (MUTCD) 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an end cap as per the manufacturer's recommendation. Direct applied sheeting shall be a smooth surface and free of wrinkles, bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

Texas Department of Transportation
DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS
D & OM (VIA) - 20

FILE:	06m1020.dgn	DR: TXDOT	CR: TXDOT	DR: TXDOT	CR: TXDOT
	12/01	December 1989	COM: SGT	JOB:	HSR027
	4-92	8-90	REVISIONS:	001	HSR027
	8-95	3-15	002	COUNTY:	
	4-98	7-20	003	DIST:	
			004	STATE:	
				SHEET NO.:	39



GENERAL NOTES

- This drawing is a general overview of CASS TL-4 Barrier System. Refer to the drawings for details on cable termination, post installation, options and specifications. CASS-TL4 system has been successfully tested with opposite installation.
- CASS is designed for bi-directional traffic flows and can be installed on either side of the median. Contact Trinity or refer to manual (S) for additional information.
- All concrete for CASS footings shall be TxDOT class A. If class A or stronger concrete is utilized for the mowstrip, please see chart below for allowable footing depth and sleeve deviations.
- All posts shall be socketed unless otherwise specified.
- All cables shall be pre-stretched unless otherwise specified.
- For payment see Special Specification "Cable Barrier System".
- CASS-TL4 shall be installed on shoulders or medians with slopes of 1:1 or greater. Slopes shall be as specified in the drawings. Grading of site and/or appropriate fill materials may be required to ensure proper installation. Inconsistencies that could interfere with the ability of the installer to consistently maintain installations in "ditch sections".
- CASS TL-4 post spacing may be modified to avoid obstacles that contact the mowstrip. The maximum post spacing shall not exceed 30'. Reducing or increasing the spacing of concrete may be required to meet this requirement. Please consult manual (S) or TxDOT Memo(s) for modifications in "ditch sections".
- Post foundations may be drilled through existing pavement. Please see the post foundation chart for minimum footing requirements in various applications.
- For aesthetic purposes Trinity recommends all sleeves, driven posts, and concrete cable tie posts be installed reasonably close to the cable (see detail 1-3).
- CASS-TL4 shall be installed in accordance with the following classification: If solid rock/concrete is encountered below maximum post height space limit of 20'. Reducing or increasing the spacing of concrete may be required to meet this requirement. Please contact Trinity about alternate footing design (S). Trinity suggests the use of "Mow Strips" for erosion prevention and ease of maintenance / installed drainage.
- See the Texas MUTCD for proper "Barrier" Delineation.

MOW STRIP DETAIL		CONCRETE FOOTING CHART	
MOW STRIP	DEPTH	WIDTH	FOOTING TUBE SLEEVE REBAR RING
NONE		30" Min. 27" Min.	YES
HMA	6" Min. 3" Min.	24" Min. 15" Min.	NO
HMA	8" Min. 3" Min.	24" Min. 15" Min.	NO
HMA	3" Min. 3" Min.	24" Min. 15" Min.	NO
Concrete	3" Min. 3" Min.	24" Min. 15" Min.	NO

CABLE TENSION CHART	
FAIRMET/ PRE-STRETCHED	DEVICES
10	7000
10	6000
10	5000
30	6000
30	5000
50	5000
50	4000
80	4300
90	4000
100	3600
120	3000
130	2700
140	2500
150	2300

Trinity Highway Products, LLC.
 2525 Stemmons Freeway
 Dallas, TX 75204
 Phone: (800) 644-7976
 Product: INFO@TRIN.NET

Allows deviation from chart in tension force
 +800-200 pounds/force. Cable tension readings are typically higher in curved cable sections.


Design Division Standard

TRINITY
CABLE SAFETY SYSTEM
(TL-4)

CASS (TL4) - 14

FILE CASS TL4.dgn	DATE	BY	APP	CHK
01/11/2014	March 2014	EBB	B1	1/0027
REVISIONS	COM	SEC	APP	
1	001			
2	001			
3	001			
4	001			
5	001			
6	001			
7	001			
8	001			
9	001			
10	001			
11	001			
12	001			
13	001			
14	001			
15	001			
16	001			
17	001			
18	001			
19	001			
20	001			
21	001			
22	001			
23	001			
24	001			
25	001			
26	001			
27	001			
28	001			
29	001			
30	001			
31	001			
32	001			
33	001			
34	001			
35	001			
36	001			
37	001			
38	001			
39	001			
40	001			
41	001			
42	001			
43	001			
44	001			
45	001			
46	001			
47	001			
48	001			
49	001			
50	001			

DISCLAIMER: TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. The use of this standard is governed by the Texas Engineering Practice Act. No warranty is made by TxDOT for any purpose whatsoever.



- GENERAL NOTES**
- For additional information contact Gibraltar, Inc. at 1-800-495-8957, 830-796-5444, or see the manufacturer's product manual.
 - All concrete shall be CLASS A.
 - The Cable Barrier System shall be installed on shoulders or on medians with slopes of 6:1 or flatter. If installed on slopes steeper than 6:1 up to 4:1 the TL-4 system performs as a TL-3 and Gibraltar must be contacted for various guidelines related to placement.
 - The Cable Barrier System is accepted by the FHWA Test Level - 4.
 - See the Texas MUTCD for proper "Barrier" delineation.
 - Rock Clause: Where solid rock is encountered:
 - For socketed post, continue digging 12" diameter, 15" deep into rock or the required plan depth, whichever comes first.
 - For driven post, core drill a 4" diameter hole 18" deep into rock or the required plan depth, whichever comes first.
 - For Anchor post, continue digging 24" diameter, 30" deep into rock or the required plan depth, whichever comes first.
 - Tolerances:
 - * LP ± 3" out of plumb, at top
 - * Cable height = 1"
 - * Anchor Post = 5" off of Cable Reference Line
 - The Gibraltar cable barrier system shall be installed in NCHRP Report 350 standard compacted soil. Soil must be well drained.
 - All non-welded rebar by others.
 - Minimum recommended line post foundation.
 - Without mowstrip, 36" Deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long
 - With 4" minimum depth hot mix asphalt, 30" deep x 12" diameter foundations with #3 rebar ring x 8" diameter with two #4 rebar vertical bars 30" long.
 - With 3" minimum depth concrete mowstrip, 24" deep x 12" diameter foundations. (No rebar required)
 - Direct drive post 42" deep.

DEFLECTION	
Deflection	Post Spacing
8'-0"	20 FT
7'-0"	12 FT
6'-8"	10 FT

* Allowable Deviation from Chart +/- 10%

CABLE TENSION CHART #	
-10 * F	8000
0 * F	7600
10 * F	7200
20 * F	6800
30 * F	6400
40 * F	6000
50 * F	5600
60 * F	5200
70 * F	4800
80 * F	4400
90 * F	4000
100 * F	3600
110 * F	3200


Design Origin Standard
Texas Department of Transportation

GIBRALTAR CABLE BARRIER SYSTEM (TL-4)

GBRLTR(TL4) - 14


FILE: GBR-TL4-TL4.00P
 DATE: 03/01/2014
 REVISIONS: 0409, 01, 001, 002, 003, 004, 005, 006, 007, 008, 009, 010, 011, 012, 013, 014, 015, 016, 017, 018, 019, 020, 021, 022, 023, 024, 025, 026, 027, 028, 029, 030, 031, 032, 033, 034, 035, 036, 037, 038, 039, 040, 041, 042, 043, 044, 045, 046, 047, 048, 049, 050, 051, 052, 053, 054, 055, 056, 057, 058, 059, 060, 061, 062, 063, 064, 065, 066, 067, 068, 069, 070, 071, 072, 073, 074, 075, 076, 077, 078, 079, 080, 081, 082, 083, 084, 085, 086, 087, 088, 089, 090, 091, 092, 093, 094, 095, 096, 097, 098, 099, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000

DISCLAIMER: THIS STANDARD IS GOVERNED BY THE TEXAS ENGINEERING PRACTICE ACT. NO WARRANTY OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE. THE USER OF THIS STANDARD ASSUMES ALL LIABILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




DOWNSTREAM ANCHOR TERMINAL (DAT)

NOTE: ONLY FOR DOWNSTREAM USE, WHEN LOCATED OUTSIDE THE HORIZONTAL CLEARANCE AREA OF OPPOSING TRAFFIC.



4 TERMINAL RAIL ELEMENT FOR DAT



GENERAL NOTES

1. THE DETAIL SHOWN IS THE MINIMUM LENGTH OF NEED (LON) FOR A DOWNSTREAM ANCHOR TERMINAL (DAT) CONNECTED TO A CONCRETE RAIL.
2. THE RAIL SECTION AT THE END POST IS SUPPORTED BY THE BEARING POST BRACKET. THE RAIL ELEMENT IS NOT ATTACHED TO THE END POST.
3. THE FOUNDATION TUBES SHALL NOT PROJECT MORE THAN 3 3/4\"/>

MOW STRIP INSTALLATION

IF A MOW STRIP IS REQUIRED WITH THE DAT THE FOLLOWING INSTALLATION PROCEDURE SHALL BE USED: ALL FOUNDATION TUBES AND THE TWO CHANNEL STRUTS MAY BE OMITTED. THIS WILL REQUIRE A FULL POUR AT THE FOUNDATION TUBES.


#	(DAT) PARTS LIST	QTY
1	STEEL FOUNDATION TUBE	2
2	DAT TERMINAL POST	2
3	CHANNEL STRUT	2
4	TERMINAL RAIL ELEMENT	1
5	SHELF ANGLE BRACKET	1
6	BCT BEARING PLATE	1
7	BCT POST SLEEVE	1
8	GUARDRAIL ANCHOR BRACKET	1
9	(ROUNDED) W-BEAM END SECTION	1
10	BCT CABLE ANCHOR	1
11	RECESSED NUT, GUARDRAIL	20
12	1 1/4\"/>	
13	10\"/>	
14	5/8\"/>	
15	3/8\"/>	
16	5/8\"/>	
17	3/8\"/>	

Design Division Standard
Texas Department of Transportation


METAL BEAM GUARD FENCE (DOWNSTREAM ANCHOR TERMINAL) TL-3 MASH COMPLIANT

GF (31) DAT - 19


FILE# GF(31)0019.dgn
DWT-KDOOT CJK KM DBR YIP CJC/CGL/AG
DATE: 01-NOVEMBER 2019
COM# BCT JOB
REV# 01 001
DIST COUNTY SHEET NO.
05 001
TITLE: FENCE
33




TYPICAL POST PLACEMENT
NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.
MBGF LENGTH OF NEED (L)



ELEVATION MID-SPAN RAIL SPLICE
SHOWING A 25' - 0\"/>




ELEVATION 25' - 0\"/>




RAIL SPLICE DETAIL
(8) MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6' - 3\"/>




BUTTON HEAD BOLT
NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.




WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST



LOW FILL CULVERT POST



HIGH FILL CULVERT POST

NOTE: TWO INSTALLATION OPTIONS.
1. BOLT-THROUGH OPTION: REQUIRES A 6\"/>

2. EPOXY ANCHOR OPTION: THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9\"/>

GENERAL NOTES


1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 840 "METAL BEAM GUARD FENCE," EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25' - 0" OR 12' - 6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3' - 1 1/2" C-C OR 6' - 3" C-C. A SPECIAL TRANSITION SECTION OF GUARDRAIL.
3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (AWC 610) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED UNLESS OTHERWISE SHOWN IN THE PLANS. GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSTED TO CONFORM WITH ITEM 840 "METAL BEAM GUARD FENCE." UNLESS OTHERWISE SHOWN IN THE PLANS, POSTS LOCATED BELOW OR BELOW THE TOP SURFACE OF THE PAVEMENT SHALL BE PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
8. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0.618 OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 4" INTO THE ROCK, AND SOLID ROCK SHALL BE REMOVED TO THE REQUIRED POST LENGTH. AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
9. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
10. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
11. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS TO ACCOMMODATE METAL POSTS AND LOCKS INTO METAL BEAM GUARD FENCE MAY BE USED. MATERIAL SHALL BE SUBSTITUTED FOR STEEL POSTS. MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
12. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT OR CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-10.
13. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE TOP OF THE PAVEMENT OR FOR A PAVEMENT OVERLAY, USE 10 FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SOULDER SLOPE TO THE BACK OF RAIL. MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

DESIGN STANDARD

Texas Department of Transportation
METAL BEAM GUARD FENCE
TL-3 MASH COMPLIANT
GF (31) - 19


FILED 03/11/19, 09:01	DISTRICT 01	DATE	BY
REVISIONS	NOVEMBER 2019	COMPL. SCHED.	00
4/09	81	COUNTY	TRAVIS
10/5	10/5	TITLE	STANDARD
			34

DESIGNER'S RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR DAMAGES RESULTING FROM ITS USE.
 THIS STANDARD IS COVERED BY THE TEXAS ENGINEERING PRACTICE ACT. NO WARRANTY OR INCORPORATION OF THIS STANDARD TO OTHER FORMATS OR FOR DAMAGES RESULTING FROM ITS USE.
 THIS STANDARD IS COVERED BY THE TEXAS ENGINEERING PRACTICE ACT. NO WARRANTY OR INCORPORATION OF THIS STANDARD TO OTHER FORMATS OR FOR DAMAGES RESULTING FROM ITS USE.




TYPICAL PLAN VIEW
Transition to W-Beam

- (5) 3/8" dia. heavy hex head bolts (ASTM A325 or A449)
- (10) 1 1/2" O.D. washer under each hex bolt head and nut, (ASTM A194 or A563)
- Thrie-Beam Connector to Concrete Rail
- 4-#5 Gr-60 Galv. Rebar 18" Long
- Type II Curb (See precast curb note)
- Concrete curb Type II subsidiary to Metal Beam Guard Fence Transition. If curb height is less than 4" it will be tapered down beginning of the last 7 ft post to a maximum height of 4" at the first 6 ft post.
- If shown elsewhere in the plans, additional curb underneath guardrail will be paid for by the linear foot.




TYPICAL ELEVATION VIEW


- 2 - 12'-6" Long Thrie-Beam (12 Gauge) (Nested)
- 15/16" x 1/2" Slotted Holes
- 3/4" x 2 1/2" Slotted Holes
- Terminal Connector (10 Gauge)
- 12 - 3/8" Dia. x 2" Burdon head splice bolts (See General Note 7)
- Only top post bolt required at this post location, Bottom field drilling and is optional.



WOOD BLOCK TO STEEL POST



WOOD BLOCK TO RECTANGULAR WOOD POST



WOOD BLOCK TO ROUND WOOD POST

GENERAL NOTES

1. Concrete curb may be cast-in-place or precast as shown on this sheet. When used in conjunction with thrie-beam guard fence transitions, curb shall be Type II (Typically 5 1/2" height above surface). See CCCC for details. All curb heights are shown in the plans in conjunction with the transition. The concrete curb shall be continuous to the seventh post.
2. Contact the Design Division for drainage cut options needed within the curb section of the transition.
3. The type of post (round wood, rectangular wood or steel) will be shown elsewhere in the plans.
4. The post length shall be marked on all 7'-0" long posts by the location of the curb. The curb shall be located within the top 10" of the post. Wooden posts shall be marked with a brand, and steel posts with a stencil, before galvanizing.
5. Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans. The thrie-beam terminal connector and the thrie-beam transition to w-beam shall be of the same material, but shall not be less than 10 gauge.
6. Contractor shall verify that the locations of bolt holes match those in the thrie-beam terminal connector prior to ordering materials.
7. Unless otherwise shown in the plans, transitions shall be placed with the block face in front of or directly above the curb face.
8. Install terminal connector with (12) rectangular guardrail plate washers (TRM03) and (12) 3/8" x 2" burdon head splice bolts with recessed nuts.
9. Burdon head "post bolts & nuts" shall meet the requirements of (ASTM A307), and shall be of sufficient length to extend through the full thickness of the terminal connector and into the thrie-beam transition a minimum of 1" remaining bolt length to meet required length.
10. Fittings (bolts, nuts, and washers) shall be galvanized in accordance with Item 445, Galvanizing. Fittings shall be subsidiary to the bid item.
11. Crown shall be widened to accommodate transitions.
12. If solid rock is encountered. See the MBGF standard sheet for the proper installation guidelines.

ONLY FOR USE IN MAINTENANCE REPAIRS.

Design Division Standard
Texas Department of Transportation
METAL BEAM GUARD FENCE TRANSITION (THRIE-BEAM TRANSITION)
MBGF (TR) - 19

FILE#	MBGF19-19.dgn	DATE	10/11/2019	DESIGNER	ST	DATE	10/11/2019	CHECKED	ST	DATE	10/11/2019	SCALE	AS SHOWN	SHEET NO.	31
-------	---------------	------	------------	----------	----	------	------------	---------	----	------	------------	-------	----------	-----------	----

THRIE-BEAM TRANSITION TO W-BEAM (10 Gauge)



CONNECTION TO CONCRETE BRIDGE RAIL AND TRAFFIC BARRIERS



THRIE-BEAM TERMINAL CONNECTION




TYPICAL THRIE-BEAM CURB



SECTION A-A



SECTION B-B



SECTION C-C



BRIDGE APPROACH - UPSTREAM



BRIDGE APPROACH - DOWNSTREAM




PLATE WASHERS ARE INSTALLED UNDER THE TERMINAL CONNECTOR. INSTRUCTIONS

BRIDGE APPROACH - UPSTREAM: THE NESTED RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF RAIL.
BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.

NOTES:

- (5) 3/8" dia. heavy hex bolts, length will vary depending on width of concrete rail, leave 1" of bolt length past the 3/8" hex nut. Trim as required.
- See General Notes: 6 & 7 for additional connection details.

PRECAST CURB TYPE II

Cast-in-place concrete curb shall be precast with 4-#5 Gr-60 Galv. Rebar spaced 18" long. The 12" x 2" section of curb may be cast in two sections.
Section 1: 5'-8" long
Section 2: 6'-6" long with the last 3'-6" of curb tapered to 6" at the right. Female ends connected with 1-#5 Gr-60 Galv. Rebar 18" long.

DISCLAIMER:

THIS STANDARD IS GOVERNED BY THE TEXAS ENGINEERING PRACTICE ACT. NO WARRANTY OR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR DAMAGES RESULTING FROM ITS USE.

DATE:


10/11/2019

FILE#:

MBGF19-19.dgn

NOTE: SECTION MAY BE REQUIRED TO INSTALL THE QUADGUARD ELITE M10 TO THE OBJECT BEING SHIELDED.


QUADGUARD ELITE M10 24" WIDE (6 BAY) SYSTEM



BACKUP ASSEMBLY TYPES FOR SYSTEM TRANSITIONS

SYSTEM TRANSITIONS TYPES
1 QUAD-BEAM TO CONCRETE SAFETY BARRIER
2 QUAD-BEAM TO CONCRETE BRIDGE RAIL
3 QUAD-BEAM TO CONCRETE END SHOE
4 QUAD-BEAM TO THRIE-BEAM RAIL
5 QUAD-BEAM TO W-BEAM RAIL

NOTE: TRANSITION ASSEMBLIES FOR THE QUADGUARD ELITE M10 TO THRIE-BEAM OR W-BEAM FENCE REQUIRES 1'-BEAM POSTS. ALL POSTS #6x8-5/9 1'-BEAMS (18" LONG).



NOTE: STANDARD IS A BASIC REPRESENTATION OF THE QUADGUARD ELITE M10 SYSTEM AND IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT TRINITY HIGHWAY - ENERGY ABSORPTION INC. AT 11888323-6374.
- SEE THE RECENT QUADGUARD ELITE M10 PRODUCT DESCRIPTION ASSEMBLY MANUAL FOR IMPACT PERFORMANCE CHARACTERISTICS AND DESIGN LIMITATIONS AND THE DRAWING PACKAGE FOR NARROW 24" SYSTEM BEFORE INSTALLING THE QUADGUARD ELITE M10 AT ANY GIVEN LOCATION.
- FOR BI-DIRECTIONAL TRAFFIC: THE LOCATION AND OR WIDTH OF THE QUADGUARD ELITE M10 IS RESTRICTED. AS BI-DIRECTIONAL TRAFFIC APPROACHES THE REAR OF THE QUADGUARD ELITE M10, THE QUADGUARD ELITE M10 SHOULD NOT EXTEND FURTHER INTO THE TRAFFIC-SIDE OF THE BARRIER THAN THE OBSTACLE. ANY TRANSITION INSTALLED MUST EITHER BE TANGENT TO BOTH QUADGUARD ELITE M10 AND OBSTACLE OR MUST ANGEL TOWARD FIELD SIDE OF THE BARRIER.
- SYSTEM TRANSITION: APPROPRIATE TRANSITION PANELS OR SIDE PANELS WILL BE REQUIRED FOR PROPER IMPACT PERFORMANCE. THE CORRECT PANEL (S) TO USE WILL DEPEND ON THE DIRECTION OF TRAFFIC FLOW AND WHAT TYPE OF BARRIER OR ROAD FEATURE THE QUADGUARD ELITE M10 SYSTEM IS SHIELDING. SEE THE QUADGUARD ELITE M10 PRODUCT DESCRIPTION & ASSEMBLY MANUAL FOR FURTHER DETAILS.
- COMPONENTS FOR THE QUADGUARD ELITE M10 BACKUP AND REINFORCING DETAILS ARE SHOWN ON THE QUADGUARD ELITE M10 PRODUCT DESCRIPTION & ASSEMBLY MANUAL.
- CONCRETE PAD SHALL BE 6" MIN. REINFORCED 28MPA (4,000 PSI) (P.C.) OR 8" MIN. NON-REINFORCED CONCRETE (P.C.) TO A MINIMUM DEPTH OF 12" MIN. WIDE BY 60" LONG ANCHOR BOLT IS NOT REQUIRED WHEN USING 8" CONCRETE PAD INSTALLED AGAINST AN IMMOVABLE STRUCTURE, E.G. CONCRETE WALL.
- IF THE CROSS-SLOPE VARIES MORE THAN 2% OVER THE LENGTH OF THE SYSTEM, THE CONCRETE PAD WILL REQUIRE LEVELING. MAXIMUM PERMISSIBLE CROSS-SLOPE IS 8%.
- THE INSTALLATION AREA SHOULD BE FREE OF CURBS, ELEVATED OBJECTS, OR DEPRESSIONS.
- THE QUADGUARD ELITE M10 SYSTEM SHOULD BE INSTALLED APPROXIMATELY PARALLEL WITH THE BARRIER.
- FOR THE TENSION STRUT BACKUP THE DISTANCE BETWEEN THE BACK OF BACKUP AND THE BARRIER WALL SHOULD NOT EXCEED 7" IN ANY CASE.
- TXDOT HAS ONLY APPROVED THE 24" WIDE QUADGUARD ELITE M10 SYSTEM. THE QUADGUARD ELITE M10 PRODUCT DESCRIPTION AND ASSEMBLY MANUAL INCLUDES SYSTEM WIDTH OF 24". ONLY THE 24" SYSTEM IS ALLOWED TO BE INSTALLED ON TEXAS ROADWAYS.

FOUNDATION & ANCHORING REQUIREMENTS

FOUNDATION TYPES: A, B, C, & D
FOUNDATION TYPE A REINFORCED CONCRETE PAD OR ROADWAY
FOUNDATION: 6" MINIMUM DEPTH (P.C.C.)
ANCHORAGE: 7" STUDS EMBEDDED 5 1/2" - APPROVED ADHESIVE
FOUNDATION TYPE B ASPHALT OVER P.C.C.
FOUNDATION: 3" MIN. (A.C.) OVER 3" MIN. (P.C.C.)
ANCHORAGE: 18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE
FOUNDATION TYPE C ASPHALT OVER SUBBASE
FOUNDATION: 6" MIN. (A.C.) OVER 6" MIN. (C.S.)
ANCHORAGE: 18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE
FOUNDATION TYPE D ASPHALT ONLY
FOUNDATION: 8" MIN. (A.C.)
ANCHORAGE: 18" THREADED ROD EMBEDDED 16 1/2" - APPROVED ADHESIVE

KEY:
ASPHALT CONCRETE (A.C.)
PORTLAND CEMENT CONCRETE (P.C.C.)
NOTE: SEE TRINITY'S PRODUCT DESCRIPTION ASSEMBLY MANUAL FOR THE APPROVED ADHESIVE.
IF THE UNIT IS ANCHORED TO ASPHALT CONCRETE, IT SHOULD BE RELOCATED TO ADEQUATE FUTURE PERFORMANCE.
TENSION STRUT BACKUP MAY BE USED IN CONSTRUCTION ZONES ON ASPHALT CONCRETE (A.C.) FOR TEMPORARY USE ONLY.

Design Origin Standard
Texas Department of Transportation

**TRINITY HIGHWAY
ENERGY ABSORPTION
QUADGUARD ELITE M10
(MASH TL-3)**


QGE LITE (M10) (N) - 20

FILE: qge111em020z01.dgn	DATE: 11/08/20	BY: JRM	CHK: JRM	APP: JRM
PROJECT: 6489 B1	JOB: 001	REV: 001	DATE: 11/08/20	BY: JRM
REVISIONS:	DIST:	COUNTY:	SHEET NO.:	38
05	05	HAILE		

LOW MAINTENANCE


GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS AT 25'-0" C-C OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE TRANSITION SECTIONS OF GUARDRAIL.
3. RAIL HEAD "POST" BOLTS (ASTM A307) SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT (ASTM A563) AND 3/4" ROUND WASHER (ASTM F436) AND NOT MORE THAN 1" BEYOND IT. BUTTON HEAD "SPRICE" BOLTS (ASTM A307) ARE 3/4" X 1-1/2". FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." BOLTS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
4. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
5. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
6. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
7. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. SEE OF (31) STANDARD FOR INSTALLATION GUIDANCE.
8. POSTS SHALL NOT BE SET IN CONCRETE.
9. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCES SHALL BE USED. THE CONTRACTOR SHALL VERIFY THAT THE MATERIAL PRODUCER LIST (MPL) MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
11. REFER TO STANDARD GF(31) FOR ADDITIONAL DETAILS.
12. RAIL HEIGHT ADJUSTMENT IS ASSESSED AT TL-3 MASH COMPLIANT FOR STEEL POST HEIGHT TRANSITION TO 28" STEEL POST GUARDRAIL.




ELEVATION VIEW

WOOD INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



HARDWARE LIST	
QTY	DESCRIPTION
1	9'-4 1/2" W-BEAM RAIL ELEMENT 120A.
1	25'-0" W-BEAM RAIL ELEMENT 120A. (TYP)
6	7 1/2" DIA X 6'-0" DOMED ROUND WOOD POSTS (TYP)
6	6" X 8" X 68" RECTANGULAR WOOD POSTS (TYP)
6	W6 X 8.5 OR W6 X 9 X 72" STEEL POSTS (TYP)
6	6" X 8" X 14" WOOD BLOCKS OR COMPOSITE (TYP)
6	3/4" X 18" GUARDRAIL BOLTS WITH NUTS (FBB04)
6	3/4" X 10" GUARDRAIL BOLTS WITH NUTS (FBB03)
24	3/4" X 1-1/4" GUARDRAIL SPLICE BOLTS WITH DOUBLE RECESSED NUTS (ASTM A563) (FBB01)



NOTE: HARDWARE SHALL MEET THE FOLLOWING REQUIREMENTS.
 GUARDRAIL POST BOLTS (ASTM A307 GR. A)
 GUARDRAIL ROUND WASHERS (ASTM F436)
 GUARDRAIL DOUBLE RECESSED NUTS (ASTM A563)
 GUARDRAIL SPLICE BOLTS (ASTM A307 GR. A)
 GUARDRAIL SPLICE NUTS (ASTM A563)

METAL BEAM GUARD FENCE
RAIL HEIGHT ADJUSTMENT
(28" TO 31")
TL-3 MASH COMPLIANT
RAIL-ADJ(A)-19


FILED: 10/1/2019	DIST: 001	DATE: 10/1/2019
DATE: NOVEMBER 2019	COUNTY: DALLAS	PROJECT: 19000000000000000000
REVISIONS:	BY:	DATE:
1	10/1/2019	10/1/2019

Design Division Standard
 Texas Department of Transportation
 DIST: 001
 COUNTY: DALLAS
 DATE: 10/1/2019
 SHEET NO.: 39

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE TEXAS ENGINEERING PRACTICE ACT. NO WARRANTY OR ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

GENERAL NOTES

1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN FOR THE PLAN. THE EXACT POSITION OF THE POST SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
2. RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 3" - 1 1/2" C-C OR 6" - 3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE TRANSITION SECTIONS OF GUARDRAIL.
3. BUTTON HEAD "POST" BOLTS (ASTM A307) SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT (ASTM A563) AND 3/4" ROUND WASHER (ASTM A307) AND 1/2" METAL BEAM HEAD "SPLICE" BOLTS (ASTM A307) ARE 3/8" X 1-1/4" WITH 3/8" NUTS (ASTM A563).
4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
8. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. SEE OF (31) STANDARD FOR INSTALLATION GUIDANCE.
9. POSTS SHALL NOT BE SET IN CONCRETE.
10. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
11. REFER TO STANDARD OF (31) FOR ADDITIONAL DETAILS.
12. RAIL HEIGHT ADJUSTMENT IS ASSESSED AT TL-3 MASH COMPLIANT FOR STEEL POST HEIGHT TRANSITION TO 28" STEEL POST GUARDRAIL.



* "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.

QTY	DESCRIPTION
1	25' - 0" W-BEAM RAIL ELEMENT 12GA. (TYP)
5	7 1/2" DIA X 6' - 0" DOMED ROUND WOOD POSTS (TYP)
5	6" X 8" X 68" RECTANGULAR WOOD POSTS (TYP)
5	W6 X 8.5 OR W6 X 9 X 72" STEEL POSTS (TYP)
5	6" X 8" X 14" WOOD BLOCKS OR COMPOSITE (TYP)
5	3/8" X 18" GUARDRAIL BOLTS AND NUTS (FBB04)
5	3/8" ROUND WASHERS (ASTM F436) (FWC160)
5	3/8" X 10" GUARDRAIL BOLTS AND NUTS (FBB03)
16	3/8" X 1-1/4" GUARDRAIL SPLICE BOLTS WITH DOUBLE RECESSED NUTS (ASTM A563) (FBB01)

POST AND BLOCK-OUT TYPES AVAILABLE

[FOR WOOD POST]

[FOR STEEL POST]

NOTE: HARDWARE SHALL MEET THE FOLLOWING REQUIREMENTS.


GUARDRAIL POST BOLTS (ASTM A307 GR. A)

GUARDRAIL ROUND WASHERS (ASTM F436)

GUARDRAIL DOUBLE RECESSED NUTS (ASTM A563)

GUARDRAIL SPLICE BOLTS (ASTM A307 GR. A)

GUARDRAIL SPLICE NUTS (ASTM A563)








Design Division Standard

Texas Department of Transportation

METAL BEAM GUARD FENCE RAIL HEIGHT ADJUSTMENT (28" TO 31") TL-3 MASH COMPLIANT RAIL-ADJ(B)-19

FILE: rail-adj(b)	DATE: 11/01/19	BY: JRM	REV: 1
PROJECT: 2019	CONTRACT: 2019	SHEET NO.:	40
REVISIONS:	DATE:	BY:	

DISCLAIMER: This standard is governed by the conversion of any kind of results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of any kind of results or damages resulting from its use.



GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT (888) 323-8374, 2525 N. STEVENSON FREEWAY, DALLAS, TX 75207
- FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE SOFTSTOP END TERMINAL PRODUCT DESCRIPTION ASSEMBLY MANUAL, PN-62027B
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, OBJECT MARKERS ON THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD. FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSTITUTED TO THE BID ITEM, ITEM 445, "GALVANIZING".
- A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, DIVISION MATERIAL PRODUCTION LIST (MPL) FOR CERTIFIED PRODUCERS.
- IF SOLID ROCK IS ENCOUNTERED, SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MOW STANDARD FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- GRADE LINE SHALL BE LAPPED IN AN UPWARD DIRECTION PARALLEL TO THE SOFTSTOP SYSTEM DIRECTLY TO A RIGID BARRIER.
- UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SOFTSTOP SYSTEM BE CURED.
- ANY ENCROACHMENT ON THE SHOULDER SHALL BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.

NOTES

NOTE A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3 3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE B PART PN-5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN-5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) W-BEAM SPLICE LOCATED BETWEEN LINE POST (4) AND LINE POST (5)

NOTE C GUARDRAIL PANEL 25'-0" PN-610 ANCHOR RAIL 25'-0" PN-152150 LRP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

MAIN SYSTEM COMPONENTS

PART	QTY	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
152020	1	SOFTSTOP HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
152050	1	SOFTSTOP ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
152050A	1	POST #0 - ANCHOR POST (6" - 5 1/2")
152050B	1	POST #1 - (S/TP) (4" - 3 1/2")
152050C	1	POST #2 - (S/TP) (6" - 0")
152050D	1	POST #3 THRU #6 - 1-BEAM (W6 X 8.5) (6" - 0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" X 8" X 14")
6777B	1	BLOCKOUT - WOOD (ROUTED) (4" X 1 1/2" X 14")
152070	1	ANCHOR KEEPER PLATE (24 GA)
152060	1	ANCHOR PLATE WASHER (1/2" THICK)
152010	2	ANCHOR POST ANGLE (110° LONG)
152020	2	ANGLE STRUT

HARDWARE

49022	1	1" ROUND WASHER F436
39085	1	1" HEAVY HEX NUT A563 GR.DH
37176	2	3/4" X 2 1/2" HEX BOLT A325
37010	4	3/4" ROUND WASHER F436
37040	2	3/4" HEAVY HEX NUT A563 GR.DH
33600	16	3/4" X 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
33400	25	3/4" W-BEAM RAIL SPLICE NUTS HGR
35000	7	3/4" X 10" HGR POST BOLT A307
33910	1	3/4" X 1 1/2" HEX HD BOLT A325
44960	1	3/4" X 9" HEX HD BOLT A325
103240	2	3/4" X 2 1/2" HEX HD BOLT GR-5
1032860	2	3/4" X 1 1/2" HEX HD BOLT GR-5
32400	6	3/4" ROUND WASHER (WIDE)
32450	3	3/4" HEX NUT A563 GR.DH
58528	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE B

REVISIONS










NO.	DATE	BY	CHKD	APP'D	DESCRIPTION
1	07/01/2016	001	001		ISSUE FOR CONSTRUCTION

Trinity Highway
SOFTSTOP END TERMINAL
MASH - TL-3
SGT (10S) 31-16

FILE: SPT10S3116
 DATE: 07/01/2016
 SHEET NO. 41

NOTES:

1. STANDARD IS A BASIC REPRESENTATION OF THE SOFTSTOP END TERMINAL. IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.



GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL SOLUTIONS, CONTACT THE MANUFACTURER'S TECHNICAL SUPPORT DEPARTMENT AT (707) 374-6800.
- FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE MAX-TENSION INSTALLATION INSTRUCTION MANUAL, P/N MAXM REV D (GEN 3516).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MARK STRIP STANDARD.
- ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
- SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
- COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF RMS 910, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (AMPL) FOR CERTIFIED PRODUCERS.
- REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
- SOLID ROCK IS ELATIONERED. SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- A DRIVING GAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
- MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
- IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
- THE SYSTEM IS SHOWN WITH 12'-6" MGBF PANELS, 25'-0" MGBF PANELS ARE ALSO ALLOWED.
- A MINIMUM OF 12'-6" OF 12GA. MGBF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM # PART NUMBER DESCRIPTION QTY

1	BS1-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BS1-1610061-00	GROUND STRUT - GALVANIZED	1
3	BS1-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BS1-1610063-00	W6X9 L-BEAM POST 6FT. - GALVANIZED	1
5	BS1-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BS1-1610065-00	TSS PANEL - INNER SIDE SLIDER	1
7	BS1-1610066-00	TOOTH - GEOMET	1
8	BS1-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BS1-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BS1-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	W-BEAM COMPOSITE-BLOCKOUT XT110	1
13	BS1-102027-00	X-LITE SQUARE WASHER	4
14	BS1-4004386	1/2" X 3" ALL-THREAD BOLT (GR.5)GEOMET	1
15	BS1-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	7
16	BS1-2001885	3/4" X 1 1/2" GUARD FENCE BOLTS (GR.2)M GAL	48
17	4001115	3/4" X 10" GUARD FENCE BOLTS M GAL	8
18	2001636	3/4" WASHER F436 STRUCTURAL M GAL	2
19	2001116	3/4" RECESSED GUARD FENCE NUT (GR.2)M GAL	2
20	4001116	3/4" X 2" ALL THREAD BOLT (GR.5)GEOMET	59
21	BS1-1701063-00	DELINEATION MOUNTING (BRACKET)	1
22	BS1-2001887	1/2" X 3/4" SCREW 5D HH 410SS	1
23	BS1-2001887	1/2" X 3/4" SCREW 5D HH 410SS	1
24	4002051	GUARDRAIL WASHER RECT. ASHTO FMR03	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	W-BEAM TIMBER-BLOCKOUT - PDB01 B	8
27	BS1-1004431	25" W-BEAM GUARDRAIL PANEL 8-SPACE, 12GA.	2
28	MAXM Rev. (D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.

** ALTERNATIVE ITEMS NOT SHOWN.

ITEM 26) 8" WOOD-BLOCKOUTS

ITEM 27) 25 GUARD FENCE PANELS

NOTE: STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

DATE: _____

FILE: _____

DESIGNER: _____

DATE: _____

FILE: _____

DATE: _____

FILE: _____

DATE: _____







FILE: _____

DATE: _____

FILE: _____

MAX-TENSION END TERMINAL
MASH - TL-3
SGT (11S)31-18

FILE: 591118318-00P	REV: 1.000	CR: KM	DR: T0001	CL: CL
DATE: FEBRUARY 2018	CONF: SECT	JOB: 7400	SHEET: 31	THROW: HIGHWAY
REVISIONS:	NO.	DATE	BY	DESCRIPTION
	01			
	02			
	03			
	04			
	05			
	06			
	07			
	08			
	09			
	10			
	11			
	12			
	13			
	14			
	15			
	16			
	17			
	18			
	19			
	20			
	21			
	22			
	23			
	24			
	25			
	26			
	27			
	28			



DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: _____ FILE: _____

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL. IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

NOTE: APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: ADJUST WIDTH ACCORDINGLY WHEN OFFSET IS USED. (OFFSET "OPTION" SHOWN)

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL. IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435, 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
- FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, OBJECT MARKER ON THE FRONT FACE OF THE GUARDRAIL AND REFLECTIVE ORANGE PLACEMENT MARKERS TO THE GUARDRAIL TO THE STANDARDS REQUIRED IN TEXAS LAWS. OBJECT MARKER SHALL CONFORM TO STRIP STANDARD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY NOW STRIP STANDARD.
- HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445. "GALVANIZING". FITTINGS SHALL BE SUBSTITUTED TO THE BID ITEM.
- SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKS. 7210.0. MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND /OR (POST 2), CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSP STANDARD FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- SYSTEM MUST BE ATTACHED TO STANDARD 31" MBGF.
- UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
- IF FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRUING ON THE SHOULDER, THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
- THE SYSTEM IS SHOWN WITH TWO 12'-6" MBGF PANELS, ONE 25'-0" MBGF PANEL IS ALSO ALLOWED IN THEIR PLACE.
- A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 INTO THE GROUND. THE CAP SHALL BE USED TO PREVENT DAMAGE TO THE MELOD PLATES. USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE MELOD PLATES.

MAIN SYSTEM COMPONENTS

ITEM	QTY	DESCRIPTION
A	1	MSKT IMPACT HEAD
B	1	W-BEAM GUARDRAIL END SECTION, 12 GO.
C	1	POST 1 - TOP (6" X 6" X 1/4" TUBE)
D	1	POST 1 - BOTTOM (6" X 6" X 1/4" TUBE)
E	1	POST 2 - ASSEMBLY TOP
F	1	POST 2 - ASSEMBLY BOTTOM (6" X 6" X 1/4" TUBE)
G	1	BEARING PLATE
H	1	BCT CABLE ANCHOR ASSEMBLY
J	1	GROUND STRUT
K	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")
L	6	COMPOSITE BLOCKOUTS
M	1	W-BEAM MGS RAIL SECTION (12'-6")
N	2	WOOD BLOCKOUT 6" X 8" X 14"
O	1	W-BEAM MGS RAIL SECTION (25'-0")

SMALL HARDWARE

ITEM	QTY	DESCRIPTION
0	2	3/4" x 1" HEX BOLT (GRD 5)
1	2	WASHER
2	2	HEX NUT
3	25	3/4" DIA. x 1 1/4" SPLICE BOLT (POST 2)
4	2	3/4" DIA. x 9" HEX BOLT (GRD A449)
5	3	WASHER
6	33	DIG. H.G.R. NUT
7	1	1/4" DIA. x 1 1/2" HEX BOLT (GRD A449)
8	1	ANCHOR CABLE HEX NUT
9	2	ANCHOR CABLE WASHER
10	1	ANCHOR BOLT
11	8	1/2" x 1 1/2" A325 BOLT WITH CAPTIVE WASHER
12	8	STRUCTURAL NUTS
13	8	1/4" O.D. x 3/8" I.D. STRUCTURAL WASHERS
14	2	BEARING PLATE RETAINER TIE
15	2	CT-100ST
16	6	3/4" x 10" H.G.R. BOLT
17	1	OBJECT MARKER 18" X 18"
18	1	E3151

SEE NOTES:

- * ALTERNATIVE ITEMS NOT SHOWN.
- ** ITEM (P) 8" WOOD-BLOCKOUT
- ** ITEM (O) 25' GUARD FENCE PANEL

Texas Department of Transportation

Design Division Standard

SINGLE GUARDRAIL TERMINAL

MSKT-MASH-TL-3

SGT (12S)31-18


FILE: sgt12s3118.dgn	DWG NO.	CHKM	DRYVP	CHKL
TXDOT: APRIL 2018	CONF SECT	JOB	HIGHWAY	
REVISIONS	DATE	BY	NO.	
	DIST	COUNTY		
	US	STATE		
				43

BE PREPARED TO STOP
USE ONLY WHEN FLAGGERS
CONTROL TRAFFIC
 (See Notes 2 & 3)


CW3-4 48" X 48"
 (F flags - See note 1)

CW20-7 48" X 48"
 (F flags - See note 1)

For either TCP (1-3a) or TCP (1-3b)



TCP (1-3a)
 2-LANE ROADWAY WITH PAVED SHOULDERS
 ONE LANE CLOSED
 ADEQUATE FIELD OF VIEW



TCP (1-3b)
 2-LANE ROADWAY WITH PAVED SHOULDERS
 ONE LANE CLOSED
 INADEQUATE FIELD OF VIEW

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flagger		

Posted Speed *	Formula	Minimum Taper Lengths **	Suggested Maximum Channelizing Devices	Minimum Sign Spacing Distance	Suggested Longitudinal Buffer Space "b"
30	$L = \frac{WS^2}{60}$	10' - 12' On a 10' or 12' taper	On a 10' or 12' taper	30' - 60'	90'
35	$L = \frac{WS^2}{60}$	150' - 165'	180' - 30'	35' - 70'	120'
40	$L = \frac{WS^2}{60}$	205' - 225'	245' - 40'	40' - 80'	155'
45	$L = \frac{WS^2}{60}$	265' - 295'	320' - 45'	45' - 90'	195'
50	$L = WS$	500' - 550'	600' - 50'	100' - 400'	240'
55	$L = WS$	600' - 605'	660' - 55'	110' - 500'	295'
60	$L = WS$	700' - 715'	780' - 65'	130' - 700'	410'
65	$L = WS$	800' - 820'	900' - 75'	150' - 900'	475'
70	$L = WS$	900' - 925'	1000' - 90'	175' - 1000'	540'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L=Length of Taper (FT), W=Width of Offset (FT), S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>




- GENERAL NOTES**
- Flags attached to signs where shown are REQUIRED.
 - All traffic control devices illustrated are REQUIRED, except those denoted as optional.
 - Flagger control should NOT be used unless roadway conditions or heavy traffic volume require additional emphasis to safely control traffic. Additional flaggers may be positioned in advance of traffic queues to alert traffic to reduce speed.
 - Do not place signs in the presence of construction equipment. Signs should be placed laterally across the closed lane to re-emphasize closure. Laterally placed channelizing devices should be repeated every 500 to 1000 feet in urban areas and every 1/4 to 1/2 mile in rural areas.
 - A Shadow Vehicle with a TMA should be used anytime it can be positioned in the work zone to protect workers and the public. It should be used to protect workers and the public. It should adversely affect the performance or quality of the work. If workers are no longer present but road work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
 - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, off to those shown in order to protect wider work spaces, which separate two-way traffic should be spaced on tapers at 20' or 15' where S is the speed in mph. This tighter device spacing is intended for the area of conflicting markings not the entire work zone.

Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO LANE ROADS
TCP (1-3) - 18

FILED	tcp-1-3-18.dgn	DATE	12/15/18	SHEET NO.	47
DATE	December 1985	BY	6669 SJ	COUNTY	DADE
REVISIONS	2-94	BY	4-98	COUNTY	DADE
	8-95	BY	2-12	COUNTY	DADE
	1-97	BY	2-18	COUNTY	DADE

DISCLAIMER
 The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



LEGEND

Type	Symbol	Description
Channelizing Devices	■	Channelizing Devices
Truck Mounted Attenuator (TMA)	⊠	Truck Mounted Attenuator (TMA)
Portable, Changeable Message Sign (PCMS)	M	Portable, Changeable Message Sign (PCMS)
Traffic Flow	→	Traffic Flow
Flag	◇	Flag

TCP (1-5) - 18

FILE: TCP-5-18.dgn
DATE: February 2012
REVISED: 2-18

STATE: TEXAS
COUNTY: []
JOB: []
SHEET NO.: 49

TRAFFIC CONTROL PLAN
LANE CLOSURES FOR
DIVIDED HIGHWAYS

GENERAL NOTES

- Flags attached to signs where shown, are REQUIRED.
- All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated otherwise in the plans, or for routine maintenance work, when approved by the Engineer.
- Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or safety of the work. The Shadow Vehicle should be used for all work conditions require the traffic control to remain in place. Type 3 Barricodes or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

TYPICAL USAGE


MOBILE	SHORT TERM DURATION	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY

Formula

Posted Speed * Minimum Taper Lengths ** Suggested Maximum Channelizing or Channeled Devices Minimum Sign Spacing Suggested Longitudinal Buffer Space "b"


30	10' WS ² / 60	205' 165' 180' 30'	60'	120'	90'
35	L = 60	205' 225' 245' 35'	70'	160'	120'
40		265' 295' 320' 40'	80'	240'	155'
45		450' 495' 540' 45'	90'	320'	195'
50	L = WS	500' 550' 600' 50'	100'	400'	240'
55		600' 660' 720' 60'	120'	600'	295'
60		650' 715' 780' 65'	130'	700'	410'
70		700' 770' 840' 70'	140'	800'	475'
75		750' 825' 900' 75'	150'	900'	540'

* Conventional Roads Only
** Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed(MPH)



TCP (5-1a)

WORK AREA ON SHOULDER



TCP (5-1b)

WORK AREA ON SHOULDER

LEGEND

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed * k	Formula	Minimum Desirable Taper Lengths ft.	Suggested Maximum Spacing of Channelizing Devices ft.	Longitudinal Buffer Space ft.
30	W ²	150', 115', 120', 110', 105', 100', 95', 90'	10', 11', 12', 13', 14', 15', 16', 17'	30'
35	L = 60	205', 225', 245', 265', 285', 305', 320', 40'	35', 70', 120', 155', 195', 240', 295'	90'
40	L = 60	265', 295', 320', 40', 45', 50', 550', 600', 60', 120', 295'	45', 90', 195', 240', 295'	90'
45	L = 60	450', 495', 540', 45', 50', 550', 600', 60', 120', 295'	45', 90', 195', 240', 295'	90'
50	L = 60	500', 550', 600', 50', 100', 110', 120', 130', 140', 150', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'
55	L = 60	550', 600', 660', 55', 110', 120', 130', 140', 150', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'
60	L = 60	600', 660', 720', 60', 120', 130', 140', 150', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'
65	L = 60	650', 715', 780', 65', 130', 140', 150', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'
70	L = 60	700', 770', 840', 70', 140', 150', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'
75	L = 60	750', 825', 900', 75', 150', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'
80	L = 60	800', 880', 960', 80', 160', 170', 180', 190', 200', 210', 220', 230', 240', 250', 260', 270', 280', 290', 300', 310', 320', 330', 340', 350', 360', 370', 380', 390', 400', 410', 420', 430', 440', 450', 460', 470', 480', 490', 500', 510', 520', 530', 540', 550', 560', 570', 580', 590', 600', 610', 620', 630', 640', 650', 660', 670', 680', 690', 700', 710', 720', 730', 740', 750', 760', 770', 780', 790', 800', 810', 820', 830', 840', 850', 860', 870', 880', 890', 900', 910', 920', 930', 940', 950', 960', 970', 980', 990', 1000'	50', 100', 150', 200', 250', 300', 350', 400', 450', 500', 550', 600', 650', 700', 750', 800', 850', 900', 950', 1000'	90'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L = Length of Taper (FT) W = Width of Offset (FT) S = Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	TCP (5-1-D)	TCP (5-1-B)	TCP (5-1-B)	TCP (5-1-B)

GENERAL NOTES

- A Shadow vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the performance or quality of the work. Type 3 barricades or drums may be used in lieu of shadow vehicles on foot are no longer present when approved by the Engineer.
- 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in position. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.


Texas Department of Transportation
 Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN
 SHOULDER WORK FOR
 FREEWAYS / EXPRESSWAYS**

TCP (5-1) - 18


FILE#	TCPS-1-18.dgn	DATE	05/11/11
PROJECT	REVISIONS	DATE	05/11/11
NO.	DESCRIPTION	BY	DATE
1	001	001	11/02/07
2	002	001	11/02/07
3	003	001	11/02/07
4	004	001	11/02/07
5	005	001	11/02/07
6	006	001	11/02/07
7	007	001	11/02/07
8	008	001	11/02/07
9	009	001	11/02/07
10	010	001	11/02/07
11	011	001	11/02/07
12	012	001	11/02/07
13	013	001	11/02/07
14	014	001	11/02/07
15	015	001	11/02/07
16	016	001	11/02/07
17	017	001	11/02/07
18	018	001	11/02/07
19	019	001	11/02/07
20	020	001	11/02/07
21	021	001	11/02/07
22	022	001	11/02/07
23	023	001	11/02/07
24	024	001	11/02/07
25	025	001	11/02/07
26	026	001	11/02/07
27	027	001	11/02/07
28	028	001	11/02/07
29	029	001	11/02/07
30	030	001	11/02/07
31	031	001	11/02/07
32	032	001	11/02/07
33	033	001	11/02/07
34	034	001	11/02/07
35	035	001	11/02/07
36	036	001	11/02/07
37	037	001	11/02/07
38	038	001	11/02/07
39	039	001	11/02/07
40	040	001	11/02/07
41	041	001	11/02/07
42	042	001	11/02/07
43	043	001	11/02/07
44	044	001	11/02/07
45	045	001	11/02/07
46	046	001	11/02/07
47	047	001	11/02/07
48	048	001	11/02/07
49	049	001	11/02/07
50	050	001	11/02/07

DISCLAIMER
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TCP (6-10)

TYPICAL FREEWAY ONE LANE CLOSURE



TCP (6-1b)

TYPICAL FREEWAY TWO LANE CLOSURE

LEGEND	
Channelizing Devices	Truck Mounted Attenuator (TMA)
Heavy Work Vehicle	Portable Changeable Message Sign (PCMS)
Trailer Mounted Flashing Arrow Board	Traffic Flow
Sign	Flag
Flag	Logger

Proposed Speed	Formula	Minimum Taper Lengths "L"	Suggested Maximum Spacing of Channelizing Devices "B"	Suggested Maximum Spacing of Channelizing Devices "B"
45		10' 11' 12'	On a Taper	195'
50		450' 495' 540'	On a Taper	195'
55	L=WS	500' 550' 600' 650'	On a Taper	240'
60		600' 660' 720' 780'	On a Taper	295'
65		650' 715' 780' 840'	On a Taper	350'
70		700' 770' 840' 900'	On a Taper	410'
75		750' 825' 900' 975'	On a Taper	475'
80		800' 880' 960' 1040'	On a Taper	540'

**Taper lengths have been rounded off.
 L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE			
MOBILE	SHORT DURATION	STATIONARY	INTERMEDIATE TERM STATIONARY
			LONG TERM STATIONARY

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted elsewhere in the plans.
- Drums or 42 cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42 cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer.
- All construction signs and barricades placed during any phase of work shall remain in place until the work is completed.
- The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction.
- Static message boards or changeable message signs starting the date and duration of work shall be placed in advance of the work zone.
- Static message boards or changeable message signs shall be placed a minimum of seven (7) calendar days in advance of the actual closure.
- Signs shall be placed in advance of the work zone. Information formatted as shown on 806 (6) such as "MERGE LEFT", recommended advisory speed, delay information, or other specific warnings.
- Duplicate construction warning signs should be erected on the median side of freeways where median width will permit and traffic volume justifies the signing.
- The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the MUTCD.
- Signs shall be placed in advance of the work zone. Information formatted as shown on 806 (6) such as "MERGE LEFT", recommended advisory speed, delay information, or other specific warnings.
- Intermediate term stationary work should be mounted at 7' to the bottom of the sign.
- Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.
- When possible, PMS units should be located in advance of the last available exit ramp to allow for the removal of the sign face. Signs should be removed in advance of the exit ramp to improve advance warning in case of unanticipated queuing or congestion.
- For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.


Texas Department of Transportation
 Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
FREEWAY LANE CLOSURES

TCP (6-1) - 12


FILE:	1006-1.dgn	DATE:	1/10/07	BY:	1/10/07	CHK:	1/10/07	APP:	1/10/07
REVISIONS:	1/10/07	REVISIONS:	FEBRUARY 1998	COM:	1/10/07	REV:	1/10/07	APP:	1/10/07
	8-12			6/09	81	001			
				015					

DATE: 1/10/07



TCP (6-2a)

**ENTRANCE RAMP OPEN
WORK WITHIN 500' OF RAMP**



TCP (6-2b)

ENTRANCE RAMP CLOSED

LEGEND

██████	Type 3 Barricade	■	Channelizing Devices
▣	Heavy Work Vehicle	▣	Truck Mounted Attenuator (TMA)
▣	Trailer Mounted Flashing Arrow Board	▣	Portable Changeable Message Sign (PCMS)
▣	Sign	▣	Traffic Flow
▣	Flag	▣	Flagger

Posted Speed	Formula	Minimum Taper Lengths * L	Suggested Maximum Channelizing Devices	Suggested Longitudinal Buffer Space B			
45		450'	495'	540'	90'	195'	
50		500'	550'	600'	50'	100'	240'
55		550'	605'	660'	55'	110'	295'
60	L=WS	600'	660'	720'	60'	120'	350'
65		650'	715'	780'	65'	130'	410'
70		700'	770'	840'	70'	140'	475'
75		750'	825'	900'	75'	150'	540'
80		800'	880'	960'	80'	160'	615'

**Taper lengths have been rounded off.
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DEPARTION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓	✓	✓	✓	✓

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices not shown in the plan may be omitted when stated otherwise.
- ADDED LANE SYMBOL (CMS-3) sign may be omitted when sign between ramp and mainline can be seen from both roadways.
- See "Advance Notice List" on BC (6) for recommended date and time formatting options for PMS Phase 2 message.
- The EHO ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.


Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.



**TRAFFIC CONTROL PLAN
WORK AREA NEAR RAMP**


TCP (6-2) - 12

FILE	TCP-2.dgn	DR	TxDOT	CR	TxDOT	DR	TxDOT	CR	TxDOT
REVISED	FEBRUARY 1994	COM	TACT	JOB					
DATE	4-30-8-92	DIST		COUNTY					
	4-38								
	8-12								



TCP (6-3a)

ENTRANCE RAMP OPEN



TCP (6-3b)

**EXIT RAMP CLOSED
TRAFFIC EXITS PRIOR TO CLOSED RAMP**

LEGEND

Type	3 Barricade	Channelizing Devices
Heavy Work Vehicle	Truck Mounted Attenuator (TMA)	Portable Changeable Message Sign (PCMS)
Trailer Mounted Flashing Arrow Board	Sign	Traffic Flow
Flag	Logger	

Posted Speed	Formula	Minimum Desirable Taper Lengths "L"	Suggested Maximum Channelizing Device Spacing	Suggested Longitudinal Buffer Space "B"
45		10' (11' for 100' or less taper)	On a Taper	195'
50		450' (495' for 100' or less taper)	On a Taper	240'
55		500' (550' for 100' or less taper)	On a Taper	295'
60	L = WS	550' (605' for 100' or less taper)	On a Taper	350'
65		600' (660' for 100' or less taper)	On a Taper	410'
70		650' (715' for 100' or less taper)	On a Taper	475'
75		700' (770' for 100' or less taper)	On a Taper	540'
80		750' (825' for 100' or less taper)	On a Taper	615'

** Taper lengths have been rounded off.
L = Length of Taper (FT), W = Width of Offset (FT), S = Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SUPT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓	✓	✓	✓	✓

GENERAL NOTES:
1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation
Traffic Operations Division Standard

TRAFFIC CONTROL PLAN
WORK AREA BEYOND RAMP

TCP (6-3) - 12


FILE:	1096-3.dgn	DRW:	TxDOT	CHK:	TxDOT	EXT:	TxDOT
DATE:	FEBRUARY 1994	COM:	ECT	JOB:	HOUSTON	SHEET NO.:	93
REVISIONS:	1-97 8-98	DESIGN:	01	DATE:	01/01	TITLE:	
4-98 8-12		COUNTY:	05	DATE:	05	SHEET NO.:	93

USE STREET A	USE STREET B
EXIT	EXIT
CLOSED	CLOSED

Or, as an option when exits are numbered

USE EXIT XX	USE EXIT XY
EXIT XX	EXIT XY
CLOSED	CLOSED


Place 1 mile (approx.) in advance of Street A exit.



TCP (6-4a)
EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP

Place 1 mile (approx.) in advance of closed ramp.

EXIT RAMP CLOSED
TRAFFIC EXITS PAST CLOSED RAMP



TCP (6-4b)
EXIT RAMP OPEN

LEGEND

	Type 3 Barricade		Channelizing Devices (CDs)
	Truck Mounted Attenuator (TMA)		Portable Changeable Message Sign (PCMS)
	Trailer Mounted Flashing Arrow Board		Traffic Flow
	Sign		Flagger

Posted Speed	Formula	Minimum Desirable Taper Lengths - L (feet)	Suggested Maximum Spacing of Channelizing Devices (feet)	Suggested Maximum Spacing of Buffer Space (feet)
45		450'	495'	540'
50		500'	550'	600'
55		550'	605'	660'
60		600'	660'	720'
65		650'	715'	780'
70		700'	770'	840'
75		750'	825'	900'
80		800'	880'	960'

L=Length of Taper.(FT) W=Width of Offset.(FT) S=Posted Speed(MPH)
 **Taper lengths have been rounded off.

TYPICAL USAGE

MOBILE	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices depicted in the triangle symbol may be omitted when stored elsewhere in the plans.
- See BC Standards for sign details.

*A shadow vehicle equipped with a Truck Mounted Attenuator is to be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.


Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.




TRAFFIC CONTROL PLAN
WORK AREA AT EXIT RAMP

TCP (6-4) - 12


FILE:	TC06-4.dgn	DATE:	12/01/01	PROJECT:	1994	CONTRACT:	6409	SHEET NO.:	001
REVISIONS:	1-97 6-98	REVISIONS:	4-98 6-12	COUNTY:	DADE	DIST:	05	SHEET NO.:	001
				CITY:	MIAMI			SHEET NO.:	001



TCP (6-8C)



TCP (6-8B)



TCP (6-8C)

LEGEND

Type 3 Barricade	Channelizing Devices (CDs)
Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Portable Changeable Message Sign (PCMS)	Portable Changeable Message Sign (PCMS)
Traffic Flow	Traffic Flow
Flag	Flagger

Posted Speed	Formula	Maximum Distance	Suggested Maximum Channelizing Device Buffer Space
MPH	L	ft	ft
45	450' / 495'	340'	45'
50	500' / 550'	600'	50'
55	550' / 605'	660'	55'
60	600' / 660'	720'	60'
65	650' / 715'	780'	65'
70	700' / 770'	840'	70'
75	750' / 825'	900'	75'
80	800' / 880'	960'	80'


**Taper lengths have been rounded off.
L = Length of Taper (FT) W = Width of Offset (FT)
S = Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SWAY	INTERMEDIATE	LONG TERM
✓	✓	✓	✓
DURATION	STATIONARY	STATIONARY	STATIONARY

GENERAL NOTES

- Place channelizing devices in the gore at 20' spacing.
- See the Standard Highway Sign Design for Texas (SHSD) for sign details.
- The PCMS may be omitted when a permanent DMS is used in the gore. The sign location to display a similar message as called for on the PCMS.
- When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) for traffic control details.
- Truck mounted attenuator is required.
- The PCMS may be omitted if replaced with a "RAMP CLOSED" AHEAD (CW20RP-3D) Sign.
- Roadway ADT should be greater than 10,000.



WORK IN EXIT GORE FOR ADT GREATER THAN 10,000

TCP (6-8) - 14

FILE: T026-R-029	REV: TxDOT	CH: TxDOT	DATE: TxDOT	EX: TxDOT
REVISED: FEBRUARY 2014	REVISED: 6/09	REVISED: 8/1	REVISED: 11/07	REVISED: 11/07
PROJECT: REVISIONS	DIST: 001	COUNTY: 001	SHEET NO. 48	TOTAL 54

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

LEGEND

Type 3 Barricade	Channelizing Devices (CDs)
Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Portable Changeable Message Sign (PCMS)	Portable Changeable Message Sign (PCMS)
Flashing Arrow Board	Traffic Flow
Sign	Flagger

Posted Speed	Formula	Maximum Distance (ft)	Suggested Maximum Channelizing Device Buffer Space (ft)
45	$4.50 \times \frac{L}{100} + 195$	540	90
50	$5.00 \times \frac{L}{100} + 240$	600	100
55	$5.50 \times \frac{L}{100} + 295$	660	110
60	$6.00 \times \frac{L}{100} + 350$	720	120
65	$6.50 \times \frac{L}{100} + 410$	780	130
70	$7.00 \times \frac{L}{100} + 475$	840	140
75	$7.50 \times \frac{L}{100} + 540$	900	150
80	$8.00 \times \frac{L}{100} + 615$	960	160

**Taper lengths have been rounded off.
 L=Length of Taper (ft), W=Width of Offset (ft)
 S=Posted Speed (MPH)

TYPICAL USAGE

MOBILE	✓	STATIONARY	✓
CURVE	✓	TEMPORARY	✓
DURATION	✓	PERMANENT	✓
		STATIONARY	
		LOW TRAFFIC	
		STATIONARY	

GENERAL NOTES


- Place channelizing devices in the gore at 20' spacing.
- See the Standard Highway Sign Design for Texas (SHSD) for sign details.
- The PCMS may be omitted when a permanent DMS sign is available in an appropriate location to display a similar message as called for on the PCMS.
- When it is determined that a through lane should be closed in addition to the exit ramp, refer to TCP(6-4) and TCP(6-8) for traffic control details.
- Truck mounted attenuators are required.
- The PCMS may be omitted if replaced with a "ROAD WORK 1/2 MILE" (CW20-1E).
- Roadway ADT should be less than 10,000.




WORK IN EXIT GORE FOR ADT LESS THAN 10,000

TCP (6-9) - 14

FILE:	TCP6-9-09p	REV:	TxDOT	CHK:	TxDOT	DATE:	1/00	PROJECT:	HOVWAY
REVISED:	February 2014	REVISED:	SI	REVISED:	SI	REVISED:	SI	REVISED:	SI
			001		001		001		001
			001		001		001		001
			001		001		001		001
			001		001		001		001
			001		001		001		001
			001		001		001		001
			001		001		001		001



TCP (6-9a)




TCP (6-9b)

Warning sign and rumble strip sequence in opposite direction is same as below.


TABLE 1

Flagger-to-Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
1/8 Mile	≥ 4,500	2
1/4 Mile	< 3,500	1
1/4 Mile	≥ 3,500	2
1/2 Mile	< 2,600	1
1/2 Mile	≥ 2,600	2
1 Mile	< 1,600	1
1 Mile	≥ 1,600	2
> 1 Mile	N/A	2



WZ (RS-10)

RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



WZ (RS-1b)

RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

- GENERAL NOTES**
- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
 - The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the second rumble strip in the array and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
 - Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be placed in the Compliance Work Zone Traffic Control Devices.
 - Remove Temporary Rumble Strips before removing the advanced warning signs.
 - Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
 - Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
 - This standard sheet shall be used in conjunction with other appropriate TCP standard, MUTCD typical application or project specific detail for the project.
 - The one-lane two-way application may utilize a Flagger, a Portable Flagger Assistance Device (PFAD) or a Portable Traffic Signal (PTS).
 - Replace defective Temporary Rumble Strips as directed by the Engineer.
 - Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

TABLE 2

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

LEGEND

Type 3 Barricade	Channelizing Devices
Heavy Work Vehicle	Truck Mounted Attenuator (TMA)
Trailer Mounted Flashing Arrow Panel	Portable Changeable Message Sign (PCMS)
Sign	Traffic Flow
Flag	Flagger

Posted Speed * S	Formula	Minimum Taper Lengths ** L	Suggested Maximum Spacing of Channelizing Devices S _c	Minimum Spacing of Devices S _d	Suggested Longitudinal Spacing of Buffer Space S _b
30	L = WS	150'	165'	30'	60'
35	L = WS	205'	225'	35'	70'
40	L = WS	265'	295'	40'	80'
45	L = WS	330'	370'	45'	90'
50	L = WS	400'	450'	50'	100'
55	L = WS	480'	540'	55'	110'
60	L = WS	570'	640'	60'	120'
65	L = WS	670'	750'	65'	130'
70	L = WS	780'	870'	70'	140'
75	L = WS	900'	1000'	75'	150'

* Conventional Roads Only
 ** Taper lengths have been rounded off.
 L = Length of Taper (FT), W = Width of Offset (FT)
 S = Posted Speed (MPH)

TYPICAL USAGE

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓	✓			

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, MUTCD typical application, or project specific details for the project.

* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.



Texas Department of Transportation
 Traffic Safety Division Standard

TEMPORARY RUMBLE STRIPS

WZ (RS) - 22

FILE: WZRS22.dgn	REV: 12/01	DATE: 12/01	BY: TxDOT
PROJECT: November 2012	REV: 01/12	DATE: 01/12	BY: TxDOT
REVISIONS: 6469/81	DATE: 01/12	BY: TxDOT	REASON: H0027
2-14	1-22	001	001
4-16		005	005


HALE COUNTY, TEXAS
 SHEET NO. 58



FOR USE WITH MBGF CONNECTIONS TO CONCRETE BRIDGE RAILS AND TRAFFIC BARRIERS

GENERAL NOTES

- The type of post (round wood post, rectangular wood post, or steel post) will be shown elsewhere in the plans. The exact position of transitions shall be shown elsewhere in the plans or as directed by the Engineer.
- Rail element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified on the plans.
- Button head "post" bolts (ASTM A307) shall be of sufficient length to embed into the concrete at least 1" beyond it. Button head "splice" bolts (ASTM A307) are 3/8" x 2" (at triple rail splices) with 3/8" double recessed nuts (ASTM A563).
- Fittings (bolts, nuts, and washers) shall be specified in accordance with Item 445, "Galvanizing." Fittings shall be substitutable to the B1G item requiring construction of the transition.
- Crown will be widened to accommodate transitions.
- If solid rock is encountered. See the MBGF standard sheet for the proper installation guidance.
- Posts shall not be set in concrete.
- Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DMS-7210, "Composite Material Posts and Blocks for Metal Beam Guard Fence" may be substituted for posts and blocks for Metal Beam Guard Fence. The substitution must maintain a Material Producer List (MPL) for producers of material conforming to DMS-7210. Only producers on the MPL can furnish composite material posts and/or blocks.
- Refer to MBGF standard sheet for additional details.



ONLY FOR USE IN MAINTENANCE REPAIRS.

Texas Department of Transportation
Design Division
Standard

**METAL BEAM GUARD FENCE
TRANSITION (TL2)
(Low Speed Transition)
MBGF (TL2) - 19**

FILE: MD071219.dgn	DR: TADOT	CR: NM	INR: BD	CHK: JP
NOVEMBER 2019	COMP: SGT	JOB: 6409	DESIGN: B1	THROTT: 1
REVISIONS:	DATE:	BY:	APP: 05	SHEET NO.: 59

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General/Permit required for projects with 10 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with item 306.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

- No Action Required Required Action
- No Action Required Required Action

Action No. _____

1. Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000.

2. This project disturbs less than one acre of surface area. The contractor is responsible for any PSL's as defined in the Standard Specification for Construction and Maintenance of Highways, Streets, and Bridges (2014 Edition, Item 7, Section 7.7, Page 4.3). The total disturbed acreage is the combined acreage to be disturbed on the project and any contractor PSL's. This EPIC must be updated if the disturbed area increases to one or more acres during the course of construction. It may become necessary to post a site notice and/or NOI for the project and/or PSL's.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
- Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
- Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
- Individual 404 Permit Required
- Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

-
-
-
-

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

- | | | |
|--|--|--|
| Erosion | Sedimentation | Post-Construction TSS |
| <input type="checkbox"/> Temporary Vegetation | <input type="checkbox"/> Silt Fence | <input type="checkbox"/> Vegetative Filter Strips |
| <input type="checkbox"/> Blankets/Mulching | <input type="checkbox"/> Rock Berm | <input type="checkbox"/> Retention/Irrigation Systems |
| <input type="checkbox"/> Mulch | <input type="checkbox"/> Triangular Filter Dike | <input type="checkbox"/> Extended Detention Basin |
| <input type="checkbox"/> Sodding | <input type="checkbox"/> Sand Bag Berm | <input type="checkbox"/> Constructed Wetlands |
| <input type="checkbox"/> Interceptor Swole | <input type="checkbox"/> Straw Bale Dike | <input type="checkbox"/> Wet Basin |
| <input type="checkbox"/> Diversion Dike | <input type="checkbox"/> Brush Berms | <input type="checkbox"/> Erosion Control/Compost |
| <input type="checkbox"/> Erosion Control/Compost | <input type="checkbox"/> Erosion Control/Compost | <input type="checkbox"/> Mulch Filter Berm and Socks |
| <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Mulch Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks |
| <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Compost Filter Berm and Socks | <input type="checkbox"/> Vegetation Lead Ditches |
| | <input type="checkbox"/> Stone Outlet Sediment Traps | <input type="checkbox"/> Sand Filter Systems |
| | <input type="checkbox"/> Sediment Basins | <input type="checkbox"/> Crassy Socks |

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/bush removal commitments.

- No Action Required Required Action

Action No. _____

- Comply with Executive Order 13112 on Invasive Plant Species.
- Comply with TxDOT Executive Memorandum on beneficial landscaping.
- Comply with temporary and permanent vegetation stabilization protocols of the SW3P.

V. FEDERAL LISTED, PROPOSED, THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES, AND MIGRATORY BIRDS.

- No Action Required Required Action

Action No. _____

- Do not handle or harm Texas horned lizards, prairie dogs, barn swallows or burrowing owls.
- No prairie dog dens can be damaged or crossed with equipment without the approval of the Engineer.
- No nests of burrowing owls (in prairie dog holes) can be disturbed or damaged (See General Notes).
- No nests of barn swallows (likely on structures such as bridges) can be disturbed or damaged (See General Notes).
- Obey the Bald and Golden Eagle Protection Act. Do not handle, harm, capture, disturb, or kill the species. Do not handle, harm, or take nests, eggs, feathers, bones, or eagles.
- Obey the Migratory Bird Treaty Act of 1916, of which details there cannot be any handling or harming of migratory bird species including their eggs, nests, or feathers.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects): Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.

Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labeling as required by the Act.

LIST OF ABBREVIATIONS

- SWP: Best Management Practice
- OSP: Construction General Permit
- TPDES: Texas Department of State Head In Services
- FHWA: Federal Highway Administration
- MSA: Memorandum of Agreement
- MS4: Municipal Separate Stormwater Sewer System
- MTWA: Migratory Bird Treaty Act
- NOI: Notice of Intent
- NO: Notice of Intent
- SPCC: Spill Prevention Control and Countermeasure
- SWP: Stormwater Pollution Prevention Plan
- PDN: Pre-Construction Notification
- PSL: Project Specific Location
- TCCO: Texas Commission on Environmental Quality
- TPDES: Texas Department of State Head In Services
- TPDES: Texas Department of State Head In Services
- TxDOT: Texas Department of Transportation
- TBE: The enhanced and Endangered Species
- USACE: U.S. Army Corps of Engineers
- USFWS: U.S. Fish and Wildlife Service

VII. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects): Monitor an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with site work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- Dead or distressed vegetation (not identified as normal)
 - Trash piles, drums, canisters, barrels, etc.
 - Unstable smells or odors
 - Evidence of leaching or seepage of substances
- Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection. Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the dates for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

VIII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action No. _____

- Monitor equipment muffler systems and work hour restrictions to reduce traffic noise.
- No PSL's may be located in the prairie dog towns, prairie lakes (wet or dry) or stream beds (wet or dry).
- No dumping of construction material in prairie lakes or stream beds regardless of property owner requests.
- Contractor must obtain historical and archeological clearances for all-site PSL's.
- Contractor is responsible for air quality permits for concrete and asphalt batched site plants.
- Contractor is responsible for water appropriation or impoundment TCEO permits.
- Contractor will protect environmentally sensitive areas with fencing, work sequencing or scheduling as directed.
- PSL's beyond the project right-of-way have "individual operator" status under the TPDES Construction General Permit and the Contractor is responsible for the SW3P and any TCEO permits.
- No waste material of any type may be placed at any location where it could be washed into a water of the U.S. or a surface water of Texas.
- Flood elevations will not be increased to a level that would violate flood plain regulations or ordinances.
- Contractor shall remove all construction debris daily from the waterway by close of business, where applicable.
- The SW3P, including best management practices, must be in-place prior to disturbing soil.

		ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS EPIC	
Design Division Standard	FILE: epic.dgn	DW: TxDOT	DW: VP
TxDOT: February 2015	CONF: BCT	JOB:	H00047
9-10-2015	REVISIONS:	D01:	D02:
9-23-2015	9-23-2015	D03:	D04:
10-15-2015	10-15-2015	COUNTY:	SHEET NO.:
10-15-2015	10-15-2015	SCALE:	91