Docusign Envelope ID: 6FA9E080-CB81-476D-A8F8-9F5D5C6E51BB

INDEX OF SHEETS SHEET NO. DESCRIPTION 1 TITLE SHEET 2 INDEX OF SHEETS	STATE OF TEXAS DEPARTMENT OF TRANSPORTATION
FINAL PLANS DATE OF LETTING: DATE WORK BEGAN: DATE WORK COMPLETED:	PLANS OF PROPOSED ROUTINE MAINTENANCE federal - aid project number: f 2025(193), Etc. CSJ 0039-07-264, E+c.
DATE WORK ACCEPTED: FINAL CONTRACT COST: CONTRACTOR:	LIMITS: SH 107, FM 495, US 83, SH 336
LIST OF APPROVED FIELD CHANGES, CHANGE ORDERS & SUPPLEMENTAL AGREEMENTS:	CAMERON COUNTY LIMITS: US 77, FM 1419, FM 802, FRONTAGE RD.
	PROJECT DESCRIPTION: BRIDGE STRUCTURE REPAIR
THIS IS TO CERTIFY THAT THE CONSTRUCTION WORK WAS PERFORMED IN ACCORDANCE WITH THE PLANS, CONTRACT AND LISTED FIELD CHANGES.	13 14 14 10 11 11 11 11 11 11 11 11 11
	LOCATION MAP NOT TO SCALE
	REFER TO LOCATION MAPS IN PLANS FOR LOCATIONS NOT SHOWN IN MAP ABOVE. EXCEPTIONS: NONE EQUATIONS: NONE RAILROAD CROSSINGS: NONE
TDLR INSPECTION NOT REQUIRED	RECOMM FOR LE
SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION ON SEPTEMBER 1, 2024 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023).	Texas Department of Transportation ALL RIGHTS RESERVED

ب 8 F ILE: DATE:

—DocuSigned by: PEDRO K. Alvarez


CONT	SECT	JOB			HIGH₩	۹Y
0039	07	264,	ETC.	ΙH	-69E,	ETC.
DIST		COUN	NT Y	SHEET NO.		
PHR	C/	MERON	I, ETC			1

DESIGN SPEED

MAIN LANES:	VARIOUS MPH
FRONTAGE ROADS:	VARIOUS MPH
RAMPS	VARIOUS MPH

<u>A.D.T.</u>

2022:	VARIOUS	VPD
2042:	VARIOUS	VPD



INDEX OF SHEETS

SHEET NO. DESCRIPTION

GENERAL

1234 5678 9	TITLE SHEET INDEX OF SHEETS GENERAL NOTES (SHEET 1 OF 3) GENERAL NOTES (SHEET 2 OF 3) GENERAL NOTES (SHEET 3 OF 3) SUMMARY OF ESTIMATED QUANTITIES ESTIMATE & QUANTITY SHEET (SHEET 1 OF 2) ESTIMATE & QUANTITY SHEET (SHEET 2 OF 3) ESTIMATE & QUANTITY SHEET (SHEET 3 OF 3) TRAFFIC CONTROL PLAN STANDARDS
10	<pre>[D] TRAFFIC CONTROL PLAN NOTES</pre>
11	TCP SEQUENCE OF CONSTRUCTION (SHEET 1 OF 4)
12	TCP SEQUENCE OF CONSTRUCTION (SHEET 2 OF 4)
13	TCP SEQUENCE OF CONSTRUCTION (SHEET 3 OF 4)
14	TCP SEQUENCE OF CONSTRUCTION (SHEET 4 OF 4)
15-26	[S] BC(1)-21 THRU BC(12)-21
27	[S] TCP (1-5)-18
28	[S] TCP (6-1)-12
29	[S] TCP (6-2)-12
30	[S] TCP (6-3)-12
31	[S] TCP (6-6)-12
32	[S] TCP (6-7)-12

BRIDGES

33	SUPERSTRUCTURE SPALL REPAIRS CAMERON COUNTY LOCATION MAP
34	SUPERSTRUCTURE SPALL REPAIR (SHEET 1 OF 4)
35	SUPERSTRUCTURE SPALL REPAIR (SHEET 2 OF 4)
36	SUPERSTRUCTURE SPALL REPAIR (SHEET 3 OF 4)
37	SUPERSTRUCTURE SPALL REPAIR (SHEET 4 OF 4)
38	SUBSTRUCTURE SPALL REPAIRS HIDALGO COUNTY LOCATION MAP
39	SUBSTRUCTURE SPALL REPAIR (SHEET 1 OF 3)
40	SUBSTRUCTURE SPALL REPAIR (SHEET 2 OF 3)
41	SUBSTRUCTURE SPALL REPAIR (SHEET 3 OF 3)
42	GRAVITY FED SEALANT REPAIRS CAMERON COUNTY LOCATION MAP
43	GRAVITY FED SEALANT REPAIR (SHEET 1 OF 2)
44	GRAVITY FED SEALANT REPAIR (SHEET 2 OF 2)
45	SUPERSTRUCTURE DRAIN INLET CLEANING CAMERON COUNTY LOCATION MAP
46	SUPERSTRUCTURE DRAIN INLET CLEANING


ENVIRONMENTAL ISSUES

47	EPIC	(SHEE	T 1 OF	2)	
48	EPIC	(SHEE	T 2 OF	2)	
49	TPWD	BMPs	(SHEET	1 0	F3)
50	TPWD	BMPs	(SHEET	2 0	F3)
51	TPWD	BMPs	(SHEET	3 0	F3)





*THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



Project Number:

County: Cameron, Etc.

Highway: IH-69E, Etc.

2024 SPECS GENERAL NOTES:

General Requirements and Covenants to ITEMS 1 thru 9:

For all pits or quarries, comply with the "Texas Aggregate Quarry and Pit Safety Act."

Provide on a weekly basis a list of equipment, including idle equipment, utilized on the project that week.

The 1-800 call services for utility locations do not include TxDOT facilities. Contact the Pharr District Signal Section (956-702-6225) for coordination regarding TxDOT underground lines.

ITEM 2: Instructions to Bidders

Contractor questions on this project are to be addressed to the following individual(s):

Andres Espinoza, P.E., San Benito Area Engineer; Gabriel Villareal, P.E., Assist. Area Engineer; Francisco Cantu, P.E., District Maintenance;

Andres.Espinoza@txdot.gov Gabriel.Villarreal@txdot.gov Francisco.J.Cantu@txdot.gov

Control: 0039-07-264, Etc.

Contractor questions will be accepted through email, phone, and in person by the above individuals. Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Information found on TxDOT's FTP server will be considered for informational purposes only. Index of /pub/txdot-info/Pre-Letting Responses/Pharr District/21-Pharr District (Construction) (state.tx.us)

Project Number:

County: Cameron, Etc.

Highway: IH-69E, Etc.

ITEM 4: Scope of Work of the type identified in the contract at locations that have not yet been determined.

ITEM 5: Control of the Work

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Proposal Submission" found online Precast at https://www.txdot.gov/business/resources/highway/bridge/bridge-publications.html#design. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.

ITEM 6: Control of Materials

To comply with the latest provisions of Build America, Buy America Act (BABA Act) of the Bipartisan Infrastructure Law, the contractor must submit an original of the TxDOT Construction Material Buy America Certification Form for all items classified as construction materials. This form is not required for materials classified as a manufactured product.

Refer to the Buy America Material Classification Sheet for clarification on material categorization.

The Buy America Material Classification Sheet is located at the below link. https://www.txdot.gov/business/resources/materials/buy-america-material-classificationsheet.html for clarification on material categorization.

ITEM 7: Legal Relations and Responsibilities In accordance with Article 7.2.4. of the standard specifications, roadway, or lane closures during the following key dates and/or special events are prohibited:

- National Holidays
- The day before a National Holiday

ITEM 8: Prosecution and Progress

TxDOT is required to provide 10 working days advanced written notice of all proposed bridge widening, rehabilitation, or demolition work to the Texas Department of State Health Services (TDSHS) to allow them the opportunity to both verify information provided regarding asbestos containing materials and abatement and observe the demolition/renovation work. Considering

This Contract includes non-site-specific work. Multiple work orders will be used to procure work

• During emergency events such as natural disasters or as directed by the Engineer

General Notes

Project Number:

County: Cameron, Etc.

Highway: IH-69E, Etc.

that this notice will be provided TDSHS at the beginning of the project for all affected bridge work based on start and finish dates included in the Contractor's original submitted work schedule, any schedule changes proposed by the Contractor shall be submitted to TxDOT at least 15 days prior to the revised or original start date to accommodate the required coordination with TDSHS.

Control: 0039-07-264, Etc.

Working days will be computed and charged in accordance with Article 8.3.1.6. defined as follows:

Work and time charges will continue until the start of the bird nesting season. Upon the start of the bird nesting season, work and time charges will stop for a maximum period of 120-Working days for the bird nesting season delay to be completed. Time charges in accordance with Article 8.3.1.4. will resume at the end of the 120-day bird nesting season delay or earlier if mutually agreed in writing by the Engineer and Contractor.

Prepare progress schedules as a Bar Chart.

Bridge repairs and/or improvements at bridge locations/phases 3, 4, 5, 6, 8, 9, 10, and 11 shall be done at night in accordance with Article 8.3.3.2.1.

ITEM 421: Hydraulic Cement Concrete

Provide Sulfate Resistant Concrete for all concrete piling and drilled shafts.

Provide equipment at the batch plant for determining the free moisture and/or absorption of aggregates in accordance with applicable TXDOT Test.

Provide the following items for concrete batch inspection in accordance with specifications outlined in DMS-10101, "Computer Equipment":

- (1) One Desktop Microcomputer or One Laptop Microcomputer
- (2) One Integrated Printer/Scanner/Copier/Fax Unit
- (3) Contractor-Furnished Software
- (4) Hardware

Submit to the Engineer for approval the project locations for all Portland Cement concrete washout areas prior to starting any concrete work.

Fiber Reinforced Concrete is not permitted.

Project Number:

County: Cameron, Etc.

Highway: IH-69E, Etc.

ITEM 427: Surface Finishes for Concrete Provide surface finishes for concrete as follows:

- determined by the Engineer).
- sealer coating (color to be determined by the Engineer).

Concrete traffic barrier/railing (roadway and bridge) and retaining wall coping - opaque sealer coating (color to be determined by the Engineer) to all exposed surfaces.

ITEM 502: Barricades, Signs, and Traffic Handling Shadow vehicles equipped with Truck-Mounted Attenuators are required for traffic handling. See notes for Item 505: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA), for additional references pertaining to the TMAs.

Replace/relocate all regulatory signs removed due to construction operations with the same sign on fixed support(s) immediately upon its removal. First obtain Project Engineer approval before removing any regulatory roadway sign. Required flaggers are to be available to direct traffic during sign intermediate down time.

Relocate any Directional Sign Assemblies removed during construction operations immediately upon their removal.

These signs shall be relocated to a location in accordance with the Latest Version of the "Texas Manual on Uniform Traffic Control Devices". In no case will a sign be removed without a replacement sign and support(s) being readily available and a location established. Removal and relocation of these signs required for traffic control will not be paid for directly but shall be considered subsidiary to Item 502.

From the beginning to the end of the project, all traffic control devices need to be in acceptable condition as per the Texas Quality Guidelines for Work Zone Traffic Control Devices.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The "Safety Contingency" is not intended to be used in lieu of bid Items established by the contract.

Remove and dispose of all litter, debris, objectionable material, excess materials that accumulate at the base of all traffic control devices as directed by the Engineer.

Control: 0039-07-264. Etc.

(1) Bridge overpass and underpass structures – surface area I, opaque sealer coating (color to be

(2) Bridge waterway crossings and bridge class box culvert structures - surface area II, opaque

General Notes

Project Number:

County: Cameron, Etc.

Highway: IH-69E, Etc.

ITEM 504: Field Office and Laboratory

For this project a field office will not be required at the project site.

ITEM 505: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)

In addition to the shadow vehicles with truck mounted attenuator (TMA) that are specified as being required on the traffic control plan for the project, provide 0 additional shadow vehicle(s) with TMA. Therefore, 2 total shadow vehicles with TMA will be required on this project for the type of work as shown on the plans. The Contractor will be responsible for determining if one or more of his construction operations will be ongoing at the same time and thus determine the total number of TMAs needed for the project.

Control: 0039-07-264, Etc.

ITEM 5029: Bird Exclusion Methods

Contractor's attention is directed to the plan's EPIC sheets, Bird Exclusion Detail standard sheets and shall refer to the Migratory Bird Treaty Act requirements. Also, refer to the TPWD BMPSs sheets for specific adherence to the environmental requirements of the Best Management Practices.

Project Number:


County: Cameron, Etc.

Highway: IH-69E, Etc.

Control: 0039-07-264, Etc.

General Notes

BID CODE	DESCRIPTION	UNIT	EST.	FINAL	TOTAL EST.	TOTAL FINAL
0429 - 7009	CONC STR REPAIR (STANDARD)	SF	130.14		130.14	
0764 - 7001	DRAIN INLET CLEANING	ΕA	31		31	
0780 - 7005	CNC CRACK REPAIR (FLOOD) (GRAVITY)	SF	11,835		11,835	
0500 - 7001	MOBILIZATION	LS	1		1	
0505 - 7003	TMA (MOBILE OPERATION)	DAY	69		69	
0502 - 7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	4		4	
5029 - 7001	BIRD EXCLUSION METHOD	SF	93.98		93.98	



SUMMARY OF ESTIMATED QUANTITIES

				SHE	ET	1 OF 1
© 20		CONT	SECT	JOB		HIGHWAY
DS:	ск:	0039	07	264	١	/ARIOUS
DW:	ск;	DIST		COUNTY		SHEET NO.
		PHR		VARIOUS		6



CONTROLLING PROJECT ID 0039-07-264

Estimate & Quantity Sheet

DISTRICT Pharr

HIGHWAY IH 2, IH 69E, SS 115

COUNTY Cameron, Hidalgo

		CONTROL SECTIO	ON JOB	0039-0	7-264	0039-0	07-265	0039-0	7-266	0039-0	07-267	0039-0	07-268	0039-0	07-269
		PROJ	ECT ID	A0020	9509	A00209510		A00209512		A00209513		A00209514		A00209516	
		C	OUNTY	Came	ron	Cam	eron	Came	eron	Cam	eron	Cam	eron	Cam	eron
		ню	HWAY	IH 6	9E	ін е	69E	IH 6	59E	ін (69E	IH	69E	ін	69E
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL
	429-7009	CONC STR REPAIR (STANDARD)	SF	23.760		1.150		35.010							
	500-7001	MOBILIZATION	LS	1.000											
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО	4.000											
	505-7003	TMA (MOBILE OPERATION)	DAY	69.000											
	764-7001	DRAIN INLET CLEANING	EA												
	780-7005	CNC CRACK REPAIR (FLOOD)(GRAVITY)	SF							960.000)	1,107.000		672.000	,
	5029-7001	BIRD EXCLUSION METHOD	SF	23.760											
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000											
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000											



DISTRICT	COUNTY	CCSJ	SHEET
Pharr	Cameron, Etc.	0039-07-264, Etc.	07



CONTROLLING PROJECT ID 0039-07-264

Estimate & Quantity Sheet

DISTRICT Pharr

HIGHWAY IH 2, IH 69E, SS 115

COUNTY Cameron, Hidalgo

		CONTROL SECTIO	ON JOB	0039-0	7-270	0039-07	7-271	0039-0	7-272	0039-0	8-107	0039-1	6-072	0039-1	7-210
		PROJ	ECT ID	A0020	9517	A00209	9519	A0020	9521	A0020	9522	A0020	9523	A0020	9529
		C	OUNTY	Came	ron	Came	ron	Came	eron	Came	ron	Came	eron	Hida	lgo
		ню	GHWAY	IH 6	9E	IH 69	θE	IH 6	9E	IH 6	9E	IH 6	9E	ін	2
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL	EST.	FINAL
	429-7009	CONC STR REPAIR (STANDARD)	SF											4.490	
	500-7001	MOBILIZATION	LS												
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO												
	505-7003	TMA (MOBILE OPERATION)	DAY												
	764-7001	DRAIN INLET CLEANING	EA									31.000			
	780-7005	CNC CRACK REPAIR (FLOOD)(GRAVITY)	SF	672.000		3,876.000		3,876.000		672.000					
	5029-7001	BIRD EXCLUSION METHOD	SF											4.490	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS												
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS												



DISTRICT	COUNTY	CCSJ	SHEET
Pharr	Cameron, Etc.	0039-07-264, Etc.	08



CONTROLLING PROJECT ID 0039-07-264

Estimate & Quantity Sheet

DISTRICT Pharr **HIGHWAY** IH 2, IH 69E, SS 115 COUNTY Cameron, Hidalgo

		CONTROL SECTIO	ON JOB	3 1804-01-087			
		PROJ	PROJECT ID COUNTY		9524		
		C			go	TOTAL EST.	TOTAL FINAL
		HIG	HWAY	SS 1	15		
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	429-7009	CONC STR REPAIR (STANDARD)	SF	65.730		130.140	
	500-7001	MOBILIZATION	LS			1.000	
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	МО			4.000	
	505-7003	TMA (MOBILE OPERATION)	DAY			69.000	
	764-7001	DRAIN INLET CLEANING	EA			31.000	
	780-7005	CNC CRACK REPAIR (FLOOD)(GRAVITY)	SF			11,835.000	
	5029-7001	BIRD EXCLUSION METHOD	SF	65.730		93.980	
	18	EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS			1.000	
		SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS			1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Pharr	Cameron, Etc.	0039-07-264, Etc.	09

GENERAL NOTES AND SPECIFICATIONS DATA:

USE A POWER-BROOM WHEN CLEANING THE ROADWAY AS NEEDED.

REMOVE & DISPOSE ALL MATERIAL NOT DEEMED SALVAGEABLE BY THE ENGINEER, UNLESS OTHERWISE SHOWN ON THE PLANS.

ON EXISTING PAVEMENT THAT WILL REMAIN IN PLACE, SAND BLAST OR SURFACE TREAT IN ORDER TO REMOVE EXISTING STRIPING.

DO NOT BLOCK DRAINAGE WHEN HANDLING & STOCKPILING EXCAVATED MATERIAL.

MAINTAIN ACCESS TO DRIVEWAYS AND INTERSECTIONS THROUGH ALL PHASES OF CONSTRUCTION.

MAINTAIN POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.

ALWAYS COMPLETE THE PROPOSED DRIVEWAYS DURING THEIR TCP PHASE BEFORE SWITCHING TRAFFIC TO A NEW PHASE UNLESS DIRECTED BY THE ENGINEER.

TRAFFIC CONTROL DEVICES:

AT THE COMMENCEMENT OF THE PROJECT, ALL TRAFFIC CONTROL DEVICES SHALL BE IN ACCEPTABLE CONDITION, AND MAINTAINED THROUGHOUT THE DURATION OF THE PROJECT, AS PER GUIDELINES FOR TEMPORARY TRAFFIC CONTROL DEVICES AND FEATURES.

NOTIFY THE AREA ENGINEER (AE) IN WRITING (E-MAIL IS ACCEPTABLE) ONCE THE TRAFFIC CONTROL PLAN(TCP) AND ALL TRAFFIC CONTROL DEVICES HAVE BEEN INSTALLED AS PER PLANS ON THE PROJECT SO THAT THE DEPARTMENT'S RESPONSIBLE PERSON ACCOMPANIED BY THE CONTRACTOR'S RESPONSIBLE PERSON CAN CONDUCT A NIGHT INSPECTION ON THE SAID TCP AND TRAFFIC CONTROL DEVICES. COMMENCEMENT OF WORK WILL NOT BE AUTHORIZED NOR ALLOWED UNTIL THE AE NOTIFIES THE CONTRACTOR IN WRITING (E-MAIL IS ACCEPTABLE) TO PROCEED WITH THE WORK.

CONTRACTOR SHALL HAVE A SUFFICIENT AMOUNT OF TRAFFIC CONTROL DEVICES IN ACCEPTABLE CONDITION TO REPLACE ANY DAMAGED TRAFFIC CONTROL DEVICE WITHIN 24 HOURS OF NOTIFICATION.

PROVIDE ADDITIONAL SIGNS AND BARRICADES AS NECESSARY TO ADDRESS FIELD CONSTRUCTIBILITY & VISIBILITY. THESE ADDITIONAL SIGNS WILL BE CONSIDERED SUBSIDIARY TO ITEM 502.

REMOVE OR COMPLETELY COVER ALL EXISTING SIGNS WHICH ARE IN CONFLICT WITH THE TRAFFIC CONTROL PLAN.

ADJUST STOP SIGNS AS NEEDED ON INTERSECTING STREETS DURING THE VARIOUS CONSTRUCTION PHASES. DO NOT REMOVE ANY EXISTING STOP SIGNS UNTIL TEMPORARY SIGNS ARE IN PLACE.

COORDINATE THE TRAFFIC CONTROL PLAN AND THE VARIOUS SEQUENCES OF CONSTRUCTION WITH ADJACENT CONSTRUCTION PROJECTS IF APPLICABLE. TO ENSURE THE UNINTERRUPTED AND SAFE FLOW OF TRAFFIC.

NOTIFY THE ENGINEER IN WRITING WHEN MAJOR TRAFFIC CHANGES ARE TO BE MADE. NOTIFICATIONS MUST BE GIVEN A MINIMUM OF THREE WORKING DAYS PRIOR TO THE CHANGE.

ALL WORK ZONE PAVEMENT MARKINGS FOR THIS PROJECT SHALL BE 0.100 INCHES (100 MIL) THICK THERMOPLASTIC.

SAFETY:

PROTECT EXPOSED PITS THAT MUST REMAIN OPEN DURING NON-WORKING HOURS AS PER OSHA REQUIREMENTS.

THE PORTION OF THIS PROJECT WHICH COINCIDES WITH EXISTING ROADS AND/OR PRIVATE DRIVES SHALL BE KEPT OPEN TO TRAFFIC AT ALL TIMES, UNLESS OTHERWISE PROVIDED FOR OR APPROVED BY THE ENGINEER. THE CONTRACTOR WILL BE REQUIRED TO MAINTAIN, AT ALL TIMES, TWO LANES OF _____ AND ____ * SURFACED MAINLANE ROADWAYS, DURING MAINLANE RECONSTRUCTION, UNLESS OTHERWISE NOTED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION REQUIRING TEMPORARY LANE CLOSURES OF MAIN

LANES RESULTING IN LESS THAN THE MINIMUM NUMBER OF LANES AS SPECIFIED IN PREVIOUS NOTE, SHALL BE DURING OFF-PEAK HOURS. DURING THE PEAK HOURS THE CONTRACTOR SHALL MAINTAIN THE MINIMUM REQUIRED NUMBER OF LANES OPEN TO TRAFFIC.

FOR THE PURPOSES OF THIS TRAFFIC CONTROL PLAN, THE FOLLOWING DEFINITIONS SHALL APPLY: PEAK HOURS

MON.-FRI. 6:00 A.M. TO 8:30 A.M. MON.-FRI. 4:00 P.M. TO 7:00 P.M.

OFF-PEAK HOURS

MON. -FRI. 9:00 A.M. TO 4:00 P.M.


NIGHTTIME HOURS


MON.-FRI. 7:00 P.M. TO 6:00 A.M. WEEKEND HOURS

FRI. 9:00 A.M. TO MON. 6:00 A.M.

TRAFFIC CONTROL PLAN NOTES

*INCLUDE TRAVEL DIRECTION (NORTHBOUND, SOUTHBOUND, EASTBOUND OR WESTBOUND)







THE CONTRACTOR MAY OPT TO SUBMIT AN ALTERNATE CONSTRUCTION SEQUENCE AND TRAFFIC CONTROL PLAN, SIGNED AND SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF TEXAS. SUCH PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR CONSIDERATION. HOWEVER, THE CONTRACTOR MUST FOLLOW THE TCP CONSTRUCTION PHASES AS SHOWN ON THE TCP PLANS.

THE CONTRACTOR SHALL BE PROHIBITED FROM WORKING SIMULTANEOUSLY ON MULTIPLE PHASES. THE CONTRACTOR SHALL COMPLETE ALL STEPS IN EACH PHASE PRIOR TO INITIATING AND COMMENCING THE SUBSEQUENT CONSTRUCTION PHASE.

IN ADDITION TO THE GENERAL NOTES REQUIREMENTS, THE FOLLOWING PROVISIONS GOVERN THIS CONTRACT.

SEQUENCE OF CONSTRUCTION.

CONSTRUCT THE VARIOUS ROADWAYIMPROVEMENTS IN ELEVEN (11) MAIN PHASES AS NOTED IN THIS NARRATIVE.

INSTALL PROJECT LIMIT SIGNS, ADVANCE WARNING SIGNS, AND CROSSROAD BARRICADES/SIGNS AS SHOWN ON THE TRAFFIC CONTROL PLANS (TCP), AND IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD), LATEST EDITION, AND/OR AS DIRECTED BY THE ENGINEER. THESE SIGNS SHALL BE ERECTED AND PLACED PRIOR TO COMMENCING ANY PROPOSED ROADWAY CONSTRUCTION AND SHALL REMAIN IN PLACE FOR THE DURATION OF THE PROJECT AND UNTIL FINAL ACCEPTANCE OF THE PROJECT BY TXDOT. PORTABLE CHANGEABLE MESSAGE BOARDS SHALL BE PLACED TO NOTIFY TRAVELING PUBLIC ON

PLANNED ROADWAY CLOSURE DATE(S) OR MOVEMENTS RESTRICTIONS A MINIMUM OF FIVE (5) WORKING DAYS IN ADVANCE OF ROADWAY CLOSURE.

PHASE I: US 77 (I 69E) SOUTHBOUND

LOCATION:

BRIDGE 1 - NBI: 21-031-0-0039-07-209 CROSSING SPUR 54

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- CLOSE RIGHT SHOULDER AND RIGHT LANE TO THRU TRAFFIC. REFER TO TCP (1-5a).
- DURING THIS PHASE, ACCESS ON SHOULDER AND RIGHT LANE UNDER US 77 SB THROUGH EB SPUR 54 SHALL NOT BE ALLOWED. CONTRACTOR SHALL PLACE TRAFFIC CONTROL DEVICES AS SHOWN ON THE TCP STANDARDS.
- 4. CLEAN AND PATCH EXISTING CONCRETE GIRDERS AS SHOWN ON PLANS.
- 5. REMOVE LANE CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 2: US 77 (I 69E) NORTHBOUND

LOCATION: BRIDGE 2 - NBI: 21-031-0-0039-07-304 CROSSING M ST

- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH WB M ST.
- 3. DURING THIS PHASE, ACCESS TO N FRONTAGE RD THROUGH U-TURN SHALL NOT BE ALLOWED. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AS NEEDED, REFER TO TCP (1-5).
- 4. CLEAN AND PATCH EXISTING CONCRETE RAIL AS SHOWN ON PLANS.
- 5. REMOVE LANE CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

Texas Department of Transportation						
TCP SEQUENCE OF CONSTRUCTION SHEET 1 OF 4						
FILE:		DN: RRE		1 1	RRE	ск:
CTXDOT	August 2017	CONT	SECT	JOB		HIGHWAY
	REVISIONS	0039	07	264		VARIOUS
		DIST		COUNTY		SHEET NO.
		PHR		VARIOUS		11

PHASE 3: US 77 (I 69E) BOTH DIRECTIONS

LOCATIONS:

BRIDGE 4 - NBI: 21-031-0-0039-07-306 CROSSING F ST. BRIDGE 3 - NBI: 21-031-0-0039-07-305 CROSSING F ST.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH EXPRESSWAY 83 (FRONTAGE RD.).
- 3. DURING THIS PHASE, ACCESS ALONG US 77 (I 69E) NORTH BOUND AND SOUTHBOUND SHALL NOT BE ALLOWED OVER F ST. GOING SOUTHBOUND FROM EXIT 24 TO ONRAMP AFTER RANGERVILLE RD. GOING NORTHBOUND FROM EXIT 24 TO ONRAMP AFTER J ST. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AS NEEDED. REFER TO TCP (6-6)-12.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRUTRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED FROM 7:00 PM - 6:00 AM.
- 5. CLEAN AND SEAL EXISTING CRACKS OVER BENTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 4: US 77 (I 69E) BOTH DIRECTIONS

LOCATIONS:

BRIDGE 6 - NBI: 21-031-0-0039-07-331 CROSSING FM 509 (HELEN MOORE RD). BRIDGE 5 - NBI: 21-031-0-0039-07-330 CROSSING FM 509 (HELEN MOORE RD).

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- DETOUR TRAFFIC THROUGH EXPRESSWAY 83 (FRONTAGE RD.).
- DURING THIS PHASE, ACCESS TO US 77 (I 69E) NORTH BOUND AND SOUTHBOUND SHALL NOT BE 3. ALLOWED OVER FM 509. GOING SOUTHBOUND FROM EXIT 22 TO ONRAMP AFTER FM 509. GOING NORTHBOUND FROM EXIT 22 TO ONRAMP AFTER FM509. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AS NEEDED. REFER TO TCP (6-6)-12.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRUTRAFFIC. THRU TRAFFIC WILL NOT 4 BE ALLOWED FROM 7:00 PM - 6:00 AM.
- 5. CLEAN AND SEAL EXISTING CRACKS OVER BENTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 5: US 77 (I 69E) NORTHBOUND

LOCATION:

- BRIDGE 7 NBI: 21-031-0-0039-07-366 CROSSING RESACA DE LOS FRESNOS.
- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- CLOSE LEFT SHOULDER TO THRU TRAFFIC. REFER TO TCP (1-5a).
- 3. SHALL PLACE TRAFFIC CONTROL DEVICES AS SHOWN ON THE TCP STANDARDS.
- CLEAN AND PATCH EXISTING CONCRETE COPINGS AS SHOWN ON PLANS.
- 5. REMOVE LANE CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

DURING THIS PHASE, ACCESS ON LEFT LANE ALONG US 77 NB SHALL NOT BE ALLOWED. CONTRACTOR

Texas Department of Transportation						
TCP SEQUENCE OF CONSTRUCTION						
FILE:	DN: R	RE	1	V: RRE	ск:	
CTxDOT August 201	7 сом	IT SECT	JOB		HIGHWAY	
REVISIONS	003	9 07	264		VARIOUS	
	DIST	r	COUNTY		SHEET NO.	
	PH	R	VARIOUS		12	

PHASE 6: US 77 (I 69E) BOTH DIRECTIONS

LOCATIONS:

BRIDGE 8 - NBI: 21-031-0-0039-07-376 CROSSING FM 732 UPRR US 77 BUS. BRIDGE 9 - NBI: 21-031-0-0039-07-377 CROSSING FM 732 UP RR US 77 BUS.

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- DURING THIS PHASE, ACCESS TO US 77 (I 69E) SOUTHBOUND AND NORTHBOUND SHALL NOT BE ALLOWED 3. OVER FM 432 UPRR US 77 BUS. GOING SOUTHBOUND FROM EXIT 18 TO ONRAMP AFTER EXIT 16. GOING NORTHBOUND FROM EXIT 17 TO ONRAMP AFTER FM 732. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AS NEEDED. REFER TO TCP (6-6)-12.
- 4. ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRUTRAFFIC. THRU TRAFFIC WILL NOT BE ALLOWED FROM 7:00 PM - 6:00 AM.
- 5. CLEAN AND SEAL EXISTING CRACKS AS SHOWN ON PLANS.
- REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 7: US 77 (I 69E) NORTHBOUND

LOCATION:

BRIDGE 10 - NBI: 21-031-0-0039-08-224 CROSSING RUNNELS ST (FR T/A).

- 1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD AND LOOP 499.
- 3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) NORTHBOUND SHALL NOT BE ALLOWED OVER RUNNELS ST (FR T/A). FROM EXIT 16 TO ONRAMP AFTER RUNNELS ST (FR T/A). CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AS NÉEDED. REFER TO TCP (6-6)-12.
- ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRUTRAFFIC. THRU TRAFFIC WILL NOT 4. BE ALLOWED FROM 7:00 PM - 6:00 AM.
- 5. CLEAN AND SEAL EXISTING CRACKS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

PHASE 8: US 77 (I 69E) NORTHBOUND

LOCATION: BRIDGE 11 - NBI: 21-031-0039-16-170 CROSSING SH 4 12-14 & 24TH ST.

- ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DETOUR TRAFFIC THROUGH FRONTAGE RD.
- EXIT 1A (SH 4) TO 12 ST. CONTRACTOR SHALL PLACE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AS NEEDED. REFER TO TCP (6-6)-12.
- 4. BE ALLOWED FROM 7:00 PM - 6:00 AM.
- 5. CLEAN EXISTING DRAIN INLETS JOINTS AS SHOWN ON PLANS.
- 6. REMOVE ROAD CLOSURE SETUPS AND PROCEED TO NEXT PHASE.

1. INSTALL THE DETOUR SIGNS, TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE

3. DURING THIS PHASE, ACCESS TO US 77 (I 69E) NORTHBOUND SHALL NOT BE ALLOWED FROM

ROADWAY SHALL BE CLOSED DURING CONSTRUCTION TO THRUTRAFFIC. THRU TRAFFIC WILL NOT

Texas Department of Transportation						
TCP SEQUENCE OF CONSTRUCTION SHEET 3 OF 4						
FILE:		DN: RRE		1	DW: RRE	ск:
C TxDOT	August 2017	CONT	SECT	JOB		HIGHWAY
	REVISIONS	0039	07	264		VARIOUS
		DIST		COUNTY		SHEET NO.
		PHR		VARIOL	IS	13

PHASE 9: SP 115 NB NORTHBOUND

LOCATION:

BRIDGE 12 - NBI: 21-109-0-1804-01-002 CROSSING MAIN FLDWY PILOT CHANNEL.

- 1. INSTALL THE TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL TH ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DEWATER AROUND PILES TO BE PATCHED.
- 3. CLEAN AND PATCH EXISTING PILES AS SHOWN ON PLANS.
- 4. REMOVE TCP SETUPS AND PROCEED TO NEXT PHASE.

PHASE 10: US 83 EASTBOUND ML & FR

LOCATION:

BRIDGE 13 - NBI: 21-109-0-0039-17-315 CROSSING EDINBURG MAIN CANAL.

- 1. INSTALL THE TRAFFIC CONTROL DEVICES, AND SW3P ELEMENTS AS SHOWN ON THE STANDARDS OR AS DIRECTED BY THE ENGINEER. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL THE ENGINEER HAS PROVIDED WRITTEN APPROVAL.
- 2. DEWATER AROUND PILES TO BE PATCHED.
- 3. CLEAN AND PATCH EXISTING PILES AS SHOWN ON PLANS.
- 4. REMOVE TCP SETUPS AND PROCEED TO NEXT PHASE.

Image: Texas Department of Transportation Bridge Division Standard						
TCP SEQUENCE OF CONSTRUCTION						
				5	SHEET	4 OF 4
		DN: RRE		CK:	DW: RRE	CK:
FILE:		BIG TOLE				
FILE:	August 2017	CONT	SECT	JOB		HIGHWAY
	August 2017 REVISIONS		SECT	_{јов} 264		HIGHWAY
	•	CONT				

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- The Barricade and Construction Standard Sheets (BC sheets) are intended 1. to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the 2. responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop. sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the 9. BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown ON BC(2). THE OBEY WARNING SIGNS STATE LAW sign. STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES. CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility" Apparel." or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.


COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- 1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEE	<u> </u>	0F	12			
Texas Department	of Tra	nsp	ortation		Sa Div	affic afety vision ndard
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS BC(1)-21						
FILE: bc-21.dgn	DN: T:	K DOT	ск: TxDOT	DW:	TxDOT	ск: TxDOT
© TxDOT November 2002	CONT	SECT	JOB		нI	GHWAY
REVISIONS 4-03 7-13	0039	07	264		VAF	RIOUS
9-07 8-14	DIST		COUNTY			SHEET NO.
5-10 5-21	PHR		VARIOUS	6		15
95						

SHEET 1 OF 12



TYPICAL	CONSTRUCTION	WARNING	SIGN	SIZE	AND	SPACING ^{1,5,6}

SIZE

Sign Number or Series	Conventional Road	Expressway/ Freeway
CW20 ⁴ CW21 CW22 CW23 CW25	48" × 48"	48" × 48"
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" × 36"	48" × 48"
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" × 48"	48" × 48"

SF	PACING
Posted Speed	Sign∆ Spacing "X"
MPH	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500 ²
60	600 ²
65	700 ²
70	800 ²
75	900 ²
80	1000 ²
*	* 3

★ For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

ightarrow Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.

REVISION

8-14

9-07

96

7-13 5-21

6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

									_
			L	EGE	ND]
		Ι	Туре	3 Bo	prri	cade			
		000	Chann	eliz	zing	Devic	es		
		4	Sign						
-		x	Warni Spaci TMUTC	ing s ing c D fo	sigr char or s	Constru Size torti sign uiremen	and he	ť	
			SHEE	T 2	OF	12			-
r. T)	Te	🗣 ° xas Depa	rtment o	of Tra	nsp	ortation		Sa Div	affic ofety vision ndard
e	BARF	RICAD PI	_		-	ONST IMI		UCT	ION
			BC	(2) -	-21			
	C 11 C	a 21 daa		DNA T		CK. TYDOT	0.00		CK. TYDOT
	-	oc-21.dgn November 200	02	dn: T: cont	xDOT sect	ск: TxDOT Job	DW:	ТхDOT ні	ck:TxDOT ghway

0039 07

DIST

264


COUNT

VARIOUS

VARIOUS

SHEET NO

16



As long as any of these conditions exist, the work zone speed limit signs should remain in place.


SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

- "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

Texas Departme	ent of Transp	oortation	S Di	raffic afety vision andard
BARRICADE			UCI	
WORK ZON		EDLI		
WORK ZON	NE SPE	EDLI	MI	
WORK ZON	NE SPE	ED LI	MI Txdot	T
WORK ZON FILE: bc-21.dgn © TXDOT November 2002 REVISIONS	NE SPE	ED LI -21	TxDOT	Т ск: ТхD0
WORK ZON FILE: bc-21.dgn © TxDOT November 2002	NE SPE	ED LI -21 	TxDOT	Т ск: Т.х.DO IGHWAY



GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer. Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports
- guide the traveling public safely through the work zone.
- the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- the Engineer can verify the correct procedures are being followed.
- damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

<u>DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)</u>

- regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- more than one hour. c.
- Short, duration work that occupies a location up to 1 hour.
- Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.) e.

SIGN MOUNTING HEIGHT

- as shown for supplemental plaques mounted below other signs.
- the ground. Long-term/Intermediate-term Signs may be used in Lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to
- appropriate Long-term/Intermediate sign height.

SIZE OF SIGNS

SIGN SUBSTRATES

- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave. centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300
- for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- intersections where the sign may be seen from approaching traffic. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely
- covered when not required.
- entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs. Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight. Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list. Sandbags shall only be placed along or laid over the base supports of the
- traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

No warranty of any for the conversion m its use. Texas Engineering Practice Act". TxDDT assumes no responsibility t results or damages resulting fro DISCLAIMER: The use of this standard is governed by the "Te kind is made by TxDDT for any purpose whatsoever. of this standard to other formats or for incorrect

All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and

The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in

The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZICD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a guestion regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so

The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or

Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used

The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in

Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting

Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.

The bottom of Long-term/intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except

The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZICD lists each substrate that can be used on the different types and models of sign supports. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6"

White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background. 3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of

Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any

When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the


98

SHEET 4 OF 12

st Texas Department of Transportation Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

	BC	(4) -	21				
.E:	bc-21.dgn	DN: T)	<dot< td=""><td>ск: TxDOT</td><td>DW:</td><td>TxDC</td><td>)T</td><td>ск: ТхDOT</td></dot<>	ск: TxDOT	DW:	TxDC)T	ск: ТхDOT
)TxDOT	November 2002	CONT	SECT	JOB			нIC	GHWAY
	REVISIONS	0039	07	264		١	/AR	OUS
9-07	8-14	DIST		COUNTY				SHEET NO.
7-13	5-21	PHR		VARIOUS	S			18



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to 2. eight characters per word), not including simple words such as "TO," "FOR, " "AT, " etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) 5. along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to 7. start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
 Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together, Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

			1
WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Nor thbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN SAT
Do Not	DONT	Saturday	SAT SERV RD
East	F	Service Road	
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SL IP S
Emergency Vehicle		South	-
Entrance, Enter	ENT	Southbound	(route) S SPD
Express Lane	EXP LN	Speed Street	SPU
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving			
Hazardous Material		Trovelers	TRVLRS
High-Occupancy	HOV	Tuesday	TUES
Vehicle		Time Minutes	TIME MIN
Highway	HWY	Upper Level	UPR LEVEL
Hour (s)	HR, HRS	Vehicles (s)	VEH, VEHS WARN
Information	INFO	Warning	
lt Is	ITS	Wednesday	WED WT LIMIT
Junction	JCT	Weight Limit West	
Left	LFT		
Left Lane	LFT LN	Westbound Wet Pavement	(route) W WET PVMT
Lane Closed	LN CLOSED	Will Not	WEIPVMI
Lower Level	LWR LEVEL		
Maintenance	MAINT		

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

	ΠP			
FREEWAY CLOSED X MILE		FRONTAGE ROAD CLOSED		RO X
ROAD CLOSED AT SH XXX		SHOULDER CLOSED XXX FT		FL XX
ROAD CLSD AT FM XXXX		RIGHT LN CLOSED XXX FT		R I NA XX
RIGHT X LANES CLOSED		RIGHT X LANES OPEN		ME TR XX
CENTER LANE CLOSED		DAYTIME LANE CLOSURES		L GI X X
NIGHT LANE CLOSURES		I-XX SOUTH EXIT CLOSED		DI X
VARIOUS LANES CLOSED		EXIT XXX CLOSED X MILE		RO/ I S⊦
EXIT CLOSED		RIGHT LN TO BE CLOSED		XX
MALL DRIVEWAY CLOSED		X LANES CLOSED TUE - FRI		TR S XX
XXXXXXXX BLVD CLOSED	×	LANES SHIFT in	Phase	1 must

Other Cor	ndition List
ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	L ANE S SH I F T

Action to Take/Effect on Travel List MERGE FORM RIGHT X LINES RIGHT DETOUR USE XXXXX NEXT RD EXIT X EXITS USE USE EXIT EXIT XXX I-XX NORTH STAY ON USE US XXX I-XX F SOUTH TO I-XX N TRUCKS WATCH USE FOR US XXX N TRUCKS WATCH EXPECT FOR DELAYS TRUCKS PREPARE EXPECT DELAYS то STOP REDUCE END SPEED SHOULDER XXX FT USE USE WATCH OTHER FOR ROUTES WORKERS STAY ĪΝ LANE

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS. 2. The 1st phase (or both) should be selected from the
- "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate. 2. Roadway designations IH, US, SH, FM and LP can be interchanged as
- appropriate.
- be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary. 7. FT and MI. MILE and MILES interchanged as appropriate.
- 8. AT. BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a
- location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

be used with STAY IN LANE in Phase 2.


FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the some size arrow.

Roadway

designation # IH-number, US-number, SH-number, FM-number


Phase 2: Possible Component Lists




* * See Application Guidelines Note 6.

XX AM

EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can















GENERAL NOTES

- 1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS


- Pre-gualified plastic drums shall meet the following requirements:
- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- 3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- 3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.






DETECTABLE PEDESTRIAN BARRICADES

- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures. 2. Where pedestrians with visual disabilities normally use the
- closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5, Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.

È.



(Maximum Sign Dimension)

Chevron CW1-8, Opposing Traffic Lane

Divider, Driveway sign D70a, Keep Right

R4 series or other signs as approved

by Engineer



12" x 24" Vertical Panel mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums


SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- 1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- 3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- 5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- 6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- 8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SH	EET 8	OF	12			
Texas Department	nt of Tra	nsp	ortation		Sa Div	affic nfety rision ndard
BARR I CADE CHANNEL						
В	C (8) -	-21			
FILE: bc-21.dgn	DN: T:	xDOT	ск: TxDOT	DW:	TxDOT	ск: TxDOT
CTxDOT November 2002	CONT	SECT	JOB		нI	GHWAY
REVISIONS	0039	07	264		VAF	RIOUS
4-03 8-14 9-07 5-21	DIST		COUNTY			SHEET NO.
7-13	DUD			-		SHEET NO.
(-1)	PHR		VARIOU	S		22

See Ballast

Note 3



- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the out side of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact. 2. LCDs may be used instead of a line of cones or drums.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length
- should be designed to optimize road user operations considering the available geometric conditions. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

or may be mounted on drums

4. The OTLD shall be orange with a black nonreflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	D	Minimur esirab er Lena X X	le gths	Spacin Channe	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	2	150'	1651	180'	30'	60′
35	$L = \frac{WS^2}{60}$	205'	225′	245'	35′	70′
40	60	265'	295′	320'	40′	80′
45		450'	495′	540'	45′	90′
50		500'	550'	600'	50 <i>'</i>	100′
55	L=WS	550'	605′	660 <i>′</i>	55 <i>'</i>	110′
60	L - 11 S	600 <i>'</i>	660 <i>'</i>	720'	60 <i>'</i>	120′
65		650′	715′	780′	65 <i>'</i>	130'
70		700′	770′	840'	70′	140'
75		750'	825′	900'	75′	150'
80		800'	880′	960'	80 <i>'</i>	160'

XX Taper lengths have been rounded off. L=Length of Taper (FT.) W=Width of Offset (FT.) S=Posted Speed (MPH)


SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12 Traffic Safety Division Standard Texas Department of Transportation

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

		BC	(9) -	- 2 1			
FILE:	bc-21.dgn		DN: T)	K DOT	ск: TxDOT	DW:	TxDOT	ск: TxDOT
(C) TxDOT	November 2002		CONT	SECT	JOB		н	IGHWAY
	REVISIONS		0039	07	264		VA	ARIOUS
9-07	8-14		DIST		COUNTY			SHEET NO.
7-13	5-21		PHR		VARIOU	S		23
107						_		

DC/01 21



	SHEE	r 10) 0	F 12			
	★° ēxas Department o	of Tra	nsp	ortation		È	Traffic Safety Division tandard
	RICADE AI CHANNELI BC	ZIN	IG		I		
FILE:	bc-21.dgn	DN: T:	K DOT	ск: TxDOT	DW:	TxDO	T CK: TxDOT
(C) TxDOT	November 2002	CONT	SECT	JOB			HIGHWAY
	REVISIONS	0039	07	264		١	ARIOUS
9-07	8-14 5-21	DIST		COUNTY			SHEET NO.
7-13	5-21	PHR		VARIOU	s –		24

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 3. Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- 5. When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.

MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- 4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- 6. Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECU TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARK TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guiden shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by Engineer or designated representative. Sampling and testing is m normally required, however at the option of the Engineer, either or "B" below may be imposed to assure quality before placement or roadway.
 - A. Select five (5) or more tabs at random from each lot or sh and submit to the Construction Division, Materials and Pav Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix (5) tabs at 24 inch intervals on an asphaltic pavement in straight line. Using a medium size passenger vehicle or pir run over the markers with the front and rear tires at a sp of 35 to 40 miles per hour, four (4) times in each direction more than one (1) out of the five (5) reflective surfaces be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARK


- Raised pavement markers used as guidemarks shall be from the ap product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applie butyl rubber pad for all surfaces, or thermoplastic for concretsurfaces.


Guidemarks shall be designated as:

YELLOW - (two amber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

	DEPARTMENTAL MATERIAL SPECIFICA	
	PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
	TRAFFIC BUTTONS EPOXY AND ADHESIVES	DMS-4300 DMS-6100
EW	BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6100
57	PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
	TEMPORARY REMOVABLE, PREFABRICATED	
	PAVEMENT MARKINGS	DMS-8241
e pad	TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242
ן	A list of prequalified reflective raised pavement non-reflective traffic buttons, roadway marker pavement markings can be found at the Material I web address shown on BC(1).	tabs and othe
_		
5		
ne ent		
nt		
ve D, No II		
ved		
Veu		
-		
	SHEET 11 OF 12	Traffic
		Traffic Safety Division
	SHEET 11 OF 12	Safety
		Safety Division
		Safety Division Standard
	Texas Department of Transportation	Safety Division Standard
	Texas Department of Transportation	Safety Division Standard
	Texas Department of Transportation BARRICADE AND CONST PAVEMENT MARKIN	RUCTIO
	BARR I CADE AND CONST PAVEMENT MARK II BC (111) - 21	Safety Division Standard
	Texas Department of Transportation BARR I CADE AND CONST PAVEMENT MARK II BC (111) - 21 FILE: DC-21.dgn DNL TXDOT CKL TXDOT CONT SECT JOB CONT SECT JOB	Safety Division Standard RUCTIOI NGS
	Texas Department of Transportation BARR CADE AND CONST PAVEMENT MARK I BC (111) - 21 FILE: DC-21. dgn	Safety Division Standard RUCTIOI NGS

105





LEGEND									
	Type 3 Barricade		Channelizing Devices						
□‡	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)						
Ē	Trailer Mounted Flashing Arrow Board	Ś	Portable Changeable Message Sign (PCMS)						
-	Sign	2	Traffic Flow						
\bigtriangleup	Flag	ЦO	Flagger						

Posted Speed X	Formula	Minimum Desirable Taper Lengths X X		Spacir Channe		Minimum Sign Spacing "x"	Suggested Longitudina। Buffer Space	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"
30	ws ²	150'	165'	180'	30′	60′	120'	90'
35	$L = \frac{WS}{60}$	205′	225′	245'	35′	70′	160'	120'
40	80	265′	295′	320'	40′	80′	240'	155′
45		450'	495 <i>'</i>	540'	45′	90′	320'	1951
50		500'	550ʻ	600′	50 <i>'</i>	100'	400′	240′
55	L=WS	550'	605 <i>'</i>	660′	55 <i>'</i>	110′	500'	295′
60	L #3	600 <i>'</i>	660 <i>'</i>	720'	60 <i>'</i>	120′	600′	350′
65		650'	715′	780′	65 <i>'</i>	130'	700'	410′
70		700′	770′	840'	70′	140′	800′	475′
75		750'	825′	900′	75′	150′	900′	540′

🗙 Conventional Roads Only

XX Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)


TYPICAL USAGE									
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY					
		1							

GENERAL NOTES

1. Flags attached to signs where shown, are REQUIRED.

- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- 3. Channelizing devices used to close lanes may be supplemented with the Chevron Alignment Sign placed on every other channelizing device. Chevrons may be attached to plastic drums as per BC Standards.
- 4. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 5. Additional Shadow Vehicles with TMAs may be positioned in each closed lane, on the shoulder or off the paved surface, next to those shown in order to protect a wider work space.

) for lane ils if a is needed	Texas L	Department of Tr	ansp	oortation		Traffic perations Division tandard
ane which required ramp.	L	AFFIC CO ANE CLOS DIVIDED	SUF	RES	FOR	N
20RP-3D " X 48"		TCP (1			-	
	FILE: tcp1-5-1		ТОС	CK: TXDOT	DW: TxDOT	CK: TxDOT
RAMPS	\sim	uary 2012 cont	SECT	JOB		HIGHWAY
	2-18 REVISI	ons 003	9 07	264	N	ARIOUS
	2 10	DIST		COUNTY		SHEET NO.
		PHF	2	VARIO	US	27
	1551					



- bottom of the sign.

¥A shadow ver a Truck Mour typically re vehicle equi be used if 30' to 100' area of crew adversely af performance.

LEGEND											
	z Type 🛛	Type 3 Barricade				Ch	annelizi	ing Devices			
] Неалу	Heavy Work Vehicle					uck Mour tenuator				
Ē		Trailer Mounted Flashing Arrow Board			M			Changeable ign (PCMS)			
-	Sign	Sign			\Diamond	Tr	offic F	low			
$\langle \rangle$	Flag	Flag			LO	۴ı	agger				
Posted Speed	Formula	Minimum Desirable Taper Lengths "L" X X		le	- Spa Chan	icin ine I	l Maximum ng of izing ces	Suggested Longitudinal Buffer Space			
		10' Offset	11' Offset	12' Offse	On a t Taper		On a Tangent	"B"			
45		450'	495′	540'	45′		90'	1951			
50		500'	550′	600	50′		100'	240'			
55	L=WS	550'	605 <i>'</i>	660	′ 55 <i>′</i>		110'	295′			
60	L-W3	600'	660′	720'	60′		120'	350′			

80 800' 880' 960' 80' 160' 615' XX Taper lengths have been rounded off.

650' 715' 780

700' 770' 840'

750' 825' 900'

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

65*'*

70'

75′

130'

140'

150'

410'

475'

540'

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	1	1	4					

GENERAL NOTES

65

70

75

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

2. Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer. 3. All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.

4. The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction. 5. Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.

6. Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.

7. Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing. 8. The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD. 9. Warning signs for intermediate term stationary work should be mounted at 7' to the

10.Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.


11. When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion. 12.For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.

13. The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

ticle equipped with the Attenuator is equired. A shadow pped with a TMA shall t can be positioned in advance of the exposure without fecting the work		Texas Depo Traffic Opera TRAFFIC REEWAY TC	tions L CON AN	Divisi UTF E	ion Standa ROL	PL SU	_AN Res	
	FILE:	tcp6-1.dgn	DN: TxD	_	CK: TXDOT	r	TxDOT	ск: TxDOT
	© TxDOT	December 2023	CONT	SECT	JOB		HI	SHWAY
	8-12	REVISIONS	0039	07	264		V,	ARIOUS
	0-12		DIST		COUNTY			SHEET NO.
			PHR		VARIOL	JS		28

201





	LEGEND								
<u>~~~~</u>	Type 3 Barricade		Channelizing Devices						
□¤	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)						
Ð	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)						
-	Sign	2	Traffic Flow						
$\langle \lambda \rangle$	Flag		Flagger						

Posted Speed	Formula	Minimum Desirable Taper Lengths "L" XX		Špacir Channe		Suggested Longitudinal Buffer Space	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	"B"
45		450′	495′	540'	45′	90′	1951
50		500'	550′	600'	50 <i>'</i>	100'	240'
55	L=WS	550'	605 <i>'</i>	660'	55 <i>'</i>	110'	295′
60	L-#3	600 <i>'</i>	660 <i>'</i>	720′	60 <i>'</i>	120'	350'
65		650′	715′	780′	65′	130′	410′
70		700′	770'	840 <i>′</i>	70′	140'	475′
75		750'	825 <i>'</i>	900ʻ	75′	150'	540'
80		800'	880′	960'	80′	160'	615'

XX Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE								
MOBILE	AOBILE SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY							
	1	1	1					

GENERAL NOTES

 All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

- ADDED LANE Symbol (CW4-3) sign may be omitted when sign between ramp and mainlane can be seen from both roadways.
 See "Advance Notice List" on BC(6) for recommended date
- See "Advance Notice List" on BC(6) for recommended date and time formatting options for PCMS Phase 2 message.
 The END ROAD WORK (G20-2) sign may be omitted when it
- conflicts with G20-2 signs already in place on the project.


*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Del Traffic Oper		of Trans Ion Standard	portai	tion
TRAFFIC	CONT			
IRAFFIC	CONT		LAN	l
WORK AR	FA NF			
WORK AR	LA NE			
WORK AR	LA NE	,AR R#	4. 4 11	
			-	
		.an n/	-	
		-2) - 1	-	ск: ТхД
T(CP (6-	-2) - 1	2 TxDOT	CK: TXD
FILE: tcp6-2.dgn	CP (6-	- 2) - 1	2 TxDOT	
FILE: tcp6-2.dgn © TxDOT February 1994	DN: TXDOT CONT SECT	- 2) - 1 ck: txdot dw: job	2 TxDOT	IGHWAY



DATE:



	LEGEND								
<u>~ ~ ~ ~ ~</u>	Type 3 Barricade		Channelizing Devices						
	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)						
Ð	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)						
4	Sign	2	Traffic Flow						
$\langle \rangle$	Flag	٩	Flagger						

Posted Speed	Formula	Desirable Spacin Taper Lengths "L" Channe Formula <u>X X</u> Dev		Suggested Maximum Spacing of Channelizing Devices		Suggested Longitudinal Buffer Space	
		10' Offset	11' Offset			On a Tangent	"В"
45		450′	495′	540'	45′	90′	195'
50		500'	550'	600′	50 <i>'</i>	100′	240′
55	L=WS	550'	605′	660′	55 <i>'</i>	110'	295′
60	2 113	600 <i>'</i>	660 <i>'</i>	720'	60 <i>'</i>	120′	350′
65		650 <i>'</i>	715′	780′	65 <i>'</i>	130'	410′
70		700'	770'	840'	70′	140′	475′
75		750'	825′	900′	75′	150′	540 <i>′</i>
80		800'	880'	960'	80 <i>'</i>	160′	615′

XX Taper lengths have been rounded off. L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
	1	1	4			


GENERAL NOTES:

 All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

USE TREET A EXIT	Texas De Traffic Open		of Trans ion Standard	-	tion
on when ered	TRAFFIC	CONT	ROL P	LAN	١
				-	-
USE			// WALLY	J A 14	D
XIT XX	WORK ARE	A BEI	IOND I	KAM	Ρ
			- 3) - 1	•	Ρ
approx.)			-3)-1	•	Ск: ТхDOT
approx.)	T	CP (6	- 3) - 1	1 2	
approx.)	FILE: tcp6-3.dgn © TxDOT February 1994 REVISIONS		- 3) - 1	12 • TxDOT	ск: TxDOT
approx.)	FILE: tcp6-3.dgn ©TxDOT February 1994	CP (6	- 3) - 1	12 • TxDOT	CK: TxDOT



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDDT for any purpose whatsoever. TxDDT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

LEGEND									
	z Type	Type 3 Barricade				Cr	nannelizi	ing Devices	
] Heavy	Heavy Work Vehicle					Truck Mounted Attenuator (TMA)		
		er Mou ing Ar		bard	M	Portable Changeable Message Sign (PCMS)			
		ing Ar ution		bard	\diamondsuit	т	raffic F	low	
4	Sign	Sign							
Posted Speed	Formula	D Taper 10'	Minimur esirab Lengtl XX 11' Offset	le hs "L"	Spa Chan D On a	icir ine iev	d Maximum ng of Lizing ices On a Tangent	Suggested Longitudinal Buffer Space "B"	
45		450'	495′		45'		90'	195'	
50		500'	550'	600′	50'		100′	240'	
55	L=WS	550'	605′	660′	55′	•	110'	295′	
60	L - # 3	600'	660 <i>'</i>	720′	60'		120'	350'	
65		650 <i>'</i>	715'	780′	651	'	130'	410′	
70		700'	770′	840′	70'		140'	475′	
75		750'	825′	900′			150'	540'	
80		800'	880′	960′	80'	'	160′	615'	

XX Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE							
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY			
	1	1	4				

GENERAL NOTES


 All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

- Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE RIGHT," recommended speed, delay, exit information, or other specific warnings.
- 3. Where queuing is anticipated beyond signing shown, additional PCMS signs, other warning signs, devices or Law Enforcement Officers should be available to warn approaching high speed traffic of the end of the queue, as directed by the Engineer.
- 4. Entrance ramps located from the advance warning area to the exit ramp should be closed whenever possible.
- The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.
- 6. The allotted amount of nights for road cloures in each county are given: Hidalgo - 4 nights Cameron - 4 nights Zapata - 2 nights

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation Traffic Operations Division Standard						
TRAFFIC						N
FREEWA	YC	LC)SUR	E		
ТС	:P (6	6 -	6) -	1	2	
FILE: tcp6-6.dgn	DN: TxDC	T	ск: TxDOT	DW:	TxDOT	ск: TxDOT
		SECT	JOB			
©⊺xDOT February 1994	CONT S	DEUI	JOB			IGHWAY
© TxDOT February 1994 REVISIONS	0039		264			IIGHWAY VARIOUS
0						



LEGEND							
	Channelizing Devices	\oplus	Control Position (CP)				
€	Portable Changeable Message Sign (PCMS)		Barrier Vehicle with Truck Mounted Attenuator				
	Law Enforcement Officer's Vehicle(LEOV)	∿	Traffic Flow				

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
	 ✓ 					

GENERAL NOTES

1.All traffic control devices shall conform with the latest edition of the Texas Manual on Uniform Traffic Control Devices (TMUTCD). Additional guidelines for traffic control devices may be found in the TMUTCD. Signs conflicting with the roadway closure sequence should be completely removed or covered. Additional traffic control devices may be required for closure of access roads, cross streets, exit and entrance ramps as directed by the Engineer.

2.Low enforcement officers and all workers involved should review and understand all procedures before the roadway closure sequence begins. Pre-work meetings may be held for this purpose. Local emergency services and media should have advance notification of roadway closure, expected dates and approximate times of closures.

3.Law enforcement officers shall be in uniform and have jurisdiction in the locale of the work area. An additional WARNING Law Enforcement Officer's Vehicle (LEOV) may be used on the median side of the roadway where median shoulder width permits (See sequence #9).

4. The roadway closure should be during off-peak hours, as shown in the plans, or as directed by the Engineer.


5. Work should be limited to approximately 15 minutes maximum duration unless otherwise directed by the Engineer based on existing roadway conditions. If the work is not complete within 15 minutes, or if the end of the traffic queue extends past the most distant advance warning signs, the work area should be cleared of all equipment, materials, personnel, and other items, and the roadway reopened. When the queue has dissipated and the traffic flow appears normal the roadway closure sequence may be repeated.

6.For traffic volumes greater than 1000 Passenger Cars Per Hour Per Lane (PCPHPL), or for roadway closures that exceed 15 minutes, see details elsewhere in the plan.

7. If traffic queues beyond the advance warning signs during one road closure sequence, the advance warning should be extended prior to repeating the road closure sequence. When possible, PCMS signs should be located in advance of the last available exit prior to the closure to allow motorists the choice of an alternate route.

THIS PLAN IS INTENDED TO BE USED AT LOCATIONS/TIMES WHEN TRAFFIC VOLUMES ARE LESS THAN 1000 PASSENGER CARS PER HOUR PER LANE.


1	Texas Dep Traffic Oper					oortai	tion
S	TRAFFIC	RAT	0	N FR	E	EWA	•
	CLOSUR					_	
FILE:	TC		6-	QUEN • 7) -	• 1	_	CK: TXDOT
FILE:	tcp6-7. dgn	:P (6-	- 7) -	• 1	2 TxDOT	CK: TXDOT
	tcp6-7.dgn	P (6 - DOT SECT	- 7) -	• 1	2 TxDOT	
	tcp6-7.dgn February 1998 REVISIONS	P (6 - DOT SECT	- 7) - ск: ТхDOТ ЈОВ	• 1	2 TxDOT	IGHWAY




CAMERON COUNTY LOCATION MAP

RIDGE NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	GPS COORDINATES
1	21-031-0-0039-07-209	US 77 SB	SPUR 54	26.19534378, -97.71991612
2	21-031-0-0039-07-304	US 77 NB	M ST	26.17953956, -97.71002523
7	21-031-0-0039-07-366	US 77 NB	RESACA DE LOS FRESNOS	26.13092589, -97.64230785







REPAIR 3 NBI: 21-031-0-0039-07-209 Span #2 - 3rd West Girder

NBI			REPAIR WIDTH		TOTAL (SF)	CNC STR REPAIR (STANDARD)	BIRD EXCLUSION METHOD
	IBI HIGHWAY CROSSED FEATURE/ ROADWAY	(FT)	(FT)	(31)	0429	5029	
					7009	7001	
						SF	SF
1-0-0039-07-209	US 77 SB	SPUR 54	3.5	1.55	5.4	5.4	5.4
1-0-0039-07-209	US 77 SB	SPUR 54	5.083	1.54	7.83	7.83	7.83
1-0-0039-07-209	US 77 SB	SPUR 54	5.083	1.54	7.83	7.83	7.83
				TOTALS		21.06	21.06


SEQUENCE OF CONSTRUCTION

ADDRESS AFFECTED AREA.

CLEAN UP AREA, AND MOVE TO NEXT LOCATION.

GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

N.T.S		Sh	eet 1 of	4	
Texas Department	of Tra	nsp	ortation		Bridge Division Standard
SUPER: SPAL					
FILE:	DN: RRE		ск:	DW: RRE	CK:
CTxDOT November 2023	CONT	SECT	JOB		HIGHWAY
REVISIONS	0039	07	264		VARIOUS
	DIST		COUNTY		SHEET NO.
	PHR		VARIOL	JS	34




	BRIDGE NO.	REPAIR NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	REPAIR WIDTH (FT)	REPAIR ⁻ LENGTH (FT)		CNC STR REPAIR (STANDARD)	BIRD EXCLUSION METHOD
					RUADVAY				0429	5029
									7009	7001
									SF	SF
	1	4	21-031-0-0039-07-209	US 77 SB	SPUR 54	1.54	1.75	2.7	2.7	2.7
	2	5	21-031-0-0039-07-304	US 77 NB	M ST	0.85	1.35	1.15	1.15	0
							TOTALS		3.85	2.7

SET UP TCP.

REMOVE TCP.

REPAIR 4 NBI: 21-031-0-0039-07-209 Span #2 - 4th to last to the West Girder



0.85*1.35 = 1.15 sqft

REPAIR 5 NBI: 21-031-0-0039-07-304 EAST BRIDGE RAIL NW ABUTMENT

SEQUENCE OF CONSTRUCTION

ADDRESS AFFECTED AREA.

CLEAN UP AREA, AND MOVE TO NEXT LOCATION.

GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

N.T.S	Sheet 2 of 4								
Texas Department	of Transportation				Bridge Division Standard				
SUPERSTRUCTURE SPALL REPAIR									
FILE:	DN: RRE	DN: RRE CK:		DW: F	RRE	СК:			
CTxDOT November 2023	CONT	SECT	JOB		не	HIGHWAY			
REVISIONS	0039	07	264		VA	RIOUS			
	DIST	COUNTY			SHEET NO.				
	PHR		VARIOUS			35			




	BRIDGE NO.	REPAIR NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	REPAIR WIDTH (FT)	REPAIR LENGTH (FT)	TOTAL (SF)	CNC STR REPAIR (STANDARD) 0429 7009 SF
	7	6	21-031-0-0039-07-366	US 77 NB	RESACA DE LOS FRESNOS	6.104	1.208	7.37	7.37
		7	21-031-0-0039-07-366	US 77 NB	RESACA DE LOS FRESNOS	5.2083	2.4	12.5	12.5
		8	21-031-0-0039-07-366	US 77 NB	RESACA DE LOS FRESNOS	1.875	4.146	7.77	7.77
Į							TOTALS		27.64

SET UP TCP.

REMOVE TCP.

REPAIR 6 NBI: 21-031-0-0039-07-366 Coping of retaining wall at North bridge corner at NW backwall



1.875*4.146 = 7.77 sqft

REPAIR 7 & 8 NBI: 21-031-0-0039-07-366 Coping of retaining wall at North bridge corner at NW backwall

SEQUENCE OF CONSTRUCTION

ADDRESS AFFECTED AREA.

CLEAN UP AREA, AND MOVE TO NEXT LOCATION.

GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

N.T.S	Sheet 3 of 4								
Texas Department	of Transportation				D	Bridge Division Standard			
SUPERSTRUCTURE SPALL REPAIR									
FILE:	DN: RRE		CK: DW: RRE		RRE	ск:			
CTxDOT November 2023	CONT	SECT	JOB			HIGHWAY			
REVISIONS	0039	07	264		VARIOUS				
	DIST		COUNTY			SHEET NO.			
	PHR		VARIOL	JS		36			



BRIDGE NO.	REPAIR NO.	NBI	HIGHWAY		REPAIR WIDTH (FT)		TOTAL (SF)	CNC STR REPAIR (STANDARD 0429 7009 SF
7	9	21-031-0-0039-07-366	US 77 NB	RESACA DE LOS FRESNOS	6.104	1.208	7.37	7.37
						TOTALS		7.37

REPAIR 9 NBI: 21-031-0-0039-07-366 Coping of retaining wall at East bridge corner

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose wh TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

SEQUENCE OF CONSTRUCTION

SET UP TCP.


ADDRESS AFFECTED AREA.

CLEAN UP AREA, AND MOVE TO NEXT LOCATION.

REMOVE TCP.

GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

N.T.S		Sł	neet 4 of	4	
Texas De	epartment of	Trans	oortation	D	Pridge Division Standard
S	UPERS SPALL				
FILE		RRE	ск:	DW: RRE	ск:
CTxDOT November	2023 co	ONT SECT	JOB		HIGHWAY
REVISION	s 00	39 07	264		VARIOUS
	DI	вт	COUNTY	r	SHEET NO.
	PH	IR	VARIOL	JS	37




HIDALGO COUNTY LOCATION MAP

NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	GPS COORDINATES		
21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	26.17322222, -98.25042222		
21-109-0-0039-17-315	US 83 EB ML & FR	EDINBURG MAIN CANAL	26.22469099, -98.35635648		

BRIDGE NO.

12

Texas Department of Transportation								
SUBSTRUCTURE SPALL REPAIRS								
HIDALG LOCA				-				
FILE:	DN: RRE		ск:	DW: RRE		ск:		
CTxDOT August 2017	CONT	SECT	JOB		HIG	HWAY		
REVISIONS	0039	07	264		VAF	OUS		
	DIST		COUNTY	· · ·		SHEET NO.		
	PHR		VARIOL	JS		38		



	BRIDGE NO.		NBI	HIGHWAY	CROSSED FEATURE/ REPAIR REPAIR ROADWAY WIDTH LENGTI	REPAIR	TOTAL	CNC STR REPAIR (STANDARD)	BIRD EXCLUSIO METHOD	
		REPAIR NO. NBI	HIGHWAY	ROADWAY	(FT)	(FT)	(SF)	0429 7009	5029 7001	
┢									SF	SF
	12	1	21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	1.33	13	17.33	17.33	5.4
		2	21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	1.33	5	6.67	6.67	7.83
Г							TOTALS		24	24


SEQUENCE OF CONSTRUCTION

SET UP FO CONDUCT ADDRESS CLEAN UF AFFECTE

REPAIR 1 NBI: 21-109-0-1804-01-002 BENTS 2 & 3 FRACTURES IN PILES



REPAIR 2 NBI: 21-109-0-1804-01-002 FAILED PATCH AT 2ND PILE FROM EAST AT BENT 3 LOOKING SOUTH



NOTE: PROP. FORM SETTING WILL NOT BE PAID FOR DIRECTLY BUT WILL BE SUBSIDIARY TO THE BID ITEM INVOLVED.

SET UP FORMS AROUND AFFECTED AREA. (SEE DETAIL BELOW) CONDUCT DEWATERING OPERATIONS.

ADDRESS AFFECTED AREA.

CLEAN UP AREA, DISASSEMBLE FORMS, AND MOVE TO NEXT AFFECTED AREA.

GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

4′ (TYP.)


N.T.S			Sh	eet 1 of	3	
	★ ° Texas Department	of Tra	nsp	ortation		Bridge Division Standard
SUBST SPAL				-		
FILE:		DN: RRE		ск:	DW: RRE	CK:
CT XDOT	November 2023	CONT	SECT	JOB		HIGHWAY
	REVISIONS	0039	07	264		VARIOUS
		DIST		COUNTY		SHEET NO.
		PHR		VARIOU	10	39



	BRIDGE NO.	REPAIR NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	REPAIR WIDTH (FT)	REPAIR LENGTH (FT)	TOTAL	CNC STR REPAIR (STANDARD)	BIRD EXCLUSIO METHOD
	BRIDGE NO.	REFAIR NO.	NDI	HIGHWAT				(SF)	0429	5029
									7009	7001
									SF	SF
	12	3	21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	1.33	8.875	11.83	11.83	11.83
		4	21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	1.33	5	6.7	6.7	6.7
		5	21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	1.33	11.42	15.2	15.2	15.2
Г							TOTALS		33.73	33.73

16"/12" * 8-'10 1/2" = 11.83 sqft

REPAIR 3 & 4 NBI: 21-109-0-1804-01-002 BENTS 2 & 3 FRACTURES IN PILES



REPAIR 5 NBI: 21-109-0-1804-01-002 CRACK IN 4TH PILE FROM THE EAST IN BENT 3 LOOKING SOUTH EAST

SEQUENCE OF CONSTRUCTION

SET UP FORMS AROUND AFFECTED AREA. (SEE DETAIL BELOW)

CONDUCT DEWATERING OPERATIONS.

ADDRESS AFFECTED AREA.

CLEAN UP AREA, DISASSEMBLE FORMS, AND MOVE TO NEXT AFFECTED AREA.


GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional Information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

(TYP.) — 4 ′

N.T.S.


NOTE: PROP. FORM SETTING WILL NOT BE PAID FOR DIRECTLY BUT WILL BE SUBSIDIARY TO THE BIDS ITEMS INVOLVED.

N.T.S			Sh	eet 2 C)F 3	
	🗲 ° Texas Department	t of Tra	nsp	ortatio		Bridge Division Standard
	SUBS SPA					
FILE:		DN: RRE		ск:	DW: RRE	ск:
CTXDOT	November 2023	CONT	SECT	JOB		HIGHWAY
	REVISIONS	0039	07	264	ļ.	VARIOUS
		DIST		COUNT	ry .	SHEET NO.
		PHR		VARIO	110	40




BRIDGE NO.	REPAIR NO.	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	REPAIR		TOTAL	CNC STR REPA I R (STANDARD)	BIRD EXCLUSION METHOD
BRIDGE NO.	REPARTNO.	AIC NO. NOI HIGHWAT RUADWA	RUADWAY	(FT)	(FT)	(SF)	0429	5029	
							7009	7001	
								SF	SF
12	6	21-109-0-1804-01-002	SP 115 NB	MAIN FLDWY PILOT CHANNEL	1.33	6	8	8	8
13	7	21-109-0-0039-17-315	US 83 EB ML& FR	EDINBURG MAIN CANAL	1.33	1.38	1.83	1.83	1.83
13	8	21-109-0-0039-17-315	US 83 EB ML& FR	EDINBURG MAIN CANAL	1.33	2	2.66	2.66	2.66
						TOTALS		12.49	12.49

REPAIR 6 NBI: 21-109-0-1804-01-002 BENTS 2 & 3 FRACTURES IN PILES



1.333' * 2' = 2.66 sf



REPAIR 7 & 8 NBI: 21-109-0-0039-17-315 PILES 2 & 3 FROM SW TO SE BENT *WATER LEVEL ON 04/06/2023 WAS APPROX. 4 FT WILL BE ADDED TO REPAIR CY

SEQUENCE OF CONSTRUCTION

SET UP FORMS AROUND AFFECTED AREA. (SEE DETAIL BELOW) CONDUCT DEWATERING OPERATIONS.


ADDRESS AFFECTED AREA.

CLEAN UP AREA, DISASSEMBLE FORMS, AND MOVE TO NEXT AFFECTED AREA.

GENERAL NOTES: Refer to Item 429 and Concrete Repair Manual for additional Information not shown here Vertical & Overhead Repairs that are to be done on bridge rails shall be performed from the outside of the roadway.

-4′ (TYP.)

N.T.S			Sh	eet 3 O	F 3	
Texa	∽ [®] as Department	of Tra	nsp	ortation	D	ridge livision tandard
	SUBS ⁻ SPAL					
FILE:		DN: RRE		ск:	DW: RRE	CK:
CTXDOT No	ovember 2023	CONT	SECT	JOB		HIGHWAY
0	ovember 2023 REVISIONS	CONT 0039	SECT	_{јов} 264		HIGHWAY VARIOUS
0						




CAMERON COUNTY LOCATION MAP

	BRIDGE NO.	BRIDGE NBI HIGHWAY		CROSSED FEATURE/ ROADWAY	GPS COORDINATES
Γ	3	0039-07-305	US 77 SB	F St	26.17512128, -97.70195343
Γ	4	0039-07-306	US 77 NB	F St	26.17531965, -97.70253585
	5	0039-07-330	US 77 SB	FM 509	26.14979925, -97.66702977
	6	0039-07-331	US 77 NB	FM 509	26.14998611, -97.66776685
Γ	8	0039-07-376	US 77 SB	FM 732	26.10912913, -97.604693
	9	0039-07-377	US 77 NB	FM 732	26.10949828, -97.60492473
l	10	0039-08-224	US 77 NB	RUNNELS ST	26.09399025, -97.58960597

A

N.T.S						
Bridge Division Texas Department of Transportation						ivision
GRAVITY FED SEALANT REPAIRS CAMERON COUNTY LOCATION MAP						
FILE:	LE: DN: RRE CK: DW: R			RRE	ск:	
CTxDOT August 2017	CONT	SECT	JOB			HIGHWAY
REVISIONS	0039	07	264		1	VARIOUS
	DIST		COUNTY			SHEET NO.
	PHR		VARIOL	JS		42



SEQUENCE OF CONSTRUCTION

SET UP TCP.

ADDRESS AFFECTED AREA.

CLEAN UP AREA.


REMOVE TCP AND MOVE TO NEXT LOCATION.

DGE NO.	NBI	NO. OF INTERIOR BENTS	REPAIR WIDTH (FT)	REPAIR LENGTH (FT)	TOTAL (SF)	CNC CRACK REPAIR (FLOOD) (GRAVITY) 780 6006 SF
3	21-031-0-0039-07-305	2	6	80	960	960
4	21-031-0-0039-07-306	1 1	6 6	92.25 92.25	1107	1107
5	21-031-0-0039-07-330	2	6	56	672	672
6	21-031-0-0039-07-331	2	6	56	672	672
	21-031-0-0039-07-376	2	6	81		3876
8		1	6	64	3876	
		7	6	60		
		2	6	81		
9	21-031-0-0039-07-377	1	6	64	3876	3876
		7	6	60		
10	21-031-0-0039-08-224	2	6	56	672	672
					TOTALS	11835



GENERAL NOTES: Deck Flood material shall not flood over expansion joints. Refer to Item 780 and Concrete Repair Manual for additional information not shown here Refer to Sheet 44 for sample repair area

N.T.S	Sheet 1 of 2						
	Texas Department of Transportation						
GRAVITY-FED SEALANT REPAIR							
FILE:		DN: RRE		ск:	DW: RRE	ск:	
C TxDOT	December 2023	CONT	SECT	JOB	,	HIGHWAY	
	REVISIONS	0039	07	264		VARIOUS	
		DIST		COUNTY	r	SHEET NO.	
		PHR		VARIOL	JS	43	



SAMPLE DECK FLOOD REPAIR AREA OVER INTERIOR BENTS (GAVITY - FED)




Flood Deck Area

GENERAL NOTES:

Deck Flood material shall not to flood over joints. Refer to Item 780 and Concrete Repair Manual for application instruction Refer to GRAVITY-FED SEALANT REPAIR Sheet for flood area dimensions

N.T.S	Sheet 2 of 2						
Texas Department of Transportation							
	DN: RRE	<u> </u>		DW:	RRE	ск:	
CTxDOT August 2017	CONT	SECT	JOB		ню	SHWAY	
REVISIONS	0039	07	264		VAF	RIOUS	
	DIST		COUNTY			SHEET NO.	
	PHR		VARIOU	JS		44	



CAMERON COUNTY LOCATION MAP

GE	NBI	HIGHWAY	CROSSED FEATURE/ ROADWAY	GPS COORDINATES
1	21-031-0-0039-16-170	US 77 NB	SH 4 12-14 & 24TH ST	25.90894022, -97.48820231

Ň

N.T.S							
Texas Department of Transportation							ivision
SUPERSTRUCTURE DRAIN INLET CLEANING						5	
CAMERON COUNTY LOCATION MAP							
FILE:		DN: RRE		ск:	DW:	RRE	ск:
CTXDOT	August 2017	CONT	SECT	JOB			HIGHWAY
	REVISIONS	0039	07	264			VARIOUS
		DIST		COUNTY			SHEET NO.
		PHR		VARIO	JS		45



NBI: 21-031-0-0039-16-170 TYPICAL CLOGGED DECK DRAIN ALONG SHOULDERS

				7001 EA
1 21-031-0-0039-16-170	US 77 NB	SH 4 12-14 & 24TH ST	31	31
		TOTALS		31

SEQUENCE OF CONSTRUCTION

SET UP TCP.

ADDRESS AFFECTED AREA.

CLEAN UP AREA. REMOVE TCP AND MOVE TO NEXT LOCATION.

> GENERAL NOTES: Refer to Item 764 for additional information not shown here

N.T.S	Sheet 1 of 1						
Bridge Division Texas Department of Transportation							
SUPERSTRUCTURE							
DRAIN INLET CLEANING							
FILE:	DN: RRE		ск:	DW: RRE	ск:		
CTxDOT November 2023	CONT	SECT	JOB		HIGHWAY		
REVISIONS	0039	07	264		VARIOUS		
	DIST		COUNTY		SHEET NO.		
	PHR		VARIOU	JS	46		

developed during coordination with re	esource agencies, local governmental nal design must be reported to the E	nental Permits, Issues and Commitments have been entities and the general public. Any change ingineer prior to the commencement of construction	 II. Clean Water Act, Sections 401 and 404 Compliance - The Contractor's designated and qualified Contra project site daily to ensue compliance with SW3P shall be provided to TxDOT within 48 hours, in a
I. Clean Water Act, Section 402; Storr			5. Other Project Specific Actions:
Action Items Required :	☐ No Action Required		
plans and maintained appropriate	e SW3P by installing Best Management ly throughout construction. BMPs mu as necessary as construction progres	Practices (BMPs) as indicated in the construction ust be in place prior to the start of construction. sses.	
2. For all construction PSL's off the regulations pertaining to the pre-	he ROW, the contractor must certify eservation of cultural resources, no	compliance with all applicable laws, rules and atural resources and the environment.	III. Cultural Resources
3. 🔀 Based on the acreage of impact,	select the appropriate box below:		Action Items Required :
This project will disturb les therefore, a NOI and TPDES Si or	ss than 1 acre of soil and is not pa te Notice are not required for this	rt of a larger common plan of development; project.	1. Refer to the 2014 TxDOT Standard Specifications Bridges, Item 7.7.1., in the event historical is
required but a TPDES Site Not	ice is required. The Construction S	ut less than 5 acres; therefore a NOI is not ite Notice (CSN) is required to be posted at ew by the public, TCEQ, EPA and other Inspectors.	Upon discovery of archeological artifacts (bones area and contact the Engineer immediately. 2. Other Project Specific Actions:
This project will disturb equips The NOI and Site Notice are r	ual to or more than 5 acres of soil equired to be posted at the constru	and will require a NOI and TPDES Site Notice. ction site in a publicly accessible location.	
4. 🔀 Need to address MS4 requirements (Cameron & Hidalgo Counties only		needed	
II. Clean Water Act, Sections 401 and 4			<u>IV. Vegetation Resources</u>
Action Items Rquired :	No Action Required		Action Items Required :
1. Filling, dredging or excavating unless specified in the USACE per	in any water bodies, rivers, creeks, rmit and approved by the Engineer.	streams, wetlands or wet areas is prohibited The contractor shall adhere to all agreements,	1. In accordance with the 2014 TxDOT Standard Speci install temporary or permanent seeding for erosi for all seeding and replanting of right of way w
	red by the NWP as regulated by the L I of the terms and conditions associ		2. In accordance with Executive Order 13112 on inva scaping, native species of plants shall be used
🗌 No Permit Required			for rural roadways. (Required for Rural Setting
🗌 Nationwide Permit 14 - PCN nc	ot Required (less than 1/10th acre w	aters or wetlands affected)	3. Preserve vegetation where possible throughout th stream banks, bed and approach sections.
🗌 Nationwide Permit 14 - PCN Re	equired (1/10th to <1/2 acre, 1/3 in	n tidal waters)	4. Other Project Specific Actions:
🗌 Individual 404 Permit Require	d		
🗴 Other Nationwide Permit Requi	red: NWP# <u>NWP 3a</u>		
construction methods that change	r obtaining new or revised Section 4 Impacts To Waters Of The U.S., incl ill be maintained and not degraded.	104 permit(s) for Contractor initiated changes in uding wetlands. The Contractor will ensure that	
3. Best Management Practices for app	plicable Section 401 General Conditi	ons:	
General Condition 12 - Categorie	s I and II BMPs required		
Category I (Erosion Control) Temporary Vegetation Blankets, Matting Mulch Sodding	 Interceptor Swale Diversion Dike Erosion Control Compost 	 Mulch Filter Berms and/or Socks Compost Filter Berms and/or Socks Compost Blankets 	
Category II (Sedimentation Contro			
Silt Fence Rock Berm	□ Hay (Straw) Bale Dike □ Brush Berms	 Mulch Filter Berms and/or Socks Compost Filter Berms and/or Socks 	Pharr District Contact No. 956-702-6100
🗌 Triangular Filter Dike	Sediment Basins	Stone Outlet Sediment Traps	List of Abbreviations BMP: Best Management Practice NWP: Nationwide Perminition
□ Sand Bag Berm General Condition 21 - Category Category III (Post-Construction □ Vegetative Filter Strips □ Retention/Irrigation □ Extended Detention Basin	 Erosion Control Compost III BMPs required TSS Control) Wet Basins Grassy Swales Vegetation-Lined Ditches 	 Mulch Filter Berms and/or Socks Compost Filter Berms and/or Socks Sand Filter Systems 	BMP:Best Management PracticeNWP:Nationwide PermitCCP:Construction General PermitPCN:Pre-ConstructionDSHS:Texas Department of State Health ServicesPSL:Project SpecificSEMA:Federal Emergency Management AgencySW3P:Storm Water PolluFHWA:Federal Highway AdministrationSW3P:Storm Water PolluMOU:Memorandum of AgreementTHC:Texas HistoricalMOU:Memorandum of UnderstandingTPDES:Texas Pollutant (

-X

—X

-X

Continued:

actor Responsible Person Environmental (CRPe) will monitor the P and TPDES General Permit TXR 150000. Daily Monitoring Reports accordance with Item 506.3.1.

No Action Required

For Construction And Maintenance Of Highways, Streets, And ssues or archeological artifacts are found during construction. s, burnt rock, flint, pottery, etc.) cease work in the immediate

No Action Required

ifications; Item 164 - Seeding For Erosion Control; provide and ion control as shown on the plans or as directed by the Engineer where possible. (Required for Urban Settings)

asive species and the Executive Memorandum on Beneficial Landfor all seeding and replanting of right of way where possible gs)

he project and minimize clearing, grubbing and excavation within



ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)

		SHEET 1	OF 2
FED.RD. DIV.NO.		PROJECT NO.	HIGHWAY NO.
6			VARIOUS
STATE	DISTRICT	COUNTY	VARIOUS
TEXAS	PHR	VARIOUS	SHEET
CONTROL	SECTION	JOB	NO.
0039	07	264	47

Revised 01/30/2017

NWP: Nationwide Permit PCN: Pre-Construction Notification PSL: Project Specific Location SPCC: Spill Prevention Control and Countermeasure SW3P: Storm Water Pollution Prevention Plan TCCQ: Texas Commission on Environmental Quality THC: Texas Historical Commission TPDES: Texas Pollutant Discharge Elimination System TPMD: Texas Porks and Wildlife Department TxDOT: Texas Department of Transportation T&E: Threatened and Endangered Species USACE:U.S. Army Corp of Engineers USFWS:U.S. Fish and Wildlife Service

V. Federal Listed, and Proposed Threatened and Endangered Species, Critical Habitat, State Listed Species, Candidate Species and Migratory Birds	VI. Hazardous Materials on Contamination Issues - Continued:
Action Items Required :	 Does the project involve any bridge class structure rehabined including box culverts)?
 1. Under the Migratory Bird Treaty Act (MBTA) of 1918, codified at 16 U.S.C. § 703-712 and as enforced by the USFWS, the proposed construction work will not remove active nests from bridges, trees, ground and other structures during migratory bird nesting season, (February 1st. through October 1st.). If the Contractor needs to perform work within the right of way during nesting season, a qualified Biologist shall conduct a survey to determine if active nests are present. If present, the Contractor shall maintain a buffer zone around the nest(s) as directed by the Biologist. The buffer zone will be protected from clearing and disturbance until such time as the Biologist has determined that the nest(s) is no longer active. Prior to the nesting season, existing bridges and culverts should be treated against migratory bird nesting by utilizing Bird Exclusion Methods. Bird Exclusion Methods should be monitored and maintained throughout the nesting season. Refer to Standard Bird Exclusion Details. 2. There is the potential for the presence of state-listed species & species. Taking is defined as the collection, hooking, hunting, netting, shooting, or share by any means or devices. If any listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. 3. Other Project Specific Actions: Example Comparison (IEOPARDUS PARADALIS) MEXICAN TREE FROG (SMILISCA BAUDINI) SOUTH TEXAS SIREN (SIREN SP.) WHITE-LIPPED FROG (LEPTODACTYLUS CORNUTUM) 	 Yes ➤ No If "No", then no further action required. If "Yes", then TxDOT is responsible for completing an asked Are the results of the asbestos inspection positive (is as Yes No If "Yes", then TxDOT must retain a Texas Department of State consultant to assist with the notification, develop abater activities as necessary. The notification form to DSHS muprior to scheduled abatement activities and/or demolition. If "No", then TxDOT is still required to notify DSHS 15 were activities of the asbestos is responsible for providing the date(s) for careful coordination between the Engineer and an Asbestos delays and subsequent claims.
TEXAS TORTOISE (GOPHERUS BERIANDIERI) TEXAS INDIGO SNAKE (DYRMARCHON MELANURUS EREBENNU)	
2. SEE EPIC SHEET SUPPLEMENTAL FOR TPWD BMPs.	<u>VII. Other Environmental Issues</u>
	Action Items Required : No Action
	1. 🔀 Noise
	Contractor shall make every reasonable effort to minimize as work hour controls and proper maintenance of equipment
	2. 🔀 Air
	Contractor shall practice common dust control techniques s unpaved road surfaces and vehicle speed reduction shall be during construction.
VI. Hazardous Materials on Contamination Issues	Contractor should minimize MSAT by utilizing measures to e
Action Items Required :	limits on idling, increase use of cleaner burning diesel e as appropriate.
General (applies to all projects):	
Comply with the Hazard Communication Act (HCA) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used.	
Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the HCA.	
Maintain an adequate supply of on-site spill response materials as indicated in the MSDS. In the event of a spill, take immediate action to mitigate the spill as indicated in the MSDS and in accordance with safe work practices. Contact the TxDOT Pharr District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.	
Contact the Engineer if any of the following are detected:	
 Dead or distressed vegetation (identified as not normal) Trash piles, drums, canisters, barrels, etc. Undesirable smells or odors Evidence of leaching or seepage of contaminant substances 	
Any other evidence indicating possible hazardous materials or contamination discovered on site.	Pharr District Contact No. 956-702-6100 Revis
1. 🔀 If potentially hazardous material and/or contaminated media (i.e.: soil, groundwater, surface water, sediment,	List of Abbreviations
building materials) are unexpectedly encountered during construction, assure that such materials and contami- nation are handled according to applicable federal and state regulations, cease work in the immediate area and contact the Engineer immediately.	BMP:Best Management PracticeNWP:Nationwide PermitCGP:Construction General PermitPCN:Pre-Construction NotificationCRPe:Contractor Responsible Person EnvironmentalPSL:Project Specific LocationDSHS:Texas Department of State Health ServicesFECC:Spill Prevention Control and CFHMA:Federal Highway AdministrationVSC:Spill Prevention Control and CMOA:Memorandum of AgreementTCCQ:Texas Cormission on EnvironmentalMOU:Memorandum of AgreementTPDES:Texas Pollutant Discharge ElimMSA:Municipal Separate Stormwater Sewer SystemTMDI:Texas Department of TransporteMSA:Moigratory Bird Treaty ActThereatened and Endangered SpectNOT:Notice of IntentUSACE:U.S. Army Corp of EngineersNOT:Notice of TerminationUSFWS:U.S. Fish and Wildlife Service

-X

—×

-X

ued

rehabilitation or replacements (bridge class structures

an asbestos assessment/inspection.

(is asbestos present)?

nt of State Health Services (DSHS) licensed asbestos p abatement/mitigation procedures, and perform management DSHS must be postmarked at least 15 working days olition.

HS 15 working days prior to any scheduled demolition.

nte(s) for abatement activities and/or demolition with sbestos Consultant in order to minimize construction

Action Required

inimize construction noise through abatement measures such uipment mufflers.

niques such as surface chemical treatment or watering of shall be implemented to minimize and prevent airborne dust

res to encourage use of EPA required cleaner diesel fuels, diesel engines, and other emission limitation techniques,

Texas Department of Transportation PHARR DISTRICT

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)

			SHEET 2	OF 2		
	FED.RD. DIV.NO.		HIGHWAY NO.			
I	6					
	STATE	DISTRICT	COUNTY	VARIOUS		
	TEXAS	PHR	VARIOUS	SHEET		
	CONTROL	SECTION	JOB	NO.		
	0039	07	264	48		

Revised 01/30/2017

otification ontrol and Countermeasure ion Prevention Plan n Environmental Quality ommission scharge Elimination System Idlife Department f Transportation angered Species ingineers gineers

TPWD BMPs

Under Section 12,0011 of the Texas Parks and Wildlife Code. Texas Parks and Wildlife Department (TPWD) is charged with "providing recommendations that will protect fish and wildlife resources to local, state, and federal agencies that approve, permit, license, or construct developmental projects" and "providing information on fish and wildlife resources to any local, state, and federal agencies or private organizations that make decisions affecting those resources."

The purpose of this section is to provide beneficial management practices (BMP) that should be implemented during construction, and maintenance activities statewide for transportation projects with the goal of avoidance and minimization of impacts to natural resources. Statewide Standard BMP pertain to all fish and wildlife species, including state-listed species and other Species of Greatest Conservation Need (SGCN). Implementing the recommendations as outlined below will improve conservation of species and their habitat.

X General Design/Construction BMPs

- **X** Prior to start of construction, information will be provided to personnel of the potential for all state-listed threatened species or other SGCN to occur within the project area and should be advised of relevant rules and regulations to protect plants, fish, and wildlife.
- Contractor should avoid harming all wildlife species if encountered and allow them to safely leave the project site. Due diligence should be used to avoid killing or harming any wildlife species in the implementation of transportation projects.
- Contractors should install wildlife exclusion fencing and should examine the inside of the exclusion area daily to determine if any wildlife species have been trapped inside the area of impact and provide safe egress opportunities prior to initiation of construction activities.
- Apply hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas around wetlands and in riparian areas.
- Contractor should use woven natural fiber netting in which the mesh design allows the threads to move, therefore allowing expansion of the mesh openings. Plastic netting should be avoided.
- Project staging areas, stockpiles, temporary construction easements, and other project related sites should be situated in previously disturbed areas to avoid or minimize impacts to sensitive or unique habitats including intact native vegetation, floodplains, riparian corridors, wetlands, playa lakes, and habitat for wildlife species.
- When lighting is added, consider wildlife impacts from light pollution and incorporating dark-sky practices into design strategies. Minimize sky glow by focusing light downward, with full cutoff luminaries to avoid light emitting above the horizontal. The minimum amount of night-time lighting needed for safety and security should be used.

X Vegetation BMPs

- X Minimize the amount of vegetation cleared. Removal of native vegetation, particularly mature native trees and shrubs should be avoided. Impacted vegetation should be replaced with in-kind on-site replacement /restoration of native vegetation. It is strongly recommended that trees greater than 12 inches in
- diameter at breast height (DBH) that are removed be replaced. TPWD/₃₂ s experience indicates that for ecologically effective replacement, a ratio of three trees for every one (3:1) lost should be provided to either on-site or off-site. Trees less than 12 inches DBH should be replaced at a 1:1 ratio.
- The use of any non-native vegetation in Landscaping and revegetation is discouraged. Locally adapted native species should be used.
- The use of seed mix that contains seeds from only regional ecotype native species is recommended

Invasive Species BMPs

- For all work in water bodies designated as $\frac{3}{32}$ infested $\frac{3}{32}$ or $\frac{1}{32}$ positive $\frac{1}{32}$ for invasive zebra (Dreissena polymorpha) OR quagaa mussels (Dreissena bugensis) as well as waters downstream of these lakes, all machinery, equipment, vessels, or vehicles coming in contact with such waters should be cleaned prior to leaving the site to remove any mud, plants, organisms, or debris, water drained (if applicable), and dried completely before use in another water body to prevent the potential spread of invasive mussels. X
- Care should be taken to prevent the spread of aquatic and terrestrial invasive plants during construction activities. Care should be taken to avoid the spread of aquatic invasive
- plants such as giant Salvinia (Salvinia molesta), common salvinia (Salvinia minima), hydrilla (Hydrilla verticillata), water hyacinth (Eichhornia spp.), Eurasian watermilfoil (Myriophyllum spicatum), water lettuce (Pistia stratiotes), and alligatorweed (Alternanthera philoxeroides) from infested water bodies into areas not currently infested. All machinery, equipment, vessels, boat trailers, or vehicles coming in contact with waters containing aquatic invasive plant species should be cleaned prior to leaving the site to remove all aquatic plant material and dried completely before use on another water body to prevent the potential spread of invasive plants. Removed plants should be transported for disposal in a secure manner to prevent dispersal.
- \square Only native or non-invasive plants should be planted. Care should be taken to avoid mowing invasive giant reed (Arundo donax), which spreads by fragmentation, and to clean equipment if inadvertently mowed to prevent spread. If using hay bales for sediment control, use locally grown weed-free hay to prevent the spread of invasive species. Leave the hay bales in place and allow them to break down, as this acts as mulch assisting in revegetation.

X Stream Crossinas BMPs

X Riparian buffer zones should remain undisturbed.

X Dewatering BMPs

Impact avoidance measures for aquatic organisms, including all native fish and freshwater mussel species, regardless of state-listing status, should be considered during project planning and construction activities.

Wildlife Crossing BMPs

□ Incorporate wildlife crossings with fencing, particularly in areas that bisect wildlife travel corridors or seasonal movement routes to avoid further habitat fragmentation and minimize wildlife-vehicle interactions.

□ Rare Plant BMPs

Avoid impacts and minimize unavoidable impacts. Plant locat fenci prote growi is th plant proje plant herbi handon st

Avoid impacts and infimite undertable impacts. Fight locations should be protected with temporary barrier fencing and contractors should be instructed to avoid protected areas. Conducting construction outside of the growing season or after a plant has produced mature fruit is the preferred way to avoid/minimize impacts to SGCN plant populations. Staging areas, stockpiles, and other project related sites on TXDOT ROW should not impact SGCN			C 201	7	epartment of Transp RR DISTRICT	portation
		EPIC	SHEE	T SUPPLEME	NTALS	
hand-held spot sprayers, several meters from rare plants, on still or days with little wind).				TPW	D BMPs	
	Pharr District Contact No. 956-702-6100	Revised 02/24/2022				
	List of Abbreviations]		SHEET	1 OF 3
BMP: Best Management Practice CCP: Construction General Permit	MSAT: Mobile Source Air Toxic MBTA: Migratory Bird Treaty Act	TCEQ: Texas Commission on Environmental Quality THC: Texas Historical Commission	FED.RD. DIV.NO.		PROJECT NO.	HIGHWAY NO.
CRPe: Contractor Responsible Person Environmental	r Responsible Person Environmental NOI: Notice of Intent	TPDES:Texas Pollutant Discharge Elimination System	6			VARIOUS
DSHS: Texas Department of State Health Services FEMA: Federal Emergency Management Agency	NOT: Notice of Termination NWP: Nationwide Permit	TPWD: Texas Parks and Wildlife Department TxDOT:Texas Department of Transportation	STATE	DISTRICT	COUNTY	VARIOUS
FHWA: Federal Highway Administration	PCN: Pre-Construction Notification	T&E: Threatened and Endangered Species	TEXAS	PHR	VARIOUS	SHEET
MOA: Memorandum of Agreement MOU: Memorandum of Understanding	PSL: Project Specific Location SPCC: Spill Prevention Control and Countermeasure	USACE:U.S. Army Corp of Engineers USFWS:U.S. Fish and Wildlife Service	CONTROL	SECTION	JOB	NO.
MS4: Municipal Separate Stormwater Sewer System	SW3P: Storm Water Pollution Prevention Plan		0039	07	264	49

i D

-X

-X

Rare Plants BMPs (Continued)

If there are unintended impacts to SGCN populations, these impacts should be reported to TPWD Transportation Staff. During project period, conduct work during times of the year when plants are dormant and/or conditions minimize disturbance of the habitat.

Bird BMPs

X

X

X

X

X Avoid vegetation clearing activities during the general bird nesting season, February 15th to October 1st to minimize adverse impacts to birds.

Do not collect, capture, relocate, or transport birds.

 eggs, young, or active nests without a permit.
 Minimize extended human presence near nesting birds during construction and maintenance activities. Protect sensitive habitat areas with temporary barriers or fencing to limit human foot- traffic and off-road vehicle use to alert and discourage contractors from causing any unintentional impacts.

X Minimize construction noise above ambient levels during general bird nesting season to minimize adverse impacts on birds.

Minimize construction lighting during the general bird nesting season by scheduling work activities between dawn and dusk.

X Rookeries BMPs

In general, nesting dates for herons and egrets range from early February to late August in Texas, depending on the species. Great blue herons (GBHE) (Ardea herodis) are usually the first to nest. When GBHE get disrupted from the nest and abandon nesting, then the other species of herons and egrets may not attempt to nest at the colony that year. If rookeries are encountered, avoid and minimize disturbance during nesting to protect rookery species and their habitat.

Vegetation clearing in a primary buffer area of 300 meters (984 feet) from a rookery or heronry periphery should be avoided. Utilizing areas that have already been cleared within this buffer area may be acceptable depending on site-specific characteristics. Additionally, human foot-traffic or machinery use should not occur within this buffer area during the nesting season.

Clearing activities or construction using heavy machinery in a secondary buffer area of 1000 meters (3281 feet) from the heronry periphery should be avoided during the breeding season (courting and nesting).

X Fish BMPs

- The following Fish BMP apply to projects for all fish species in waters of the state to minimize impacts to water quality and aquatic passage from transportation projects.
- For projects in waters of the state and work is adjacent to
- water: follow Water Quality and Stream Crossing BMPs.
 For projects in waters of the state and work is in the water: follow Water Quality, Stream Crossing, and Dewatering BMP.

X Aquatic Invertebrate BMPs

- For projects within the range of a SGCN or state-listed species and work is adjacent to water: Water Quality and Stream Crossing BMP
- For projects within the range of a SGCN or state-listed species and work is in the water: Water Quality, Stream Crossing, and Dewatering BMP.
- For spring-seep associated caddisflies (Cheumatopsyche morsei, Chimarra holzenthali, and Hydroptila ouachita): Avoid or minimize impacts to the natural riparian buffer along stream channel including native shrubs and trees.

X Cravfish BMP

- For projects within the range of a SGCN or state-listed species and work is adjacent to water: Water Quality and Stream Crossing BMP. **X** For projects within the range of a SGCN or state-listed
- species and work is in the water: Water Quality, Stream Crossing, and Dewatering BMP.
- X Avoid or minimize impacts to the natural riparian buffer that provides terrestrial and aquatic plant matter for the diet of most cravfish species.

X Freshwater Mussel BMP

- In addition to Water Quality and Stream Crossing BMP, follow the most recent, ¹/₃₂ TPWD³/₃₂ TxDOT Annual Work Plan for Pre-Construction Surveys, Aquatic Resources Relocations, and Other Best Management Practices to Avoid, Minimize, and
- Mitigate Impacts to Freshwater Resources. %32 When work is adjacent to the water: Water Quality BMP implemented as part of the Texas Commission on Environmental Quality (TCEQ) Stormwater Pollution Prevention Plan (SWPPP) for a construction general permit or any conditions of the 401 Water Quality Certification for the project will be implemented.

□ Insect Pollinator BMP

- Deep soil disturbances, such as, tilling or deep disking in areas that host aggregations of ground- nesting bees should be avoided. Tilling and disking also may promote the invasion or germination of non-native plants. Different species of native ground-nesting bees prefer different soil conditions, although research suggests that many ground In areas with these soil types consider leaving open patches of soil.
- Allow dead trees to stand (so long as they do not pose a risk to property or people) and protect shrubs and herbaceous plants with pithy or hollow stems (e.g., cane fruits, sumac, elderberry), as these provide nesting habitat for tunnel-nesting native bees. Retain dead or dying branches whenever it is safe and practical at the edges of the ROW. Wood- boring beetle larvae often fill dead trees and branches with narrow tunnels into which tunnel- nesting bees will establish nests. Additionally, bumble bees may choose to nest in wood piles.
- Retain rotting logs at edges of the ROW where some bee species may burrow tunnels in which to nest.

□ Insect Pollinator BMP (Continued)

- Protect sloped or well-drained ground sites where plants are sparse and direct access to soil is available. These are the areas where ground-nesting bees may dig nests. Turning the soil destroys all ground nests that are present at that depth and hinders the emergence of bees that are nesting deeper in the around.
- Protect grassy thickets, or other areas of dense, low cover from mowing or other disturbance. These are the sites where bumble bees might find the nest cavities they need, as well as annual and perennial wildflowers that can provide important food resources.
- Where available and economical, native plants and seed should be procured from local eco-type providers. Seed mixes should be diverse and include as many ecoregion natives as possible ensuring full season floral resources. Species by Texas corregion can be found in the Texas Management Recommendations for Native Insect Pollinators in Texas document:
- https://tpwd.texas.gov/publications/pwdpubs/media/pwd*bk*w7000*1813.pdf Planting at least three different native flowering plants within each of three blooming periods are recommended (spring summer, early fall) in high rainfall regions of Texas. In drier region's of the state, a target of three native flowering plants wiťhin each of two blooming periods can be used.

Small Mammal BMP

For Coues' rice rat (Oryzomys couesi aquaticus):

□ Minimize impacts to wetland, resaca, oxbow Conversion of property containing cave or cliff features to transportation purposes should be avoided lake. and marsh habitats Water Quality BMP

Fossorial Mammal BMP

- When a construction zone is adjacent to active BTPD burrows or pocket gopher mounds, erect barriers to discourage individuals moving through or into the construction area.
- When seeding or revegetation is planned in an area adjacent to BTPD burrows or pocket gopher mounds, a vegetative barrier should be considered in the planting to discourage dispersal into the ROW.

🗶 <u>Bat BMP</u>

BMP:

DSHS:

MOU:

MOA: Memorandum of Aareement

- For activities that have the potential to impact structures, cliffs or caves, or trees; a qualified biologist will perform a habitat assessment and occupancy survey of the feature(s) with roost potential as early in the planning process as possible or within one year before project letting.
- For roosts where occupancy is strongly suspected but unconfirmed during the initial survey, revisit feature(s) at most four weeks prior to scheduled disturbance to confirm absence of bats.
- If bats are present or recent signs of occupation (i.e., piles of guano, distinct musky odor, or staining and rub marks at potential entry points) are observed, take appropriate measures to ensure
- that bats are not harmed, such as implementing non-lethal exclusion activities or timing or phasing of construction.
 Exclusion devices can be installed by a qualified individual between September 1 and March 31. Exclusion devices should be used for a minimum of seven days when minimum nighttime temperatures are about 50% for the provide the sector. are above 50°F AND minimum daytime temperatures are above 70°F. Prior to exclusion, ensure that alternate roosting habitat is available in the immediate area. If no suitable roosting habitat is available, installation of alternate roosts is recommended to replace the loss of an occupied roost. If alternate roost sites are not provided, bats may seek shelter in other inappropriate sites, such as buildings, in the surrounding area.

Pharr District Contact No. 956-702-6100

List of Abbreviations MSAT: Mobile Source Air Toxic Best Management Practice TCEQ: Texas Commissic CCP: Construction General Permit CRPe: Contractor Responsible Person Environmental MBTA: Migratory Bird Treaty Act NOI: Notice of Intent NOI: Notice of Termination THC: Texas Historico TPDES:Texas Pollutant Texas Department of State Health Services TPWD: Texas Parks and FEMA: Federal Emergency Management Agency FHWA: Federal Highway Administration NWP: Nationwide Permit TxDOT:Texas Departmen PCN: Pre-Construction Notification PSL: Project Specific Location T&F: Threatened and USACE:U.S. Army Corp Memorandum of Understanding Spill Prevention Control and Countermeasure USFWS: U.S. Fish and I MS4: Municipal Separate Stormwater Sewer System SW3P: Storm Water Pollution Prevention Plan

ÿ

-X

-X

X Bat BMP (Continued)

 \square

X

X

 \square

If feature(s) used by bats are removed as a result of construction, replacement structures should incorporate bat-friendly design or artificial roosts should be constructed to replace these features.

Avoid unnecessary removal of dead fronds on native and ornamental palm trees in south Texas (Cameron, Hidalgo, Willacy, Kenedy, Brooks, Kleberg, Nueces, and San Patricio counties) from April 1 through October 31. If removal of dead fronds is necessary at other times of the year, limit frond removal to extended warms periods (nighttime temperatures = 55°F for at least two consecutive nights), so bats can move away from the disturbance and find new roosts.

Large hollow trees, snags (dead standing trees), and trees with shaqqy bark should be surveyed for colonies and, if found, should not be disturbed until the bats are no longer occupying these features. Post-occupancy surveys should be conducted by a qualified biologist prior to tree removal from the landscape.

Retain mature, large diameter hardwood forest species and native/ornamental palm trees.

In all instances, avoid harm or death to bats. Bats should only be handled as a last resort and after communication with TPWD.

X Aquatic Amphibian and Reptile BMP

For projects within existing right-of-way (ROW) when work is in water or will permanently impact a water feature and potential habitat exists for the target species complete the following:

X Minimize impacts to wetlands, temporary and permanent open water features, including depressions, and riverine habitats.

Maintain the existing hydrologic regime and any connections between wetlands and other aquatic features.

Use barrier fencing to direct animal movements away from construction activities and areas of potential

wildlife-vehicle collisions in construction areas directly adjacent, or that may directly impact, potential habitat for the target species.

Apply hydromulching and/or hydroseeding in areas for soil stabilization and/or revegetation of disturbed areas around wetlands and in riparian areas. If erosion control blankets or mats will be used, the product should not contain netting, but should only contain loosely woven natural fiber netting in which the mesh design allows the threads to move, therefore allowing expansion of the mesh openings.

Plastic netting should be avoided. Project specific locations (PSLs) proposed within state-owned ROW should be located in uplands away from aquatic features.

When work is directly adjacent to the water, minimize impacts to shoreline basking sites (e.g., downed trees, sand bars, exposed bedrock) and refugia/overwinter sites (e.g., brush and debris piles, crayfish burrows, aquatic logjams, and leaf packs).

	PHARR DISTRICT			
EPIC SHEET SUPPLEME				MENTALS
		TPW	D BMP	S
Revised 02/24/2022				
	_		SHEE	T 2 OF 3
on on Environmental Quality al Commission	FED.RD. DIV.NO.		PROJECT NO.	HIGHWAY NO.
t Discharge Elimination System	6			VARIOUS
nd Wildlife Department ent of Transportation	STATE	DISTRICT	COUNTY	VARIOUS
		PHR	VARIOUS	SHEET
I Endangered Species	TEXAS	F E E E E E		
	CONTROL	SECTION	JOB	NO.

	Aquatic Amphibian and Reptile BMP (Continued)	Internet and Internet and Terrestrial Amphibian and Reptile I	BMP (Continued)	OTHER PERTINEN
	☐ If gutters and curbs are part of the roadway design, install gutters that do not include the side box inlet and include sloped (i.e., mountable) curbs to allow small animals to leave roadway. If this modification to the entire curb system is not possible, install sections of sloped curb on either side of the storm water drain for several feet to allow small animals to leave the roadway. Priority areas for these design recommendations are those with nearby wetlands or other aquatic features.	appropriate locally sourced a control blankets or mats will contain nylon netting, but sl natural fiber netting in which	I be used, the product should not hould only contain loosely woven ch the mesh design allows the llowing expansion of the mesh buld be avoided.	☐ <u>Trifold Availa</u> ☐ Ocelot i Pelican ☐ Ashy dog ☐ <u>Stockcards Ava</u> ☐ Mitigata
	For projects that require acquisition of additional ROW and work within that new ROW is in water or will permanently impact a water feature, implement BMP for projects within existing ROW above plus those below:	Strecker's chorus frog/White-lipped Aquatic Amphibian and Reptile Terrestrial Amphibian and Rep Water Quality BMP Vegetation BMP	d frog/Woodhouse's toad	☐ Texas To ☐ Harveste
	 For sections of roadway adjacent to wetlands or other aquatic features, install wildlife barriers that prevent climbing. Barriers should terminate at culvert openings in order to funnel animals under the road. The barriers should be of the same length as the adjacent feature or 80 feet long in each direction, or whichever is the lesser of the two. For culvert extensions and culvert replacement/installation, incorporate measures to funnel animals toward culverts such as concrete wingwalls and barrier walls with overhangs. When riprap or other bank stabilization devices are necessary, their placement should not impede the movement of terrestrial or aquatic wildlife through the water feature. Biotechnical streambank stabilization of vegetative and structural materials should be used. 	 Sheep Froq Minimize disturbance to burre Aquatic Amphibian and Reptile Terrestrial Amphibian and Rep Water Quality BMP Vegetation BMP South Texas Siren (Large Form) 	e BMP ptile BMP allow waters with vegetative cover	
	 Terrestrial Amphibian and Reptile BMP For open trenches and excavated pits, install escape ramps at an angle of less than 45 degrees (1:1) in areas left uncovered. Visually inspect excavation areas for trapped wildlife prior to backfilling Avoid or minimize disturbing or removing cover objects, such as downed trees, rotting stumps, brush piles, and leaf litter. If avoidance or minimization is not practicable, consider removing cover objects prior to the start of the project and 	Black-striped snake/Eastern box to snake/Plateau spot-tailed earless Slender glass lizard/Speckler race lizard/Texas Indigo snake/Western snake/Western massasauga Terrestrial Amphibian and Rep Vegetation BMP	lizard/ Reticulate collared lizard/ er/Tamaulipan spot-tailed earless n box turtle/Western hognose	
	 replace them at project completion. Examine heavy equipment stored on site before use, particularly after rain events when reptile and amphibian movements occur more often, to ensure use will not harm individuals that might be seeking temporary refuge. Due to increased activity (mating) of reptiles and amphibian during the spring, construction activities like clearing or grading should attempt to be scheduled outside of the spring (March-May) season. Also, timing ground disturbing activities before October when reptiles and amphibians become less active and may be using 	Aquatic Amphibian and Reptile Water Quality BMP	n the selection of Project Specific	
	 burrows in the project area is also encouraged. If Texas tortoises (Gopherus berlandieri) or box turtles (Terrepene spp.) are present in a project area, they should be removed from the area and relocated between 100 and 200 meters from the project area. After removal of the individuals, the area that will be disturbed during active construction and project specific locations should be fenced off to exclude reentry by turtles, tortoises, and other reptiles. The exclusion fence should be constructed and maintained as follows: 	X <u>Texas Tortoise</u>	overed overnight or visually inspected al of the species ptile BMP	
X - X - X	 The exclusion fence should be constructed with metal flashing or drift fence material. Rolled erosion control mesh material should not be used. The exclusion fence should be buried at least 6 inches deep and be at least 24 inches high. The exclusion fence should be maintained for the life of the project and only removed after the construction is 		Pharr District Contact No. 956-702-6100 List of Abbreviations	1
Date Printed:	completed and the disturbed site has been revegetated.	BMP: Best Management Practice CCP: Construction General Permit CRPe: Contractor Responsible Person Environmental DSHS: Texas Department of State Health Services FEMA: Federal Emergency Management Agency FHWA: Federal Highway Administration MOA: Memorandum of Agreement MOU: Memorandum of Understanding MS4: Municipal Separate Stormwater Sewer System	MSAT: Mobile Source Air Toxic MBTA: Migratory Bird Treaty Act NOI: Notice of Intent NOT: Notice of Termination NWP: Nationwide Permit PCN: Pre-Construction Notification PSL: Project Specific Location SPCC: Spill Prevention Control and Countermeasure SW3P: Storm Water Pollution Prevention Plan	ICEQ: Texas Commission on E THC: Texas Historical Comm TPDES:Texas Pollutant Disch TPWD: Texas Parks and Wildl TxDOT:Texas Department of T T&E: Threatened and Endang USACE:U.S. Army Corp of Eng USFWS:U.S. Fish and Wildlift

-X

—×

— X

NT INFORMATION

able

information n information ogweed

ailable

tory Bird Treaty Act Tortoise ter Ants and Horn Lizards

	Texas Department of Transportation PHARR DISTRICT EPIC SHEET SUPPLEMENTALS			
TPWD BMPs				
			SHEET	3 OF 3
on on Environmental Quality al Commission	FED.RD. DIV.NO.		PROJECT NO.	HIGHWAY NO.
t Discharge Elimination System	6			VARIOUS
d Wildlife Department nt of Transportation	STATE	DISTRICT	COUNTY	VARIOUS
Endangered Species	TEXAS	PHR	VARIOUS	SHEET
of Engineers Wildlife Service	CONTROL	SECTION	JOB	NO.
	0039	07	264	51