

# STATE OF TEXAS TEXAS DEPARTMENT OF TRANSPORTATION



## PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

**WORK CONSISTING OF CULVERT REPAIR**  
CSJ: 6462-75-001  
COUNTY: LAVACA, ETC.


FED. RD. DIST. NO.	PROJECT NO.	SHEET NO.
6	RMC - 646275001	1
STATE	STATE DIST.	COUNTY
TEXAS	YKM	\$CTY\$
CONT.	SECT.	JOB
\$C\$	\$S\$	\$J\$
		\$HWY\$

CONTRACTOR: \_\_\_\_\_  
 DATE OF LETTING: \_\_\_\_\_  
 DATE WORK BEGAN: \_\_\_\_\_  
 DATE WORK COMPLETED: \_\_\_\_\_  
 DATE WORK ACCEPTED: \_\_\_\_\_  
 FINAL CONTRACT COST: \$ \_\_\_\_\_

LIST OF APPROVED FIELD CHANGES:



YOAKUM DISTRICT



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

*Mark C. Netardus P.E.*

MAINTENANCE ENGINEER

10/15/2024

DATE


### DEWITT, FAYETTE, GONZALES, LAVACA YOAKUM DISTRICT

EXCEPTIONS: NONE  
 EQUATIONS: NONE  
 RAILROAD CROSSINGS: NONE

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, SEPTEMBER 1, 2024 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT:

THIS IS TO CERTIFY THAT THE CONSTRUCTION WORK WAS PERFORMED IN ACCORDANCE WITH THE PLANS, CONTRACT AND LISTED FIELD CHANGES.

\_\_\_\_\_, P. E. \_\_\_\_\_  
 AREA ENGINEER DATE



APPROVED FOR LETTING:

10-15-24

DATE


*Michael Brzozowski P.E.*  
 DIRECTOR OF OPERATIONS



**TEXAS DEPARTMENT OF TRANSPORTATION**  
 © YEAR \$ BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED

SHEET NO.	DESCRIPTION
<b>GENERAL</b>	
1	TITLE SHEET
2	INDEX OF SHEETS
3	PROJECT LOCATION MAP
4-6	GENERAL NOTES
7-9	STRUCTURE SUMMARY & DETAILS
10-11	ESTIMATE & QUANTITY SHEET
<b>TCP STANDARD SHEETS</b>	
12-23	BC(1-12)-21
24	TCP(2-1)-18
25	TCP(2-2)-18
26	WZ(RS)-22
<b>DRAINAGE</b>	
27-31	CULVERT LAYOUT
32-33	INLET DETAILS
34-48	CULVERT LAYOUT
<b>DRAINAGE STANDARD SHEETS</b>	
49	BCS
50	SCC-MD
51-52	SCC-3 & 4
53	SCP-MD
54	SCP-5
55	SCP-6
56	PW
57-58	SETB-CD
59-60	SETP-CD
61	SETP-PD
62-64	SETP-CD-A
65	CH-PW-0 (MOD)
<b>BRIDGE STANDARD SHEETS</b>	
66-67	SRR
<b>TRAFFIC STANDARD SHEETS</b>	
68	D & OM(1)-20
69	D & OM(2)-20
70	D & OM(4)-20
<b>ENVIRONMENTAL</b>	
71	ENVIRONMENTAL PERMITS, ISSUES & COMMITMENTS
72-74	SWP3
<b>ENVIRONMENTAL STANDARD SHEETS</b>	
75	EC(1)-16
76	TRB-24 (1)
77	TRB-15(2)
<b>RAILROAD STANDARD SHEETS</b>	
78	RAILROAD SCOPE OF WORK
79-80	RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS

PATH: T:\YKMAN\NEXIPS&E\Worksets\YKM\_Project\_Workset\_Template\Index\_of\_Sheets.dgn  
FILE: Index\_of\_Sheets.dgn  
DATE: 10/9/2024



*Mark C. Netardus P.E.*

10/09/2024





## INDEX OF SHEETS

Texas Department of Transportation  
©2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 1 OF 1

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET No.
TEXAS	YKM	LAVACA, ETC.	2

THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



## PROJECT LOCATION MAP

 **Texas Department of Transportation**  
 ©2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED  
 SHEET 1 OF 1

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	3

PATH: T:\YKM\TRAFFIC\Design Projects\FY 24\YAO CULVERTS\Plan Sheets  
 FILE: \_PROJECT LOCATION MAP.DGN  
 DATE: 9/11/2024

**Project Number: 6462-75-001**

**County: LAVACA, ETC.**

**Highway: SH 95, ETC.**

**GENERAL NOTES:**

Contractor questions on this project are to be addressed to the following individual(s):

Covey Morrow IV [Covey.Morrow@txdot.gov](mailto:Covey.Morrow@txdot.gov)

Chase Hermes [Chase.Hermes@txdot.gov](mailto:Chase.Hermes@txdot.gov)

Contractor questions will be accepted through email, phone, and in person by the above individuals.

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

**I. UNION PACIFIC RAILROAD COMPANY**

**PROTECTION OF FIBER OPTIC CABLE SYSTEMS**

Fiber optic cable systems may be buried on the railroad's property. Protection of the fiber optic cable systems is of extreme importance since any break could disrupt service to users resulting in business interruption and loss of revenue and profits. The state and/or its contractor shall telephone the railroad during normal business hours (7:00 a.m. to 9:00 p.m., central time, Monday through Friday, except holidays) at 1-888-877-7267 (also a 24-hour, seven-day number for emergency calls) to determine if fiber optic cable is buried on the railroad's premises to be used by the state. If it is, the state and/or its contractor will telephone the telecommunications company(ies) involved, arrange for a cable locator and make arrangements for relocation or other protection of the fiber optic cable prior to beginning any work on the railroad's premises.

Individual structures will be extended on one side at a time through completion before construction work is begun on the opposite side unless otherwise directed.

Do not work on the roadway before sunrise or after sunset unless otherwise approved.

Leave all traffic lanes open to traffic at night, weekends and holidays unless otherwise approved.

**Project Number: 6462-75-001**

**County: LAVACA, ETC.**

**Highway: SH 95, ETC.**

The following standard detail sheets have been modified:

CH-PW-0

Leave all intersecting roadways, side streets, and entrances open during construction unless otherwise approved. Should there be a request to restrict access for such reasons as parallel culvert replacement, reconstruction, etc., approval will be required 48 hours in advance and the contractor will be required to coordinate satisfactorily with any affected property owners.

Unless otherwise approved, maintain a minimum safety clearance from the edge of the travelway for material stockpiled in proximity of traffic lanes based on the current average traffic count of the particular highway as follows:

0 - 1500 = 16 feet

Over 1500 = 30 feet

In the event the above requirements cannot be met, make arrangements to stockpile material off the right of way.

At those locations where centerline structures are to be replaced, remove existing structures and install new structures in half widths. Work and materials required for temporary bulkheads will be considered subsidiary. One-way traffic will be allowed during daylight hours only.

The Department will provide the cylinder testing machine for this project. Deliver the test specimens to the engineer's curing facilities as directed.

Do not clean out concrete trucks within the right of way.

The contractor shall field verify all existing pipe, box culvert, and safety end treatments sizes prior to fabrication of related items. All work involved with field verifying will not be measured or paid for directly but will be subsidiary to pertinent items.

The contractor must coordinate with Texas Parks & Wildlife Department (TPWD) at PR 11 in Palmetto State Park and Neasloney Wildlife Management Area located in Gonzales County prior to construction. The contractor should arrange with TPWD to have a representative present during all excavation to collect any historic CCC Rocks that are found.

**ITEM 7: LEGAL RELATIONS AND RESPONSIBILITIES**

No significant traffic generator events identified.

If the contractor proposes work beyond the TxDOT obtained permit limitations, the contractor is responsible for additional costs, delays, and obtaining new or revised permits prior to construction.



**Project Number: 6462-75-001**

**County: LAVACA, ETC.**

**Highway: SH 95, ETC.**

**ITEM 8: PROSECUTION AND PROGRESS**

Provide progress schedule as a Bar Chart.

**ITEM 132: EMBANKMENT**

Furnish Type C embankment consisting of suitable earth material such as loam, clay or other such material that will form a stable embankment and has a plasticity index of at least 15 but not more than 40.

**ITEM 400: EXCAVATION AND BACKFILL FOR STRUCTURES**

Flexible base (Ty D) may be used for cement stabilized backfill aggregate, as approved.

**ITEM 432: RIPRAP**

Place 1/2 inch expansion joint material between the two concrete areas or structures where riprap is placed against other concrete such as concrete pavement and structures unless otherwise shown on the plans or as directed. This work will not be paid for directly but will be subsidiary to the pertinent items.

Unless otherwise shown on the plans or directed, riprap will be 5" deep and reinforced; reinforced toewalls 6" wide and 12" deep will be placed around the perimeter of each location.

The dimension as shown in the stone protection bid item description is the stone size as described in the specification. The required thickness will be as shown elsewhere in the plans.

**ITEM 460: CORRUGATED METAL PIPE**

Corrugations shall be 2 2/3 by 1/2 inch and minimum 16 gauge.

**ITEM 462: CONCRETE BOX CULVERTS AND DRAINS**

Use precast concrete boxes on this project except at SH 237.

**Project Number: 6462-75-001**

**County: LAVACA, ETC.**

**Highway: SH 95, ETC.**

When extending box culverts, if footings and interior walls are not broken back to expose reinforcement, embed steel dowels into the concrete to splice with the "F" bars of the proposed footing and wall extensions. Embed dowels a minimum of 12" into the new construction to meet the minimum splice requirements of Item 440. Match the number, size and grade of dowel bars to the proposed "F" bars. Epoxy for dowel bar embedment will be as approved. This work will not be paid for directly but will be subsidiary to pertinent items.

For payment purposes, the culvert extension quantities are measured from the outside edge of the existing culvert headwall and do not include any necessary breakback into the existing culvert. Alternatives to the breakback including doweling may be allowed or directed dependent on related standard sheets (skew/fill depth) and other applicable general notes. All work related to breakback and alternative construction methods is subsidiary to pertinent items.

Removing and disposing of portions of existing structures including wingwalls, headwalls, safety end treatments, etc. is subsidiary to the proposed culvert extension, proposed end treatment, or remove structure (small)(large)(box culvert)(pipe) items.

**ITEMS 464 & 467: REINFORCED CONCRETE PIPE & SAFETY END TREATMENT**

If required, concrete collars, will be used at pipe joints. Collars will be reinforced as directed. No direct compensation will be made for concrete collars and they will be subsidiary to the pertinent items.

**ITEM 467: SAFETY END TREATMENT**

Precast safety end treatment sections will not be allowed.

Provide reinforced concrete riprap for all pipe safety end treatments. Round corners on safety end treatment riprap to a minimum 12 inch radius as directed. The riprap will not be paid for directly but will be subsidiary to Item 467.

Provide and use a form along the cut end of the pipe when placing the adjacent reinforced concrete riprap for pipe safety end treatment sections.

Riprap cross slope above the working point may need to be flatter than 6:1 slope to improve driveway tie-in as directed by the engineer.

**Project Number: 6462-75-001**

**County: LAVACA, ETC.**

**Highway: SH 95, ETC.**

**ITEM 496: REMOVING STRUCTURES**

Remove existing structures and install new structures in half widths. Work and materials required for temporary bulkheads will be subsidiary.

Material removed under this item will not be deemed salvageable.

**ITEM 502: BARRICADES, SIGNS, AND TRAFFIC HANDLING**

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be

mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Use WZ(RS)-22 in conjunction with TCP(2-2).

Use TCP(2-2b) for one-lane, two-way traffic control.

When using TCP(2-2b), a pilot car is required to lead traffic through the work space with or without channelizing devices on the center line unless otherwise approved.

When using TCP(2-2b), channelizing devices may be omitted during base, subgrade and seal coat operations unless otherwise directed. Flaggers will be required at public intersections when channelizing devices are omitted.

When using TCP(2-2b), arrow boards, displaying the caution mode, may be used to enhance the flagger stations. If used, place the arrow board in advance of the flagger station a distance of  $\frac{1}{2}X$ , the sign spacing distance shown on BC(2). Use arrow boards as shown on BC(7).

When using TCP(2-2b), the temporary 24" stop line and the CW16-2P plaques may be omitted.

When using TCP(2-2b), an additional "Road Work Ahead" and "Be Prepared To Stop" signs will be required on each end of the lane closure unless otherwise approved.

Provide suitable warning lights mounted high enough to be visible from all directions on all construction equipment, including pilot vehicles, and operate warning lights when the equipment is within the right of way. Equip other equipment such as trucks, trailers, autos, etc., with emergency flashers and use emergency flashers while within the work area.

**Project Number: 6462-75-001**

**County: LAVACA, ETC.**

**Highway: SH 95, ETC.**

The utilization of TCP (2-2b) while work is being performed at cross culvert locations shall be considered subsidiary to Item 502, "Barricades, Signs, and Traffic Handling". Any additional measures desired by the contractor and as approved by the engineer, will be at the contractor's entire expense.

Project limit traffic control devices will not be required for this project.

**ITEM 505: TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA)**

The TMA/TA used for installation/removal of traffic control for a work area will be subsidiary to the TMA/TA used to perform the work.

**ITEM 506: TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS**


1. See SWP3 plan sheet for total disturbed acreage.
2. The disturbed area in this project, all project locations in the contract, and contractor project specific locations (PSLs), within one (1) mile of the project limits, for the contract will further establish the authorization requirements for storm water discharges.
3. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans.
4. Obtain any required authorization from the TCEQ for any contractor PSLs for construction activities on or off right-of-way (ROW).
5. When the total disturbed area for all projects in the contract and PSLs within one (1) mile of the project limits exceeds five (5) acres, provide a copy of the contractor NOI.
6. Provide a signed sketch detailing the location of any contractor's PSLs on ROW or within one (1) mile of the project.

**STRUCTURE SUMMARY**

CULVERT LOCATION			DESCRIPTION	ITEM 104 REMOVE CONC (RIPRAP) SY	ITEM 132 EMBANKMENT (VEHICLE) (ORD COMP) (TY C) EST CY	ITEM 400			ITEM 402 TRENCH EXCAVATION PROTECTION LF	ITEM 432		ITEM 460 CMP (GAL STL) 18" 24" LF LF		ITEM 462 CONC BOX CULVERT 4'X3' 5'X2' 6'X4' LF LF LF			ITEM 464 RC PIPE (CL III) AR DES 4 6 12" 18" 24" 30" LF LF LF LF LF LF								
						CEM STABIL BKFL CY	CUT & RESTORING PAV SY	* STRUCT EXCAV CY		RIPRAP (CONC) (CL C) CY	RIPRAP (STONE PROTECTION) (12 IN) CY	4'X3' LF	5'X2' LF	6'X4' LF	AR DES 4 LF	AR DES 6 LF	12" LF	18" LF	24" LF	30" LF					
COUNTY	ROADWAY	STA																							
<b>NON-BRIDGE CLASS CULVERTS</b>																									
Fayette	FM 154	273+25 RT	EXIST 1 - 18" X 36.5' CMP TO BE REMOVED PROP 1 - 18" X 40' CMP & SET (TY II)(18")(CMP)(6:1)(P) LT & RT USING SETP-PD.		4.1	6.9	10	16.7				40													
Fayette	FM 155	492+75 LT	EXIST 1 - DES 2 X 51.3' CMP WITH SETS TO BE REMOVED. PROP 1 - 18" X 54' RCP & SET (TY II)(18")(RCP)(6:1)(P)(LT & RT) USING SETP-PD.		2.1	11.8	16	30.8																	54
Fayette	FM 2503	72+67	EXIST 1 - 30" X 32' RCP W/ HEADWALLS TO BE REMOVED PROP 1 - 30" X 43' RCP & SET (TY II)(30")(RCP)(4:1)(C) LT & RT USING SETP-CD.		7.0	15.8	15	50.0	43																43
Fayette	SH 159	175+50 LT	EXIST 1 - 24" X 57.5' CMP TO BE REMOVED PROP 1 - 30" X 66' RCP & SET (TY II)(30")(RCP)(6:1)(P) LT & RT USING SETP-PD.		22.9	24.2	12	85.4	66																66
Fayette	SH 237	799+49.85	EXIST 1 - CENTERLINE 4' X 3' CBC & 2 - PARALLEL 24" CMPS. REMOVE CBC HEADWALL, & CMP SET. EXTEND 4' X 3' CBC 8.5' LT USING SCC-3&4 AND SCC-MD. EXTEND EXIST 24" CMPS 7' & 17' TO STUB INTO PROPOSED CBC EXTENSION. BACKFILL DITCH TO GRADE & SOD.	28	23.5	8.9		7.1	32	1		24	8.5												
DeWitt	FM 3157	85+65	EXIST 1 - DES 6 X 44' CMP TO BE REMOVED PROP 2 - DES 4 X 48' RCP & SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.					36.2	32												96				
DeWitt	FM 239	163+59.4	EXIST 1 - 30" X 38' CMP TO BE REMOVED. PROP 1 - 30" X 40' RCP & SET (TY II)(30")(RCP)(3:1)(C) LT & RT USING SETP-CD.		5.6	14.6	15	45.5	40																40
DeWitt	FM 766	512+10 LT	EXIST 1 - 18" X 36' CMP TO BE REMOVED. PROP 1 - 18" X 44' RCP & SET (TY II)(18")(RCP)(6:1)(P) LT & RT USING SETP-PD.		4.7	9.7	13	24.8																44	
DeWitt	FM 951	30+50	EXIST 2 - DES 6 X 42' CMP TO BE REMOVED. PROP 2 - DES 6 X 42' RCP & SET (TY II)(DES 6)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.		11.1	46.1	42	68.0	42																68
DeWitt	FM 240	403+23	EXIST 1 - 30" X 30' CMP TO BE REMOVED. PROP 1 - DES 4 X 38' RCP & SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.		5.3	13.9	17	35.7													38				
DeWitt	FM 238	196+35	EXIST 2 - DES 6 X 40' CMP TO BE REMOVED PROP 1 - 5' X 2' X 40' CBC & SET (TY I)(S=5 FT)(HW = 3 FT)(3:1)(C) LT & RT USING SETB-CD, SCP-MD, BCS, SCP-5.		3.1	12.8	35	50.3	40					40											
Gonzales	US 90	2155+00	EXIST 1 - DES 5 CMP STUBBED INTO 4' X 2.5' CBC LT & RT. 60.6' TO BE REMOVED PROP 1 - 5' X 2' X 68' CBC & SET (TY I)(S = 5 FT)(HW = 3 FT)(4:1)(C) LT & RT USING BCS, SCP-5, SETB-CD, SCP-MD.		4.1	21.8	36	82.1	68					68											
Gonzales	PR 11	5+15	EXIST 1 - 12" X 20' CMP TO BE REMOVED PROP 1 - 12" X 32' RCP.		0.9	4.9	12	8.5																	32
Gonzales	PW	11+52	EXIST 2 - 24" X 20' CMP EXTEND 2' LT & ADD HEADWALL (CH - PW - 0) (DIA= 24 IN) USING HEADWALL (CH-PW-0 (MOD)).				7	5.3			10	4													
Lavaca	FM 340	97+50 LT	EXIST 1 - 24" X 29.5' RCP EXTEND 4' LT & 15' RT ADD SET (TY II)(24")(RCP)(6:1)(P) LT & RT USING SETP-PD.		7.2	4.3		16.0																	19
Lavaca	SH 95	327+50	EXIST 1 - 6' X 4' X 61.6' CBC TO BE REMOVED. PROP 1 - 6' X 4' X 62' CBC & WINGWALL (PW - 1) (HW=5 FT) LT & RT USING SCP-MD, SCP-6, PW, BCS.	32		30.8	42	130.0	62	5	13			62											
Lavaca	FM 155	197+11	EXIST 1 - 24" X 30.5' CMP REMOVE 2' LT & RT EXTEND 5' LT & RT & SET (TY II)(24")(CMP)(6:1)(P) LT & RT USING SETP-PD.		5.0			14.7				10													
Lavaca	FM 3283	65+31	EXIST 2 - 24" X 39' CMP TO BE REMOVED PROP 2 - 24" X 37' RCP & SET (TY II)(24")(RCP)(3:1)(C) LT & RT USING SETP-CD.		3.6	22.2	26	55.7																	74
Lavaca	SH 95	206+90.3	EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE REMOVE EXIST CONC RIPRAP RT PLACE CONC RIPRAP RT.	22							5														
Lavaca	SH 95	219+82	EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE REMOVE EXIST CONC RIPRAP RT PLACE CONC RIPRAP RT.	22							5														
<b>PROJECT TOTALS</b>					<b>104</b>	<b>110.2</b>	<b>284.9</b>	<b>330</b>	<b>827.2</b>	<b>441</b>	<b>16</b>	<b>23</b>	<b>40</b>	<b>38</b>	<b>8.5</b>	<b>108</b>	<b>62</b>	<b>134</b>	<b>68</b>	<b>32</b>	<b>98</b>	<b>93</b>	<b>149</b>		

PATH: C:\DESIGN\_PROJECTS\YKM\_Workset\_Template\Index\_of\_Sheets  
 FILE: Index\_of\_Sheets.dgn  
 DATE: 9/11/2024

\* FOR CONTRACTOR'S INFORMATION ONLY.



*Mark C. Netardus P.E.*

09/13/2024

**STRUCTURE SUMMARY & DETAILS**


Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED  
 SHEET 1 OF 3

FED. RD. DIV. NO. 6		PROJECT NO.	
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	7

## STRUCTURE SUMMARY

CULVERT LOCATION			DESCRIPTION	ITEM 466		ITEM 467											
				HEADWALL (CH - PW - 0)  (DIA= 24 IN)	WINGWALL (PW - 1)  (HW=5 FT)	SET (TY I)		SET (TY II)									
						(S=5FT) (HW=3FT) (3:1)	(S=5FT) (HW=3FT) (4:1)	18" CMP (6:1)	18" RCP (6:1)	24" CMP (6:1)	24" RCP (3:1)	30" RCP (6:1)	30" RCP (3:1)	30" RCP (4:1)	30" RCP (6:1)	DES 4 RCP (4:1)	DES 6 RCP (4:1)
COUNTY	ROADWAY	STA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	
<b>NON-BRIDGE CLASS CULVERTS</b>																	
Fayette	FM 154	273+25 RT	EXIST 1 - 18" X 36.5' CMP TO BE REMOVED PROP 1 - 18" X 40' CMP & SET (TY II)(18")(CMP)(6:1)(P) LT & RT USING SETP-PD.													2	
Fayette	FM 155	492+75 LT	EXIST 1 - DES 2 X 51.3' CMP WITH SETS TO BE REMOVED. PROP 1 - 18" X 54' RCP & SET (TY II)(18")(RCP)(6:1)(P)(LT & RT) USING SETP-PD.													2	
Fayette	FM 2503	72+67	EXIST 1 - 30" X 32' RCP W/ HEADWALLS TO BE REMOVED PROP 1 - 30" X 43' RCP & SET (TY II)(30")(RCP)(4:1)(C) LT & RT USING SETP-CD.														2
Fayette	SH 159	175+50 LT	EXIST 1 - 24" X 57.5' CMP TO BE REMOVED PROP 1 - 30" X 66' RCP & SET (TY II)(30")(RCP)(6:1)(P) LT & RT USING SETP-PD.														2
Fayette	SH 237	799+49.85	EXIST 1 - CENTERLINE 4' X 3' CBC & 2 - PARALLEL 24" CMPS. REMOVE CBC HEADWALL, & CMP SET. EXTEND 4' X 3' CBC 8.5' LT USING SCC-3&4 AND SCC-MD. EXTEND EXIST 24" CMPS 7' & 17' TO STUB INTO PROPOSED CBC EXTENSION. BACKFILL DITCH TO GRADE & SOD.														
DeWitt	FM 3157	85+65	EXIST 1 - DES 6 X 44' CMP TO BE REMOVED PROP 2 - DES 4 X 48' RCP & SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.														2
DeWitt	FM 239	163+59.4	EXIST 1 - 30" X 38' CMP TO BE REMOVED. PROP 1 - 30" X 40' RCP & SET (TY II)(30")(RCP)(3:1)(C) LT & RT USING SETP-CD.													2	
DeWitt	FM 766	512+10 LT	EXIST 1 - 18" X 36' CMP TO BE REMOVED. PROP 1 - 18" X 44' RCP & SET (TY II)(18")(RCP)(6:1)(P) LT & RT USING SETP-PD.													2	
DeWitt	FM 951	30+50	EXIST 2 - DES 6 X 42' CMP TO BE REMOVED. PROP 2 - DES 6 X 42' RCP & SET (TY II)(DES 6)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.														2
DeWitt	FM 240	403+23	EXIST 1 - 30" X 30' CMP TO BE REMOVED. PROP 1 - DES 4 X 38' RCP & SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.														2
DeWitt	FM 238	196+35	EXIST 2 - DES 6 X 40' CMP TO BE REMOVED PROP 1 - 5' X 2' X 40' CBC & SET (TY I)(S=5 FT)(HW = 3 FT)(3:1)(C) LT & RT USING SETB-CD, SCP-MD, BCS, SCP-5.				2										
Gonzales	US 90	2155+00	EXIST 1 - DES 5 CMP STUBBED INTO 4' X 2.5' CBC LT & RT. 60.6' TO BE REMOVED PROP 1 - 5' X 2' X 68' CBC & SET (TY I)(S = 5 FT)(HW = 3 FT)(4:1)(C) LT & RT USING BCS, SCP-5, SETB-CD, SCP-MD.													2	
Gonzales	PR 11	5+15	EXIST 1 - 12" X 20' CMP TO BE REMOVED PROP 1 - 12" X 32' RCP.														
Gonzales	PW	11+52	EXIST 2 - 24" X 20' CMP EXTEND 2' LT & ADD HEADWALL (CH - PW - 0) (DIA= 24 IN) USING HEADWALL (CH-PW-0 (MOD)).	1													
Lavaca	FM 340	97+50 LT	EXIST 1 - 24" X 29.5' RCP EXTEND 4' LT & 15' RT ADD SET (TY II)(24")(RCP)(6:1)(P) LT & RT USING SETP-PD.													2	
Lavaca	SH 95	327+50	EXIST 1 - 6' X 4' X 61.6' CBC TO BE REMOVED. PROP 1 - 6' X 4' X 62' CBC & WINGWALL (PW - 1) (HW=5 FT) LT & RT USING SCP-MD, SCP-6, PW, BCS.													2	
Lavaca	FM 155	197+11	EXIST 1 - 24" X 30.5' CMP REMOVE 2' LT & RT EXTEND 5' LT & RT & SET (TY II)(24")(CMP)(6:1)(P) LT & RT USING SETP-PD.													2	
Lavaca	FM 3283	65+31	EXIST 2 - 24" X 39' CMP TO BE REMOVED PROP 2 - 24" X 37' RCP & SET (TY II)(24")(RCP)(3:1)(C) LT & RT USING SETP-CD.													2	
Lavaca	SH 95	206+90.3	EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE REMOVE EXIST CONC RIPRAP RT PLACE CONC RIPRAP RT.														
Lavaca	SH 95	219+82	EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE REMOVE EXIST CONC RIPRAP RT PLACE CONC RIPRAP RT.														
<b>PROJECT TOTALS</b>				<b>1</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>4</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>4</b>	<b>2</b>

PATH: C:\DESIGN\PROJECTS\YKM\Worksheet\_Template\Index\_of\_Sheets.dgn  
 FILE: Index\_of\_Sheets.dgn  
 DATE: 9/11/2024



*Mark C. Netardus P.E.*

09/13/2024

## STRUCTURE SUMMARY & DETAILS

Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED


FED. RD. DIV. NO. 6		PROJECT NO.	
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	8

SHEET 2 OF 3




### STRUCTURE SUMMARY

CULVERT LOCATION			DESCRIPTION	ITEM 496 REMOV STR (SMALL) EA	ITEM 506		ITEM 658 INSTL OM ASSM (OM-2Y) (WC) GND EA	ITEM 752 SPOT TREE TRIMMING /BRUSH REMOVAL LF
					TEMP SEDMT CONT FENCE (INSTALL) LF	TEMP SEDMT CONT FENCE (REMOVE) LF		
COUNTY	ROADWAY	STA						
<b>NON-BRIDGE CLASS CULVERTS</b>								
Fayette	FM 154	273+25 RT	EXIST 1 - 18" X 36.5' CMP TO BE REMOVED PROP 1 - 18" X 40' CMP & SET (TY II)(18")(CMP)(6:1)(P) LT & RT USING SETP-PD.	1	20	20		
Fayette	FM 155	492+75 LT	EXIST 1 - DES 2 X 51.3' CMP WITH SETS TO BE REMOVED. PROP 1 - 18" X 54' RCP & SET (TY II)(18")(RCP)(6:1)(P)(LT & RT) USING SETP-PD.	1	20	20		
Fayette	FM 2503	72+67	EXIST 1 - 30" X 32' RCP W/ HEADWALLS TO BE REMOVED PROP 1 - 30" X 43' RCP & SET (TY II)(30")(RCP)(4:1)(C) LT & RT USING SETP-CD.	1	20	20	2	
Fayette	SH 159	175+50 LT	EXIST 1 - 24" X 57.5' CMP TO BE REMOVED PROP 1 - 30" X 66' RCP & SET (TY II)(30")(RCP)(6:1)(P) LT & RT USING SETP-PD.	1	20	20		
Fayette	SH 237	799+49.85	EXIST 1 - CENTERLINE 4' X 3' CBC & 2 - PARALLEL 24" CMPS. REMOVE CBC HEADWALL, & CMP SET. EXTEND 4' X 3' CBC 8.5' LT USING SCC-3&4 AND SCC-MD. EXTEND EXIST 24" CMPS 7' & 17' TO STUB INTO PROPOSED CBC EXTENSION. BACKFILL DITCH TO GRADE & SOD.		20	20		
DeWitt	FM 3157	85+65	EXIST 1 - DES 6 X 44' CMP TO BE REMOVED PROP 2 - DES 4 X 48' RCP & SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.	1	20	20	2	
DeWitt	FM 239	163+59.4	EXIST 1 - 30" X 38' CMP TO BE REMOVED. PROP 1 - 30" X 40' RCP & SET (TY II)(30")(RCP)(3:1)(C) LT & RT USING SETP-CD.	1	20	20	2	
DeWitt	FM 766	512+10 LT	EXIST 1 - 18" X 36' CMP TO BE REMOVED. PROP 1 - 18" X 44' RCP & SET (TY II)(18")(RCP)(6:1)(P) LT & RT USING SETP-PD.	1	20	20		
DeWitt	FM 951	30+50	EXIST 2 - DES 6 X 42' CMP TO BE REMOVED. PROP 2 - DES 6 X 42' RCP & SET (TY II)(DES 6)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.	1	20	20	2	
DeWitt	FM 240	403+23	EXIST 1 - 30" X 30' CMP TO BE REMOVED. PROP 1 - DES 4 X 38' RCP & SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT USING SETP-CD-A.	1	20	20	2	
DeWitt	FM 238	196+35	EXIST 2 - DES 6 X 40' CMP TO BE REMOVED PROP 1 - 5' X 2' X 40' CBC & SET (TY I)(S=5 FT)(HW = 3 FT)(3:1)(C) LT & RT USING SETB-CD, SCP-MD, BCS, SCP-5.	1	20	20	2	
Gonzales	US 90	2155+00	EXIST 1 - DES 5 CMP STUBBED INTO 4' X 2.5' CBC LT & RT. 60.6' TO BE REMOVED PROP 1 - 5' X 2' X 68' CBC & SET (TY I)(S = 5 FT)(HW = 3 FT)(4:1)(C) LT & RT USING BCS, SCP-5, SETB-CD, SCP-MD.	1	20	20	2	
Gonzales	PR 11	5+15	EXIST 1 - 12" X 20' CMP TO BE REMOVED PROP 1 - 12" X 32' RCP.	1	20	20	2	
Gonzales	PW	11+52	EXIST 2 - 24" X 20' CMP EXTEND 2' LT & ADD HEADWALL (CH - PW - 0) (DIA= 24 IN) USING HEADWALL (CH-PW-0 (MOD)).		20	20	2	
Lavaca	FM 340	97+50 LT	EXIST 1 - 24" X 29.5' RCP EXTEND 4' LT & 15' RT ADD SET (TY II)(24")(RCP)(6:1)(P) LT & RT USING SETP-PD.		20	20		
Lavaca	SH 95	327+50	EXIST 1 - 6' X 4' X 61.6' CBC TO BE REMOVED. PROP 1 - 6' X 4' X 62' CBC & WINGWALL (PW - 1) (HW=5 FT) LT & RT USING SCP-MD, SCP-6, PW, BCS.	1	20	20	2	30
Lavaca	FM 155	197+11	EXIST 1 - 24" X 30.5' CMP REMOVE 2' LT & RT EXTEND 5' LT & RT & SET (TY II)(24")(CMP)(6:1)(P) LT & RT USING SETP-PD.		20	20	2	
Lavaca	FM 3283	65+31	EXIST 2 - 24" X 39' CMP TO BE REMOVED PROP 2 - 24" X 37' RCP & SET (TY II)(24")(RCP)(3:1)(C) LT & RT USING SETP-CD.	1	20	20	2	
Lavaca	SH 95	206+90.3	EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE REMOVE EXIST CONC RIPRAP RT PLACE CONC RIPRAP RT.		20	20		5
Lavaca	SH 95	219+82	EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE REMOVE EXIST CONC RIPRAP RT PLACE CONC RIPRAP RT.		20	20		
<b>PROJECT TOTALS</b>				<b>14</b>	<b>400</b>	<b>400</b>	<b>24</b>	<b>35</b>





- CUT & RESTORE PAVEMENT NOTES:**
1. ACP IS SUBSIDIARY TO ITEM 400 CUT AND RESTORE PAVEMENT.
  2. PROVIDE A SMOOTH AND UNIFORM DRIVING SURFACE AS APPROVED BY THE ENGINEER.



### SEEDING SUMMARY

LOCATION	ITEM 164			ITEM 166	ITEM 168	REMARKS
	BROADCAST SEED (PERM) (RURAL) (CLAY) SY	BROADCAST SEED (TEMP) (WARM) SY	BROADCAST SEED (TEMP) (COOL) SY	* FERTILIZER 500 LBS/AC TON	VEGETATIVE WATERING 13.58 MG/AC X 3 CYCLES TGL	
AS APPROVED OR DIRECTED BY THE ENGINEER	400	100	100	0.03	3.37	
<b>PROJECT TOTALS</b>	<b>400</b>	<b>100</b>	<b>100</b>	<b>0.03</b>	<b>3.37</b>	



## STRUCTURE SUMMARY & DETAILS

NOT TO SCALE

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

*Mark C. Netardus P.E.*

09/13/2024

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	9



CONTROLLING PROJECT ID 6462-75-001

DISTRICT Yoakum  
HIGHWAY SH0095

COUNTY Lavaca

# Estimate & Quantity Sheet

CONTROL SECTION JOB				6462-75-001		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00206750			
COUNTY				Lavaca			
HIGHWAY				SH0095			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	104-7006	REMOV CONC (RIPRAP)	SY	104.000		104.000	
	132-7017	EMBANK (VEH)(OC)(TY C)	CY	110.200		110.200	
	164-7002	BROADCAST SEED (PERM_RURAL_CLAY)	SY	400.000		400.000	
	164-7005	BROADCAST SEED (TEMP_WARM)	SY	100.000		100.000	
	164-7006	BROADCAST SEED (TEMP_COOL)	SY	100.000		100.000	
	168-7001	VEGETATIVE WATERING	TGL	3.370		3.370	
	400-7006	CUT & RESTORING PAV	SY	330.000		330.000	
	400-7010	CEM STABIL BKFL	CY	284.900		284.900	
	402-7001	TRENCH EXCAVATION PROTECTION	LF	441.000		441.000	
	432-7006	RIPRAP (CONC)(CL C)	CY	16.000		16.000	
	432-7041	RIPRAP (STONE PROTECTION)(12 IN)	CY	23.000		23.000	
	460-7003	CMP (GAL STL 18 IN)	LF	40.000		40.000	
	460-7005	CMP (GAL STL 24 IN)	LF	38.000		38.000	
	462-7004	CONC BOX CULV (4 FT X 3 FT)	LF	8.500		8.500	
	462-7006	CONC BOX CULV (5 FT X 2 FT)	LF	108.000		108.000	
	462-7012	CONC BOX CULV (6 FT X 4 FT)	LF	62.000		62.000	
	464-7001	RC PIPE (CL III)(12 IN)	LF	32.000		32.000	
	464-7003	RC PIPE (CL III)(18 IN)	LF	98.000		98.000	
	464-7005	RC PIPE (CL III)(24 IN)	LF	93.000		93.000	
	464-7007	RC PIPE (CL III)(30 IN)	LF	149.000		149.000	
	464-7043	RC PIPE (ARCH)(CL III)(DES 4)	LF	134.000		134.000	
	464-7045	RC PIPE (ARCH)(CL III)(DES 6)	LF	68.000		68.000	
	466-7101	HEADWALL (CH - PW - 0) (DIA= 24 IN)	EA	1.000		1.000	
	466-7175	WINGWALL (PW - 1) (HW=5 FT)	EA	2.000		2.000	
	467-7095	SET (TY I)(S= 5 FT)(HW= 3 FT)(3:1)(C)	EA	2.000		2.000	
	467-7096	SET (TY I)(S= 5 FT)(HW= 3 FT)(4:1)(C)	EA	2.000		2.000	
	467-7304	SET (TY II) (18 IN) (CMP) (6: 1) (P)	EA	2.000		2.000	
	467-7308	SET (TY II) (18 IN) (RCP) (6: 1) (P)	EA	4.000		4.000	
	467-7324	SET (TY II) (24 IN) (CMP) (6: 1) (P)	EA	2.000		2.000	
	467-7325	SET (TY II) (24 IN) (RCP) (3: 1) (C)	EA	2.000		2.000	
	467-7328	SET (TY II) (24 IN) (RCP) (6: 1) (P)	EA	2.000		2.000	
	467-7345	SET (TY II) (30 IN) (RCP) (3: 1) (C)	EA	2.000		2.000	
	467-7346	SET (TY II) (30 IN) (RCP) (4: 1) (C)	EA	2.000		2.000	
	467-7348	SET (TY II) (30 IN) (RCP) (6: 1) (P)	EA	2.000		2.000	
	467-7440	SET (TY II) (DES 4) (RCP) (4: 1) (C)	EA	4.000		4.000	
	467-7456	SET (TY II) (DES 6) (RCP) (4: 1) (C)	EA	2.000		2.000	
	496-7036	REMOV STR (SMALL)	EA	14.000		14.000	



DISTRICT	COUNTY	CCSJ	SHEET
Yoakum	Lavaca	6462-75-001	10



# Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6462-75-001

DISTRICT Yoakum  
HIGHWAY SH0095

COUNTY Lavaca

CONTROL SECTION JOB				6462-75-001		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00206750			
COUNTY				Lavaca			
HIGHWAY				SH0095			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	500-7001	MOBILIZATION	LS	1.000		1.000	
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	6.000		6.000	
	506-7039	TEMP SEDMT CONT FENCE (INSTALL)	LF	400.000		400.000	
	506-7041	TEMP SEDMT CONT FENCE (REMOVE)	LF	400.000		400.000	
	658-7056	INSTL OM ASSM (OM-2Y)(WC)GND	EA	24.000		24.000	
	752-7002	SPOT TREE TRIMMING / BRUSH REMOVAL	LF	35.000		35.000	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

DATE: 9/11/2024 \$TIME\$  
 FILE: \$FILES\$

**WORKER SAFETY NOTES:**



1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

<p><b>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT</b>  <a href="http://www.txdot.gov">http://www.txdot.gov</a></p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS


SHEET 1 OF 12

			
<p><b>BARRICADE AND CONSTRUCTION          GENERAL NOTES          AND REQUIREMENTS</b></p> <p><b>BC (1) - 21</b></p>			
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT November 2002	CONT	SECT	HIGHWAY
REVISIONS		JOB	VARIOUS
4-03 7-13	6462	75	001
9-07 8-14	DIST	COUNTY	SHEET NO.
5-10 5-21	YKM	LAVACA, ETC.	12
95			




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TYPICAL LOCATION OF CROSSROAD SIGNS**



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
  - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
  - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
  - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
  - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
  - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

**T-INTERSECTION**



**CSJ LIMITS AT T-INTERSECTION**

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

**TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>1,5,6</sup>**

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "X" Feet (Apprx.)
CW20 <sup>4</sup>	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 <sup>2</sup>
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 <sup>2</sup>
			65	700 <sup>2</sup>
			70	800 <sup>2</sup>
			80	1000 <sup>2</sup>
*			*	* <sup>3</sup>


\* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

**GENERAL NOTES**


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

**WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS**




When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS**



**SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS**



**NOTES**

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
  - \*\* CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
  - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
  - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



**BARRICADE AND CONSTRUCTION PROJECT LIMIT**

**BC (2) - 21**


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT SECT	JOB	HIGHWAY	
REVISIONS	6462 75	001	VARIOUS	
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	YKM	LAVACA, ETC.	13	

DATE: 9/11/2024 \$TIME\$ FILE: \$FILES\$

# TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



## GUIDANCE FOR USE:

### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

## GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:
 

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
  - Law enforcement.
  - Flagger stationed next to sign.
  - Portable changeable message sign (PCMS).
  - Low-power (drone) radar transmitter.
  - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

SHEET 3 OF 12



## BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT


BC (3) - 21

FILE:	bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		6462	75	001	VARIOUS
9-07	8-14	DIST	COUNTY	SHEET NO.	
7-13	5-21	YKM	LAVACA, ETC.	14	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS**



\* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

**ATTACHMENT FOR SIGN SUPPORTS**




Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports

**Nails shall NOT be allowed.**  
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

**STOP/SLOW PADDLES**

1. STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
2. STOP/SLOW paddles shall be retroreflectORIZED when used at night.
3. STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
4. Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B <sub>FL</sub> OR C <sub>FL</sub> SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

1. Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
2. When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
3. When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
4. If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
5. If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRs standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
6. Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

1. Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
2. Wooden sign posts shall be painted white.
3. Barricades shall NOT be used as sign supports.
4. All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
5. The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
6. The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
7. The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
8. Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
9. The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

1. The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - a. Long-term stationary - work that occupies a location more than 3 days.
  - b. Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - c. Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - d. Short, duration - work that occupies a location up to 1 hour.
  - e. Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

**SIGN MOUNTING HEIGHT**

1. The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
2. The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
3. Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
4. Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
5. Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

**SIZE OF SIGNS**

1. The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

**SIGN SUBSTRATES**

1. The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
2. "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
3. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

**REFLECTIVE SHEETING**

1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
2. White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
3. Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>FL</sub> or Type C<sub>FL</sub>, shall be used for rigid signs with orange backgrounds.

**SIGN LETTERS**

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

**REMOVING OR COVERING**

1. When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
2. Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
3. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
4. When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
5. Burlap shall NOT be used to cover signs.
6. Duct tape or other adhesive material shall NOT be affixed to a sign face.
7. Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

**SIGN SUPPORT WEIGHTS**

1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
2. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
3. Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
4. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
5. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as fire inner tubes) shall NOT be used.
6. Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
7. Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
8. Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

**FLAGS ON SIGNS**

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12





**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	YKM	LAVACA, ETC.	15	


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

**WEDGE ANCHORS**  
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

**OTHER DESIGNS**  
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
  - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- \* See BC(4) for definition of "Work Duration."  
\*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.  
□ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

**BC(5) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	YKM	LAVACA, ETC.	16	

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$



WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

# RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

## PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

## Phase 1: Condition Lists

### Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

### Other Condition List

FRONTAGE ROAD CLOSED
SHOULDER CLOSED XXX FT
RIGHT LN CLOSED XXX FT
RIGHT X LANES OPEN
DAYTIME LANE CLOSURES
I-XX SOUTH EXIT CLOSED
EXIT XXX CLOSED X MILE
RIGHT LN TO BE CLOSED
X LANES CLOSED TUE - FRI

ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT

ROAD REPAIRS XXXX FT
LANE NARROWS XXXX FT
TWO-WAY TRAFFIC XX MILE
CONST TRAFFIC XXX FT
UNEVEN LANES XXXX FT
ROUGH ROAD XXXX FT
ROADWORK NEXT FRI-SUN
US XXX EXIT X MILES
LANES SHIFT *

\* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

## Phase 2: Possible Component Lists

### Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE *

### Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

### Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

### \*\* Advance Notice List

TUE-FRI XX AM-X PM
APR XX-XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM-XX AM

\*\* See Application Guidelines Note 6.

## APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

## WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

## FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canot	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	Hwy	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number

DATE: 9/11/2024 \$TIME\$ FILE: \$FILES\$




## BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	YKM	LAVACA, ETC.	17	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



**CONCRETE TRAFFIC BARRIER (CTB)**


- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

**LOW PROFILE CONCRETE BARRIER (LPCB)**



**DELINEATION OF END TREATMENTS**

**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**

**WARNING LIGHTS**


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>FL</sub> or C<sub>FL</sub> Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

**ATTENTION**  
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) - 21**

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		6462	75	001	VARIOUS				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	YKM	LAVACA, ETC.		18				

DATE: 9/11/2024 \$TIME\$  
 FILE: \$FILES\$



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
 FILE: \$FILES\$

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign  
(Maximum Sign Dimension)  
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel  
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>FL</sub> or Type C<sub>FL</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) - 21**


FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		6462	75	001	VARIOUS				
4-03	8-14	DIST	COUNTY	SHEET NO.					
9-07	5-21	YKM	LAVACA, ETC.	19					
7-13									

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**FIXED**  
(Rigid or self-righting)


**DRIVEABLE**



**PORTABLE**


**VERTICAL PANELS (VPs)**

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**


- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



Fixed Base w/ Approved Adhesive (Driveable Base, or Flexible Support can be used)

- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>FL</sub> or Type C<sub>FL</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



**LONGITUDINAL CHANNELIZING DEVICES (LCD)**

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

**WATER BALLASTED SYSTEMS USED AS BARRIERS**

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long cones and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

**GENERAL NOTES**

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * X			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80	800'	880'	960'	80'	160'	

\*X Taper lengths have been rounded off.  
L=Length of Taper (FT.) W=Width of Offset (FT.)  
S=Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	YKM	LAVACA, ETC.	20	

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


**TYPE 3 BARRICADES**

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




**TYPICAL STRIPING DETAIL FOR BARRICADE RAIL**




**TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES**

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

**TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION**



PERSPECTIVE VIEW




PLAN VIEW

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

**CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS**




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.  
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.



**TRAFFIC CONTROL FOR MATERIAL STOCKPILES**

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	YKM	LAVACA, ETC.	21	

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$



## WORK ZONE PAVEMENT MARKINGS

### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

## Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE  
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER  
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS


- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - (two amber reflective surfaces with yellow body).  
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


**BC(11) - 21**

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
2-98 9-07 5-21	DIST	COUNTY	SHEET NO.	
1-02 7-13	YKM	LAVACA, ETC.	<b>22</b>	
11-02 8-14				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

## PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

## CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectorized pavement markings.




RAISED PAVEMENT MARKERS

## LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectorized pavement markings.






RAISED PAVEMENT MARKERS

## TWO-WAY LEFT TURN LANE


## STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



### SOLID LINES




### BROKEN LINES



### REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



## BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC(12)-21

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."




FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	YKM	LAVACA, ETC.	23	
11-02 8-14				

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$



LEGEND			
	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	$L = \frac{WS^2}{60}$	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE				
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓	✓	✓

- GENERAL NOTES**
- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.
  - Stockpiled material should be placed a minimum of 30 feet from nearest traveled way.
  - Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
  - See TCP(5-1) for shoulder work on divided highways, expressways and freeways.
  - Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.
  - CW21-5 "SHOULDER WORK" signs may be used in place of CW20-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.





<b>TRAFFIC CONTROL PLAN</b>				
<b>CONVENTIONAL ROAD</b>				
<b>SHOULDER WORK</b>				
<b>TCP (2-1) - 18</b>				
FILE: tcp2-1-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
2-94 4-98	DIST	COUNTY	SHEET NO.	
8-95 2-12	YKM	LAVACA, ETC.	24	
1-97 2-18				



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$



**LEGEND**

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "x" Distance	Suggested Longitudinal Buffer Space "B"	Stopping Sight Distance
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent			
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'	200'
35		205'	225'	245'	35'	70'	160'	120'	250'
40		265'	295'	320'	40'	80'	240'	155'	305'
45	L = WS	450'	495'	540'	45'	90'	320'	195'	360'
50		500'	550'	600'	50'	100'	400'	240'	425'
55		550'	605'	660'	55'	110'	500'	295'	495'
60		600'	660'	720'	60'	120'	600'	350'	575'
65		650'	715'	780'	65'	130'	700'	410'	645'
70		700'	770'	840'	70'	140'	800'	475'	730'
75		750'	825'	900'	75'	150'	900'	540'	820'

\* Conventional Roads Only  
\*\* Taper lengths have been rounded off.  
L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

**TYPICAL USAGE**

	MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
		✓	✓	✓	

**GENERAL NOTES**

- Flags attached to signs where shown, are REQUIRED.
  - All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
  - The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
  - Flaggers should use two-way radios or other methods of communication to control traffic.
  - Length of work space should be based on the ability of flaggers to communicate.
  - A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
  - Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.
- TCP (2-2a)**
- The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban areas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
  - The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum mounting height.
- TCP (2-2b)**
- Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
  - If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles. (See table above).
  - Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situations.

**Texas Department of Transportation** Traffic Operations Division Standard

**TRAFFIC CONTROL PLAN**  
**ONE-LANE TWO-WAY**  
**TRAFFIC CONTROL**

**TCP (2-2) - 18**

FILE: tcp2-2-18.dgn	DN:	CK:	DW:	CK:
© TxDOT December 1985	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
8-95 3-03	DIST	COUNTY	SHEET NO.	
1-97 2-12	YKM	LAVACA, ETC.	25	
4-98 2-18				




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

Warning sign and rumble strip sequence in opposite direction is same as below.

Flagger to Flagger (Length of Work Area)	ADT	# of Rumble Strip Arrays
1/8 Mile	< 4,500	1
	≥ 4,500	2
1/4 Mile	< 3,500	1
	≥ 3,500	2
1/2 Mile	< 2,600	1
	≥ 2,600	2
1 Mile	< 1,600	1
	≥ 1,600	2
> 1 Mile	N/A	2



RUMBLE STRIPS ON ONE-LANE TWO-WAY APPLICATION



RUMBLE STRIPS FOR LANE CLOSURE ON CONVENTIONAL ROADWAY

GENERAL NOTES

- Each Rumble Strip Array should consist of three rumble strips spaced center to center at the spacing shown in Table 2, placed transverse across the lane at locations shown.
- The CW17-2T "RUMBLE STRIPS AHEAD" sign should be located after the CW20-1D "ROAD WORK AHEAD" sign and spaced as shown. If traffic is observed to be queuing, or is expected to queue beyond the Rumble Strips, the CW17-2T sign and the first Rumble Strip Array may be located upstream of the CW20-1D sign as necessary to provide needed warning.
- Temporary Rumble Strips will be considered subsidiary to Item 502, and shall be a product listed on the Compliant Work Zone Traffic Control Devices.
- Remove Temporary Rumble Strips before removing the advanced warning signs.
- Temporary Rumble Strips should not be used on horizontal curves, loose gravel, soft or bleeding asphalt, heavily rutted pavements or unpaved surfaces.
- Temporary Rumble Strips shall be installed and maintained as per manufacturer's recommendations.
- This standard sheet shall be used in conjunction with other appropriate TCP standard, TMUTCD typical application or project specific detail for the project.
- The one-lane two-way application may utilize a flagger, an Automated Flagger Assistance Device (AFAD) or a Portable Traffic Signal (PTS).
- Replace defective Temporary Rumble Strips as directed by the Engineer.
- Temporary Rumble Strips may be used on freeways or expressways based on engineering judgment and written direction from the Engineer.

Speed	Approximate distance between strips in an array
≤ 40 MPH	10'
> 40 MPH & ≤ 55 MPH	15'
= 60 MPH	20'
≥ 65 MPH	* 35' +

	Type 3 Barricade		Channelizing Devices
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)
	Trailer Mounted Flashing Arrow Panel		Portable Changeable Message Sign (PCMS)
	Sign		Traffic Flow
	Flag		Flagger

Posted Speed *	Formula	Minimum Desirable Taper Lengths **			Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X" Distance	Suggested Longitudinal Buffer Space "B"
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent		
30	L = WS <sup>2</sup> / 60	150'	165'	180'	30'	60'	120'	90'
35		205'	225'	245'	35'	70'	160'	120'
40		265'	295'	320'	40'	80'	240'	155'
45	L = WS	450'	495'	540'	45'	90'	320'	195'
50		500'	550'	600'	50'	100'	400'	240'
55		550'	605'	660'	55'	110'	500'	295'
60		600'	660'	720'	60'	120'	600'	350'
65		650'	715'	780'	65'	130'	700'	410'
70		700'	770'	840'	70'	140'	800'	475'
75		750'	825'	900'	75'	150'	900'	540'

\* Conventional Roads Only  
 \*\* Taper lengths have been rounded off.  
 L=Length of Taper (FT) W=Width of Offset (FT)  
 S=Posted Speed (MPH)

MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
	✓	✓		

◆ Signs are for illustrative purposes only. Signs required may vary depending on the TCP, TMUTCD Typical Application, or project specific details for the project.  
 \* For posted speeds in excess of 65 MPH, it is recommended that spacing is increased as speed limits increase. Increasing space between rumble strips will improve effectiveness.



Texas Department of Transportation  
 Traffic Safety Division Standard


## TEMPORARY RUMBLE STRIPS

### WZ (RS) - 22


FILE: wzrs22.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2012	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
2-14 1-22	DIST	COUNTY	SHEET NO.	
4-16	YKM	LAVACA, ETC.	26	

LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV



LAT: 29.790662°N  
LONG: 97.094830°W



**CULVERT STA 273+25 RT**  
EXIST 1 - 18" X 36.5' CMP TO BE REMOVED  
PROP 1 - 18" X 40' CMP &  
SET (TY II)(18")(CMP)(6:1)(P) LT & RT  
USING SETP-PD.



*Mark C. Netardus P.E.*

09/13/2024



**CULVERT LAYOUT**  
FM 154 - FAYETTE CO  
SCALE: 1" = 10'



Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 1 OF 20


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	27

LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV



LAT: 29.799862°N  
LONG: 96.796716°W



**CULVERT STA 492+75 LT**  
EXIST 1 - DES 2 X 51.3' CMP WITH SETS TO BE REMOVED  
PROP 1 - 18" X 54' RCP &  
SET (TY II)(18")(RCP)(6:1)(P)(LT & RT)  
USING SETP-PD.





*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
FM 155 - FAYETTE CO  
SCALE: 1" = 10'  
Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	28

LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV

EXIST ROW


EXIST ROW



LAT: 29.847853°N  
LONG: 96.691608°W



**CULVERT STA 72+67**  
EXIST 1 - 30" x 32' RCP W/ HEADWALLS TO BE REMOVED  
PROP 1 - 30" X 43' RCP &  
SET (TY II)(30")(RCP)(4:1)(C) LT & RT  
USING SETP-CD.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
FM 2503 - FAYETTE CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 3 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	29





LEGEND




CEM STAB BKFL




CUT & RESTORE PAV



LAT: 29.950439°N  
LONG: 96.725217°W



**CULVERT STA 175+50 LT**  
EXIST 1 - 24" x 57.5' CMP TO BE REMOVED  
PROP 1 - 30" x 50' RCP &  
SET (TY II)(30")(RCP)(6:1)(P) LT & RT  
USING SETP-PD.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**

SH 159 - FAYETTE CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 4 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	30


LEGEND




CEM STAB BKFL



CUT & RESTORE PAV



LAT: 30.068973°N  
LONG: 96.694772°W




NOTES:

- 1 - SEE INLET DETAILS SHEETS
- 2 - INLET GRATE IS CONSIDERED SUBSIDIARY TO ITEM 432-7004

**CULVERT STA 799+49.85**

EXIST 1 - CENTERLINE 4' X 3' CBC &  
2 - PARALLEL 24" CMPS  
REMOVE CBC HEADWALL, & CMP SET  
EXTEND 4' X 3' CBC 8.5' LT USING SCC-3&4, SCC-MD, & INLET DETAILS SHEETS  
EXTEND EXIST 24" CMPS 7' & 17' TO STUB INTO PROPOSED CBC EXTENSION  
BACKFILL DITCH TO GRADE & SEED.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**


SH 237 - FAYETTE CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED


SHEET 5 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	31

① May be changed as directed by the Engineer.




**PLAN**




**TYPICAL APRON PLAN**

(Showing reinforcing in walls and in apron)




**GRATE MOUNTING DETAIL**

1/2" Dia x 6" Hex Head Anchor Bolt (ASTM-A307) or Threaded Rod (ASTM-A36) with one Plain Steel Washer placed under Hex Nut. One additional Hex Nut shall be furnished for each Threaded Rod.




Flush or 1/16" Max

**ANCHOR BOLT OPTIONS**




**SECTION A-A**

(See SCC-3 & 4 for Culvert Plan of Reinf Steel For Extension)



**SECTION B-B**



*Mark C. Netardus P.E.*

09/13/2024


**SH 237  
INLET DETAILS**

NTS

Texas Department of Transportation  
©2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	32

SHEET 1 OF 2




**PIPE CONNECTION DETAIL**

Connecting pipes should enter within 10° of normal to inlet wall. If necessary, pipe elbow or curved approach alignment should be used to stay within this limit.




**GRATE ORIENTATION DETAIL**


If possible, horizontal grate inlet should be oriented such that both traffic and ditch water approach parallel to bars on grate. If this is not possible, orientation must favor traffic flow. Grate is not to be used under direct traffic, rather it is to be used in ditches and medians away from the roadway.




**GRATE PLAN**



**BARS L (#4)**




**BARS V (#4)**



**SECTION C-C**

**GENERAL NOTES:**

- Apron shall be cast-in-place.
- In areas of conflict between reinforcing steel, blockouts, pipes, anchor bolts or other reinforcing steel, the reinforcement shall be bent or adjusted to clear as directed by the Engineer.
- Anchor Bolts are 1/2" Dia ASTM A307 Grade A bolts (or A36 threaded rods with one tack welded hex head nut each) with one hex head nut and one plain steel washer.
- Structural Steel for grates shall conform to the requirements of ASTM Designation A-36 or AISI Designation M1010-M1020.
- All reinforcing steel shall be Grade 60 unless otherwise noted.
- All steel components except reinforcing, shall be galvanized after fabrication. Galvanizing damaged during transport or construction shall be repaired in accordance with the specifications.
- All concrete shall be Class "C" (f'c = 3,600 psi).



*Mark C. Netardus P.E.*

09/13/2024

**SH 237  
INLET DETAILS**

NTS

Texas Department of Transportation  
©2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	33




LEGEND

-  CEM STAB BKFL
-  CUT & RESTORE PAV

EXIST ROW


EXIST ROW




LAT: 28.976442°N  
LONG: 97.291028°W

EXIST ROW

EXIST ROW



**CULVERT STA 86+65**  
EXIST 1 - DES 6 X 44' CMP TO BE REMOVED  
PROP 2 - DES 4 X 48' RCP &  
SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT  
USING SETP-CD-A.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
FM 3157 - DEWITT CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 6 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	34



LEGEND




CEM STAB BKFL




CUT & RESTORE PAV



LAT: 28.891406°N  
LONG: 97.575144°W



**CULVERT STA 163+59.40**  
EXIST 1 - 30" x 38' CMP TO BE REMOVED  
PROP 1 - 30" X 40' RCP &  
SET (TY II)(30")(RCP)(3:1)(C) LT & RT  
USING SETP-CD.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**

FM 239 - DEWITT CO

SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 7 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	35


LEGEND



CEM STAB BKFL




CUT & RESTORE PAV




← FM 766

LAT: 29.279911°N  
LONG: 97.354950°W



**CULVERT STA 512+10 LT**  
EXIST 1 - 18" x 36' CMP TO BE REMOVED  
PROP 1 - 18" X 44' RCP &  
SET (TY II)(18" )(RCP)(6:1)(P) LT & RT  
USING SETP-PD.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**



FM 766 - DEWITT CO  
SCALE: 1" = 10'


Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 8 OF 20


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	36

LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV



LAT: 29.306422°N  
LONG: 97.244436°W



**CULVERT STA 30+50**  
EXIST 2 - DES 6 x 42' CMP TO BE REMOVED  
PROP 2 - DES 6 X 42' RCP &  
SET (TY II)(DES 6)(RCP)(4:1)(C) LT & RT  
USING SETP-CD-A.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
FM 951 - DEWITT CO  
SCALE: 1" = 10'



Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 9 OF 20


FED. RD. DIV. NO. 6		PROJECT NO.	
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	37



LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV

EXIST ROW




LAT: 28.997630°N  
 LONG: 97.506410°W

EXIST ROW



**CULVERT STA 403+23**  
 EXIST 1 - 30" X 30' CMP TO BE REMOVED  
 PROP 1 - DES 4 X 38' RCP &  
 SET (TY II)(DES 4)(RCP)(4:1)(C) LT & RT  
 USING SETP-CD-A.



*Mark C. Netardus P.E.*



09/13/2024


**CULVERT LAYOUT**  
 FM 240 - DEWITT CO  
 SCALE: 1" = 10'

Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED SHEET 10 OF 20


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	38

LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV



LAT: 29.166791°N  
LONG: 97.511668°W



**CULVERT STA 196+35**  
EXIST 2 - DES 6 x 40' CMP TO BE REMOVED  
PROP 1 - 5' X 2' X 40' CBC &  
SET (TY I)(S=5 FT)(HW= 3 FT)(3:1)(C) LT & RT  
USING SETB-CD, SCP-MD, BCS, SCP-5.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
FM 238 - DEWITT CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED


SHEET 11 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	39

LEGEND


-  CEM STAB BKFL
-  CUT & RESTORE PAV

EXIST ROW



LAT: 29.703456°N  
LONG: 97.344158°W


EXIST ROW



EXIST ROW

**CULVERT STA 2155+00**

EXIST 1 - DES 5 CMP STUBBED INTO 4' X 2.5' CBC LT & RT. 60.6' TO BE REMOVED  
 PROP 1 - 5' X 2' X 68' CBC &  
 SET (TY I)(S = 5 FT)(HW = 3 FT)(4:1)(C) LT & RT  
 USING BCS, SCP-5, SETB-CD, SCP-MD.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**



US 90 - GONZALES CO  
 SCALE: 1" = 10'


Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED

SHEET 12 OF 20


FED. RD. DIV. NO. 6		PROJECT NO.	
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	40

LEGEND

 CEM STAB BKFL  
 CUT & RESTORE PAV




LAT: 29.593403°N  
LONG: 97.585703°W



- NOTES:
- 1 - CONTRACTOR MUST COORDINATE WITH TPWD PRIOR TO CONSTRUCTION
  - 2 - CARE IS TO BE TAKEN TO AVOID AS MANY ROOTS AS POSSIBLE FROM EXISTING TREES
  - 3 - CCC ROCK IS NOT TO BE DISTURBED UNLESS OTHERWISE APPROVED OR DIRECTED BY THE ENGINEER

**CULVERT STA 5+15**  
EXIST 1 - 12" X 20' CMP TO BE REMOVED  
PROP 1 - 12" X 32' RCP.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
PR 11 - GONZALES CO  
SCALE: 1" = 10'



Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED


SHEET 13 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	41




**LEGEND**

-  CEM STAB BKFL
-  CUT & RESTORE PAV




LAT: 29.554656°N  
LONG: 97.676339°W



- NOTES:
- 1 - CONTRACTOR MUST COORDINATE WITH TPWD PRIOR TO CONSTRUCTION
  - 2 - SEE CH-PW-0 (MOD) SHEET
  - 3 - USE CUT & RESTORE PAVEMENT DETAIL

**CULVERT STA 11+52**  
EXIST 2 - 24" X 20' CMP  
EXTEND 2' LT & ADD  
HEADWALL (CH - PW - 0) (DIA= 24 IN)  
USING HEADWALL (CH-PW-0 (MOD)).



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
PW - GONZALES CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

FED. RD. DIV. NO. 6		PROJECT NO.	
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	42

LEGEND




CEM STAB BKFL




CUT & RESTORE PAV


FM 340



LAT: 29.450193°N  
LONG: 96.998973°W



**CULVERT STA 97+50 LT**  
EXIST 1 - 24" X 29.5' RCP  
EXTEND 4' LT & 15' RT  
ADD SET (TY II)(24")(RCP)(6:1)(P) LT & RT  
USING SETP-PD.



Mark C. Netardus P.E.

09/13/2024

**CULVERT LAYOUT**



FM 340 - LAVACA CO  
SCALE: 1" = 10'


Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 15 OF 20


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	43

**LEGEND**


-  CEM STAB BKFL
-  CUT & RESTORE PAV



LAT: 29.591575°N  
 LONG: 97.140722°W



**CULVERT STA 327+50**  
 EXIST 1 - 6' X 4' X 61.6' CBC TO BE REMOVED  
 PROP 1 - 6' X 4' X 62' CBC &  
 WINGWALL (PW - 1) (HW=5 FT) LT & RT  
 USING SCP-MD, SCP-6, PW, BCS.



*Mark C. Netardus P.E.*


09/13/2024

**CULVERT LAYOUT**  
 SH 95 - LAVACA CO  
 SCALE: 1" = 10'

Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED


FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	44

SHEET 16 OF 20




← FM 155

LAT: 29.500331°N  
LONG: 96.735586°W



**CULVERT STA 197+11**  
EXIST 1 - 24" X 30.5' CMP  
REMOVE 2' LT & RT  
EXTEND 5' LT & RT &  
SET (TY II)(24") (CMP)(6:1)(P) LT & RT  
USING SETP-PD.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**  
FM 155 - LAVACA CO  
SCALE: 1" = 10'

Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED SHEET 17 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	45




LEGEND

-  CEM STAB BKFL
-  CUT & RESTORE PAV

EXIST ROW


EXIST ROW




LAT: 29.457203°N  
LONG: 96.786083°W

EXIST ROW

EXIST ROW



**CULVERT STA 65+31**  
EXIST 2 - 24" X 39' CMP TO BE REMOVED  
PROP 2 - 24" X 37' RCP &  
SET (TY II)(24")(RCP)(3:1)(C) LT & RT  
USING SETP-CD.



*Mark C. Netardus P.E.*



09/13/2024

**CULVERT LAYOUT**  
FM 3283 - LAVACA CO  
SCALE: 1" = 10'


Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 18 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	46



**CULVERT STA 206+90.3**  
EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE  
REMOVE EXIST CONC RIPRAP RT  
PLACE CONC RIPRAP RT.



*Mark C. Netardus P.E.*

09/13/2024



**CULVERT LAYOUT**

SH 95 - LAVACA CO  
SCALE: 1" = 10'


Texas Department of Transportation  
© 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
ALL RIGHTS RESERVED

SHEET 19 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	47



**CULVERT STA 219+82**  
 EXIST 1 - 6' X 4' X 81.7' CBC TO REMAIN IN PLACE  
 REMOVE EXIST CONC RIPRAP RT  
 PLACE CONC RIPRAP RT.



*Mark C. Netardus P.E.*

09/13/2024

**CULVERT LAYOUT**

SH 95 - LAVACA CO  
 SCALE: 1" = 10'

Texas Department of Transportation  
 © 2024 BY TEXAS DEPARTMENT OF TRANSPORTATION  
 ALL RIGHTS RESERVED

SHEET 20 OF 20

FED. RD. DIV. NO.		PROJECT NO.	
6			
CONT.	SECT.	JOB	HIGHWAY NO.
6462	75	001	VARIOUS
STATE	DIST.	COUNTY	SHEET NO.
TEXAS	YKM	LAVACA, ETC.	48

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert No. Spans ~ Span X Height	Max Fill Height (Ft)	Applicable Box Culvert Standard (4)	Applicable Wingwall or End Treatment Standard	Skew Angle (0°, 15°, 30° or 45°)	Side Slope or Channel Slope Ratio (SL:1)	T Culvert Top Slab Thickness (In)	U Culvert Wall Thickness (In)	C Estimated Curb Height (Ft)	Hw (1) Height of Wingwall (Ft)	A Curb to End of Wingwall (Ft)	B 0 set of End of Wingwall (Ft)	Lw Length of Longest Wingwall (Ft)	Ltw Culvert Toewall Length (Ft)	Atw Anchor Toewall Length (Ft)	Riprap Apron (CY)	Class "C" Conc (Curb) (CY) (2)	Class "C" Conc (Wingwall) (CY) (3)	Total Wingwall Area (SF)
SH 237 @ Round Top Mercantile (Lt)	1 ~ 4' x 3'	0.25'	SCC-3&4	None	0°	2:1	8"	7"	0.479'	N/A'	N/A	N/A	N/A	N/A	N/A	0.0	0.1	N/A	N/A
FM 238 (Both)	1 ~ 5' x 2'	3.25'	SCP-5	SETB-CD	0°	3:1	6"	6"	0.250'	2.500'	N/A	N/A	6.500'	N/A	6.167'	0.0	0.2	2.8	N/A
US 90 STA 2155+00 (Both)	1 ~ 5' x 2'	3.25'	SCP-5	SETB-CD	0°	3:1	6"	6"	0.250'	2.500'	N/A	N/A	6.500'	N/A	6.167'	0.0	0.2	2.8	N/A
SH 95 @ LCR 95D (Both)	1 ~ 6' x 4'	3.5'	SCP-6	PW-1	0°	2:1	7"	7"	0.250'	4.833'	N/A	N/A	9.667'	7.167'	N/A	0.0	0.2	13.2	186

**NOTES:**

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets; 30° maximum for safety end treatment

SL:1 = Horizontal : 1 Vertical

- Side slope at culvert for arched or straight wingwalls.
- Channel slope for parallel wingwalls.
- Slope must be 3:1 or flatter for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)

B = 0 set of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)

Atw = Length of anchor toewall (applicable to safety end treatment only)

Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt. Area for four wingwalls (two structure ends) if Both.

① Round the wall heights shown to the nearest foot for bidding purposes.

② Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class S concrete is required for the top slab of the culvert, also provide Class S concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.


③ Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.

④ Regardless of the type of culvert shown on this sheet, the Contractor has the option of furnishing cast-in-place or precast culverts unless otherwise shown elsewhere on the plans. If the Contractor elects to provide culverts of a different type than those shown on this sheet, it is the Contractor's responsibility to make the necessary adjustments to the dimensions and quantities shown.

**SPECIAL NOTE:**

This sheet is a supplement to the box culvert standards. It is to be filed out by the culvert specifier and provides dimensions for the construction of the box culvert wingwalls and safety end treatments.

An Excel 2010 spreadsheet to assist in completing this table can be downloaded from the Bridge Standards (English) web page on the TxDOT web site. The completed sheet must be signed, sealed, and dated by a licensed Professional Engineer.



Mark C. Netardus, P.E.

09/13/2024


		<b>Bridge Division Standard</b>	
<h2>BOX CULVERT SUPPLEMENT</h2> <h3>WINGS AND END TREATMENTS</h3>			
<h1>BCS</h1>			
FILE: CD-BCS-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT	February 2020	REVISIONS	
6462	75	001	VARIOUS
DIST	COUNTY	SHEET NO.	
YKM	LAVACA, ETC.	49	

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




PLAN OF SKEWED ENDS ~ FROM 0° TO 15° ⑦




PLAN OF SKEWED ENDS ~ OVER 30° TO 45°




PLAN OF SKEWED ENDS ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°



PLAN OF ANGLE SECTION ~ OVER 30° TO 45°



LENGTHENING DETAIL ①

- ① For skewed box culverts with less than 2'-0" of  $\ell$ , break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.  
For non-skewed box culverts with less than 2'-0" of  $\ell$  and for skewed or non-skewed culverts with a  $\ell$  depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension,  $N_b$ , of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.  
Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the normal riding surface, adjust the "H" dimension to provide a smooth riding surface.

- ② When the spacing between Bars B becomes less than half of the normal spacing, cut bars to avoid conflict.
- ③ The length of Bars B vary in the skewed end sections.
- ④  $[One\ half\ of\ overall\ width] \times [tangent\ of\ the\ skew\ angle]$
- ⑤ Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- ⑥ When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- ⑦ At the Contractor's option, for skews of 15° or less, place Bars B, C, and D parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B shown on the Single Box Culverts Cast-In-Place (SCC) standards sheets to accommodate the skew.

**CONSTRUCTION NOTES:**

Do not use permanent forms.  
When required, lap Bars H 1'-8" for uncoated or galvanized bars.  
Provide a minimum of 1 1/2" clear cover.

**MATERIAL NOTES:**

Provide Grade 60 reinforcing steel.  
Provide galvanized reinforcing steel, if required elsewhere in the plans.  
Provide Class C concrete ( $f'_c = 3,600$  psi) with these exceptions:  
provide Class S concrete ( $f'_c = 4,000$  psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the normal riding surface.

**GENERAL NOTES:**

Designed according to AASHTO LRFD Bridge Design Specifications.  
Refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for details of straight sections of culvert.  
For skewed sections and angle sections, refer to Single Box Culverts Cast-in-Place (SCC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.  
For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the culvert Single Box Culverts Cast-In-Place (SCC) standard sheets by the cosine of the skew angle.


Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING


		<b>Bridge Division Standard</b>	
<b>SINGLE BOX CULVERTS CAST-IN-PLACE MISCELLANEOUS DETAILS</b>			
<b>SCC-MD</b>			
FILE: CD-SCC-MD-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT February 2020	CONT: 6462	SECT: 75	JOB: 001
REVISIONS	COUNTY: YKM		HIGHWAY: LAVACA, ETC.
	SHEET NO.		50

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard is assumed to be the responsibility of the user. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




**TYPICAL SECTION**




**PLAN OF REINF STEEL**




**SECTION THRU CURB**



BARS C



BARS D



BARS K (#4)  
(Spa = 1'-0" Max)  
(Length = 4'-2")

- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above nished grade.
  - For structures with bridge rail, construct curbs flush with nished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR.  
Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.  
If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

**CONSTRUCTION NOTES:**

- Do not use permanent forms.
- Chamfer the bottom edge of the top slab 3" at the entrance.
- Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut out or raised, Bars C and D may be reversed.

**MATERIAL NOTES:**

- Provide Grade 60 reinforcing steel.
- Provide galvanized reinforcing steel if required elsewhere in the plans.
- Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
  - culverts with overlay,
  - culverts with 1-to-2 course surface treatment, or
  - culverts with the top slab as the final riding surface.
- Provide bar laps, where required, as follows:
  - Uncoated or galvanized ~ #4 = 1'-8" Min
  - Uncoated or galvanized ~ #5 = 2'-1" Min

**GENERAL NOTES:**

- Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
- See the Single Box Culverts Cast-In-Place Miscellaneous Detail (SCC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.  
Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2



**SINGLE BOX CULVERTS  
CAST-IN-PLACE  
0' TO 30' FILL**

**SCC-3 & 4**

FILE: CD-SCC34-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	51	

DISCLAIMER:  
 The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever.  
 TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
 FILE: \$FILE\$

SECTION DIMENSIONS				FILL HEIGHT ⑤	BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																								QUANTITIES														
					Bars B				Bars C				Bars D				Bars M ~ #4				Bars F1 ~ #4 at 18" Spa			Bars F2 ~ #4 at 18" Spa			Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total								
					S	H	T	U	No.	Size	Spa	Length	Weight	No.	Size	Spa	Length	Weight	" X "	" Y "	No.	Size	Spa	Length	Weight	" Y "	" Z "	No.	Spa	Length	Weight	No.	Length	Wt	No.	Length	Weight	Length	Wt	No.	Wt	Conc (CY)	Reinf (Lb)
3' - 0"	2' - 0"	8"	7"	30'	108	#5	9"	3' - 11"	441	108	#4	9"	5' - 4"	385	2' - 6"	2' - 10"	108	#4	9"	5' - 1"	367	2' - 10"	2' - 3"	108	9"	2' - 0"	144	3	39' - 9"	80	19	39' - 9"	505	3' - 11"	10	10	28	0.292	48.1	0.3	38	12.0	1,960
3' - 0"	3' - 0"	8"	7"	30'	108	#5	9"	3' - 11"	441	108	#4	9"	6' - 4"	457	3' - 6"	2' - 10"	108	#4	9"	5' - 1"	367	2' - 10"	2' - 3"	108	9"	3' - 0"	216	3	39' - 9"	80	23	39' - 9"	611	3' - 11"	10	10	28	0.335	54.3	0.3	38	13.7	2,210
4' - 0"	2' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	5' - 8"	613	2' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	2' - 0"	144	3	39' - 9"	80	21	39' - 9"	558	4' - 11"	13	12	33	0.342	63.4	0.4	46	14.1	2,581
4' - 0"	3' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	6' - 8"	721	3' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	3' - 0"	216	3	39' - 9"	80	25	39' - 9"	664	4' - 11"	13	12	33	0.385	70.5	0.4	46	15.8	2,867
4' - 0"	4' - 0"	8"	7"	30'	108	#5	9"	4' - 11"	554	162	#4	6"	7' - 8"	830	4' - 6"	3' - 2"	162	#4	6"	5' - 5"	586	3' - 2"	2' - 3"	108	9"	4' - 0"	289	3	39' - 9"	80	25	39' - 9"	664	4' - 11"	13	12	33	0.428	75.1	0.4	46	17.5	3,049

⑤ For direct tra c culverts ( ll height ≤ 2 ft.), identify the required box size and select the option with the minimum ll height.

HL93 LOADING SHEET 2 OF 2




**SINGLE BOX CULVERTS  
 CAST-IN-PLACE  
 0' TO 30' FILL**

**SCC-3 & 4**


FILE: CD-SCC34-21.dgn	DN: TBE	CK: BMP	DW: TxDOT	CK: TxDOT
TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
04/2021 Updated X values.	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	52	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**MULTIPLE UNIT PLACEMENT**



**SECTION B-B**




**DETAIL "A" (13)**




**WINGWALL CONNECTION**

(Also applies to safety end treatment.)




**SECTION THRU TOP SLABS LESS THAN 8"**




**SECTION THRU CURB**

QUANTITIES PER FOOT OF CURB (10)	
Reinforcing Steel	4.12 Lb
Concrete	0.037 CY



**BARS C (#4)**  
(Spa = 1'-0" Max)



**BARS K (#4)**  
(Spa = 1'-0" Max)  
(Length = 4'-2")

- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail, bicycle rail, or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- Extend curb, wingwall, or safety end treatment reinforcing into concrete closure. Bend or trim, as necessary, any reinforcing that does not t into closure area.
- Provide a 3'-0" Min cast-in-place concrete closure. Break back boxes in the eld or cast boxes short. Provide bands of reinforcing in the closure that are the same size and spacing as in the precast box section. Provide #4 longitudinal reinforcement spaced at 12 inches Max within the closure. Except where shown otherwise, construct the cast-in-place closure ush with the inside and outside faces of the precast box section.
- For multiple unit placements, adjust the length of the closure for the interior walls as necessary. Provide a 3'-0" Min cast-in-place closure in the top slab, bottom slab, and exterior wall. See Section B-B detail when interior walls are cast full length.
- Extend precast box reinforcing a minimum of 1'-0" into concrete closure (Typ).
- Place bands of reinforcing matching the inside and outside face reinforcing in the gaps of the top and bottom slabs. Place a band matching the outside face reinforcing of the wall in the gaps of the walls (placed in the outside face only). Tack weld the bands to the exposed reinforcing at each point of contact.
- For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above nished grade.
  - For structures with bridge rail, construct curbs ush with nished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- Cement stabilized back II between boxes is considered part of the box culvert for payment.
- All curb concrete and reinforcing is considered part of the box culvert for payment.
- Any additional concrete and reinforcing required for the closures will be considered subsidiary to the box culvert for payment.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- For multiple unit placement with overlay, with 1 to 2 course surface treatment, or with the top slab as the nial riding surface, provide wall closure as shown in Detail "A".
- This dimension may be increased with approval of the Engineer to allow the precast boxes to be tunneled or jacked in accordance with Item 476, "Jacking, Boring, or Tunneling Pipe or Box." No payment will be made for any additional material in the gap between adjacent boxes.


**MATERIAL NOTES:**

- Provide Grade 60 reinforcing steel.
- Provide ASTM A1064 welded wire reinforcement.
- Provide Class C concrete (f'c = 3,600 psi) for the closures.
- Provide cement stabilized back II meeting the requirements of Item 400, "Excavation and Back II for Structures."
- Any additional concrete required for the closures will be considered subsidiary to the box culvert.


**GENERAL NOTES:**

- Designed according to AASHTO LRFD Bridge Design Specifications.
- Refer to the Single Box Culverts Precast (SCP) standard sheets for details and notes not shown.
- Chamfer the bottom edge of the top slab closure 3 inches at culvert closure ends.


Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bars dimensions are out-to-out of bars.



**ANGLE DETAIL**



**SECTION A-A**



**PLAN OF SKEWED ENDS**

(Showing multi-box placement.)

HL93 LOADING

		<b>Bridge Division Standard</b>	
<b>BOX CULVERTS PRECAST MISCELLANEOUS DETAILS</b>			
<b>SCP-MD</b>			
FILE: CD-SCP-MD-20.dgn	DN: GAF	CK: LMW	DW: BWH/TxDOT
©TxDOT February 2020	CONT	SECT	JOB
REVISIONS	6462	75	001
	DIST	COUNTY	SHEET NO.
	YKM	LAVACA, ETC.	53

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard to the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

BOX DATA


SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) <sup>②</sup>							① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8	
5	2	8	7	6	< 2	-	0.19	0.27	0.18	0.14	0.19	0.19	0.17	6.0
5	2	6	6	6	2 < 3	44	0.22	0.20	0.16	0.14	-	-	-	5.1
5	2	6	6	6	3 - 5	44	0.16	0.14	0.14	0.14	-	-	-	5.1
5	2	6	6	6	10	36	0.15	0.14	0.14	0.14	-	-	-	5.1
5	2	6	6	6	15	36	0.20	0.18	0.18	0.14	-	-	-	5.1
5	2	6	6	6	20	36	0.26	0.23	0.24	0.14	-	-	-	5.1
5	2	6	6	6	25	36	0.33	0.29	0.29	0.14	-	-	-	5.1
5	2	6	6	6	30	36	0.39	0.34	0.35	0.14	-	-	-	5.1
5	3	8	7	6	< 2	-	0.19	0.31	0.21	0.14	0.19	0.19	0.17	6.6
5	3	6	6	6	2 < 3	45	0.18	0.24	0.19	0.14	-	-	-	5.7
5	3	6	6	6	3 - 5	36	0.14	0.17	0.16	0.14	-	-	-	5.7
5	3	6	6	6	10	36	0.14	0.16	0.17	0.14	-	-	-	5.7
5	3	6	6	6	15	35	0.16	0.21	0.22	0.14	-	-	-	5.7
5	3	6	6	6	20	35	0.21	0.27	0.28	0.14	-	-	-	5.7
5	3	6	6	6	25	35	0.26	0.34	0.34	0.14	-	-	-	5.7
5	3	6	6	6	30	35	0.31	0.41	0.41	0.14	-	-	-	5.7
5	4	8	7	6	< 2	-	0.19	0.33	0.24	0.14	0.19	0.19	0.17	7.2
5	4	6	6	6	2 < 3	45	0.16	0.27	0.22	0.14	-	-	-	6.3
5	4	6	6	6	3 - 5	45	0.14	0.19	0.18	0.14	-	-	-	6.3
5	4	6	6	6	10	36	0.14	0.18	0.18	0.14	-	-	-	6.3
5	4	6	6	6	15	35	0.14	0.23	0.24	0.14	-	-	-	6.3
5	4	6	6	6	20	35	0.17	0.30	0.31	0.14	-	-	-	6.3
5	4	6	6	6	25	35	0.21	0.37	0.38	0.14	-	-	-	6.3
5	4	6	6	6	30	35	0.25	0.44	0.45	0.14	-	-	-	6.3
5	5	8	7	6	< 2	-	0.19	0.35	0.26	0.14	0.19	0.19	0.17	7.8
5	5	6	6	6	2 < 3	45	0.14	0.29	0.24	0.14	-	-	-	6.9
5	5	6	6	6	3 - 5	45	0.14	0.21	0.20	0.14	-	-	-	6.9
5	5	6	6	6	10	45	0.14	0.19	0.20	0.14	-	-	-	6.9
5	5	6	6	6	15	36	0.14	0.24	0.25	0.14	-	-	-	6.9
5	5	6	6	6	20	35	0.15	0.31	0.32	0.14	-	-	-	6.9
5	5	6	6	6	25	35	0.18	0.38	0.39	0.14	-	-	-	6.9
5	5	6	6	6	30	35	0.21	0.46	0.47	0.14	-	-	-	6.9



FILL HEIGHT 2 FT AND GREATER



FILL HEIGHT LESS THAN 2 FT



**MATERIAL NOTES:**  
Provide 0.03 sq. in./ft. minimum longitudinal reinforcement at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.  
Provide Class H concrete ( $f'c = 5,000$  psi).

**GENERAL NOTES:**  
Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.  
See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.  
In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design II height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)."

① For box length = 8'-0"  
② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcing per linear foot of box length. AS5 is minimum required area of reinforcing per linear foot of box width.

HL93 LOADING

Texas Department of Transportation  
Bridge Division Standard

**SINGLE BOX CULVERTS  
PRECAST  
5'-0" SPAN**

**SCP-5**


FILE: CD-SCP05-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
CONT	SECT	JOB	HIGHWAY	
6462	75	001	VARIOUS	
DIST	COUNTY	SHEET NO.		
YKM	LAVACA, ETC.	54		

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard to the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$


BOX DATA

SECTION DIMENSIONS					Fill Height (ft.)	M (Min) (in.)	REINFORCING (sq. in. / ft.) <sup>②</sup>							① Lift Weight (tons)
S (ft.)	H (ft.)	TT (in.)	TB (in.)	TS (in.)			AS1	AS2	AS3	AS4	AS5	AS7	AS8	
6	2	8	7	7	< 2	-	0.23	0.27	0.19	0.17	0.19	0.17	7.2	
6	2	7	7	7	2 < 3	43	0.25	0.21	0.17	0.17	-	-	6.8	
6	2	7	7	7	3 - 5	43	0.20	0.17	0.17	0.17	-	-	6.8	
6	2	7	7	7	10	39	0.20	0.17	0.17	0.17	-	-	6.8	
6	2	7	7	7	15	39	0.26	0.20	0.20	0.17	-	-	6.8	
6	2	7	7	7	20	39	0.34	0.26	0.26	0.17	-	-	6.8	
6	2	7	7	7	25	39	0.43	0.32	0.32	0.17	-	-	6.8	
6	2	7	7	7	30	39	0.52	0.38	0.39	0.17	-	-	6.8	
6	3	8	7	7	< 2	-	0.20	0.31	0.22	0.17	0.19	0.19	7.9	
6	3	7	7	7	2 < 3	43	0.21	0.24	0.19	0.17	-	-	7.5	
6	3	7	7	7	3 - 5	39	0.17	0.18	0.17	0.17	-	-	7.5	
6	3	7	7	7	10	39	0.17	0.18	0.19	0.17	-	-	7.5	
6	3	7	7	7	15	38	0.22	0.24	0.24	0.17	-	-	7.5	
6	3	7	7	7	20	38	0.28	0.31	0.31	0.17	-	-	7.5	
6	3	7	7	7	25	38	0.35	0.38	0.39	0.17	-	-	7.5	
6	3	7	7	7	30	38	0.42	0.46	0.46	0.17	-	-	7.5	
6	4	8	7	7	< 2	-	0.19	0.34	0.25	0.17	0.19	0.19	8.6	
6	4	7	7	7	2 < 3	43	0.19	0.27	0.21	0.17	-	-	8.2	
6	4	7	7	7	3 - 5	39	0.17	0.21	0.19	0.17	-	-	8.2	
6	4	7	7	7	10	39	0.17	0.20	0.21	0.17	-	-	8.2	
6	4	7	7	7	15	38	0.18	0.27	0.27	0.17	-	-	8.2	
6	4	7	7	7	20	38	0.24	0.34	0.35	0.17	-	-	8.2	
6	4	7	7	7	25	38	0.29	0.43	0.42	0.17	-	-	8.2	
6	4	7	7	7	30	38	0.35	0.51	0.52	0.17	-	-	8.2	
6	5	8	7	7	< 2	-	0.19	0.37	0.28	0.17	0.19	0.19	9.3	
6	5	7	7	7	2 < 3	43	0.17	0.30	0.24	0.17	-	-	8.9	
6	5	7	7	7	3 - 5	43	0.17	0.23	0.21	0.17	-	-	8.9	
6	5	7	7	7	10	39	0.17	0.22	0.23	0.17	-	-	8.9	
6	5	7	7	7	15	38	0.17	0.28	0.29	0.17	-	-	8.9	
6	5	7	7	7	20	38	0.20	0.37	0.38	0.17	-	-	8.9	
6	5	7	7	7	25	38	0.25	0.45	0.46	0.17	-	-	8.9	
6	5	7	7	7	30	38	0.30	0.54	0.55	0.17	-	-	8.9	
6	6	8	7	7	< 2	-	0.19	0.38	0.30	0.17	0.19	0.19	10	
6	6	7	7	7	2 < 3	52	0.17	0.32	0.26	0.17	-	-	9.6	
6	6	7	7	7	3 - 5	52	0.17	0.24	0.22	0.17	-	-	9.6	
6	6	7	7	7	10	43	0.17	0.23	0.24	0.17	-	-	9.6	
6	6	7	7	7	15	39	0.17	0.29	0.31	0.17	-	-	9.6	
6	6	7	7	7	20	39	0.18	0.38	0.39	0.17	-	-	9.6	
6	6	7	7	7	25	38	0.23	0.46	0.48	0.17	-	-	9.6	
6	6	7	7	7	30	38	0.27	0.55	0.57	0.17	-	-	9.6	




CORNER OPTION "A" CORNER OPTION "B"

FILL HEIGHT 2 FT AND GREATER



CORNER OPTION "A" CORNER OPTION "B"

FILL HEIGHT LESS THAN 2 FT



SECTION A-A

(Showing top and bottom slab joint reinforcement.)

**MATERIAL NOTES:**

Provide 0.03 sq. in./ft. minimum longitudinal reinforcing at each face in slabs and walls. This minimum requirement may be met by the transverse wires when wire mesh reinforcement is used.  
Provide Class H concrete (f'c = 5,000 psi).

**GENERAL NOTES:**

Designs shown conform to ASTM C1577. Refer to ASTM C1577 for information or details not shown.  
See Box Culverts Precast Miscellaneous Details (SCP-MD) standard sheet for details and notes not shown.  
In lieu of furnishing the designs shown on this sheet, the contractor may furnish an alternate design that is equal to or exceeds the box design for the design II height in the table. Submit shop plans for alternate designs in accordance with Item "Precast Concrete Structural Members (Fabrication)."

HL93 LOADING

		<b>Bridge Division Standard</b>	
<h2>SINGLE BOX CULVERTS PRECAST</h2> <h3>6'-0" SPAN</h3> <h3>SCP-6</h3>			
FILE: CD-SCP06-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
©TxDOT February 2020	CONT	SECT	JOB
REVISIONS	6462	75	001
DIST	COUNTY		SHEET NO.
YKM	LAVACA, ETC.		55

① For box length = 8'-0"

② AS1 thru AS4, AS7 and AS8 are minimum required areas of reinforcement per linear foot of box length. AS5 is minimum required area of reinforcement per linear foot of box width.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

**TABLE OF DIMENSIONS AND REINFORCING STEEL**  
(Wings for one structure end)




Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings) ④		Estimated Quantities per ft of Toewall (1-toewall)	
	W	X	Y	Z	Bars J1		Bars J2		Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
					Size	Spa	Size	Spa				
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

**TABLE OF WINGWALL REINFORCING**  
(2-wings)

Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

**TABLE OF TOEWALL REINFORCING**

Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



**WING DIMENSION FORMULAS:**

(All values are in feet.)

$$Hw = H + T + C$$

$$Lw = (Hw)(SL) \div \cosine(\theta) \text{ for Type PW-1}$$

$$= (Hw - 1')(SL) \div \cosine(\theta) \text{ for Type PW-2 and } Hw \ge 4'$$

$$= (Hw - 0.5')(SL) \div \cosine(\theta) \text{ for Type PW-2 and } Hw < 4'$$








For cast-in-place culverts:  
Ltw = [(N)(S) + (N + 1)(U)] ÷ cosine(θ)

For precast culverts:  
Ltw = [(N)(2U + S) + (N - 1)(0.5')] ÷ cosine(θ)  
Total Wingwall Area (two wings ~ SF)  
= (2)(Hw)(Lw) for Type PW-1  
= (2)(Hw)(Lw) - 6 SF for Type PW-2 and Hw ≥ 4'  
= (2)(Hw)(Lw) - 1.5 SF for Type PW-2 and Hw < 4'

Hw = Height of wingwall  
Lw = Length of wingwall  
Ltw = Culvert toewall length  
N = Number of culvert spans  
SL:1 = Channel slope ratio. (horizontal: 1 vertical, usual value is 2:1)  
θ = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.

- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"  
For 30° skew ~ 2"  
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
  - For structures without bridge rail, construct curbs no more than 3" above nished grade.
  - For structures with bridge rail, construct curbs with nished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.



**DETAILS FOR NON-SKEWED BOX CULVERTS**

**DETAILS FOR SKEWED BOX CULVERTS**  
(Showing 30° skew.)

**DESIGNER NOTES:**

Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall. Type PW-2 can only be used for applications without a railing mounted to the wingwall.

**MATERIAL NOTES:**

Provide Class C concrete (f'c=3,600 psi).  
Provide Grade 60 reinforcing steel.  
Provide galvanized reinforcing steel if required elsewhere in the plans.

**GENERAL NOTES:**

Designed in accordance with AASHTO LRFD Bridge Design Specifications.  
Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.  
See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information. Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.



**CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2**


PW

FILE: CD-PW-20.dgn	DN: GAF	CK: CAF	DW: TxDOT	CK: TxDOT
©TxDOT February 2020 REVISIONS	CONT SECT	JOB	HIGHWAY	
	6462 75	001	VARIOUS	
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	56	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$



**TYPICAL WINGWALL ELEVATION**

(Pipe runners not shown for clarity.)



**ISOMETRIC VIEW OF TYPICAL INSTALLATION**

**WING DIMENSION CALCULATIONS:**

$$Hw = H + T + C - 0.250'$$

$$Lw = (Hw - 0.333') (SL)$$

For cast-in-place culverts:  
 $Atw = (N) (S) + (N + 1) (U)$

For precast culverts:  
 $Atw = (N) (2U + S) + (N - 1) (0.500')$

$$\text{Total Wingwall Area (SF)} = (0.5) (Hw + 0.333') (Lw) (N + 1)$$

$$\text{Total Concrete Volume (CY)} = [(\text{Wingwall Area}) (0.583') + (Lw) (Atw) (0.583') + (Atw) (1.167') (1.167' - 0.583')] \div (27)$$

**PIPE RUNNER DIMENSION CALCULATIONS:**

$$\text{Pipe Runner Length} = (Lw) (K1) - (1.917')$$

$$\text{Total Reinforcing (Lb)} = (1.55) (Lw) (Atw) + (4.43) (Atw) + (K2) (Hw) (N + 1) (\sqrt{Lw})$$

C = Height of curb above top of top slab (feet)  
Hw = Height of wingwall (feet)  
K = Constant value for use in formulas  
Slope SL:1 K1 K2  
3:1 ~ 1.054 ~ 7.45  
4:1 ~ 1.031 ~ 8.49  
6:1 ~ 1.014 ~ 10.30  
Atw = Anchor toewall length (feet)  
Lw = Length of wingwall (feet)  
N = Number of culvert barrels  
SL:1 = Side slope ratio (horizontal : 1 vertical)  
See applicable box culvert standard for H, S, T, and U values.

**MATERIAL NOTES:**  
Provide Grade 60 reinforcing steel.  
Provide galvanized reinforcing steel if required elsewhere in the plans.  
Adjust reinforcing as necessary to provide a minimum clear cover of 1 1/2".  
Provide Class "C" concrete (f'c = 3,600 psi).  
Provide pipe runners, cross pipes, and anchor pipes meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
Provide ASTM A307 bolts.  
Galvanize all steel components, except the concrete reinforcing, unless required elsewhere in the plans, after fabrication.  
Repair galvanizing damaged during transport or construction in accordance with the Item 445, "Galvanizing."

**GENERAL NOTES:**  
Designed according to AASHTO LRFD Bridge Design Specifications.  
The safety end treatments shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.  
Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.  
The quantities for pipe runners, reinforcing steel, and concrete resulting from the formulas given herein are for Contractor's information only.  
See the Box Culvert Supplement (BCS) standard sheet for additional dimensions and information.  
Alternate design drawings bearing the seal of a professional engineer will be acceptable for precast construction of the safety end treatments.


Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.

SHEET 1 OF 2

Texas Department of Transportation  
Bridge Division Standard


**SAFETY END TREATMENT FOR 0° SKEW BOX CULVERTS (MAXIMUM Hw = 7'-0") TYPE I ~ CROSS DRAINAGE SETB-CD**

FILE: CD-SETBCD-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	57	



**SECTION A-A**

(Showing typical wingwall and wing slab reinforcing. Pipe runners not shown for clarity.)




**PLAN VIEWS OF CORNER DETAILS**

- Recommended values of slope are: 3:1, 4:1, and 6:1. Provide 3:1 or steeper slope.
- 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures without railing and curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet.
- Wingwall and slab thicknesses may be the same as the adjacent culvert wall and slab thicknesses (7" minimum). If thicknesses greater than the minimum (7") are used, no changes will be made in quantities and no additional compensation will be allowed.
- For vehicle safety, reduce curb height, if necessary, to provide a maximum 3" projection. No changes will be made in quantities and no additional compensation will be allowed for this work.
- For culverts with C = 0", the precast culvert reinforcing may extend 1'-0" minimum into wingwall. Wingwall Bars D and R may be omitted. Otherwise, refer to the Wingwall Connection detail on the Box Culvert Precast Miscellaneous Details (SCP-MD) standard sheet.


**TABLE OF REINFORCING BAR SIZES AND SPACING**

Bar	Size	Spacing
C	#4	10" Max
D	#4	Match F and E
E	#4	1'-0" Max
F	#4	1'-3" Max
G	#6	As shown
J	#4	10" Max
K	#4	1'-0" Max
R	#4	As shown




DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard is for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




NOTE: At Contractor's option, make the cross pipe continuous across the inside wingwalls. If option is selected, omit the sleeve pipe and make a 1 5/16 inch diameter through hole in the cross pipe to accept the anchor bolt at the centerline of each inside wingwall.


**CROSS PIPE INSTALLATION DETAILS**




**FOR USE IN OUTSIDE CULVERT BAY**



**CROSS PIPE AND CONNECTIONS DETAILS**




**BOTTOM ANCHOR PIPE DETAILS**




**BOTTOM ANCHOR TOEWALL DETAILS**

(Wingwall not shown for clarity.)



**CROSS PIPE SLEEVE PIPE DETAILS**




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

**PIPE RUNNER DETAILS**

- ⑥ Cross pipe is the same size as the pipe runner. Cross pipe stub out is the same size as the anchor pipe.
- ⑦ Note that actual slope of safety pipe runner may vary slightly from side slope.
- ⑧ Take care to ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1#2" hole to ensure that the lap of the safety pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.

Maximum Pipe Runner Length	Required Pipe Runner Size			Required Anchor Pipe Size		
	Pipe Size	Pipe O.D.	Pipe I.D.	Pipe Size	Pipe O.D.	Pipe I.D.
10'-0"	3" STD	3.500"	3.068"	2" STD	2.375"	2.067"
19'-8"	4" STD	4.500"	4.026"	3" STD	3.500"	3.068"
34'-2"	5" STD	5.563"	5.047"	4" STD	4.500"	4.026"



**SIDE ELEVATION**


(Showing pipe runner with Cross Pipe Connection Option A1 and Bottom Anchor Toewall Option B2. Wingwall not shown for clarity.)

SHEET 2 OF 2

				<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT FOR 0° SKEW BOX CULVERTS (MAXIMUM Hw = 7'-0") TYPE I ~ CROSS DRAINAGE SETB-CD</b>					
FILE: CD-SETBCD-20.dgn	DN: GAF	CK: CAT	DW: TxDOT	CK: TxDOT	
©TxDOT	February 2020	CONT	SECT	JOB	HIGHWAY
	REVISIONS	6462	75	001	VARIOUS
		DIST	COUNTY		SHEET NO.
		YKM	LAVACA, ETC.		58




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



NOTE: All pipe runners, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.


**SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER**

(Showing corrugated metal pipe (CMP) culvert. Details of reinforced concrete pipe (RCP) culvert are similar.)



**SIDE ELEVATION OF CAST-IN-PLACE CONCRETE**

(Showing reinforced concrete pipe (RCP) culvert. Details of corrugated metal pipe (CMP) culvert are similar. Pipe runners not shown for clarity)



**ISOMETRIC VIEW OF TYPICAL INSTALLATION**

(Showing installation with no skew.)

**CROSS PIPE LENGTHS AND PIPE RUNNER LENGTHS (1)(2)**

Nominal Culvert I.D.	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length											
			3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
			0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
24"	1' - 7"	3' - 5"	N/A	N/A	N/A	5' - 10"	N/A	N/A	N/A	8' - 1"	N/A	N/A	N/A	12' - 9"
27"	1' - 8"	3' - 8"	N/A	N/A	5' - 5"	6' - 11"	N/A	N/A	7' - 7"	9' - 7"	N/A	N/A	11' - 11"	14' - 11"
30"	1' - 10"	3' - 11"	N/A	N/A	6' - 4"	8' - 0"	N/A	N/A	8' - 9"	11' - 0"	N/A	N/A	13' - 8"	17' - 0"
33"	1' - 11"	4' - 2"	6' - 2"	6' - 5"	7' - 3"	9' - 1"	8' - 6"	8' - 10"	10' - 0"	12' - 5"	13' - 3"	13' - 9"	15' - 5"	19' - 2"
36"	2' - 1"	4' - 5"	6' - 11"	7' - 3"	8' - 2"	10' - 2"	9' - 6"	9' - 11"	11' - 2"	13' - 10"	14' - 9"	15' - 3"	17' - 2"	21' - 3"
42"	2' - 4"	4' - 11"	8' - 6"	8' - 10"	9' - 11"	12' - 4"	11' - 7"	12' - 0"	13' - 6"	16' - 8"	17' - 9"	18' - 5"	20' - 8"	25' - 7"
48"	2' - 7"	5' - 5"	10' - 1"	10' - 5"	11' - 9"	N/A	13' - 7"	14' - 2"	15' - 10"	N/A	20' - 9"	21' - 6"	24' - 2"	N/A
54"	3' - 0"	5' - 11"	11' - 8"	12' - 1"	N/A	N/A	15' - 8"	16' - 3"	N/A	N/A	23' - 10"	24' - 8"	N/A	N/A
60"	3' - 3"	6' - 5"	13' - 3"	N/A	N/A	N/A	17' - 9"	N/A	N/A	N/A	26' - 10"	N/A	N/A	N/A

**TYPICAL PIPE CULVERT MITERS (3)**

Side Slope	0° Skew	15° Skew	30° Skew	45° Skew
3:1	3:1	3.106:1	3.464:1	4.243:1
4:1	4:1	4.141:1	4.619:1	5.657:1
6:1	6:1	6.212:1	6.928:1	8.485:1

**CONDITIONS WHERE PIPE RUNNERS ARE NOT REQUIRED (2)**

Nominal Culvert I.D.	Single Pipe Culvert	Multiple Pipe Culverts
12" thru 21"	Skews thru 45°	Skews thru 45°
24"	Skews thru 45°	Skews thru 30°
27"	Skews thru 30°	Skews thru 15°
30"	Skews thru 15°	Skews thru 15°
33"	Skews thru 15°	Always required
36"	Normal (no skew)	Always required
42" thru 60"	Always required	Always required

**STANDARD PIPE SIZES AND MAX PIPE RUNNER LENGTHS (1)**

Pipe Size	Pipe O.D.	Pipe I.D.	Max Pipe Runner Length
2" STD	2.375"	2.067"	N/A
3" STD	3.500"	3.068"	10' - 0"
4" STD	4.500"	4.026"	19' - 8"
5" STD	5.563"	5.047"	34' - 2"

**ESTIMATED CONCRETE RIPRAP QUANTITIES (CY) (5)**

Nominal Culvert I.D.	3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
12"	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.6	0.7	0.7	0.7	0.8
15"	0.5	0.5	0.5	0.6	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9
18"	0.5	0.5	0.6	0.6	0.6	0.7	0.7	0.8	0.8	0.8	0.9	1.0
21"	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9	0.9	0.9	1.0	1.2
24"	0.6	0.7	0.7	0.8	0.8	0.8	0.8	1.0	1.0	1.0	1.1	1.3
27"	0.7	0.7	0.8	0.9	0.8	0.9	0.9	1.1	1.1	1.1	1.2	1.4
30"	0.8	0.8	0.8	0.9	0.9	0.9	1.0	1.2	1.2	1.2	1.3	1.6
33"	0.8	0.8	0.9	1.0	1.0	1.0	1.1	1.3	1.3	1.4	1.5	1.7
36"	0.9	0.9	0.9	1.1	1.1	1.1	1.2	1.4	1.4	1.5	1.6	1.8
42"	1.0	1.0	1.1	1.3	1.2	1.3	1.3	1.6	1.6	1.7	1.8	2.1
48"	1.1	1.1	1.2	N/A	1.4	1.4	1.5	N/A	1.9	1.9	2.1	N/A
54"	1.3	1.3	N/A	N/A	1.6	1.6	N/A	N/A	2.1	2.1	N/A	N/A
60"	1.4	N/A	N/A	N/A	1.7	N/A	N/A	N/A	2.3	N/A	N/A	N/A

(1) Provide pipe runner of the size shown in the tables. Provide cross pipe of the same size as the pipe runner. Provide cross pipe stub out and bottom anchor pipe of the next smaller size pipe as shown in the Standard Pipe Sizes and Max Pipe Runner Lengths table.

(2) This standard allows for the placement of only one pipe runner across each culvert pipe opening. In order to limit the clear opening to be traversed by an errant vehicle, the following conditions must be met:

For 60" culvert pipes, the skew must not exceed 0°.  
 For 54" culvert pipes, the skew must not exceed 15°.  
 For 48" culvert pipes, the skew must not exceed 30°.  
 For all culvert pipe sizes 42" and less, the skew must not exceed 45°.

If the above conditions cannot be met, the designer should consider using a safety end treatment with a red wings. For further information, refer to the TxDOT Roadway Design Manual.

(3) Miter = slope of mitered end of pipe culvert.

(4) Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap."

(5) Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only.

SHEET 1 OF 2




**SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE**

**SETP-CD**


FILE: CD-SETP-CD-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	59	

DATE: 9/11/2024 \$TIME\$ FILE: \$FILES\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**OPTION A1**      **OPTION A2**  
**CROSS PIPE AND CONNECTIONS DETAILS**




**SIDE ELEVATION OF SAFETY END TREATMENT INSTALLATION**

(Showing pipe runner with Cross Pipe Connection Option A1 and Anchor Pipe Option B2 on corrugated metal pipe (CMP) culvert. Reinforced concrete pipe culvert (RCP) details are similar. Riprap not shown for clarity)




**PLAN OF SKEWED INSTALLATION**




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

**PIPE RUNNER DETAILS**




**OPTION B1**      **OPTION B2**  
**BOTTOM ANCHOR PIPE DETAILS** ⑩




**OPTION B1**      **OPTION B2**  
**BOTTOM ANCHOR TOEWALL DETAILS**

(Culvert and riprap not shown for clarity.)



**SECTION A-A**  
**SHOWING CROSS PIPE AND ANCHOR TOEWALL**



**SHOWING TYPICAL PIPE CULVERT AND RIPRAP**

- ④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap."
- ⑥ Recommended values of side slope are 3:1, 4:1, and 6:1. All quantities, calculations, and dimensions shown herein are based on these recommended values. Slope of 3:1 or steeper is required for vehicle safety.
- ⑦ Note that actual slope of pipe runner may vary slightly from side slope of riprap and trimmed culvert pipe edge.
- ⑧ Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1/2 inch hole to ensure that the lap of the pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.

**MATERIAL NOTES:**  
Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.  
Provide pipe runners, cross pipes, and anchor pipes conforming to the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.  
Provide ASTM A307 bolts and nuts.  
Galvanize all steel components, except concrete reinforcing, after fabrication.  
Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**  
Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.  
Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.  
Payment for riprap and toewall is included in the price bid for each safety end treatment.  
Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap."




**SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE SETP-CD**

FILE: CD-SETP-CD-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	60	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




NOTE: All cross pipes, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.

**SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER**

(Showing corrugated metal pipe (CMP) culvert. Details at reinforced concrete pipe (RCP) culvert are similar.)




**ISOMETRIC VIEW OF TYPICAL INSTALLATION**




**SIDE ELEVATION OF CAST-IN-PLACE CONCRETE**


(Showing reinforced concrete pipe (RCP) culvert. Details at corrugated metal pipe (CMP) culvert are similar.)



**PIPE WITH BOLTED ANCHOR**




**PIPE WITH ANCHOR BARS**




**SECTION C-C**

**CROSS PIPE DETAILS**



**DETAIL "A"**


(Showing invert with corrugated metal pipe (CMP) culvert. Reinforced concrete pipe (RCP) culvert details are similar. Cross pipes not shown for clarity.)




**SECTION B-B**

(Cross pipes not shown for clarity.)

Limits of riprap (to be included with SET for payment) (5)



**SHOWING TYPICAL PIPE CULVERT AND RIPRAP**



**SHOWING CROSS PIPE WITH BOLTED ANCHOR**

**SECTION A-A**

**CROSS PIPE LENGTHS, REQUIRED PIPE SIZES, AND RIPRAP QUANTITIES**

Nominal Culvert I.D.	Conc Riprap (CY) (6)	Pipe Culvert Spa ~ G	Single Barrel ~ Q1	Multi-Barrel ~ Q1	Q2	Conditions for Use of Cross Pipes	Cross Pipe Sizes
12"	0.6	0' - 9"	N/A	2' - 1"	1' - 9"	3 or more pipe culverts	3" Std (3.500" O.D.)
15"	0.7	0' - 11"	N/A	2' - 5"	2' - 2"		
18"	0.8	1' - 2"	N/A	2' - 10"	2' - 8"		
21"	0.9	1' - 4"	N/A	3' - 2"	3' - 1"		
24"	0.9	1' - 7"	N/A	3' - 6"	3' - 7"	3 or more pipe culverts	3 1/2" Std (4.000" O.D.)
27"	1.0	1' - 8"	N/A	3' - 10"	3' - 11"		
30"	1.1	1' - 10"	N/A	4' - 2"	4' - 4"	2 or more pipe culverts	4" Std (4.500" O.D.)
33"	1.2	1' - 11"	4' - 2"	4' - 5"	4' - 8"		
36"	1.3	2' - 1"	4' - 5"	4' - 9"	5' - 1"	All pipe culverts	4" Std (4.500" O.D.)
42"	1.5	2' - 4"	4' - 11"	5' - 5"	5' - 10"		
48"	1.7	2' - 7"	5' - 5"	6' - 0"	6' - 7"	All pipe culverts	5" Std (5.563" O.D.)
54"	2.0	3' - 0"	5' - 11"	6' - 9"	7' - 6"		
60"	2.2	3' - 3"	6' - 5"	7' - 4"	8' - 3"		
66"	2.4	3' - 3"	6' - 11"	7' - 10"	8' - 9"		
72"	2.7	3' - 4"	7' - 5"	8' - 5"	9' - 4"		

- The proper installation of the first cross pipe is critical for vehicle safety. Place the top of the first cross pipe no more than 6" above the flow line.
- Provide cross pipes, except the first bottom pipe, of the size shown in the table. Provide a 3 1/2" standard pipe (4" O.D.) for the first bottom pipe.
- Install the third cross pipe from the bottom of the culvert using a bolted connection. Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access. At the Contractor's option, install all other cross pipes using the bolted connection details.
- Match cross slope as shown elsewhere in the plans. Cross slope of 6:1 or steeper is required for vehicle safety.
- Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap."
- Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for contractor's information only.

**MATERIAL NOTES:**

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. Provide cross pipes that meet the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 (Gr B), or API 5LX52. Provide ASTM A307 bolts and nuts. Galvanize all steel components, except concrete reinforcing, after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

**GENERAL NOTES:**

Cross pipes are designed for a traversing load of 10,000 pounds at yield as recommended by Research Report 280-2F, "Safety Treatment of Roadside Parallel-Drainage Structures", Texas Transportation Institute, March 1981. Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the cross pipes. Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap." Payment for riprap and toewall is included in the Price Bid for each Safety End Treatment.

				<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT FOR 12" DIA TO 72" DIA PIPE CULVERTS TYPE II ~ PARALLEL DRAINAGE SETP-PD</b>					
FILE: CD-SETP-PD-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF	
©TxDOT	REVISIONS	6462	75	001	VARIOUS
	DIST	COUNTY		SHEET NO.	
	YKM	LAVACA, ETC.		61	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$


## CROSS PIPE LENGTHS AND PIPE RUNNER LENGTHS ① ③

### Corrugated Metal Pipe (CMP) Culverts

Design	Pipe Culvert Span	Pipe Culvert Rise	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length												
					3:1 Side Slope				4:1 Side Slope				6:1 Side Slope				
					0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	
1	17"	13"	1' - 0"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
2	21"	15"	1' - 2"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
3	28"	20"	1' - 5"	3' - 9"	N/A	N/A	3' - 5"	4' - 7"	N/A	N/A	4' - 11"	6' - 5"	N/A	N/A	7' - 11"	10' - 2"	
4	35"	24"	1' - 8"	4' - 4"	3' - 10"	4' - 0"	4' - 7"	6' - 0"	5' - 5"	5' - 8"	6' - 6"	8' - 4"	8' - 8"	9' - 1"	10' - 3"	12' - 11"	
5	42"	29"	1' - 11"	4' - 11"	5' - 1"	5' - 4"	6' - 1"	7' - 10"	7' - 2"	7' - 5"	8' - 6"	10' - 9"	11' - 2"	11' - 8"	13' - 2"	16' - 6"	
6	49"	33"	2' - 2"	5' - 6"	6' - 2"	6' - 5"	7' - 4"	N/A	8' - 6"	8' - 10"	10' - 0"	N/A	13' - 3"	13' - 9"	15' - 6"	N/A	
7	57"	38"	2' - 5"	6' - 2"	7' - 6"	7' - 9"	N/A	N/A	10' - 2"	10' - 7"	N/A	N/A	15' - 9"	16' - 4"	N/A	N/A	


### Reinforced Concrete Pipe (RCP) Culverts

Design	Pipe Culvert Span	Pipe Culvert Rise	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length												
					3:1 Side Slope				4:1 Side Slope				6:1 Side Slope				
					0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	
1	22"	13 1/2"	1' - 0"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
2	26"	15 1/2"	1' - 2"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
3	28 1/2"	18"	1' - 5"	3' - 9 1/2"	N/A	N/A	2' - 10"	3' - 10"	N/A	N/A	4' - 2"	5' - 5"	N/A	N/A	6' - 9"	8' - 9"	
4	36 1/4"	22 1/2"	1' - 8"	4' - 5 1/4"	3' - 5"	3' - 7"	4' - 2"	5' - 6"	4' - 11"	5' - 1"	5' - 11"	7' - 7"	7' - 11"	8' - 3"	9' - 5"	11' - 11"	
5	43 3/4"	26 5/8"	1' - 11"	4' - 0 3/4"	4' - 6"	4' - 8"	5' - 5"	6' - 11"	6' - 4"	6' - 7"	7' - 6"	9' - 7"	10' - 0"	10' - 5"	11' - 9"	14' - 10"	
6	51 1/8"	31 5/16"	2' - 2"	5' - 8"	5' - 9"	6' - 0"	6' - 10"	N/A	7' - 11"	8' - 3"	9' - 4"	N/A	12' - 4"	12' - 10"	14' - 6"	N/A	
7	58 1/2"	36"	2' - 5"	6' - 3 1/2"	6' - 11"	7' - 3"	N/A	N/A	9' - 6"	9' - 11"	N/A	N/A	14' - 9"	15' - 4"	N/A	N/A	




### ISOMETRIC VIEW OF TYPICAL INSTALLATION

(Showing installation with no skew.)



### SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER

(Showing corrugated metal pipe (CMP) culvert. Details of reinforced concrete pipe (RCP) culvert are similar.)



### PLAN OF SKEWED INSTALLATION

### TYPICAL PIPE CULVERT MITERS ④

Side Slope	0° Skew	15° Skew	30° Skew	45° Skew
3:1	3:1	3.106:1	3.464:1	4.243:1
4:1	4:1	4.141:1	4.619:1	5.657:1
6:1	6:1	6.212:1	6.928:1	8.485:1

### STANDARD PIPE SIZES AND MAX PIPE RUNNER LENGTHS ①

Pipe Size	Pipe O.D.	Pipe I.D.	Max Pipe Runner Length
2" STD	2.375"	2.067"	N/A
3" STD	3.500"	3.068"	10' - 0"
4" STD	4.500"	4.026"	19' - 8"
5" STD	5.563"	5.047"	34' - 2"

### CONDITIONS WHERE PIPE RUNNERS ARE NOT REQUIRED ③

Design	Single Pipe Culvert	Multiple Pipe Culverts
1 and 2	Skews thru 45°	Skews thru 45°
3	Skews thru 35°	Skews thru 10°
4	Normal (no skew)	Always required
5 thru 7	Always required	Always required

### MATERIAL NOTES:

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. Provide pipe runners, cross pipes, and anchor pipes that meet the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52. Provide ASTM A307 bolts and nuts. Galvanize all steel components, except concrete reinforcing, after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

### GENERAL NOTES:

Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981. Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the Pipe Runners. Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap." Payment for riprap and toewall is included in the price bid for each safety end treatment.


- Provide pipe runner of the size shown in the tables. Provide cross pipe of the same size as the pipe runner. Provide cross pipe stub out and bottom anchor pipe of the next smaller size pipe as shown in the Standard Pipe Sizes and Max Pipe Runners Lengths table.
- Recommended values of slope are 3:1, 4:1, and 6:1. All quantities, calculations, and dimensions shown herein are based on these recommended values. Slope of 3:1 or steeper is required for vehicle safety.
- This standard allows for the placement of only one pipe runner across each culvert pipe opening. In order to limit the clear opening to be traversed by an errant vehicle, the following conditions must be met:  
  
For Design 1 through 5 culvert pipe sizes, the skew must not exceed 45°. For Design 6 culvert pipes, the skew must not exceed 30°. For Design 7 culvert pipes, the skew must not exceed 15°.  
  
If the above conditions cannot be met, the designer should consider using a safety end treatment withared wings. For further information, refer to the TxDOT "Roadway Design Manual."
- Miter = slope of mitered end of pipe culvert.

SHEET 1 OF 3

				<b>Bridge Division Standard</b>	
<b>SAFETY END TREATMENT FOR DESIGN 1 TO 7 ARCH PIPE CULVERTS TYPE II ~ CROSS DRAINAGE SETP-CD-A</b>					
FILE: CD-SETP-CD-A-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF	
©TxDOT	February 2020	CONT	SECT	JOB	HIGHWAY
	REVISIONS	6462	75	001	VARIOUS
		DIST	COUNTY	SHEET NO.	
		YKM	LAVACA, ETC.	62	


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$



SHOWING TYPICAL PIPE CULVERT AND RIPRAP

**SECTION A-A**



**SIDE ELEVATION OF CAST-IN-PLACE CONCRETE**

(Showing reinforced concrete pipe (RCP) culvert. Details of corrugated metal pipe (CMP) culvert are similar. Pipe runners not shown for clarity.)

Design	3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
	1	0.5	0.5	0.5	0.6	0.6	0.6	0.6	0.7	0.7	0.7	0.8
2	0.5	0.5	0.6	0.6	0.6	0.6	0.6	0.7	0.7	0.8	0.8	1.0
3	0.6	0.6	0.7	0.8	0.7	0.7	0.8	0.9	0.9	1.0	1.0	1.2
4	0.7	0.7	0.8	0.9	0.8	0.9	0.9	1.0	1.1	1.1	1.2	1.4
5	0.8	0.8	0.9	1.0	1.0	1.0	1.1	1.2	1.3	1.3	1.4	1.7
6	0.9	1.0	1.0	N/A	1.1	1.1	1.2	N/A	1.4	1.5	1.6	N/A
7	1.0	1.1	N/A	N/A	1.3	1.3	N/A	N/A	1.7	1.7	N/A	N/A

- ④ Miter = slope of mitered end of pipe culvert.
- ⑤ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap."
- ⑥ Quantities shown are for one end of one pipe culvert. For multiple pipe culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only.


**SAFETY END TREATMENT FOR DESIGN 1 TO 7 ARCH PIPE CULVERTS TYPE II ~ CROSS DRAINAGE SETP-CD-A**

FILE: CD-SETP-CD-A-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	63	




DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




**CROSS PIPE AND CONNECTIONS DETAILS**




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

**PIPE RUNNER DETAILS**




**BOTTOM ANCHOR PIPE DETAILS**




**BOTTOM ANCHOR TOEWALL DETAILS**

(Culvert and riprap not shown for clarity.)



**SHOWING CROSS PIPE AND ANCHOR TOEWALL**

**SECTION A-A**



**SIDE ELEVATION OF SAFETY END TREATMENT INSTALLATION**

(Showing pipe runner with Cross Pipe Connection Option A1 and Anchor Pipe Option B2 on corrugated metal pipe (CMP) culvert. Reinforced concrete pipe (RCP) culvert details are similar. Riprap not shown for clarity.)

- ⑦ Note that actual slope of pipe runner may vary slightly from side slope of riprap and trimmed culvert pipe edge.
- ⑧ Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- ⑨ After installation, inspect the 1#2" hole to ensure that the lap of the pipe runner with the bottom anchor pipe is adequate.
- ⑩ At fabricator's option, a heat bend to a smooth 5" radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.

SHEET 3 OF 3



**SAFETY END TREATMENT FOR DESIGN 1 TO 7 ARCH PIPE CULVERTS TYPE II ~ CROSS DRAINAGE**

**SETP-CD-A**

FILE: CD-SETP-CDA-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	64	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**TABLE OF VARIABLE DIMENSIONS (5) AND QUANTITIES FOR ONE HEADWALL**


Slope	Dia of Pipe (D)	Values for One Pipe			Values To Be Added for Each Add'l Pipe		
		W	Reinf (Lbs) (1)	Conc (CY) (2)	W	Reinf (Lbs) (1)	Conc (CY) (2)
2:1	24"	14' - 0"	217	2.1	3' - 7"	34	0.4
6:1	24"	38' - 0"	644	5.8	3' - 7"	34	0.4

**TABLE OF CONSTANT DIMENSIONS**


Dia of Pipe (D)	G	K (5)	H	T	E
24"	1' - 7"	1' - 0"	3' - 8"	0' - 9"	2' - 0"

**TABLE OF (6) REINFORCING STEEL**


Bar	Size	Spa	No.
A1	#5	~	2
A2	#5	1' - 6"	~
E	#5	~	2
F	#5	1' - 0"	~




**ELEVATION**




**ELEVATION**



**SECTION AT CENTER OF PIPE**



**PLAN OF NON-SKEWED PIPES**



**PLAN OF NON-SKEWED PIPES**


**MATERIAL NOTES:**  
Provide Grade 60 reinforcing steel.  
Provide Class C concrete (f'c = 3,600 psi).

**GENERAL NOTES:**  
Designed according to AASHTO LRFD Bridge Design Specifications.  
Do not mount bridge rails of any type directly to these culvert headwalls.  
This standard may not be used for wall heights, H, exceeding the values shown.


NTS

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.

- Total quantities include one 3'-1" lap for bars over 60' in length.
- Quantities shown are for concrete pipe and will increase slightly for metal pipe installations.
- Indicated slope is perpendicular to centerline pipe or pipes.
- For vehicle safety, construct curbs no more than 3" above finished grade. Reduce curb heights, if necessary, to meet these requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- Dimensions shown are usual and maximum.
- Quantities shown are for one structure end only (one headwall).



**BARS F2**



Mark C. Netardus, P.E.


09/13/2024

Texas Department of Transportation		Bridge Division Standard	
<b>CONCRETE HEADWALLS WITH PARALLEL WINGS FOR NON-SKEWED PIPE CULVERTS</b>			
<b>NEASLONEY PW CH-PW-0 (MOD)</b>			
FILE: CD-CH-PW0-20.dgn	DN: TxDOT	CK: TxDOT	OW: TxDOT
©TxDOT February 2020	CONT: 6462	SECT: 75	JOB: 001
REVISIONS	COUNTY: YKM		HIGHWAY: VARIOUS
	SHEET NO. 65		


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




PLAN



ELEVATION




SECTION A-A AT CAP




SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A



CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

**GENERAL NOTES:**


Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.  
See elsewhere in plans for locations and details of shoulder drains.

SHEET 1 OF 2


				<b>Bridge Division Standard</b>	
<h2>STONE RIPRAP</h2>					
<h3>SRR</h3>					
FILE: IMS-SRR-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES	
©TxDOT	April 2019	CONT	SECT	JOB	HIGHWAY
	REVISIONS	6462	75	001	VARIOUS
		DIST	COUNTY	SHEET NO.	
		YKM	LAVACA, ETC.	66	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$




**FIGURE 1 ~ TYPE R STONE RIPRAP**  
dry or grouted




**FIGURE 2 ~ TYPE F STONE RIPRAP**  
dry or mortared



**FIGURE 3 ~ TYPE F STONE RIPRAP**  
grouted




**FIGURE 4 ~ COMMON STONE RIPRAP**  
dry or grouted



**FIGURE 5 ~ PROTECTION STONE RIPRAP**

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.  
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



**PROTECTION STONE RIPRAP TOE OPTIONS** ⑤

SHEET 2 OF 2



**STONE RIPRAP**

**SRR**

FILE: MS-SRR-19.dgn	DN: AES	CK: JGD	DW: BWH	CK: AES
©TxDOT April 2019 REVISIONS	CONT 6462	SECT 75	JOB 001	HIGHWAY VARIOUS
	DIST YKM	COUNTY LAVACA, ETC.	SHEET NO. 67	



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		
SHEETING	Yellow, White or Red Type B or C reflective sheeting				Yellow, White or Red Type B or C Reflective Sheeting				<b>INSTL DEL ASSM</b> (D-XX)SZ X (XXXX)XXX (XX) <b>NUMBER OF REFLECTORS</b> S = Single D = Double <b>COLOR OF REFLECTORS</b> W = White Y = Yellow R = Red <b>REFLECTOR UNIT SIZE</b> 1 or 2 <b>TYPE OF POST OR DELINEATOR</b> WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector <b>TYPE OF MOUNT</b> GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF

OBJECT MARKERS								D & OM DESCRIPTIVE CODES		
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)	INSTL OM ASSM (OM-XX) (XXXX)XXX (XX)	
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4	TYPE OF OBJECT MARKER	NUMBER OF REFLECTORS OR DIRECTION
									1, 2, 3, or 4	X = 3-Size 2 reflector units (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector units (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only)
SHEETING	Yellow-Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting			Red -Type B <sub>FL</sub> or C <sub>FL</sub> Sheeting	TYPE OF POST	TYPE OF MOUNT
POST TYPE	TWT	WC	WC	WFLX	TWT			TWT	WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing	GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic
MOUNT TYPE	WAS, WAP	GND	GND	GND, SRF	WAS, WAP			WAS, WAP	DIRECTION	
									If Required BI = Bi-Directional	

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.		
DEVICE	GF1	GF2	CTB	W1-8		W1-6					
SHEETING	Yellow, White, Red			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)	SIZE (W x L)	48" x 24" (Conventional)	60" x 30" (Expressway & Freeway)
NOTE	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only		MOUNTING HEIGHT	7'-0"	
				NOTE	1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).						

**Texas Department of Transportation**  
Traffic Safety Division Standard

**DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION**  
D & OM(1)-20

FILE: dcm1-20.dgn	DN: TXDOT	CK: TXDOT	DN: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
10-09 3-15	DIST	COUNTY		SHEET NO.
4-10 7-20	YKM	LAVACA, ETC.		68

20A



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

**POST TYPE AND SUPPORT FOUNDATION DETAILS**

**TYPE OF BARRIER MOUNTS**


**WING CHANNEL (WC)**

**FLEXIBLE POSTS (YFLX, WFLX)**


**WEDGE ANCHOR SYSTEMS**

**GUARD FENCE ATTACHMENT**


**GND**




**GND**




**SRF**




**WAS**




**WAP**



**GF 1**



**GF 2**



**NOTES**

1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only.
2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.


**NOTES**

1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices.
2. Install per manufacturer's recommendations.
3. Post length may vary to meet field conditions.
4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.

**NOTE**

1. Install per manufacturer's recommendations.

**CONCRETE TRAFFIC BARRIER (CTB)**






**GENERAL NOTES**

1. Place delineators on a section of roadway at a consistent distance from the edge of pavement.
2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction.
3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible.
4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation.
5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface.
6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.

**TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS**

**CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN**

**DELINEATORS AND TYPE 2 OBJECT MARKERS**



**NOTE**

Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

**NOTE**

Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

See general notes 1, 2 and 3.



**DELINEATOR & OBJECT MARKER INSTALLATION**


**D & OM(2)-20**

FILE: dom2-20.dgn	DW: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
10-09 3-15	DIST	COUNTY		SHEET NO.
4-10 7-20	YKM	LAVACA, ETC.		<b>69</b>

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 9/11/2024 \$TIME\$  
FILE: \$FILES\$

**CROSSOVERS**




**DETAIL 1**

**FOR CULVERTS WITHOUT MBGF**




**DETAIL 2**

**FREEWAY DELINEATION FOR RAMPS AND ACCELERATION/DECELERATION LANES**




**DETAIL 3**

**TYPICAL APPLICATION OF DEAD END BARRICADE**



**DETAIL 4**

**TYPICAL DEAD END BARRICADE INSTALLATION**



**NOTES**

- Barricade striping shall be red and white reflective sheeting for all permanent road closures.
- Barricade striping is red and white sloping toward the center of the roadway.
- Type 3 Barricade Supports should be anchored to soil or pavement as described in compliant Work Zone Traffic Control Devices List, section D.2.f and D.2.g.

**DETAIL 5**

LEGEND	
	Bidirectional Delineator
	Delineator
	OM-3
	Barricade
	Sign
	OM-2
	Double Delineator



**DELINEATOR & OBJECT MARKER PLACEMENT DETAILS**

**D & OM(4) - 20**

FILE: dom4-20.dgn	DN: TxDOT	CK: TxDOT	DN: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	6462	75	001	VARIOUS
3-15	DIST	COUNTY	SHEET NO.	
7-20	YKM	LAVACA, ETC.	70	

**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

This SWP3 has been developed in accordance with the TPDES Construction General Permit TXR150000 (CGP). The Texas Department of Transportation (TxDOT) ensures that project specifications include adequate best management practices (BMPs) for this project.

For all projects with soil disturbing activity and for projects that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans and the projects environmental permits, issues, and commitments (EPICs). A copy of the CGP is included in Attachment 2.12 of the SWP3 binder.

**1.0 SITE/PROJECT DESCRIPTION**

**1.1 PROJECT CONTROL SECTION JOB (CSJ):**  
6462-75-001

**1.2 PROJECT LIMITS:**

From: SEE PROJECT LOCATION MAP

To: \_\_\_\_\_

**1.3 PROJECT COORDINATES:**

BEGIN: (Lat) SEE INDIVIDUAL, (Long) PROJECT SHEETS

END: (Lat) \_\_\_\_\_, (Long) \_\_\_\_\_

**1.4 TOTAL PROJECT AREA (Acres):** <1 AC

**1.5 TOTAL AREA TO BE DISTURBED (Acres):** <1 AC

**1.6 NATURE OF CONSTRUCTION ACTIVITY:**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**1.7 MAJOR SOIL TYPES:**

Soil Type	Description
SEE PROJECT LOCATION MAP	
Location 1: Singleton fine sandy loam	1 to 3 percent slopes
Location 2: Frelsburg clay	3 to 5 percent slopes
Location 3: Hallettsville fine sandy loam	1 to 3 percent slopes
Location 4: Straber loamy fine sand	1 to 5 percent slopes
Location 5: Dubina loamy fine sand	2 to 5 percent slopes
Location 6: Tremona gravelly loamy sand	1 to 5 percent slopes
Location 7: Papalote fine sandy loam	1 to 3 percent slopes
Location 8: Sarnosa fine sandy loam	1 to 3 percent slopes

**1.8 PROJECT SPECIFIC LOCATIONS (PSLs):**

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

**1.9 CONSTRUCTION ACTIVITIES:**

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.5.)

- Mobilization
- Install sediment and erosion controls
  - Blade existing topsoil into windrows, prep ROW, clear and grub
  - Remove existing pavement
- Grading operations, excavation, and embankment
  - Excavate and prepare subgrade for proposed pavement widening
  - Remove existing culverts, safety end treatments (SETs)
    - Remove existing metal beam guard fence (MBGF), bridge rail
    - Install proposed pavement per plans
  - Install culverts, culvert extensions, SETs
    - Install mow strip, MBGF, bridge rail
    - Place flex base
- Rework slopes, grade ditches
  - Blade windrowed material back across slopes
  - Revegetation of unpaved areas
  - Achieve site stabilization and remove sediment and erosion control measures
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.10 POTENTIAL POLLUTANTS AND SOURCES:**

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
  - Sanitary waste from onsite restroom facilities
  - Trash from various construction activities/receptacles
  - Long-term stockpiles of material and waste
  - Discharges from concrete washout activities, runoff from concrete cutting activities, and other concrete related activities.
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.11 RECEIVING WATERS:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
SEE PROJECT LOCATION MAP	
Location 1: No tributary near project location	No classified waterbody near project location
Location 2: Pecan Creek	Segment ID 1402 Colorado River
Location 3: Dutys Creek	Segment ID 1402 Colorado River
Location 4: No tributary near project location	Segment ID 1402G Cedar Creek Reservoir/ Lake Fayette

\* Add (\*) for impaired waterbodies with pollutant in ().

**1.12 ROLES AND RESPONSIBILITIES: TxDOT**

- Development of plans and specifications
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
  - Submit NOI/CSN to local MS4
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR**

- Day To Day Operational Control
- Submit Notice of Intent (NOI) to TCEQ (≥5 acres)
- Post Construction Site Notice
  - Submit NOI/CSN to local MS4
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Complete and submit Notice of Termination to TCEQ
- Maintain SWP3 records for 3 years
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**1.14 LOCAL MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) OPERATOR COORDINATION:**

MS4 Entity

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**

FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				72
STATE	STATE DIST.	COUNTY		
TEXAS	YKM	LAVACA, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
6462	75	001	VARIOUS	



**STORMWATER POLLUTION PREVENTION PLAN (SWP3):**

**2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE**

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

**2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:**

**T / P**

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.2 SEDIMENT CONTROL BMPs:**

**T / P**

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

Sediment control BMPs requiring design capacity calculations (See SWP3 Attachment 1.3.):

**T / P**

- Sediment Trap
  - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
  - 3,600 cubic feet of storage per acre drained
- Sedimentation Basin
  - Not required (<10 acres disturbed)
  - Required (>10 acres) and implemented.
    - Calculated volume runoff from 2-year, 24-hour storm for each acre of disturbed area
    - 3,600 cubic feet of storage per acre drained
  - Required (>10 acres), but not feasible due to:
    - Available area/Site geometry
    - Site slope/Drainage patterns
    - Site soils/Geotechnical factors
    - Public safety
    - Other: \_\_\_\_\_

**2.3 PERMANENT CONTROLS:**

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.4 OFFSITE VEHICLE TRACKING CONTROLS:**

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.5 POLLUTION PREVENTION MEASURES:**

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_
- Other: \_\_\_\_\_

**2.6 VEGETATED BUFFER ZONES:**

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

**2.7 ALLOWABLE NON-STORMWATER DISCHARGES:**

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

**2.8 DEWATERING:**

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

**2.9 INSPECTIONS:**

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

When dewatering activities are present, a daily inspection will be conducted once per day during those activities and documented in accordance with CGP and TxDOT requirements.

**2.10 MAINTENANCE:**

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.5 of this SWP3.

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**



FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				73
STATE	STATE DIST.	COUNTY		
TEXAS	YKM	LAVACA, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
6462	75	001	VARIOUS	



**1.7 MAJOR SOIL TYPES CONTINUED:**

Soil Type	Description
SEE PROJECT LOCATION MAP	
Location 9: Heiden clay	3 to 5 percent slopes
Location 10: Papalote fine sandy loam	1 to 3 percent slopes
Location 11: Orelia fine sandy loam	0 to 2 percent slopes
Location 12: Elmendorf-Denhawken cmlpx	1 to 3 percent slopes
Location 13: Bosque clay loam	0 to 1 percent slopes, frequently flooded
Location 14: Silstid loamy fine sand	1 to 5 percent slopes
Location 15: Hallettsville fine sandy loam	1 to 3 percent slopes
Location 16: Frelsburg clay	3 to 5 percent slopes
Location 17: Tremona loamy fine sand	1 to 5 percent slopes
Location 18: Straber loamy fine sand	1 to 5 percent slopes
Location 19 & 20: Bleiberville clay	1 to 3 percent slopes

**1.11 RECEIVING WATERS CONTINUED:**

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.


Tributaries	Classified Waterbody
SEE PROJECT LOCATION MAP	
Location 5: Boggy Branch	Segment ID 1402A Cummins Creek
Location 6: Hog Branch, Fivemile Creek, Twelvemile Creek	Segment ID 1807 Coleta Creek
Location 7: No tributary near project location	Segment ID 1901E Manahuilla Creek
Location 8: No tributary near project location	No classified waterbody near project location
Location 9: Queens Creek, McCoy Creek	Segment ID 1803 Guadalupe River
Location 10: Yorktown Creek	No classified waterbody near project location
Location 11: Cooper Ccreek	No classified waterbody near project location
Location 12: Elm Creek	Segment ID 1803G Sandy Fork
Location 13: No tributary near project location	Segment ID 1808 Lower San Marcos River
Location 14: Clemens Creek	Segment ID 1804 Guadalupe River
Location 15: Smothers Creek	Segment ID 1602B *Rocky Creek (Impaired for Bacteria)
Location 16: No tributary near project location	Segment ID 1602C *Lavaca River (Impaired for Dissolved Oxygen)
Location 17: No tributary near project location	No classified waterbody near project location
Location 18: Sandy Branch	Segment ID 1605 Navidad River
Location 19 & 20: Boggy Creek	Segment ID 1602B *Rocky Creek (Impaired for Bacteria)

**STORMWATER POLLUTION PREVENTION PLAN (SWP3)**


FED. RD. DIV. NO.	PROJECT NO.			SHEET NO.
				74
STATE	STATE DIST.	COUNTY		
TEXAS	YKM	LAVACA, ETC.		
CONT.	SECT.	JOB	HIGHWAY NO.	
6462	75	001	VARIOUS	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

9/24/2024  
SF FILE



**TEMPORARY SEDIMENT CONTROL FENCE**



**HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL**

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

**SEDIMENT CONTROL FENCE USAGE GUIDELINES**

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT<sup>2</sup>. Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


**LEGEND**

Sediment Control Fence




**GENERAL NOTES**

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.



				<b>Design Division Standard</b>	
<b>TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE &amp; VERTICAL TRACKING</b>					
<b>EC(1) - 16</b>					
FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS	6462	75	001	VARIOUS	
	DIST	COUNTY	SHEET NO.		
	YKM	LAVACA, ETC.	75		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





TREE REMOVAL

STEP 1:  
CUT 1/3 WAY THROUGH BOTTOM OF LIMB 8" TO 12" ABOVE MAIN STEM (OR TRUNK).


STEP 2:  
REMOVE LIMB 4" TO 6" BEYOND THE FIRST CUT

STEP 3:  
REMOVE STUB WITH A SMOOTH CUT SO THAT TRACE COLLAR OF THE REMOVED LIMB PROTRUDES APPROXIMATELY 1/2" FROM THE MAIN STEM




TREE TRIMMING

SUCKERS ARE SMALL BRANCHES THAT OCCUR BENEATH MAIN BRANCHES REMOVE SUCKERS TO HEIGHT OF THE LOWEST MAIN BRANCH



STEPS 1, 2 AND 3 APPLY WHEN REMOVING LIMBS 2" IN DIAMETER OR LARGER.



BRUSH REMOVAL

GENERAL NOTES:

TREE TRIMMING


1. TRIM AND REMOVE ALL TREE LIMBS ON THE PAVEMENT SIDE OF THE TRUNK 18' ABOVE THE PAVEMENT OR BRIDGE DECK ELEVATION, UNLESS OTHERWISE SHOWN ON THE PLANS.
2. TRIM AND REMOVE ALL TREE LIMBS BETWEEN THE TRUNK AND R.O.W. LINE 10' ABOVE NATURAL GROUND, TERRAIN OR OTHER STRUCTURE ELEVATION, UNLESS OTHERWISE SHOWN ON THE PLANS.

TREE REMOVAL

3. FOR TREES MARKED FOR REMOVAL, THE DIAMETER OF TREES ARE DETERMINED BY MEASUREMENT OF THE TRUNK CIRCUMFERENCE 3' ABOVE THE GROUND. TREES WITH TRUNKS OF LESS THAN 4" DIAMETER ARE CONSIDERED TO BE BRUSH. TREES WITH MULTIPLE TRUNKS AT THE POINT OF MEASUREMENT ARE MEASURED AND PAID FOR SEPARATELY.
4. MEASUREMENTS FOR PAYMENT OF TREE DIAMETERS ARE DIVIDED INTO THE RANGES SHOWN IN TABLE 1.

PAY ITEM	RANGE FOR PAY ITEMS			
	TRUNK DIAMETER *		TRUNK CIRCUMFERENCE	
	LOWER LIMIT IS GREATER THAN	UPPER LIMIT IS LESS THAN OR EQUAL TO	LOWER LIMIT IS GREATER THAN	UPPER LIMIT IS LESS THAN OR EQUAL TO
752 7005	4	12	12 1/2	37 1/2
752 7006	12	18	37 1/2	56 1/2
752 7007	18	24	56 1/2	75 1/2
752 7008	24	30	75 1/2	94
752 7009	30	36	94	113
752 7010	36	42	113	132
752 7011	42	48	132	151
752 7012	48	60	151	188 1/2
752 7013	60	72	188 1/2	226

\*SEE GENERAL NOTE #3.



BRUSH REMOVAL UNDER BRIDGE AND IN CHANNEL

9/11/2024 \$TIME\$ \$FILES\$


Maintenance Division Standard

## TREE AND BRUSH REMOVAL

### TRB-24 (1)


FILE:	DN: JEO	CK: LJB	DW: HD	CK: MJJ
© TxDOT SEPTEMBER 2024	CONT	SECT	JOB	HIGHWAY
REVISIONS 3/2015	6462	75	001	VARIOUS
	DIST	COUNTY	SHEET NO.	
	YKM	LAVACA, ETC.	76	

DISCLAIMER  
 The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



BRUSH REMOVED TO WITHIN 1" OF GROUND <4" DIAMETER TRUNK IS DEFINED AS BRUSH UNLESS OTHERWISE DIRECTED

EXAMPLE: UNDIVIDED HIGHWAY



BRUSH REMOVED TO WITHIN 1" OF GROUND <4" DIAMETER TRUNK IS DEFINED AS BRUSH UNLESS OTHERWISE DIRECTED

EXAMPLE: DIVIDED HIGHWAY WITH FRONTAGE ROADS

LEVELS DISPLAYED
1

GENERAL NOTES:

TREE TRIMMING AND BRUSH REMOVAL

1. PAYMENT BY THE CENTERLINE MILE IS MADE TO THE NEAREST 1/100 (0.01) MILE.
2. LIMITS OF WORK ARE SHOWN AS DISTANCES FROM REFERENCE MARKERS (RM).
3. PAY ITEMS BY THE CENTERLINE MILE INCLUDE ALL TREE TRIMMING OR BRUSH REMOVAL IN THE RIGHT OF WAY ON BOTH SIDES OF THE HIGHWAY. FOR DIVIDED HIGHWAYS, THE MEDIAN IS INCLUDED. FOR HIGHWAYS WITH FRONTAGE ROADS, THE AREAS BETWEEN THE FRONTAGE ROADS AND MAIN LANES, AND THE AREAS OUTSIDE OF THE FRONTAGE ROADS ARE INCLUDED.
4. BRUSH REMOVAL AND TREE TRIMMING UNDER BRIDGES, IN AND ALONG CHANNELS AND EASEMENTS ARE PAID FOR BY THE ACRE FOR AREAS DESIGNATED ON THE PLANS.



TREE AND BRUSH REMOVAL  
 TRB-15 (2)

NOT TO SCALE		SHEET 2 OF 2	
FILE: TRB-15(2).DGN	DRAWN: JEO	CHECKED: DM/LJB	DW: -
REVISED: 5/13/2004	LJB	YKM	77
REVISED: 9/24/2004	LJB	COUNTY	CONTROL SECTION JOB HIGHWAY
REVISED: APRIL 2015	JEO	LAVACA, ETC.	6462 75 001 VARIOUS



**DISCLAIMER:**  
 The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

**I. WORK AT CROSSING LOCATIONS (AT GRADE, HIGHWAY OVERPASS, HIGHWAY UNDERPASS, PEDESTRIAN, OR CLOSED/ABANDONED)**

This project is adjacent or parallel work, not within RR ROW:  
 DOT No.: near 744659X  
 Crossing Type: At Grade  
 RR Company Operating Track at Crossing: Union Pacific Railroad Company  
 RR Company Owning Track at Crossing: Union Pacific Railroad Company  
 RR MP: 0109.280  
 RR Subdivision: Cuero  
 City: Muldoon  
 County: Fayette  
 CSJ at this Crossing: 6462-75-001  
 Latitude: 29.7905252  
 Longitude: -97.0947364

Scope of Work, including any TCP, to be performed by State Contractor:

REMOVE AND REPLACE CULVERT AT THE INTERSECTION OF FM 154 AND CHARCOAL COMPANY LANE/CR 471. DURING THE ONE LANE TWO-WAY TRAFFIC CONTROL OPERATIONS A RAILROAD FLAGGER AND CONSTRUCTION FLAGGER MUST BE PRESENT FOR THE DURATION OF THE WORK THROUGH BNSF RIGHT OF WAY.

Scope of Work to be performed by Railroad Company:

NONE

**II. FLAGGING & INSPECTION**

No. of Days of Railroad Flagging Expected: 3

On this project, night or weekend flagging is:

Expected  
 Not Expected

Flagging services will be provided by:

Railroad Company: 1) Txdot will pay flagging invoices. Flagging Agreement with railroad will be needed or, 2) Permitted crossing. Railroad company to provide flagging.  
 Outside Party: Contractor will pay flagging invoices to be reimbursed by TxDOT

Contractor must incorporate flaggers into anticipated construction schedule. The Railroad requires a 30-day notice if their flaggers are to be utilized. If Contractor falls behind schedule due to their own negligence and is not ready for scheduled flaggers, any flagging charges will be paid by Contractor.

Contact Information for Flagging:

**UPRR** UP.info@railpros.com  
 Call Center 877-315-0513, Select #1 for flagging  
 UP.request@nrssinc.net  
 Call Center 877-984-6777

**BNSF** BNSFinfo@railprosfs.com  
 Call Center 877-315-0513, Select #1 for flagging

**CPKCR** KCS.info@railpros.com  
 Call Center 877-315-0513, Select #1 for flagging  
 Bottom Line On-Track Safety Services  
 bottomline076@aol.com, 903-767-7630

OTHERS:

Contractor must incorporate railroad construction inspection into anticipated construction schedule.

Not Required  
 Required. Contact Information for Construction Inspection:

**III. CONSTRUCTION WORK TO BE PERFORMED BY THE RAILROAD**

Required.  
 Not Required  
 Railroad Point of Contact:

Coordinate with TxDOT for any work to be performed by the Railroad Company. TxDOT must issue a work order for any work done by the Railroad Company prior to the work being performed.

**IV. RAILROAD INSURANCE REQUIREMENTS**

The Contractor shall confirm the insurance requirements with the Railroad as the insurance limits are subject to change without notice.

Insurance policies and corresponding certificates of insurance must be issued by the contractor on behalf of the Railroad. Separate insurance policies and certificates are required when more than one Railroad Company is operating on the same right of way, or when several Railroad Companies are involved and operate on their own separate right of ways.

No direct compensation will be made to the Contractor for providing the insurance coverages shown below or any deductibles. These costs are incidental to the various bid items.

Escalated Limits	
Type of Insurance	Amount of Coverage (Minimum)
Workers Compensation	\$500,000 / \$500,000 / \$500,000
Commercial General Liability	\$2,000,000 / \$4,000,000
Business Automobile	\$2,000,000

Railroad Protective Liability Limits	
<input type="checkbox"/> Not Required	
<input checked="" type="checkbox"/> Non - Bridge/Typical Maintenance Projects. Includes repairs to overpass/underpass and culvert structures	\$2,000,000 / \$6,000,000
<input type="checkbox"/> Bridge Structure Projects. Includes new construction or replacement of overpass/underpass structures	\$5,000,000 / \$10,000,000
<input type="checkbox"/> Other:	

**V. CONTRACTOR'S RIGHT OF ENTRY (CROE)**

Not Required  
 Required: UPRR Maintenance Consent Letter. TxDOT to assist  
 Required: TxDOT to assist in obtaining the UPRR CROE  
 Required: Contractor to obtain
 

- BNSF: <https://bnsf.railpermitting.com>
- CPKCR [https://jllrpg.360works.com/fmi/webd/rpo\\_web\\_kcs.fmp12](https://jllrpg.360works.com/fmi/webd/rpo_web_kcs.fmp12)
- Other Railroads: \_\_\_\_\_

To view previously approved CROE templates agreed upon between the State and Railroad, see: <https://www.txdot.gov/business/resources/railroad-highway-crossing/sample-right-of-entry-agreements.html>

Approved CROE templates are not to be modified by the Contractor.

Contractor shall not operate within Railroad Right of Way without an executed Construction & Maintenance Agreement between the State and the Railroad and an executed CROE between the Contractor and the Railroad if required on project.

**VI. RAILROAD COORDINATION MEETING**

A Railroad Coordination Meeting is required. See item 5, Article 8.1, of the Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges Manual for more details.

**VII. RAILROAD SAFETY ORIENTATION**

A. Complete the Railroad's course "Orientation for Contractor's Safety," and maintain registration prior to working on the Railroad's property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.

UPRR, BNSF, CPKCR will not accept on-track safety training certificates from other Railroads. Refer to each Railroad's specific contractor right of entry for training information.

Know and follow the Contractor's Right of Entry Agreement EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

**VIII. SUBCONTRACTORS**

Contractor shall not subcontract work without written consent of TxDOT. Subcontractors are subject to the same insurance requirements as the Prime Contractor.

**IX. EMERGENCY NOTIFICATION**

**In Case of Railroad Emergency**  
 Call: Union Pacific Railroad Company  
 Railroad Emergency Line at: 888-877-7267  
 Location: DOT near 744659X  
 RR Milepost: 0109.280  
 Subdivision: Cuero

**RRD Review Only**  
 Initials: *[Signature]*  
 Date: 07/30/2024

		<b>Rail Division</b>
<b>RAILROAD SCOPE OF WORK</b> PROJECT SPECIFIC DETAILS		
FILE: rr-scope-of-work.pdf	DN: TxDOT	CK: _____
© TxDOT June 2014	CONT: 6462	SECT: 75
	JOB: 001	HIGHWAY: CR 471@FM 154
6/2023	DIST: YKM	COUNTY: FAYETTE
		SHEET NO. _____

**PART 1 - GENERAL**

**1.01 DESCRIPTION**

This project includes construction work within the right of way and/or properties of the Railroad and adjacent to its tracks, wire lines and other facilities. These sheets describe the minimum special requirements for coordination with the Railroad when working upon, over or under Railroad Right of Way or when impacting current or future Railroad operations. Coordinate with the Railroad while performing the work outlined herein, and afford the same cooperation with the Railroad as with TxDOT. Complete all submittals and work in accordance with TxDOT Standard Specifications, Railroad Guidelines and AREMA recommendations as modified by these minimum special requirements or as directed in writing by the Railroad Designated Representative.

For purposes of this project, the Railroad Designated Representative is the person or persons designated by the Railroad Manager of Industry and Public Projects to handle specific tasks related to the project.

**1.02 REQUEST FOR INFORMATION / CLARIFICATION**

Submit Requests for Information ("RFI") involving work within any Railroad Right of Way to the TxDOT Engineer. The TxDOT Engineer will submit the RFI to the Railroad Designated Representative for review and approval for RFI's corresponding to work within Railroad Right of Way. Allow six (6) weeks total time for review and approval, which includes four (4) weeks for review and approval by the Railroad.

**1.03 PLANS / SPECIFICATIONS**

TxDOT has received written Railroad approval of the plans and specifications for this project. Any revisions or changes in the plans after award of the Contract must have the approval of TxDOT and the Railroad.

**PART 2 - UTILITIES AND FIBER OPTIC**

Construct all utility installations in accordance with current AREMA recommendations, Railroad, TxDOT and owning utility specifications and requirements. Railroad general guidelines can be found on the Railroad website or by contacting the Railroad Designated Representative.

**PART 3 - CONSTRUCTION**

**3.01 GENERAL**

- A. Perform all work in compliance with all applicable Railroad, Federal Railroad Administration (FRA), and TxDOT rules and regulations. Arrange and conduct work in a manner that does not endanger or interfere with the safe operation of the tracks and property of the Railroad and the traffic moving on such tracks, or the wires, signals and other property of the Railroad, its tenants or licensees, at or in the vicinity of the Work. The safe operation of railroad train movements takes precedence over any work to be performed by the Contractor. The Contractor is responsible for train delay cost and lost revenue claims due to any delays or interruption of train operations resulting from Contractor's construction or other activities.
- B. Construction activities within 15 feet of the operational tracks will only be allowed if absolutely necessary and the Railroad's Designated Representative grants approval. Construction activities within 15 feet of the operational track(s) preferably allow the tracks to stay operational. In such cases, coordination and approval by the Railroad Track Manager is required with regard to schedule, flagging, and slow orders. See Sections 3.07 and 3.08 for additional information.
- C. Provide track protection for all work equipment (including rubber tired equipment) operating within 25 feet from nearest rail. When not in use, keep Contractor machinery and materials at least 50 feet from the Railroad's nearest track.
- D. Vehicular crossings of railroad track are allowed only at existing crossings, or haul road crossings developed with Railroad approval.
- E. The Contractor is also advised that new railroad facilities within the project may be built by the Railroad. If applicable, these facilities are delineated in the plans. Be aware of the limits of responsibilities and coordinate efforts with the Railroad and TxDOT.
- F. Railroad requirements do not allow work within 50 feet of track centers when a train passes the work site and all personnel must clear the area within 50 feet of the track centerline and secure all equipment. Additional allowances may be pursued as outlined in 3.02 and 3.03.
- G. All permanent clearances shall be verified before project closing.

**3.02 RAILROAD OPERATIONS**

- A. Trains and/or equipment are expected on any track, at any time, in either direction. Become familiar with the train schedules in this location and structure bid assuming intermittent track windows in this period, as defined in Paragraph B that follows.
- B. All railroad tracks within and adjacent to the contract site are active, and rail traffic over these facilities shall be maintained throughout the Project. Activities may include both through moves and switching moves to local customers. railroad traffic and operations will occur continuously throughout the day and night on these tracks and shall be maintained at all times as defined herein. Coordinate and schedule the work so that construction activities do not interfere with railroad operations.
- C. Coordinate work windows with TxDOT and the Railroad's Designated Representative. Types of work windows include Conditional Work Windows and Absolute Work Windows, as defined below:
  - 1. Conditional Work Window: A Conditional Work Window is a period of time that railroad operations have priority over construction activities. When construction activities may occur on and/or adjacent to the railroad tracks within 25 feet of the nearest track, a railroad flag person will be required. At the direction of the railroad flag person, upon approach of a train, and when trains are present on the tracks, the tracks must be cleared (i.e., no construction equipment, materials or personnel within 25 feet, or as directed by the Railroad Designated Representative, from the tracks). Conditional Work Windows are available for the Project.
  - 2. Absolute Work Window: An Absolute Work Window is a period of time that construction activities are given priority over railroad operations. During this time frame, the designated railroad track(s) will be inactive for train movements and may be fouled by the Contractor. At the end of an Absolute Work Window, the railroad tracks and/or signals must be completely operational for train operations and all Railroad, Public Utilities Commission (PUC) and FRA requirements, codes and regulations for operational tracks must be satisfied. In the situation where the operating tracks and/or signals have been affected, the Railroad will perform inspections of the work prior to placing that track back into service. Railroad flag persons will be required for construction activities requiring an Absolute Work Window. Absolute Work Windows will not generally be granted. Any request will require a detailed explanation for Railroad review.

**3.03 RIGHT OF ENTRY, ADVANCE NOTICE AND WORK STOPPAGES**

- A. Do not perform any work within Railroad Right of Way without a valid executed Right of Entry Agreement if required on this project.
- B. Give advance notice to the Railroad as required in the "Contractor's Right of Entry Agreement" before commencing work in connection with construction upon or over Railroad Right of Way and observe the Railroad's rules and regulations with respect thereto.
- C. Perform all work upon Railroad Right of Way in a manner to avoid interference with or endanger the operations of the Railroad. Whenever work may affect the operations or safety of trains, submit the work method to the Railroad Designated Representative for approval. Approval does not relieve the Contractor from liability. Do not commence any work which requires flagging service or inspection service until the flagging protection required by the Railroad is available at the job site. See Section 3.15 for railroad flagging requirements.
- D. Make requests in writing for both Absolute and Conditional Work Windows, at least 30 days in advance of any work. Include in the written request:
  - 1. Exactly what the work entails.
  - 2. The days and hours that work will be performed.
  - 3. The exact location of work, and proximity to the tracks.
  - 4. The type of window requested and the amount of time requested.
  - 5. The designated contact person.

Provide a written confirmation notice to the Railroad at least 48 hours before commencing work in connection with approved work windows when work is within 25 feet of nearest rail. Perform all work in accordance with previously approved work plans.
- E. Make provisions to protect operations and property of the Railroad should a condition arising from, or in connection with the work, require immediate and unusual action. If in the judgment of the Railroad Designated Representative such provisions are insufficient, the Railroad Designated Representative may require or provide such provisions as deemed necessary. In any event, such provisions shall be at the Contractor's expense and without cost to the Railroad or TxDOT. The Railroad or TxDOT shall have the right to order the Contractor to temporarily cease operations in the event of an emergency or, if in the opinion of the Railroad Designated Representative, the Contractor's operations could endanger railroad operations. In the event of such an order, immediately notify TxDOT of the order.

**3.04 INSURANCE**

Do not begin work upon or over Railroad Right of Way until furnishing the Railroad with the insurance policies, binders, certificates and endorsements required by the "Contractor's Right of Entry Agreement", and until the Railroad Designated Representative has advised TxDOT that such insurance is in accordance with the Agreement.

**3.05 RAILROAD SAFETY ORIENTATION**

- A. Complete the railroad course "Orientation for Contractor's Safety", and maintain current registration prior to working on railroad property. This course is required to be completed annually by Contractor and Subcontractor personnel working on site.
 

"UPRR, BNSF, KCS/TEXMEX will not accept on-track safety training certificates from other railroads. Refer to Railroad specific contractor right of entry for training information."
- B. Know and follow the "Contractor's Right of Entry Agreement" EXHIBIT D, MINIMUM SAFETY REQUIREMENTS regarding clothing, personal protective equipment, and general safety requirements.

**3.06 COOPERATION**

The Railroad will cooperate with Contractor so that work may be conducted in an efficient manner, and will cooperate with Contractor in enabling use of Railroad Right of Way in performing the work.

**3.07 MINIMUM CONSTRUCTION CLEARANCES FOR FALSEWORK AND OTHER TEMPORARY STRUCTURES**

Abide by the following minimum temporary clearances during the course of construction:


- A. 15' - 0" (BNSF) (UPRR) and 14' - 0" (KCS) horizontal from centerline of track
- B. 22' (KCS) and 21' - 6" (UPRR & BNSF) vertically above top of rail.

For construction clearance less than listed above, obtain local Railroad Operating Unit review and approval.

**3.08 APPROVAL OF REDUCED CLEARANCES**

- A. Maintain minimum track clearances during construction as specified in Section 3.07.
- B. Submit any proposed infringement on the specified minimum clearances to the Railroad Designated Representative through TxDOT at least 30 days in advance of the work. Do not proceed with such infringement without written approval by the Railroad Designated Representative.
- C. Do not commence work involving an approved infringement without receiving written assurance from the Railroad Designated Representative that arrangements have been made for any necessary flagging service.

DATE: 10/9/2024 \$TIME\$  
FILE: \$FILES\$

 <b>Texas Department of Transportation</b>				<b>Rail Division</b>	
RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
© TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS March 2020	6462	75	001	VARIOUS	
DIST	COUNTY			SHEET NO.	
YKM	LAVACA, ETC.			79	

**3.09 MAINTENANCE OF RAILROAD FACILITIES**

- A. Maintain all ditches and drainage structures free of silt or other obstructions resulting from Contractor's operations. Repair eroded areas and any other damage within Railroad Right of Way and repair any other damage to the property of the Railroad, or its tenants.
- B. Perform all such maintenance and repair of damages due to the Contractor's operations at Contractor's expense.
- C. Submit a proposed method of erosion control for review by the Railroad prior to beginning any grading on the project site. Comply with all applicable local, state and federal regulations when developing and implementing such erosion control.

**3.10 SITE INSPECTIONS BY RAILROAD'S DESIGNATED REPRESENTATIVE**

- A. In addition to the office reviews of construction submittals, site inspections may be performed by the Railroad Designated Representative at significant points during construction, including the following if applicable:
  1. Pre-construction meetings.
  2. Pile driving/drilling of caissons or drilled shafts.
  3. Reinforcement and concrete placement for railroad bridge substructure and/or superstructure.
  4. Erection of precast concrete or steel bridge superstructure.
  5. Placement of waterproofing (prior to placing ballast on bridge deck).
  6. Completion of the bridge structure.
- B. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.
- C. Provide a detailed construction schedule, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to TxDOT for submittal to the Railroad Designated Representative for review prior to commencement of work. Include the anticipated dates when the above listed events will occur. Update this schedule for the above listed events as necessary and each month at a minimum to allow the Railroad to schedule site inspections.

**3.11 RAILROAD REPRESENTATIVES**

Railroad representatives, conductors, flag person or watch person will be provided by the Railroad at expense of TxDOT to protect Railroad facilities, property and movements of its trains or engines. In general, the Railroad will furnish such personnel or other protective services as follows:

- A. When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from nearest rail of any track on which trains may operate, or when any object is off the ground and any dimension thereof could extend inside the 25 foot limit, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
- B. For any excavation below elevation of track subgrade if, in the opinion of the Railroad Designated Representative, track or other railroad facilities may be subject to settlement or movement.
- C. During any clearing, grubbing, excavation or grading in proximity to railroad facilities, which, in the opinion of the Railroad Designated Representative, may endanger railroad facilities or operations.
- D. During any Contractor's operations when, in the opinion of the Railroad Designated Representative, railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines, or pipe lines, may be endangered.
- E. Arrange with the Railroad Designated Representative to provide the adequate number of flag persons to accomplish the work.

**3.12 COMMUNICATIONS AND SIGNAL LINES**

If required, the Railroad will rearrange its communications and signal lines, its grade crossing warning devices, train signals and tracks, and facilities that are in use and maintained by the Railroad's forces in connection with its operation at expense of TxDOT. This work by the Railroad will be done by its own forces and it is not a part of the Work under this Contract.

**3.13 TRAFFIC CONTROL**

Coordinate any operations that control traffic across or around railroad facilities with the Railroad Designated Representative.

**3.14 CONSTRUCTION EXCAVATIONS AND BORING ACTIVITIES UNDER TRACK**

- A. Take special precaution and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of TxDOT, OSHA, AREMA and Railroad "Guidelines for Temporary Shoring".
- B. The project plans indicate whether there are fiber optic lines or other such telecommunications systems that require consideration. Regardless, contact the necessary call center to determine if such cable systems are present:

UPRR 1-800-336-9193  
7:00 AM to 9:00 PM CST Monday-Friday except holidays,  
staffed 24 hrs/day for emergencies  
48 hrs notice required

BNSF 1-800-533-2891  
24 hour number  
5 working days notice required

KCS 1-800-344-8377  
Texas One Call, a 24 hour number  
48 hrs notice required, excluding weekends and holidays

If a telecommunications system is buried anywhere on or near railroad property, coordinate with TxDOT, the Railroad and the Telecommunication Company(ies) to arrange for relocation or protective measures prior to beginning work on or near railroad property. Refer to the project General Notes for additional information.


- C. Projects involving a boring or jack and bore operation under track such as drainage pipes or culverts and utilities require an installation plan reviewed and approved by the Railroad and TxDOT prior to proceeding with such construction. A railroad inspector and contractor assisted monitoring of ground and track movement is required to maintain safe passage of rail traffic. Stop installation and do not allow passage of trains if movements in excess of 1/4 inch vertical or horizontal is detected in the tracks. Immediately repair the damage to the satisfaction of TxDOT and the Railroad before proceeding.

**3.15 RAILROAD FLAGGING**

Per the Right of Entry Agreement for flagging, notify the Railroad Representative at least 10 working days in advance of Contractor's work and at least 30 working days in advance of any Contractor's work in which any person or equipment will be within 25 feet of nearest rail or as specified in the Contractor Right of Entry (CROE).

**3.16 CLEANING OF RIGHT-OF-WAY**

When work is complete, remove all tools, implements, and other materials brought into Railroad Right of Way and leave the right of Way in a clean and presentable condition to the satisfaction of TxDOT and the Railroad.

 Texas Department of Transportation				Rail Division	
<b>RAILROAD REQUIREMENTS FOR NON-BRIDGE CONSTRUCTION PROJECTS</b>					
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT	
©TxDOT October 2018	CONT	SECT	JOB	HIGHWAY	
REVISIONS	6462	75	001	VARIOUS	
March 2020	DIST	COUNTY	SHEET NO.		
	YKM	LAVACA, ETC.	80		