

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6473-00-001
CSJ: 6473-00-001
HIGHWAY: IH020, ETC.
LIMITS OF WORK: PALO PINTO

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
DESCRIPTION: FLEXIBLE BASE (MATERIAL ONLY)

RECOMMENDED
FOR LETTING: 9/20/2024
Date

RECOMMENDED
FOR LETTING: 9/20/2024
Date

DocuSigned by:
Kory D. Colun, P.E.

DocuSigned by:
Elijah Belenon P. E.


APPROVED
FOR LETTING: 9/20/2024
Date

DocuSigned by:
Janet Crawford

INDEX OF SHEETS

- 1 TITLE SHEET
- 2A-C GENERAL NOTES
- 3 ESTIMATE & QUANTITY SHEET
- 4 DELIVERY SITES SHEET

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, SEPTEMBER 1, 2024 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2024			
FED.RD. DIV. NO	PROJECT NO.	SHEET NO.	
6	6473-00-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	PALO PINTO	
CONTROL	SECTION	JOB	HWY NO.
6473	00	001	IH020, ETC.
FILENAME			DATE
MMC 6473-00-001			3/25/2024

Project Number: MMC-6473-00+-001

Control: 6473-00-001

County: PALO PINTO COUNTY

Highway: IH0020, Etc.

GENERAL NOTES:

General:

This purpose of this contract is to supply **Flexible Base Material** at the following locations:

Site 1	Various Locations within Palo Pinto County
--------	--

This contract includes an item for pickup. Materials shall be available for pickup within 75 miles of the TxDOT office located at 2400 US 180 W, Mineral Wells, TX 76067. Load material into TxDOT equipment at time of pickup.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through the Maintenance Section Supervisor or Representative:

MINERAL WELLS
2400 US 180 W Mineral Well, TX 76067 940-325-2414

Bids will be received at if locate let, use 2501 SW Loop 820, Fort Worth, TX 76133.

Special Notes:

Contractor questions on this project are to be emailed to the following individuals:

Area Engineer: Korey Coburn
Project Manager: Ester Kuhn

Korey.Coburn@TxDOT.gov
Ester.Kuhn@TxDOT.gov

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Project Number: MMC-6473-00+-001

Control: 6473-00-001

County: PALO PINTO COUNTY

Highway: IH0020, Etc.

Section 10.2 - Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Section 10.4 – Scope of Work:

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended twice, not to exceed 540 calendar days for the entire contract term if mutually agreed.

Section 10.8 - Prosecution and Progress:

There are 365 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Types of accepted haul vehicles include End Dumps.

Work Orders. There will be a minimum of seven working days allowed to deliver material as of the date of the work order except for Expedited Work Orders (EWO) as further defined in Article 10.8.5. Issuance of Expedited Work Order. The actual number of days allowed for delivery of materials will be shown in the Contract and work order; however, anything less than seven working days in the Contract or work order (except for an EWO) is not allowed.

Work Order will specify a delivery site by the bid item in the contract and quantity to be supplied.

Unless otherwise directed, prosecute the work continuously to completion of the Work Order.

Project Number: MMC-6473-00+-001

Control: 6473-00-001

County: PALO PINTO COUNTY

Highway: IH0020, Etc.

Item 8010 – Flexible Base (Materials Only):

Grading Requirements

Test to be accordance with TxDOT Standard Test Methods

Item Desc.	Linear Shrinkage	LL	Wet Ball	WBMV (incr. passing #40 sieve)
Item 247 Flex Base	6.0 max	40 max.	40 max.	20% max.


PERCENT RETAINED ON SIEVE:

1-3/4"	No. 4	No. 40
0-10	45-75	50-85

Flexible Base will not contain more than 1% by weight of clay balls.


ESTIMATE SUMMARY

ITEM-CODE			DESCRIPTION	UNIT	TOTAL	
ITEM NO.	DESC. CODE	SP NO.			EST.	FINAL
8010	7002		FL BS (SITE DEL) (TY A GR 3) (SITE 1)	TON	2,500	

 Texas Department of Transportation				
ESTIMATE AND QUANTITIES				
DESIGN	FED RD. DIV. NO.	MAINTENANCE PROJECT NO.		HIGHWAY NO.
	6	6473-00-001		IH020, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
	TEXAS	FTW	PALO PINTO	
CHECK	CONTROL	SECTION	JOB	3
	6473	00	001	

SITE NO.	MAINTENANCE OFFICE	DELIVERY SITE	ITEM NO.	DES. NO.	UNIT	QUANTITY
1	MINERAL WELLS	2400 US 180 W., MINERAL WELLS, TX 76067	8010	7002	TON	2,500

* APPROXIMATE LOCATIONS FOR DELIVERY

				
DELIVERY SITE SHEET				
DESIGN	FED RD. DIV. NO.	MAINTENANCE PROJECT NO.		HIGHWAY NO.
	6	6473-00-001		IH020, ETC.
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	FTW	TARRANT	
CHECK	CONTROL	SECTION	JOB	4
	6473	00	001	