Docusign Envelope ID: 749EDCC4-CB54-471D-9DF3-243944460C1B

THE ENGINEER.

SEE SHEET 2 FOR INDEX OF SHEETS

CONSTRUCTION SIGN AND BARRICADE PLACEMENT SHALL BE IN ACCORDANCE WITH PART VI OF THE

TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, AS SHOWN ON THE BC STANDARDS, AS SPECIFIED HEREIN OR AS DIRECTED BY


STATE OF TEXAS DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED HIGHWAY ROUTINE MAINTENANCE CONTRACT IH 30

TITUS COUNTY

PROJECT NO.: A00211799 TITUS COUNTY

FOR THE CONSTRUCTION OF SAFETY IMPROVEMENTS CONSISTING OF TREE REMOVAL ON RIGHT OF WAYNET LENGTH OF PROJECT = 1,667 FT = 0.32 MI.LIMITS: FROM FM 1402 TO 0.32 MI. EAST OF FM 1402



SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, SEPTEMBER 1, 2024 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT:

NO EQUATIONS NO EXCEPTIONS NO RAILROAD CROSSINGS

© 2024 By Texas Department of Transportations All Rights Reserved



MAINTEN	NO.		
RMC	1		
DIST.		COUNTY	
ATL		TITUS	
SECT.	JOB	H I GHŴ	AY NO.
05	001	IH	30
ADT	(2022)	= 26,35	
	RMC DIST. ATL SECT. 05 DESI ADT	RMC 6472-05-001 D151. ATL ATL	ATL TITUS SECT. JOB HIGH

FINAL PLANS

LETTING DATE:	_
DATE CONTRACTOR BEGAN WORK:	_
DATE WORK WAS COMPLETED & ACCEPTED:	_
FINAL CONTRACT COST: \$	_
CONTRACTOR :	_

The construction work was performed in substantial compliance with the contract.

P.E.

DATE

Texas Department of Transportation RECOMMENDED 10/21/2024 20____ FOR LETTING: DocuSigned by: Jason Dupre, P.E - 251945 S9708159FC MAINTENANCE APPROVED 10/18/2024 ____ FOR LETTING: DocuSigned by DISTRICT ENGINEER

DATE: \$DATE\$ FILE: \$FILE\$

INDEX OF SHEETS

<u>GENERAL</u>

- 1 TITLE SHEET
- 2 INDEX OF SHEETS
- **3** TYPICAL SECTIONS
- 4, 4A-4C GENERAL NOTES
- 5 ESTIMATE & QUANTITY

TRAFFIC CONTROL PLAN STANDARDS

- **# 6-17** BC (1)-21 THRU BC (12)-21
- **# 18** TCP (5-1)-18
- **# 19** TCP (6-1)-12
- **# 20** TCP (6-3)-12
- **# 21** TCP (6-4)-12
- **# 22** TCP (6-5)-12

ROADWAY DETAILS

23 TREE REMOVAL AND TRIMMING DETAIL

ENVIRONMENTAL ISSUES

24 ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)



THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ON THIS SHEET WITH A # HAVE BEEN ISSUEDBY ME AND ARE APPLICABLE TO THIS PROJECT.


NAME

DATE



Texas Department of Transportation

FH#A TEXAS		FEDERAL A	ID PROJECT	NO.	SHEET NO.			
DIVISION					2			
STATE		DISTRICT		COUNTY				
TEXA	S	ATL		TITUS				
CONTRO	L	SECTION	JOB	HIGHWAY NO.				
6472	2	05	001	ΙH	30			
6472	2	05	001	ΙH	30			



RM= 163+0.40 TO 163+0.09

ROW - 200'



TYPICAL SECTIONS

NOT TO SCALE

© 2024	א ¢	Texas De		of Transpo						
<u> </u>			2	HEET 1	OF I SHEET					
FHRA TEXAS		FEDERAL AID PROJECT NO.								
DIVISION										
STATE		DISTRICT		COUNTY						
TEXA	S	ATL		TITUS						
CONTRO	L	SECTION	JOB HIGHNAY NO.							
6472	2	05	001	ΙH	30					

County: Titus

Highway: IH0030

GENERAL NOTES:

General:

Contractor questions on this project are to be addressed to the following individual(s):

- Jason R. Dupree, P.E. Director of Maintenance Jason.Dupree@txdot.gov
- Charlotte Aslin Maintenance Program Specialist <u>Charlotte.Aslin@txdot.gov</u>

Questions may be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:

https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

Questions regarding the plans and/or the project after the contract has been awarded should be referred to the Managing Supervisor:

Wendy Starkes, P.E. Mt. Pleasant Area Engineer 2210 West Ferguson Road Mt. Pleasant, Texas 75455 (903) 572-8511

This project consists of performing prep right of way tree removal in Titus County.

Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A Contractor awarded multiple contracts must be capable and sufficiently staffed to concurrently process any or all contracts.

Prior to beginning operations, the Department will arrange a preconstruction conference between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the contract, proposed procedures and the plans for performing the work while providing for safe passage of traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed.

Sheet

Control: 6472-05-001

Project Number: A00211799

County: Titus

Highway: IH0030

Use care to avoid disturbing the existing roadway surface. Repair any damages caused by Contractor operations. If damage is not corrected, costs associated with the Department making the repairs (including labor and materials) will be deducted from any payment due the Contractor.

Dispose of all waste material in accordance with all state and federal laws. For waste material disposed of on private property, ensure the material is not visible from a highway. Acquire and furnish to the Department, copies of written agreements between the Contractor and property owner prior to disposal.

Limit the use of the roadway for the hauling of material to legal loads.

Keep the traveled surfaces used in hauling operations free of dirt or other materials.

Clean dirt, grass and any debris off the roadway and shoulder prior to each construction activity. Haul any residue off the project and dispose of as noted. The cost associated with this work will be subsidiary to various bid items.

Do not park personal vehicles of employees within the right of way at any time, including any section closed to public traffic, unless the vehicle is being used for the construction procedures. If approved by the Department, employees may park on the right of way at sites where the contractor has his office or equipment and materials storage yard.

Clean up and remove all loose material resulting from contract operations each day before work is suspended for that day.

Repair all pavement damaged by the Contractor's forces during construction. Such repair is to be considered incidental to the various bid items in the project and must be approved by Engineer.

Repair all fences damaged by the Contractor's forces during construction. Such repair is to be considered incidental to the various bid items in the project and must be approved by Engineer.

Department-approved safety hats and safety vests will be worn by all workers and visitors when:

Workers are outside of vehicles at all outdoor worksites. This includes those who occasionally visit worksites either on the highway surface or right of way.

Working in areas where there is a danger of head injury from impact, from falling or flying objects, or from electrical shock or burns.

Non-compliance with this requirement will be grounds for suspension of work.

The Contractor is responsible for notifying the utility companies when plans call for work to be accomplished in the general vicinity of any underground utilities located on State right of way.

Sheet 4

Control: 6472-05-001

County: Titus

Sheet

Control: 6472-05-001

Highway: IH0030

Forward copies of all correspondence between any resource agencies as listed in Item 7 or Special Provisions thereto.

The SWP3 for this project will be as directed.

Item 2: Instructions to Bidders

This project includes plan sheets that are not part of the bid proposal. Views plans on-line or download from the web at: <u>https://www.txdot.gov/business/letting-bids/plans-online.html</u>.

Order plans from any of the plan reproduction companies shown on the web at: <u>http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm</u>.

Item 4: Scope of Work

Prep right of way will consist of removing trees and stumps on IH 30 right of way in Titus County.

Remove trees and stumps as directed by the Engineer. See Summary Sheet in the plans for roadways and limits for prep right of way.

Verbally notify the Engineer or his representative by 8:15 a.m. on any day that work is planned but the Contractor will not be working, for whatever reason.

Item 5: Control of the Work

Attention is directed to the presence of underground utilities owned by the Department (irrigation, signal and illumination) on the right of way on this project. Call for locations at the TxDOT Signal Shop (903-799-1360).

Contact all utility companies for the exact location of underground utilities before boring, trenching or any other work that might interfere with or damage existing utilities.

Repair any damage caused to utilities by Contractor operations at own expense and restore service in a timely manner.

Item 7: Legal Relations and Responsibilities

This project is considered a maintenance activity and is exempt from the Construction General Permit (CGP) coverage.

No significant traffic generator events.

Item 8: Prosecution and Progress

Working days will be charged in accordance with Section 8.3.1.6., "Other," and defined below:

Working days will be charged Monday through Thursday, excluding National or State Holidays, if weather or other conditions permit the performance of the principal unit of work underway, as

Project Number: A00211799

County: Titus

Highway: IH0030

determined by the Engineer, for a continuous period of at least 7 hours between 7 A.M. and 6 P.M. The Contractor has the option to work off the pavement on Fridays and Saturdays, but lane and shoulder closures will not be permitted without written permission of the Engineer. Work on Sundays and National Holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Friday, Saturday, Sunday, or holiday, and weather or other conditions permit the performance of work for 7 hours between 7:00 A.M. and 6:00 P.M., a working day will be charged.

Provide progress schedules meeting the requirements of Section 8.5.5.1.

Supply an adequate size crew experienced in the type of work described within these specifications and capable of performing the work in a safe and timely manner. Furnish all equipment, tools, and machinery for the proper prosecution of the work. Equipment, tools, and machinery will be on the work site in good operating condition and have all manufacturers' safety features in proper working condition prior to beginning work and remain in place during the prosecution of the work. All equipment, tools, and machinery will be capable of maintaining a continuous work schedule for the satisfactory completion of the project.

Unless otherwise approved, work will not begin before daylight and all operations will stop in sufficient time to have signs removed from the road before dark.

ITEM 100: Preparing Right of Way

Do not burn trash, debris, etc. on State right of way. Burning material not suitable for sale or mulch will be allowed off State right of way in accordance with local laws, ordinances, codes, resolutions, and regulations. Burn only when smoke will not reduce visibility on adjacent roads.

Clearing shall be performed by mechanical equipment, such as tracked mulching tractors, that will minimize ground disturbance. Produce a wood-chip mulch derived from the trunks and branches of trees, shrubs, and other vegetation cleared. Any merchantable chips may be removed and sold. The chipped material produced shall not exceed 6 inches by 3 inches in size. Trees shall be cut and removed or mulched without the stumps or roots being disturbed to prevent ground disturbance. Tree and brush stumps shall be severed or ground flush with the natural ground in a way that allows the Prep Right of Way limits to be mowed in the future. Any wood-chip mulch produced (and not hauled off of right of way) shall be evenly spread across the area being cleared. Spread mulch over cleared area not exceeding a depth of 6 inches.

Merchantable timber and woodchips in the clearing area may be removed only if ground conditions are suitable to prevent rutting and significant soil disturbance of the right of way.

The contractor shall exercise care so that other trees, shrubs, grass, and other vegetation designated to remain are not damaged. Smooth any ruts/disturbance in clearing area to match original ground conditions. Every precaution shall be taken to prevent timber from falling on private property.

Control: 6472-05-001

County: Titus

Highway: IH0030

Low-hanging, unsound, or unsightly branches shall be removed from trees or shrubs designated to remain along the edge of the clearing limits. Trimming shall be done by skilled workers and according to good tree surgery practices. In general, branches hanging over the clearing limits shall be trimmed to a minimum height of 20 feet from the ground for trees that remain in place.

ITEM 164: Seeding for Erosion Control

PERMANENT PLANTING MIXTURE Species and Rates (lb. PLS/ac.)

(Season: January 15 to May 15)

Hooded Windmillgrass (Burnet)	0.3
Sand Dropseed (Taylor)	0.2
Little Bluestem (Coastal Plains)	2.0
Florida Paspalum (Harrison)	2.25
Splitbeard Bluestem (Neches)	1.0
Sand Lovegrass (Mason)	0.4
Red Lovegrass (Duval)	0.2
Hairy Grama (Chaparral)	0.4

TEMPORARY SEEDING FOR EROSION CONTROL

Warm Season (Season: February 1 to August 31) Brownton Millet 20

Cool Season (Season: September 1 to January 31) Oats 30 30 Wheat Little Barley 5.0 Western Wheatgrass 5.0

Adjust the seeding mixture and rates if directed.

Inoculate crimson clover seed with a legume inoculant. Sow inoculated seed dry, with either hand operated or mechanical equipment, after the fertilizer is placed.

Do not use Bahia grass.

Sheet

Control: 6472-05-001

Highway: IH0030

County: Titus

Project Number: A00211799

Use broadcast seeding for temporary erosion control, when and as directed. This will not be paid for directly but is subsidiary to the various bid items.

Use additional temporary seeding if permanent seeding is placed outside the optimum growing season shown for this item, if directed.

ITEM 166: Fertilizer

When seeding between September 1 and January 1, place one-half of the amount of fertilizer specified for seeding with the seeds and place the remainder the following spring unless otherwise directed. When seeding is placed between January 1 and June 1, place onehalf the amount of fertilizer specified for seeding with the seeds and place the remainder 30 days later unless otherwise directed.

Apply fertilizer (13-13-13) at a rate of 300 lbs. /5000 sq. yds.

ITEM DESCRIPTION *166 Fertilizer (13-13-13) 300 lb.

*FOR CONTRACTOR'S INFORMATION ONLY.

Item 502: Barricades, Signs and Traffic Handling

Please note that Item 502 "Barricades, Signs and Traffic Handling" is a bid item on this contract. Traffic control supplied by the contractor in accordance with this contract will be considered subsidiary to the other items in the contract.

Restrict the movement of equipment across traffic lanes to an absolute minimum.

Use strobe lights or rotating beacons on all motorized equipment, operating on or adjacent to the road surface.

Existing traffic signs which provide conflicting information to the driver during various stages will be covered until such time that a conflict no longer exists.

Furnish and install all signs, barricades, and other incidentals necessary for proper traffic control, in accordance with Part VI of the Texas Manual on Uniform Traffic Control Devices for Streets and Highways, or as directed. All warning signs must be factory made and in satisfactory condition.

Comply with TCP standards included in these plans. If there is a situation not covered by these standards, then comply with the applicable TCP sheets that are available on the web at: http://www.txdot.gov/insdtdot/orgchart/cmd/cserve/standard/toc.htm

Control: 6472-05-001

BASIS OF ESTIMATE

RATE	UNIT	QUANTITY
/5,000 sq. yd. of Seed	ton	14

County: Titus

Highway: IH0030

Item 503: Portable Changeable Message Signs

Use Portable Changeable Message Signs as required by the applicable TCP or as directed. Requirements for PCMS and payment will be handled in accordance with Article 503.5.

Portable Changeable Message Signs (PCMS) will be used on this contract. The Portable Changeable Message Signs will be used in advance of tree removal operations where conditions and traffic control plan standards warrant the use of message signs. Place a PCMS 1500 feet in advance of the last available exit ramp prior to lane closure to allow motorists an opportunity to take an alternate route. Place other PCMS as directed. Multiple work locations will require multiple sets of message signs. They may also be required at other locations as directed by the Engineer. The Portable Changeable Message Signs required by traffic control plan standards will be paid for by the day after installed and fully operational. The Portable Changeable Message Signs required for other locations directed by the Engineer may be paid for by the each after installed and fully operational.

Item 505: Truck-Mounted Attenuator (TMA) and Trailer Attenuator (TA)

The shadow vehicle with truck mounted attenuator (TMA) will not be optional but will be required as shown on the appropriate traffic control plan sheets.

A total of one (1) shadow vehicle with TMA will be required for work. The contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMA's needed for the project.

Control: 6472-05-001

Sheet 4C

E	ST. FINAL.									L ITEM CODE DESCR		DESCRIPT	
	- · · · · · · · · · · · · · · · · · · ·	AL. EST.	FINAL.	EST.	FINAL.	EST.	FINAL.	EST.	FINAL.	Т	ITEM NO.	DESC. SP CODE NO.	
											100	7001	PREPARING ROW
				_							164	7005	BROADCAST SEED (TEM
-						-			-		164	7006	BROADCAST SEED (TEM
					_				_	-	164	7073	BOND FBR MTRX SEED
-						-				-	168	7001	VEGETATIVE WATERING
			-		-		-		-		169	7043	SOIL RETENTION BLAN
									-		500	7001	MOBILIZATION
					-	-		-	-	+ -	502	7001	BARRICADES, SIGNS
						-			+	+	503 505	7001	PORTABLE CHANGEABL TMA (STATIONARY)
						-	-	1.	-	-	505	7001	IMA (SIAIIONARI)
						-	-		-	1			
				1				1					
			_										
					-	_				_			
							-			-			
-			-		-	-			-	1			
-							-		-	-			
-			_	-		-				+			
-								-	+	+			
-								5		1			
-			-	-									
				-								-	

	U		
	N	TOT	AL
	Т	EST.	FINAL
	AC	3.31	
	SY	16,044	
	SY	16,044	
RAL) (SAND)	SY	16,044	
1)(TY B)	TGL SY	258 16,044	
I) (II B)	LS	10,044	
IC HANDLING	MO	1	
SIGN	DAY	17	
	DAI	17	
	~		
PRI	O IECT NO		SHEET NO.
	OJECT NO. 5472-05-001		5
RWC P			
CIAIE	OUNTY	CONT. SECT.	

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

- 1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the 2. responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed 3. by a licensed professional engineer for approval. The Engineer may develop. sign and seal Contractor proposed changes.
- 4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- 5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- 8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the 9. BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- 10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown ON BC(2). THE OBEY WARNING SIGNS STATE LAW sign. STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES. CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, ČSJ limit signs are not required.
- 11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- 12. The Engineer has the final decision on the location of all traffic control devices.
- 13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

- 1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility" Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- 2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.


COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

- 1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- 2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LI
http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LI
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE M
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICE
TRAFFIC ENGINEERING STANDARD SHEETS

NE	AT
IST	(CWZTCD)
/ANU	ALS)"
ł	
ES (TMUTCD)

SHEE	T 1	OF	12				
Texas Department of	of Tra	nsp	ortation		Sa Div	affic fety ision ndard	
BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS BC(1)-21							
FILE: bc-21.dgn		(DOT	CK: TXDOT	DW:	TxDOT	ск: TxDOT	
CTxDOT November 2002	CONT	SECT	JOB		ні	SHWAY	
4-03 7-13	6472	05	001		IΗ	30	
9-07 8-14	DIST		COUNTY			SHEET NO.	
5-10 5-21	ATL		TITUS			6	
95							



TYPICAL	CONSTRUCTION	WARNING	SIGN	SIZE	AND	SPACING ^{1,5,6}

SIZE

Sign Number or Series	Conventional Road	Expressway/ Freeway
CW20 ⁴ CW21 CW22 CW23 CW25	48" × 48"	48" × 48"
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" × 36"	48" × 48"
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" × 48"	48" × 48"

SF	PACING
Posted Speed	Sign∆ Spacing "X"
MPH	Feet (Apprx.)
30	120
35	160
40	240
45	320
50	400
55	500 ²
60	600 ²
65	700 ²
70	800 ²
75	900 ²
80	1000 ²
*	* 3

★ For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.


ightarrow Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES

- 1. Special or larger size signs may be used as necessary.
- 2. Distance between signs should be increased as required to have 1500 feet advance warning.
- 3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 4. 36" x 36" "ROAD WORK AHEAD" (CW20-1D)signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- 5. Only diamond shaped warning sign sizes are indicated.
- 6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

		LEGEND								
	⊢ Type 3 Barricade									
		000	Channelizing Devices							
		4	Sign							
-	X See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.									
			SHEET 2 OF 12		•					
·.	Te	🗣 ° xas Depa	rtment of Transportation	Sa Div	affic fety ision ndard					
	BARRICADE AND CONSTRUCTION PROJECT LIMIT									
	BC (2) - 21									

		70 V E	-	~ •				
FILE:	bc-21.dgn	DN: T:	KDOT	CK: TXDOT DW:		TxDOT	ск: TxDOT	
© TxDOT	November 2002	CONT	CONT SECT JOB HIGHW				GHWAY	
	REVISIONS	6472	05	001		II	+ 30	
9-07	8-14				SHEET NO.			
7-13	5-21	ATL	TITUS				7	
06								



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width

f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).


GENERAL NOTES

- 1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- 2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- 3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.


4. Frequency of work zone speed limit signs should be: 40 mph and greater 0.2 to 2 miles 35 mph and less 0.2 to 1 mile

- 5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- 6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE"(G20-5aP) plaque and the "SPEED LIMIT"(R2-1)signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- 7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- 8. Techniques that may help reduce traffic speeds include but are not limited to: A. Law enforcement.
 - B. Flagger stationed next to sign.
 - C. Portable changeable message sign (PCMS).
 - D. Low-power (drone) radar transmitter.
 - E. Speed monitor trailers or signs.
- 9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- 10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.





	ET 3	OF	12						
Texas Department	t of Tra	nsp	ortation		S. Di	raffic afety vision andard			
BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT BC (3) - 21									
FILE: bc-21.dgn	dn: TxD	OT	CK: TXDOT	Dw:	TxDOT	ск: TxDOT			
(C)TxDOT November 2002	CONT	SECT	JOB		н	IGHWAY			
		2 05 001 IH 30							
REVISIONS	6472	0.5	001		•	н 30			
<u> </u>	6472 DIST	05	COUNTY			H 30 SHEET NO.			



GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white. Barricades shall NOT be used as sign supports
- guide the traveling public safely through the work zone.
- the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- the Engineer can verify the correct procedures are being followed.
- damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- for identification shall be 1 inch.

The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

- regard to crashworthiness and duration of work requirements.
- a. Long-term stationary work that occupies a location more than 3 days.
- more than one hour. c.
- Short, duration work that occupies a location up to 1 hour. d.
- Mobile work that moves continuously or intermittently (stopping for up to approximately 15 minutes.) e.

SIGN MOUNTING HEIGHT

- as shown for supplemental plaques mounted below other signs.
- the ground. Long-term/Intermediate-term Signs may be used in Lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to
- appropriate Long-term/Intermediate sign height.

SIZE OF SIGNS

The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave. centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- 1. All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300

SIGN LETTERS

1. All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- intersections where the sign may be seen from approaching traffic. Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely
- covered when not required.
- entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting. Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS

- 1. Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used. The sandbags will be tied shut to keep the sand from spilling and to maintain a
- constant weight. Rock, concrete, iron, steel or other solid objects shall not be permitted
- for use as sign support weights. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

1. Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

No warranty of any for the conversion m its use. Texas Engineering Practice Act". TxDDT assumes no responsibility t results or damages resulting fro DISCLAIMER: The use of this standard is governed by the "Te kind is made by TxDDT for any purpose whatsoever. of this standard to other formats or for incorrect

WHITE TYPE B OR C SHEETING LEGEND & BORDER BLACK ACRYLIC NON-REFLECTIVE FILM

- or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

LEGEND & BORDER

All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and

The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in

The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZICD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a guestion regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so

The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or

Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used

<u>DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)</u>

The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in

Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting

Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.

The bottom of Long-term/intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except

The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above

Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZICD lists each substrate that can be used on the different types and models of sign supports. All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6"

for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1). White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background. 3. Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of

Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any

When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the


SHEET 4 OF 12

Texas Department of Transportation

Traffic Safety Division Standaro

BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

		BC	(4) -	·21				
LE:	bc-21.dgn		DN: T)	<dot< td=""><td>ск: TxDOT</td><td>Dw:</td><td>TxDOT</td><td>CK: TXDOT</td></dot<>	ск: TxDOT	Dw:	TxDOT	CK: TXDOT	
) TxDOT	November 2002		CONT	SECT	JOB		HIGHWAY		
	REVISIONS		6472	05	001			IH 30	
9-07	8-14 5-21		DIST	DIST COUNTY			SHEET NO.		
7-13			ATL		TITUS	TITUS		9	



Docusign Envelope ID: 9B2F9C1E-3D11-4E4F-945F-F7DC2A6F7178

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

PORTABLE CHANGEABLE MESSAGE SIGNS

- 1. The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to 2. eight characters per word), not including simple words such as "TO," "FOR, " "AT, " etc.
- 3. Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- 4. Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) 5. along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to 7. start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message 9. should be steady burn or continuous while displayed.
- 10. Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
 Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- 13. Do not display messages that scroll horizontally or vertically across the face of the sign.
- 14. The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- 15. PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- 16. Each line of text should be centered on the message board rather than left or right justified.
- 17. If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Cannot	CANT	North	N
Center	CTR	Nor thbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
	EMER	Slippery	SLIP
Emergency		South	S
Emergency Vehicle		Southbound	(route) S
Entrance, Enter	ENT	Speed	SPD
Express Lane	EXP LN	Street	ST
Expressway	EXPWY	Sunday	SUN
XXXX Feet	XXXX FT	Telephone	PHONE
Fog Ahead	FOG AHD	Temporary	TEMP
Freeway	FRWY, FWY	Thursday	THURS
Freeway Blocked	FWY BLKD	To Downtown	TO DWNTN
Friday	FRI	Traffic	TRAF
Hazardous Driving	HAZ DRIVING	Travelers	TRVLRS
Hazardous Material		Tuesday	TUES
High-Occupancy	HOV	Time Minutes	TIME MIN
Vehicle	HWY	Upper Level	UPR LEVEL
Highway		Vehicles (s)	VEH, VEHS
Hour(s)	HR, HRS	Warning	WARN
Information	INFO	Wednesday	WED
lt Is	ITS	Weight Limit	WTLIMIT
Junction	JCT	West	W
Left	LFT	Westbound	(route) W
Left Lane	LFT LN	Wet Pavement	WET PVMT
Lane Closed	LN CLOSED	Will Not	WONT
Lower Level	LWR LEVEL		
Maintenance	MAINT		

RECOMMENDED	PHASES	AND	FORMATS	FOR	PCMS	MESSAGES	DUR
						• • • · · ·	

(The Engineer may approve other messages not specifically covered here.)

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

		other con	UITION LIST
FREEWAY CLOSED X MILE	FRONTAGE ROAD CLOSED	ROADWORK XXX FT	ROAD REPAIRS XXXX FT
ROAD CLOSED AT SH XXX	SHOULDER CLOSED XXX FT	FLAGGER XXXX FT	LANE NARROWS XXXX FT
ROAD CLSD AT FM XXXX	RIGHT LN CLOSED XXX FT	RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
RIGHT X LANES CLOSED	RIGHT X LANES OPEN	MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
CENTER LANE CLOSED	DAYTIME LANE CLOSURES	LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
NIGHT LANE CLOSURES	I-XX SOUTH EXIT CLOSED	DETOUR X MILE	ROUGH ROAD XXXX FT
VARIOUS LANES CLOSED	EXIT XXX CLOSED X MILE	ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
EXIT CLOSED	RIGHT LN TO BE CLOSED	BUMP XXXX FT	US XXX EXIT X MILES
MALL DRIVEWAY CLOSED	X LANES CLOSED TUE - FRI	TRAFFIC SIGNAL XXXX FT	LANES SHIFT ¥
XXXXXXXX BLVD CLOSED	* LANES SHIFT in Phase	1 must be used wit	n STAY IN LANE in Pho

Other Con	dition List
ROADWORK XXX FT	ROAD REPAIRS XXXX FT
FLAGGER XXXX FT	LANE NARROWS XXXX FT
RIGHT LN NARROWS XXXX FT	TWO-WAY TRAFFIC XX MILE
MERGING TRAFFIC XXXX FT	CONST TRAFFIC XXX FT
LOOSE GRAVEL XXXX FT	UNEVEN LANES XXXX FT
DETOUR X MILE	ROUGH ROAD XXXX FT
ROADWORK PAST SH XXXX	ROADWORK NEXT FRI-SUN
BUMP XXXX FT	US XXX EXIT X MILES
TRAFFIC SIGNAL XXXX FT	LANES SHIFT

Action to Take/Effect on Travel List MERGE FORM RIGHT X LINES RIGHT DETOUR USE XXXXX NEXT RD EXIT X EXITS USE USE EXIT EXIT XXX I-XX NORTH STAY ON USE US XXX I-XX F SOUTH TO I-XX N TRUCKS WATCH USE FOR US XXX N TRUCKS WATCH EXPECT FOR DELAYS TRUCKS PREPARE EXPECT DELAYS ТΟ STOP REDUCE END SPEED SHOULDER XXX FT USE WATCH USE OTHER FOR ROUTES WORKERS STAY ĪΝ LANE

APPLICATION GUIDELINES

- 1. Only 1 or 2 phases are to be used on a PCMS. 2. The 1st phase (or both) should be selected from the
- "Road/Lane/Ramp Closure List" and the "Other Condition List".
- 3. A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- 4. A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- 5. If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- 6. For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- 1. The words RIGHT, LEFT and ALL can be interchanged as appropriate. 2. Roadway designations IH, US, SH, FM and LP can be interchanged as
- appropriate.
- be interchanged as appropriate.
- 4. Highway names and numbers replaced as appropriate.
- 5. ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- 6. AHEAD may be used instead of distances if necessary. 7. FT and MI. MILE and MILES interchanged as appropriate.
- 8. AT. BEFORE and PAST interchanged as needed.
- 9. Distances or AHEAD can be eliminated from the message if a
- location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC. THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.


FULL MATRIX PCMS SIGNS

- 1. When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 und CHANGEABLE MESSAGE SIGNS" above.
- 2. When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of t shall maintain the legibility/visibility requirement listed above
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and for, or replace that sign.
- 4. A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC some size arrow.

Roadway

RING ROADWORK ACTIVITIES

Phase 2: Possible Component Lists




* * See Application Guidelines Note 6.

XX AM

EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can

		SF	IEET 6	OF	12				
		╋ [®] Texas Departme	ent of Tra	insp	ortation		Sa Div	affic nfety rision ndard	
BARRICADE AND CONSTRUCTI PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)									
nder "PORTABLE		_		•	•••				
the Engineer, it		E	3C (6) -	-21				
<u>.</u> .	FILE:	bc-21,dgn	DN: T:	xDOT	CK: TxDOT	DW:	TxDOT	ск: TxDOT	
d shall not substitute	C TxDOT	November 2002	CONT	SECT	JOB		нт	GHWAY	
		REVISIONS	6472	05	001		I۲	1 30	
C(7), for the	9-07	8-14	DIST		COUNTY			SHEET NO.	
	7-13	5-21	ATL		TITUS	5	11		
	100								

Docusign Envelope ID: 9B2F9C1E-3D11-4E4F-945F-F7DC2A6F7178













GENERAL NOTES

- 1. For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- 2. For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- 3. For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- 4. Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 5. Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- 6. The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS


- Pre-gualified plastic drums shall meet the following requirements:
- 1. Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- 2. The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- 3. Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- 4. Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- 5. The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- 6. The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectorized space between any two adjacent stripes shall not exceed 2 inches in width.
- 7. Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- 8. Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- 9. Drum body shall have a maximum unballasted weight of 11 lbs.
- 10. Drum and base shall be marked with manufacturer's name and model number.


RETROREFLECTIVE SHEETING

- 1. The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- 2. The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- 1. Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- 2. Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- 3. Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- 4. The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- 5. When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- 6. Ballast shall not be placed on top of drums.
- 7. Adhesives may be used to secure base of drums to pavement.






DETECTABLE PEDESTRIAN BARRICADES

- 1. When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures. 2. Where pedestrians with visual disabilities normally use the
- closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- 3. Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian
- 4. Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- 5, Warning lights shall not be attached to detectable pedestrian barricades.
- 6. Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.

È C



(Maximum Sign Dimension)

Chevron CW1-8, Opposing Traffic Lane

Divider, Driveway sign D70a, Keep Right

R4 series or other signs as approved

by Engineer



12" x 24" Vertical Panel mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums


SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- 1. Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- 2. Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- 3. Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- 4. Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- 5. Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- 6. Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- 7. Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- 8. R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHE	ET 8	OF	12							
Texas Departmen	t of Tra	nsp	ortation		Sa Div	affic fety ision ndard				
CHANNEL	BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES									
) -		DW:	TxDOT	ck: TxDOT				
FILE: bc-21.dgn (C)TxDOT November 2002		SECT	JOB	UWI		CKE I XUUT SHWAY				
REVISIONS	6472	05	001			30				
4-03 8-14 9-07 5-21	DIST		COUNTY			SHEET NO.				
7-13	ATL		TITUS			13				
102										


See Ballast

Note 3



- 1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- 2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- 3. Chevrons, when used, shall be erected on the out side of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- 4. To be effective, the chevron should be visible for at least 500 feet.
- 5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- 6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- 1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- 3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and
- 4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- 5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- 6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- 2. Water ballosted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- 3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- 1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- 2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- 3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- 4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- 5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- 7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

		_					
Posted Speed	Formula	Minimum Desirable Taper Lengths X X			Suggested Maximum Spacing of Channelizing Devices		
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	
30	2	150'	1651	180′	30'	60'	
35	$L = \frac{WS^2}{60}$	205'	225′	245'	35′	70′	
40	60	265'	295′	320'	40′	80′	
45		450 <i>'</i>	495′	540'	45′	90'	
50		500'	550'	600'	50 <i>'</i>	100'	
55	L=WS	550'	605′	660 <i>'</i>	55 <i>'</i>	110′	
60	L - 11 S	600'	660'	720'	60 <i>'</i>	120′	
65		650′	715′	780′	65 <i>'</i>	130'	
70		700′	700' 770' 840'			140'	
75		750′	750' 825' 900'			150′	
80		800′	880′	960'	80 <i>'</i>	160′	

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND

XX Taper lengths have been rounded off.

S=Posted Speed (MPH)

L=Length of Taper (FT.) W=Width of Offset (FT.)

MINIMUM DESIRABLE TAPER LENGTHS


SHEET 9 OF 12

st Texas Department of Transportation Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

		BC	(9) -	·21				
LE:	bc-21.dgn		dn: T>	DOT	ск: TxDOT	Dw:	TxDOT	ск: TxDOT	
TxDOT	November 2002		CONT SECT		JOB		HIGHWAY		
	REVISIONS		6472	05	001		IH	30	
9-07	8-14		DIST		COUNTY			SHEET NO.	
7-13	5-21		ATL		TITUS			14	
03									





104

SHEE1	r 10	0	F 12		
Texas Department	of Tra	nsp	ortation	Ĺ	Traffic Safety Division tandard
BARRICADE AI CHANNELIZ	ZIN	IG			
FILE: bc-21.dgn	DN: T)	<dot< th=""><th>CK: TXDOT D</th><th>w: T×DC</th><th>T CK: TXDOT</th></dot<>	CK: TXDOT D	w: T×DC	T CK: TXDOT
© TxDOT November 2002	CONT	SECT	JOB		HIGHWAY
REVISIONS	6472	05	001		IH 30
9-07 8-14 7-13 5-21	DIST		COUNTY		SHEET NO.
1-13 3-21	ATL		TITUS		15

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ (STPM).
- 6. When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- 1. Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- 1. Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- 3. The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- 4. The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- 7. Over-painting of the markings SHALL NOT BE permitted.
- 8. Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- 10.Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



STAPLES OR NAILS SHALL NOT BE USED TO SECU TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARK TABS TO THE PAVEMENT SURFACE

- Temporary flexible-reflective roadway marker tabs used as guiden shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by Engineer or designated representative. Sampling and testing is m normally required, however at the option of the Engineer, either or "B" below may be imposed to assure quality before placement or roadway.
 - A. Select five (5) or more tabs at random from each lot or sh and submit to the Construction Division, Materials and Pav Section to determine specification compliance.
 - B. Select five (5) tabs and perform the following test. Affix (5) tabs at 24 inch intervals on an asphaltic pavement in straight line. Using a medium size passenger vehicle or pir run over the markers with the front and rear tires at a sp of 35 to 40 miles per hour, four (4) times in each direction more than one (1) out of the five (5) reflective surfaces be lost or displaced as a result of this test.
- 3. Small design variances may be noted between tab manufacturers.
- 4. See Standard Sheet WZ(STPM) for tab placement on new pavements. Standard Sheet TCP(7-1) for tab placement on seal coat work.


RAISED PAVEMENT MARKERS USED AS GUIDEMARK

- Raised pavement markers used as guidemarks shall be from the ap product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applie butyl rubber pad for all surfaces, or thermoplastic for concretsurfaces.


Guidemarks shall be designated as:


YELLOW - (two amber reflective surfaces with yellow body). WHITE - (one silver reflective surface with white body).

	DEPARTMENTAL MATERIAL SPECIFICAT	IONS
	PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
	TRAFFIC BUTTONS	DMS-4300
IEW	EPOXY AND ADHESIVES	DMS-6100
57	BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
	PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
	PAVEMENT MARKINGS	DMS-8241
 _	TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242
ve pad	A list of prequalified reflective raised pavement non-reflective traffic buttons, roadway marker to pavement markings can be found at the Material Po web address shown on BC(1).	abs and othe
2		
ks		
ne 'A" the		
oment nent		
tive kup, ed n. No nall		
e		
oved		
oved		
or		
	SHEET 11 OF 12	
		Traffic
	★*	Safety Division
		Safety
	Texas Department of Transportation	Safety Division Standard
	Texas Department of Transportation	Safety Division Standard
	Texas Department of Transportation	Safety Division Standard
	Texas Department of Transportation	Safety Division Standard
	Texas Department of Transportation BARRICADE AND CONSTI PAVEMENT MARKIN	Safety Division Standard
	Texas Department of Transportation BARRICADE AND CONSTI PAVEMENT MARKIN BC(111)-21	Safety Division Standard
	Texas Department of Transportation BARR I CADE AND CONSTINE PAVEMENT MARK IN BC (111) - 21 FILE: bc-21. dgn DN: TXDOT CK: TXDOT C	Safety Division Standard
	Texas Department of Transportation BARR I CADE AND CONSTI PAVEMENT MARK IN BC (111) - 21 FILE: bc-21. dgn DNI: TXDOT CK: TXDOT	Safety Division Standard



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDD1 for any purpose whatsoever. TxDD1 assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





LEGEND							
<u>~~~~</u>	Type 3 Borricode		Channelizing Devices				
	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)				
Ē	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)				
4	Sign	2	Traffic Flow				
\langle	Flag	Ŀ	Flogger				

Posted Speed X	Formula	D	Minimur esirab er Len X X	le	Špa Chan	ted Maximum cing of nelizing evices On a	Suggested Longitudinal Buffer Space "B"		
		Offset	Offset	Offset	Taper	Tangent			
30	<u>ws</u> ²	150'	165′	180'	30'	60 <i>'</i>	90'		
35	$L = \frac{WS}{60}$	205'	225′	245'	35′	70 <i>'</i>	120'		
40	00	265′	295′	320'	40′	80'	155'		
45		450'	495′	540'	45′	90'	195'		
50		500'	550 <i>'</i>	600′	50'	100′	240'		
55	L=WS	550'	605′	660 <i>'</i>	55′	110′	295 <i>'</i>		
60	L-45	600 <i>'</i>	660′	720'	60 <i>'</i>	120'	350′		
65		650'	715′	780'	65′	130′	410′		
70		700'	770'	840'	70′	140′	475′		
75		750ʻ	825′	900′	75′ 150′		540 <i>'</i>		
80		800 <i>'</i>	880'	960'	80′	160′	615′		

X Conventional Roads Only

**Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH


TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	TCP (5-1a)	TCP (5-1b)	TCP (5-1b)					

GENERAL NOTES

- A Shadow Vehicle with a TMA should be used anytime it can be positioned 30' to 100' in advance of the area of crew exposure without adversely effecting the performance or quality of the work. Type 3 barricades or drums may be substituted when workers on foot are no longer present when approved by the Engineer.
- 2. 28" tall or taller one-piece cones will be allowed only for Short Duration or Short Term stationary operations when workers are present to maintain the devices upright and in proper location. Intermediate Term stationary work areas should use Drums, Vertical Panels or 42" tall two-piece cones.

$\langle \rangle$		★* Texas Department	of Tra	nsp	ortatior	7	Ope Div	raffic erations vision andard
AD RK AD -1D K 48"	F	TRAFFIC SHOULDE REEWAYS	R	WO	RK	FO	R	-
		TCP (5 - 1)	-18	1		
	FILE:	tcp5-1-18.dgn	DN:		СК:	Dw:		CK:
	© ⊺xDOT	February 2012	CONT	SECT	JOB		н	IGHWAY
		REVISIONS	6472	05	001		I	Н 30
	2-18		DIST		COUNT	Y		SHEET NO.
	1901		ATL		TITU	IS		18
	1901		ATL		TITU	IS		18

190



				LEC	GEND							
	z Type 🛛	3 Barr	icade			Ch	Channelizing Devices					
] Неату	Heavy Work Vehicle				Truck Mounted Attenuator (TMA)						
Ē		Trailer Mounted Flashing Arrow Board			M	Portable Changeable Message Sign (PCMS)						
-	Sign			\Diamond	Traffic Flow							
\bigtriangleup	Flag	Flag			ЦO	Flagger						
Posted Speed	Formula	Minimum Desirable Taper Lengths "L" rmula X X		Desirable Spo Taper Lengths "L" Char			Spa Chan D	icir inel ievi	d Maximum ng of lizing ices	Suggested Longitudinal Buffer Space		
		10' Offset	11' Offset	12' Offse	On a Tape			"В"				
45		450'	495′	540'	451		90 <i>'</i>	195′				
50		500'	550'	600'	50'		100'	240′				
55	L=WS	550'	605 <i>'</i>	660	55'		110'	295′				
60	L-W3	600'	660'	720'	60'	·	120'	350′				

XX Taper lengths have been rounded off.

650' 715' 780

700' 770' 840'

750' 825' 900'

800' 880' 960'

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

65′

70'

75′

80'

130'

140'

150'

160'

410'

475'

540'

615'

TYPICAL USAGE							
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY			
	1	1	4				

65

70

75

80

1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

2. Drums or 42" cones are the typical channelizing devices. For Intermediate Term Stationary work, drums shall be used on tapers with drums or 42" cones used on tangent sections. Other channelizing devices may be used as directed by the Engineer. 3. All construction signs and barricades placed during any phase of work shall remain in place until removal is approved by the Engineer.

4. The Engineer may direct the Contractor to furnish additional signs and barricades as required to maintain traffic flow, detours and motorist safety during construction. 5. Static message boards or changeable message signs stating the date and duration of ramp or freeway lane closures shall be placed a minimum of seven (7) calendar days in advance of the actual closure.

6. Phase 2 of the PCMS message should include appropriate information formatted as shown on BC(6), such as "MERGE LEFT," recommended advisory speed, delay information, or other specific warnings.


7. Duplicate construction warning signs should be erected on the medians side of freeways where median width will permit and traffic volume justifies the signing. 8. The number of closed lanes may be increased provided the spacing of traffic control devices, taper lengths and tangent lengths meet the requirements of the TMUTCD. 9. Warning signs for intermediate term stationary work should be mounted at 7' to the

10.Warning signs shown shall be appropriately altered for left lane closures. When signs are mounted at 1' height for short term stationary or short duration work, sign versions shown in the SHSD for Texas with distances on the sign face rather than mounted on a plaque below the sign may be used.

11. When possible, PCMS units should be located in advance of the last available exit ramp prior to the lane closure to allow motorists an alternate route. They may also be relocated to improve advance warning in case of unanticipated queuing or congestion. 12.For Intermediate Term Stationary work at night, floodlights should be used to illuminate the work area and equipment crossings. Floodlights shall not produce a disabling glare condition for road users or workers.

13. The END ROAD WORK (G20-2) sign may be omitted when it conflicts with G20-2 signs already in place on the project.

nicle equipped with hted Attenuator is equired. A shadow	7	Texas Traffic				of Tra i on Stando		ortati	'on
pped with a TMA shall t can be positioned in advance of the v exposure without fecting the work	TRAFFIC CONTROL PLAN FREEWAY LANE CLOSURES								
			TCF	P (6-	-1)-	• 1	2	
	FILE:	tcp6-1.dgn		dn: Tx	DOT	ск: TxDOT	DW:	TxDOT	ск: TxDOT
	(C) TxDOT	February 19	98	CONT	SECT	JOB		HIC	HWAY
	8-12	REVISIONS	1	6472	05	001		ΙH	30
	0-12			DIST		COUNTY		Ş	HEET NO.
				ATL		TITU	s		19



DATE:

LEGEND								
<u>~ ~ ~ ~ ~</u>	Type 3 Barricade		Channelizing Devices					
□þ	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)					
Ð	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)					
4	Sign	2	Traffic Flow					
\bigtriangledown	Flag	٩	Flagger					

Posted Speed	Formula	D	Minimur esirab Lengtl X X	le	Spacir Channe		Suggested Longitudinal Buffer Space
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	"В"
45		450'	495′	540'	45′	90′	195′
50		500'	550 <i>'</i>	600′	50 <i>'</i>	100'	240′
55	L=WS	550'	605′	660′	55 <i>'</i>	110'	295′
60	2 113	600 <i>'</i>	660 <i>'</i>	720'	60 <i>'</i>	120'	350′
65		650′	715′	780 <i>'</i>	65 <i>'</i>	130'	410′
70		700'	770'	840'	70′	140′	475′
75		750′	825′	900'	75′	150′	540′
80		800′	880′	960'	80′	160'	615′

XX Taper lengths have been rounded off. L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	-	-	4					

GENERAL NOTES:


1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.


XA shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

USE	Texas Department of Transporta	tion
TREET A	Traffic Operations Division Standard	
EXIT		
on when bered	TRAFFIC CONTROL PLAN	N I
USE	WORK AREA BEYOND RAM	D
XIT XX		
(approx.) Street A	TCP (6-3) -12	
	FILE: tcp6-3.dgn DN: TxDOT CK: TxDOT DW: TxDOT	CK: TXDOT
		1]GHWAY
		Н 30
	1-97 8-98 DIST COUNTY 4-98 8-12	SHEET NO.
	4-98 8-12 ATL TITUS	20
	203	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDDT for any purpose whatsoever. TxDDT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





LEGEND									
	⊐ Type :	3 Barr	icade			Cr	Channelizing Devices (CDs)		
] Неалу	Heavy Work Vehicle					Truck Mounted Attenuator (TMA)		
Ē		iler Mounted shing Arrow Board			M		Portable Changeable Message Sign (PCMS)		
-	Sign				\Diamond	Т	low		
\Diamond	Flag				Flagger				
Posted Speed	Formula	D	Minimur esirab Lengtl X X 11'	le	Cr	spacti nanne	sted Maximum nacing of Suggested Innelizing Longitudina Devices Buffer Spac a 0 n a "B"		
45		Offset 450'	Offset 495'			per 15'	Tangent 90'	195'	
50		500'	550'		-	50'	100'	240'	
55	L=WS	550'	605 <i>'</i>	660	1 5	5 <i>'</i>	110'	295′	
60	L - W 3	600'	660'	720'	6	50 <i>1</i>	120'	350′	
65		650 <i>'</i>	715'	780	' 6	65 <i>1</i>	130'	410′	
70		700′	770'	840′		'0 <i>'</i>	140'	475′	
75		750'	825′	900	′ 7	'5 <i>'</i>	150'	540′	
80		800 <i>'</i>	880'	960	' E	30 <i>'</i>	160'	615'	

XX Taper lengths have been rounded off.

L=Length of Taper (FT) W=Width of Offset (FT) S=Posted Speed (MPH)

TYPICAL USAGE								
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY				
	1	1	4					

GENERAL NOTES


1. All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation Traffic Operations Division Standard									
TRAFFIC CONTROL PLAN WORK AREA AT EXIT RAMP									
TC	P (<u>6</u> .	-4) - 1	2					
TILE: tcp6-4, dgn		6 -	- 4) - 1 ck: TxDOT dw:	2	ck: TxDOT				
- •		<u> </u>		T×DOT	CK: TXDOT				
TILE: tcp6-4, dgn	DN: T)	(DOT SECT	CK: TXDOT DW:	T×DOT					
TLE: tcp6-4.dgn TxDOT Feburary 1994 REVISIONS 1-97 8-98	DN: T) CONT	(DOT SECT	CK: TXDOT DW: JOB	T×DOT	IGHWAY				
TILE: tcp6-4.dgn TxDOT Feburary 1994 REVISIONS	DN: T) CONT 6472	(DOT SECT	ск: TxDOT Dw: JoB OO1	T×DOT	IIGHWAY H 30				

^{2.} See BC Standards for sign details.



	LEGEND							
<u>~~~~</u>	Type 3 Barricade		Channelizing Devices					
	Heavy Work Vehicle	K	Truck Mounted Attenuator (TMA)					
Ð	Trailer Mounted Flashing Arrow Board	M	Portable Changeable Message Sign (PCMS)					
+	Sign	2	Traffic Flow					
$\langle \lambda \rangle$	Flag	۵ ₀	Flagger					

Posted Speed	Formula	D	Minimum Suggested Maximum Desirable Spacing of oper Lengths "L" Channelizing ** Devices		Suggested Longitudina। Buffer Space		
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	"B"
45		450'	495′	540'	45′	90'	1951
50		500'	550ʻ	600'	50 <i>'</i>	100'	240'
55	L=WS	550'	605 <i>'</i>	660 <i>'</i>	55 <i>'</i>	110'	295 <i>'</i>
60	2	600 <i>'</i>	660'	720′	60 <i>'</i>	120'	350'
65		650′	715′	780′	65′	130'	410'
70		700′	770'	840 <i>′</i>	70′	140'	475′
75		750'	825 <i>'</i>	900ʻ	75'	150'	540'
80		800'	880′	960'	80'	160'	615'

XX Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	E SHORT SHORT TERM INTERMEDIATE LONG TERM DURATION STATIONARY TERM STATIONARY STATIONARY								
	1	1	4						


GENERAL NOTES

- All traffic control devices illustrated are REQUIRED. Devices denoted with the triangle symbol may be omitted when stated elsewhere in the plans.
- 2. See BC standards for sign details.
- If adequate longitudinal buffer length "B" does not exist between the work space and the exit ramp, consideration should be given to closing the ramp.

*A shadow vehicle equipped with a Truck Mounted Attenuator is typically required. A shadow vehicle equipped with a TMA shall be used if it can be positioned 30' to 100' in advance of the area of crew exposure without adversely affecting the work performance.

Additional requirements for lane closures and advance signing shall be as shown on TCP (6-1) or as directed by the Engineer.

TRAFFIC CO WORK AREA BE	-	•			
TCP) (6-	-5) - 1	2	
FILE: tcp6-5.dgn DN	a: To	xDOT	CK: TXDOT DW:	TxDOT	ск: TxDOT
©⊺xDOT Feburary 1998 ¢	CONT	SECT	JOB	нI	GHWAY
REVISIONS 64	472	05	001	I۲	+ 30
	DIST		COUNTY		SHEET NO.
4-98 8-12 A	١TL		TITUS		22




NOTE: AREAS THAT ARE DISTURBED DURING TREE REMOVAL OR TRIMMING SHALL BE SEEDED WITH THE SAME SEED FOUND ELSEWHERE IN THE PLANS.

> DO NOT TRIM OR REMOVE LIMBS OR BRUSH PAST THE R.O.W. WITH OUT RIGHT-OF-ENTRY PERMIT. DO NOT TRIM ON RAILROAD R.O.W.

WHEN APPROVED TREE TRIMMING MULCH CAN BE DISTRIBUTED ON R.O.W. BUT MUST BETWEEN 1 INCHES AND 3 INCHES IN SIZE. DO NOT ALLOW MULCH TO REMAIN WITHIN 4 FEET OF: FLOW LINE OF DITCHES, EDGE OF PAVED DITCHES, OR DRAINAGE FLOW LINES.

SPREAD MULCH TO A SMOOTH AND UNIFORM THICKNESS OF NO MORE THAN 3 INCHES IN DEPTH.


EXACT LIMITS AND QUANTITIES TO BE VERIFIED IN THE FIELD.



STUMP GRINDING DETAIL







NOT TO SCALE

Docusign Envelope ID: 9B2F9C1E-3D11-4E4F-945F-F7DC2A6F7178

soeve use.

TxDOT for any purpose what: domoges resulting from its

ይዖ

is mode results

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind IXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect

STORMWAT	ER POLLUTION P	REVENTION-CLEAN WATER	ACT SECTION 402	III. CULTURAL RESOURCES	VI. HAZARDOUS
required f disturbed Item 506.	or projects with 1 soil must protect	r Discharge Permit or Constr 1 or more acres disturbed so for erosion and sedimentati	il. Projects with any on in accordance with	Refer to TxDOT Standard Specifications in the even archeological artifacts are found during construct archeological artifacts (bones, burnt rock, flint, work in the immediate area and contact the Engineer	ion. Upon discovery of hazardous material pottery, etc.) cease making workers awa
They may n		ay receive discharges from t d prior to construction acti	-	🛛 No Action Required 🗌 Required Act	on Obtain and keep or used on the project
1. N/A				Action No.	Paints, acids, so compounds or addi
2.					products which ma
No No	Action Required	Required Action		1.	Maintain an adequ In the event of c
Action	No.			2.	in accordance wit
	• stormwater pollu Ince with TPDES Per	tion by controlling erosion rmit TXR 150000	and sedimentation in	3.	immediately. The of all product sp
	with the SW3P and d by the Engineer.	revise when necessary to co	ontrol pollution or	4.	Contact the Engir * Dead or dis * Trash piles
				IV. VEGETATION RESOURCES	* Undesirable * Evidence of
the sit	e, accessible to	otice (CSN) with SW3P inform the public and TCEQ, EPA or specific locations (PSL's) i	other inspectors. ncrease disturbed soil	Preserve native vegetation to the extent practical Contractor must adhere to Construction Specification 164, 192, 193, 506, 730, 751, 752 in order to comp invasive species, beneficial landscaping, and tree	Don Requirements Specs 162, In with requirements for
area to) 5 acres or more,	submit NOI to TCEQ and the	Engineer.		If "No", there
	I OR NEAR STREA TIONS 401 AND	AMS, WATERBODIES AND WE 404	TLANDS CLEAN WATER	🛛 No Action Required 🗌 Required Acti	on If "Yes", then Are the result
USACE Per	mit required for	filling, dredging, excavatio	ng or other work in any	Action No.	Yes
		eks, streams, wetlands or we		1.	If "Yes", the
	ractor must adhere owing permit(s):	e to all of the terms and cor	nditions associated with		the notificati activities as
				2.	15 working day
🛛 No Per	mit Required			3.	If "No", then
	wide Permit 14 - 1 nds affected)	PCN not Required (less than	1/10th acre waters or	4.	scheduled demo In either case activities and
Natior	wide Permit 14 - I	PCN Required (1/10 to <1/2 c	acre, 1/3 in tidal waters)		asbestos consu
🗌 Indivi	dual 404 Permit Re	equired		V. FEDERAL LISTED, PROPOSED THREATENED, END	ANGERED SPECIES, Any other evide
🗌 Other	Nationwide Permit	Required: NWP#		CRITICAL HABITAT, STATE LISTED SPECIES, AND MIGRATORY BIRDS.	CANDIDATE SPECIES ON site. Haza
and check		ers of the US permit applies Practices planned to control		🛛 No Action Required 🗌 Required Acti	on 1.
1.				Action No.	2.
2.				1.	3.
3.				2.	VII. OTHER ENV
					(includes r
4.				3.	No Actic
to be per		ary high water marks of any ers of the US requiring the Bridge Layouts.		4.	Action No.
Best Mar	agement Practic	es:		If any of the listed species are observed, cease work do not disturb species or habitat and contact the Eng	
Erosion		Sedimentation	Post-Construction TSS	work may not remove active nests from bridges and othe	er structures during
🗌 Temporar	y Vegetation	Silt Fence	Vegetative Filter Strips	nesting season of the birds associated with the nests. are discovered, cease work in the immediate area, and	
Blankets	/Matting	Rock Berm	Retention/Irrigation Systems	Engineer immediately.	
Mulch		🗌 Triangular Filter Dike	Extended Detention Basin		
Sodding		Sand Bag Berm	Constructed Wetlands	LIST OF ABBREVIATIONS	
	tor Swale	🗌 Straw Bale Dike	Wet Basin	BMP: Best Management Practice SPCC: Spill Prever	tion Control and Countermeasure
_		🗌 Brush Berms	Erosion Control Compost	CGP: Construction General Permit SW3P: Storm Water	Pollution Prevention Plan tion Notification
Diversion					
Diversion	Control Compost	Erosion Control Compost	Mulch Filter Berm and Socks	FHWA: Federal Highway Administration PSL: Project Spec	ific Location
Diversion Erosion Mulch Fi	Control Compost Iter Berm and Socks	Erosion Control Compost	Compost Filter Berm and Socks	FHWA: Federal Highway Administration PSL: Project Spect MOA: Memorandum of Agreement TCEQ: Texas Carmis MOU: Memorandum of Understanding TPDES: Texas Pollut	ific Location sion on Environmental Quality ant Discharge Elimination System
Diversion Erosion Mulch Fi	Control Compost Iter Berm and Socks	Erosion Control Compost Erosion Control Compost Mulch Filter Berm and Socks Compost Filter Berm and Socks	Compost Filter Berm and Socks	FHWA: Federal Highway Administration PSL: Project Spect MOA: Memorandum of Agreement TCEQ: Texas Cormis MOU: Memorandum of Understanding TPDES: Texas Ponilut MS4: Municipal Separate Stormwater Sewer System TPWD: Texas Poniks MBTA: Migratory Bird Treaty Act TxDOT: Texas Depart	ific Location sion on Environmental Quality ant Discharge Elimination System

MATERIALS OR CONTAMINATION ISSUES

ies to all projects):

zard Communication Act (the Act) for personnel who will be working with s by conducting safety meetings prior to beginning construction and re of potential hazards in the workplace. Ensure that all workers are onal protective equipment appropriate for any hazardous materials used. -site Material Safety Data Sheets (MSDS) for all hazardous products t, which may include, but are not limited to the following categories: vents, asphalt products, chemical additives, fuels and concrete curing ives. Provide protected storage, off bare ground and covered, for be hazardous. Maintain product labelling as required by the Act.

te supply of on-site spill response materials, as indicated in the MSDS. spill, take actions to mitigate the spill as indicated in the MSDS, safe work practices, and contact the District Spill Coordinator pontractor shall be responsible for the proper containment and cleanup lls.

er if any of the following are detected: ressed vegetation (not identified as normal) drums, canister, barrels, etc. smells or odors leaching or seepage of substances

t involve any bridge class structure rehabilitation or ridge class structures not including box culverts)?

🛛 No

no further action is required. TxDOT is responsible for completing asbestos assessment/inspection.

of the asbestos inspection positive (is asbestos present)?

TxDOT must retain a DSHS licensed asbestos consultant to assist with n, develop abatement/mitigation procedures, and perform management ecessary. The notification form to DSHS must be postmarked at least prior to scheduled demolition.

TxDOT is still required to notify DSHS 15 working days prior to any ition.

the Contractor is responsible for providing the date(s) for abatement or demolition with careful coordination between the Engineer and tant in order to minimize construction delays and subsequent claims.

nce indicating possible hazardous materials or contamination discovered dous Materials or Contamination Issues Specific to this Project:

Required Required Action

RONMENTAL ISSUES

gional issues such as Edwards Aquifer District, etc.)

Required

Required Action

Texas Department of Transportation

Design Division Standard

ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS

EPIC

FILE: epic.dgn	dn: Tx[TOC	ск: RG	Dw: '	٧P	ck:AR
© TxDOT: February 2015	CONT	SECT	JOB		,	HIGHWAY
REVISIONS 12-12-2011 (DS)	6472	05	001		Ι	H 30
05-07-14 ADDED NOTE SECTION IV.	DIST		COUNTY			SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	ATI		TITUS	5		24