

FEDERAL AID PROJECT NO.			
BR 2025 (133), ETC			
CONT	SECT	JOB	HIGHWAY
0923	23	032, ETC	CR 508, ETC
DIST	COUNTY		SHEET NO.
BWD	MILLS, ETC		1

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

PLANS OF PROPOSED STATE HIGHWAY IMPROVEMENT

FEDERAL AID PROJECT NO. BR 2025 (133)

CR 508 AT DRAW
MILLS COUNTY

FOR THE CONSTRUCTION OF BRIDGE REPLACEMENT
CONSISTING OF REPLACE BRIDGE AND APPROACHES

LIMITS: ON CR 508 AT DRAW

DESIGN SPEED = MEETS OR EXCEEDS EXISTING
ADT (2019) = 50
ADT (2038) = 50
RURAL LOCAL

0923-23-032 LENGTH OF PROJECT

ROADWAY	= 481.86 FT	= 0.09 MI.
BRIDGE	= 60.14 FT	= 0.01 MI.
TOTAL	= 542 FT	= 0.10 MI.

REQUIRED SIGNS SHALL BE IN ACCORDANCE WITH BC (1)- 21 THRU BC (12)- 21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".


TDLR INSPECTION NOT REQUIRED



[Signature]
10/2/2024

VOLUME 1

CONTRACT CSJ: 0923-23-032



PROJECT CR 508
CSJ: 0923-23-032
END STA 18+77.00

PROJECT CR 508
CSJ: 0923-23-032
BEGIN STA 13+35.00

THE CONSTRUCTION WORK WAS PERFORMED IN ACCORDANCE WITH THE PLANS AND CONTRACT.

AREA ENGINEER _____ 20 _____


SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, SEPTEMBER 1, 2024 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRED CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, OCTOBER 23, 2023).

EQUATIONS: NONE
EXCEPTIONS: NONE
NO RAILROAD CROSSING - NONE ELIMINATED

9/19/2024

CONCURRENCE:

Signed by: *[Signature]*
MILLS COUNTY JUDGE



10/2/2024

SUBMITTED FOR LETTING:

[Signature]
CONSULTANT ENGINEER

10/2/2024

RECOMMENDED FOR LETTING:

DocuSigned by: *[Signature]*
77D14777834646F
DISTRICT DIRECTOR OF TRANSPORTATION
PLANNING AND DEVELOPMENT

10/3/2024

RECOMMENDED FOR LETTING:


DocuSigned by: *[Signature]*
58E2D01C26B344F...

PLOT SCALE: 1"=0.000' / ft. 9/26/2024 2:38:29 PM USER: wosthoff MODEL:TxDOT Design dwg://leg-pw-bentley.com/ieo-pw-01/Documents/2163D_TXDOT_88-9IDP5025/4-Design/Plan_Set/S01-General/CR508-TITL-SHT.dgn

INDEX OF SHEETS

SHEET NUMBER	DESCRIPTION
GENERAL	
1	TITLE SHEET
2	INDEX OF SHEETS
3	TYPICAL SECTIONS
4, 4A-4C	GENERAL NOTES
5, 5A	ESTIMATE AND QUANTITY SHEET
6	QUANTITY SUMMARIES
7	CONTROL INDEX SHEET
8	HORIZONTAL & VERTICAL CONTROL
TRAFFIC CONTROL PLAN	
9	TRAFFIC CONTROL PLAN
TRAFFIC CONTROL PLAN STANDARDS	
# 10-21	BC(1) - (12)-21
ROADWAY DETAILS	
22	HORIZONTAL ALIGNMENT DATA
23-24	PLAN AND PROFILE
25	RIPRAP LAYOUT
ROADWAY STANDARDS	
# 26	D&OM(1)-20
# 27	D&OM(2)-20
# 28	D&OM(3)-20
# 29	D&OM(5)-20
# 30	D&OM(VIA)-20
# 31	GF(31)-19
# 32	GF(31)TRTL2-19
# 33	SGT(10S)31-16
# 34	SGT(11S)31-18
# 35	SGT(12S)31-18
# 35A	BED-14
BRIDGE DETAILS	
36	DRAINAGE AREA MAP
37-38	HYDRAULIC DATA
39	CULVERT LAYOUT
## 40	BCS
BRIDGE STANDARDS	
## 41	NBIS
## 42-43	MC-8-13
## 44	MC-MD
## 45	PW
46-47	OMITTED
## 48-50	TYPE T223
## 51-52	CSAB
## 53-54	SRR
STORM SEWER POLLUTION PREVENTION PLAN	
55	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)
56-57	SW3P
58	SW3P LAYOUT
58A	TEMPORARY CROSSING DETAIL
STORM SEWER POLLUTION PREVENTION PLAN STANDARDS	
# 59	EC(1)-16
# 60	EC(2)-16

##THE STANDARD SHEETS SPECIFICALLY IDENTIFIED HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.




 _____ 9/26/2024
 SIGNATURE DATE




THE STANDARD SHEETS SPECIFICALLY IDENTIFIED HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.


 _____ 9/26/2024
 SIGNATURE DATE




NO.	DATE	REVISION	APPROV.
 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161			
 Texas Department of Transportation ©2024 Bryan District			
CR 508 AT DRAW INDEX OF SHEETS			
SHEET 1 OF 1			
FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	2

PLOT SCALE: 1/20,000' / ft. USER: wosthoff MODEL: TXDOT Design
 9/26/2024 2:39:26 PM
 pw://ea-pw.bentley.com/ea-pw-01/Documents/21630 TXDOT 88-9DP5025/4-Design/Plan Set/501-General/CR508-IN-01.dgn
 REV DATE: \$SAVED\$
 CSJ: 0923-23-032



EXISTING CR 508 APPROACH ROADWAY



PROPOSED CR 508 APPROACH ROADWAY

FROM STA 14+40.00 TO STA 15+76.00
FROM STA 16+36.14 TO STA 17+38.00

PROPOSED BRIDGE CLASS CULVERT STA 15+76.00 TO STA 16+36.14

TRANSITION FROM EXISTING WIDTH TO PROPOSED WIDTH:
STA 13+35.00 TO STA 14+40.00
STA 17+38.00 TO STA 18+77.00

ITEM	CODE	DESCRIPTION	UNIT	QUANTITY
247	7178	FL BS (CMP IN PLC) (TY A GR 4)(FINAL POS)	CY	271


FL BS (CMP IN PLC) (TY A GR 4)(FINAL POS) EST @ 50.0 CY/STA AVG (TOTAL 271 CY)



10/11/2024 *William Osthoff*

NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY
SUITE 3425 HOUSTON, TEXAS 77079
(832) 494-3800 FIRM REGISTRATION No. F-10161



**CR 508 AT
DRAW
TYPICAL SECTIONS**

SHEET 1 OF 1

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	3

PLOT SCALE: 1/20,000' / ft. USER: wosthoff MODEL: TXDOT Design
10/11/2024 9:13:36 AM pw://ea-pw.bentley.com/ea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/501-General/CR508-RTS-01.dgn
REV DATE: \$SAVED\$ CSJ: 0923-23-032

GENERAL NOTES

TEST TO BE IN ACCORDANCE WITH
TEXAS DEPARTMENT OF TRANSPORTATION
STANDARD TEST METHODS.

Item	Description	Soil Constants		
		Max LL.	Max. PI	Min. PI
132	Embankment (Final)(Ord Comp)(Ty C)	40	30	3
247	FI Bs (Cmp In Plc) (Ty A Gr 4)(Final Pos)			3

Job control samples for gradation and P.I. testing will be taken from the windrow after blade mixing.

TEXAS ONE CALL

Fiber optic cable systems, gas lines, underground power lines, water lines, sewer lines, and other various utilities may be buried within the project limits. Protection of these utility systems is of extreme importance since any break could disrupt service to users resulting in business interruption and loss of revenue and profits. The Contractor shall telephone Texas One Call at 1-800-344-8377 (a 24-hour number), to determine if utilities are buried anywhere on the project in accordance with all UNDERGROUND FACILITY DAMAGE PREVENTION AND SAFETY laws. This action, however, will in no way be interpreted as relief of responsibilities under the terms of the Contract as set out in the plans and specifications. Coordinate the repair of all damages caused by daily operations and have facilities restored to service in a timely manner as directed at no additional cost to TxDOT.

GENERAL

Contractor questions on this project are to be addressed to the following individual(s):

<u>Name</u>	<u>Email Address</u>
Chris Graf, P.E.	Chris.Graf@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individual(s).

Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:
<https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors>

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

The term "Article" or "Section" referred to hereon is defined in the forward of the Standard Specifications for Construction and Maintenance of Highways, Streets, And Bridges adopted by the Texas Department of Transportation November 2014.

The total disturbed area is shown on the SW3P sheet(s).

The Contractor will establish drainage in ditches before seeding or as directed by the Engineer.

Watering for dust control will be required as Directed by the Engineer and will be considered subsidiary to the various bid items.

ITEM 5 CONTROL OF WORK

The responsibility for the construction surveying on this contract will be in accordance with Section 5.9.1. "Method A".

The contractor will be required to place and maintain Blue Tops with wooden hubs for new flexible base.

Prior to contract letting, bidders may obtain a free computer diskette or a computerized transfer of files (from the Engineer's office) that contains the earthwork information. If copies of the actual cross-sections in addition to, or instead of, the diskette are requested, they will be available at the Engineers office for borrowing by copying companies for the purpose of making copies for the bidder at the bidder's expense.

Precast Alternate Proposals:

When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with "Standard Operating Procedure for Alternate Precast Proposal Submission" found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor."

ITEM 6 CONTROL OF MATERIALS

The Buy America Material Classification Sheet is located at the below link.

<https://www.txdot.gov/business/resources/materials/buy-america-material-classification-sheet.html> for clarification on material categorization.

ITEM 7 LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

ITEM 8 PROSECUTION AND PROGRESS

Working days will be computed and charged in accordance with Section 8.3.1.4. "Standard Workweek". Work will not be performed without time being charged unless otherwise exempted by the Section as defined above.

Work on Sunday(s) will not be allowed.

Working day charges will be in accordance with **SP 008---005. This delay is for the manufacturing of bridge beams.**

Work on each location must be considered substantially complete and open to full traffic before moving to the next location. Only one location will be under construction at a time and will be constructed in the following order:

- 1st 0923-23-032 CR 508
- 2nd 0923-23-033 CR 112
- 3rd 0923-25-027 CR 252

PROJECT SCHEDULES

Critical Path Method (CPM) scheduling will be required to be submitted and maintained monthly by the Contractor unless otherwise directed by the Engineer. (8.5.2.)

ITEM 9 MEASUREMENT AND PAYMENT

Monthly estimates will be computed from the 26th of the previous month through the 25th of the current month unless otherwise approved in writing by the Engineer.

ITEM 100 PREPARING RIGHT OF WAY

Trees that are to be trimmed and brush that is to be trimmed or removed that are not over the roadway or bridge(s), will be trimmed or removed in accordance with the Roadside Vegetation Management Manual to a height of fourteen feet. Remove limbs at the trunk with less than twenty-one feet of clearance above the

pavement or bridge(s). All trees and brush that are to be trimmed as directed by the Engineer, will not be paid for directly but will be considered subsidiary to Item 100 "Preparing Right Of Way".

See the "Environmental" section of the plans for additional information.

Perform "Preparing Right of Way" operations in the usual manner within the limits of the excavation and fill areas. Remove only such trees and brush as designated by the Engineer. Exercise care to avoid disturbing the native grasses unnecessarily during construction, removal of the existing bridge, and during the installation of the temporary fence.

Blade and windrow the top 8 inches of vegetative material. In the cut sections blade 2' past the ditch. In the fill sections, blade past the construction limits. Once ditch slopes and drainage have been established and approved, blade the windrow evenly over the disturbed area within the construction limits. This work is to be done as the job progresses and in conjunction with seeding. Work on the project may be suspended, if in the opinion of the Engineer, the Contractor does not make a good faith effort to stabilize loose material as the project progresses. Time will not be suspended. This work is subsidiary to Item 100.

The removal of existing and temporary fence will not be paid for directly but will be considered subsidiary to Item 100 "Preparing Right Of Way".

ITEM 164 SEEDING FOR EROSION CONTROL

The Contractor should anticipate two (2) separate mobilizations for seeding at each project location.

Blade and windrow outside construction limits, grass, weeds, and topsoil to grass roots depth.

ITEM 166 FERTILIZER

Fertilize all areas of project to be seeded.

Furnish and apply fertilizer with analysis of 20-10-10 at a rate of 300 bulk pounds per acre.

ITEM 247 FLEXIBLE BASE

A grader (a road grader, a blade, a maintainer, or a motor grader) will be used to process base unless otherwise approved by the Engineer.

Place new flexible base in lifts of approximately equal depth not to exceed 6 inches unless otherwise directed.

Aggregate Material Requirements

Property	Test Method	Grade 4 ²			
Sampling	Tex-400-A				
Master gradation sieve size (cumulative % retained)	Tex-110-E				
2-1/2"		0			
1-3/4"		0-10			
7/8"		10-35			
3/8"		30-65			
#4		45-75			
#40	65-90				
Liquid Limit, % Max	Tex-104-E	40			
Plasticity Index, Max ¹	Tex-106-E	10			
Plasticity index, Min ¹		3			
Wet ball mill, % Max	Tex-116-E	40			
Wet ball mill, % Max increase passing the #40 sieve		20			
Min compressive strength, psi	Tex-117-E				
lateral pressure 0 psi		20			
lateral pressure 3 psi		-			
lateral pressure 15 psi		175			

- Determine plastic index in accordance with [Tex-107-E](#) (linear shrinkage) when liquid limit is unattainable as defined in [Tex-104-E](#).
- Grade 4 may be further designated as Grade 4A, Grade 4B, etc.

ITEM 416 DRILLED SHAFT FOUNDATIONS

Casing is anticipated for the installation of the drilled shafts. Refer to **Section 416.3.3** for requirements.

In accordance with Section 416.5.2 core holes will be paid at \$200 each. 4 core holes total will be paid for this project.

ITEM 420 CONCRETE SUBSTRUCTURES

All Class C Concrete has been measured for plan quantity payment.

ITEM 421 HYDRAULIC CEMENT CONCRETE

Furnish dome lids with 4" x 8" cylinder test molds.

Strength testing equipment is not required for Contract controlling test.

ITEM 427 SURFACE FINISHES FOR CONCRETE

Surface Area II will receive a rub finish.

ITEM 432 RIPRAP

Locations and quantities may be varied as directed by the Engineer to accommodate field conditions.

Due to field conditions changing during the removal of the existing bridge and the construction of the new structure, riprap will be verified by the Engineer before the Contractor installs the riprap. Riprap located under the bridge will be installed before the bridge beams are installed.

Limit excavation to within 1' of riprap. If excavation exceeds these limits without the Engineer's approval, riprap will be extended to the limits of the disturbance. No additional compensation will be allowed for this work.

All riprap stone protection shall have toe walls in accordance to standard SRR.

ITEM 496 REMOVING STRUCTURES

Handle materials when removing structures in accordance with Item 6.

Exercise care to avoid disturbing the native grasses unnecessarily during removal of the existing bridge.

Notify TxDOT at least 60 days prior to any bridge removal. The Texas Department of State Health Services (DSHS) requires TxDOT to notify the DSHS of the bridge removal even if no asbestos is present. The notification form to retain/notify the DSHS licensed asbestos consultant must be postmarked at least 10 working days prior to the scheduled abatement and/or demolition. If the work does not happen on the notified date, then another 10 Working-Day, Prior-To-Work Notification will be required.

Provide a detailed plan for the removal of the existing structure to include the schedule of removal and list of all equipment to be used.

ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING

The Contractor will be required to keep all TCP devices clean. If notified by the Engineer to clean the TCP devices, the Contractor will have until the end of that daylight period to comply. Failure to comply will result in a suspension of all work until the TCP devices are clean. Time will not be suspended.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic

management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

All equipment operated by the Contractor on or within thirty feet (30') of the roadway will have a functioning flashing beacon mounted on it. Motor graders will have two standard orange warning flags mounted on them in addition to the flashing beacon.

The Contractor will be responsible for maintaining the edge of the roadway throughout the project in a traversable condition and/or as directed by the Engineer. Salvaged milling may be used as directed by the Engineer. This work will not be paid for directly and will be considered subsidiary to Item 502 "Barricades, Signs, and Traffic Handling".

All devices shown on the TCP Standards are required and considered subsidiary to Item 502 unless specifically outlined elsewhere in the plans.

All signs will be constructed in accordance with the details shown in the current Standard Highway Sign Designs for Texas manual.

ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

The Contractor should anticipate multiple mobilizations for the installation of BMP's on this project.

BMP's will not be installed until authorized by the Engineer.

The Engineer will determine actual time and placement locations of BMP's and temporary measures once construction has begun.

Stockpile sites may be cleared of cover vegetation, but the vegetation root system will not be destroyed.

ITEM 540 METAL BEAM GUARD FENCE

Metal beam guard fence will not be installed until the embankment and flex base is complete.

ITEM 552 WIRE FENCE

Wire fence quantities shown on the plans are approximate and may be adjusted in the field as approved by the Engineer.

Notify the Engineer three weeks prior to beginning any fence work.

All corner/pull posts, line posts, and braces, shall be steel pipe with a minimum of 2" Std. pipe (2.375" O.D., 0.154" wall thickness) with a 1 1/4" Std. pipe brace (1.660" O.D., 0.140" wall thickness), with a 2"x2"x1/4" angle, or other as approved by the Engineer.



CONTROLLING PROJECT ID 0923-23-032

DISTRICT Brownwood

COUNTY Mills, San Saba

HIGHWAY COUNTY ROAD 112, COUNTY ROAD 252, COUNTY ROAD 508

Estimate & Quantity Sheet

CONTROL SECTION JOB				0923-23-032		0923-23-033		0923-25-027		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00194464		A00199094		A00199095			
COUNTY				Mills		Mills		San Saba			
HIGHWAY				COUNTY ROAD 508		COUNTY ROAD 112		COUNTY ROAD 252			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	100-7002	PREPARING ROW	STA	6.000		6.000		3.900		15.900	
	110-7001	EXCAV (ROADWAY)	CY	614.000		250.000		260.000		1,124.000	
	110-7002	EXCAV (CHANNEL)	CY	183.000		58.000		105.000		346.000	
	132-7005	EMBANK (FNL)(OC)(TY C)	CY	35.000		71.000		110.000		216.000	
	164-7001	BROADCAST SEED (PERM_RURAL_SAND)	SY					526.000		526.000	
	164-7002	BROADCAST SEED (PERM_RURAL_CLAY)	SY	1,072.000		1,699.000				2,771.000	
	164-7005	BROADCAST SEED (TEMP_WARM)	SY	536.000		850.000		263.000		1,649.000	
	164-7006	BROADCAST SEED (TEMP_COOL)	SY	536.000		850.000		263.000		1,649.000	
	168-7001	VEGETATIVE WATERING	TGL	25.000		36.000		11.000		72.000	
	169-7022	SOIL RET BLKT(SL_STEEP_CLAY_LONG_SPRY)	SY	1,072.000		1,699.000				2,771.000	
	169-7024	SOIL RET BLKT(SL_STEEP_SAND_LONG_SPRY)	SY					526.000		526.000	
	247-7178	FL BS (CMP IN PLC)(TY A GR 4)(FNAL POS)	CY	271.000		276.000		185.000		732.000	
	400-7010	CEM STABIL BKFL	CY	80.000		41.000		43.000		164.000	
	402-7001	TRENCH EXCAVATION PROTECTION	LF	66.000						66.000	
	416-7004	DRILL SHAFT (24 IN)	LF					84.000		84.000	
	416-7005	DRILL SHAFT (30 IN)	LF			156.000				156.000	
	420-7012	CL C CONC (ABUT)	CY			27.200		19.600		46.800	
	422-7005	REINF CONC SLAB (BOX BEAM)	SF			1,701.000				1,701.000	
	422-7007	REINF CONC SLAB (SLAB BEAM)	SF					1,040.000		1,040.000	
	422-7020	SHEAR KEY	CY			8.600				8.600	
	425-7017	PRESTR CONC SLAB BEAM (5SB12)	LF					197.500		197.500	
	425-7026	PRESTR CONC BOX BEAM (4B20)	LF			258.000				258.000	
	425-7027	PRESTR CONC BOX BEAM (5B20)	LF			129.000				129.000	
	432-7041	RIPRAP (STONE PROTECTION)(12 IN)	CY			163.000		183.000		346.000	
	432-7043	RIPRAP (STONE PROTECTION)(18 IN)	CY	125.000						125.000	
	450-7008	RAIL (TY T223)	LF	233.000		162.000		104.000		499.000	
	454-7003	ARMOR JOINT (SEALED)	LF			50.000		44.000		94.000	
	462-7022	CONC BOX CULV (8 FT X 5 FT)	LF	180.000						180.000	
	466-7175	WINGWALL (PW - 1) (HW=5 FT)	EA	2.000						2.000	
	496-7009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.000		1.000		1.000		3.000	
	500-7001	MOBILIZATION	LS	0.300		0.410		0.290		1.000	
	502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4.000		5.000		4.000		13.000	
	506-7003	ROCK FILTER DAMS (INSTALL) (TY 3)	LF	80.000						80.000	
	506-7011	ROCK FILTER DAMS (REMOVE)	LF	80.000		80.000				160.000	
	506-7039	TEMP SEDMT CONT FENCE (INSTALL)	LF	900.000		1,220.000		812.000		2,932.000	

DISTRICT	COUNTY	CCSJ	SHEET
Brownwood	Mills	0923-23-032	5



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 0923-23-032

DISTRICT Brownwood

COUNTY Mills, San Saba

HIGHWAY COUNTY ROAD 112, COUNTY ROAD 252, COUNTY ROAD 508

CONTROL SECTION JOB				0923-23-032		0923-23-033		0923-25-027		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00194464		A00199094		A00199095			
COUNTY				Mills		Mills		San Saba			
HIGHWAY				COUNTY ROAD 508		COUNTY ROAD 112		COUNTY ROAD 252			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL	EST.	FINAL	EST.	FINAL		
	506-7041	TEMP SEDMT CONT FENCE (REMOVE)	LF	900.000		1,220.000		812.000		2,932.000	
	506-7048	ROCK FILTER DAMS (INSTALL) (TY 2) 6:1	LF			80.000				80.000	
	540-7002	MTL W-BEAM GD FEN (STEEL POST)	LF	275.000		450.000		188.000		913.000	
	540-7006	MTL BEAM GD FEN TRANS (TL2)	EA	4.000		4.000		4.000		12.000	
	544-7001	GUARDRAIL END TREATMENT (INSTALL)	EA	4.000		4.000		4.000		12.000	
	552-7001	WIRE FENCE (TY A)	LF	692.000						692.000	
	552-7003	WIRE FENCE (TY C)	LF					100.000		100.000	
	552-7004	WIRE FENCE (TY D)	LF					100.000		100.000	
	552-7010	WIRE FENCE (WATER GAP)	LF					40.000		40.000	
	644-7073	REMOVE SM RD SN SUP&AM	EA	1.000		1.000				2.000	
	658-7013	INSTL DEL ASSM (D-SW)SZ 1(BRF)CTB (BI)	EA	2.000		1.000		4.000		7.000	
	658-7016	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF1 (BI)	EA					20.000		20.000	
	658-7019	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)	EA	7.000		9.000				16.000	
	4003-7001	TIP TESTING(DRILL SHAFT)	EA			1.000		2.000		3.000	
	18	SAFETY CONTINGENCY: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000						1.000	
		EROSION CONTROL MAINTENANCE: CONTRACTOR FORCE ACCOUNT WORK (PART)	LS	1.000						1.000	



DISTRICT	COUNTY	CCSJ	SHEET
Brownwood	Mills	0923-23-032	5A

EROSION CONTROL SUMMARY

164 7002	164 7005	164 7006	SUBSIDIARY	168 7001	169 7022	506 7003	506 7011	506 7039	506 7041
BROADCAST SEED (PERM_RURAL_CL AY)	BROADCAST SEED (TEMP_WARM)	BROADCAST SEED (TEMP_COOL)	FERTILIZER	VEGETATIVE WATERING	SOIL RET BLKT(SL_STEEP_ CLAY_LONG_SPRY)	ROCK FILTER DAMS (INSTALL) (TY 3)	ROCK FILTER DAMS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
SY	SY	SY	TON	TGL	SY	LF	LF	LF	LF
1072	536	536	0.04	25	1072	80	80	900	900

ROADWAY SUMMARY

110 7001	110 7002	132 7005	247 7178	432 7043	540 7002	540 7006	544 7001	552 7001	658 7013	658 7019
EXCAVATION (ROADWAY)	EXCAVATION (CHANNEL)	EMBANK (FNL)(OC)(TY C)	FL BS (CMP IN PLC)(TY A GR 4)(FNAL POS	RIPRAP (STONE PROTECTION)(18 IN)	MTL W-BEAM GD FEN (STEEL POST)	MTL BEAM GD FEN TRANS (TL2)	GUARDRAIL END TREATMENT (INSTALL)	WIRE FENCE (TY A)	INSTL DEL ASSM (D-SW)SZ 1(BRF)CTB (BI)	INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)
CY	CY	CY	CY	CY	LF	EA	EA	LF	EA	EA
614	183	35	271	21	275	4	4	692	2	7



REMOVAL SUMMARY

100 7002	496 7009	644 7073
PREPARING ROW	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	REMOVE SM RD SN SUP&AM
STA	EA	EA
6	1	1

PLOT SCALE: 1/20,000' / ft. USER: wosthorf MODEL: TXDOT Design
 10/11/2024 4:33:20 PM pw://lea-pw.bentley.com/lea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/501-General/CR508-00-01.dgn
 REV DATE: \$SAVED\$ CSJ: 0923-23-032

NO.	DATE	REVISION	APPROV.
13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800		FIRM REGISTRATION No. F-10161	
Texas Department of Transportation ©2024 Bryan District			
CR 508 AT DRAW QUANTITY SUMMARIES			
SHEET 1 OF 1			
FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	6

CONTROL POINT NUMBER	SURFACE COORDINATES		GRID COORDINATES		LATITUDE (N)	LONGITUDE (W)	ELEVATION	DESCRIPTION
	NORTHING	EASTING	NORTHING	EASTING				
1003	10,528,103.17	2,818,152.93	10,526,839.95	2,817,814.80	31°32'14.90903"	-98°39'36.66711"	1351.90	3-1/4" TxDOT ALUMINUM DISK SET
1004	10,528,558.65	2,818,118.68	10,527,295.37	2,817,780.55	31°32'19.42096"	-98°39'36.98370"	1368.87	3-1/4" TxDOT ALUMINUM DISK SET
1005	10,527,684.63	2,818,128.14	10,526,421.46	2,817,790.01	31°32'10.77147"	-98°39'37.02622"	1364.47	3-1/4" TxDOT ALUMINUM DISK SET



PRINT DATE	REVISION DATE
5/22/2024	


I HEREBY CERTIFY THAT THE CONTROL INFORMATION SHOWN HEREON WAS ESTABLISHED UNDER MY DIRECT SUPERVISION AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Jeffrey L. Fansler
2024-05-22

JEFFREY L. FANSLER DATE
RPLS NO. 4348




6500 West Freeway, Suite 300
Fort Worth, Texas 76116
817.445.1016 | Fax 817.445.1017
www.cobbfendley.com
TBPELS Land Surveying Firm No. 10046700



CONTROL INDEX SHEET

NOTES:

- COORDINATES SHOWN HEREON ARE REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983, CENTRAL ZONE AND ARE ADJUSTED TO SURFACE USING THE TxDOT MILLS COUNTY SURFACE ADJUSTMENT FACTOR 1.000120 (GRID NORTHING & GRID EASTING * 1.000120 = SURFACE) ORIGIN 0, 0. VALUES WERE DERIVED UTILIZING THE TxDOT REALTIME REFERENCE NETWORK (VRS).
- VERTICAL IS BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) GEOID 12B. VALUES WERE DERIVED FROM UTILIZING THE TxDOT REALTIME REFERENCE NETWORK (VRS).
- FIELD SERVICES WERE PERFORMED IN AUGUST OF 2023




0 50 100
HORIZONTAL SCALE IN FEET

REV DATE: 5/22/2024
CS: 0923-23-032
FILENAME: F:\Projects\2022\0208 IEAV03_Brownwood_Bridges\400_CAD\402_Survey\DWG\Control Sheets\CR508\MRF092323032_CR508_Control_Sheets.dgn

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6		CR508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	7


REV DATE: 5/22/2024
 CS: 0923-23-032
 FILENAME: F:\Projects\2022\0208 IEAV03_Brownwood_Bridges\400_CAD\402_Survey\DCN\Control Sheets\CR508\MRF092323032_CR508_Control_Sheets.dgn



CP-1005
 GRID COORDINATES
 N: 10,526,421.46
 E: 2,817,790.01
 ELEV.: 1364.47

COORDINATE ZONE:
 TEXAS CENTRAL
 NAD83/2011 ADJUSTMENT
 LAT.: 31°32'10.77147"
 LONG.: -98°39'37.02622"


3-1/4" ALUMINUM DISK W/ REBAR SET FLUSH WITH NATURAL GROUND
 ON THE WEST SIDE OF CR 508 AND ±0.42 MILES NORTH OF THE INTERSECTION
 OF CR 508 & CR 521. ±3.0' EAST OF A WIRE FENCE. ±411.0' SOUTHWEST
 OF A WEIGHT LIMIT SIGN. ±36.0' WEST OF A WIRE FENCE
 ± 8.2 MILES NORTHWEST OF GOLDTHWAITE.



CP-1004
 GRID COORDINATES
 N: 10,527,295.37
 E: 2,817,780.55
 ELEV.: 1368.87

COORDINATE ZONE:
 TEXAS CENTRAL
 NAD83/2011 ADJUSTMENT
 LAT.: 31°32'19.42096"
 LONG.: -98°39'36.98370"


3-1/4" ALUMINUM DISK W/ REBAR SET FLUSH WITH NATURAL GROUND
 ON THE WEST SIDE OF CR 508 AND ±0.42 MILES NORTH OF THE INTERSECTION
 OF CR 508 & CR 521. ±297.0' NORTHEAST OF A WEIGHT LIMIT SIGN. ±352.0'
 NORTHWEST OF THE NORTHEAST CORNER OF THE WEST BRIDGE HEADWALL
 BRIDGE DECK. ±48.0' WEST OF A POWER POLE. ± 8.2 MILES NORTHWEST
 OF GOLDTHWAITE.



CP-1003
 GRID COORDINATES
 N: 10,526,839.95
 E: 2,817,814.80
 ELEV.: 1351.90

COORDINATE ZONE:
 TEXAS CENTRAL
 NAD83/2011 ADJUSTMENT
 LAT.: 31°32'14.90903"
 LONG.: -98°39'36.66711"

3-1/4" ALUMINUM DISK W/ REBAR SET FLUSH WITH NATURAL GROUND
 ON THE EAST SIDE OF CR 508 AND ±0.42 MILES NORTH OF THE INTERSECTION
 OF CR 508 & CR 521. ±42.0' SOUTHEAST OF THE SOUTHEAST CORNER OF THE
 WEST BRIDGE HEADWALL. ±37.0' SOUTHEAST OF THE SOUTHWEST CORNER OF
 OF THE EAST BRIDGE HEADWALL. ±12.0' NORTH OF A WEIGHT LIMIT SIGN.
 ± 8.2 MILES NORTHWEST OF GOLDTHWAITE.



I HEREBY CERTIFY THAT THE CONTROL INFORMATION
 SHOWN HEREON WAS ESTABLISHED UNDER MY
 DIRECT SUPERVISION AND IS TRUE AND CORRECT
 TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Jeffrey L. Fansler
 2024-05-22
 DATE

JEFFREY L. FANSLER
 RPLS NO. 4348







CobbFendley
 6500 West Freeway, Suite 300
 Fort Worth, Texas 76116
 817.445.1016 | Fax 817.445.1017
 www.cobbfendley.com
 TBPELS Land Surveying Firm No.
 10046700








CR 508
HORIZONTAL & VERTICAL
CONTROL

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6		CR508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	8



PLOT SCALE: 24000.0000' / ft. USER: wosthoff MODEL: TXDOT Design
 9/26/2024 4:32:47 PM pw:/fca-pw.bentley.com/idea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/502-TCP/CR508-TC-P1.dgn
 REV DATE: \$SAVED\$ CSJ: 0923-23-032

- ①  W16-8P 30"x18"
M4-9S 30"x24"
- ②  W16-8P 30"x18"
M4-9L 30"x24"
- ③  W16-8P 30"x18"
M4-9R 30"x24"
- ④  W16-8P 30"x18"
M4-8 24"x18"
- ⑤  M4-10L 48"x18"
R11-4 60"x30"
- ⑥  M4-10R 48"x18"
R11-4 60"x30"

- ⑦  CW20-3D 36"x36"
G20-6 48"x30"
- ⑧  CW20-3B 36"x36"
R11-2 48"x30"
- ⑨  CW20-3C 36"x36"
G20-2a 36"x18"
- ⑩  G20-2a 36"x18"
- ⑪  R20-3 48"x42"


TRAFFIC CONTROL SEQUENCE:
 THE CONTRACTOR SHALL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK TO THE AREA ENGINEER PRIOR TO THE BEGINNING OF CONSTRUCTION, WHICH GENERALLY CONFORMS TO THE FOLLOWING SEQUENCE:

1. INSTALL PROJECT LIMIT SIGNING AND BARRICADES AND SW3P PRIOR TO BEGINNING ANY OTHER WORK.
2. ALL ROAD CLOSURE SIGNING SHALL BE IN PLACE PRIOR TO ANY ACTIVITIES WHICH WILL PROHIBIT THROUGH TRAFFIC AND SHALL BE PLACED MORE THAN 24 HOURS PRIOR TO SUCH ACTIVITY.
3. COMPLETE THE CONSTRUCTION OF THE BRIDGE AND APPROACHES ACCORDING TO THE PLANS AND SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER.
4. THE ROADWAY SHALL BE OPEN TO THROUGH TRAFFIC AS SOON AS DETERMINED PRACTICAL BY THE ENGINEER.
5. COMPLETE ALL OTHER WORK AS DIRECTED BY THE ENGINEER.




GENERAL NOTES:
 SIGNS SHALL BE PLACED IN ACCORDANCE WITH THE BARRICADE AND CONSTRUCTION STANDARDS OR AS DIRECTED BY THE ENGINEER.
 OTHER SIGNS AS DETAILED IN THE BARRICADE AND CONSTRUCTION STANDARDS AND IN THE TMUTCD MAY BE USED AS REQUIRED BY THE ENGINEER IN ORDER TO PROVIDE FOR THE SAFE PASSAGE OF TRAFFIC THROUGH THE PROJECT. PAYMENT FOR ALL SUCH SIGNS, BARRICADES OR TRAFFIC CONTROL DEVICES SHALL BE CONSIDERED SUBSIDIARY TO ITEM 502 "BARRICADES, SIGNS AND TRAFFIC HANDLING".
 PROVIDE ACCESS TO AND FROM DRIVEWAYS AND ALL ADJACENT PROPERTY AT ALL TIMES.

N



LEGEND	
↓	SIGN
I	TY III BARRICADES

DETOUR LENGTH: 7.0 MILES
 ADT: <400



9/26/2024
William Osthoff

NO.	DATE	REVISION	APPROV.
IEA		13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800	FIRM REGISTRATION No. F-10161
		Texas Department of Transportation Bryan District ©2024	
CR 508 AT DRAW			
TRAFFIC CONTROL PLAN			
SHEET 1 OF 1			
FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	9

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
 FILE:

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:

1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12




**BARRICADE AND CONSTRUCTION
 GENERAL NOTES
 AND REQUIREMENTS**

BC (1) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	0923	SECT	23	JOB	032	HIGHWAY	CR 508
REVISIONS		DIST	COUNTY		SHEET NO.				
4-03	7-13	BWD	MILLS		10				
9-07	8-14								
5-10	5-21								


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Δ Spacing "x" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW25			50	400
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	55	500 ²
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			80	1000 ²
*			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

Δ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "x" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC (2) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BWD	MILLS	11	

DATE: FILE:

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) - 21

FILE:	bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS		0923	23	032	CR 508
9-07	8-14	DIST	COUNTY	SHEET NO.	
7-13	5-21	BWD	MILLS	12	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS



* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC (4) - 21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BWD	MILLS	13	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
□ See the CWZTCD for the type of sign substrate that can be used for each approved sign support.

BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0923	23	032	CR 508				
9-07	8-14	DIST	COUNTY	SHEET NO.					
7-13	5-21	BWD	MILLS	14					

DATE:
FILE:

WHEN NOT IN USE, REMOVE THE PCMS FROM THE RIGHT-OF-WAY OR PLACE THE PCMS BEHIND BARRIER OR GUARDRAIL WITH SIGN PANEL TURNED PARALLEL TO TRAFFIC

RECOMMENDED PHASES AND FORMATS FOR PCMS MESSAGES DURING ROADWORK ACTIVITIES

(The Engineer may approve other messages not specifically covered here.)

PORTABLE CHANGEABLE MESSAGE SIGNS

- The Engineer/Inspector shall approve all messages used on portable changeable message signs (PCMS).
- Messages on PCMS should contain no more than 8 words (about four to eight characters per word), not including simple words such as "TO," "FOR," "AT," etc.
- Messages should consist of a single phase, or two phases that alternate. Three-phase messages are not allowed. Each phase of the message should convey a single thought, and must be understood by itself.
- Use the word "EXIT" to refer to an exit ramp on a freeway; i.e., "EXIT CLOSED." Do not use the term "RAMP."
- Always use the route or interstate designation (IH, US, SH, FM) along with the number when referring to a roadway.
- When in use, the bottom of a stationary PCMS message panel should be a minimum 7 feet above the roadway, where possible.
- The message term "WEEKEND" should be used only if the work is to start on Saturday morning and end by Sunday evening at midnight. Actual days and hours of work should be displayed on the PCMS if work is to begin on Friday evening and/or continue into Monday morning.
- The Engineer/Inspector may select one of two options which are available for displaying a two-phase message on a PCMS. Each phase may be displayed for either four seconds each or for three seconds each.
- Do not "flash" messages or words included in a message. The message should be steady burn or continuous while displayed.
- Do not present redundant information on a two-phase message; i.e., keeping two lines of the message the same and changing the third line.
- Do not use the word "Danger" in message.
- Do not display the message "LANES SHIFT LEFT" or "LANES SHIFT RIGHT" on a PCMS. Drivers do not understand the message.
- Do not display messages that scroll horizontally or vertically across the face of the sign.
- The following table lists abbreviated words and two-word phrases that are acceptable for use on a PCMS. Both words in a phrase must be displayed together. Words or phrases not on this list should not be abbreviated, unless shown in the TMUTCD.
- PCMS character height should be at least 18 inches for trailer mounted units. They should be visible from at least 1/2 (.5) mile and the text should be legible from at least 600 feet at night and 800 feet in daylight. Truck mounted units must have a character height of 10 inches and must be legible from at least 400 feet.
- Each line of text should be centered on the message board rather than left or right justified.
- If disabled, the PCMS should default to an illegible display that will not alarm motorists and will only be used to alert workers that the PCMS has malfunctioned. A pattern such as a series of horizontal solid bars is appropriate.

Phase 1: Condition Lists

Road/Lane/Ramp Closure List

FREEWAY CLOSED X MILE
ROAD CLOSED AT SH XXX
ROAD CLSD AT FM XXXX
RIGHT X LANES CLOSED
CENTER LANE CLOSED
NIGHT LANE CLOSURES
VARIOUS LANES CLOSED
EXIT CLOSED
MALL DRIVEWAY CLOSED
XXXXXXXX BLVD CLOSED

Other Condition List

FRONTAGE ROAD CLOSED
SHOULDER CLOSED XXX FT
RIGHT LN CLOSED XXX FT
RIGHT X LANES OPEN
DAYTIME LANE CLOSURES
I-XX SOUTH EXIT CLOSED
EXIT XXX CLOSED X MILE
RIGHT LN TO BE CLOSED
X LANES CLOSED TUE - FRI

ROADWORK XXX FT
FLAGGER XXXX FT
RIGHT LN NARROWS XXXX FT
MERGING TRAFFIC XXXX FT
LOOSE GRAVEL XXXX FT
DETOUR X MILE
ROADWORK PAST SH XXXX
BUMP XXXX FT
TRAFFIC SIGNAL XXXX FT

ROAD REPAIRS XXXX FT
LANE NARROWS XXXX FT
TWO-WAY TRAFFIC XX MILE
CONST TRAFFIC XXX FT
UNEVEN LANES XXXX FT
ROUGH ROAD XXXX FT
ROADWORK NEXT FRI-SUN
US XXX EXIT X MILES
LANES SHIFT *

* LANES SHIFT in Phase 1 must be used with STAY IN LANE in Phase 2.

Phase 2: Possible Component Lists

Action to Take/Effect on Travel List

MERGE RIGHT
DETOUR NEXT X EXITS
USE EXIT XXX
STAY ON US XXX SOUTH
TRUCKS USE US XXX N
WATCH FOR TRUCKS
EXPECT DELAYS
REDUCE SPEED XXX FT
USE OTHER ROUTES
STAY IN LANE *

Location List

AT FM XXXX
BEFORE RAILROAD CROSSING
NEXT X MILES
PAST US XXX EXIT
XXXXXXXX TO XXXXXXX
US XXX TO FM XXXX

Warning List

SPEED LIMIT XX MPH
MAXIMUM SPEED XX MPH
MINIMUM SPEED XX MPH
ADVISORY SPEED XX MPH
RIGHT LANE EXIT
USE CAUTION
DRIVE SAFELY
DRIVE WITH CARE

** Advance Notice List

TUE-FRI XX AM - X PM
APR XX - XX X PM-X AM
BEGINS MONDAY
BEGINS MAY XX
MAY X-X XX PM - XX AM
NEXT FRI-SUN
XX AM TO XX PM
NEXT TUE AUG XX
TONIGHT XX PM - XX AM

** See Application Guidelines Note 6.

APPLICATION GUIDELINES

- Only 1 or 2 phases are to be used on a PCMS.
- The 1st phase (or both) should be selected from the "Road/Lane/Ramp Closure List" and the "Other Condition List".
- A 2nd phase can be selected from the "Action to Take/Effect on Travel, Location, General Warning, or Advance Notice Phase Lists".
- A Location Phase is necessary only if a distance or location is not included in the first phase selected.
- If two PCMS are used in sequence, they must be separated by a minimum of 1000 ft. Each PCMS shall be limited to two phases, and should be understandable by themselves.
- For advance notice, when the current date is within seven days of the actual work date, calendar days should be replaced with days of the week. Advance notification should typically be for no more than one week prior to the work.

WORDING ALTERNATIVES

- The words RIGHT, LEFT and ALL can be interchanged as appropriate.
- Roadway designations IH, US, SH, FM and LP can be interchanged as appropriate.
- EAST, WEST, NORTH and SOUTH (or abbreviations E, W, N and S) can be interchanged as appropriate.
- Highway names and numbers replaced as appropriate.
- ROAD, HIGHWAY and FREEWAY can be interchanged as needed.
- AHEAD may be used instead of distances if necessary.
- FT and MI, MILE and MILES interchanged as appropriate.
- AT, BEFORE and PAST interchanged as needed.
- Distances or AHEAD can be eliminated from the message if a location phase is used.

PCMS SIGNS WITHIN THE R.O.W. SHALL BE BEHIND GUARDRAIL OR CONCRETE BARRIER OR SHALL HAVE A MINIMUM OF FOUR (4) PLASTIC DRUMS PLACED PERPENDICULAR TO TRAFFIC ON THE UPSTREAM SIDE OF THE PCMS, WHEN EXPOSED TO ONE DIRECTION OF TRAFFIC. WHEN EXPOSED TO TWO WAY TRAFFIC, THE FOUR DRUMS SHOULD BE PLACED WITH ONE DRUM AT EACH OF THE FOUR CORNERS OF THE UNIT.

FULL MATRIX PCMS SIGNS

- When Full Matrix PCMS signs are used, the character height and legibility/visibility requirements shall be maintained as listed in Note 15 under "PORTABLE CHANGEABLE MESSAGE SIGNS" above.
- When symbol signs, such as the "Flagger Symbol" (CW20-7) are represented graphically on the Full Matrix PCMS sign and, with the approval of the Engineer, it shall maintain the legibility/visibility requirement listed above.
- When symbol signs are represented graphically on the Full Matrix PCMS, they shall only supplement the use of the static sign represented, and shall not substitute for, or replace that sign.
- A full matrix PCMS may be used to simulate a flashing arrow board provided it meets the visibility, flash rate and dimming requirements on BC(7), for the same size arrow.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

WORD OR PHRASE	ABBREVIATION	WORD OR PHRASE	ABBREVIATION
Access Road	ACCS RD	Major	MAJ
Alternate	ALT	Miles	MI
Avenue	AVE	Miles Per Hour	MPH
Best Route	BEST RTE	Minor	MNR
Boulevard	BLVD	Monday	MON
Bridge	BRDG	Normal	NORM
Canal	CANT	North	N
Center	CTR	Northbound	(route) N
Construction Ahead	CONST AHD	Parking	PKING
CROSSING	XING	Road	RD
Detour Route	DETOUR RTE	Right Lane	RT LN
Do Not	DONT	Saturday	SAT
East	E	Service Road	SERV RD
Eastbound	(route) E	Shoulder	SHLDR
Emergency	EMER	Slippery	SLIP
Emergency Vehicle	EMER VEH	South	S
Entrance, Enter	ENT	Southbound	(route) S
Express Lane	EXP LN	Speed	SPD
Expressway	EXPWY	Street	ST
XXXX Feet	XXXX FT	Sunday	SUN
Fog Ahead	FOG AHD	Telephone	PHONE
Freeway	FRWY, FWY	Temporary	TEMP
Freeway Blocked	FWY BLKD	Thursday	THURS
Friday	FRI	To Downtown	TO DWNTN
Hazardous Driving	HAZ DRIVING	Traffic	TRAF
Hazardous Material	HAZMAT	Travelers	TRVLR
High-Occupancy Vehicle	HOV	Tuesday	TUES
Highway	HWY	Time Minutes	TIME MIN
Hour(s)	HR, HRS	Upper Level	UPR LEVEL
Information	INFO	Vehicles (s)	VEH, VEHS
It Is	ITS	Warning	WARN
Junction	JCT	Wednesday	WED
Left	LFT	Weight Limit	WT LIMIT
Left Lane	LFT LN	West	W
Lane Closed	LN CLOSED	Westbound	(route) W
Lower Level	LWR LEVEL	Wet Pavement	WET PVMT
Maintenance	MAINT	Will Not	WONT

Roadway designation # IH-number, US-number, SH-number, FM-number




BARRICADE AND CONSTRUCTION PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

BC (6) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BWD	MILLS	15	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)


- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.




Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

DATE:
FILE:

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation
Traffic Safety Division Standard

BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
	0923	23	032	CR 508
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BWD	MILLS	16	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:


- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING



- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.

BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.




Each drum shall have a minimum of 2 orange and 2 white stripes using Type A or Type B retroreflective sheeting with the top stripe being orange.




This detail is not intended for fabrication. See note 3 and the CWZTCD list for providers of approved Detectable Pedestrian Barricades

DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign
(Maximum Sign Dimension)
Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer



12" x 24" Vertical Panel
mount with diagonals sloping down towards travel way

Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (8) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0923	23	032	CR 508				
4-03	8-14	DIST	COUNTY		SHEET NO.				
9-07	5-21	BWD	MILLS		17				
7-13									


DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
- LCDs may be used instead of a line of cones or drums.
- LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
- LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
- LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
- Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
- Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
- Water ballasted systems used as barriers shall not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
- When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
- Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
- Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
- Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
- The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths * *			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80	800'	880'	960'	80'	160'	

* * * Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) - 21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS		0923	23	032	CR 508				
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	BWD	MILLS		18				


DATE: FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL




TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES

Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.




PLAN VIEW

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION



PERSPECTIVE VIEW




PLAN VIEW

Increase number of plastic drums on the side of approaching traffic if the crown width makes it necessary. (minimum of 2 and maximum of 4 drums)

1. Where positive redirection capability is provided, drums may be omitted.
2. Plastic construction fencing may be used with drums for safety as required in the plans.
3. Vertical Panels on flexible support may be substituted for drums when the shoulder width is less than 4 feet.
4. When the shoulder width is greater than 12 feet, steady-burn lights may be omitted if drums are used.
5. Drums must extend the length of the culvert widening.

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (10) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
9-07 8-14	DIST	COUNTY	SHEET NO.	
7-13 5-21	BWD	MILLS	19	

DATE: FILE:

WORK ZONE PAVEMENT MARKINGS

GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet WZ(STPM).
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foil back) shall meet the requirements of DMS-8240.


MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 599.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE
TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER
TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
 - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
 - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line. Using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet WZ(STPM) for tab placement on new pavements. See Standard Sheet TCP(7-1) for tab placement on seal coat work.

RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:
 YELLOW - (two amber reflective surfaces with yellow body).
 WHITE - (one silver reflective surface with white body).

DEPARTMENTAL MATERIAL SPECIFICATIONS	
PAVEMENT MARKERS (REFLECTORIZED)	DMS-4200
TRAFFIC BUTTONS	DMS-4300
EPOXY AND ADHESIVES	DMS-6100
BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS	DMS-6130
PERMANENT PREFABRICATED PAVEMENT MARKINGS	DMS-8240
TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS	DMS-8241
TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS	DMS-8242

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

SHEET 11 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS


BC(11) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
	0923	23	032	CR 508
REVISIONS	DIST	COUNTY	SHEET NO.	
2-98 9-07 5-21	BWD	MILLS	20	
1-02 7-13				
11-02 8-14				

PAVEMENT MARKING PATTERNS




REFLECTORIZED PAVEMENT MARKINGS - PATTERN A




REFLECTORIZED PAVEMENT MARKINGS - PATTERN B

Pattern A is the TXDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS - PATTERN A




RAISED PAVEMENT MARKERS - PATTERN B

CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

EDGE & LANE LINES FOR DIVIDED HIGHWAY




REFLECTORIZED PAVEMENT MARKINGS

Prefabricated markings may be substituted for reflectORIZED pavement markings.




RAISED PAVEMENT MARKERS

LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS



REFLECTORIZED PAVEMENT MARKINGS


Prefabricated markings may be substituted for reflectORIZED pavement markings.






RAISED PAVEMENT MARKERS

TWO-WAY LEFT TURN LANE


STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS



SOLID LINES




BROKEN LINES



REMOVABLE MARKINGS WITH RAISED PAVEMENT MARKERS

If raised pavement markers are used to supplement REMOVABLE markings, the markers shall be applied to the top of the tape at the approximate mid length of tape used for broken lines or at 20 foot spacing for solid lines. This allows an easier removal of raised pavement markers and tape.



SHEET 12 OF 12



BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS

BC (12) - 21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 1998	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
1-97 9-07 5-21	DIST	COUNTY	SHEET NO.	
2-98 7-13	BWD	MILLS	21	
11-02 8-14				

Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:

Alignment Name: BL CR508
 Alignment Description:

Alignment Style: Alignment\Baseline

Station	Northing	Easting
---------	----------	---------


Element: Linear

POT	() 1000.000 R1	10527559.92	2818146.192
-----	-----------------	-------------	-------------

POT	() 2092.059 R1	10528651.92	2818134.827
-----	-----------------	-------------	-------------

Tangential Direction: N0.596°W

Tangential Length: 1092.059




5/31/2024

William Osthoff

NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY
 SUITE 3425 HOUSTON, TEXAS 77079
 (832) 494-3800 FIRM REGISTRATION No. F-10161




**CR 508 AT
 DRAW CREEK
 HORIZONTAL ALIGNMENT
 DATA**


SHEET 1 OF 1

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	22


PLOT SCALE: 120.0000' / ft. USER: wosthoff MODEL: TXDOT Design
 5/31/2024 7:45:52 PM pw://ea-pw.bentley.com/ea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/503-Roadway/CR508-RD-ALD01.dgn
 REV DATE: \$SAVED\$ CSJ: 0315-06-047



- NOTES:**
- SEE BRIDGE LAYOUT FOR BRIDGE TYPICAL SECTIONS.
 - STOCKPILE AND REUSE EXISTING TOPSOIL INSIDE RIGHT OF WAY.
 - EXISTING UTILITIES ARE BASED ON THE BEST AVAILABLE INFORMATION. CONTRACTOR TO FIELD VERIFY UTILITY LOCATIONS PRIOR TO BEGINNING CONSTRUCTION.
- * REMOVAL OF EXISTING FENCE IS SUBSIDIARY TO ITEM 100-7002 PREPARING ROW. QUANTITY IS FOR INFORMATION ONLY.



10/15/2024 *William Osthoff*



NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161



Texas Department of Transportation ©2024
Bryan District

**CR 508 AT DRAW
PLAN AND PROFILE**


SHEET 1 OF 2

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	23

PLOT SCALE: 600.00000083 ft./ft. MODEL: CR508-SHEET-01
 10/15/2024 3:42:45 PM USER: wosthoff
 pw://ea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-9DP5025/4-Design/Plan Set/503-Roadway/CR508-RPP-01.dgn
 REV DATE: \$SAVED\$
 CSJ: 0923-23-032



- NOTES:**
1. SEE BRIDGE LAYOUT FOR BRIDGE TYPICAL SECTIONS.
 2. STOCKPILE AND REUSE EXISTING TOPSOIL INSIDE RIGHT OF WAY.
 3. EXISTING UTILITIES ARE BASED ON THE BEST AVAILABLE INFORMATION. CONTRACTOR TO FIELD VERIFY UTILITY LOCATIONS PRIOR TO BEGINNING CONSTRUCTION.
- * REMOVAL OF EXISTING FENCE IS SUBSIDIARY TO ITEM 100-7002 PREPARING ROW. QUANTITY IS FOR INFORMATION ONLY.



10/11/2024 *William Osthoff*

1380																						1380			
1375																						1375			
1370																						1370			
1365																						1365			
1360																						1360			
1355																						1355			
1350																						1350			
1345																						1345			
1340																						1340			
1335																						1335			
	PROP ELEV																								
	EXIST ELEV																								
		1,352.89	1,352.90	1,353.55	1,353.54	1,354.21	1,354.20	1,355.00	1,354.90	1,355.81	1,355.69	1,356.62	1,356.55	1,357.43	1,357.40	1,358.31	1,358.23	1,359.37	1,361.07	1,362.84	1,364.77	1,366.67	1,368.55	1,370.35	1,371.92
		17+00				18+00				19+00				20+00											

NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161

Texas Department of Transportation ©2024 Bryan District


CR 508 AT DRAW PLAN AND PROFILE

SHEET 2 OF 2

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	24

PLOT SCALE: 600.0000083 ft / ft. MODEL: CR508-SHEET-02
 10/11/2024 3:24:40 PM USER: wosthoff
 pw://ea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-91DP5025/4-Design/Plan Set/503-Roadway/CR508-RPP-02.dgn
 REV DATE: \$SAVED\$
 CSJ: 0923-23-032


PLOT SCALE: 1/8" = 10' (1:80)
 10/11/2024 3:24:52 PM USER: wosthoff
 MODEL: BL_CR508 - Plan 1
 pw://iea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/503-Roadway/CR508-RD-RIPRAP.dgn
 REV DATE: \$SAVED\$
 CSJ: 0923-23-032



DRAW



- NOTES:
- RIPRAP LIMITS SHOWN ARE APPROXIMATE AND BASED ON BEST AVAILABLE INFORMATION. LIMITS, SHAPES AND GRADING MAY BE ADJUSTED TO FIT SITE CONDITIONS AS DIRECTED.
 - SEE SRR STANDARD FOR ADDITIONAL STONE RIPRAP DETAILS.



10/11/2024 *William Osthoff*

NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161

Texas Department of Transportation ©2024
 Bryan District

**CR 508 AT DRAW
 RIPRAP LAYOUT**

SHEET 1 OF 1

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	25

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES	
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRF = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back
						SHEETING Yellow, White or Red Type B or C reflective sheeting NOTE 1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.			
				SHEETING Yellow, White or Red Type B or C Reflective Sheeting		POST TYPE WC YFLX, WFLX WC YFLX, WFLX		MOUNT TYPE GND GND, SRF GND GND, SRF	

OBJECT MARKERS								D & OM DESCRIPTIVE CODES	
DEVICE	Type 1 (OM-1)	Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)	INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
		OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	
SHEETING Yellow-Type B _{FL} or C _{FL} Sheeting		SHEETING Yellow - Type B or C Sheeting			SHEETING Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			SHEETING Red -Type B _{FL} or C _{FL} Sheeting	
POST TYPE TWT		POST TYPE WC WC WFLX			POST TYPE TWT			POST TYPE TWT	
MOUNT TYPE WAS, WAP		MOUNT TYPE GND GND GND, SRF			MOUNT TYPE WAS, WAP			MOUNT TYPE WAS, WAP	

DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600

BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.
DEVICE 	DEVICE 	DEVICE 	SIZE (W x L)		MOUNTING HEIGHT		SIZE (W x L)		
SHEETING Yellow, White, Red NOTE 1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.			SIZE (W x L) 18" x 24" (Conventional) 24" x 30" (Conventional Oversize) 30" x 36" (Expressway) 36" x 48" (Freeway)		MOUNTING HEIGHT 4'-0" or 7'-0" 7'-0" Only		SIZE (W x L) 48" x 24" (Conventional) 60" x 30" (Expressway & Freeway)		
NOTE 1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			NOTE 1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).						

Texas Department of Transportation

DELINEATOR & OBJECT MARKER MATERIAL DESCRIPTION

D & OM(1)-20

FILE: dom1-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	BWD	MILLS	26	

20A

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS	
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT
GND	GND	SRF	WAS	WAP	GF 1
	EMBEDDED		STEEL	PLASTIC	GF 2
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.	NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.		NOTE 1. Install per manufacturer's recommendations.		

TYPE OF BARRIER MOUNTS	
GUARD FENCE ATTACHMENT	
GF 1	GF 2
CONCRETE TRAFFIC BARRIER (CTB)	
GENERAL NOTES 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.	

TYPES 1, 3, AND 4 OBJECT MARKERS AND CHEVRONS
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)

CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN
NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.

DELINEATORS AND TYPE 2 OBJECT MARKERS
See general notes 1, 2 and 3.

Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	BWD	MILLS	27	

20B


DATE:
 FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign




DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20

FILE: dom3-20.dgn	DW: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	BWD	MILLS	28	


TWO-WAY, TWO LANE ROADWAY WITH REDUCED WIDTH APPROACH RAIL



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


TWO-WAY, TWO LANE ROADWAY WITH METAL BEAM GUARD FENCE (MBGF)



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

TWO-WAY, TWO LANE ROADWAY BRIDGE WITH NO APPROACH RAIL



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



DELINEATOR & OBJECT MARKER PLACEMENT DETAILS








D & OM(5) - 20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CON: 0923	SECT: 23	JOB: 032	HIGHWAY: CR 508
7-20	DIST: BWD	COUNTY: MILLS	SHEET NO. 29	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



* Adjust to fit attenuator per manufacturer's recommendation, or as directed by the Engineer



OBJECT MARKERS SMALLER THAN 3 FT²




NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

NOTES



- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- Mounting should be flush with top of attenuator. Minimum size 96" x 24".






DATE:
FILE:

<p>DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</p> <p>D & OM(VIA) - 20</p>			
FILE: domvia20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT
© TXDOT December 1989	CONT: 0923	SECT: 23	JOB: 032
REVISIONS		HIGHWAY: CR 508	
4-92 8-04	DIST: BWD		COUNTY: MILLS
8-95 3-15			SHEET NO.: 30
4-98 7-20			
20G			

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 3/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.




- * POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.
- NOTE: TWO INSTALLATION OPTIONS.
1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
 2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.
- NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

		Design Division Standard	
<h2>METAL BEAM GUARD FENCE</h2> <h3>TL-3 MASH COMPLIANT</h3> <h3>GF(31)-19</h3>			
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS	0923	23	032
	DIST	COUNTY	SHEET NO.
	BWD	MILLS	31

DATE: FILE:

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TxDOT FOR ANY PURPOSE WHATSOEVER. TxDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: FILE:






- (5) 7/8" DIA. HEAVY HEX HEAD BOLTS (ASTM A325 OR A449)
- (10) 1 3/4" O.D. WASHER UNDER EACH HEX BOLT HEAD AND NUT.
- (5) 7/8" DIA. HEAVY HEX NUTS (ASTM A194 OR A563)

NOTE: HEAVY HEX BOLT LENGTH WILL VARY DEPENDING ON WIDTH CONCRETE RAIL, LEAVE 1" OF BOLT LENGTH PAST THE 7/8" HEX NUT. TRIM AS REQUIRED.

NOTE: CHAMFER REQUIRED ON CONCRETE RAILS THAT EXTEND BEYOND THE FACE OF GUARDRAIL TRANSITION.



- GENERAL NOTES**
- THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF TRANSITIONS SHALL BE AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. REFER TO GF(31) STANDARD SHEET.
 - RAIL ELEMENT SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS.
 - FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM REQUIRING CONSTRUCTION OF THE TRANSITION.
 - BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC160) AND NOT MORE THAN 1" BEYOND IT. TRIM BOLT LENGTH TO MEET REQUIRED LENGTH.
 - POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 - CROWN SHALL BE WIDENED TO ACCOMMODATE TRANSITIONS.
 - WHERE SOLID ROCK IS ENCOUNTERED, CONTACT THE DESIGN DIVISION FOR ADDITIONAL GUIDANCE. (512) 416-2678
 - UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TxDOT, MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210. ONLY PRODUCERS ON THE MPL CAN FURNISH COMPOSITE MATERIAL BLOCKS.
 - REFER TO GF(31) STANDARD SHEET & BRIDGE RAILING DETAILS FOR ADDITIONAL DETAILS.
 - FOR ROUND WOOD POSTS SYSTEMS, ALL ROUND WOOD POSTS SHALL BE 7 1/2" DIA. MINIMUM THROUGHOUT THE TRANSITION.




- (2) 5/8" BUTTON HEAD POST BOLTS & NUTS: (FBB04)
- (1) 5/8" FLAT WASHER: (FWC140) UNDER EACH NUT


- (1) 5/8" BUTTON HEAD POST BOLT & NUT: (FBB04)
- (1) 5/8" FLAT WASHER: (FWC140) UNDER EACH NUT

PLATE WASHER INSTRUCTIONS

BRIDGE APPROACH - UPSTREAM: THE SHORT RAIL LAPS OVER THE TERMINAL CONNECTOR. PLATE WASHERS ARE INSTALLED UNDER THE SPLICE NUTS AGAINST INSIDE OF CONNECTOR.
BRIDGE EXIT - DOWNSTREAM: THE TERMINAL CONNECTOR LAPS OVER THE NESTED RAIL. PLATE WASHERS ARE INSTALLED UNDER THE BOLT HEAD AGAINST OUTSIDE OF CONNECTOR.




SECTION A-A




SECTION B-B

NOTE: * "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.




WOOD BLOCK TO ROUND WOOD POST

NOTE: TOENAIL WITH ONE 16D GALV. NAIL TO PREVENT BLOCK ROTATION.



WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST


LOW-SPEED TRANSITION

**METAL BEAM GUARD FENCE
THRIE-BEAM TRANSITION
TL-2 MASH COMPLIANT
GF(31)TR TL2-19**

FILE: gf31tr+1219.dgn		DN: TxDOT	CK: KM	DW: VP	CK: CGL/AG
© TxDOT: NOVEMBER 2019		CONT	SECT	JOB	HIGHWAY
REVISIONS		0923	23	032	CR 508
		DIST	COUNTY	SHEET NO.	
		BWD	MILLS	32	

Texas Department of Transportation
Design Division Standard

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



- ### GENERAL NOTES
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: TRINITY HIGHWAY AT 1(888)323-6374, 2525 N. STEMMONS FREEWAY, DALLAS, TX 75207
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE; SoftStop END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL. PN: 620237B
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL AND REFER TO THE LATEST ROADWAY MGBF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IT IS ACCEPTABLE TO INSTALL THE SoftStop IMPACT HEAD PARALLEL TO THE GRADE LINE OR WITH AN UPWARD TILT.
 - DO NOT ATTACH THE SoftStop SYSTEM DIRECTLY TO A RIGID BARRIER.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE SoftStop SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRoACHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.



NOTE A THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 3-3/4" MIN. TO 4" MAX. ABOVE FINISHED GRADE.

NOTE B PART PN: 5852B RIGHT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING) PART PN: 5851B LEFT-SIDE (HIGH INTENSITY REFLECTIVE SHEETING)

NOTE C W-BEAM SPLICE LOCATED BETWEEN LINE POST (4) AND LINE POST (5) GUARDRAIL PANEL 25'-0" PN: 61G ANCHOR RAIL 25'-0" PN: 15215G LAP GUARDRAIL IN DIRECTION OF TRAFFIC FLOW.

PART	QTY	MAIN SYSTEM COMPONENTS
620237B	1	PRODUCT DESCRIPTION ASSEMBLY MANUAL (LATEST REV.)
15208A	1	SoftStop HEAD (SEE MANUAL FOR RIGHT-LEFT APPROACH)
15215G	1	SoftStop ANCHOR RAIL (12GA) WITH CUTOUT SLOTS
61G	1	SoftStop DOWNSTREAM W-BEAM RAIL (12GA) (25'-0")
15205A	1	POST #0 - ANCHOR POST (6'-5 3/8")
15203G	1	POST #1 - (SYTP) (4'-9 1/2")
15000G	1	POST #2 - (SYTP) (6'-0")
533G	6	POST #3 THRU #8 - I-BEAM (W6 x 8.5) (6'-0")
4076B	7	BLOCKOUT - WOOD (ROUTED) (6" x 8" x 14")
6777B	7	BLOCKOUT - COMPOSITE (4" x 7 1/2" x 14")
15204A	1	ANCHOR PADDL
15207G	1	ANCHOR KEEPER PLATE (24 GA)
15206G	1	ANCHOR PLATE WASHER (1/2" THICK)
15201G	2	ANCHOR POST ANGLE (10" LONG)
15202G	1	ANGLE STRUT

HARDWARE		
4902G	1	1" ROUND WASHER F436
3908G	1	1" HEAVY HEX NUT A563 GR.DH
3717G	2	3/4" x 2 1/2" HEX BOLT A325
3701G	4	3/4" ROUND WASHER F436
3704G	2	3/4" HEAVY HEX NUT A563 GR.DH
3360G	16	5/8" x 1 1/4" W-BEAM RAIL SPLICE BOLTS HGR
3340G	25	5/8" W-BEAM RAIL SPLICE NUTS HGR
3500G	7	5/8" x 10" HGR POST BOLT A307
3391G	1	5/8" x 1 3/4" HEX HD BOLT A325
4489G	1	5/8" x 9" HEX HD BOLT A325
4372G	4	5/8" WASHER F436
105285G	2	5/8" x 2 1/2" HEX HD BOLT GR-5
105286G	1	5/8" x 1 1/2" HEX HD BOLT GR-5
3240G	6	5/8" ROUND WASHER (WIDE)
3245G	3	5/8" HEX NUT A563 GR.DH
5852B	1	HIGH INTENSITY REFLECTIVE SHEETING - SEE NOTE:B




**TRINITY HIGHWAY
SOFTSTOP END TERMINAL
MASH - TL-3
SGT (10S) 31-16**

FILE: sgt10s3116		DNE: TxDOT		CK: KM		DWN: VP		CK: MB/VP	
© TxDOT: JULY 2016		CONT	SECT	JOB	JOB	CR	CR	CR	CR
		REVISIONS	0923	23	032				508
		DIST	COUNTY						SHEET NO.
		BWD	MILLS						33

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SoftStop END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.






DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




- NOTES:
- ITEM ② COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (9) THRU LINE POST (2).
 - DO NOT INSTALL A BLOCKOUT AT LINE POST (1).

NOTE: SECURE THE (TSS) PANEL TO OUTSIDE OF RAIL 2 WITH THE PANEL ARROWS POINTING TOWARDS THE HEAD.




- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
 - FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL. P/N MANMAX REV D (ECN 3516).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
 - COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
 - IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
 - MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
 - IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
 - THE SYSTEM IS SHOWN WITH 12'-6" MBSF PANELS, 25'-0" MBSF PANELS ARE ALSO ALLOWED.
 - A MINIMUM OF 12'-6" OF 12GA. MBSF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM#	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT.-GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	5/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	5/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev-(D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1



* TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
 ** ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

APPROACH GRADING AT GUARDRAIL END TREATMENTS

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Texas Department of Transportation Design Division Standard

MAX-TENSION END TERMINAL


MASH - TL-3

SGT (11S) 31-18

FILE: sg+11s3118.dgn	DN: TxDOT	CK: KM	DW: TxDOT	CK: CL
© TxDOT: FEBRUARY 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
DIST	COUNTY		SHEET NO.	
BWD	MILLS		34	

DATE:
FILE:



DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.




- * NOTES:**
- ITEM (M) COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (8) THRU LINE POST (3).
 - ITEM (P) WOOD BLOCKOUTS CAN BE USED AS ALTERNATE.

- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Go.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. * *
 * ITEM (P) 8" WOOD-BLOCKOUT
 * * ITEM (Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard

SINGLE GUARDRAIL TERMINAL

MSKT-MASH-TL-3




SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TxDOT	CK: KM	DW: VP	CK: CL
© TxDOT: APRIL 2018	CONT SECT	JOB	HIGHWAY	
REVISIONS	0923	23	032	CR 508
DIST	COUNTY		SHEET NO.	
BWD	MILLS		35	

DATE:
FILE:



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



GENERAL NOTES

1. For more detail: See GF(31), SGT()31, GF(31)TR, and GF(31)TL2 standard sheets.
2. Quantities of metal beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
3. Use average daily traffic (ADT) for the current year to determine MBGF length of need in accordance with the Roadway Design Manual unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-750 ADT) highways, use length determinations for the higher volume category.
4. MBGF may not be required to shield departure end of bridge unless other obstacles within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
5. Downstream anchor terminals (DAT) are only for downstream end anchorage use, outside the horizontal clearance area of opposing traffic.
6. Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. (This requires a minimum of three standard line posts plus the DAT terminal, See Detail A)
7. The crown shall be widened to accommodate MBGF. Typically the "front slope" break should be 2'-0" from the back of the MBGF post. This applies to new construction on new alignment or where existing roadway cross section is to be widened to increase roadway width. This does not apply to rehabilitation work where existing roadway crown width is to be retained (See Typical Cross Section at MBGF).
8. For restrictive bridge widths: The MBGF should be properly transitioned from the existing bridge rail to the adjoining MBGF (See MBGF Transition Standards). Metal beam guard fence at these bridge location(s) shall be flared at the rate of 25:1 or flatter, and be of the length necessary to locate the terminal end at the 2 ft. "maximum" offset from the shoulder edge in the approach direction.
9. Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
10. A minimum 25' length of MBGF will be required.



Note: All rail elements shall be lapped in the direction of adjacent traffic.

		Design Division Standard	
BRIDGE END DETAILS (METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS) BED-14			
FILE: bed14.dgn	DN: TxDOT	CK: AM	DW: BD/VP
© TxDOT: December 2011	CONTRACT NO. 0923	SECTION 23	JOB NO. 032
REVISIONS			HIGHWAY CR 508
REVISED APRIL 2014 SEE (MEMO 0414)	DIST. 23	COUNTY. MILLS	SHEET NO. 35A

HYDROLOGIC COMPUTATIONS

CR 508	
OMEGA EM REGRESSION EQUATIONS (Equation 4-12 and Table 4-4 of TxDOT HDM)	
CONTRIBUTING DRAINAGE AREA, (SQ.MI.)	24.43
MEAN ANNUAL PRECIPITATION (IN) (FIGURE 4-6)	31
MAIN CHANNEL SLOPE, (FT/FT)	0.0058
OMEGA EM (FIGURE 4-5)	-0.106
PEAK FLOWRATE (2-YR), (CFS)	1,005
PEAK FLOWRATE (5-YR), (CFS)	2,196
PEAK FLOWRATE (10-YR), (CFS)	3,169
PEAK FLOWRATE (25-YR), (CFS)	4,775
PEAK FLOWRATE (50-YR), (CFS)	6,221
PEAK FLOWRATE (100-YR), (CFS)	8,000

Regression equation

$$Q_2 = P^{1.398} S^{0.270} \times 10^{[0.776\Omega + 50.98 - 50.30A - 0.0058]}$$

$$Q_5 = P^{1.308} S^{0.372} \times 10^{[0.885\Omega + 16.62 - 15.32A - 0.0215]}$$

$$Q_{10} = P^{1.203} S^{0.403} \times 10^{[0.918\Omega + 13.62 - 11.97A - 0.0289]}$$

$$Q_{25} = P^{1.140} S^{0.446} \times 10^{[0.945\Omega + 11.79 - 9.819A - 0.0374]}$$





$$Q_{50} = P^{1.105} S^{0.476} \times 10^{[0.961\Omega + 11.17 - 8.997A - 0.0424]}$$

$$Q_{100} = P^{1.071} S^{0.507} \times 10^{[0.969\Omega + 10.82 - 8.448A - 0.0467]}$$

NOTES:


- DRAINAGE AREA DELINEATED USING 70CM RESOLUTION LIDAR DATA.
- DESIGN AND CHECK STORM EVENTS ARE 2-YR AND 100-YR.
- THE OFF-SYSTEM PROJECT DESIGN STORM WAS DETERMINED BASED ON FHWA POLICY 'SAME OR SLIGHTLY BETTER' THAN EXISTING.
- DISCHARGES WERE CALCULATED FOLLOWING THE OMEGA EM REGRESSION EQUATIONS AS PROVIDED IN TxDOT HYDRAULIC DESIGN MANUAL.
- NO HYDROLOGY CHECK IS REQUIRED IN ADDITION TO THE REGRESSION METHOD GIVEN NATURE OF CROSSING (OFF-SYSTEM) AND THE SIZE OF WATERSHED.
- THE SCS RESERVOIRS IDENTIFIED WITHIN THE WATERSHED WERE CONSIDERED TO BE FULL FOR HYDROLOGY CALCULATIONS OF OFF-SYSTEM CROSSING.
- THIS SITE IS NOT INCLUDED IN A FEMA FLOOD INSURANCE STUDY AND NO FLOODPLAINS HAVE BEEN IDENTIFIED.
- USACE HEC-RAS VERSION 6.4.1 UTILIZED FOR THE HYDRAULIC ANALYSIS.
- ALL ELEVATIONS BASED ON THE NAVD88 VERTICAL DATUM.
- THE DOWNSTREAM BOUNDARY CONDITION WAS ESTABLISHED USING NORMAL DEPTH WITH A DOWNSTREAM SLOPE OF 0.0059 FT/FT.
- AS SHOWN ON THE VELOCITY CURVE, INCREASE IN VELOCITY AT LOWER WATER SURFACE ELEVATION IS DUE TO THE IRREGULAR CHANNEL SHAPE AT BOUNDING CROSS-SECTION AND AT STRUCTURE.

LEGEND


-  DRAINAGE AREA ID
-  DRAINAGE AREA SQ. MI.
-  DRAINAGE AREA BOUNDARY
-  DRAINAGE FLOW ARROW

REFERENCES:

- TxDOT'S HYDRAULIC DESIGN MANUAL (SEPTEMBER 2019).
- MULTIPLE TOPOGRAPHIC DATA SOURCES:
BRAZOS RIVER BASIN LIDAR 2016-70CM RESOLUTION
HURRICANE LIDAR 2019-70CM RESOLUTION



CONVEYANCE CURVE




VELOCITY CURVE



NO.	DATE	REVISION	APPROV.



IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161



**CR 508
HYDRAULIC DATA SHEET
STA 16+06
CULVERT AT DRAW
DRAINAGE AREA MAP**

SHEET 1 OF 3

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	36




PLOT SCALE: 1.0453556 ft / ft. MODEL: BDR_PLAN_1
 5/29/2024 4:54:33 PM USER: spradhan
 pw://ea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-9DP5025/4-Design/Drainage/Hydraulic Data Sheets/CR 508/CR_508_HDS_01.dgn
 REV DATE: \$SAVED\$
 CSJ: 0315-06-047


HYDRAULIC COMPUTATIONS

HEC-RAS River: MULLIN CREEK Reach: MULLIN CREEK REA

Reach	River Sta	Profile	Plan	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
MULLIN CREEK REA	2280	2-YR	Pre-Project	1004.96	1350.95	1357.46		1357.68	0.002110	3.77	266.58	66.19	0.33
MULLIN CREEK REA	2280	2-YR	Post-Project	1004.96	1350.95	1357.46		1357.68	0.002111	3.77	266.56	66.18	0.33
MULLIN CREEK REA	2280	100-YR	Pre-Project	7999.72	1350.95	1363.38	1361.21	1364.90	0.005088	10.39	1114.66	283.53	0.59
MULLIN CREEK REA	2280	100-YR	Post-Project	7999.72	1350.95	1363.38	1361.21	1364.90	0.005088	10.39	1114.62	283.51	0.59
MULLIN CREEK REA	2054	2-YR	Pre-Project	1004.96	1351.86	1356.15	1355.49	1356.74	0.010312	6.20	162.10	63.72	0.69
MULLIN CREEK REA	2054	2-YR	Post-Project	1004.96	1351.86	1356.14	1355.49	1356.74	0.010350	6.21	161.90	63.69	0.69
MULLIN CREEK REA	2054	100-YR	Pre-Project	7999.72	1351.86	1361.68	1361.05	1363.43	0.008528	11.39	1001.68	246.06	0.74
MULLIN CREEK REA	2054	100-YR	Post-Project	7999.72	1351.86	1361.69	1361.05	1363.43	0.008521	11.38	1002.03	246.19	0.74
MULLIN CREEK REA	1804	2-YR	Pre-Project	1004.96	1349.37	1355.14	1353.21	1355.36	0.003008	3.77	266.45	87.73	0.38
MULLIN CREEK REA	1804	2-YR	Post-Project	1004.96	1349.37	1355.11	1353.21	1355.34	0.003079	3.80	264.20	87.40	0.39
MULLIN CREEK REA	1804	100-YR	Pre-Project	7999.72	1349.37	1360.43	1358.41	1361.67	0.005026	9.46	1155.46	316.36	0.58
MULLIN CREEK REA	1804	100-YR	Post-Project	7999.72	1349.37	1360.44	1358.41	1361.68	0.005015	9.45	1156.59	316.85	0.58
MULLIN CREEK REA	1552	2-YR	Pre-Project	1004.96	1349.78	1353.23	1352.90	1353.89	0.014362	6.50	154.54	72.85	0.79
MULLIN CREEK REA	1552	2-YR	Post-Project	1004.96	1349.78	1353.76	1352.90	1354.17	0.007473	5.18	193.86	78.61	0.58
MULLIN CREEK REA	1552	100-YR	Pre-Project	7999.72	1349.78	1358.60	1358.12	1360.06	0.007929	10.63	1217.16	353.71	0.71
MULLIN CREEK REA	1552	100-YR	Post-Project	7999.72	1349.78	1358.58	1358.12	1360.06	0.008012	10.67	1211.37	353.40	0.72
MULLIN CREEK REA	1332	2-YR	Pre-Project	1004.96	1347.28	1351.82	1350.32	1352.07	0.004464	4.02	250.10	100.66	0.45
MULLIN CREEK REA	1332	2-YR	Post-Project	1004.96	1347.28	1350.28	1350.28	1351.30	0.023444	8.09	124.27	65.61	1.00
MULLIN CREEK REA	1332	100-YR	Pre-Project	7999.72	1347.28	1358.24	1354.92	1358.75	0.002224	5.94	1750.14	388.56	0.38
MULLIN CREEK REA	1332	100-YR	Post-Project	7999.72	1347.28	1358.22	1354.91	1358.73	0.002246	5.96	1742.30	386.78	0.38
MULLIN CREEK REA	1312			Culvert									
MULLIN CREEK REA	1276	2-YR	Pre-Project	1004.96	1345.18	1350.39	1348.90	1350.65	0.003460	4.10	245.26	84.97	0.41
MULLIN CREEK REA	1276	2-YR	Post-Project	1004.96	1345.18	1350.39	1348.88	1350.67	0.003605	4.28	234.95	84.93	0.42
MULLIN CREEK REA	1276	100-YR	Pre-Project	7999.72	1345.18	1358.06	1354.07	1358.62	0.001926	6.49	1866.99	414.60	0.37
MULLIN CREEK REA	1276	100-YR	Post-Project	7999.72	1345.18	1358.06	1354.07	1358.62	0.001926	6.49	1866.99	414.60	0.37
MULLIN CREEK REA	1089	2-YR	Pre-Project	1004.96	1344.60	1350.12	1347.38	1350.24	0.001126	2.70	371.85	96.13	0.24
MULLIN CREEK REA	1089	2-YR	Post-Project	1004.96	1344.60	1350.12	1347.38	1350.24	0.001126	2.70	371.85	96.13	0.24
MULLIN CREEK REA	1089	100-YR	Pre-Project	7999.72	1344.60	1357.80	1352.38	1358.27	0.001410	5.76	1890.10	885.91	0.32
MULLIN CREEK REA	1089	100-YR	Post-Project	7999.72	1344.60	1357.80	1352.38	1358.27	0.001410	5.76	1890.10	885.91	0.32
MULLIN CREEK REA	867	2-YR	Pre-Project	1004.96	1342.92	1349.83	1346.20	1349.98	0.001129	3.14	319.97	64.46	0.25
MULLIN CREEK REA	867	2-YR	Post-Project	1004.96	1342.92	1349.83	1346.20	1349.98	0.001129	3.14	319.97	64.46	0.25
MULLIN CREEK REA	867	100-YR	Pre-Project	7999.72	1342.92	1356.90	1353.00	1357.81	0.002679	8.10	1372.66	761.57	0.44
MULLIN CREEK REA	867	100-YR	Post-Project	7999.72	1342.92	1356.90	1353.00	1357.81	0.002679	8.10	1372.66	761.57	0.44
MULLIN CREEK REA	648	2-YR	Pre-Project	1004.96	1343.74	1348.99	1347.42	1349.45	0.006739	5.48	183.43	62.09	0.56
MULLIN CREEK REA	648	2-YR	Post-Project	1004.96	1343.74	1348.99	1347.42	1349.45	0.006739	5.48	183.43	62.09	0.56
MULLIN CREEK REA	648	100-YR	Pre-Project	7999.72	1343.74	1356.23	1354.01	1357.13	0.003731	8.21	1400.88	618.55	0.50
MULLIN CREEK REA	648	100-YR	Post-Project	7999.72	1343.74	1356.23	1354.01	1357.13	0.003731	8.21	1400.88	618.55	0.50



EXISTING STREAM CROSS-SECTION @ STRUCTURE



PROPOSED STREAM CROSS-SECTION @ STRUCTURE

NOTES:

- DESIGN AND CHECK STORM EVENTS ARE 2-YR AND 100-YR.
- THE OFF-SYSTEM PROJECT DESIGN STORM WAS DETERMINED BASED ON FHWA 'SAME OR SLIGHTLY BETTER' THAN EXISTING.
- DISCHARGES WERE CALCULATED FOLLOWING THE OMEGA EM REGRESSION EQUATIONS AS PROVIDED IN TxDOT HYDRAULIC DESIGN MANUAL.
- THIS SITE IS NOT INCLUDED IN A FEMA FLOOD INSURANCE STUDY AND NO FLOODPLAINS HAVE BEEN IDENTIFIED.
- USACE HEC-RAS VERSION 6.4.1 UTILIZED FOR THE HYDRAULIC ANALYSIS.
- ALL ELEVATIONS BASED ON THE NAVD88 VERTICAL DATUM.
- THE DOWNSTREAM BOUNDARY CONDITION WAS ESTABLISHED USING NORMAL DEPTH WITH A DOWNSTREAM SLOPE OF 0.0059 FT/FT
- THE MODEL CONVERGENCE (PROPOSED WSE = EXISTING WSE) IS ACHIEVED AT RS 2280.
- BASED ON THE WSE DATA, NO ADVERSE IMPACTS ARE OBSERVED DUE TO THE PROPOSED IMPROVEMENTS.


REFERENCES:

- TxDOT'S HYDRAULIC DESIGN MANUAL (SEPTEMBER 2019).
- MULTIPLE TOPOGRAPHIC DATA SOURCES:
BRAZOS RIVER BASIN LIDAR 2016-70CM RESOLUTION
HURRICANE LIDAR 2019-70CM RESOLUTION



NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161




CR 508 HYDRAULIC DATA SHEET STA 16+06 CULVERT AT DRAW

SHEET 2 OF 3

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	37

PLOT SCALE: 1.0453556 ft / ft. MODEL: BDR PLAN 1
 5/29/2024 5:04:16 PM USER: spradhian
 pw://ea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-9DP5025/4-Design/Drainage/Hydraulic Data Sheets/CR 508/CR_508_HDS_02.dgn
 REV DATE: \$SAVED\$
 CSI: 0315-06-047



STREAM PROFILE

PRE-PROJECT CONDITIONS - 2YR CULVERT OUTPUT

Plan: Pre-Project MULLIN CREEK MULLIN CREEK REA RS: 1312 Culv Group: Culvert #1

Q Culv Group (cfs)	947.32	Culv Full Len (ft)	
# Barrels	5	Culv Vel US (ft/s)	8.48
Q Barrel (cfs)	189.46	Culv Vel DS (ft/s)	9.97
E.G. US. (ft)	1352.07	Culv Inv El Up (ft)	1347.96
W.S. US. (ft)	1351.82	Culv Inv El Dn (ft)	1347.80
E.G. DS (ft)	1350.65	Culv Frctn Ls (ft)	0.07
W.S. DS (ft)	1350.39	Culv Exit Loss (ft)	0.59
Delta EG (ft)	1.41	Culv Entr Loss (ft)	0.75
Delta WS (ft)	1.42	Q Weir (cfs)	57.64
E.G. IC (ft)	1352.07	Weir Sta Lft (ft)	812.00
E.G. OC (ft)	1351.87	Weir Sta Rgt (ft)	898.29
Culvert Control	Inlet	Weir Submerg	0.00
Culv WS Inlet (ft)	1350.19	Weir Max Depth (ft)	0.87
Culv WS Outlet (ft)	1349.70	Weir Avg Depth (ft)	0.37
Culv Nml Depth (ft)	1.49	Weir Flow Area (sq ft)	31.67
Culv Crt Depth (ft)	2.23	Min El Weir Flow (ft)	1351.20

POST-PROJECT CONDITIONS - 2YR CULVERT OUTPUT

Plan: Post-Project MULLIN CREEK MULLIN CREEK REA RS: 1312 Culv Group: Culvert #1

Q Culv Group (cfs)	1004.96	Culv Full Len (ft)	1.68
# Barrels	6	Culv Vel US (ft/s)	4.45
Q Barrel (cfs)	167.49	Culv Vel DS (ft/s)	4.19
E.G. US. (ft)	1350.73	Culv Inv El Up (ft)	1345.66
W.S. US. (ft)	1350.28	Culv Inv El Dn (ft)	1345.37
E.G. DS (ft)	1350.67	Culv Frctn Ls (ft)	0.00
W.S. DS (ft)	1350.39	Culv Exit Loss (ft)	0.00
Delta EG (ft)	0.06	Culv Entr Loss (ft)	0.06
Delta WS (ft)	0.10	Q Weir (cfs)	
E.G. IC (ft)	1349.92	Weir Sta Lft (ft)	
E.G. OC (ft)	1350.73	Weir Sta Rgt (ft)	
Culvert Control	Outlet	Weir Submerg	
Culv WS Inlet (ft)	1350.36	Weir Max Depth (ft)	
Culv WS Outlet (ft)	1350.37	Weir Avg Depth (ft)	
Culv Nml Depth (ft)	1.58	Weir Flow Area (sq ft)	
Culv Crt Depth (ft)	2.39	Min El Weir Flow (ft)	1351.60

NOTES:

- DESIGN AND CHECK STORM EVENTS ARE 2-YR AND 100-YR.
- USACE HEC-RAS VERSION 6.4.1 UTILIZED FOR THE HYDRAULIC ANALYSIS.
- ALL ELEVATIONS BASED ON THE NAVD88 VERTICAL DATUM.
- THE DOWNSTREAM BOUNDARY CONDITION WAS ESTABLISHED USING NORMAL DEPTH WITH A DOWNSTREAM SLOPE OF 0.0059 FT/FT

PRE-PROJECT CONDITIONS - 100YR CULVERT OUTPUT

Plan: Pre-Project MULLIN CREEK MULLIN CREEK REA RS: 1312 Culv Group: Culvert #1

Q Culv Group (cfs)	565.27	Culv Full Len (ft)	18.00
# Barrels	5	Culv Vel US (ft/s)	3.77
Q Barrel (cfs)	113.05	Culv Vel DS (ft/s)	3.77
E.G. US. (ft)	1358.75	Culv Inv El Up (ft)	1347.96
W.S. US. (ft)	1358.24	Culv Inv El Dn (ft)	1347.80
E.G. DS (ft)	1358.62	Culv Frctn Ls (ft)	0.01
W.S. DS (ft)	1358.06	Culv Exit Loss (ft)	0.00
Delta EG (ft)	0.12	Culv Entr Loss (ft)	0.11
Delta WS (ft)	0.18	Q Weir (cfs)	7434.45
E.G. IC (ft)	1358.69	Weir Sta Lft (ft)	717.33
E.G. OC (ft)	1358.75	Weir Sta Rgt (ft)	1120.33
Culvert Control	Outlet	Weir Submerg	0.89
Culv WS Inlet (ft)	1350.96	Weir Max Depth (ft)	7.56
Culv WS Outlet (ft)	1350.80	Weir Avg Depth (ft)	3.99
Culv Nml Depth (ft)		Weir Flow Area (sq ft)	1609.92
Culv Crt Depth (ft)	1.58	Min El Weir Flow (ft)	1351.20

POST-PROJECT CONDITIONS - 100YR CULVERT OUTPUT


Plan: Post-Project MULLIN CREEK MULLIN CREEK REA RS: 1312 Culv Group: Culvert #1

Q Culv Group (cfs)	1212.96	Culv Full Len (ft)	30.00
# Barrels	6	Culv Vel US (ft/s)	5.05
Q Barrel (cfs)	202.16	Culv Vel DS (ft/s)	5.05
E.G. US. (ft)	1358.73	Culv Inv El Up (ft)	1345.66
W.S. US. (ft)	1358.22	Culv Inv El Dn (ft)	1345.37
E.G. DS (ft)	1358.62	Culv Frctn Ls (ft)	0.03
W.S. DS (ft)	1358.06	Culv Exit Loss (ft)	0.00
Delta EG (ft)	0.11	Culv Entr Loss (ft)	0.08
Delta WS (ft)	0.16	Q Weir (cfs)	6786.77
E.G. IC (ft)	1358.68	Weir Sta Lft (ft)	717.37
E.G. OC (ft)	1358.73	Weir Sta Rgt (ft)	1120.23
Culvert Control	Outlet	Weir Submerg	0.89
Culv WS Inlet (ft)	1350.66	Weir Max Depth (ft)	7.15
Culv WS Outlet (ft)	1350.37	Weir Avg Depth (ft)	3.73
Culv Nml Depth (ft)		Weir Flow Area (sq ft)	1501.94
Culv Crt Depth (ft)	2.71	Min El Weir Flow (ft)	1351.60



NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161



CR 508 HYDRAULIC DATA SHEET STA 16+06 CULVERT AT DRAW



SHEET 3 OF 3

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	38

PLOT SCALE: 1.0453556 ft / ft. MODEL: BDR_PLAN_1
 5/29/2024 5:07:10 PM USER: spradhan
 pw://ea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-9DP5025/4-Design/Drainage/Hydraulic Data Sheets/CR 508/CR_508_HDS_03.dgn
 REV DATE: \$SAVED\$
 CSI: 0315-06-047

CK: RP
DW: FP
CK: WW
DM: RP

ITEM	DESCRIPTION	UNIT	QUANTITY
400 7010	CEM STABIL BKFL	CY	80
402 7001	TRENCH EXCAVATION PROTECTION	LF	66
432 7043	RIPRAP(STONE PROTECTION)(18 IN)	CY	104
450 7008	RAIL (TY T223)	LF	233
462 7022	CONC BOX CULV (8 FT X 5 FT)	LF	180
466 7175	WINGWALL (PW - 1) (HW = 5 FT)	EA	2
496 7009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1




- Notes:
1. No precast allowed
 2. Top slab shall be class S

DESIGN SPEED: MEETS OR EXCEEDS EXISTING
 ADT (2019): 50
 ADT (2038): 50
 FUNCTION CLASS: RURAL LOCAL
 EXISTING NBI: 231670AA0508001
 PROPOSED NBI: 23167AA0508002



10/11/2024



Station	Notes	Hydraulic Data	Station
1370			1370
1360			1360
1350			1350
1340			1340
1330			1330
1320			1320
1310			1310
1300			1300



HYDRAULIC DATA

Q (2) (EXIST)	= 1,004.96 cfs
V (2) (EXIST)	= 9.97 fps
WSE (2) (EXIST)	= 1,351.82 ft
Q (100) (EXIST)	= 7,999.72 cfs
V (100) (EXIST)	= 3.34 fps
WSE (100) (EXIST)	= 1,359.62 ft
Q (2) (PROP)	= 1,004.96 cfs
V (2) (PROP)	= 4.19 fps
WSE (2) (PROP)	= 1,350.28 ft
Q (100) (PROP)	= 7,999.72 cfs
V (100) (PROP)	= 4.62 fps
WSE (100) (PROP)	= 1,359.61 ft

NO.	DATE	REVISION	APPROV.



**BRIDGE CLASS
 CULVERT LAYOUT
 CR 508 STA 16+06.07**

SHEET 1 OF 1

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	39

PLOT SCALE: 0.08333333 ft / in
 10/11/2024 9:23:27 AM
 USER: fasket MODEL: 508 BR PLN
 pw://iea-pw.bentley.com/iea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/507-Bridge/57-CR-508/Archive/508_BR_BCL01.dgn
 REV DATE: \$SAVED\$
 CSJ: 0923-23-032 FILENAME:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2024 9:32:21 AM
 FILE: \\ieo-pw_bentley.com\ieo-pw-01\Documents\2163D TxDOT 88-91DP5025\4-Design\Plan Set\S07-Br Idge\S7-CR-508\CD-BCS-20.dgn

Culvert Station and/or Creek Name followed by applicable end (Lt, Rt or Both)	Description of Box Culvert No. Spans ~ Span X Height	Max Fill Height (Ft)	Applicable Box Culvert Standard (4)	Applicable Wingwall or End Treatment Standard	Skew Angle (0°, 15°, 30° or 45°)	Side Slope or Channel Slope Ratio (SL:1)	T Culvert Top Slab Thickness (In)	U Culvert Wall Thickness (In)	C Estimated Curb Height (Ft)	Hw (1) Height of Wingwall (Ft)	A Curb to End of Wingwall (Ft)	B O set of End of Wingwall (Ft)	Lw Length of Longest Wingwall (Ft)	Ltw Culvert Toewall Length (Ft)	Atw Anchor Toewall Length (Ft)	Riprap Apron (CY)	Class "C" Conc (Curb) (CY) (2)	Class "C" Conc (Wingwall) (CY) (3)	Total Wingwall Area (SF)
CR 508 AT DRAW CREEK (BOTH)	6 ~ 8' X5'	0'	MC-8-13	PW-1	30	3:1	8"	7"	0.500	6.167	N/A	N/A	21.362	60.141	N/A	0.0	2.2	42.2	526

NOTES:

Skew = 0° on SW-0, FW-0, SETB-CD, SETB-SW-0, and SETB-FW-0 standard sheets; 30° maximum for safety end treatment

- SL:1 = Horizontal : 1 Vertical
- Side slope at culvert for arched or straight wingwalls.
 - Channel slope for parallel wingwalls.
 - Slope must be 3:1 or steeper for safety end treatments.

T = Box culvert top slab thickness. Dimension can be found on the applicable box culvert standard sheet.

U = Box culvert wall thickness. Dimension can be found on the applicable box culvert standard sheet.

C = Curb height

See applicable wing or end treatment standard sheets for calculations of Hw, A, B, Lw, Ltw, Atw, and Total Wingwall Area.

Hw = Height of wingwall

A = Distance from face of curb to end of wingwall (not applicable to parallel or straight wingwalls)

B = O set of end of wingwall (not applicable to parallel or straight wingwalls)

Lw = Length of longest wingwall.

Ltw = Length of culvert toewall (not applicable when using riprap apron)

Atw = Length of anchor toewall (applicable to safety end treatment only)
 Total Wingwall Area = Wingwall area in sq. ft. for two wingwalls (one structure end) if Lt or Rt.
 Area for four wingwalls (two structure ends) if Both.

- Round the wall heights shown to the nearest foot for bidding purposes.
- Concrete volume shown is for box culvert curb only. For curbs using the Box Culvert Rail Mounting Details (RAC) standard sheet quantities shown must be increased by a factor of 2.25. If Class S concrete is required for the top slab of the culvert, also provide Class S concrete for the curb. Curb concrete is considered part of the Box Culvert for payment.
- Concrete volume shown is total of wings, footings, culvert toewall (if any), anchor toewalls (if any) and wingwall toewalls. Riprap aprons, culverts, and curb quantities are not included.
- Regardless of the type of culvert shown on this sheet, the Contractor has the option of furnishing cast-in-place or precast culverts unless otherwise shown elsewhere on the plans. If the Contractor elects to provide culverts of a different type than those shown on this sheet, it is the Contractor's responsibility to make the necessary adjustments to the dimensions and quantities shown.






10/4/2024




				Bridge Division Standard
BOX CULVERT SUPPLEMENT WINGS AND END TREATMENTS				
BCS				
FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CR: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
DIST	COUNTY	SHEET NO.		
BWD	MILLS	40		

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE:
FILE:



BRIDGE SIGN LOCATIONS



BRIDGE CLASS CULVERT SIGN PLACEMENT



SHEETING REQUIREMENTS

Usage	Color	Sign Face Material
Background	White	Type B or C Sheeting
Letters and Symbols	Black	Type B or C Sheeting

- ① Bridge identification sign location
- ② Alternate sign placement location for exterior concrete beams.
- ③ If adjacent bridges are less than 2 feet apart, these signs may be omitted.
- ④ 1/4" Diameter stainless steel expansion anchor with hex nut, washer, and spring-lock washer.

SIGN NOTES:

Standard sign designs can be found in the Standard Highway Sign Designs for Texas (SHSD).

Use the Clearview Alphabet CV-2W for the letters and symbols.

MATERIAL NOTES:

Provide lateral spacing between letters and numerals conforming with the SHSD, and any approved changes thereto. Provide a balanced appearance when spacing is not shown.

Provide aluminum sign blanks with a minimum thickness of 0.080" that meet the requirements of DMS-7110.

Provide sign face materials that meet the requirements of DMS-8300 and the sheeting requirements shown in the table.

Provide 1/4" diameter stainless steel expansion anchors with one hex head nut, one flat washer, and one helical spring-lock washer each.

Use torque controlled mechanical expansion anchors that are approved for use in cracked concrete by the International Code Council, Evaluation Service (ICC-ES). Provide anchor products that have a designated ICC-ES Evaluation Report number. The approval status must be maintained on the ICC-ES website under Division 031600 for Concrete Anchors.

Unless otherwise approved by the Engineer: do not use adhesive anchors; do not use expansion anchors that are not included in the ICC-ES approval list; and do not use expansion anchors that are only approved for use in uncracked concrete.

Use anchors manufactured with stainless steel expansion wedges. Anchors manufactured with carbon steel expansion wedges are not allowed. Anchor bodies can be either zinc-plated carbon steel or stainless steel. For application in marine environments, provide both stainless steel anchor bodies and expansion wedges.

GENERAL NOTES:

Prior to hole drilling, locate rebar to ensure clearing of existing reinforcement and/or strands.

Prior to installation, obtain approval of sign locations from the Engineer. Avoid placement of sign over travel lanes and pedestrian walkways. Submit proposed installation method to Engineer prior to beginning work. Install anchors as shown on plans and in accordance with the anchor manufacturer's published installation instructions.

Do not install anchors sections of members under tension.

For new construction, the signs and anchors are subsidiary to the bridge. For installations on existing structures, the signs and anchors are paid under Item 442, "Metal for Structures." Each sign weighs 28 lbs.




**NBIS
BRIDGE IDENTIFICATION
SIGN STANDARD**


NBIS

FILE:	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT	
©TxDOT	October 2024	CONT	SECT	JOB	HIGHWAY
	REVISIONS	0923	23	032	CR 508
		DIST	COUNTY	SHEET NO.	
		BWD	MILLS	41	


DATE: 3/22/2024 12:25:08 PM
 FILE: \\ieo-pw-bentley.com:ieo-pw-01\Documents\2163D TXDOT 88-91DP5025\4-Design\Plan Set\S07-BrIDGE-STANDARD-CD-MC813-20.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TYPICAL SECTION




PART PLANS



SECTION THRU CURB

TABLE OF BAR DIMENSIONS		
H	"X"	"Y"
3'-0"	3'-6 1/2"	5'-1"
4'-0"	4'-6 1/2"	5'-1"
5'-0"	5'-6 1/2"	5'-1"
6'-0"	6'-6 1/2"	5'-1"
7'-0"	7'-6 1/2"	5'-1"
8'-0"	8'-6 1/2"	5'-1"



- ① 0" Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0", refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Rail Anchorage Curb (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- ② For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade. Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- ③ For curbs less than 1'-0" high, tilt Bars K or reduce bar height as necessary to maintain cover. For curbs less than 3" high, Bars K may be omitted.
- ④ 1'-0" typical. 2'-3" when the Rail Anchorage Curb (RAC) standard sheet is referred to elsewhere in the plans.

The Contractor may replace Bars B, C, D, E, F1, F2, M, Y, and/or Z with deformed welded wire reinforcement (WWR) meeting the requirements of ASTM A1064. The area of required reinforcement may be reduced by the ratio of 60 ksi / 70 ksi. Spacing of WWR is limited to 4" Min and 18" Max. When required, provide lap splices in the WWR of the same length required for the equivalent bar size, rounded up for wire sizes between conventional bar sizes. The lap length required for WWR is never less than the lap length required for uncoated #4 bars.

Example conversion: Replacing No. 6 Gr 60 at 6" Spacing with WWR
 Required WWR = (0.44 sq. in. per 0.5 ft.) x (60 ksi / 70 ksi) = 0.755 sq. in. per ft.
 If D30.6 wire is used to meet the 0.755 sq. in. per ft. requirement in this example, the required spacing = (0.306 sq. in.) / (0.755 sq. in. per ft.) x (12 in. per ft.) = 4.86" Max spacing. Required lap length for the provided D30.6 wire is 2'-1" (the same minimum lap length required for uncoated #5 bars, as listed under MATERIAL NOTES).

CONSTRUCTION NOTES:
 Do not use permanent forms.
 Chamfer the bottom edge of the top slab 3" at the entrance.
 Optionally, raise construction joints shown at the flow line by a maximum of 6". If this option is taken, Bars M may be cut off or raised, Bars C and D may be reversed, and Bars Y and Z may be reversed.

MATERIAL NOTES:
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel if required elsewhere in the plans.
 Provide Class C concrete (f'c = 3,600 psi) for culvert barrel and curb, with the following exceptions: provide Class S concrete (f'c = 4,000 psi) for top slabs of:
 • culverts with overlay,
 • culverts with 1-to-2 course surface treatment, or
 • culverts with the top slab as the final riding surface.
 Provide bar laps, where required, as follows:
 • Uncoated or galvanized ~ #4 = 1'-8" Min
 • Uncoated or galvanized ~ #5 = 2'-1" Min
 • Uncoated or galvanized ~ #6 = 2'-6" Min

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications for the range of fill heights shown.
 See the Multiple Box Culverts Cast-In-Place Miscellaneous Detail (MC-MD) standard sheet for details pertaining to skewed ends, angle sections, and lengthening.

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2

Texas Department of Transportation
 Bridge Division Standard


**MULTIPLE BOX CULVERTS
 CAST-IN-PLACE
 8'-0" SPAN
 0' TO 13' FILL
 MC-8-13**

FILE:	DN: TBE	CK: BMP	DW: TXDOT	CK: TXDOT
©TXDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
DIST	COUNTY		SHEET NO.	
BWD	MILLS		42	

DATE: 3/22/2024 12:25:09 PM
 FILE: \\leo-pw_bent ley.com:leo-pw-01\Documents\2163D TXDOT 88-91DP5025\4-Design\Plan Set\507-Br\Ige\7-Standard\CRS08\BRIDGE-STANDARDS\CD-MC813-20.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


NUMBER OF SPANS	SECTION DIMENSIONS				BILLS OF REINFORCING STEEL (For Box Length = 40 feet)																																QUANTITIES												
					Bars B				Bars C & D				Bars E				Bars F1 ~ #4			Bars F2 ~ #4			Bars M ~ #4			Bars Y & Z ~ #4				Bars H 4 ~ #4		Bars K		Per Foot of Barrel		Curb		Total											
	S	H	T	U	No.	Size	Spa	Length	Wt	No.	Size	Spa	Bars C		Bars D		No.	Size	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Length	Wt	No.	Spa	Bars Y		Bars Z		Length	Wt	No.	Wt	Conc (CY)	Ref (Lb)	Conc (CY)	Ref (Lb)	Conc (CY)	Ref (Lb)
													Length	Wt	Length	Wt																				Length	Wt	Length	Wt										
2	8'-0"	3'-0"	8"	7"	162	#6	6"	17'-6"	4,258	108	#6	9"	8'-8"	1,406	8'-2"	1,325	162	#6	6"	12'-9"	3,102	12	18"	39'-9"	319	56	18"	39'-9"	1,487	108	9"	3'-0"	216	54	9"	4'-7"	165	7'-3"	262	17'-6"	47	38	106	1.071	313.5	1.3	153	44.2	12,693
3	8'-0"	3'-0"	8"	7"	162	#6	6"	26'-1"	6,347	108	#6	9"	8'-8"	1,406	8'-2"	1,325	162	#6	6"	21'-4"	5,191	18	18"	39'-9"	478	80	18"	39'-9"	2,124	108	9"	3'-0"	216	108	9"	4'-7"	331	7'-3"	523	26'-1"	70	56	156	1.560	448.5	1.9	226	64.3	18,167
4	8'-0"	3'-0"	8"	7"	162	#6	6"	34'-8"	8,435	108	#6	9"	8'-8"	1,406	8'-2"	1,325	162	#6	6"	29'-11"	7,279	24	18"	39'-9"	637	104	18"	39'-9"	2,762	108	9"	3'-0"	216	162	9"	4'-7"	496	7'-3"	785	34'-8"	93	72	200	2.048	583.5	2.6	293	84.5	23,634
5	8'-0"	3'-0"	8"	7"	162	#6	6"	43'-3"	10,524	108	#6	9"	8'-8"	1,406	8'-2"	1,325	162	#6	6"	38'-6"	9,368	30	18"	39'-9"	797	128	18"	39'-9"	3,399	108	9"	3'-0"	216	216	9"	4'-7"	661	7'-3"	1,046	43'-3"	116	90	251	2.537	718.6	3.2	367	104.7	29,109
6	8'-0"	3'-0"	8"	7"	162	#6	6"	51'-10"	12,612	108	#6	9"	8'-8"	1,406	8'-2"	1,325	162	#6	6"	47'-1"	11,457	36	18"	39'-9"	956	152	18"	39'-9"	4,036	108	9"	3'-0"	216	270	9"	4'-7"	827	7'-3"	1,308	51'-10"	138	106	295	3.026	853.6	3.8	433	124.9	34,576
2	8'-0"	4'-0"	8"	7"	162	#6	6"	17'-6"	4,258	108	#6	9"	9'-8"	1,568	8'-2"	1,325	162	#6	6"	12'-9"	3,102	12	18"	39'-9"	319	56	18"	39'-9"	1,487	108	9"	4'-0"	289	54	9"	4'-7"	165	9'-3"	334	17'-6"	47	38	106	1.136	321.2	1.3	153	46.8	13,000
3	8'-0"	4'-0"	8"	7"	162	#6	6"	26'-1"	6,347	108	#6	9"	9'-8"	1,568	8'-2"	1,325	162	#6	6"	21'-4"	5,191	18	18"	39'-9"	478	80	18"	39'-9"	2,124	108	9"	4'-0"	289	108	9"	4'-7"	331	9'-3"	667	26'-1"	70	56	156	1.646	458.0	1.9	226	67.8	18,546
4	8'-0"	4'-0"	8"	7"	162	#6	6"	34'-8"	8,435	108	#6	9"	9'-8"	1,568	8'-2"	1,325	162	#6	6"	29'-11"	7,279	24	18"	39'-9"	637	104	18"	39'-9"	2,762	108	9"	4'-0"	289	162	9"	4'-7"	496	9'-3"	1,001	34'-8"	93	72	200	2.156	594.8	2.6	293	88.8	24,085
5	8'-0"	4'-0"	8"	7"	162	#6	6"	43'-3"	10,524	108	#6	9"	9'-8"	1,568	8'-2"	1,325	162	#6	6"	38'-6"	9,368	30	18"	39'-9"	797	128	18"	39'-9"	3,399	108	9"	4'-0"	289	216	9"	4'-7"	661	9'-3"	1,335	43'-3"	116	90	251	2.667	731.7	3.2	367	109.9	29,633
6	8'-0"	4'-0"	8"	7"	162	#6	6"	51'-10"	12,612	108	#6	9"	9'-8"	1,568	8'-2"	1,325	162	#6	6"	47'-1"	11,457	36	18"	39'-9"	956	152	18"	39'-9"	4,036	108	9"	4'-0"	289	270	9"	4'-7"	827	9'-3"	1,668	51'-10"	138	106	295	3.177	868.5	3.8	433	130.9	35,171
2	8'-0"	5'-0"	8"	7"	162	#6	6"	17'-6"	4,258	108	#6	9"	10'-8"	1,730	8'-2"	1,325	162	#6	6"	12'-9"	3,102	12	18"	39'-9"	319	62	18"	39'-9"	1,646	108	9"	5'-0"	361	54	9"	4'-7"	165	11'-3"	406	17'-6"	47	38	106	1.201	332.8	1.3	153	49.4	13,465
3	8'-0"	5'-0"	8"	7"	162	#6	6"	26'-1"	6,347	108	#6	9"	10'-8"	1,730	8'-2"	1,325	162	#6	6"	21'-4"	5,191	18	18"	39'-9"	478	88	18"	39'-9"	2,337	108	9"	5'-0"	361	108	9"	4'-7"	331	11'-3"	812	26'-1"	70	56	156	1.733	472.8	1.9	226	71.3	19,138
4	8'-0"	5'-0"	8"	7"	162	#6	6"	34'-8"	8,435	108	#6	9"	10'-8"	1,730	8'-2"	1,325	162	#6	6"	29'-11"	7,279	24	18"	39'-9"	637	114	18"	39'-9"	3,027	108	9"	5'-0"	361	162	9"	4'-7"	496	11'-3"	1,217	34'-8"	93	72	200	2.264	612.7	2.6	293	93.1	24,800
5	8'-0"	5'-0"	8"	7"	162	#6	6"	43'-3"	10,524	108	#6	9"	10'-8"	1,730	8'-2"	1,325	162	#6	6"	38'-6"	9,368	30	18"	39'-9"	797	140	18"	39'-9"	3,717	108	9"	5'-0"	361	216	9"	4'-7"	661	11'-3"	1,623	43'-3"	116	90	251	2.796	752.7	3.2	367	115.1	30,473
6	8'-0"	5'-0"	8"	7"	162	#6	6"	51'-10"	12,612	108	#6	9"	10'-8"	1,730	8'-2"	1,325	162	#6	6"	47'-1"	11,457	36	18"	39'-9"	956	166	18"	39'-9"	4,408	108	9"	5'-0"	361	270	9"	4'-7"	827	11'-3"	2,029	51'-10"	138	106	295	3.328	892.6	3.8	433	137.0	36,138
2	8'-0"	6'-0"	8"	7"	162	#6	6"	17'-6"	4,258	108	#6	9"	11'-8"	1,893	8'-2"	1,325	162	#6	6"	12'-9"	3,102	12	18"	39'-9"	319	68	18"	39'-9"	1,806	108	9"	6'-0"	433	54	9"	4'-7"	165	13'-3"	478	17'-6"	47	38	106	1.265	344.5	1.3	153	51.9	13,932
3	8'-0"	6'-0"	8"	7"	162	#6	6"	26'-1"	6,347	108	#6	9"	11'-8"	1,893	8'-2"	1,325	162	#6	6"	21'-4"	5,191	18	18"	39'-9"	478	96	18"	39'-9"	2,549	108	9"	6'-0"	433	108	9"	4'-7"	331	13'-3"	956	26'-1"	70	56	156	1.819	487.6	1.9	226	74.7	19,729
4	8'-0"	6'-0"	8"	7"	162	#6	6"	34'-8"	8,435	108	#6	9"	11'-8"	1,893	8'-2"	1,325	162	#6	6"	29'-11"	7,279	24	18"	39'-9"	637	124	18"	39'-9"	3,293	108	9"	6'-0"	433	162	9"	4'-7"	496	13'-3"	1,434	34'-8"	93	72	200	2.372	630.6	2.6	293	97.5	25,518
5	8'-0"	6'-0"	8"	7"	162	#6	6"	43'-3"	10,524	108	#6	9"	11'-8"	1,893	8'-2"	1,325	162	#6	6"	38'-6"	9,368	30	18"	39'-9"	797	152	18"	39'-9"	4,036	108	9"	6'-0"	433	216	9"	4'-7"	661	13'-3"	1,912	43'-3"	116	90	251	2.926	773.7	3.2	367	120.3	31,316
6	8'-0"	6'-0"	8"	7"	162	#6	6"	51'-10"	12,612	108	#6	9"	11'-8"	1,893	8'-2"	1,325	162	#6	6"	47'-1"	11,457	36	18"	39'-9"	956	180	18"	39'-9"	4,780	108	9"	6'-0"	433	270	9"	4'-7"	827	13'-3"	2,390	51'-10"	138	106	295	3.479	916.8	3.8	433	143.0	37,106
2	8'-0"	7'-0"	8"	7"	162	#6	6"	17'-6"	4,258	108	#6	9"	12'-8"	2,055	8'-2"	1,325	162	#6	6"	12'-9"	3,102	12	18"	39'-9"	319	68	18"	39'-9"	1,806	108	9"	7'-0"	505	54	9"	4'-7"	165	15'-3"	550	17'-6"	47	38	106	1.330	352.1	1.3	153	54.5	14,238
3	8'-0"	7'-0"	8"	7"	162	#6	6"	26'-1"	6,347	108	#6	9"	12'-8"	2,055	8'-2"	1,325	162	#6	6"	21'-4"	5,191	18	18"	39'-9"	478	96	18"	39'-9"	2,549	108	9"	7'-0"	505	108	9"	4'-7"	331	15'-3"	1,100	26'-1"	70	56	156	1.905	497.0	1.9	226	78.1	20,107
4	8'-0"	7'-0"	8"	7"	162	#6	6"	34'-8"	8,435	108	#6	9"	12'-8"	2,055	8'-2"	1,325	162	#6	6"	29'-11"	7,279	24	18"	39'-9"	637	124	18"	39'-9"	3,293	108	9"	7'-0"	505	162	9"	4'-7"	496	15'-3"	1,650	34'-8"	93	72	200	2.480	641.9	2.6	293	101.8	25,968
5	8'-0"	7'-0"	8"	7"	162	#6	6"	43'-3"	10,524	108	#6	9"	12'-8"	2,055	8'-2"	1,325	162	#6	6"	38'-6"	9,368	30	18"	39'-9"	797	152	18"	39'-9"	4,036	108	9"	7'-0"	505	216	9"	4'-7"	661	15'-3"	2,200	43'-3"	116	90	251	3.056	786.8	3.2	367	125.5	31,838
6	8'-0"	7'-0"	8"	7"	162	#6	6"	51'-10"	12,612	108	#6	9"	12'-8"	2,055	8'-2"	1,325	162	#6	6"	47'-1"	11,457	36	18"	39'-9"	956	180	18"	39'-9"	4,780	108	9"	7'-0"	505	270	9"	4'-7"	827	15'-3"	2,750	51'-10"	138	106	295	3.631	931.7	3.8	433	149.1	37,700
2	8'-0"	8'-0"	8"	7"	162	#6	6"	17'-6"	4,258	108	#6	9"	13'-8"	2,217	8'-2"	1,325	162	#6	6"	12'-9"	3,102	12	18"	39'-9"	319	74	18"	39'-9"	1,965	108	9"	8'-0"	577	54	9"	4'-7"	165	17'-3"	622	17'-6"	47	38	106	1.395	363.8	1.3	153	57.1	14,703
3	8'-0"	8'-0"	8"	7"	162	#6	6"	26'-1"	6,347	108	#6	9"	13'-8"	2,217	8'-2"	1,325	162	#6	6"	21'-4"	5,191	18	18"	39'-9"	478	104	18"	39'-9"	2,762	108	9"	8'-0"	577	108	9"	4'-7"	331	17'-3"	1,244	26'-1"	70	56	156	1.992	511.8	1.9	226	81.6	20,698
4	8'-0"	8'-0"	8"	7"	162	#6	6"	34'-8"	8,435	108	#6	9"	13'-8"	2,217	8'-2"	1,325	162	#6	6"	29'-11"	7,279	24	18"	39'-9"	637	134	18"	39'-9"	3,558	108	9"	8'-0"	577	162	9"	4'-7"	496	17'-3"	1,867	34'-8"	93	72	200	2.588	659.8	2.6	29		

3/22/2024 12:25:14 PM
 DATE: 3/22/2024 12:25:14 PM
 FILE: \\leo-pw-bentley.com:leo-pw-01\Documents\2163D.TXDOT.88-91DP5025\4-Design\Plan Set\507-BrIDGE-STANDARDS\CD-MC-MD-20.dgn
 The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PLAN OF SKEWED ENDS ~ FROM 0° TO 15°


PLAN OF ANGLE SECTION ~ FROM 0° TO 15°



PLAN OF ANGLE SECTION ~ OVER 15° TO 30°




PLAN OF ANGLE SECTION ~ OVER 30° TO 45°




PLAN OF SKEWED ENDS ~ OVER 15° TO 30°

- ① For skewed box culverts with less than 2'-0" of fill, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension.
 For non-skewed box culverts with less than 2'-0" of fill and for skewed or non-skewed culverts with a fill depth of 2'-0" or greater, break back the top slab to provide a 1'-10" minimum lap of the existing longitudinal bars with the longitudinal bars in the extension. Alternatively, if the box is non-skewed, embed #6 anchor bars with a Type III, Class C, D, E, or F anchor adhesive into the existing walls, top and bottom slab at 1'-6" center-to-center spacing. Minimum embedment depth is 8". Anchor adhesive chosen must be able to achieve a basic bond strength in tension, N_{ba} , of 26.4 kips. Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing." Test adhesive anchors in accordance with Item 450.3.3, "Tests." Test 3 anchors per 100 anchors installed.
 Break back wings and apron as necessary to install the extension. Clean and extend the exposed wingwall and apron reinforcing into the extension. When lengthening existing box culverts with dimensions different than current standard dimensions, form horizontal and vertical transitions as directed by the Engineer. Match bottom slabs to maintain an uninterrupted flow line. Field bend existing and new reinforcing into transitions and maintain specified cover requirements. For top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface, adjust the "H" dimension to provide a smooth riding surface.
- ② When the spacing between Bars B or Bars E becomes less than half of the normal spacing, cut bars to avoid conflict.
- ③ The length of Bars B and Bars E will vary in the skewed end sections.
- ④ $[0.5 \times \text{overall width}] \times [\text{tangent of the skew angle}]$



PLAN OF SKEWED ENDS ~ OVER 30° TO 45°



LENGTHENING DETAIL

- ⑤ Place Bars F1 and F2 continuously through the angle section. Bend Bars F1 and F2 to remain parallel to the walls of the box culvert.
- ⑥ When necessary to avoid conflict in acute corners, shorten the slab extension leg of Bars C and Bars D to a minimum of 1'-6" for skews of 30° thru 45°.
- ⑦ At the Contractor's option, for skews of 15° or less, place Bars B, C, D, and E parallel to the skewed end while maintaining spacing along centerline of box. Increase lengths of Bars B and Bars E shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets to accommodate the skew.
- ⑧ Extend Bars E as shown on the MC standard sheet for direct traffic culverts.

CONSTRUCTION NOTES:

Do not use permanent forms.
 When required, lap Bars H 1'-8" for uncoated or galvanized bars.
 Provide a minimum of 1 1/2" clear cover.

MATERIAL NOTES:

Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel, if required elsewhere in the plans.
 Provide Class C concrete ($f'c = 3,600$ psi) with these exceptions:
 provide Class S concrete ($f'c = 4,000$ psi) for top slabs of culverts with overlay, with 1-to-2 course surface treatment, or with the top slab as the final riding surface.

GENERAL NOTES:

Designed according to AASHTO LRFD Bridge Design Specifications.
 Refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for details of straight sections of culvert.
 For skewed sections and angle sections, refer to Multiple Box Culverts Cast-in-Place (MC) standard sheets for slab and wall dimensions, bar sizes, maximum bar spacing, and any other details not shown.
 For skewed ends with curbs, adjust length of Bars H, number of Bars K, curb concrete volume, and reinforcing steel weight by dividing the values shown on the Multiple Box Culverts Cast-In-Place (MC) standard sheets by the cosine of the skew angle.

Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING

Texas Department of Transportation
 Bridge Division Standard

MULTIPLE BOX CULVERTS CAST-IN-PLACE MISCELLANEOUS DETAILS

MC-MD




FILE: 0923	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
0923	CONT: 23	SECT: 032	JOB: CR 508	HIGHWAY: 44
DIST: BWD		COUNTY: MILLS		SHEET NO.: 44

DATE: 3/22/2024 12:25:19 PM
 FILE: \\leo-pw_bent\lev.com:leo-pw-01\Documents\2163D TXDOT 88-91DP5025\4-Design\Plan Set\S07-BrIDGE-STANDARDS\CD-PW-20.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TABLE OF DIMENSIONS AND REINFORCING STEEL (Wings for one structure end)												
Maximum Wingwall Height Hw	Dimensions				Variable Reinforcing				Estimated Quantities per ft of wing (2-wings) ④	Estimated Quantities per ft of Toewall (1-toewall)		
	W	X	Y	Z	Bars J1		Bars J2					
					Size	Spa	Size	Spa	Reinf (Lb/Ft)	Conc (CY/Ft)	Reinf (Lb/Ft)	Conc (CY/Ft)
2'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	48.64	0.406	6.85	0.071
2'-9"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.31	0.424	6.85	0.071
3'-0"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	49.98	0.444	6.85	0.071
3'-3"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.32	0.462	6.85	0.071
3'-6"	2'-10"	10"	1'-0"	7"	#4	1'-0"	#4	1'-0"	53.98	0.480	6.85	0.071
4'-0"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	55.77	0.532	6.85	0.071
4'-6"	3'-2"	1'-2"	1'-0"	7"	#4	1'-0"	#4	1'-0"	59.77	0.568	6.85	0.071
5'-0"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	63.45	0.632	6.96	0.075
5'-6"	3'-9"	1'-7"	1'-2"	7"	#4	1'-0"	#4	1'-0"	67.46	0.668	6.96	0.075
6'-0"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	80.67	0.730	7.07	0.078
6'-6"	4'-4"	2'-0"	1'-4"	7"	#5	1'-0"	#5	1'-0"	85.05	0.768	7.07	0.078
7'-0"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	92.15	0.864	8.07	0.093
7'-6"	5'-0"	2'-3"	1'-9"	8"	#5	1'-0"	#5	1'-0"	96.54	0.902	8.07	0.093
8'-0"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	139.04	0.962	8.13	0.095
8'-6"	5'-6"	2'-8"	1'-10"	8"	#5	6"	#5	6"	144.47	1.000	8.13	0.095
9'-6"	6'-0"	2'-10"	2'-2"	9"	#5	6"	#5	6"	156.93	1.136	8.41	0.110
10'-6"	6'-5"	3'-0"	2'-5"	9"	#6	6"	#5	6"	196.27	1.234	8.57	0.117
11'-6"	7'-2"	3'-6"	2'-8"	11"	#6	6"	#6	6"	230.13	1.438	9.52	0.140
12'-6"	7'-8"	3'-9"	2'-11"	1'-0"	#7	6"	#6	6"	283.41	1.592	9.74	0.157
13'-6"	8'-2"	4'-0"	3'-2"	1'-2"	#8	6"	#6	6"	348.72	1.804	10.02	0.186
14'-6"	8'-10"	4'-5"	3'-5"	1'-4"	#9	6"	#6	6"	432.94	2.046	10.30	0.218
15'-6"	9'-6"	4'-10"	3'-8"	1'-6"	#9	6"	#7	6"	489.52	2.302	11.24	0.253
16'-0"	9'-11"	5'-0"	3'-11"	1'-7"	#9	6"	#7	6"	505.72	2.448	11.47	0.279

TABLE OF WINGWALL REINFORCING (2-wings)			
Bar	Size	No.	Spa
D1	#6	~	1'-0"
D2	#6	~	1'-0"
E1	#4	~	1'-0"
F	#4	~	1'-0"
G	#6	~	8"
M1	#4	4	~
P	#4	~	1'-0"
V	#4	~	1'-0"

TABLE OF TOEWALL REINFORCING			
Bar	Size	No.	Spa
J3	#4	~	1'-0"
M2	#4	2	~
E2	#4	~	1'-0"



WING DIMENSION FORMULAS:
 (All values are in feet.)

$Hw = H + T + C$
 $Lw = (Hw) (SL) \div \cosine (\theta)$ for Type PW-1
 $= (Hw - 1') (SL) \div \cosine (\theta)$ for Type PW-2 and $Hw \ge 4'$
 $= (Hw - 0.5') (SL) \div \cosine (\theta)$ for Type PW-2 and $Hw < 4'$


For cast-in-place culverts:
 $Ltw = [(N) (S) + (N + 1) (U)] \div \cosine (\theta)$

For precast culverts:
 $Ltw = [(N) (2 U + S) + (N - 1) (0.5')] \div \cosine (\theta)$
 Total Wingwall Area (two wings ~ SF)
 $= (2)(Hw)(Lw)$ for Type PW-1
 $= (2)(Hw)(Lw) - 6 SF$ for Type PW-2 and $Hw \ge 4'$
 $= (2)(Hw)(Lw) - 1.5 SF$ for Type PW-2 and $Hw < 4'$

Hw = Height of wingwall
 Lw = Length of wingwall
 Ltw = Culvert toewall length
 N = Number of culvert spans
 $SL:1$ = Channel slope ratio. (horizontal: 1 vertical, usual value is 2:1)
 θ = Culvert skew

See applicable box culvert standard sheet for S, H, T, and U values.

- Skew = 0°
- At discharge end, chamfer may be 3/4" minimum.
- For 15° skew ~ 1"
For 30° skew ~ 2"
For 45° skew ~ 3"
- Quantities shown are for two Type PW-1 wings. Adjust concrete volume for Type PW-2 wings. To determine estimated quantities for two wings, multiply the tabulated values by Lw. Quantities shown do not include weight of Bars D.
- Provide weepholes for Hw = 5'-0" and greater. Fill around weepholes with coarse gravel.
- Extend Bars E2 1'-6" minimum into the wingwall footing.
- Lap Bars M1 1'-6" minimum with Bars M2.
- Place Bars G as shown, equally spaced at 8" maximum. Provide at least two pairs of Bars G per wing.
- 0' Min to 5'-0" Max. Estimated curb heights are shown elsewhere in the plans. For structures with pedestrian rail or curbs taller than 1'-0, refer to the Extended Curb Details (ECD) standard sheet. For structures with T631 or T631LS bridge rail, refer to the Mounting Details for T631 & T631LS Rails (T631-CM) standard sheet. Refer to the Box Culvert Rail Mounting Details (RAC) standard sheet for structures with bridge rail other than T631 or T631LS.
- For vehicle safety, the following requirements must be met:
 - For structures without bridge rail, construct curbs no more than 3" above finished grade.
 - For structures with bridge rail, construct curbs flush with finished grade.
 Reduce curb heights, if necessary, to meet the above requirements. No changes will be made in quantities and no additional compensation will be allowed for this work.
- 1'-0" typical. 2'-3" when the Box Culvert Rail Mounting Details (RAC) standard sheet is referred to elsewhere in the plans.
- 3'-0" for Hw < 4'.
- 6" for Hw < 4'.








DESIGNER NOTES:
 Type PW-1 can be used for all applications and must be used if railing is to be mounted to the wingwall. Type PW-2 can only be used for applications without a railing mounted to the wingwall.

MATERIAL NOTES:
 Provide Class C concrete (f'c=3,600 psi).
 Provide Grade 60 reinforcing steel.
 Provide galvanized reinforcing steel if required elsewhere in the plans.


GENERAL NOTES:
 Designed in accordance with AASHTO LRFD Bridge Design Specifications.
 Depth of toewalls for wingwalls and culverts may be reduced or eliminated when founded on solid rock, when directed by the Engineer.
 See Box Culvert Supplement (BCS) standard sheet for wingwall type and additional dimensions and information. Quantities for concrete and reinforcing steel resulting from the formulas given on this sheet are for the Contractor's information only.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing dimensions are out-to-out of bars.




		Bridge Division Standard	
<h2>CONCRETE WINGWALLS WITH PARALLEL WINGS FOR BOX CULVERTS TYPES PW-1 AND PW-2</h2>			
<h3>PW</h3>			
FILE:	DN: GAF	CK: CAT	DW: TXDOT
©TXDOT February 2020	CONTRACT NO. 0923	SECTION 23	JOB NO. 032
REVISIONS			COUNTY CR 508
	DIST. BWD	COUNTY MILLS	SHEET NO. 45

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




TYPE 1 CURB

Used for curbs from 8" to 9" (Showing "C" = 9"). Showing T223 Rail, other rails similar. (Bars L(#5) on T223 and C223 Rails are not used for this structure). Bars RH(#5) required on standards T80HT, T80SS and T224 are not required when used with the RAC standard.




TYPE 2 CURB

Used for curbs over 9" to 2'-0" (Showing "C" = 2'-0"). Showing T223 Rail, other rails similar. (Bars L(#5) on T223 and C223 Rails are not used for this structure). Bars RH(#5) required on standards T80HT, T80SS and T224 are not required when used with the RAC standard.



TYPE 3 CURB

Used for curbs over 2'-0" to 5'-0" (Showing "C" = 4'-0"). Showing T223 Rail, other rails similar. (Bars L(#5) on T223 and C223 Rails are not used for this structure). Bars RH(#5) required on standards T80HT, T80SS and T224 are not required when used with the RAC standard.



TYPICAL CURB PLAN

Showing typical installation on skewed culvert. (Bars L(#5) on T223 and C223 Rails are not used for this structure). Bars RH(#5) required on standards T80HT, T80SS and T224 are not required when used with the RAC standard.

Curb Height "C"	Section Type	Bars S, U, & Z Spa
8" to 9"	1	12"
Over 9" to 2'-0"	2	9"
Over 2'-0" to 3'-0"	3	7"
Over 3'-0" to 5'-0"	3	5"

Curb Height "C"	Section Type	Reinf Steel (Lb/LF)	Class "C" Concrete (CY/LF)
8"	1	21.5	0.056
9"	1	21.5	0.063
1'-0"	2	29.7	0.083
1'-6"	2	30.6	0.125
2'-0"	2	31.5	0.167
3'-0"	3	44.6	0.250
4'-0"	3	56.8	0.333
5'-0"	3	60.0	0.417

- "T" is equal to the culvert top slab thickness. For Precast Boxes with slabs less than 8" thick, see SCP-MD Standard for additional details.
- Tilt Bars L hook as necessary to maintain cover.
- Optional Bars L are to be used only for Precast Box Culverts with 3'-0" closure pours.
- Quantities shown are for Contractor's information only. Quantities are per Linear Foot of curb length. The values for each section type in table can be interpolated for intermediate values of Curb Height, "C".

CONSTRUCTION NOTES:

When using this anchorage curb, omit normal culvert curb reinforcing bars K and H shown on the culvert standard sheets. For vehicle safety, the top of the curb must be flush with the finished grade.


MATERIAL NOTES:

Provide Grade 60 reinforcing steel. Galvanize all reinforcing steel if required elsewhere. Provide bar laps, where required, as follows:
Uncoated or galvanized ~ #4 = 1'-11"
Provide Class "C" concrete (f'c=3,600 psi). Provide Class "C" (HPC) concrete if shown elsewhere in the plans.

GENERAL NOTES:

Designed according to AASHTO LRFD Bridge Design Specifications. The rail anchorage curb details have sufficient strength for use with all standard rail types. See appropriate rail standard for approved design speed restrictions, notes and details not shown. This anchorage curb is considered part of the Box Culvert for payment. These details are for use with curbs that are 8" to 5'-0" tall only. Curb heights that are less than or greater than those shown will require special design.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.




Texas Department of Transportation Bridge Division Standard

RAIL ANCHORAGE CURB BOX CULVERT RAIL MOUNTING DETAILS (CURBS 8" TO 5'-0" TALL ONLY) RAC

FILE: CD-RAC-20.dgn	DN: GAF	CK: TxDOT	DW: TxDOT	CK: GAF
REVISONS	CONT	SECT	JOB	HIGHWAY
0923	23	032	CR	508
DIST	COUNTY	SHEET NO.		
BWD	MILLS	46		

DISCLAIMER:
 The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever.
 TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
 FILE:



INSTALLATION AT PARALLEL CULVERT WINGWALLS
 See culvert wingwall standard for bars and details not shown.

⑤ Bars G (#5), as identified on the PARALLEL WINGS PW standard sheet, must extend 1'-6" into the Anchorage Curb similar to that shown for a normal culvert curb.

SHEET 2 OF 2




**RAIL ANCHORAGE CURB
 BOX CULVERT
 RAIL MOUNTING DETAILS
 (CURBS 8" TO 5'-0" TALL ONLY)**

RAC


FILE: CD-RAC-20.dgn	DN: GAF	CK: TxDOT	DW: TxDOT	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
	DIST	COUNTY	SHEET NO.	
	BWD	MILLS	47	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:



ROADWAY ELEVATION OF RAIL ON BRIDGE



ROADWAY ELEVATION OF RAIL ON BOX CULVERTS

Showing 0° skew culvert. Skewed culverts similar. See RAC standard for details not shown. Vertical joints in concrete rail are not required, unless shown elsewhere.





- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Wingwall Length minus 5'-0" (Varies)

SHEET 1 OF 3

				Bridge Division Standard	
<h2>TRAFFIC RAIL</h2>					
<h3>TYPE T223</h3>					
FILE: RL-T223-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: AES	
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY	
REVISIONS	0923	23	032	CR	508
	DIST	COUNTY	SHEET NO.		
	BWD	MILLS	48		

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard by the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Wingwall Length minus 5'-0" (Varies)
- ③ Increase 2" for structures with overlay.
- ④ Bars L(#5) are part of rail reinforcing and are included in unit price bid for railing. Space with Bars U. Bars L match slab bar cover. Bars L may be bundled with top slab reinforcing if spacing is equivalent.
- ⑤ Bars SU1(#3), SU2(#3) and WU(#5) not shown for clarity.
- ⑥ Substitute Bars U(#5) for Bars WU(#5) when parapet end is located on anchorage curb over culvert top slab. Use Bars WU(#5) in culvert parallel wings.


SHEET 2 OF 3

		Bridge Division Standard	
<h2>TRAFFIC RAIL</h2>			
<h3>TYPE T223</h3>			
FILE: RL-T223-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT September 2019	CONT	SECT	JOB
REVISIONS	0923	23	032
DIST	COUNTY		SHEET NO.
BWD	MILLS		49


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



**SECTION C-C
ON ABUTMENT WINGWALLS
OR CIP RETAINING WALLS**




**SECTION D-D
ON ABUTMENT WINGWALLS
OR CIP RETAINING WALLS**



**AT POST
ON BRIDGE SLAB**

**AT OPENING
ON BRIDGE SLAB**




**ELEVATION AT
ABUTMENT WINGWALL**

Box culvert parallel wings or rail anchorage curb similar.

SECTIONS THRU RAIL

Sections on box culverts similar.

- ② Wingwall Length minus 5'-0" (Varies)
- ③ Increase 2" for structures with overlay.
- ④ Bars L(#5) are part of rail reinforcing and are included in unit price bid for railing. Space with Bars U. Bars L match slab bar cover. Bars L may be bundled with top slab reinforcing if spacing is equivalent.
- ⑥ Substitute Bars U(#5) for Bars WU(#5) when parapet end is located on anchorage curb over culvert top slab. Use Bars WU(#5) in culvert parallel wings.
- ⑦ When vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls on traffic side of wall, move the horizontal wingwall/retaining wall reinforcing to the inside of Bars WU where bars conflict.
- ⑧ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑨ At the Contractor's option, Bars V may be replaced by extending Bars U to 2'-5 1/4" above the roadway surface without overlay.



PLAN OF RAIL AT EXPANSION JOINTS

Example showing Slab Expansion Joints without breakbacks.

CONSTRUCTION NOTES:

Face of rail and parapet must be vertical transversely unless otherwise shown in the plans or approved by the Engineer.
Provide water barriers at openings draining onto undercrossing roadways and sidewalks. They may be cast-in-place or precast in convenient lengths and bonded to the bridge deck with an approved epoxy cement.
Chamfer all exposed corners.


MATERIAL NOTES:

Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.
Provide Grade 60 reinforcing steel.
Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized.
Deformed Welded Wire Reinforcing (WWR) (ASTM A1064) of equal size and spacing may be substituted for Bars U, V, and WU unless noted otherwise. Provide the same laps as required for reinforcing bars.
Provide bar laps, where required, as follows:
Uncoated or galvanized ~ #5 = 2'-0"
Epoxy coated ~ #5 = 3'-0"


GENERAL NOTES:

This rail has been evaluated by full-scale crash test to meet MASH TL-3 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.
Do not use this railing on bridges with expansion joints providing more than 5" movement.
Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
Shop drawings are not required for this rail.
Average weight of railing with no overlay is 358 plf.


Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.




BARS L (#5)




BARS U (#5) ⑨




BARS S (#3)



BARS SU (#3)



BARS V (#5) ⑨




BARS WU (#5)

TRAFFIC RAIL

TYPE T223


FILE: RL-T223-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: AES
REVISIONS	CONT	SECT	JOB	HIGHWAY
	0923	23	032	CR 508
	DIST	COUNTY	SHEET NO.	
	BWD	MILLS	50	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



OPTION 1 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.



OPTION 1 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans, flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a) If flowable backfill is to be placed over MSE backfill, then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b) Place flowable fill in lifts not exceeding 2 feet in height. Place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).

GENERAL NOTES:

See the Bridge Layout for selected Option. Option 1 is intended for construction only requiring plasticity index (PI) controlled embankment fill or excavation in competent soils/rocks in order to construct the abutment. Option 2 is intended for new construction requiring high plasticity embankment fill with a PI greater than 30 or pavement built in poor native soil. Poor soils are defined as high plasticity clays or expansive clays.


Construct abutment backfill in accordance with Item 400, "Excavation and Backfill for Structures".

Provide Cement Stabilized Backfill (CSB) meeting the requirements of Item 400, "Excavation and Backfill for Structures", to the limits shown at bridge abutments.


If required elsewhere in the plans, provide Flowable Backfill meeting the requirements of Item 401, "Flowable Backfill", to the limits shown at bridge abutments.

Details are drawn showing left forward skew. See Bridge Layout for actual skew direction.

These details do not apply when Concrete Block retaining walls are used in lieu of wingwalls.



WITHOUT APPROACH SLAB



WITH APPROACH SLAB
(Showing BAS-C, BAS-A similar.)

SECTION A-A

SHEET 1 OF 2




CEMENT STABILIZED ABUTMENT BACKFILL BRIDGE ABUTMENT

CSAB

FILE: MS-CSAB-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONTRACT	SECTION	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
02-20: Added Option 2. 03-23: Updated General Notes.	DIST	COUNTY	SHEET NO.	
	BWD	MILLS	51	


DATE:
FILE:

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




OPTION 2 ~ PLAN WITH WINGWALLS

Cast-in-place retaining walls similar.




OPTION 2 ~ PLAN WITH MSE RETAINING WALLS

- ① Usual limit of Cement Stabilized Backfill is at end of wingwall. Extend CSB limits as required to maintain a slope no steeper than 1:1 at bottom of backfill.
- ② Bench backfill as shown with 12" (approximate) bench depths.
- ③ Where MSE retaining walls are present, adjust CSB limits to accommodate the select fill zone. See retaining wall details for additional information.
- ④ When distance between select fill zones is less than 5'-0", MSE select fill may be substituted for cement stabilized backfill with approval from the Engineer.
- ⑤ If shown in the plans, flowable backfill can be used as a substitute for cement stabilized backfill with the following constraints:
 - a). If flowable backfill is to be placed over MSE backfill, then a filter fabric will be placed over the MSE backfill prior to placement of the flowable fill; and
 - b). Place flowable fill in lifts not exceeding 2 feet in height. Place each successive lift when the previous lift has stiffened/hardened (i.e. has lost its flowability).
- ⑥ 1'-0" for BAS-A
1'-10" for BAS-C



WITHOUT APPROACH SLAB



SECTION B-B

WITH APPROACH SLAB
(Showing BAS-C, BAS-A similar.)

SHEET 2 OF 2



**CEMENT STABILIZED
ABUTMENT BACKFILL
BRIDGE ABUTMENT**


CSAB

FILE: MS-CSAB-23.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT April 2019	CONTRACT	SECTION	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
02-20: Added Option 2. 03-23: Updated General Notes.	DIST	COUNTY	SHEET NO.	
	BWD	MILLS	52	


DATE:
FILE:

DISCLAIMER: This standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard for the conversion of this standard to other formats or for incorrect results or damages resulting from its use. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 3/22/2024 12:25:38 PM
 FILE: \\leo-pw_bentley.com:leo-pw-01\Documents\2163D TxDOT 88-91DP5025\4-Design\Plan Set\507-BrIDGE\7-Standard\CR508_BRIDGE_7-Standard\MS-SRR-19.dgn




PLAN



ELEVATION




SECTION A-A AT CAP



SECTION B-B

Provide toewall when shoulder drain is located adjacent to limits of stone riprap. Omit toewall when thickness of protection riprap is greater than 18".



CAP OPTION A

CAP OPTION B

DETAIL C

① Top of cap to top of riprap dimension varies as directed by the Engineer. Provide 9" Min for beam/slab type bridges and 1'-6" for slab span, box beam, or slab beam bridges.

GENERAL NOTES:
 Refer to Item 432, "Riprap" for stone size and gradation, and construction details. See Layout for limits and thickness of riprap specified.
 See elsewhere in plans for locations and details of shoulder drains.

				Bridge Division Standard	
<h2>STONE RIPRAP</h2>					
<h3>SRR</h3>					
FILE:	DN: AES	CK: JGD	DW: BWH	CK: AES	
©TxDOT	April 2019	CONT	SECT	JOB	HIGHWAY
	REVISIONS	0923	23	032	CR 508
		DIST	COUNTY	SHEET NO.	
		BWD	MILLS	53	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 3/22/2024 12:25:39 PM
 FILE: \\leo-pw_bentley.com:leo-pw-01\Documents\2163D TxDOT 88-91DP5025\4-Design\Plan Set\S07-Br idge\7-Standard\CR508_BRIDGE_STANDARD\MS-SRR-19.dgn




FIGURE 1 ~ TYPE R STONE RIPRAP
dry or grouted




FIGURE 2 ~ TYPE F STONE RIPRAP
dry or mortared





FIGURE 3 ~ TYPE F STONE RIPRAP
grouted

- ② Provide bedding material instead of filter fabric if shown elsewhere in plans. See Layout for thickness of bedding material.
- ③ Minimum toe depth is the larger of the maximum scour depth or 2 times the riprap thickness.
- ④ "Y" and Height need to be defined. See layout or detail sheet for values if this option is used.
- ⑤ List Stone Protection as size (XX inch) and thickness (YY inch) on the layout.
Example: Riprap (Stone Protection) XX inch, Thickness = YY inch.



PROTECTION STONE RIPRAP TOE OPTIONS ⑤




FIGURE 4 ~ COMMON STONE RIPRAP
dry or grouted




FIGURE 5 ~ PROTECTION STONE RIPRAP ⑤

STONE RIPRAP

SRR

FILE:	DN: AES	CK: JGD	DW: BWH	CK: AES
©TxDOT	April 2019	CONT SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
DIST	COUNTY		SHEET NO.	
BWD	MILLS		54	

UPDATED 6/1/2017

Prepared by *****
DATE: 5/31/2024 6:54:11 PM
FILE: pw://ieo-pw_bentley.com:ieo-pw-01/Documents/2163D TXDOT 88-9IDP5025/4-Design/Plan Set/509-Environmental/EPIC_CR_508.dgn

During the planning phase of project development the following environmental permits, issues, and commitments have been developed during coordination with resource agencies, local governmental entities, and the general public. Any change orders and/or deviations from the final design must be reported to the Engineer prior to the commencement of construction activities, as additional environmental clearances may be required.

I. Clean Water Act, Sec. 402 Texas Pollutant Discharge Elimination System

(Addresses CGP and MS4 Storm Water requirements for the project.)
(In the event that the Contractor implements a PSL on or within one mile of the project, a Site Notice and/or a NOI will apply.)

No Action Required Required Action

Action No. 1 Commitment No. 1
The project disturbs less than one acre of surface area. The contractor is responsible for the PSL as defined in the Standard Specifications for construction and Maintenance of Highways, Street, and Bridges (2014 Edition, Section 7.7.6, Page 42). The total disturbed acreage is the combined acreage to be disturbed on the project and the contractor's PSL.

The EPIC must be updated if the disturbed area increases to one or more acres during the course of construction (refer to following sections). It may become necessary to post a site notice and/or NOI for the project and/or PSL. MS4 operators that receives discharge from the project: -N/A-

II. Clean Water Act, Section 401 and 404 Compliance

(Addresses Nationwide Permits, Individual Permits, and Wetlands.)
(Filling, dredging, or excavating in any water bodies, rivers, creeks, streams, wetlands, or wet area is prohibited unless specified in the USACE permit and approved by the Engineer.)
(When temporary fills implemented, only stated TxDOT standards will be used unless written authorization for an alternative is obtained from the Engineer. No equipment is allowed in any stream channel below the Ordinary High Water Mark except on temporary stream crossings or drill pads.)

No Action Required 404 Permit and 401 Certification Required

Permit	Required Action	Waters of the US	App. Plan Sheet(s)
NWP #14	Adher to permit and general/regional conditions	Draw	See Bridge Layout

Best Management Practices for applicable 401 General Conditions:

- General Condition 12 - Categories I and II BMPs required
- Category I (Erosion Control)
 - Temporary Vegetation
 - Mulch
 - Interceptor Swale
 - Erosion Control Compost
 - Compost Filter Berms and Socks
 - Category II (Sedimentation Control)
 - Sand Bag Berm
 - Silt Fence
 - Triangular Filter Dike
 - Stone Outlet Sediment Traps
 - Erosion Control Compost
 - Compost Filter Berms and Socks
- General Condition 25 - Category III BMPs required
- Category III (Post-Construction TSS Control)
 - Retention/Irrigation
 - Extended Detention Basin
 - Vegetative Filter Strips
 - Grassy Swales
 - Erosion Control Compost
 - Compost Filter Berms and Socks
 - Blankets, Matting
 - Sod
 - Diversion Dike
 - Mulch Filter Berms and Socks
 - Compost Blankets
 - Rock Berm
 - Hay Bale Dike
 - Brush Berms
 - Sediment Basins
 - Mulch Filter Berms and Socks

III. Cultural Resources

(Addresses any special circumstances associated with cultural resources, such as archeological or historic sites.)
(Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.)

No Action Required Required Action

Action No.	Station (Rt/Lt)	Commitment
1.	---	---

IV. Vegetation Resources

(Addresses any special circumstances associated with vegetation, such as large trees to be avoided, or mitigation that will occur as part of the project.)

No Action Required Required Action

Action No.	Station (Rt/Lt)	Commitment
1.	All	Avoid non-mow locations for stockpiles and equipment parking/storage.
2.	Project Limits	Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

V. Federal Listed, Proposed, Threatened, Endangered Species, Critical Habitat, State Listed Species, Candidate Species, and Migratory Bird Treaty Act (MBTA)

(Addresses any special habitat that may need to be avoided, lists any threatened or endangered species where habitat was observed and might be impacted within the project area, and lists any precautions such as nesting seasons for migratory birds.)

No Action Required Required Action

Species Potentially within Project Area & Description
Habitat Description
The contractor should be aware that there could be various species in the project area including the Texas Horned Lizard. Avoid placing Project Specific Locations (PSLs) in areas with harvester ants. If there are large nests observed in trees to be removed contact District Environmental Coordinator prior to cutting down. Other species may also be in the area and harm to any species should be avoided. Contact the District Environmental Coordinator, Andrew Chisholm (325) 643-0442 with any questions.

The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. Migration patterns would not be affected by the proposed project. The contractor will remove all old migratory bird nests from any structure where work would be done from September 1 through the end of February. In addition, the contractor will be prepared to prevent migratory birds from building nests between March 1 and August 31, per the Environmental Permits, Issues, and Commitments (EPIC) plans. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young shall be avoided.

VI. Hazardous Material or Contamination Issues

(Addresses any previously identified high risk sites associated with hazardous materials that may be encountered during construction.)

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contractor will follow all applicable storage and management requirements for liquid oil products, liquid petroleum products, and other chemical liquids as per 40 CFR 112 (a.k.a. SPCC) and/or TCEQ Construction General Permit for storm water management.

Contact the Engineer if any of the following are detected:
Dead or distressed vegetation (not identified as normal)
Trash piles, drums, canisters, barrels, etc.
Undesirable smells/odors
Underground storage tanks
Evidence of leaching or seepage of substances
Any other evidence indicating possible hazardous materials or contamination discovered on-site

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structure not including box culverts)?

Yes No

If "No", then no further action is required.
If "Yes", then TxDOT is responsible for completing an asbestos assessment/inspection. Are the results of the asbestos inspection positive (is asbestos present)?

Yes No

If "Yes", then TxDOT must retain a Texas Department of State Health Services (DSHS) licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled abatement and/or demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Bridges on this project may contain Lead-Containing Paint (LCP) or other items that contain lead. The location of (LCP) is identified in the General Notes. Item 6.10.1.2 in the 2014 TxDOT Standard Specifications shall be utilized for this project.

VII. Other Environmental Issues

(Addresses any other environmental issues that may not have been covered in other sections.)

No Action Required Required Action

Action No.	Station (Rt/Lt)	Commitment
------------	-----------------	------------

LIST OF ABBREVIATIONS

- BMP: Best Management Practice
- CGP: Construction General Permit
- DSHS: Texas Department of State Health Services
- FEMA: Federal Emergency Management Agency
- FHWA: Federal Highway Administration
- MOA: Memorandum of Agreement
- MOU: Memorandum of Understanding
- MS4: Municipal Separate Stormwater Sewer System
- MBTA: Migratory Bird Treaty Act
- NOI: Notice of Intent
- NOT: Notice of Termination
- NWP: Nationwide Permit
- SPCC: Spill Prevention Control and Countermeasure
- SW3P: Storm Water Pollution Prevention Plan
- PCN: Pre-Construction Notification
- PSL: Project Specific Location
- TCEQ: Texas Commission on Environmental Quality
- TPDES: Texas Pollutant Discharge Elimination System
- TPWD: Texas Parks and Wildlife Department
- TxDOT: Texas Department of Transportation
- T&E: Threatened and Endangered Species
- USACE: U.S. Army Corp of Engineers
- USFWS: U.S. Fish and Wildlife Service

CR 508 ENVIRONMENTAL PERMITS, ISSUES, AND COMMITMENTS (EPIC)

Texas Department of Transportation BROWNWOOD DISTRICT

CONT	SECT	JOB	HIGHWAY
0923	23	032	CR 508
DIST	COUNTY	SHEET NO.	
BWD	MILLS	55	

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

This SWP3 has been developed in accordance with TxDOT policy for projects disturbing less than 1 acre of soil, and not part of a larger common plan of development.

For projects with less than one acre of soil disturbing activity and that have Environmental, Permits, Issues, and Commitments (EPICs) dependent on stormwater controls and water quality measures TxDOT will maintain a SWP3 with all pertinent records, correspondence, environmental documents, etc. at the project field office, Area Office, or electronically.

This SWP3 is consistent with requirements specified in applicable stormwater plans, and the project's environmental permits, issues, and commitments (EPICs).

1.0 SITE/PROJECT DESCRIPTION

1.1 PROJECT CONTROL SECTION JOB (CSJ):

0932-23-032

1.2 PROJECT LIMITS:

From: On CR 508 at Draw

To:

1.3 PROJECT COORDINATES:

BEGIN: (Lat) 31°32'09.55"N, (Long) 98°39'36.81"W

END: (Lat) 31°32'20.31"N, (Long) 98°39'36.77"W

1.4 TOTAL PROJECT AREA (Acres): 0.61

1.5 TOTAL AREA TO BE DISTURBED (Acres): 0.61

1.6 NATURE OF CONSTRUCTION ACTIVITY:

Construction of bridge replacement consisting of replacing bridge and approaches.

1.7 MAJOR SOIL TYPES:

Soil Type	Description
Sunev Clay Loam, 1% to 3% slopes	Entire project; 90% sunev, cool, and similar soils, well drained, low rate of runoff, and moderate erosion potential

1.8 PROJECT SPECIFIC LOCATIONS (PSLs):

PSLs must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. PSLs may be identified during preconstruction meetings or during the construction process. Please choose from the options below:

- PSLs determined during preconstruction meeting
- PSLs determined during construction
- No PSLs planned for construction

Type	Sheet #s

All off-ROW PSLs required by the Contractor are the Contractor's responsibility. The Contractor shall secure all permits required by local, state, federal laws for off-ROW PSLs. The contractor shall provide diagrams, areas of disturbance, acreage, and BMPs for all off-ROW PSLs within one mile of the project.

1.9 CONSTRUCTION ACTIVITIES:

(Use the following list as a starting point when developing the Construction Activity Schedule and Ceasing Record in Attachment 2.3.)

- Mobilization
- Install sediment and erosion controls
- Blade existing topsoil into windrows, prep ROW, clear and grub
- Remove existing pavement
- Grading operations, excavation, and embankment
- Excavate and prepare subgrade for proposed pavement widening
- Remove existing culverts, safety end treatments (SETs)
- Remove existing metal beam guard fence (MBGF), bridge rail
- Install proposed pavement per plans
- Install culverts, culvert extensions, SETs
- Install mow strip, MBGF, bridge rail
- Place flex base
- Rework slopes, grade ditches
- Blade windrowed material back across slopes
- Revegetation of unpaved areas
- Achieve site stabilization and remove sediment and erosion control measures

Other: _____
 Other: _____
 Other: _____

1.10 POTENTIAL POLLUTANTS AND SOURCES:

- Sediment laden stormwater from stormwater conveyance over disturbed area
- Fuels, oils, and lubricants from construction vehicles, equipment, and storage
- Solvents, paints, adhesives, etc. from various construction activities
- Transported soils from offsite vehicle tracking
- Construction debris and waste from various construction activities
- Contaminated water from excavation or dewatering pump-out water
- Sanitary waste from onsite restroom facilities
- Trash from various construction activities/receptacles
- Long-term stockpiles of material and waste
- Discharges from concrete washout activities, runoff from concrete cutting activities, and other concrete related activities

Other: _____
 Other: _____
 Other: _____

1.11 RECEIVING WATERS:

Receiving waters must be depicted on the Environmental Layout Sheets in Attachment 1.2 of this SWP3. Include Segment # for receiving waters.

Tributaries	Classified Waterbody
Draw (aka Mullin Creek)	Lower Pecan Bayou (1417)


* Add (*) for impaired waterbodies with pollutant in ().

1.12 ROLES AND RESPONSIBILITIES: TxDOT

- Development of plans and specifications
- Perform SWP3 inspections
- Maintain SWP3 records and update to reflect daily operations
- Other: _____
- Other: _____

1.13 ROLES AND RESPONSIBILITIES: CONTRACTOR

- Day To Day Operational Control
- Maintain schedule of major construction activities
- Install, maintain and modify BMPs
- Other: _____
- Other: _____



William Osthoff

10/11/2024

CR 508 at Draw
STORMWATER POLLUTION PREVENTION PLAN (SWP3)
(Less Than 1 Acre)

FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	SEE TITLE SHEET		56
STATE	STATE DIST.	COUNTY	
TEXAS	BWD	MILLS	
CONT.	SECT.	JOB	HIGHWAY NO.
0923	23	032	CR 508

STORMWATER POLLUTION PREVENTION PLAN (SWP3):

2.0 BEST MANAGEMENT PRACTICES (BMPs) AND CONTROLS, INSPECTION, AND MAINTENANCE

The Contractor shall be the responsible party for implementing the BMPs described herein and for complying with the SWP3 for control of erosion and sedimentation during day-to-day operations. The Contractor shall implement changes to this SWP3 approved by TxDOT within the times specified in this SWP3 or the CGP.

2.1 EROSION CONTROL AND SOIL STABILIZATION BMPs:

T / P

- Protection of Existing Vegetation
- Vegetated Buffer Zones
- Soil Retention Blankets
- Geotextiles
- Mulching/ Hydromulching
- Soil Surface Treatments
- Temporary Seeding
- Permanent Planting, Sodding or Seeding
- Biodegradable Erosion Control Logs
- Rock Filter Dams/ Rock Check Dams
- Vertical Tracking
- Interceptor Swale
- Riprap
- Diversion Dike
- Temporary Pipe Slope Drain
- Embankment for Erosion Control
- Paved Flumes
- Other: Preservation of natural resources
- Other: Vegetation lined ditches
- Other: _____
- Other: _____

2.2 SEDIMENT CONTROL BMPs:

T / P

- Biodegradable Erosion Control Logs
- Dewatering Controls
- Inlet Protection
- Rock Filter Dams/ Rock Check Dams
- Sandbag Berms
- Sediment Control Fence
- Stabilized Construction Exit
- Floating Turbidity Barrier
- Vegetated Buffer Zones
- Vegetated Filter Strips
- Other: _____
- Other: _____
- Other: _____
- Other: _____

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.3 PERMANENT CONTROLS:

(Coordinate post-construction BMPs with appropriate TxDOT maintenance sections.)

BMPs To Be Left In Place Post Construction:

Type	Stationing	
	From	To
No permanent controls are planned.		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.4 OFFSITE VEHICLE TRACKING CONTROLS:

- Excess dirt/mud on road removed daily
- Haul roads dampened for dust control
- Loaded haul trucks to be covered with tarpaulin
- Stabilized construction exit
- Daily street sweeping
- Other: Dampen disturbed soil areas as needed for dust control.

Other: _____

Other: _____

Other: _____

2.5 POLLUTION PREVENTION MEASURES:

- Chemical Management
- Concrete and Materials Waste Management
- Debris and Trash Management
- Dust Control
- Sanitary Facilities
- Other: Avoid storing portable sanitary units, concrete washouts or chemicals within 50-ft upgradient of a receiving water without adequate pollution controls.
- Other: Capture saw cutting debris and concrete slurry for proper disposal.
- Other: _____
- Other: _____

2.6 VEGETATED BUFFER ZONES:

Natural vegetated buffers shall be maintained as feasible to protect adjacent surface waters. If vegetated natural buffer zones are not feasible due to site geometry, the appropriate additional sediment control measures have been incorporated into this SWP3.

Type	Stationing	
	From	To
No vegetative buffer for stream. Sediment fence, rock filter dams, & erosion control logs in lieu of.		

Refer to the Environmental Layout Sheets/ SWP3 Layout Sheets located in Attachment 1.2 of this SWP3

2.7 ALLOWABLE NON-STORMWATER DISCHARGES:

- Fire hydrant flushings
- Irrigation drainage
- Pavement washwater (where spills or leaks have not occurred, and detergents are not used)
- Potable water sources
- Springs
- Uncontaminated groundwater
- Water used to wash vehicles or control dust
- Other allowable non-stormwater discharges as allowed by TPDES GP TXR150000.

2.8 DEWATERING:

Dewatering discharges of accumulated stormwater, groundwater, and surface water including discharges from dewatering of trenches, excavations, foundations, vaults, and other points of accumulation are prohibited unless managed by appropriate controls to prevent and minimize the offsite discharge of sediment and other pollutants.

2.9 INSPECTIONS:

All disturbed areas and erosion and sediment control devices shall be inspected at least once every seven (7) days. Inspections shall be performed by TxDOT as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3 .

2.10 MAINTENANCE:

Control measures shall be properly installed according to specifications. If it is determined that a BMP or control measure is not operating effectively, maintenance must be accomplished as soon as possible and before the next anticipated rain event, but in no case later than 7 calendar days after being able to access the site. Maintenance shall be performed by the Contractor as indicated on the Field Inspection and Maintenance Report Form 2118 and retained in Attachment 2.3 of this SWP3.



William Osthoff


10/11/2024

CR 508 at Draw

STORMWATER POLLUTION PREVENTION PLAN (SWP3) (Less Than 1 Acre)


FED. RD. DIV. NO.	PROJECT NO.		SHEET NO.
6	SEE TITLE SHEET		57
STATE	STATE DIST.	COUNTY	
TEXAS	BWD	MILLS	
CONT.	SECT.	JOB	HIGHWAY NO.
0923	23	032	CR 508

PLOT SCALE: 1/8" = 100' ft. USER: wosthoff MODEL: BL_CR508 - CR 508 SW3P
 10/11/2024 3:54:52 PM pw://lea-pw.bentley.com/lea-pw-01/Documents/21630 TXDOT 88-9IDP5025/4-Design/Plan Set/509-Environmental/CR508_SW3P_01.dgn
 REV DATE: \$SAVED\$ CSJ: 0923-23-032



LEGEND


- ➔ PROPOSED LANE
- ➔ EXISTING LANE
- ▨ STONE RIPRAP
- SEEDING
- ⊙ SEDIMENT CONTROL FENCE
- ⊙ ROCK FILTER DAM
- ~ DIRECTION OF FLOW



10/11/2024 *William Osthoff*

NO.	DATE	REVISION	APPROV.

IEA 13501 KATY FREEWAY SUITE 3425 HOUSTON, TEXAS 77079 (832) 494-3800 FIRM REGISTRATION No. F-10161



**CR 508 AT DRAW
 SW3P LAYOUT**



ITEM	DESCRIPTION	UNIT	QUANTITY
164-7002	BROADCAST SEED (PERM_RURAL_CLAY)	SY	1072
164-7005	BROADCAST SEED (TEMP_WARM)	SY	536
164-7006	BROADCAST SEED (TEMP_COOL)	SY	536
SUBSIDIARY	FERTILIZER	TON	0.04
168-7001	VEGETATIVE WATERING	TGL	25
169-7022	SOIL RET BLKT(SL_STEEP_CLAY_LONG_SPRY)	SY	1072
506-7003	ROCKFILTER DAMS (INSTALL) (TY 3)	LF	80
506-7011	ROCKFILTER DAMS (REMOVE)	LF	80
506-7039	TEMP SEDMT CONT FENCE (INSTALL)	LF	900
506-7041	TEMP SEDMT CONT FENCE (REMOVE)	LF	900

SHEET 1 OF 1

FED. RD. DIV. NO.	PROJECT NUMBER	HIGHWAY NUMBER	
6	SEE TITLE SHEET	CR 508	
STATE	DISTRICT	COUNTY	
TEXAS	BWD	MILLS	
CONTROL	SECTION	JOB	SHEET NO.
0923	23	032	58

TEMPORARY CROSSING FOR CONSTRUCTION TRAFFIC ONLY

DRAWING NOT TO SCALE



Inset

Note: Temporary crossing will not be paid for directly but will be considered subsidiary to pertinent items.

DATE: \$DATE\$
FILE: \$FILE\$


DWG: \$DWG\$
CHK: \$CHK\$
DNE: \$DNE\$

TEMPORARY CROSSING DETAIL




CONT	SECT	JOB	HIGHWAY
0923	23	032	CR 508
DIST	COUNTY		SHEET NO.
23	MILLS		58A

5/21/2024
 5012122024
 08/12/12:12:00
 iea-pw-bentley.com:iea-pw-01/Documents/21630 TXDOT 88-91DP5025/4-Design/Plan Set/S09-Environmental/9-Standards/ec116.dgn
 DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TXDOT for any purpose whatsoever. TXDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

- Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
- Perform vertical tracking on slopes to temporarily stabilize soil.
- Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
- Do not exceed 12" between track impressions.
- Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

TEMPORARY EROSION,
 SEDIMENT AND WATER
 POLLUTION CONTROL MEASURES
 FENCE & VERTICAL TRACKING
 EC(1)-16

FILE: ec116	DN: TXDOT	CK: KM	DW: VP	DN/CK: LS
© TXDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS	0923	23	032	CR 508
	DIST	COUNTY	SHEET NO.	
	BWD	MILLS	59	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 5/31/2024
 FILE: pw://iea-pw.bentley.com/iea-pw-01/Documents/2163D TXDOT 88-91DP5025/4-Design/Plan Set/509-Environmental/9-Standards/ec216.dgn




FILTER DAM AT TOE OF SLOPE

— (RFD1) —




FILTER DAM AT SEDIMENT TRAP

— (RFD1) — OR — (RFD2) —




FILTER DAM AT CHANNEL SECTIONS


— (RFD1) — OR — (RFD2) — OR — (RFD3) —




PLAN VIEW




"V" SHAPE PLAN VIEW




PROFILE



SECTION C-C




SECTION B-B



TYPE 4 (SACK GABIONS)

— (RFD4) —



SECTION A-A

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

PLAN SHEET LEGEND

- Type 1 Rock Filter Dam — (RFD1) —
- Type 2 Rock Filter Dam — (RFD2) —
- Type 3 Rock Filter Dam — (RFD3) —
- Type 4 Rock Filter Dam — (RFD4) —

		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC (2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT: 0923	SECT: 23	JOB: 032
REVISIONS		HIGHWAY: CR 508	
DIST: BWD	COUNTY: MILLS	SHEET NO.: 60	