

STATE OF TEXAS

DEPARTMENT OF TRANSPORTATION

MATERIALS MAINTENANCE CONTRACT

PROJECT NO. MMC 6475-42-001
CSJ: 6475-42-001
HIGHWAY: SH 144, ETC.
LIMITS OF WORK: HOOD/
SOMERVELL COUNTIES

FOR PURCHASE AND DELIVERY OF MATERIALS ONLY
DESCRIPTION: DENSE GRADED HOT MIX ASPHALT (MATERIAL ONLY)

RECOMMENDED
FOR LETTING: 10/29/2024
Date

RECOMMENDED
FOR LETTING: 10/29/2024
Date

DocuSigned by:
Sarah J. Homer, PE

AREA ENGINEER

DocuSigned by:
Elijah Belenon P. E.

MAINTENANCE ENGINEER

APPROVED FOR
LETTING: 10/29/2024
Date


DocuSigned by:
Janet Crawford

DIRECTOR OF MAINTENANCE

INDEX OF SHEETS

- 1 TITLE SHEET
- 2A-C GENERAL NOTES
- 3 ESTIMATE & QUANTITY SHEET
- 4 DELIVERY SITES SHEET

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION, SEPTEMBER 1, 2024 AND SPECIAL SPECIFICATION ITEMS INCLUDED IN THE CONTRACT SHALL GOVERN ON THIS PROJECT.

© 2024			
FED.RD. DIV. NO.	PROJECT NO.	SHEET NO.	
6	6475-42-001	1	
STATE	DISTRICT	COUNTY	
TEXAS	FTW	HOOD/SOMERVELL	
CONTROL	SECTION	JOB	HWY NO.
6475	42	001	SH 144, ETC.
FILENAME			DATE
MMC 6475-42-001			10/22/2024

Project Number: MMC-647542001

Control: 6475-42-001

County: Hood/Somervell Counties

Highway: SH 144, Etc.

GENERAL NOTES:

General:

This purpose of this contract is to supply **Dense Graded Hot Mix Asphalt and Asphaltic Concrete Patching Material** at the following locations:

Site 1	Various Locations within Hood and Somervell Counties
--------	--

This contract includes an item for pickup. Materials shall be available for pickup within 75 miles of the TxDOT office located at 5721 SH 144, Granbury TX 76048. Load material into TxDOT equipment at time of pickup.

Each contract awarded by the Department stands on its own as such, is separate from other contracts. A Contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

Coordinate work through the Maintenance Section Supervisor or Representative:

Granbury 5721 SH 144 Granbury, TX 76048 (254) 897-2647

Bids will be received at 6230 East Stassney Lane, Austin, TX 78744.

Contractor questions on this project are to be emailed to the following individuals:

Area Engineer: Sarah Horner
Project Manager: Jarred Word

Sarah.Horner@txdot.gov
 Jarred.Word@txdot.gov

All Contractor questions will be reviewed by the Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>

All questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, CCSJ/Project Name.

Project Number: MMC-647542001

Control: 6475-42-001

County: Hood/Somervell Counties

Highway: SH 144, Etc.

Section 10.2 - Instructions to Bidders:

This project includes plan sheets that are not part of the bid proposal. View or download plans at:

<https://www.dot.state.tx.us/business/plansonline/ftpinfo.htm>

Section 10.4 – Scope of Work:

Prior to beginning operations, the Department will arrange a coordination call between representatives of the Department and the Contractor. In this meeting, the representatives from all parties will discuss the Contract, proposed procedures, and plans for performing the work while providing safe passage for traffic at all times. Specifications, unusual conditions, and other pertinent items regarding the work will also be discussed. Limit the use of the roadway for the hauling of material to legal loads. Keep the traveled surfaces used in hauling operations free of dirt or other materials.

In accordance with Article 10.4.3.1, this contract may be extended once, not to exceed 730 calendar days for the entire contract term if mutually agreed.

Section 10.8 - Prosecution and Progress:

There are 365 calendar days on this contract. Calendar days will be charged in accordance with Article 10.8.2., "Contract Term".

Types of accepted haul vehicles include End Dumps.

Work Orders. There will be a minimum of seven working days allowed to deliver material as of the date of the work order except for Expedited Work Orders (EWO). The actual number of days allowed for delivery of materials will be shown in the Contract and work order; however, anything less than seven working days in the Contract or work order (except for an EWO) is not allowed.

Work Order will specify a delivery site by the bid item in the contract and quantity to be supplied.

Unless otherwise directed, prosecute the work continuously to completion of the Work Order.

Item 8011 – Dense-Graded Hot Mix Asphalt (Materials Only):

No Blending, of the material to meet SAC A will be allowed.

Substitute binders are not allowed on this project.

RAP and RAS are not permitted in any surface and level-up mixes on this project

Project Number: MMC-647542001

Control: 6475-42-001

County: Hood/Somervell Counties

Highway: SH 144, Etc.

Furnish a mix design to the State's representative to be sent to the District Laboratory for verification testing.

Use the Boil Test, Test Procedure Tex-530-C, and provide only mixes that produce zero percent (0%) stripping for design verification and during production.

Use only Department MPL approved asphalt release agents. Diesel and/or solvents in the production, transportation, and/or construction of the mix is prohibited.

No material shall be left in the haul vehicle overnight.

Canvas covers and insulating of the truck bodies will be required.

Contractor must have equipment and personnel to supply a minimum of 500 ton per day.

Include the approved mix design number on each delivery ticket.

Item 8019 – Asphaltic Conc Patch Material (Materials Only):

This item will be measured by the ton as defined in the plans and specifications. Delivery location will be listed in each Work Order.



Estimate & Quantity Sheet

CONTROLLING PROJECT ID 6475-42-001

DISTRICT Fort Worth

COUNTY Hood


HIGHWAY SH0144

CONTROL SECTION JOB				6475-42-001		TOTAL EST.	TOTAL FINAL
PROJECT ID				A00212555			
COUNTY				Hood			
HIGHWAY				SH0144			
ALT	BID CODE	DESCRIPTION	UNIT	EST.	FINAL		
	8011-7019	D-GR HMA TY B PG 64-22 SAC B (PICKUP)	TON	600.000		600.000	
	8011-7020	D-GR HMA TY B PG 64-22 SAC B (DEL) ST1	TON	600.000		600.000	
	8011-7038	D-GR HMA TY C PG 64-22 (DEL) SITE 1	TON	1,400.000		1,400.000	
	8011-7055	D-GR HMA TY D PG 64-22 (PICKUP)	TON	1,000.000		1,000.000	
	8011-7056	D-GR HMA TY D PG 64-22 (DEL) SITE 1	TON	4,000.000		4,000.000	
	8012-7040	ASPH CONC PATCH MAT (DEL)(ST1)	TON	1,000.000		1,000.000	

DISTRICT	COUNTY	CCSJ	SHEET
Fort Worth	Hood	6475-42-001	3

SITE NO.	MAINTENANCE OFFICE	DELIVERY SITE	ITEM NO.	DES. NO.	UNIT	QUANTITY
1	GRANBURY	VARIOUS LOCATIONS WITHIN HOOD/SOMERVELL	8011	7019	TON	600
1	GRANBURY	VARIOUS LOCATIONS WITHIN HOOD/SOMERVELL	8011	7020	TON	600
1	GRANBURY	VARIOUS LOCATIONS WITHIN HOOD/SOMERVELL	8011	7038	TON	1,400
1	GRANBURY	VARIOUS LOCATIONS WITHIN HOOD/SOMERVELL	8011	7055	TON	1,000
1	GRANBURY	VARIOUS LOCATIONS WITHIN HOOD/SOMERVELL	8011	7056	TON	4,000
1	GRANBURY	VARIOUS LOCATIONS WITHIN HOOD/SOMERVELL	8012	7040	TON	1,000

* APPROXIMATE LOCATIONS FOR DELIVERY

				
DELIVERY SITE SHEET				
DESIGN	FED RD. DIV. NO.	MAINTENANCE PROJECT NO.		HIGHWAY NO.
	6	6475-42-001		SHEET NO.
GRAPHICS	STATE	DISTRICT	COUNTY	
CHECK	TEXAS	FTW	HOOD	
CHECK	CONTROL	SECTION	JOB	4
	6475	42	001	